This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

+ *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.

+ *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.

+ *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.

+ *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at `http://books.google.com/`

NATURE

Nature April 23rd 1891

Robert William Parsons

Engraved by [illegible]

[illegible]

NATURE

A WEEKLY

ILLUSTRATED JOURNAL OF SCIENCE

VOLUME XXIII.

NOVEMBER 1880 to APRIL 1881

"To the solid ground
Of Nature trusts the mind which builds for aye."—WORDSWORTH

LIBRARY
LELAND STANFORD JUNIOR
UNIVERSITY

London and New York:
MACMILLAN AND CO.
1881

LONDON :
R. CLAY, SONS, AND TAYLOR, PRINTERS,
BREAD STREET HILL, E.C.

LIBRARY
LELAND STANFORD JUNIOR
UNIVERSITY

INDEX

ABERDEEN UNIVERSITY, Duncan's Herbarium presented to, 252
Aberdeenshire Agricultural Association, 576
Aberration of Instinct, Geo. J. Romanes, F.R.S., 433; Rev. T. H. Waller, 484
Acetous Fermentation, A. Herzen on, 86
Ackroyd (Wm.), Lecture Representation of the Aurora Borealis, 458
Acoustical Constant, Note on an, W. J. Grey and J. T. Dunn, 146
Acoustics in China, John Fryer and Dr. W. H. Stone, 448
Actinia, Crabs and, Col. H. Stuart-Wortley, 529
Adams (Prof. W. Grylls, F.R.S.), Scientific Principles involved in Electric Lighting, 580, 605
Aëronautical Society's Annual Report, 20
Aëronautics in Russia, 298
Afghan Campaign, Geographical Results of, Capt. T. H. Holdich, 159
Africa: Dr. Holub's Proposed Journey across, 22; Rev. T. J. Comber's New Map of, 22; Keith Johnston and J. Thomson's Expedition, 38; Notes on the Geology of East Central, Joseph Thomson, 102; J. Thomson's Report on the East African Expedition, 134; Geology of East Central, and the Subterranean Forest in Bombay, W. T. Blanford, 145; Progress of Exploration in, 160; Exploration of the Ogowé and Congo, 323; Mitchinson's "Expiring Continent," 399; Birds of, 467; E. G. Ravenstein's Map of Eastern Africa, 518
Agram, the Earthquakes at, 63, 83, 106, 156, 182, 253, 297, 419, 439, 492, 516, 530
"Agricultural Chemistry of Japan, Contributions to," 456
Agricultural Association, Aberdeenshire, 576
Agricultural Communism in Greece, W. Mattieu Williams, 579
"Aide-Mémoire du Voyageur," D. Kaltbrunner, 217
Air, Analysis of the, at Montsouris, by M. Davy, 63
Aitken (John), Dust, Fogs, and Clouds, 195, 204, 311, 384
Albatross, Notes on the Mode of Flight of the, Arthur W. Bateman, 125; Howard Sargent, 362
Alcoholic Liquids, Freezing Points of, M. Raout on, 85
Algæ, 359; of the Gulf of Finland, 494
Algiers: Observatory, M. Tripier appointed Director of, 107; French Association for the Advancement of Science at, 319, 491, 515, 541; G. F. Rodwell, 582, 606
Algol in 1880, Minima of, 255, 517
Alkali and Sulphuric Acid, Prof. Lunge, Prof. H. E. Roscoe, F.R.S., 73, 99, 215
Allen (J. A.), North American Pinnipeds, 261
Allman (Dr. Geo. J., F.R.S.), Hailstorm in Dorsetshire, 146
Almeida (Prof. J. Charles d'), Death of, 63; Obituary Notice of, 106
Alpine Flowers, Francis Darwin, 333
Alston (Edward Richard), Obituary Notice of, 485
Amber, the Collecting of, 298
American Naturalist, 161, 282, 378, 449, 499
American Indian Languages, A. H. Keane, 503
American Entomologist, 321
American Journal of Science, 402
Anabæna Living in Botrydium, 158
Ancient Stone Implements, Modern Use of, D. Budde, 218
Ancient Monuments, Sir John Lubbock's Motion on, 467
Ancient Astronomy, 493
Anemone, Sir John Dalzell's, 495
Animal Reasoning, 219
Animal Life, Natural Conditions and, Prof. E. Ray Lankester, F.R.S., 405
Animals, Mind in, Geo. J. Romanes, F.R.S., 501
Animal Development, Albert Kölliker, 480
Annalen der Physik und Chemie, 71, 187, 306, 449, 474, 545
Antarctic Expedition, the Italian, 87
Anthropology: Anthropological Institute, 96, 162, 212, 331, 403, 450, 475, 499, 571, 620; Presentation of Drawings to, by Mr. B. H. Hodgson, F.R.S., 107; Prehistoric Anthropology of the Crimea, M. Merijkovsky on, 63, 107; the Washington Society of Anthropology, 84
Ants, Bees, and Wasps, Observations on, Sir J. Lubbock, Bart., F.R.S., 255
Apprenticeship Schools in Paris, 321
Appulse, near, of Jupiter to a Fixed Star, 158; J. Birmingham, 170
Archæopteryx macrura, 276
Archibald (E. Douglas), Average Height of Barometer in London, 243; Abnormal Variations of Barometric Pressure in the Tropics, and their Relations to Sun-Spots, Rainfall, and Famines, 399; Abnormal Barometric Gradient between London and St. Petersburg in the Sun-Spot Cycle, 618
Architects, Naval, 568
Archives des Sciences Physiques et Naturelles, 71, 235, 283, 425, 594
Arctic Exploration, Commander Cheyne's Scheme, 134
Arlberg Tunnel, 321
Armstrong (Prof. Henry E.), Chemistry of the Future, Sir B. C. Brodie, Bart., F.R.S., 141
Artificially Digested Food, on the Digestive Ferments, and on the Preparation of, Dr. Wm. Roberts, 169
Aryan Village, An, Edward B. Tylor, F.R.S., 525
Asparagine, the Function of, 277
Astronomy: Astronomical Column, 21, 43, 65, 85, 114, 158, 182, 206, 254, 276, 298, 321, 371, 396, 441, 493, 517, 542, 591; Astronomische Nachrichten, 372; Urania, 383; Ancient Astronomy, 493
"Atlas of Physiological Botany," Dr. Dodel-Port's, 157
Atmospheric Pressure of the British Islands, 470
"Atomic Theory," Ad. Wurtz, Translated by E. Cleminshaw, 5
Atoms, Prof. Dewar on, at the Royal Institution, 181
Atti della R. Accademia dei Lincei, 235, 474, 594
Attwood's (Geo.) "Practical Blowpipe Assaying," Dr. C. Le Neve Foster, 191
Aurora: Display of, 42; Height of the, H. T. H. Groneman, 56; Aurora of November 3, J. Rand Capron, 76; Aurora observed at Ovoca, Co. Wicklow, November 3, G. H. Kinahan, 100; the August Auroras, W. Stanley Jevons, F.R.S., 148; Bottomley's Experiments with Vacuum Tubes and the, Prof. Silvanus P. Thompson, 289; Observations of Aurora Borealis, 84; Lecture Representation of the Aurora Borealis, Wm. Ackroyd, 458; Aurora of January 31, Prof. Osmond Fisher, John Harmer, R. W. Taylor, G. W. Prevost, 329; Aurora and Electric Storm of January 31, W. H. Preece, George M. Seabrooke, G. M. Whipple, Rev. S. J. Perry, F.R.S., J. Rand Capron, E. J. Lowe, G. Henry Kinahan, Gerard A. Kinahan, F. Horner, W. J. Spratling, D. Traill, 348; Aurora of January 31, Position of Auroral Rays, T. W. Backhouse, 410; Tacitus on Aurora, 459, 484; Sound of the Aurora, E. Alloway Paukhurst, J. Shaw, 484; George F. Burder, 529; M. L. Rouse, 556; Dr. John Rae, F.R.S.,

605; Auroral Phenomena, Dr. C. M. Ingleby, 363; Auroric Light, G. H. Kinahan, 410
Australian Plants in India, Dr. G. Bidie, 555
Austria, Earthquake Shock in, 42, 63
Austrian Myriopods, Dr. Robert Latzel, 167
Avalanches from Mont Pourri, 396
Awdry (Mrs. W.), "Easy Lessons in Light," 32
Ayrton (Prof. W. E.), Wire Torsion, 35; Measuring the Index of Refraction of Ebonite, 519

Backhouse (T.W.), Aurora of January 31, Position of Auroral Rays, 410
Baker (J. G.), Plants of Madagascar, 125; Eaton's Ferns of North America, 479
Balance, a New, 42
Ball (V.), on the Identity of some Ancient Diamond Mines in India, especially those mentioned by Tavernier, 490
Baller (Mr.), Opium Harvest at Kweichow, 151
Banjaluka (Bosnia), Earthquake Shock in, 182
Banks of the Yang-tse at Hankow, H. B. Guppy, 507
Barfoed's (Dr. Chr. Th.), "Lehrbuch der Organischen Qualitativen Analyse," 335
Barometer, Average Height of, in London, E. Douglas Archibald, 243
Barometric Cycles, Prof. Balfour Stewart, 237
Barometric Pressure, Abnormal Variations of, in the Tropics, and their Relation to Sun-spots, Rainfall, and Famines, Fred. Chambers, 88, 107; E. Douglas Archibald and Fred. Chambers, 399
Barometric Pressure, Periodic Oscillations of, Dr. J. Allan Broun, 556
Barometric and Solar Cycles, S. A. Hill, 409; Prof. Balfour Stewart, F.R.S., 457
Barometric Gradient, Abnormal, between London and St. Petersburg in the Sun-spot Cycle, E. Douglas Archibald, 618
Batavia, Natural History Notes from, 275
Bateman (Arthur W.), Notes on the Mode of Flight of the Albatross, 125
Baynes (Robert E.), Critical Temperature of Ethylene, 186
Becquerel (M.), Subscription for raising a Statue to, 156
Bedford College, Physical Science at, 181
Bees, Ants, and Wasps, Observations on, Sir. J. Lubbock, Bart., F.R.S., 255
Beetles, Birds, and Fishes, Food of, 494
Belgian Entomological Society, 62
Belgium, Geological Survey of, 184
Bell's (Prof. Graham) Photophone, 15
Bells, Vibration of, with Liquids in them, 278
Bendery, Skeleton of a Mammoth discovered at, 371
Bennett (Alfred W.), Natural Science for Women, 195
Benzene, the Heat of Formation of, 207
Bergsö (Herr V.), on the Habits of the Tarentula, 84
"Bericht über die Thätigkeit der Botanischen Section der Schlesischen Gesellschaft im Jahre 1877," 264
Berichte über die Verhandlungen der naturf. Gessells. zu Freiburg-im-Breisgau, 499
Berlin: Geographical Society, 87, 188, 284, 399, 420
Berne: Second International Conference at, 233; Earthquake at, 348, 396
Berthoud Borel and Co., New Discovery in Practical Telegraphy by, 85
Beryllium, Atomic Weight of, 57, 374
Bibliography, a New Medical Catalogue, 28
Bibliothèque Belge, 64
Bidie (Dr. G.), Australian Plants in India, 555
Bidwell (Shelford), the Photophone, 58; Tele-Photography, 344
Bigsby (Dr. J. J.), Death of, 389
Biological Notes, 158, 276, 494, 543
Biology of Plants, 310
Bird (Isabella L.), "Unbeaten Tracks in Japan," 12
Birds: Soaring of, S. E. Peal, 10; W. Larden, 77; European and North American, 277; British Birds, Prof. A. Newton, F.R.S., 287; Birds Laying in January, J. H. Willmore, 314; Migration of Birds, 484; Food of Birds, Fishes, and Beetles, 494
Birmingham (J.), the Appulse of Jupiter to a Fixed Star on November 20, 170; Probably New Variable Star, 555
Birmingham: Endowment of Research in, 304; Mason Science College, 440
Bismuth Compounds, 374
Black Sheep, Chas. Darwin, F.R.S., 193
Blackheath Holes, 320; C. E. de Rance, 365
Blaikie (W. Garden, D.D.), "Life of David Livingstone," &c., 238
Blake Cruise, 494
Blanford (W. T.), Geology of East Central Africa and the Subterranean Forest in Bombay, 145
Blood-Vessels of Valves of the Heart, 159
Blowpipe, Practical, Assaying, by Geo. Attwood, Dr. C. Le Neve Foster, 191
Bombay, Subterranean Forest in, 105; Geology of East Central Africa and, W. T. Blanford, 145
Boricky (Prof. Dr. Emanuel), Death of, 319
Boron and Vanadium, 373
Bosnia and Herzegovina, Geology of, Prof. Arch. Geikie, F.R.S., 224
Boston, Mass., U.S.A., American Academy of Arts and Sciences, 451
Botanical Clubs, 107
Botanical Society, Formation of a, for Northern Thuringia, 181
Botanisches Centralblatt, 241
Botanische Jahrbücher für Systematik Pflanzengeschichte und Pflanzengeographie, 263
Botany: Handbook of, Dr. N. J. C. Müller, 142; Atlas of Physiological, Dr. Dodel-Port's, 157; "Botany for Children," Rev. Geo. Henslow, 241
Botrydium, Anabæna Living in, 158
Bott (W.), Salts of Zinc, 78
Bottomley (J. T.), Experiments with Vacuum Tubes, 218, 243; Elasticity of Wires, 281; his Experiments with Vacuum Tubes and the Aurora, Prof. Silvanus P. Thompson, 289
Bouch (Sir Thomas), Death of, 19
Bournemouth and Vancouver Island, Climates of, Alfred R. Wallace, 169
Boys (C. V.), the Influence of a Tuning-Fork on a Garden Spider, 149
Brain, Concealed Bridging Convolutions in a Human, W. Carter, 556
Brain-Weight, 277
Braun (Dr. C.), Measuring the Height of Clouds, 458
Breath, Temperature of the, Dr. R. E. Dudgeon, 10, 76; Dr. Wm. Roberts, 55; Dr. C. J. McNally, 217, 244; Dr. William McLaurin, 244
Brescia, Earthquake at, 205
Bressa Prize, 540
Brewster (Sir David), Centenary of the Birthday of, 614
Briggs (T. R. Archer), Flora of Plymouth, 74
Brighton Aquarium, Death of the Male Sea-Lion in, 253
Brine-Springs, Subsidence of Land caused by Natural, Thos. Ward, 388
British Animals, Extinct, Prof. W. Boyd Dawkins, F.R.S., 431
British Association, Meeting at York, 1881, 275, 613
British Birds, Prof. Alfred Newton, F.R.S., 287
British Butterflies, Colours of, J. Innes Rogers, 435; Rev. W. Clement Ley, 458
British Columbia, Prof. Whitney on the Glaciation of, Geo. M. Dawson, 290
British Earthquakes, 117; Prof. J. P. O'Reilly, 170
British Islands, Atmospheric Pressure of the, 470
"British Marine Polyzoa," T. Hincks, F.R.S., 51
British Medical Association, Annual Meeting for 1881 at Ryde, 131
British Museum, John Millar's Botanical Drawings at, 83; the Catalogue of Birds, 439; the Catalogue of Printed Books, 440
Brodhurst (B. E.), Phosphorescent Centipedes, 99
Brodie (Sir Benjamin C., F.R.S.), Death of, 106; Obituary Notice of, 126
Brorsen's Comet in 1842, 298
Broun (Allan D.), Flying-Fish, 508
Broun (Dr. J. Allan, F.R.S.), Periodic Oscillations of Barometric Pressure, 556
Brown (Horace T.), Electrical Thermometer for Determining Temperatures at a Distance, 464
Brownell (J. T.), a Case of Fascination, 314; Ice-Casts of Tracks, 484
Bucharest, Curious Result since the Recent Earthquake at, 253
Buckland (Frank), Obituary Notice of, 175; Museum of Economic Fish Culture, 232; Proposed Memorial to, 468, 516; British Fishes, 576

Buckley (Arabella B.), "Life and her Children," 123
Budde (D.), Modern Use of Ancient Stone Implements, 218
Bulletin de l'Académie Royale des Sciences de Belgique, 211, 402, 474
Bulletin de l'Académie Impériale des Sciences de St. Pétersbourg, 593
Bunsen (Robert Wilhelm), "Scientific Worthies," Prof. H. E. Roscoe, F.R.S., 597
Burbidge (F. W.), "Gardens of the Sun," 143
Burder (George F.), Sound of the Aurora, 529
Burdo (Adolphe), the Niger and the Benuch: Travels in Central Africa, 169
Burmah, another Earthquake Shock at, 253
Butler (S.), "Unconscious Memory," 285, 312, 335
Butterflies: in Winter, Thomas W. Shore, 364; Colours of British Butterflies, J. Innes Rogers, 435; Rev. W. Clement Ley, 458
Byeloukher Mountain, the Glacier of, 210

Caird (Very Rev. Principal), Portrait of, presented to the Glasgow University, 320
Calderon, Bi-Centenary of, Major F. F. J. Ricardo-Seaver, 457
California, the former Indians of, 253
Calves, Fluke in, 244
Cambrian Sandstones near Loch Maree, Curious Impressions in, 93
Cambridge Philosophical Society, 163
Campbell (Sir Geo.), on Indian Agriculture, 541
Canoe, Discovery of, in the Marshes of Corcellettes, 106
Cape of Good Hope, Longitude of the, 21
Cape Catalogue, the New, 276
Capillarity, Volkmann's Experiments in, 133
Capron (J. Rand), Condition of Jupiter, 34; Aurora of November 3, 76; Parhelion, 291; Aurora and Electric Storm of January 31, 348
Carbon, on the Spectrum of, 313; Dr. W. M. Watts, 197, 265, 361; Prof. G. D. Liveing, F.R.S., 265, 338
Carbon, the Estimation of, 615
Cardamoms, a New Work on, 347
Carnelley's (Dr.) Hot Ice, Dr. Oliver J. Lodge, 264; Experiments on Ice under Low Pressures, 341
Carnot (M.), proposed Statue to, 439
Carpenter (W. Lant), Falls of Niagara in Winter, 511
Carr (G. S.), "Synopsis of Elementary Results in Pure and Applied Mathematics," 603
Carter (William), Chlorophyll, 388; Concealed Bridging Convolutions in a Human Brain, 556
Carvalho (S. N., jun.), Chalk, 193
Casamicciola in the Island of Ischia, Earthquake at, 439, 468, 492, 516
Cassell's Natural History, 317
Cave, the Schipka, 296
Cave Animals and Multiple Centres of Species, D. Wetterhan, 458
Census of 1881, 540
Census of the Indian Empire, 419
Centipedes, Phosphorescent, B. E. Brodhurst, 99
Cephei, Ceraski's Variable Star J, 21, 43, 255, 322
Ceraski's Circumpolar Variable Star, 21, 43, 255, 322
Cervus maral, 419
Cetonia inda, 65
Ceylon, the Botanical Gardens at Peradeniya, 65
Chalk, 243; S. N. Carvalho, jun., 193
Challenger, Volume I. of the Publications of the, Prof. T. H. Huxley, F.R.S., 1, 33, 43
Chambers (Fred.), Abnormal Variations of Barometric Pressure in the Tropics, and their Relation to Sun-Spots, Rainfall and Famines, 88, 107, 399
Chambers's Handbook of Astronomy, 418
Charing Cross Station, Jablochkoff Light at, 64
Charleville, Ireland, Shock of Earthquake at, 180
Charts and Maps, Recent, of Curves of Equal Magnetic Variation or Declination, 314
Chasles (Michel), Death of, 174; Obituary Notice of, R. Tucker, 224
Chatel (M.), Dust, Fogs, and Smoke, 436
Chemistry: Chemical Society, 47, 95, 162, 211, 306, 403, 425, 474, 523, 547, 571, 619; Chemical Notes, 85, 207, 373, 396, 469, 565, 615; Chemistry, M. Fremy on, at the Paris Museum of Natural History, 83; Chemistry of the Future, Prof. Henry E. Armstrong, F.R.S., 141; Nature of the Chemical Elements, Dr. Edmund J. Mills, F.R.S., 193; German Chemical Society, 436; Experimental Chemistry for Junior Students, 456; the Effects of Frost on Chemicals, 347; Society of Chemical Industry, 516, 541
Cheques, Bankers', New Process for making, 373
Chesapeake Zoological Laboratory, 279
Cheshire Subsidences, Landslips, T. Mellard Reade, 219
Chimborazo and Cotopaxi, Edward Whymper's Ascents of, 323
China, Exploration of, 45; Coal Mines in, 297; Acoustics in, John Fryer and Dr. W. H. Stone, 448
Chio, Earthquake at, 541, 564
Chlorophyll in the Epidermis of Plants, 158
Chlorophyll, William Carter, 388; Sydney H. Vines, 561
Chronograph, Dent's, 59
"Chrysanthemum," New Japanese Magazine, 371
Ciamician (G.), Influence of Pressure and Temperature on Vapours and Gases, 160
Cinchona Bark, Importations of, from Jamaica, 132, 157
Cincinnati Measures of Double Stars, 396
Citania, Rev. R. Burton Leach, 363
City and Guilds of London Institute, 473, 614
Civilisation? What is, 166
Clairvoyance, an Article in Scribner's Monthly on, 19
Clark (Edwin), Distance of Clouds, 244
Classification of Statures, 494
Claypole (Prof. E. W.), Minerva Ornaments at Troy, and Net-Sinkers, 292; Migration of the Wagtail, 387
Climate of Vancouver Island, Capt. Edmund H. Verney, 147; Alfred R. Wallace, 169; William Pengelly, F.R.S., 267; Dr. Geo. M. Dawson, 385
Climates, Geological, Prof. Samuel Haughton, F.R.S., 8, 98, 145, 290, 313, 384; Prof. P. Martin Duncan, F.R.S., 145; J. J. Murphy, 290; Alfred R. Wallace, 124, 217, 266; William Ingram, 169; J. Starkie Gardner, 193; Dr. Maxwell T. Masters, 266; Dr. John Rae, F.R.S., 337; Dr. A. Woeikoff, 362
Clouds, on estimating the Height of, by Photography and the Stereoscope, John Harmer, 194
Clouds, Distance of, Edwin Clark, 244
Clouds, Measuring the Height of, Dr. C. Braun, 458
Clouds, Fogs, Dusts, &c., John Aitken, 195, 384; W. H. Preece, Dr. H. J. H. Groneman, 336
Coal-Dust, Colliery Explosions and, Hon. Rollo Russell, 193
"Coal Fields of Great Britain," Prof. Hull's, 321
Cod, on the Red Colour of Salt, 543
Coffee, Cultivation of, in Gaboon, 299; Liberian, 541; Coffee-Leaf Disease, 354
Collett (Col. H.), Occultation of 73 Piscium, 458
Colliery Explosions, Mr. Plimsoll's Cure for, W. Galloway, 170
Colliery Explosions and Coal-dust, Hon. R. Russell, 193
Colours of British Butterflies, J. Innes Rogers, 435; Rev. W. Clement Ley, 458
Colour, the Eye and Intensity of, 543
Comets: of 1812 and 1815, 21, 542; Discovery of a Comet, 43; Hartwig's Comet (1880 *d*), 43; Comet Finders, 82; the Third, of 1869, 85; Faye's Comet, 115; Swift's Comet, 115, 182, 255, 322, 372, 441; Comets of Hartwig and Swift, 158; a New Comet, 183; Comet 1873 VII., 206; Pechüle's Comet, 207; Winnecke's Comet, 254; Brorsen's Comet in 1842, 298; Encke's Comet in 1881, 396
Communism, Agricultural, in Greece, W. Mattieu Williams, 579
Compass-Bearing, Mode of Masking or Cutting off Sharply by the Light from Revolving Apparatus on any desired, by means of a Reciprocating Screen, Thomas Stevenson, 560
Compressibility of Gases, Herr Roth, 43
Congress of the French Learned Societies, 619
Coniferæ, a Chapter in the History of the, J. Starkie Gardner, 251, 412
Conifers, Dimorphic Leaves of, Dr. Maxwell T. Masters, 267
Conscious Matter, Stewart Duncan, Geo. J. Romanes, F.R.S., 553
Conservatoire des Arts et Metiers, 294
Constable (F.C.), Jelly Fish, 170
Constant, Acoustical, Note on an, W. J. Grey and J. T. Dunn, 146
Contact Electricity, on a Method of Measuring, Prof. Sir William Thomson, F.R.S., 567
Continents always Continents, Prof. James D. Dana, 410
Continuous Motion, Speed Governor for, Prof. J. Ewing, 473

Convolutions in a Human Brain, Concealed Bridging, W. Carter, 556
Coppinger (Dr. R. W.), Rapidity of Growth in Corals, 53; Oceanic Phenomenon, 482
Coral Reefs and Islands, Joseph Le Conte, 77
Corals, Rapidity of Growth in, Dr. R. W. Coppinger, 53
Corean Archipelago, Notes on the Geology of, H. B. Guppy, 417
Corfield's (Prof.) Lectures on Health to Ladies, 231
Corn, Feeding a Gull with, W. A. Forbes, 483
Cornu (Maxime), Phylloxera in France, 127
Cortambert (M. Eugène), Death of, 439
Cossa (Dr. Luigi), Political Economy, 97
Crabs and Actinia, Col. H. Stuart-Wortley, 529
Crannog, Submarine, at Ardmore, 42
Crawford (Consul), at Oporto, on the Disease in the Port Wine District, 20
Crimea, Prehistoric Anthropology of the, N. Mereshkovsky on, 63, 107
Crimea, Phylloxera in the, 253
Crinoids, Interesting New, 377
Criterion of Reality, 144
Crookes (W., F.R.S.), Heat Conduction in Highly Rarefied Air, 234; Viscosity of Gases at High Exhaustions, 421, 443
Cure for Smoke, the New, J. A. C. Hay, 386
Cutler's Company's Hall, Lectures at, 85
Cycles, Barometric, Prof. Balfour Stewart, 237

Dalzell's (Sir John), Anemone, 495
Dana (Prof. James D.), Continents always Continents, 410
Dana's (Edward S.), Text-book of Mechanics, 552
Darwin (Charles F.R.S.), Sir Wyville Thomson and Natural Selection, 32; Homage to, 57, 393; Black Sheep, 193; Movement of Plants, 409; on Vivisection, 583; Movements of Leaves, 603
Darwin (Francis), Physiology of Plants, 178; Alpine Flowers, 333
Darwin (G. H., F.R.S.), on Tidal Friction in Connection with the History of the Solar System, 389
Dawkins (Prof. W. Boyd, F.R.S.), Prehistoric Europe, 309, 361, 482; Extinct British Animals, 431
Dawson (Dr. Geo. M.), Prof. Whitney on the Glaciation of British Columbia, 290; Climate of Vancouver Island, 385
Dawson (J. W., F.R.S.), Geological Relations of Gold in Nova Scotia, 578
Davy (M.), Analysis of the Air at Montsouris, 63
Day (Dr. Francis), Work on Fishes, 107; "Fishes of Great Britain and Ireland," 264
Death, Signs of, 494
Deep-Sea Exploration, J. Gwyn Jeffreys, F.R.S., 300, 324
Deep-Sea Ophiurans, 464
Delesse (Achille), Death of, 516; Obituary Notice of, 535
Dembowski (Baron), Death of, 322
Dent's Chronograph, 59
Development of Human Intelligence, 617
Dew and Fog, 398
Dewar (Prof.), on Atoms, at the Royal Institution, 181
Diamond Mines in India, on the identity of some, especially those mentioned by Tavernier, V. Ball, 490
Dimorphic Leaves of Conifers, Dr. Maxwell T. Masters, 267
Dimorphism of Flowers, New Cases of, Errors Corrected, Dr. Hermann Müller, 337
Disease in Italy, Statistics of, 543
Disinfectant, a New, 374
Distance of Clouds, Edwin Clark, 244
Dobbie (James J.), Oxidation of Quinine, 243
Dodel-Port's (Dr.) "Atlas of Physiological Botany," 157
Dorsetshire, Hailstorm in, Dr. Geo. J. Allman, F.R.S., 146
Dortmund, Shock of Earthquake at, 106
Double Stars, Cincinnati Measures of, 396; Herschel 3945, 591
Dublin, Scientific Societies of, 316
Dudgeon (Dr. R. E.), Temperature of the Breath, 10, 76
Duncan (John), the Alford Weaver-Botanist, Wm. Jolly, 252, 269; Fund for, 317, 491
Duncan (Prof. P. Martin, F.R.S.), Geological Climates, 145; elected President of the Royal Microscopical Society, 418
Duncan's (Stewart) Conscious Matter, Geo. J. Romanes, F.R.S., 553
Duncombe (Cecil), Squirrels Crossing Water, 484
Dundee Naturalists' Society, Annual *Conversazione*, 370
Dunes and Moving Sands, 569
Dunn (J. T.), Note on an Acoustical Constant, 146
Dust, Fogs, and Clouds, John Aitken, 195, 311, 384; W. H. Preece, Dr. H. J. H. Groneman, 336; Hon. Rollo Russell, 267; M. Chatel, 436
Dutch Arctic Cruisers, Zoological Results of, 205
Duveyrier (M. Henri) on the Sources of the Niger, 184
Dynamics of "Radiant Matter," on some Points relating to the, S. Tolver Preston, 461; Wm. Muir, 483
Dynamite, Preparation of, 492
Dynamite Mine, St. Petersburg, 531
"Dytiscidæ, Avis préliminaire d'une Nouvelle Classification de la Famille des," Dr. Sharp, 98

Earth Currents—Electric Tides, 424
Earthquakes: at Valparaiso, 20; Shock, in Southern Austria, 42; in Austria, 63; Shock in the Tyrol, 83; at Agram, 63, 83, 106, 132, 156, 182, 253, 297, 419, 439, 492, 516; Prof. v. Hochstetter on the, 106; Prof. Szabo on, 530; in Scotland and North of Ireland, 106; at Dortmund, 106; British Earthquakes, 117; Prof. J. P. O'Reilly, 170; Dr. Novak on Earthquakes, 156; Prof. Rudolph Falb on, 156, 205; in Germany, 156; at Wiesbaden, 156; in Banjaluka (Bosnia) and in Agram, 182; at Charleville, Ireland, 182; at Brescia, Schloss Trakostyan, and Smyrna, 205; in Roumania, Transylvania, Hungary, &c., 232; at Rousdorf, 253; at Bucharest, 253; Shock at Burmah, 253; at Peshawur, 275; in Switzerland, January 27, 320; in Bologna, Florence, Venice, Padua, Ferrara, &c., 320; at Berne, 348, 396; in the Swiss Jura, information of, 369; at St. Petersburg, 370; at St. Michael's in the Azores, 419; St. Ivan-Zelina, Agram, &c., 439; at Casamicciola in the Island of Ischia, 439, 468, 492, 516; in Switzerland, 468; in Ischia, H. J. Johnston-Lavis, 497; at Chio, 541, 564; Earthquake Warnings, 529; at San Cristobal, 564; Earthquake of November 28, 1880, in Scotland and Ireland, 591
Eaton's "Ferns of North America," J. G. Baker, 479
Eaton (Rev. A. E.), the Oldest Fossil Insects, 507; Winter Gnats (Trichocera), 554
Ebonite, Measuring the Index of Refraction of, Professors Ayrton and Perry, 519
Echinodermata, the Locomotive System of, G. J. Romares, F.R.S., 545
Eclipse, Solar, of December 31, 65
Eclipses, Lunar, 1880–84, 114
Edinburgh: Royal Society, 212, 451, 475, 500, 571, 595
Edison Electric Light in New York, 614
Education in Science, Mr. Mundella on, 134
Education, Introduction of Hypotheses in School, Dr. Hermann Müller on, 157
Egerton (Sir Philip de Malpas Grey), Death of, 541; Obituary Notice of, 579
Eggs, Testing the Age of, 132
Elasticity of Wires, J. T. Bottomley, 281
Electricity: Electric Lighting at London Railway Stations, 64; Incandescent Electric Lights, 104; the Maxim Light, 131; and Navigation on the Rhine, 132; Lighthouses illuminated by Electricity, 347; New Method of Dividing Electric Light, 373; Electric Lighting in the City, 440; Scientific Principles involved in Electric Lighting, Prof. W. Grylls Adams, F.R.S., 580, 605; Electric Light in New York, 614; New Discovery in Electric Induction, 85; Electric Dust Figures, 208; on the Thermic and Optic Behaviour of Gases under the Influence of the Electric Discharge, Dr. Arthur Schuster, F.R.S., 258; a New Electric Motor, 278; Trial of Electric Railways at the Electrical Exhibition, Paris, 296; Electric Discharges in Gases, 397; Electric Tides in Telegraphic Circuits, 346; Electric Tides, Earth Currents, 424; Electrical Thermometer for Determining Temperatures at a Distance, Horace T. Brown, 464; Future Development of Electrical Appliances, Geo. Rayleigh Vicars, 528; Herr Hoorweg on Electricity, 43; Behaviour of Electricity in Gases, Herr Narr, 43; Place du Carrousel to be Lighted with, 254; the Relation between Electricity and Light, Dr. O. J. Lodge, 302; Proposed International Exhibition of Electricity, 84, 320, 347; Seeing by Electricity, 423; a New Mode of obtaining Electricity by Friction, 441; on a Method of Measuring Contact Electricity, Prof. Sir William Thomson, F.R.S., 567; Electricity and Gas as Heating Agents, C. W. Siemens, F.R.S., 326, 351; Molecular Electromagnetic Induction, Prof. D. E. Hughes, F.R.S., 519

Ellis (William), Correspondence of Phenomena in Magnetic Storms, 33; Magnetic Storm of 1880, August, 482
Elongation of Mimas, 255
Elsden (J. Vincent), Microscopic Structure of Malleable Metals, 391
Encke's Comet in 1881, 396
"Encyclopædia Britannica," Vols. X., XI., 119
Endowment of Research in Birmingham, 304
Entomological Collection, the late John Miers', F.R.S., Presentation of, to the Ashmolean Museum at Oxford, 41
Entomological Society, 116, 162, 307, 404, 475, 620
Entomological Society of Belgium, 62
Epidermis of Plants, Chlorophyll in the, 158
Epping Forest and County of Essex Naturalists' Field Club, 20, 276
Equus Prjevalski, 494
Erbium, Atomic Weight of, 86
Erhard (M.), Death of, 19
Ernst (Dr. A.), Some Remarks on *Peripatus Edwardsii*, Blanch, 446
Esparto Grass, Irish, 437
"Ethnographisch-Anthropologische Abtheilung des Museum Godeffroy in Hamburg. Ein Beitrag zur Kunde der Südsee-Völker," J. D. E. Schmeltz und Dr. med. R. Krause, 168
Ethylene, Critical Temperature of, Robert E. Baynes, 186
Etna Observatory, 559
Eucalyptus in Rangoon, 370
Europe, Lava Fields of North-Western, Prof. Arch. Geikie, F.R.S., 3
Europe, Prehistoric, Prof. W. Boyd Dawkins, F.R.S., 309, 361, 482; Dr. James Geikie, F.R.S., 336, 458; Dr. James Geikie, F.R.S., R. H. Tiddeman, 433, 528
Europeans and North American Birds, 277
Everett (Prof. J. D., F.R.S.), a General Theorem in Kinematics, 99
Eves (Florence), Girton and Newnham Colleges, 291
Evolution, Formula of, Prof. Tait on, 78
Evolution, Prof. Huxley on, 203, 227
Ewing (Prof. J.), Speed Governor for Continuous Motion, 473
Exner (Frank), on Thermo-Electricity, 44; a Correction, 170
Exner and Young, Professors, Prof. C. A. Young, 312
Exploration, Deep-Sea, J. Gwyn Jeffreys, F.R.S., 300, 324
Explosion, Recent Gas, Herbert McLeod, F.R.S., 8
Explosions, Colliery, Mr. Plimsoll's cure for, W. Galloway, 170
Explosions, Colliery, and Coal-Dust, Hon. R. Russell, 193
Explosive Gas in a Lake, J. Shaw, 435
"Exposé Historique concernant le Cours des Machines, dans l'Enseignement de l'École Polytechnique," 75
Extinct British Animals, Prof. W. Boyd Dawkins, F.R.S., 431
Eye and Intensity of Colour, 543

Falb (Prof. Rudolph) on Earthquakes, 156, 205
Falls of Niagara in Winter, W. Lant Carpenter, 511
Faraday Lecture, Prof. Helmholtz's, 535
Fascination, L. P. Gratacap, 56; Arthur Nicols, 77; J. T. Brownell, 314; Carl Ochsenius, 508
Faye's Comet, 115
Feeding a Gull with Corn, W. A. Forbes, 483
"Fer Bravais," Experiments on, 86
Ferns of North America, J. G. Baker, 479
Fiji, Baron A. von Hugel's proposed Work on, 45
Finland, Baron Nordenskjöld in, 340
Finland, Algæ of the Gulf of, 494
Firth (Mark), Death of, 106
Fish, Jelly, F. C. Constable, 170
Fish, Flying-, Francis P. Pascoe, 312; R. E. Taylor, 388; Allan D. Broun, 508
Fish-Culture in the United States, 532
"Fishes of Great Britain and Ireland," Dr. Francis Day, 107, 264
Fishes, Dr. Günther, F.R.S., on, 213
Fishes, Birds, and Beetles, Food of, 494
Fishes, British, Frank Buckland, 576
Fisheries, German, Union, Offer of a Prize by the, 205
Fisheries Exhibition at Norwich, 564, 588
Fishery Society, Rhenish, foundation of, at Cologne, 158
Fisher (Dr. Ferd.) appointed Editor of the Jahresbericht für die chemische Technologie, 106
Fisher (Rev. Osmond), "Physics of the Earth's Crust," 131; Aurora of January 31, 329
Flame-Length, Note on, Lewis T. Wright, 527
Flammarion (M.), a Knight of the Légion d'Honneur, 439
Fletcher (Thos), Dr. Siemens' New Cure for Smoke, 91
Flight of the Albatross, Notes on the Mode of, Arthur W. Bateman, 125
"Flora of Plymouth," T. R. Archer Briggs, 74
Florence, Collection of Italian Vertebrates at, 41
Flowers, New Cases of Dimorphism in—Errors Corrected, Dr. Hermann Müller, 337
Fluke in Calves, 244
Fluor-spar, Hankel on, 133
Flying-Fish, Francis P. Pascoe, 312; R. E. Taylor, 388; Allan D. Broun, 508
Fog and Dew, 398
Fogs, Dust, and Clouds, John Aitken, 195, 311, 384; W. H. Preece, Dr. H. T. H. Groneman, 336; M. Chatel, 436; Hon. Rollo Russell, 267
Fogs of London, 165
Food of Birds, Fishes, and Beetles, 494
Forest, Subterranean, in India, 105
Formula of Evolution, Prof. Tait on, 78
Fossil Insects, Oldest, Dr. H. A. Hagen, 483; Rev. A. E. Eaton, 507
France, Phylloxera in, Maxime Cornu, 127
Franz-Josef Land, Exploration of, 278
Free Libraries in Scotland, 64
Freezing Points of Alcoholic Liquids, M. Raout on, 85
Fremy (M.), on Chemistry at the Paris Museum of Natural History, 83
French Institute, Annual Meeting of, 19
French Association, Meeting at Algiers, 319, 491, 515, 541; G. F. Rodwell, 582, 606
French Learned Societies, Congress of, 619
Frere (Sir Bartle) at the Geographical Society's Meeting, 87
Fret, Greek, Alfred C. Haddon, 9
Fritsch's (Dr.) Method of taking Casts of Skeletons, 275
Frost, Vibration of Telegraph Wires during, T. Mellard Reade, 314; F. T. Mott, 338
Frost, the Effects of, on Chemicals, 347
Fryer (John), Acoustics in China, 448
Fungal Growths in the Animal Body, 277

Galloway (W.), Mr. Plimsoll's Cure for Colliery Explosions, 170
"Gardens of the Sun," F. W. Burbidge, 143
Gardner (J. Starkie), Geological Climates, 53, 193; a Chapter in the History of the Coniferæ, 251, 412; Geologising at Sheppey, 293
Garrod (Prof. A. H.), Publication of his Scientific Papers, 491
Gas-Burner, Regenerative, Herr F. Siemens', 131
Gas Explosion, Recent, Herbert McLeod, F.R.S., 8
Gas, Explosive, in a Lake, J. Shaw, 435
Gas-Grate, Dr. Siemens's, Dr. R. Douglas Hale, 145
Gases and Vapours, their Dissolving Power on one another, 86
Gases and Vapours, Spectra of, Influence of Pressure and Temperature on, G. Ciamician, 160
Gas and Electricity as Heating Agents, C. W. Siemens, F.R.S., 326, 351
Gases, on the Thermic and Optic Behaviour of, under the Electric Discharge, Dr. Arthur Schuster, F.R.S., 258
Gases, Viscosity of, at High Exhaustions, W. Crookes, F.R.S., 421, 443
Gaseous Matter, Action of an Intermittent Beam of Radiant Heat upon, Prof. Tyndall, F.R.S., 374
Geelong Vineyards, Phylloxera in the, 181
Gegenbaur's Morphologisches Jahrbuch, 283
Geikie (Prof. Arch., F.R.S.), Lava Fields of North-Western Europe, 3; Mineralogical Society of Great Britain and Ireland, 150; Geology of Bosnia and Herzegovina, 224; Murchison Medal awarded to, 346; Wallace's "Island Life," 357, 391
Geikie (Dr. James, F.R.S.), "Prehistoric Europe," 336, 433
Geography: Geographical Notes, 21, 44, 87, 134, 159, 184, 210, 233, 255, 278, 299, 323, 398, 420, 443, 495, 518, 544, 565; Geographical Results of the Afghan Campaign, Capt. T. H. Holdich, 159; Geographical Societies of the World, 299, *see also* Royal Geographical Society

Geology: Geological Changes of Level, Sir C. Wyville Thomson, F.R.S., 33; Geological Society, 71, 140, 161, 211, 330, 403, 426, 449, 523, 547, 595; Medals Awarded by, 394; Geological Notes, 184; Geological Age of the North Highlands of Scotland, Prof. Edward Hull, F.R.S., 289; Geological Climates, Prof. Samuel Haughton, F.R.S., 8, 98, 145, 241, 290, 313, 384; Prof. P. Martin Duncan, F.R.S., 145; Dr. A. Woeikoff, 241, 362; J. J. Murphy, 290; J. Starkie Gardner, 53, 193; Alfred R. Wallace, 124, 217, 266; Dr. Maxwell T. Masters, 266; William Ingram, 160; Dr. John Rae, F.R.S., 337; Geology of East Central Africa and the Subterranean Forest in Bombay, W. T. Blanford, 145; Geological Survey of Belgium, 184; Geology of Bosnia and Herzegovina, Prof. Archd. Geikie, F.R.S., 224; Geologising at Sheppey, J. Starkie Gardner, 293; Geology of the Corean Archipelago, H. B. Guppy, 417; International Geological Congress, C. E. de Rance, 510; Geological Relations of Gold in Nova Scotia, J. W. Dawson, F.R.S., 578
Geometrical Optics, W. G. Logeman, 125; Phenomena of, 372
Geometrical Teaching, 414
German Rivers, the Quantities of Water in, 94
German Fisheries Union, Offer of a Prize by the, 205
German Chemical Society, 436
Gifford (Lord) on Scientific Education, 64
Giglioli (Prof. H. H.), *Lophiomys Imhausi*, 291
Gilmour (Rev. James), Mongol Doctors, 132
Girton and Newnham Colleges, Florence Eves, 291
Glaciers, Retrograde Motion of, Herr W. Gröbner on, 181
Glaciation of British Columbia, Prof. Whitney on, Geo. M. Dawson, 290
Gladstone (Dr. J. H., F.R.S.), the Refraction Equivalents of Carbon, Hydrogen, and Nitrogen in Organic Compounds, 378
Glasenap (M.), on Refraction, 373
Glasgow, Naval and Marine Engineering Exhibition at, 41
Gleanings, Nile, 526
Goat with Two Kinds of Wives, 277
Gnats, Winter (Trichocera), Rev. A. E. Eaton, 554
Godeffroy Museum at Hamburg, 320
Godwin Austen (H. H.), Squirrel Crossing Water, 340
Gold in Newfoundland, 472
Gold in Nova Scotia, Geological Relations of, J. W. Dawson, F.R.S., 578
Gore (J. E.), Variable Stars, 362
Göttingen Royal Society of Sciences, 356
Gould (John, F.R.S.), Death of, 346; Obituary Notice of, 364; his Ornithological Collections, 491
Grahame Medal, 19, 181
"Grallatores and Natatores of the Estuary of the Tay," 516
Grasshoppers in Russia, 157
Grataciap (L. P.), Fascination, 56
Greece, Agricultural Communism in, W. Mattieu Williams, 572
Greek Fret, Alfred C. Haddon, 9
Grey (W. J.), Note on an Acoustical Constant, 146
Grigorieff (M.), on Japanese Gardens, 205
Gröbner (Herr W.), Retrograde Motion of Glaciers, 181
Groneman (Dr. H. T. H.), Height of the Aurora, 56; Dust, Fogs, and Clouds, 337
Groves (Thos. B.), Phosphorescence of the Sea, 411
"Guaco" and Snake-bites, 182
Guamarus pulex, 419
Guenée (Achille) Death of, 252
Gull, Feeding a, with Corn, W. A. Forbes, 483
Günther (Dr., F.R.S.), on Fishes, 213
Guppy (H. B.), the Yang-tse, the Yellow River, and the Pei-ho, 35, 99; Notes on the Geology of the Corean Archipelago, 417; Banks of the Yang-tse at Hankow, 507; Oceanic Phenomenon, 507
Gyrostat, a Liquid, 69

Habich (E. J.), "Études géométriques et cinématiques," &c., 603
Haddon (Alfred C.), Greek Fret, 9
Hagen (Dr. H. A.), Oldest Fossil Insects, 483
Hailstones, Remarkable, Col. Foster Ward on, 233
Hailstorm in Dorsetshire, Dr. George J. Allman, F.R.S., 146
Hale (Dr. R. Douglas), Dr. Siemens' Gas Grate, 145
Hampe (Prof. Ernst), Death of, 156
Hand, Skin-furrows of the, Sir W. J. Herschel, 76
Hankow, Banks of the Yang-tse at, H. B. Guppy, 507
Hannay (J. B.), Hot Ice, 504
"Harcourt and Madan's Chemistry," 181
Harmer (John), on Estimating the Height of Clouds by Photography and the Stereoscope, 194; Aurora of January 31, 329
Hartwig's Comet (1880 *d*), 43
Hartwig and Swift, Comets of, 158
Harvard College, U.S., Observatory of, 321
Haughton (Prof. Samuel, F.R.S.), Geological Climates, 8, 98, 145, 241, 290, 384
Hay (J. A. C.), New Cure for Smoke, 360, 386
Hay (Col. Drummond), Birds of the Estuary of the Tay, 516
Heart, Blood-Vessels of Valves of the, 159
"Hear, Easy Lessons in," C. A. Martineau, 32
Heat of Formation of a Compound, A. P. Laurie, 35
Heat Conduction in Highly Rarefied Air, W. Crookes, F.R.S., 234
Heat of Stellar Masses, Samuel J. Wallace, 579
Heintz (Dr. Wilhelm), Death of, 181; Obituary Notice of, 245
Heller (Prof. Karl B.), Death of, 205
Helmholtz's (Prof.) Faraday Lecture, 535
Henslow (Rev. George), Regelation, 11; "Botany for Children," 241
Herculaneum, Discovery by Prof. Giuseppe Novi of a Magnificent Bathing Establishment near, 182
Herring, Prof. Huxley, F.R.S., 607
Herschel (Sir W. J.), Skin-furrows of the Hand, 76
Herschel's First Observation of Uranus, 299
Herschel (Sir William), J. R. Hind, F.R.S., 429, 453, 573
Herschel 3945, the Double Star, 591
Herschel (Prof. A. S.), Infusible Ice, 383
Herzegovina and Bosnia, Geology of, Prof. Archd. Geikie, F.R.S., 224
Herzen (Herr A.), Acetous Fermentation, 86
Hewitt (William), "Class-Book of Elementary Mechanics," 53
Highbury Microscopical and Scientific Society, 64
Highlands, North, of Scotland, Geological Age of, Prof. Edward Hull, F.R.S., 289
Hill (S. A.), Barometric and Solar Cycles, 409; Indian Winter Rains, 604
Hincks (T., F.R.S.), "A History of British Marine Polyzoa," 31
Hind (J. R., F.R.S.), Sir William Herschel, 429, 453, 573
Histology, Atlas of, 382
Hochstetter (Prof. v.) on the Agram Earthquake, 106
Hodgson (Brian Houghton, F.R.S.), Presentation of Drawings to the Anthropological Institute, 107
Holdich (Capt. T. H.), Geographical Results of the Afghan Campaign, 159
Holub (Dr.), on the Art Faculty of the Australians, 20; Proposed Journey Across Africa, 22
Hoorweg (Herr), on Electricity, 43
Hörner (F.), Aurora and Electric Storm of January 31, 348
Hot Ice, *see* Ice
Hubbard (Fred.), Squirrels Crossing Water, 484
Hugel (Baron A. von), Proposed Work on Fiji, 45
Hughes (Prof. McK.), Scientific Use of the Late Severe Weather, 346
Hughes (Prof. D. E., F.R.S.), Molecular Electro-magnetic Induction, 519; Permanent Molecular Torsion of Conducting Wires produced by the Passage of an Electric Current, 569
Hull (Prof. Edward, F.R.S.), Geological Age of the North Highlands of Scotland, 289
Hull's (Prof.) "Coal-Fields of Great Britain," 321
Human Brain, Concealed Bridging Convolutions in a, W. Carter, 556
Human Intelligence, Development of, 617
Humblot (M. Léon), Return to Paris from Madagascar, 41
Humboldt Institution for Natural Research and Travel, 371
Hungary, Earthquake Shock in, 232
Hunterian Lectures, the, 395
Hutton (F. Wollaston), "Manual of the New Zealand Mollusca," 7
Huxley (Prof. T. H., F.R.S.), First Volume of the Publications of the *Challenger*, 1; *Challenger* Publications, 33; on Evolution, 203, 227; Appointed to the Inspectorship of Fisheries, 275; Herring, 607
Hydrochloric Acid, the Influence of, on Metallic Chlorides, 397
Hypotheses in School Education, Introduction of, Dr. Hermann Muller, 157

Ice, Hot, 34; Prof. John Perry, 288; Dr. Oliver J. Lodge, 264, 504; J. B. Hannay, 504; Geo. B. Richmond, 504; Ice intrusive in Peat, T. Mellard Reade, 339; Experiments on Ice

under Low Pressures, Dr. Thos. Carnelley, 341; Infusible Ice, Prof. A. S. Herschel, 383; Ice-Casts of Tracks, J. T. Brownell, 484
Incandescent Electric Lights, 104
Index of Refraction of Ebonite, Measuring the, Professors Ayrton and Perry, 519
India, Subterranean Forest in, 105; on the Identity of some Ancient Diamond Mines in, especially those mentioned by Tavernier, V. Ball, 490; Australian Plants in, Dr. G. Bidie, 555
Indian Empire, Census of the, 419
Indian, American, Languages, A. H. Keane, 503
Indian Winter Rains, S. A. Hill, 604
Indians of Southern California, 253
Indigo, 390
Indo-Chinese and Oceanic Races—Types and Affinities, A. H. Keane, 199, 220, 247, 271
Indo-Chinese and Oceanic Races, Classification of the, H. J. Murton, 508; A. H. Keane, 529
Induction Current from Leyden-Jar Discharge, W. Larden, 529
Infinity, Disturbing, in Lord Rayleigh's Solution for Waves in a Plane Vortex Stratum, Sir William Thomson, 45, 70
Infusible Ice, Prof. A. S. Herschel, 383
Infusoria, a Manual of the, W. Saville Kent, 264
Ingleby (Dr. C. M.), Auroral Phenomena, 363
Ingram (William), Geological Climates, 169
Inherited Memory, an Experiment on, W. Mattieu Williams, 508
"Injurious Insects, Notes of Observations of," Eleanor A. Ormerod, 432
Innes (Cosmo), Dr. Siemens' New Cure for Smoke, 91
Innsbruck, Inverted Rainbow seen at, 157
"Insects, Aid to the Identification of," 98
"Insects, Injurious, Notes of Observations of," Eleanor A. Ormerod, 432
Insects, Organs of Smell in, 440
Insects, Oldest Fossil, Dr. H. A. Hagen, 483; Rev. A. E. Eaton, 507
Instinct, Aberration of, Geo. J. Romanes, F.R.S., 433; Rev. T. H. Waller, 484
Institution of Civil Engineers, 162, 212, 308, 356, 380, 451, 475, 524, 595
Integral Calculus, Elementary Treatise on, B. Williamson, F.R.S., 241
Intelligence, Development of Human, 617
Intensity of Colour, the Eye and, 543
International Medical Congress, 418
International Geological Congress, C. E. de Rance, 510
Iodide of Lead, Coefficients of Expansion of, 594
Ireland, North of, Earthquake Shocks felt in, 106
Ireland and Scotland, Earthquake of November 28, 1880, in, 591
Irish Esparto Grass, 437
Iron and Steel Institute, 491; Annual Meeting of the, 614
Ischia, Earthquake in, H. J. Johnston-Lavis, 497
Isoetes lacustris, 544
"Island Life," Correction of an Error in, Alfred R. Wallace, 195
"Island Life," Prof. Arch. Geikie, F.R.S., 357, 391
Isopods, Marine, of New England, 543
Isotherms of the North of Europe, 470
Italy, Statistics of Disease in, 543

Jablochkoff Light, Introduction of, by M. Hervé-Mangon, into the Conservatoire, Paris, 64; at Victoria and Charing Cross Stations, 64
Jacob (F.), Improved Arrangement of Scale for Reflecting Instruments, 527
Jahrbücher für wissenschaftliche Botanik, 288
Jamaica Cinchona Barks, Superiority of, Mr. Morris, 157
Jamaica Public Gardens, 614
Janson's Star of 1600, 276
January, Birds laying in, J. H. Willmore, 314
Japan, 600; Recent Works on, II., 12; Contributions to the Agricultural Chemistry of, 456; M. Grigorieff on Japanese Gardens, 205
Jeffreys (Dr. J. Gwyn, F.R.S.), New Zealand Molluscs, 7; Deep-Sea Exploration, 300, 324
Jelly-fish, F. C. Constable, 170
Jentink (F. A.), Squirrels Crossing Water, 388
Jevons (W. Stanley, F.R.S.), the August Auroras, 148; Recent Mathematico-Logical Memoirs, 485
Jochenstein, Discovery of Bronze Implements at, 157
Johns Hopkins University Fellowships, 259
Johnston, Keith, and Thomson's African Expedition, 38
Johnston-Lavis (H. J.), Earthquake in Ischia, 497
Jolly (William), John Duncan, the Alford Weaver and Botanist, 269
Jones (Thomas Rymer, F.R.S.), Obituary Notice of, 174
Journal of the Indian Archipelago, 42
Journal de Physique, 47, 115, 235, 402, 449, 594
Journal of the Russian Physical and Chemical Society, 95
Journal of the Franklin Institute, 115, 211, 402, 449
Journal of Anatomy and Physiology, Normal and Pathological, 161, 378
Journal of the Royal Microscopical Society, 161, 259, 449
Journal and Proceedings of the Royal Society of New South Wales, 401
Journal of the Asiatic Society of Bengal, 449
Journal of Physiology, 449
Jupiter, Condition of, J. Rand Capron, 34; Near Appulse of, to a Fixed Star, 158, 170; Occultation of 73 Piscium by, 183; Red Spot upon Jupiter's Disk, 517
Jupp (H. B.), Localisation of Sound, 386

Kaltbrunner (D.), "Aide-Mémoire du Voyageur," 217
Kant (Immanuel), Marble Bust of, 205
Keane (A. H.), "Max Müller and the Philosophy of Language," 30; "Philosophy of Language," Ludwig Noiré, 124; Indo-Chinese and Oceanic Races—Types and Affinities, 199, 220, 247, 271; American-Indian Languages, 503; Classification of the Indo-Chinese and Oceanic Races, 529
Keene (T. H.), "Practical Fisherman," 603
Kent (W. Saville), "A Manual of the Infusoria," 264
Kent's Cavern Committee, 296
Kew Gardens Report, 22
Kew Museums, Enlargement of, 564
Kiew, Russo Byzantine Antiquities found near, 321
Kinahan (G. H.), Aurora Observed at Ovoca, co. Wicklow, November 3, 100; Aurora and Electric Storm of January 31, 348; Auroric Light, 410
Kinahan (Gerrard A.), Aurora and Electric Storm of January 31, 348
Kinematics, a General Theorem in, Geo. M. Minchin, 62, 170; Prof. J. D. Everett, F.R.S., 99; J. J. Walker, 125
King (Capt. H., R.N.), Instances of Fascination, 84
King (Clarence), Resignation of, 540
Kingfisher, the Great, and Snakes, 298
Knowles (W. J.), Minerva Ornaments, 411
Köliker (Albert), on Animal Development, 480
Kosmos, 47, 211
Krefft (Gerard), Death of, 589
Krause (Dr. Ernst), "Unconscious Memory," Mr. Samuel Butler, 288
Krause (Karl Christian Friedrich), Centenary of the Birth of, 371
Kuhlmann (Charles Frederick), Obituary Notice of, 316
Kuntze (Dr. Otto), Sargassum, 70, 146
Kweichow, Opium Harvest at, Mr. Baller on, 158

Lake Leman, Warm Winter at, 254
Lamp, Prize for the Invention of a New, 347
Land, Subsidence of, Caused by Natural Brine Springs, Thos. Ward, 388
Landslips: Thos. Ward, 144; the Cheshire Subsidences, T. Mellard Reade, 219
Language, Philosophy of, Ludwig Noiré, A. H. Keane, 124
Lankester (Prof. E. Ray, F.R.S.), Natural Conditions and Animal Life, 405
Larden (W.), Soaring of Birds, 77; Induction-Current from Leyden-jar Discharge, 529
Latzel (Dr. Robert), Austrian Myriopods, 167
Laurie (A. P.), Heat of Formation of a Compound, 35
Lava Fields of North-Western Europe, Prof. Arch. Geikie, F.R.S., 3
Leaves, Movements of, M. L. Rouse, 195; Charles Darwin, F.R.S., 603
Lécard (M.), Death of, 181
Le Conte (Prof. Joseph), Coral Reefs and Islands, 77; on the Space Protected by Lightning-conductors, 386
Leichhardt, Discovery of Relics of, 420, 443

Leipzig, Proposed Zoological Garden at, 253
Level, Geological Changes of, Sir C. Wyville Thomson, 33
Level of the Sea, on the Practicability of Living at Great Elevations above the, Edward Whymper, 459
Leverrier and his Theory of Saturn, 298
Ley (Rev. W. Clement), Colours of British Butterflies, 458
Leyden-jar Discharge, Induction Current from, W. Larden, 529
Libya, the Languages of, 84
Libyan Desert, Dr. Karl Zittel on, 19
"Life and her Children: Glimpses of Animal Life from the Amœba to the Insects," Arabella B. Buckley, 123
Light, Easy Lessons in, Mrs. W. Awdry, 32
Light and Electricity, the Relation between, Dr. O. J. Lodge, 302
Light and the Transpiration of Plants, 159
Lighthouses, Lighting by Electricity, 296, 347
Lightning Conductors: Richard Anderson on, 296; on the Space protected by, Prof. J. Le Conte, 386
Limmat, Dredging the Bed of the, 297
Lindsay (Dr. Lauder), Death of, 131
Linnean Society, 71, 115, 330, 379, 426
Liquids: the Rapidity of the Evaporation of, 86; Viscosity of, 397
Liquids and Solids at High Temperatures, John Aitken, 34
Livadia, Russian Imperial Yacht, 27; the Accident to, 63
Liveing (Prof. G. D., F.R.S.), on the Spectrum of Carbon, 265, 338
Liverpool College of Chemistry, Re-opening of, 468
Living at Great Elevations above the Level of the Sea, on the Practicability of, Edward Whymper, 459
Livingstone, Life of, by W. Garden Blaikie, D.D., 238
Lizard, the Horned, of Australia, 402
Lloyd (Rev. Humphrey), Death of, 275; Obituary Notice of, 292
Localisation of Sound, H. B. Jupp, 386
Lockyer (J. Norman, F.R.S.), on the Iron Lines Widened in Solar Spots, 425
Locusts, the Natural Enemies of, 565
Lodge (Dr. Oliver J.), Dr. Carnelley's Hot Ice, 264, 504; the Relation between Light and Electricity, 302
Logeman (W. G.), Geometrical Optics, 125
Logic, Symbolical, Hugh MacColl, 578
London, Smokeless, W. D. Scott Moncrieff, 151, 193; W. Mattieu Williams, 169; Average Height of Barometer in, 184; Fogs of, 165
London Mathematical Society, 577
Loomis (Prof.), Storm Centres in Tropical Regions, 322
Lophiomys Imhausi, Prof. H. H. Giglioli, 291
Lorenz (Prof.), on his Theory of "Refraction-Constants," 43
Low Temperature, Rev. S. J. Perry, F.R.S., 268
Lowe (E. J.), Aurora and Electric Storm of January 31, 348
Löwenberg's "Geschichte der geographischen Entdeckungsreisen im Alterthum und Mittelalter," 481
Lubbock (Sir J., Bart., F.R.S.), Observations on Ants, Bees, and Wasps, 255
Lunar Eclipses, 1810-84, 114
Lunge (Prof. George), "Sulphuric Acid and Alkali," Prof. H. E. Roscoe, F.R.S., 73

MacColl (Hugh), Symbolical Logic, 578
Mackay, the Town of, 492
McLaurin (Dr. William), Temperature of the Breath, 244
Maclay (Dr. Miklukho), his Travels, 44
MacLennan (D.), Primitive Marriage Customs, 584
McLeod (Herbert, F.R.S.), Recent Gas Explosion, 8
McNally (Dr. C. J.), Temperature of the Breath, 217, 244
MacOwan (Prof.) appointed Director of the Botanic Garden, Cape Town, 231
Madagascar, Plants of, J. G. Baker, 125
Magellan Straits, Post Office in, 254
"Magic Mirrors," French, 616
Magnetic Storms, Correspondence of Phenomena in, W. Ellis, 33
Magnetic Storm of 1880, August, William Ellis, 482
Magnetic Variation or Declination, on some Recent Charts and Maps of Curves of Equal, 314
Magnetic Survey of the Missouri, Prof. Francis E. Nipher, 583
Magnetic Declination, Prof. Balfour Stewart, F.R.S., 592
Maderen (M. van), Death of, 516
Malleable Metals, Microscopic Structure of, J. Vincent Elsden, 391
Mammee Apples, Exportation of, 65
Man, Palæolithic, Worthington G. Smith, 604
Manchester: Literary and Philosophical Society, 236, 475
Manchester Field Naturalists' Society, 370
Maps, United States Weather, 1878, 39
Mariette (M.), "Mariette Bey," Death of, 320
Marine Isopods of New England, 543
Markham (Albert H.), a Polar Reconnaissance, 455
Marriage Customs, Primitive, D. MacLennan, 584
Marsden's "List of British Birds," 467
Martineau (C. A.), Easy Lessons in Heat, 32
Masters (Dr. Maxwell T.), Geological Climates, 266; Dimorphic Leaves of Conifers, 267
Mathematical Society, 71, 161, 283, 379, 474, 577, 594
Mathematico-Logical Memoirs, Recent, Prof. W. Stanley Jevons, F.R.S., 485
Mauritius, Meteorological Observations at, for 1877, 322
Mauritius, Zoological Results of Prof. K. Möbius's Visit to, H. N. Moseley, F.R.S., 514
Maxim Electric Light, 131
Mechanics, Class-Book of Elementary, William Hewitt, 53
Mechanics, Text-Book of, Edward S. Dana, 552
Medical Catalogue, a, 28
Medical Etiquette in Paris, a Case of, 64
Medical Gymnasium, Paris, 297
Mémoires de la Société des Sciences Physiques et Naturelles de Bordeaux, 433
Memoirs of the St. Petersburg Society of Naturalists, 474
Memory, Unconscious, Samuel Butler, Geo. J. Romanes, F.R.S., 285; S. Butler, Dr. Ernst Krause, 288; S. Butler, 312; Butler's, Geo. J. Romanes, F.R.S., T. R. R. Stebbing, 335
Memory, an Experiment on Inherited, W. Mattieu Williams, 508
Memphis, Discovery of Two Pyramids to the North of, 297
Mendeleef (Prof.), and the St. Petersburg Academy, 156, 205
Mercadier's Researches on the Photophone, 366
Meredith (Louisa Anne), "Tasmanian Friends and Foes: Feathered, Furred, and Finned," 143
Mereshkovsky (M.), Prehistoric Anthropology of the Crimea, 63, 107
Mesembrianthemum, not Mesembryanthemum, 158
Messina, Tea Plantation Established near, 254
Metallurgy, Introductory Lecture to the Course of, at the Royal School of Mines, Prof. W. Chandler Roberts, F.R.S., 65
Metals, the Conduction of Electricity and Heat in, 44
Metals, Microscopic Structure of Malleable, J. Vincent Elsden, 391
Meteorology: Meteorological Society, 96, 211, 307, 427, 500, 620; Meteorological Notes, 183, 322, 470; State of Meteorology in United States, 183; Average Height of Barometer in London, 184; E. Douglas Archibald, 243; Prof. Loomis on Storm Centres in Tropical Regions, 322; Dr. Meldrum's Observations at Mauritius, 1877, 322; the Recent Severe Weather, 329, 363, 411; Siberian Meteorology, Dr. A. Woeikof, 437; Meteorology in Mexico, 489; Meteorological Observatory at Port-au-Prince, Haiti, 516, *see also* Barometer
Meteors, 516; Rev. S. J. Perry, F.R.S., 34; M. A. Veeder, 147; November Meteors, 158; J. Parnell, 508
Meteoric Stone, Fall of, at Wiener Neustadt, 297
Metz Geological and Archæological Society, Details of the Roman Antiquities found near Metz, 321
Mexico, Meteorology in, 489
Miao-tze Tribes of China, 518
Microphone, M. Boudet's New, 278
Microscopical Society, *see* Royal
Microscopic Structure of Malleable Metals, J. Vincent Elsden, 391
"Midgets," Abnormal Dentition of the, 419
Migration of the Wagtail, 529; Prof. E. W. Claypole, 387; Dr. John Rae, F.R.S., 411
Migration of Birds, 484
Mills (Dr. Edmund J., F.R.S.), Nature of the Chemical Elements, 193
Milne-Edwards (M.), Medal presented to, 83, 564
Mimas, Elongation of, 255
Minchin (George M.), a General Theorem in Kinematics, 62, 170
Mind in Animals, Geo. J. Romanes, F.R.S., 501

Mineral Resources of Newfoundland, Alex. Murray, 46
Mineralogical Society of Great Britain and Ireland, Prof. Arch. Geikie, F.R.S., 150, 212; General Meeting, 182
Minerva Ornaments at Troy, and Net-Sinkers, Prof. E. W. Claypole, 292; W. J. Knowles, 411
Minerva Club, 297
Mines, Cause of Accidents in, 320
Mines, Ventilation of, 517
Minimum Energy, on an Experimental Illustration of, Sir William Thomson, F.R.S., 69
Minor Planets, 517; in 1881, 396
Missouri, Magnetic Survey of, Prof. Francis E. Nipher, 583
Mitchell (Arthur), "Past in Present, What is Civilisation?" 166
Mitchinson (A. W.), "The Expiring Continent," 399
"Mock Sun," J. E. H. Peyton, 314
Moebius (Prof. K.), Zoological Results of his Visit to Mauritius, H. N. Moseley, F.R.S., 514
Molecular Electromagnetic Induction, Prof. D. E. Hughes, F.R.S., 519
Molison (A. R.), Photophone, 78
Moll (M.), Death of, 156
Molloy (Gerald), "Outline of a Course of Natural Philosophy," 32
Molluscs, New Zealand, Dr. J. Gwyn Jeffreys, F.R.S., 7
Moncrieff (W. D. Scott), Smokeless London, 151
Montsouris, Analysis of the Air at, by M. Davy, 63
Montsouris Observatory *Annuaire*, 469
Mont Cenis Tunnel, New Entrance to, 253
Montgolfier (Mdlle. de), Death of, 181
Mont Pourri, Avalanche from, 396
Mook (Dr. Fr.), Death of, 234
Morren's (Prof. E.), Correspondance Botanique, 253
Morris (Mr.), Superiority of Jamaica Cinchona Bark, 157
Moseley (H. N., F.R.S.), Zoological Results of Prof. K. Moebius' Visit to Mauritius, 514
Mott (F. T.), Vibration of Telegraph Wires during Frost, 338
Movements of Leaves, M. L. Rouse, 195
Movements of Plants, Charles Darwin, F.R.S., 409
Muir (William), Dynamics of "Radiant Matter," 483
Müller's (Dr. Fritz), "Ueber die von den Trichopterenlarven der Provinz Santa Catharina verfertigen Gehäuse," 192
Müller (Dr. Hermann), Introduction of Hypotheses in School Education, 157; New Cases of Dimorphism in Flowers, Errors Corrected, 337
Müller (Prof. Max), and the Philosophy of Language, A. H. Keane, 30; at University College, 381
Mulsant (Etienne), Death of, 107
Multiple Centres of Species, Cave Animals and, D. Wetterhan, 458
Mundella (Right Hon. A. J.), on Education, 106, 134
Murphy (Joseph John), Geological Climates, 290
Murray (Alex.), Mineral Resources of Newfoundland, 46
Murton (H. J.), Classification of the Indo-Chinese and Oceanic Races, 508
Museums, Opening of, on Sundays, 395
Museum, New, of Natural History, 549, 577
Music, Photophonic, 124
Musk Deer, 36
Myriopods, Austrian, Dr. Robert Latzel, 167

Nägeli (Carl von), the Works of, Sydney H. Vines, 78
Naini Tal Landslip, 184
Naphtha Region of the Apsheron Peninsula, 42
Naples, Zoological Station at, 315, 418
Narr (Herr), Electricity in Gases, 43
Natural Conditions and Animal Life, Prof. E. Ray Lankester, F.R.S., 405
"Natural" Experiment in Polarised Light, Charles T. Whitmell, 268
Natural History, Cassell's, 317
Natural History, New Museum of, 549, 577
Natural Philosophy, Outlines of a Course of, Gerald Molloy, 32
Natural Science for Women, Alfred W. Bennett, 195
Natural Selection, Sir Wyville Thomson and, Charles Darwin, F.R.S., 32, 53
Naumann, Monument to, in the Schlossgarten at Köthen, 205
Naval Architects, 568
Naval and Marine Engineering Exhibition at Glasgow, 41
Navigation, Electric Light and, on the Rhine, 132
Net-Sinkers, Minerva Ornaments at Troy *v.*, Prof. E. W. Claypole, 292
New England, Marine Isopods of, 543
New Guinea, Alfred R. Wallace, 152, 175; Salvadori's Ornithology of, 243
New Zealand Molluscs, Dr. J. Gwyn Jeffreys, F.R.S., 7
New Zealand, the Forests of, 65
Newcastle Libraries, Catalogue of, 262
Newfoundland: Mineral Resources of, Alex. Murray, 46; Gold in, 472
Newton (Prof. Alfred, F.R.S.), British Birds, 287; "The Oldest Picture in the World," 555
Niagara, Falls of, in Winter, W. Lant Carpenter, 511
Niépce (Nicephore), Statue of, 296
Nice Observatory, Information regarding, 156
Nicols (Arthur), Fascination (?), 77
Niger, the Discovery of the Sources of, 87
"Niger and the Benueh: Travels in Central Africa," Adolphe Burdo, 169
Niger, Sources of the, M. Henri Duveyrier on, 184
Nile Gleanings, 526
Nipher (Prof. Francis E.), Magnetic Survey of Missouri, 583
Nordenskjöld's (Baron) Arrival at St. Petersburg, 231; at the Meeting of the Russian Geographical Society, 299; in Finland, 340
Noiré (Ludwig), "Max Müller and the Philosophy of Language," A. H. Keane, 30; Philosophy of Language, A. H. Keane, 124
North American Pinnipeds, J. A. Allen, 261
North American and European Birds, 277
North America, Ferns of, D. C. Eaton, J. G. Baker on, 479
Northern Microscopist, 440
Northern Thuringia, Formation of a Botanical Society for, 181
Nova of 1600, the So-called, 371
Nova Scotia, Geological Relations of Gold in, J. W. Dawson, F.R.S., 578
Novak (Dr.), on Earthquakes, 156
November Meteors, 158

Oberthür's "Études d'Entomologie," 84
Observatories: M. Tripier appointed Director of the Algiers, 107; Nice, 156; Harvard College, U.S., 321; Paris, 533; Etna Observatory, 559
Occultation (?) of 73 Piscium by Jupiter, 183; Col. H. Collett, 458
Oceanic Races, Indo-Chinese and, Types and Affinities, A. H. Keane, 199, 220, 247, 271
Oceanic Races and Indo-Chinese, Classification of the, H. J. Murton, 508; A. H. Keane, 529
Oceanic Phenomenon, Dr. R. W. Coppinger, 482; H. B. Guppy, 507
Ochsenius (Carl), Fascination, 508
Oeltzen, the Star 17681, Prof. Edward C. Pickering, 338
"Oldest Picture in the World," Prof. Alfred Newton, F.R.S., 555
Oleomargarine, 469
Oliver (Capt. S. P.), Les Lettres d'Outre-Mer, 434
Ophiurans, Deep-Sea, 464
Opium Harvest at Kweichow, Mr. Baller on, 158
Optics, Geometrical, 125, 372
Optical Telegraph, an, 372
O'Reilly (Prof. J. P.), British Earthquakes, 170
Ormerod (Eleanor A.), "Notes of Observation of Injurious Insects," 432
Ornithology of New Guinea, Salvadori's, 240
Oscillations, Periodic, of Barometric Pressure, Dr. J. Allan Broun, F.R.S., 556
Outre-Mer, Les Lettres d', Capt. S. P. Oliver, 434
Owen (Prof., F.R.S.), on the Horned Lizard of Australia, 402
Oxford, Proposed New Statutes, 23, 115; Report of Oxford University Commission, 466, 471, 509
Oxidation of Quinine, Dr. W. Ramsay and J. J. Dobbie, 243
Oxygen and Ozone, 207
Ozone, 125, 363; J. Rand Capron, 219; Liquefaction of, 86; Ozone and the Colour of the Sky, 373

Palestine, Eastern, Exploration of, 495
Palladium, the Elasticity of, 133
Palæolithic Man, Worthington G. Smith, 604

Palliser (J. W.), "Complete Course of Problems in Practical Plane Geometry," 264
Paola, Earthquake at, 614
Parallax, Solar, 441, 493, 598
Parhelion, J. Rand Capron, 291
Paris: Academy of Sciences, 24, 48, 72, 116, 140, 163, 187, 236, 255, 260, 283, 308, 332, 356, 380, 428, 451, 466, 476, 493, 518, 524, 548, 572, 596, 620; Muséum d'Histoire Naturelle, 63; M. Fremy on Chemistry at, 83; a Case of Medical Etiquette in, 64; Paris Observatory, 533; the Object-glass of the New Telescope, 64; Annual *Soirée* at, 346; Proposed International Congress of Electricians at, 84, 347, 369, 439; Medical Gymnasium in, 297; the Time of Day in, 367
Parnell (J.), Meteors, 508
Pascoe (Francis P.), the Thresher, 35; Flying-fish, 312
"Past in the Present, What is Civilisation?" Arthur Mitchell, 166
Pankhurst (E. Alloway), Sound of the Aurora, 464
Peal (S. E.), Soaring of Birds, 10; Pile Dwellings, 218
Peat, Ice Intrusive in, T. Mellard Reade, 339
Pechüle's Comet, 207
Pei-ho, the Yang-tse and the Yellow River, Dr. A. Woeikof, 9; H. B. Guppy, 35, 99
Pengelly (William, F.R.S.), Climate of Vancouver Island, 267; Proposed Portrait of, 540
Periodic Oscillations of Barometric Pressure, Dr. J. Allan Broun, F.R.S., 556
Peripatus Edwardsii, Blanch, some Remarks on, Dr. A. Ernst, 446
Pernitric Acid, 470
Perry (Rev. S. J., F.R.S.), Meteor, 34; Low Temperature, 268; Aurora and Electric Storm of January 31, 348
Perry (Prof. John), Wire Torsion, 35; Hot Ice, 288; Measuring the Index of Refraction of Ebonite, 519
Perseids in August, 1880, 372
Peruvian Antiquities, W. Reiss and A. Stübel, 75
Peruvian Bark, 189
Peshawur, Earthquake at, 275
Petermann's Mittheilungen, 87, 185, 279, 399, 566, 495
Peyton (J. E. H.), Mock Sun, 314
Phenomena in Magnetic Storms, Correspondence of, W. Ellis, 33
Phenomenon, Oceanic, Dr. R. W. Coppinger, 482
Philippines, Report on the, 299
Philosophy of Language, Max Müller and, A. H. Keane, 30
Philosophy of Language, Ludwig Noiré, 124; A. H. Keane, 124
Phonograph, a New Kind of, 441
Phonograph, Enlarged Impressions from, 373
Phosphorescence of the Sea, Thos. B. Groves, 411
Phosphorescent Centipedes, B. E. Brodhurst, 99
Photographic Society, 163, 235, 355, 428, 524
Photography and the Stereoscope, on Estimating the Height of Clouds by, John Harmer, 194
Photometer, Dr. Fuchs' New, 278; a New Centigrade, 442
Photophone: Prof. Graham Bell's, 15; Shelford Bidwell on, 58; Experiments with the, Prof. Graham Bell and M. Janssen, 86; a Foreshadowed Photophone, 63; A. R. Molison on, 78; Lord Rayleigh, F.R.S., on, 274; Prof. Silvanus P. Thompson on, 331; Photophone Experiments, 354; Mercadier's Researches on the Photophone, 366; Herbert Tomlinson on, 457; Photophonic Music, 124
Phylloxera in France, Maxime Cornu, 127; the Probability of Phylloxera Crossing the Tropics, 147; in the Geelong Vineyards, 181; in the Crimea, 253
Physical Notes, 43, 86, 133, 208, 278, 372, 397, 441, 517, 616
Physical Society, 95, 162, 187, 331, 403, 450, 499, 547, 595
Physical Science at Bedford College, 181
Physical Nature of the Sun, Study of the, Prof. Piazzi Smyth, 554
"Physics of the Earth's Crust," Rev. Osmond Fisher, 131
Physiological Botany, Atlas of, Dr. Dodel-Port's, 157
Physiological Significance of Transpiration of Plants, 494
Physiology of Plants, Francis Darwin, 178
Piano, Stenographic, 440
Pickering (Prof. Edward C.), the Star Oeltzen 17681, 338; Spectrum of the Star Ll. 13412, 604
Picture, the Oldest, in the World, Prof. Alfred Newton, F.R.S., 555
Pile-Dwellings, S. E. Peal, 218
Pinguicula Alpina, 159
Pinnipeds, North American, J. A. Allen, 261
Piscium (73), Occultation of, by Jupiter, 183; Col. H. Colbeit, 458
Planets, Minor, 396, 517
Plants of Madagascar, J. G. Baker, 125
Plants: Chlorophyll in the Epidermis of, 158; Light and the Transpiration of, 159; Physiology of, Francis Darwin, 178
Plants, Biology of, 310
Plants, Australian, in India, Dr. G. Bidie, 555
Plants, Movement of, Charles Darwin, F.R.S., 409
Plants, Physiological Significance of Transpiration of, 494
Plimsoll's (Mr.) Cure for Colliery Explosions, W. Galloway, 156
Plymouth, Flora of, T. R. Archer Briggs, 74
Poggendorff's Biographical Dictionary, Supplement to, 231
Polar Research, the Future of, 49
Polar Reconnaissance, Albert H. Markham, 455
Polarisation of Light, Experiment in, 442
Polarised Light, "Natural" Experiment in, Charles T. Whitmell, 268
Political Economy, Dr. Luigi Cossa, 97
Polyergus lucidus, the Shining Slave-Maker, 543
Polyzoa, British Marine, T. Hincks, F.R.S., 51
"Pompeii," a New Journal, 232
Pompeii, Discoveries at, 371; Excavations in the Ninth Region of, 440
Port-au-Prince, Haiti, Meteorological Observatory at, 516
Portuguese Pompeii, a, 297
Post Office in Magellan Straits, 254
Practical Plane Geometry, Complete Course of Problems in, J. W. Palliser, 264
Predicter, Tide, Sir William Thomson, F.R.S., 578; Edward Roberts, 555
Preece (W. H.): On the Conversion of Radiant Energy into Sonorous Vibrations, 496; Dust, Fogs, and Clouds, 336; Aurora and Electric Storm of January 31, 348
Prejevalsky (Col.): his Travels in China, 21, 45, 173; Account of, 399; at St. Petersburg, 418
Prehistoric Europe: Prof. W. Boyd Dawkins, F.R.S., 309, 361, 482; Dr. James Geikie, F.R.S., 336, 433, 458; R. H. Tiddeman, 433, 528
Prehistoric Man, Exploration of the Remains of, in Russia, 107
Preston (S. Tolver), on some Points relating to the Dynamics of "Radiant Matter," 461
Prevost (G. W.), Aurora of January 31, 329
Primitive Marriage Customs, D. MacLennan, 584
Prism, the Passage of Light through a, 397
Proceedings of the Royal Irish Academy, 401
Proceedings of the Linnean Society of New South Wales, 449, 522
Prussia, Education in, 115
Pyramids, Discovery of, to the North of Memphis, 297

Quarterly Journal of Microscopical Science, 296, 378
Quekett Microscopical Club, 439, 451
Quinine, Oxidation of, Dr. W. Ramsay and James J. Dobbie, 243

Radiant Heat, Action of an Intermittent Beam of, upon Gaseous Matter, Prof. Tyndall, F.R.S., 374
"Radiant Matter," on some Points Relating to the Dynamics of, S. Tolver Preston, 461; William Muir, 483
Radiant Energy, on the Conversion of, into Sonorous Vibrations, W. H. Preece, 496
Radiophone, the, 209, 373
Rae (Dr. John, F.R.S.), Geological Climates, 337; Migration of the Wagtail, 411; Sound of the Aurora, 605
Rainbow, Inverted, seen at Innsbruck, 157
Rains, Indian Winter, S. A. Hill, 604
Ramsay (Dr. W.), Oxidation of Quinine, 243
Rance (C. E. de), Blackheath Holes, 365; International Geological Congress, 510
Rankine's (Macquorn, F.R.S.) Scientific Papers, Prof. Osborne Reynolds, F.R.S., 477
Raout (M.), Experiments on the Freezing-Points of Acoholic Liquids, 85
Rayleigh's (Lord) Solution for Waves in a Plane Vortex Stratum on a Disturbing Infinity in, Sir William Thomson, 45, 70; the Photophone, 274
Reade (T. Mellard), Landslips—the Cheshire Subsidences, 219;

Vibration of Telegraph Wires during Frost, 314; Ice Intrusive in Peat, 339
Reale Istituto Lombardo di Scienze e Lettere, 211, 235, 306, 425, 474, 499, 594; Prizes of, 231
Reality, Criterion of, 144
Red Colour of Salt Cod, 543
Reed (Sir Charles), Death of, 516
Reed (Sir E. J., F.R.S.), "Japan; its History," &c., 12
Reflecting Instruments, Improved Arrangement of Scale for, F. Jacob, 527
Refraction, M. Glasenap on, 373
Regelation, Rev. George Henslow, 11
Reiss (W.) and A. Stübel, Peruvian Antiquities, 75
Research, Endowment of, in Birmingham, 304
Revista of the Society of Instruction of Oporto, 298
Revue d'Anthropologie, 83
Revue des Sciences Naturelles, 47, 283
Revue des Sciences, 515
Revue Internationale des Sciences, 594
Revue Internationale des Sciences biologiques, 95, 161, 306, 449
Reynolds (Prof. Osborne, F.R.S.), Macquorn Rankine's Scientific Papers, 477
Rhenish Fishery Society, Foundation of a, at Cologne, 158
Rhine, Electric Light and Navigation on the, 132
Rhinoceros, Colossal, Discovery of in Siberia, 275
Rhinoceros Merckii in Siberia, Recent Discovery of the Body of, 466
Ricarde-Seaver (Major F. J.), Bi-Centenary of Calderon, 457
Richmond (Geo. B.), Hot Ice, 504
Rivers, German, the Quantity of Water in, 94
Rivista Scientifico-Industriale, 47, 115, 211, 402, 425, 474, 594
Roberts (Dr. William), Temperature of the Breath, 55; "On the Digestive Ferments, and on the Preparation and Use of Artificially Digested Food," 169
Roberts (Prof. W. Chandler, F.R.S.), Introductory Lecture to the Course of Metallurgy at the Royal School of Mines, 65
Roberts (Edward), Tide Predicter, 467, 555
Rodwell (G. F.), French Association for the Advancement of Science at Algiers, 582, 606
Rogers (J. Banting), New Game, "A Voyage Round the World," 134
Rogers (J. Innes), Colours of British Butterflies, 435
Rolleston (Prof.), His Lecture on the Modifications of the External Aspects of Organic Nature Produced by Man's Interference, 19
Romanes (George J., F.R.S.), Butler's "Unconscious Memory," 285, 335; Aberration of Instinct, 433; Mind in Animals, 501; the Locomotive System of Echinodermata, 345; Conscious Matter, 553
Roscoe (Prof. H. E., F.R.S.), Prof. Lunge's "Sulphuric Acid and Alkali," 73, 99, 215; "Scientific Worthies," Robert Wilhelm Bunsen, 597
Roth (Herr), Compressibility of Gases, 43
Roumania, Earthquake Shock in, 232
Rousdorf, Shock of Earthquake felt at, 253
Rouse (M. L.): Movements of Leaves, 195; Tacitus on the Aurora, 459; Sound of the Aurora, 556
Routledge (Robert), "Popular History of Science," 52
Royal School of Mines, Introductory Lecture to the Course of Metallurgy at the, Prof. W. Chandler Roberts, F.R.S., 65
Royal Society, 283, 330, 355, 378, 402, 425, 474, 499, 545, 569, 594; Officers and Council, 41; Medals awarded, 62, 138; Address of the President, Dr. William Spottiswoode, 111, 135; the *Times* on Dr. Spottiswoode's Address at, 130; proposed New Fellows, 563
Royal Society of Literature, 163
Royal Asiatic Society, 162, 332
Royal Astronomical Society, Anniversary Meeting, 394
Royal College of Science, Dublin, 297
Royal Geographical Society, 21, 398, 420, 443, 495, 518, 544, 565; Medals, 565; Sir Bartle Frere at, 87
Royal Institution, Lecture Arrangements of, 19, 254; Friday Evening Lecture, 130; Prof. Dewar on Atoms at the, 181
Royal Microscopical Society, 140, 162, 427, 500
Ruchonnet's (Charles), "Exposition Géométrique des Propriétes générales des Courbes," "Éléments de Calcul approximatif," 481
Russell (Hon. Rollo), Colliery Explosions and Coal-Dust, 193; Dust and Fogs, 267
Russia: Account of Communes, &c., 45; Exploration of the Remains of Prehistoric Man in, 107
Russian Geographical Society, 44, 255, 443; and Universal Time, 255; Prof. Nordenskjöld and, 299
Russian Imperial Yacht *Livadia*, 27, 63
Russo-Byzantine Antiquities found near Kiew, 321
Ryde, Annual Meeting of the British Medical Association at, 131

Sachs (E. T.), Natural History Notes from Batavia, 275
St. Ivan-Zelina, Earthquake at, 439
St. Michael's in the Azores, Earthquake at, 419
St. Petersburg Geological Society, Meeting of, 107
St. Petersburg, Earthquake at, 370
St. Petersburg Dynamite Mine, 531
Salts of Zinc, S. W. Bott, 78
Salvadori's Ornithology of New Guinea, 240
San Cristobal, Earthquake at, 564
Sands, Moving, and Dunes, 569
Sandstones, Cambrian, near Loch Maree, Curious Impressions in, 93
Sanitary Assurance Association, 50
Sanitary Institute of Great Britain, 320
Santarem and Citania, 297
Sargassum, Dr. Otto Kuntze, 70, 146
Sargent (Howard), Mode of Flight of the Albatross, 362
Saturn, Leverrier's Theory of, 298
Schipka Cave, 296; Animal Remains in the, 446
Schloss Trakostyan, Earthquake at, 205
Schmeltz (J. D. E.) und Dr. med. R. Krause, "Die ethnographisch-anthropologische Abtheilung des Museum Godeffroy in Hamburg. Ein Beitrag zur Kunde der Südsee-Völker," 168
Schriften der physikalisch-ökonomischen Gesellschaft zu Königsberg, 306, 402
Schuster (Dr. Arthur), on the Thermic and Optic Behaviour of Gases under the Influence of the Electric Discharge, 258
"Science, a Popular History of," Robert Routledge, 52
Scientific Education, Lord Gifford on, 64; Mr. Mundella on, 134
Science, Natural, for Women, Alfred W. Bennett, 195
Science at Algiers, French Association for the Advancement of, G. F. Rodwell, 582, 606
Sciences, Songs of the—I. Zoology, 148
Scientific Societies of Dublin, 316
SCIENTIFIC WORTHIES, XVII.—Robert Wilhelm Bunsen, Prof. H. E. Roscoe, F.R.S., 597
Scotch Fisheries Improvement Association, 232
"Scotland, Free Libraries of," 64
Scotland, Slight Shocks of Earthquake in, 106, 591
Scott-Moncrieff (W. D.), Smokeless London, 193
Sea, Phosphorescence of the, Thomas B. Groves, 411
Seabrooke (George M.), Aurora and Electric Storm of January 31, 348
Sea-Lion, Death of, at the Brighton Aquarium, 253
Seeing by Electricity, 423
Selenium, 218, 412
Semellé (Count de), Death of, 45
Semper (Prof. Karl), "Natural Conditions of Existence and Animal Life," 405
Shadows cast by Venus, Charles T. Whitmell, 579
Sharp (Dr.), "Avis préliminaire d'une Nouvelle Classification de la Famille des Dytiscidæ," 98
Shaw (J.), Explosive Gas in a Lake, 435; Sound of the Aurora, 484
Shaw-Lefevre's Collections, 369
Sheep, Black, Charles Darwin, F.R.S., 193
Sheppey, Geologising at, J. Starkie Gardner, 293
Shining Slave-Maker (*Polyergus lucidus*), 543
Siberia, Recent Discovery of the Body of *Rhinoceros Merckii* in, 466
Siberian Meteorology, Dr. A. Woeikof, 437
Siemens' (Dr. C. William, F.R.S.) New Cure for Smoke, 25, 366; D. A. Stevenson, Cosmo Innes, Thomas Fletcher, Dr. C. W. Siemens, F.R.S., 91; Gas-Grate, Dr. R. Douglas Hale, 145; Gas and Electricity as heating Agents, 326, 351
Siemens (Herr F.), on his "Regenerative Gas-Burner," 131
Signs of Death, 494
Sitka in Alaska, Cyclone accompanied by Earthquake Shocks at, 83
Sitzungsberichte der Naturwissenschaftlichen Gesellschaft Isis in Dresden, 594

Skating, Statics and Dynamics of, Charles Alexander Stevenson, 268
Skeleton of a Mammoth discovered at Bendery, 371
Skeletons, Dr. Fritsch's Method of taking Casts of, 275
Skin Furrows of the Hand, Sir W. J. Herschel, 76
Sky, the Colour of, and Ozone, 373
Small-pox, Dr. Richardson on, 589
Smell, Organs of, in Insects, 440
Smith (Worthington G.), Palæolithic Man, 604
Smoke, New Cure for, Dr. C. William Siemens, F.R.S., 25, 91, 360; D. A. Stevenson, Cosmo Innes, Thomas Fletcher, J. A. C. Hay, 386
Smoke in the Metropolis, Deputation to the Lord Mayor on, 131
Smoke Abatement, 246
Smoke, Dust, Fogs, &c., M. Chatel, 436
Smokeless London, W. D. Scott-Moncrieff, 151, 198; W. Mattieu Williams, 169
Smyrna, Earthquake at, 205
Smyth (Prof. Piazzi), Study of the Physical Nature of the Sun, 554
Snake Bites and Guaco, 182
Snakes and the Great Kingfisher, 298
Soaring of Birds, S. E. Peal, 10; W. Larden, 77
So-called Nova of 1600, 371
Society of Arts, 20; Papers to be read at the, before Easter, 232
Society of Telegraph Engineers' *Soirée*, 563
Solar Cycles, Barometric and, S. A. Hill, 409
Solar Cycles, Barometric and, Prof. Balfour Stewart, F.R.S., 457
Solar Eclipse of December 31, 65
Solar Eclipse of 1878, 591
Solar Parallax, 441, 493, 591
Solar Physics, Course of Lectures on, 491
Solar Spots, on the Iron Lines widened in, J. Norman Lockyer, F.R.S., 425
Solar Systems, Tidal Friction in Connection with the History of the, G. H. Darwin, F.R.S., 389
Solids and Liquids at High Temperatures, John Aitken, 34
Songs of the Sciences—I. Zoology, 148
Sonorous Vibrations, on the Conversion of Radiant Energy into, W. H. Preece, 496
Sound of the Aurora, E. Alloway Paukhurst, J. Shaw, 484; M. L. Rouse, 556; Dr. John Rae, F.R.S., 605
Sound, Localisation of, H. B. Jupp, 386
Spallanzani, Proposed Erection of a Monument to, 41
Sparrow, the, and Division of Labour, G. C. Wallich, 579
Species, Cave Animals and Multiple Centres of, D. Wetterhan, 458
Spectra of Vapours and Gases, Influence of Pressure and Temperature on, G. Ciamician, 160
Spectroscopic Notes, 1879-80, Prof. C. A. Young, 281
Spectrum of Carbon, 313; W. M. Watts, 197, 265, 361; Prof. G. D. Liveing, F.R.S., 265, 338
Spectrum of the Star Ll. 13412, Prof. Edward C. Pickering, 604
Speed-Governor for Continuous Motion, Prof. J. Ewing, 473
Spencer (Herbert) and Prof. Tait, 100, 123, 144
Spherohedry in Crystallisation, 398
Sphygmography, 438
Spider, Garden, the Influence of a Tuning-Fork on a, C. V. Boys, 149
Spinoza, Publication of the Complete Works of, 156
Spottiswoode (Dr. William, F.R.S.), Royal Society Address, 111, 135
Spratling (W. J.), Aurora and Electric Storm of January 31, 348
Squirrel Crossing Water, H. H. Godwin-Austen, 340; F. A. Jentink, 388; Frederick Hubbard, Cecil Duncombe, 484; T. V. Sládek, 459
Standard Thermometers, 400
Stars: Ceraski's Circumpolar Variable, 21, 43, 322; Variable Stars U Cephei and U Geminorum, 542; a probable Variable Star, 115; J. Birmingham, 517 555,; Variable Stars, 206, 493; J. E. Gore, 362; Star Lalande 1013-4, 85; Near Appulse of Jupiter to a Fixed Star, 158; J. Birmingham, 170; Janson's Star of 1600, 276; Star Oeltzen 17681, Prof. Edward C. Pickering, 338; Spectrum of the Star Ll 13412, Prof. Edward C. Pickering, 604; Cincinnati Measures of Double Stars, 396; Double-Star Herschel 3945, 591
Statistical Map of England, 399
Statistical Society, 322, 428
Statures, Classification of, 494
Steam-Pressure Regulator, a New, 372
Stebbing (T. R. R.), Butler's "Unconscious Memory," 335
Stellar Masses, Heat of, Samuel J. Wallace, 579
Stenhouse (Dr. John, F.R.S.), Death of, 231; Obituary Notice of, 244
Stenographic Machine, 468
Stenographic Piano, 440
Stephenson (George), Centenary of the Birth of, 515
Stereoscope and Photography, on Estimating the Height of Clouds by the, John Harmer, 194
Stevenson (Charles Alexander), Statics and Dynamics of Skating, 268
Stevenson (D. A.), Dr. Siemens' New Cure for Smoke, 91
Stevenson (Thomas), Mode of Masking or Cutting off Sharply the Light from Revolving Apparatus on a desired Compass-bearing by means of a Reciprocating Screen, 560
Stewart (James), his Return from Livingstonia, Lake Nyassa, 22
Stewart (Prof. Balfour, F.R.S.), Barometric Cycles, 237, 457; Magnetic Declination, 592
Stone Implements, Ancient, Modern Use of, D. Budde, 218
Stone (Dr. W. H.), Acoustics in China, 448
Storm Centres in Tropical Regions, Prof. Loomis, 322
Stübel (A.) and W. Reiss, Peruvian Antiquities, 75
Subsidence of Land caused by Natural Brine-Springs, Thomas Ward, 388
Sugar, Cane, Inversion of, 85
"Sulphuric Acid and Alkali," Prof. Lunge, Prof. H. E. Roscoe, F.R.S., 73, 99, 215
Sunday Society, 156
Sunday Lecture Society, 419
Sunlight, the Chemical Intensity of, 86
"Sun, Mock," J. E. H. Peyton, 314
Sun-spots, Liznar on, 133
Sun-Spots, Rainfall, and Famines, Abnormal Variations of Barometric Pressure in the Tropics, and their Relations to, E. Douglas Archibald, Fred. Chambers, 399
Sun-Spot Cycle, Abnormal Barometric Gradient between London and St. Petersburg in the, E. Douglas Archibald, 618
Sun, Study of the Physical Nature of the, Prof. Piazzi Smyth, 554
Swan (J. W.), Incandescent Lights, 104
Switzerland: Earthquake in, January 27, 320; Earthquakes in, 468
Swift's Comet, 115, 158, 182, 255, 322, 441
Sydney Botanical Gardens, Native Cucumbers and New Seeds at, 20
Sydney, Zoological Gardens at, 371
Symbolical Logic, Hugh MacColl, 578
Szabo (Prof.), Earthquakes at Agram in 1880-81, 530

Tacitus on the Aurora, M. L. Rouse, 459, 484
Tait (Prof. P. G.), on the Formula of Evolution, 78; Mr. Spencer and, 100, 123, 144
Tait (Mr. Lawson), Bedroom Ventilation, 157
Tarentula, *Lycosa tarentula*, Latr., Herr V. Bergsö on, 84
Tashkent College, 44
"Tasmanian Friends and Foes; Feathered, Furred, and Finned," Louisa Anne Meredith, 143
Tavernier, on the Identity of some Ancient Diamond Mines in India, especially those mentioned by, V. Ball, 490
Taylor (R. W.), Aurora of January 31, 329
Taylor (R. E.), Flying-fish, 388
Tea Plantation established near Messina, 254
Telegraph, an Optical, 372
Telegraph Wires, Vibration of, during Frost, T. Mellard Reade, 314; F. T. Mott, 338
Telegraphy, Berthoud Borel and Co.'s New Discovery in, 85
Telegraphy without Wires, an Experiment in, 320
Telephone in Paris, 63; and the Magnetic Receiver, 371; Telephonic Amenities, 590
Tele-Photography, Shelford Bidwell, 344
Telescope, Prof. C. A. Young's New, 346
Tempel (Dr. Wilhelm), King Humbert's Prize Awarded to, 252
Temperature of the Breath, Dr. R. E. Dudgeon, 10, 76; Dr. William Roberts, 55; C. J. McNally, 217, 244; Dr. William McLaurin, 244
Temperature, Critical, of Ethylene, Robert E. Baynes, 186

Temperature, on a Method of Determining the Critical, for any Liquid and its Vapour, without Mechanism, Sir William Thomson, F.R.S., 87
Temperature, Low, Rev. S. J. Perry, F.R.S., 268
Temperatures, Electrical Thermometer for Determining, at a Distance, Horace T. Brown, 464
Tennant (Prof. James), Death of, 418
Theorem, General, in Kinematics, J. J. Walker, 125; Geo. M. Minchin, 170
"Thermal Bar," M. Forel on, 86
Thermic and Optic Behaviour of Gases under the Influence of the Electric Discharge, Dr. Arthur Schuster, F.R.S., 258
Thermo-electricity, Herr Exner on, 44
Thermo-magnetic Thermoscope, a New, 372
Thermometer, Electrical, for Determining Temperatures at a Distance, Horace T. Brown, 464
Thermometers, Standard, 400
Thompson (Prof. Silvanus P.), Bottomley's Experiments with Vacuum Tubes and the Aurora, 289
Thomson and Keith Johnston's African Expedition, 38
Thomson (Joseph), Notes on the Geology of East Central Africa, 102; Report on His East African Expedition, 134
Thomson (Sir William), on a Disturbing Infinity in Lord Rayleigh's Solution for Waves in a Plane Vortex Stratum, 45, 70; on an Experimental Illustration of Miniumum Energy, 69; on a Method of Determining the Critical Temperature for any Liquid and its Vapour without Mechanism, 87; Tide Predicter, 482, 578; on a Method of Measuring Contact Electricity, 567
Thomson (Sir Wyville, F.R.S.), Natural Selection, Charles Darwin, F.R.S., 32, 53; Geological Changes of Level, 33
Thresher, the, Francis P. Pascoe, 35
Thullium, Separation of, 86
Tidal Friction in Connection with the History of the Solar System, G. H. Darwin, F.R.S., 389
Tide Predicter, Sir William Thomson, F.R.S., 482, 578; Edward Roberts, 467, 555
Tiddeman (R. H.), Prehistoric Europe, 433, 528
Timbuctoo, Dr. Lenz on, 544
Time, Universal, and the Russian Geographical Society, 255
Time-Signal Apparatus, a New, 347
Time of Day in Paris, 367
Times, the, on Dr. Spottiswoode's Address at the Royal Society, 130
Tomlinson (Herbert), the Photophone, 457
Tonbridge School, Science at, 516
Töpler Air-Pump, Improved Form of, 616
Torsion, Wire, Prof. John Perry and Prof. W. E. Ayrton, 35
Total Solar Eclipse of 1878, 591
Towson (John Thomas), Death of, 231
Tracks, Ice Casts of, J. T. Brownell, 484
Traill (D.), Aurora and Electric Storm of January 31, 348
Transactions and Proceedings of the Botanical Society of Edinburgh, 522
Transactions of the Yorkshire Naturalists' Union, 161
Transit of Venus Commission, 231, 388, 467
Transylvania, Earthquake Shock at, 232
Trichocera, Winter Gnats, Rev. A. E. Eaton, 554
Trichopterenlarven, Ueber die von den, der Provinz Santa Catharina verfertigen Gehäuse, Dr. Fritz Müller, 192
Trimen's Journal of Botany, 259
Tripier (M.), appointed Director of the Algiers Observatory, 107
Tropics, Abnormal Variations of Barometric Pressure in the, and their Relation to Sun-Spots, Rainfall and Famines, Fred. Chambers, 88, 107, 399; E. Douglas Archibald, 399
Tropics, the Probability of Phylloxera Crossing the, 147
Troy, Minerva Ornaments at, *v.* Net-Sinkers, Prof. E. W. Claypole, 292
Tucker (R.), Obituary Notice of Michael Chasles, 234
Tuning-Fork, the Influence of, on a Garden Spider, C. V. Boys, 149
Tunnel, the Arlberg, 321
Tylor (Edward B., F.R.S.), the Aryan Village, 525
Tyndall (Prof., F.R.S.), Action of an Intermittent Beam of Radiant Heat upon Gaseous Matter, 374
Types and Affinities, Indo-Chinese and Oceanic Races, A. H. Keane, 199, 220, 247, 271

Umbrette, the Tufted, 37
"Unconscious Memory," Samuel Butler, George J. Romanes, F.R.S., 285, 335; Samuel Butler, 288, 312; Dr. Ernst Krause, 288; T. R. R. Stebbing, 335
Union Géographique du Nord de la France, 398
United States Weather Maps, 39, 147
United States, Meteorology in, 183
U.S. Geological and Geographical Survey of the Territories, 1879-80, 481
United States, Fish-Culture in the, 532
University College, Prof. Max Müller at, 381
University Intelligence, 23, 47, 71, 87, 115, 139, 160, 186, 211, 259, 282, 330, 354, 377, 401, 424, 473, 498, 544, 569, 593, 619
Urania, 383
Uranium, New Compounds of, 86
Uranus, Herschell's First Observation of, 299

Vacuum Tubes, Experiments with, J. T. Bottomley, 218, 243; Bottomley's Experiments with, and the Aurora, Prof. Silvanus P. Thompson, 289; Experiments with, 442
Valparaiso, Earthquake in, 20
Vanadium, the Sulphides of, 208
Vancouver Island, Climate of, Capt. Edmund H. Verney, 147; William Pengelly, F.R.S., 267; Dr. George M. Dawson, 385; and Bournemouth, Climates of, Alfred R. Wallace, 169
Vapours, Specific Volume of, 397
Vapours and Gases: their Dissolving Power on one another, 86; Spectra of, Influence of Pressure and Temperature on, G. Ciamician, 160
Variable Stars, 21, 115, 206, 362, 493, 517, 542, 555
Vaucauson, Exhibition of his MS., &c., in Paris, 63
Veeder (M. A.), Meteors, 147
Vega Fund, the, 160
Ventilation, Bedroom, Mr. Lawson Tait on, 157
Venus: Transit of, Commission, 231, 388; Shadows Cast by, Chas. T. Whitmell, 579
Verglas in Italy, 517
Verney (Capt. Edmund H.), Climate of Vancouver Island, 147
Vertebrates, Italian, at Florence, 41
Vesuvius: Flow of Lava from the Crater of, 20; the Eruption of, 43, 83, 440, 542
Vibration of Telegraph Wires during Frost, T. Mellard Reade, 314; F. T. Mott, 338
Vicars (George Rayleigh), Vox Angelica, 34, 77; Future Development of Electrical Appliances, 528
Victoria (Philosophical) Institute, 236, 307, 356, 404, 500, 548
Victoria, Royal Society of, 64
Victoria University, 593
Victoria Station, Jablochkoff Light at, 64
Vienna: Geographical Society, 22; Imperial Academy of Sciences, 48, 72, 96, 140, 164, 188, 284, 308, 356, 380, 404, 476, 500, 548, 596; Imperial Institute of Geology, 164, 476, 596; Observatory, the New Telescope, 469
Vines (Sydney H.), the Works of Carl von Nägeli, 78; Chlorophyll, 561
Viscosity of Gases at High Exhaustions, W. Crookes, F.R.S. 421, 443
Vivisection, Charles Darwin, F.R.S., on, 583
Volcanoes, Vesuvius, 20, 43, 83, 440, 542
Voldifjord, appearance of a Colony of Beavers on the, 84
Vox Angelica, George Rayleigh Vicars, 34, 77

Wagner (Prof. Johannes Rudolf von), Obituary Notice of, 11
Wagtail, Migration of, 529; Prof. E. W. Claypole, 387; Dr. John Rae, F.R.S., 411
Walker (J. J.), a General Theorem in Kinematics, 125
Wallace (Alfred R.), Geological Climates, 124, 217, 266; New Guinea, 152, 175; Climates of Vancouver Island and Bournemouth, 169; Correction of an Error in "Island Life," 195; Pension Conferred upon, 275
Wallace (Samuel J.), Heat of Stellar Masses, 579
Wallich (G. C.), Sparrow and Division of Labour, 579
Walsingham (Lord), Fertilisation of Yucca, 76
Ward (Thomas), Landslips, 144; Subsidence of Land Caused by Natural Brine Springs, 388
Ward (Col. Foster), on some Remarkable Hailstones, 233
Warnings, Earthquake, 529
Washington Society of Anthropology, 84
Wasps, Bees, Ants, and, Observations on, Sir J. Lubbock, Bart., F.R.S., 255

Water, Expansion of, in Freezing, 321
Water, Squirrels Crossing, F. A. Jentink, 388; Frederick Hubbard, Cecil Duncombe, 484
Watson (Prof. J. C.), Obituary Notice of, 155
Watson (Ellen), proposed Memorial to, 474
Watts (Dr. W. M.), Spectrum of Carbon, 197, 265, 361
Weather Maps, United States, 39, 147
Weather, Recent severe, 329, 363, 411
Wetterhan (D.), Cave Animals and Multiple Centres of Species, 458
Weyprecht (Lieut. Karl), Death of, 544
Wheat and Barley, English, in Cawnpore, 370
Whipple (G. M.), Aurora and Electric Storm of January 31, 348
"Whitaker's Almanack," Scientific Summary, 232; the Geography of, 232, 279
White (William), Death of, 320
Whitmell (Charles T.) "Natural" Experiment in Polarised Light, 268; Shadows Cast by Venus, 579
Whitney (Prof.), on the Glaciation of British Columbia, George M. Dawson, 290
Whymper (Edward), on the Practicability of Living at Great Elevations above the Level of the Sea, 459; Ascents of Chimborazo and Cotopaxi, 323
Wiener Neustadt, Fall of a Meteoric Stone at, 297
Wiesbaden, Earthquake Shock at, 156
Williams (W. Mattieu), Smokeless London, 169; Experiment on Inherited Memory, 508; Agricultural Communism in Greece, 579
Williamson (B., F.R.S.), "Elementary Treatise on the Integral Calculus," 241
Willmore (J. H.), Birds Laying in January, 314
Winnecke's Comet, 254
Winter Rains, Indian, S. A. Hill, 604
Wire Torsion, Professors John Perry and W. E. Ayrton, 35
Wires, Elasticity of, J. T. Bottomley, 281
Woeikof (Dr. A.), the Yang-tse, the Yellow River, and the Pei-ho, 9; Geological Climates, 241, 362; Siberian Meteorology, 437
Wolf, the Japanese, 36
Women: Natural Science for, Alfred W. Bennett, 195; Degrees to, 394
Wood (Searles Valentine), Obituary Notice of, 40; Order Zeuglodontia, Owen, 54, 339
Wood (E.), his Collection of Fossils, 275
Wortley (Col. H. Stuart), Crabs and Actinia, 529
Wright (Lewis T.), Note on Flame Length, 527
Wurtz (Ad.), "The Atomic Theory," 5

Xanthium strumarium, its Poisonous Effects on Cattle, 182

Yang-tse, the Yellow River, and the Pei-ho, Dr. A. Woeikof, 9; H. B. Guppy, 35, 99, 507
Yorkshire Vertebrata, Handbook of, 467
Young Men's Society for Home Study, U.S., 254, 297
Young (Prof. C. A.), Spectroscopic Notes, 1879-80, 281
Young, Professors Exner and, Prof. C. A. Young, 312
Young (Lamont), Mysterious Disappearance of, 346
Yucca, Fertilisation of, Lord Walsingham, 76

Zarafshan, the Glacier of the, M. Mushketoff's Exploration of, 44
Zeitschrift für wissenschaftliche Zoologie, 161, 306, 545
Zeuglodontia, Order, Owen Searles V. Wood, jun., 54, 388
Zinc, Salts of, S., W. Bott, 78
Zittel (Dr. Karl), on the Geology of the Libyan Desert, 19
Zoological Record for 1878, 8; the Staff of, 63
Zoological Gardens, Additions to, 21, 420, 441, 469, 493, 516, 542, 565, 591, 615
Zoological Garden, Proposed, at Leipzig, 253
Zoological Gardens, Sydney, 371
Zoological Society's Living Collection, Illustrations of New or Rare Animals in, 35, 415, 487
Zoological Society, 95, 161, 187, 259, 306, 355, 427, 499, 571
Zoological Laboratory, Chesapeake, 279
Zoological Station at Naples, 315
Zoological Stations at Watson's Bay, 589
Zoological Results of the Visit of Prof. K. Möbius to Mauritius, H. N. Moseley, F.R.S., 514
Zoology, Songs of the Sciences, I., 148

LY ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
Nature trusts the mind which builds for aye."—WORDSWORTH

THURSDAY, NOVEMBER 4, 1880 [PRICE SIXPENCE

[All Rights are Reserved.

neral Post Office.]

IEDAL.

sf the Chemical Section of the
in commemoration of the work
of the Mint, will be awarded at
Paper on any subject in Pure or

pers, not later than 1st February
tion, Dr. J. J. Dobbie, Chemical

HOOL of MINES,

NGTON W. SMYTH, M.A.,
ury Lectures on Mining, at half-
past, November 8th, to be con-
ding Tuesday, Thursday, Friday,

F. W. RUDLER, Registrar.

IP SCHOOL
ENGINEERING.

LER, Esq., Lectures by JOHN
rks on the Steam Engine); by
e of Engineers and Shipbuilders
RETARY, Polytechnic, 309, Regent

EXPEDITION,

ATIONS FROM,

THOMSON.
ng., Depth, &c., in Box, 30s.
ing Anatomy of the Monkey, in

ity Road, E.C., about 100 yards

ches of Microscopy.

MINERALOGY.

w prices, Educational Collections
y arranged to illustrate the text-
Davies, Skertchley, Dana, Page,
ol and College Museums are also
logues post free.
N, 6d. SHEFFIELD.

IC.—CLASSES for
diversity Examinations, under the
G, D.Sc., F.L.S., London Uni-
Sc., Preliminary Scientific M.B.,
the work practical.

CE COMPANY,

ALL.

STABLISHED 1807.
. — — — — £3,043,543
an — — — — £1,300,000
be had at the Office, or from any

REYS, Actuary and Secretary.

BROWNING'S PLATYSCOPIC LENS.

Engraved Reed Slip.

A NEW ACHROMATIC COMBINATION,

COMBINING THE DEFINITION OF A MICROSCOPE WITH THE PORTABILITY OF A POCKET LENS.

The Platyscopic Lens is invaluable to botanists, mineralogists, or entomologists, as it focusses about three times as far from the object as the Coddington Lenses. This allows opaque objects to be examined easily.

The Platyscopic Lens is made of three degrees of power, magnifying respectively, 15, 20, and 30 diams.: the lowest power, having the largest field, is the best adapted for general use.

The Lenses are set in Ebonite Cells, and mounted in Tortoiseshell Frames.

Price of the Platyscopic Lens, mounted in Tortoiseshell, magnifying either 15, 20, *or* 30 *diameters*, 18*s.* 6*d.*

Illustrated description sent free.

JOHN BROWNING, 63, STRAND, LONDON, W.C.

SUNSHINE RECORDER,

Of the form adopted by the Meteorological Council of the Royal Society, and supplied to more than thirty of their Stations, as well as to several private Observatories.

JORDAN'S GLYCERINE BAROMETER,

In which the inch of the ordinary Barometer is expanded to nearly Eleven Inches, and which is in successful use at the Kew Observatory, at the *Times* Office, the Geological Museum, Jermyn Street, and other places.—See the *Times* of October 25th.

For information, &c., apply to R. J. LECKY, care of Kirkland, Cope, and Co., 33, Salisbury Street, Strand, London.

FOR SALE.—"NATURE" (Unbound).—Vols 16, 17, 18, and 21, and Nos. 471, 472, 473 (of Vol. 19), and Nos. 512–522 (of Vol. 20), and Nos. 540.—READER, 29, Bedford Street, NATURE Office.

MUSEUMS AND COLLECTORS.

MR. DAMON, of WEYMOUTH, will forward an abridged Catalogue of his Collections in Natural History Objects, including RECENT SHELLS (Foreign and British), FOSSIL REMAINS, MINERALS, ROCKS, MARINE ZOOLOGY, &c., &c., &c.

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER. 48N. Tollington Road. Holloway, London. N.

MINERALOGY AND GEOLOGY.

FINE SPECIMENS of ORANGITE, ENSTATITE, BREVICITE, EUXENITE, AUGITE, PYROSMALITE.

UNIQUE SPECIMENS of ADULARIASPHENE and SMOKY QUARTZ.

FINE CRYSTALLISED CROMFORDITES and MATLOCKITE, Derbyshire.

XENOTINE CRYSTALLISED, Valais; WOLLASTONITE CRYSTALLISED.

COLLECTIONS FOR STUDENTS, from £2 2s. COLLECTIONS FOR BEGINNERS, from 4s. BLOWPIPE CASES AND APPARATUS.

PRIVATE LESSONS AND EVENING CLASSES.

Catalogues free.

SAMUEL HENSON,
277 (*Late* 113*a*), STRAND, LONDON, W.C.

GEOLOGY.—In the Preface to the STUDENT'S ELEMENTS of GEOLOGY, by Lyell, 1874, he says: "As it is impossible to enable the reader to recognise rocks and minerals at sight by aid of verbal descriptions or figures, he will do well to obtain a well-arranged collection of specimens, such as may be procured from Mr. TENNANT (149, Strand), Teacher of Mineralogy at King's College, London." These Collections are supplied on the following terms, in plain Mahogany Cabinets:—

100 Specimens, in Cabinet, with 3 Trays	£2 2 0
200 Specimens, in Cabinet, with 5 Trays	5 5 0
300 Specimens, in Cabinet, with 9 Drawers	10 10 0
400 Specimens, in Cabinet, with 13 Drawers	21 0 0

More extensive Collections at 50 to 5,000 Guineas each.

THIN GLASS FOR MICROSCOPIC MOUNTING, of best quality. Circles, 3*s.* 6*d.* per ounce; Squares, 2*s.* 9*d.*; post free 2*d.* extra; Ground edged Slips, 5*s.* per gross: also other Mounting Materials and Objects prepared for mounting.—CHAS. PETIT, 151, High Street. Stoke Newington, N.

NORTH BRITISH AGRICULTURIST

is the only Agricultural Journal in Scotland, and circulates extensively amongst Landed Proprietors, Factors, Farmers, Farm-bailiffs, and others interested in the management of landed property throughout Scotland and the Northern Counties of England.

The AGRICULTURIST has also a very considerable circulation on the Continent of Europe, America, Australia, and the Colonies.

The AGRICULTURIST is published every Wednesday afternoon in time for the evening mails, and contains Reports of all the principal British and Irish Markets of the week, besides Telegraphic Reports of those held on the day of publication.

The Veterinary Department is edited by one of the leading Veterinarians in the country, and is invaluable to the breeder and feeder as a guide to the rearing of animals, and their treatment when labouring under disease.

Full Reports are given of the Meetings of the Royal Agricultural Society of England, the Royal Agricultural Society of Ireland, the Highland and Agricultural Society of Scotland, the Scottish Chamber of Agriculture, and all the principal Agricultural Associations throughout Great Britain and Ireland.

For Advertisers addressing themselves to Farmers a better medium does not exist.

Price 3*d.* By post 3½*d.* Annual Subscription, payable in advance, 14*s.*
Office—377, High Street, Edinburgh.
Post-Office Orders payable to Charles Anderson, Jun., Edinburgh.
ESTABLISHED 1843.

LA SEMAINE FRANÇAISE: a Weekly Newspaper and Review in the French Language. Politics, Literature, Science, Art, Varieties, Notes. Price 3*d.*, through booksellers, and at the railway bookstalls. Office, 37, Southampton Street. Strand, W.C.

LA SEMAINE FRANÇAISE: Journal Française pour l'Angleterre: Politique, Littérature, Sciences, Arts, Variétés, Nouvelles, et Notes. Un exemplaire par la poste, 3½*d.*, en timbres poste. Abonnement franco par la poste—un an, 15*s.* 2*d.*; six mois, 7*s.* 7*d.* Prix 3*d.*, chez tous les libraires et aux gares des chemins de fer. On s'abonne aux bureaux, 37, Southampton Street, Strand, Londres, W.C.

LA SEMAINE FRANÇAISE.—"'La Semaine Française' has been brought out in London for the benefit of those English readers who may wish to study contemporary French from all points of view, instead of confining their reading to one particular Gallic print. It certainly merits success."—*Graphic.*

LA SEMAINE FRANÇAISE.—"The numbers before us are full of good things. . . . . It will be far better for most than any one of the best papers published in Paris itself. We are much pleased with the character of it, and believe it will be highly valued in all those many households where French is cultivated. The printing is very well done."—*Queen.*

TERMS OF SUBSCRIPTION:—

	s.	*d.*
Three months	3	10
Six ,, ...	7	7
Twelve ,, ...	15	2

P.O.O. payable to T. SPANSWICK, at King Street, Covent Garden, W.C.
Publishing Office, 37, Southampton Street, Strand, W.C.

LIVING SPECIMENS FOR THE MICROSCOPE.

THOMAS BOLTON, NATURALISTS' and MICROSCOPISTS'
STUDIO, 17, ANN STREET, BIRMINGHAM.

T. B. has last week sent to his subscribers water containing a variety of Diatoms, Desmids, Infusoria, and Rotifers, with Sketches of Eight different Species of Rotifers. He has also sent out Amœba, Difflugia, Raphidiophrys, Choano-flagellata, Cristatella, Stephanoceros, &c.

Weekly announcements will be made in this place of organisms T. B. is supplying.

Specimen Tube, One Shilling, post-free.

Twenty-six Tubes in course of Six Months for Subscription of £1 1s.

Price List of Specimens on application, with stamped addressed envelope.

Portfolio of Drawings, No. 3, One Shilling.

50 ROCKS, 50 FOSSILS, 50 MINERALS,

NEATLY ARRANGED IN A
DEAL CABINET, STAINED AND POLISHED, LOCK AND KEY.
EACH SPECIMEN LABELLED AND CATALOGUED.

Price complete, £1 10*s.*

THE ROCKS illustrate the Order and Range of Deposition, &c.

THE FOSSILS are representative of the Genera found in the most important Deposits.

THE MINERALS are selected for their known uses in the Arts and Manufactures, and are extremely characteristic.

Names and Localities guaranteed.

THOMAS J. DOWNING, Geologist, &c.,
38, WHISKIN STREET, LONDON, E.C.
Catalogues Free.

FIRST-CLASS AND THIRD-CLASS AWARDS

AT SYDNEY EXHIBITION
FOR COLLECTIONS FOR TEACHERS AND STUDENTS, OF
MINERALS, FOSSILS, AND ROCKS

Used with success by all Geological Science Teachers in the United Kingdom. Single Specimens, Hammers, and all requisites, of

JAMES R. GREGORY,

Geologists' Repository and Museum, 88, Charlotte Street, Fitzroy Square
New Lists of Collections, Apparatus, Rock Sections, &c., post free.

On the 1st of every Month.

TRIMEN'S JOURNAL OF BOTANY,

BRITISH AND FOREIGN.

New Series. Edited by JAMES BRITTEN, F.L.S., British Museum.

CONTENTS.—Original Articles by leading Botanists.—Extracts, and Notices of Books and Memoirs.—Articles in Journals.—Botanical News.—Proceedings of Societies.

Price 1*s.* 3*d.* Subscription for One Year, payable in advance, 12*s.*
London: WEST, NEWMAN, & CO., 54, Hatton Garden, E.C.

"The leading Farmers' paper."—CLARE SEWELL READ, ESQ., M.P.

THE CHAMBER OF AGRICULTURE JOURNAL

AND FARMERS' CHRONICLE
(PRICE 3*d.* WEEKLY).

The representative organ of the Central and Provincial Chambers of Agriculture; *gives fuller reports of the discussions and proceedings* of this extensive organisation than any other agricultural paper. It devotes *special attention to the treatment of Agricultural Questions by Parliament*, besides containing ample Reports of the LATEST LONDON and COUNTRY CORN, CATTLE, HOP, PROVISION, and other Markets, with Original Articles on Practical Farming, the Dairy, Herd and Flock News, Horticulture, &c., &c. It is despatched every Monday evening in time for the country post.

Terms of Subscription, payable in advance, post free:—3 months, 3*s.* 9½*d.*; 6 months, 7*s.* 7*d.*; 12 months, 15*s.* 2*d.*
Published by W. PICKERING, 21, Arundel Street, Strand, London, W.C.

5me ANNÉE **L'ÉLECTRICITÉ** 5me ANNÉE

Paris. — 16, rue du Croissant. — Paris

Revue spéciale populaire, illustrée, bi-mensuelle contenant 24 pages grand in-8° à deux colonnes, formant chaque année un magnifique volume de 400 pages orné de plus de 200 gravures.

Rédacteur en chef: **W. DE FONVIELLE**
Directeur: **E. de Clisson**

Envoi gratis de numéro spécimen sur demande

Un numéro **75** *centimes*

Paris et Départements: Un an..... 12 fr.
Étranger. — Union postale: Un an..... 14 fr.

Les Abonnements partent du 5 et du 20 de chaque mois.

No. 1 ready November 11, price 6*d*.

THE SCIENTIFIC ROLL.

CONTENTS.

1. Introduction.
2. Essay I. On the Diurnal Periodicity.
3. General Bibliography on Climate from 1485 to 1830.

Subscription Price for Vol. I., 7*s*. 6*d*., payable in advance to A. RAMSAY, 6, Kent Gardens, Ealing.

London: BRADBURY, AGNEW, & CO., Bouverie Street.

THE NEW BIOLOGICAL JOURNAL.

ARCHIVES DE BIOLOGIE.

Edited by Professors EDOUARD VAN BENEDEN of Liège, and VAN BAMBEKE of Ghent.

This Journal is devoted to the publication of original Memoirs on the Embryology, Histology, Physiology, and Comparative Anatomy of Plants and Animals. Each number is illustrated with numerous Coloured Plates, and appears at the commencement of the Quarter.

Price:—A Single Number, Six Shillings and Sixpence. Annual Subscription: Twenty-five Shillings, or Twenty-seven Shillings post free.

Orders received by Messrs. WILLIAMS & NORGATE, 14, Henrietta Street, Covent Garden, London.

In the first two numbers have appeared:—

VAN BENEDEN: On the Embryology of the Mammalia.
VAN BAMBEKE: On the Cleavage of the Egg in Batrachia.
FOR HINGER: On the Termination of Nerves in the Muscles of Insects.
FREDERIQUE AND VANDEVELDE: On the Physiology of the Muscles and Nerves of the Lobster.
MACLEOD: On the Harderian Gland of the Duck, &c., &c.

THE "HANSA"

Published since 1864 in Hamburg, is the only independent professional paper in Germany, dedicated exclusively to Maritime Objects. Essays, Critiques, Reviews, Reports, Advertisements. Strict eye kept upon the development of Maritime Affairs in every respect. Every second Sunday one Number in 4to at least; frequent supplements and drawings. Subscription at any time; preceding numbers of the year furnished subsequently. Price 12*s*. for twelve months. Advertisements 4*d*. a line, widely spread by this paper; considerable abatement for 3, 6, 12 months' insertion. Business Office: Aug. Meyer and Dieckmann, Hamburg, Alterwall. 28. Edited by W. v. FREEDEN, M.R., Hamburg, Alexander Street, 8.

NATURE SERIES.

THE SPECTROSCOPE AND ITS APPLICATIONS. By J. N. LOCKYER, F.R.S. With Illustrations. Second Edition. Crown 8vo. 3*s*. 6*d*.

THE ORIGIN AND METAMORPHOSES OF INSECTS. By Sir JOHN LUBBOCK, M.P., F.R.S. With Illustrations. Crown 8vo. 3*s*. 6*d*. Second Edition.

THE TRANSIT OF VENUS. By G. FORBES, B.A., Professor of Natural Philosophy in the Andersonian University, Glasgow. With numerous Illustrations. Crown 8vo. 3*s*. 6*d*.

THE COMMON FROG. By St. George MIVART, F.R.S. Illustrated. Crown 8vo. 3*s*. 6*d*.

POLARISATION OF LIGHT. By W. SPOTTISWOODE, LL.D., President of the Royal Society. Illustrated. Second Edition. Crown 8vo. 3*s*. 6*d*.

ON BRITISH WILD FLOWERS CONSIDERED IN RELATION TO INSECTS. By Sir JOHN LUBBOCK, M.P., F.R.S. Illustrated. Second Edition. Crown 8vo. 4*s*. 6*d*.

THE SCIENCE OF WEIGHING AND MEASURING. By H. W. CHISHOLM, Warden of the Standards. Illustrated. Crown 8vo. 4*s*. 6*d*.

HOW TO DRAW A STRAIGHT LINE; A Lecture on Linkages. By A. B. KEMPE, B.A. Illustrated. Crown 8vo. 1*s*. 6*d*.

LIGHT: A Series of Simple, Entertaining, and Useful Experiments in the Phenomena of Light for the Use of Students of every Age. By ALFRED M. MAYER and CHARLES BARNARD. With Illustrations. Crown 8vo. 2*s*. 6*d*.

SOUND: A Series of Simple, Entertaining, and Inexpensive Experiments in the Phenomena of Sound, for the Use of Students of every Age. By A. M. MAYER, Professor of Physics in the Stevens Institute of Technology, &c. With numerous Illustrations. Crown 8vo. 3*s*. 6*d*.

SEEING AND THINKING. By Prof. W. K. CLIFFORD, F.R.S. With Diagrams. Crown 8vo. 3*s*. 6*d*.

DEGENERATION: A Chapter in DARWINISM. By Prof. E. RAY LANKESTER, F.R.S. Illustrated. Crown 8vo. 2*s*. 6*d*.

(Others to follow.)

MACMILLAN & CO., LONDON.

Now ready, price 5*s*.

THE JOURNAL OF THE ANTHROPOLOGICAL INSTITUTE OF GREAT BRITAIN AND IRELAND. Vol. X. No. 1.

CONTENTS.

1. On the Central South African Tribes from the South Coast to the Zambesi. By Dr. Emil Holub.
2. Notes on the Western Regions. Translated from the "Tsĕĕn Han Shoo." Book 96, Part 1. By A. Wylie, Esq.
3. On the Origin of the Plough and Wheel Carriage. By E. B. Tylor, Esq., F.R.S., President.
4. Visualised Numerals. By Francis Galton, Esq., F.R.S.
5. On Nicobarese Ideographs. By V. Ball, Esq., M.A., F.G.S.
6. Notes on the Polynesian Race. By C. Staniland Wake, Esq., M.A.I. Anthropological Miscellanea.

London: TRÜBNER & CO., 57 and 59, Ludgate Hill.

THE QUARTERLY REVIEW,

No. 300, is PUBLISHED THIS DAY.

CONTENTS.

I.—RECENT TRAVELS IN JAPAN.
II.—CICERO.
III.—ART COLLECTIONS.
IV.—MR. MORLEY'S DIDEROT.
V.—THE CAMISARDS.
VI.—OLYMPIA.
VII.—THE NEWSPAPER PRESS.
VIII.—THE MARSHAL DUKE OF SALDANHA.
IX.—SIX MONTHS OF A LIBERAL GOVERNMENT.

JOHN MURRAY, Albemarle Street.

THE ENTOMOLOGIST'S MONTHLY MAGAZINE.

Price Sixpence, Monthly, 24 pages 8vo, with occasional Illustrations.

Conducted by J. W. DOUGLAS, R. MCLACHLAN, F.R.S., E. C. RYE, F.Z.S. and H. T. STAINTON, F.R.S.

This Magazine, commenced in 1864, contains standard articles and notes on all subjects connected with Entomology, and especially on the Insects of the British Isles.

Subscription—Six Shillings per Volume, post free. The volumes commence with the June number in each year.

Vols. I. to V. (strongly bound in cloth) may be obtained by purchasers of the entire set to date, at the increased price of 10*s*. each; the succeeding vols. may be had separately or together, at 7*s*. each.

London: JOHN VAN VOORST, 1, Paternoster Row.

N.B.—Communications, &c., should be sent to the Editors at the above address.

On the 1st of every Month, price Sixpence.

THE ENTOMOLOGIST:

AN ILLUSTRATED JOURNAL OF BRITISH ENTOMOLOGY.

Edited by JOHN T. CARRINGTON,

With the Assistance of

FREDERICK BOND, F.Z.S. | JOHN A. POWER, M.D.
EDWARD A. FITCH, F.L.S. | J. JENNER WEIR, F.L.S.
F. BUCHANAN WHITE, M.D.

Contains Articles by well-known Entomologists on all branches of the Science; on Insects injurious or beneficial to Farm or Garden; Notes on Habits, Life-Histories; occurrence of Rarities, &c.; there are monthly lists of Duplicates and Desiderata.

Numerous WOODCUT ILLUSTRATIONS, to the printing of which especial attention is given, and occasional LITHOGRAPHED and CHROMO-LITHOGRAPHED PLATES.

SIMPKIN, MARSHALL, & CO., Stationers' Hall Court.

On the 1st of every Month, price One Shilling.

THE ZOOLOGIST:

A MONTHLY MAGAZINE OF NATURAL HISTORY.

Third Series. Edited by J. E. HARTING, F.L.S., F.Z.S., Member of the British Ornithologists' Union; contains—

Original articles by well-known naturalists in every branch of zoology; habits of animals; arrival and departure of migratory birds; occurrence of rare birds; distribution and migration of British fresh-water fish; new or rare marine fish; local aquaria; British reptiles; British land and fresh-water mollusca, with remarks on the haunts and habits of the species; and other matters of general interest to those who delight in natural history. Reports of the Linnean, Zoological, and Entomological Societies. Reviews of natural history books. Occasional translations from foreign zoological journals of important and interesting articles in various branches of zoology. There are occasional woodcuts.

JOHN VAN VOORST, 1, Paternoster Row.

HOLLOWAY'S OINTMENT A CERTAIN REMEDY

For BAD BREASTS, OLD WOUNDS, and SORES. If effectually rubbed on the Neck and Chest, it cures SORE THROATS, BRONCHITIS, COUGHS and COLDS; and for GOUT, RHEUMATISM, and all Skin Diseases it is unequalled.

Original Popular Work upon the Natural History of Tasmania.

TASMANIAN FRIENDS & FOES,

FEATHERED, FURRED, AND FINNED.

By MRS. LOUISA A. MEREDITH,

Author of "My Home in Tasmania," "Some of my Bush Friends in Tasmania," "Our Island Home," &c., &c.

ILLUSTRATED BY EIGHT COLOURED PLATES FROM DRAWINGS BY THE AUTHOR, AND NUMEROUS WOODCUTS.

In this book the Author has gathered and woven into connected sequence some of the most interesting incidents and observations which a residence of thirty-nine in years in Tasmania has served to collect. Every adventure narrated is strictly true, and the anecdotes of birds and animals are facts, set down simply from the experience of the Author and her family.

The Author confutes the statement generally accepted by Naturalists, that the Marsupials, in accordance with their low development of brain, show a low degree of intelligence.

Quarto, Gilt Edges, handsomely bound in Cloth, price 21s.

London: MARCUS WARD & CO., 67 and 68, Chandos Street; and Royal Ulster Works, Belfast.

Now ready, post quarto, cloth gilt, 272 pages. Price 16*s*.

LIGHTNING

CONDUCTORS:

THEIR

HISTORY, NATURE, AND MODE OF APPLICATION.

By RICHARD ANDERSON, F.C.S., F.G.S.,

Member of the Society of Telegraph Engineers; Assoc. Inst. C.E.

With numerous Illustrations.

"The book is one to be commended to the builders of, or dwellers in, lofty houses, to the deans of our cathedrals, to the parsons of churches with lofty spires or towers, and to all owners, constructors, or occupiers of buildings which, from their height or situation, are exposed to danger from lightning."—*The Athenæum.*

"The book is clearly and sensibly written, and sufficiently illustrated, and is the work of a practical man who thoroughly understands what he is talking about."—*The Academy.*

London: E. & F. N. SPON, 46, Charing Cross.

New York: 446, Broome Street. 1880.

Small 8vo, 12*s*.

ZOOLOGICAL CLASSIFICATION:

A HANDY BOOK OF REFERENCE.

Second Edition, with Additions and a Glossary.

By FRANCIS P. PASCOE, F.L.S., &c.

"An exceedingly valuable compendium of zoology."—*Popular Science Review.*

VAN VOORST, Paternoster Row.

NOW READY.

SECOND EDITION,

GRIFFIN'S CHEMICAL HANDICRAFT.

PRICE 4*s*. 7*d*. POST FREE.

A CATALOGUE OF CHEMICAL APPARATUS:

ILLUSTRATED, CLASSIFIED, DESCRIPTIVE.

Demy 8vo, 480 pp., Illustrated with 1,600 Woodcuts.

Most Complete and Cheapest List of Apparatus.

JOHN J. GRIFFIN AND SONS, 22, GARRICK STREET, LONDON, W.C.

THOMAS D. RUSSELL'S

NATURAL HISTORY STORES,

48, ESSEX STREET, STRAND, W.C.

Students and others are invited to inspect the Collections of British and Foreign Shells, Corals, Zoophytes, Annelids, Crustacea, Echinoderms, Minerals, Fossils, Rock Specimens, Microscopic Objects, &c.

Cabinets, Geologist's Hammers, Glass Capped Boxes, Card Trays, Tablets, Glass Slips, Micro-Thin Glass, Canada Balsam, Marine Glue, and other requisites for the Geologist and Microscopist.

Catalogues Post Free.

THE BREWERS' GUARDIAN:

A Fortnightly Paper devoted to the Protection of Brewers' Interests, Licensing, Legal, and Parliamentary Matters.

REVIEW OF THE MALT AND HOP TRADES; AND WINE AND SPIRIT TRADE RECORD.

The Organ of the Country Brewers.

"The Brewers' Guardian" is published on the evenings of every alternate Tuesday, and is the only journal officially connected with brewing interests. Subscription, 16*s*. 6*d*. per annum, post free, dating from any quarter-day. Single Copies 1*s*. each. Registered for transmission abroad.

Offices—5, Bond Court, Walbrook, London, E.C.

Fourth Edition, Revised, medium 8vo, cloth, 18*s*.

DESCHANEL'S NATURAL PHILOSOPHY. An Elementary Treatise. Translated and Extended by J. D. EVERETT, D.C.L., F.R.S.E., Professor of Natural Philosophy in Queen's College, Belfast. Illustrated by 760 Wood Engravings and Three Coloured Plates, and accompanied by a Series of Problems.

Also, separately, in Four Parts, limp cloth, 4*s*. 6*d*. each.

Part I.—MECHANICS, HYDROSTATICS, and PNEUMATICS.
Part II.—HEAT. Part III.—ELECTRICITY and MAGNETISM.
Part. IV.—SOUND and LIGHT.

"Systematically arranged, clearly written, and admirably illustrated, it forms a model work for a class in experimental physics."—*Saturday Review.*

Fcap. 8vo, cloth, 3*s*. 6*d*.

ELEMENTARY TEXT-BOOK OF PHYSICS. By Prof. EVERETT, Translator and Editor of Deschanel's "Natural Philosophy," &c. Illustrated by numerous Woodcuts.

"We have no hesitation in warmly recommending it as a good text-book for junior classes."—*Nature.*

London: BLACKIE & SON, 49 and 50, Old Bailey.

New Edition, very much enlarged, 21*s*.

HOW TO WORK WITH THE MICROSCOPE.

By LIONEL S. BEALE, F.R.S.,

President of the Royal Microscopical Society.

THE FIFTH EDITION,

Strongly bound and enlarged to 530 Pages, with 100 Plates, some of which are Coloured, is now ready.

HARRISON & SONS, Pall Mall.

ASTRONOMICAL TELESCOPE.

BATEMAN'S

WONDERFUL £5 5*s*. INSTRUMENT

Is the finest ever yet attempted. 3-inch Achromatic Object Lenses. Entirely constructed of polished brass; total length, 4 feet 10 inches; very highly finished with Altitude and Azimuth Movements, Rackwork, fine Adjustment, one Terrestrial and one Huyghenian Astronomical Eyepiece; will show Jupiter's Belts, Crescent Form of Venus, resolve many Nebulæ and Clusters, and divide many Double Stars, &c., &c. Prospectus post free.

J. BATEMAN,

29, CHEAPSIDE; 104, STRAND; ROYAL POLYTECHNIC, 309, REGENT STREET, AND 131, HIGH HOLBORN, LONDON.

BRYCE-WRIGHT'S LATEST ARRIVALS.

MINERALS.—Crystallised Hessite, Crystallised Golds, Krennerite, Crystallised Atacamites, Malacone, Euclase, Edingtonite, Suzannite, Chanarcillite, Proustite, &c.

METEORITES.—Specimens of the following Falls:—Wold Cottage, Yorkshire; Java; Orvinio, Italy; Amana, Ohio; Tipperary, Ireland; Java; Orvinio, Italy; Estherville; Hainholz; Grosnagy, Russia; Borkut; Carthago Co.; Bates Co.; Sierra di Chaco; Ashville Co.; Bates Co.; Pallas; Ashville Co., &c., &c.

BRYCE-WRIGHT, F.R.G.S., &c.,

Mineralogist and Expert in Gems and Precious Stones,

90, GREAT RUSSELL STREET, BLOOMSBURY, LONDON, W.C.

LY ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
Nature trusts the mind which builds for aye."—WORDSWORTH

MBER 4, 1880

'HE PUBLICATIONS LENGER"

ince the *Challenger* re-
ruise, and the scientific
erhaps somewhat impa-
of the long series of
results of the investiga-
igers who ever left the
pose of enlarging the

ases in which impatience
In the "General Intro-
Thomson prefaces the
n the first volume of the
esponsible, he mentions
collected and preserved
filled 2270 large glass
o glass tubes, and 176
80 tin cases held objects

of material, Sir Wyville
be his duty to obtain, as
, the co-operation of the
artment, irrespective of
ig to find that, in reply
men of science of great
iated themselves with a
ers. This matter being
o be distributed to their
workers, rarely men of
embarked in months or
us investigation. Along
cess of writing out the
executing the illustrations
to be finished before the
ns.
ith the amount of expendi-
all these processes mean,
t seven treatises, illustrated
y executed plates, are now ready for distribution, and that three more volumes of no less magnitude are to be issued before the end of the year; so that the fifteen or sixteen volumes of which the whole work is to consist may reasonably be expected to be in the hands of the public by 1884.

The "Zoological Reports," as these separate treatises upon each group of specimens are termed, are printed as they are completed, and are to be issued, without reference to the order which they will eventually occupy, as soon as sufficient matter to form a volume is ready. Each memoir will be separately paged, and will have its own legend for reference. This arrangement has been adopted in order that working naturalists may have access to the "Reports" as early as practicable, and that the multiplication of synonyms by the simultaneous publication of species by different observers may be avoided. With this object in view, it would perhaps have been even better to have issued every "Report" as it was ready; but it may be that there are practical difficulties in the way of the adoption of this course.

The present writer, though a fairly swift reader, does not profess to have perused the seven elaborate memoirs now presented on behalf of the *Challenger*; nor if he had does he lay claim to that zoological omniscience which would justify him in criticising them in detail. But as Mr. Brady deals with the Ostracoda, Mr. Davidson with the Brachiopoda, Dr. Günther with the Shore Fishes, Prof. Kölliker with the Pennatulidæ, Mr. Moseley with those groups of Corals which he has made his special study, Mr. Parker with the Development of the Chelonian Skull, and Prof. Turner with the Cetacea, it is questionable if any extant finite knowledge is likely to enable its possessor to say anything more or better than they have said on these respective topics. And, as has been already remarked, there can be no sort of doubt as to the artistic excellence of the 122 quarto plates which illustrate and adorn the text.

Sir Wyville Thomson's "General Introduction," however, is extremely readable both in size and in substance, and may be commended to that patient omnivore, the General Reader, who will find in its earlier pages a readily intelligible account of the fittings and appliances of the *Challenger*, and of the means by which the greatest depths of the sea have been made to yield some, at any

rate, of the secrets of the busy life which, contrary to all the beliefs of the naturalists of a past generation, blindly toils and moils in the darkness and cold of the marine abysses.

The latter half of the "Introduction" will be no less interesting to the biologist, since it embodies the general conclusions at which the scientific director of the Expedition has arrived, in a dissertation on the nature and distribution of the fauna of the deep sea.

Sir W. Thomson considers that the most "prominent and remarkable biological result" of the four years' work of the *Challenger* is the final establishment of the fact "that the distribution of living beings has no depth-limit, but that animals of all the marine invertebrate classes, and probably fishes also, exist over the whole of the floor of the ocean." As to the exact nature of this deep-sea fauna at the greatest depths, he speaks with some hesitation; but, at about 2000 fathoms, the list given on pages 36 and 37 proves that there is a large and a varied assemblage of forms of life. Upwards, this characteristic deep-sea fauna extends to about 600 fathoms, and is richest between this depth and 1000 or 1200 fathoms. Around all coasts, in temperate regions, the local shore forms, which occupy successive zones of depth as, on land, they characterise zones of height, gradually die out towards the 200-fathom line. Nor is there any close relation between the abyssal and the shore faunæ of any given latitude or longitude—on the contrary, the abyssal fauna is singularly uniform and appears "to have been derived from a genetic source different from that of the shore fauna." In fact, Sir Wyville Thomson appositely compares the abyssal ocean—that is the sea everywhere below 200 fathoms or thereabouts—to a world-wide lake of comparatively still water, which, in its deeper parts, is very cold, its temperature neither rising nor falling appreciably beyond the average of 35° F.

Thus there is a certain parallel between land and sea distribution, inasmuch as all Alpine floræ present marked analogies with circumpolar floræ. The cold land is discontinuous, whence it presents, as it were, islands of analogous population all over the world; while the cold water being continuous, the continuity in its population is correspondingly unbroken. But the uniformity and invariability of conditions is far more complete in the abyssal lake than on the mountain-tops; and the homogeneity of the population harmonises with that of the medium in which it lives.

Sir Wyville Thomson draws attention to the fact that this widespread abyssal fauna

". . . . has a relation to the deep-water fauna of the Oolite, the Chalk, and the Tertiary formations, so close that it is difficult to suppose it in the main other than the same fauna which has been subjected to a slow and continuous change under slightly varying circumstances according to some law, of the nature of which we have not as yet the remotest knowledge" (p. 49).

"There is every reason to believe that the existing physical conditions of this area date from a very remote period, and that the present fauna of the deep sea may be regarded as directly descended from faunæ which have necessarily occupied the same deep sea. . . . That the present abyssal fauna is the result of progressive change there can be no room for doubt; but it would seem that in this case, the progress has been extremely slow, and that it has been brought about almost in the absence of those causes—such as minor and local oscillations of the crust of the earth producing barriers and affecting climate—on which we are most inclined to depend for the modification of faunæ. The discovery of the abyssal fauna, accordingly, seems to have given us an opportunity of studying a fauna of extreme antiquity, which has arrived at its present condition by a slow process of evolution from which all causes of rapid change have been eliminated" (p. 50).

That the deep-sea fauna presents us with many forms which are the dried and but little modified descendants of Tertiary and Mesozoic species is a proposition which few who attend to the evidence will be disposed to deny. But I may venture to express some doubt, whether it may not be well to keep a conclusion of such gravity and so well founded, apart from views respecting the absence of "minor local oscillations of the crust of the earth" in the area of the present great ocean basins, which Sir Wyville Thomson expresses more fully elsewhere.

"There seems to be sufficient evidence that all changes of level since the close of the Palæozoic period are in direct relation to the present coast lines.

"There does not seem to be a shadow of reason for supposing that the gently undulating plains, extending for over a hundred million of square miles, at a depth of 2500 fathoms beneath the surface of the sea, and presenting, like the land, their local areas of secular elevation and depression, and their centres of more active volcanic disturbance were *ever* raised, at all events in mass, above the level of the sea; such an arrangement, indeed, is inconceivable" (p. 46).

I must plead ignorance of the "sufficient evidence" to which Sir Wyville Thomson refers; in fact, I should have thought that the sufficient evidence lay in the other direction. Surely there is evidence enough and to spare that the Cretaceous sea, inhabited by various forms, some of whose descendants Sir W. Thomson, as I believe justly, recognises in the present deep-sea fauna, once extended from Britain over the greater part of Central and Southern Europe, North Africa, and Western Asia to the Himalayas. In what possible sense can the change of level which has made dry land and sometimes mountain masses of nine-tenths of this vast area be said to be "in direct relation to the present existing coast lines"?

That the abyssal plains were ever all elevated, at once, is certainly so improbable that it may justly be termed inconceivable; but there is nothing, so far as I am aware, in the biological or geological evidence at present accessible, to render untenable the hypothesis that an area of the mid-Atlantic or of the Pacific sea-bed as big as Europe should have been upheaved as high as Mont Blanc and have subsided again any time since the Palæozoic epoch, if there were any grounds for entertaining it.

In concluding the "Introduction" Sir Wyville Thomson expresses "a strong personal impression" on two points. The one is that the study of the abyssal fauna lends a powerful support to the doctrine of evolution. The other is, that "the character of the abyssal fauna refuses to give the least support to the theory which refers the evolution of species to extreme variation guided only by natural selection." But the grounds assigned for the latter opinion are hardly so cogent as might be desirable.

"Species are just as distinctly marked in the abyssal

fauna as elsewhere, each species varying within its definite range as each species appears to have varied at all times past and present" (p. 50).

Exactly so; the abyssal species are like species elsewhere. The difficulties in the way of the application of the evolution of species by variation and selection therefore in this case cannot be greater than elewhere. In fact, from the sentences which end the "Introduction" it seems doubtful whether they are not less than in many other cases.

"Transition forms linking species so closely as to cause a doubt as to their limit are rarely met with. There is usually no difficulty in telling what a thing is" (p. 50).

Hence it appears that the study of the abyssal fauna has satisfied Sir Wyville Thomson that transitional forms are sometimes met with; and that, sometimes, he has found a difficulty in "telling what a thing is." And this admission is all that the most ardent disciple of Mr. Darwin could desire.

However, the value of the great work which is now being brought before the public does not lie in the speculations which may be based upon it, but in the mass and the solidity of the permanent additions which it makes to our knowledge of natural fact. Sir Wyville Thomson and his colleagues must be congratulated on having made an excellent beginning; the looker-on may properly content himself with wishing them a speedy and a good ending.

T. H. HUXLEY

THE LAVA-FIELDS OF NORTH-WESTERN EUROPE

FROM the earliest times of human tradition the basin of the Mediterranean has been the region from which our ideas of volcanoes and volcanic action have been derived. When the old classical mythology passed away and men began to form a more intelligent conception of a nether region of fire, it was from the burning mountains of that basin that the facts were derived which infant philosophy sought to explain. Pindar sang of the crimson floods of fire that rolled down from the summit of Etna to the sea as the buried Typhoeus struggled under his mountain load. Strabo, with matter-of-fact precision and praiseworthy accuracy, described the eruptions of Sicily and the Aeolian Islands, and pointed out that Vesuvius, though it had never been known as an active volcano, yet bore unequivocal marks of having once been corroded by fires that had eventually died out from want of fuel. In later centuries, as the circle of human knowledge and experience has widened, it has still been by the Mediterranean type that the volcanic phenomena of other countries have been judged. When a geologist thinks or writes of volcanoes and volcanic action, it is the structure and products of such mountains as Etna and Vesuvius that are present to his mind. Nowhere over the whole surface of the globe have eruptions been witnessed different in kind though varying in degree from those of the Mediterranean vents. And hence even among those who have specially devoted themselves to the study of volcanoes there has been a tacit assumption that from the earliest times and in all countries of the world where volcanic outbreaks have occurred, it has been from local vents like those of Etna, the Aeolian Islands, the Phlegraean Fields, or the Greek Archipelago.

If one were to assert that this assumption is probably erroneous, that the type of volcanic "cones and craters" has not been in every geological age and all over the earth's surface the prevalent one, that, on the contrary, it is the less portentous, though possibly always the most frequent type of volcanic action, and belongs perhaps to a feebler or waning degree of volcanic excitement—these statements would be received by most European geologists with incredulity, if not with some more pronounced form of dissent. Yet I am convinced that they are well founded, and that a striking illustration of their truth is supplied by the greatest of all the episodes in the volcanic history of Europe—that of the basalt-plateaux of the north-west.

It is now some twelve years since Richthofen pointed out that on the Pacific slope of North America there is evidence of the emission of vast floods of lava without the formation of cones and craters. Geologists interested in these matters may remember with what destructive energy Scrope reviewed his "Natural System of Volcanic Rocks"; how he likened it to the old crude ideas that had been in vogue in his younger days, and which a study of the classical district of Auvergne had done so much to dispel; and how he ridiculed what he regarded as "fanciful ideas" and "untenable distinctions," which it was "a miserable thing" to find still taught in mining-schools abroad. My own reverence for the teaching of so eminent a master and so warm-hearted a friend led me to acquiesce without question in the dictum of the author of "Considerations on Volcanoes." Having rambled over Auvergne with his admirable sections and descriptions in my hand, I knew his contention as to the removal of cones and craters by denudation and the survival of more or less fragmentary plateaux once connected with true cones to be undoubtedly correct with respect at least to that region. Nevertheless there were features of former volcanic action on which the phenomena of modern volcanoes seemed to me to throw very little light. In particular the vast number of fissures which in Britain had been filled with basalt and now formed the well-known and abundant "dykes" appeared hardly to connect themselves with any known phase of volcanism. The area over which these dykes can be traced is probably not less than 100,000 square miles, for they occur from Yorkshire to Orkney, and from Donegal to the mouth of the Tay. As they pierce formations of every age, including the Chalk, as they traverse even the largest faults and cross from one group of rocks into another without interruption or deflection, as they become more numerous towards the great basaltic plateaux of Antrim and the Inner Hebrides, and as they penetrate the older portions of these plateaux, I inferred that the dykes probably belonged to the great volcanic period which witnessed the outburst of these western basalts. Further research has fully confirmed this inference. There can be no doubt that the outpouring of these great floods of lava of which the hills of Antrim, Mull, Morven, Skye, Faroe, and part of Iceland are merely surviving fragments and the extravasation of these thousands of dykes are connected manifestations of volcanic energy during the Miocene period.

But this association of thin nearly level sheets of basalt piled over each other to a depth of sometimes 3,000 feet, with lava-filled fissures sometimes 200 miles distant from

them, presented difficulties which in the light of modern volcanic action remained insoluble. The wonderfully persistent course and horizontality of the basalts with the absence or paucity of interstratified tuffs, and the want of any satisfactory evidence of the thickening and uprise of the basalts towards what might be supposed to be the vents of eruption were problems which again and again I attempted vainly to solve. Nor so long as the incubus of "cones and craters" lies upon one's mind does the question admit of an answer. A recent journey in Western America has at last lifted the mist from my geological vision. Having travelled for many leagues over some of the lava-fields of the Pacific slope, I have been enabled to realise the conditions of volcanism described by Richthofen and, without acquiescing in all his theoretical conclusions, to judge of the reality of the distinction which he rightly drew between "massive eruptions" and ordinary volcanoes with cones and craters. Never shall I forget an afternoon in the autumn of last year upon the great Snake River lava desert of Idaho. It was the last day of a journey of several hundred miles through the volcanic region of the Yellowstone and Madison. We had been riding for two days over fields of basalt, level as lake bottoms, among the valleys, and on the morning of the last day, after an interview with an armed party of Indians (it was only a few days before the disastrous expedition of Major Thornburgh, and the surrounding tribes were said to be already in a ferment), we emerged from the mountains upon the great sea of black lava which seems to stretch illimitably westwards. With minds keenly excited by the incidents of the journey, we rode for hours by the side of that apparently boundless plain. Here and there a trachytic spur projected from the hills, succeeded now and then by a valley up which the black flood of lava would stretch away into the high grounds. It was as if the great plain had been filled with molten rock which had kept its level and wound in and out along the bays and promontories of the mountain-slopes as a sheet of water would have done. Copious springs and streams which issue from the mountains are soon lost under the arid basalt. The Snake River itself, however, has cut out a deep gorge through the basalt down into the trachytic lavas underneath, but winds through the desert without watering it. The precipitous walls of the cañon show that the plain is covered by a succession of parallel sheets of basalt to a depth of several hundred feet. Here and there, I was told, streams that have crossed from the hills and have flowed underneath the lava-desert issue at the base of the cañon-walls, and swell the Snake River on its way to the Pacific. The resemblance of the horizontal basalt-sheets of this region to those with which I was familiar at home brought again vividly before my mind the old problem of our Miocene dykes and Richthofen's rejected type of "massive" or fissure eruptions. I looked round in vain for any central cone from which this great sea of basalt could have flowed. It assuredly had not come from the adjacent mountains, which consisted of older and very different lavas round the worn flanks of which the basalt had eddied. A few solitary cinder cones rose at wide intervals from the basalt plain, as piles of scoriæ sometimes do from the vapour vents on the surface of a Vesuvian lava-stream, and were as unequivocally of secondary origin. Riding hour after hour among these arid wastes, I became convinced that all volcanic phenomena are not to be explained by the ordinary conception of volcanoes, but that there is another and grander type of volcanic action, where, instead of issuing from separate vents and piling up cones of lava and ashes around them, the molten rock has risen in fissures, sometimes accompanied by the discharge of little or no fragmentary material, and has welled forth so as to flood the lower ground with successive horizontal sheets of basalt. Recent renewed examination of the basalt-plateaux and associated dykes in the west of Scotland has assured me that this view of their origin and connection, which first suggested itself to my mind on the lava-plains of Idaho, furnishes the true key to their history.

The date of these lava-floods of the Snake River is in a geological sense quite recent. They have been poured over the bottoms of the present valleys, sealing up beneath their sheets of solid stone river-beds and lake-floors with their layers of gravel and silt. The surface of the lava is in many places black and bare as if it had cooled only a short while ago. Yet there has been time for the excavation of the Snake River cañon to a depth of 700 feet through the basalt-floor of the plain. In so arid a climate, however, the denudation of this floor must be extremely slow. Much of the plain is a verdureless waste of loose sand and dust which has gathered into shifting dunes. Save in the gorges laid open by the main river and some of its tributaries hardly any sections have yet been cut into the volcanic floor. Dykes and other protrusions of basalt occur on the surrounding hills, but the chief fissures or vents of emission are still no doubt buried beneath the lava that escaped from them.

In North-Western Europe, however, the basalt-sheets were erupted as far back as Miocene times. Since then, exposed to many vicissitudes of geological history—subterranean movement and changes of climate, with the whole epigene army of destructive agencies, air, rain, frost, streams, glaciers, and ice-sheets—the volcanic plateaux, trenched by valleys two or three thousand feet deep and a mile or more in breadth, and stripped bodily off many a square mile of ground over which they once spread, have been so scarped and cleft that their very roots have been laid bare. Viewed in the light of the much younger basalts of the Western Territories of North America, their history becomes at last intelligible and more than ever interesting. We are no longer under the supposed necessity of finding volcanic cones vast enough to have poured forth such wide-spread floods of basalt. The sources of the molten rock are to be sought in those innumerable dykes which run across Britain from sea to sea, and which in this view of their relations at once fall into their place in the volcanic history of the time.

No more stupendous series of volcanic phenomena has yet been discovered in any part of the globe. We are first presented with the fact that the crust of the earth over an area which in the British Islands alone amounted to probably not less than 100,000 square miles, but which was only part of the far more extensive region that included the Faroe Islands and Iceland, was rent by innumerable fissures in a prevalent east and west or south-east and north-west direction. These fissures, whether due

to sudden shocks or slow disruption, were produced with such irresistible force as to preserve their linear character and parallelism through rocks of the most diverse nature, and even across old dislocations having a throw of many thousand feet. Yet so steadily and equably did the fissuring proceed over this enormous area, that comparatively seldom was there any vertical displacement of the sides. We rarely meet with a fissure which has been made a true fault with an upthrow and downthrow side.

The next feature is the rise of molten basalt up these thousands of fissures. The most voluminous streams of lava that have issued from any modern volcanic cone appear but as a minor manifestation of volcanic activity when compared with the filling of those countless rents over so wide a region. Mining operations in the Scottish coal-fields have shown that dykes do not always reach the surface. In all parts of the country, too, examples may be observed of breaks in the continuity of dykes. The same dyke vanishes for an interval and reappears on the same line, but is doubtless continuous underneath. What proportion of the dykes ever communicated with the surface at the time of their extravasation is a question that may perhaps never be answered. It is difficult to believe that a considerable number of them did not overflow above ground even far to the east of the main and existing outflows. But so extensive has been the subsequent denudation that all trace of such superficial emission has been removed. The general surface of the country has been lowered by sub-aërial waste several hundred feet at least, and the dykes now protrude as hard ribs of rock across the hills.

Traced westwards the dykes increase in abundance, till at last they reach the great basaltic plateaux. Macculloch long ago sketched them in Skye, rising through the Jurassic rocks and merging into the overlying sheets of basalt. Similar sections occur in the other islands and in the north of Ireland. The lofty mural escarpments presented by the basalt plateaux once extended far beyond the limits to which they have now been reduced. The platform from which they have been removed shows in its abundant dykes the fissures up which the successive discharges of lava rose to the surface, where they overflowed in wide level sheets like those still so fresh and little eroded in Western North America.

That there were intervals between successive outpourings of basalt is indicated by the occasional interstratification of seams of coal and shale between the different flows. These partings contain a fragmentary record of the vegetation which grew on the neighbouring hills and which may even have sometimes found a foothold on the crumbling surface of the basalt floor until overwhelmed by fresh floods of lava. Not a trace of marine organisms has anywhere been found among these interstratifications. There is every reason to believe that the volcanic eruptions were all subaërial. Sheet after sheet was poured forth over the wide valley between the mountains of Donegal and the Outer Hebrides on the one side and those of the north-east of Ireland and the west of Scotland on the other, until the original surface had been buried in some places 3000 feet beneath volcanic ejections.

I believe that the most stupendous outpourings of lava in geological history have been effected not by the familiar type of conical volcano, but by these less known fissure-eruptions. Both types are of course only manifestations in different degrees of the same volcanic energy. It is by no means certain that the "massive" or fissure type belongs wholly to former geological periods. In particular one is disposed to inquire whether the great Icelandic lava-floods of 1783—the most voluminous on record—may not have been connected rather with the opening of wide-reaching fissures than with the emissions of a single volcanic cone. The reality and importance of the grander phase of volcanism marked by fissure-eruptions have been recognised by some of the able geologists who in recent years have explored the Western States and Territories of the American Union. But they have not yet received due acknowledgment on this side of the Atlantic, where the lesser type of cones and craters has been regarded as that by which all volcanic manifestations must be judged. We are fortunate in possessing in the north-west of Europe so magnificent an example of fissure-eruptions, and one which has been so dissected by denudation that its whole structure can be interpreted. The grand examples on the Pacific slope of America have yet to be worked out in detail, and will no doubt cast much fresh light on the subject, more especially upon those phenomena of which in Europe the traces have been removed by denudation. But the other continents also are not without their illustrations. The basaltic plateaux of Abyssinia and the "Deccan traps" of India probably mark the sites of some of the great fissure-eruptions which have produced the lava-fields of the Old World. In their recent admirable *resumé* of the "Geology of India," Messrs. Medlicott and Blanford describe the persistent horizontality of the vast basalt-sheets of the Deccan, the absence of any associated volcanic cones or the least trace of them in that region, and the abundance of dykes in the underlying platform of older rocks where it emerges from beneath the volcanic plateaux. They confess the difficulty of explaining the origin of such enormous outpourings of basalt by reference to any modern volcanic phenomena. Their descriptions of these Indian Cretaceous lava-floods might, however, be almost literally applied to the Miocene plateaux of North-western Europe and to the Pliocene or recent examples of Western North America.

ARCH. GEIKIE

THE ATOMIC THEORY

The Atomic Theory. By Ad. Wurtz, Membre de l'Institut, &c. Translated by E. Cleminshaw, M.A. (London: C. Kegan Paul and Co., 1880.)

THE latest addition to the International Scientific Series is at once a scientific treatise and an artistic work. The translator has very fairly maintained the clearness and crispness of the French style, whereby the book is marked with a distinct individuality and self-completeness.

The sharpness of the impression which this work produces on the mind is gained without making any great sacrifice of accuracy, although it must be confessed there is, in some chapters, a lack of detailed facts, which is against the value of the work as a reference book for the advanced student; and in others there is too free a use of fancy, which faculty is not synonymous with that

other without which no great scientific work can be produced, viz., imagination.

The work is divided into two books: the first, and most valuable, treating of "Atoms," the second of "Atomicity." The historical introduction is very full, and remarkable for the clear exposition of the work of Richter, which was of so much importance in the subsequent development of the doctrine of atoms. The error, which is still fallen into in some books, of attributing the "law of proportionality" to Wenzel is pointed out and corrected.

Full justice is not done to the work of Avogadro, on which, confirmed as it has been by physical evidence, rests the structure of modern chemistry. The distinction between "integral molecules" and "elementary molecules" was clearly stated by Avogadro in 1811, three years before the date of the publication of Ampère's letter to the Comte Berthollet. Ampère's attempt to extend the hypothesis to facts concerning crystalline bodies cannot be regarded as an improvement on the simpler conception of Avogadro.

But throughout this work there is a manifest resolve to abate no jot nor tittle of that assertion, which, made with the plenary knowledge of a chemical Philistine, sounded the keynote of M. Wurtz's well-known "History of the Atomic Theory."

The statement on p. 42 of the reasons for adopting H_2 as the standard of molecular weights is neither clear nor satisfactory. The student might readily suppose that this standard is adopted simply for the sake of convenience; he might also be led to regard the statement of Avogadro's law, on this page, as a deduction from some vaguely-expressed relations between the number of atoms in elementary molecules and the volumes occupied by these atoms.

Few text-books make clear the fundamental deficiency of the Daltonian theory, viz., the absence of any trustworthy means for determining the weights of the "atoms" (or as we now say, molecules) of compound bodies. Dalton, and Berzelius after him, laid down rules for determining these weights, but the rules of both chemists were wholly empirical. "The atomic weight of an element is the smallest amount of that element which combines with unit-weight of hydrogen to form an atom of a compound," but so long as the "atom" of the compound was undefined, the atomic weight of the element could not be determined.

Avogadro furnished chemists with a means of determining the molecular weights of all gasifiable bodies; and in modern chemistry determinations of molecular weights of many compounds of a given element, and analyses of these compounds, must precede the determination of the atomic weight of the element itself.

The atomic weight of an element is the smallest amount of that element—referred to hydrogen as unity—contained in the molecule, that is in two gaseous volumes of any compound thereof. For lack of a clear differentiation between atom and molecule, and for lack of a definite statement of how atomic weights are determined, the full and valuable table, extending from p. 104 to 109, loses much of its meaning. This table, by the way, very closely resembles a table which occurs in Lothar Meyer's "Die modernen Theorieen"; the alterations made by M. Wurtz certainly do not add to the value of the table.

Dalton's objections to the generalisation of Gay Lussac, that "equal volumes of gases contain equal numbers of atoms," was, as we now know, perfectly justifiable, but on p. 35 Dalton is said to have repudiated "the solid support which the great French chemist gave to his ideas."

Gay Lussac's generalisations could not be true, said Dalton, because of such a reaction as that between nitrogen and oxygen, wherein equal volumes of each combine, and the product, nitric oxide, measures twice the volume of either; that is, there are, according to Gay Lussac, twice as many atoms of nitric oxide as of oxygen or nitrogen; but as elementary atoms are chemically indivisible, this is impossible. Berzelius obviated, or rather shirked, the difficulty by applying Gay Lussac's generalisations to elementary gases only, but a full reconciliation between the views of Dalton and those of Gay Lussac was only possible when Avogadro's fruitful idea of the existence of molecules as distinct from atoms was fully recognised in chemical science.

In describing the physical methods for checking atomic weight determinations, the law of Dulong and Petit is stated in too absolute a manner; if the data concerning the specific heats of the elements are carefully considered, it is evident that in many cases the value varies very much with temperature, that in others no direct determination of specific heat has yet been made, and that the law cannot be regarded as a final statement of the connection between the specific heats and atomic weights of the elements.

The state of our knowledge with regard to the structure of molecules, indeed, renders a full understanding of specific heat at present impossible. The dynamical theory of gases has not yet been fully worked out in this direction.

Although the "law of Avogadro" is a deduction from the dynamical theory of gases, and as such is invested with an authority which no mere collection of empirical facts can bestow upon it, yet nowhere in M. Wurtz's book is this insisted upon.

The compromise between an atomic and an equivalent system of notation, which was so long adopted by chemists, is well described and its evils fully laid bare.

The objectors to Avogadro's law are more numerous and more important in France than in this country or in Germany, hence M. Wurtz devotes considerable space to the subject of dissociation, which he discusses with much clearness and wealth of illustration.

The demonstration on pp. 121-123 of the monatomic character of the mercury molecule is admirable.

In the list of names of those who have pointed out relations between the atomic weights of elements and properties of their compounds, there is a serious omission, viz., the name of A. R. Newlands. This subject of relation between atomic weights and properties of compounds is discussed on pp. 154-176. A better idea of Mendelejeff's "periodic law" may be obtained from these pages than probably from any other English text-book, but surely it would have been well had the author more explicitly acknowledged his indebtedness to Lothar Meyer's work. The graphic representation of the relations between the atomic weights and physical properties of the elements—taken from Meyer's book—has not hitherto been in the hands of the English student.

The second part of M. Wurtz's book, dealing with Valency, is not, in our opinion, of equal value with the first.

After reading these chapters one finds it hard to find a reason for introducing into science the conception of valency, so variable and shifting is this property of atoms made to appear.

On p. 229 it is stated that chlorine is monovalent in $HClO$, pentavalent in $HClO_2$, and heptavalent in $HClO_3$.

Scarcely a hint is given of the many objections to extending considerations concerning valency, in any but a most tentative manner, to non-gasifiable bodies. The theory of molecular as distinct from atomic compounds is dismissed; all are regarded as atomic, and the valencies of the atoms seem variable at pleasure. Where proof of the valency of atoms is not forthcoming, assertion is used in its place.

The author's treatment of affinity is not satisfactory. "Affinity is the force of combination, chemical energy." "Atoms attract each other, and this atomic attraction is affinity." "Thus we know that while hydrogen is united to chlorine with extreme energy, oxygen combines with less force." Surely the translator is to blame for some of these sentences.

The theory of valency deserved a more rigorous and exact treatment than M. Wurtz has given it.

We leave the book, feeling that it is the production of a brilliant author, not the work of a deep thinker.

M. M. P. M.

NEW ZEALAND MOLLUSCS

Manual of the New Zealand Mollusca. By Frederick Wollaston Hutton, F.G.S. Published by command. (Wellington, 1880.)

IN an interesting article which appeared in NATURE, vol. xxii. p. 461, entitled "The New Zealand Institute," attention was called to the publications of the Institute and to the excellent work in science achieved by the author of the manual above mentioned, and by many other naturalists, as well by geologists, chemists, astronomers, archæologists, physicists, and philosophers. When the traditional New Zealander visits the ruins of the old country, it is to be feared that he will lament our ignorance instead of expressing his admiration of our past eminence.

Prof. Hutton seems to have contributed to the publications of the Institute a number of valuable papers on "the various divisions of the fauna of New Zealand." We are not quite sure that our knowledge of any one department of the fauna would be so much advanced by a multifarious zoologist as by a specialist who has devoted himself to the study of that department. The division of labour is not less desirable in natural history than in other equally extensive fields of work. The material is so vast that a Linné, Buffon, or Cuvier would be now rather an anachronism than a marvel.

The present work is called "A Systematic and Descriptive Catalogue of the Marine and Land Shells, and of the soft Mollusks and Polyzoa of New Zealand and the adjacent Islands." It belongs to the Colonial Museum and Geological Survey Department, of which Dr. Hector, the well-known geologist, is the director. Its scope is most useful; and, as the preface by Dr. Hector very properly states, "an accurate knowledge of the affinities and distribution of the recent shells of New Zealand is a very necessary element in the geological survey of the country, as it must form the basis of our Tertiary geology, upon the correct deciphering of which many questions of the highest interest depend." And he adds, "Shells afford the most reliable data for palæontologists; but before the extinct shell-fauna can be utilised, the recent shells of the area must be thoroughly determined." This is quite true. We are disposed, however, to carry the process a step further. It is not enough to determine or make out the recent shells, but they must be critically compared with their fossil analogues. For want of such comparison the late Prof. Nyst, M. Vandenbroeck, and other Belgian palæontologists have unfortunately caused some confusion by a wrong identification of recent or living species with Tertiary species.

The "Manual" contains 237 pages. There are no plates or illustrations. It appears to comprise all that is known of the subject, and to have been conscientiously and on the whole carefully written. But, like all other books, it is not faultless. In the Bibliography "Linneus" is the name given as the author of the 12th edition of the "Systema Naturæ." It ought to be "Linné," according to the title-page and dedication. "Gastropoda" is now the usual, as well as correct, spelling of the class, not "Gasteropoda." The shell of the family *Patellidæ* is not a simple cone, but is spiral in the young. The *Bullidæ* are not all eyeless. The sub-order "Lucinacea" is described as having the gills, "one on each side"; but in one of the families of this sub-order there are "two gills on each side." The family "*Radulidæ*" is stated to have the foot "not byssiferous"; *Limahians* with its foot spins a byssus and makes its curious nest. In the "Artificial Key to the Marine Shells" the remarkable class *Solenoconchia* (or as Prof. Hutton in another place prefers to call it, "Scaphopoda") is omitted. The shell in "*Capulidæ*" is described as "not spiral." These and other less important errors can be corrected in a future edition. We regret, but are not surprised, to see the remark that "not much dependence can be placed on the localities in Mr. Cuming's collection," which was purchased for the British Museum at a large price. This is the case with all dealers, and it sadly disturbs our ideas of geographical distribution. We are inclined to question even such species as *Ostrea edulis*, *Mytilus edulis* and *Lucina* (*Loripes*) *divaricata* as indigenous to New Zealand. These are included in a list of sixty-four species believed by the author to be the only New Zealand species of which there is evidence that they are found anywhere else, although he admits that the identification has in most cases been made solely by descriptions and figures. The same remark applies to *Cypræa europæa*, "*Philippia lutea*" = *Solarium hybridum*, *Littorina cærulescens* = *ueritoides*, and *Crepidula unguiformis*. But, *per contra*, the *Saxicava australis* of Lamarck is scarcely a variety of *S. rugosa*, Linné. The diagnosis of the soft parts, or "animal," of *Vitrina* and *Succinea*, viz., "too large to enter the shell," does not suit the European species of those genera. In the family *Assiminiidæ* the eyes are placed not "on the middle of the tentacles," but on their tips. "*Odostomia lactea*" is not the Linnean species of

Turbo, but another species so named by Mr. Angas. Nor is the *Nucula sulcata* of A. Adams the same as Bronn's much older species of that name. But a serious defect of the work consists in the description of the shells. We give one instance among many. *Littorina novæ zealandiæ* is described as "somewhat globosely turbinated," with the whorls "spirally irregularly linearly grooved;" and the characters of the several species are not arranged systematically or in any kind of sequence. Dog-Latin would be almost preferable to such English. Perhaps, however, the description of species made by the late Mr. Reeve may have been copied from his "Conchologia Iconica." Prof. Hutton says that there are "between 300 and 400 species" of the New Zealand mollusca and polyzoa. This is considerably less than half the number of those species which have been recorded as inhabiting the British seas.

J. GWYN JEFFREYS

OUR BOOK SHELF

The Zoological Record for 1878; being vol. xv. of the Record of Zoological Literature, edited by E. C. Rye. (London: John Van Voorst, 1880.)

THIS publication seems to pursue the even tenor of its very useful way. The editor has to acknowledge grants of 250*l.* towards the expenses of the work from the British Association for the Advancement of Science, the Royal Society, and the Zoological Society of London. The "Record of the Arachnida for 1878" has been unavoidably postponed until vol. xvi., and Mr. Kirby has for the future undertaken all of the groups of the Insecta with the exception of the Coleoptera, which the editor will still review. Entomologists will perceive with regret that they thus lose the services of Mr. McLachlan, who has reported on the Neuroptera and Orthoptera since 1869. A special committee has been appointed to endeavour to expedite the publication of the annual volume, and arrangements have been made, both as regards the contributors and printers, which it is hoped will have the eventual effect of bringing out the record of one year's work during the succeeding year. This would be an immense boon, and though it is obvious that it cannot be effected at the first attempt, still the editor confidently expects that the Record of 1879 will be published in the beginning of 1881, and let us hope that ere the end of that year we may also have the Record of that one now coming to a close.

LETTERS TO THE EDITOR

[*The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts. No notice is taken of anonymous communications.*]

[*The Editor urgently requests correspondents to keep their letters as short as possible. The pressure on his space is so great that it is impossible otherwise to ensure the appearance even of communications containing interesting and novel facts.*]

The Recent Gas Explosion

ON my return after the vacation the experiments on the explosion of gases in tubes were continued.

A tube was constructed by winding narrow strips of paper helically round a glass tube about 8 mm. in diameter; two-thirds of the width of the paper being glued, it was so wound as to make a tube of three thicknesses of paper. The interior of the tube was afterwards varnished with shellac. At the ends short pieces of glass tube about 5 mm. in diameter were fixed, one being provided with platinum wires in order to inflame the gas; the total length of the tube was 4360 mm.

The tube was filled with a mixture of oxygen and hydrogen, the end of the glass tube with the wires was plugged with wet cotton wool, the other tube being closed with an india rubber cap; a spark was then passed. At a distance of 650 mm. from the open end, at which the ignition took place, the outer covering of the tube was split; at a distance of 1,900 mm. from the same point was a hole, at 3030-3040 another hole, and at 3085-3100 a third hole. The india-rubber cap was blown off the end of the tube. At the third hole the interior coating of the tube was torn and blown back towards the opening, showing that the orifice had allowed the escape of gas from both directions. Measuring the distances between the holes and the ends of the tube, we have the following numbers:—From end to first split, 650 mm.; from split to first hole, 1250; from first hole to mean of second and third, 1200; from this point to end of tube, 1260.

There seemed to be some doubt as to the uniformity of this tube, so another was made by rolling a strip of paper helically along a glass tube in such a manner that the edges did not overlap. A glued strip was wound over this so as to cover the joint; and a third to cover the joint of the second, the edges not overlapping and yet touching one another throughout. The process was very tedious, and as the result showed, not successful. This tube was 7·5 mm. in diameter, and the glass ends 4·5, the total length being 8390 mm. The end of the tube farthest from the wires was firmly closed, after introducing the explosive mixture. When the gas was exploded in the tube 14 holes were made, in some places the tube giving way at joints, but without any great tear of the paper. Starting from the end of the tube the first hole was at 620 mm., the other holes being distant from one another 650, 530, 100, 475, 375, 320, 580, 455, 370, 885, 2115, 365, 85, and the other end 465 from the last hole.

A third tube was now constructed, but on a different principle. A sheet of glued paper was wound round a brass tube and, at once removed; in this way a tube about 275 mm. long and 135 wide, and consisting of about 5 layers of paper was obtained. Thirty-two of these were joined end to end by glueing narrow strips of paper round the joints. The tube was varnished inside and out, and when completed was 9000 mm. long. The experiment was made after dark, and it was not found out until afterwards that a small quantity of water had entered the tube from the gas-holder while introducing the gas. In this case the explosion made 10 holes, but the joints obviously considerably strengthened the tube in their neighbourhood. The distances between the holes were not more regular than in the previous case. From the end to first hole 757 mm.; the other holes being distant 660, 1595, 146, 484, 230, 295, 308, 1325, 585, to end 2615. The end was not opened by the explosion.

Although these experiments have not exhibited the regularity I anticipated, they show that a tube burst by an explosive mixture must not be expected to open along its whole length.

Cooper's Hill, October 25 HERBERT MCLEOD

Geological Climates

I WAS not surprised at reading Mr. Duncan's letter in supposed reply to my communication to NATURE, vol. xxii. p. 532, as it fully proves my case against the slipshod logic of geologists in general. He writes:—"Where I now write, on the Bag-shot sands and gravels of Cooper's Hill, facing the cold north with a touch of the east, there is a patch of bamboo canes in full leaf. They were in full leaf at this time last year. The plant survived out of doors the extreme frost and fogs of last winter and other evidences of a temperate climate, and it has been in beautiful leaf all this summer.

"Now everybody knows that in torrid India the bamboo grows . . ."

Mr. Duncan might as well have told your readers that where he now writes, "facing the warm south with a touch of the west," he beheld before his astonished eyes a tuft of grasses.

He has not named the *species* of the "patch of bamboo canes" which delighted his eyes, and which "everybody" knows came from "torrid India."

If Mr. Duncan does not know, at least "everybody" does, that species of the bamboo canes flourish in every latitude from Northern China to Southern Chili, including "torrid India," where in some places you may have a half-inch thick of ice, in consequence of the starlight radiation of a clear summer's night.

I have before me a list of twenty-four species of bamboo canes cultivated in most of the gardens of Europe, but they are all, with the exception of a species from the Himalayas (not "torrid India"), imported from the severe climates of Northern Japan and China.

At Fota, in the Cove of Cork, at Bamboo Island, they have lived, fruited, and reproduced themselves for nearly thirty years, and will probably continue to do so in the future, although no Corcagian will be silly enough to believe in consequence thereof that he is living in the climate of "torrid India."

In fact, I adduced the evidence of *Araucaria Cunninghami, a most delicate self-registering plant thermometer*, in testimony of the Eocene climate of Bournemouth; and I find myself confronted with Mr. Duncan's clumsy thermometer with *not a single fixed point on its scale*, in the shape of an unspecified "*clump of bamboo canes.*" Let Mr. Duncan name the species included in his "clump," and I shall discuss the question fully with him.

The facts stated in my letter, although by no means uncommon, prove most convincingly to those who can appreciate them the untenable nature of Lyell's theory of the cause of change of geological climates.

I must state my argument again :—

1. In Eocene times groves of Moreton Bay pine lived, flourished, and held their ground at Bournemouth against all comers.

2. At the present time groves or forests of Moreton Bay pine live, flourish, and hold their ground at Moreton Bay against all comers.

3. Therefore the climate of Bournemouth in Eocene times was similar to that of Moreton Bay at the present time.

Geologists often make use of syllogisms much less conclusive than the above, which is as good as any commonly used in biological reasoning, such as it is.

The present mean temperature of Bournemouth is 20° F. below what it was in Eocene times, which is equivalent to a difference of latitude in the northern hemisphere between 31° N. and 51° N.

Sir Charles Lyell[1] feebly attempts to get rid of scientific conclusions as to temperature in two ways :—

1. By a denial of the specific identity of the former and recent species compared.

2. By the unproved hypothesis of competing plants whose superior vigour and not climatal conditions, account for the absence of the species which formerly flourished.

In the case of the Moreton Bay pine I shall leave Mr. Gardner to defend the asserted identity of species; and I meet Sir Charles Lyell's second supposition (which is really romance writing, and not science) by the assertion that the Moreton Bay pine, even if protected by man, will perish in any locality whose *mean winter temperature* falls below 57° F.

The present mean January temperature of Bournemouth is 37°·4 F., a temperature which would destroy in a single night a whole forest of Moreton Bay pines.

I was of course well aware that my argument from the former existence of Moreton Bay pines at Bournemouth was only one of many similar arguments that might be advanced from the former existence of plants or corals in localities in which they do not now live.

I know nothing, except from books, of the water temperature necessary for the several species of corals, nor do I know whether any species of the tertiary corals found in England are *specifically identical* with corals now living elsewhere. If Mr. Duncan would give us precise information on this subject he would throw most valuable light on geological climates.

The corals would give us more information upon the question than plants, because they would gauge for us the temperature of the water in England; that is to say, the temperature of the former Gulf streams of the tertiary period, from which we could calculate numerically the increase of solar radiation, necessary to produce such former Gulf streams; and possibly afterwards a measure of geological time.

I have elsewhere[2] shown that the fossil tertiary plant beds of the Arctic regions show a falling off of temperature similar to that which has been proved at Bournemouth, of which the following is a summary :—

	Lat.	Mean annual temperature in Miocene time.	Reduction at present.
	°	°	°
Grinnell Land ...	81·44	42·3 F.	44·00 F.
Spitzbergen	78·00	51·8 ,,	35·30 ,,
Disco	70·00	55·6 ,,	36·00 ,,
		Eocene.	
Bournemouth ...	50·50	70·75 ,,	20·35 ,,

I again assert that it is not possible to explain these facts without introducing causes differing in amount from those now acting on our planet.

SAML. HAUGHTON

Trinity College, Dublin, October 16

[1] "Principles," vol. i. p. 173 (twelfth edition).
[2] "Lectures of Physical Geography," p. 344.

The Yang-tse, the Yellow River, and the Pei-ho

I READ with great interest the paper on the Yang-tse, &c., in NATURE, vol. xxii. p. 486. It seems to me that Mr. Guppy has underestimated the quantity of water and sediment in these rivers. As to the Yang-tse, this arises from the year 1877 being one of the driest in Western and Central China generally, and thus the summer flood must have been one of the lowest on record. Besides what we know of the character of the season, an indirect proof of this can be had by comparing the rate of discharge in April and at the time of highest flood, as given by Mr. Guppy, with what is said by Mr. Oxenham, in his paper on the inundations of the Yang-tse.[1] According to the latter the rise of water in April is not very large, the river not yet inundating its banks, and being thirty feet below the summer level. Thus in an average year the discharge in April would by far not equal half of that of August, as found by Mr. Guppy, but more probably be even below one-fifth of that of flood-time.

On this account the data given by Mr. Guppy for the Yang-tse are far below the average as to the discharge of water, and probably even more so as to the amount of sediment, as the proportion of sediment increases during high floods. In 1877 the loess country of North-West China was subject to the severest drought, so that the Han river, which generally contributes so much to the sediment of the main river, must have been very low in summer.

As to the estimation of the discharge of water in the Pei-ho, it is certainly much below the actual quantity, for Mr. Guppy has taken only the months of December to March, *i.e.* months of low water. The monsoon character of the rains, *i.e.* the great prevalence of summer over winter rains, is far more marked in Northern China than in the middle part of that country, so that the flood discharge of the rivers during and after the rains (*i.e.*, from July to October) must be enormously in excess over that of winter. If, as Mr. Guppy says, the Pei-ho rises only six feet at Tien-tsin, this must be due to the banks being very low, so that the river during flood-time inundates the plain to a very great extent.

My conclusion is this :—Mr. Guppy having underestimated the discharge of water of the Yang-tse and Pei-ho in the mean of the year, this must have been even more the case as to the amount of sediment carried. Thus the relatively short time at which he estimates that the surrounding seas will be filled by the sediment carried by the great Chinese rivers has to be greatly shortened, and if he thinks 36,000 years enough for the work, I should estimate that 28,000 years would be sufficient.

A. WOEIKOF

Schpalernajo 8, St. Petersburg, October 15

[1] *Journ.* R. Geog. Soc., 1875.

Greek Fret

IN NATURE, vol. xxii. pp. 513-14, there is a very interesting account of the development of ornament as illustrated by General Pitt Rivers' Anthropological Collection. I would venture to suggest that though in the majority of cases the Greek fret pattern

FIG. 1.—Gateway at Labnah (Plate 19).

was independently evolved in different countries from the "double loop-coil," yet a study of the plates in Mr. Catherwood's beautiful work, "Views of Ancient Monuments in Central America" (1844), suggests to me the probability that the builders of those remarkable structures arrived at the "Greek pattern" through a degradation of the conventionalised human

face. The accompanying tracings from Catherwood's work will sufficiently explain my meaning.

Fig. 1, from the gateway at Labnah, pl. xix.; Fig. 2, from the gateway of the great Teocallis Uxmal, pl. xii.; Fig. 3, from



2.

FIG. 2.—Gateway of the Great Teocallis Uxmal (Plate 12).

Las Monjas Chichen Itza, pl. xxi., illustrate the development of the fret. Fig. 4, from Las Monjas Chichen Itza, pl. xxi., shows another modification of the human face.

In his "Grammar of Ornament" Owen Jones says (p. 35): "In Mr. Catherwood's illustrations of the architecture of Yucatan



3

FIG. 3.—Las Monjas Chichen Itza (Plate 21).

we have several varieties of the Greek fret: one especially is thoroughly Greek. But they are, in general, fragmentary like the Chinese." The reason I would assign for this "fragmentary" nature of the design is that it was just passing from the disjointed *ornament* to the *pattern* stage. An examination of the plates

FIG. 4.—Las Monjas Chichen Itza (Plate 21).

will prove the profuse employment of the more or less grotesquely modified human face in mural decoration.

The hypertrophy of one set of organs, with the atrophy of another, and modification of a third, are paralleled in the specialisations of all degraded forms. ALFRED C. HADDON

Zoological Museum, Cambridge

Temperature of the Breath

I AM unable to see what bearing "I. J. M. P.'s" suggestion that I should try the effect of dipping my thermometer, enveloped in a tightly-rolled handkerchief, in water at 108° has on this subject. Every one of course knows that a thermometer in such circumstances would eventually acquire the temperature of the water in which it is immersed.

The state of the matter is simply this: On the one hand works on physiology agree in stating that the normal temperature of the breath is from 95° to 97°, and that of the interior of the body from 98°·5 to 99°·5. These are what Mr. McNally would call "ascertained physiological truths." On the other hand I find that by breathing on the bulb of a thermometer enveloped in about twenty folds—more or less—of a silk, cotton, or woollen cloth for five minutes, the thermometer indicates temperatures varying—owing to conditions not yet precisely ascertained—from 102° to 108°, which, as every one knows, are temperatures vastly greater than the accepted temperature of the breath or interior of the body.

There is no question of squeezing up the reading of a delicate thermometer by the tightness of the enveloping material, for the thermometer used in these experiments is an ordinary clinical thermometer, such as I use daily in practice, the bulb of which is made of such stout glass that no amount of pressure short of breaking the bulb will move the mercury in the slightest degree.

The following variation in the mode of experimenting precludes the possibility of any pressure on the thermometer. I put the thermometer in a glass tube about three-fourths of an inch bore, open at both ends, packed the stem loosely with cotton wool, but left the bulb free at one end of the tube. I then enveloped the whole in a silk handkerchief and breathed through twelve folds of the material into the end of the tube where the bulb of the thermometer was, untouched by cotton wool, glass tube, or silk handkerchief. After five minutes the thermometer showed a temperature of 102°. In this case, and I believe also in my former experiments, the enveloping material merely acted as a bad conductor, retaining the heat produced by the breath.

As any one can easily repeat these experiments for himself, I would suggest to your correspondents that they should do so. When the facts have been established by reiterated experiments—my own observations have been corroborated by several of my friends—the explanation or significance of them will no doubt be speedily arrived at. Provisionally I suggest that these observations show respiration to be a powerful agent for getting rid of the superfluous caloric of the body.

How is this heat communicated to the breath? If it had anything to do with the conversion of the carbon of the blood into carbonic acid, the quantity of carbonic acid passed off by the breath would be greater when the temperature of the latter is higher, less when it is lower. But Letellier's experiments show that the amount of carbonic acid exhaled is greatly *increased by external cold*, and *diminished by heat*; whereas my experiments apparently show that the temperature of the breath is *lower in external cold, higher in heat*.

To solve the questions suggested by these experiments one would require the aid of a physiological laboratory, but as that is not at my command, and, moreover, as I could not devote the necessary time to them, I must leave their solution to others.

October 20 R. E. DUDGEON

Soaring of Birds

I BEG to send you some data on the above subject, as I live where the phenomenon is of daily occurrence. Most of the large birds but here soar, *i.e.* can circle round and round without flapping the wings, and also can *rise* thus from 100 or 200 feet to some 8,000 by same means. The pelican, the adjutant, and several large birds allied to it, the vulture and the cyrus, rise thus.

Firstly they rise by flapping the wings vigorously, and when up some 100 or 200 feet, *if there is a breeze*, begin to soar in large circular sweeps, rising 10 to 20 feet at each lap, the whole bird being otherwise quite motionless, and the wings extended rigidly.

We have two steady winds here, from north-east and west-south-west, and in one of these the birds rise to great heights, and can be seen as small specks up in the blue, and watched with telescope, going round and round, motionless otherwise. The following data are trustworthy:—The birds weigh from 20 to 40 lbs.; spread of wings, 10 to 12 feet; stand 3 to 5 feet high; speed flying or soaring, about 15 to 35 miles per hour (estimated).

They rise by flapping the wings. If there is no wind they { do not / cannot } soar; they generally begin to soar at 100 to 200 feet elevation when above the level of the forest. In soaring they { do not / cannot } go in a right line, but in large curves of a spiral that leans to *leeward*.

At each lap they can rise 10 to 20 feet, but lose position laterally of 20 to 50 feet to leeward. The soaring can go on without once flapping the wings, till the bird is almost out of sight.

If near, the feather-tips make a loud musical "sing," and the presence often first known by it. If watched, they come

round again nearly to the same place. With gun or rifle against a tree-stem, I have often been able to spot the intersection with my aim beforehand, lap by lap; the drift is to leeward.

I take it the explanation is, that in passing round *with* the wind, and by slightly falling, great impetus is gained, which is slowed down by turning to meet and rise on the wind *like a kite* (if near, this is *seen*). I have seen the albatross and gulls floating, but this case or these cases exemplify a major problem of rising as well steadily and without effort; it is also a clearer problem, the solution of which more or less solves the minor problems of mere flotation.

The line of flight is thus:—



Sapakati, Sibsagor, Asam S. E. PEAL

Regelation

IT is stated in NATURE, vol. xxii. p. 589, that Faraday gave the name of *Regelation* to the phenomenon of two pieces of ice freezing together. Surely this is an error? It was in 1856 when Sir Joseph D. (then Dr.) Hooker, Professors Tyndall and Huxley, and the present writer were in Switzerland together. Prof. Tyndall asked us to suggest a suitable term for the process; and it was Sir Joseph Hooker who said he could think of none better than *Regelation*. Prof. Tyndall instantly accepted it as exactly conveying the meaning he required.

Agassiz, however, in writing upon the difficulties of ascertaining the temperatures of glaciers by introducing thermometers into borings, alludes amongst others to "la difficulté d'extraire les fragmens détachés qui se *regelaient* constamment" ("Études sur les Glaciers," p. 203). This shows that a similar expression had occurred to him as suitable for this phenomenon, as early as 1840, in which year his "Études" were published.

GEORGE HENSLOW

JOHANNES RUDOLF VON WAGNER

WE have already briefly alluded to the loss suffered by chemistry in the sudden death from heart-disease of Prof. von Wagner, which occurred at Würzburg, October 4. Johannes Rudolf Wagner was born February 13, 1822, at Leipzig. As a student in the university of his native city he made choice of chemistry as a profession, and supplemented the then somewhat limited advantages of the Leipzig laboratory by a course of study at Paris, whither students from numerous countries were attracted by the brilliant lectures and investigations of Dumas. His residence there was followed by a lengthy journey to the various centres of scientific interest in France, Belgium, Holland, and Germany, after which he returned in 1846 to Leipzig to accept a position as assistant in the chemical laboratory of the university. In 1851 he was appointed Extraordinary Professor of Technical Chemistry at the Nürnberg Polytechnic. In 1856 he accepted a call to the Chair of Technology at the University of Würzburg, a position which he occupied until the time of his death. During this same time he also filled two important offices, that of Director of the Technological Conservatory at Würzburg, and (until 1868) that of Royal Examiner of the establishments for Technical Instruction in Bavaria. His peculiar abilities and wide range of experience led to his being frequently sent abroad by the Bavarian Government on scientific missions, notably in 1858 to England and Holland, and in 1861 to Paris. The same reasons led to his being called upon to play an important *rôle* in the International Exhibitions of the past twenty years. He was successively appointed on the juries for chemical products at the Exhibitions of London (1862), Paris (1867), and Amsterdam (1869). At Vienna (1873) he was the Chief Commissioner of Bavaria, and at Philadelphia (1876) he was a leading member of the German Commission. The marked services which he rendered in connection with the Vienna Exhibition were recognised by his sovereign, who raised him to the nobility, and decorated him with the Order of the Crown. Prof. von Wagner was the recipient likewise of numerous decorations from most of the European countries.

The career of Wagner has been one of unusual and varied activity. Apart from the multifarious duties of an executive character which we have briefly enumerated, he found time to render to pure chemistry, and especially to applied chemistry, services of incalculable value. Like Poggendorff in physics and Kopp in pure chemistry, his inclination led him towards the literary side of his favourite studies, and it is on his accomplishments as an author that his fame chiefly rests. Still, as an investigator Wagner possessed remarkable and many-sided aptitudes, and his name is associated with numerous researches, the majority of which aim at the practical application of scientific facts, or seek to ascertain the chemical nature of important industrial products. One of his first investigations (1847) was on yeast, and included a thorough study of its nature and growth, and especially of the influence exercised by the presence of foreign bodies on the phenomena of fermentation. In 1849 he commenced a research on the oil of rue, which was carried on at various intervals, and to which we owe much of our knowledge of the constituents of this important essence. In 1850 he assigned to the alkaloïd conine the structure of a dibutyryl-amine, a formula verified long after by Schiff's synthesis (1871) of paraconine, and by Michael and Gundelach's brilliant synthesis a few months since, of methyl-conine. Among other noteworthy theoretical results, mention may be made of his extensive monograph on polymeric isomorphism (1851), and his experiments in the same year establishing the nature of mercur-ammonium compounds as substituted ammonias—mercury replacing hydrogen—by a distillation of the well-known "white precipitate" with amyl-mercaptan, which yielded sulphide of mercury and hydrochloride of amylamine. Shortly after he showed that the compounds imperatorin and peucedonine obtained from the roots of sulphur-wort and allied plants were identical, and established their chemical nature as angelate of the hydrate of peucedyle. One of Wagner's most important researches, commenced in 1850 and taken up several times since, had for an object the colouring-matters of fustic. In its course he discovered morin-tannic acid, which in company with morin gives to fustic wood its tinctorial properties. He studied carefully its reactions and its derivatives; and among the latter discovered pyrocatechin, the product of the destructive distillation of the acid. In 1853 he undertook a thorough examination of the oil of hops, separating the different chemical components, and finding amongst them quercitrin and morin-tannic acid. At this epoch he succeeded in obtaining the remarkable alloy formed by the union of four parts of potassium with 2½ parts of sodium, which is liquid at ordinary temperatures, and resembles mercury in appearance. In 1867 he contributed an interesting research on the rapid increase of solubility of carbonates in water containing carbonic acid under various pressures. At the same time he broached a theory of the formation of deposits of a graphite, in which he attributed it to a decomposition of cyanides in nature analagous to that occurring in the manufacture of soda. Among his more important analytical researches were the determinations (1860) of the quantities of oil present in the nuts and seeds of many forest trees. As an able deviser of analytical methods Wagner exhibited numerous proofs. Among these mention may be made of the use of the iodine reaction for analysing chlorides of lime (1859), the use of iodine likewise for the determination of the alkaloïds (1861), the volumetric deter-

mination of tannic acid by means of sulphate of cinchonine (1866), the test for wool in silk fabrics by using nitro-prusside of sodium to show the presence of the sulphur contained in wool (1867), the application of ammonium vanadate to detect the presence of tannin in red wines (1877), and other tests for detecting methyl-eosine in the presence of eosine, nitrobenzene in the oil of bitter almonds, paraffine in bees-wax, stearic acid in paraffine, &c. Equally numerous were the improved methods of preparing chemical compounds and products introduced by him, including the preparation of pelargonate of ethyl, used extensively in perfumery, of finely-divided copper, of rufigallic acid, of calcium iodide, of precipitated alumina, of chloride of mercury, of arsenate of sodium, of benzoic acid, &c.

Among Wagner's purely technical researches reference may be made to the application of pyrocatechin for photographic purposes (1855), the determination of densities for technical use (1859), the method for purifying water for tinctorial purposes (1863), the use of paraffine for preserving sodium, and his important research (1877) on the reactions of vanadium compounds with a large variety of organic commercial products, in the course of which he obtained several important tinctorial results.

As an author Prof. von Wagner has manifested a degree of talent and a fertility surpassed by but few of his scientific contemporaries. An easy, lucid style, an intimate familiarity with the entire range of subjects touched upon, a fulness of detail united to a logical, systematic treatment of the matters in question, and a happy adaptation to the wants of even elementary knowledge, have rendered his works universal favourites. This is especially true of his "Handbook of Chemical Technology," which has survived a twelfth edition in Germany, and has been rendered accessible to French and English-speaking students by the masterly translations of Gautier and Crookes. It is doubtful whether in any other branch of applied science a manual exists which is so widely disseminated and has met with such practically universal success. Among Wagner's other works are: "Die Chemie" (1860; sixth edition 1873), "Theorie und Praxis der Gewerbe," 5 vols. (1857-64), "Die chemische Fabrikindustrie," second edition (1869), "Regesten der Sodafabrikation" (1866), and "Studien auf der Pariser Ausstellung" (1868). The technical journals of the past thirty years contain numerous monographs from his pen on individual branches of chemical manufacture, full of valuable information and statistics obtained by Wagner from private sources, and replete with those fruitful suggestions natural to a mind familiar at once with the facts of science and with their widespread applications. Unquestionably Wagner's chief literary achievement is his celebrated "Jahresbericht über die Leistungen der chemischen Technologie." Started eight years after the appearance of Liebig and Kopp's well-known "Jahresbericht" for chemistry in all its departments, this work of Wagner's has for a quarter of a century kept the industrial and scientific world promptly, thoroughly, and accurately informed of the progress made in every branch of applied chemistry. In its fulness and exactness it is an admirable type of the annual review, now regarded as indispensable for every branch of human activity by the German mind; and the vast influence which it has exercised upon the development of chemical industries is impossible to measure. The "Jahresbericht" for 1879, recently issued, forms a portly volume of 1,300 pages, with over one hundred woodcuts, and in its reviews evidences at every step a critical spirit able to cope with the scientific and practical questions constantly evoked.

Personally Prof. von Wagner was of a most attractive disposition, admired by his students not only for his rare talents as a lecturer, but also for his amiable character. His loss is felt as severely in a widespread social circle as in the world of science. T. H. N.

JAPAN[1]

II.

MISS BIRD'S work on Japan, as we have said, is cast in quite a different mould from that of Sir Edward Reed. With the exception of one or two chapters, she devotes her two volumes entirely to a record of her own experiences, casting them as in her well-known books on the Sandwich Islands and the Rocky Mountains, into the form of a series of letters. These have evidently been written in the midst of the experiences which they record, and this gives them a reality and a freshness which they could not have otherwise had. Her "Unbeaten Tracks in Japan" has all the best characteristics of her book on the Sandwich Islands. Indeed it seems to us that for the majority of readers it will have far more of novelty and quite as much interest as any of her previous works, while we doubt if any other book on Japan yet published gives so full and real an insight into the everyday life and the condition of the bulk of the people. Her work well deserves the title it bears. Many of the districts into which she, amidst all sorts of difficulties, succeeded in penetrating were certainly never before visited by a European woman, if indeed by a European of either sex. Sir E. Reed speaks of the people along parts of his route rushing out to see the "Chinese" pass; but so strange and literally uncouth did Miss Bird's appearance seem in some districts that the people could only set her down as an "Aino." She of course saw all the usual sights in the usual tracks, all that Sir Edward Reed saw; and for this her intimacy with Sir Harry Parkes and his universally beloved lady procured her every facility. The result is not the almost unmixed admiration which we find in Sir Edward Reed's volumes; but then it should be remembered that she was not the guest of the Japanese Government, but practically of the representative of the English Government; and although Miss Bird is a thoroughly independent observer, still her *opinions* may have taken somewhat of their colour from her special surroundings. She states fully both sides of the question of Japanese progress, and while giving full credit to the Government for the best intentions, and admitting that vast progress has been made in recent years, still she has many drawbacks to point out. And no wonder; we fear that she, like some others who write on Japan, look for too much, and expect to find a Europe in the East, instead of a country struggling out of the bonds that swaddled it till only fifteen years ago. Still her criticisms are wholesome, and charitable, and good-natured, and we trust that they will come under the notice of those to whom, if taken in good part, they might be greatly beneficial. Miss Bird has much to say on the work of missionaries in Japan, but that is a subject into which we cannot enter here. She spent much of her time in the great centres among missionaries, and had ample opportunities of seeing the nature of the work they are doing. And her observations are of the greatest interest, and must be instructive to those who are hoping that the Japanese will ultimately put on the religious habiliments which have been shaped for centuries to the people of the West. One unfortunate result we may mention, and that is the deterioration of the manners of those who have been long under missionary influence. Surely this is not necessary.

Of course the great interest of Miss Bird's book is connected with her solitary journey, quite unhampered by official guidance, north through the centre of the Main Island, and most of all her sojourn in Yezo among the strange remnant of people known as Ainos. Her journey

[1] "Japan: its History, Traditions, and Religions, with the Narrative of a Visit in 1879." By Sir Edward J. Reed, K.C.B., F.R.S., M.P. Two vols. With Map and Illustrations. (London: John Murray, 1880.) "Unbeaten Tracks in Japan." By Isabella L. Bird. Two vols. With Map and Illustrations. (Same Publisher.) Continued from vol. xxii. p. 612.

through the Main Island gives us the other side of the picture to that seen in such well-known centres as Tokio, Yokohama, and Kioto—by far the finest city in Japan, the home of art and culture, according to Miss Bird. She gives very sad and sometimes very disgusting pictures of the condition of the people in some parts of the country through which she passed with her amusing and clever guide Ito. In one district the villages, she tells us, have reached the lowest abyss of filthiness; still she found the people here, as everywhere else, courteous, kindly, industrious, and free from gross crimes. Indeed, although naturally an object of intense interest wherever she went, and the centre of hundreds and sometimes thousands of eyes, she had rarely if ever to complain of discourtesy. Everywhere everybody was courteous and obliging, and except in the open towns, rarely was an attempt at extortion made. While part of the centre of the island is dreary enough, much of it is of the rarest beauty, with its fine mountains, rich woods, and rapid deeply cutting rivers. At Niigata and other open ports she notes with satisfaction the rapid spread of European medical treatment under the care of the medical missionaries, some of whom are doing excellent work. At Niigata, especially Dr. Palm's influence is wide-spread, and thousands of people have been weaned from the Chinese system of treatment to that offered by Dr. Palm and his numerous native assistants, most of them men of the best type, who have established among themselves a society similar to some of the medical societies which meet in London and elsewhere. At Niigata Miss Bird made the acquaintance of an interesting bookseller. "This bookseller, who was remarkably communicative, and seems very intelligent, tells me that there is not the same demand now as formerly for native works on the history, geography, and botany of Japan. He showed me a folio work on botany in four thick volumes, which gives root, stalk, leaf, flower, and seed of every plant delineated (and there are 400), drawn with the most painstaking botanical accuracy, and admirable fidelity to colour. This is a book of very great value and interest. He has translations of some of the works of Huxley, Darwin, and Herbert Spencer, which, he says, are bought by the young men attending the higher school. The 'Origin of Species' has the largest sale. This man asked me many questions about the publishing and bookselling trade in England, and Ito acquitted himself admirably as an interpreter. He had not a single book on any subject connected with religion."

In a letter from Kaminoyama, to the north-east of Niigata, she gives a graphic picture of the incongruities to be met with in the present transition state of the country:—"We rode for four hours through these beautiful villages on a road four feet wide, and then, to my surprise, after ferrying a river, emerged at Tsukuno upon what appears on the map as a secondary road, but which is in reality a main road twenty-five feet wide, well kept, trenched on both sides, and with a line of telegraph poles along it. It was a new world at once. The road for many miles was thronged with well-dressed foot-passengers, *kurumas*, pack-horses, and waggons either with solid wheels, or wheels with spokes but no tires. It is a capital carriage-road, but without carriages. In such civilised circumstances it was curious to see two or four brown-skinned men pulling the carts, and quite often a man and his wife—the man unclothed, and the woman unclothed to her waist—doing the same. Also it struck me as incongruous to see telegraph wires above, and below, men whose only clothing consisted of a sun-hat and fan; while children with books and slates were returning from school, conning their lessons."

As far north as Kubota, quite 200 miles north of Niigata, Miss Bird found a normal school established, with twenty-five teachers and 700 pupils between the ages of six and twenty. "They teach reading, writing, arithmetic, geography, history, political economy after John Stuart Mill, chemistry, botany, a course of natural science, geometry, and mensuration." Indeed she found evidence everywhere of the schoolmaster being abroad all over the country, and of the purpose of the Government to make education, after the models of Europe and America, universal and compulsory; and among the educated classes, the familiarity with the works of the most advanced English scientific writers—Huxley, Darwin, and Spencer especially—struck her greatly.

FIG. 1.—Ainos of Yezo.

To the ethnologist Miss Bird's notes on the Ainos, the

aborigines of the Island of Yezo, and possibly of all Japan, will prove of special interest. We already know much about the physique and the habits of these strange people; but Miss Bird's notes of what she saw and heard during the weeks she lived in their houses, saw their daily life, heard what they had to say of themselves, their history, and their superstitions, are a real addition to our existing knowledge of them. As usual all sorts of things were said by people in Hakodaté to prevent her from trusting herself alone among these uncivilised people, but Miss Bird took her own womanly way, and was rewarded. These Ainos she found of fierce outer aspect, with their long shaggy hair and beards, broad faces, and rough bodies, but in speech and manner gentler than the gentlest Hawaiian. Their soft and feminine speech constantly struck her, and in genuine politeness they are not surpassed by the Japanese. Here is a picture of Aino domestic life:—

FIG. 2.—Aino Houses.

"I am in the lonely Aino land, and I think that the most interesting of my travelling experiences has been the living for three days and two nights in an Aino hut, and seeing and sharing the daily life of complete savages who go on with their ordinary occupations just as if I were not among them. I found yesterday a most fatiguing and over-exciting day, as everything was new and interesting, even the extracting from men who have few if any ideas in common with me, all I could extract concerning their religions and customs, and that through an interpreter. I got up at six this morning to write out my notes, and have been writing for five hours, and there is shortly the prospect of another savage *séance*. The distractions, as you imagine, are many. At this moment a savage is taking a cup of *saké* by the fire in the centre of the floor. He salutes me by extending his hands and waving them towards his face, and then dips a rod in the *saké*, and makes six libations to the god—an upright piece of wood with a fringe of shavings planted in the floor of the room. Then he waves the cup several times towards himself, makes other libations to the fire, and drinks. Ten other men and women are sitting along each side of the fire-hole, the chief's wife is cooking, the men are apathetically contemplating the preparation of their food; and the other women, who are never idle, are splitting the bark of which they make their clothes. I occupy the guest seat—a raised platform at one end of the fire, with the skin of a black bear thrown over it."

FIG. 3.—Ainos at home (From a Japanese sketch).

These Ainos drink enormous quantities of *saké*, the national liquor of Japan; they can drink three times as much as a Japanese without being affected by it, and the drinking of it is with them the chief act of worship to the rude gods, if gods they be, which are stuck up in various parts of their huts. Here is another picture:—

"About nine the stew was ready, and the women ladled it into lacquer bowls with wooden spoons. The men were served first, but all ate together. Afterwards *saké*, their curse, was poured into lacquer bowls, and across each bowl a finely-carved '*saké-stick*' was laid. These sticks are very highly prized. The bowls were waved several time with an inward motion, then each man took his stick and, dipping it into the *saké*, made six libations to the fire, and several to the 'god,' a wooden post, with a quantity of spiral white shavings falling from near the top."

The intense fondness of the Ainos for their children is a marked feature in their character, and the instantaneous and implicit obedience of the latter to their parents is as great as with the Japanese themselves. Their hospitality is genuine, universal, and almost profuse. "In every house the same honour was paid to a guest. This seems a savage virtue which is not strong enough to survive much contact with civilisation. Before I entered one lodge the woman brought several of the finer mats, and arranged them as a pathway for me to walk to the fire upon. They will not accept anything for lodging or for anything that they give, so I was anxious to help them by buying some of their handiwork, but found even this a difficult matter. They were very anxious to give, but when I desired to buy they said they did not wish to part with their things. I wanted what they had in actual use, such as a tobacco-box and pipe-sheath, and knives with carved handles and scabbards, and for three of these I offered 2½ dollars. They said they did not care to sell them, but in the evening they came saying they were not worth more than 1 dollar 10 cents, and they would sell them for that; and I could not get them to take more. They said it was 'not their custom.'"

All that Miss Bird tells us of her visit to the Ainos is well worth quoting; but we have space for only one more quotation, and that with reference to their physique:—

"After the yellow skins, the stiff horse hair, the feeble eyelids, the elongated eyes, the sloping eyebrows, the flat noses, the sunken chests, the Mongolian features, the puny physique, the shaky walk of the men, the restricted totter of the women, and the general impression of degeneracy conveyed by the appearance of the Japanese, the Ainos make a very singular impression. All but two or three that I have seen are the most ferocious-looking of savages, with a physique vigorous enough for carrying out the most ferocious intentions, but as soon as they speak the countenance brightens into a smile as gentle as that of a woman, something which can never be forgotten. The men are about the middle height, broad-chested, broad-shouldered, 'thick-set,' very strongly built, the arms and legs short, thick, and muscular, the hands and feet large. The bodies, and specially the limbs, of many are covered with short bristly hair. I have seen two boys whose backs are covered with fur as fine and soft as that of a cat. The heads and faces are very striking. The foreheads are very high, broad, and prominent, and at first sight give one the impression of an unusual capacity for intellectual development; the ears are small and set low; the noses are straight, but short, and broad at the nostrils; the mouths are wide, but well formed; and the lips rarely show a tendency to fulness. The neck is short, the cranium rounded, the cheek-bones low, and the lower part of the face is small as compared with the upper, the peculiarity called a 'jowl' being unknown. The eyebrows are full, and form a straight line nearly across the face. The eyes are large, tolerably deeply set, and very beautiful, the colour a rich liquid brown, the expression singularly soft, and the eyelashes long, silky, and abundant. The skin has the Italian olive tint, but in most cases is thin, and light enough to show the changes of colour in the cheek. The teeth are small, regular, and very white; the incisors and 'eye teeth' are not disproportionately large, as is usually the case among the Japanese; there is no tendency towards prognathism; and the fold of integument which conceals the upper eyelids of the Japanese is never to be met with. The features, expression, and aspect are European rather than Asiatic.

"The 'ferocious savagery' of the appearance of the men is produced by a profusion of thick soft black hair, divided in the middle, and falling in heavy masses nearly to the shoulders. Out of doors it is kept from falling over the face by a fillet round the brow. The beards are equally profuse, quite magnificent, and generally wavy, and in the case of the old men they give a truly patriarchal and venerable aspect, in spite of the yellow tinge produced by smoke and want of cleanliness. The savage look produced by the masses of hair and beard, and the thick eyebrows, is mitigated by the softness in the dreamy brown eyes, and is altogether obliterated by the exceeding sweetness of the smile, which belongs in greater or less degree to all the rougher sex.

"I have measured the height of thirty of the adult men of this village, and it ranges from 5 feet 4 inches to 5 feet 6½ inches. The circumference of the heads averages 22·1 inches, and the arc, from ear to ear, 13 inches. According to Mr. Davies the average weight of the Aino adult masculine brain, ascertained by measurement of Aino skulls, is 45·90 ounces avoirdupois, a brain weight said to exceed that of all the races, Hindoo and Mussulman, on the Indian plains, and that of the aboriginal races of India and Ceylon, and is only paralleled by that of the races of the Himalayas, the Siamese, and the Chinese Burmese. Mr. Davies says, further, that it exceeds the mean brain weight of Asiatic races in general. Yet with all this the Ainos are a stupid people!"

The coast Ainos, Miss Bird tells us, she found had more hair on their bodies than those in the interior, and in some other respects differed in appearance, a difference probably to be accounted for by their mode of life and their surroundings. The Aino garments are often exceedingly handsome, being decorated with "geometrical" patterns in which the Greek fret takes part, in coarse blue cotton, braided most dexterously with scarlet and white thread. The modesty of the women is very remarkable, sometimes almost excessive even to European notions; nor do they seem to be the unmitigated drudges that most savage women are. The great hero of the Ainos is Yoshitsuné, who is also the most popular hero of Japanese history; the Ainos worship him, and Miss Bird was permitted to visit his shrine on a hill near Biratori, the Aino village at which she spent most of her time. He lived in the twelfth century, and was the brother of the Shôgun of the time, whose jealousy, according to some, compelled him to take refuge in Yezo. "None believe this more firmly than the Ainos themselves, who assert that he taught their fathers the arts of civilisation, with letters and numbers, and gave them righteous laws, and he is worshipped by many of them under a name which signifies Master of the Law. I have been told by old men in Biratori, Usu, and Lebungé, that a later Japanese conqueror carried away the books in which the arts were written, and that since his time the arts themselves have been lost, and the Ainos have fallen into their present condition! On asking why the Ainos do not make vessels of iron and clay as well as knives and spears, the invariable answer is, 'The Japanese took away the books.'" This, combined with some other things which Miss Bird tells us of these Ainos, makes it seem quite possible that they are now a degenerate remnant of a people who formerly were comparatively cultured, and who may possibly have had "books" which the Japanese, their conquerors and masters, "took away." These strange people are certainly worthy of further study. The illustrations we are able to give, by the kindness of Mr. Murray, will give the reader some idea of their appearance and habits. We strongly recommend the reader to go to Miss Bird's volumes for further information of what she saw and heard while sojourning among them.

Again we commend these two works to all who desire to get, in comparatively short space, a very complete view of the past history and present condition of Japan.

BELL'S PHOTOPHONE

BY the courtesy of Prof. Graham Bell we are at length able to do somewhat ampler justice to his latest discovery than has hitherto been possible. He has supplied us with certain details not hitherto published, and has also furnished us with drawings of his apparatus and experiments. Prof. Bell is at present in Paris, and, as was mentioned in our columns last week, has there repeated some of his experiments.

Our readers are already aware that the object of the photophone is the transmission of sounds both musical and vocal to a distance by the agency of a beam of light of varying intensity; and that the first successful attempts made by Prof. Bell and his co-labourer, Mr. Sumner Tainter, were based upon the known property of the element selenium, the electric resistance of which varies with the degree of illumination to which it is exposed. Hence, given a transmitting instrument such as a flexible mirror by which the vibrations of a sound could throw into vibration a beam of light, a receiver consisting of sensitive selenium forming part of an electric circuit with a battery and a telephone should suffice to translate the varying intensities of light into corresponding varying intensities of electric current, and finally into vibrations of the telephone disk audible once more as *sound*. This funda-

mental conception dates from 1878, when in lecturing before the Royal Institution Prof. Bell announced the possibility of hearing a shadow fall upon a piece of selenium included in a telephone circuit. The photophone, however, outgrew the particular electrical combination that suggested it; for not the least of the remarkable points in this research is the discovery that audible vibrations are set up in thin disks of almost every kind of



FIG. 1.—The Musical Telephone.

material by merely throwing upon them an intermittent light. Hence in theory, if not in practice, the receiver may be reduced to the divine simplicity of a mere disk of



FIG. 2.—Theoretical Diagram of the Articulating Photophone.

vulcanite or of zinc, on one side of which the vibrating beam of light falls, and at the other side of which the hearer listens.



FIG. 3.—Section of the Selenium Receiver, shown at s in Fig. 2.

With the photophone, however, as with the telephone, there are instruments of different degrees of perfection. The original imperfect musical telephone of Philip Reis could only transmit musical tones, because it worked by rapid abrupt interruptions of the electric current; while the articulating telephone of Graham Bell was able to transmit speech, since by its essential construction it was able to send undulating currents to the distant receiving station.

We may in like manner classify the forms of photophone under two heads, as (1) articulating photophones, and (2) musical photophones; the former being able to transmit speech because they work by beams of light whose intensity can vary in undulatory fluctuations, like those of vocal tones; the latter being able to transmit simple musical tones only, since they work by mere *interruptions* of a fixed beam of light.

Up to the present time, Prof. Bell informs us, the simple receiving disk of ebonite or hard rubber has only served for a musical photophone: the reproduction of the tones of the voice by its means has not yet been demonstrated in practice—at least to his satisfaction. For while it produces unmistakable musical tones by the direct action of an intermittent light, in the experiments made hitherto with articulate speech the instruments have by necessity been so near to one another that the voice of the speaker was audible through the air. Under these circumstances it is extremely difficult to say whether the sounds that are heard proceed from the diaphragm, or whether they merely came through the air to the ear, and if they come from the diaphragm, whether they are really the result of the varying light, and not mere sound vibrations taken up by the disk from the speaker's voice crossing the air. Prof. Bell hopes soon to settle this point, however, by an appeal to experiment on a larger scale with the receiving and transmitting instruments at greater distances apart, and with glass windows in between to shut off all sounds.

In Fig. 1 we illustrate the simple musical photophone of Bell and Tainter. It might perhaps be described without injustice as an *optical siren*, producing sounds from intermittent beams of light, as the *siren* of Cagniard de Latour produces them from intermittent puffs of air. A beam of light from the sun or from a powerful artificial source, such as an electric lamp, falls upon a mirror M, and is reflected through a large lens L, which concentrates

the rays to a focus. Just at the focus is interposed a disk pierced with holes—forty or so in number—arranged in a circle. This disk can be rotated so that the light is interrupted from one to five or six hundred times per second. The intermittent beam thus produced is received by a lens T, or a pair of lenses upon a common support, whose function is to render the beam once more parallel, or to concentrate it upon the disk of ebonite placed immediately behind, but not quite touching them. From the disk a tube conveys the sounds to the ear. We may remind our readers here that this apparent direct conversion of light into sound takes place, as Prof. Bell found, in disks of all kinds of substances—hard rubber, zinc, antimony, selenium, ivory, parchment, wood, and that he has lately found that disks of carbon and of thin glass, which he formerly thought exceptions to this property, do also behave in the same way. We may perhaps remark without impropriety that it is extremely improbable that the apparent conversion of light into sound is by any means a direct process. It is well known that luminiferous rays, when absorbed at the surface of a medium, warm that surface slightly, and must therefore produce physical and molecular actions in its structure. If it can be shown that this warming effect and an intermediate cooling by conduction can go on with such excessive rapidity that beams of light falling on the surface at intervals less than the hundredth of a second apart produce a discontinuous molecular action of alternate expansion and contraction, then the mysterious property of matter revealed by these experiments is accounted for.

However this may be, the musical photophone, as represented in Fig. 1, produces very distinct sounds, of whose existence and dependence for their production on the light the listener may satisfy himself by cutting off the light at any moment with the little opaque disk fixed on the end of the little lever just in front of the holes in disk R, and which can be worked by a Morse key like a telegraph instrument, thus producing at will alternate sounds and silences. With this musical photophone sounds have been carried by an interrupted beam of light for a distance exceeding a mile; there appears, indeed, no reason why a much greater range might not be attained.

The articulating photophone is that to which hitherto public attention has been most largely directed, and in which a selenium receiver plays a part. Fig. 2 gives in diagram form the essential parts of this arrangement. A mirror M reflects a beam of light as before through a lens L, and (if desired for the purpose of experimentally cutting off the heat-rays) through a cell A containing alum-water, and casts it upon the transmitter B. This transmitter, shown again in Fig. 5, consists of a little disk of thin glass, silvered on the front, of about the size of the disk of an ordinary telephone, and mounted in a frame, with a flexible india-rubber tube about sixteen inches long leading to a mouthpiece. A second lens R, interposed in the beam of light after reflection at the little mirror, renders the rays approximately parallel. The general view of the transmitting apparatus given in Fig. 5 enables the relative sizes and positions of the various parts (minus the alum-cell which is omitted) to be seen. The screw adjustments of the support serve to direct the beam of light in the desired direction.

It may be well to explain once for all *how* the vibrations of the voice can affect the intensity of the reflected beam far away. The lenses are so adjusted that when the mirror B is flat (*i.e.* when not vibrating) the beam projected from the apparatus to the distant station shall be nearly focussed on the receiving instrument. Owing to the optical difficulties of the problem it is impossible that the focussing can be more than approximate. Now, matters being thus arranged, when the speaker's voice is thrown against the disk B it is set into vibration, becomes alternately bulged out and in, and made slightly convex or concave, the degree of its alteration in form varying with every vibration of the voice. Suppose at any instant —say by a sudden displacement such as takes place when the letter "T" is sounded—the disk becomes considerably convex; the beam of light will no longer be concentrated upon the receiving instrument, but will cover a much wider area. Of the whole beam, therefore, only a relatively small portion will fall upon the receiving instrument; and it is therefore possible to conceive that, if perfectly adjusted, the illumination should be proportional to the displacement of the disk, and vary therefore with every vibration with the utmost fidelity.

The receiver of the articulating photophone is shown on the right-hand side of the diagram (Fig. 2) sketched by Prof. Bell. A mirror of parabolic curve C C serves to concentrate the beam and to reflect it down upon the selenium cell S, which is included in the circuit of a battery P along with a pair of telephones T and T. Here again a general view like that given in Fig. 6 facilitates the comprehension of the principal parts of the apparatus. The sensitive selenium cell is seen in the hollow of the parabolic mirror which is mounted so as to be turned in any desired direction. The battery standing upon the ground furnishes a current which flows through the selenium cell and through the telephones. When a ray of light falls on the selenium—be it for ever so short an instant—the selenium increases in conductivity, and instantly transmits a larger amount of electricity, and the observer with the telephones hears the ray, or the succession of them;—hears



FIG. 4.—Diagram to show the action of the Selenium Receiver.

indeed their every fluctuation in a series of sounds which, since each vibration corresponds to a vibration of the voice of the distant speaker, reproduce the speaker's tones.

The great difficulty to be overcome in the use of selenium as a working substance arose from its very high resistance. To reduce this to the smallest possible quantity, and at the same time to use a sufficiently large surface whereon to receive the beam of light, was the problem to be solved before any practical result could be arrived at. After many preliminary trials with gratings and perforated disks of various kinds, Prof. Bell and Mr. Tainter finally settled upon the ingenious device to be described. A number of round brass disks, about two inches in diameter, and a number of mica disks of a diameter slightly less, were piled upon one another so as to form a cylinder about two and a half inches in length. They were clamped together from end to end, the clamping rods also serving to unite the disks of brass electrically in two sets, alternate disks being joined, the 1st, 3rd, 5th, &c., being united together, and the 2nd, 4th, 6th, &c., being united in another series. This done, the edges between the brass disks were next filled with seleninum, which was rubbed in at a temperature sufficiently high to reach the melting-point of selenium. After this the selenium was carefully annealed to bring it into the sensitive crystalline state. Then the cell is placed in a lathe and the superfluous selenium is turned off until the edges of the brass disks are bared. Fig. 3 shows, in section, the construction of such a cell. Prof. Bell has also used cells in which the selenium filled only the *alternate* spaces between disks, the intermediate spaces being occupied by

mica disks of equal diameter with the brass disks. But this arrangement was in no way preferable, for in practice



FIG. 5.—The Articulating Photophone. The Transmitter.

it was found that moisture was apt to penetrate at the surface of the bare mica, spoiling the effect.

Fig. 4 is a diagram which simply illustrates the action of the selenium receiver, and shows, firstly, the way of



FIG. 6.—The Articulating Photophone. The Selenium Receiver.

connecting the alternate disks; and secondly, that the current from the battery P cannot go round the telephone

circuit without passing somewhere through selenium from one brass disk to the next. The special advantages of the "cell" devised by Prof. Bell are that in the first place the thickness of the selenium that the current must traverse is nowhere very great; that in the second, this photo-electrical action of light on selenium being almost entirely a *surface* action, the arrangement by which all the selenium used is a thin surface film could hardly be improved upon; and that thirdly, the symmetry of the cylindrical cell specially adapts it for use in the parabolic mirror. These details will be of great interest especially to those who desire to repeat for themselves the experimental transmission of sound by light. The greatest distance to which articulate speech has yet been transmitted by the selenium-cell-photophone is 213 metres, or 233 yards.

When sunlight is not available recourse must be had to an artificial source of sufficient power. During the recent experiments made by Prof. Bell in Paris the weather has been adverse, and the electric light has been called into requisition in the *ateliers* of M. Bregnet (Fig. 7, which is kindly supplied us by Prof. Bell). The distance in these experiments between the transmitting diaphragm B and the parabolic reflector C C of the receiver was fifteen metres, the entire length of the room in which



FIG. 7.—The Photophone with Electric Light.

the experiments were made. Since at this distance the spoken words were themselves perfectly audible across the air, the telephones connected with the selenium-cell were placed in another apartment, where the voices were heard without difficulty and without doubt as to the means of transmission.

Of the earlier and less perfect forms of the photophone little need be said. One device, which in Prof. Bell's hands worked very successfully over a distance of eighty-six yards, consisted in letting the beam of light pass through a double grating of parallel slits lying close to one another, one of which was fixed, the other movable and attached to a vibrating diaphragm. When these were placed exactly one in front of the other the light could traverse the apparatus, but as the movable grating slid more or less in front of the fixed one more or less of the light was cut off. Speaking to the diaphragm therefore caused vibrations which shut or opened, as it were, a door for the beam of light, and altered its intensity. The mirror transmitter of thin glass silvered was however found superior to all others; and it is hard to see how it could be improved upon, unless possibly by the use of a thin disk of silver itself accurately surfaced and polished.

Whatever be the future before the photophone, it assuredly deserves to rank in estimation beside the now familiar names of the telephone and the phonograph.

NOTES

THE Triennial Gold Medal of the Chemical Section of the Philosophical Society of Glasgow, founded in commemoration of the work of Thomas Graham, F.R.S., late Master of the Mint, will be awarded, at the end of the present session, for the best paper on any subject in pure or applied chemistry. Authors are requested to send in their papers not later than February 1, 1881, addressed to the Secretary of the Section, Dr. J. J. Dobbie, Chemical Laboratory, University of Glasgow.

THE annual meeting of the five academies which constitute the French Institute was held on Monday last week, when M. E. Levasseur gave an address on the Ethnography of France, and Col. Perrier described the operation he undertook to connect geodetically Algeria and Spain.

THE Royal Institution Lecture arrangements (not yet complete) for the ensuing season (before Easter) will include the Christmas course by Prof. Dewar; and courses by Professors Tyndall and Schäfer, the Rev. William Haughton, the Rev. H. R. Haweis, Mr. H. H. Statham, Mr. Reginald S. Poole, and others. Friday Evening Discourses will probably be given by Mr. Warren De La Rue, Prof. Tyndall, Sir John Lubbock, Sir William Thomson, Dr. J. Burdon Sanderson, Dr. Andrew Wilson, Dr. Arthur Schuster, Mr. Alexander Buchan, Dr. W. H. Stone, Dr. W. J. Russell.

THE death is announced of Sir Thomas Bouch, the engineer of the Tay Bridge. It is believed that his system received a severe shock on account of the Tay Bridge disaster and the proceedings consequent on it.

M. ERHARD, the well-known French cartographer, died on October 23. M. Erhard was a naturalised Frenchman, having been born at Freiburg-im-Breisgau.

AMONG Mr. Stanford's announcements of forthcoming works are the following:—"Prehistoric Europe: a Geological Sketch," by Dr. James Geikie, F.R.S.; a fourth edition of "The Coal-Fields of Great Britain," by Prof. Edward Hull, F.R.S.; "Life and her Children: Glimpses of Animal Life from the Amœba to the Insects," by Arabella B. Buckley; "Index Geographicus Indicus: a Gazetteer of India," by J. F. Barness; "The Flora of Algeria, considered in Relation to the Physical History of the Mediterranean Region and Supposed Submergence of the Sahara," by W. Mathews; "Water Supply of England and Wales: its Geology, Underground Circulation, Surface Distribution, and Statistics," by C. E. de Rance.

IN the November number of *Scribner's Monthly* is a curious article on Second Sight or Clairvoyance, by an "Ex-Conjuror" (Mr. Henry Hatton), in which it is shown that the whole thing is an elaborate system of mnemonics. The article has all the appearance of being genuine.

IN reference to the notice in NATURE, vol. xxii. p. 587, on the address of Dr. Karl Zittel on the subject of the geology of the Libyan Desert, we should state that while the paper contains Zittel's opinions of the observations and collections of other travellers, it is mainly derived from the Professor's personal examination of the physiography of that country, and of the fossils which he there collected, when, as a member of the expedition under the leadership of Dr. Rohlfs, he visited the Libyan Desert in the winter of 1873-74.

THE lecture on "The Modifications of the External Aspects of Organic Nature produced by Man's Interference," delivered by Prof. Rolleston to the Royal Geographical Society in 1879, has just been published in that Society's *Journal*. Amongst other interesting matters Prof. Rolleston rectifies an error into which all or most translators of Cæsar have fallen respecting

the Scotch fir. Cæsar ("De Bello Gallico," v. 12) says of Britain, "Materia cujusque generis, ut in Gallia, est *præter fagum atque abietem*," which words have been generally taken to mean, "There is wood of all kinds to be found in Britain, as in Gaul, *except* the beech and the fir." The word *præter* however does not always mean "except," but sometimes "besides," as quotations from Cicero and Plautus aptly illustrate. Prof. Rolleston further remarks that "an historian who was or was not a professed botanist, might without any sensible man blaming him, speak nowadays of all the common pines 'Scotch,' 'umbrella,' 'cluster,' &c., as 'pines'; my present belief is that Julius would similarly have spoken of them all as *abietes*, and would probably have included the 'firs' proper under the same name as these 'pines.'"

AT the last meeting of the Epping Forest and County of Essex Naturalists' Field Club, held Saturday, October 30, it was announced that H.R.H. the Duke of Connaught, Ranger, had consented to become the Patron of the Club. Arrangements are being made to get up a course of winter science lectures in connection with the Club, the first of these being fixed for November 10, by Mr. J. E. Harting, who will lecture on "Forest Animals." It was further announced that a lecture had been promised during the session by Mr. A. R. Wallace.

PROF. BOYD DAWKINS has lately shown in his "Early Man in Britain" that "although the Neolithic men were immeasurably above the Cave-men in culture, they were far below them in the arts of design;" and further that the Cave-man "possessed a singular talent for representing the animals he hunted, and his sketches reveal to us that he had a capacity for seeing the beauty and grace of natural form not much inferior to that which is the result of long-continued civilisation in ourselves, and very much higher than that of his successors in Europe in the Neolithic age." That this faculty of design or artistic aptitude is still independent of advanced or advancing civilisation is shown by Dr. Holub in a paper "On the Central South African Tribes," just published in the *Journal* of the Anthropological Institute. Mr. Holub remarks in connection with the Bushmen, that these people "regarded as the lowest types of Africans, in one thing excel all the other South African tribes whose acquaintance I made between the south coast and 10° south latitude. I have in my possession about 200 sketches on wood and stone and ostrich shells, by various tribes, but every one who knows anything about drawing must acknowledge that those which were done by Bushmen are superior to any of the others."

IT is stated that some samples of a new seed and also of the native cucumber, collected in Central Australia by Mr. Vesey Brown, have been received at the Sydney Botanical Gardens. The former is a small black pea, which grows in pods similar to those of the ordinary pea; it is supposed to be edible, and resembles the nardoo. The cucumbers are about the size of walnuts, and are said to make an excellent pickle.

A RECENT report to the Foreign Office by Mr. Consul Crawford at Oporto on matters connected with the wine trade contains observations on the ravages of the parasitic insect, *Phylloxera vastatrix*, in the port wine district, and the means taken to avert them, and is illustrated by a sketch map of Northern Portugal, showing the progress of the disease.

AT the opening meeting of the Eastbourne Natural History Society on October 15, Mr. F. C. S. Roper read a paper on the additions to the fauna and flora of the Cuckmere district during the past year.

IN the Fourteenth Annual Report of the Aëronautical Society of Great Britain are papers on Aëronautics, by Mr. T. Moy, the "Mechanical Action of the Air," by Mr. Phillips; "Artificial Flight," by Mr. F. W. Brearey; "Aërial Propellers," by Mr. R. C. Jay.

VALPARAISO advices to August 21 give particulars of the earthquake of August 14. The *Chilian Times* says:—"The duration of the shock was nearly ninety seconds. No serious damage was done to buildings in Valparaiso. At Vina del Mar, one of the towers of the church fell and another was shaken out of its level, and will probably have to be pulled down. The roof of the Quillota parish church fell in. At Llaillai eighteen or twenty houses were destroyed. Illapel suffered very severely. One strange item reported is the occurrence of 'huracane de agua,' whatever they may be. The Governor of Illapel in his first telegram stated that three of these had burst in the Cordillera. Now it is stated that there were thirty observed. One paper spoke of them as 'water volcanoes.' From Coquimbo it is reported that high columns of water were thrown up from the bay. An *employé* of the Transandine Telegraph Company felt the shock while crossing the highest parts of the Andes. He states that it was the strongest earthquake he has ever felt."

A NAPLES telegram of November 2 states that Vesuvius is now very active; lava continues to flow from the crater, and present indications point to the probability of increased eruptive energy.

THE first meeting of the Society of Arts is announced for November 17, when the opening address will be delivered by F. J. Bramwell, F.R.S., Chairman of the Council. Before Christmas the following papers will be read:—November 24—"Barry's Influence on English Art," by J. Comyns Carr. December 1—"The Photophone," by W. H. Preece. December 8—"London Fogs," by Dr. A. Carpenter. December 15—"The Use of Sound for Signals," by E. Price Edwards. The following papers are down on the list for reading after Christmas:—"Buying and Selling: its Nature and its Tools," by Prof. Bonamy Price. "The Participation of Labour in the Profits of Enterprise," by Sedley Taylor, M.A., *late Fellow* of Trinity College, Cambridge. "The Gold Fields of India," by Hyde Clarke. "Flashing Signals for Lighthouses," by Sir William Thomson, F.R.S. "The Present Condition of the Art of Wood-carving in England," by J. Hungerford Pollen, "Ten Years' Experience of the Working of the Trade Mark Act," by E. C. Johnson. "Trade Prospects," by Stephen Bourne. "The Manufacture of Aërated Waters," by T. B. Bruce Warren. "The Compound Air Engine," by Col. F. Beaumont, R.E. "Improvements in the Treatment of Esparto for the Manufacture of Paper," by William Arnot, F.C.S. "Deep Sea Investigation, and the Apparatus used in it," by J. Y. Buchanan. "The Discrimination and Artistic Use of Precious Stones," by Prof. A. H. Church. "Indian Agriculture," by W. R. Robertson. Five courses of lectures are announced under the Cantor bequest: First course—Five lectures on "Some Points of Contact between the Scientific and Artistic Aspects of Pottery and Porcelain," by Prof. A. C. Church. Second Course—Three lectures on "Watchmaking," by Edward Rigg, M.A. Third course—Four lectures on "The Scientific Principles involved in Electric Lighting," by Prof. W. G. Adams, F.R.S. Fourth course—Three lectures on "The Art of Lace-making," by Alan S. Cole. Fifth course—Three lectures on "Colour Blindness and its Influence upon Various Industries," by R. Brudenell Carter. The two Juvenile Lectures, for children of Members, during the Christmas holidays, will be by G. J. Romanes, F.R.S., on "Animal Intelligence." The arrangements for the "Indian," "Foreign and Colonial," and "Chemical and Physical" Sections will be announced after Christmas.

THE following is the title of the essay to which the "Howard Medal" of the Statistical Society will be awarded in November,

1881 :—"On the Jail Fever, from the earliest Black Assize to the last recorded outbreak in recent times." The essays to be sent in on or before June 30, 1881. The Council have decided to grant the sum of 20*l.* to the writer who may gain the "Howard Medal" in November, 1881.

THE additions to the Zoological Society's Gardens during the past week include a Sykes's Monkey (*Cercopithecus albigularis*) from West Africa, presented by the Officers of the Royal Yacht; a Green Monkey (*Cercopithecus callitrichus*) from West Africa, presented by Mr. A. Haynes; a Rhesus Monkey (*Macacus erythræus*) from India, presented by the Rev. J. Saunders, B.A.; a Two-toed Sloth (*Cholopus didactylus*) from Demerara, presented by Mr. G. H. Hawtayne, C.M.Z.S.; an Egyptian Jerboa (*Dipus ægyptius*) from Egypt, presented by Major Money; a Common Trumpeter (*Psophia crepitans*) from Demerara, presented by Mr. J. Stovell; two Silver Pheasants (*Euplocamus nycthemerus*) from China, presented by Miss C. Hallett; an Indian Gazelle (*Gazella bennetti*) from India, deposited; an Ursine Dasyure (*Dasyurus ursinus*) from Tasmania, a Common Wigeon (*Mareca penelope*), a Grey Plover (*Squatarcola helvetica*), a Knot (*Tringa canutus*), a Greenshank (*Totanus cadidris*), British, a Horned Ceratophrys (*Ceratophrys cornuta*) from Santa Marta, purchased.

OUR ASTRONOMICAL COLUMN

THE COMETS OF 1812 AND 1815.—We learn from M. Schulhof, of the Bureau des Longitudes, Paris, that in conjunction with M. Bossert he has undertaken a rigorous investigation of the orbit of the comet of 1812, which Encke showed to have a period of about seventy years, and which will consequently be again approaching its perihelion. M. Schulhof hopes to complete the calculations early in the ensuing year. He has discovered a series of original observations by Blanpain at Marseilles, which he considers to be amongst the best, if not the best series that are available; the original observations by Lindenau have also been received, but unfortunately nothing is to be found of the long series by Zach and Triesnecker. From the manuscripts preserved at Paris some corrections have been applicable to the results as printed. To this we may add that Flaugergues' differences of right ascension and declination from his comparison stars are published in the fifth volume of Zach's *Correspondance astronomique*. These observations of Flaugergues' at Viviers, and those made at Paris as they appear in the first folio volume, were reduced several years since by Mr. W. E. Plummer, now of the University observatory, Oxford, and from three very carefully formed normals he deduced a period of revolution about a year and a half shorter than that assigned by Encke in *Zeitschrift für Astronomie*, t. ii., so that the comet may now be expected at any time. At the instance of Prof. Winnecke sweeping ephemerides have been prepared by M. Mahn of Strassburg. It is however M. Schulhof's intention, on the completion of his investigation of the orbit, to furnish observers with ephemerides similar to those which have led to the re-discovery of several lost planets.

An able calculator at Vienna has nearly finished a new discussion of the observations of the comet of 1815 (Olbers' comet), which, according to Bessel's researches, is due at perihelion in February, 1887. This result may be materially changed by the more complete reduction of such series of observations as we possess in their original form, and a recomputation of the perturbations, with more accurate values of the planetary masses than were available at the date of Bessel's work.

CERASKI'S CIRCUMPOLAR VARIABLE STAR.—From the estimated magnitudes of Schwerd and Carrington, and Mr. Knott's epoch of minimum given in NATURE last week, the most probable period appears to be 2·49085d., to be reckoned from 1880, October 23·4672 Greenwich mean time. While the telescope is turned towards Ceraski's star, it may be suggested that Lalande 1013-4 in Cassiopeia should receive attention; at present we have the discordant estimates 10m. and 5m. of Lalande, 1790 September 29, and 1797 November 10 respectively, and 7·7 in the *Durchmusterung*; the star is 6m. on Harding's Atlas, and is not found in Fedorenko's catalogue, or in Argelander's zones; its position for 1880 is in R.A. 0h. 33m. 22s., N.P.D. 38° 46·8′.

THE LONGITUDE OF THE CAPE.—We understand that arrangements are being made for the telegraphic connection of the Royal Observatory, Cape of Good Hope, with Aden, which has already been connected with Greenwich, Mr. Gill taking an active part in the operation. The next desirable work of this kind will be the connection of an Australian observatory with the observatory at Madras, which is well-determined with reference to Greenwich.

GEOGRAPHICAL NOTES

COL. PREJEVALSKY writes from "Houi-de-Tin, plateau of the Hoang-ho, May, 1880." Having packed up and sent off all his collections to Alashan, he left his camp, 25 versts from the town of Donkyr, on March 20, to reach the Hoang-ho, 83 versts from Donkyr. Here the Yellow River turns abruptly from north-east to east, at the small valley of Gomi, inhabited by Tungut cultivators, and forming the extreme point of the habitable lands of the Hoang-ho. The river here is pretty wide, and has a very rapid current. The banks are wooded, with here and there pretty clumps of poplars and weeping willows. The river here is 8,000 feet above sea-level. After ten days at Gomi, Prejevalsky's party resumed their route. From Gomi the journey along the Hoang-ho was very difficult, the banks being deeply cut by steep ravines, which can only be noticed when close upon them. A stream usually flows at the bottom of these ravines, which are bordered by trees and wild arbutus. As soon as ever the party touched the Si-Fan territory a horseman appeared and, telling them they would soon be murdered, disappeared—a threat happily not realised. Indeed the Si-Fan became so reconciled to the presence of the intruders as to sell them butter and sheep. At 130 versts from Gomi they found in the ravines bordering the river vast forests frequented by innumerable birds, especially blue pheasants. The second local rarity was rhubarb, which was met with in prodigious quantities. The old roots of this plant reach colossal proportions. One of these roots, taken at hazard, weighed 26 lb. The mouth of the Churmysh, an affluent of the Hoang-ho, was reached 130 versts below Gomi, by the course of the river. Having examined the country for a distance of 40 versts, Prejevalsky was convinced that it was impossible to cross the enormous chain of mountains which extends along the Yellow River, the summits of which are lost in the clouds. Gaping ravines are met with at every verst, and there is not the least trace of vegetation, and therefore no forage for animals. He decided to return to Gomi. Thence he went to Houi-De, 60 versts on the south bank of the river, and sent his interpreter to Sinin to inform the local authorities that Prejevalsky wished to reach the mountain regions of eternal snow. The Amban of Sinin informed Prejevalsky that it was impossible to allow him to proceed to the Koko-nor, or to penetrate further into Houi-De, where there was a revolt of the Tunguts. Prejevalsky decided to spend the month of June where he was, exploring the fauna and flora, and afterwards go north towards Cheibsen, where he would remain during July, and complete his explorations in the mountains. The weather, he says, was detestable, cold and wet, with the thermometer sometimes 12° below zero C. He had collected 250 specimens of plants, 500 species of birds, and many of fish. The geography of the country traversed had, moreover, been observed and noted, astronomical, barometrical, and thermometrical observations made, and sketches taken of the various types of natives. He doubts much whether the Hoang-ho makes the enormous curve represented in maps; he did not observe any such curve in the 250 versts explored by him. He expected to reach Alashan about August 20.

IN the Geographical Society's *Proceedings* for November Mr. C. R. Markham supplies a brief but lucid account of Lieut. Schwatka's expedition to King William Land, and of the previous state of our knowledge respecting the remains, &c., of the Franklin Expedition, and he arrives at the conclusion that we have gained but little by this last attempt to obtain information beyond that gathered by Sir L. McClintock. Lieut. Schwatka's journey, however, he considers to have been a most remarkable one, and in some respects without a parallel. Dr. Christison follows with a paper descriptive of a journey made some twelve years ago to Central Uruguay. The geographical notes are numerous this month, and furnish much useful information, especially in regard to Africa. Under the head of "Corre-

spondence" we find letters by Adm. R. C. Mayne on a possible communication between Skyring Water, Straits of Magellan, and Smyth's Channel, and by Capt. Alexanderson on the subject of some observations made during a recent voyage along the Loango Coast of West Africa. The maps given this month are of King William Land and the Estancia de San Jorge, Uruguay, with a small inset map of the whole republic.

As we announced last week, the Vienna Geographical Society has issued an appeal for subscriptions for an Austrian expedition, which Dr. Emil Holub has decided on undertaking. Dr. Holub intends crossing the whole length of Africa from south to north. He will start from the Cape of Good Hope and penetrate to the Zambesi, thence explore the Maruthemambunda territory, the watershed district between the Zambesi and the Congo, visit the lake sources of the Congo, and from there through Darfur he will try to reach Egypt. Dr. Holub expects the journey to extend over three years. The expenses, he reckons, will amount to about 50,000 florins, 5000 of which he can himself supply.

Lord Aberdare will preside at the first meeting of the Geographical Society next Monday evening, when Mr. Jos. Thomson, the Commander of the East African Expedition, who has lately returned from Zanzibar, will give an account of his journey to the Lukuga outlet of Lake Tanganyika, *viâ* the head of Lake Nyassa. Mr. Thomson's paper promises to be unusually interesting, as the country traversed by him was for the most part previously unexplored.

Another African traveller, Mr. James Stewart, C.E., has just returned to England from Livingstonia, Lake Nyassa. Mr. Stewart, it will be remembered, also crossed the unknown belt of country between Lakes Nyassa and Tanganyika by a different route, for the most part, from Mr. Thomson's, and arrived at the south end of the latter lake only a day or two after him.

In the November number of their *Chronicle* the London Missionary Society publish a full account of Dr. Southon's interview with Mirambo on the subject of the murder of Messrs. Carter and Cadenhead, and the main facts elicited by him appear to exonerate that chief from any direct share in the unfortunate occurrence. Mohammed, Capt. Carter's servant, succeeded in saving the journals of both Carter and Cadenhead, and all the most important manuscripts and letters of the former.

The Baptist Missionary Society hope to publish in the December number of their *Herald* an admirable map which they have just received from the Rev. T. J. Comber of their Congo Mission, who has been for some time stationed at San Salvador. It is stated to be very carefully drawn to scale, and to exhibit the many and important discoveries made by the missionaries in their various journeys towards Stanley Pool; it will also show the relative positions of the various towns to Banana, Mboma, San Salvador, Makuta, and other important centres.

The new *Bulletin* of the Antwerp Geographical Society contains papers by M. Bernardin on the Fiji Islands, their resources, progress, &c., and by Dr. L. Delgeur, vice-president of the Society, on cartography among the ancients.

We have received from Danzig an excellent little guide-book to that city, with special reference to the scientific and medicinal points of interest of the town and district, compiled from the recent meeting of the German Association. It is a model of its kind, and contains an admirable series of special maps.

Doctors Rohlfs and Stecker have left Suez for Massowah and Abyssinia.

In the *North American Review* are appearing M. Desiré Charnay's notes of his exploring work in Mexico. The November number contains the third instalment.

KEW GARDENS REPORT

From the just-issued "Report on the Progress and Condition of the Royal Gardens at Kew" for 1879 we take the following items:—

Some idea of the magnitude of the destruction caused by the hailstorm of August 3, 1879, may be obtained from the fact that the number of panes broken was 38,649, and the weight of broken glass eighteen tons. The plantations along the Grass Avenue skirting the river have all been greatly improved, very poor specimens removed and replaced by Holm oaks, which will eventually render the avenue practically an evergreen one. This portion of the grounds suffers greatly from the unconsumed smoke of the gas-works and manufactories at Brentford, which is not only most prejudicial to the plants, but so blackens the labels that they become illegible in a few years. Some interesting notes are given on the cultivation of the various kinds of india-rubber. According to Hecht, Levis, and Kahn's Report for 1879, Para rubber (*Hevea*) is still the largest source of supply. The total import into England during the year was 4651 tons. Liverpool received 25 tons of Ceará Scrap rubber and 900 tons of African (*Landolphia*), while London imported 350 tons from Assam (*Ficus elastica*), 250 tons from Borneo (*Willughbeia*), and 550 from Mozambique (*Landolphia*). Considerable attention has been paid at Kew during the past year to the examination of the African Landolphias and Malayan rubber-yielding Willughbeias, and the results will be given in the next report. Additional facts to those contained in the previous Report are given on the introduction of South American species into the Old World. From Singapore Mr. Murton reports:—"The plants of Hevea and Castilloa in the gardens are now large plants, but hitherto propagation from the strong growths they are making seems rather difficult, whereas they used to propagate freely from the weak wood produced while in pots.' Preparations are being made in Burma for the cultivation of Ceará Scrap (*Manihot glasiovii*), while Dr. King reports that the Ceará rubber promises to grow well in Calcutta; seeds have been distributed to various parts of India, and the plant seems to thrive well in Upper India. Singapore does not seem to suit Ceará Scrap, according to Mr. Murton, while at Zanzibar it yields seed most abundantly, but the seeds are slow to germinate. At Zanzibar the Pará rubber is a less quick grower than the Ceará and does not branch. At Mergui eight Pará trees, the survivors of a batch of seedlings received from Dr. King in 1877, continue to do well in the office compound. At Calcutta, according to Dr. King, Pará rubber continues to be as disappointing as ever; he believes it is useless to try it anywhere except in the south of Burma or the Andamans, and perhaps in Malabar. Mr. Jenman reports that the atmospheric conditions in Jamaica appear favourably adapted to the Pará rubber. Equally important information is given as to the cultivation of mahogany in the Old World. On this the Report says: "This may now be regarded as an accepted success. The tree grows well in many parts of India and in Ceylon, and in the former there is a local demand for the wood. In this country new uses are found for it, one of the most recent being for the linings and panellings of railway carriages instead of teak, which is now exclusively used for ship-building. It is not easy to see any valid arguments against the cultivation of a tree the timber of which is of admitted excellence for a variety of purposes and the growth of which is apparently attended with little difficulty. As late as 1876 the Government of Bengal was adverse to mahogany planting. This policy has now, however, been modified, and in his report for 1878–79 Dr. Brandis, the Inspector-General of Forests, reports: 'Of the exotic trees which are cultivated by way of experiment mahogany is the most important, and its success seems not improbable, though it is too early yet to form final conclusions upon the subject.' Mahogany is also cultivated as an experiment in Burma and the Chittagong district of Bengal. The tree is known to thrive well near Calcutta, and every effort should be made to cultivate it in those forest districts where climate and other circumstances are favourable." Experiments are being made in Queensland, and favourable reports come from Saharunpore and Singapore. Some curious notes are contained in the Report on Chestnut Flour: "We are indebted to Mr. D. E. Colnaghi, H.B.M.'s Consul at Florence, for specimens of the dried chestnuts, flours, and *necci* (the cakes made from them), which are so important an article of subsistence in the Apennines. The collection of the specimens for Kew was due to the kindness of Dr. L. Bacci of Castigliano, in the mountains of Pistoja. The fresh chestnuts are dried, or rather roasted, for three days and nights in a *seccatoio*, or drying room, on a latticed floor covering a chamber in which a fire is lighted. The husk is then easily removable, and the kernel is ready to be ground into flour, which is of a pinkish colour. This is mixed to the consistence of cream with water, and poured on fresh chestnut leaves to be baked into small circular cakes, *necci*, between heated stones. The collection having been divided between the museum of the Royal Gardens and the Food Collection, Bethnal Green, Prof. Church, who has charge of the latter, has obligingly furnished us with the following analysis of the flour:—

Moisture	14·0
Oil or fat	2·0
Proteids	8·5
Starch	29·2
Dextrin and soluble starch	22·9
Sugar	17·5
Cellulose, &c.	3·3
Ash	2·6
	100·0

The cakes were found to contain only 6·7 per cent. of proteids, with 3·4 per cent. of flour. The large amount of dextrin is due to the high temperature to which the chestnuts are subjected in the process of drying. Prof. Church thinks that chestnut-flour ought to be of easy digestibility, and a suitable children's food, considering that it contains over 40 per cent. of nutritious matters soluble in pure water. The Museum of the Royal Gardens is indebted to Mr. George Maw for a specimen of a product used, according to the Rev. Wentworth Webster, who procured it, as tea in the Basses Pyrenées in France, and on the Spanish side of the Pyrenées in Navarre. It was found to consist of the dried shoots of a species of *Lithospermum*, which was identified with probability as *L. officinale*." Mr. Noble advocates the cultivation of rye-straw (*Secale cereale*) as a paper material, not inferior to esparto. Mr. W. L. Booker, H.M.'s Consul at San Francisco, sent some specimens of a scented wood from the highlands of Mexico, known as Lin-a-Loa, and which has been identified with a wood already in the Kew Museum, and which appears to be yielded by a species of *Bursera*. Further material in the shape of dried specimens, with both fruit and flowers, is much to be desired for the purpose of ascertaining definitely the tree which produces it. The name Lin-a-Loa is clearly a corruption of Lign Aloës, which has been identified with *Aquilaria agallocha*, otherwise known as eaglewood (Kew Report, 1878, p. 36). This is however a tree confined to the Old World, and the Mexican one has no connection with it. The wood of the latter is imported into this country for manufacture into perfumery, a fragrant oil known as otto of linaloe being distilled from it. On the interesting Chinese timber-tree known as the Nan-mu-tree, and referred to in the Report for 1877, some information has been obtained from Mr. Baber:—"Two days' journey south-east of Chungking in Szechuen I found several specimens of about a foot in diameter, one of them having a straight branchless trunk of 100 feet in height, with the branches and foliage rising 25 feet above that; another had 70 feet of bare straight stem, and 90 feet of total altitude. Although the trunks are branchless, yet in many cases they send out shoots resembling saplings, which rise parallel with the trunk. The wood is white and close-grained, and I do not believe that the pillars at the Ming tombs near Peking are of this wood. They look more like true teak. I have seen some much larger trees than the above, some two feet and more in diameter, straight and of great altitude. They are used in Szechuen for bridge work." Eventually, through the instrumentality of Père Vincot, who resides at Chungking, flowering specimens were transmitted to the Kew Herbarium. From these a figure has been prepared, and they entirely confirm the previous identification of the tree by Prof. Oliver (from the leaves alone) as a near ally of *Phœbe pallida* (one of the laurel family). The genus *Phœbe* is now merged in *Persea*, and Prof. Oliver has described the Nan-mu under the name of *Persea nan-mu*, distinguishing it from *Persea* (*Phœbe*) *pallida* "chiefly in stature, in the form of the acumen of the leaves and the character of the indumentum." On a block of Pai-chai wood sent by Mr. W. M. Cooper, H.B.M.'s Consul at Ningpo, Mr. R. J. Scott reports:—"The most striking quality I have observed in this wood is its capacity for retaining water and the facility with which it surrenders it. This section, which represents one-tenth of the original piece, weighed 3 lbs. 4½ ozs. At the end of twenty-one days it had lost 1 lb. 6¾ ozs. in an unheated chamber. At the end of another fourteen days, in a much elevated temperature, it only lost ¼ oz. In its present state of reduced bulk its weight is 1 lb. 10 ozs. It is not at all likely to supersede box; but it may be fit for coarser work than that for which box is necessary." The principal researches conducted in the laboratory during the past year have been those of Mr. Marshall Ward, on the development of the embryo-sac, published in the *Journal* of the Linnean Society, vol. xvii; pp. 519–546; Prof. Church, continued investigation on albinism in leaves, published in the *Journal* of the Chemical Society, January, 1880. The laboratory has also been employed for the experimental demonstrations given to the *employés* of the Royal Gardens, and for the examination of the University of London for the degree of Doctor of Science in the subject of physiological botany.

UNIVERSITY AND EDUCATIONAL INTELLIGENCE

OXFORD.—The examinations for the degree of Bachelor of Medicine will commence in the medical department of the Museum as follows:—

The First (Scientific) Examination) November 29.

The Second (Final) Examination, December 6.

Candidates for either of these examinations, and candidates for the certificate in Preventive Medicine and Public Health are requested to send in their names on or before November 15 to the Regius Professor of Medicine at the Museum.

The University of Oxford Commissioners have given notice that all new scholarships and exhibitions granted by the Colleges shall be subject to the provisions of any new statutes which may be made by the Commissioners in relation to the length of tenure and emoluments of such scholarships and exhibitions.

The University Commissioners at present sitting have forwarded to the Hebdomadal Council six proposed statutes which they contemplate making, subject to any representation which they may receive from the Council on the appointment and duties of University Professors and Readers. The proposed statutes include certain general regulations applicable to the whole Professoriate. Each Professor must reside six months in each year between October 1 and the ensuing July 1. Each Professor, besides his regular course of lectures, must give one public lecture every year. Each Professor must give private instruction to students in matters relevant to the subject of his lectures, and must examine the students who have attended his lectures at the end of each course.

The following are the particular regulations applicable to the Savilian Professor of Astronomy, the Professor of Experimental Philosophy, the Waynflete Professor of Chemistry, the Linacre Professor of Human and Comparative Anatomy, the Waynflete Professor of Physiology, and the Wykeham Professor of Physics. Section 7 relates to the three proposed new professorships.

(1) The Professor shall deliver one course of fourteen lectures at least in each of two out of the three University terms (Easter and Trinity Terms being counted as one); every course shall extend over seven weeks at least, and not fewer than two lectures shall be delivered in each week.

(2) He shall be ready to give the private instruction required by the General Regulations on two days in each week in which he lectures, and during one hour at least on each of such days.

(3) The laboratory under the charge of each Professor, and, in the case of the Savilian Professor of Astronomy, the University Observatory, shall be open for eight weeks in each term (Easter and Trinity Terms being counted as one), and at such other times, and for such hours, as the University may by statute determine.

Students shall be admitted to the University Observatory and to the laboratory under the charge of each Professor, upon such conditions as the University shall from time to time by statute determine, and upon the terms of paying such fees, not exceeding such amount as may be fixed by any statute of the University in force for the time being, as the Professor may from time to time require.

(4) Except for some grave reason to be approved by the Vice-Chancellor, the Professor shall, for seven weeks in each term (Easter and Trinity Terms being counted as one), and during some part of three days in each week, be ready to give instruction in the subjects of his Chair to such students as shall have been admitted to the laboratory under his charge (or, in the case of the Savilian Professor of Astronomy, to the University Observatory); and such instruction shall be given in the laboratory or observatory (as the case may be) or in some class-room connected therewith.

(5) The Professor shall also, at the close of each term, inform any college which may request him to do so as to the regularity of attendance and the proficiency of the students belonging to such college who have been admitted into the laboratory or observatory under his charge, and shall give like information, if requested, to the delegates of students not attached to any college or hall.

The Particular Regulations next following shall be applic-

able to the several Professors named in them respectively (that is to say):

(1) The Savilian Professor of Astronomy shall have the charge of the University Observatory, and shall undertake the personal and regular supervision of the same, and of the several demonstrators and other assistants employed therein, and shall be responsible for all the work carried on there.

(2) The Professor of Experimental Philosophy shall have the charge of the Clarendon Laboratory, and shall undertake the personal and regular supervision of the same, and of the several demonstrators and other assistants employed therein, and shall be responsible for all the work carried on there.

(3) The Waynflete Professor of Chemistry shall have the charge of the Chemical Laboratories in the University Museum, or such part thereof as the University may by statute assign to him, and shall undertake the personal and regular supervision of the same, and of the several demonstrators and other assistants employed therein, and shall be responsible for all the work carried on there.

(4) The Linacre Professor of Human and Comparative Anatomy shall have the charge of the Anatomical and Ethnological Collections and the Anatomical Laboratories in the University Museum, or such part thereof as the University may by statute assign to him; and shall undertake the personal and regular supervision of the same, and of the several demonstrators and other assistants employed therein, and shall be responsible for all the work carried on there.

(5) The Professor of Botany and Rural Economy shall have the charge and supervision of the Botanical Gardens and Botanical Collections belonging to the University; and it shall be part of his duty to make such Gardens and Collections accessible to, and available for, the instruction of students attending his lectures.

(6) The Professors of Geology and Mineralogy respectively shall have the charge and supervision of the Geological and Palæontological Collections, and of the Mineralogical Collection, belonging to the University; and it shall be part of their duties to make such collections respectively accessible to, and available for the instruction of, students attending their lectures.

(7) { The Professor of Classical Archæology,
The Wykeham Professor of Physics, and
The Waynflete Professor of Physiology,

shall, in like manner, if the University by Statute shall think fit to charge them therewith, undertake the charge of any collections or laboratories connected with the subjects of their respective Chairs, which the University may from time to time assign to them, and shall have similar duties in respect thereof.

(8) The several Professors named in the foregoing particular regulations shall in the performance of the duties committed to them by such regulations be subject to the statutes of the University for the time being in force in that behalf.

This Statute is proposed to be made by the University of Oxford Commissioners under the Universities of Oxford and Cambridge Act, 1877, for the University.

SOCIETIES AND ACADEMIES

PARIS

Academy of Sciences, October 26.—M. Wurtz in the chair.—The following papers were read:—On attenuation of the virus of chicken-cholera, by M. Pasteur. If the most virulent virus (to be got from a fowl which has died of the chronic form of the disease) be taken and successive cultivations made of it in the pure state, in bouillon of fowl's muscles, the interval of time between one sowing and another is found to affect the virulence. With intervals up to one month, six weeks, or two months, no change of virulence is noted, but as the interval is enlarged the virus is found to become weaker. The attenuation does not take place with mathematical regularity. No change can be detected in the microscopic organisms to account for the changes in its power. But M. Pasteur shows by experiments (in which some bouillon, to which a little strong virus had been added, was inclosed and kept some time in sealed tubes) that it is probably the oxygen of the air that attenuates the virulence. May it not then also affect other kinds of virus?—Experimental study of the action of the organism of sheep, more or less refractory to splenic fever, on the infectious agent; what becomes of specific microbia introduced directly into the circulation by large transfusions of anthracoid blood, by M. Chauveau. After such transfusion into animals whose resistance to the disease is considerable and strengthened by preventive inoculation, the bacterian rods soon disappear from the blood (in a few hours one cannot find them). They are not destroyed, however, but are arrested in the capillary system of the lungs and of other parenchymatous organs, where they may be found with retained vitality when the transfusion has been rapidly fatal. When the animal survives more than three days the bacteria disappear from the lung and the spleen (as well as the blood), and health may be regained. One region alone proves favourable to maintenance and development of the bacterian life, viz., the surface of the brain (pia mater), and the development there has quite special characters (elongation and inflexion of the rods and appearance of spores), resembling those which belong to artificial cultivations. The infectious activity of these bacteria of the pia mater is considerable.—On linear differential equations, by M. Appell.—The Secretary announced the opening of a subscription for erection of a monument to the memory of Spallanzani in his native town.—On the class of linear differential equations, with rational coefficients, the solution of which depends on the quadrature of an algebraic product which contains no other irrationality than the square root of an entire and rational polynome, by M. Dillner.—Photography of the nebula of Orion, by Prof. Draper.—Application of selenium to the construction of a photo-electric regulator of heat for the burning in of stained glass windows, by M. Germain. As far as possible from the muffle furnace is placed a dark chamber closed by a parabolic reflector, the focus of which is in the axial line of the telescope commonly used. At this focus is a ball of selenium between two cups of brass, leaving a zone of selenium visible. One cup is connected by German silver wire to a thermo-electric pile (of thirty elements), adapted for strong heat and exposed to that of the muffle, and the pile is connected (by the other poles of its elements) to the side of a stoppered porous vessel filled with water, ensuring a sensibly constant temperature on that side. The thermo-electric current increases with the temperature, and while the part of the muffle covered by the telescope remains dark, the selenium does not effectively alter in resistance, but when a cherry-red tint is reached (indicating time to stop), the resistance of the selenium is reduced about a fourth. The current gains strength and sounds a bell, or affects a system whereby the fuel is diverted. (With the pile is connected a galvanometer, a condenser, and other secondary arrangements.)—On some modifications undergone by glass, by M. Salleron. He calls attention to the corrosion, deformation, and fracture of areometers used in sugar-works which treat molasses by osmose; where the instruments are kept several days in a liquid at 95°, of density, 1014 (2° B), and containing sugar 115 gr., ash 91 gr.; total 206 gr. per litre. The ash consists of chloride of potassium and organic salts of potash. The cracks are all more or less spiral in form.—Influence of light on germination, by M. Panchon. He measured the quantities of oxygen absorbed during germination by identical lots of seeds. Light (he finds) accelerates the absorption in a constant manner; the advantage in favour of light being from a fourth to a third of the quantity absorbed in darkness. The degree of illumination is relative to the quantity absorbed. The respiratory acceleration in seeds illuminated by day persists for several hours in the darkness. The accelerative influence of light is more intense at low temperatures.

CONTENTS

	Page
The First Volume of the Publications of the "Challenger." By Prof. T. H. Huxley, F.R.S.	1
The Lava Fields of North-Western Europe. By Prof. Archibald Geikie, F.R.S.	3
The Atomic Theory	5
New Zealand Molluscs. By Dr. J. Gwyn Jeffreys, F.R.S.	7
Our Book Shelf:— "The Zoological Record for 1878"	8
Letters to the Editor:— The Recent Gas Explosion.—Herbert McLeod, F.R.S.	8
Geological Climates.—Prof. Saml. Haughton, F.R.S.	8
The Yang-tse, the Yellow River, and the Pei-ho.—Dr. A. Woeikof	9
Greek Fret.—Alfred C. Haddon (*With Illustrations*)	9
Temperature of the Breath.—Dr. R. E. Dudgeon	10
Soaring of Birds.—S. E. Peal (*With Diagram*)	10
Regelation.—Rev. George Henslow	11
Johannes Rudolf von Wagner	11
Japan, II. (*With Illustrations*)	12
Bell's Photophone (*With Illustrations*)	15
Notes	19
Our Astronomical Column:— The Comets of 1812 and 1815	21
Ceraski's Circumpolar Variable Star	21
The Longitude of the Cape	21
Geographical Notes	21
Kew Gardens Report	22
University and Educational Intelligence	23
Societies and Academies	24

TO NATURE
. . 28s.
. . 14s. 6d.
. . 7s. 6d.
s, the Continent, and
:—
. . 30s. 6d.
. . 15s. 6d.
. . 8s.
reet, Strand.

SIETIES.

EMBER 4.
ds of Vanadium and Sulphur: ric Oxidation of Phosphorus Peroxide of Hydrogen: C. T. Vapours of Benzene, Toluene, Bismuth Compounds. Part I. Compounds: M. M. Pattison —On the Colour Properties , Cobalt, Iron, Manganese, and naphthalin upon Salicylic Acid: Zinc Compounds upon the Frankland, F.R.S., and C. G. lic Cyanide: Dr. E. Frankland ates of Iron: Spencer Pickering. Sec. I.: Dr. C. ical Dynamics. R. A. Wright and A. E. Menke. r. Armstrong and N. E. Graham. knowledge of the Flora of North- alkaloids of South Australia: J. G. om Madagascar: J. G. Baker.

EMBER 5.
Geologists' Association: its Origin

EMBER 8.
rney in East and Central Africa;

A. Cascu.

EMBER 9.
, at 8.

n Anthropological Colour-Phenomena, F.R.S.—On Different Stages ge in Prehistoric Times: J. F. in Russia: Prince Paul Poutiatin.

OVEMBER 10.
I.
-Notes on some Acanthometidæ: scope: Dr. Carpenter, C.B. Forest Animals: J. E. , at 8.—Forest Animals: J. E.

EMBER 11.
ations respecting the Translation ons Formulæ: The President— Double Focus and Three Single ferry, F.R.S.—Further Remarks : Rev. C. Taylor.

BER 12.

EMBER 13.
f Mistuned Consonances of the ote on Prof. Exner's Paper on and Perry.—On Action at a

(DICHROIC).
ACK INK
ELSE EVER PRODUCED.
k is used. It has been adopted d Railway Companies throughout

ws easily from the Pen. tting-paper may be applied at the s incol of writing.
ssrs. BARCLAY & SONS, Farringdon Newgate F. NEWBERY & SONS. Newgate & Co., Duke chester; J. AUSTIN & Co., Duke ietornoster Row: and to be had of

Limited), Dublin.

f the SKULL. By
ian Professor, Royal College of Sc., Lecturer on Botany in Guy's Crown 8vo. 10s. 6d.
CO., London.

SWIFT & SON,
OPTICIANS.

MESSRS. SWIFT'S CHALLENGE BINOCULAR & MONOCULAR MICROSCOPE in Cabinet, from £14 to £18 12s.

Just published, a Pamphlet to the Uninitiated, with Instructions how to select a Microscope and test its Optical and Mechanical Qualities, for 7 Stamps. Catalogue fully Illustrated for 3 Stamps.

UNIVERSITY OPTICAL WORKS,
UNIVERSITY STREET,
LONDON, W.C.

NOTICE OF REMOVAL.
JAMES HOW & CO.,
SCIENTIFIC INSTRUMENT MAKERS,
73, FARRINGDON ST., LONDON
(LATE OF 5, ST. BRIDE ST., AND 2, FOSTER LANE).
HOW'S STUDENT'S MICROSCOPE. HOW'S MICROSCOPE LAMP.
Rock Sections and other Objects for the Microscope.

R. W. NEEVES,
PHILOSOPHICAL INSTRUMENT
AND
INTENSITY COIL MAKER.
PRICE LIST, FOUR STAMPS.
55, SIDMOUTH STREET, LONDON, W.C.

J. ORME & CO.,
(Late M. JACKSON & CO.)
MANUFACTURERS AND IMPORTERS OF
SCIENTIFIC APPARATUS
AND
CHEMICALS.
SOLE AGENTS FOR HICKLEY'S PATENT TELEPHONES,
Price 50s. per Pair, Cash with Order.
Price Lists sent on receipt of Three Stamps for Postage.
For Trade Terms inclose Business Card.
65, BARBICAN, LONDON, E.C.

S. C. TISLEY & Co.,
OPTICIANS,
172, BROMPTON ROAD, S.W.
(Close to South Kensington Museum).
THE PHONEIDOSCOPE
An Instrument for Observing the Colour-Figures of Liquid Films under the action of Sonorous Vibrations.
Being a visible demonstration of the Vibratory and Molecular Motion of a Telephone Plate.
The PHONEIDOSCOPE, with 3 Discs, Bottle of Solution, Descriptive Pamphlet, &c., in Cardboard Box, 10s. 6d.
MANUFACTURED AND SOLD WHOLESALE AND RETAIL BY
S. C. TISLEY & Co., 172, BROMPTON ROAD, LONDON, S.W.
TELEPHONIC ELECTRICITY. All Materials supplied for experimental purposes.
Price Lists of Electrical and Acoustic Apparatus, with Drawings and Description of the Harmonicograph, Post Free, 1d.

MESSRS. MACMILLAN & CO.'S PUBLICATIONS.

Complete in Five Vols., price £6.

A SYSTEM OF MEDICINE.

Edited by J. RUSSELL REYNOLDS, M.D., F.R.S., &c.

Vol. I.—GENERAL DISEASES; or, AFFECTIONS of the WHOLE SYSTEM. 8vo. 25*s.*

Vol. II.—LOCAL DISEASES.—The NERVOUS SYSTEM.—The DIGESTIVE SYSTEM. 25*s.*

Vol. III.—LOCAL DISEASES.—The DIGESTIVE SYSTEM (continued)—The RESPIRATORY SYSTEM. 8vo. 25*s.*

Vol. IV.—LOCAL DISEASES.—DISEASES of the ORGANS of CIRCULATION.—The HEART. 21*s.*

Vol. V.—DISEASES of the ORGANS of CIRCULATION (continued).—The BLOOD-GLANDULAR SYSTEM.—URINARY ORGANS.—FEMALE REPRODUCTIVE ORGANS.—CUTANEOUS SYSTEM.—GENERAL INDEX, &c. 25*s.*

Also now publishing in Twenty-four Monthly Parts, price 5*s.* each. Parts 1 to 18 now ready.

Just published, in 8vo, price 18*s.* Vol. I.

COMPARATIVE EMBRYOLOGY: A TREATISE ON. By F. M. BALFOUR, M.A., F.R.S. With Illustrations. In 2 Vols.

Now ready, in 8vo, with Illustrations, price 18*s.*, Vol. I.

A TEXT-BOOK OF THE PHYSIOLOGICAL CHEMISTRY OF THE ANIMAL BODY, INCLUDING AN ACCOUNT OF THE CHEMICAL CHANGES OCCURRING IN DISEASE. By ARTHUR GAMGEE, M.D., F.R.S., Professor in the Victoria University, Manchester, Brackenbury Professor of Physiology in the Owens College. In 2 Vols.

"The arrangement and plan of the whole work are excellent, and the student has here for the first time a book in the English language which is available for the study as well as the laboratory."—*The Lancet.*

A TREATISE ON CHEMISTRY. Vols. I. and II.—INORGANIC CHEMISTRY. By Professors ROSCOE and SCHORLEMMER, of the Owens College, Manchester. With numerous Illustrations.

Vol. I.—THE NON-METALLIC ELEMENTS. 8vo. 21*s.* Vol. II.—METALS. Two Parts, 18*s.* each. [Vol. III.—ORGANIC CHEMISTRY *in the Press.*

"It would be difficult to praise it too highly.....The arrangement is clear and scientific, and the facts gained by modern research are fairly represented and judiciously selected, and the style throughout is singularly lucid."—*The Lancet.*

COMPARATIVE ANATOMY: ELEMENTS OF. By Prof GEGENBAUR. A Translation by F. J. BELL, B.A., revised with Preface by Prof. E. RAY LANKESTER, F.R.S. With numerous Illustrations. 8vo. 21*s.*

"We do not hesitate to say that this is the best and most complete work on comparative anatomy in the language. . . . Any student who has made himself familiar with this work may consider that he possesses a sound elementary knowledge of animal morphology."—*The Lancet.*

THE PRACTITIONER'S HANDBOOK OF TREATMENT; OR, THE PRINCIPLES OF THERAPEUTICS. By J. MILNER FOTHERGILL, M.D., Assistant-Physician to the Victoria Park Hospital. 8vo. 16*s.*

"A practical and suggestive work."—*The Lancet.* [*Second Edition, Revised and Enlarged, now ready.*

The ANTAGONISM of THERAPEUTIC AGENTS, AND WHAT THEY TEACH US. By J. M. FOTHERGILL, M.D. Crown 8vo. 6*s.*

DISEASES OF THE SKIN: The Treatment of. By Dr. M'CALL ANDERSON. Crown 8vo. 5*s.*

LECTURES ON CLINICAL MEDICINE. By Dr. M'CALL ANDERSON. Illustrated. 8vo. 10*s.* 6*d.*

ON ANEURISM, ESPECIALLY of the THORAX AND THE ROOT OF THE NECK. By R. BARWELL, F.R.C.S. Crown 8vo. 3*s.* 6*d.*

ON PARALYSIS FROM BRAIN DISEASE IN ITS COMMON FORMS. By H. CHARLTON BASTIAN, M.D., F.R.S. Illustrated. Crown 8vo. 10*s.* 6*d.*

DISEASES OF THE EYE. By R. BRUDENELL CARTER, F.R.C.S. With Illustrations. 8vo. 16*s.*

DEFECTS OF VISION WHICH ARE REMEDIABLE BY OPTIC APPLIANCES. By R. B. CARTER, F.R.C.S. Illustrated. 8vo. 6*s.*

EYESIGHT, GOOD AND BAD. By R. B. CARTER, F.R.C.S. Second Edition. Crown 8vo. 6*s.*

PHYSIOLOGY AND PATHOLOGY OF THE BREAST and its LYMPHATIC GLANDS. By C. CREIGHTON, M.D. With Illustrations. 8vo. 9*s.*

THE GERM THEORY APPLIED TO THE EXPLANATION OF THE PHENOMENA OF DISEASE. By T. MACLAGAN, M.D. 8vo. 10*s.* 6*d.*

THE PATHOLOGY OF MIND. By H. MAUDSLEY, M.D. New Edition, Revised and Enlarged. 8vo. 18*s.*

THE PHYSIOLOGY OF MIND. By H. MAUDSLEY, M.D. New Edition, Revised and Enlarged. Crown 8vo. 10*s.* 6*d.*

BODY AND MIND. By H. MAUDSLEY, M.D. New Edition, Enlarged. Crown 8vo. 6*s.* 6*d.*

THE PRACTITIONER: A JOURNAL OF THERAPEUTICS AND PUBLIC HEALTH. Edited by T. L. BRUNTON, M.D., F.R.S. Price 1*s.* 6*d.* monthly.

CONTENTS.—Original Communications, Reviews, Clinic of the Month, Extracts from the British and Foreign Journals, Notes and Queries, and Department of Public Health.

PHARMACOLOGY AND THERAPEUTICS; or, Medicine Past and Present. By T. LAUDER BRUNTON, M.D., F.R.S. Crown 8vo. 6*s.*

PHARMACOGRAPHIA: a History of the Principal Drugs of Vegetable Origin met with in Great Britain and India. By F. A. FLUCKIGER, M.D., and D. HANBURY, F.R.S. Second Edition, revised. 8vo. 21*s.*

TEXT-BOOK OF PHYSIOLOGY. By MICHAEL FOSTER, M.D., F.R.S. With Illustrations. New Edition. 8vo. 21*s.*

THE CARE OF THE INSANE, AND THEIR LEGAL CONTROL. By J. C. BUCKNILL, M.D., F.R.S. Crown 8vo. 3*s.* 6*d.*

WATER SUPPLY. By J. H. BALFOUR BROWNE. Crown 8vo. 2*s.* 6*d.*

ELEMENTARY BIOLOGY. By Prof. HUXLEY and H. N. MARTIN. Crown 8vo. 6*s.*

PHYSIOGRAPHY: an Introduction to the Study of NATURE. By Prof. HUXLEY, F.R.S. With Coloured Plates and Woodcuts. New and Cheaper Edition. Crown 8vo. 6*s.*

THE MORPHOLOGY OF THE SKULL. By Prof. PARKER, F.R.S., and G. T. BETTANY, B.Sc. Illustrated. Crown 8vo. 10*s.* 6*d.*

THE OSTEOLOGY OF THE MAMMALIA. A Series of Lectures by Prof. W. H. FLOWER, F.R.S., F.R.C.S. Illustrations. Crown 8vo. 10*s.* 6*d.*

PRACTICAL CHEMISTRY FOR MEDICAL STUDENTS, specially arranged for the First M.B. Course. By M. M. PATTISON MUIR, F.R.S.E. 18mo. 1*s.* 6*d.*

ELEMENTARY LESSONS IN ANATOMY. By ST. GEORGE MIVART, F.R.S. With 400 Illustrations. 18mo. 6*s.* 6*d.*

LESSONS IN ELEMENTARY PHYSIOLOGY. By Prof. HUXLEY. Illustrated. New Edition. 18mo. 4*s.* 6*d.*

LESSONS ON PRESCRIPTIONS AND THE ART OF PRESCRIBING. By W. H. GRIFFITHS, Ph.D., L.R.C.P.E. New Edition. 18mo. 3*s.* 6*d.*

MACMILLAN AND CO., Bedford Street, Strand, W.C.

Messrs. MACMILLAN & CO.'S PUBLICATIONS.

ETCHING AND ETCHERS. By P. G. HAMERTON. New Edition, Revised, with 48 New Plates. Columbier 8vo. £5 5s.

The text of the new Edition has been thoroughly revised, and increased by one-fifth. Several new Chapters and a new Preface have been added, whilst matter which had become unnecessary or disproportionate has been removed, to make room for studies of more importance. [*Immediately.*

LIFE OF WILLIAM BLAKE. With Selections from his Poems and other Writings. By ALEXANDER GILCHRIST. A New and Enlarged Edition, Illustrated from BLAKE'S own Works, with Additional Letters and a Memoir of the Author. 2 vols. Medium 8vo. [*Immediately.*

ISLAND LIFE; or, the Phenomena of Insular Faunas and Floras, with their Cause, including an entire revision of the Problem of Geological Climates. By ALFRED RUSSEL WALLACE, Author of "The Malay Archipelago," "The Geographical Distribution of Animals," &c. Medium 8vo, with Illustrations and Maps. 18s.

A VISIT TO WAZAN, THE SACRED CITY of MOROCCO. By ROBERT SPENCE WATSON. 8vo, with Map and Illustrations. 10s. 6d.

"Mr. Watson's account of his experiences in Morocco is much more pleasant than that of any other traveller's we know of . . . . and as a record of an independent and unprejudiced observer his little book, slight as it is, is of value."—*Times.*

IDEAL CHEMISTRY. By Sir BENJAMIN BRODIE, Bart., F.R.S. Crown 8vo. 2s.

GOETHE'S FAUST. Translated into English Verse, with Notes and Preliminary Remarks, by JOHN STUART BLACKIE, F.R.S.E., Professor of Greek in the University of Edinburgh. Second Edition, carefully revised and largely rewritten. Crown 8vo. 9s.

ETIENNE DOLET: the Martyr of the Renaissance. A Biography, with a Bibliographical Appendix, containing a descriptive catalogue of the books written, edited, or printed by Dolet. By R. C. CHRISTIE, M.A., Lincoln College, Oxford, Chancellor of the Diocese of Manchester. With Illustrations. 8vo. 18s.

"Mr. Christie's book may be cited as, in many respects, a model biography."—*Athenæum.*

"He draws portraits of persecutors from the life, worthy of the art of Rabelais and Bunyan."—*St. James's Gazette.*

STUDIES IN DEDUCTIVE LOGIC. By W. STANLEY JEVONS, LL.D., F.R.S., Professor of Political Economy in University College, London. Crown 8vo. 6s. . . .

GUIDE TO THE STUDY OF POLITICAL ECONOMY. By Dr. LUIGI COSSA. Professor of Political Economy in the University of Pavia. Translated from the Second Italian Edition. With a Preface by W. STANLEY JEVONS, F.R.S. Crown 8vo. 4s. 6d.

THE IRISH LAND LAW. By ALEXANDER G. RICHEY, Q.C., LL.D., Deputy Regius Professor of Feudal and English Law in the University of Dublin. Crown 8vo. [*Immediately.*

With Twenty-five Illustrations by WALTER CRANE.

THE NECKLACE OF PRINCESS FIORIMONDE: and other Stories. By MARY DE MORGAN. Extra fcap. 8vo. 6s.

ALSO AN EDITION, Printed by Messrs. R. and R. Clark, on hand-made paper. The Plates, initial letters, head and tail pieces being printed on India paper and mounted in the text.

The Edition is limited to ONE HUNDRED COPIES. Fcap. 4to.

ENGLISH MEN OF LETTERS. Edited by JOHN MORLEY. Crown 8vo. 2s. 6d.

LOCKE. By Professor FOWLER. New Volume.

New Book by the Author of "The Tapestry Room," &c.

A CHRISTMAS CHILD: a Sketch of a Boy-life. By MRS. MOLESWORTH, Author of "Carrots," "The Cuckoo Clock," &c. Illustrated by WALTER CRANE. Globe 8vo.

New Book by the Author of "When I was a Little Girl," &c.

PANSIE'S FLOUR BIN. By the Author of "St. Olave's," &c. Illustrated by ADRIAN STOKES. Globe 8vo. 4s. 6d.

ESSAYS ON ART AND ARCHÆOLOGY. By C. T. NEWTON, C.B., LL.D., Keeper of Greek and Roman Antiquities at the British Museum. 8vo. 12s. 6d.

"Mr. Newton deserves the gratitude of all Students of Archæology, for these masterly Essays. . . . . are the fruit of a lifetime of exhaustive scholarship, and of such individual research as it seldom falls to the lot of any archæologist to accomplish."—*Westminster Review.*

MODERN GREECE: Two Lectures delivered before the Philosophical Institution of Edinburgh, with Papers on "The Progress of Greece," and "Byron in Greece." By R. C. JEBB, M.A., LL.D., Professor of Greek in the University of Glasgow. Crown 8vo. 5s.

"Modern Greece needs but few words of recommendation to those interested in one of the most urgent and important questions of the day . . . . . We have to add an expression of our hope that the book, which is both scholarly and popular, will obtain all the success which it certainly deserves."—*Westminster Review.*

CICERO'S LIFE AND LETTERS. Being a Translation of the Letters in Mr. WATSON'S Selection, with Historical and Critical Notes, by the Rev. G. E. JEANS, M.A. 8vo. 10s. 6d.

"The style . . . . is life-like, and shows literary power, nor is it superfluous to add that it is for the most part really English and idiomatic."—*Academy.*

"Mr. Jeans' translation deserves to take its place side by side with Davies and Vaughan's 'Republic,' and Church and Brodribb's 'Tacitus.'"—*St. James's Gazette.*

HISTORY OF THE ENGLISH PEOPLE. By JOHN RICHARD GREEN. Vol. IV. THE REVOLUTION, 1683—1760. MODERN ENGLAND, 1760—1815. 8vo, with 3 Maps and Index, 16s. (Vols. I. to III. 16s. each.) [*Concluding Volume.*

"A work that most students of history may turn to with advantage, and that will be almost sure to take rank among the great classics of our literature."—*Globe.*

READINGS FROM ENGLISH HISTORY. Selected and Edited by JOHN RICHARD GREEN. In Three Parts, each 1s. 6d.

"We cannot imagine a better reading-book for the highest standard of our elementary schools, but it is a book which will have great charms also for the most cultivated readers."—*Guardian.*

PLINY'S LETTERS. Book III. Edited by Professor JOHN E. B. MAYOR, M.A. With Life of Pliny by G. H. RENDALL, M.A. Fcap. 8vo. 5s. [Macmillan's Classical Series.

XENOPHON'S ANABASIS. Books I.—IV. Edited by Professors W. W. GOODWIN and J. W. WHITE, of Harvard University. Fcap 8vo. 5s. [Macmillan's Classical Series.

LIVY.—SCENES FROM THE HANNIBALIAN WAR. Adapted for the use of Beginners by G. C. MACAULAY, M.A., Assistant-Master at Rugby. Post 8vo. 1s. 6d. [Macmillan's Elementary Classics.

MACMILLAN AND CO., LONDON.

STANDARD AND OBSERVATORY TIMEKEEPERS.

TRADE DENT MARK MANUFACTURED BY E. DENT & CO. TRADE DENT MARK

	Guineas.
Standard Clock, suitable for Private Residences in Town or Country, or Public Institutions, beating seconds and going eight days with once winding; in carved and decorated oak or mahogany case ... ... from	35
(*a*) The same, but going one month with once winding ... ... from	40
Standard Observatory Mean-time Clock	80
(*a*) The same, but furnished with electrical contact apparatus with eccentric screw adjustments for dropping a time ball, or transmitting hourly signals	92
Standard Observatory Sidereal Clock	80
(*a*) The same, but furnished with electrical contact apparatus with fine vertical and horizontal screw adjustments for transmitting seconds, currents for controlling other clocks, &c.	95
(*b*) The same, but arranged to omit the current at every 60th second, for pricking on chronograph barrel, &c.	97

	Guineas.
Standard Observatory Clock, of the most refined construction, with barometric compensation, &c. ...	160
(*a*) The same, with Sir Geo. Airy's escapement ...	170
(*b*) The same, with M. Leverrier's electrical contact system	200

The New Standard Clock (the primary standard timekeeper of the United Kingdom) of the Royal Observatory, Greenwich, was constructed by E. Dent & Co., and precisely similar instruments are now being made for the Royal Observatories of Spain and Belgium. Standard Clocks of less refined construction for the Observatories of Edinburgh (Royal), Dunsink (Royal Irish), Oxford (University), Pulkowa (Russian Imperial), Geneva (National Swiss); and many others, Foreign and Colonial, have been manufactured.

Galvanic Chronographic Apparatus, for registering the time of occurrence of transits and other astronomical phenomena ... ... from 120

The Great Galvanic Chronograph of the Royal Observatory, Greenwich, and the still more powerful Apparatus for the Royal Observatory, Brussels, and other smaller ones for other Observatories were constructed by E. Dent & Co.

E. DENT & CO.,

WATCH, CLOCK, AND CHRONOMETER MAKERS,

61, STRAND, & 34, ROYAL EXCHANGE. FACTORY, GERARD STREET, LONDON.

MICROSCOPIC SPECIALITIES.

		£	s.	d.
Series	I.—24 Medical Pathological Preparations, in Case	2	2	0
,,	II.—24 Physiological Preparations, in Case	2	2	0
,,	III.—24 Educational ,, ,,	2	2	0
,,	IV.—48 Physiological ,, ,,	4	4	0
Series	V.—24 Preparations from the Frog, in Case	2	2	0
,,	VI.—24 Surgical Pathological Preparations	2	2	0
,,	A.—48 Diatomaceæ (selected)	2	10	0
,,	B.—24 ,, (very rare)	1	11	6

Pathological and Physiological Preparations in great and constantly increasing variety, and of most valuable descriptions. 15*s.* to 30*s.* per doz.

Descriptive Lists and full particulars on application to

ARTHUR C. COLE & SON,

ST. DOMINGO HOUSE, OXFORD GARDENS, NOTTING HILL, LONDON, W.

LATE OF 62, ST. DOMINGO VALE, EVERTON, LIVERPOOL.

W. LADD & CO.,

SCIENTIFIC INSTRUMENT MANUFACTURERS,

(*By Appointment to the Royal Institution of Great Britain*),

11 AND 12, BEAK STREET, REGENT STREET, W.

IMPROVED HOLTZ ELECTRICAL MACHINES. GRAMME'S MAGNETO-ELECTRIC MACHINE for Laboratory use.

PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3*s.* per oz.

Physical Apparatus of every Description.

ILLUSTRATED CATALOGUE, SIXPENCE.

PATERSON'S NEW CATALOGUE OF PHYSICAL APPARATUS.

LANTERN SLIDES for SCIENTIFIC LECTURES. Season 1880-1. Post free 6 Stamps.
Complete Sets of Physical Apparatus for Science Primers and all the Physical Text-books in use in Schools and Colleges.
Siemens and Gramme Dynamo Machines and Lamps for hire.
Schools supplied with Apparatus as per Science and Art Departments' Requirements in the Sections of Light, Heat, Sound, and Electricity.
Electric Signals for Houses, Hotels, &c., Colliery Signals, Lightning Conductors. The Gower-Bell Loud-speaking Telephone.

EDWARD PATERSON, Electrical Engineer.

SHOW ROOMS AND STEAM WORKS:—76, LITTLE BRITAIN, E.C. (late 3, Bedford Court, W.C.).

MOLISON'S HARMONOGRAPH; executes the Harmonic Curves in the most perfect manner. 15*s.* and 20*s.*

Illustrated Catalogue of Electrical Apparatus, Part 1, *post free*, 6 *Stamps. Ditto, Electric Signals, Part* 2, 6 *Stamps.*

Printed by R. CLAY, SONS, AND TAYLOR, at 7 and 8, Bread Street Hill, Queen Victoria Street, in the City of London, and published by MACMILLAN AND CO., at the Office, 23 and 30, Bedford Street, Covent Garden.—THURSDAY, November 4, 1880.

ATURE

ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
ere trusts the mind which builds for aye."—WORDSWORTH

THURSDAY, NOVEMBER 11, 1880 [PRICE SIXPENCE

[All Rights are Reserved.

al Post Office.]

OF LONDON.

f this Society for the Session November, at half-past Eight iare, W.

ATER, F.R.S., Secretary.

TY of LONDON.

TES for SALE.—Apply to y's Gardens, Regent's Park,

Y EXAMINA-

or Matriculation, B.Sc., Civil H. PAUL, B.Sc. (Lond.), is in Chemistry at the Labora- in connexion with W., where he works in con- igh Course of Practical and

TORIAL TELE-

ray, of best quality, massive by Cooke, &c. Price £250. ddress J. WATSON, Vane

.—CLASSES for

sity Examinations, under the D.Sc., F.L.S., London Uni- Preliminary Scientific M.B., work practical.

Y.

S AND STUDENTS.

of these Collections.

s, Apparatus, Rock Sections, of

GORY,

TZROY SQUARE.

onstantly arriving.

NERALOGY.

prices, Educational Collections rranged to illustrate the text- avies, Skertchley, Dana, Page, and College Museums are also ies post free.

vid SHEFFIELD.

E COMPANY,

.L.

BLISHED 1807.

— — — — £3,043,548

— — — — £1,500,000

had at the Office, or from any

TYS, Actuary and Secretary.

BROWNING'S LANTERNS.

THE NEW

THREE-WICK LANTERN.

PRICE

£4 7s. 6d.

New Illustrated Catalogue of Electric Lanterns, Magic Lanterns, Slides, and Diagrams, Stereos.

Illustrated List of Instruments, for Presents or School Prizes, at Prices from 5s. to £10, sent free.

JOHN BROWNING,

63, STRAND, LONDON, W.C.

GEOLOGY.—In the Preface to the STUDENT'S ELEMENTS of GEOLOGY, by Lyell, 1874, he says: "As it is impossible to enable the reader to recognise rocks and minerals at sight by aid of verbal descriptions or figures, he will do well to obtain a well-arranged collection of specimens, such as may be procured from Mr. TENNANT (149 Strand), Teacher of Mineralogy at King's College, London." These Collections are supplied on the following terms, in Mahogany Cabinets:—

100 Specimens, in Cabinet, with 3 Trays	... ...	£1	1 0
200 Specimens, in Cabinet, with 5 Trays	... ...	3	3 0
300 Specimens, in Cabinet, with 9 Drawers	... ...	10	10 0
400 Specimens, in Cabinet, with 13 Drawers	... ...	21	0 0

More extensive Collections at 50 to 1,000 Guineas each.

TO MICROSCOPISTS.

LIVING DIATOMS.

Bacillaria paradoxa, Pleurosigma, and other Marine Diatoms. Tubes 9*d*. each. Three different for 2*s*. post free.

W. SHRUBSOLE, Jpr., Sheerness-on-Sea.

PARCELS of CHEAP FINE-ART PHOTOGRAPHS for Albums, Scrap-books, Framing, &c., sent by post for approval and selection. No obligation to purchase any, and no expense incurred beyond the postage. Copies of celebrated Pictures, English and Foreign, Statuary, Views, Portraits of Fair Celebrities, Political, Literary, Poets, Musical Composers, &c. 6000 different Subjects. Carte, Cabinet, and larger sizes from 1*d*. each. Catalogue post free. Specimen Photograph, 3 Stamps.—Address F. SHEARER, Photographic Publisher, Wandsworth, London.

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 48N, Tollington Road, Holloway, London, N.

MINERALOGY AND GEOLOGY.

FINE SPECIMENS of ORANGITE, ENSTATITE, BREVICITE, EUXENITE, AUGITE, PYROSMALITE.

UNIQUE SPECIMENS of ADULARIASPHENE and SMOKY QUARTZ.

FINE CRYSTALLISED CROMFORDITES and MATLOCKITE, Derbyshire.

XENOTINE CRYSTALLISED, Valais; WOLLASTONITE CRYSTALLISED.

COLLECTIONS FOR STUDENTS, from £2 2s. COLLECTIONS FOR BEGINNERS, from 4s. BLOWPIPE CASES AND APPARATUS.

PRIVATE LESSONS AND EVENING CLASSES.

Catalogues free.

SAMUEL HENSON,
277 (*Late* 113*a*), STRAND, LONDON, W.C.

50 ROCKS, 50 FOSSILS, 50 MINERALS,

NEATLY ARRANGED IN A
DEAL CABINET, STAINED AND POLISHED, LOCK AND KEY.
EACH SPECIMEN LABELLED AND CATALOGUED.

Price complete, £1 10s.

THE ROCKS illustrate the Order and Range of Deposition, &c.

THE FOSSILS are representative of the Genera found in the most important Deposits.

THE MINERALS are selected for their known uses in the Arts and Manufactures, and are extremely characteristic.

Names and Localities guaranteed.

THOMAS J. DOWNING, Geologist, &c.,
38, WHISKIN STREET, LONDON, E.C.
Catalogues Free.

"The leading Farmers' paper."—CLARE SEWELL READ, ESQ., M.P.

THE CHAMBER OF AGRICULTURE JOURNAL

AND FARMERS' CHRONICLE
(PRICE 3*d.* WEEKLY).

The representative organ of the Central and Provincial Chambers of Agriculture; *gives fuller reports of the discussions and proceedings* of this extensive organisation than any other agricultural paper. It devotes *special attention to the treatment of Agricultural Questions by Parliament*, besides containing ample Reports of the LATEST LONDON and COUNTRY CORN, CATTLE, HOP, PROVISION, and other Markets, with Original Articles on Practical Farming, the Dairy, Herd and Flock News, Horticulture, &c., &c. It is despatched every Monday evening in time for the country post.

Terms of Subscription, payable in advance, post free:—3 months, 3*s.* 9½*d.*; 6 months, 7*s.* 7*d.*; 12 months, 15*s.* 2*d.*

Published by W. PICKERING, 21, Arundel Street, Strand, London, W.C.

THE "HANSA"

Published since 1864 in Hamburg, is the only independent professional paper in Germany, dedicated exclusively to Maritime Objects. Essays, Critiques, Reviews, Reports, Advertisements. Strict eye kept upon the development of Maritime Affairs in every respect. Every second Sunday one Number in 4to at least; frequent supplements and drawings. Subscription at any time; preceding numbers of the year furnished subsequently. Price 12*s.* for twelve months. Advertisements 4*d.* a line, widely spread by this paper; considerable abatement for 3, 6, 12 months' insertion. Business Office: Aug. Meyer and Dieckmann, Hamburg, Alterwall, 28. Edited by W. V. FREEDEN, M.R., Hamburg, Alexander Street, 8.

R. W. NEEVES,
PHILOSOPHICAL INSTRUMENT
AND
INTENSITY COIL MAKER.

PRICE LIST, FOUR STAMPS.

55, SIDMOUTH STREET, LONDON, W.C.

THOMAS D. RUSSELL'S
NATURAL HISTORY STORES,

48, ESSEX STREET, STRAND, W.C.

Students and others are invited to inspect the Collections of British and Foreign Shells, Corals, Zoophytes, Annelids, Crustacea, Echinoderms, Minerals, Fossils, Rock Specimens, Microscopic Objects, &c.

Cabinets, Geologist's Hammers, Glass Capped Boxes, Card Trays, Tablets, Glass Slips, Micro-Thin Glass, Canada Balsam, Marine Glue, and other requisites for the Geologist and Microscopist.

Catalogues Post Free.

LIVING SPECIMENS FOR THE MICROSCOPE.

THOMAS BOLTON, NATURALISTS' and MICROSCOPISTS'
STUDIO, 17, ANN STREET, BIRMINGHAM.

T. B. has last week sent to his subscribers specimens of some of the Choano-flagellata, figured in the first part of W. Saville Kent's "Manual of the Infusoria," just published; together with a drawing of six different species, all sketched by Mr. Kent from specimens attached to a bit of weed sent him by Mr. Bolton. He has also sent out *Amœba princeps*, Actinosphærium, Acdulta, Stephanoceros, &c.

Weekly announcements will be made in this place of organisms T. B. is supplying.

Specimen Tube, One Shilling, post-free.

Twenty-six Tubes in course of Six Months for Subscription of £1 1s.

Price List of Specimens on application, with stamped addressed envelope.

Portfolio of Drawings, No. 3, One Shilling.

LA SEMAINE FRANÇAISE: a Weekly

Newspaper and Review in the French Language. Politics, Literature, Science, Art, Varieties, Notes. Price 3*d.*, through booksellers, and at the railway bookstalls. Office, 37, Southampton Street Strand, W.C.

LA SEMAINE FRANÇAISE: Journal Française pour l'Angleterre: Politique, Littérature, Sciences, Arts, Variétés, Nouvelles, et Notes. Un exemplaire par la poste, 3½*d.*, en timbres poste. Abonnement franco par la poste—un an, 15*s.* 2*d.*; six mois, 7*s.* 7*d.* Prix 3*d.*, chez tous les libraires et aux gares des chemins de fer. On s'abonne aux bureaux, 37, Southampton Street, Strand, Londres, W.C.

LA SEMAINE FRANÇAISE:—"'La Semaine Française' has been brought out in London for the benefit of those English readers who may wish to study contemporary French from all points of view, instead of confining their reading to one particular Gallic print. It certainly merits success."—*Graphic.*

LA SEMAINE FRANÇAISE.—"The numbers before us are full of good things. . . . It will be far better for most than any one of the best papers published in Paris itself. We are much pleased with the character of it, and believe it will be highly valued in all those many households where French is cultivated. The printing is very well done."—*Queen.*

TERMS OF SUBSCRIPTION:—							*s.*	*d.*
Three months	...	...	...	...	...	...	3	10
Six ,,	...	...	...	...	...	...	7	7
Twelve ,,	...	...	...	...	...	...	15	2

P.O.O. payable to T. SPANSWICK, at King Street, Covent Garden, W.C.

Publishing Office, 37, Southampton Street, Strand, W.C.

THE ENTOMOLOGIST'S MONTHLY MAGAZINE.

Price Sixpence, Monthly, 24 pages 8vo, with occasional Illustrations.

Conducted by J. W. DOUGLAS, R. MCLACHLAN, F.R.S., E. C. RYE, F.Z.S. and H. T. STAINTON, F.R.S.

This Magazine, commenced in 1864, contains standard articles and notes on all subjects connected with Entomology, and especially on the Insects of the British Isles.

Subscription—Six Shillings per Volume, post free. The volumes commence with the June number in each year.

Vols. I. to V. (strongly bound in cloth) may be obtained by purchasers of the entire set to date, at the increased price of 10*s.* each; the succeeding vols. may be had separately or together, at 7*s.* each.

London: JOHN VAN VOORST, 1, Paternoster Row.

N.B.—Communications, &c., should be sent to the Editors at the above address.

NORTH BRITISH AGRICULTURIST

is the only Agricultural Journal in Scotland, and circulates extensively amongst Landed Proprietors, Factors, Farmers, Farm-bailiffs, and others interested in the management of landed property throughout Scotland and the Northern Counties of England.

The AGRICULTURIST has also a very considerable circulation on the Continent of Europe, America, Australia, and the Colonies.

The AGRICULTURIST is published every Wednesday afternoon in time for the evening mails, and contains Reports of all the principal British and Irish Markets of the week, besides Telegraphic Reports of those held on the day of publication.

The Veterinary Department is edited by one of the leading Veterinarians in the country, and is invaluable to the breeder and feeder as a guide to the rearing of animals, and their treatment when labouring under disease.

Full Reports are given of the Meetings of the Royal Agricultural Society of England, the Royal Agricultural Society of Ireland, the Highland and Agricultural Society of Scotland, the Scottish Chamber of Agriculture, and all the principal Agricultural Associations throughout Great Britain and Ireland.

For Advertisers addressing themselves to Farmers a better medium does not exist.

Price 3*d.* By post 3½*d.* Annual Subscription, payable in advance, 14*s.*

Office—377, High Street, Edinburgh.

Post-Office Orders payable to Charles Anderson, Jun., Edinburgh.

ESTABLISHED 1843.

Lately published.

EARLY MAN in BRITAIN, and his

PLACE in the TERTIARY PERIOD. By W. BOYD DAWKINS, F.R.S., Professor of Geology in Owens College, Manchester. Medium 8vo, with numerous Illustrations. 25*s.*

MACMILLAN & CO., London.

With Illustrations and Maps, medium 8vo, 18*s*.

ISLAND LIFE:

OR, THE PHENOMENA OF INSULAR FAUNAS AND FLORAS, WITH THEIR CAUSES, INCLUDING AN ENTIRE REVISION OF THE PROBLEM OF GEOLOGICAL CLIMATES. By ALFRED RUSSEL WALLACE, Author of "The Malay Archipelago," "The Geographical Distribution of Animals," &c.

"Mr. Wallace has long devoted himself to the e problems of geographical distribution; and his new volume gives us the cream of his latest thinking in a pleasant and eminently readable form. No other living naturalist has the same union of high literary excellence with profound scientific knowledge. His wonderful grasp of detail, depth of insight, and breadth of view remind one at every turn of Darwin, with whom he shares the honours of discovery in the theory of natural selection; but beyond this he has a lightness of touch, a beauty of style, and an ingenuity in unravelling intricate difficulties which are all his own. . . . 'Island Life' is a work to be accepted almost without reservation from beginning to end. . . . Whoever reads his book must be charmed with it."—*St. James's Gazette.*

"The present volume, though in some respects intended as a popularisation of Mr. Wallace's previous works on the distribution of animals, yet contains an immense amount of new and important matter for the man of science, as well as much delightful reading for the less instructed public. It is, in fact, the final outcome of the author's most mature thought and research on the special subject which he has made most peculiarly his own. . . . The work throughout abounds with interest. . . . It may be read with equal pleasure by those who are already acquainted with the general principles of distribution and by those who wish for the first time to learn something about modern biological geography."—*Athenæum.*

MACMILLAN AND CO., LONDON.

A HANDBOOK OF DOUBLE STARS.

With a Catalogue of Twelve Hundred Double Stars, and extensive Lists of Measures. With additional Notes bringing the Measures up to 1879. For the use of Amateurs. By EDWARD CROSSLEY, F.R.A.S., JOSEPH GLEDHILL, F.R.A.S., and JAMES M. WILSON, M.A., F.R.A.S. With Illustrations. 8vo. 21*s*.

Just ready. 8vo. 1*s*.

CORRECTIONS, NOTES, &c., TO THE HANDBOOK OF DOUBLE STARS.

"The volume is one which may be expected to find its way to the shelves of most amateurs and students of astronomy."—*Nature.*

"This is a truly delightful work, and one which will admirably supply a want. Into the hands of abler, more impartial and painstaking observers and compilers than the authors' its preparation could not have fallen."—*The Astronomical Register.*

"Will be welcomed by all who take an interest in the subject of double stars."—*Academy.*

"The names of the authors, noted authorities on the subject treated of, will lead the reader to open this volume with the feeling that in it he has a treasure of lore on the knowledge brought to light in the last hundred years respecting the relative motions of physically connected stars, nor will he be disappointed."—*Athenæum.*

"One of the most valuable additions to the library of the amateur astronomer that has been made for many years. It is full of information of perennial interest to the student and the practical observer, and assuredly ought to be upon the table of every single observatory in the United Kingdom, and of all those in other parts of the world where the language in which it is written is intelligible."—*The English Mechanic.*

"The book is well and clearly printed, and we heartily recommend it to our readers as a most valuable contribution to the literature of double-star astronomy."—*The Observatory.*

MACMILLAN AND CO., LONDON.

W. LADD & CO.,

SCIENTIFIC INSTRUMENT MANUFACTURERS,

(*By Appointment to the Royal Institution of Great Britain*),

11 AND 12, BEAK STREET, REGENT STREET, W.

IMPROVED HOLTZ ELECTRICAL MACHINES. GRAMME'S MAGNETO-ELECTRIC MACHINE for Laboratory use.

PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3*s*. per oz.

Physical Apparatus of every Description.

ILLUSTRATED CATALOGUE, SIXPENCE.

PATERSON'S NEW CATALOGUE OF PHYSICAL APPARATUS.

LANTERN SLIDES for SCIENTIFIC LECTURES. Season 1880–1. Post free 6 Stamps.
Complete Sets of Physical Apparatus for Science Primers and all the Physical Text-books in use in Schools and Colleges.
Siemens and Gramme Dynamo Machines and Lamps for hire.
Schools supplied with Apparatus as per Science and Art Departments' Requirements in the Sections of Light, Heat, Sound, and Electricity.
Electric Signals for Houses, Hotels, &c., Colliery Signals, Lightning Conductors. The Gower-Bell Loud-speaking Telephone.

EDWARD PATERSON, Electrical Engineer.

SHOW ROOMS AND STEAM WORKS:—76, LITTLE BRITAIN, E.C. (late 3, Bedford Court, W.C.).

MOLISON'S HARMONOGRAPH; executes the Harmonic Curves in the most perfect manner. 15*s*. and 20*s*.

Illustrated Catalogue of Electrical Apparatus, Part 1, *post free*, 6 *Stamps. Ditto, Electric Signals, Part* 2, 6 *Stamps.*

In Memoriam: W. J. Macquorn Rankine.

MISCELLANEOUS SCIENTIFIC PAPERS.

By W. J. MACQUORN RANKINE, C.E., LL.D., F.R.S.,

Late Regius Professor of Civil Engineering in the University of Glasgow.

With MEMOIR by P. G. TAIT, M.A., Professor of Natural Philosophy in the University of Edinburgh; and FINE PORTRAIT on STEEL.

Edited by W. J. MILLAR, C.E.

In One Vol., Royal 8vo, Cloth, with Plates and Diagrams. [*Nearly ready.*

London: CHARLES GRIFFIN AND COMPANY, Stationers' Hall Court.

A NEW AND IMPROVED EDITION.

This day is published,

A MANUAL OF ZOOLOGY,

FOR THE USE OF STUDENTS.

WITH A GENERAL INTRODUCTION ON THE PRINCIPLES OF ZOOLOGY.

BY HENRY ALLEYNE NICHOLSON,

M.D., D.Sc., Ph.D., &c., &c.,

Professor of Natural History in the University of St. Andrew's.

Sixth Edition, Revised and Enlarged. With Glossary of Scientific Terms, and Index. Illustrated with 452 Engravings on Wood. Crown 8vo, pp. 866, 14s.

"It is the best manual of Zoology yet published, not merely in England, but in Europe."—*Pall Mall Gazette.*

"The best treatise on Zoology in moderate compass that we possess."—*Lancet.*

Just Published. By the same Author.

A MANUAL of PALÆONTOLOGY. For

the Use of Students. With a General Introduction on the Principles of Palæontology. Second Edition, Revised throughout, and greatly Enlarged. Illustrated with 722 Engravings. Two Volumes 8vo, 42s.

"The most complete and systematic treatise on the subject in the English language. It has not only been thoroughly revised, and to a great extent rewritten, but so much enlarged by the addition of new matter that it may claim to be considered, to all intents and purposes, a new book."—*Saturday Review*, 25th September, 1880.

By the same Author

TEXT-BOOK of ZOOLOGY. Third Edition. 6s.
INTRODUCTORY TEXT-BOOK of ZOOLOGY. Fourth Edition. 3s.
OUTLINES of NATURAL HISTORY. Second Edition. 1s. 6d.
ANCIENT LIFE-HISTORY of the EARTH. 10s. 6d.
ON THE STRUCTURE AND AFFINITIES of the "TABULATE CORALS" of the PALÆOZOIC PERIOD. Royal 8vo, 21s.

WILLIAM BLACKWOOD & SONS, Edinburgh and London.

JUST PUBLISHED, in 4to, cloth, price 6s.

ELASTICITY AND HEAT.

BY

SIR WILLIAM THOMSON,

Professor of Natural Philosophy in the University of Glasgow, &c.,

Being Articles contributed to the "Encyclopædia Britannica."

May be had separately, price 4s. each.

Edinburgh: ADAM & CHARLES BLACK.

Now ready, in demy 8vo, price 24s.

ON THE STUDY OF FISHES.

By ALBERT C. L. G. GÜNTHER, M.A., F.R.S.,

Keeper of the Zoological Department in the British Museum.

CONTENTS.

1. History and Literature.—2. External Parts.—3. The Skeleton.—4. Myology.—5. Neurology.—6. The Organs.—7. Growth and Variation.—8. Palæontology.—9. Distribution.—10. Classification.—11. Collecting and Preserving.—12. Index.

Illustrated with 330 Wood Engravings.

Edinburgh: ADAM & CHARLES BLACK.

NEW WORK BY MR. DARWIN.

NEXT WEEK, with Woodcuts, crown 8vo, 15s.

The POWER of MOVEMENT in PLANTS.

By CHARLES DARWIN, LL.D., F.R.S., assisted by FRANCIS DARWIN.

JOHN MURRAY, Albemarle Street.

PERUVIAN BARK.

NEXT WEEK, with Maps and Woodcuts, post 8vo, 14s.

A POPULAR ACCOUNT of the INTRO-

DUCTION of CHINCHONA CULTIVATION into BRITISH INDIA, 1860–80. By CLEMENTS R. MARKHAM, C.B., F.R.S.

JOHN MURRAY, Albemarle Street.

THE BOTANIST IN EASTERN LANDS.

NEXT WEEK, with Illustrations, crown 8vo, 14s.

THE GARDENS of the SUN. A Natu-

ralist's Journal on the Mountains and in the Forests and Swamps of Borneo and the Sulu Archipelago. By F. W. BURBIDGE, Trinity College, Botanical Gardens, Dublin.

JOHN MURRAY, Albemarle Street.

THE NATURALIST IN SIBERIA.

NEXT WEEK, with Illustrations, crown 8vo, 14s.

SIBERIA in EUROPE. A Naturalist's

Visit to the Valley of the Petchora in North-East Russia. With Descriptions of Birds and their Migrations. By HENRY SEEBOHM, F.Z.S., F.L.S., F.R.G.S.

JOHN MURRAY, Albemarle Street.

Just published, price £2.

PHILOSOPHICAL TRANSACTIONS.

The FELLOWS of the ROYAL SOCIETY are hereby informed that the Second Part of the PHILOSOPHICAL TRANSACTIONS, Vol. 171, for the year 1880, is now published, and ready for delivery on application at the Office of the Society in Burlington House, daily, between the hours of 10 and 4.

Burlington House. WALTER WHITE, Assistant Secretary, R.S.

NEW WORK BY LIONEL S. BEALE.

Now ready, pp. 230, demy 8vo, 5s.

SLIGHT AILMENTS:

THEIR NATURE AND TREATMENT.

By LIONEL S. BEALE, M.B., F.R.S., F.R.C.P.,

Professor of the Principles and Practice of Medicine in King's College, London.

J. & A. CHURCHILL, New Burlington Street.

BRYCE-WRIGHT'S LATEST ARRIVALS.

MINERALS.—Crystallised Hessite, Crystallised Golds, Krennerite, Crystallised Atacamites, Malacone, Euclase, Edingtonite, Suzannite, Chanarcillite, Proustite, &c.

METEORITES.—Specimens of the following Falls:—Wold Cottage, Yorkshire; Java; Orvinio, Italy; Amana, Ohio; Tipperary, Ireland; Java; Orvinio, Italy; Estherville; Hainholz; Grosnagy, Russia; Borkut; Carthago Co.; Bates Co.; Sierra di Chaco; Ashville Co.; Bates Co.; Pallas; Ashville Co., &c., &c.

BRYCE-WRIGHT, F.R.G.S., &c.,

Mineralogist and Expert in Gems and Precious Stones,

90, GREAT RUSSELL STREET, BLOOMSBURY, LONDON, W.C.

THURSDAY, NOVEMBER 11, 1880

DR. SIEMENS'S NEW CURE FOR SMOKE

THE growing obscurity which distinguishes the winter atmosphere of London has disposed men to consider whether it is an indispensable evil connected with the use of coal in great centres of population, or whether means can be found of providing the warmth and comfort which the copious use of mineral fuel affords us without having to pay the penalty of dispensing with the solar ray, of finding ourselves and everything we touch covered with soot, and of occasionally having, even at midday, to grope our way with a feeling akin to suffocation.

I am decidedly of opinion that the evil is one which not only admits of remedy, but that its cure would result from a closer attention to the principles of economy in the use of fuel.

Until within recent years wasteful expenditure was the rule both in the application of fuel to our large manufacturing operations and for domestic purposes, but great strides have been made within the last twenty years to improve our mode of burning fuel both under our steam boilers and in the metallurgical furnace. The Regenerative Gas Furnace, which was the subject of Faraday's last discourse at the Royal Institution in 1862 has contributed its share to this result, combining as it does considerable economy, with the entire absence of smoke from the chimney.

Since by the employment of gaseous fuel results such as these are realised, there seems no *à priori* reason why analogous results should not attend its application on a smaller scale, even down to the means of heating our apartments, which, although a small application in each individual instance, amounts, in the aggregate, to the largest of all the uses of mineral fuel.

Gas-grates have been tried by individuals desiring progress, but I know several instances in which on account of the great comparative expense incurred, and objections raised to the smell, and dry heat, as it is called, in the room, the time-honoured smoky but cheerful coal-fires were reinstated.

A gas-grate that was arranged in my billiard-room in the usual fashion, consisting of three air-gas-pipes with apertures distributed over the fire-grate, and covered with pumice-stone, presented certainly a cheerless appearance, and filled the room (notwithstanding a fair chimney-draught) with fumes, rendering the benefit of the fire a doubtful one. These fumes could not have passed into the room from the upper surface of the pumice-stone owing to its proximity to the chimney; but a little consideration made me come to the conclusion that these gases really proceeded from the ash-pan into the room. The products of combustion set up by the gas flames ascend no doubt so long as they are intensely hot, but in giving off their heat to the inert pumice-stone they rapidly cool, and being heavier than atmospheric air, descend through the grate between the lines of gas flames, and thus reach the apartment. Moreover the gas burnt towards the back of the fireplace takes scarcely any part in providing a red radiating surface in front of the grate, serving only to baffle the draught passing towards the chimney from the room.

The first condition to be realised in an efficient gas-grate consists in suppressing all gas orifices except immediately behind the bottom front bar, and in substituting for the grate a solid dead plate. Instead of using inert matter such as pumice-stone, I consider it far more economical and efficacious to transfer the heat of the gas flames to gas coke or anthracite, which when once heated helps the gas to increase and maintain a sufficient temperature for radiation through its own slow combustion. The gas should not be mixed in the pipe with atmospheric air to produce a Bunsen flame, as is frequently done, because by using the unmixed gas a rich flame is set up between the pieces of coke near the front of the grate, producing to the eye an appearance similar to a well-ignited ordinary coal fire, and the hot carbonaceous matter through which it percolates ensures its entire combustion before reaching the chimney. Heat will however gradually accumulate towards the back of the fire, notwithstanding the suppression of the grate bars, and in order to obtain the utmost economy this heat should be utilised to increase the temperature of the gas flames and of the coke in front of the grate.

To accomplish this I have constructed a grate according to the annexed sketch. The iron dead plate *c* is riveted to a stout copper plate *a* facing the back of the fire-grate, and extending five inches both upwards and downwards from the point of junction. The dead plate *c* stops short about an inch behind the bottom bar of the grate to make room for a half-inch gas-pipe *f*, which is perforated with holes of about one-twentieth of an inch in diameter placed zig-zag at distances of three-quarters of an inch along its upper surface. This pipe rests upon a lower plate *d*, which is bent downwards towards the back so as to provide a vertical and horizontal channel of about one inch in breadth between the two plates. A trap-door *e*, held up by a spring, is provided for the discharge of ashes falling into this channel. The vertical portion of this channel is occupied by a strip of sheet copper about four inches deep, bent in and out like a lady's frill and riveted to the copper back piece. Copper being an excellent conductor of heat, and this piece presenting (if not less than a quarter of an inch thick) a considerable sectional conductive area, transfers the heat from the back of the grate to the frill-work in the vertical channel. An air current is set up by this heat, which, in passing along the horizontal channel, impinges on the line of gas flames and greatly increases their brilliancy. So great is the heat imparted to the air by this simple arrangement that a piece of lead of about half a pound in weight introduced through the trap-door into this channel melted in five minutes, proving a temperature to exist exceeding 619° F. or 326° C. The abstraction of heat from the back has moreover the advantage of retarding the combustion of the coke there while promoting it at the front of the grate.

The sketch represents a fireplace at my office, in a room of 7,200 cubic feet capacity facing the north. I always found it difficult during cold weather to keep this room at 60° F. with a coal fire, but it has been easily maintained at that temperature since the grate has been altered to the gas-coke grate just described.

This heating arrangement is not however essentially necessary; in several of the grates which I have altered for gas I have simply closed up the space below the bottom bar by means of a close-fitting ash-pan, and introduced the gaspipe behind the lower bar, an alteration which can be effected at very trifling expense, and presents the advantage of great cleanliness, the ash-pan being withdrawn only at intervals of several days for emptying. The appearance of the fire however is in that case much less brilliant than when the hot-air arrangement is added.

In order to test the question of economy I have passed the gas consumed in the grate through a Parkinson's 10-light dry gas-meter supplied to me by the Woolwich, Plumstead, and Charlton Consumer's Gas Company; the coke used is also carefully weighed.

The result of one day's campaign of nine hours is a consumption of 62 cubic feet of gas and 22 lb. of coke (the coke remaining in the grate being in each case put to the debit of the following day). Taking the gas at the average London price of 3*s.* 6*d.* per 1000 cubic feet and the coke at 18*s.* a ton, the account stands thus for nine hours:—



a, Copper plate ¼ inch thick and 10 inches wide at back of grate; *b*, frill of copper $\frac{1}{16}$ inch thick; *c*, iron dead plate riveted to plate *a*; *d*, angle plate with trap-door *e* for removing ashes; *f*, gas-pipe about ½ inch diameter with holes ¾ inch apart.

	d.
62 cubic feet of gas at 3*s.* 6*d.* per thousand ...	2·604
22 lb. coke at 18*s.* a ton	2·121
Total ...	4·725

or at the rate of 0·524*d.* per hour. In its former condition as a coal-grate the consumption exceeded generally two and a half large scuttles a day, weighing 19 lb. each, or 47 lb. of coal, which at 23*s.* a ton equals 5·7*d.* for nine hours, being 0·633*d.* per hour. This result shows that the coke-gas fire, as here described, is not only a warmer but a cheaper fire than its predecessor, with the advantages in its favour that it is thoroughly smokeless, that it can be put off or on at any moment (which in most cases means considerable economy), that it is lit without the trouble of laying the fire, as it is called, and keeps alight without requiring to be stirred.

It may appear strange at first that the use of the separated coke and gas to produce a given effect should be fully as cheap as using the raw material combining the two constituents, but the solution may be found in the

circumstance that in the case of the coke-gas fire no heat flashes up the chimney, but is utilised entirely for raising the coke in front of the grate to the condition most favourable to radiation into the room.

I hold that it is almost barbarous to use raw coal for any purpose, and that the time will come when all our fuel will be separated into its two constituents before reaching our factories or our domestic hearths. Such a measure would not only furnish us with the complete solution of the smoke question, but would be of great value also as a money saving. In conclusion I may observe that I have taken up this question without the idea of profit, and shall be happy to furnish builders and others desirous to introduce the grate here described with the necessary indications to insure success. C. WILLIAM SIEMENS

THE RUSSIAN IMPERIAL YACHT, "LIVADIA"

IN NATURE, vol. xxii. p. 270, we gave an account of this remarkable ship, and stated that we should report the results of her trials to our readers. We there said "it cannot be doubted that her speed will surpass 14 knots," and we pretty plainly intimated that it would, in our judgment, fall substantially short of 17 knots; in point of fact it has fallen between these limits, and nearer the higher than the lower, the average mean speed at the measured distance being 15·864 knots. The details of the several runs, which have not previously been published in London, we believe, are as follows :—

No. of Run.	Indicated H.P.	Speed in Knots.
1	12,267	15·69
2	11,704	15·53
3	12,387	15·83
4	12,437	15·65
5	12,857	15·92
6	12,472	15·65
Average	12,354	15·725

The trials of the *Livadia* were greatly hurried, the vessel going down the river on a Wednesday, making a preliminary run under steam on the following day, Thursday; on Friday she made a run at full speed for six hours, giving an average of 15 knots; and on Saturday she made her measured mile trials. Those who understand the conditions under which these steam trials were made will see at once that it was not possible to obtain the best results with a ship thus put under steam day after day, her boiler tubes getting doubtless more or less foul, and her machinery also falling somewhat out of perfect condition, especially where there were three separate sets of engines to be cared for. The bottom was also foul from having been three months in the wet dock at Fairfield. The effect of haste in making the trials is visible in the variations of horse-power developed upon the runs, there being a difference of more than 1000 h.p. between the power developed, for example, on the second run as compared with that of the fifth. The speeds given above show less discrepancies than the horse-powers, but it can hardly be doubted that the *Livadia* as she is can be driven at over 16 knots under fair conditions, without any alteration whatever. It is, as has been said elsewhere, highly probable that some improvements might be made in the screw propellers, as it is not to be expected that the best conditions were secured at the first attempt. In fact we have evidence that the central screw was set at a pitch different from that of the side-screws, and runs at a different speed; it now appears likely that the pitch should have been the same in all cases, and when the opportunity offers this change will probably be made, and the speed again taken. Other slight modifications will doubtless also be tried, and those of our own naval architects, who have well considered all the facts, have formed the opinion that if all minor causes of interference with the best performance are removed, a speed approaching 17 knots may be reached in the *Livadia*. It needs no words of ours to convince the scientific world that whether any great increase of speed be obtained with this vessel or not, the Russian Government has rendered a vast service to naval science by demonstrating on a large scale and in a public and unquestionable manner, the fact that a vessel whose breadth is enormous, and whose length is but one and a half times her breadth, may with no very inordinate expenditure of power be made to take a high place among the few fastest ships of the world.

But the interest in the *Livadia*, while it is greatest as regards her high-speed trials, by no means ends there. Her steaming performances with diminished steam power are also very interesting. In considering these the reader should remember that in this case as in all cases of fast ships going with reduced power and at reduced speed, the performances are subject to a double disadvantage: first the *weight* of the machinery carried is of course in excess of what is needed to produce the reduced power; and secondly, the friction and other losses are likewise in corresponding excess. For example, when the *Livadia* is steaming say at 11 to 12 knots, she is employing less power than any one of her three sets of engines produces; and if she had not to go beyond such a speed she might dispense with the other two sets of engines and boilers, and thus be relieved of nearly 1000 tons of weight, and of two-thirds of the frictional and other losses which she is obliged to undergo when steaming at 11 or 12 knots with all her engines working at a reduced speed. Bearing these facts in mind, we may now state that the reduced steaming of the *Livadia* is reported officially to have given the following results :—

Aggregate Ind. H.P.	Speed.	Wind.	Tide.
2969	11 knots	With	Slightly
4770	13 ,,	,,	,,
8940	15 ,,	Against	Slightly against
10,037	15½ ,,	,,	Against

The indicated horse-powers above given were calculated from diagrams, and the speed was taken by log. The results were reported, we know, in perfect good faith, and are a correct indication, in the main, of the relation between power and speed in the *Livadia* with her present screws, &c. They nevertheless appear to us to exhibit on the face of them some slight discrepancy, which is amply accounted for by the fact that the speeds were, as we have said, taken by the log, which does not admit of that minute accuracy which may and ought to characterise measured mile-trial results. The above figures are borne out by the sea-passages of the yacht. She steamed continuously in fair and moderate weather at an average speed of somewhat more than 12 knots with an average expenditure of about 4000 Ind. H.P.

With all the above facts and figures before us we see

clearly how vain have been the prejudices, and how baseless the predictions, which condemned ships of this type as incompatible with even moderately good speeds, and as ridiculous when the attainment of high speed was contemplated. It is with no small feelings of vanity, but with a genuine pride in a great scientific triumph which we ventured to predict beforehand, that we have witnessed the *Livadia's* success. It is a success which England may well envy, and of which the Russian Government may well be proud. Its bearing upon the future of steam navigation cannot fail to be considerable even in the mercantile marine, while it is quite impossible for the war navies of the world to escape its influence. Our long-standing objections to the *Inflexible* and *Italia* types of ship are well known to our readers, the construction of such ships under the name of first-class ironclads being most trying even to the common sense, and much more to the scientific sense, of the country. With the *Livadia* in existence, and with the facilities which such great breadth as hers offers to the production of armoured ships worthy of the name, the exposure of our first-class ships to the destructive effects both of shells and of torpedoes, will not be endured. We congratulate Admiral Popoff upon the established success of the great idea which he was the first to propound, and as the idea would still have remained a mere idea but for the powerful patronage of the Grand Duke Constantine, we gladly recognise again the scientific acumen and that "courage of his opinions" which distinguish His Imperial Highness. By consenting to the trial of so great a naval experiment in a yacht of his own, the Emperor of Russia has secured a sea-palace of great speed, of unexampled accommodation, and of a freedom from rolling and pitching such as no other ship in the world enjoys.

On the last-named points—those of pitching and rolling—we have to record very remarkable results. We are informed on the best authority that in the gale in the Bay of Biscay, with waves running over twenty feet high, when ordinary vessels were seen rolling and pitching heavily, and even when the gale and the sea were at their highest, the greatest roll to leeward was 5 degrees, and that to windward 4 degrees, while the greatest pitch was 4 degrees and the greatest "'scend" 3 degrees. This extreme limitation of motion was most extraordinary, excluding almost all the usual incidents of sea-life. Nothing was secured on board, and nothing fell throughout the storm. There were occasionally heavy blows of the sea under the flat shallow bow, and these caused much vibration at times; but nothing was disturbed, and even the paint is nowhere cracked throughout the wood-built cabins and palaces of the ship.

In the accident which the *Livadia* met with on her voyage from Brest to Ferrol, by striking heavily downwards upon some floating object or objects during a heavy gale in the Bay of Biscay, with a high and confused sea running, the value of water-tight subdivision has been strikingly demonstrated. The injuries done by the blows were extended by the heavy strokes of the sea under the bluff bow, and several of the forward compartments were filled. A scientific friend who inspected the bow after the compartments were pumped out in the harbour of Ferrol, informs us that in two or three places the bulkhead divisions had evidently been badly struck and made leaky at the bottom, and in one compartment the sea was plainly visible through the broken plating. And yet nothing was known on board of these injuries when at sea beyond the fact (ascertained by "sounding") that a forward compartment of the double bottom had been somehow filled, so effectually was the ship proper preserved from all injury within the double bottom, and so little effect had the filling of the forward spaces upon the trim and behaviour of the ship! The *Livadia* is constructed of steel, and is as lightly built as our own fast steel ships of the latest date; and as a similar accident to the recent one might occur again, as it may to any ship of light draught and great buoyancy, it would no doubt be prudent to add something to the strength of the outer bottom where most exposed to strains and blows; but this is a matter of detail which we leave the naval architect to discuss. The great lesson to be derived from the incident is the immeasurable value of double bottoms and of great compartmental subdivision in sea-going structures. An ordinary large steam yacht not so subdivided might have been lost under like circumstances, and certainly would have been more or less jeopordised and more or less injured internally; in the present case not a particle of injury to the interior of the ship or to her costly fittings was sustained, and hours after the accident, with a very high and confused sea still running, the Lord High Admiral of Russia and his guests dined as safely, as easily, and almost as quietly as if he had been ashore in his summer palace of Orianda.

A MEDICAL CATALOGUE

Index Catalogue of the Library of the Surgeon-General's Office, U.S. Army. Vol. i., A—Berliúski. 4to, pp. 888. (Washington: Government Printing Office.)

THE saying of Hippocrates, that art is long and time is short, is so true, not merely of medical art, but of work in general, that most working men find their lives gliding so quickly away that they do not attempt great works, and very probably would not succeed if they did so. But every now and then we come across men whose energy is so marvellous, and whose power of getting through work is so enormous, that we are struck with amazement at it. Such a man is Dr. Billings, to whose extraordinary energy and perseverance we owe the present work. This purports to be only a catalogue of the Library of the Office of the Surgeon-General of the United States Army, and Dr. Billings takes care to call attention to the fact that it is not a complete medical bibliography, and that any one who relies upon it as such will commit a serious error. "It is," he says, "a catalogue of what is to be found in a single collection; a collection so large, and of such a character, that there are few subjects in medicine with regard to which something may not be found in it, but which is by no means complete." It is not, however, a mere catalogue in the ordinary sense of the word, inasmuch as its contents are not confined to the names and titles of books and their authors. It is also a catalogue of subjects, so that any one wishing to read up a particular subject will find under the appropriate heading a list of the chief works bearing upon it. Nor is this all. There are other catalogues in which a similar arrangement has not only been

attempted but successfully carried out. But this catalogue differs from all others inasmuch as it is the only compilation in which the herculean task of arranging in proper order the contents, not only of books, but of medical periodicals, has ever been essayed. To any person who is aware of the enormous extent of medical periodical literature, and who has had personal experience of the time and labour involved in looking up a few references, it seems almost incredible that any man should have had the courage to venture upon the task which Dr. Billings has successfully accomplished. To give the faintest idea of the work, we take a single heading—Amputation, and we find, besides a large number of works and references under this title itself, several other headings on the treatment of amputation, cases and statistics of amputation, double amputation, history of amputation, intra-uterine amputation, methods of amputation, multiple amputation, sequelæ and after treatment of amputation, spontaneous amputation, amputation in the course of disease, amputation in gunshot wounds, amputation in infants, amputation in joints, amputation in pregnancy, carpal and metacarpal amputations, tarsal and meta-tarsal amputation, amputations at ankle-joint, amputations of arm, amputations of breast, amputations at elbow-joint, amputations of fingers and toes, amputations of foot, amputations of fore-arm, amputations of hip-joint, amputations of knee-joint, amputations of leg, amputations at shoulder-joint, amputations of thigh, amputations of toes, amputations at wrist-joint, besides cross references to Amputation considered under other heads, such as Gangrene, Hospitals, Surgery, Umbilical Cord, Arteries, Limbs, Osteomyelitis, Spinal Cord, Stumps, Frost-bite, Pregnancy, Pyæmia, Elbow-joint, Breast, Tibia, Ankle-joint, Astragalus, Aneurisms, Arm, Artery, Humerus, &c. On taking a single one of these headings, we find under it nineteen books, and on then attempting to count the references to periodical literature we go along until we come to the end of the letter C, and then stop in despair, for we have already got a hundred references, and find that to proceed to the end of the alphabet will be a work of both time and labour. The wearisomeness of counting the number of references in a small fraction of one sub-head may give the reader some notion of the labour involved in hunting out and writing down the materials, and yet, after all, such idea would be very imperfect, for the labours of Dr. Billings and his assistants have not consisted merely in giving these references. A much greater amount of time and trouble has probably been consumed in the consideration of what should be left out than by the labour of arranging and compiling what should be put in, for in indexing journals and transactions the general rule which they have followed has been that only original articles should be taken, though occasionally important papers in several periodicals, and reprints when the originals have not been in the library, have been indexed. In describing the arrangement of the book we cannot do better than quote Dr. Billings' own words :—

"This catalogue includes both authors and subjects—the names being arranged in dictionary order in a single alphabet. Under the subject-headings are included the titles of original articles in the medical journals and transactions contained in the Library, for which reason the Catalogue is commonly spoken of by those who are familiar with it as the 'Index-Catalogue,' and the name has been adopted as being brief and at the same time distinctive.

"The form adopted is essentially that shown in the 'Specimen Fasciculus' published in 1876, and it has been selected after a careful consideration of the criticisms and suggestions brought out by that fasciculus.

"The great majority of physicians, and especially of American physicians, who have given their opinion, have expressed a decided preference for this form; and although a librarian might find a complete separation of the catalogue of authors from that of subjects a little more convenient, the demand on the part of those who are to use it is very decidedly for the combination here given.

"The following points have been kept in view in the selection and arrangement of the subject-headings :—

"I. Those titles have been selected for subjects for which it is presumed that the majority of educated English-speaking physicians would look in an alphabetical arrangement.

"II. Where there is doubt as between two or more subject-headings, cross-references are given.

"III. Where both an English and a Latin or Greek word are in common use to designate the same subject, the English word is preferred, and references are given from the others.

"IV. As a rule, substantives rather than adjectives are selected for subject-headings. Exceptions occur to this in anatomical nomenclature, as 'Lachrymal duct'; 'Thyroid gland.'

"V. In names of subjects derived from personal names, the latter precede, as 'Addison's disease'; 'Eustachian tube.'

"VI. Local diseases or injuries are as a rule placed under the name of the organ or locality affected, as 'Kidney (*Abscess of*)'; 'Neck (*Wound of*).' There are exceptions to this, in accordance with Rule I., *e.g.*, 'Abscess (*Perinephritic*).'

"VII. Cases in which one disease is complicated with or immediately followed by another are placed under the name of the first disease with the sub-heading '*Complications and Sequelæ*.'

"VIII. When the main subject of an article is the action of a given remedy in general, or its action in several diseases, it is indexed under the name of the remedy; but if it relate to its action in but one disease, it is indexed under the name of the disease.

"IX. The amount of sub-division made under the principal subject-heads depends very greatly upon the number of references to be classed.

"X. As a rule, the references are given from general to more special heads, but not the reverse. It is presumed, for instance, that those who wish to consult the literature on 'Aphasia' will turn to 'Brain (*Diseases of*)' and 'Nervous System (*Diseases of*),' as well as to 'Aphasia,' without being directed to do so by a cross-reference under the latter title.

"XI. Under the name of an organ will be found the books and papers relating to the anatomy and physiology of that organ. Following this usually come the abnormities and malformations of the organ, then its diseases, then its tumours, and lastly, its wounds and injuries.

"Anonymous works or papers are entered in regular order under the first word of the title not an article or preposition. Russian and Japanese titles are transliterated, and a translation is usually appended. Greek *names* are transliterated for the sake of uniformity in type.

"In indexing journals and transactions, the general rule has been that only original articles should be taken, but occasionally important papers are indexed in several periodicals; and sometimes a reprint is indexed when the original is not in the Library.

"The List of Abbreviations of Titles of Periodicals prefixed to this volume shows the journals and transactions which have been indexed to the present time. The right-hand column exhibits the volumes or numbers possessed by the Library, and, negatively, the deficiencies, which it is my earnest desire to fill. The List of Abbreviations is separately paged in order that it may be bound by itself, if desired, for use with succeeding volumes.

"Some of the abbreviations of names of places, especially in the United States, might have been still further shortened if the Catalogue had been intended for use only in this country. But an analysis, by subjects, of so large a collection of medical periodicals is, necessarily, useful in St. Petersburg, for example, as well as in Washington, its measure of utility in any locality being the extent of the collection of medical periodical literature therein. Intelligibility to foreigners, therefore, has been regarded as a quality essential to the abbreviations in question.

"In indicating pagination, the rule is that where the article does not exceed two pages in extent the first page only is given. If it exceed two pages, both the first and last pages are noted.

"The work of preparing this Catalogue began in 1873, and has been carried on persistently, and as rapidly as the amount of clerical aid available and the nature of the work would permit.

"The present volume includes 9090 author-titles, representing 8031 volumes and 6398 pamphlets. It also includes 9000 subject-titles of separate books and pamphlets, and 34,604 titles of articles in periodicals."

The rapid progress of every branch of science, medical and otherwise, and the proportionate, or perhaps we ought almost to say disproportionate, increase of medical and scientific periodical literature, render it exceedingly difficult for the student to keep himself *au courant* with the newest discoveries. The Royal Society's Catalogue of scientific papers conferred an inestimable boon upon scientific men, but it left much to be desired, inasmuch as it gave only the names of authors, and contained no index of subjects. Sometimes, too, its strict confinement to periodical literature is felt as an imperfection, for in cases where discoveries have been published in the form of pamphlets of a few pages, one searches through the Catalogue in the vain expectation of finding them. However, we have hitherto had nothing at all resembling it in medical literature, but now we possess the first volume of a work which greatly excels it both in scope and size. Such defects as the volume possesses are due to the imperfections of the library of which it is a catalogue, and it is to be hoped that all those (and their name must be legion) who profit by the use of this remarkable production, will do their best to enable Dr. Billings to make good the deficiencies.

It is clear that, however complete any catalogue may be at the time of its publication, the constant appearance of new books and pamphlets day by day and month by month must render it more and more defective. In order to supplement this catalogue, and prevent this gradually increasing deficiency from being felt as an evil, Dr. Billings and Dr. Fletcher are now publishing the *Index Medicus*, a monthly classified record of the current medical literature of the world. This is published by F. Leypoldt in New York, and by Trübner and Co. in London. The great labour and expense involved in getting out this monthly index require for it a large circulation. At present, we believe, it is published at a loss, and an increased number of subscribers is urgently requested in order to permit its continuance. We therefore trust that every one who finds his time and labour saved by this Index-Catalogue will show his gratitude to Dr. Billings and those who have assisted him, not only by helping to supply the wants of the library at Washington, but by subscribing regularly to the *Index Medicus*.

We cannot conclude this brief notice without congratulating the United States Government on having in its service such men as Dr. Billings and his able assistants, Doctors Fletcher, Yarrow, and Chadwick, nor without expressing the thankfulness which every medical man owes to them for the great boon they have conferred on medicine in printing and issuing the present Index-Catalogue.

THE PHILOSOPHY OF LANGUAGE

Max Müller and the Philosophy of Language. By Ludwig Noiré. (London: Longmans, Green, and Co. 1879.)

THE substance of this work has already appeared in the German periodical *Nord und Süd*, and the author here tells us that he has reproduced it in an enlarged form and in an English dress in order to do full justice to Max Müller's great merits in clearing the way "for future investigators." He considers that eminent services have been rendered to the cause of linguistic studies by the writings of the illustrious Oxford professor, and four out of the five chapters comprising this treatise are mainly occupied in putting this somewhat obvious fact in the clearest light. But he holds, in common probably with Max Müller himself, that the problem of the ultimate origin of articulate speech has not been solved in the brilliant and deservedly popular "Lectures on the Science of Language." Many difficulties are there removed, much light is thrown upon a great number of obscure points, several abstruse questions are treated with an amazing wealth of illustration, bringing them home to the meanest capacity, and sundry popular views, notably those stigmatised as the "Pooh-pooh" and "Bow-wow" theories, are either exploded, or reduced to their proper value. But the mystery of origin, the inexplicable ultimate residuum of roots, forming the constituent elements of all speech, remains almost unassailed, though distinct service has undoubtedly been done by narrowing down the question to this one issue. A still greater service is done when the gifted writer emphatically declares that these roots "are not, as is commonly maintained, merely scientific abstractions, but they were used originally as real words." This gave the death-blow to the Platonic "types," ideas, metaphysical entities and concepts which had still continued to obscure the subject, and block the way like so much mediæval rubbish. Herr Noiré aptly compares them to the *ova*, whence all animal and vegetable life. "By their development and uninterrupted growth all the known languages of the world have reached their marvellous structure, and become the body of reason and the instrument of mind" (p. 55).

In the last chapter, which will doubtless be read with the greatest curiosity, the author takes up the subject where Max Müller had left it, and develops the theory on

the origin of language, which he had already broached in his "Ursprung der Sprache," specially devoted to that question. The essential peculiarity of the view here advocated is contained in the following passage:—"Language is the CHILD OF WILL, of an active, not of a passive state; the roots of words contain the *proper activity of men*, and receive their significance from the *effects* of this activity in so far as it is phenomenal, *i.e.* visible. Human thought arises from a double root, the subjective activity, or the will, and the objective phenomenon which is accessible to the senses."

Language is further represented as "a product of *association* and of the community of feeling which is developed, intensified, and finally carried to perfection by community of life" (p. 81). Great stress is laid on the fact that human thought has a double root, the subject or individual activity, and its effect in the action, whence it follows that "the life of language stands in an indissoluble relation to the development of human action" (p. 83). The earliest meanings of verbal roots are all said to be "referred to human action," such notions as to dig, strike, scrape, scratch, tear, lying at the root of endless derived and secondary concepts.

Human thought is conceived as "an active process, a self-conscious, self-confident activity, not as a crude materialism imagines, the accidental play of unconscious atoms" (p. 88). This active process is traced to common action, and language itself becomes "the voice of the community" (p. 88). The essence of language consists in the naming of things, while the power of forming a notion of a thing, that is, of a group of phenomena grasped and conceived as one, constitutes the essential difference between man and the brute creation. At the same time man can conceive of things only "because he has the gift of speech, because he can give them a name" (p. 90).

The power of giving names flowed from the power of using signs. "He used signs and thereby attained to the power of using names also; or, in other words, of betokening again by a sound what he had noted before." The transition from one process to the other, attributed to the active will, is stated to be "the most important part of the theory" (p. 92).

Then the power of giving signs to things grows out of the habit of modifying them for his own use. "Men dug caves, plaited twigs, stripped the beasts of their skin, the trees of their bark. Hence was developed the marvellous hitherto unexplained gift of abstraction, and this in the most natural way. Man learnt to conceive a thing as he learnt to create things. His own creations were the first *things* for him" (p. 92). So that language conceives objects only "in so far as human action has touched, modified, reconstructed them; in a word, in so far as they have received *form*." Even such things as exist independently of the human will, or lie beyond the sphere of human action, are nevertheless brought within the sphere of human speech. "They become objects of human thought in the same way as the rest, that is to say, they are named as they would be, if the human hand had formed them" (p. 98).

Such is the line of argument pursued in the attempt to build up a new theory of articulate speech, which is here conceived by an evident disciple of Schopenhauer and the Monistic school, as an emanation of the self-conscious human will, flowing from the power of forming abstract ideas, and dealing primarily and exclusively with such things only as are either the direct creation, or brought under the direct control and modifying influence of man. But this seems to be a complete perversion of the natural sequence of events in the evolution of man and all his faculties. Of these the very highest, next at all events to the moral sense, consequently the latest to be developed, was the conscious will. In the lowest savage tribes it is still often so feeble as scarcely to be distinguished from mere sensation and animal impulse. Yet the speech even of the rudest tribes is almost invariably found to be of a very intricate mechanism, subject to definite laws of structure and harmony, possessed at times of a copious vocabulary, embracing a variety of objects entirely beyond the influence or control of man himself, objects whose names cannot by the most violent straining be traced to those of things created or modified by human action. It is very easy to quote a few instances in support of such a theory as this, especially from such highly imaginative languages as those of the Aryan family, in which analogy and metaphor have had such free play during a long period of comparative culture. But hundreds of such examples would bring us no nearer than we were before to the starting point, to the faculty of naming things and actions, to the reason of certain sounds being selected in preference to others wherewith to name them.

The question still remains unanswered, whence came the "limited store of sounds with which man accompanied his action," and which are said to have in some mysterious way "associated themselves with the objects produced or modified by the action." The difficulty does not lie in the derivation of *cælum* or *hole* from a primitive root *sku* or *ku*, but in tracing the origin of this root itself, and, in general, of all roots, whether they have to do with human action or not. For it is not for a moment to be supposed that all the roots even of the Aryan family can be identified with the names of things subject to human influence. Such are, for instance, *as* expressive of mere existence, hence passive rather than active, *idh*, *indh*, to burn, whence αἴθω, αἰθήρ, *æstus*, *heat*, &c., words all applicable primarily rather to the powers of nature than of man; *ud*, *und*, to flow, whence ὑδος, *udum*, *undo*, Goth. *wato*, *water*, &c., a purely natural object named directly from a purely natural conception; *svan*, to resound, whence *sonus*, *sound*; *svanitam*, *sonitus*, all words expressive of natural noise, and if Eichhoff is right in connecting the Gothic *sangws* and English *song* with this root, then these human actions can be conceived only as secondary derivatives from the primary idea of natural sound. This is the logical order of sequence, but it is as subversive of the author's theory as are many other Aryan roots which need not here be quoted. Enough has been said to show that this theory, while leaving the real question of origin untouched, will apply in any case to a part only of the original stock of roots in the Aryan family. Nor, as stated, will it help us in the least towards an explanation even of these.

On the whole it is to be feared that our author leaves the matter much where Max Müller left it at the end of his "Science of Language"; for the theory here advocated assuredly does not answer the questions: How do mere cries become phonetic types? How can sensations be changed into concepts? These questions can be answered

only by divesting the mind of all metaphysical vagaries, and approaching the discussion in a spirit of strict loyalty to the established principles of evolution. The universe is not "a mental phenomenon," as Schopenhauer would call it, nor is speech the deliberate product of conscious will. It is an organism which, like all other organisms, had its origin in a germ, and its slow growth and silent development in suitable surroundings, independently of all conscious action. Yet in dealing with a subject of this sort one still feels how much easier it is to refute error than to establish truth. "*Utinam tam facile vera invenire possim quam falsa convincere.*" A. H. KEANE

OUR BOOK SHELF

Easy Lessons in Science. Edited by Prof. F. W. Barrett. I. *Easy Lessons in Heat.* By C. A. Martineau. II. *Easy Lessons in Light.* By Mrs. W. Awdry. (London: Macmillan and Co., 1880.)

THESE excellent little lesson books deserve a wide circulation. Well and clearly written, they are at the same time strictly of the "scientific" rather than of the so-called "popular" style of exposition; there being none of the objectionable sensational element with which certain French works in light science have too greatly familiarised us. The cuts with which the volumes before us are illustrated are numerous, appropriate, and many of them original. In each case the reader is instructed in the simple apparatus needed to repeat the experiments described; so that a teacher who desires to give to young pupils a few elementary lessons in the sciences of heat and light will find here the very text-books most suited to his requirements. Miss C. A. Martineau's "Lessons in Heat" follows the usual order of text-books in that science. The first lesson deals with expansions, the second with notions of temperature, the third tells "how heat spreads," and so forth, and in the concluding chapters some of the fundamental facts of the relation between heat and mechanical work are made known. One experiment which we do not remember meeting with before in the shape in which it is given deserves to be cited. It is a variation on Davy's old experiment with flame and gauze. "Put a bit of camphor *on* the wire gauze, and hold a light *under* it. The vapour of the camphor passes freely through the gauze, catches fire, and burns with a blue flame till the whole of the camphor has been turned into vapour and burned. But the flame does not pass through the gauze to set fire to the solid camphor."

Mrs. Awdry's "Lessons on Light" are no less felicitous in their treatment of the subject. The usual popular text-book on Optics abounds in descriptions of different optical instruments, telescopes, microscopes, kaleidoscopes, and the like, without much trouble being expended upon first principles. But in these lessons first principles claim the prominent place: the first point explained is the law of inverse squares, and the second the geometrical laws of refraction and reflection—and the explanations are admirably yet quite simply done. A most interesting feature is that the latter half of these easy lessons is devoted to physical optics. One chapter on the wave-theory, and two entitled "Measurings" prepare the way for a capital lesson on Diffraction. A lesson on the Spectrum and one on the Rainbow close the series.

We do not say that there is no room for criticism in judging these little volumes. A professed teacher of Natural Philosophy might grumble at the omission of certain things that claim prominence in all the older text-books and in many of the syllabuses of contemporary examinations. Yet we would challenge such critics to produce a more useful, or suggestive, or accurate set of lessons, or one more entirely free from the two besetting faults of sensational popularisation and educational cram.

It is to be hoped that Prof. Barrett will continue his labours in adding to the series he has so ably edited.

Outline of a Course of Natural Philosophy, with Specimen Examination Papers. By Gerald Molloy, D.D. (London: Simpkin, Marshall, and Co., 1880.)

THIS work of 114 pages contains a syllabus-outline of the course of lectures in Natural Philosophy by Dr. Molloy, at the Catholic University of Ireland, and is reprinted chiefly to meet the wants of teachers in intermediate schools. To the syllabus, which is remarkably full and complete, is appended an extensive series of examination papers on all branches of physics except light, electricity, and magnetism, which are promised to follow. These questions, though chiefly elementary, have been carefully prepared, and are a valuable part of the work. In an appendix Dr. Molloy reprints a paper giving an account of his particular form of bichromate battery, which appears to be peculiarly suited to the needs of schools and colleges, where a powerful battery of convenient form is required to be in readiness for occasional use.

LETTERS TO THE EDITOR

[*The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts. No notice is taken of anonymous communications.*]

[*The Editor urgently requests correspondents to keep their letters as short as possible. The pressure on his space is so great that it is impossible otherwise to ensure the appearance even of communications containing interesting and novel facts.*]

Sir Wyville Thomson and Natural Selection

I AM sorry to find that Sir Wyville Thomson does not understand the principle of natural selection, as explained by Mr. Wallace and myself. If he had done so, he could not have written the following sentence in the Introduction to the Voyage of the *Challenger*:—"The character of the abyssal fauna refuses to give the least support to the theory which refers the evolution of species to extreme variation guided only by natural selection." This is a standard of criticism not uncommonly reached by theologians and metaphysicians, when they write on scientific subjects, but is something new as coming from a naturalist. Prof. Huxley demurs to it in the last number of NATURE; but he does not touch on the expression of *extreme variation*, nor on that of evolution being guided *only* by natural selection. Can Sir Wyville Thomson name any one who has said that the evolution of species depends only on natural selection? As far as concerns myself, I believe that no one has brought forward so many observations on the effects of the use and disuse of parts, as I have done in my "Variation of Animals and Plants under Domestication"; and these observations were made for this special object. I have likewise there adduced a considerable body of facts, showing the direct action of external conditions on organisms; though no doubt since my books were published much has been learnt on this head. If Sir Wyville Thomson were to visit the yard of a breeder, and saw all his cattle or sheep almost absolutely true, that is, closely similar, he would exclaim: "Sir, I see here no extreme variation; nor can I find any support to the belief that you have followed the principle of selection in the breeding of your animals." From what I formerly saw of breeders, I have no doubt that the man thus rebuked would have smiled and said not a word. If he had afterwards told the story to other breeders, I greatly fear that they would have used emphatic but irreverent language about naturalists. CHARLES DARWIN

Down, Beckenham, Kent, November 5

Geological Changes of Level

IN a most friendly notice in your last issue of the *Memoirs* forming the first volume of the official Report of the *Challenger* Expedition, Prof. Huxley takes exception to a sentence in my short Introduction. "There seems to be sufficient evidence that all changes of level since the close of the Palæozoic period are in direct relation to the present coast lines," and he asks in what possible sense this can be the case.

I fully admit the criticism, and that the sentence as it stands does not explain itself.

That it is not a relation of ordinary parallelism Lyell's and D'Orbigny's maps of old coast-lines, a map published by myself in "The Depths of the Sea," and particularly the beautiful later maps of Jurassic, Cretaceous, and Tertiary France by M. Delesse, abundantly show. I have explained my idea of the relation in position between the recent deposits and those of the Tertiary and Secondary periods in "The Depths of the Sea" (pp. 472-476) at some length. I believe that the Jurassic, the Cretaceous, and the Tertiary formations are essentially *marginal* deposits, and that their belts of deposition form approximately a series of contour bands upon an elevation which has persisted throughout a long series of local and general oscillations, the sum of which has raised the whole through a small vertical range. Such oscillations have also, doubtless, affected the bottom of the sea, but nowhere to such an extent as to modify in any important degree the conditions of the abyssal region.

Prof. Huxley says, "There is nothing, so far as I am aware, in the biological or geological evidence at present accessible, to render untenable the hypothesis that an area of the mid-Atlantic or of the Pacific sea-bed as big as Europe should have been upheaved as high as Mont Blanc and have subsided again any time since the Palæozoic epoch, if there were any grounds for entertaining it." I think however he will admit that the following *Challenger* data, if they can be established, afford at least a presumption against an oscillation of such a kind, at all events in post-Triassic times, beyond which it is difficult to stretch even the imagination.

The careful researches of my colleagues, Mr. Murray and the Abbé Renard, with which I have had the advantage of being familiar during their progress, have led us to the belief that (1) the chalk of the Cretaceous period was not laid down in what we now consider deep-water, and that its fauna, consisting mainly of shallow-water forms, merely touches the upper limit of the abyssal fauna; and (2) that no beds exist in the series of known sedimentary rocks which correspond in composition and in structure with the beds now in process of formation in the abyssal sea ("The Atlantic," vol. ii. p. 299).

The hypothesis of the elevation of a mass of land equal to Europe and as high as Mont Blanc in the middle of one of the great ocean basins could in our present state of knowledge be defensible only on the supposition that it was a phenomenon of the same order as the elevation of some portion of our existing continental land, and there is now, to say the least, grave reason for doubting that any rock which is due to accumulations formed at depths over 2500 fathoms, the average depth of the basins to which Prof. Huxley refers, enters into the composition of any existing continent. The present land consists of a set of crystalline rock-axes of various ages, with a long succession of sedimentary deposits, all of which give evidence of having been laid down in water of moderate depth, piled up upon and against them. Such a hypothesis therefore, besides being without a single fact in its support, would be met by a strong adverse argument from analogy, and would be, so far, in a worse case than the hypothesis of the origin of species by natural selection.

I thoroughly agree, however, with my friend Prof. Huxley that "the value of the great work which is now being brought before the public does not lie in the speculations which may be based upon it, but in the mass and the solidity of the permanent additions which it makes to our knowledge of natural facts," and I imagine that all of us who are engaged in that work look upon it as our first and paramount duty to present these natural facts which have been acquired as simply and as effectively as we can. Still the generalisations or impressions, or whatever they may be, of the few men selected to observe these facts are as much a part of the result of the Expedition as anything else, and I think it is also our duty to offer them to our fellow-workers for what they are worth. C. WYVILLE THOMSON

Bonsyde, Linlithgow, November 6

"The First Volume of the Publications of the 'Challenger'"—A Correction

THERE is a typographical error in my notice of the *Challenger* publications, published in last week's NATURE, for which I should, of course, be disposed to blame the printer, had it not been hinted to me that my handwriting is sometimes not so clear as might be wished.

I appear (p. 2) to agree with the proposition that "the deep-sea fauna presents us with many forms which are the *dried* and but little modified descendants of Tertiary and Mesozoic species."

As few things can be much wetter than the inhabitants of the ocean abysses, this opinion seems to be, to say the least, eccentric.

But "dried" should have been printed "direct," which was the word denoted by my graphic symbols. T. H. HUXLEY

4, Marlborough Place, Abbey Road, N.W., November 7

Correspondence of Phenomena in Magnetic Storms

THE Astronomer-Royal having lately received from the Observatory of Zi-ka-wei, in China (latitude 31° 12′ north, longitude, from Greenwich, 8h. 6m. east), lithographed copies of the photographic traces of the declination and horizontal force magnets, extending from August 11 to 14, and from August 17 to 20 of the present year, has placed them in my hands for comparison with the Greenwich records. Some particulars of this comparison are herewith annexed. Greenwich time is used throughout.

A general examination of the two sets of curves shows that the disturbances were usually greater in magnitude at Greenwich than at Zi-ka-wei. Comparing the curves in detail, it is found that on August 11, at 10.20[1] a.m., after a quiet period, the declination and horizontal force magnets at Greenwich both made a sudden start, which was the commencement of a magnetic disturbance, lasting until midnight. An apparently equally sudden start (from a quiescent state), in both declination and horizontal force, is shown on the Zi-ka-wei curves, occurring in declination at 10.12 a.m., and in horizontal force at 10.20 a.m. (as nearly as the small scale on which the curves are drawn will allow measures to be made). This first motion was to decrease the west declination and increase the horizontal force at both places. A bold motion in the two Zi-ka-wei curves at 11.30 a.m. (increase of declination, decrease of horizontal force) has corresponding decrease of horizontal force at Greenwich, not accompanied, however, by much motion in declination. And of numerous fluctuations occurring at Greenwich between noon and midnight of the same day, some appear to correspond with motions at Zi-ka-wei, whilst others do not.

A calm state follows at both places, until near noon of August 12. On this day at about 11.40 a.m. the magnets at Greenwich made a further start, and until 4 p.m. the movements were large. A corresponding start is also shown in both the Zi-ka-wei curves (commencing, according to the register, some minutes sooner than at Greenwich), the movements following being similarly large. Afterwards, until 6 a.m. of August 13, considerable oscillation was nearly continually shown at Greenwich, there being especially a large change of declination between 7 and 9 p.m. (August 12); but there is no strongly-marked motion at the latter time at Zi-ka-wei, and the changes are throughout much smaller than at Greenwich. Later on August 13 further oscillations occur at both places, but the separate motions are in no particular accordance. The period of disturbance seems definitely to come to an end at both places at 6 a.m. on August 14.

A period of quiet is broken at Greenwich on August 18, at 1.45 p.m., by a sharp though small movement both in declination and horizontal force (increase of both). There is a corresponding sharp increase (after quietude) of horizontal force at Zi ka-wei, but no change of declination. A bold increase of declination and decrease of horizontal force at Greenwich at 7 a.m. of August 19 is accompanied by a similar decrease of horizontal force at Zi-ka-wei, but with little change of declination. Bolder changes occur at the latter place at noon, but with comparatively small change at Greenwich. The magnets become quiet at both places at or near midnight of August 19.

The general result of this comparison of Greenwich and Zi-ka-wei curves appears to be that, after a quiet period, the first indication of disturbance, if sudden (it need not be large) occurs simultaneously or nearly so at both places, but that during the

[1] Approximately stated to be 10.30 in my previous letter (NATURE, vol. xxii. p. 361), and so quoted by Mr. Whipple (p. 558). The time above given is more exact.

continuance of disturbance the oscillations of the magnets seem to be so locally modified that it becomes difficult to trace correspondence: some movements appear to correspond, and some not. A strongly-marked bend in the trace at one place may appear, as it were, stunted in that at the other place, or may not be perceptible at all. The disturbances appear to die out at pretty much the same time at both places. All this confirms very much what Mr. Whipple has already pointed out as regards Melbourne (NATURE, vol. xxii. p. 558).

M. Dechevrens, in some remarks which accompany the sheet of curves, notes that the disturbance of August 11–14 is the greatest experienced since the establishment of photographic registration at Zi-ka-wei in the year 1877, and he considers that the changes then observed (those of vertical force included, of which he gives no curves) are similar to such as would be produced by a powerful magnet placed in a certain defined position. It may perhaps be here pointed out that the results given by the Astronomer-Royal in his paper, "First Analysis of One Hundred and Seventy-seven Magnetic Storms" (*Phil. Trans.* for 1863) appear to give no support to a theory of this kind, and indeed seem conclusively to show that at Greenwich the observed disturbances cannot be accounted for in any such way.

It should be added that M. Dechevrens reports also that strong earth currents were experienced on August 11 and 12 on the submarine telegraph lines connecting Shanghai with Nagasaki and with Hong-Kong, as well as on the land lines in Japan, so much so that correspondence was frequently interrupted, but that no interruption appears to have been experienced on the occasion of the generally smaller magnetic disturbance of August 18. WILLIAM ELLIS

Royal Observatory, Greenwich, November 6

Meteor

A VERY large and brilliant meteor was observed here at 6h. 41m. p.m. G.M.T., on November 8. Its size was at least equal to one-fourth of that of the full moon, and it lit up the whole garden for about a second and a half. It was pear-shaped. The colour was white, and left behind it a pale red train. Its path was from a point half-way between α and δ Persei to 3° above ν Ursæ Majoris. The sky was rather hazy at the time.

Stonyhurst Observatory, November 9 S. J. PERRY

Condition of Jupiter

ON the evening of the 2nd I had a fine view of Jupiter with my 6-inch Cook's equatorial. The general appearance of the planet was remarkable for the bright colouring of the belts and of the red spot, a circumstance strongly noted by a gentleman who was observing with me, and who had not seen the planet for some time.

I could not however trace the usual white ring round the red spot. Below the red equatorial belt was a row of four or five small irregularly-shaped spots, nearly black in tint, and resembling sun-spots seen under a low power.

These dark spots seem now affecting Jupiter's surface in several parts, and are certainly not usual to it. About 9h. 26m. Satellite I. was occulted. I watched it gradually coming to contact, and at last it seemed to advance on the face of the planet, at least one-half of its diameter appearing to project thereon. It then faded out gradually.

September 3, 1879, at 9h. 8m., with the same instrument Satellite III. reappearing after occultation, was slightly (but certainly) projected on to the disk of the planet. It will be interesting to notice whether the present condition of Jupiter will be accompanied by more than ordinary displays of auroræ, of which symptoms have already appeared.

Guildown, November 6 J. RAND CAPRON

P.S.—Since writing the above accounts reach me of auroræ at Brighton on the 3rd and in the Orkneys on the 4th instant.

Vox Angelica

MANY of your readers may be acquainted with the nature of the Vox Angelica stop on a good organ. It consists of two ranks of pipes of small scale and delicate quality of tone, one of which is tuned slightly sharp, so that a wavy (hence called *Unda Maris*) sound is produced. Now it is possible to obtain very similar effects on an ordinary Estey American organ. Given the viola and violetta stops to be drawn out, wrap a band of india-rubber (an ordinary elastic band does very well) round the neck of the viola stop so that it cannot return completely home, on moderate pressure, and allowing a fraction of an inch to intervene between its true final position when inactive; beats will be heard of intensity depending upon the deviation from complete occlusion of this stop. The nearer the viola stop is to occlusion the more rapid the beats; but it is undesirable to obtain rapidity, as the lower notes are too prominently out of tune in this case. Anybody can, by experiment, determine the proper amount of deviation to be employed, and having done this the effect is remarkably good. On an Estey, the two stops mentioned are the only admissible ones for such an experiment, from consideration of overtones. No doubt some of your readers may adopt a more elaborate and convenient method of regulating the deviation than by elastic bands, after some experiments. It may seem a paradox to obtain beautiful concordant effects by the use of discordant vibrational relations, but it is undeniable that on a first-class organ the Voix Celeste, or Vox Angelica, or Unda Maris, is a most beautiful stop, and is capable of producing perfect *con sordini* effects. GEORGE RAYLEIGH VICARS

Woodville House, Rugby, November 3

Solids and Liquids at High Temperatures

SOME years ago I made an investigation much simpler but somewhat similar to that referred to by Prof. Carnelley in NATURE, vol. xxii. p. 435. An account of the experiments then made was communicated to the Royal Scottish Society of Arts, 1874–75. One of the results of that investigation was that while we do know something about the temperatures at which different forms of matter change from one state to another when a "*free surface*" is present, yet we are utterly ignorant of the temperature at which that change will take place when no "*free surface*" is present. It will be necessary here to explain that a "*free surface*" is any surface of the body under examination at which it is *free* to change its state. A surface of water, for instance, in contact with its own vapour is a "*free surface*" for the water passing into the gaseous state. The surface of a piece of ice in water, again, is a "*free surface*" at which the water may freeze or the ice may melt. And what are known as the freezing, melting, and boiling points of water are the temperatures at which these changes take place when such "*free surfaces*" are present. As to what the freezing, melting, and boiling points are when these "*free surfaces*" are absent, we have at present no knowledge whatever. All we know is that the freezing point is lower, and the "melting" and "boiling points" are higher, than when "*free surfaces*" are present.

The first of these points is too well known to be referred to here. The last point was illustrated in the paper referred to by an experiment in which water was heated in a metal vessel under atmospheric pressure to a temperature far above the "boiling point," when the water exploded and violently ejected itself from the vessel. The superheating of the water was accomplished by carefully excluding all "*free surfaces*" by bringing the water into as perfect contact with the metal of the vessel as possible.

Many experiments were also made to get direct and thermometric experimental illustration of the existence of ice at a temperature above the "melting point," but no satisfactory illustrations were got, on account of the great difficulty of getting quit of "*free surfaces.*" Of course so long as there existed a "*free surface*" at the surface of contact of the ice with the thermometer, the temperature at that part could not rise above the "melting point." It was however shown by indirect evidence that ice may exist at a temperature above the "freezing point" by referring to the well-known and beautiful experiment of passing a beam of light through a block of ice. When this is done with the aid of proper apparatus it is seen that the heat of the ray is absorbed by the ice, and that melting takes place at different points inside the block. Now the presumption is that the heat is absorbed at all points inside the block, but as the melting only takes place at certain points the heat absorbed where there is no melting must raise the temperature of the ice at those points above the "melting point," and the heat there absorbed by the ice will be conducted to the "*free surfaces,*" where it is spent in melting the ice.

Now though I was perfectly prepared to find that Prof. Carnelley had succeeded in heating the *inside* of a block of ice to a temperature above the "melting-point," I certainly did not expect so high a temperature as his experiments indicate to be

possible. But what is still more puzzling is how Prof. Carnelley succeeded in burning his fingers with the ice. Our previous knowledge would lead us to suppose that the outside surface of the block of ice was a *free surface*, and that therefore it would be impossible, however high the temperature of the inside of the block, to heat the outside above the "melting point," as we should expect the ice to melt or to sublime at the outside, and keep the temperature at 0° C.

These expectations being disappointed, we naturally look to the decreased pressure under which Prof. Carnelley's experiments were made for an explanation of this most unexpected state of matters. Now it is very evident that when dealing with pressures of about one atmosphere, and with temperatures of 120° and 180° C., that pressure, as pressure, has nothing whatever directly to do with the "melting point" of the ice. While this is the case, it is equally evident that it has a most important influence on the surroundings of the ice. At the pressure of 4·6 mm., at which the experiments were made, no water would be present, there would be nothing but ice and water-vapour. Here then appears to be the great teaching of Prof. Carnelley's experiments. *They show that the surface of ice bounded by its own vapour is not a "free surface."* This result is so very unexpected that much consideration will be necessary before we can re arrange our ideas to meet the new facts.

We might imagine that nothing could be more free than the surface of a body bounded by nothing but its own vapour, yet Prof. Carnelley's experiments seem to say it really is not so, and not being a *"free surface,"* we of course know nothing whatever of how high the temperature will require to be before the ice will melt under these conditions.

These experiments of Prof. Carnelley's are so interesting that we wait with impatience a full description of them. His results indicate something new with regard to the influence of a liquid on its melting solid. I observe that Prof. Carnelley's results are doubted by most of your correspondents, but for the present we must accept them when Prof. Carnelley distinctly states that the temperature of the ice was taken by means of a thermometer in contact with the ice. JOHN AITKEN

Darroch, Falkirk, N.B., October 30

Wire Torsion

IN the letter in NATURE, vol. xxii. p. 604, which we wrote at the request of Major Herschel, who asked for information regarding the connection between tensional and torsional strains of a brass wire, we mentioned that there were many papers scattered through the *Proceedings* of learned societies dealing with the fluidity of metals. There is one communication to which we might specially have referred, as it deals in particular with the torsional yielding of wires under tension, and this is a paper on "Torsion," by Prof. G. Wiedemann, in the *Annalen der Physik und Chemie*, No. 4, vol. vi., 1879, pp. 485-520, and of which a translation is given in the *Philosophical Magazine*, vol. ix., January 1880, pp. 1-15, and February, pp. 97-109. The first part of this paper gives a detailed account of experiments which show :—(1) That a brass wire often subjected to a particular torsion, either in one or in both directions, becomes "killed" for any less torsions, that is, follows Hooke's law for its temporary torsions; (2) that a wire under tension acquires greater torsional set from a given torsional couple than when the wire is unextended; (3) that a wire under even considerable tension may be killed by torslon in alternately opposite directions, that is, it will obey Hooke's law for any tension or torsion less than the stresses actually applied originally. Prof. Wiedemann in the second part of his paper considers the well-known "agitation effects," and enters on an explanation of the phenomenon based upon molecular allineations referring to the magnetisation theory of Weber and Kolrausch which is based on the same idea.

The strains in Prof. Wiedemann's wires were however much less than in those used in Major Herschel's experiments.

JOHN PERRY
London, November 8 W. E. AYRTON

Heat of Formation of a Compound

IN NATURE, vol. xxii. p. 608, there is a paper on "Recent Chemical Research," in which under the head of work by Thomsen the following law is enunciated :—

"The heat of formation of a compound substance is the difference between the sum of the heats of combustion of the constituent elements of the compound and the heat of combustion of the compound itself." After that it is shown that this is not the true heat of formation of the compound, as many important corrections have to be made. On referring to Berthelot's "Essai de Mécanique Chimique" I find the following :—"The heat of formation of an organic compound from its elements is the difference between the sum of the heats of total combustion of its elements and the heat of combustion of the compound with formation of identical products."

Can any of your readers inform me whether Thomsen or Berthelot first enunciated this law?

Another point is, that Berthelot apparently makes no reference to the corrections for the heat absorbed in dissociating the molecules of the elements, &c. A. P. LAURIE

Edinburgh, November 1

The Yang-tse, the Yellow River, and the Pei-ho

IN replying to the letter of your correspondent (NATURE, vol. xxii. p. 559) on the subject of my recent paper on these three rivers, I have to thank him for his very probable explanation of the excessive estimate made by Sir George Staunton of the amount of sediment discharged by the Yellow River.

The estimate given in my paper of the water-discharge of the River Plate is *ipso facto* an assumption made by Mr. George Higgin from Mr. Bateman's calculation of the minimum flow of that river, which he found to be 670,000 cubic feet per second. It might have been better, however, if I had added Mr. Higgin's qualifying remark that such an estimate of the mean volume of water was "very much under the mark" (NATURE, vol. xix. p. 555).

The anomaly of the surface current varying in velocity with the same average depth of water has not been unnoticed by myself, though I am unable to give a satisfactory explanation of the difficulty. H. B. GUPPY

Woodlane, Falmouth, November 6

The Thresher

WHAT is the "thresher"? It is generally assumed to be the fox-shark (*Alopias vulpes*), but in a recent number of *Land and Water*—which I have only just seen—Mr. Frank Buckland says that he believes it to be "the gladiator dolphin or sword grampus" (*Orca gladiator*). This he infers from a drawing of Lord A. Campbell's, of which he gives a copy. The tail, he says, is not that of the fox-shark. But as it is heterocercal it cannot be that of a grampus or any other Cetacean. Whatever it is I suppose that there is no doubt that it throws itself out of the water ("high as the masthead" [of a trawler] one of Mr. Buckland's correspondents avers). Does it do so more than once? Once, many years ago, between Sydney and New Zealand, I saw, what they said was a fight between a thresher and a whale, but there was nothing to be seen beyond a splashing of the water. Last year off Lisbon I witnessed a similar event. Does the sword-fish also attack the whale? Lord A. Campbell, in the letter accompanying his drawing, estimated the length of *his* thresher at "upwards of thirty feet;" this is twice the length given by Yarrell. FRANCIS P. PASCOE

October 30

Since the above was written I see that Dr. Günther, in his new work on Fishes, says: "Statements that it (the fox-shark) has been seen to attack whales and other large cetaceans rest upon erroneous observations" (p. 322).

"STUDENT" should refer to Newcomb's "Popular Astronomy" with respect to the larger telescopes. For results he must refer to the publications of the Royal and Astronomical Societies, the Washington Observatory, &c.

PAUL LAFARGUE.—We regret we have no further details on the labours of the U.S. Fish Commission in increasing the food supply of the country.

ILLUSTRATIONS OF NEW OR RARE ANIMALS IN THE ZOOLOGICAL SOCIETY'S LIVING COLLECTION

I.

THE sagacious founders of the Zoological Society of London made it a special rule that no dividends or gifts of any kind should be distributed amongst the

members. On the contrary, every Fellow has to contribute an annual sum towards the maintenance of the Society's establishment, unless he prefers to pay a life-composition in lieu thereof. Moreover, the Society are so fortunate as to be unencumbered by borrowed capital. They have consequently no burden in the shape of interest to be provided for. It follows that after putting aside from their income a sum sufficient to meet the annual expenditure, they are able to devote the surplus to new buildings in the Gardens, and to the acquisition of new and rare subjects for the menagerie. While the supply of lions, tigers, elephants, and other well-known animals must always be kept up for the delectation of the ordinary public, and for the maintenance of the best possible living series of animals, it is also thus in their power to acquire animals of specially scientific value, in which the casual observer would take little interest, and which would, therefore, be quite ineligible except in a scientific point of view. This course of action has been adopted for many years, more especially since the foundation of the office of "Prosector" to the Society. For these special acquisitions not only delight the eyes of the intellectual observer while they live, but furnish the prosector with subjects for his studies when dead. Those who are acquainted with the *Proceedings* and *Transactions* of the Zoological Society of London will be well aware of the amount of work that has thus been accomplished as regards the anatomy of many of the rarer birds and mammals.

FIG. 1.—The Musk-deer (*Moschus moschiferus*). (From a drawing by Mr. J. Wolf from nature.)

It is, however, by no means by purchase only that rare animals are added to the Zoological Society's collection. Numerous friends and correspondents in almost every corner of the earth are in constant communication with the Secretary of the Society, and are ever endeavouring to obtain specimens that may be acceptable to the collection. In fact the donations have of late years become so numerous that they have not unfrequently rivalled in number and interest the objects acquired by purchase. Taking the acquisitions from these two sources together, there are always a considerable number of objects in the Society's collection that specially invite the attention of the observant naturalist. Amongst these rarities there are at the present moment the following, of which illustrations are given, drawn upon wood by Mr. J. Smit, an artist constantly employed by the Zoological Society.

1. The musk-deer (*Moschus moschiferus*) was well known to the older writers on zoology as the animal that has from long periods of time supplied the "musk" of commerce. This scent is still much in vogue in the East, but in Western Europe has been long superseded by more refined perfumes, though it may be remarked that one of the fashionable dealers in Bond Street still keeps a stuffed musk-deer in his window, and is doubtless ready to supply the product in question.

FIG. 2.—The Japanese Wolf (*Canis hodophylax*).

The musk-deer was until recently usually associated with another group of mammals to which it has really very little affinity. Dr. Gray and other systematists united it with the Chevrotains (*Tragulus*) of India and tropical Africa—a group of ruminants remarkable for their small size and hornless heads, and presenting somewhat of the appearance of diminutive antelopes. M. Alphonse Milne-Edwards of Paris was, we believe, the first naturalist to show that this allocation was unnatural. In his excellent essay on the Chevrotains, published in 1864, M. Milne-Edwards proved conclusively that these little-understood animals constitute a peculiar family of ungulates quite distinct from either the Bovidæ or Cervidæ, and in fact in some respects approaching more nearly to the pigs (Suidæ). The correctness of these observations has been since fully demonstrated by Prof. Flower, Mr. Garrod, and other systematists.

The musk-deer therefore remains unique in its own group, and constitutes a special division of the Cervidæ

Office of the Chief Signal Officer,

UNITED STATES ARMY.

Charted from Actual Observations taken Simultaneously. Series commencing September, 1877.

No. V.



or deer-family, remarkable for its absence of antlers in both sexes, the extraordinary prominence of the canine teeth (well shown in the illustration), the musk-producing organ, and other peculiarities.

It is to the great exertions of Sir Richard Pollock, K.C.S.I., lately Commissioner at Peshawur, that the Zoological Society are indebted for their living examples of the musk-deer, the only specimens, it is believed, that have ever been brought to Europe in captivity. A female of this animal was first received from Sir Richard Pollock in 1869. Although it did not live long in the Gardens, it gave Prof. Flower an opportunity of preparing a most valuable paper on its anatomy.[1] The same generous donor presented in 1877 a pair of this scarce animal, obtained from the Cashmere Hills, of which the male, now in excellent condition and fully adult, still survives, and is the subject of the accompanying illustration.

The musk-deer is found throughout the mountainous districts of Central and Eastern Asia, ranging, as the recent Russian explorers have shown, into Amoorland. Southwards it extends into the Himalayas, but is here, as Jerdon tells us, only met with at great elevations, rarely descending in summer below a height of 8000 feet, and extending as high as the upper limits of the forests.

Hodgson says that the musk-deer is "solitary, living in retired spots near rocks or in the depths of the forests: they leap well, but cannot climb nor descend slopes well. They rut in winter, and produce one or two young, usually in the cleft of a rock. In six weeks the young can shift for themselves, and are driven off by the mother."

The musk-deer, as stated by Jerdon, is wonderfully sure-footed, and over rocky and precipitous ground perhaps has no equal. It appears to eat chiefly grasses and lichens. If twins are produced the two are kept apart, it being very solitary in its habits, even in infancy. The musk is milky for the first year or two, afterwards granular. The dung of the males smells of musk, but the body does not, and females do not smell of it in the slightest degree. The flesh is dark red, and the young is considered to afford the best venison in India.

The musk-deer is much sought after by the hunter for its musk, many being shot and snared annually. A good musk-pod is valued at from ten to fifteen rupees. The musk as sold is often much adulterated with blood, liver, &c. One ounce is about the average produce of the pod.

2. The species of the genus *Canis* known as wolves—that is *Canis lupus* and its representative forms—are widely spread over the northern hemisphere, extending in the Old World as far south as Abyssinia (*Canis simensis*) and India (*Canis pallipes*). In North America the larger *Canis occidentalis* take their place in the Arctic regions and Rocky Mountains, but as it goes south, gradually gives place to the very distinct prairie-wolf (*Canis latrans*), which seems to range as far down as the Central American Isthmus.

The existence of a true wolf in Japan has been known to us since 1847 from its description and figure in Temminck and Siebold's "Fauna Japonica," under the name *Canis hodophylax*. But this animal has been very little known in Europe except from the specimens in the Leyden Museum, and as it is altogether omitted in Dr. Gray's Catalogue of the Carnivores, appears to be not even represented in the well-stored galleries of the British Museum. It is to an active correspondent in Japan—Mr. H. Heywood Jones—that the Zoological Society are indebted for their unique specimens of this scarce carnivore, which is now very difficult to be procured, having been driven into the recesses of the wooded mountains.

In general form and proportions the Japanese wolf much resembles its well-known congener of Europe, but is of inferior size and more slender make. According to Siebold its native name is "Jamainu."

3. The Tufted Umbrette (*Scopus umbretta*) or "Hammerkop" of the Cape Colonists, is a well-known bird both to natives and travellers all over Central and Southern Africa, but in Europe has only hitherto been recognised as a somewhat scarce object to be found in the principal museums. The example now in the Zoological Society's Gardens, which was acquired a few weeks ago by purchase from a dealer in Liverpool, is, it is believed, the only living specimen yet brought to Europe. The umbrette has been usually placed by systematists among the storks, and by Prof. Reinhardt was supposed to be the nearest ally of the *Balæniceps rex* (without doubt a Ciconiine form). But those who have studied its nimble gait and active habits, as shown in life, will not readily agree to this opinion. Nothing can well be more different from the staid, stolid demeanour of the stork than the lively action of the umbrette, which rather reminds one of a curlew or sand-piper. It is probable, however, that its real place will be found to be amongst the spoonbills and ibises (Plataleidæ), a group usually associated with the storks, although it must be recollected that the late Prof. Garrod maintained that (as "Schizorhinæ") the Plataleidæ would be better placed with the Limicolæ. When the present specimen dies the question of its position will be quickly decided by the Society's prosector,

FIG. 3.—The Tufted Umbrette (*Scopus umbretta*).

[1] "On the Structure and Affinities of the Musk-Deer (*Moschus moschiferus*, Linn.)," by William Henry Flower, F.R.S., V.P.Z.S.—P.Z.S., 1875, p. 159.

but long may we wait, it is to be hoped, before this event shall happen.

Of the curious nesting habits of *Scopus* we have excellent accounts from Brehm, Heuglin, and other naturalists who have visited the Upper Nile. But one of our own countrymen, a not less active or experienced observer—has likewise written a most interesting account of this bird's economy, and we cannot do better than transcribe a part of it.

"The *Hammerkop* (literally hammerhead)," says Mr. Layard in "The Birds of South Africa," "is found throughout the Colony and all the way to the Zambezi, frequenting ponds, marshes, rivers, and lakes. It is a strange, weird bird, flitting about with great activity in the dusk of the evening, and preying upon frogs, small fishes, &c. At times, when two or three are feeding in the same small pool, they will execute a singular dance, skipping round one another, opening and closing their wings, and performing strange antics.

"They breed on trees and on rocky ledges, forming a huge structure of sticks, some of them of considerable thickness. These nests are so solid that they will bear the weight of a large, heavy man on the domed roof without collapsing. The entrance is a small hole, generally placed in the most inaccessible side. The eggs, three to five in number, are of a pure white, axis 1″ 9‴; diam. 1″ 4‴.

"On my late friend Jackson's farm, at Nel's Poort, there is a singular rocky glen between two hills. In this spot a beautiful permanent spring called 'Jackalsfontein' takes its rise. Of course, in consequence, there are a few wild almond and other trees, and the place is a little oasis amid the barren mountains. It is a favourite resort of wild animals, hyænas, leopards, jackals, &c., and here Mr. Jackson has constructed one of his most successful hyæna-traps. On the ledges of the rocks in this secluded spot a colony of Hammerkops have built for years. Some of the nests are quite inaccessible, while others can be reached with a little trouble. I counted six or eight within fifty yards, and some of them contained at least a large cartload of sticks. Mr. Jackson told me they occupied the same nest year after year, and added to it or repaired it as required. About some that I visited I found brass and bone buttons, bits of crockery, bleached bones, &c. Mr. Jackson said if a 'Tottie' lost his knife or tinder-box on the farm, or within some miles of the place, he made a point of examining the hammerkops' nests, and frequently with success, the birds, like the 'Bowerbird' of Australia, embellishing their dwellings with any glittering or bright-coloured thing they can pick up."

A SUCCESSFUL AFRICAN EXPEDITION

AFRICA is overrun with explorers of all nationalities. Too often of late have we had to read of failures, of abortive attempts on the part of expensively-equipped expeditions to reach the field of their work, or of deaths by fever or assassination after the first difficulties were overcome. In spite of all, however, the unprecedented activity of recent years in this favourite field of exploration has pretty well filled up, with the leading features at least, that great blank space in the heart of the continent which in the rude maps of our schoolboy days was marked "unexplored." In the very centre of that space there is still however a blank, giving ample scope for work for the numerous Belgian expeditions that have hitherto done so little. It was to fill up this blank to some extent that the Geographical Society, about two years ago, obtained subscriptions to send out an expedition under young Keith Johnston, who had inherited an enthusiasm for geographical work quite worthy of the name he bore. As his subordinate and as geologist to the expedition, the Society appointed another young Scotchman, Mr. Joseph Thomson, a pupil of Prof. Geikie, who recommended him to the Geographical Society. To him, we grieve to say, it has been left to tell the story of the expedition, which he did, and did well, on Monday night at the opening meeting of the Geographical Society. This expedition is remarkable in many respects, in some points more remarkable than any other African expedition that we know of. The outline of its story is soon told. With 150 of the best men that could be found in and around Zanzibar Keith Johnston left that place in May, 1879, and striking at once to the south-west, made for the north end of Lake Nyassa, which was the real starting-point for fresh work. Little more than a month after the start, young Johnston, who seemed to have the nerve and stamina of an athlete, succumbed to the malarious influences of the coast region, and was buried by his companion at Behobeho, to the north of the Lufiji river. Mr. Thomson, inexperienced youth of twenty-two though he was, was equal to the emergency. With admirable tact and nerve he took his place as the sole leader of the expedition, and accomplished even more than the work which the Society had chalked out for it. By an unexplored route, through barren wastes and over lofty mountains, through the sneaking Wakhutu and the warlike Mahenge, he and his followers made their way till their eyes were gladdened and their weary spirits refreshed by the sight of the waters of Nyassa. Thence, after brief rest, they resumed their march over the lofty and undulating plateau, which they found occupied the region between the north end of Nyassa and the south shore of Tanganyika. Leaving here the bulk of his followers, Mr. Thomson, with a handful of men, trudged his way over the rugged western shores of Lake Tanganyika, to visit the Lukuga and settle the question whether it was an outlet or an affluent of the lake, a question, which, one would think, could be easily solved, but on which Stanley and Cameron published diametrically opposite statements. After visiting the missionary station near the mouth of the river, and running across to Ujiji, Mr. Thomson returned to the Lukuga and traced it for some miles of its downward course. After barely escaping from the murderous Warua with their lives, the party sailed down the lake, and rejoining their companions made the return journey to Zanzibar along the usual caravan route with unprecedented rapidity, in about a year after the expedition set out under their late chief. Mr. Thomson declared with just pride that all this was accomplished without the shedding of a drop of blood for either offensive or defensive purposes; with one exception he brought all his men back "in the best of health and condition"; he has collected certain information about a considerable region which no white man had previously visited; he has solved one of the few remaining great problems of African geography; and he has located with certainty a great salt lake (Hikwa) whose existence previously had only been based on native rumour. Mr. Thomson is a trained geologist, and as such he has doubtless seen more than almost any previous explorer. He tells us of the metamorphic schists and gneiss which compose the mountains of the great central plateau; of the many extinct volcanic cones that lie around the north-west end of Lake Nyassa, and of the metamorphic clay slates, felspathic rocks and volcanic porphyries and tuffs that look down on the lake from the north and north-east. His further geological insight may dispel some of the illusions that seem to be abroad as to the abounding wealth of the African interior. Much of the country between the coast and Nyassa is barren waste; and the chief characteristic of the region between Nyassa and Tanganyika he found to be "utter barrenness and the absence of anything worth trading for." Instead of the mountains of iron and the miles of surface coal, nowhere did he see a single metal in a form which a white man would for a moment look at as a profitable or workable speculation; there is very little more iron, he

maintains, than is sufficient to supply the simple wants of the natives. Coal he saw none, and he does not believe that such a thing exists over the wide area embraced in his route. This may be discouraging, but it is wholesome, and may prove a check to the wild schemes sometimes broached by speculators for opening up the African interior. From the Chimboya Mountains to the south-east of Tanganyika Mr. Thomson found numerous streamlets flowing southwards, doubtless to join the Chambeze, which, after passing through many a lake and levying tribute from a region one million square miles in extent, pours its almost Amazonian volume, as the Congo, 3000 miles below, into the bosom of the broad Atlantic. The much-debated Lukuga he found, as Mr. Hore had found shortly before him, to be a broad and rapid river, flowing westwards from the Tanganyika Lake to the Lualaba, as the Congo here is called; and Lake Hikwa he saw was a fine sheet of water with no outlet, lying among the lofty mountains, which stretch away east from Southern Tanganyika. What may be the extent and value of the purely geographical observations obtained by Mr. Thomson we have no means of knowing; doubtless in this respect the expedition suffered in the death of Mr. Johnston, who was a trained geographer. But in other respects, in information as to the structure of the country, the nature of its products, and the character of its varied peoples, the expedition under Mr. Thomson has been fruitful to a high degree; altogether it is one of the best pieces of original work which our not too energetic Geographical Society has ever done. Mr. Thomson's well-written and well-read paper was received with enthusiasm by an unusually distinguished audience. We trust to be able very shortly to give details concerning both the geography and geology of the Central Plateau from Mr. Thomson's own hands.

UNITED STATES WEATHER MAPS, DECEMBER, 1878

IMPORTANT changes took place this month in the distribution of the earth's atmosphere as compared with what obtained during the previous month, and these were accompanied with at least equally important changes in the geographical distribution of the temperature.

If a line be drawn from Texas to Newfoundland across the Atlantic, the north of France and Germany, thence curving round to south-eastward through the Black Sea, the Caucasus, India, the East India Islands, and Australia to the south island of New Zealand, it is found to pass through a broad and extended region where atmospheric pressure was throughout considerably below the average of December, and this low pressure was still further deepened at various points along the line. Again, another line passing from Australia through the Philippine Islands, Japan, Mantchooria, Behring's Straits, and Alaska, also marks out an extensive region where pressure was uninterruptedly below the mean.

On the other hand atmospheric pressure was above the average, and generally largely so, over the United States to west of long. 90°, over Greenland, Iceland, Farö, Shetland, and over a large portion of the Old Continent bounded by a line drawn from Lapland round by Lake Balkhash, Canton, Pekin, to at least the upper waters of the Lena. Another area of high pressure extended from Syria, through Egypt and East Africa to the Cape; and part of a third area of high pressure appeared in the north island of New Zealand.

As regards North America, the greatest excess of pressure, 0·196 inch above the average, occurred in the Columbia Valley, from which it gradually fell on proceeding eastward to a defect from the average of 0·146 inch about Lake Champlain and to northward, rising again to near the average on the north of Nova Scotia. To the north-east and north of this region exceedingly high pressures for these regions and the season prevailed, being 0·635 inch above the average in the north-west of Iceland, 0·500 inch in the south of Greenland, and at the three stations in West Greenland, proceeding northwards, 0·445, 0·402, and 0·346 inch.

West Greenland being thus on the west side of the region of high pressure which occupied the northern part of the Atlantic, and on the north-east side of the area of low pressure in the States and Canada, strong southerly winds set in over the country, and the temperature rose at the four Greenland stations proceeding from south to north to 1°·1, 8°·8, 12°·1, and 14°·4, above the averages. As the centre of lowest pressure was in the valley of the St. Lawrence about Montreal, strong northerly and westerly winds predominated to southward and westward, and there consequently the temperature was below the average, the deficiency at Chicago and St. Louis being 9°·5; and winds being easterly and northerly in California, temperature there was also under the average. On the other hand, in the New England States, the greater part of the Dominion of Canada, a considerable portion of British America, and in West Greenland, as already stated, temperature was above the average. Pressure was much higher at St. Michael's, Alaska, than it was to south-westward at St. Paul's, Behring Straits, and in connection therewith and with the prevailing winds, the temperature at St. Paul's was 2°·9 below the average, whereas at St. Michael's, where strong southerly winds prevailed, the temperature rose to 12°·0 about the normal. Hence whilst the continent of America presented striking contrasts in the distribution of pressure in December, 1878, it presented still more striking contrasts in the distribution of the temperature. Along Baffin's Bay the excess of the temperature above the normal was 14°·4, and at Behring Straits 12°·0, but in the south of Lake Michigan it was 9°·4 below it. In this last case the change of temperature from November to December was probably unprecedented, the mean for November having been 13°·7 above the average (NATURE, vol. xxii. p. 516), whilst the December temperature was 9°·5 below it, the difference being 23°·2!

Turning now to Europe, it is seen that Iceland lay on the east side of the patch of high pressure which overspread that region, northerly winds consequently prevailed, and with them a lowering of the temperature to 7°·2 below the average. The contrast this offers to West Greenland is very instructive. In both localities pressure was unusually high, but they occupied different positions, the one on the east and the other on the west of the same area of high pressure, with the inevitable result, of opposite prevailing winds, accompanied in the one case with a temperature 14°·4 above the average, and in the other 7°·2 below it. Hence as regards the temperature at the surface of the earth, it is not the height of the barometer which rules, but the situation of the locality with respect to areas of high and low pressure; or to put it more popularly, it is the winds which are chiefly concerned in the distribution of the temperature.

In Europe the area of lowest pressure occupied the southern shores of the North Sea, extending thence, though in a less pronounced form, to south-eastward. Hence over the whole of Western Europe winds were north-easterly, northerly, and in the south-west of Europe westerly; thus everywhere, from the North Cape to the north of Italy, temperature was below the normal, in some cases very greatly so, the deficiency being 10°·4 in the south of Norway, and 12°·2 in the south of Scotland. This is [the lowest monthly mean temperature known to have been recorded in Scotland since thermometric observations began to be made.

On the other hand, to the east of this area of low pressure, winds were southerly, and consequently temperatures were high. In some localities in Russia an excess of about 15°·0 occurred, and even over a large proportion

of European Russia the excess rose to 9°·0. This region of high temperature extended eastward into Siberia, as far as the Irtish, or to where the centre of the greatest excess of pressure prevailed. To the eastward of this area of highest pressure winds were northerly, and low temperature prevailed over the whole of the eastern part of Asia, the deficiency at Nertchinsk, on the Upper Amoor, being 6°·8 below the normal. Here, again, just as happened in America, places having the atmospheric pressure equally high above their average presented the strongest contrasts of temperature. Thus at Nertchinsk pressure was 0·154 inch, and at Bogoslovsk 0·211 inch above their respective averages; but at Bogoslovsk, on the west side of the anticyclonic patch of high pressure, temperature was 15°·0 above, whereas at Nertchinsk on the east side it was 6°·8 below the average.

This time of the year being the summer of the southern hemisphere, pressure falls to the annual minimum in Australia, but during December, 1878, this annual low pressure was still further diminished. Pressure at this season also falls to the annual minimum in the North Pacific and North Atlantic, and we have seen that the low pressure of these regions was likewise still further diminished. But in the case of the Atlantic it was accompanied with a vitally important difference. The centre of lowest pressure of the North Atlantic in winter, which is commonly located about Iceland, was removed many hundreds of miles to southward, and an unwonted development of extraordinarily high pressure appeared to northward, overspreading the extensive region of, at least, Baffin's Bay, Greenland, Iceland, Farö, and Shetland.

It was to this region of high pressure that the extreme severity of our British weather at the time was due. This high-pressure region was intimately connected with, and in all likelihood occasioned directly by the atmospheric movements resulting from the enormous extent of low pressure to southward, with its large centres of still lower pressures in the United States, mid-Atlantic, and the North Sea, where pressures were respectively 0·146 inch, 0·322 inch, and 0·307 inch below the normals. If future inquiry establish such a direct connection between the areas of low and high pressure, it is evident that when we come to attempt, on scientific grounds, to forecast the weather of the coming season for the British Islands, we must look to the Atlantic for the data on which the forecast is to be based.

In the winter months pressure rises to the annual maximum over Central Asia, and in America about the region of the Rocky Mountains. In December 1878, however, pressure rose in both regions greatly above its usually very high average, the excess being nearly a quarter of an inch in the valleys of the Yenisei, Obi, Irtish, and Tobal, about lat. 60°, and 0·200 in America in the Columbia Valley. It follows therefore that with the singular outstanding exception of the high-pressure area of Greenland, the meteorological peculiarities which make December, 1878, so memorable, arose out of a distribution of the earth's atmosphere, essentially the same that commonly obtains at this time of the year, but the usual irregularities in the distribution of the pressure appeared in more pronounced characters.

We have now had the pleasure, through the courtesy of the late General Myer, of presenting our readers with a series of Twelve of these unique Weather Maps, which open out a new future to meteorology. The map for December, 1878, closes the series which appears in NATURE. The questions which a perusal of these maps raises are of first importance, whether we consider the atmospheric changes they disclose, these being repeatedly so vast as to stretch across four continents at one time, besides being often profoundly interesting from their influence both on the food supplies and the commercial intercourse of nations; or the large problems hereby presented, with hints toward their solution, which underlie physical geography, climatology, and other branches of atmospheric physics. We have thus had shown us from month to month, in a way not hitherto possible, the great atmospheric changes as influenced by oceans and continents, including the important parts played in bringing about these changes, by mountain ranges, extensive plateaux, and physically well defined river basins. Much yet, however, remains to be done, principally by extending the network of observation in order that the Weather Maps may show, in an approximately adequate manner, the meteorology also of the North Pacific and the southern hemisphere. Till this be done many fundamental questions cannot be discussed, such as the inter-relations of the different continents and oceans of the globe in their bearings on successive meteorological changes; and the important inquiry as to whether the pressure of the earth's atmosphere be practically a constant from month to month, and, if not, what are the conditions or forces on which the observed differences depend. For the bringing of this great international work to so happy a consummation, we look with confidence to the War Department of the United States, since this implies no more than a continuance of the same energy and enlightened liberality that have won for the Americans their high position in meteorology.

SEARLES VALENTINE WOOD

PALÆONTOLOGY has sustained a severe loss in the death of the veteran explorer of the English Pliocene deposits. Born towards the close of the last century, the late Mr. Wood was from an early age an ardent collector and student of the fossils so abundantly found in the crag-pits of East Anglia. At this period the facilities for collecting the fossils of the English Pliocene strata were much greater than at present. Fresh pits for the purpose of obtaining the shelly marls and sands, which were then extensively used for manure, were continually being opened in the counties of Norfolk and Suffolk, while at the present time the new chemical manures have caused the crag to be quite neglected by agriculturists. The geologist who visits the Eastern Counties at the present day to study the Pliocene has to content himself with such exposures as he can find in old pits, now often overgrown with vegetation and which are used as sheepfolds or stackyards.

Mr. Searles Wood, as he himself said, was born within sight of one crag-pit; he resided for a great part of his life in the crag country, and hoped to be buried within sight of a crag-pit.

In the year 1839 Mr. Searles Wood joined the Geological Society of London. The following year was marked by the establishment of the London Clay Club by seven earnest students of fossils, of whom we believe only Prof. John Morris, formerly of University College, London, still survives. The object which the members of the London-Clay Club set before themselves was the figuring and describing of the British Tertiary fossils.

The London-Clay Club was the forerunner of, and became merged in, the Palæontographical Society of London. This Society has published between thirty and forty volumes, which have appeared annually, and has accomplished a most valuable work in the illustration of our British fossils.

At a very early date Mr. Searles Wood and his friend the late Mr. Frederick Edwards agreed to divide between them the work of describing the mollusca of the English Tertiary formations. The absence of marine Miocene formations in this country divides our British Tertiaries into two great groups, the Older Tertiaries, in which the great majority of the mollusca belong to extinct species

and the Newer Tertiaries, or crags, in which a large proportion of the forms belong to species still living in the seas of some portion of the globe. Mr. Searles Wood naturally chose the latter group for his study, and Mr. Edwards the former.

Upon the great task he had set before himself Mr. Searles Wood appears to have entered with characteristic energy, and in 1847 the Palæontographical Society was able to issue its first volume, which was entirely from the pen of Mr. Wood, and consisted of a description of the Crag Univalves, illustrated by twenty-one plates. In the years 1850, 1853, and 1855 Mr. Searles Wood was able to publish the parts of his descriptions of the Crag Bivalves, illustrated by thirty-one plates.

It soon became evident however that Mr. Edwards had taken upon his shoulders a lion's share of the work, and his friend Mr. Wood, having completed his own task, had to come to the aid of his fellow-student of the Tertiary fauna. It was then agreed that Edwards should complete his description of the Older Tertiary Univalves and that Wood should take up the description of the Bivalves. Between the years 1859 and 1877 Mr. Searles Wood published his descriptions of the Eocene Bivalves, illustrated by twenty-seven plates.

Additional discoveries of fossils having afforded Mr. Wood fresh materials, a supplement to the "Crag Mollusca" was published by him between the years 1871 and 1873. This work was illustrated by twelve plates, and included a very valuable memoir on the strata from which the fossils were obtained, written by his son, Mr. Searles V. Wood, jun., and Mr. Harmer of Norwich, who have both done so much good work in unravelling the complicated problems connected with the geology of East Anglia.

Nor did the zeal of Mr. Wood allow him to rest even here; for in 1877, in spite of his advanced age, we find him commencing a supplement to his own and Edwards's work on the Eocene mollusca.

In the year 1860 the Geological Society recognised the great services rendered to science by Mr. Searles Wood by presenting him with the blue-riband of geology, the Wollaston Medal. Prof. Phillips, who, as president of the year, handed the medal to Mr. Searles Wood, spoke in terms of well-merited praise of the important works which were the result of his patient, persevering, and successful labours.

Mr. Searles Wood and his friend Mr. Edwards were remarkable examples of a type of scientific man which, happily for us, is far more common in this country than in any other. They were both engaged in the legal profession, but found time in their leisure hours to accomplish most excellent and useful scientific work. In the volumes of the Palæontographical Society the work of amateurs like Searles Wood, Edwards, and Davidson appears side by side with that of Richard Owen, Edward Forbes, and John Phillips. The subscriptions of the members cover the cost of engraving and printing, but all other charges are defrayed by the authors, who expect and receive no kind of payment for their important labours.

The valuable collection of Tertiary fossils made by Edwards and Searles Wood have fortunately been secured by the authorities of the British Museum for our National Collection. They will in the New Natural History Museum at South Kensington be more accessible for study than at Bloomsbury, and as they contain great numbers of type specimens, will be invaluable for purposes of reference to both British and foreign palæontologists.

Mr. Searles Wood, as Treasurer of the Palæontographical Society, took the heartiest interest in its success, to which his own labours have to such a great extent contributed. Those who had the pleasure of a personal acquaintance with Mr. Searles Wood will ever remember the kindly and genial manners by which he was distinguished. J. W. J.

NOTES

THE following is the list of officers and council of the Royal Society nominated for the year ensuing. The election will take place as usual on St. Andrew's Day, November 30:—President — William Spottiswoode, M.A., D.C.L., LL.D.; Treasurer—John Evans, D.C.L., LL.D.; Secretaries—Prof. George Gabriel Stokes, M.A., D.C.L., LL.D.; Prof. Thomas Henry Huxley, LL.D.; Foreign Secretary—Prof. Alexander William Williamson, Ph.D.; other members of the Council—William Henry Barlow, Pres. Inst. C.E.; Rev. Prof. Thomas George Bonney, M.A.; George Busk, F.L.S.; Right Hon. Sir Richard Assheton Cross; Edwin Dunkin, V.P.R.A.S.; Alexander John Ellis, B.A.; Thomas Archer Hirst, Ph.D; William Huggins, D.C.L., LL.D.; Prof. John Marshall, F.R.C.S.; Prof. Daniel Oliver, F.L.S.; Prof. Alfred Newton, M.A., Pres. C.P.S.; Prof. William Odling, M.B., V.P.C.S.; Henry Tibbats Stainton, F.G.S.; Sir James Paget, D.C.L.; William Henry Perkin, Sec. C.S.; Lieut.-General Richard Strachey, R.E., C.S.I.

IT is proposed to erect a monument to Spallanzani in Scandiano, where the distinguished naturalist was born in 1729. A committee for the promotion of the scheme has been formed there, and at Reggio and Modena. A monument in marble is contemplated, more or less splendid according to the sum provided, and it will be inaugurated on August 21, 1885 (if circumstances do not allow of an earlier inauguration). The committee meanwhile propose (if practicable) to publish a new and accurate edition of the writings of Spallanzani, including some which have not hitherto appeared. Contributions are hoped for not only from Italians, but from foreigners generally among whom the work and principles of Spallanzani are honoured.

M. LEON HUMBLOT, a well-known *naturaliste-voyageur*, has just returned to Paris from Madagascar with large and valuable collections. Amongst the living specimens (destined for the Menagerie of the Jardin des Plantes) are two examples of the aye-aye (*Chiromys madagascariensis*), which, M. Humblot maintains, it is now more difficult to procure in Madagascar than in Europe; a pair of the rare carnivore *Cryptoprocta ferox*, and specimens of several of the smaller lemuroids. M. Humblot has also brought a valuable series of mammals and birds in skin and a large collection of orchids.

NO naturalist who visits Florence should omit to inspect the series of Italian vertebrates which has been brought together in the Reale Istituto degli Studii superiori, by the exertions of Prof. H. H. Giglioli. The collection embraces a series of authenticated specimens of mammals, birds, reptiles, batrachians, and fishes from every part of Italy and the adjoining districts which belong essentially to the same fauna, arranged in systematic order, and is far more complete than any other Italian collection of the same sort. Prof. Giglioli is preparing a catalogue of this collection as a basis for a new "Fauna Italica."

ON the 1st inst. a very fine Naval and Marine Engineering Exhibition was opened in the Corporation Galleries, Glasgow, altogether probably the finest exhibition of the kind we have had in this country. It is divided into five sections:—1. Naval architecture, including war vessels, sailing ships, paddle and screw steamers, yachts, dredges, and miscellaneous craft, boats and life-boats; (2) Marine engineering, including engines and parts of engines, boilers and boiler appliances, &c., governors; (3) Equipment, including anchors, boat-lowering apparatus, pumps and hydraulic machinery, steering-gear, telegraphs, windlasses, &c., machines and tools; (4) Navigation and harbour works; (5) Miscellaneous. The first section is of special interest, containing models of vessels of all ages and of all kinds, from

the *Henry Grace de Dieu* (A.D. 1514) down to the *Livadia*, many of these models having been lent by the Admiralty. Prefixed to the carefully compiled catalogue is a sketch of the rise and progress of steam navigation, more especially on the River Clyde, by Mr. W. J. Miller, C.E. The success of this exhibition is largely due to the energy and tact of the Curator of the Glasgow Industrial Museum, Mr. James Paton.

"THE Journal of the Indian Archipelago," founded and edited by the late J. R. Logan, which was published at Singapore, and ceased to appear some years since, has always been accepted by ethnologists as a valuable contribution to Malayan literature. Some of the early volumes, especially the first, have long been out of print, but Mr. David Logan, the son of the late editor, who was recently in England, has reprinted the scarce ones, thus enabling complete sets of the work to be obtained. Messrs. Trübner are, we believe, the agents in London.

THE very large and extensive entomological collection made by the late Jno. Miers, F.R.S., has been presented to the Ashmolean Museum at Oxford, and is now being studied and incorporated by Prof. Westwood. This collection is particularly rich in Brazilian insects, and thus becomes peculiarly valuable for the Oxford collection, which was, compared with other regions, poor in the neotropical fauna.

THE British Museum will shortly acquire the splendid collection of Heteromerous Coleoptera formed by Mr. Frederick Bates.

SOME unbelievers insisted that the submarine crannog described by Mr. Ussher at Ardmore, Co. Waterford, was only the remains of an old salmon weir; the late storms however seem to have set this theory at rest, as they have cut out the peat to seaward of the crannog and exposed the ancient kitchen midden, also additional piling not previously known.

AT the last meeting of the St. Petersburg Society of Naturalists Prof. Wagner exhibited the hydroids and medusæ of the White Sea he has brought home, giving a detailed description of ten species of medusæ he has discovered in that sea.

AT the last meeting of the St. Petersburg Horticultural Society M. Wolkenstein exhibited a new variety of vine which grows and fruits at Warsaw and Riga. M. Wolkenstein thinks it might fruit even at St. Petersburg. We notice also a communication by Prof. Regel on apples.

PROF. SILVANUS THOMPSON has an interesting article in the current number of *Brain* on "Optical Illusions of Motion."

WE learn from a paper published by M. Goulishambaroff in the *Journal* of the Russian Physical and Chemical Society, vol. xii. fasc. 5, that the whole of the naphtha region of the Apsheron Peninsula has an area of 4·3 square miles, which may be divided into two parts: that of Balakhany, which has given naphtha since the oldest times; and that of Sabountchi, which was explored only in 1873. The first part contains forty-seven naphtha-wells, of which only twenty-eight are productive, and yield together 6,192,000 lb. of naphtha daily. The density of this naphtha varies from 0·855 to 0·885, the average density being 0·8675; whilst the naphtha of the Sabountchi region has a density of from 0·820 to 0·860, and is extracted to an average quantity of 6,622,000 lb. The density varies from the most different causes: it varies in different wells, and usually it might be said that in the same bore the density diminishes with the depth; however, heavy naphtha is received also from very near to the surface; usually it becomes heavier when the evaporation of volatile gases is rendered easy by local circumstances. Contrary to established opinion, M. Goulishambaroff proves that the naphtha of the Apsheron Peninsula contains volatile products of a density of 0·62, but no use is made of them because of the imperfect means of purifying. The amount of photogene received varies very much, namely, from 15 to 85 per cent., the naphtha which has a density of 0·890 to 0·900 giving the lowest, and that of a density of 0·820 giving the highest, percentage; the most usual kinds of naphtha (density 0·863 to 0·870) usually give from 35 to 40 per cent. of photogene. It shows, he stated, however, that thorough measurements of the coefficient of dilatation of naphtha having not as yet been made, there remains a certain want of precision in the determinations of its specific weights.

ON the night of the 3rd inst. a magnificent display of aurora was seen from various parts of the country. We have received several communications on the subject. Mr. E. W. Prevost writes from Cirencester that the display was visible there from 6 p.m. up to about midnight. "The glow, which extended over an angle of about 100°, rose upwards to a height of 20°, leaving the central portion comparatively dark. Faint streamers occasionally showed themselves, reaching 35° in height. A shifting of the streamers from east to west was noticeable, the illuminated arc being at times extinguished on the eastern side, this extinction progressing slowly towards the centre of the arc, when the light would reappear at the eastern side. At no time, as far as I observed, did the light disappear on the western side; the colour was of a greenish-yellow and the wind due north." From Bootham, York, November 3, Mr. J. Edmund Clarke writes: "There is quite a brilliant aurora this evening, first noticed about 6.30 as a diffused light shifting from north-east to south-west, with occasional streamers. Now (7.30-8.45 p.m.) it forms a low bright arch of considerable intensity. I said 'first seen about 6.30,' but at 4.40 I called the attention of a friend to some sharply-defined red streamers in the north-east, which I then took to be sunlight. On August 12 last, about ½ to ¾ hour after sunset, my attention was called to streamers precisely similar, in every respect like those of the aurora. But careful observation showed that these were certainly radiating *from* the sun, and not converging *towards* the magnetic pole. It is certainly my impression that such was the case to-night, but being busy I did not take any special pains to ascertain. Of course this double coincidence may be a pure accident, but is it not possible that the minute substances reflecting the solar rays are actually modified by the electric field, so as to produce this remarkably distinct variety of rays? P.S.—8 p.m. Brilliant streamers from the bright arch, with some corruscations." Prof. Reilly, of the Royal College of Science for Ireland, writes that in Dublin the display was very fine. "The principal beam appeared as if slowly moving from west to east, and had a direction quite parallel to the pointers of the Great Bear. It reached at the time when seen quite up to the Polar Star. The lights were observed at earlier hours, one person having mentioned to me 6 o'clock p.m." In Orkney it showed itself as one of the most brilliant displays of aurora borealis seen for a long time. The whole northern horizon was one dark mass of clouds with a sharply-defined edge, and from these the aurora shot up in beautiful coloured streams to nearly the zenith, covering the clear sky above the clouds from north-east round to north-west. Occasionally the aurora took the form of a gigantic rainbow, and the light was as bright as moonlight.

A SMART shock of earthquake occurred on the 9th inst. throughout Southern Austria, from Vienna to the Adriatic and the frontiers of Bosnia. In the capital a rather violent shock was felt at a quarter to eight. Numerous telegrams have been received by the Meteorological Bureau at Vienna stating that shocks were felt at Serajevo, Derwenta, Brod, Pola, Trieste, Zilli, Klagenfurt, Fünfkirchen, Odenburg, Marburg, Laibach, and Gross-Kanischa. In Agram, the capital of Croatia, three shocks of earthquake occurred, a period of an hour intervening between the second

and third. One of them, which lasted ten seconds, was so powerful that not a single house remained uninjured. A general panic reigns in the town. Many of the inhabitants, including the Cardinal-Archbishop, have taken to flight. It is impossible to estimate the whole extent of the damage. The number of persons injured is at present estimated at thirty.

THE eruption of Vesuvius continues to increase in activity. Two large streams of lava are at present (November 8) flowing from the crater to the base of the cone.

IN Prof. Huxley's article on the *Challenger* Publications last week, line 11 from top of p. 2, col. 2, should read "*direct* and but little modified descendants," instead of "*dried*," &c.

OUR ASTRONOMICAL COLUMN

HARTWIG'S COMET (1880 *d*).—In a circular issued by Prof. Winnecke from the Observatory of Strasburg on the 1st inst., he gives reasons for assuming that the comet detected by Dr. Hartwig on September 29 may have a much shorter period than was conjectured in his first circular. On calculating parabolic elements from the Strasburg observations of September 29 and October 8, and one by Prof. Auwers at Berlin on October 17, MM. Ambronn and Wislicenus, students in the University of Strasburg, found the middle observation could not be more closely represented than with an error of something over two minutes of arc. Prof. Winnecke, as was stated in our previous notice, considered he had reason for suspecting the identity of Hartwig's comet with that of 1506, and a further examination of the historical descriptions has led him to direct attention to the comets of 1382, 1444, and 1569, and with the perihelion passage fixed to July 13, 1444, and October 15, 1569, he finds geocentric positions which he regards as in sufficient agreement with the records. A period of revolution of about 62½ years is therefore obtained, and an ellipse with this period has been adapted by Dr. Schur and Dr. Hartwig to the observations on September 29 and October 14 and 24. The resulting elements are as follow :—

Perihelion Passage, 1880, September 6·58949 M.T. at Berlin.

Longitude of perihelion	83 33 28	M. Eq. 1880·0.
,, ascending node ...	44 33 30	
Inclination	38 8 56	
Log. excentricity	9·990180	
Log. semi-axis major	1·196457	
Log. mean diurnal motion	1·755321	

The error of the place deduced from this ellipse on October 14 is + 28″ in longitude and the same in latitude, and it is remarked that the error in longitude does not admit of being destroyed without an increase of error in latitude. This, however, Prof. Winnecke suggests, may arise from the assumed period of 62½ years being really a multiple of the true one. The comet approaches near to the orbit of Mercury at the ascending node, though at the present time not sufficiently close to occasion any change in the character of the orbit. Still at some past epoch the effect of perturbation may have brought the orbits into coincidence or nearly so, and Prof. Winnecke hints that the planet Mercury might have been the means of impressing an elliptical form on the comet's orbit.

It is clearly a case in which those observers who are in the possession of very powerful instruments may render most material service towards deciding whether we have to do with a comet of comparatively short period. If it is practicable to secure good observations for position after the next period of moonlight, it may then be possible to obtain evidence *pro* or *con*, by direct computation of the orbit, though unfortunately observations did not commence until the comet had reached the extremity of the parameter, or in other words had attained an angular distance of 90° past the perihelion point.

DISCOVERY OF A COMET.—Lord Lindsay notifies the discovery of a comet at his observatory, Dunecht, during the night of the 7th inst., by Mr. Lohse in the constellation Lacerta ; the position at 15h. 30m. in R.A. 22h. 45m. 54s., Declination 42° 33′·7 ; daily motion in R.A. + 6m. 58s., in Decl. + 1° 8′. This is far from any position which the expected comet of 1812 could occupy on the above date.

CERASKI'S VARIABLE STAR.—Mr. Knott obtained a very complete observation of the descending and ascending light-curve of this newly-detected variable on November 2 ; the minimum appears to have occurred about 11h. G.M.T. The period will be somewhat less than 2½ days.

PHYSICAL NOTES

PROF. LORENZ has given in *Wied. Ann.*, No. 9, a development of his theory of "refraction-constants" (published before in Danish), and described experiments bearing on it. The problem contemplated was to find that function of the refractive index, freed from dispersion, and of the density of a body, which is constant with varying density of the body, supposing the molecules themselves unchanged. It is assumed that bodies consist of molecules in whose intervals light is propagated with the same velocity as in vacuous space ; further, that the bodies are isotropic, and their molecules of spherical form. Herr Lorenz arrives at a simple expression for the refraction-constant, the constancy of which, as also the correctness of the assumption as to light moving with the same velocity in the intervals of molecules as in vacuo, had to be proved. He determined the refraction constants of several bodies in the liquid and the vaporous states, viz., ethylic ether, ethylic alcohol, water, chloroform, ethylic iodide, ethylic acetate, and sulphide of carbon. The refraction was determined with sodium and lithium light, and at temperatures of 10°, 20°, and 100°. He found that in passage of the substances from the liquid to the vaporous state the refraction-constant varies very little (only about 5 per cent. at most). Dispersion also showed great constancy. Another Danish physicist, K. Prytz, has extended the inquiry to some ten other substances (*loc. cit.*), and confirmed the assumption of refraction constants.

WITH regard to electricity, Herr Hoorweg (*Wied. Ann.*, No. 9) divides all bodies into two groups, (*a*) those in which the conductivity rises with the temperature (dielectrics), and (*b*) those in which it decreases with rise of temperature (adielectrics). He endeavours to prove by experiment (1) that both dielectric bodies with adielectric, and adelectric with each other, yield contact electricity ; (2) that this electricity has always the same sign as that which arises with gentle friction or pressure. (The sometimes different action of strong friction is ascribed to the influence of the raising of temperature.) Not only does electricity arise through the different heat-motion at the places of contact of two heterogeneous substances, but this cause is fully sufficient to explain all development of electricity.

HERR NARR has lately obtained some interesting results in experimenting further on the behaviour of electricity in gases, and especially *in vacuo* (*Wied. Ann.*, No. 9). In the middle of a hollow brass sphere on a glass support was suspended a metallic ball by means of a platinum wire passing (insulated) through a metallic stopper to an electrometer. Vacua could be produced in the sphere. A charge of electricity imparted to the conducting system underwent the same process of dispersion *in vacuo* as where the space was full of gas. The outer surface of the hollow sphere, one minute and also one hour after the charging, had the same electricity as the conducting system. Herr Narr further finds that the process of dispersion in gas-filled space is not perceptibly influenced by the hollow sphere being insulated or being connected to earth, if the original charging be done while the sphere is connected to earth ; the dispersion constant diminishes in both cases, at least at the beginning. But if the conducting system be charged while the hollow sphere is insulated, the latter has in this state one minute, and likewise one hour to one hour and a half after, electricity of the same sign with the conducting system, and the first connection of the hollow sphere to earth occasions a temporary outflow. Herr Narr shows reasons for believing that the electricity on the hollow sphere finds its way through the gas-space.

A NEW series of experiments of extended range, by Herr Roth, on the compressibility of gases, is described in *Wied. Ann.*, No. 9. The relations between pressure, volume, and temperature, in the case of carbonic acid, sulphuric acid, ammonia, and ethylene, are studied. The results are mainly confirmatory of van der Waal's formulæ.

A NEW balance designed to be easily transportable, light, and yet stable, without fixing to the table, and to serve in inspection of widely various weights (by Government officials in Hungary), was lately brought before the Buda-Pesth Academy by Herr von Krasper (see *Wied. Beibl.* No. 9, p. 638). Among other features,

the prism-shaped steel bed, on which the middle knife-edge rests, is easily drawn out with the finger from the swallow-tail shaped rollers between which it is passed in the body of the balance. The beam can thus be easily removed and replaced. The balance rests on four feet. The stopping and raising arrangement is contained in a horizontal frame. Each weighing scale hangs on a conical point. Passing on to the reading, we find that the accuracy with which the balance works is, with 20 kg. weight, 2mg., with 500, 3½ mg.; and this is gained by substituting for the pointer an optical arrangement on the beam, consisting of two achromatic glass prisms, which render parallel the rays from opposite directions and send them to a telescope placed before the balance. At the two sides of the balance, about 2m. to 4m. from the middle knife-edge, two scales are set (best on the walls of the room); the images of these scales move in the field of the telescope beside each other in opposite directions, and so the corresponding divisions can be read off. These readings are independent of vibrations of the telescope, and are much more exact than those with telescope and cross threads, not to speak of the common pointer. The arrangement also permits of the centre of gravity of the balance being placed lower, the stability increased, &c. The weight of the balance is scarcely 20 kg., though both scales can carry 20 kg. weight.

EXPERIMENTS by Forbes in 1831 and by some others since seemed to warrant the view, now commonly held, that the metals fall into the same series as regards conduction of electricity and conduction of heat, that the quotient of the heat conductivity by electric conductivity is nearly constant. Herr H. F. Weber, inclined to doubt this as contradicting the view (proved for gases and liquids) that the amount of heat transferred within a substance from layer to layer is most intimately connected with the specific heat of unit volume, made new experiments in this relation (which he has described to the Berlin Academy). He measured the heat-conduction by observing the cooling of various metal rings in a space at constant temperature, and the electric conducting power of the same rings, by noting their deadening effect on the oscillations of a magnet. The result confirmed his anticipations, the quotient of heat-conduction by electric conduction being found in the closest connection with the specific heat of unit volume. Experiments by a different electrical method for metals conducting electricity badly (lead, bismuth, &c.) and for mercury gave the same result. (Ten metals in all were examined.) On the other hand, non-metallic conductors of electricity do not show the relation in question; *e.g.* the heat-conduction of carbon is at least twenty to thirty times greater than that calculated from the electric conductivity and the specific heat. Thus the relation seems to be connected with the metallic nature of the substance. Herr Weber found the heat-conducting power of all the solid metals examined to decrease with increasing temperature, but at a considerably less rate than the electric conductivity. He further offers explanations of the erroneous view adopted, noting, *inter alia*, that the experiments in one case, though exact, were on too few metals, and these had nearly the same specific heat.

PROF. R. B. WARDER of Haverford College (Pennsylvania) and Mr. W. P. Shipley have investigated the configurations assumed by floating magnets in a magnetic fluid. They have modified Prof. Mayer's original experiment by surrounding the vessel of water with a coil of wire traversed by a current, thus producing a field of force which, while still symmetrical about the centre, differs in several respects, the lines of force not being so greatly concentrated near the centre. Diagrams of various configurations are given by these experimenters in the *American Journal of Science* for October. As even a single one-fluid cell produces a current sufficient to show these results, they ought to be easy of repetition.

A COMPREHENSIVE memoir on the theory of the radiometer, by M. Mees, appears in the *Proceedings* of the Amsterdam Academy, and (in pretty full abstract) in *Wied. Beibl.*, No. 7. The author, after criticising the various theories that have been enumerated, which he arranges in three classes, offers his own explanation of the phenomena (which cannot be briefly stated here).

A FEW months ago we drew attention to certain results published by Herr Exner of Vienna, relative to thermoelectricity, and which were at variance with all the body of evidence existing in that branch of science. Herr Exner had in fact asserted that an antimony-bismuth couple possesses thermoelectric powers only so long as one of the two metals is in contact with oxygen or with a gas capable of acting on one of them. The wish we then expressed that some independent observations might be made by other physicists has met with a response across the Atlantic. Prof. C. A. Young of Princeton, N.J., communicated to the recent meeting of the American Association a paper on the thermoelectric power of a platinum-iron couple *in vacuo*. The crucial experiment was made with an exhausted glass tube containing an iron wire with platinum terminals, the terminals being again fastened to iron wires leading to a galvanometer. The tube was exhausted to one-millionth of an atmosphere. On laying the apparatus in the sunlight and alternately shading the internal or external junctions an electromotive force could be produced, which was found to be equal in every case. The conclusion Prof. Young draws from the experiment is that Exner is wrong in his statement that thermoelectric electromotive force is due to the action of the gaseous media in which the metals are plunged. The experiment was conducted in Mr. Edison's laboratory at Menlo Park.

GEOGRAPHICAL NOTES

THE glacier of the Zarafshan, one of the greatest in Central Asia, which has hitherto been very imperfectly known, was explored during this summer by MM. Mushketoff, geologist, and Ivanoff. The exploration was quite successful, and at the last meeting, October 26, of the Mineralogical Society at St. Petersburg, Prof. Mushketoff read a paper on his explorations. The lower extremity of the glacier is at the height of 9000 feet. The Galtcha people, who inhabit the upper valley of the Zarafshan, have never ascended the glacier; they say that on the summit of it there are two great pillars of stone, between which the traveller must go, and that the pillars would certainly crush together if any one ventured into the icy solitude. On August 25 the party began the ascent of the glacier on a very steep slope covered with blocks and moraines. A tunnel, no less than 3500 feet long, runs under the glacier, being the bed of the Macha River. After two days' travel the party had done seven miles on the glacier. The temperature during the day was as high as 40° Cels., and during the night as low as − 8°; some Galtchas who accompanied the party fell ill with fever. On the fourth day the party reached the first watershed, or rather the first iceshed; the whole length of the glacier to this point was sixteen miles, the width being one mile; six other glaciers, each of which is greater than the greatest Alpine glaciers, fed the principal one. At the head of it there is a wide *cirque* opening to the east; several peaks around it reach 20,000 feet. The descent on the other slope of the mountain ridge was far more steep and difficult than the ascent; the crevasses are very numerous and the glacier has several great "ice-falls," the inclination of which is no less than 50 degrees; the party was compelled to make use of small anchors and to cut steps in the ice. Two men were unwell and quite unable to go further when the party reached the foot of the eastern slope, after a very difficult journey.

THE last number of the *Izvestya* of the Russian Geographical Society contains a letter from Dr. Miklukho-Maclay. After having visited the islands of New Caledonia, Lifu, New Hebrides, Admiralty, Louisiade, &c., he reached, about the end of January, 1880, the south-eastern coast of New Guinea; here he explored several points of the coast, and thence went to the islands of the Torres Strait and to Somerset, to study the population of Northern Australia. On his voyage from Vaihan Island to Sydney he stopped at several points of the eastern coast. From Sydney M. Maclay proposes to go to Japan, and thence to return to Russia. During his stay in Brisbane he was very kindly received by the local government and by private persons, who have much facilitated his anatomical studies by allowing him to work in the old museum and to make use of the photography of the topographical department. The journey in the interior of Queensland was very much facilitated by the cordial reception he received from the squatters, and by the kind permission to travel gratuitously along all the railways. M. Maclay expresses, in a letter addressed to the *Golos*, his thanks to the Australians for the reception he met from them, and wishes that all men of science were so kindly received in Russia. On August 12 he was in the house of J. B. Bell at Jimbor, near Dallby. The Russian public subscription has already reached 606*l.* which he received at Sydney.

A GOOD example is being set by the Tashkent College. During the summer fourteen pupils of the College, under the

direction of their Professor of Natural History, M. Shelting, made an excursion in the Ala-taou Mountains. Numerous measurements of heights were made during the journey, good zoological, botanical, and geological collections, for the Museum of the College, were made, and a detailed diary of the excursion was kept by the scholars. The students of the Tashkent Normal School, as well as the pupils of the College of Verny, have also made scientific journeys for the exploration of the neighbourhood, and we learn that the College of Orenburg has requested tickets at reduced rates from the railway company for undertaking next summer a series of explorations in that little known but very interesting province. We cannot but wish that the colleges and schools of Western Europe would follow these examples; what an excellent training in natural science might thus be given, and what a mass of valuable information might be collected.

THE members of the scientific expedition which was sent out by the St. Petersburg and Moscow Societies of Naturalists for the exploration of the White Sea and of the Murmanian coast of the Arctic Ocean, and which consisted of Professors Wagner, Bogdanoff, Tsenkovsky, and eight students of the University, have returned after having done some very successful work; they bring home very rich zoological and geological collections. Professors Wagner and Tsenkovsky stayed throughout the summer at the Solovetsky Islands; M. Lavroff in Kandalaksha Bay; Prof. Bogdanoff travelled along the whole coast to Vadsö; MM. Koudravtreff and Pleske, geologists, have travelled from Kandalaksha to Kola; others have explored the flora and the fauna of the ocean; Prof. Bogdanoff has also studied the fishing.

BARON A. VON HUGEL is now engaged in writing a work upon Fiji, where he travelled and spent some time, making extremely extensive and complete anthropological collections. The work will be more particularly an ethnological one, and most of the weapons, fabrics, and other ethnographic articles are being figured to accompany the text. The crania collected by Baron von Hugel have already been acquired by the Royal College of Surgeons, and exhaustively described by Prof. Flower.

WE notice the appearance of an important work published by the Russian Geographical and Economical Societies in the first volume of a "Collection of Materials for the Knowledge of the Russian Commune." It contains detailed descriptions of the communes of the Governments Ryazan, by M. Semenoff, president of the Russian Geographical Society, MM. Litochenko, Zlatovratsky, Mme. Yakouchkin, &c.; a very complete bibliographical index of the literature concerning the communes of Russia and of Western Europe.

A TELEGRAM has been received at St. Petersburg from Col. Prejevalsky, dated from Urga, the 1st inst., stating that during the spring and summer of this year he surveyed a part of the basin of the Upper Hoang-ho and the Lake Koko Nor. He also passed through Alashan, in the centre of the Gobi desert, to Urga. Col. Prejevalsky states that during the expedition he traversed a distance of 7200 versts, and that he has succeeded in obtaining valuable scientific results.

THE death is announced, on his passage home from West Africa, of Count de Semellé, who has been recently exploring on the Lower Niger.

THE new *Bulletin* of the Société Khédiviale de Géographie contains a paper by General Purdy-Pacha on the country between Dara and Henfiah El Nabass, together with a map of that portion of Darfur, and another on Medina twenty years ago, by Col. Mohamed Sadik-Bey, illustrated by two engravings.

THE Church Missionary Society have received news that the Rev. P. O'Flaherty, their new agent in Uganda, and Mr. C. Stokes, with the Waganda chiefs and a large caravan, started from Saadaui for the interior on August 9, but in little more than three weeks Mr. O'Flaherty was taken ill at Kidete, and will be unable to proceed to the Victoria Nyanza at present.

THE same Society have also received letters from various members of the Nyanza mission, giving a much more favourable report of their position in Uganda than had reached England some time back. Rev. G. Litchfield had in consequence of ill-health made an attempt to push northwards to Lado, in order to consult Dr. Emin Effendi. In this he unfortunately failed, being stopped by Kabba Rega, the king of Unporo, who has seized M'ruli and other posts vacated by the Egyptians since Col. Gordon's departure. Mr. Litchfield accordingly returned to Rubaga, and, crossing the lake, proceeded to Upui, hoping eventually to get to Upwapwa, where Dr. Baxter is stationed.

MESSRS. CAMERON AND PIGOTT, of the China Inland Mission, have made a journey of eight months through a great part of Manchuria and a portion of Mongolia. From the treaty port of Newchwang Mr. Pigott went on to Moukden, while Mr. Cameron proceeded along the coast in an easterly direction by the borders of Corea, and then northwards to Moukden. They next journeyed through part of Mongolia into Kirin, which at first they found fertile and well-wooded, but afterwards the country became wild, poor, and sparsely populated. The city of Kirin was reached by a long steep descent through fine scenery. Fine teams of oxen were here met with, comparing favourably with some of our best breeds. After spending a few days at Kirin the two missionaries returned overland to Peking, passing the Great Wall at Shan-hai-kwan or Ling-yü-hsien.

MESSRS. RILEY AND CLARKE, of the same Society's station at Chungking, have recently paid a visit to some Lolo villages in Southern Szechuen. These mountaineers for the most part live in inaccessible fastnesses beyond the reach of the Chinese authorities, and are not confined to Szechuen and Yünnan, but under the designations of Laos and sundry other names are found throughout the extensive regions of Annam, Siam, and Burmah. Hardly anything is yet known of the Chinese Lolos and their manners and customs, but before long the agents of the China Inland Mission in the south-west will, it may be hoped, find means to collect information regarding them.

ON A DISTURBING INFINITY IN LORD RAYLEIGH'S SOLUTION FOR WAVES IN A PLANE VORTEX STRATUM[1]

LORD RAYLEIGH'S solution involves a formula equivalent to $\frac{d^2v}{dy^2} - \left(m^2 + \frac{\frac{d^2T}{dy^2}}{T - \frac{n}{m}} \right) v = 0.$

Where v denotes the maximum value of the y-component of velocity;

" m " a constant such that $\frac{2\pi}{m}$ is the wave-length;

" T " the translational velocity of the vortex-stratum when undisturbed, which is in the x-direction, and is a function of y;

" n " the vibrational speed, or a constant such that $\frac{2\pi}{n}$ is the period.

Now a vortex stratum is stable, if on one side it is bounded by a fixed plane, and if the vorticity (or value of $\frac{dT}{dy}$) diminishes as we travel (ideally) from this plane, except in places (if any) where it is constant.

To fulfil this condition, suppose a fixed bounding plane to contain ox and be perpendicular to oy; and let $\frac{dT}{dy}$ have its greatest value when $y = o$, and decrease continuously, or by one or more abrupt changes, from this value, to zero at $y = a$ and for all greater values of y.

It is easily proved that the wave-velocity, whatever be the wave-length, is intermediate between the greatest and least values of T. Hence for a certain value of y between o and a, the translational velocity is equal to the wave-velocity, or $T = \frac{n}{m}$. Hence for this value of y the second term within the bracket in Lord Rayleigh's formula is infinite unless, for the same value of y, $\frac{d^2T}{dy^2}$ vanishes.

We evade entirely the consideration of this infinity if we take only the case of a layer of constant vorticity ($\frac{dT}{dy}$ = constant from $y = o$ to $y = a$), as for this case the formula is simply

$$\frac{d^2v}{dy^2} = m^2 v,$$

[1] By Sir William Thomson. British Association, Swansea, Section A.

but the interpretation of the infinity which occurs in the more comprehensive formula suggests an examination of the stream-lines by which its interpretation becomes obvious, and which proves that even in the case of constant vorticity the motion has a startlingly peculiar character at the place where the translational velocity is equal to the wave velocity. This peculiarity is represented by the annexed diagram, which is most easily understood



if we imagine the translational velocities at $y = 0$ and $y = a$ to be in opposite directions, and of such magnitude that the wave velocity is zero; so that we have the case of standing waves. For this case the stream-lines are as represented in the annexed diagram, in which the region of translational velocity greater than wave-propagational velocity is separated from the region of translational velocity less than wave propagational velocity by a cat's-eye border pattern of elliptic whirls.

MINERAL RESOURCES OF NEWFOUNDLAND

ORES of copper have been found in all the older formations in Newfoundland, from the Laurentian gneiss at the base, to the Carboniferous series at the summit, the qualities of which vary greatly with the age and condition of the rocks with which they are associated. Thus in the Laurentian series the rich ores of variegated and sometimes grey sulphide of copper are more frequent than any other, and are for the most part in white quartz veins intersecting the strata; but while these ores have in many cases been found on analysis to yield at the rate of from 50 to 70 per cent. of metal, the quantities available at any one place hitherto tested have never yet been found sufficient to warrant an outlay of capital.

In the succeeding series, which I conceive to be the equivalent of the *Huronian* of *Canada*, and have provisionally called *intermediate*, as being intermediately situated between rocks of the Laurentian and Primordial Silurian ages, very rich ores of copper are likewise well known at many parts, chiefly in white quartz veins, and also in faults and dislocations, particularly near the junction with the fossiliferous Primordial, in which cases the indications may sometimes be regarded as favourable for the probable future development of mines. Several attempts have already been made in this direction at various parts of the distribution of the series, but except at a few places, chiefly near the junction with the newer formations, with but slender prospect of a successful issue.

By reference to the Custom House returns of exports I find that the amount and value of copper ore shipped at St. John's between the years 1854 and 1864 inclusive was as follows:—Ore, 627½ tons, value $22,980=4,596l. sterling. The places where this ore was raised are not specified, but I believe it was all derived from rocks of intermediate age, by which the greater part of the Peninsula of Avalon is occupied.

In addition to the above export from St. John's, 544 tons, valued at $19,179 were exported between the years 1875 and 1879; but a considerable, if not the larger portion of this ore was produced from Tilt Cove and other of the early openings in Notre Dame Bay.

Although the presence of copper is frequently indicated by stains of green carbonate and small nests of yellow sulphuret in the lower Primordial strata, I am not aware of any instances where the ores occur in mass, or in intersecting veins or lodes, except it may be close to their immediate junction with the older series on which they repose unconformably or butt up against in faults. At some parts of their distribution, such as in the islands of Conception Bay, these older Silurian rocks are but very little disturbed, resting in nearly a horizontal attitude, and scarcely at all altered; at other parts, such as Trinity Bay, St. Mary's Bay, Langlois Island of the Miquelons and elsewhere, they are greatly disturbed by intrusions of igneous rock, and occasionally to some extent metamorphosed; but they are almost everywhere crowded with organic remains, the types of which indicate the ages they represent, to extend from the horizon of Primordial or Cambrian to the newer Potsdam Group of the United States and Canada. Strata representative of Potsdam, Calciferous, and Levis ages, containing abundance of typical fossils, are extensively displayed on the western and northern parts of the island, the former in many cases resting directly on Laurentian gneiss unconformably; but, except it may be to a very limited extent in Canada Bay, near the Cloud Mountains, I am not aware of any deposits older than the Potsdam at these parts, nor have I seen indications of the presence of the Huronian or intermediate system north of Bonavista Bay, or anywhere near the western shores. Galena in calcareous veins is of frequent occurrence in these Lower Silurian rocks, but except in small isolated crystals or patches the ores of copper are particularly rare, and in no case such as to be considered economically valuable.

But the cupriferous formations proper of Newfoundland, according to my view of the structure, lie unconformably above all the former, and consist mainly of a set of metamorphic and igneous rocks, corresponding exactly in mineral character and condition with the rocks of the Eastern Townships of Canada described by Sir Wm. Logan under the title of the Quebec Group. I am quite aware that these views, as regards the structure, are at variance with those entertained by several distinguished geologists in Canada (whose opinions, however, do not seem to be very unanimous on the subject); and there cannot be a doubt that in many cases the evidences appear to be so contradictory at different localities that the difficulties in arriving at the truth are exceedingly great. Nevertheless, so far as my own observations go, and I have studied the succession at nearly all parts of their distribution in Newfoundland, I am led to the conclusion that the stratigraphical position of this metamorphic group belongs to a horizon intermediate between the Calciferous and Hudson River group, probably chiefly of Chazy age, which is in accord with the structure of Sir W. E. Logan.

The group consists of chloritic, dioritic, and felsite slates, interstratified with compact diorites, bands of red jasper, dolomites, great masses of serpentine, or serpentinous rock, and volcanic products. In nearly all these rocks the ores of copper are more or less disseminated; but it is amongst the schistose portions, especially the clorite slates, that they seem to be most abundant, and it is in rocks of that quality chiefly where the principal mining operations have hitherto been conducted. At some parts of the distribution these rocks are distinctly stratified, the lines of deposit being well displayed in layers of different quality: beds of jasper, conglomerate, &c. The whole series is magnesian, more or less, but particularly towards the top, which appears to be the horizon of the serpentinous masses, with large accumulations of volcanic ash. Towards the base the rocks become calcareous, the cliffs of strata much incrusted with carbonate of lime; and some strata of a pure white crystalline limestone occur which are fossiliferous. The fossils are too obscure to be identified with certainty; but one form bears a strong resemblance to a *Maclurea*, another to a *Bellerophon*, a third to a *Murchisonia*, and some rather large-sized *Encrinite* stems. Near the horizon of this limestone moreover we find a set of black slates which contain graptolites. Vast intrusive masses of granitoid rock, and great dykes of greenstone melaphyre and other traps intersect the formation.

The only mines of importance in active operation up to the present time are all situated in Notre Dame Bay, and these are Union Mine Tilt Cove, Betts Cove Mine, Colchester, in south-west arm of Green Bay, Little Bay Mine, Rabbit's Arm, and Seal Bay. Many openings and minor workings have also been made at various parts of the bay, at each of which the ores of copper were more or less indicated, some of which may eventually, when capital and skilled labour are brought to bear, be found sufficiently remunerative to be worked to advantage.

It will be seen by the annexed memoranda that the total value of the copper and nickel ore extracted since 1854, but by far the larger proportion since 1864, when the Union Mine Tilt Cove was first opened by Mr. Smith McKay, amounts to nearly one million sterling.

Memoranda showing the Quantities and Values of Copper and Nickel Ores exported from the Island of Newfoundland in the undermentioned Years

Years.	Parts cleared from.	Copper.	Nickel.	Value.	Value of nickel ore.
		Tons.	Tons.	Dollars.	Dollars.
1854 to 1864	St. John's	627½[1]		22,980	
1875 to 1879	,,	544½[2]		19,179	
	Total St. John's ...	1,172		42,159	
1869	Union Mine Tilt Cove	5,938	30	190,016	7,200
1870	,,	4,218	88	134,976	8,800
1871	,,	1,924	7	61,568	700
1872	,,	4,774[3]	8	152,768	25,60
1873	,,	5,414	233	189,490	9,320
1874	,,	4,346	—	104,304	—
1875	,,	4,838	17	179,006	1,360
1876	,,	6,464	28	232,704	2,800
1877	,,	5,389	—	194,004	—
1878	,,	4,450	—	97,966	—
1879	,,	1,964	—	35,352	—
	Total Tilt Cove ...	49,719	411	1,572,154	32,740
1875	Bett's Cove	6,280		232,360	
1876	,,	18,670		456,481	
1877	,,	42,065		1,093,768	
1878	,,	31,370		690,140	
1878	Regulus	750		34,500	
1879	,,	26,421½		475,587	
	Total Bett's Cove ...	125,556½		2,982,836	

The ores returned for 1878-79 were largely derived from Little Bay Mine and partly from Colchester, all belonging to the Bett's Cove Mining Company.

Thus the total value of the ores of copper and nickel exported since 1854 amounts to $4,629,889, or nearly £1,000,000 sterling.

ALEX. MURRAY

UNIVERSITY AND EDUCATIONAL INTELLIGENCE

CAMBRIDGE.—In Groups C and E of the Higher Local Examination this year there were respectively fifty-four and ninety-nine candidates; five obtained a first class in Group C (Mathematics) and eight a first class in Group E (Natural Science); nine candidates failed in Group C, and twenty-six failed in Group E. Three candidates answered the questions in Differential and Integral Calculus, and showed considerable knowledge. In botany a fair average of proficiency was attained; in geology the papers were below the average. In zoology inferior text-books had been too much preferred, to the exclusion very largely of practical work. The work in chemistry was unequal, but some candidates showed a very good acquaintance with the details of manipulation. Physics can scarcely be said as yet to be studied by the candidates. In physiology the answers were in some cases accurate and to the point, but the majority of candidates failed.

The elections to the Council of the Senate were made on Monday, and show in a very practical manner that residents are in favour of considerable improvement in University matters. Only one member who approves of the retention of Greek as a universal subject in the "Little-go" was elected, viz., Mr. G. F. Browne, whose place in the Council is due to his active work in connection with the University Local Examinations and his knowledge of the intentions of the University Commissioners, as one of their secretaries.

[1] Chiefly from Huronian rocks.
[2] Partly from openings in Notre Dame Bay.
[3] Cloanthite and Millarite.

Dr. Phear, Professors Cayley and Liveing, and Mr. Peile, are among those who were elected to the Council well known for their scientific eminence and breadth of view.

Prof. Stokes, Lord Rayleigh, and Mr. Vines were added to the Council of the Philosophical Society at its annual meeting.

Mr. Forbes, Prosector to the Zoological Society, has been elected to a Fellowship at St. John's College.

AT an examination held on Wednesday, October 27th ult., Mr. M. Milburn, of Longtoun, was elected to a vacant bursary in connection with the "Young" Chair of Technical Chemistry, Anderson's College, Glasgow. The bursary, which is of the value of 50*l.*, and tenable for three years, is the gift of Mr. James Young, LL.D., F.R.S., of Kelly and Dullis, founder of the Chair.

SCIENTIFIC SERIALS

Journal de Physique, October.—Experimental verification by S. Carnot, of the principle he discovered, by M. Lippmann.—Apparatus and experiments for elementary demonstration in optics, by M. Gariel.—Influence of velocity of propagation of sound in the shock of elastic bodies, by M. Elie.—New form of plates for air .pumps, by M. Terquem.—*Proceedings* of the Physical Society of St. Petersburg (including papers, in abstract, on the chemical and photographic action of light, the transmission of the current in water with unequal platina electrodes, variations of volume and coefficient of elasticity of palladium and its alloys under the influence of absorbed hydrogen, &c.).

Rivista Scientifico-Industriale, No. 18, September 30.—On the relation between terrestrial storms and the planetary relations of the solar system, by Prof. Zenger.—Excursions (geological) in the neighbourhood of Modica, by Prof. Lancetta.—Palæontological studies in Bohemia, by Prof. Fritsch.—Beats, the third sound of Tartini, and the differential resultant sounds of Helmholtz, by Dr. Crotti.

No. 19, October 15.—New registering pluviometer, by S. Grimaldi.—New apparatus with petroleum heating, by S. Esser.—On a new variety (Rosterite) of Elban beryl, by Prof. Grattarola.

Kosmos, July 1880, contains a translation of Prof. Huxley's "The Coming of Age of the Origin of Species" (*vide* NATURE, vol. xxii. p. 1).—Dr. Ernst Krause's sketch of the developmental history of the History of Development.—Dr. H. Müller, the importance of Alpine flowers in connection with the "flower theory."—H. Schneider, observations on some apes.—Prof. Dr. Caspary, the conception of a soul and its significance in connection with modern psychology.—Short contributions and extracts from journals (among the short articles is one on the resemblance between flowers and fruit, by Hermann Müller, and on the occurrence of a five-toed example of *Archibuteo lagopus*, by W. von Reichenau).

August, 1880.—Dr. Oscar Schmidt, the severance of species and natural selection.—Dr. Ernst Kranse, sketch of the developmental history of the History of Development, No 2.—Dr. Herman Müller, on the development of the colours of flowers.—Prof. A. H. Sayce, on the history of writing (translation).—Short contributions and extracts from journals.—Literature and critical notices.

Revue des Sciences Naturelles, September.—M. Mathias Duval, on the development of the spermatozoa in the frog (plates 3 and 4).—M. Lavocat, on the construction of the extremities of the limbs.—Dr. A. Godron, on the absence of a glume in the lateral spikelets of Lolium.—M. Leymerie, sketch of the Pyrenees of the Aude.—Notices of French memoirs on zoology, botany, and geology.—Bibliography and notice of the death of Dr. A. Godron.

SOCIETIES AND ACADEMIES

LONDON

Chemical Society, November 4.—Prof. H. E. Roscoe in the chair.—The following papers were read:—On the compounds of vanadium and sulphur, by E. W. E. Kay. The author shows that the products obtained by Berzelius are oxy-compounds, that the substance obtained by Berzelius in the dry way is a true trisulphide of vanadium V_2S_3; the disulphide and pentasulphide have also been prepared and are described in the present paper.—On the atmospheric oxidation of phosphorus and some reactions of ozone and peroxide of hydrogen, by C. T. Kingzett. The author concludes that in the above oxidation both ozone and peroxide of hydrogen are formed, the former

passes on in the current of air, the latter remains in the water in which the phosphorus is oxidised. In several experiments the proportion of peroxide of hydrogen to the ozone formed was as 1 to 2.—On the action of zinc ethyl on benzoylic cyanide, by E. Frankland and D. A. Louis. The product of this reaction, an amber-coloured jelly, was first decomposed and then extracted with alcohol, about 3 per cent. of a substance $C_{34}H_{19}NO_8$, named provisionally benzcyanidin, crystallising in colourless needles, was obtained. Besides this body an unstable substance was obtained which could not be purified, but which on oxidation with bichromate gave propiophenone $C_9H_{10}O$. —On the action of zinc-ethyl on cyanogen, by E. Frankland and C. C. Graham. The product of this reaction was a solid mass, which on heating to 120° yielded a colourless liquid which was propionitrile C_3H_5N., the other product of the reaction being zinc cyanide.—On bismuth and bismuth compounds, by M. M. P. Muir, G. B. Hoffmeister, and C. E. Robbs. The relative stabilities towards heat and reducing agents of the oxides, and towards heat of the hydrates are discussed, also the action of chlorine and bromine on the oxides. An attempt is made to give structural formulæ for these bodies, in which bismuth is trivalent.—On the colour-properties and relations of the metals copper, nickel, cobalt, iron, manganese, and chromium, by T. Bayley. The author has carefully compared the colours of solutions of salts of the above metals and various mixtures thereof, and especially those mixtures which yield colourless or neutral grey solutions.—Action of diazo-naphthalin on salicylic acid, by Percy Frankland.—On the basic sulphates of iron, by Spencer Pickering.—Fourth report on researches in chemical dynamics, by C. R. A. Wright, E. H. Rennie, and A. E. Menke.—On some naphthalin derivatives, by C. E. Armstrong and N. C. Graham.—On acetylorthoamidobenzoic acid, by P. P. Bedson and A. J. King.

VIENNA

Imperial Academy of Sciences, October 21.—On the propagation of ball and cylinder waves of finite width of vibration, by Dr. Tumlirz.—On the law of convulsive action (continued), by Prof. Stricker.—On the blood vessels of the valves of the heart, by Dr. Langer.—On the question of arrangement in the pyridin and chinolin series, by Dr. Skraup.—Experiments on the magnetic behaviour of iron, by Herr Haubner.—On the relation of the daily and yearly variation of temperature to the sun spot period, by Herr Liznar.

PARIS

Academy of Sciences, November 2.—M. Edm. Becquerel in the chair.—The following papers were read :—New observations on the etiology and prevention of *charbon*, by M. Pasteur. He gives a letter written by Baron von Seebach (Saxon Minister in Paris) to M. Tissandier in 1865, stating facts which afford striking confirmation of M. Pasteur's views as to the causes of the disease.—On the heat of formation of ethers formed by hydracids, by M. Berthelot. In these experiments he used his calorimetric detonator.—Heat of formation of sulphide of carbon, by M. Berthelot. The combustion of liquid sulphide of carbon liberates +246·6 cal. (Favre and Silbermann obtained 258·5 cal., but they overlooked the formation of sulphuric acid). Sulphide of carbon is formed with absorption of heat from its solid elements, but there is probably liberation of heat from gaseous sulphur and carbon.—On volcanic thunderstorms, by M. Faye. In paroxysmal eruptions the enormous amount of steam ejected causes volcanic thunderstorms, which are quite distinct from ordinary thunderstorms, especially in the absence of gyratory movements, the complete immobility of the volcanic storm (which is confined to the column of ascending clouds), and the fact that no flashes occur without the presence of ashes. The phenomena are very much those of the Armstrong electric machine. Further, there is never any mention of hail; and M. Faye thinks it is probably never produced, as it is the product of vast gyratory movements not found in volcanic clouds. He suggests the desirability of studying directly the traces of electricity in the vapours rising from the crater of Vesuvius.—On photographs of nebulæ, by M. Janssen. The photography of a very bright nebula is now comparatively easy, if one content oneself with the most luminous part, but extremely difficult if a complete image be sought comparable to those given by our large instruments. The latter is what we especially require, with a view to studying the important questions of variations of nebular structure, and calls for many able workers, furnished with the best instruments. M. Janssen is preparing observations of the kind at Meudon.—Observations of planets and comets, at Marseilles Observatory, by M. Stephan.—On the winter-egg of phylloxera, by M. Valery-Mayet. It seems certain that the hygrometric state of the air, generally very dry in Languedoc (where the author is), is the great obstacle to production of the winter egg. Whenever the sea-winds, which always blow in autumn, bring that region to the conditions of the climate in the west, the egg is produced.—Elements of the orbit of the new planet (217) discovered by M. Coggia.—On the resolution of algebraic equations; examination of the method of Lagrange, by M. West.—On linear differential equations with rational coefficients, the solution of which depends on the quadrature of a rational function of the independent variable, and of an irrational algebraic product, by M. Dillner.—On a property of uniform functions of a variable connected by an algebraic relation, by M. Picard.—On the application of the photophone to study of the sounds which occur on the sun's surface, by Prof. Bell. This was suggested by Mr. Bell in visiting the observatory at Meudon. M. Janssen put all the instruments at his disposal, and an opportunity was taken to explore a solar image 0·65 m. in diameter with the selenium cylinder. The phenomena were not sufficiently marked to justify one in affirming success, but Mr. Bell is hopeful of succeeding. M. Janssen has suggested the method of passing rapidly before an objective which should give conjugate images on the selenium apparatus, a series of solar photographs of one spot taken at intervals sufficient to show notable variations in the constitution of the spot. This is to be tried.—On the oxidation of mannite, by M. Pabst.—On the ferments of albuminoid matters, by M. Duclaux. There are certainly over a hundred species, and of these he only knows twenty at present (the physiological conditions, *i.e.* of their existence). Previous classifications prove useless. He gives some general *traits*. *Inter alia*, in milk the ferments change the caseine into soluble albumen, but while the aerobian ferments do this in a slow and regular way, the anaerobians do it with liberation of carbonic acid and hydrogen, part of which becomes sulphuretted hydrogen or even phosphides of hydrogen. In cheese-making the predominance of the aerobians has been unconsciously favoured. All the ferments studied are found in full activity in the stomach. They secrete soluble ferments, which are added to those of the organism.—Inoculation of symptomatic *charbon* by intravenous injection, and immunity conferred on the calf, the sheep, and the goat by this process, by MM. Arloing, Cornevin, and Thomas.

CONTENTS

	PAGE
DR. SIEMENS' NEW CURE FOR SMOKE. By Dr. C. WILLIAM SIEMENS F.R.S. (*With Illustration*)	25
THE RUSSIAN IMPERIAL YACHT "LIVADIA"	27
A MEDICAL CATALOGUE	28
THE PHILOSOPHY OF LANGUAGE. By A. H. KEANE	30
OUR BOOK SHELF :—	
Martineau's "Easy Lessons in Science"	32
Molloy's "Outline of a Course of Natural Philosophy, with Specimen Examination Papers"	32
LETTERS TO THE EDITOR :—	
Sir Wyville Thomson and Natural Selection.—CHARLES DARWIN, F.R.S.	32
Geological Changes of Level.—Sir C. WYVILLE THOMSON, F.R.S.	33
"The first Volume of the Publications of the *Challenger*"—A Correction.—Prof. T. H. HUXLEY, F.R.S.	33
Correspondence of Phenomena in Magnetic Storms.—WILLIAM ELLIS	33
Meteor.—Rev. S. J. PERRY, F.R.S.	34
Condition of Jupiter.—J. RAND CAPRON	34
Vox Angelica.—GEORGE RAYLEIGH VICARS	34
Solids and Liquids at High Temperatures.—JOHN AITKEN	34
Wire Torsion.—Professors JOHN PERRY and W. E. AYRTON	35
Heat of Formation of a Compound.—A. P. LAURIE	35
The Yang-tse, the Yellow River, and the Pei-ho.—Surgeon H. B. GUPPY	35
The Thresher.—FRANCIS P. PASCOE	35
ILLUSTRATIONS OF NEW OR RARE ANIMALS IN THE ZOOLOGICAL SOCIETY'S LIVING COLLECTION, I. (*With Illustrations*)	35
A SUCCESSFUL AFRICAN EXPEDITION	38
UNITED STATES WEATHER MAPS, DECEMBER, 1878	39
SEARLES VALENTINE WOOD	40
NOTES	41
OUR ASTRONOMICAL COLUMN :—	
Hartwig's Comet (1880 *d*)	43
Discovery of a Comet	43
Ceraski's Variable Star	43
PHYSICAL NOTES	43
GEOGRAPHICAL NOTES	44
ON A DISTURBING INFINITY IN LORD RAYLEIGH'S SOLUTION FOR WAVES IN A PLANE VORTEX STRATUM. By Sir WILLIAM THOMSON (*With Diagram*)	45
MINERAL RESOURCES OF NEWFOUNDLAND. By ALEX. MURRAY	46
UNIVERSITY AND EDUCATIONAL INTELLIGENCE	47
SCIENTIFIC SERIALS	47
SOCIETIES AND ACADEMIES	47

SUBSCRIPTIONS TO NATURE

Yearly . . . . . 28*s.*
Half-yearly . . . . . 14*s.* 6*d.*
Quarterly . . . . . 7*s.* 6*d.*

To the Colonies, United States, the Continent, and all places within the Postal Union :—

Yearly . . . . . 30*s.* 6*d.*
Half-yearly . . . . . 15*s.* 6*d.*
Quarterly . . . . . 8*s.*

Office: 29, Bedford Street, Strand.

DIARY OF SOCIETIES.

LONDON

THURSDAY, NOVEMBER 11.

MATHEMATICAL SOCIETY, at 8.—Considerations respecting the Translation of Series of Observations into Continuous Formulæ: The President.—On Bicircular Quartics, with a Triple and a Double Focus and Three Single Foci, all of them Collinear: H. M. Jeffery, F.R.S.—Further Remarks on the Geometrical Method of Reversion: Rev. C. Taylor.

FRIDAY, NOVEMBER 12.

ROYAL ASTRONOMICAL SOCIETY, at 8.

QUEKETT MICROSCOPICAL CLUB, at 8.

SATURDAY, NOVEMBER 13.

PHYSICAL SOCIETY, at 3.—On the Beats of Mistuned Consonances of the Form $A : 1$: R. H. M. Bosanquet.—Note on Prof. Exner's Paper on Contact Electricity: Professors Ayrton and Perry.—On Action at a Distance: Walter R. Browne.—Thermodynamic Relations of the Thermal and Ergonal Constituents of Heat in Liquids and Gases: J. M. F. Gray.

TUESDAY, NOVEMBER 16.

ZOOLOGICAL SOCIETY, at 8.30.—Report on the Additions made to the Society's Menagerie during the Months of June, July, August, and September, 1880: The Secretary.—On the Structure and Development of the Skull of the Urodeles: W. K. Parker, F.R.S.—On the Palæarctic and Æthiopian Species of Bufo: G. A. Boulenger. Communicated by Dr. A. Günther.

STATISTICAL SOCIETY, at 7.45.

HORTICULTURAL SOCIETY, at 1.—Scientific Committee.

WEDNESDAY, NOVEMBER 17.

SOCIETY OF ARTS, at 8.

GEOLOGICAL SOCIETY, at 8.—On Abnormal Geological Deposits in the Bristol District: Charles Moore.—Interglacial Deposits of West Cumberland and North Lancashire: J. B. Kendall.

METEOROLOGICAL SOCIETY, at 7.—Table of Relative Humidity: Edward E. Dymond.—Rainfall in South Africa: John G. Gamble, M.A.—The Meteorology of Mackay, Queensland: Henry L. Roth.—Thermometrical Observations on board Ship: Capt. W. F. Caborne.

CROYDON NATURAL HISTORY CLUB, at 8.

THURSDAY, NOVEMBER 18.

ROYAL SOCIETY, at 4.30.—On the Essential Properties and Chemical Character of Beryllium: L. F. Nilson and Otto Pettersen.—On the Molecular Heat and Volume of the Rare Earths and their Sulphates: L. F. Nilson and Otto Pettersen.—On the Absorption Spectra of Cobalt Salts: Dr. W. J. Russell, F.R.S.—On the Friction of Water against Solid Surfaces of different Degrees of Roughness: Prof. W. C. Unwin.

Next week, crown 8vo, with upwards of 100 Illustrations, cloth gilt, gilt edges. 6*s.*

LIFE AND HER CHILDREN:

Glimpses of Animal Life from the Amœba to the Insects.

By ARABELLA B. BUCKLEY,

Authoress of "The Fairy-land of Science," "A Short History of Natural Science," "Botanical Tables for the Use of Junior Students."

EXTRACT FROM PREFACE.

"The main object is to acquaint young people with the structure and habits of the lower forms of life; and to do this in a more systematic way than is usual in ordinary works on natural history, and more simply than in text-books on zoology. For this reason I have adopted the title 'Life and Her Children' to express the family bond uniting all living things, as we use the term 'Nature and her Works' to embrace all organic and inorganic phenomena; and I have been more careful to sketch in bold outline the leading features of each division than to dwell upon the minor differences by which it is separated into groups. I have made use of British examples in illustration wherever it was possible, and small specimens of most of the marine animals figured may be found upon our coasts at low tide."

CONTENTS:

I. Life and her Children.
II. Life's Simplest Children: How they Live, and Move, and Build.
III. How Sponges Live.
IV. The Lasso-throwers of the Ponds and Oceans.
V. How Starfish Walk and Sea-Urchins Grow.
VI. The Mantle-covered Animals and How they Live with Heads and without them.
VII. The Outcasts of Animal Life: and the Elastic-ringed Animals by Sea and by Land.
VIII. The Mailed Warriors of the Sea, with ringed bodies and jointed feet.
IX. The Snare-Weavers and their Hunting Relations.
X. Insect Suckers and Biters, which change their coats but not their bodies.
XI. Insect Gnawers and Sippers, which remodel their bodies within their coats.
XII. Intelligent Insects with helpless Children, as illustrated by the Ants.

Uniform in size and price with

THE FAIRYLAND OF SCIENCE.

By the same Authoress.

London: EDWARD STANFORD, 55, Charing Cross, S.W.

LIGHTNING CONDUCTORS.

Experience, accumulated since the time of Benjamin Franklin, proves conclusively that a Conductor made of Copper of adequate size is the best of all appliances for the protection of every description of building from the destructive effects of lightning.

NEWALL & CO.'S
PATENT COPPER LIGHTNING CONDUCTOR,

As applied to all kinds of Buildings and Shipping in all parts of the world with unvarying success, is the most Reliable, most Effective, and Cheapest Conductor ever offered to the public.

It is simple in its application, no insulators being required, and it costs only one shilling per foot for the standard size, which is safe in any storm.

R. S. NEWALL & CO., 130, STRAND, W.C.
36, WATERLOO ROAD, LIVERPOOL.
68, ANDERSTON QUAY, GLASGOW.
MANUFACTORY—GATESHEAD-ON-TYNE.

ASTRONOMICAL TELESCOPE.

BATEMAN'S

WONDERFUL £5 5*s.* INSTRUMENT

Is the finest ever yet attempted. 3-inch Achromatic Object Lenses. Entirely constructed of polished brass; total length, 4 feet 10 inches; very highly finished with Altitude and Azimuth Movements, Rackwork, fine Adjustment, one Terrestrial and one Huyghenian Astronomical Eyepiece; will show Jupiter's Belts, Crescent Form of Venus, resolve many Nebulæ and Clusters, and divide many Double Stars, &c., &c. Prospectus post free.

J. BATEMAN,

29, CHEAPSIDE; 104, STRAND; ROYAL POLYTECHNIC, 309, REGENT STREET, AND 131, HIGH HOLBORN, LONDON.

FLETCHER'S PERFECTED SOLID FLAME GAS COOKING AND HEATING BURNER.

[PATENT, 3,203.]

The only perfect Burner for Cooking, Boiling, and Dirty Laboratory Work. Free from Smell, the most powerful Burner known, and not damaged by the roughest dirtiest work. This Burner is a valuable improvement on Fletcher's well-known Solid Flame Burner, of which Thousands are in daily use. The Gauze is done away with and replaced by a Loose Perforated Dome of Solid Copper, which can be taken off and Cleaned when Choked with Dirt. The Stand is Broad and Firm, supporting Large or Small Vessels safely and steadily.



PRICE, Japanned, 6*s.* 6*d.*; Nickel-Plated, 8*s.* 6*d.*

A SMALLER SIZE IN PREPARATION.

ORIGINAL SOLID FLAME BURNER.

PRICE, with Gauze, 4*s.*; or Nickel-Plated, 5*s.*

These Burners are the same power, and will with equal ease boil an Egg, cook a Chop, boil a Kettle, or melt half a hundredweight of Lead in an Iron Pot. They will boil half a gallon of Water in a Flat Copper Kettle in Six Minutes, and work equally well with Air, Gas, or Coal-Gas.

Complete Illustrated List, Price 3*d.*, of Gas Furnaces for Crucibles, Muffles, Ladles, Porcelain Painting, &c.; Hot and Cold Blast Blowpipes; Foot, Hand, and Automatic Blowers, Ingot Moulds, &c.; with Reprint of Mr. Fletcher's Lecture to the Society of Arts *On the Application of Gaseous Fuel to Laboratory Work*, for which he was awarded the Society's Silver Medal in June, 1880.

THOS. FLETCHER,

4 & 6, *MUSEUM STREET, WARRINGTON.*

Scientific Series of Optical Lantern Slides.

THE series of Scientific Subjects which Mr. F. YORK has the honour of introducing to the notice of the public has been prepared to meet a long-felt want of a good and reliable series of photographic transparencies for illustrating Scientific Lectures. The rapid extension of Science teaching under the South Kensington Science and Art Department, and the ever-growing demand for popular Scientific Lectures, have long made a good series of illustrations a desideratum. The interest taken by the public in the Electric Light, and in such modern inventions as the Telephone and the Phonograph, has increased the call for well-illustrated Scientific Lectures; and for these there has existed, until the present time, no means of adequate illustration by the Magic Lantern.

The series now offered to the public, and to Scientific Lecturers in particular, comprises over Two Thousand Slides, and other series are in active preparation. Those already completed are:—

ELECTRICITY AND MAGNETISM. SOUND. THE TELEPHONE, MICROPHONE, &C.
THE ELECTRIC LIGHT, AND OTHER RECENT INVENTIONS. LIGHT, INCLUDING SPECTRUM ANALYSIS. HUMAN PHYSIOLOGY.
ASTRONOMY. MINES AND MINERS. HEAT. MECHANICS, HYDROSTATICS, AND PNEUMATICS. NEW INVENTIONS.

A course of Slides illustrating Chemistry, and others in Geology, Physiography, and Biology, will shortly be announced. Particular care has been taken to include in the series such subjects as Science-teachers will find of use; pictures of large or expensive apparatus; the application of Science to the Arts; and pictures of important events in the history of Science, drawn from the most reliable sources. By permission of the publishers, many of the best diagrams from the most important treatises, such as those of Tyndall, Ganot, and Roscoe, are included in the series, which will, on this account, possess a special value. No effort will be spared to make the series complete as new inventions and scientific discoveries occur.

In order to render these scientific subjects available during the dark evenings, in the schoolroom or the institute, where no scientific lecturer may be at hand, a series of popular Science Readings for the Lantern has been edited by Professor Silvanus Thompson, of University College, Bristol, which can be undertaken by any person accustomed to the now familiar style of Lantern Readings published by F. YORK. The following is a list of Science Readings for the Magic Lantern:—

ELECTRICITY AND MAGNETISM (in Three Parts). THE TELEPHONE, MICROPHONE, AND PHONOGRAPH.
THE ELECTRIC LIGHT, AND OTHER RECENT INVENTIONS. WAVES OF SOUND. HUMAN PHYSIOLOGY.

In Preparation.

RAYS OF LIGHT. MARVELS OF THE SKY.
SPECTRUM ANALYSIS, AND WHAT IT TELLS US ABOUT THE SUN AND STARS. HEAT AND COLD. FROST, ICE, AND SNOW.

The size is the usual English gauge 3¼ inches square, and the price 18*s.* per dozen. A Sample and Catalogue sent on receipt of 2*s.*

F. YORK, OPTICAL LANTERN SLIDE MANUFACTURER,
87, LANCASTER ROAD, NOTTING HILL, LONDON, W.

S. C. TISLEY & Co.,
OPTICIANS,
172, BROMPTON ROAD, S.W.
(Close to South Kensington Museum).

THE PHONEIDOSCOPE

An Instrument for Observing the Colour-Figures of Liquid Films under the action of Sonorous Vibrations.

Being a visible demonstration of the Vibratory and Molecular Motion of a Telephone Plate.

The PHONEIDOSCOPE, with 3 Discs, Bottle of Solution, Descriptive Pamphlet, &c., in Cardboard Box, 10*s.* 6*d.*

MANUFACTURED AND SOLD WHOLESALE AND RETAIL BY
S. C. TISLEY & CO., 172, BROMPTON ROAD, LONDON, S.W.

TELEPHONIC ELECTRICITY. All Materials supplied for experimental purposes.

Price Lists of Electrical and Acoustic Apparatus, with Drawings and Description of the Harmonograph, Post Free, 2d.

NOW READY,
SECOND EDITION,
GRIFFIN'S
CHEMICAL HANDICRAFT.

PRICE 4*s.* 7*d.* POST FREE.

A CATALOGUE OF CHEMICAL APPARATUS:
ILLUSTRATED, CLASSIFIED, DESCRIPTIVE.
Demy 8vo, 480 pp., Illustrated with 1,600 Woodcuts.
Most Complete and Cheapest List of Apparatus.
JOHN J. GRIFFIN AND SONS, 22, GARRICK STREET, LONDON, W.C.

HOLLOWAY'S PILLS

THIS MEDICINE

Is a Certain Cure for all Disorders of the LIVER, STOMACH AND BOWELS. A Great PURIFIER of the BLOOD; a Powerful Invigorator of the System, in cases of WEAKNESS AND DEBILITY, and is unequalled in Female Complaints

---

NOTICE OF REMOVAL.
JAMES HOW & CO.,
SCIENTIFIC INSTRUMENT MAKERS,
73, FARRINGDON ST., LONDON
(LATE OF 5, ST. BRIDE ST., AND 2, FOSTER LANE).

HOW'S STUDENT'S MICROSCOPE. HOW'S MICROSCOPE LAMP.

Rock Sections and other Objects for the Microscope.

DOLLOND,
1, Ludgate Hill, St. Paul's Churchyard.
ESTABLISHED 1750.
Manufacturer of Astronomical and Terrestrial
TELESCOPES.

THE "EDUCATIONAL" ASTRONOMICAL TELESCOPE,
With 3-inch clear aperture. Complete, £7 17*s.* 6*d.*

N.B.—These Telescopes have been introduced to meet the wants of those wishing to purchase Instruments of excellent quality optically, while the exterior is sound and good, without the cost of high finish.

The New Short-length Mercurial Barometer and Thermometer combined, price 15*s.*, particulars of which will be sent post free on application.

THIN GLASS FOR MICROSCOPIC MOUNTING, of best quality. Circles, 3*s.* 6*d.* per ounce: Squares, 2*s.* 9*d.*; post free 2*d.* extra; Ground edged Slips, 5*s.* per gross: also other Mounting Materials and Objects prepared for mounting.—CHAS. PETIT, 151, High Street, Stoke Newington, N.

FRY'S COCOA

GOLD MEDAL,
PARIS EXHIBITION.
In Packets and Tins. Pure Cocoa only, with the superfluous oil extracted.

"If properly prepared, there is no nicer or more wholesome preparation of cocoa."—*Food, Water, and Air, edited by Dr. Hassall.*

EXTRACT

J. S. FRY & SONS, Bristol and London.

Messrs. MACMILLAN & CO.'S PUBLICATIONS.

ETCHING AND ETCHERS. By P. G. HAMERTON. New Edition, Revised, with 48 New Plates. Columbier 8vo. £5 5*s.*

The text of the new Edition has been thoroughly revised, and increased by one-fifth. Several new Chapters and a new Preface have been added, whilst matter which had become unnecessary or disproportionate has been removed, to make room for studies of more importance. [*Immediately.*

LIFE OF WILLIAM BLAKE. With Selections from his Poems and other Writings. By ALEXANDER GILCHRIST. A New and Enlarged Edition, Illustrated from BLAKE'S own Works, with Additional Letters and a Memoir of the Author. 2 vols. Medium 8vo. [*Immediately.*

ISLAND LIFE; or, the Phenomena of Insular Faunas and Floras, with their Causes, including an entire revision of the Problem of Geological Climates. By ALFRED RUSSEL WALLACE, Author of "The Malay Archipelago," "The Geographical Distribution of Animals," &c. Medium 8vo, with Illustrations and Maps. 18*s.*

"The work throughout abounds with interest."—*Athenæum.*

"'Island Life' is a work to be accepted without reservation from beginning to end. . . . Whoever reads his book must be charmed with it."—*St. James's Gazette.*

A VISIT TO WAZAN, THE SACRED CITY of MOROCCO. By ROBERT SPENCE WATSON. 8vo, with Map and Illustrations. 10*s.* 6*d.*

"Mr. Watson's account of his experiences in Morocco is much more pleasant than that of any other traveller's we know of . . . . and as a record of an independent and unprejudiced observer his little book, slight as it is, is of value."—*Times.*

IDEAL CHEMISTRY. By Sir BENJAMIN BRODIE, Bart., F.R.S. Crown 8vo. 2*s.*

GOETHE'S FAUST. Translated into English Verse, with Notes and Preliminary Remarks, by JOHN STUART BLACKIE, F.R.S.E., Professor of Greek in the University of Edinburgh. Second Edition, carefully revised and largely rewritten. Crown 8vo. 9*s.*

ETIENNE DOLET: the Martyr of the Renaissance. A Biography, with a Bibliographical Appendix, containing a descriptive catalogue of the books written, edited, or printed by Dolet. By R. C CHRISTIE, M.A., Lincoln College, Oxford, Chancellor of the Diocese of Manchester. With Illustrations 8vo. 18*s.*

"Mr Christie's book may be cited as, in many respects, a model biography."—*Athenæum.*

"He draws portraits of persecutors from the life, worthy of the art of Rabelais and Bunyan."—*St. James's Gazette.*

STUDIES IN DEDUCTIVE LOGIC. By W. STANLEY JEVONS, LL.D., F.R.S., Professor of Political Economy in University College, London. Crown 8vo. 6*s.*

GUIDE TO THE STUDY OF POLITICAL ECONOMY. By Dr. LUIGI COSSA. Professor of Political Economy in the University of Pavia. Translated from the Second Italian Edition. With a Preface by W. STANLEY JEVONS, F.R.S. Crown 8vo. 4*s.* 6*d.*

THE IRISH LAND LAW. By ALEXANDER G. RICHEY, Q.C., LL.D., Deputy Regius Professor of Feudal and English Law in the University of Dublin. Crown 8vo. [*Immediately.*

With Twenty-five Illustrations by WALTER CRANE.

THE NECKLACE OF PRINCESS FIORIMONDE: and other Stories. By MARY DE MORGAN. Extra fcap. 8vo. 6*s.*

ALSO AN EDITION, Printed by Messrs. R. and R. Clark, on hand-made paper. The Plates, initial letters, head and tail pieces being printed on India paper and mounted in the text.

The Edition is limited to ONE HUNDRED COPIES. Fcap. 4to.

ENGLISH MEN OF LETTERS. Edited by JOHN MORLEY. Crown 8vo. 2*s.* 6*d.*

LOCKE. By Professor FOWLER. New Volume.

New Book by the Author of "The Tapestry Room," &c.

A CHRISTMAS CHILD: a Sketch of a Boy-life. By MRS. MOLESWORTH, Author of "Carrots," "The Cuckoo Clock," &c. Illustrated by WALTER CRANE. Globe 8vo. 4*s.* 6*d.*

New Book by the Author of "When I was a Little Girl," &c.

PANSIE'S FLOUR BIN. By the Author of "St. Olave's," &c. Illustrated by ADRIAN STOKES. Globe 8vo. 4*s.* 6*d.*

ESSAYS ON ART AND ARCHÆOLOGY. By C. T. NEWTON, C.B., LL.D., Keeper of Greek and Roman Antiquities at the British Museum. 8vo. 12*s.* 6*d.*

"Mr. Newton deserves the gratitude of all Students of Archæology, for these masterly Essays. . . . . are the fruit of a lifetime of exhaustive scholarship, and of such individual research as it seldom falls to the lot of any archæologist to accomplish."—*Westminster Review.*

MODERN GREECE: Two Lectures delivered before the Philosophical Institution of Edinburgh, with Papers on "The Progress of Greece," and "Byron in Greece." By R. C. JEBB, M.A., LL.D., Professor of Greek in the University of Glasgow. Crown 8vo. 5*s.*

"Modern Greece needs but few words of recommendation to those interested in one of the most urgent and important questions of the day . . . . . We have to add an expression of our hope that the book, which is both scholarly and popular, will obtain all the success which it certainly deserves."—*Westminster Review.*

CICERO'S LIFE AND LETTERS. Being a Translation of the Letters in Mr. WATSON'S Selection, with Historical and Critical Notes, by the Rev. G. E. JEANS, M.A. 8vo. 10*s.* 6*d.*

"The style . . . . is life-like, and shows literary power, nor is it superfluous to add that it is for the most part really English and idiomatic."—*Academy.*

"Mr. Jeans' translation deserves to take its place side by side with Davies and Vaughan's 'Republic,' and Church and Brodribb's 'Tacitus.'"—*St. James's Gazette.*

HISTORY OF THE ENGLISH PEOPLE. By JOHN RICHARD GREEN. Vol. IV. THE REVOLUTION, 1683—1760. MODERN ENGLAND, 1760—1815. 8vo, with 3 Maps and Index, 16*s.* (Vols. I. to III. 16*s.* each.) [*Concluding Volume.*

"A work that most students of history may turn to with advantage, and that will be almost sure to take rank among the great classics of our literature."—*Globe.*

READINGS FROM ENGLISH HISTORY. Selected and Edited by JOHN RICHARD GREEN. In Three Parts, each 1*s.* 6*d.*

"We cannot imagine a better reading-book for the highest standard of our elementary schools, but it is a book which will have great charms also for the most cultivated readers."—*Guardian.*

XENOPHON'S ANABASIS. Books I.—IV. Edited by Professors W. W. GOODWIN and J. W. WHITE, of Harvard University. Fcap 8vo. 5*s.* [Macmillan's Classical Series.

LIVY.—SCENES FROM THE HANNIBALIAN WAR. Adapted for the use of Beginners by G. C. MACAULAY, M.A., Assistant-Master at Rugby. Post 8vo. 1*s.* 6*d.* [Macmillan's Elementary Classics.

THE STORY OF ACHILLES, FROM HOMER'S ILIAD. Edited, with Notes and Introduction, by J. H. PRATT, M.A., Fellow of Trinity College, Cambridge, Assistant Master at Harrow; and WALTER LEAF, M.A., Fellow of Trinity College, Cambridge. Fcap. 8vo. 6*s.* [Macmillan's Classical Series.

MACMILLAN AND CO., LONDON.

Cassell, Petter, Galpin & Co.'s Announcements.

SIR GAVAN DUFFY'S NEW BOOK.

YOUNG IRELAND. By THE HON. SIR CHARLES GAVAN DUFFY. Price 21*s.*

NOTICE.—The FIRST LARGE EDITION of this book having been exhausted on the day of publication, a SECOND EDITION is being rapidly prepared, and will be ready in a few days.

"Whatever may be the shortcomings of Sir Charles Gavan Duffy's book, and we frankly concede we have not found any, it has, at all events, the advantage of being written by one who knows more about the subject of which he treats than any living man. . . . We can heartily commend Sir Charles Gavan Duffy's book to our readers as combining the narration of weighty and important historical facts with the pleasing touches and happily distracting incidents of a charming tale."—*Morning Post.*

Now ready, Vols. I. and II. Price 7*s.* 6*d.* each.

OUR OWN COUNTRY. Each containing about 200 Original Illustrations and Steel Frontispiece.

The *Times* of October 21, 1880, says:—"The beautiful work which Messrs. Cassell and Co. are publishing under the above title appeals to a very wide circle of readers. The treatment is full and comprehensive, embracing architecture, scenery, history, and antiquities, industry and art, physical geography, and natural history. The work is creditable to author, draughtsman, and engraver."

Complete in five magnificent volumes, royal 4to, cloth, 2*l.* 2*s.* each; half morocco, 3*l.* 3*s.* each; or in morocco, 5*l.* 5*s.* each.

PICTURESQUE EUROPE. With 65 exquisite Steel Plates from Original Drawings and nearly 1000 Original Illustrations by the best Artists. With Descriptive Letterpress.

"Nothing on so grand a scale has been planned before, nor anything, so far as we know, so well executed. . . . The more we study the five superb volumes in which Messrs. Cassell, Petter, Galpin, and Co. have collected a rich and varied series of pen and pencil illustrations of the picturesque scenery and buildings of Europe, the more are we impressed with the high quality of the literary as well as the artistic contents of the whole work—a single volume, indeed, of the set constitutes a charming and valuable gift."—*Spectator.*

JUST PUBLISHED, price 9*s.*

SCIENCE FOR ALL YEARLY VOLUME FOR 1880.

Edited by **Dr. Robert Brown, M.A., F.L.S.** Assisted by Eminent Scientific Writers. With about **350 Illustrations** and **Diagrams.**

The Athenæum of October 30, 1880, *says:*—

"Whatever branch of science a man may happen to be studying, he is sure to find something to his taste in turning over the pages of this work. Not to go beyond the volume which has just been issued, the astronomer will find articles on Mars, on Jupiter, and on comets; the meteorologist will learn something about clouds and dew, snow and hail, thunder and lightning; the physicist may carry on his studies in electricity and in sound; the zoologist will feel at home with corals and starfishes, butterflies and cockroaches, cuttlefishes, snails, and frogs; the botanist at one time listens to the lessons taught by plants during flowering, and at another time learns the origin of the potato disease; the mineralogist may revel among emeralds and beryls, or may descend the depths of a lead-mine; the geologist will find descriptions of extinct volcanoes; while the physical geographer turns his attention to coral islands, to rivers, and to table-lands, or, finally, diving to the sea-bottom, learns the mysteries of deep-sea life. Surely there is here sufficient diversity to please everybody who has a scientific hobby. After looking through the work we are disposed to think that, on the whole, each volume is an advance upon its predecessors, both in the character of the articles and in the excellence of the illustrations."

Now Ready, Vols. I. to IV., price 9*s.* each.

CASSELL'S NEW NATURAL HISTORY. Edited by P. MARTIN DUNCAN M.B., F.R.S., Professor of Geology, King's College, London. Illustrated throughout.

Vol. IV., now ready, contains:—

BIRDS. By R. BOWDLER SHARPE, F.L.S.
REPTILES (Tortoises, Crocodiles, Lizards, and Snakes). By Prof. P. MARTIN DUNCAN, F.R.S.
AMPHIBIANS. By Prof. P. MARTIN DUNCAN, F.R.S.

Now Ready, Vols. I. to V., price 7*s.* 6*d.* each.

THE COUNTRIES OF THE WORLD. By ROBERT BROWN, M.A., Ph.D., F.L.S., F.R.G.S. Each volume contains about 130 Illustrations.

"'The Countries of the World' shows considerable powers of graphic description, and contains a vast amount of really trustworthy geographical information. The book is profusely illustrated, most of the illustrations being appropriate and helpful."—*The Times.*

CASSELL, PETTER, GALPIN, AND CO., Ludgate Hill, London.

Printed by R. CLAY, SONS, AND TAYLOR, at 7 and 8, Bread Street Hill, Queen Victoria Street, in the City of London, and published by MACMILLAN AND CO., at the Office, 29 and 30, Bedford Street, Covent Garden.—THURSDAY, November 11, 1880.

ATURE

ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
re trusts the mind which builds for aye."—WORDSWORTH

HURSDAY, NOVEMBER 18, 1880 [PRICE SIXPENCE

d Post Office.]

[All Rights are Reserved.

F MINES.

of about Sixty Lectures on
sington, on TUESDAY next,
to be continued at the same
Fee for the Course, £4 : for

W. RUDLER, Registrar.

ITERATURE.—

AY, November 29th, at 8 p.m.,
read a Paper entitled "The
n now found in History and

V. S. W. VAUX, Secretary.

JATE in HIGH

any years' experience in Pre-
olwich Examinations, &c., is
FICAL or HEAD MASTER.
d Son, Gough Square, Fleet

C.—CLASSES for

rsity Examinations, under the
. D.Sc., F.L.S. London Uni-
. Preliminary Scientific M.B.,
e work practical.

eface to the STU-

, by Lyell, 1874, he says: "As
recognise rocks and minerals at
ures, he will do well to obtain a
ch as may be procured from Mr.
Mineralogy at King's College,
died on the following terms, in

ays	£2	2 0
ays	5	5 0
weeks	10	10 0
rawers	21	0 0

to 5,000 Guineas each.

INERALOGY.

w prices, Educational Collections
y arranged to illustrate the text-
Davies, Skerichley, Dana, Page,
ol and College Museums are also
gues post free.

N, *vid* SHEFFIELD.

'S

CAL LANTERN SLIDES

bjects:—Electricity, Magnetism,
Light, Light Spectrum Analysis,
echanics, Hydrostatics, Pneuma-
d Catalogue sent on receipt of 2r.

SLIDE MANUFACTORY,
ngton Hill, London, W.

BROWNING'S MICROSCOPES.

The MODEL MICROSCOPE, made expressly for class demonstration, has rack and fine adjustments to the body, large stage fitted with universal stage motions, removable stage fittings for apparatus, revolving diaphragm, A or B eye-pieces, and 1-in. and ½-in. combined objectives of my own manufacture.

PRICE £5 10s. 0d.

Price List of Microscopes Free.

Illustrated Catalogue of Microscopes with 41 Illustrations, 10 whole page engravings, post free, 7 stamps.

JOHN BROWNING,

Optical and Physical Instrument Maker to H.M. Government, the Royal Society, the Royal Observatory,

63, STRAND, LONDON, W.C.

Factory—Southampton Street and Exeter Street, London.

PRIZE MEDAL, 1862. ESTABLISHED 100 YEARS.

Telescopes, Spectroscopes, Opera Glasses, &c., &c.

SPECTACLES AND EYE-GLASSES

MOUNTED WITH

NEGRETTI & ZAMBRA'S

THERMOSCOPIC LENSES

OF THE FINEST

BRAZILIAN PEBBLES,

In Gold, Steel, or Tortoise-shell Frames.

NEGRETTI & ZAMBRA,

Opticians and Meteorological Instrument Makers

TO HER MAJESTY THE QUEEN,

HOLBORN VIADUCT,

45, CORNHILL, & 122, REGENT STREET, LONDON.

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 48N. Tollington Road, Holloway, London. N.

GEOLOGY.

COLLECTIONS FOR TEACHERS AND STUDENTS.

Gold Medal awarded for superiority of these Collections.

New Lists of Prices of Collections, Cabinets, Apparatus, Rock Sections and all Necessaries, of

JAMES R. GREGORY,

88, CHARLOTTE STREET, FITZROY SQUARE.

New and Interesting Minerals constantly arriving.

MINERALOGY AND GEOLOGY.

FINE SPECIMENS of ORANGITE, ENSTATITE, BREVICITE, EUXENITE, AUGITE, PYROSMALITE.

UNIQUE SPECIMENS of ADULARIASPHENE and SMOKY QUARTZ.

FINE CRYSTALLISED CROMFORDITES and MATLOCKITE, Derbyshire.

XENOTINE CRYSTALLISED, Valais; WOLLASTONITE CRYSTALLISED.

COLLECTIONS FOR STUDENTS, from £2 2s. COLLECTIONS FOR BEGINNERS, from 4s. BLOWPIPE CASES AND APPARATUS.

PRIVATE LESSONS AND EVENING CLASSES.

Catalogues free.

SAMUEL HENSON,

277 (*Late* 113*a*), STRAND, LONDON, W.C.

50 ROCKS, 50 FOSSILS, 50 MINERALS,

NEATLY ARRANGED IN A

DEAL CABINET, STAINED AND POLISHED, LOCK AND KEY.

EACH SPECIMEN LABELLED AND CATALOGUED.

Price complete, £1 10s.

THE ROCKS illustrate the Order and Range of Deposition, &c.

THE FOSSILS are representative of the Genera found in the most important Deposits.

THE MINERALS are selected for their known uses in the Arts and Manufactures, and are extremely characteristic.

Names and Localities guaranteed.

THOMAS J. DOWNING, Geologist, &c.,

38, WHISKIN STREET, LONDON, E.C.

Catalogues Free.

THIN GLASS FOR MICROSCOPIC

MOUNTING, of best quality. Circles, 3s. 6d. per ounce: Squares, 4s. 9d.; post free 2d. extra; Ground edged Slips, 5s. per gross: also other Mounting Materials and Objects prepared for mounting.—CHAS. PETIT, 151, High Street, Stoke Newington, N.

THOMAS D. RUSSELL'S

NATURAL HISTORY STORES,

48, ESSEX STREET, STRAND, W.C.

Students and others are invited to inspect the Collections of British and Foreign Shells, Corals, Zoophytes, Annelids, Crustacea, Echinoderms, Minerals, Fossils, Rock Specimens, Microscopic Objects, &c.

Cabinets, Geologist's Hammers, Glass Capped Boxes, Card Trays, Tablets, Glass Slips, Micro-Thin Glass, Canada Balsam, Marine Glue, and other requisites for the Geologist and Microscopist.

Catalogues Post Free.

On the 1st of every Month.

TRIMEN'S JOURNAL OF BOTANY,

BRITISH AND FOREIGN.

New Series. Edited by JAMES BRITTEN, F.L.S., British Museum.

CONTENTS.—Original Articles by leading Botanists.—Extracts, and Notices of Books and Memoirs.—Articles in Journals.—Botanical News.—Proceedings of Societies

Price 1s. 3d. Subscription for One Year, payable in advance, 12s.

London: WEST, NEWMAN, & CO., 54, Hatton Garden, E.C.

On the 1st of every Month, price Sixpence.

THE ENTOMOLOGIST:

AN ILLUSTRATED JOURNAL OF BRITISH ENTOMOLOGY.

Edited by JOHN T. CARRINGTON,

With the Assistance of

FREDERICK BOND, F.Z.S. | JOHN A. POWER, M.D.
EDWARD A. FITCH, F.L.S. | J. JENNER WEIR, F.L.S.
F. BUCHANAN WHITE, M.D.

Contains Articles by well-known Entomologists on all branches of the Science; on Insects injurious or beneficial to Farm or Garden; Notes on Habits, Life-Histories; occurrence of Rarities, &c.; there are monthly lists of Duplicates and Desiderata.

Numerous WOODCUT ILLUSTRATIONS, to the printing of which especial attention is given, and occasional LITHOGRAPHED and CHROMO-LITHOGRAPHED PLATES.

SIMPKIN, MARSHALL, & CO., Stationers' Hall Court.

LIVING SPECIMENS FOR THE MICROSCOPE.

THOMAS BOLTON, NATURALISTS' and MICROSCOPISTS'

STUDIO, 17, ANN STREET, BIRMINGHAM.

T. B. has last week sent to his subscribers specimens of a large Actineta, which he has been unable to identify, together with drawing of same. He has also sent out Stephanoceros, Melicerta, Floscularia, Limnias, Œcistes, Carchesium, Vaginicola, Cothurnia, Opercularia, Epistylis, Volvox, Closterium, Micrasterias, Amœbæ, &c.

Weekly announcements will be made in this place of organisms T. B. is supplying.

Specimen Tube, One Shilling, post-free.

Twenty-six Tubes in course of Six Months for Subscription of £1 1s.

Price List of Specimens on application, with stamped addressed envelope.

Portfolio of Drawings, No. 3, One Shilling.

THE NEW BIOLOGICAL JOURNAL.

ARCHIVES DE BIOLOGIE.

Edited by Professors EDOUARD VAN BENEDEN of Liège, and VAN BAMBEKE of Ghent.

This Journal is devoted to the publication of original Memoirs on the Embryology, Histology, Physiology, and Comparative Anatomy of Plants and Animals. Each number is illustrated with numerous Coloured Plates, and appears at the commencement of the Quarter.

Price:—A Single Number, Six Shillings and Sixpence. Annual Subscription: Twenty-five Shillings, or Twenty-seven Shillings post free.

Orders received by Messrs. WILLIAMS & NORGATE, 14, Henrietta Street, Covent Garden, London.

In the first two numbers have appeared:—

VAN BENEDEN: On the Embryology of the Mammalia.

VAN BAMBEKE: On the Cleavage of the Egg in Batrachia.

FOR HINGER: On the Termination of Nerves in the Muscles of Insects.

FREDERIQUE AND VANDEVELDE: On the Physiology of the Muscles and Nerves of the Lobster.

MACLEOD: On the Harderian Gland of the Duck, &c., &c.

Now Ready, price One Shilling.

The CHRISTMAS NUMBER of the

ST. JAMES'S MAGAZINE FOR 1880.

Contents.

Christmas among the Eskimo; or, The Last of Franklin and His Men.
A Christmas Adventure. M. J. P.
Love Song.
A Christmas Vigil.
'Neath Wintry Skies. By Ellys Erle.
Katharine Johnston. By Mrs. Forbes-Robertson.
An Awkward Blunder.
Christmas Bells. Charles Kendal.
A Tale of a Coat.
The Two Roses.

GRATTAN MARSHALL & CO., Paternoster Row; and all Booksellers in Town or Country.

NORTH BRITISH AGRICULTURIST

is the only Agricultural Journal in Scotland, and circulates extensively amongst Landed Proprietors, Factors, Farmers, Farm-bailiffs, and others interested in the management of landed property throughout Scotland and the Northern Counties of England.

The AGRICULTURIST has also a very considerable circulation on the Continent of Europe, America, Australia, and the Colonies.

The AGRICULTURIST is published every Wednesday afternoon in time for the evening mails, and contains Reports of all the principal British and Irish Markets of the week, besides Telegraphic Reports of those held on the day of publication.

The Veterinary Department is edited by one of the leading Veterinarians in the country, and is invaluable to the breeder and feeder as a guide to the rearing of animals, and their treatment when labouring under disease.

Full Reports are given of the Meetings of the Royal Agricultural Society of England, the Royal Agricultural Society of Ireland, the Highland and Agricultural Society of Scotland, the Scottish Chamber of Agriculture, and all the principal Agricultural Associations throughout Great Britain and Ireland.

For Advertisers addressing themselves to Farmers a better medium does not exist.

Price 3d. By post 3½d. Annual Subscription, payable in advance, 14s.

Office—377, High Street, Edinburgh.

Post-Office Orders payable to Charles Anderson, Jun., Edinburgh.

ESTABLISHED 1843.

On the 1st of every Month, price One Shilling.

THE ZOOLOGIST:

A MONTHLY MAGAZINE OF NATURAL HISTORY.

Third Series. Edited by J. E. HARTING, F.L.S., F.Z.S., Member of the British Ornithologists' Union; contains—

Original articles by well-known naturalists in every branch of zoology; habits of animals; arrival and departure of migratory birds; occurrence of rare birds; distribution and migration of British fresh-water fish; new or rare marine fish; local aquaria: British reptiles, British land and fresh-water mollusca, with remarks on the haunts and habits of the species; and other matters of general interest to those who delight in natural history. Reports of the Linnean, Zoological, and Entomological Societies. Reviews of natural history books. Occasional translations from foreign zoological journals of important and interesting articles in various branches of zoology. There are occasional woodcuts.

JOHN VAN VOORST, 1, Paternoster Row.

"The leading Farmers' paper."—CLARE SEWELL READ, ESQ., M.P.

THE CHAMBER OF AGRICULTURE JOURNAL AND FARMERS' CHRONICLE

(PRICE 3d. WEEKLY).

The representative organ of the Central and Provincial Chambers of Agriculture; *gives fuller reports of the discussions and proceedings* of this extensive organisation than any other agricultural paper. It devotes *special attention to the treatment of Agricultural Questions by Parliament*, besides containing ample Reports of the LATEST LONDON and COUNTRY CORN, CATTLE, HOP, PROVISION, and other Markets, with Original Articles on Practical Farming, the Dairy, Herd and Flock News, Horticulture, &c., &c. It is despatched every Monday evening in time for the country post.

Terms of Subscription, payable in advance, post free:—3 months, 3s. 9½d.; 6 months, 7s. 7d.; 12 months, 15s. 2d.

Published by W. PICKERING, 21, Arundel Street, Strand, London, W.C.

THE ENTOMOLOGIST'S MONTHLY MAGAZINE.

Price Sixpence, Monthly, 24 pages 8vo, with occasional Illustrations.

Conducted by J. W. DOUGLAS, R. MCLACHLAN, F.R.S., E. C. RYE, F.Z.S. and H. T. STAINTON, F.R.S.

This Magazine, commenced in 1864, contains standard articles and notes on all subjects connected with Entomology, and especially on the Insects of the British Isles.

Subscription—Six Shillings per Volume, post free. The volumes commence with the June number in each year.

Vols. I. to V. (strongly bound in cloth) may be obtained by purchasers of the entire set to date, at the increased price of 10s. each; the succeeding vols. may be had separately or together, at 7s. each.

London: JOHN VAN VOORST, 1, Paternoster Row.

N.B.—Communications, &c., should be sent to the Editors at the above address.

LA SEMAINE FRANÇAISE: a Weekly

Newspaper and Review in the French Language. Politics, Literature, Science, Art, Varieties, Notes. Price 3d., through booksellers, and at the railway bookstalls Office, 37, Southampton Street Strand, W.C.

LA SEMAINE FRANÇAISE: Journal Française pour l'Angleterre: Politique, Littérature, Sciences, Arts, Variétés, Nouvelles et Notes. Un exemplaire par la poste, 3½d., en timbres poste Abonnement franco par la poste—un an, 15s. 2d.; six mois, 7s. 7d. Prix 3d., chez tous les libraires et aux gares des chemins de fer. On s'abonne aux bureaux, 37, Southampton Street, Strand, Londres, W.C.

LA SEMAINE FRANÇAISE.—"'La Semaine Française' has been brought out in London for the benefit of those English readers who may wish to study contemporary French from all points of view, instead of confining their reading to one particular Gallic print. It certainly merits success."—*Graphic*.

LA SEMAINE FRANÇAISE.—"The numbers before us are full of good things. . . . It will be far better for most than any one of the best papers published in Paris itself. We are much pleased with the character of it, and believe it will be highly valued in all those in any households where French is cultivated. The printing is very well done."—*Queen*.

TERMS OF SUBSCRIPTION:—

	s.	d.
Three months	3	10
Six "	7	7
Twelve "	15	2

P.O.O. payable to T. SPANSWICK, at King Street, Covent Garden, W.C.

Publishing Office, 37, Southampton Street, Strand, W.C.

Now ready, post quarto, cloth gilt, 272 pages. Price 15s.

LIGHTNING CONDUCTORS:

THEIR HISTORY, NATURE, AND MODE OF APPLICATION.

By RICHARD ANDERSON, F.C.S., F.G.S., Member of the Society of Telegraph Engineers; Assoc. Inst. C.E.

With numerous Illustrations.

"The book is one to be commended to the builders of, or dwellers in, lofty houses, to the deans of our cathedrals, to the parsons of churches with lofty spires or towers, and to all owners, constructors, or occupiers of buildings which, from their height or situation, are exposed to danger from lightning."—*The Athenæum*.

"The book is clearly and sensibly written, and sufficiently illustrated, and is the work of a practical man who thoroughly understands what he is talking about."—*The Academy*.

London: E. & F. N. SPON, 46, Charing Cross.

New York: 446, Broome Street. 1880.

THE "HANSA"

Published since 1861 in Hamburg, is the only independent professional paper in Germany, dedicated exclusively to Maritime Objects. Essays, Critiques, Reviews, Reports, Advertisements. Strict eye kept upon the development of Maritime Affairs in every respect. Every second Sunday one Number in 4to at least; frequent supplements and drawings. Subscription at any time; preceding numbers of the year furnished subsequently. Price 12s. for twelve months. Advertisements 4d. a line, widely spread by this paper; considerable abatement for 3, 6, 12 months' insertion. Business Office: Aug. Meyer and Dieckmann, Hamburg, Alterwall. 28. Edited by W. v. FREEDEN, M.R., Hamburg, Alexander Street, 8.

THE BREWERS' GUARDIAN:

A Fortnightly Paper devoted to the Protection of Brewers' Interests, Licensing, Legal, and Parliamentary Matters.

REVIEW OF THE MALT AND HOP TRADES; AND WINE AND SPIRIT TRADE RECORD.

The Organ of the Country Brewers.

"The Brewers' Guardian" is published on the evenings of every alternate Tuesday, and is the only journal officially connected with brewing interests. Subscription, 16s. 6d. per annum, post free, dating from any quarter-day. Single Copies 1s. each. Registered for transmission abroad.

Offices—5, Bond Court, Walbrook, London, E.C.

5me ANNÉE L'ÉLECTRICITÉ 5me ANNÉE

Paris. — 16, rue du Croissant. — Paris

Revue spéciale populaire, illustrée, bi-mensuelle contenant 24 pages grand in-8° à deux colonnes, formant chaque année un magnifique volume de 400 pages orné de plus de 200 gravures.

Rédacteur en chef: **W. DE FONVIELLE**

Directeur: **E. de Glisson**

Envoi gratis de numéro specimen sur demande

Un numéro 75 centimes

Paris et Départements: Un an..... 12 fr.

Etranger. — Union postale: Un an..... 14 fr.

Les Abonnements partent du 5 et du 20 de chaque mois.

With Illustrations and Maps, medium 8vo, 18s.

ISLAND LIFE:

OR, THE PHENOMENA OF INSULAR FAUNAS AND FLORAS, WITH THEIR CAUSES, INCLUDING AN ENTIRE REVISION OF THE PROBLEM OF GEOLOGICAL CLIMATES. By ALFRED RUSSEL WALLACE, Author of "The Malay Archipelago," "The Geographical Distribution of Animals," &c.

"Mr. Wallace has long devoted himself to these problems of geographical distribution; and his new volume gives us the cream of his latest thinking in a pleasant and eminently readable form. No other living naturalist has the same union of high literary excellence with profound scientific knowledge. His wonderful grasp of detail, depth of insight, and breadth of view remind one at every turn of Darwin, with whom he shares the honours of discovery in the theory of natural selection; but beyond this he has a lightness of touch, a beauty of style, and an ingenuity in unravelling intricate difficulties which are all his own. . . . 'Island Life' is a work to be accepted almost without reservation from beginning to end. . . . Whoever reads his book must be charmed with it."—*St. James's Gazette*.

"The present volume, though in some respects intended as a popularisation of Mr. Wallace's previous works on the distribution of animals, yet contains an immense amount of new and important matter for the man of science, as well as much delightful reading for the less instructed public. It is, in fact, the final outcome of the author's most mature thought and research on the special subject which he has made most peculiarly his own. . . . The work throughout abounds with interest. . . . It may be read with equal pleasure by those who are already acquainted with the general principles of distribution and by those who wish for the first time to learn something about modern biological geography."—*Athenæum*.

MACMILLAN AND CO., LONDON.

S. W. SILVER & CO.'S

COLONIAL HANDBOOKS, &c.

SOUTH AFRICA, including the Cape, Natal, Orange Free State, &c. Illustrated. With Coloured Map. Third Edition. Just out. 576 pp., cloth. Price 5s.

AUSTRALIA and NEW ZEALAND; including the Fiji Islands. Third Edition, just ready. With New Coloured Map. Crown 8vo, limp cloth, 449 pp. Price 5s.

CANADA. With Coloured Map of the Dominion. Cloth. 5s. [*In the Press.*

The AUSTRALIAN GRAZIER'S GUIDE. No. 1. SHEEP. Crown 8vo, limp cloth. 2s. 6d.

—— No. 2. CATTLE. [*Shortly.*

AUSTRALIAN DICTIONARY of DATES and MEN of the TIME. By J. H. HEATON. Royal 8vo, 550 pp. Price 12s. 6d.

UPS and DOWNS: a Story of Australian Life. 312 pp. Price 2s.

SOUTH AFRICA POCKET-BOOK. With Sheet of Sketches of Cape Scenery. Seasons' Chart of the World, &c. Price 5s.

WEST INDIA POCKET-BOOKS. No. 1, LEEWARD and WINDWARD ISLANDS, and TRINIDAD, with Coloured Seasons' Chart of the World, &c. No. 2. JAMAICA, HAYTI, CUBA, the BAHAMAS, &c., with Seasons' Chart, &c., as No. 1. Price 5s. each.

THE COLONIES AND INDIA,

20 pp., every Friday Evening, price 6d.,

Contains Articles on Colonial Questions, Summaries of Latest News from the various Colonies, Special Correspondents' Letters, Colonial Inquiries and Answers, &c., &c.

A Complete List of Colonial Handbooks and Maps, post free on application to S. W. SILVER & CO., SUN COURT, 67, CORNHILL, LONDON.

EDITED BY HENRY WATTS, B.A., F.R.S.,

Editor of the *Journal* of the Chemical Society

FOWNES' PHYSICAL and INORGANIC CHMISTRY. Twelfth Edition, with Coloured Plate and 154 Engravings, crown 8vo. 8s. 6d.

Also,

FOWNES' CHEMISTRY OF CARBON COMPOUNDS; or, ORGANIC CHEMISTRY. Twelfth Edition, with Engravings, crown 8vo. 10s.

London: J. & A. CHURCHILL.

New Edition, very much enlarged, 21s.

HOW TO WORK WITH THE MICROSCOPE.

By LIONEL S. BEALE, F.R.S.,

President of the Royal Microscopical Society.

THE FIFTH EDITION,

Strongly bound and enlarged to 530 Pages, with 100 Plates, some of which are Coloured, is now ready.

HARRISON & SONS, Pall Mall.

BRYCE-WRIGHT'S LATEST ARRIVALS.

MINERALS.—Crystallised Hessite, Crystallised Golds, Krennerite, Crystallised Atacamites, Malacone, Euclase, Edingtonite, Suzannite, Chanarcillite, Proustite, &c.

METEORITES.—Specimens of the following Falls:—Wold Cottage, Yorkshire; Java; Orvinio, Italy; Amana, Ohio; Tipperary, Ireland; Java; Orvinio, Italy; Estherville; Hainholz; Grosnagy, Russia; Borkut; Carthago Co.; Bates Co.; Sierra di Chaco; Ashville Co.; Bates Co.; Pallas; Ashville Co., &c., &c.

BRYCE-WRIGHT, F.R.G.S., &c.,

Mineralogist and Expert in Gems and Precious Stones,

90, GREAT RUSSELL STREET, BLOOMSBURY, LONDON, W.C.

EDWARD STANFORD'S NEW BOOKS.

Next Week.

PRE-HISTORIC EUROPE:

A Geological Sketch.

By JAMES GEIKIE, LL.D., F.R.S., &c.

Of H.M. Geological Survey of Scotland, Author of "The Great Ice Age."

Medium 8vo, with Maps and Illustrations.

"The object of these pages is to give an outline of what appear to have been the most considerable physical changes experienced in our continent since the beginning of the Pleistocene or Quaternary period. Several general works, by some of our most accomplished geologists and archæologists, have already dealt with the subject in part, but none quite cover the ground I have endeavoured to occupy. While some of my predecessors have examined the evidence principally from the point of view of the archæologist, and others from that of the palæontologist, my aim has been to describe in a more systematic manner than has hitherto been attempted that succession of changes, climatic and geographical, which, taken together, constitute the historical geology of Pleistocene, Post-glacial, and recent times."—*Extract from Preface.*

In a few days,

THE COAL-FIELDS OF GREAT BRITAIN;

Their History, Structure, and Resources.

With Notices of the Coal-Fields of other Parts of the World.

By EDWARD HULL, M.A., F.R.S.,

Director of the Geological Survey of Ireland; Author of "The Physical Geology and Geography of Ireland."

Fourth Edition, demy 8vo, with Map and Illustrations.

"This edition has been largely re-written. It contains an entirely new chapter on Carboniferous Plants, kindly drawn up by Prof. Williamson, F.R.S., of Manchester. The classification of the Carboniferous Series of Beds has been modified in accordance with the views enunciated in my paper on this subject, read before the Geological Society of London in 1877. The account of the various coal-fields has been modified in accordance with more recent investigations as far as my information extends, and the statistical portions have been brought down to the date of 1878."—*Extract from Preface.*

Ready,

LIFE AND HER CHILDREN:

Glimpses of Animal Life from the Amœba to the Insects.

By ARABELLA B. BUCKLEY,

Authoress of "The Fairy-land of Science," "A Short History of Natural Science," "Botanical Tables for the Use of Junior Students."

Crown 8vo, with upwards of 100 Illustrations, Cloth Gilt, Gilt Edges. 6s.

EXTRACT FROM PREFACE.

"The main object is to acquaint young people with the structure and habits of the lower forms of life; and to do this in a more systematic way than is usual in ordinary works on natural history, and more simply than in text-books on zoology. For this reason I have adopted the title 'Life and Her Children' to express the family bond uniting all living things, as we use the term 'Nature and her Works' to embrace all organic and inorganic phenomena; and I have been more careful to sketch in bold outline the leading features of each division than to dwell upon the minor differences by which it is separated into groups. I have made use of British examples in illustration wherever it was possible, and small specimens of most of the marine animals figured may be found upon our coasts at low tide."

CONTENTS:

Chapter
I. Life and her Children.
II. Life's Simplest Children: How they Live, and Move, and Build.
III. How Sponges Live.
IV. The Lasso-throwers of the Ponds and Oceans.
V. How Starfish Walk and Sea-Urchins Grow.
VI. The Mantle-covered Animals and How they Live with Heads and without them.
VII. The Outcasts of Animal Life: and the Elastic-ringed Animals by Sea and by Land.
VIII. The Mailed Warriors of the Sea, with ringed bodies and jointed feet.
IX. The Snare-Weavers and their Hunting Relations.
X. Insect Suckers and Biters, which change their coats but not their bodies.
XI. Insect Gnawers and Sippers, which remodel their bodies within their coats.
XII. Intelligent Insects with helpless Children, as illustrated by the Ants.

By the same Authoress, uniform in size and price,

THE FAIRYLAND OF SCIENCE.

Nearly ready,

HOUSEHOLD SCIENCE:

Readings in Necessary Knowledge for Girls and Young Women.

Edited by REV. J. P. FAUNTHORPE, M.A.,

Principal of Whitelands College.

Dedicated by permission to His Grace the Duke of Westminster, K.G.

Post 8vo.

London: EDWARD STANFORD, 55, Charing Cross, S.W.

THURSDAY, NOVEMBER 18, 1880

THE FUTURE OF POLAR RESEARCH

WE have had quite a flood of Arctic news during the last few weeks, and the question as to the direction to be taken by future Polar research is attracting attention in various quarters. Evidently those interested in this department of exploration are thinking that "something ought to be done"; but as to what that something should be, there is likely to be difference of opinion. It is unfortunate that the United States expedition sent out at the instigation of Capt. Howgate to found a Polar colony at Lady Franklin Sound, had to turn back through some defect in the engines of the *Gulnare*. Had this ship been successful in reaching the proposed ground of the expedition's work it would no doubt have given an impetus to the scheme of Polar research which has gained the approval of the Arctic authorities of nearly all nations except our own. On the other side of the American continent no news has been received from Mr. Gordon Bennett's expedition in the *Jeannette* of later date than August, 1879, when that vessel was off Cape Serdze Kamen, all well, and on her way to Wrangel Land. All the sea within Behring Strait, both on the American and Asiatic side, was searched this summer by the *Corwyn*, but no trace of the *Jeannette* was found. The conclusion from this that the expedition has come to grief, we have already pointed out is too hasty. Everything was in her favour when off the coasts of Kamtchatka last year, and if she had fair sea-way there can be no doubt that the expedition would take advantage of it, and push on as far northwards as was safe. We should not be surprised if a year hence the *Jeannette* might emerge by Behring Strait or by Novaya Zemlya with news of equal importance to that brought back by the *Tegetthoff* years ago.

But perhaps the most generally interesting expedition on the part of the Americans is that which returned some weeks ago from searching for further relics of the crews of the *Erebus* and *Terror*. With the details of this expedition our readers are already familiar. So far as further information concerning the fate of the Franklin expedition is concerned, the results have not been of much importance, though it would seem that the scientific results are of some value. What precisely these are remains to be seen. Had the handsome volume recently published by the U.S. Government under the able editorship of Prof. Nourse, containing the narrative of Capt. C. F. Hall's second expedition, been issued before Lieut. Schwatka set out two years ago, we doubt if he would have thought it necessary to go over the same ground again.[1] Hall's devotion to the memory of Franklin is well known, and his enthusiasm for Arctic exploration was almost a religion; his *Polaris* expedition will never be forgotten. In order to obtain certain news of the fate of Capt. Crozier and the 105 men who, in April, 1848, abandoned the *Erebus* and *Terror*, Hall lived with the Eskimo in the neighbourhood of Repulse Bay and King William Land for five years, 1864–69. He, like Barry, also had heard of records possessed by the Eskimo, and to obtain these records he submitted to become an Eskimo himself for all these years. With infinite tact and patience he carried out the object of his expedition, succeeded in visiting the scene of the memorable disaster, saw many signs of the presence of white men, obtained many relics, heard many stories from eye-witnesses of the sufferings of Crozier and his men when trying to make their way to the Fish River, but obtained not a shred of any kind of record. Among the things abandoned by the men in their last despairing efforts to reach a white settlement were certainly some books, but whether written or printed could not be ascertained. The poor Eskimo had no use for such strange things, and gave them to the children to play with, and long before Hall's visit all trace of them had vanished. Indeed the information he obtained was of pretty much the same character as that just brought back by the expedition under Lieut. Schwatka. The stories told to Hall by the Eskimo as to the wanderings and sufferings of the white men are interesting, though sad. Apart from the immediate object of his expedition, Hall's long residence with the Eskimo, with whom he lived as one of themselves, yielded results of great interest. He lived in their igloos, ate their food, wore their clothing, shared their joys and sorrows, joined in their feasts, their dances, and their hunts; in short, saw more of Eskimo life than probably any one has done before or since. The details given in his journals are a contribution of great value to a knowledge of the Eskimo, and the self-denial of the high-minded and sterlingly honest man in submitting to this kind of life for so many years, for so noble a purpose, raises him to the rank of a hero. The volume edited by Prof. Nourse, with its many illustrations and handsome get-up, might well put our own Government to shame. Prof. Nourse has done his part of editor admirably, and his volume will be of permanent value. So successful has the work been that we believe a second edition has been issued. As the work is only recently published, it may fairly be recognised as a contribution to a knowledge of the Arctic situation.

This is a good summer's work for America. On the opposite side of the Pole some good work has also been done. The Dutch in their tiny vessel the *Willem Bärents* have done some good dredging in the sea between Spitzbergen and Novaya Zemlya, while Mr. Leigh Smith has added greatly to his fame as an Arctic yachtsman by his work in Franz-Josef Land. He has as we have already told, greatly extended the known area of this archipelago, and shown fair grounds for believing that it extends polewards for a considerable distance. He has proved, as was done last year also, that this Arctic land is by no means difficult to reach in an average year, and this has an important bearing on Arctic research. Last week we gave a few details of what had been done along the Murmanian coast and the White Sea by the Russian party under Prof. Wagner and we know that Baron Nordenskjöld is spending the winter in St. Petersburg preparatory to undertaking his expedition next year to the New Siberian Islands.

All this is encouraging, though it would be still more so were these various efforts undertaken on some well-concerted plan. Already has the Geographical Society been asked to lend its influence to an expedition which we cannot but regard as an anachronism. We hear

[1] "Narrative of the Second Arctic Expedition made by Charles F. Hall." Edited under the orders of the Hon. Secretary of the Navy, by Prof. J. E. Nourse, U.S.N. (Washington: Government Printing Office.)

much talk of the traditions of the English navy and the duty of England to be the first to reach the Pole. We fear the so-called traditions of the English navy must be made to conform to the requirements of modern science if she is to do any useful work in Polar discovery, just as they have been compelled to do in order that our navy may be able to keep abreast of the fighting power of other nations. To squander 30,000*l.* in one huge attempt to reach the Pole would be as mad as for a merchant to embark all his capital in one hazardous undertaking. Polar research and Polar expeditions are not incompatible, but as Dr. Neumayer showed in an admirable address at the Danzig meeting of the German Association, the former must be subordinated to and guided by the results of the latter. Preparations are being made by nearly all the countries of Europe and by America for a regular Arctic siege, to begin in 1882; the days of Arctic campaigns are past. We have reached the precincts of the citadel itself, and now the sappers and miners must begin their slow but sure work, to be capped at the proper time by a grand assault. Germany, Austria, Norway, Sweden, Russia, Denmark, the United States, and we believe Canada are all to take part in this great work by establishing observing stations at suitable points all round the Polar area; while Italy is to send out next year a scientifically equipped expedition to the Antarctic region, our knowledge of which is meagre and uncertain. This last will really be an observing as well as an exploring expedition, preparatory to the establishment of an Antarctic station. Should our Geographical Society take any steps in the direction of Arctic work, we trust it will not be to encourage the foolish venture for which the country has been canvassed for subscriptions for years. We hope that Society will see that as a scientific body, its duty is to encourage a scientific method of work; and if it appeals to Government at all, let it be to urge it, for the honour of our country, to join in the concert of both hemispheres for the siege of the Polar citadel. We have already pointed out on several occasions the vast gains to science that might be expected from the work of a series of Polar observatories established on the plans so ably sketched by Lieut. Weyprecht. As Dr. Neumayer said in the address alluded to, men of science do not demand practical or so-called utilitarian reasons before giving their adhesion to any new work; it is enough if it can be shown that such work will conduce to the advancement of knowledge. And that Weyprecht's scheme of Polar observatories, of which so many Governments approve, will lead to vast additions being made to scientific knowledge, no man of science needs to be told. In meteorology, terrestrial magnetism, biology, geology, and glacial physics, the gains would be immense; and the history of science has taught us over and over again that the surest path to practical and beneficent results is through the gate of pure scientific research. Every day is the science of meteorology becoming more and more important; but until we are thoroughly acquainted with the meteorology of the Arctic regions, that most practical of sciences is deprived of what is perhaps its most important factor. But one element of the international scheme is that of Polar exploration, conducted, however, on scientific method, and along lines indicated by a scientific knowledge of Arctic conditions such as can only be obtained by permanent observing stations. What success is likely to result from Arctic work carried out on such a method was triumphantly shown by Baron Nordenskjöld when he sailed along the North-East Passage in the *Vega*. Why then should not England set up a station on Franz-Josef Land, and another say on some part of the American coast? Let the station be provided with the means of carrying out exploration in whatever direction and by whatever means the results of continued observation may indicate—as far as the Pole itself, if need be. Unless we are blind to the teachings of science and the lessons of our last expensive expedition, it is clear that this is the only sure method of reaching the Pole, if it be thought absolutely necessary for the credit of England that she should be the first to get at a point which it will take considerable trouble to spot. If our Government be well advised, we are sure they will never give the public funds either for any great national expedition modelled on the lines of the past, nor to any private chimera got up for the glory of one man and the gratification of balloonists. We do not see how, without national discredit, England can keep aloof from an international scheme, the scientific and practical results of which will be of world-wide importance; and it is the duty of the Geographical Society to lend all the weight of its influence to induce the English Government to take up its share in the new and only effectual method of Polar exploration.

THE SANITARY ASSURANCE ASSOCIATION

IT is admitted on all hands that a vast amount of unnecessary disease, suffering, and death is caused by defective sanitary arrangements, especially as regards drainage. A few years ago, so long as there was no foul smell, and all the pipes were "properly trapped," everybody was satisfied; but properly trapped usually meant improperly ventilated, or not ventilated at all, and we know now that foul gases will pass steadily, continuously, and certainly through water in traps.

Clinical observation having demonstrated the fact that sewer air produced diseases, the prevention of the entering of such foul air into houses became of paramount importance; and the matter being thus brought to so narrow an issue, the application of well-known physical laws was all that was required; it was necessary to study the circumstances under which foul air was produced, to prevent its production as far as possible, and to take such precautions that foul air, even if formed, could not accumulate and could not find its way into houses.

Science has done much, both directly and indirectly, towards the prolongation of life; and certainly not the least important of the results of the application of scientific methods to this end in recent years has been the discovery of the ways in which a house can be made practically sewer-air proof. The laws of health are being studied more and more every day, and will soon be taught as a matter of course in all our schools; they are already recognised as a special subject of study at the Universities. People are beginning to perceive that their health is a matter which is very largely indeed in their own hands, and are beginning to turn this knowledge to account in the matter of house sanitation. At the first

meeting of the Sanitary Assurance Association, presided over by Sir Joseph Fayrer, eminent members of the two professions which must always occupy the most reponsible position in connection with household sanitary matters, the professions of medicine and architecture, bore ample evidence to this fact, and at the same time to the necessity for some organisation by which the benefit of the best advice on such matters may be brought within the reach of the many. At this meeting Mr. Mark H. Judge pointed out that the Association "was the outcome of efforts which had been going on for some months to bring together architects and medical men in connection with the important question of house sanitation," and the names already identified with the Association are a sufficient guarantee that it will be both practical and permanent in its character. Sir Joseph Fayrer rightly stated in his opening address that "there is a terrible absence of all supervision of sanitary arrangements and drainage in many of the houses of the metropolis," and that although the richer classes of the population are able to get that sanitary advice which will enable them to make their houses wholesome, "there is an enormous population left, as regards which such a thing is hardly possible." Saying that he believed the idea was beginning to grow that "sanitation generally will increase the value of life," he continued, "over and over again it has come to my knowledge, and even occurred under my own observation, that families, children and servants, have suffered by the defects of drainage or sewer air—that great enemy to public health. I would venture to offer no opinion as to the nature of the diseases that proceed from sewer air, nor even enter into any discussion on the precise character of the air—the nature of the germs and the character of the poisons that it communicates; but that it does destroy health and induce disease is beyond a doubt. That it is greatly under the control of sanitary law is equally certain, and there are men now who have so studied and comprehended the nature of those laws, that they are able, practically as well as theoretically, to give that assistance and that advice which should render those conditions almost innocuous—in fact it should prevent them altogether."

Dr. Andrew Clark, after stating that he considered the Association "one of the most pressing needs of the present time," added :—"Furthermore I am convinced that if the Association can secure and retain the services of men with the scientific and practical knowledge possessed by Prof. Corfield, and will hold itself free from undertaking the execution of the works which it may suggest, superintend, and from time to time certify as sufficient, it will do important service to the public, and confer much and just credit upon all concerned."

Mr. Edwin Chadwick, the veteran sanitarian, said that "he constantly advised people, from his knowledge, 'Do not take that house unless you have it examined first. If the drains are out of order do not take it till they are put right. That was exactly what this Association had to supply."

We are happy to state that the formation of the Association was decided upon, and the following gentlemen were appointed a committee to organise it:—George Aitchison, F.R.I.B.A.; Prof. W. H. Corfield, M.A., M.D.; Prof. F. de Chaumont, M.D., F.R.S.; Mark H. Judge, Prof. T. Hayter Lewis, F.S.A.; H. Rutherford, Barrister-at-Law; with Prof. Corfield as Chief Sanitary Officer, and Mr. Judge as Surveyor.

It is surely as necessary to be assured against preventible diseases as it is to be assured against fire, and we see from the preliminary prospectus issued that it is intended to give persons who place their houses on the Assurance Register certificates that their houses are in a satisfactory sanitary condition, and to endorse such certificates from time to time; this latter point is of great importance, as it is only by regular inspection at stated intervals that it is possible to ascertain that all continues to work satisfactorily.

A very important feature is also the proposal to examine and report on the plans of new houses, for there is at present absolutely no control exerted over the sanitary arrangements of new houses in the metropolis.

We have given such prominence to this matter because we believe that the Association will supply a widely-felt want, and will do good not only directly but indirectly too; thus wise builders will take care to have their houses supervised and certified, and will reap their reward in increased facilities for letting; architects will submit their plans for criticism and suggestion; and so the public will in many ways reap a lasting benefit. In this country few new things succeed unless public opinion is ripe for them. We are slow to adopt new ideas; but we have now learnt the importance of preventing disease, we believe that much of our health depends on the perfection of the drainage arrangements of our houses, and we are ready to place them in the hands of an association in which we can have confidence.

HINCKS'S "BRITISH MARINE POLYZOA"

A History of the British Marine Polyzoa. By Thomas Hincks, B.A., F.R.S. (London: J. Van Voorst, 1880.)

THE value to science of Mr. Van Voorst's splendid series of volumes descriptive of the Natural History of the British Islands is scarcely to be overrated. The monographs are all the work of most eminent naturalists, in whom perfect confidence may be placed, and they are sumptuously printed and illustrated with abundance of excellent plates and woodcuts. The thanks of naturalists generally are certainly due to Mr. Van Voorst. The present work is fully equal in merit to its predecessors; it consists of two volumes—one of 600 pages of text, the other containing eighty-three lithographic plates. Mr. Hincks, whose industry is indefatigable, has already contributed to Mr. Van Voorst's series the well-known excellent monograph on the Hydroid Zoophytes. The labour involved in the production of a monograph such as that now under consideration is very great. All the 235 species occurring on the British coast are figured, with one or two exceptions in cases where specimens do not exist for the purpose. All the figures have been drawn by the author himself and beautifully lithographed by Mr. Hollick. Further figures are added taken from various monographs where such are necessary for the elucidation of the subject.

The work commences with an introduction, in which the author, after expressing his obligation to Mr. Busk,

Mr. Norman, Mr. Peach, Dr. McIntosh, Prof. Ray Lankester, and others who have given him valuable aid in his work, gives an account of the structure of the Polyzoa generally, with some details concerning their development, life-history, and distribution. Several pages are devoted to the question of the name of the class concerning which it seems almost hopeless that any unanimity amongst naturalists will be attained. The author adopts J. V. Thompson's term Polyzoa on the ground of priority, and we hope it may prevail in this country, although it is scarcely probable that Continental zoologists will, as the author trusts, "reconsider the grounds on which they have hitherto given their adhesion to Ehrenberg," and give up the term Bryozoa (*Moosthierchen*).

Several pages are devoted to the question of the nature of the "brown bodies," which the author, following Prof. F. A. Smith and from his own extended observations, formerly considered to be essentially concerned in the production of new polypides by germination. He now admits that the evidence at present tallies better with the residuary theory of Nitsche and Joliet, who, as is well known, regard the bodies as merely remains of decayed polypides, but thinks that further investigation on the matter is yet required. An interesting series of woodcuts are given illustrating, as shown in a series of different species, the development of the avicularium from the first rudimentary stages, hardly distinguishable from the ordinary zoœcium, up to its most highly specialised bird's head-like form. Most readers are familiar with Mr. Darwin's account of his experiments on the avicularia of Polyozoa made during the voyage of the *Beagle* and published in his Journal. The author after citing these, and those of Mr. Busk and others, expresses himself as inclined to regard the avicularia as "charged with an offensive rather than alimentary function," believing that their vigorous movements and the snapping of their formidable jaws may drive away loafing annelids and other enemies.

Some short account of the embryonic development of the Polyozoa is given, and is illustrated by a coloured plate of larvæ taken from the splendid monograph on the subject by Dr. J. Barrois of Lille. In the matter of classification the author follows Ray Lankester as far as the main sub-classes are concerned, dividing the class according to the characters of the lophophore into the Holobranchiata, or those which have the tentacles in a continuous series, and the Pterobranchiata, in which the lophopore is broken into two distinct arms like those of Brachiopods. The Pterobranchiata include only a single genus, the remarkable Rhabdopleura of Allman. The Holobranchiata are divided, after Nitsche, into the Ectoprocta, in which the anal orifice lies without the lophophore, and the Entoprocta, in which the orifice lies within it. The latter group includes the genera Pedicellina and Loxosoma only, whilst the main mass of the existing Polyzoa come under the Ectoprocta, the marine forms of which form a single order, Gymnolæmata of Allman, which order is divided by the author according to Mr. Busk's well-known system into the sub-orders Cheilostomata, Cyclostomata, and Ctenostomata. The generic terms adopted in the work are however in many instances different from those employed by Mr. Busk and other former authors, and many familiar species have changed their names, so that the student is somewhat confused. Thus the species hitherto ranged under the genus Leptalia are separated into sections and placed under the author's three genera, Mastigophora, Schizoporella, Schizotheca, and other genera.

As before stated, the number of British species of marine Polyzoa described in the work is 235. Of these 69 have as yet not been found elsewhere, but as the author adds, no inference as to their range can be drawn from this negative fact. For 28 species Shetland is the only British locality, 8 of these not being found elsewhere, whilst the remainder are Arctic forms, with the exception of two, one of which, *Cellaria johnsoni*, ranges as far south as Madeira, and is abundant in the Mediterranean. Some of the British species have an extraordinarily wide range. Thus *Cellaria fistulosa* occurs in the Mediterranean at Madeira, in South Africa, in Scandinavia and North America, in the Indian Ocean, and in Australia and New Zealand. And there are several similar instances of almost world-wide distribution, the species not being deep-sea forms, but such as flourish between tide-marks and in shallow water, though also found at greater depths. The author suggests as a possible explanation of the wideness of range of such species, in addition to migration along coast lines and in profound depths, the agency of currents, floating timber, and ships. There is a very close resemblance between the Polyzoan fauna of the south-west coasts of France and our own, whilst a small group of Polyzoa is common to our shores and those of South Africa; but these are also Mediterranean. The author expects that a flood of light will be thrown on the subject of the distribution of the Polyzoa by the results of the *Challenger* Expedition, when published. It is obvious that in treating of any branch of the marine fauna of a restricted area, such as the British Isles, it will be necessary to make some restriction as to depth in considering questions of distribution. Once the abyssal fauna is reached by the dredge the animals obtained have no longer any special connection with the shores off which they are obtained, but belong to the ocean bottom and are mostly cosmopolitan, or rather Oceanopolitan.

The cordial thanks of zoologists are certainly due to Mr. Hincks for having produced this most useful work. It will be valuable not only to the professed naturalist, but also an entertaining addition to the sea-side libraries of those who work occasionally with the microscope for recreation.

OUR BOOK SHELF

A Popular History of Science. By Rob. Routledge, B.Sc. (London: George Routledge and Sons, 1881.)

IN looking through many of the works on popular science one is inclined to exclaim, "Oh, monstrous! but one halfpennyworth of bread to this intolerable deal of sack." Mr. Routledge's recent volume is fortunately an exception to this rule, for in it we find a clear and concise statement of the development of the main branches of physical science given in a readable form with such an amount of biographical notices as to impart a human interest to the tale. Extracts, too, from the writings of the great workers in science have been judiciously interspersed throughout the text, thus bringing the student into direct communication with the master mind. Numerous illus-

trations accompany the description; some of these are original, and others taken from the French, and none the worse for that. Most of them are well executed, but intimate friends might possibly find some fault with the likenesses of living men of science. Of course it is an easy as it would be a thankless task to point out sins of omission, and perhaps also of commission, in a book like the one under notice. Such works must not be looked upon with the eye of microscopic criticism. If the general direction which the author takes is the right one, if he does not make his task easy by glossing over all the points of difficulty, but puts his case clearly and fairly forward, he may well be excused if he omits matters which one or other of his readers may deem necessary. These conditions Mr. Routledge, as it seems to us, has satisfactorily fulfilled. We can therefore cordially recommend this "Popular History of Science," believing that it will exert a healthy influence on all who read it, and may be a powerful means of spreading the love of science amongst the rising generation. H. E. R.

Class-Book of Elementary Mechanics, adapted to the Requirements of the New Code. Part I. *Matter.* By Wm. Hewitt, B.Sc., Science Demonstrator for the Liverpool School Board. (London: George Philip and Son, 1880.)

MR. HEWITT has probably had a better chance than any other teacher of knowing by experience the working of the meagre science-subjects of the new educational code. The defects of that code, and particularly of its directions as to the subject of mechanics, are very great; nevertheless the little book which Mr. Hewitt has produced shows how, in spite of the disadvantageous system under which he works, a really good teacher will succeed in working up the subject for his pupils. We have seldom met with a *really* elementary book which at once combined to so great a degree simplicity of language, accuracy of description, and sound science. Mr. Hewitt states as his experience that the main difficulty has hitherto been to get the children to express in anything like precise language the ideas suggested to their minds by the simple experiments shown them. He therefore intended this little work to serve as a lesson-book to be read by the pupils in the intervals between the experimental lessons. This first part covers the ground prescribed by Schedule IV. for the first stage. A second part, dealing with "Force," is in preparation, and will embrace the subjects of the second and third stages. We hope Mr. Hewitt's second part will prove as satisfactory as is his first instalment. His aims are limited, indeed, by the requirements of the Code, but within those narrow limits his success is great.

LETTERS TO THE EDITOR

[*The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts. No notice is taken of anonymous communications.*]

[*The Editor urgently requests correspondents to keep their letters as short as possible. The pressure on his space is so great that it is impossible otherwise to ensure the appearance even of communications containing interesting and novel facts.*]

Sir Wyville Thomson and Natural Selection

I HAVE at least great reason to be thankful that my stupidity has not prevented me from thoroughly enjoying the teachings of Mr. Darwin and Mr. Wallace, which I confess to having regarded as chiefly masterly and charming "studies in variation," for the last twenty years.

The title of the epoch-marking book which came of age last month was, however, "The Origin of Species by Means of Natural Selection." Mr. Darwin, as I am well aware, has put forward this mode of the origin of species as a part only of a hypothesis which is universally looked upon as a supreme effort of genius.

It seemed to me, rightly or wrongly, that the fauna of the enormous area forming the abyssal region existed under conditions which held out the hope that it might throw some light upon a question which appears to underlie the whole matter, and which is still unanswered. Are physiological species the result of the gradual modification of pre-existing species by natural selection, *or by any similar process;* or are they due to the action of a law as yet utterly unknown, by which the long chain of organisms rolls off in a series of definite links?

I fear I scarcely follow Mr. Darwin's illustration. If one were to pay his first visit to a breeder's, and be shown a flock of Leicesters, never having seen or heard of a sheep before, he would see nothing but a flock of sheep, and would certainly, without justly incurring the contumely of the breeder, be entitled to set them down merely as a group of animals of the same *species*, that is to say, animals fertile with one another and producing fertile progeny. He would judge so from their common resemblance, and without previous observation or information I do not see how he could know more about them. But give him an opportunity of comparing the results of breeding throughout a long period of time, or of observing the process of breeding over half the world, which comes to much the same thing; the breeder might then have cause to rail if he had not picked up the stages of the process.

The close examination of the newer tertiaries and the careful analysis of the fauna of the deep sea seem to me fairly to represent these two methods; both of these promise to yield a mass of information in regard to the course of evolution, but as to the *mode* of the origin of species both seem as yet equally silent.

I will ask you in a week or two for space for a short paper on "The Abyssal Fauna in Relation to the Origin of Species."

C. WYVILLE THOMSON

Rapidity of Growth in Corals

THROUGH the kindness of M. Parrayon, captain of the French man-of-war *Dayot*, I have received a large coral of the fungia tribe, which was yesterday found attached to the bottom of his ship as the copper was being cleaned by native divers. The following is the history of the occurrence. The *Dayot* entered the tropical waters of the South Pacific about seven months ago, coming directly from the coast of Chile. She visited some of the islands, but made no long stay in harbour until she reached Mauga Reva (Gambia Islands), where she remained for two months in the still waters of a coral basin. On entering the basin she touched the reef slightly, and without sustaining any damage. From Mauga Reva she sailed to Tahiti, where she now lies.

Several specimens of living coral were found attached to the copper sheathing, that which I have received being the largest. It is discoidal in shape, with its upper and under surfaces respectively convex and concave, and near the centre of the under surface there is a scar, where the pedicle by which it was attached to the copper sheathing was broken through. The disk measures 9 inches in diameter, and the weight of the specimen (now half dry) is 2 lb. 14 oz. On examining the under surface another disk 3¾ inches in diameter is seen partly imbedded in the more recent coral growth. Of this old disk about one-sixth part is dead and uncovered by new coral, and is stained of a deep blue colour from contact with the copper, while the outline of the rest of this old disk is plainly discernible, although partially covered in by plates of new coral.

My impression is that on touching the reef at Mauga Reva nine weeks ago a young fungia was jammed against the copper, became attached, and subsequently grew to its present dimensions.

The case affords an interesting illustration of the rapidity of the growth of coral in these waters. R. W. COPPINGER

Tahiti, August 13

Geological Climates

SINCE contributing the chapter in the history of the Coniferæ upon which Prof. Haughton remarks, I have seen *Araucaria Cunninghami* growing in gardens round Funchal, and my belief in the specific identity of the Bournemouth Eocene plant is further strengthened; yet still, as only foliage is known in the fossil, I should hardly be prepared to contest upon that alone a question of climate, however minute the resemblance. But even with the most undisputed identity there are so many possibilities

of error in arguing from a single species, that little importance should be attached to conclusions drawn from it.

Assuming them however to be specifically identical, as I myself believe them to be, and to have required precisely the same temperature, I think Prof. Haughton's case is not quite so strong as he believes. The present mean winter temperature of Bournemouth in lat. 50° 43′ is 37° 4′, but the physical surroundings of Bournemouth are not now such as conduce to luxuriant forest growth, even if its temperature sufficed, and the conditions there in the Eocene time more probably assimilated to those of the south-west coasts of Ireland at the present day.

Now the mean of the coldest month at Valentia, lat. 51° 44′, is 44°, and it may be fairly assumed that if Valentia were a degree farther south, corresponding to Bournemouth, the temperature would be one degree higher; and if sheltered by mountains from all the northerly winds as Glengariff is, the mean might possibly be raised to 46°. Thus but 11° are required to reach the minimum of 57° supposed to be required by his Araucaria. Again, although the Moreton Bay Pine does not appear to support a less mean annual temperature than 67° to 70° between the Clarence and the Bellingen, which are its southern limits in Australia, it flourishes and ripens seeds in Madeira in a mean of 64° 96′, and although I have only noticed it in two gardens near the sea-level, I think it has only been excluded from others higher up the mountains in favour of the far more striking *Araucaria excelsa*. Moreover from its present restricted area it appears to be a declining type, which may, when more widely distributed, and possibly in presence of fewer competing species in remote Eocene time, have sustained greater extremes of climate.

Taking the species, however, as it exists, and apart from any such possibilities, uniformitarians have, it seems to me, but to account for an increase of 14° to 15°, that is if Bournemouth were near its northern limit, as seems probable from its having grown at or near the sea-level.

Supposing, as all evidence tends to prove, that Northern Europe and America were connected by continuous land in Eocene time, would not the mere fact of shutting off the Arctic Seas cause a general and perhaps sufficient rise of temperature? In N. lat. 70° Prince Albert Land has a mean of only 5° Fahr., and Lapland one of 32°, a difference of no less than 27°, caused solely by the presence of an Arctic ice-laden current. The general cooling effect of incessant oceanic circulation between the North Pole and the Tropics is, I think, scarcely taken into sufficient account, and although it may be contended that conversely the northerly flow of the Gulf Stream mitigates climate, I think that its action in Europe is chiefly in fending off the ice-laden currents from our coasts, the limit of trees penetrating quite as far north in Siberia away from the coast as at the North Cape, where they are under its influence. J. STARKIE GARDNER

Order Zeuglodontia, Owen

IN August 1848 H.M.S. *Dædalus* encountered off St. Helena a marine animal, of which a representation appeared in the *Illustrated News* of the latter part of that year. It is thirty-two years since I saw this figure, but I recollect that it was one of a blunt-nosed animal with a neck carried about four feet above the water, which was so long as to present the appearance of a serpent; and I remember that Prof. Owen, in combating at the time the idea that this was a sea-serpent, pointed out that the position of the gape in relation to the eye, as shown in the figure in the *Illustrated News*, was that of a mammal, and not that of a reptile; in consequence of which he argued that the animal seen was probably only a leonine seal, whose track through the water gave an illusory impression of great length. This idea, however, seemed to me untenable in the face of the representation in the *Illustrated News*; but it was obvious that to afford the buoyancy necessary for the support above the water of so long a neck (estimated on that occasion as sixty feet, though only the part near the head was actually out of the water), the submerged portion of the animal could not have had the shape of a serpent.

Two or three years after this, on reading the description of *Zeuglodon cetoides*, from the Tertiary (probably Upper Eocene) formations of Alabama, it struck me that the animal seen from the *Dædalus* may have been a descendant of the order to which *Zeuglodon* belonged; and I have ever since watched with interest for reports of the "great sea-serpent."

Three years ago the following appeared in the newspapers:—

"Borough of Liverpool, in the County Palatine of Lancaster to wit.

"We the undersigned, captain, officers, and crew of the barque *Pauline* (of London) of Liverpool, in the county of Lancaster, in the United Kingdom of Great Britain and Ireland, do solemnly and sincerely declare that on July 8, 1875, in lat. 5°·3′ S., long. 35° W., we observed three large sperm-whales, and one of them was gripped round the body with two turns of what appeared to be a huge serpent. The head and tail appeared to have a length beyond the coils of about 30 feet, and its girth 8 or 9 feet. The serpent whirled its victim round and round for about fifteen minutes, and then suddenly dragged the whale to the bottom head first.

"GEORGE DREVAR, *Master*
"HORATIO THOMPSON
"JOHN HENDERSON LANDELLS
"OWEN BAKER
"WILLIAM LEWARN

"Again, on July 13, a similar serpent was seen about 200 yards off, shooting itself along the surface, head and neck being out of the water several feet. This was seen only by the captain and one ordinary seaman, whose signatures are affixed.

"GEORGE DREVAR, *Master.*"

"A few moments after it was seen elevated some sixty feet perpendicularly in the air by the chief officer and the following able seamen, whose signatures are also affixed—

"HORATIO THOMPSON
"WILLIAM LEWARN

"And we make this solemn declaration, &c.

"Severally declared and subscribed at Liverpool aforesaid, the 10th day of January, 1877, before

"T. S. RAFFLES, J.P. for Liverpool."

The locality here specified was about thirty miles off the northern coast of Brazil.

In this account I thought that I recognised the grip of the whale by the long neck of the attacking animal, the appearance being confounded into the double coil of a serpent by the distance and motion of the objects; but in face of the general ridicule which has been attached to this subject, and being without any assurance that the declaration so purporting to be made was genuine, I did not venture to ventilate my long-cherished idea. A relative of mine, however, just returned from India, chancing to say that two of the officers of the steamer in which she went out had on the previous voyage witnessed an immense animal rear its neck thirty feet out of the water, and that a sketch of the object had been instantly made, and on reaching port sent to the *Graphic*, I obtained the number of that paper for July 19, 1879, and I inclose a tracing of the figures in it, which are accompanied by the following statement in the *Graphic*:—

"The accompanying engraving is a *fac-simile* of a sketch sent to us by Capt. Davison, of the steamship *Kiushiu maru*, and is inserted as a specimen of the curious drawings which are frequently forwarded to us for insertion in the pages of this journal. Capt. Davison's statement, which is countersigned by his chief officer, Mr. McKechnie, is as follows:—'Saturday, April 5, at 11.15 a.m., Cape Satano distant about nine miles, the chief officer and myself observed a whale jump clear out of the sea, about a quarter of a mile away. Shortly after it leaped out again, when I saw that there was something attached to it. Got glasses, and on the next leap distinctly saw something holding on to the belly of the whale. The latter gave one more spring clear of the water, and myself and chief then observed what appeared to be a large creature of the snake species rear itself about thirty feet out of the water. It appeared to be about the thickness of a junk's mast, and after standing about ten seconds in an erect position, it descended into the water, the upper end going first. With my glasses I made out the colour of the beast to resemble that of a pilot fish.'"

As I have not been able to find any description of the skeleton of the *Zeuglodon*, I venture to draw attention to the subject through your columns, in the hope that among your many readers in America this letter may attract the notice of some one who will tell us whether what is known of the osseous structure of *Zeuglodon cetoides* is or is not consistent with the representation in the *Graphic*. The remains of this cetacean, supposed to be extinct, indicate, according to Sir Charles Lyell, that it was at least seventy

feet in length,[1] while its great double-fanged but knife-edged molars show that it was carnivorous; and as we are not so far removed from the period of the Alabama Tertiaries as to render it improbable that members of what must once have been a great order of carnivorous cetacea, totally distinct from the orders of cetacea hitherto known as living, may still survive, I have braved the ridicule attaching to this subject so far as to invite attention to it.

The second of the two figures in the *Graphic* shows the long-necked animal to possess the cetacean tail, and its head there seems to have been turned from the observer, so that the under-side of it only is presented. The first figure shows that the whale had been seized on its flank by the powerful bite of its aggressor, and that to escape from this it had thrown itself out of the water. Having succeeded in this object the second figure shows the aggressor rearing its head and neck out of the water to discover the direction which its prey had taken, in order that it might follow it up; and so far from the charge of curious drawing made by the editor of the *Graphic* being justified, the representation of the whale can be at once recognised as fairly correct; while that of the tail of the unknown animal (which probably prompted this charge), so far from being curious, forms an important piece of evidence as showing the animal in question to be cetacean.

SEARLES V. WOOD, Jun.

Martlesham, near Woodbridge, September 27

P.S.—Since sending to you the above I have again seen my relative, and find that the cut in the *Graphic* of July 19, 1879, is not that of the instance observed from the steamer in which she came home, which was the *City of Washington*, but of a separate instance which occurred to another ship. I have not been able yet to procure the *Graphic* containing the figure of the animal seen from the *City of Washington*, but she tells me that it was pasted up in the saloon, and represented only the head and long neck of the animal, which was raised to a great height out of the water, and near to the ship; and had been drawn for the *Graphic* by a lady passenger immediately after the occurrence. These repeated and independent notices of the same long-necked animal are, however, the more confirmatory of its existence.

I find that Prof. Owen, in his article on Palæontology in the *Encyclopædia Britannica* (vol. xvii. p. 166), in giving a description of *Zeuglodon cetoides*, says that "the skull is very long and narrow *and the nostril single*," that Dr. Harlan obtained the teeth on which, correcting Harlan's reptilian reference of them, he founded the order *Zeuglodontia*, from the Miocene of Malta; and that the teeth discovered by Grateloup in the Miocene beds of the Gironde and Herault, and ascribed by him also to a reptile under the name of *Squalodon*, are those of a smaller species of *Zeuglodon*. The remains of *Squalodon*, along with those of the shark with huge teeth, *Carcharodon megalodon*, and of numerous cetaceans assigned to orders all still living, and of which some, such as *Delphinus*, belong to living *genera*, occur in the "Sables inférieurs" of Antwerp; which, though long called Miocene, are by M. Vandenbroeck regarded as older Pliocene, and as the base of that series of deposits of which the



middle and upper divisions are respectively represented by the Coralline and Red Crags of England; and with these "Sables inférieurs" the so-called Miocene of Malta, in which *Zeuglodon* is associated with *Carcharodon*, is probably coeval. Dr. Gibbes (*Jour. Acad. Nat. Sc.*, 2d. ser., vol. i. p. 143), figures and describes teeth of the Antwerp species of *Carcharodon* from both the Eocene of South Carolina and the Miocene of Alabama These various references bring the *Zeuglodonts*, with their *Carcharodon* associates, down to a late geological period, during which they co-existed with Delphinian prey; and of this prey the whale in the woodcut (which looks like a *Grampus*) seems an example.

It is most likely that Bishop Pontoppidan, a copy of the English (1755) edition of whose work I possess, concocted his two figures (one of which is that of a huge snake undulating on the waves, and the other that of a serpent-like animal with pectoral flappers or fins, resting almost on the surface of the sea, with head and tail erect out of the water like the letter U, and spouting water or steam from its mouth *in a single column*), from accounts given him by Norwegian seamen, some of whom had seen the animal in the position in which it was observed from the *Dædalus*, and others in that in which it is represented in the cut as seen from the *Kiushiu-maru*; for in the long narrative which he gives of the descriptions received from observers at numerous times, some of these agree with the one, and some with the other, though both of the Bishop's figures represent only preposterous conceptions of his own.

[The animal seen from the *Osborne*, and figured in the *Graphic* of June 30, 1877, as the "Sea-serpent," is quite a different thing from the one in question, and may have been a *manatee*.]

[1] He observes in the third edition of his "Manual of Elementary Geology" (1851), p. 208, that he visited the spot where a vertebral column of this length belonging to *Zeuglodon* had been dug up.

Temperature of the Breath

THE interesting observation made by Dr. Dudgeon (NATURE, vol. xxii. p. 241, and vol. xxiii. p. 10) to the effect that breathing on the bulb of a thermometer through several folds of flannel or silk raises the temperature of the instrument several degrees above that of the mouth and body, is easily verified. There is no doubt about the accuracy of the observation; but the explanation of it offered by Dr. Dudgeon is not satisfactory. He supposes that the heightened temperature is due to the expired air being hotter—not cooler, as is usually believed—than the mouth and body. A simple experiment sufficed to show that this view was untenable. A clinical thermometer was inserted in the cavity of the mouth, and the stem grasped by the teeth in such a way that the bulb lay free in the oral cavity. Inspiration was carried on by the nostrils, and expiration was effected by gently forcing the breath between the loosely-closed lips and the stem of the instrument. The bulb was thus placed in the centre of the stream of expired air and kept free from contact with the tongue and cheeks. Experimenting in this way, I found, at the end of five, and also of ten, minutes that the thermometer marked 97·2°—the temperature under the tongue at the time being 98·4°.

Had the breath been hotter than the mouth the instrument could not have failed to register a higher temperature than 98·4°, but being really cooler, the instrument, of course, recorded a lower temperature.

What is then the true explanation of the phenomenon observed by Dr. Dudgeon? I believe that it is simply an example of the conversion of latent into sensible heat by the rapid condensation of aqueous vapour. The organic fabrics which compose our clothing are all more or less hygroscopic—that is to say, they have the capacity of imbibing aqueous vapour and condensing it into the solid and liquid forms. The expired breath is heavily charged with aqueous vapour; and aqueous vapour, at the moment of condensation, liberates an enormous amount of latent heat, which thus becomes sensible to the thermometer. In this particular watery vapour exceeds far away all other gases.

The following experiments were made with a view of testing the correctness of this view. Two strips of flannel were prepared, each six inches long and an inch and a quarter wide. The first strip was rolled, without any preliminary preparation, round the bulb of a clinical thermometer. The bulb, thus enveloped, was inserted between the closed lips, and the expired air was forced through the porous material for a period of five minutes. The thermometer rose to 104°. The instrument was then allowed to cool, and, after having been re-set, was again inserted between the lips, and breathed through for a second period of five minutes. This time the temperature only rose to 101°. The experiment was repeated a third time for a similar period, but this time the thermometer did not rise above 98·6.

These results tallied exactly with the requirements of the condensation hypothesis. During the first period the fresh dry flannel absorbed and condensed the watery vapour passing through it with such rapidity that the liberated sensible heat was sufficient to raise the mercury several degrees above the temperature of the mouth. In the second period of five minutes the hygroscopic activity of the flannel had been greatly reduced by the previous absorption of aqueous vapour, and the thermometer only rose slightly. In the third period saturation had been approached, and the breath passed through the flannel almost without depositing any of its moisture, and accordingly the thermometer only indicated a temperature slightly higher than that of the mouth.

The second strip of flannel was subjected to a little preliminary preparation. In order to increase its hygroscopic activity it was thoroughly dried (superexsiccated) by holding it for a few minutes before the fire. When it had cooled down to the temperature of the room it was wrapped round the bulb of the thermometer, and the experiment was proceeded with as before. The result surprised me. *In one minute* the mercury had risen not only to the top of the scale (112° F.), but had filled the little bulb above it, that is to say, it had risen to at least 115° F. When the instrument had cooled it was reset, and inserted again between the lips and breathed through for three minutes. At the end of this time the scale marked 106° F. After the instrument had been cooled and reset the experiment was repeated a third time, and the temperature only reached 102° after breathing through the envelope for four minutes. A fourth trial of four minutes only produced a record of 98·4°. Here again the development of heat steadily declined as the flannel became less hygroscopic.

It is probable that, with the superexsiccated flannel the first portions of aqueous vapour condensed at the beginning of the experiment pass at once from the gaseous into the solid form, and constitute that portion of water which is incorporated in intimate union with all organic tissues. This accounts for the extreme rapidity of the development of heat at the commencement of the experiment. I found that even a single long expiration through the freshly-warmed flannel raised the mercury to 110° F.

Dr. Dudgeon's observation will not necessitate a revision of our conclusions respecting the temperature of the breath, but he has supplied us with an exceedingly elegant and easy way of demonstrating the liberation of sensible heat which takes place during the passage of water from the gaseous into the solid and liquid state.

WM. ROBERTS

Manchester, November 10

Height of the Aurora

IN NATURE, vol. xxii. p. 291, is inserted a letter of Mr. T. Rand Capron, on the determination of the height of auroræ, wherein I read: "It is unfortunate that simultaneous observations of the auroral corona are almost entirely wanting. I . . . would be glad if any particulars could now be furnished me."

Having treated the subject of the auroræ and their properties in an ample manner in my "Théorie cosmique de l'Aurore polaire" (*Memorie della Società degli Spettroscopisti Italiani*, 1878, vol. vii.), wherein I have adduced proofs of the thesis that *The corona is an optical illusion, due to the laws of celestial perspective*, I was astonished to find the alleged words used by so great an authority. That "simultaneous observations" of the auroral corona will be ever without any result, as far as its height above the earth is concerned, follows already from the known property, that the corona always shows itself in the direction of the *local* magnetic total force (given by the inclination needle).

Regretting that such a well-established fact seems not generally known, I take the liberty to refer Mr. Rand Capron to the chapter of my treatise, "Dans quelle Région de l'Atmosphère terrestre se trouvent les Rayons de l'Aurore polaire, et est-ce que la Couronne est une Chose réelle?" and will repeat here that very beautiful determinations of the height of streamers and beams were obtained by Prof. Heis and Dr. Flögel, and by Prof. Galle in Germany, showing a height of the phenomenon from 20 to 100 miles (of 15 in 1 degree). These results are published in the *Zeitschrift der oesterr. Gesellsch. f. Meteor.* vii. p. 73.

I regret to have found no earlier opportunity of answering the request of Mr. Rand Capron, but think that this letter may still have some interest, notwithstanding the valuable article by Mr. Plummer in NATURE, vol. xxii. p. 362.

Groningen (Netherlands), November 10 H. T. H. GRONEMAN

Fascination

As a contribution to this subject, at least of new material if of no decisive evidence in support of any existing theory, I offer the conclusions which Malachi Foot, Member of the College of Physicians and Surgeons, N.Y., reached in 1807 relative to this matter. A short memoir of his which I recently met was published in the *Medical Repository* for that year, entitled "An Examination of Dr. Hugh Williamson's Memoir on Fascination, to which is subjoined a New Theory of that Phenomenon," and is striking both in matter and conception.

The author, after displaying some temper over Dr. Williamson's willingness to attribute the well-accredited effects of snake-charming to terror, producing in the victim a condition which he (Dr. Williamson) terms "dementation," and "wherein extreme fear stupefies the mind and deprives him of the understanding," produces his own explanation. Although he acknowledges the paralysing effects of fright, and instances quadrupeds falling lifeless from the effect of fear, deer stricken motionless by the light of a torch, &c., yet he inveighs against the false reasoning which discovers in these cases of arrested volition any analogy to the phenomena of so-called fascination. Our author, evidently of no superstitious habit, distinctly admits the fact that the snake repeatedly captures prey by a method seemingly so occult as to merit the characterisation of fascination, and develops his theory in the light of that very thought.

He ascribes to the primary sensations of animals, in them unmodified by reflection as to their source or character, complete efficacy to awaken emotions of pleasure of an intensity to us quite incommensurate with the apparent causes which evoked them—emotions so powerful as to absorb all other secondary feeling, enfolding the animal in a delightful but numbing trance, whose stages advance from attention through ecstasy to anæsthesia. And he finds in the eye a sensory centre which most expansively responds to all outward stimuli. This much premised, he applies it to the case in hand. The snake, fixing its glittering eyes with hungry expectancy upon its victim, at the same time throws its body into graceful curves and raises its tail, undulating with a soft and inviting motion. (Foot insists upon the almost invariable accompaniment of motion as auxiliary in attracting and pleasing the prey.) The bird's eye, once caught, becomes ensnared in the endless succession of contortions, and it draws near, dominated by simple delight.

As Foot expresses it, "the pleasurable movements of the organs of vision stimulate to approach and excite an eager desire to embrace." *Reverie oculorum* ensues, and the bird flutters helpless to the ground. Foot speaks of having seen a cat succeed in similarly charming birds by wreathing the body and waving the tail. He might have confounded this with the

ordinary nervous concentration of attention common to the Felidæ before "pouncing." He speaks of larks being attracted in the South of France by means of an octagonal box holding a mirror mounted on a pivot which is turned by the wind. The reflected rays of sunlight dazzle and delight the birds, and they approach near enough to be caught by a spring net. The preliminary phase, that of attention, wherein curiosity perhaps predominates, is illustrated in the known trick of a fox amusing ducks by rolling itself down a bank, as also in the perilous interest excited in a loon by a handkerchief waved by an unseen hand. Many must have experienced, on looking over very high galleries upon floors beneath, or over sheer precipices, an almost uncontrollable impulse to throw themselves headlong down. Can this feeling be described as akin to "fascination"?

L. P. GRATACAP

Amer. Mus. Nat. Hist., N. Y., October 28

A. PERCY SMITH.—The little centipede is *Geophilus electricus*, well known to be occasionally luminous.

HOMAGE TO MR. DARWIN

ON Wednesday, November 3, a deputation from the Yorkshire Naturalists' Union waited upon Mr. Darwin at his residence, Down, Beckenham, Kent, for the purpose of presenting him with an address expressive of admiration for his long devotion to scientific research, and appreciation of the great and important results to which his investigations have led. Prof. Williamson, F.R.S., of the Owens College, Manchester, who is the president of the Union for the current year, was prevented from accompanying the deputation by the pressure of his professorial duties. The deputation arrived at Mr. Darwin's residence about 1 p.m., and was received in a most hearty manner by the great naturalist himself, Mrs. Darwin, and other members of the family. The members of the deputation were introduced individually to Mr. Darwin by Dr. Sorby, vice-president of the Union, and then the interesting ceremony of the presentation of the address was at once proceeded with. After a few words on the work of the Union by Dr. Sorby, the address was read by Mr. Thomas Hick, B.A., B.Sc., and formally presented to Mr. Darwin by Dr. Sorby. Replying to the address, Mr. Darwin assured the deputation of his deep sense of the honour the Yorkshire Naturalists' Union had conferred upon him on that occasion, and only regretted that he had not done something more deserving of such an honour. He had no idea previously that there was so strong a body of working naturalists in Yorkshire, but was pleased to learn that such was the fact, and to find from the *Transactions* that had been forwarded to him that they were doing useful work. Coming from such a body, the address was all the more gratifying to him, though he still feared he hardly merited the good things that had been said of him. The address which had been presented to him he and his family would for ever treasure and preserve, and he desired to express his warmest thanks, both to the deputation and those whom they represented, for it, and for the kind and considerate manner in which everything connected with it had been arranged. Subsequently the deputation were entertained at luncheon, and having spent a short time in familiar conversation with their hospitable host and his family, took their departure amid mutual expressions of kindness and regard.

The following is the text of the Address, which is dated August last:—

To Charles Darwin, LL.D., M.A., F.R.S. &c., &c.

SIR,—The Council and Members of the Yorkshire Naturalists' Union, all of whom, with scarcely an exception, are working students of one or more of the various branches of natural history, desire to express to you in a most respectful manner, and yet with the greatest cordiality, their admiration of your life-long devotion to original scientific research and their high appreciation of the almost unparalleled success of the investigations by which you have contributed so largely to the modern development and progress of biological science.

More especially do they desire to congratulate you on the fact that your great work on the Origin of Species will come of age at an early date, and that your life has been spared long enough to enable you to see the leading principles therein enunciated accepted by most of the eminent naturalists of the day. On the conspicuous merits of that and of your other published works they need not dwell, as those merits have been recognised and admitted even by those who have dissented most strongly from the conclusions at which you have arrived. They may nevertheless be permitted to remind you that your writings have been instrumental in giving an impetus to biological and palæontological inquiries which has no precedent in the history of science, except perhaps in that which followed the promulgation of the gravitation theory of Newton, and that which was due to the discovery of the circulation of the blood by Harvey.

One of the most important results of your long-continued labours, and one for which you will be remembered with honour and reverence as long as the human intellect exerts itself in the pursuit of natural knowledge, is the scientific basis you have given to the grand Doctrine of Evolution. Other naturalists, as you yourself have shown, had endeavoured to unravel the questions that had arisen respecting the origin, classification, and distribution of organic beings, and had even obtained faint glimpses of the transformation of specific forms. But it was left to you to show, almost to demonstration, that the variations which species of plants and animals exhibit, and in natural selection through the struggle for existence, we have causes at once natural, universal, and effective which of themselves are competent not only to explain the existence of the present races of living beings, but also to connect with them, and with one another, the long array of extinct forms with which the palæontologist has made us familiar.

Farther, the Yorkshire Naturalists are anxious to place on record their firm conviction that in the care, the patience, and the scrupulous conscientiousness with which all your researches have been conducted; in the ingenuity of the experiments you have devised; and in the repeated verifications to which your results have been submitted by your own hands, you have furnished an example of the true method of biological inquiry that succeeding generations will deem it an honour to follow, and that cannot but lead to still further conquests in the domain of organic nature.

In presenting this small tribute of their high regard and esteem, the members of the Yorkshire Naturalists' Union cannot but hope and pray that many years of happiness and usefulness may yet remain to you, and that our Science and Literature may be still further enriched with the results of your researches.

(Signed) WILLIAM C. WILLIAMSON, F.R.S., President,
H. C. SORBY, LL.D., F.R.S., Vice-President,
GEORGE BROOK, ter. F.L.S., Secretary,
WM. DENISON ROEBUCK, Secretary,

and Eleven other representative Officials.

THE ATOMIC WEIGHT OF BERYLLIUM

FOR some time chemists have been doubtful what value to assign to the atomic weight of beryllium. Some years ago Prof. Emmerson Reynolds determined the specific heat of this metal to be 0·642; this number multiplied into 9·1 gave 5·8 as the atomic heat of beryllium; in other words it confirmed the generally accepted atomic weight. In 1878 Nilson and Pettersson re-determined the specific heat of beryllium, and found the number 0·408 for the temperature interval 0°–100°; hence these chemists concluded that the atomic weight of the metal must be increased by one-half ($13·6 \times 0·408 = 5·6$). If Be = 9·1 the oxide of beryllium is BeO, and the metal is placed in the magnesium group; but if Be = 13·6 the oxide is Be_2O_3, and the metal is placed in the aluminium group. But there is no place in Mendelejeff's classification of the elements according to the magnitude of their atomic weights for a metal with the atomic weight 13·6, forming an oxide M_2O_3, and exhibiting the properties of beryllium. The value of Mendelejeff's classification is however so great that chemists were not inclined to alter the atomic weight of beryllium except upon most cogent evidence.

Nilson and Pettersson have recently repeated their determination of the specific heat of beryllium, and find these numbers:—

0°– 50° spec. heat = 0·3973 : 0°–100° spec. heat = 0·4246,
0°–200° ,, = 0·475 : 0°–300° ,, = 0·5055.

If the atomic weight is taken as 13·6 then the atomic heat for the interval—

0°–50° = 5·46 : 0°–100° = 5·79 : 0°–200° = 6·48 : 0°–300° = 6·9,

hence the Swedish chemists conclude that the atomic weight of beryllium is 13·6.

But in the last number of the *Berichte* of the German Chemical Society, Lothar Meyer has calculated, from Nilson and Pettersson's numbers, the true specific heat (*i.e.* the ratio between the quantity of heat required to raise unit weight of the given substance through 1°, starting from the given temperature, and the quantity of heat required to raise unit weight of standard substance through 1°, also starting from the given temperature) of beryllium for various temperatures: his results are as follows:—

(γ = true specific heat at temperature t : $\Delta\gamma$ = value of increase of specific heat for 1°).

t.	t.	t.
+ 23° γ = 0·3973	73·2 γ = 0·44481	157° γ = 0·5193
$\Delta\gamma$ = 0·00101	$\Delta\gamma$ = 0·00085	$\Delta\gamma$ = 0·00063

t. 256°·8 γ = 0·5819.

Hence the atomic heats of beryllium are:—

t.	Be = 9·1.	Be = 13·65.
23°	3·62	5·43
73°	4·08	6·12
157°	4·73	7·10
257°	5·29	8·94

The value of $\Delta\gamma$ decreases as the temperature rises; in this respect beryllium resembles boron, carbon, and silicon. For other elements whose specific heats increase with increase of temperature the value of $\Delta\gamma$ also increases. Lothar Meyer therefore concludes that beryllium is analogous to boron, carbon, and silicon, in that its specific heat increases as temperature increases, and in that the value of this increase is less for 1° at high than at low temperatures. Hence the atomic weight of beryllium is almost certainly 9·1, the oxide is BeO, and the metal finds its place in Mendelejeff's system of classification of the elements according to their atomic weights.

THE PHOTOPHONE

MANY readers of NATURE will doubtless be glad to know that Mr. Graham Bell's extraordinary experiments may be repeated on a small scale with very simple apparatus, no special appliances being required beyond the mirror transmitter and the selenium receiver, both of which may be easily constructed. I propose to give a short description of an arrangement which has in my hands been very successful.

The mirror is made of the thin mica which is sold by opticians for covering *carte de visite* photographs. It is cut by scissors into a circle 2¼ inches in diameter, and silvered by the process for silvering glass specula. The box in which it is mounted is an ordinary wood turned box 2½ inches in diameter. A circular hole of about 2 inches diameter is cut in the lid, behind which the mirror is laid with the reflecting side outwards, a flat ring of vulcanised india-rubber of suitable size and thickness being placed behind the mirror; when the box is closed the ring should hold the mirror firmly in position. If the lid screws on, so much the better. At the bottom of the box is cut a hole, into which is glued one end of a flexible speaking-tube 18 inches long, having at its other end a wooden mouthpiece. It will be found convenient to attach a short wooden arm to the box in a direction perpendicular to its axis. By means of this arm the transmitter may be held in a clamp in any desired position.

This completes the transmitter as described by Mr. Bell. I have made a small addition which, though not essential, is a decided improvement. At the back of the mirror I cemented a disk of calico 1 inch in diameter, in the centre of which had been previously inserted a loop of silk half an inch long. A hole ⅛ inch diameter is bored perpendicularly in the side of the box at a point about ½ inch from the mirror end of it, and in this hole is inserted a piece of watch-spring 1⅛ inch long, with its flat sides parallel to the top and bottom of the box. The spring is fixed into the hole with wooden plugs so that one end is flush with the outer surface of the box; the other end where it intersects the axis is bent into a shallow hook. Into this hook is slipped the silken loop, and the tension of the spring draws the mirror into a slightly concave form, and seems to make it respond more perfectly to sound vibrations.

By far the most important part of the whole apparatus is the selenium "cell." After making some dozens of different forms, most of which were more or less sensitive, but none satisfactory, I tried the one now to be described, which turned out very successful. Take a slip of mica 2¼ inches long and ¾ inch broad, and beginning at ¼ inch from one end, wind round it in the form of a flat screw some No. 40 copper wire. The pitch of the screw is $\frac{1}{16}$ inch, that is, each wire on the two faces of the mica is $\frac{1}{16}$ inch from its neighbours. Continue winding up to ¼ inch from the other extremity; then fix the two ends of the wire by passing them through holes drilled in the mica. Now take a second wire and carefully wind this on beside the other, thus forming a second screw, the threads of which are midway between those of the original one. Fix this as before. Great care must be taken that the two wires do not touch each other at any point: it will be well to make sure of this by testing with a galvanometer before proceeding further. If a lathe is at hand, the tedious operation of winding may be very greatly facilitated. Turn a cylinder of hard wood 4½ inches long and 1 inch in diameter: cut this cylinder *longitudinally* into two equal parts, and between the two semi-cylinders thus formed place, sandwich-like, a slip of mica of equal breadth. Secure the ends with screws. Smooth down the whole in the lathe, and when the edges of the mica are quite flush with the surface of the wood, cut upon the cylinder a screw of thirty-two threads to the inch. On removing the mica from the cylinder its two edges will be found to be beautifully and regularly notched. Wind the first wire into alternate notches, and the second into the others. The wire should be annealed to take away its springiness and make it lie flat, and the mica should be stout enough to bear tight winding without buckling.

For the succeeding operation a retort-stand at least 15 inches high is convenient. Fix one ring 15 inches above the foot; on a lower ring stand a medium-sized Bunsen burner. On the top ring lay a flat sheet of brass $\frac{1}{16}$ inch thick, and on the brass a piece of mica (to save waste selenium). Place the embryo cell on the mica, laying small weights on its two ends to keep it steady and bring it into closer contact. Having brought the Bunsen burner close under the brass, melt a few grains of vitreous selenium in a small spoon and let four or five drops fall upon different parts of the cell. Spread the melted selenium evenly over the surface with a slip of mica, pressing it well between the wires. During this process the temperature must be carefully regulated by raising or depressing the burner. If it is not high enough, the selenium will begin to crystallise; if too high, the selenium will gather up into drops, being apparently repelled from the surface of the cell. The temperature should in fact be just above the fusing point of crystalline selenium. When a smooth surface is obtained, quickly remove the cell with microscope forceps and let it cool. Its surface will now be smooth and lustrous.

The cell must next be annealed. And here my expe-

rience differs in a remarkable manner from that of Mr. Bell, as stated in his celebrated lecture. It is true that selenium may be rendered crystalline in "a few minutes," but in this condition I find it far less sensitive to light than after it has undergone a process of long heating and slow cooling. My method is as follows:—The brass plate being cool, lay the cell upon it again, and place the burner at its lowest possible point. The selenium will soon begin to crystallise, as evidenced by its surface assuming a dull leaden appearance. (If the crystallisation has not begun in five minutes, raise the burner an inch or two.) In from five to ten minutes the whole of the selenium should be crystallised. Then very gradually raise the burner until signs of fusion just begin to appear. This will probably take place when the flame is within 3 inches of the brass. Instantly remove the burner, and in about ten seconds re-crystallisation will occur. Now fix the burner $\frac{1}{2}$ inch below the point at which it was when fusion commenced, and let it remain for four hours, merely looking at it from time to time to ascertain that, owing to increase of gas pressure or other causes, the heat has not become too great. After four hours begin the cooling by lowering the burner an inch or two, and repeat this operation every ten or fifteen minutes, until the burner is at its lowest point. Then slightly lower the gas-flame at short intervals, until it is finally extinguished. When the brass plate is quite cool the cell may be removed.

I may mention that I first made a cell of this form, which I believe to be original, on October 28.[1] If the two wires were wound on a cylinder made of some suitable non-conductor (*e.g.* slate) with a double screw cut upon its surface, a cell might be formed which, it appears to me, would unite all the advantages of Mr. Bell's with far greater simplicity.

My experiments were made with the transmitter and selenium cell above described, a magic-lantern with a 4-inch condenser, the focussing lenses being removed, two plano-convex lenses obtained by separating a 3½-inch condenser, a "blow-through" lime-light, a battery of eleven cells (small Leclanché's answer well), and a pair of Bell telephones. It is essential that the bobbins of the latter be wound with finer wire than that generally used. Mine contain No. 40 (instead of 35 or 36), and I intend to try 42. Their diameter is also larger than usual—1¾ inch.

The transmitter is clamped so that its axis is inclined at an angle of about 30° to that of the lantern condenser, the centre of the mirror being 7 or 8 inches from the centre of the condenser; and the position of the lime-light is so adjusted that the condensed rays may just cover the whole surface of the mirror.

The reflected beam is rendered as nearly parallel as possible by one of the plano-convex lenses (this can only be done approximately), while the other, placed a foot or two away, concentrates the light upon the selenium cell, forming an elliptical image of the mirror. The major axis of the ellipse should be parallel to the length of the cell, and the minor axis slightly longer than its width. A great deal depends upon the focussing, and the best results have been obtained when the image of the mirror was not quite sharp. The selenium cell is joined in circuit with the battery and the pair of telephones, the latter being for obvious reasons placed in a distant room. The arrangements are now complete, and a person listening with a telephone applied to each ear will, if everything is right, plainly hear words which are spoken into the transmitter. When I first made the experiment I was so much astonished at the distinctness of the reproduction that I believed that one of the battery connections must be defective, thus acting like a microphone. This was disproved by screening the mirror, when all sound instantly ceased.

Though the articulation is not perfect, it is far better than I had expected, judging from the accounts of the performances of the photophone in Paris. A leading article might not be altogether intelligible, but ordinary colloquial phrases are readily understood. The loudness of the reproduced speech varies in an unaccountable manner. Sometimes the voice is rendered almost as loudly as in an ordinary telephone; at other times, under apparently the same conditions, it is scarcely audible. Alternations from loudness to faintness, and *vice versâ*, frequently occur in a single sentence.

The distances across which the beam is carried have varied in my experiments from 1 foot (when the two plano-convex lenses were in actual contact) to rather more than 4 feet.[1] With a larger receiving lens this distance could be greatly extended, especially if the electric light were used.

For the "musical" effects produced by an interrupted beam I use a disk of zinc 1 foot in diameter, having eight radial slits cut in it, and mounted upon a vacuum tube rotator. The cell is placed 6 inches from the lantern condenser, and the disk made to rotate close before it. The sound produced is very loud, and can be heard when the telephones are at a distance of a foot or more from the ears.

It is very singular, that whereas I have been so successful in repeating Mr. Bell's more complex experiments, I have utterly failed in all attempts to produce sound by the simple incidence of an interrupted beam upon a thin diaphragm. I have experimented with disks of ebonite varying from $\frac{1}{64}$ to $\frac{1}{4}$ inch in thickness, and with several metals, and can only suppose that my source of light is not sufficiently powerful.

SHELFORD BIDWELL

[1] If a larger surface is desired, two or more of these cells may be placed together side by side, the ends of the wires being properly connected. The width of ¼ inch for a single cell cannot be much exceeded, because the expansion produced by the heat necessary for melting the selenium would make the wires on a wider surface so loose as to touch each other.

[1] With a 5½-inch receiving lens the distance has been increased to upwards of 10 feet.

THE CHRONOGRAPH

MESSRS. E. DENT AND CO., of the Strand and Royal Exchange, London, have been for some time past at work upon three galvanic chronographs of unusual accuracy and power. They surpass in both respects, so far as we know, any similar instruments yet constructed; and we believe, therefore, some account of them will be interesting to our readers. They are destined respectively for the Royal Observatory of Brussels, for the Japanese Government, and for the Egyptian Government.

The advantages of the "chronographic" registration of the times of observations in observatories are not to be gainsaid. In the absence of any such arrangement an astronomer, whilst watching through his telescope, has to compute the time by counting up the clock-beats. More often than not he will find that no clock-beat exactly coincides with the instant of his observation. He must then reckon the difference—the fraction of the second elapsed—by judgment as best he is able. Skilled observers can reckon to tenths of seconds, but these are large and coarse amounts compared with what may be noted upon such chronographs as those we are referring to. In any case the astronomer must make a hurried memorandum of his results; otherwise he is liable to forget them.

The Astronomer-Royal was, we believe, the first to introduce a system of astronomical chronographic measurement into England; and he designed and had constructed at the Royal Observatory a large apparatus for the purpose. The reader must bear in mind that though differing in some respects both in their mechanism and the means employed, the chronographs we are going to describe are fundamentally the same as the Astronomer-Royal's.

C C (see Fig. 1) is a cylinder around which one thickness of paper is wrapped, and underneath it is a long screw W W. A wheel on the axis of C C gears into one mounted on W W; thus when the cylinder turns, the screw turns. W W is tapped through the lower portion of a carriage K (compare Fig. 2), and K rests on rails parallel with W W. When the screw W W turns, K cannot turn too, and is therefore propelled by the screw up or down the rails underneath the cylinder.

L is clockwork which drives the screw, and consequently the cylinder and carriage. The rapidity with which L moves is regulated by the pendulum P P. P P is a conical pendulum; that is, instead of oscillating, it swings round in the surface of a cone. P P is suspended by two pairs of springs S S, S S at right angles to each other.

Let us consider the actions of C C and K (see Fig. 2). K carries two prickers, one of which is placed in electrical communication with the Observatory standard clock. It



Fig. 1.



Fig. 2.

is so arranged that at every beat of the standard clock (except the 60th second of each minute) the pricker shall rise and puncture the paper wrapped round the cylinder. Now suppose that whilst the clock keeps pricking, the cylinder is turning, and the carriage K moving to the left. Then we shall get a succession of pricks marked off upon the cylinder in the form of a slightly inclined spiral, and the distance between each prick will represent one second. Every 60th prick (or second) being omitted, the occurrence of each minute is easily distinguished.

The carriage K carries another pricker alongside the clock-pricker — this is the observation-pricker. The observation-pricker is placed in electrical communication with any instrument in the observatory the astronomer may be going to use, and it is so arranged that the astronomer by merely pressing down a stud can cause the observation-pricker to rise and puncture the paper on the cylinder. This it will do somewhere alongside the spiral of clock-pricks. By reference to the latter the time of the observation can then be determined to the $\frac{1}{100}$th of a second.

Let us examine the pricks on the cylinder (Fig. 2). The spiral of the clock-pricks winds around the cylinder

from left to right. As the cylinder turns once in two minutes, there is between each prick and its fellow similarly positioned on the next spiral a difference in time of two minutes. As stated above, we note by the absence of the pricks the occurrence of the minutes. By reference to the figures placed (for explanation) along the top and side of the section of the cylinder, we see that the time of the highest prick on the left-hand spiral was 9h. 12m. 46s. Following the course of the spiral down towards the



FIG. 3.

pricker which is tracing it, we first pass the blank line indicating the occurrence of the next minute, and then come to three observation-pricks at about the 8th and 9th seconds beyond it. These in practice would be measured off and their values determined to the $\frac{1}{50}$th or $\frac{1}{100}$th of a second. There are other observation-pricks at the 22nd second, the 24th, and 25th, and there is a group of others at about the 40th.

When all the observations have been reckoned up the paper is put away, and it is not the least advantage of

FIG. 4.

the "chronographic" method that in any case of doubt the original observation can be itself referred to years afterwards.

As the paper is moving whilst being punctured, the prickers have to be mounted on springs to enable them to yield a little. In Fig. 3 is a side view of the pricker, G G being the spring, and C C a portion of the cylinder.

There is no difficulty in reading off the observations after a little practice: but in order to facilitate the eye in following the sequence of the punctures—before the paper is used a continuous spiral line is ruled upon it which shall exactly correspond with their course. This is done in the following way (see Fig. 1):—At T are two clutch-wheels, which connect the screw and cylinder with the clock-work L. By moving a lever near them the clock-work is thrown out of gear, and simultaneously the winch on the left is thrown into gear with the screw. On the carriage K (see Fig. 2) is a little roller E, and by moving a handle this is sprung up against the paper on the cylinder. The winch before referred to is now turned, the cylinder rapidly revolves, and the carriage quickly traverses the screw, the spiral line meanwhile being traced by the pressure of E upon the paper of the cylinder. To prevent damage to the prickers during the operation, the act of disengaging the clock-work breaks their electrical communication, and they can neither of them be raised until the clutch-work is restored. The cylinder moves very swiftly whilst the line is being traced, and were it brought to a standstill suddenly great damage would be done. To prevent this it is arranged that when the carriage K is approaching either extremity of the screw it shall work a brake arrangement B B, which brings the machinery quietly to repose. The act of putting the clutch-wheels T into position again also releases the brake. The clutch-wheels T are mounted on a spring, so that should their teeth not correspond when they are put into gear, one will give and wait for the other to overtake it.

It is desirable that the clock L should drive C C with great uniformity; and as the time of a conical pendulum is affected in a very great degree by any variation in the force of the clock-train, a special governing arrangement, the invention of the Astronomer-Royal, is employed. U (see Fig. 4) is a trough filled with glycerine and water. Power reaches the pendulum by means of its connection with the vertical spindle seen at the centre of the trough, which rises from the clock-work. In this connection there is a joint, and a dipper D forms part of it. Too much power drives out the pendulum, and it would then go faster, were it not that the dipper, entering the glycerine and water more deeply, checks its motion. On the other hand, whenever the power falls off the pendulum performs a smaller circle, thereby lifting the dipper a little more away from the liquid, and diminishing the resistance in exactly the same proportion as the force. The pointer X is a very delicate index of the angle the pendulum is swinging. The compensatory action of this governor is very considerable; doubling the power produces no perceptible difference in the time. The quickness with which it works is surprising; an infinitesimal change in the power is immediately indicated on the scale A, showing how well the apparatus is doing its work.

To prevent damage to the governor and the more delicate clock-wheels by any sudden check to the cylinder, a ratch-wheel arrangement has been introduced, which, when the cylinder is suddenly stopped, enables the pendulum to run on until it comes to rest gradually, by want of power.

Fig. 1 gives a very faint idea of the dimensions of the apparatus. The cylinder C C is 12 inches in diameter, and 30 inches long. Its weight is about 70 lb. The space between each seconds prick is $\frac{3}{10}$ inch, and the distance between the successive turns of the spiral of pricks $\frac{3}{16}$ inch. There is room on the paper for 200 spirals, and as each is more than one yard long, we can get more than 200 yards ($6\frac{2}{3}$ hours) of continuous observation without disturbing the instrument. There is always a spare cylinder covered with paper kept ready to replace the first.

The iron base-plate on which the instrument is mounted weighs over 3 cwt., the rails on which the carriage K runs are cast in one piece with it, and, along with all other bearing surfaces are planed. The pendulum, which weighs some 18 lb., and is compensated, goes round once in two seconds. Its suspension-piece weighs 2 cwt. As

regards the accuracy of the construction of these chronographs, the best criterion is to be found in the force that is required to work them. We find that 7 foot-pounds per hour drives the clock-work and pendulum; 7 foot-pounds more drives the carriage as well; and only 3 foot-pounds more is wanted for the cylinder—17 foot-pounds per hour for the whole instrument. Considering the resistance of the carriage, the resistance of the glycerine, and the weight of the cylinder, we think the result as surprising as it is satisfactory.

THE BELGIAN ENTOMOLOGICAL SOCIETY

IN April, 1855, a circular with ten signatures was addressed to entomologists residing in Belgium, proposing the formation of a National Entomological Society, the students of Insecta and allies having at that time no organisation, no central meeting-place for interchange of ideas, no special medium in which to publish the results of their researches. The proposal was met by cordial approval, and the first volume of the *Annales* of the newly-formed Society, published in 1857, indicated a strength of forty-seven effective and four honorary members, with Baron de Selys-Longchamps as president. At first its publications were occupied almost entirely by subjects concerning the Belgian fauna, the volumes were thin, and each represented the work of more than one year. The Society was however well grounded, and notwithstanding occasional short periods of depression, it gradually increased in the number of its members, in the wideness of the scope of the papers read at its meetings, and in reputation as one of the leading entomological societies. Naturally the size of the volumes of the *Annales*, and the frequency of their appearance, also increased, and now the Society produces a volume each year that no similar society need be ashamed of. The twenty-second volume appeared in 1879, showing that the weakness inherent on infancy was soon overcome. The list in this volume shows a total of 171 effective Members (including many foreigners, of whom, however, only six are our own countrymen), twelve Honorary Members (including Messrs. Stainton and Westwood), with the addition of Corresponding and Associate Members. It had also at that time acquired the distinction of being recognised by the State and of receiving a certain amount of State aid.

On October 18, 1880, the Society celebrated its twenty-fifth anniversary, rejoicing in the attainment of more than its majority, on which occasion the present President (M. Weinmann) read a short congratulatory address, and the indefatigable secretary (M. Preudhomme de Borre, to whom the Society owes much of its recent success) gave an instructive sketch of the history and progress of the Society. On that occasion an especial honour was bestowed upon its first president, Baron de Selys-Longchamps (recently elected President of the Belgian Senate), by conferring upon him (in spite of his protestations) the title of Honorary President, a graceful tribute to one who for so long had continually used his energies, his social and scientific position, and his purse in furthering its interests.

Even apart from purely scientific considerations, the history of Belgium is so indissolubly mixed up with our own, and the feeling of fraternity so close, that all students of entomology in this country cannot but reciprocate the mutual congratulations that passed on this occasion between the native members; and the hearty and unaffected demonstrations of friendship accorded to our own entomologists who have attended the meetings of the Society show how warmly they welcome those of the foreign members who occasionally visit Brussels. The meetings are held in a room in the Royal Natural History Museum, in which is the library, and in connection with the entomological collection of the Museum. The annual subscription is small, and entitles the members to receive all the publications, including elaborate separate reports of the proceedings at the monthly meetings. We hope soon to see Englishmen figuring far more numerously in the lists of members. R. McL.

A GENERAL THEOREM IN KINEMATICS

THE following theorem with regard to the motion of a rigid body will doubtless be interesting to mathematical physicists :—

In all cases of the motion, parallel to one plane, of a rigid body there is at every instant a point, J, of no acceleration, in the plane of motion; the acceleration of every point, P, in the plane is in magnitude directly proportional to the distance, JP; and its direction makes with JP an angle which, though varying with the time, is at any instant the same for all points in the body.

If ω is the angular velocity of the body at any instant and $\dot{\omega}$ the angular acceleration, the angle between JP and the direction of acceleration of P is

$$\tan^{-1}\frac{\dot{\omega}}{\omega^2}.$$

We have therefore in all cases of uniplanar motion of a solid body an *instantaneous acceleration centre*, which is analogous to the ordinary instantaneous [velocity] centre.

Of course the ordinary equation

$$I\dot{\omega} = L,$$

which holds for motion round an axis fixed in space and in the body, and which expresses that the moment of the external forces about the axis is equal to the moment of the forces of inertia, holds also for the instantaneous acceleration centre.

As a particular case, whenever a solid moves with constant angular velocity, the accelerations are all directed towards the same point at any instant, and it follows that the resultant stress exerted over the surface of any little lump of the matter is a force directed to this point, if no continuous forces act.

This centre can be in any case geometrically constructed by a rule analogous to that for the ordinary instantaneous centre.

When I had hit upon this theorem I mentioned it to Prof. Wolstenholme, who at once looked out for its extension to three dimensional motion. The result is very simple.

In all cases of the motion of a solid body there is at every instant a point, J, of no acceleration; and if at J there be drawn two axes, JA and JB, which are those respectively round which the resultant angular velocity, ω, and the resultant angular acceleration, $\dot{\omega}$, take place, the acceleration of any point, P, is compounded of two—one along the perpendicular, p, from P on JA, and the other perpendicular to JB and to the perpendicular, q, from P on JB, these two components being, respectively,

$$\omega^2 p \text{ and } \dot{\omega} q.$$

It seems surprising that such a simple and general property of the motion of a rigid body should not have been well known long ago. GEORGE M. MINCHIN

Royal Indian Engineering College,
Cooper's Hill, November 6

NOTES

THE awards of medals for the present year made by the President and Council of the Royal Society are as follows :—The Copl y Medal to Prof. James Joseph Sylvester, F.R.S., for his long-continued investigations and discoveries in mathematics; a Royal Medal to Prof. Joseph Lister, F.R.S., for his contributions on various physiological and biological subjects published in the Philosophical *Transactions* and *Proceedings* of the Royal

Society and elsewhere, and for his labours, practical and theoretical, on questions relating to the antiseptic system of treatment in surgery; a Royal Medal to Capt. Andrew Noble, F.R.S., for his researches (jointly with Mr. Abel) into the action of explosives, his invention of the chronoscope, and other mathematical and physical inquiries; the Rumford Medal to Dr. William Huggins, F.R.S., for his important researches in astronomical spectroscopy, and especially for his determination of the radial component of the proper motions of stars; the Davy medal to Prof. Charles Friedel of Paris for his researches on the organic compounds of silicon, and other investigations.

WE regret to have to record the death of M. d'Almeïda, secretary of the French Société de Physique, and editor of the *Journal de Physique*. M. d'Almeïda published a "Traité de Physique" in collaboration with M. Boutin. The *Comptes rendus* of the Academy of Sciences contain a number of his memoirs.

MR. SPOTTISWOODE, president of the Royal Society, was present at the sitting of the French Academy of Sciences on the 15th inst. He witnessed experiments made at Meritens' workshop on the magneto-electric engines which have been ordered by the Trinity House. The trials were successful.

SIR EDWARD REED writes from Corunna to the *Times* of yesterday, pointing out, as we were able to do last week, that the reports as to the injury sustained by the *Livadia* have been greatly exaggerated, and were not more than a few Clyde shipwrights could have repaired in a couple of days. There was no difficulty in getting the two injured compartments put to rights, barring the laziness of the French shipwrights. The *Livadia* returns to Ferrol for the winter, as her services are not required by her Imperial owner.

FURTHER details concerning the earthquake in Austria on the 9th confirm the reports as to its extent and severity. At Agram there were three shocks—the first, at 7.24 a.m., was the most formidable and lasted ten seconds; the second, also severe, occurred at 7.30; while the third, which was much the weakest, took place at 8.28 a.m. The first shock is described as circular. It was followed by violent oscillations from north-north-east to south-south-west. After it the whole town was covered by a dense cloud of dust caused by the falling down of chimneys, walls, and houses in every direction. From Laibach, Marburg, Klagenfurt, Kanizsa, Serajevo, Derwent, Brod, Pola, Trieste, Cilli, and the region of the river Drave, intelligence has been received of more or less severe shocks about the time of the first great shock in Agram. The earthquake was also felt in both Vienna and Pesth, but so slightly that it attracted the notice of only a few persons. The direction of the motion was everywhere the same, from north-east to south-south-west. As far as can be judged from the information hitherto received, the movement extended from the 44th to the 48th degree north latitude, and from the 32d to the 37th degree of east longitude (Ferro). From almost every district on the right bank of the Danube there is news of a greater or less disturbance with more or less damage done, while from the other side there is no such intelligence from even a single place. It was also felt at Szegedin and on the Theiss. Slight shocks were also felt on the night of the 9th and morning of the 10th, at Agram, and at noon on the 11th, a shock caused a number of houses to fall; the last was preceded by slighter shocks at 5.30 and 11 a.m. The disturbance was continued on the evening of the 11th, and on the morning, afternoon, and evening of the 12th. In the neighbourhood of Agram two mud volcanoes are said to be formed and in full eruption, and several hot springs have risen. The earth has also been rent in many places in the open country, and considerable quantities of mud with hot water and sulphur have been thrown out. The Vienna correspondent of the *Times* writes under the date of November 14: "The earth has been rent in many places in the open country, and considerable quantities of mud and hot water with sulphur have been thrown out. One of the largest of these rents is near the village of Resnik. Agram has often been visited by these earthquakes, especially within the last few years. Indeed scarcely a year has passed without more or less violent shocks." On the night of the 15th–16th there were at least five shocks at intervals between midnight and 4 a.m. Geologists have gone from Vienna and Berlin to Agram to study the phenomena more closely.

MR. J. MUNRO has drawn our attention to the fact that in NATURE, vol. xviii. p. 169, there appeared a short letter signed "J. F. W." and dated from Kew, June 3, 1878, suggesting the principle of Prof. Bell's photophone. The letter is as follows:—"Till now I have looked in vain for any account in NATURE of experiments with the telephone or phonoscope, inserted in the circuit of a selenium (galvanic) element (see NATURE, vol. xvii. p. 312). One is inclined to think that by exposing the selenium to light, the intensity of which is subject to rapid changes, sound may be produced in the phonoscope. Probably by making use of selenium, instead of the tube-transmitter with charcoal, &c., of Prof. Hughes, and by exposing it to light as above, the same result may be obtained. I should be glad to know whether experiments have been made in this direction; for if the above should prove true, there is no doubt that many applications would be the result."

OUR entomological readers will be glad to know that Mr. McLachlan will still continue his valuable services to the *Zoological Record*, reporting as usual on the groups of the Neuroptera and Orthoptera. Mr. Rye will henceforth confine himself to editorial work, while the groups hitherto recorded by him will be undertaken by Mr. Kirby, who will also do the Coleoptera.

LARGE additions are now being made to the Muséum d'Histoire Naturelle in the Jardin des Plantes at Paris. A new front is being erected and two new sides, which, combined with the former "Galerie," will form a hollow square. This square will be covered with glass and used for the exhibition of skeletons of whales and other specimens of inordinate dimensions. The total cost of these buildings is estimated at five million francs (160,000*l.*).

UNDER the auspices of the Russian Geographical Society M. Merejkovsky has been investigating the prehistoric anthropology of the Crimea. He has explored numerous caverns and made large collections of skulls, and the conclusion he comes to is that the age of stone in the Crimea may be divided into three periods: 1. Diluvian period, with mammoth fauna and arms of large dimensions, rudely worked. 2. Alluvial period, with contemporaneous fauna and the use of the arrow. 3. A later period, remarkable for the use of stone arrows, with scarcely any arms of large dimensions. In the Ural M. Malakhof has obtained important results, both geodetical and anthropological. He believes he has discovered on the Neïva, 75 versts from Ekaterineborg, traces of a prehistoric city.

A REGULAR analysis of the air is carried on by M. Davy at Montsouris. It has been found that the number of bacteria was twice greater than usual during the last period of high mortality.

THE President of the French Republic has established telephonic communication between the Elysée and the Chamber of Deputies, as well as the Senate. The first message of this instrument was the intelligence that the Cabinet had been placed in a minority.

AN interesting exhibition took place on Sunday, the 14th, at the Paris Conservatoire des Arts et Métiers, Rue St. Martin. The *portefeuille* of Vaucauson was opened for the first time to

public inspection. On this occasion the most important documents of this collection were affixed to the walls, with a number of other articles belonging to the archives. The most interesting is certainly the original letter written by Fulton to Mollard explaining to him the principles of steamboat construction. The letter is very long and exhaustive, and is accompanied by a drawing. M. Mollard returned a very cold answer after having meditated for a full month, and he says that "Mr. Fulton's communication will be lodged in the archives of the Conservatoire." The date of Fulton's communication is the beginning of Pluviose, An. 11; Mollard's answer is not exhibited, but has been seen by our correspondent.

THE Jablochkoff light has been introduced by M. Hervé-Mangon into the Conservatoire. It will be fed by a Gramme machine, which the establishment has purchased for its constant use. The light will be placed in the amphitheatre, where M. Hervé-Mangon delivers, twice a week, his own lectures.

THE lighting of the Victoria Station of the District Railway by means of the Jablochkoff electric light has been so successful that it has been also applied to the Charing Cross Station, and will shortly be introduced at Earl's Court.

M. MARTIN is engaged in polishing the object-glass of the large refracting telescope now building at the Paris Observatory. The diameter of this exceptional lens is 73 centimetres, and its weight 200 kilograms. The quality of the glass having proved defective it has already broken twice, and the operation is now being made on the third casting.

ON the occasion of the opening of the Ronalds Library at the Society of Telegraph Engineers, a considerable number of rare and curious books relating to electricity, magnetism, navigation, &c., was exhibited. A list of these has been printed and would be valuable to any one interested in the history of the departments of science concerned.

A GOOD example of the thoroughness of German education is given in the publication by Brockhaus of Leipzig of an "English Scientific Reader," edited by Dr. F. J. Wershoven, its purpose being to familiarise students with the style and terms used by the best English scientific writers. The first part relates to physics, chemistry, and chemical technology, and the extracts are made with great judgment. Among the authors from whom selections are made are Clerk-Maxwell, Fleeming Jenkin, Crookes, Roscoe, Lockyer, Rankine, Bloxam, George Wilson.

WE have received the first two volumes of a new "Bibliothèque Belge," for the popularisation of the sciences and arts, published at Mons by Manceaux. The two volumes received are "Traité élémentaire de Météorologie," by MM. J. C. Houzeau and A. Lancaster, two names well known in connection with this subject; and "Zoologie élémentaire," by Prof. Felix Plateau, whose name must also be familiar to our readers in connection with original research in a special department of the subject. Both volumes are well printed and illustrated. Among the volumes to follow are "Palæontology and Conchology," by A. Briart; "Geology," by F. Cornet; "Botany," by F. Crépin; "Mineralogy," and "Mineral Physiology," by L. L. de Koninck; "Mechanics," by H. Hubert; "Astronomy," by M. Niesten; "The Beginnings of Animal Life," by E. van Beneden; and "Physics," by vand der Mensbrugghen.

PROF. CORNELIUS DOELTER of Gratz was to proceed on the 15th inst. to Paris, thence to set out on a mission of scientific investigation to West Africa.

ACCORDING to official reports of the statistics of Bosnia and Herzegovina, these contain 1272 parishes, 43 towns, 31 markets, 5042 villages, 189,662 houses, 200,747 dwellings. Of the 1,158,440 inhabitants 607,789 are male, 550,681 female, 448,613 Mahommetan confession, 496,761 Greek-Oriental, 209,391 Roman Catholic, 3426 Jewish, 249 other confessions.

THE Procureur-General of Paris having complained, in his official address on the occasion of the opening of the courts, that the legal experiments in cases of poison were executed without sufficient precautions being taken against the professional prejudices of the operator, all the medical advisers of the criminal courts in Paris sent in their resignation, after having taken the advice of the Dean of the School of Medicine and other scientific authorities. Their number is nineteen.

A FAIRLY satisfactory Report is given by Surgeon-Major Bidie on the Government Central Museum at Madras. The number of visitors, especially female, continues to increase, and the special arrangements for native ladies attracted an average of 116 on the afternoon of the first Saturday of each month.

THE *Garden* has increased its size and reduced its price, introducing several improvements.

LORD GIFFORD, one of the Scotch judges, in opening the session at the Edinburgh School of Art the other day, summed up very neatly the advantages which a full and accurate scientific knowledge would bestow on those who were engaged in any practical work whatever—(1) That scientific knowledge of their subject would make work, whatever it was, intelligent, not mechanical; (2) it would make their work skilful and easy; (3) it would enable them to produce more exact and perfect work; (4) it would make their work advancing and progressive; and (5) it would make their lifework in itself delightful, and a source of pure and profound joy.

A VERY favourable Twelfth Report of the Working Men's College is issued. This institution completed its twenty-fifth year last year, and during its existence has doubtless done much good. The science classes have attracted an increasing number of students in recent years.

UNDER the title of "The Free Libraries of Scotland" some useful information is brought together in a pamphlet by "An Assistant Librarian." The towns in Scotland in which there are free libraries are Airdrie, Dundee, Forfar, Galashiels, Glasgow (Mitchell Library), Hawick, Paisley, Thurso. The University towns of Edinburgh, Aberdeen, and St. Andrews are still without such useful institutions; the Act has been adopted in Inverness and Dunfermline; Arbroath has twice rejected the proposal to adopt the Free Libraries Act.

WE are glad to notice that the Highbury Microscopical and Scientific Society is increasing in numbers and has some good papers promised for the new year. It gave its fourth annual *soirée* at Harecourt Hall on October 14, and the president, Mr. Frederick Fitch, F.R.M.S., gave his address on the "History of the Microscope and Microscopic Research" on October 28. On Saturday, the 13th inst., a visit will be paid to the Museum of Practical Geology under the guidance of Prof. Rudler, F.G.S.

IN the *Transactions* of the Royal Society of Victoria, April 1880, recently received, the Rev. R. H. Codrington contributes some valuable "Notes on the Customs of Mota, Banks Islands." Since Mr. Tylor in his "Early History of Mankind" so graphically sketched the remarkable custom of the "*couvade*" all information as to its further geographical distribution is ethnologically valuable, and Mr. Codrington here adds the Banks Islands to the area in which it is practised. There is also a tradition that among the inland mountains there is or used to be a race of wild men, which agrees with the stories that are current in most of the Asiatic Islands. The *Mota* practices here described are not to be confounded with those of the *Motu* of New Guinea.

A NEW destructive insect is recorded from America; *Cetonia inda*, a beetle which, according to the *American Naturalist*, was harmless, feeding on the sap of freshly cut maple-trees, has within two or three years become very abundant and destructive in different parts of New England. During the past summer it collected in great numbers on green corn, "eating the kernels and partly destroying a field in Middleboro, Mass."

FAVOURABLE reports reach us as to the thriving condition of the Botanical Gardens, Peradeniya, Ceylon, under the direction of Dr. Trimen, who recently succeeded Dr. Thwaites. In the experimental nurseries, our contemporary the *Colonies* says, good work was being done. Every effort was being made to extend the cultivation of *Cinchona*, the export of which for the season, up to the date of latest advices, had been 1,135,236 lb. In the district of Kotmale report represented the india-rubber tree as flourishing, and the export of its valuable juice from the colony may, it is hoped, be eventually looked upon for supplementing the falling off in export of this valuable article from the forests where it is indigenous.

THE *Colonies and India* draws attention to the riches of the New Zealand forests in their indigenous timbers. Though the woods of New Zealand, like those of Australia, are by no means unknown in this country, owing to the assistance afforded for making their acquaintance through the various International Exhibitions, they are nevertheless almost unknown in commerce in consequence of their extreme hardness and the cost of freight in bringing such heavy material so long a distance. Our contemporary thinks that the timbers "will become of much greater value when it is more generally known when to cut and how to season them." We are told that experiments in this direction are being made in order to test their value for various purposes. Several of the best woods are enumerated, and it is said of the "Matai" (*Podocarpus spicata*) that Mr. Buchanan "reports having found a tree of this species prostrate on a piece of land near Dunedin, which from various circumstances was estimated to have been exposed for at least three hundred years in a dense damp bush under conditions most favourable to decay. It was still however sound and fresh."

MAMMEE APPLES (*Mammea americana*) are, we understand, being exported in quantities from the West Indies to New York. The result of the experiment is being watched with some interest.

IN the last number of the *Revue d'Anthropologie* has appeared not only an excellent photograph of the late Dr. Paul Broca, but also a biographical sketch and a complete list of his various contributions to science. His contributions to medical science commence in 1847, and his first anthropological memoir bears date 1850; from these dates to the time of his death this "Bibliographie" is a record of both untiring industry and scientific production, which will be remembered as long as anthropology remains a science.

OUR ASTRONOMICAL COLUMN

THE SOLAR ECLIPSE OF DECEMBER 31.—Although the eclipse of the sun on the last day of the present year will not in any part of these islands amount to six-tenths of the sun's diameter, it is nevertheless as large a one as will be visible until May 28, 1900, and only that on the morning of June 17, 1890, will compare with it in magnitude in the interval. The *Nautical Almanac* furnishes the results of direct calculations for Greenwich, Edinburgh, Dublin, Cambridge, Oxford, and Liverpool. If to the results for the former three observatories we apply the very convenient Littröw-Woolhouse method of distributing the predictions, we shall have the following formulæ for finding Greenwich mean times of first contact, greatest phase and last contact, and the magnitude of the eclipse at any place within or near to the area comprised:—

	h.	m.	
First contact	= 1	41·14	− [9·9891] L + [9·6113] M
Greatest phase	= 2	36·32	− [9·7942] L + [9·3838] M
Last contact	= 3	28·63	− [9·4618] L + [8·7599] M

Where the latitude of the place is put = 50° + L, and M is the longitude from Greenwich in minutes of time reckoned positive to the east, and negative to the west. Quantities in square brackets are logarithms.

Or the following may be substituted with sufficient accuracy, the factors of L and M being now numbers:—

	h.	m.	
First contact	= 1	41·14	− 0·98 L + 0·41 M
Greatest phase ...	= 2	36·32	− 0·62 L + 0·24 M
Last contact	= 3	28·63	− 0·29 L + 0·06 M

and the magnitude will be = 0·368 + 0·013 L − 0·002 M. If we test these formulæ upon Oxford, the latitude of which is 51° 45′ 36″, longitude 5m. 2·6s. W., we have then L = + 1·76°, and M = − 5·04m; then for first contact the expression becomes 1h. 41·14m. + 1·76 × − 0·98 − 5·04m. × 0·41 = 1h. 41·14m. − 1·72m. − 2·07m. = 1h. 37·35m. Greenwich mean time, or applying the longitude − 5·04m. = 1h. 32·3m. agreeing with the *Nautical Almanac*, and similarly for the other phases. The differences from direct calculations will be within 0·2m., if the place is not too distant.

THE DUNECHT COMET.—There appears to be no doubt now that the comet discovered by Mr. Lohse at Lord Lindsay's Observatory on November 7 is the same as that detected by Mr. Lewis Swift at Rochester, N.Y., on October 11, which had not been previously observed in Europe. The elements, according to the calculations of Mr. S. C. Chandler, jun., of Boston, U.S., and those of Dr. Copeland and Mr. Lohse at Dunecht, have great resemblance to the elements of the third comet of 1869, discovered by M. Tempel, and there seems a probability that he may thus be found to have detected no fewer than four comets of comparatively short period. If the revolution of this comet should prove to be performed in a little less than eleven years it will be found that it must approach very near to the orbit of Mars shortly before the descending node, and, which is of more importance, within 0·4 of the earth's mean distance, from the orbit of Jupiter in about heliocentric longitude 257°. Mr. Chandler sends us elements calculated from approximate positions on October 21, 25, 28, and in his letter dated November 2 points out their great similarity to those of the Comet 1869 III., and in a circular received from Lord Lindsay we find an orbit computed from Dunecht observations on November 7, 9, and 10; we have thus for comparison:

	Comet of 1880.		Comet of 1869.
	Chandler.	Copeland and Lohse.	Bruhns.
T ...	Nov. 7·714	... Nov. 6·6127	Nov. 20·7168
	° ′	° ′ ″	° ′ ″
π ...	41 41·0	... 40 24 10	41 17 13
Node ...	295 25·4	... 300 49 41	292 40 29
i ...	7 21·7	... 7 22 13	6 55 0
Log. *q* ...	0·04262	... 0·043314	0·042416
Motion.	Direct.	Direct.	Direct.

Mr. Chandler's T is for meridian of Washington, the other two for that of Greenwich. An ephemeris which he adds proves the identity of Swift's comet with that found by Mr. Lohse.

It may be remarked that, taken as a whole, there is a distant resemblance to the elements of the comet of Biela.

INTRODUCTORY LECTURE TO THE COURSE OF METALLURGY AT THE ROYAL SCHOOL OF MINES [1]

THE distinguished metallurgist who has held this lecturership since the foundation of the Royal School of Mines, concluded the introductory lecture he delivered more than a quarter of a century ago [2] by pointing out to the students who were then beginning their course that "in proportion to the success with which the metallurgic art is practised in this country will the interests of the whole population, directly or indirectly, in no inconsiderable degree be promoted." This is a fact that none of his students are likely to forget.

Looking back on the actual advance of this country during the

[1] By Prof. W. Chandler Roberts, F.R.S., Chemist of the Mint. Condensed by the Author.

[2] *Records* of the School of Mines, vol. i. pt. 1 (1852) p. 127.

past thirty years, and remembering that the success with which any manufacturing art is practised must bear a direct relation to the way in which it is taught, we cannot but feel how greatly this development of metallurgical knowledge must have been influenced by Dr. Percy's labours. During this period the conditions under which metallurgy is practised have changed considerably; for the field of knowledge has so widely extended, the scale on which operations are conducted is now so great, and the mechanical appliances they involve are so varied and complicated, that while the interest of our subject is deepened its difficulty is gravely increased.

In turning to the history of metallurgy, more especially in its relation to chemical science, it is easy to be led away by the charm of the antiquarian riches of our subject into devoting too much time to this kind of literary research; I may remind you however that much of what is both interesting and full of suggestion, even at the present day, is to be found buried in the treatises by the old writers whose work we inherit and continue.

Primitive metallurgical processes are referred to in some of the oldest known historical records; naturally therefore the development of metallurgy as a science must have been long preceded by its practice as an art, an art for which a place has even been claimed among the religious systems of antiquity.[1] The earlier literature of the subject consists mainly of descriptions of processes; but it is well known that chemistry was to a great extent built up on a metallurgic basis, and Black's singularly advanced definition of chemistry as the "effects produced by heat and mixture"[2] might well be applied to metallurgy. But of all the phenomena of our subject, probably none have more contributed to advance the science of chemistry than those bearing upon the relations between oxygen and lead; indeed the interest attaching to the mutual behaviour of these two elements is so great that I propose devoting a few minutes to its consideration, more especially as I am anxious to indicate the influence of an ancient process on the scientific views of the present day.

When lead is melted with free access of air, a readily fusible substance forms on its surface. This substance may be allowed to flow away, or if the metal is contained in a suitable porous receptacle, the fusible oxide sinks into this containing vessel; in either case the oxidation of the lead affords a means of separating it from precious or inoxidisable metals if any were originally present in the lead. The above fact has been known from remote antiquity, and the early Jewish writers allude to it as old and well known. They clearly show, for instance, that lead can be removed from silver by being "consumed of the fire," while the silver is not affected. That the Greeks knew and practised the method is abundantly proved, if only by certain specimens of gold and silver now in the adjoining museum, which were recently discovered by Dr. Schliemann. The Arabians investigated the subject; for passing to Geber,[3] the greatest of the early chemists (he died in 777), we find a remarkable account of cupellation; he also describes the conversion of lead into a fine powder by calcination with much clearness, and he noticed the fact that after calcination the mass has "acquired a new weight in the operation." I think his subsequent observations on the reduction of altered metals from their "calxes" show that he knew the weight to be increased; in any case it is interesting to remember that his work was in a sense quantitative. He moreover was cognisant of the fact that two different substances may be produced by heating lead in air, and he assumed that "in the fire of calcination a fugitive and inflammable substance is abolished." The alchemists refer continually to the subject, and "deliver themselves," as Roger Bacon said, in his "Speculum Alchimæ," "in the enigmas and riddles with which they clouded and left shadowed to us the most noble science." In the middle of the sixteenth century the truly accomplished metallurgist Biringuccio,[4] contemporary of Paracelsus and Agricola, seems to have been specially attracted by the phenomenon in question, and he remarks: "If we had not lead we should work in vain for the precious metals, for without its aid we could not extract gold or silver from the stones containing them. . . . The alchemists also," he said, "make use of it in their operations, calcining it by itself or with other substances; but," he goes on to observe, "the calcination, conducted in a reverberatory furnace, is accompanied by a marvellous effect, the result of which should not be passed by in silence; for lead thus treated increases 10 per cent. in weight, and, considering that most things are consumed in the fire, it is remarkable that the weight of lead is increased, and not diminished." Although he subsequently gives evidence of much accurate knowledge of practical metallurgy, his views as to this particular phenomenon were hardly in advance of Geber's; but we may claim Biringuccio as an early metallurgist, who knew the facts, and recognised that they were theoretically important. It was not until nearly a century later (1630) that a French chemist, Jean Rey,[1] stated that the increase in weight came from the air. The problem attracted much attention in England, and it is not a little interesting that among the very first experiments recorded by our own Royal Society is a metallurgical series relating to the weight of lead increased in the fire on the "copels" at the assay office in the Tower, the account being brought in by Lord Brouncker in February, 1661.[2] [Subsequently, in 1669, John Mayo showed that the increase in weight of calcined metals was due to a "spiritus" from the air.[3] Boyle heated lead in a small retort,[4] and attributed the increase in weight, as Lemery also did,[5] to his having "arrested and weighed igneous corpuscles."[6]

I need hardly point out how important this calcination of lead was considered by those who defended the Phlogistic theory in regard to chemical change, a theory which, for more than a century, exerted so profound an influence on scientific thought. [As this theory originated with a metallurgist, Becker, it was considered at some length, and it was made evident that the main aim of chemical investigation down to the end of last century was the explanation of calcination, combustion, or oxidation, and that lead was especially useful in solving the problem.]

I might perhaps add that the *absorption* of oxygen by molten litharge has furnished M. Ste. Claire-Deville,[7] a physicist and metallurgist, with an important step in the argument as to dissociation, and thus connects the history of the metal with the great advance on the borderland of chemistry and physics in modern times, to which I shall constantly refer.

The above remarks will, I trust, be sufficient to show that conclusions of the utmost importance in the history of chemical theory were based on a very ancient metallurgical process; but I have also selected lead as an illustration, because, in the gradual development of the knowledge derived in the first instance from its metallurgy, there is much that is typical of the mutual relation of theory and practice that still prevails.

When Dr. Percy began his teaching, he considered at some length the kind of assistance that other sciences might be expected to render our subject, considered as a manufacturing art; and this at the time was necessary for two reasons:[8] first, because he was "able to adduce from his own observation several striking cases in illustration of the advantage of the application of science to practical metallurgy; and, second, because the practice of metallurgy, so far as relates to magnitude of operation, having been developed to an unparalleled extent in this country in the absence of specific public instruction on the subject, it was necessary to justify the providing of such instruction."

The absence of accurate knowledge on the part of those engaged in metallurgy was lamented as long ago as 1700, in an "Inaugural Dissertation of Pyrotechnical Metallurgy," delivered, on March 25 of that year, in the University of Magdeburg; no less a person than the great supporter of the theory of Phlogiston, George Ernest Stahl, presided, and the lecturer was

[1] Rossignol, "Les Métaux dans l'Antiquité" (1863).
[2] "Lectures by Joseph Black, M.D.," vol. i. p. 8 (Edin., 1803).
[3] "The Works of Geber," translated by R. Russell (1686), pp. 74, 78, 220, 234.
[4] "Pirotechnia" (Vinegia, 1540), translated into French by T. Vincent (Rouen, 1627), p. 41.

[1] "Essays de Jean Rey" (reprinted in Paris, 1777), p. 64.
[2] MS. Register Book of the Royal Society.
[3] "Tractatus quinque Medico-Physici," p. 25 *et seq.* (Oxonii, 1674).
[4] Collected works, vol. iii. (1744), p. 347.
[5] "Cours de Chymie" (1675), and English edition (1686), p. 107.
[6] I am indebted to my friend Prof. Ferguson, M.A., of the University of Glasgow, whose eminence as a historian of chemistry is well known, for several interesting additional facts in connection with the calcination of metals. After referring to Eck (1489), Glauber (1651), and others, he writes: "One of the most curious passages I know is in the 'Hippocrates Chemicus' of Otto Tachen, or Tachenius, a German who lived at Venice and published his book there in 1666. He describes how lead, when burnt to minium, increases in weight. This increase he ascribes to a substance of acid character in the wood used for burning, and then, by a very curious course of argument, based on the saponifying powers of litharge, makes out that lead is of the nature of or contains an alkali, which combines with the 'occult acid of the fat.' This is a curious anticipation of a very modern classification which brings lead into relationship with the alkalies and alkaline earths, as well as of Chevreul's investigations."
[7] "Leçons sur la Dissociation," 1864.
[8] *Records* of the School of Mines, vol. i. pt. 1 (1852), p. 128.

Fritschius, who said:[1]—"If in any part of the working of metals there is commonly more owing to experience than reason, truly it is in fusion or melting . . . nevertheless if the reason be asked why the business succeedeth well in this way but in another doth not succeed at all, you have no solid answer, but only that most general one, which is most commonly false, viz. that one fire is stronger and another weaker, and so insufficient." It is just a century since Bishop Watson, Professor of Chemistry and Regius Professor of Divinity in the University of Cambridge, pointed out[2] that "the improvement of metallurgy and other mechanic arts dependent on chemistry might best be made by public establishment of an Academy, the labours of which should be destined to that particular purpose;" and the School of Mines, thus foreshadowed, was established in 1851, its principal object being to "discipline the students thoroughly in the principles of those sciences upon which the operations of the miner and metallurgist depend."

Our honoured founder, Sir Henry de la Beche, in his Address at the opening of the School of Mines,[3] said:—"We still too frequently hear of practical knowledge, as if in a certain sense opposed to a scientific method of accounting for it, and as if experience, without that advantage, was more trustworthy than the like experience with it." Such remarks might, with truth, be made at the present day; but it should nevertheless be remembered that many metallurgical works are successfully conducted in this country by so-called practical men. I do not mean the kind of man so forcibly described by Mr. Bramwell[4] as one "whose wisdom consists in standing by, seeing, but not investigating the new discoveries which are taking place around him . . . the aim and object of such a man being to ensure that he should never make a mistake by embarking his capital or his time in that which has not been proved by men of large hearts and large intelligence;" nor do I mean the man who accepts no rule but the "rule of thumb"; but I do mean practical men possessing technical knowledge of a high order, whose careful observation enables them to use the results of past experience in dealing with circumstances and conditions analogous to those they have met with before, and with which long practice has made them familiar. It would be difficult to overrate the value and importance of such knowledge as theirs, and, when we remember the scale on which smelting and other operations are carried on, it will be obvious that this kind of knowledge can only be gained in the works, and not in the laboratory or lecture-room; for, however careful the metallurgical teaching here may be, it can only be practical in a limited sense. At the same time it must be borne in mind that a man trained to scientific methods starts with the enormous advantage of being able to deal with circumstances and conditions that are new to him, and with which therefore he cannot be said to be "familiar." The technical skill that time and opportunity can alone give him will then rest on a solid basis. I repeat, however, that I am anxious at the outset to guard against undervaluing the teaching of experience unaided by reasoning that we should recognise as scientific; for it is only necessary to witness such operations as the roasting of a large mass of ore on the bed of a furnace, or the forging of many tons of iron under a steam hammer, to appreciate the value of the subtle skill of sight and touch on which success depends.

I have thus ventured to trace the relation between scientific and technical men, as hitherto there have been misunderstandings on both sides, or, as Dr. Williamson so well observes:[5]—"Men of detail do not sufficiently appreciate the value and usefulness of ideas, or of general principles: and men of science, who learn to understand and control things more and more by the aid of the laws of nature, are apt to expect that all improvements will result from the development and extension of their scientific methods of research, and not to do justice to the empirical considerations of practical expediency, which are so essential to the realisation of industrial success in the imperfect state of our scientific knowledge."

While it is no longer necessary to justify the scientific teaching of metallurgy, as Dr. Percy did, it is as important as ever that the true relation of Theory and Practice should be clearly understood. It rarely happens that a process can be transferred from the laboratory to the works without important modifications; and we must remember that metallurgy is a manufacturing art, and that, when the truth of a theory has been demonstrated, a dividend has to be earned; this would indeed often be difficult without the aid of the technical man. Practical men have, however, ceased to undervalue science; and the most practical body of men in the world, in the best sense of the term, the iron-masters of this country, on whom its prosperity so largely depends, formed themselves ten years ago into an Iron and Steel Institute, many of the members of which possess high scientific attainments and are distinguished for scientific research.

Let us turn, then, to the advice given us by those who are accustomed to deal with metals on a large scale. Mr. I. Lowthian Bell stated in his address as president of the Institute in 1873[1]:—"If we would avoid the failure of what may be designated unscientific practice, or the failure of impracticable science, we must seek to combine commercial intelligence with a knowledge of those natural laws which form the only trustworthy groundwork of the complicated processes in which we are engaged."

Dr. Siemens[2] said in 1877:—"It is not many years since *practical* knowledge was regarded as the one thing requisite in an iron-smelter, whilst *theoretical* knowledge of the chemical and mechanical principles involved in the operations was viewed with considerable suspicion;" and he adds, with reference to the teaching of the School of Mines and of a general Technical University:—"But it must not be supposed that I would advocate any attempt at comprising in its curriculum a practical working of the processes which the student would have to direct in after-life. . . . Let technical schools confine themselves to teaching those natural sciences which bear upon practice, but let practice itself be taught in the workshop and in the metallurgical establishment."

The president for 1879, Mr. E. Williams, a most eminently practical man, and one of the founders of the prosperity of the great Cleveland iron district, urged[3] "educated intellectual young men, who now hang listlessly about the professions . . . to break through the absurd old prejudice against seemingly rough work," in order that they may act as scientifically trained managers.

I have thus appealed to authorities, because my own practical work has been mainly confined to a limited branch of metallurgy. I say limited, for although, on looking into the matter, I find, to my surprise, that I have during the last ten years been responsible for the fineness of 330 tons of gold and 740 tons of silver, this, though of a total value of forty-seven millions sterling, is a comparatively small bulk of metal, and the operations through which it passes are seldom complicated; but I am none the less convinced that in metallurgical works generally, as in a mint, the work can only be efficiently conducted by taking advantage to the utmost extent of the aid that science has to offer, a mint only differing from other works by the extraordinary care and vigilance which must be exercised to insure accuracy and avoid loss in dealing with the precious metals. Even this difference is less marked than formerly, and as attention to minute details is becoming more and more essential to the profitable conduct of works, my experience in this respect will be useful to you.

As regards the actual training in the school, I believe that our utmost efforts should be devoted to giving the students a thorough acquaintance with scientific methods and metallurgical principles, furnishing them at the same time with as many well-ascertained *facts* as possible. Here I may perhaps be permitted to quote a few words from Prof. Huxley's[4] recent address at Birmingham, as they bear so directly on our subject; he said, "What people call applied science is nothing but the application of pure science to particular classes of problems. It consists of deductions from those general principles, established by reasoning and observation, which constitute pure science. No one can safely make these deductions until he has a firm grasp of the principles; and he can obtain that grasp only by personal experience of the processes of observation and of reasoning on which they are founded."

In one important branch of metallurgy—assaying—the teaching in the School is thoroughly practical, and the operations you may in future be called upon to conduct will not differ from those taught in this laboratory. The teaching will, I am glad to say, be now specially entrusted to my friend Mr. Smith, the value of whose instruction in my own case I gratefully acknowledge.

[1] "Pyrotechnical Metallurgy," by J. C. Fritschius of Schwartzburg (translated in 1704), p. 203.
[2] "Chemical Essays," 2nd edition (1782), vol. i. p. 47.
[3] *Records* of the School of Mines, vol. i. pt. 1 (1852), p. 20.
[4] British Association Report, Brighton (1872), p. 238.
[5] "A Plea for Pure Science" (Inaugural Lecture, University College, London, 1870).

[1] *Journal* of the Iron and Steel Institute (1873), No. 1, p. 12.
[2] *Ibid.* (1877). No. 1, p. 7.
[3] *Ibid.* (1879), No. 1, p. 24.
[4] NATURE, vol. xxii. p. 548.

It can hardly be questioned that until the School of Mines was established the metallurgical success and reputation of this country rested to a remarkable extent on the exceptional skill of its technical men. I think therefore we may fairly be asked to consider whether the metallurgical teaching of the School has been justified, and how far advance has been due to trained scientific thought.

Of all the metallurgical operations conducted in this country, those connected with iron are, of course, the most important. The production of pig-iron alone in the United Kingdom has increased from two million seven hundred thousand tons in 1852 to six million two hundred thousand tons last year, a maximum slightly in excess of this figure having been reached in the year 1872. Now the Bessemer process, the first patent in connection with which was taken out in 1855, has reduced the cost of steel from 50*l.* to 6*l.* per ton, and has changed the whole aspect of the iron and steel manufacture; indeed, the success with which this process alone is conducted may almost be regarded as an index of our national prosperity. Notwithstanding the almost universal depression of trade during the last few years, the outturn of steel has been steadily increasing; and it is estimated that in 1879 this country produced nearly a million tons in the Bessemer converter, double the entire produce of the remainder of the world in the year 1870 by the same process.[1] The outturn of Bessemer steel in America has, however, advanced with still more rapid strides; for last year she actually produced, with far fewer converters, ninety-four thousand tons more than this country. It will be evident, therefore, that every improvement effected in this process is of truly national importance, and I would briefly refer to the greatest that has been introduced in recent years.

In 1855 the fact was established that pig-iron from the blast-furnace contains the greater part of the phosphorus originally present in the ore. Dr. Percy pointed out that phosphorus is not eliminated in a sensible degree in the Bessemer process, as it is in the old process of puddling; and he stated that if the Bessemer process is to be "generally applicable in this country, it must be supplemented by the discovery of a process of producing pig-iron sensibly free from sulphur and phosphorus, with the fuel and ores which are now so extensively employed in our blast-furnaces."[2] The problem, so far as it relates to the elimination of phosphorus, has received the attention of many of the first metallurgists in this and other countries;[3] but the practical application of basic linings in the Bessemer converter is the outcome of Dr. Percy's teaching; for Mr. S. G. Thomas was a student of the School of Mines, and his partner, Mr. Gilchrist, is an Associate. Mr. Snelus is also an Associate, and Mr. Riley long worked in the metallurgical laboratory. The process not only gives hope that it will be possible to utilise the large quantities of ore in the well-known Cleveland district, but is also widely practised with success on the Continent.[4] It is probable therefore that the large deposits of ore in the basin of the Saar, and those of Lorraine and Luxembourg, which in extent are equal to the Cleveland district, while containing a much greater amount of phosphorus, will now be available. During a recent visit to the Hoerde Works in Westphalia, where I witnessed the operation, Herr Massenez, the director, told me that 10,000 tons of "Thomas-Gilchrist" metal have already been produced there since the adoption of the process a few months ago. . . .

I had intended to indicate the metallurgical work done by the more prominent men who have been associated with the school, but I found that it would not be possible, in the brief time at my disposal, to do justice to such as Bauerman, Dick, Gibb, Hackney, Matthey, Pearce, Riley, Willis, and others, whose labours have placed them so high in the ranks of English metallurgists. You will, however, as the course proceeds, have opportunity of becoming familiar with their names.

In referring to the past teaching of the school I must remind you of the importance of rigorous and minute inorganic analysis; and it is the more necessary that I should do so from the fact that the peculiar charm of organic research appears, as has been pointed out by Prof. Abel,[5] to lead the younger chemists to "under-estimate the value and importance, in reference to the advancement of science, of the labours of the plodding investigator of analysis." I am satisfied, however, that, if we bear the traditions of the chemical and metallurgical laboratories of the School of Mines in view, we are not likely to under-rate the importance of analytical work; and much conclusive evidence as to the value of the teaching of the past thirty years is afforded by the labours of the accomplished analysts who have from time to time worked under Dr. Percy's direction.

The direct influence of the School on the success with which metallurgy has been practised in this country has been most marked, and would alone afford an answer to the question whether the possession of high scientific attainments is generally advantageous to the successful conduct of metallurgical works. It must not be forgotten that our subject is constantly receiving valuable aid from branches of science other than chemistry; and this can hardly be better shown than by the growing importance of physical research in connection with metallurgical problems. I would incidentally remind you that it is the more important for us to consider this, because special attention was directed to the question in the evidence given before the Royal Commission on Scientific Instruction,[1] whose recommendations will, it is to be hoped, extend the influence of the School of Mines.

In connection with this branch of our subject a most prominent position must be given to the production of high temperatures, as it will be obvious that we have principally to consider the reactions of the elements when under the influence of heat. In the first half of the present century temperatures higher than the melting point of zinc were not known with any degree of certainty; but in 1856[2] M. Henri Ste. Claire-Deville pointed out that chemistry at high temperatures, that is to say, up to the blue-white heat at which platinum volatilises and silica fuses, remained to be studied. Since then, in conjunction with M. Troost, he has given us certain fixed points, such for instance as the boiling points of cadmium and zinc; and Deville's researches on dissociation have entirely modified the views generally entertained in regard to the theory of combustion. Indeed we owe so much to this illustrious teacher, that the best homage we can offer him will be to work in the directions he has indicated. M Stas has proved that it is perfectly easy to distil even large quantities of silver from one lime crucible to another,[3] a fact which has been taken advantage of by Mr. Lockyer and myself in some experiments on the absorption-spectra of the vapours of certain metals at high temperatures.[4]

As regards scientific advance of a more essentially practical character, the gradual discovery of the fact that in certain cases fuel can be best employed if it be previously converted into gas, and the recognition of the advantages to be derived from a preliminary heating of the gases and the air, has led to the wide adoption of the regenerative system, by which the waste heat of the furnace is utilised for heating the incoming air or combustible mixture of air and gas necessary to effect the required operation. Dr. Siemens has thus shown us how to economise fuel to a vast extent, it being now possible to produce a ton of steel by the use of 12 cwt. of small coal instead of three tons of coke required to melt it in the old form of furnace. By the command of high temperatures, moreover, he has developed new processes in the metallurgy of iron, which are resulting in the replacement of the old "cinder-mixed" wrought iron by "cinder-free" ingot iron and steel.[5] The degree of heat attainable by the regenerative furnace is, however, limited to the temperature of dissociation of carbonic acid and aqueous vapour, so that the temperature never can exceed about 2600° C.; but during the present year[6] Dr. Siemens has employed the far greater heat of the electric arc for the fusion of steel and platinum.[7] Bearing in mind the interest excited by recent experiments on the effect of intense heat on bodies now considered to be elementary, we may expect physicists to look to us for aid in developing the methods of employing high temperatures.

The essential difference in the properties of certain alloys produced by a small difference of composition brings me to one very distinctive feature of metallurgy, the enormous influence

[1] *Times*, December 31, 1879.
[2] "Metallurgy—Iron and Steel" (1864), p. 819.
[3] M. Gruner, *Annales des Mines* (1869), t. xvi. p. 199.
[4] M. Gruner, *Annales des Mines*, part 1 (1879), p. 146; H. von Tunner, *Zeitschrift der berg- und hüttenmännischen Vereins für Steyermark u. Kärnten*, xii. Jahrg., Mai-Juni 1880; Herr J. Massenez, *Engineering*, vol. xxx. (1880), p. 198.
[5] British Association Report, Plymouth (1877), p. 44.

[1] Report, vol. ii. Minutes of Evidence, p. 86 (1874).
[2] *Ann. Chim. et Phys.* [3], t. xlvi. p. 182; *Comptes rendus*, t. xc. (1880), p. 773.
[3] "Sur les Lois des Proportions chimiques" (1865), p. 37.
[4] *Proc.* Roy. Soc. vol. xxiii. (1875), p. 344.
[5] Akerman, *Journal* of the Iron and Steel Institute, No. 2 (1878), p. 360.
[6] *Engineering*, vol. xxix. (1880), p. 478.
[7] Figures convey but little impression as to such high temperatures; but it may be mentioned that Dewar has given 7000° C. as approximately the temperature of the electric arc (Brit. Assoc. Rep. 1873, p. 466), and, according to Rossetti, the true temperature of the sun can hardly be less than 10,000° C. or more than 20,000° C.—*Phil. Mag.* [5], vol. viii. p. 550 (1879).

exerted on a large mass of metal by a trace of another metal or metalloid—that is, by a quantity so small that it appears to be out of all proportion to the mass in which it is distributed.

I think it may safely be asserted that in no other branch of applied science has the operator to deal with quantities that are at once so vast and so minute; and the course will not have proceeded far before you will recognise this fact.

It may be that the trace to be extracted is alone of value—as, for instance, the few grains of gold that can be profitably extracted from each ton of a material, which, though containing only one part of gold in five millions by volume, is thereby entitled to be regarded as an auriferous deposit that can be profit ably worked; or it may be the minute percentage of a metalloid which must be extracted in order that the physical properties of a large mass of metal may not be entirely altered.

[Numerous instances of the influence of small traces of metals and metalloids, including the following, were then given:—]

In 1866 Graham showed,[1] by experiments with which I had the privilege of being connected, that the presence of occluded gases in metals often exerts a marked influence on their molecular structure. In the case of iron he urged that metallurgists should study the effects of occluded gases, more especially carbonic oxide, the weight of which, according to his experiments, could not exceed the $\frac{1}{15}$ per cent. of the weight of iron in which it was present. The significance of such facts is now under consideration by a Committee of the Institution of Mechanical Engineers,[2] and the question of the presence of gas in steel, either occluded or retained in the form of bubbles, is further being investigated by Chernoff,[3] Müller,[4] and others.

M. Nyst, of the Brussels Mint, has lately found that the presence of $\frac{15}{100}$ per cent. of silicon in standard gold will so affect its molecular grouping as to render it possible for a thin strip to bend by its own weight, as zinc would, in the flame of a candle.

The growing importance of physical research in connection with metallurgy is shown by the fact that physical methods are now constantly appealed to by those interested in metallurgy, more especially in the case of iron and steel. We are told, for instance, that the hardness of steel may be correctly inferred from a numerical determination of its coercive force;[5] it is sought to establish the actual nature of the change in the mode of existence of the carbon in steel that accompanies hardening by determining its thermo-electric properties;[6] and the hope is held out[7] to us that the time will soon come when boiler-makers will electrically test their plates, possibly by the aid of the induction-balance, just as they now test them for ductility and tenacity. I can only add the expression of a belief that this powerful weapon of molecular research which Prof. Hughes has given us will yield good results in the hands of some of you.

The results of mechanical tests are also of the highest importance. Not long since the appearance of the fracture of a sample of metal was considered to afford trustworthy and sufficient evidence as to its nature and properties; but such rough methods have given place, in the hands of Kirkaldy and others, to the rigorous physical and mechanical investigation to which metals must now be submitted as a matter of ordinary routine. The results, tabulated or plotted into curves, which mark the influence of each constituent or impurity, form permanent records of the greatest value.[8]

It has only been possible for me to indicate the more important conditions affecting the successful practice of metallurgy. I have traced the relation between technical and scientific workers; but there is yet another condition of somewhat recent growth. The enormous scale on which operations are now conducted renders it more necessary than formerly for those engaged in metallurgical enterprise to seek the aid of capitalists. The result is that a large share in the control of many important works falls to the non-scientific members of the Board of Directors, men of high commercial ability, but whose knowledge of the importance of scientific work is necessarily limited. It is true that they may recognise the necessity for scientific aid in the works with which they are connected, but they are too often unconscious of the labour and difficulty that are involved in the attainment of accurate scientific knowledge. I am convinced, however, that facts are gradually compelling them to recognise that the value of a metal may entirely depend on whether it does or does not contain a trace of impurity, and that the exact method of treatment to be adopted depends much on the character of the materials employed; they will therefore examine more carefully than they have hitherto done the qualifications of men to whom important duties are entrusted, and will insist that the services of only adequately trained metallurgists shall be secured.

I shall have to direct your attention to the minute care with which details affecting commercial interests are now investigated;[1] and your success will further depend on the facility with which you are able to use the "tools of thought" furnished by chemistry, physics, and mechanics. Whether you will ever possess the tact and judgment necessary to direct such works as Dowlais with an army of 10,000 people, obviously depends on personal qualifications which I can but little influence.

I venture to hope that you will, by original research, add to the general advance of science, for, as the late Prof. Clifford has reminded us, what have often proved to be the most useful parts of science have been investigated for the sake of truth, and not for their usefulness.

Dr. Percy found metallurgy practised in this country mainly as an empirical art. He may well feel, to borrow the words of an old writer, that in his hands "the business of metallurgy and essaying has not only been illustrated but also improv'd, amended, and enrich'd"; for his works contain a record of its progress, his teaching and researches have secured it a scientific basis, and he has trained a body of scientific workers, in whose hands the immediate future of metallurgy to a great extent rests. Bearing in mind how much the progress of our science means to England, I cannot but be conscious that, in attempting to continue this work, I undertake a grave responsibility.

[1] *Phil. Trans.* 1866, p. 438.
[2] First Report of the Committee on the Hardening, Tempering, and Annealing of Steel, 1879.
[3] "On the Structure of Cast Steel Ingots." Translated for the Institution of Mechanical Engineers by W. Anderson, C.E (1879).
[4] *Berichte der deutschen chemischen Gesellschaft*, 1879, No. xii. 93; *Glaser's Annalen für Gewerbe und Bauwesen*, August, 1880, p. 138.
[5] Trève and Durassier, *Comp. rend.*, t. lxvx. (1875), p. 799; Watten hofen, *Journal* of the Iron and Steel Institute, 1879, No. 1, p. 305.
[6] Barus, *Phil. Mag.* [5], vol. viii. p. 341.
[7] W. H. Johnson, *Chemical News*, vol. xlii. (1880), p. 70.
[8] V. Deshayes, "Classement et Emploi des Aciers" (Paris, 1880); also *Bull.* Chem. Soc. tom. xxxi. (1879), p. 166.

[1] In illustration of this see an exhaustive mathematical paper on the values of iron ores, by Prof. A. Habets: *Cuyper's Revue Universelle des Mines* (1877), t. i. p. 504.
[2] By Sir William Thomson, F.R.S. British Association, Swansea, Section A.

ON AN EXPERIMENTAL ILLUSTRATION OF MINIMUM ENERGY[2]

THIS illustration consists of a liquid gyrostat of exactly the same construction as that described and represented by the annexed drawing, repeated from NATURE, February 1, 1877, p. 297, 298, with the difference that the figure of the shell is prolate instead of oblate. The experiment was in fact conducted with the actual apparatus which was exhibited to the British Association at Glasgow in 1876, altered by the substitution of a



shell having its equatorial diameter about $\frac{8}{7}$ of its axial diameter, for the shell with axial diameter $\frac{8}{7}$ of equatorial diameter which was used when the apparatus was shown as a successful gyrostat.

The oblate and prolate shells were each of them made from the two hemispheres of sheet copper which plumbers solder together to make their globular floaters. By a little hammering it is easy to alter the hemispheres to the proper shapes to make either the prolate or the oblate figure.

Theory had pointed out that the rotation of a liquid in a rigid shell of oval figure, being a configuration of maximum energy for given vorticity, would be unstable if the containing vessel is left to itself supported on imperfectly elastic supports, although it would be stable if the vessel were held absolutely fixed, or borne by perfectly elastic supports, or left to itself in space unacted on



by external force; and it was to illustrate this theory that the oval shell was made and filled with water and placed in the apparatus. The result of the first trial was literally startling, although it ought not to have been so, as it was merely a realisation of what had been anticipated by theory. The framework was held as firmly as possible by one person with his two hands, keeping it as steady as he could. The spinning by means of a fine cord[1] round a small V pulley of ½-inch diameter on the axis of the oval shell, and passing round a large fly-wheel of 3 feet diameter turned at the rate of about one round per second, was continued for several minutes. This in the case of the oblate shell, as was known from previous experiments, would have given amply sufficient rotation to the contained water to cause the apparatus to act with great firmness like a solid gyrostat. In the first experiment with the oval shell the shell was seen to be rotating with great velocity during the last minute of the spinning; but the moment it was released from the cord, and when, holding the framework in my hands, I commenced carrying it towards the horizontal glass table to test its gyrostatic quality, the framework which I held in my hands gave a violent uncontrollable lurch, and in a few seconds the shell stopped turning. I saw that one of the pivots had become bent over, by yielding of the copper shell in the neighbourhood of the stiff pivot-carrying disk, soldered to it, showing that the liquid had exerted a very strong couple against its containing shell, in a plane through the axis, the effort to resist which by my hands had bent the pivot. The shell was refitted with more strongly attached pivots, and the experiment has been repeated several times. In every case a decided uneasiness of the framework is perceived by the person holding it in his hands during the spinning; and as soon as the cord is cut and the person holding it carries it towards the experimental table, the framework begins, as it were, to wriggle round in his hands, and by the time the framework is placed on the table the rotation is nearly all gone. Its utter failure as a gyrostat is precisely what was expected from the theory, and presents a truly wonderful contrast from what is observed with the apparatus and operations in every respect similar, except having an oblate instead of a prolate shell to contain the liquid.

[1] Instead of using a long cord first wound on a bobbin, and finally wound upon the circumference of the large wheel as described in NATURE, February 1, 1877, p. 297, I have since found it much more convenient to use an endless cord little more than half round the circumference of the large wheel, and less than half round the circumference of the V pulley of the gyrostat; and to keep it tight enough to exert whatever tangential force on the V pulley is desired by the person holding the framework in his hand. After continuing the spinning by turning the fly-wheel for as long a time as is judged proper, the endless cord is cut with a pair of scissors and the gyrostat released.

ON A DISTURBING INFINITY IN LORD RAYLEIGH'S SOLUTION FOR WAVES IN A PLANE VORTEX STRATUM

IN the paper in last week's NATURE under this heading by Sir William Thomson, the lower part of the illustration was inadvertently turned round at the last moment by the printer; the cut should stand as follows:—



SARGASSUM[1]

THIS paper opens with a discussion of the value of the species *Sargassum bacciferum*, the particular species of this genus which is well known as the Gulf-weed. The author considers that the floating plants to which this name has been given are simply fragments of many varieties or species of Sargassum, more particularly of *S. vulgare*. In support of this view he points out that, from the accounts of nearly all authors who have examined specimens, it appears that the lower part of the stem had been broken across, and that it is therefore fair to conclude that they belong to plants which are rooted under ordinary circumstances. This conclusion had been already arrived at by Rumphius, C. Agardh, Rennell, Humboldt, and more recently by G. von Martens; but of these writers Rennell and Humboldt are of opinion that the floating fragments continue to grow, and in this they agree with Thunberg, Meyen, and Harvey. Dr. Kuntze contends that there is not sufficient evidence forthcoming to establish the correctness of this view. He urges that, even admitting that some growth takes place, it is only temporary, and that it therefore affords no ground for regarding these as pelagic plants. The only other cases of growth of Fuci when floating are offered by *Macrocystis pyrifera* (Sir Joseph Hooker, "Flora Antarctica," vol. i.), and by *Fucus vesiculosus* (Mr. Moseley, "Notes by a Naturalist on the *Challenger*"), and doubtless Dr. Kuntze's objections apply to these also. The question naturally arises as to whether these floating plants are actively living, or are dying, or dead.

In the case of Sargassum Dr. Kuntze considers that their bright yellow colour is due to changes taking place, either preliminary to or in consequence of death, in the brown colouring-matter of the attached forms to which he believes the floating fragments belong. Mr. Moseley, however, is of opinion that this is the natural colour of these plants whilst living. It does not appear that any such difference in colour has been noticed in attached and floating specimens of Macrocystis or of Fucus, and this is a fact which is not in harmony with Dr. Kuntze's views respecting Sargassum. Again, the general observation that these floating Fuci have no reproductive organs offers a further difficulty which they do not explain. Dr. Kuntze endeavours to meet the difficulty by stating that he has found receptacles occasionally in free-swimming individuals, and he gives figures of two plants bearing them; but neither from the figures nor from his account of them is it possible to conclude with certainty that the bodies in question are really of a reproductive nature; and he explains the usual absence of these organs in the floating individuals by suggesting that the receptacles, being the most fragile parts of the plant, are the most readily destroyed, and further that, owing to the small number of air-chambers with which they are provided, they would sink on becoming detached. In this case, as in that of the colour, these explanations respecting Sargassum will only become valid when they are found to hold good of Macrocystis and of Fucus also. It is apparent that the

[1] "Revision von Sargas um und das sogenannte Sargasso-Meer." Von Dr. Otto Kuntze (*Engler's botanische Jahrbücher*, Bd. i. Heft iii., 1880). Leipzig, Engelmann.)

evidence offered in support of Dr. Kuntze's views is at present incomplete, and that further researches into the life-history of these plants must be made before these views can be generally accepted.

After an elaborate systematic revision of the genus, Dr. Kuntze goes on to discuss the Sargasso Sea. He draws attention to the wide divergences which exist between the accounts given of it by different travellers. Thus Humboldt and Maury speak of it as a mass of gulf-weed having an area of thousands of square miles, whereas others—Sir Wyville Thomson, for instance—describe it as consisting of small scattered patches. Dr. Kuntze concludes that there is no reason for assigning a definite and constant area to it. It appears that the patches of weed occur more frequently in the region of calms, but at times it is either absent or present only in small quantities even there. A wind blowing for a considerable time in one direction might, under certain circumstances, cause the aggregation of patches into a mass of some extent, such as is to be found, for instance, in the neighbourhood of the Bermudas in spring after the equinoctial gales, but even this would be but small when compared with Humboldt's estimate.

UNIVERSITY AND EDUCATIONAL INTELLIGENCE

OXFORD.—The following gentlemen have been nominated by the Vice-Chancellor as examiners for the Degree of Bachelor of Medicine. In the first examination for M.B. :—S. H. West, M A., M.B. Christ Church; J. A. Dale, M.A. Balliol; A. G. Vernon Harcourt, M.A. Christ Church. In the second examination for M.B. :—T. K. Chambers, M.D., Christ Church; James Andrews, M.D., Wadham; T. P. Teale, M.A., M.B., Brasenose. In the examination in Preventive Medicine :—W. Ogle, M.D. Corpus; G. W. Child, M.D. Exeter; W. F. Donkin, M.A. Magdalen; Douglas Galton, Capt. R.E., Hon. D.C.L.

A Fellowship will shortly be offered by University College for proficiency in biology. The details are not yet announced.

SCIENTIFIC SERIALS

Annalen der Physik und Chemie, No. 10.—On the influence of curvature of the wall on the constants of capillarity in wetting liquids, by P. Volkmann.—Constructions for anomalous dispersion, by E. Ketteler.—On Newton's dust-rings (continued), by K. Exner.—On calculation of the correction for temperature in calorimetric measurements, by L. Pfundler.—Chemical energy and electromotive force of various galvanic combinations, by J. Thomsen.—On the photo- and thermo-electric properties of fluor spar, by W. Hankel.—On electrical elementary laws, by E. Riecke.—Remarks on some recent electro-capillary experiments, by E. Lippmann.—Experimental researches on weakly magnetic substances (third part), by P. Silow.—Researches on the height of the atmosphere and the constitution of gaseous heavenly bodies (continued), by A. Ritter.—Reply to Herr Herwig "On the Heat-Conductivity of Mercury," by H. F. Weber.—Reply to Herr Winckelmann's remarks in a recent number, by the same.

Archives des Sciences Physiques et Naturelles, October 15.—Contributions to a study of the colouring-matters of plants, by J. B. Schnetzler.—Practical study of marine zoology; the zoological station of Naples, by E. Yung.—Sixty-third session of the Helvetic Society of Natural Sciences, held at Brigue on September 13-15, 1880; Proceedings in the departments of Physics and Chemistry, Geology, Botany, Zoology and Medicine.

SOCIETIES AND ACADEMIES

LONDON

Linnean Society, November 4.—Prof. Allman, F.R.S., president, in the chair.—The session opened by Mr. H. C. Sorby showing drawings of some British sea-anemones, with habitat on the upper fronds of long seaweeds in deep water; and he recorded having seen a solitary cream-coloured cetacean on the English coast.—Mr. Arthur Bennett drew attention to a new British Chara (*C. stelligera*), remarkable for the presence of stellate bulbils on the stems.—Mr. E. M. Holmes exhibited two marine algæ new to Britain, viz., *Dasya gibbesii*, from Berwick-on-Tweed, and *Ectocarpus terminalis* from Weymouth; and also species of *Callithamnion*, with antheridia and trichophore on the same branchlet.—Prof. T. S. Cobbold exhibited a remarkable trematode from the horse. It was discovered by Dr. Sonsini at Zagazig during the Egyptian plague, with which outbreak, however, the parasite had no necessary connection. The worm (*Gastrodiscus sonsinonis*) appeared to be an aberrant amphistome furnished with a singular ventral disk, whose concavity was lined with about 200 small suckers having a tesselated aspect. In this respect its nearest approach was a worm infesting a genus of spinny-finned fishes (*Cataphractus*) belonging to the Triglidæ. According to Prof. Leuckart's recent anatomical investigation, however, doubts are thrown on its amphistomoid affinities.—Mr. G. F. Angas showed the leaf of *Hermas giganteæ*, an umbelliferous plant of the Cape used as tinder by the Hottentots.—Mr. E. A. Webb exhibited a monstrous bramble (*Rubus fruticosus*) with flowers represented by elongated axes covered with minute pubescent bracts and apices fasciated.—A communication by Dr. G. Watt was read, viz., contribution to the flora of North-West India. The geographical features of the district are noted. He divides it into three areas: the first range, Ravee-Basin, with magnificent forests of *Cedrus deodara* on its northern slopes, has on the southerly ones vegetation with an Indian facies, being barely outside the humid influence of the tropical rains of the plains; the second range, comprising Pangi, Lower Lahore, and British Lahore, has a flora altogether changed, dry short summers and snow-clad mountains giving a climate and plant-life of quite a different cast; the third range evinces still further change of flora, this assuming a Thibetan type. Some 300 species of plants are noted, four being new.—A paper on the Papilionidæ of South Australia, by J. G. Otto Tepper, was read. The butterflies of this part of Australia are comparatively few in numbers, and sombre colours prevail thus seemingly in harmony with the surroundings of their habitat. The paucity of numbers the author attributes to the dryness of the climate. Notes on the habits accompany the descriptions of the species.—Notes on a collection of flowering plants from Madagascar were read by Mr. J. G. Baker. The flowering plants are less known than the ferns from this interesting island; two new genera are denoted, viz. (1) *Kitchingia*, belonging to the Crassulaceæ, a succulent herb with fleshy sessile leaves and large bright red flowers in lax terminal cymes; (2) *Rodocodon*, a liliaceous plant with red flowers and peculiar spurred bracts: it comes between *Muscaria* and *Urginea*. Thirty new species are described.—Messrs. Edw. Brown, H. E. Dresser, and T. F. Pippe were elected Fellows of the Society.

Mathematical Society, November 11.—Mr. C. W. Merrifield, F.R.S., president, in the chair.—The Treasurer's and Secretaries' reports were read and adopted.—After the ballot had been taken, the gentlemen whose names are given on p. 614 of the last volume were declared duly elected as the Council for the present session.—Mr. S. Roberts, F.R.S., the new president, having taken the chair, Mr. Merrifield read his valedictory address, "Considerations respecting the Translation of Series of Observations into Continuous Formulæ."—On the motion of Prof. Cayley, F.R.S., the address was ordered to be printed in the *Proceedings*.—Mr. H. M. Jeffery, F.R.S., then read a paper on bicircular quartics, with a triple and double focus, and three single foci, all of them collinear.—Mr. Tucker (hon. sec.) communicated parts of a paper by the Rev. C. Taylor, further remarks on the geometrical method of reversion.

Geological Society, November 3.—Robert Etheridge, F.R.S., president, in the chair.—Bernard Barham Woodward was elected a Fellow of the Society.—The President announced that the original portrait of Dr. William Smith, painted by M. Fourau in the year 1838, had been presented to the Society by Mr. William Smith of Cheltenham.—The following communications were read :—On the serpentine and associated rocks of Anglesey, with a note on the so-called Serpentine of Porth-dinllеyn (Caernarvonshire), by Prof. T. G. Bonney, F.R.S., Sec. G.S. Several patches of serpentine are indicated on the Geological Survey map on the western side of Anglesey, near Tre Valley Station, and a considerable one on Holyhead Island, near Rhoscolyn. These really include three very distinct varieties of rocks: (1) compact green schistose rocks, (2) gabbro, (3) true serpentine. The author described the mode of occurrence of each of these, and their relations, the serpentine being almost certainly intrusive in the schist, and the gabbro in the serpentine. The microscopic structure of the various rocks was described in detail, especially of the last. It presents the usual characteristics, and is an altered olivine rock which has contained bronzite. One or two varieties are rather peculiar; an ophicalcite and a compact chloritic schist containing chromite are also noticed.

At Porthdinlleyn there is no serpentine, but a remarkably interesting series of agglomerates and (probably) lava-flows of a basic nature, which may now be denominated diabases.—Note on the occurrence of remains of recent plants in brown iron ore, by J. Arthur Phillips, F.G.S. The fossilising ironstone described by the author occurs at Rio Tinto, in the province of Huelva, Spain, in close proximity to the celebrated copper mines of that name, where it forms a thick horizontal capping of a hill known as the Mésa de los Pinos. In this iron ore Dr. Carruthers has identified the following vegetable remains:—Leaves and acorns of *Quercus ilex*, Linn.; leaves and seed of a two-leaved species of *Pinus*, most probably *Pinus pinea*, Linn.; the cone of *Equisetum arvense*, Linn.; and a small branch of a species of *Erica*. There is also a well-marked leaf of a dicotyledonous plant not yet identified. The plants are evidently all of the same species as are still found growing in Spain. The author attributes this deposit of ironstone to the decomposition, partly by organic agency, of ferruginous salts, derived from the oxidation of iron pyrites, which flowed into a marsh or shallow lagoon. Subsequently to this the valleys of the Rio Agrio and Rio Tinto were eroded, leaving the Mésa de los Pinos with its thick capping of iron ore.—Notes on the locality of some fossils found in the Carboniferous rocks at T'ang Shan, situated, in a north north-east direction, about 120 miles from Tientsin, in the province of Chih Li, China, by James W. Carrall, F.G.S., with a note by Wm. Carruthers, F.R.S. The author described the locality from which he obtained some plant-remains of apparently Carboniferous age, and stated that mining operations had been carried on by a Chinese company in the district since the year 1878. Several seams of coal occur, varying in thickness from 11 inches to 6 feet. Mr. Carruthers stated in a note that the specimens submitted to him belong to a species of *Annularia*, probably *A. longifolia*, Brough, abundant in the British coal-measures, and found both on the Continent and in North America.

PARIS

Academy of Sciences, November 8.—M. Edm. Becquerel in the chair.—The following papers were read:—On the heat of formation of dimethyl, and on its relation with the methylic and ethylic series, by M. Berthelot.—Researches on the Upper Cretaceous of the northern slope of the Pyrenees, by M. Hébert.—Observations on phylloxera, by M. Henneguy. From over three years' observations he is quite convinced that vines not attacked may be saved, and those which have not suffered too much be restored. Vine-growers have three efficacious modes of treatment: sulphocarbonates, sulphide of carbon, and submersion. But the treatment must be repeated each year (at least for a time), and must extend over the whole vineyard. To destroy the winter egg in the bark, decortication and treatment with sulphide of carbons has proved good; also application of flame to the stock with a "pyrophore" (the latter is more effectual than application of boiling water, also easier and more economical). The spontaneous recovery of seemingly dead vines is only temporary; new roots form after abundant rain, and supply sap for fresh shoots. If the insects (which persist) be destroyed before they reach these roots, the vine may quite recover.—Observations on the influence of last season on the development of phylloxera; on insecticides, by M. Boiteau. August and September were so rainy as to be very unfavourable to the insect. Most of the vines that still exist will be saved. Sulphide of carbon is largely used by all kinds of proprietors. Among other directions as to its use, he says, the quantity per square metre should be 15 to 20 gr.—Preparation of a new alimentary substance, *nutricine*, by M. Moride. Raw meat, freed from bones and tendons, is passed into suitable machines with nitrogenised alimentary substances (bread, *e.g.*), which absorb its water, and form perhaps organic combinations with it. The whole is dried in air or a mild stove, then pulverised and sifted. The powder got is grey or yellowish, and has an agreeable taste. With albumen, fats, or gummed water, solid cakes or cubes may be made of it, to be afterwards divided for soups, sauces, &c. The substance is very nutritive, and keeps indefinitely if not exposed to moisture or too great heat.—The Secretary stated that a great many applications had been made for seeds of the vines of Soudan. M. Lécard has published a *brochure* on this vine, and is collecting all the seeds he can to send home.—On algebraic equations; examination of the propositions of Abel, by M. West.—Researches on the transformation of oxygen into ozone by the electric *effluve* in presence of a foreign gas, by MM. Hautefeuille and Chappuis. Even a very little chlorine hinders the transformation, and when introduced destroys ozone previously formed. Nitrogen occasions a larger transformation than if the oxygen were unmixed, and had the same pressure as in the mixture. The formation of ozone in presence of hydrogen is greater than in that of nitrogen. With fluoride of silicium a large proportion of ozone is formed (the *effluve* becoming a luminous rain of fire). The authors theorise on these results.—Action of chlorine and hydrochloric acid on chloride of lead, by M. Ditte.—On the combinations of ammonia gas with chloride and iodide of palladium, by M. Isambert. The tensions of dissociation are weaker at the same temperature the greater the heat of combination.—On the formation of chloroform by alcohol and chloride of lime; equation of the reaction and cause of the liberation of oxygen manifested, by M. Béchamp. *En résumé*, the chloroform is produced without liberation of gas; the swelling is due exclusively to the chloroform, which is in a medium the temperature of which is higher than its boiling point, and to the tension of its vapour; the gaseous liberation only commences when it has completely distilled, and the temperature rises so as to reach that which is necessary to make the mixture of chloride of lime and water boil.—On the organisation and the development of the Gordians, by M. Villot.—M. de Treux described a bolide observed at Amiens on November 2, at 4.58 p.m. Its diameter seemed about a sixth of that of the moon. Visible 10 to 15 sec. the bolide was successively blue, yellow, and red; bright sparks being given out at each change of colour.—A geological map of Spain, by M. de Botella, was presented.

VIENNA

Imperial Academy of Sciences, November 4.—On the theory of so-called electric expansion or electrostriction, by L. Boltzmann.—Measurements of co-vibration for the case of strong deadening, by C. Laske.—On cells and intermediate substances, by S. Stricker.—The psychic activity of the coating of the brain, considered from a physiological standpoint, by L. Schneeder.—Description and sketch of a steerable balloon, by W. Bosse.—On mesitylendisulpho-acid, by J. Barth and T. Herzig.—On the absorption of solar radiation by the carbonic acid of our atmosphere, by E. Lecher.—On some properties of the capillary electrometer, by J. Hepperger.

November 11.—On the Tsubra deer (*Cervus Lüdorffii*, Bohlan), by L. T. Fitzinger.—On the question as to the nature of galvanic polarisation, by F. Exner.—On the latent heat of vapours, by C. Puschl.—Theory of acceleration-curves, by F. Wittenbauer.—On derivatives of cinchonin acid and of chinolin, by H. Weidel and A. Cobenzel.—On croton-aldehyde and its derivatives, by A. Lieben and T. Yeisel.—On reduction of croton chloral, by the same.

CONTENTS

	PAGE
THE FUTURE OF POLAR RESEARCH	49
THE SANITARY ASSURANCE ASSOCIATION	50
HINCKS'S "BRITISH MARINE POLYZOA"	51
OUR BOOK SHELF:—	
Routledge's "Popular History of Science"	52
Hewitt's "Class-Book of Elementary Mechanics, adapted to the Requirements of the New Code"	53
LETTERS TO THE EDITOR:—	
Sir Wyville Thomson and Natural Selection.—Sir C. WYVILLE THOMSON, F.R.S	53
Rapidity of Growth in Corals.—Dr. R. W. COPPINGER	53
Geological Climates.—J. STARKIE GARDNER	53
Order Zeuglodontia, Owen.—SEARLES V. WOOD, Jun. (*With Illustration*)	54
Temperature of the Breath.—Dr. WM. ROBERTS	55
Height of the Aurora.—H. T. H. GRONEMAN	56
Fascination.—L. P. GRATACAP	56
HOMAGE TO MR. DARWIN	57
THE ATOMIC WEIGHT OF BERYLLIUM	57
THE PHOTOPHONE. By SHELFORD BIDWELL	58
THE CHRONOGRAPH (*With Illustrations*)	59
THE BELGIAN ENTOMOLOGICAL SOCIETY	62
A GENERAL THEOREM IN KINEMATICS. By GEORGE M. MINCHIN	62
NOTES	62
OUR ASTRONOMICAL COLUMN:—	
The Solar Eclipse of December 31	65
The Dunecht Comet	65
INTRODUCTORY LECTURE TO THE COURSE OF METALLURGY AT THE ROYAL SCHOOL OF MINES. By Prof. W. CHANDLER ROBERTS, F.R.S.	65
ON AN EXPERIMENTAL ILLUSTRATION OF MINIMUM ENERGY. By Sir WILLIAM THOMSON, F.R.S. (*With Diagrams*)	69
SARGASSUM	70
UNIVERSITY AND EDUCATIONAL INTELLIGENCE	71
SCIENTIFIC SERIALS	71
SOCIETIES AND ACADEMIES	71

NATURE
8s.
4s. 6d.
7s. 6d.
Continent, and

10s. 6d.
15s. 6d.
8s.
rand.

IES.

and Chemical Cha-
n.—On the Molecular
hlorates: L. F. Nilson
Cobalt Salts: Dr. W.
ainst Solid Surfaces of
n.
ouda: Dr. J. Dennis
new element: Rev. G.
of a New Order of
McClean and Harry

Manganese: Spencer
Preparation by means
one and A. Tribe.—On
Pyruvic Series, Part 2:

ects of Pottery: Prof.

opometry: Dr. Paul
enland Wake.
Graham Bell's Photo-

24.
Key to English Spelli-
F. G. Fleay, M.A.
tem of Subdividing the

nglish Art: J. Conyns

7s.

CHROIC).
INK
EVER PRODUCED.
. It has been adopted
y Companies throughout

from the Pen.
er may be applied at the
f writing.
CLAY & SONS, Farring-
NEY & SONS, Newgate
J. AUSTIN & Co., Duke
f Row; and to be had of

), Dublin.

CO.,
O.)
PORTERS OF
ARATUS

S.
NT TELEPHONES,
h Order.
amps for Postage.
iness Card.
NDON, E.C.

THE NEW GAS FIRE
(ON DR. SIEMENS'S PRINCIPLE)
MAY BE SEEN IN ACTION, AND PRICES AND PARTICULARS HAD, ON APPLICATION TO
FRANCIS HAMMOND
5, Chandos Street, Charing Cross,
LONDON, W.C.

ASTRONOMICAL TELESCOPE.
BATEMAN'S
WONDERFUL £5 5s. INSTRUMENT
Is the finest ever yet attempted. 3-inch Achromatic Object Lenses. Entirely constructed of polished brass; 2 ft. 6 in. length, 4 feet to inches; very highly finished with Adjusts and Azimuth Movements, Rackwork, fine Adjustment, one Terrestrial and one Huygenian Astronomical Eyepiece; will show Jupiter's Belts, Crescent Form of Venus, resolve many Nebulæ and Clusters, and divide many Double Stars, &c., &c. Prospectus post free.
J. BATEMAN,
29, CHEAPSIDE; 104, STRAND; ROYAL POLYTECHNIC, 309, REGENT STREET, AND 131, HIGH HOLBORN, LONDON.

NOW READY,
SECOND EDITION,
GRIFFIN'S
CHEMICAL HANDICRAFT.
PRICE 4s. 7d. POST FREE.
A CATALOGUE OF CHEMICAL APPARATUS:
ILLUSTRATED, CLASSIFIED, DESCRIPTIVE.
Demy 8vo. 480 pp. Illustrated with 1,600 Woodcuts.
Most Complete and Cheapest List of Apparatus.
JOHN J. GRIFFIN AND SONS, 22, GARRICK STREET, LONDON, W.C.

R. W. NEEVES,
PHILOSOPHICAL INSTRUMENT
AND
INTENSITY COIL MAKER.
PRICE LIST, FOUR STAMPS.
55, SIDMOUTH STREET, LONDON, W.C.

S. C. TISLEY & Co.,
OPTICIANS,
172, BROMPTON ROAD, S.W.
(Close to South Kensington Museum)
THE PHONEIDOSCOPE
An Instrument for Observing the Colour-Figures of Liquid Films under the action of Sonorous Vibrations.
Being a visible demonstration of the Vibratory and Molecular Motion of a Telephone Plate.
The PHONEIDOSCOPE, with 3 Discs, Bottle of Solution, Descriptive Pamphlet, &c., in Cardboard Box, 10s. 6d.
MANUFACTURED AND SOLD WHOLESALE AND RETAIL BY
S. C. TISLEY & CO., 172, BROMPTON ROAD, LONDON, S.W.
TELEPHONIC ELECTRICITY. All Materials supplied for experimental purposes.
Price Lists of Electrical and Acoustic Apparatus, with Drawings and Description of the Harmonograph, Post Free, 2d.

EAGLE INSURANCE COMPANY,
70, PALL MALL.
FOR LIVES ONLY. ESTABLISHED 1807.
Accumulated Funds — — — — — — £1,043,812
Also a Subscribed Capital of more than — — — — — £1,000,000
Reports, Prospectuses, and Forms may be had at the Office, or from any of the Company's Agents, post free.
GEORGE HUMPHREYS, Actuary and Secretary.

MANUALS FOR STUDENTS.

FLOWER (W. H.)—AN INTRODUCTION TO THE OSTEOLOGY OF THE MAMMALIA. Being the Substance of the Course of Lectures delivered at the Royal College of Surgeons of England in 1870. By W. H. FLOWER, F.R.S., F.R.C.S., Hunterian Professor of Comparative Anatomy and Physiology. With numerous Illustrations. Second Edition enlarged. Crown 8vo. 10*s.* 6*d.*

FOSTER and BALFOUR—THE ELEMENTS OF EMBRYOLOGY. By MICHAEL FOSTER, M.D., F.R.S., and F. M. BALFOUR, M.A. Part I. Crown 8vo. 7*s.* 6*d.*

FOSTER and LANGLEY—A COURSE OF ELEMENTARY PRACTICAL PHYSIOLOGY. By MICHAEL FOSTER, M.D., F.R.S., and J. N. LANGLEY, B.A. Fourth Edition. Crown 8vo. 6*s.*

HOOKER (Dr.)—THE STUDENT'S FLORA OF THE BRITISH ISLANDS. By Sir J. D. HOOKER, K.C.S.I., C.B., P.R.S., M.D., D.C.L. Second Edition, Revised. Globe 8vo. 10*s.* 6*d.*

"Cannot fail to perfectly fulfil the purpose for which it is intended."—*Land and Water.*

"Certainly the fullest and most accurate manual of the kind that has yet appeared."—*Pall Mall Gazette.*

HUXLEY and MARTIN—A COURSE OF PRACTICAL INSTRUCTION IN ELEMENTARY BIOLOGY. By Professor HUXLEY, F.R.S., assisted by H. N. MARTIN, M.B., D.Sc. New Edition, revised. Crown 8vo. 6*s.*

"It is impossible for an intelligent youth, with this book in his hand, placing himself before any one of the organisms described, and carefully following the directions given, to fail to verify each point to which his attention is directed."—*Athenæum.*

HUXLEY—PHYSIOGRAPHY. An Introduction to the Study of Nature. By Professor HUXLEY, F.R.S. With numerous Illustrations, and Coloured Plates. New and Cheaper Edition. Crown 8vo. 6*s.*

OLIVER (Professor)—FIRST BOOK OF INDIAN BOTANY. By DANIEL OLIVER, F.R.S., F.L.S., Keeper of the Herbarium and Library of the Royal Gardens, Kew, and Professor of Botany in University College, London. With numerous Illustrations. Extra fcap. 8vo. 6*s.* 6*d.*

"It contains a well-digested summary of all essential knowledge pertaining to Indian Botany, wrought out in accordance with the best principles of scientific arrangement."—*Allen's Indian Mail.*

PARKER and BETTANY—THE MORPHOLOGY OF THE SKULL. By Professor PARKER and G. T. BETTANY. Illustrated. Crown 8vo. 10*s.* 6*d.*

Other Volumes of these Manuals will follow.

MACMILLAN AND CO., LONDON.

Now publishing, in Crown 8vo. Price 2*s.* 6*d.* each.

ENGLISH MEN OF LETTERS.

Edited by JOHN MORLEY.

*** Upwards of 130,000 Vols. of this series have been issued.

LOCKE. By Prof. FOWLER.

"In the case of Locke's biographer we venture to say that Mr. Morley has been exceptionally fortunate. A pen more competent than Prof. Fowler's for this particular work might have been sought, and sought in vain."—*Examiner.*

BYRON. By Prof NICHOL.

"Decidedly one of the most careful and valuable of the whole series. When a book is so good as Prof. Nichol's, there is little to be said about it except to recommend it as widely as may be."—*Athenæum.*

POPE. By LESLIE STEPHEN.

"The writer's eminent qualities as a critic, his judgment, his wit, his abundant knowledge of eighteenth-century literature, and his keen enjoyment of literary form, have equipped him handsomely for the task he has undertaken."—*St James's Gazette.*

COWPER By GOLDWIN SMITH.

"Mr. Goldwin Smith has sketched, in a few decisive touches, the genius of the poet and weakness of the man."—*Daily News.*

CHAUCER. By Prof. A. W. WARD.

"Far away the best connected account of Chaucer and his works to be found in English."—*Academy.*

BUNYAN. By J. A. FROUDE.

"He has given us a real study of Bunyan's life and character, and at the same time a real study of his books."—*Athenæum.*

SOUTHEY. By Prof. DOWDEN.

"A truly scholarly and delightful monograph."—*Examiner.*

HAWTHORNE. By HENRY JAMES, JUN.

"He has made a careful, conscientious, and even vivid literary portrait, such as few of our own writers could have made."—*New York Nation.*

MILTON. By MARK PATTISON.

"Mr. Pattison's achievement is deserving of high praise. He has put life into old facts, he has taken an impartial estimate of a great man whose name is too often used for purposes of party."—*Spectator.*

JOHNSON. By LESLIE STEPHEN.

"The new series opens well with Mr. Leslie Stephen's sketch of Dr. Johnson. It could hardly have been done better, and it will convey to the readers for whom it is intended a juster estimate of Johnson than either of the two essays of Lord Macaulay."—*Pall Mall Gazette.*

SCOTT. By R. H. HUTTON.

"We could not wish for a more suggestive introduction to Scott and his poems and novels."—*Examiner.*

GIBBON. By J. C. MORISON.

"As a clear, thoughtful, and attractive record of the life and works of the greatest among the world's historians, it deserves the highest praise."—*Examiner.*

SHELLEY. By J. A. SYMONDS.

"The lovers of this great poet are to be congratulated at having at their command so fresh, clear, and intelligent a presentment of the subject, written by a man of adequate and wide culture."—*Athenæum.*

HUME. By Prof. HUXLEY, F.R.S.

"It may fairly be said that no one now living could have expounded Hume with more sympathy or with equal perspicuity."—*Athenæum.*

GOLDSMITH. By WILLIAM BLACK.

"Mr. Black brings a fine sympathy and taste to bear in his criticism of Goldsmith's writings, as well as his sketch of the incidents of his life."—*Athenæum.*

DEFOE. By W. MINTO.

"Mr. Minto's book is careful and accurate in all that is stated, and artful in all that it suggests. It will repay reading more than once."—*Athenæum.*

BURNS. By Principal SHAIRP.

"It is impossible to desire fairer criticisms than Principal Shairp's on Burns's poetry. . . . None of the series has given a truer estimate either of character or of genius than this volume."—*Spectator.*

SPENSER. By the Very Rev. the DEAN OF ST. PAUL'S.

"Dr. Church is master of his subject, and writes always with good taste."—*Academy.*

THACKERAY. By ANTHONY TROLLOPE.

"Mr. Trollope's sketch is excellently adapted to fulfil the purpose of the series in which it appears."—*Athenæum.*

BURKE. By JOHN MORLEY.

"It is no disparagement to the literary studies already published in this admirable series to say that none of them have surpassed, while few have equalled, this volume on Burke."—*British Quarterly Review.*

Others in Preparation.

MACMILLAN AND CO., LONDON.

LADD & CO.,
NSTRUMENT MANUFACTURERS,
nt to the Royal Institution of Great Britain),
EAK STREET, REGENT STREET, W.
HINES. GRAMME'S MAGNETO-ELECTRIC MACHINE for Laboratory use.
WDER—very brilliant—for Paint and other purposes, 3*s.* per oz.
tical Apparatus of every Description.
TED CATALOGUE, SIXPENCE.

TALOGUE OF PHYSICAL APPARATUS.
TURES. Season 1880–1. Post free 6 Stamps.
rimers and all the Physical Text-books in use in Schools and Colleges.
ps for hire.
d Art Departments' Requirements in the Sections of Light, Heat, Sound, and Electricity.
Signals, Lightning Conductors. The Gower-Bell Loud speaking Telephone.
PATERSON, Electrical Engineer.
ES:—56, LITTLE BRITAIN, E.C. (late 3, Bedford Court, W.C.).
executes the Harmonic Curves in the most perfect manner. 1*s.* and 2*s.*
Part 1, *post free*, 6 *Stamps. Plate, Electric Signals, Part* 2, 6 *Stamps.*

Medium 8vo, price 18*s.* Vol. I.
A TREATISE ON
VE EMBRYOLOGY.
BY
LFOUR, M.A., F.R.S.,
ad Lecturer of Trinity College, Cambridge.
In Two Vols. Illustrated.
LLAN AND CO., LONDON.

FIC WORTHIES.
D BY THE LATE C. H. JEENS.
the Portraits that have appeared in the above Series.

SIR WYVILLE THOMSON.
SIR WILLIAM THOMSON.
HERMANN L. F. HELMHOLTZ.
SIR JOSEPH DALTON HOOKER.
WILLIAM HARVEY.
SIR GEORGE B. AIRY.
L. LOUIS R. AGASSIZ.
RICHARD OWEN.

5.
India paper, may be had from the Publishers, price 5*s. each, or*
fit in Handsome portfolio for £1 5*s. carriage paid.*
MAY BE HAD SEPARATELY, PRICE 6*s.*
FEW COMPLETE SETS CAN BE MADE UP.
O.Os payable to MACMILLAN & CO.,
D STREET, STRAND.

VAL.
AKERS,
NDON
ANE).
SCOPE LAMP.
scope.

HOLLOWAYS OINTMENT A CERTAIN REMEDY
For BAD BREASTS, OLD WOUNDS, and SORES. If effectually rubbed on the Neck and Chest, it cures SORE THROATS, BRONCHITIS, COUGHS and COLDS; and for GOUT, RHEUMATISM, and all Skin Diseases it is unequalled.

WANTED, Clean Copies of NATURE, No. 472, *for November* 14, 1878. *Address—Office of NATURE*, 29, *Bedford Street, Strand.*

Messrs. MACMILLAN & CO.'S PUBLICATIONS.

ETCHING AND ETCHERS. By P. G. HAMERTON. New Edition, Revised, with 48 New Plates. Columbier 8vo.

The text of the new Edition has been thoroughly revised, and increased by one-fifth. Several new Chapters and a new Preface have been added, whilst matter which had become unnecessary or disproportionate has been removed, to make room for studies of more importance. *[Immediately.*

LIFE OF WILLIAM BLAKE. With Selections from his Poems and other Writings. Illustrated from BLAKE'S own Works. By ALEXANDER GILCHRIST. A New and Enlarged Edition, with Additional Letters and a Memoir of the Author. 2 vols. Medium 8vo. *[Immediately.*

ISLAND LIFE; or, the Phenomena of Insular Faunas and Floras, with their Causes, including an entire revision of the Problem of Geological Climates. By ALFRED RUSSEL WALLACE, Author of "The Malay Archipelago," "The Geographical Distribution of Animals," &c. Medium 8vo, with Illustrations and Maps. 18*s.*

"The work throughout abounds with interest."—*Athenæum.*

"'Island Life' is a work to be accepted without reservation from beginning to end. . . Whoever reads his book must be charmed with it."—*St. James's Gazette.*

A VISIT TO WAZAN, THE SACRED CITY of MOROCCO. By ROBERT SPENCE WATSON. 8vo, with Map and Illustrations. 10*s. 6d.*

"Mr. Watson's account of his experiences in Morocco is much more pleasant than that of any other traveller's we know of . . . and as a record of an independent and unprejudiced observer his little book, slight as it is, is of value."—*Times.*

IDEAL CHEMISTRY. By Sir BENJAMIN BRODIE, Bart., F.R.S. Crown 8vo. 5*s.*

FOOD FOR THE INVALID, THE CONVALESCENT, THE DYSPEPTIC, AND THE GOUTY. By J. MILNER FOTHERGILL, M.D., Author of "The Practitioner's Handbook," &c. Crown 8vo. 3*s. 6d.* *[Immediately.*

STUDIES IN DEDUCTIVE LOGIC. By W. STANLEY JEVONS, LL.D., F.R.S., Professor of Political Economy in University College, London. Crown 8vo. 6*s.*

"Besides these answers to questions which greatly increase the value of the book, and make it almost an independent manual of the subject, Professor Jevons has taken occasion to supplement his previous works in various directions. It is indispensable to the many students of the higher logic."—*Athenæum.*

GUIDE TO THE STUDY OF POLITICAL ECONOMY. By Dr. LUIGI COSSA, Professor of Political Economy in the University of Pavia. Translated from the Second Italian Edition. With a Preface by W. STANLEY JEVONS, F.R.S. Crown 8vo. 4*s. 6d.*

THE IRISH LAND LAW. By ALEXANDER G. RICHEY, Q.C., LL.D., Deputy Regius Professor of Feudal and English Law in the University of Dublin. Crown 8vo. 7*s. 6d.* *[Immediately.*

With Twenty-five Illustrations by WALTER CRANE.

THE NECKLACE OF PRINCESS FIORIMONDE: and other Stories. By MARY DE MORGAN. Extra fcap. 8vo. 8*s.*

ALSO AN EDITION, Printed by Messrs. R. and R. Clark, on hand-made paper. The Plates, initial letters, head and tail pieces being printed on India paper and mounted in the text.

"The stories display considerable originality, and Mr. Crane's characteristic illustrations combine with Miss de Morgan's pretty fancies to form a charming gift-book."—*Graphic.*

The Edition is limited to ONE HUNDRED COPIES. Fcap. 4to.

ENGLISH MEN OF LETTERS. Edited by JOHN MORLEY. Crown 8vo. 2*s. 6d.*

LOCKE. By Professor FOWLER. *New Volume.*

"In the case of Locke's biographer we venture to say that Mr. Morley has been exceptionally fortunate. A pen more competent than Professor Fowler's for this particular work might have been sought, and sought in vain."—*Examiner.*

A CHRISTMAS CHILD: a Sketch of a Boy-life. By MRS. MOLESWORTH, Author of "Carrots," "The Cuckoo Clock," &c. Illustrated by WALTER CRANE. Globe 8vo. 4*s. 6d.*

PANSIE'S FLOUR BIN. By the Author of "When I was a Little Girl," &c. Illustrated by ADELAIDE STONES. Globe 8vo. 4*s. 6d.*

"Worthy to be classed with 'Alice in Wonderland;' and in some respects is better adapted to juvenile comprehension."—*Morning Post.*

ESSAYS ON ART AND ARCHÆOLOGY. By C. T. NEWTON, C.B., LL.D., Keeper of Greek and Roman Antiquities at the British Museum. 8vo. 12*s. 6d.*

"Mr. Newton deserves the gratitude of all Students of Archæology for these masterly Essays. . . . . are the fruit of a lifetime of exhaustive scholarship, and of such individual research as it seldom falls to the lot of any archæologist to accomplish."—*Westminster Review.*

MODERN GREECE: Two Lectures delivered before the Philosophical Institution of Edinburgh, with Papers on "The Progress of Greece," and "Byron in Greece." By R. C. JEBB, M.A., LL.D., Professor of Greek in the University of Glasgow. Crown 8vo. 5*s.*

"Modern Greece needs but few words of recommendation to those interested in one of the most urgent and important questions of the day. . . . We have to add an expression of our hope that the book, which is both scholarly and popular, will obtain all the success which it certainly deserves."—*Westminster Review.*

CICERO'S LIFE AND LETTERS. Being a Translation of the Letters in Mr. WATSON'S Selection, with Historical and Critical Notes, by the Rev. G. E. JEANS, M.A. 8vo. 10*s. 6d.*

"The style . . . is life-like, and shows literary power, nor is it superfluous to add that it is for the most part really English and idiomatic."—*Academy.*

"Mr. Jeans' translation deserves to take its place side by side with Davies and Vaughan's 'Republic,' and Church and Brodribb's 'Tacitus.'"—*St. James's Gazette.*

HISTORY OF THE ENGLISH PEOPLE. By JOHN RICHARD GREEN. Vol. IV. THE REVOLUTION, 1683—1760. MODERN ENGLAND, 1760—1815. 8vo, with 3 Maps and Index, 16*s.* (Vols. I. to III. 16*s.* each.) *[Concluding Volume.*

"A work that most students of history may turn to with advantage, and that will be almost sure to take rank among the great classics of our literature."—*Globe.*

READINGS FROM ENGLISH HISTORY. Selected and Edited by JOHN RICHARD GREEN. In Three Parts, each 1*s. 6d.*

"We cannot imagine a better reading-book for the highest standard of our elementary schools, but it is a book which will have great charms also for the most cultivated readers."—*Guardian.*

XENOPHON'S ANABASIS. Books I.—IV. Edited by Professors W. W. GOODWIN and J. W. WHITE, of Harvard University. Fcap. 8vo. 5*s.* [Macmillan's Classical Series.

LIVY.—SCENES FROM THE HANNIBALIAN WAR. Adapted for the use of Beginners by G. C. MACAULAY, M.A., Assistant-Master at Rugby. Post 8vo. 2*s. 6d.* [Macmillan's Elementary Classics.

THE STORY OF ACHILLES, FROM HOMER'S ILIAD. Edited, with Notes and Introduction, by the late J. H. PRATT, M.A., Fellow of Trinity College, Cambridge, Assistant Master at Harrow: and WALTER LEAF, M.A., Fellow of Trinity College, Cambridge. Fcap. 8vo. 6*s.* [Macmillan's Classical Series.

MACMILLAN AND CO., LONDON.

Printed by R. CLAY, SONS, AND TAYLOR, at 7 and 8, Bread Street Hill, Queen Victoria Street, in the City of London, and published by MACMILLAN AND CO., at the Office, 29 and 30, Bedford Street, Covent Garden.—THURSDAY, November 18, 1880.

TURE

STRATED JOURNAL OF SCIENCE

"To the solid ground
e mind which builds for aye."—WORDSWORTH

AY, NOVEMBER 25, 1880 [PRICE SIXPENCE

[All Rights are Reserved.

EMENT AND

APER on the F. GRAHAM
ELL, F.R.S.,

ed to apply as ars be admitted of the Society.

, Secretary.

D.
ED POUNDS REATISE wa are known as to be accom-

in the English nglish transla- xst, 1883, and . Each Essay enled envelope

complied with. plication at the

REAT

N.
of Six Lectures on TUESDAY, 30, 1880, and

ainea (Children e Season: Two

RN SLIDES

ty, Magnetism, trium Analysis, tatics, Pneuma- on receipt of 2d.

URER.

SES for ons, under the London, Uni- cientific M.B.,

BROWNING'S MICROSCOPES.

The "COMPLETE" MICROSCOPE, with rack and fine adjustment to body, mechanical motions to stage, removable fittings for apparatus, revolving diaphragm with 3 apertures, A or B eye-piece, 1 in. 1⅝ and ½ in. 75° objectives, of which the performance will be guaranteed.

PRICE £7 10s. 0d.

Price List of Microscopes Free.

A New Edition of the Illustrated Catalogue of Microscopes, with 81 Illustrations, 80 whole page engravings, post free, 7 stamps.

BROWNING'S new Cheap Series of high-power Objectives, ½-in. 85', £3 7s. 6d.; ¼-in. 90°, £2 12s. 6d.; 1/8-in. 95°, £3 3s. od.

JOHN BROWNING,

Optical and Physical Instrument Maker to H.M. Government, the Royal Society, the Royal Observatories of Greenwich, Edinburgh, &c., &c.

63, STRAND, LONDON, W.C.

Factory—Southampton Street and Exeter Street, London.
PRIZE MEDAL, 1862. ESTABLISHED 100 YEARS.
Telescopes, Spectroscopes, Opera Glasses, &c., &c.

SPECTACLES AND EYE-GLASSES

MOUNTED WITH

NEGRETTI & ZAMBRA'S

THERMOSCOPIC LENSES

OR THE FINEST

BRAZILIAN PEBBLES,

In Gold, Steel, or Tortoise-shell Frames.

NEGRETTI & ZAMBRA,

Opticians and Meteorological Instrument Makers

TO HER MAJESTY THE QUEEN,

HOLBORN VIADUCT,

45, CORNHILL, & 122, REGENT STREET, LONDON.

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 48a, Tollington Road, Holloway, London, N.

GEOLOGY.—In the Preface to the STUDENT'S ELEMENTS of GEOLOGY, by Lyell, 1874, he says: "As it is impossible to enable the reader to recognise rocks and minerals at sight by aid of verbal descriptions or figures, he will do well to obtain a well-arranged collection of specimens, such as may be procured from Mr. TENNANT (149, Strand), Teacher of Mineralogy at King's College, London." These Collections are supplied on the following terms, in plain Mahogany Cabinets:—

100 Specimens, in Cabinet, with 3 Trays	...	...	£2 2 0
200 Specimens, in Cabinet, with 5 Trays	...	...	5 5 0
300 Specimens, in Cabinet, with 9 Drawers	...	...	10 10 0
400 Specimens, in Cabinet, with 13 Drawers	...	...	21 0 0

More extensive Collections at 50 to 5,000 Guineas each.

GEOLOGY.

COLLECTIONS FOR TEACHERS AND STUDENTS.

Gold Medal awarded for superiority of these Collections.

New Lists of Prices of Collections, Cabinets, Apparatus, Rock Sections and all Necessaries, of

JAMES R. GREGORY,

88, CHARLOTTE STREET, FITZROY SQUARE.

New and Interesting Minerals constantly arriving.

THOMAS D. RUSSELL'S

NATURAL HISTORY STORES,

48, ESSEX STREET, STRAND, W.C.

Students and others are invited to inspect the Collections of British and Foreign Shells, Corals, Zoophytes, Annelida, Crustacea, Echinoderms, Minerals, Fossils, Rock Specimens, Microscopic Objects, &c.

Cabinets, Geologist's Hammers, Glass Capped Boxes, Card Trays, Tablets, Glass Slips, Micro-Thin Glass, Canada Balsam, Marine Glue, and other requisites for the Geologist and Microscopist.

Catalogues Post Free.

MINERALOGY AND GEOLOGY.

FINE SPECIMENS of ORANGITE, ENSTATITE, BREVICITE, EUXENITE, AUGITE, PYROSMALITE.

UNIQUE SPECIMENS of ADULARIASPHENE and SMOKY QUARTZ.

FINE CRYSTALLISED CROMFORDITES and MATLOCKITE, Derbyshire.

XENOTINE CRYSTALLISED, Valais; WOLLASTONITE CRYSTALLISED.

COLLECTIONS FOR STUDENTS, from £2 2s. COLLECTIONS FOR BEGINNERS, from 42. BLOWPIPE CASES AND APPARATUS.

PRIVATE LESSONS AND EVENING CLASSES.

Catalogues free.

SAMUEL HENSON,

277 (*Late* 113a), STRAND, LONDON, W.C.

GEOLOGY AND MINERALOGY.

JOHN TYM has ready for Sale, at low prices, Educational Collections of Fossils, Rocks, and Minerals, specially arranged to illustrate the text-books of Lyell, Geikie, Bonney, Collins, Davies, Skertchley, Dana, Page, Jukes, &c. Series of Specimens for School and College Museums are also supplied at very reasonable prices. Catalogues post free.

Postal Address:—CASTLETON, *via* SHEFFIELD.

50 ROCKS, 50 FOSSILS, 50 MINERALS,

NEATLY ARRANGED IN A

DEAL CABINET, STAINED AND POLISHED, LOCK AND KEY.

EACH SPECIMEN LABELLED AND CATALOGUED.

Price complete, £1 10s.

THE ROCKS illustrate the Order and Range of Deposition, &c.

THE FOSSILS are representative of the Genera found in the most important Deposits.

THE MINERALS are selected for their known uses in the Arts and Manufactures, and are extremely characteristic.

Names and Localities guaranteed.

THOMAS J. DOWNING, Geologist, &c.,

38, WHITKIN STREET, LONDON, E.C.

Catalogues Free.

On the 1st of every Month.

TRIMEN'S JOURNAL OF BOTANY,

BRITISH AND FOREIGN.

New Series. Edited by JAMES BRITTEN, F.L.S., British Museum.

CONTENTS.—Original Articles by leading Botanists.—Extracts, and Notices of Books and Memoirs.—Articles in Journals.—Botanical News.—Proceedings of Societies.

Price 1s. 9d. Subscription for One Year, payable in advance, 12s.

London: WEST, NEWMAN, & CO., 54, Hatton Garden, E.C.

LIVING SPECIMENS FOR THE MICROSCOPE,

THOMAS BOLTON, NATURALISTS' and MICROSCOPISTS' STUDIO, 17, ANN STREET, BIRMINGHAM.

T. B. has last week sent to his subscribers the curious Larval Form of Trochosphere of the Marine Polyzoon *Alcyonidium*. He has also sent out an interesting gathering of Desmids and Diatoms, also *Cleve opsammata*, *Peridinium cornutum*, *Stephanoceros Eichhornii*, *Volvox globator*, &c.

Weekly announcements will be made in this place of organisms T. B. is supplying.

Specimen Tube, One Shilling, post-free.

Twenty-six Tubes in course of Six Months for Subscription of £1 1s.

Price List of Specimens on application, with stamped addressed envelope.

Portfolio of Drawings, No. 3, One Shilling.

THIN GLASS FOR MICROSCOPIC

MOUNTING, of best quality. Circles, 3d. *per* ounce; Squares, 2s. 9d.; post free 2d. extra; Ground edged Slips, 5s. per gross; also other Mounting Materials and Objects prepared for mounting.—CHAS. PETIT, 131, High Street, Stoke Newington, N.

Now Ready, price One Shilling.

The CHRISTMAS NUMBER of the

ST. JAMES'S MAGAZINE FOR 1880.

Contents.

Christmas among the Eskimo; or, The Last of Franklin and His Men.
A Christmas Adventure. M. J. P.
Love Song.
A Christmas Vigil.
'Neath Wintry Skies. By Ellys Erle.
Katharine Johnston. By Mrs. Forbes-Robertson.
An Awkward Blunder.
Christmas Bells. Charles Kendal.
A Tale of a Coat.
The Two Roses.

GRATTAN MARSHALL & CO., Paternoster Row; and all Booksellers in Town or Country.

NORTH BRITISH AGRICULTURIST

is the only Agricultural Journal in Scotland, and circulates extensively amongst Landed Proprietors, Factors, Farmers, Farm-bailiffs, and others interested in the management of landed property throughout Scotland and the Northern Counties of England.

The AGRICULTURIST has also a very considerable circulation on the Continent of Europe, America, Australia, and the Colonies.

The AGRICULTURIST is published every Wednesday afternoon in time for the evening mails, and contains Reports of all the principal British and Irish Markets of the week, besides Telegraphic Reports of those held on the day of publication.

The Veterinary Department is edited by one of the leading Veterinarians in the country, and is invaluable to the breeder and feeder as a guide to the rearing of animals, and their treatment when labouring under disease.

Full Reports are given of the Meetings of the Royal Agricultural Society of England, the Royal Agricultural Society of Ireland, the Highland and Agricultural Society of Scotland, the Scottish Chambers of Agriculture, and all the principal Agricultural Associations throughout Great Britain and Ireland.

For Advertisers addressing themselves to Farmers a better medium does not exist.

Price 3d. By post 3½d. Annual Subscription, payable in advance, 14s.

Office—377, High Street, Edinburgh.

Post-Office Orders payable to Charles Anderson, Jun., Edinburgh.

ESTABLISHED 1843.

THE ENTOMOLOGIST'S MONTHLY MAGAZINE.

Price Sixpence, Monthly, 74 pages 8vo, with occasional Illustrations.

Conducted by J. W. DOUGLAS, R. MCLACHLAN, F.R.S., E. C. RYE, F.Z.S. and H. T. STAINTON, F.R.S.

This Magazine, commenced in 1864, contains standard articles and notes on all subjects connected with Entomology, and especially on the Insects of the British Isles.

Subscription—Six Shillings per Volume, post free. The volumes commence with the June number in each year.

Vols. I. to V. (strongly bound in cloth) may be obtained by purchasers of the entire set to date, at the increased price of 10s. each; the succeeding vols. may be had separately or together, at 7s. each.

London: JOHN VAN VOORST, 1, Paternoster Row.

N.B.—Communications, &c., should be sent to the Editors at the above address.

THE "HANSA"

Published since 1861 in Hamburg, is the only independent professional paper in Germany, dedicated exclusively to Maritime Objects. Essays, Critiques, Reviews, Reports, Advertisements. Strict eye kept upon the development of Maritime Affairs in every respect. Every second Sunday one Number in 4to at least; frequent supplements and drawings. Subscription at any time; preceding numbers of the year furnished subsequently. Price 12s. for twelve months. Advertisements 4d. a line, widely spread by this paper; considerable abatement for 3, 6, 12 months' insertion. Business Office: Aug. Meyer and Dieckmann, Hamburg, Alterwall, 28. Edited by W. v. FREEDEN, M.R., Hamburg, Alexander Street, 8.

DIAN:
rewers' Interests,
tters.
AND SPIRIT TRADE

rs of every alternate
h brewing interests,
om any quarter-day.
nd.
n, E.C.

nce.
IST:
ENTOMOLOGY.

R, M.D.
LS, F.L.S.

all branches of the
Garden: Notes on
ere are monthly lists

IG of which especial
nd CHROMO-LITHO-

' Hall Court.

illing.

:
HISTORY.
Z.S., Member of the
ES—
branch of zoology:
ry birds: occurrence
resh-water fish: new
ritish land and fresh-
of the species; and
t in natural history.
l Societies. Reviews
on foreign zoological
branches of zoology.

Row.

: a Weekly
Politics, Literature,
h booksellers, and at
treet Strand, W.C.

l Française pour
s, Variétés, Nouvelles,
nbres poste. Abonne-
: 7s. 7d. Prix 3d., chez
er. On s'abonne aux
es, W.C.

Semaine Fran-
nefit of those English
nch from all points of
articular Gallic print.

numbers before
etter for most than any
We are much pleased
hly valued in all these
he printing is very well

£. s. d.
... 3 10
... 7 7
... 15 2
Covent Garden, W.C.
t, Strand, W.C.

TÉ 5me ANNÉE
— Paris
bi mensuelle
deux colonnes,
illique volume
gravures.
NVIELLE
ion
ur demande
nés
..... 12 fr.
..... 14 fr. 6
de chaque mois.

MANUALS FOR STUDENTS.

FLOWER (W. H.)—AN INTRODUCTION TO THE OSTEOLOGY OF THE MAMMALIA. Being the Substance of the Course of Lectures delivered at the Royal College of Surgeons of England in 1870. By W. H. FLOWER, F.R.S., F.R.C.S., Hunterian Professor of Comparative Anatomy and Physiology. With numerous Illustrations. Second Edition enlarged. Crown 8vo. 10s. 6d.

FOSTER and BALFOUR—THE ELEMENTS OF EMBRYOLOGY. By MICHAEL FOSTER, M.D., F.R.S., and F. M. BALFOUR, M.A. Part I. Crown 8vo. 7s. 6d.

FOSTER and LANGLEY—A COURSE OF ELEMENTARY PRACTICAL PHYSIOLOGY. By MICHAEL FOSTER, M.D., F.R.S., and J. N. LANGLEY, B.A. Fourth Edition. Crown 8vo. 6s.

HOOKER (Dr.)—THE STUDENT'S FLORA OF THE BRITISH ISLANDS. By Sir J. D. HOOKER, K.C.S.I., C.B., F.R.S., M.D., D.C.L. Second Edition, Revised. Globe 8vo. 10s. 6d.

"Cannot fail to perfectly fulfil the purpose for which it is intended."—*Land and Water.*

"Certainly the fullest and most accurate manual of the kind that has yet appeared."—*Pall Mall Gazette.*

HUXLEY and MARTIN—A COURSE OF PRACTICAL INSTRUCTION IN ELEMENTARY BIOLOGY. By Professor HUXLEY, F.R.S., assisted by H. N. MARTIN, M.B., D.Sc. New Edition, revised. Crown 8vo. 6s.

"It is impossible for an intelligent youth, with this book in his hand, placing himself before any one of the organisms described, and carefully following the directions given, to fail to verify each point to which his attention is directed."—*Athenæum.*

HUXLEY—PHYSIOGRAPHY. An Introduction to the Study of Nature. By Professor HUXLEY, F.R.S. With numerous Illustrations, and Coloured Plates. New and Cheaper Edition. Crown 8vo. 6s.

OLIVER (Professor)—FIRST BOOK OF INDIAN BOTANY. By DANIEL OLIVER, F.R.S., F.L.S., Keeper of the Herbarium and Library of the Royal Gardens, Kew, and Professor of Botany in University College, London. With numerous Illustrations. Extra Fcap. 8vo. 6s. 6d.

"It contains a well-digested summary of all essential knowledge pertaining to Indian Botany, wrought out in accordance with the best principles of scientific arrangement."—*Allen's Indian Mail.*

PARKER and BETTANY—THE MORPHOLOGY OF THE SKULL. By Professor PARKER and G. T. BETTANY. Illustrated. Crown 8vo. 10s. 6d.

Other Volumes of these Manuals will follow.

MACMILLAN AND CO., LONDON.

Now Ready, in demy 8vo, pp. 720, price 24s.

AN INTRODUCTION TO THE STUDY OF FISHES.

By ALBERT C. L. G. GÜNTHER, F.R.S., &c.,
Keeper of the Zoological Department in the British Museum.

Contents.

1. HISTORY and LITERATURE.
2. EXTERNAL PARTS.
3. The SKELETON.
4. MYOLOGY.
5. NEUROLOGY.
6. The ORGANS.
7. GROWTH and VARIATION.
8. PALÆONTOLOGY.
9. DISTRIBUTION.
10. CLASSIFICATION.
11. COLLECTING and PRESERVING.
12. INDEX.

Illustrated with 320 Wood Engravings.

Edinburgh: A. & C. BLACK.

CLASS-BOOK of ELEMENTARY MECHANICS: an Introduction to Natural Philosophy. By W. HEWITT, B.Sc., Science Demonstrator for the Liverpool School Board. Part I. Matter. Crown 8vo, 1s. 6d.

"We have seldom met with a really elementary book which at once combined to so great a degree simplicity of language, accuracy of description, and sound science."—*Nature*.

"It is very pleasant to meet with a book so fresh, so thorough, and so simple."—*Schoolmaster*.

London: G. PHILIP & SON, 32, Fleet Street.
Liverpool: PHILIP, SON, & NEPHEW, 51, South Castle Street.

Crown 8vo, 467 pages, with a Map of the District.

FLORA OF PLYMOUTH.

An Account of the Flowering Plants and Ferns found within Twelve Miles of the Town.

With Brief Sketches of the Topography, Geology, and Climate of the Area and History of Local Botanical Investigation.

By T. R. ARCHER BRIGGS, F.L.S.

JOHN VAN VOORST, 1, Paternoster Row.

NATURE SERIES.

THE SPECTROSCOPE AND ITS APPLICATIONS. By J. N. LOCKYER, F.R.S. With Illustrations. Second Edition. Crown 8vo. 3s. 6d.

THE ORIGIN AND METAMORPHOSES OF INSECTS. By Sir JOHN LUBBOCK, M.P., F.R.S. With Illustrations. Crown 8vo. 3s. 6d. Second Edition.

THE TRANSIT OF VENUS. By G. FORBES, B.A., Professor of Natural Philosophy in the Andersonian University, Glasgow. With numerous Illustrations. Crown 8vo. 3s. 6d.

THE COMMON FROG. By St. George MIVART, F.R.S. Illustrated. Crown 8vo. 3s. 6d.

POLARISATION OF LIGHT. By W. SPOTTISWOODE, LL.D., President of the Royal Society. Illustrated. Second Edition. Crown 8vo. 3s. 6d.

ON BRITISH WILD FLOWERS CONSIDERED IN RELATION TO INSECTS. By Sir JOHN LUBBOCK, M.P., F.R.S. Illustrated. Second Edition. Crown 8vo. 4s. 6d.

THE SCIENCE OF WEIGHING AND MEASURING. By H. W. CHISHOLM, Warden of the Standards. Illustrated. Crown 8vo. 4s. 6d.

HOW TO DRAW A STRAIGHT LINE; A Lecture on Linkages. By A. B. KEMPE, B.A. Illustrated. Crown 8vo. 1s. 6d.

LIGHT: A Series of Simple, Entertaining, and Useful Experiments in the Phenomena of Light for the Use of Students of every Age. By ALFRED M. MAYER and CHARLES BARNARD. With Illustrations. Crown 8vo. 2s. 6d.

(Others to follow.)

MACMILLAN & CO., LONDON.

Next week,

THE COAL-FIELDS OF GREAT BRITAIN:

Their History, Structure, and Resources.

With Descriptions of the Coal-Fields of our Indian and Colonial Empire, and of other Parts of the World.

By EDWARD HULL, M.A., F.S.A.,
Director of the Geological Survey of Ireland; Author of "The Physical Geology and Geography of Ireland."

Fourth Edition, Revised, Embodying the Reports of the Royal Coal Commission, demy 8vo, with Maps and Illustrations.

"This edition has been largely re-written. It contains an entirely new chapter on Carboniferous Plants, kindly drawn up by Prof. Williamson, F.R.S., of Manchester. The classification of the Carboniferous Series of Beds has been modified in accordance with the views enunciated in my paper on this subject, read before the Geological Society of London in 1877. The account of the various coal-fields has been modified in accordance with more recent investigations as far as my information extends, and the statistical portions have been brought down to the date of 1878."—*Extract from Preface*.

London: EDWARD STANFORD, 55, Charing Cross, S.W.

This day.

PRE-HISTORIC EUROPE:

A Geological Sketch.

By JAMES GEIKIE, LL.D., F.R.S., &c.,
Of Her Majesty's Geological Survey of Scotland; Author of "The Great Ice Age."

Medium 8vo, with Maps and Illustrations. Cloth, 25s.

"The object of these pages is to give an outline of what appear to have been the most considerable physical changes experienced in our continent since the beginning of the Pleistocene or Quaternary period. Several general works, by some of our most accomplished geologists and archæologists, have already dealt with the subject in part, but none quite cover the ground I have endeavoured to occupy. While some of my predecessors have examined the evidence principally from the point of view of the archæologist, and others from that of the palæontologist, my aim has been to describe in a more systematic manner than has hitherto been attempted that succession of changes, climatic and geographical, which, taken together, constitute the historical geology of Pleistocene, Post-glacial, and recent times."—*Extract from Preface*.

London: EDWARD STANFORD, 55, Charing Cross, S.W.

Ready,

THE FLORA OF ALGERIA,

Considered in Relation to the Physical History of the Mediterranean Region, and Supposed Submergence of the Sahara.

By W. MATHEWS, M.A.

Demy 8vo, with Coloured Map, cloth, 21s. 6d.

London: EDWARD STANFORD, 55, Charing Cross, S.W.

EDITED BY HENRY WATTS, B.A., F.R.S.,
Editor of the *Journal* of the Chemical Society

FOWNES' PHYSICAL and INORGANIC CHMISTRY. Twelfth Edition, with Coloured Plate and 154 Engravings, crown 8vo. 8s. 6d.

Also,

FOWNES' CHEMISTRY OF CARBON COMPOUNDS; or, ORGANIC CHEMISTRY. Twelfth Edition, with Engravings, crown 8vo. 10s.

London: J. & A. CHURCHILL.

BRYCE-WRIGHT'S LATEST ARRIVALS.

MINERALS.—Crystallised Hessite, Crystallised Golds, Krennerite, Crystallised Atacamites, Malacone, Euclase, Edingtonite, Suzannite, Chanarcillite, Proustite, &c.

METEORITES.—Specimens of the following Falls:—Wold Cottage, Yorkshire; Java; Orvinio, Italy; Amana, Ohio; Tipperary, Ireland; Java; Orvinio, Italy; Estherville; Hainholz; Grosnagy, Russia; Borkut; Carthago Co.; Bates Co.; Sierra di Chaco; Ashville Co.; Bates Co.; Pallas; Ashville Co., &c., &c.

BRYCE-WRIGHT, F.R.G.S., &c.,

Mineralogist and Expert in Gems and Precious Stones,

90, GREAT RUSSELL STREET, BLOOMSBURY, LONDON, W.C.

THURSDAY, NOVEMBER 25, 1880

SULPHURIC ACID AND ALKALI

On the Manufacture of Sulphuric Acid and Alkali. By George Lunge, Professor of Technology in the Zurich Polytechnic School, formerly Manager of the Tyne Alkali Works, South Shields. Vol. ii. (London: Van Voorst, 1880.)

THIS volume forms a fitting sequel to the first volume of Prof. Lunge's valuable work (noticed in NATURE, vol. xx. p. 263) on the alkali manufacture. The praise we bestowed upon the earlier volume may without stint be applied to this. Clearness and conciseness in style remarkable in a foreigner, accuracy and fulness in the description of both old and new processes, and admirable woodcuts of apparatus and manufacturing plant, constitute the chief merits of this by far the best treatise extant on the most important branch of chemical industry. The value of works on technical science, as well, we may also add, of the teaching of such subjects, depends not only on a sound knowledge of the scientific principles upon which the manufactures are based, but likewise upon a thorough acquaintance with technical minutiæ and the special details of construction and operation, the due observation of which is necessary for the manufacturer's success. Either one of these conditions may be fulfilled by a host of authors, but to find both fully developed, as is the case with Prof. Lunge, is rare. Manufacturers themselves, many of whom may be fully competent to the task, are, for obvious reasons, not given to make known the details of their successful manufacture. Nor is the professional chemical engineer likely to do more than describe the most common and well-known processes. Dr. Lunge enjoys the great advantage of having had manufacturing experience, if not along the whole line, at least over a very large portion of his subject; and to this he now adds that of a position in which every motive urges him to impart his knowledge unreservedly to his readers.

A criticism worth having of a book like the one under review should by good rights imply a knowledge of manufacturing detail at least comparable with that of the author. To this the present writer can lay no claim, whilst mere indiscriminate praise is a mode of treatment to which he would not subject the readers of NATURE, either for their sake or for his own. In order therefore to find out how far this work really teaches what it professes to teach, how far it is abreast of the improvements of the day, and how far it expresses a sound opinion on vexed trade questions such as "open" as against "closed" salt-cake roasters, or as Hargreaves salt-cake process as against the old Leblanc's process, the writer has called to his assistance his friend and former pupil, Mr. John H. Crossley of Widnes, in whose ability in both the theoretical and practical side of the subject he has the greatest confidence, and to whom he is indebted for an opinion on these questions.

The opening chapters of the volume are devoted to a discussion of the various methods of making salt-cake or sodium sulphate the first great step in the production of alkali from common salt. It is a fact worthy of note that although Leblanc's process had been in successful work in France from the year 1797, seventeen years elapsed before this was taken up in England at Walker-on-Tyne by Losh. This may be perhaps accounted for by the war then raging by which communication between the two countries was almost entirely cut off, but especially because of the high war duty on salt, which in 1805 amounted to no less than 30*l.* per ton, and which existed up to the year 1823! This may be regarded as the year of birth of the manufacture on a large scale, and in this year James Muspratt, whom we are glad still to be able to salute as the veteran founder of the alkali trade, erected works at Liverpool, where common salt was decomposed with sulphuric acid and the Leblanc process carried out completely. The difference in cost of production in the early part of the century and in recent years is seen by the fact that in 1814 soda crystals cost 60*l.* per ton, whilst in 1861 the price was 4*l.* 10*s.*

Dr. Lunge goes into the question of "Close" *versus* "Open" salt-cake roasters pretty fully, but deriving his practical experience from Newcastle, where open furnaces are almost exclusively employed, it is not surprising to find a leaning towards the latter form betrayed in spite of his attempt to place the matter before his readers in an impartial manner. One of his arguments in favour of open roasters is that stronger sulphate is obtained by their use; he says (p. 93) "Owing to the higher temperature of an open roaster it is much easier to calcine the salt-cake and to decompose the common salt completely. In blind furnaces this can only be obtained by employing a large area and consequently a very thin layer of material and spending a good deal of time over the calcining process. This of course is much easier with furnaces possessing two muffles to one pan."

Against this fact it may be mentioned that though the Lancashire close roasters are certainly built larger than the Newcastle open ones, a much larger charge is worked, and many works regularly turn out salt-cake testing above 97 per cent., and this too in furnaces with one muffle only, the double form he speaks of and figures on pp. 72 and 90, being certainly represented in practice by one or two isolated specimens only.

Dr. Lunge (p. 116) gives 14–15 cwt. as usual charges of salt for close roasters, but as much as 18 cwt. are frequently worked at one operation. In this same question the author hardly gives due prominence to the "Plus Pressure" system, which is now doing good work with regard to close roasters. Probably the appendix to be published with vol. iii. will deal with this.

The description (pp. 115–125) of the actual working of a salt-cake furnace is very good indeed.

Chapter IV., on Hargreaves' Process, is also excellent, and is probably the best description extant; the only fault that could be found is that the figures show a double line of cylinders separated by an arch, the idea being to allow of having a drawing-door on each side of the cylinders. This however is not by any means compensated for by the greater loss of heat by radiation. Only the earlier plants are built this way, the more modern erections having the cylinders built back-to-back so as to form one solid block.

Dr. Lunge wisely refrains from much speculation as to the future of this most ingenious process. "If we are to

pronounce finally upon the prospects of this process," he says (p. 158), "we shall not find this quite an easy task. A few years ago English alkali-makers had such a high opinion of that process that no new vitriol chambers were built, and the question was discussed whether it was more worth while to work down the existing chambers, or to defray the cost of the new plant at once. Afterwards a less sanguine opinion gained ground, and it seemed as if Hargreaves's process would again be put into the background." At the present moment the writer believes that the outlook for the Hargreaves process is more favourable than ever.

Chapters V. and XII., on the Cost of producing Sulphate and Soda-ash, can only serve to give an approximate idea of the matter. The exact cost involved is not readily imparted by manufacturers, and is moreover governed by local circumstances, such as the current price of labour, &c.

The latter half of the volume is concerned with the second stage in the manufacture of alkali known as the black ash process. In this the salt-cake is heated with limestone and coal, the resulting carbonate of soda being removed by lixiviation from the insoluble alkali makers' waste. The first part of the chapter on Hand Furnaces appears to be very complete, and the figures on the plate facing p. 386 are correct and well-drawn. This can hardly be said of that portion relating to the modern revolving furnaces, this is probably the weakest part of the book, the author having apparently had no practical experience on this point. Figures of two revolvers are given; of these Fig. 182 may be said to represent a fairly good design, though one single wide evaporating pan is considered more convenient for repairs than two narrow ones. As regards the speed of revolution (p. 411) Dr. Lunge is a little out. He says the revolver gearing must be capable of giving speeds of one revolution in four minutes to five revolutions in one minute, "usually the highest velocity does not exceed one revolution per minute." Those figures are not correct for the present style of working. Revolvers should be able to go a good deal slower, but speeds as high as seven to eight revolutions per minute should always be possible, especially when working the Pechiney-Weldon process, when the after charge has to be very well and rapidly mixed through the rest. This can hardly be obtained when the large spin-wheel on the revolver is worked from a worm-wheel as Dr. Lunge describes, a pinion-wheel should be used. The author (p. 406) says, "Leaving aside the older constructions of revolving furnaces, we shall only describe two of the most modern." The first of these has been spoken of above; the second, figured pp. 414 and 415, a revolver fired by gas, was erected at one works only in 1870, and was found to be a failure; after running a year or two it was entirely reconstructed to burn fuel. Since then the mechanical bogies and engine gearing have been completely altered, so that the figures can hardly be said to represent one of the "most modern constructions."

Regarding chimney power Dr. Lunge says (p. 412) that usually every two revolvers have a chimney 6 feet diameter and 100 feet high to themselves. This is certainly not sufficient for the most economical working; to stint a revolver of draught is a serious mistake.

On another point in the black-ash process Dr. Lunge's opinions do not tally with those of Lancashire manufacturers. A few years ago Mr. Mactear of St. Rollox proposed a plan of adding from 6 to 10 per cent. of lime to the black-ash in excess of that usually worked. This apparently simple process was believed by some likely to work wonders, and statements were made as to the actual gain of many thousands of pounds per annum in a single works by its adoption. Dr. Lunge gives more credit to this than some of our Lancashire friends seem inclined to do.

The remaining processes in the great suite of chemical changes involved in the alkali trade are as thoroughly discussed by Dr. Lunge as those which have now been noticed. Divergent views concerning many details of these may doubtless be held by various manufacturers, but all will agree in the opinion not only that this is an excellent book, but that it would be very difficult for any one to write a better one.

H. E. ROSCOE

THE FLORA OF PLYMOUTH

Flora of Plymouth: an Account of the Flowering Plants and Ferns found within Twelve Miles of the Town, with Brief Sketches of the Topography, Geology, and Climate of the Area and History of Local Botanical Investigation. By T. R. Archer Briggs, F.L.S. With Map. 8vo, pp. xxxv. and 432. (London: Van Voorst, 1880.)

THIS is a model local flora. Mr. Briggs is well known as one of the most experienced and trustworthy amongst the botanists who have made a special study of British Phanerogamia. He has established a claim upon the gratitude of his fellow-workers by acting for several years as the honorary distributor of their Exchange Club, and in this capacity has received and sent out many thousands of specimens. The present work is the result of the rambles of twenty years, and as he has restricted its limits to a radius of twelve miles from the town, the whole of the district has been within walking distance of his home, and it is probable that there is no tract in Britain of which the plants have been worked out and placed on record in such a thorough and exhaustive manner. A radius of twelve miles from Plymouth includes a great variety of soil and situation. There are the maritime plants of the seashore and the tidal reaches of the Tamar and its affluents. Inland there are in the low country besides the stream-sides, meadows, and cultivated fields, plenty of woods and deep shady lanes with high banks and thick hedgerows, and the twelve miles radius reaches to a height of 1,700 feet on Dartmoor, and includes a considerable space of open uncultivated heathy and swampy ground. The district is not rich in limestone nor in ponds, but except in the plants which affect these two kinds of station there is full scope so far as situation goes to suit all their varied requirements in habitat.

Out of the 1,680 species enumerated in the last edition of the London Catalogue 873, or considerably more than half, are found within the radius covered by this book. Out of these 728 are natives, and the other 145 more or less certainly introduced by human agency.

It is interesting to have an area so far west in the island so thoroughly worked out, and certainly one of the most instructive points in connection with the matter is to note which British plants fail to reach and become very rare within the area. Taking the species according to their types of distribution as classified by Mr. Watson in the fourth volume of his "Cybele Britannica," and adopting the more stringent scale of species-limitation which he there follows, we find that out of 1,425 British species 764 grow in the neighbourhood of Plymouth. The 120 species of Watson's highland or extreme northern type and the 49 local or doubtful species are not represented here at all. Of the eighty-one species of his Scottish type we get only 5, and out of the 37 species of his intermediate type only 3 enter into the Plymouth area. So that the boreal element of the British flora, 238 species, is represented at Plymouth only by 8 species, such plants as *Rubus saxatilis*, *Gnaphalium dioicum*, *Polypodium Phegopteris*, *Polypodium Dryopteris*, and *Lycopodium Selago* lurking in very small quantity in the recesses of Dartmoor. Of Watson's 70 Atlantic or specially western species Plymouth has 36; of Watson's 127 Germanic or specially eastern species Plymouth has only 16; of the 532 species spread almost universally through Britain Plymouth has 484. Perhaps the most noteworthy point of all is that of Watson's 409 plants of the English type of distribution, plants spread widely through England, but running out in a northern direction north of the Humber and in the Scotch Lowlands, Plymouth gets only 220, or little more than half. Amongst the absentees in widely-spread English plants, for instance, are the common Forget-me-not (*Myosotis palustris*), the Mistletoe, *Genista tinctoria*, *Veronica Anagallis*, *Glyceria aquatica*, and *Scirpus lacustris;* and amongst the great rarities the common harebell (*Campanula rotundifolia*), the cowslip, the common butter-bur, *Hieracium boreale* and *vulgatum*, and some of the common south-country weeds, like *Solanum nigrum* and *Mercurialis annua*, which round about London are exceedingly plentiful. In the critical genera of British plants Plymouth is rich in rubi and roses, very poor in willows and hieracia. Amongst the rarities of the neighbourhood are *Polycarpon tetraphyllum*, *Erynium campestre*, *Pyrus Briggsii*, a curious pear with fruit like that of a small crab-apple, *Physospermum cornubiense*, and two species of *Hypericum*, *bæticum*, and *linariifolium*, and it produces some curious hybrid epilobia and rumices.

The area is divided into five districts, founded on river-drainage, two of which are in Cornwall and three in Devonshire; and under these the special localities of the species are carefully traced out, the abundance in which each occurs being particularised, and the claims of each to be regarded as wild being in all doubtful cases carefully investigated.

As stated in the title, the book includes a map and short sketches of the climatology and geology of the district, and of the progress of botanical investigation within its bounds from the days of Lobel and Parkinson down to the present day. We can recommend it with confidence to all our readers who are interested in geographical botany as one of the most complete, conscientious, and interesting works of its kind that have ever appeared.

OUR BOOK SHELF

Peruvian Antiquities: The Necropolis of Ancon in Peru. A Series of Illustrations of the Civilisation and Industry of the Empire of the Incas. Being the Results of Excavations made on the Spot. By W. Reiss and A. Stübel. (London: Asher and Co., 1881.)

A FIRST instalment now lies before us of this magnificent undertaking, which, if fully realised, bids fair to rival in scientific interest and typographical splendour Lord Kingsborough's great work on Mexican Antiquities. Reserving a full notice for a later stage of the project, it will suffice here briefly to indicate its main features, and direct attention to its paramount importance for antiquarian and ethnological studies. The authors, who have lately returned from South America laden with archæological treasures of all kinds, have been encouraged by the munificence of the directors of the Berlin Royal Museum to place the results of many years' diligent research at the disposal of the public. Under the general heading of "Peruvian Antiquities" the publishers, Messrs. Asher and Co., of Berlin and London, propose to issue simultaneously in English and German a series of folio volumes illustrating the whole field of the ancient Quichua-Aymara culture, such as it existed at the time of the Spanish invasion. The publication will spread over a number of years, each volume appearing in separate parts varying in number according to the nature of the subject. Each part will contain a number of chromolithographic engravings with corresponding pages of explanatory text. These illustrations, which of course are the great feature of the work, will be produced in the most finished style of modern typographic art, and will consist of perfect facsimiles either in natural or reduced size of every conceivable object associated with the ancient civilisation of the Incas. The series begins with a volume devoted entirely to the "Necropolis of Ancon," now an obscure watering place and fishing village on the Peruvian coast, a little north of Lima, but in pre-Spanish times evidently the centre of a thickly-peopled district that had long been occupied by a settled population. The "finds" made in the mummy graves of this burial-place are of extraordinary archæological interest, illustrating in the most vivid manner every aspect of the social and domestic life of the ancient Peruvians. The volume is to be completed during the course of the ensuing two years in ten uniform parts, as above described, and to judge from Part I., which has just appeared, it is likely to prove of the utmost value to the antiquary and ethnologist. But our remarks on all details must be postponed till this volume is completed. The English text has been entrusted to Mr. A. H. Keane, whose special knowledge of the subject must ensure accuracy in the descriptive and explanatory part of the work.

Exposé Historique concernant le Cours des Machines, dans l'Enseignement de l'École Polytechnique. 23 pp. (Paris: Gauthier-Villars, 1880.)

THE council for the improvement of the course of study at the Polytechnic School has for some time had under consideration a revision of the *Programme d'Instruction* of the two years' course, and at different times, for instance in 1865, steps have been taken with a view to their improvement, but, according to this pamphlet, different circumstances, especially in 1870, have deferred the realisation of such schemes. Upon such a wide subject our author does not venture, but he confines himself merely to that part which relates to the *Cours de Machines*. We are indebted for this very interesting and full historical sketch of the matter from the very foundation of the school to the veteran geometer, M. Chasles.

LETTERS TO THE EDITOR

[*The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts. No notice is taken of anonymous communications.*]

[*The Editor urgently requests correspondents to keep their letters as short as possible. The pressure on his space is so great that it is impossible otherwise to ensure the appearance even of communications containing interesting and novel facts.*]

Fertilisation of Yucca

IN NATURE, vol. xxii. pp. 606, 607, appears a letter to which my attention has only to-day been called—signed E. L. Layard—on the subject of the fertilisation of yuccas successfully introduced and cultivated in New Caledonia.

The writer shows himself to be under some misapprehension as to the generic characters and appearance of the insect which is generally credited with the fertilisation of these plants in their native country. The moth of the genus *Pronuba*, to which he refers, is not a "large moth having yellow under-wings." Although a common species belonging to the *Noctuidæ*, standing in our British lists under the genus *Triphæna* (Ochs), but included in Dr. Standinger's European Catalogue in the genus *Agrotis* (Ochs), is distinguished by the specific, not generic, name *pronuba* (Lin.), as well as by the characteristic appearance to which your correspondent evidently alludes.

The genus *Pronuba* (Riley) was founded for the reception of *Pronuba yuccasella* (Riley) (see *Proceedings* Acad. Sci. Missouri, ii. pp. 55, 333; *Report* Nox. Ins. Missouri, v. 151, vi. 131; *Canadian Entomologist*, iv. 182; Hayden's *Bulletin* of the U.S. Geological and Geographical Survey, iii. 121–141, &c.), which has also been described by Prof. Zeller in the *Verhandlungen der zoologisch-botanischen Gesellschaft in Wien*, 1873, vol. xxiii. pp. 232, 233, under the name *Tegeticula alba*.

This small white moth, of which some varieties have a few black dots on the fore-wings, belongs to the Lepidopterous group *Tineina* (Stn.), possibly to the family *Hyponomeutidæ*. Prof. Riley finds that the female, which has the basal joints of the maxillary palpi developed into a long curved tentacle furnished with spines, uses these appendages to collect and convey the pollen of the yucca to the tube of the stigma, which it could not otherwise reach; the eggs are then deposited, and the larva feeds upon the fruit, subsequently hibernating and becoming a pupa on the earth. It would be most interesting to ascertain whether *Pronuba yuccasella* (Riley) has been introduced with the yucca into New Caledonia, or whether any other insect, either indigenous or not indigenous to North America, has been found to take its place in carrying on the work of fertilisation. Prof. Riley considers the fact that yuccas introduced into the more northern portions of America have failed to produce seed may be attributed to the absence of *Pronuba*.

If Mr. Layard will direct his attention to this point he can scarcely fail to supply some valuable and instructive evidence bearing upon the subject. WALSINGHAM

Eaton House, Eaton Square, November 13

Skin Furrows of the Hand

ALLOW me to contribute the information in my possession in furtherance of the interesting study undertaken by your Japan correspondent (vol. xxii. p. 605).

I have been taking sign-manuals by means of finger-marks for now more than twenty years, and have introduced them for practical purposes in several ways in India with marked benefit.

The object has been to make all attempts at personation, or at repudiation of signatures, quite hopeless wherever this method is available.

(1) First I used it for pensioners whose vitality has been a distracting problem to Government in all countries. When I found all room for suspicion effectually removed here, I tried it on a larger scale in the several (2) registration offices under me, and here I had the satisfaction of seeing every official and legal agent connected with these offices confess that the use of these signatures lifted off the ugly cloud of suspiciousness which always hangs over such offices in India. It put a summary and absolute stop to the very idea of either personation or repudiation from the moment half a dozen men had made their marks and compared them together. (3) I next introduced them into the jail, where they were not unneeded. On commitment to jail each prisoner had to sign with his finger. Any official visitor to the jail after that could instantly satisfy himself of the identity of the man whom the jailor produced by requiring him to make a signature on the spot and comparing it with that which the books showed.

The ease with which the signature is taken and the hopelessness of either personation or repudiation are so great that I sincerely believe that the adoption of the practice in places and professions where such kinds of fraud are rife is a substantial benefit to morality.

I may add that by comparison of the signatures of persons now living with their signatures made twenty years ago, I have proved that that much time at least makes no such material change as to affect the utility of the plan.

For instance, if it were the practice on enlisting in the army to take (say) three signatures—one to stay with the regiment, one to go to the Horse Guards, and one to the police at Scotland Yard—I believe a very appreciable diminution of desertions could be brought about by the mere fact that identification was become simply a matter of reference to the records.

And supposing that there existed such a thing as a finger-mark of Roger Tichborne, the whole Orton imposture would have been exposed to the full satisfaction of the jury in a single sitting by requiring Orton to make his own mark for comparison.

The difference between the general character of the rugæ of Hindoos and of Europeans is as apparent as that between male and female signatures, but my inspection of several thousands has not led me to think that it will ever be practically safe to say of any single person's signature that it is a woman's, or a Hindoo's, or not a male European's. The conclusions of your correspondent seem, however, to indicate greater possibilities of certainty. In single families I find myself the widest varieties.

15, St. Giles, Oxford, November 13 W. J. HERSCHEL

P.S.—It would be particularly interesting to hear whether the Chinese have really used finger-marks *in this way*. Finger-dips (mere blots) are common in the East, as "marks."

The Aurora of the 3rd Instant

MR. E. DOWLEN has kindly communicated to me some particulars of the above as seen by him at Southport.

He first noticed the aurora at 6h. 50m. (it had however been visible before that time) as a greenish white glow on the north horizon. This gradually rose until 7h. 45m., when the top of the arch was estimated at two-thirds of the way up between the horizon and the Great Bear. It then gradually died out from the ends of the arch, and at 8h. 30m. had disappeared. During the time it was watched the following changes took place:—

From 7h. to 7h. 15m. it faded away from the eastern end until 7h. 30m., when nearly half the arch was gone. The western end then seemed to gather itself up somewhat, and to get brighter. After this the ends again lengthened out until 7h. 45m., when the whole began to fade away. At 7h. 25m. a narrow-arched band of black cloud concentric with the auroral arch was formed. It seemed to start from the ends, and meet over the middle point. At first this lay close upon the aurora. It then rose quickly, passed through the Great Bear, and vanished. It took about ten minutes to form, rise, and disappear.

Mr. Dowlen saw no streamers, but faint ones might have been present and escaped notice owing to adjacent gas-lamps. The aurora was at no time bright, and Mr. Dowlen doubts whether any beyond the green line would have been seen in the spectroscope.

The cloud formation detailed seems to me of considerable interest. J. RAND CAPRON

Guildown, November 19

Temperature of the Breath

THERE is no doubt that Dr. Roberts has discovered the true explanation of the phenomena that puzzled me and a good many others to whom I showed them. I have repeated Dr. Roberts's method of heating the enveloping material so as to expel all moisture from it, cooling it down to the temperature of the room and then breathing through it. In every case where I did so the thermometer showed a rise to 112° and upwards at the end of a minute; at the end of two minutes the index was pushed into the small bulb at the top, showing a temperature of about 116°. It is evident, therefore, that the high temperature observed is not the actual temperature of the breath, but is

caused by the caloric evolved by the transition of the aqueous vapour of the breath into the liquid or solid form.

Before seeing Dr. Roberts's explanation I referred the matter to the greatest living authority on heat, and he, after carefully repeating my experiments, was of opinion that the heat was produced by the compression of the air when forced through the material. Had he known of Dr. Roberts's simple but ingenious variation of the experiment there is no doubt he would have accepted Dr. Roberts's explanation. R. E. DUDGEON

November 18

THE following experiment may serve to supplement the observations of Dr. Roberts as to the cause of the high reading of a thermometer wrapped in a handkerchief and placed in the mouth. An ordinary non-registering thermometer was wrapped in about twelve folds of a dry linen handkerchief placed in the mouth, and the following readings taken at intervals of one minute:—Inspiration was effected through the nostrils, expiration through the handkerchief. The thermometer was in the mouth from the beginning to the end of the experiment. Temperature under the tongue before commencing, 37°·0 C. The reading of the thermometer wrapped as above described, one minute after introduction into the mouth, was 43°·0. At the end of the second minute, 44°·1, 3rd 42°·9, 4th 41°·2, 5th 39°·6, 6th 38°·2, 7th 37°·1, 8th 36°·9, 9th 36°·9, &c. After the experiment the temperature under the tongue was 37°·6. Capillarity is probably the chief cause of the rapid condensation of water, and the consequent liberation of heat in the dry fabric.

In connection with the above I may mention a schoolboy's trick, viz., gripping the arm of a schoolfellow with the teeth and breathing forcibly through his coat-sleeve. The sensation of heat thus produced is much greater than when the breath is allowed to impinge on the bare skin.

In conclusion, I must freely confess that Dr. Dudgeon completely upset my objection, as to compression of the bulb having anything to do with the high reading, by the experiments quoted in his last letter. F. J. M. P.

Coral Reefs and Islands

IN my letter on "Coral Reefs and Islands," published in NATURE, vol. xxii. p. 558, I have just noticed an important slip in writing which demands correction.

In the third paragraph and ninth line, for *metres* read *miles*, so that the passage shall read thus: "On the Florida coast we have barriers with channels 10–40 *miles* wide."

More accurately, the space between the southern coast of Florida and the line of Keys (old barrier reef) gradually widens from a few miles in its eastern to more than 40 miles in its western part. The channel between the line of Keys and the present reef is 6–7 miles wide and about 150 miles long.

Berkeley, California, November 2 JOSEPH LECONTE

Vox Angelica

I HAVE received a letter from Mr. Samuel Ray of Stoke Newington with reference to my remarks on the Vox Angelica stop on an Estey American organ. Mr. Ray informs me that Gordon's supplementary tuning-valve is used for the desired effects. The *rationale* of the method is, that by partly closing the mute the reeds are flattened, just as one reed is when the key is partially depressed. Mr. Ray also says, that by pulling out the stop a little way and making the reeds beat the latter are liable to be drawn out of tune; but this was the original method, but is now improved upon. A separate mute is placed on the top of the tubes, so that the wind strikes one of the sets of reeds vertically, whereby undue strain is avoided.

GEORGE RAYLEIGH VICARS

Woodville House, Rugby, November 18

Fascination (?)

PROBABLY none of your readers have thought it worth while to make any comment on the letters on this subject which have recently appeared, because it would seem needless to discuss the *origin* of "fascination" by means of the eye of a snake (or whatever may be the stimulus to the alleged condition) while all the evidence we can obtain from these reptiles in confinement proves that the condition does not exist. It devolves upon those who might object to observations on reptiles in a glass case as untrustworthy, to show us why—all their other actions being normal—the prisoners should not exhibit the same habit in respect to this "fascination," as they are alleged to practise when free. It is rather late in the year now; but if Mr. L. P. Gratacap will take the first opportunity of seeing snakes feed, and if any of your readers will pay a visit to the Zoological Gardens, both he and they will, I think, come to the conclusion that, beyond the expression of a little surprise (on the part of ducks and pigeons chiefly) which soon wears off at the sight of an *unfamiliar* object, both the birds and animals regard the snakes with marked unconcern. I have seen a guinea-pig, after finding no place of exit from the cage, quietly settle itself down in the midst of the coils of an Australian constrictor, shut its eyes and go to sleep. Ten minutes afterwards the snake had moved, and the guinea-pig was washing its face with its paws. Not once, but a dozen times, a rabbit has nibbled the nose of a River Jack viper (*V. rhinoceros*) in a pretty, inquiring way, heedless of the strong blows the reptile would administer with its snout to the impertinent investigator of that queer-looking object. For fully ten minutes one day a rabbit sat gazing at the poised and threatening head of a puff adder, now and then reaching forward to smell the reptile's nose, and anon sitting on its hind legs to wash its ears, and again returning to the "fascinating" object of its inquiries. If during that time the rabbit had fallen into the state of trance, it was so soon released from that condition as to be able to attend to its own comfort and busy itself about its toilet. The birds show no more recognition than the other animals of the dangerous position in which they are placed. We see them hopping about on the snakes and pecking lustily at their scales; sitting on the branches, preening their feathers and behaving themselves just as though no such dreadful (or pleasing?) sensation as "fascination" was possible!

I saw once a sparrow perched upon the body of a snake twisted round a branch, and preening itself. By-and-by a constrictor crept up slowly, touched the bird with its nose, and then threw the crushing folds around it. The deliberate approach of the snake and the unconscious attitude of the sparrow, concerned about its private affairs, would have staggered any ordinary believer in "fascination." I have closely watched the behaviour of snakes *intent* on feeding. It may be a sudden rush, when the victim has no time to see its enemy, or the gradual, lazy advance of the reptile; in either case the doomed victim betrays no suspicion of danger—at least so far as I have been able to ascertain after passing some hundreds of hours contemplating the snakes in the unequalled representative collection of the Zoological Society.

The expression in Mr. Gratacap's letter, "glittering" eyes, applied to the orbits of a snake, which are veiled by the "antocular" membrane, and capable of very slight movement, may remind us of Virgil's "Suffecti sanguine et igni," and help to confirm the "basilisk" (not a snake, by-the-by) superstition, but can only serve to perpetuate a myth. Whatever may be the value of Mr. Foot's opinion, I would ask, "Who has ever seen a snake 'raise its tail' after the manner of the cats?"

Charles Darwin has much to say on this subject to any one who chooses to consult the "Origin of Species." He does not see any advantage in the cat's "waving" tail or the noise of the "rattle" of *Crotalus*, for no predatory animal would derive any benefit from a signal of warning to its prey. The snake certainly never "waves" its tail when intent on mischief.

ARTHUR NICOLS

Soaring of Birds

REFERRING to NATURE, vol. xxiii. p. 10, may I suggest the following?—The question seems to be: "How can birds, having attained a certain elevation, thence rise without further muscular effort?" If I am not in error in what follows, they can theoretically do so if they *start* with a difference between their horizontal velocity and that of the wind, and *end* with a less difference; *e.g.*, if they start at rest with respect to the earth, and end by drifting with the wind entirely.

Take this last case, and consider the earth as plane, and the wind as horizontal, and having a velocity $= v$ with respect to the [earth and] bird. Finally we suppose the bird gains a horizontal momentum $= mv$. Then, by conservation of horizontal momentum, the only force acting being vertical, the air must lose an equal horizontal momentum.

Now we know that in all cases of bodies colliding and ultimately acquiring the same velocity, while we have conservation

of momentum we have loss of visible kinetic energy, except when the coefficient of restitution = 1. This kinetic energy is transformed into the vibrational kinetic energy of sound and heat in general.

But cannot we have it partly transformed into potential energy by "soaring" against gravity? On this supposition we have the two laws, conservation of momentum where no forces act, and conservation of energy, holding. But we have visible kinetic energy lost and *partly transformed into potential energy with respect to the earth*, partly (as usual) into vibrational kinetic energy of sound and heat. [The *sound* is evident in the "singing" of the wings.]

It seems to me that the swooping referred to by your correspondent is only a matter of convenience to the bird, and does not really affect the mechanical question; and that the comparison to a kite (which is held by a string) is not very satisfactory. But from my own observation of sea-gulls I do not think one can say that all the manœuvres and turns of the bird in the air are performed without real muscular effort, though certainly without *flaps* of the wing; and if there be muscular effort there can be work done—against gravity in this case.

The above is only a suggestion. I wish to induce some more mathematical reader to write a clear answer on this interesting question. W. LARDEN

Cheltenham, November 8

The Photophone

ON reading the description published in NATURE, vol. xxiii. p. 15, of Prof. Graham Bell's wonderful discovery, the transmission of speech by light, I notice that in "the photophone" the varying of the intensity of the beam of light thrown on the receiving instrument is accomplished by the simple and ingenious means of allowing the sound-waves to beat on the back of a thin plane mirror. It seems to me, however, that this arrangement is not complete, and is open to some objection. As the plane mirror will, if provision be not made against it, become convex and concave alternately, it must, unless the vibrations be confined within very narrow limits, give in one vibration *two* periods of maximum and minimum illumination at the receiver, and therefore the received sounds, apparently, should be (assuming the periods between each maximum and minimum illumination to be of the same duration, which could never exactly occur) an octave higher than those transmitted. This I think follows from the fact that the rays from the mirror would be dispersed not only when convex, but also when concave, *after* they had passed the focus. If, therefore, the vibrations of the mirror are sufficiently great to bring its focus between the mirror and the receiving instrument, there would be a second point of minimum illumination. If however the mirror were made slightly convex, or were constrained by a spring or otherwise, this defect would be cured.

Curiously enough, *theoretically* "the photophone" is the more effective the greater the distance between the transmitter and the receiver, as the degree of variation of the intensity of light falling on the selenium will be, when perfectly adjusted, greater as the distance increases, and it is on this element that the intensity of the sound depends. A. R. MOLISON

Ffynone Club, Swansea, November 15

[Our correspondent is obviously right in supposing that with a beam of light focussed accurately upon the selenium receiver a *single* complete vibration of the transmitting disk would produce *two* periods of maximum and minimum illumination. This would not however be the case if the lenses were not set originally to exact focus, for then a displacement of the disk in one direction would scatter the rays more, while a displacement in the other would concentrate them more. In practice, we believe, exact focussing is never obtained or even attempted.—ED.]

Salts of Zinc

IN Roscoe and Schorlemmer, vol. ii. p. 264, it states: "The salts of zinc do *not* impart to the non-luminous flame any tint;" and on p. 258, "the metal burns with a bright *white* flame."

What then is the green colour imparted to the Bunsen flame by zinc sulphate due to? Also the green flame obtained by heating metallic zinc on charcoal before the blowpipe? S.

THE green tint referred to by "S." (*supra*) as imparted by zinc sulphate to the Bunsen flame is only observed whilst the water of crystallisation contained in the salt is being given off; the dry salt which remains imparts no colour to the flame. It therefore appears probable that the green colouration of the flame is caused by very finely divided particles of the salt being carried off into the upper part of the flame by the escaping water of crystallisation. These particles then become so intensely heated as to emit the peculiar greenish light and very likely suffer previous reduction by the carbon of the flame. Other zinc salts, especially the acetate, impart to the flame, when first heated, a greenish-blue tint resembling that observed when metallic zinc is burnt in the air, this being doubtlessly due to a partial reduction of the acetate. The characteristic zinc lines (6362 and 6099 in the red, and 4928, 4924, and 4911 in the blue) are not seen in the case of the salts or when the metal is burnt. A more correct description of the combustion of zinc than that referred to would be: "the metal burns with a bluish-white flame."

Chemical Laboratory, Owens College W. BOTT

THE WORKS OF CARL VON NÄGELI

THE beginning of the forties in the present century marks an important epoch in the history of botany. The "Naturphilosophie" which had for many years so banefully influenced the development of the science, was being routed by the energetic attacks of Schleiden. Botanists were becoming alive to the fact that if their study was to have a place as a science by the side of physics and of chemistry, it must be pursued by the inductive method; that speculation must give way to research, and, above all, that development must be studied before any conclusions could be drawn from the investigation of mature forms. The early discoveries of von Mohl, and the demonstration of the cellular structure of the tissues by Schleiden, were among the first fruits of this awakening. To this period belongs also Nägeli's first contribution to science—a paper on the Development of the Pollen (1842). The first sentence in the introduction shows how thoroughly Nägeli was imbued with the same spirit which possessed Schleiden. He says:—"The right knowledge of an object includes an acquaintance with its mature form and a study of its development: the one is dependent upon the other, and the one without the other is insufficient to afford a complete conception of the object." The actual observations detailed in the paper appear from the drawings to have been accurate, and they were an important addition to the knowledge of the subject; but their interpretation was so far influenced by Schleiden's theory of cell-formation, which was then prevalent, that the process of the development of the pollen grains is described as being one of free cell-formation.

In the year 1844 appeared the first number of the *Zeitschrift für wissenschaftliche Botanik*, edited—probably on account of the sympathy existing between them—by Schleiden and Nägeli. This short-lived periodical (1844 to 1846) was practically an organ for the publication of Nägeli's researches and for the expression of his views, for it does not contain a single contribution from Schleiden's pen. The first number opens with an article—a sort of confession of scientific faith—"On the Present Aims of Natural History, and especially of Botany," in which he gives an account of the actual state of botanical knowledge, and strongly urges the necessity of empirical study in order that the generalisations of the science might be in the future, not baseless speculations, but inductions resting upon a firm foundation of ascertained fact. The *Zeitschrift* further contains an important paper "On the Nuclei of Cells and the Formation and Growth of Cells," in which the process of free cell-formation, which Schleiden had asserted to be universal, is shown to be only one of the processes by which a multiplication of cells is effected; these processes are clearly defined and classified. This is followed by a number of researches on the morphology of the lower cryptogams, which are of interest inasmuch as they open up new lines of approach to the study of the complicated morphology of more highly

organised plants. Nägeli showed, for instance, that since in a unicellular alga (*Caulerpa*) a morphological differentiation of root, stem, and leaf is indicated, morphological is not dependent upon histological differentiation. He discovered also that in the organs of certain cryptogams growth is effected by the repeated segmentation of a single apical cell, and that this segmentation may take place always in one plane only (*Delesseria*), or in two or three planes (stem of *Echinomitrium*, *Phascum*, *Iungermannia*, leaves of mosses).

In the following year (1847) he published his work on "The Classification of the Algæ" ("Die Neueren Algensysteme"), which is of great value, partly on account of the acute criticisms on the various proposed classifications of this group of plants which it contains, but more particularly on account of the number of new facts concerning their structure and life-history which are contributed. The descriptions of *Valonia*, *Udotea*, and *Acetabularia* may be especially mentioned: it is shown that they have essentially the same structure as *Caulerpa*. The same praise may be awarded to another work, "The Genera of Unicellular Algæ," which appeared two years later.

The next publication of importance was the first number of the *Pflanzenphysiologische Untersuchungen*, and the most interesting of the papers which it contains is the one on the Primordial Utricle. Attention is directed to its presence in all living cells, to its influence upon the osmosis of substances in solution into or out of the cell, and to its activity in forming the cell-wall; in short, it is clearly shown to be the living portion of the cell. The second number did not appear until 1858, although the MS. was ready in 1855, the delay being due principally to Nägeli's removal from Freiburg to Zürich, and then again from Zürich to Munich on his acceptance of the Professorship of Botany in that University. Although it must have been vexatious, still the delay enabled Nägeli to extend his researches in various directions and thus contributed materially to make the great work on starch-granules one of the most complete monographs which was ever written on any subject. This second number is entirely taken up by this work, which gives an account of these bodies, including their structure, development, chemical composition, and physical properties, as well as their distribution in plants. It is a monument of patient, accurate investigation, devoted to a subject which appears, at first sight, to be of limited interest, but which ultimately suggested one of the most remarkable generalisations of modern times, namely, what is known as Nägeli's theory of the structure of organised bodies. The primary fact upon which this theory is based is the property which starch-granules have of swelling-up—that is, of absorbing a certain amount of fluid with a consequent increase of bulk—when treated with certain reagents (dilute acids and alkalies), and of diminishing in size in consequence of a loss of water when treated with other reagents (alcohol). From these phenomena he inferred that the starch-granule consists of solid particles, which are impenetrable by water, but which are capable of taking up a certain amount of water between them, and that the amount of this water may vary according to circumstances. When the granule is absolutely dry, these solid particles—to which he gave the name of *molecules*—apparently come into perfect contact, for the granule does not lose its transparency, which would be the case if air were included in its substance.

It may be remarked here parenthetically that the word *molecule* used by Nägeli to designate these solid particles has not the same sense as it has when it is used in chemistry; one of these molecules is probably an aggregation of chemical molecules. In order to avoid any possible confusion on this score Nägeli has substituted the word *micella* for molecule in his more recent works. The forces by which these micellæ, with their surrounding watery areas, are held together are, firstly, the attraction existing between the micellæ; and secondly, the attraction which exists between each micella and the water which surrounds it; the latter of these attractions must necessarily be greater than the former, but whereas the former varies inversely as the square of the distance, the latter must vary inversely as some higher power. Thus, if A represent the attraction between two micellæ, B the attraction between a micella and the water, and D the distance between two micellæ, the limit of swelling-up or imbibition will be reached when $\frac{B}{D^{2+x}} = \frac{A}{D^2}$. As to the form of the micellæ, it is evident that they are not spherical or oval, for in that case the starch-granules would necessarily contain air when dry, and further, the denser parts of them would have to contain at least 26 per cent. of water, whereas, as a matter of fact, they only contain 14 per cent. They must be therefore more or less polyhedral, but they are not equiaxial since the swelling-up does not take place equally in all directions.

By this theory it was found possible to explain satisfactorily certain difficult points of structure, such, for instance, as the stratification of starch-granules and the striation and stratification of cell-walls. All these depend upon the alternation, in one or more planes, of dense and less dense layers. The proportion of solid to fluid is greater in the dense than in the less dense layers, or, in the terms of Nägeli's theory, the relative size of the micellæ to the watery areas surrounding them is greater in the layers of greater density. Further, this theory affords a satisfactory explanation of the mode of growth of a cell-wall. It is easy to understand that when the limit of extensibility is nearly reached—that is, when the micellæ of the membrane are separated as far as possible—new micellæ can be deposited in the interstices, the extended condition of the membrane being thus rendered permanent. This mode of growth is commonly known as *growth by intussusception*.

This is the stage to which the development of the theory is brought in this work. In the year 1862 Nägeli published a paper in the *Proceedings* of the Bavarian Academy on the "Application of Polarised Light to the Study of the Structure of Plants," which advanced it very considerably. He found, in the first place, that organised structures, such as starch-granules or cell-walls, are doubly refractive, and that this property is not affected by causing them to increase or diminish in size in consequence either of the absorption or removal of water, or by mechanical stretching or pressure. From this he concluded that the double refraction is not a property of the organised structure as a whole, but that it belongs to each individual micella: hence these micellæ must be crystalline. Again, from the interference colours which these objects present when examined with polarised light, he ascertained that the crystalline micellæ have three axes of elasticity, that they must be bi-axial crystals; and further, by comparing the effect produced by the passage of polarised light through glass under various degrees of pressure, he arrived at the conclusion that the micellæ are so arranged in the membrane of which they form part that one of their axes of elasticity is perpendicular to the surface, whereas the other two axes lie in the plane of the membrane. In a subsequent paper contained in the same periodical, he shows that the crystals of proteid substance, which occur in various seeds and tubers, have the same molecular constitution as starch-granules and cell-walls. By close and acute reasoning from carefully observed facts, Nägeli has therefore succeeded in establishing this theory of the molecular constitution of organised bodies, a theory which satisfactorily explains many of the peculiarities of structure and properties which they present. There can be little doubt that it is justifiable to extend this theory to the explanation of the intimate structure of protoplasm; in fact, in his later publications Nägeli has asserted as much, and in

this he is supported by such authorities as Sachs and Strasburger; but it is impossible to say anything at present as to the form and arrangement of the micellæ of protoplasm beyond this, that they do not so act upon polarised light as to suggest that they are crystalline. Full details on this subject, as well as a vast amount of other information, is given in the treatise on the Microscope (second edition, 1877), which Nägeli wrote together with Schwendener; fortunately an English edition of this important work may soon be expected to appear.

In tracing the development of Nägeli's theory, it has been necessary to depart from the chronological order of his works. In the years between 1858 and 1868 he published his *Beiträge zur wissenschaftlichen Botanik*, which include several important works, for the most part anatomical. In the first number there is an elaborate paper on "The Arrangement of the Fibro-vascular Bundles and the Mode of Growth in the Stem and Root of Vascular Plants," which is important as containing a purely morphological classification of the different forms of tissue of which these organs consist. This is followed by a detailed account, in the fourth number, of the mode of growth in thickness and of the arrangement of the fibro-vascular bundles in the stem among the Sapindaceæ, and this number also contains Nägeli's well-known investigation into the mode of development and growth of roots, in which Leitgeb was associated with him. This publication has a further interest connected with it, in that Schwendener's first papers on what is now known as his Lichen-theory appeared in it.

During this period Nägeli frequently contributed papers (the *Botanische Mittheilungen*) on a variety of subjects of botanical interest to the *Proceedings* of the Bavarian Academy, an activity which continues up to the present time. Allusion has already been made to some of these, and it would be worth while, did space permit, to give an account of most of them. Among the more important the following may be mentioned:—"On the Sieve-Tubes of Cucurbita," "On the Proteid Crystalloids of the Brazil-nut," "On the Development of Varieties," "A Theory of Hybridisation." Of late years Nägeli has turned his attention more especially to the study of the chemical composition and vital processes of the lower Fungi, such as Yeast and Bacteria. Among the interesting results obtained is the discovery, in yeast-cells, of a ferment (invertin) which converts cane- into grape-sugar, and of peptones. But the real importance of these researches only became apparent on the publication of two larger works, viz.: "The Lower Fungi in their Relation to Infectious Disease" (1877), and "A Theory of Fermentation" (1879). It is of course impossible to give here anything like a satisfactory account of the contents of these two books. The first treats fully of the important part played by Bacteria in infection and contagion, showing, in fact, that these organisms are the causes and carriers of the various forms of disease. In the second, after an exhaustive account of the process of alcoholic fermentation has been given, a new theory of it is propounded, based, not upon chemical principles, like that of Liebig, but upon the principles of molecular physics. Fermentation is defined as being "the communication of the oscillations of the molecules, groups of atoms, and atoms of the substances composing the living protoplasm to the molecules of the fermentible substance, in consequence of which the equilibrium of the molecules of that substance is disturbed, and decomposition is the result." It is also pointed out that, in the case of yeast, the sugar is to some extent decomposed within the cells, but for the most part outside them.

Though this account of his works is but little more than an enumeration of them, yet it will suffice to show how important are Nägeli's contributions to botanical science in the departments of morphology, anatomy, and physiology, not merely as additions to the accumulated store of facts, but as new generalisations from those facts, and as opening up fields for future research.

SYDNEY H. VINES

PROF. TAIT ON THE FORMULA OF EVOLUTION[1]

ANOTHER point to which I ought thus early to direct your attention is the necessity for perfect definiteness of language in all truly scientific work. Want of definiteness may arise from habitual laziness, but it much more commonly indicates a desire to appear to know where knowledge is not. Avoid absolutely all so-called scientific writings in which (as Clerk-Maxwell said) the attempt is made to "give largeness of meaning" to a word by using it sometimes in one sense and sometimes in another. It is true that we may thus economise in our language, and avoid the necessity for introducing new and hard terms. But it would be a most expensive and pernicious economy. It is only a blockhead who could object to the use of a new term for a new idea.

Our only source of information in physical science is the evidence of our senses. To interpret truly this evidence, which is always imperfect and often wholly misleading, is one of the tasks set before Reason. It is only by the aid of reason that we can distinguish between what is physically objective, and what is merely subjective. Outside us there is no such thing as noise or brightness:—these no more exist in the aerial and ethereal motions, which are their objective cause, than does pain in the projectile which experience has taught us to avoid. You will find many prominent ideas, relics of a less enlightened age, from which Natural Philosophy has not yet wholly shaken itself free, which owed their existence solely to the confusion of the subjective with the objective.

With observation and experiment as our sole sources of information we have no right, in physical science, to introduce *à priori* reasoning. We may (unprofitably of course) speculate on what things might have been, but we must not dogmatise on what they ought to have been; we must simply try to discover what they are.

For aught that we can tell, the properties of matter, and physical laws in general, might have been other than we find them to be. How can any one of us tell whether his conscious self might not have been associated in life with the body of an Eskimo or of a New Zealander, instead of with what he (no doubt) considers its much preferable tenement? Speculations of such a kind must always be wholly unproductive and unprofitable, but for all that we cannot but allow that they are not intrinsically absurd.

Some years ago a critic of Mr. Herbert Spencer's Philosophy happened to quote from a book of mine the remark I have just made (that the properties of matter might have been other than we find them to be). Mr. Spencer's observation on this point is highly instructive. Had he not been a severely grave philosopher I should have taken it for a joke. He said, "Does this express an experimentally ascertained truth? If so, I invite Prof. Tait to describe the experiments."[2] Mr. Spencer has quite recently published a species of analytical inquiry[3] into my "mental peculiarities," "idiosyncrasies of thought," "habits of mind," "mental traits," and what not. From his illustrative quotations it appears that some or all of these are manifested wherever there are differences between myself and my critic in the points of view from which we regard the elements of science. Hence they are not properly personal questions at all, but

[1] Part of an Introductory Lecture delivered October 26, 1880.

[2] In my letter (NATURE, vol. ix. p. 402) will be found an illustrative anecdote, which Mr. Spencer declares to be "*not to the point.*" A great scientific man, to whom I showed the correspondence, remarked that Mr. Spencer must be the only man in England who could not see the perfect appositeness of the anecdote.

[3] *Appendix to First Principles, dealing with Criticisms.* (Williams and Norgate, 1880.)

questions specially fitted for discussion here and now. I may, therefore, commence by inquiring what species of "mental peculiarity" my critic himself exhibited when he seriously asked me whether I had proved *by experiment* that a thing might have been what it is not ! !

The title of Mr. Spencer's pamphlet informs us that it deals with *Criticisms;* and I am the first of the subjects brought up in it for vivisection, albeit I have been guilty (on Mr. Spencer's own showing) only of "*tacitly*" expressing an opinion ! Surely my vivisector exhibits here also some kind of "mental peculiarity." Does a man become a critic because he quotes, with commendation if you like, a clever piece of analysis or exposition published by another ?

In NATURE for July 17, 1879, I reviewed Sir E. Beckett's able little book, "Origin of the Laws of Nature," and as an illustration of that author's method I said :—

"He follows out in fact, in his own way, the hint given by a great mathematician (Kirkman) who made the following exquisite translation of a well-known definition :—

"'Evolution is a change from an indefinite, incoherent, homogeneity to a definite, coherent, heterogeneity, through continuous differentiations and integrations.'

"[Translation into plain English]—'Evolution is a change from a nohowish, untalkaboutable, all-alikeness, to a somehowish and in-general-talkaboutable not-all-alikeness, by continuous somethingelsifications and stick-togetherations.'"

Later in my article occurs the following paragraph, which also is quoted by Mr. Spencer :—

"When the purposely vague statements of the materialists and agnostics are thus stripped of the tinsel of high-flown and unintelligible language, the eyes of the thoughtless who have accepted them on authority (!) are at last opened, and they are ready to exclaim with Titania

"Methinks 'I was enamour'd of an ass.'"

The translation is from Kirkman's remarkable work, "Philosophy without Assumptions," which at that date I had just read with pleasure and profit. Humiliating as the confession may appear, I there saw Mr. Spencer's "Formula" for the first time, and I did not notice the title given to it. Hence, in quoting it from Kirkman, I very naturally called it by its proper name, a "Definition." For this I have incurred the sore displeasure and grave censure of the inventor of the definition. It seems I should have called him the *discoverer of the formula!* Now this is no petty quibble on words. It involves, as you will see immediately, an excessively important scientific distinction, to which your attention cannot be too early directed.

Mr. Spencer complains that an American critic (whose estimate is "tacitly" agreed in by Mr. Matthew Arnold) says of the "Formula of Evolution" :—"This may be all true, but it seems at best rather the blank form for a universe than anything corresponding to the actual world about us." On which I remark, with Mr. Kirkman, "Most just, and most merciful!" But mark what Mr. Spencer says :—

"On which the comment may be that one who had studied celestial mechanics as much as the reviewer has studied the general course of transformations, might similarly have remarked that the formula—'bodies attract one another directly as their masses and inversely as the squares of their distances,' was at best but a blank form for solar systems and sidereal clusters."

We now see why Mr. Spencer calls his form of words a *Formula*, and why he is indignant at its being called a *Definition.* He puts his Formula of Evolution along-side of the Law of Gravitation ! Yet I think you will very easily see that it is a definition, and nothing more. By the help of the Law of Gravitation (not very accurately quoted by Mr. Spencer) astronomers are enabled to predict the positions of known celestial bodies four years beforehand, in the *Nautical Almanac*, with an amount of exactness practically depending merely upon the accuracy of the observations which are constantly being made :—and, with the same limitation, the prediction could be made for 1900 A.D., or 2000 A.D., if necessary. If now Mr. Spencer's form of words be a formula, in the sense in which he uses the term as applied to the Law of Gravitation, it ought to enable us to predict, say four years before-hand, the history of Europe, with at least its main political and social changes ! For Mr. Spencer says that his "formula" expresses "all orders of changes in their general course,—astronomic, geologic, biologic, psychologic, sociologic"; and therefore "could not possibly be framed in any other than words of the highest abstractness."

Added, November 11, 1880.

Mr. Kirkman has lately "discovered a formula" more general than that of Evolution, the "Formula of Universal Change." Here it is :—

"Change is a perichoretical synechy of pamparallagmatic and porroteroporeumatical differentiations and integrations."

Even to this all-embracing formula, with Mr. Spencer's leave, I would apply the humbler but fitter term "definition."

Of Mr. Spencer's farther remarks there are but three which are directed specially against myself. (Mr. Kirkman is quite able to fight his own battles.) He finds evidence of "idiosyncrasies" and what not, in the fact that, after proclaiming that nothing could be known about the physical world except by observation and experiment, I yet took part in writing the "Unseen Universe"; in which arguments as to the Unseen are based upon supposed analogies with the seen. He says :—"clearly, the relation between the seen and the unseen universes cannot be the subject of any observation or experiment; since, by the definition of it, one term of the relation is absent." I do not know exactly what "mental peculiarity" Mr. Spencer exhibits in this statement. But it is a curious one. Am not I, the thinker, a part of the Unseen; no object of sense to myself or to others; and is not that term of relationship between the seen and the Unseen always present ? But besides this, Mr. Spencer mistakes the object of the book in question. The theory there developed was not put forward as probable, its purpose was attained when it was shown to be conceivable and not inconsistent with any part of our present knowledge.

Mr. Spencer's second fault-finding is *àpropos* of a Review of *Thomson and Tait's Nat. Phil.* (NATURE, July 3, 1879) by Clerk-Maxwell. Maxwell, knowing of course perfectly well that the authors were literally quoting Newton, and that they had expressly said so, jocularly remarked "Is it a fact that 'matter' has any power, either innate or acquired, of resisting external influences ?" Mr. Spencer says :—"And to Prof. Clerk-Maxwell's question thus put, the answer of one not having a like mental peculiarity with Prof. Tait, must surely be—No." Mr. Spencer, not being aware that the passage is Newton's, and not recognising Maxwell's joke, thinks that Maxwell is at variance with the authors of the book !

Finally, Mr. Spencer attacks me for inconsistency &c. in my lecture on Force (NATURE, September 21, 1876). I do not know how often I may have to answer the perfectly groundless charge of having, in that Lecture, given two incompatible definitions of the same term. At any rate, as the subject is much more important than my estimates of Mr. Spencer's accuracy or than his estimates of my "mental peculiarities," I may try to give him clear ideas about it, and to show him that there is no inconsistency on the side of the mathematicians, however the idea of force may have been muddled by the metaphysicians. For that purpose I shall avoid all reference to "differentiations" and "integrations"; either as they

are known to the mathematicians, or as they occur in Mr. Spencer's "Formula." Of course a single line would suffice, if the differential calculus were employed.

Take the very simplest case, a stone of mass M, and weight W, let fall. After it has fallen through a height h, and has thus acquired a velocity v, the Conservation of Energy gives the relation

$$M\frac{v^2}{2} = Wh.$$

Here both sides express *real things*; $M\frac{v^2}{2}$ is the kinetic energy acquired, Wh the work expended in producing it.

But if we choose to divide both sides of the equation by $\frac{v}{2}$ (the average velocity during the fall) we have (by a perfectly legitimate operation)

$$Mv = Wt,$$

where t is the time of falling. This is read:—*the momentum acquired is the product of the force into the time during which it has acted.* Here, although the equation is strictly correct, it is an equation between purely artificial or non-physical quantities, each as unreal as is the product of a quart into an acre. It is often mathematically convenient, but that is all. The introduction of these artificial quantities is, at least largely, due to the strong (but wholly misleading) testimony of the "muscular" sense.

Each of these modes of expressing the same truth, of course gives its own mode of measuring (and therefore of defining) force.

The second form of the equation gives

$$W = \frac{Mv}{t}.$$

Here, therefore, force appears as the time-rate at which momentum changes; or, if we please, as the time-rate at which momentum is produced by the force. In using this latter phrase we adopt the convenient, and perfectly unmisleading, anthropomorphism of the mathematicians. This is the gist of a part of Newton's second Law.

The first form of the equation gives

$$W = \frac{M\frac{v^2}{2}}{h},$$

so that the same force now appears as the space-rate at which kinetic energy changes; or, if we please, as the space-rate at which energy is produced by the force.

Here are some of Mr. Spencer's comments:—"force is that which changes the state of a body; force is a rate, and a rate is a relation (as between time and distance, interest and capital); therefore a relation changes the state of a body."

The contradiction which Mr. Spencer detects here, and over which he waxes eloquent and defiant, exists in his own mind only. The anthropomorphism which has misled him is but a convenient and harmless relic of the old erroneous interpretations of the impressions of sense.

P. G. TAIT

COMET-FINDERS

IT is only lately that the meteorites, or many of them which we see of a night making bright streaks in the heavens, have been shown to belong to definite streams having definite orbits and periods, and with the increase of our knowledge of these orbits the number of comets identified as travelling in the same orbits as meteor-streams has likewise advanced.

Now that the intimate relation between comets and meteorites has been settled, greater interest attaches to the discovery of these casual visitors, many of which have passed in our neighbourhood unobserved. This is shown by the increased number of comets seen, now that it is part of the business of several observatories to keep up a systematic search.

To do this properly, a telescope of large field of view is required, and a constant sweeping of the heavens must be kept up, and to do this with an ordinary equatorial is extremely tedious, owing to the continual change of the position of the body required.

To go back to early days of comet-finding, we call to mind the first instrument specially constructed for the purpose, so far as we are aware. It is a telescope of Galilean construction, with an object-glass of 2½ inches



diameter, and having a total length of 5 inches. This was made by Dollond during the first few years of this century for Dr. Kitchener. Since that time astronomical instruments have grown apace, and we have now before us Dr. Carl's "Repertorium für Experimental-Physik" containing a description of the new comet-finder constructed by Herr Schneider for the Observatory at Vienna.

The telescope of this instrument has an object-glass of

6 inches aperture and 4½ feet focal length, and the mounting is a striking change from what we are usually accustomed to see. The great point to be attained by it is to carry the telescope equatorially and allow it to move on a declination axis in such a manner that the eye-end remains stationary while sweeping the heavens. It will be seen from the plate which, by the kindness of Dr. Carl, we are able to reproduce, that the declination axis is carried above the polar axis somewhat in the usual way, but that the telescope, instead of being carried by its middle at the end of the declination axis, is carried by a frame, O, so that the eyepiece is in the prolongation of that axis, and also in the prolongation of the polar axis, so that it remains stationary, while the object-glass sweeps in all directions. The handles D and N, within easy reach of the observer, enable him to give the requisite motion to the telescope without the change of position necessary with an ordinary instrument. The telescope is balanced on the declination axis F by the counter-weight Q, and the excess of weight on one side of the polar axis is balanced by the counter-weights Q Q Q.

Herr Schneider proposes to mount telescopes of much greater size, say 30 or 40 feet long, in the same manner.

NOTES

M. MILNE-EDWARDS having completed the publication of his great work on "Physiologie Comparée," a subscription has been opened by M. Dumas, the Perpetual Secretary of the Academy of Sciences, for the purpose of presenting the veteran zoologist with a gold medal. Subscriptions are to be sent to M. Maindron at the Secretariat of the Academy of Sciences, or to M. Victor Masson, publisher, Boulevard St. Germain, Paris. M. Milne-Edwards's great work is composed of fourteen large octavo volumes—the first four of which are out of print—of 500 pages each; the publication began in 1857, and has been accomplished by twenty-three years of continual work. It includes all the lectures which have been delivered by M. Milne-Edwards at the Museum of Natural History during that lengthened period, and could not have been accomplished if the author had not had the advantage of the immense scientific resources accumulated in that establishment during the last two centuries for the study of nature.

A VIENNA correspondent sends us the following data regarding the Agram earthquake:—The damp ejected matter of the mud-volcano at Resnica near Agram was found to contain no elementary sulphur nor sulphuretted hydrogen, but it contained sulphur metals decomposable by acids, and earthy carbonates, along with organic substances of a humus nature. The chief constituent of it is fine sand with water, and it comes from no great depth. The mud-volcano at Sevete, near Agram, also ejects (2 m. high) chiefly a clayey-sandy mud, which may be thrown up by movements of the ground water. The Gratz geologist, Peters (writing in the *Tagespost*), characterises the Agram earthquake of November 9 to 14 as one of the most normal which could be observed in that region. The movement kept exactly the direction of south-south-west, and was thus precisely at right angles to the chief direction of the Eastern Alps. The entire breadth of the territory affected appears to be indicated by the towns of Klagenfurt (Carinthia) and Szegedin (Hungary). Since the formation of the Alps, and so through a long series of geological periods, all subterranean movements in this region of Central Europe have been in this one direction (as Süss first showed). For some months past movements have been perceived to be in progress in various localities. That Agram should be affected as it has been is explained by an inspection of the geological map. Not very far north from that town rises a remarkable block of greenstone surrounded by chlorite schist, limestone and other layers. A not very broad band of recent Tertiary deposits separates the low ground from that mountain block, which thus forms a comparatively fixed point in the system. Every movement coming from south-south-west propagated by these strata must impinge horizontally on the greenstone block, and cause a greater or less curvature of the strata, which manifests itself most where the lower ground remains free from Tertiary deposits. Unfortunately for Agram the strongest movement was directed precisely against that mountain block, and so upon the town before it. The whole phenomenon has nothing to do with volcanic processes. The repetition of the shocks is easily explained by the reaction from curvature of the strata not occurring all at once. In opposition to Peters, the astronomer and meteorologist, Rudolph Falb of Gratz, holds the Agram earthquake to be volcanic, and connected with the strong attraction of subterranean lava by the moon. They seem to have continued at more or less frequent intervals during the past week.

IN several parts of the Tyrol (Hall, Thaur, Rum, Innsbruck) an earthquake-shock was experienced on the 14th inst. about 9.15 a.m., and on the same day there was a considerable shock (lasting 20 sec.) in Bavaria, at Partenkirchen and Mittenwald about 8 p.m. Dr. Franz Woehner has been delegated by the Vienna Academy to Croatia to report on the phenomena.

A CYCLONE accompanied by earthquake shocks is reported to have occurred at Sitka in Alaska on October 25, causing much devastation.

JUST after the death of its founder, Dr. Broca, the well-known *Revue d'Anthropologie* entered on its tenth year. His successor in the direction of the *Revue*, Dr. Topinard, issues a prospectus intimating that it will be continued with renewed energy on the lines laid down by its founder. The *Revue* embraces all the varied departments of anthropology, and its editor has the collaboration of the most eminent workers in the varied departments in France. Broca left a great number of anthropological papers in various stages of completeness, and these are to be published in successive numbers of the *Revue*, which deserves every encouragement.

THE laboratory of M. Lacazes Duthiers at the Sorbonne has been opened this year again for experiments in zoology. In the summer it will be transferred to the coast station in Britanny.

THE Paris Museum of Natural History being situated in a somewhat out-of-way place, is rather deserted by the students, and great efforts are made to render the course of lectures which are delivered there unusually attractive. M. Fremy, Lecturer on Chemistry, will speak on the great discoveries in chemistry made almost simultaneously in Paris and in London about a century ago, and will perform all the original experiments, some of them with the very instruments which were used by the discoverers.

A VERY interesting acquisition has just been made by the botanical department of the British Museum. In 1783-4 John Millar made a series of water-colour drawings for the Earl of Bute, showing the "leaves, stalks, and ramifications of plants, for the purpose of ascertaining their several species." They are bound in five volumes, with an elaborately flourished title-page, and fill 928 octavo pages. The museum has purchased the drawings.

THE seismograph on Mount Vesuvius is said to indicate great subterranean dynamism. Streams of lava continue to flow down the north-west side of the cone, and are increasing both in volume and number. "The Vesuvian eruption," the *Times* correspondent states, "has entered on a phase of greatly increased activity. The news reached us on Saturday, but, as it appeared only in those papers which are directly interested in the Funicular

Railway, it was looked upon as an exaggeration to attract Sunday excursionists. It is now, however, confirmed that the lava is flowing over the side towards Naples, and, after having destroyed the outwork built to protect the upper station of the railway, is running rapidly in a vivid streak of fire parallel to the line, but at a distance which does not thus far imperil its safety. The spectacle is described as magnificent, and crowds were out watching the course of the lava and speculating on the fate of the Funicular Railway."

AN International Congress of Electricians accompanied by an International Exposition of Electricity will be held in Paris during the autumn of 1881. This Exposition is to be opened (under the patronage of the Government, though at the pecuniary risk of private parties) on August 1, and to continue until November 15 following. The Congress of Electricians will meet on November 15 in the rooms of the Palace of the Trocadéro. Opportunity will be given for exhaustive research in all the various branches. The Exposition will remain open each evening until eleven o'clock to afford opportunities of testing the practicability of the different systems of electric lighting. The Congress is to assemble under the presidency of the Minister of Posts and Telegraphs, and the vice-presidency of three French and three foreign delegates.

ON February 10, 1879, a few gentlemen interested in the study of man met in the Smithsonian Institution to devise a method of mutual improvement. The effort resulted in the formation of the Anthropological Society of Washington, with Major Powell for president, and Dr. Reynolds and Prof. O. T. Mason as recording and corresponding secretaries. Twenty-four papers have been read, which, if one might judge from their titles, are most interesting and valuable contributions. We learn from the *American Naturalist* that it is not yet decided whether a journal will be published, inasmuch as the Smithsonian Institution and the Bureau of Ethnology "afford ample opportunities of preserving all papers of permanent value." Without doubting this fact, we still hope that this young and vigorous society may not only have its own publication, but also that a long career of activity may ensue to provide the material for filling the pages of the same.

HERR V. BERGSÖ, in a recent work, "Fra Mark og Skov," has given some interesting data in regard to the habits of the Tarentula, *Lycosa tarentula*, Latr., whose nests he has traced and examined on the Roman Campagna. He found that the nest, which was well rounded and smooth, was approached by a tunnel which, after running about a foot straight down below the surface of the ground, made a sudden short turn before it finally descended for about another foot into the spider's abode. The entrance to the tunnel is concealed by an arched covering made by the interlacing of grasses and leaves. The eggs are inclosed in a spun bag, and the young appear in the autumn, when they immediately seat themselves on the body of the mother where they remain till about April, neither parent nor offspring seeking food during their hybernation. As many as 291 individuals were on one occasion removed in February from the body of an emaciated tarentula. The superstitious error of assuming that the bite of the animal induces an irresistible desire of dancing is due to the fact, that dancing having been originally employed as a remedy against the poison, which is believed to be eliminated by profuse perspiration, the action of the poison was confounded with the means of its eradication.

EXOTIC butterflies have long, from their beauty, engaged the enthusiastic attention of wealthy collectors, some of whom, as notably the late Mr. Hewiston, have also enriched entomological literature with works containing coloured figures of their favourite insects. M. C. Oberthür of Rennes, who, with his brother René, is the possessor of a very extensive entomological museum, in which is contained the late Dr. Boisduval's collection of Lepidoptera, has just published his Quatrième livraison of a work, "Études d'Entomologie," which has more or less regularly appeared during the last few years. The present part is devoted to the "Papilionidæ" of his collection, and six coloured plates illustrate the species and varieties which he considers it necessary to describe.

MUCH interest has been excited in Norway by the recent appearance of a colony of beavers on the Voldifjord, a branch of the Frierfjord, which is at a considerable distance from the beaver-station still remaining at Omli on Nedenæs.

UNDER the title *Iagttagelser over Nordlys anstillede i Norge, Sverige og Danmark*, bearbeidede af Sophus Tromholt (Christiania), we have the results yielded by 839 observations of the aurora borealis, at 132 Scandinavian stations, on 154 nights, between September 1878 and April 1879 on which the northern light was visible. These observations are arranged under four heads in accordance with (1) longitude and latitude of stations; (2) time of year and age of moon; (3) colour, form, and altitude of streamers; (4) sound. Herr Tromholt considers that it may be accepted as certain, that the aurora is a local phenomenon, circumscribed by narrow limits, and manifested at inconsiderable distances from the earth's surface; that the light is generally white, and less often red or green, but that in latitudes higher than Bergen it not unfrequently presents spectral colours; and that the accompaniment of sound is an indisputable fact in relation to the auroral phenomenon. We learn from *Naturen* that Herr Tromholt has resumed his observations of the aurora borealis, to which he has devoted his attention for many years. It is his intention to make a catalogue of every recorded manifestation of the northern light in Norway; and for this purpose he requests the co-operation of other observers, and will be grateful for reference to any foreign sources of information, such as ships' logs, journals, weather tables, almanacs, &c., which might yield materials towards the better elucidation of this phenomenon.

IN a letter addressed to Mr. Cust by Prof. F. W. Newman, and just published in the *Journal* of the Royal Asiatic Society, on the Libyan languages, the writer remarks that St. Augustine in his own day attested that one language prevailed in Roman Africa, and that it was quite natural to suppose the same to be the case now, when a large and striking similarity was found in the leading nouns and verbs. The changes however induced in 1500 years have broken up the original unity, and Prof. Newman states that we are now forced to admit at least four languages, each differing from the other more than German from Dutch, or Portuguese from Spanish.

THE annual course of five lectures in connection with the Brown Institution will be delivered by Dr. W. S. Greenfield, Professor-Superintendent, in the theatre of the University of London, Burlington Gardens, W., on December 13, 15, 17, 20, and 22, at 5.30 p.m. Subject: Further Investigations on Anthrax and Allied Diseases in Man and Animals. Microscopic specimens will be exhibited on December 22 from 4.30 p.m.

WE learn from *Psyche* that Miss Emily A. Smith, a well-known entomologist of Peoria, Illinois, has gone to Leipzig, where, if the university authorities will allow it, she will pursue a general course of zoological work in the new laboratory of Prof. Leuckart. This lady was recently elected a member of the Entomological Society of London.

CAPT. H. KING, R.N., writes with reference to the instances of fascination mentioned at p. 56, vol. xxiii., that having heard that the American ostrich might be enticed within gunshot by a person lying upon his back and kicking his legs and arms in the

air, he tried this with perfect success in Uruguay; he supposes that curiosity was the motive. A large coral upon the copper of a man-of-war, Capt. King states, is not unprecedented; he remembers in 1839 seeing one of the size and shape of a large cauliflower, taken from the bottom of a vessel of the Indian navy, in the Persian Gulf, by a pearl-diver.

PROF. GRAHAM BELL has promised to read a paper before the Society of Arts upon his "Photophone" at the ordinary meeting on Wednesday, December 1. As considerable interest is likely to attach to this paper it is announced that only members of the Society can be admitted, and that they will be required to provide themselves with special tickets issued for the occasion.

WE referred in the "Physical Notes" of our issue of November 11 to a paper read before the American Association at Boston by Prof. Young, which combated certain phenomena in thermo-electricity which were alleged to have been observed by Herr Exner. We have since received from Mr. T. Brown of Belfast a letter in which, on behalf of Prof. Franz Exner of Vienna, he expressly disavows any such discoveries as those which Prof. Young has set himself to refute. We readily accord to our courteous correspondent the opportunity for this disavowal, since any reflections cast even inadvertently upon the accuracy of Prof. Franz Exner's work might unfairly prejudice readers against the general reliability of the researches which he has published in another department of science, and which our readers are aware are just now exciting considerable attention.

IN NATURE, vol. xxii. p. 616, it was stated, on the authority of the Japanese papers, that Prof. Atkinson had, "during a sojourn in the Mitake Mountains of the Province of Koshu, discovered another valuable deposit of coal." We are now informed that although Mr. Atkinson visited the Mitake Mountains last summer, he can lay no claim to so important a discovery.

THE Hon. Sir Ashley Eden, K.C.S.I., has appointed Babu Ambika Churn Sen, M.A., and Synd Sakhawat Hossein, B.A., a native of Behar, to the two scholarships of 200*l.* a year each, recently created by the Bengal Government to be held at the Royal Agricultural College, Cirencester.

THE Procureur-General of Paris having sent an explanatory note stating that he did not mean to attack the character of the medical advisers of the public prosecutor, but merely to give vent to his peculiar views, these gentlemen have withdrawn their resignations and resumed their work.

THE Cutlers' Company have arranged for a course of lectures being delivered, or papers read, at the hall of the company during the ensuing winter season. The course will consist of four lectures or papers upon subjects intimately connected with the materials used in the manufacture of cutlery, the lectures to take place on the following dates:—Wednesday, December 1, 1880; Wednesday, January 5, 1881; Wednesday, February 2, 1881; Wednesday, March 2, 1881. Sir Henry Bessemer, C.E., F.R.S., has promised to commence the course, and will, on December 1, read a paper "On the Manufacture and Uses of Steel, with special reference to its employment for Edge Tools." The admission will be entirely free, but by ticket, which may be obtained on application to the hon. secretary, addressed to the Cutlers' Hall.

IT is announced that the electric cable manufacturing firm, Berthoud Borel and Co. of Cortaillod, in Neuchâtel, have made a highly important discovery in practical telegraphy. After a long and expensive series of experiments they have succeeded in devising a method of laying cables whereby the inductions of the electric current from one wire to another, although the wires are in juxtaposition, is prevented. This discovery, it is asserted, removes the last obstacle in the way of the widest possible extension of facilities for telephonic communication.

OUR ASTRONOMICAL COLUMN

THE THIRD COMET OF 1869.—This comet, the orbit of which has so close a resemblance to that of the comet discovered by Mr. Swift on October 11, was detected at Marseilles by M. Tempel on November 27, 1869, in the constellation Pegasus, and appears to have been last observed on December 31 at Leipsic and Kremsmunster, the hope of seeing it after the next period of moonlight not having been verified. On November 29 Dr. Vogel, observing at Leipsic, described it as a very faint large object elongated in the direction of the declination circle: in the comet-seeker its diameter was about 6'. On December 7 it was still very faint, large, and elongated in the direction 300°, the central condensation very slight. On the following night its diameter was 5'; it had "a peculiar milky appearance" and hardly any central condensation, so that observations were attended with difficulty. On the 21st it was seen only with much exertion of the eye, but on the 31st, though the comet was very faint, Prof. Bruhns considered his separate comparisons certain to about ten seconds of arc. At Kremsmunster Prof. Strasser found it "extraordinarily faint" during its entire visibility, and in consequence of wanting central condensation, very difficult to observe, and hence considered that his positions would not possess the ordinary degree of accuracy. The elements of the orbit were calculated by Tiele, Oppolzer, Schulhof, and Bruhns, the parabolic orbit published by the latter in No. 1788 of the *Astronomische Nachrichten* being founded upon nearly the whole extent of observation; he remarks with respect to it:—"Eine angestellte Vergleichung hiesigen Beobachtungen scheint aber doch auf eine Abweichung der Bahn von der Parabel hinzudeuten . . ." We are not aware that any further examination of this point was made. If the period of revolution be really something less than eleven years, the circumstance of the comet having escaped observation prior to 1869 will not nevertheless occasion surprise, considering that both in 1869 and 1880 it has approached near the earth and has yet been very faint and diffused, so that when the perihelion passage has occurred at other seasons of the year it might be beyond reach of the telescope. It will be most essential for the theory of the comet's motion that observations should be continued as long as possible at the present appearance, that if it prove to be one of short period its next return to perihelion may be closely predicted: the computation of the planetary perturbations during the period 1869–80 will of course be a necessary process with this object in view.

THE STAR LALANDE 1013-4.—Mr. G. Knott has examined this star, to which we lately drew attention, as being credited with the very discordant magnitudes 5, 7·7, and 10. He writes from Cuckfield on November 21: "I looked the star up on November 8 and again on November 19, and found it on each occasion 7·9 mag., and sensibly equal to B.D. + 51°, No. 131, which forms a convenient comparison star. This estimate, it will be seen, agrees nearly with that in the *Durchmusterung*; Harding marks the star 6m.

CHEMICAL NOTES

IN the last number of the *Berichte* of the German Chemical Society Herr v. Lippmann describes experiments which show that a solution of pure cane sugar, when charged with carbon dioxide, is slowly converted into inverted sugar. If the carbon dioxide be pumped into the sugar solution under pressure, the rate of inversion is considerably increased: at 100° the inversion takes place rapidly.

IN the *Annales Chim. et Phys.* the results of M. Raout's experiments on the freezing points of alcoholic liquids are detailed. An aqueous solution of alcohol containing 1·6 per cent. by volume freezes at − 0·5; a solution containing 47·9 per cent. freezes at − 32°. The freezing point of solutions containing from 24 to 51 gram alcohol per 100 grm. water is decreased by 0°·528 for each gram of alcohol: when more than 51 grm. alcohol are present to 100 grm. water no regular decrease in the freezing point was observable. The freezing points of various wines are given in the paper referred to.

IN *Comptes rend.* M. Kessler announces that he has prepared a crystallised hydrate of hydrofluosilicic acid, viz., $H_2SiF_6 . 2H_2O$. The hydrate is a hard, colourless, very deliquescent solid, which fumes strongly in air, and melts at about 19°.

In the same journal M. de la Source describes his experiments on the dialysis of ferric oxide dissolved in a solution of ferric chloride. "Fer Bravais" of medicine consists of $30Fe_2O_3 . Fe_2Cl_6$; after three months' dialysis of a dilute solution of this substance the greater part of the chlorine had passed into the dyalysate, the proportion of ferric oxide to chloride was then $116Fe_2O_3 . Fe_2Cl_6$, and the chlorine yet continued to pass through the dialyser. The author thinks that ferric hydrate is, *per se*, under certain conditions soluble in water.

Herr A. Herzen describes in *Bied. Centralblatt* some experiments on acetous fermentation. In each of three flasks was placed 100 c.c. pure water: to the first flask 10 per cent. pure alcohol and a drop from the surface of a fermenting wine full of *Mycoderma aceti* were added; to the second flask were added 5 per cent. of pure acetic acid and a drop of the fermenting wine; and to the third flask were added 5 per cent. acetic acid, 5 per cent. of a saturated solution of boric acid, and a drop of the fermenting wine. After eight days at 25° no *Mycoderma* appeared in the first flask, much appeared in the second, and a little in the third. Hence the author concludes that *Mycoderma aceti* lives at the expense of acetic acid already formed in wine, and that it does not cause the transformation of alcohol into acetic acid, but that it is rather a consequence of this chemical change; further, that boric acid retards the development of *Mycoderma*, but does not prevent it in presence of already-formed acetic acid.

In *Dingler's Polytech. Journal* a paper appears by Drs. Lunge and Schäppi, on bleaching-powder. The results confirm the now generally accepted formula first proposed by Odling, viz., CaOClCl.

It was shown some time ago by H. T. Brown that alcoholic fermentation proceeds more slowly under diminished than under ordinary pressure. According to Boussingault (*Compt. rend.*), however, sugar is rapidly transformed into alcohol by the action of yeast, if the carbon dioxide and alcohol, as these are produced, be rapidly removed from the fermenting liquid. Addition of alcohol soon stops fermentation under ordinary circumstances; Boussingault shows that if the vessel containing the fermenting liquid be connected with an air-pump which is worked energetically, fermentation proceeds rapidly even when a considerable amount of alcohol has been added to the liquid.

In connection with the recent liquefaction of ozone by Hautefeuille and Chappuis, the following numbers, from a paper by the same authors in *Compt. rend.*, are of interest, as showing the exact influence of temperature and pressure on the ozonising of oxygen. Diminution of pressure does not tend to increase the amount of ozone produced, but decreased temperature exerts a marked action in increasing the amount of oxygen transformed into ozone:—

Tension of oxygen.	Tension of ozone.				Proportion of ozone by weight.			
	−23°.	0°.	20°.	100°.	−23°.	0°.	20°.	100°.
760	108·70	82·84	53·96	—	0·214	0·149	0·106	—
380	51·68	38·76	31·54	1·48	0·204	0·152	0·125	0·0117
300	40·20	30·60	22·20	—	0·201	0·1525	0·112	—
225	24·80	22·95	15·52	0·088	0·191	0·153	0·104	0·0118
180	22·30	16·58	10·52	—	0·181	0·137	0·089	—

A. Ditte describes in *Compt. rend.* a number of new fluorine compounds of uranium; the most important are $UF_6 . 8HF$ and UO_2F_2, produced by the action of hydrofluoric acid on the oxide U_3O_8; when the former compound is heated in a closed platinum dish it melts, gives off hydrofluoric acid and small quantities of the oxyfluoride UOF_4, which compound is produced in larger quantity by heating the above-mentioned oxyfluoride, UO_2F_2, in a closed vessel. The hexfluoride UF_6 is produced by heating the double salt $UF_6 . 8HF$ in an open crucible. Various double salts are also described, the general formula being $UO_2F_2 . 4MF$, where M may be K, Na, Li, Rb, or Tl.

Cleve has made a redetermination of the atomic weight of the very rare metal erbium (*Compt. rend.*). Assuming the formula of the oxide to be Er_2O_3, the atomic weight of the metal is 166. Pure erbia, Er_2O_3, is a beautiful rose-coloured earth, slowly soluble in acids, having a specific gravity of 8·64, and forming salts characterised by a deep-red colour; several of these salts are described by Cleve.

The same author has succeeded in separating nearly pure *thulium*; this metal and its salts are colourless, but solutions of the salts show two absorption bands, one strongly marked in the red, and one broad band in the blue. The atomic weight of thulium is 129·6 or 170·7, according as the metal is regarded as di- or tri-valent.

PHYSICAL NOTES

It is stated that amongst the recent discoveries of Prof. Bell in connection with the photophone research is the interesting fact that melted sulphur conducts electrically like selenium, but only at temperatures below that at which it thickens and becomes dark and viscid.

The *Comptes rendus* for November 2 informs us that Prof. Graham Bell and M. Janssen have attempted to *hear* with the photophone the sounds believed to accompany the rapid commotions taking place in the solar photosphere. The experiments were made at the Observatory of Meudon, a selenium cylinder being placed in different parts of an image of the sun some two feet in diameter. No very conclusive results were obtained, but M. Janssen has further suggested that a sort of concentrated effect might be obtained by passing a number of successive photographs of a sun-spot across a beam of light, the variations of the intensity of the beam producing sounds when they fall upon the sensitive "photophonic pile" of selenium. Some experiments in furtherance of this suggestion are now proceeding.

Having undertaken a series of researches upon the rapidity of evaporation of liquids, in dependence from the cohesion of molecules on their surfaces, M. Sreznevsky has measured how this rapidity varies with the variations of the height of the meniscus. He has established that, the diameter of the meniscus remaining invariable, the rapidity of evaporation increases as the height of the meniscus diminishes, that is, as its radius increases. There is however an anomaly as to this last law for distilled water: when the evaporation is measured in a meniscus the height of which is greater than the radius of its basis, the rapidity of evaporation increases throughout, however the radius of the meniscus begins by diminishing, and increases only after having passed through a minimum, but this minimum does not have a corresponding minimum in the rapidity of evaporation.

At the recent meeting of the Helvetic Society of Natural Sciences M. Forel described a *thermal bar* which is developed in winter parallel to the shore of a lake of fresh water, and which separates the pelagic from the littoral region. The water of the former region remains long, and in some lakes always, at a temperature above 4° C.; in the littoral region, if the winter be cold, the temperature descends between 4° and zero; and between the two there is a band of water at 4°, descending to the bottom —a kind of mountain with crest parallel to the shore and a talus on either side.

M. Dufour described at the same meeting an apparatus for indicating the variations of chemical intensity of the sunlight. It has some likeness to Draper's tithonometer; the principle is, opposing the variable action of light on a mixture of chlorine and hydrogen, with an electric current (of variable intensity, and measurable each instant), which by its passage causes decomposition of a quantity of hydrochloric acid equal to that produced by action of the light on the mixture of chlorine and hydrogen. The apparatus is like a Rumford differential thermometer; in one bulb is some hydrochloric acid solution, with carbon electrodes, in the other some sulphuric acid. The light acts on the former. One mode of measurement is to note the time taken in displacement of the sulphuric acid column a certain distance along the connecting tube. Then bring back the column to its original position by passing the current.

M. Pictet has lately made experiments (*Arch. de Sci.*) as to the dissolving power of gases and vapours on one another. Various solutions of alcohol and water were successively put into one of two glass balloons connected by a tube; pressure was diminished with an air-pump, so that the space became filled with vapours from the mixture. By closing the tapered point of the second balloon with the blowpipe, the apparatus allowed of distillation being effected with small differences of temperature. Plunging successively the balloon that held the solution in water at from 0° to 80°, and the other in water only 1° or a fraction of a degree below that of the liquid, M. Pictet got condensed products, the quality of which indicated what "affinity of solution" existed between water and alcohol. The following conclusions were arrived at: The weight of condensed liquid is proportional, in unit time, to

the *difference of temperature* between the liquid in ebullition and the condensed liquid. The weight of liquid condensed in unit time is independent of the interior pressure or of the mean temperature during distillation. Analysis shows that the gases have no power of solution on one another. M. Pictet was thus led to an industrial process for rectification of spirits.

GEOGRAPHICAL NOTES

AT the meeting of the Geographical Society on Monday, Sir Bartle Frere read what may best be described as a suggestive paper on Temperate South Africa as a route to the Central Equatorial Region. After defining the temperate region as the vast tract of country extending to Cape Frio on the Atlantic coast and to the mouth of the River Tugela on the opposite side of the continent, and giving a brief account of its geography, &c., Sir Bartle addressed himself chiefly to the task of pointing out how it could be made available as a base of operations in exploring the country north of the Zambesi, and suggesting agencies which might be turned to account for the extension of geographical knowledge. These agencies are the traders and hunters, who have a wide acquaintance with many regions otherwise unknown, and missionaries of various denominations. The latter have no less than eighty-four fixed stations beyond the colonial boundaries, manned by 812 Europeans, many of whom are highly-cultivated and intelligent men, and have great opportunities for acquiring geographical information. Sir Bartle Frere also hoped that the Council of the Society might see their way to urging the Government to undertake a proper survey of the coast-line, as well as of the interior of the five colonies.

AT the meeting of the Berlin Geographical Society on November 6 the safe arrival of Dr. Lenz at Timbuctoo (by a route not before taken by any European) was announced. Two of his followers were lost in the desert, and two had gone back. Dr. Stecker (who lately went to Massowah with Herr Rohlfs) will, according to circumstances, either push through the Galla regions or to the East coast, or to the Great Lakes. Major v. Mechow reached a town on the Quanza, in the territory of the Hollo, about 200 km. from Malange on July 19, after great difficulties, especially in carriage of the boat. The natives were friendly throughout. A little above the place reached are the two last falls of the Quanza, between which is the mouth of the Cambo. The Major seems to have been the first white to visit these waterfalls. He was going to Löpung with a view to determine the course of the Quanza. Dr. Pogge and Lieut. Wissmann were also travelling in that region the same month, intending to reach Mussumba, the residence of the Muata Jambo; Dr. Pogge's object is to establish stations in the interior. Lieut. Wissmann will make journeys for topographical and collecting purposes. The Italian traveller, Dr. Matteucci, is seeking to reach Bornu from South Dar-For, going round Wadai and Bagirmi. *Inter alia* the Society resolved to memorialise the German Government to take part in the international project of systematic Polar investigation.

AT the sitting of November 19 of the Société de Géographie of Paris M. Zweifel received the palm of Officer of the Academy as a reward for the discovery of the sources of the Niger, in company with M. Marius Moustier. The laureate declining to speak himself, an address was delivered on behalf of him and his companions by Dr. Harmand, the well-known explorer of Cochin China. It appears that MM. Zweifel and Moustier saw a granite rock from which the powerful stream takes its rise; but they were not admitted to the site, owing to the high priest of Tembi Saleh, who inhabits an island situated on a small lake formed by the stream at a very few miles from its source. So something more remains to be done to complete the work begun by Laing, Reade, and Blyden.

SIR ALLEN YOUNG leaves England next month in his yacht, and will visit, among other places, the Canary Islands, a portion of the West Coast of Africa, and St. Helena, extending his voyage as far as the Cape, where he will make preparations and inquiries for a projected expedition of discovery to be undertaken by him to the Antarctic regions. It will be remembered that the *Erebus* and *Terror*, commanded by Sir J. Ross and Capt. Crozier, penetrated in 1841 to 78° 4′ S., a latitude which has never been reached before or since.

THE November number of *Petermann's Mittheilungen* has a long paper by Spiridion Gopčević, containing his ethnographical studies in Upper Albania. A very fine map embodies the important results of Severzov's exploration of the Pamir in 1878, with accompanying text, followed by an account of Lieut.-Col. Pjevzov's journey through Mongolia in 1878-9, to Kuku-Choto and Kalgan. A summary is given of the Arctic work of 1880, followed by the usual monthly notes.

THE first *Bulletin* of the recently-formed International Geographical Institute at Berne consists of a programme of the projected Italian Antarctic Expedition under Lieut. Bone, which is to leave Genoa in March 1881. A sketch is given of what has been previously done in this region, showing that the field is practically virgin so far as scientific work is concerned. The programme of the Italian expedition is very comprehensive, and the ultimate object is to pave the way for the establishment of an Antarctic observing station.

NO. 3 of vol. iii. of the *Deutsche geographische Blätter*, the organ of the Bremen Geographical Society, contains the continuation of the unfortunate Dr. Rutenberg's journal in Madagascar, and the lecture given at the Danzig meeting of the German Association by Dr. Neumayer on "Polar Expeditions or Polar Research?" To the latter able lecture we referred last week, the point insisted on being that while the two are perfectly congruous, the former should be subjected to the latter, which must be carried out on the system of Polar observatories advocated by Weyprecht, and to which nearly every civilised nation adheres except England.

THE new number of the Marseilles Geographical Society's *Bulletin* contains a very voluminous account by Messrs. Zweifel and Moustier, of their expedition to the sources of the Niger. This memoir is illustrated by a map showing their route, and supplemented by an appendix containing information as to the natural resources of the country traversed, the races of the interior, &c.

THE last part of *Le Globe* contains a paper (with map) on the Island of Cyprus, by M. Paul Chaix, and some account of recent researches in the Pamir, furnished by M. Veniukoff.

IN the current number of *Les Missions Catholiques*, M. Armbruster has commenced a series of papers on Corea, drawn from information furnished from time to time by the Romish missionaries, the only Europeans who have ever had any opportunity of acquiring a real knowledge of the interior.

UNIVERSITY AND EDUCATIONAL INTELLIGENCE

OXFORD.—The preliminary examination in the Natural Science School begins on Monday next, November 29. The Final Honour School begins on Monday, December 6.

The Brakenbury Scholarship in Natural Science at Balliol College has been awarded to Mr. William Stroud, from Owens College, for proficiency in physics and chemistry. *Proxime accessit* Mr. A. D. Hall, from Manchester Grammar School. Mr. J. J. Hart, Manchester Grammar School, and Mr. J. E. Marsh of Balliol, are honourably mentioned.

ON A METHOD OF DETERMINING THE CRITICAL TEMPERATURE FOR ANY LIQUID AND ITS VAPOUR WITHOUT MECHANISM[1]

A PIECE of straight glass tube—60 centimetres is a convenient length—is to be filled with the substance in a state of the greatest purity possible. It is to contain such a quantity of the substance that, at ordinary atmospheric temperatures, about 3 or 4 centimetres of the tube are occupied by steam of the substance, and the remainder liquid. Fix the tube in an upright position, with convenient appliances for warming the upper 10 centimetres of the length to the critical temperature, or to whatever higher or lower temperature may be desired; and for warming a length of 40 centimetres from the bottom to some lower temperature, and varying its temperature conveniently at pleasure.

Commence by warming the upper part until the surface of separation of liquid and steam sinks below 5 centimetres from the top. Then warm the lowest part until the surface rises

[1] By Sir William Thomson, British Association, Swansea, Section A. Tuesday, August 31.

again to a convenient position. Operate thus, keeping the surface of separation of liquid and solid at as nearly as possible a constant position of 3 centimetres below the top of the tube, until the surface of separation disappears.

The temperature of the tube at the place where the surface of separation was seen immediately before disappearance is the critical temperature.

It may be remarked that the changes of bulk produced by the screw and mercury in Andrews' apparatus are, in the method now described, produced by elevations and depressions of temperature in the lower thermal vessel. By proper arrangements these elevations and depressions of temperature may be made as easily, and in some cases as rapidly, as by the turning of a screw. The dispensing with all mechanism and joints, and the simplicity afforded by using the substance to be experimented upon, and no other substance in contact with it, in a hermetically sealed glass vessel, are advantages in the method now described. It is also interesting to remark that in this method we have continuity through the fluid itself all at one equal pressure exceeding the critical pressure, but at different temperatures in different parts, varying continuously from something above the critical temperature at the top of the tube to a temperature below the critical temperature in the lower part of the tube.

The pressure may actually be measured by a proper appliance on the outside of the lower part of the tube to measure its augmentation of volume under applied pressure. If this is to be done, the lower thermal vessel must be applied, not round the bottom of the tube, but round the middle portion of it, leaving, as already described, 10 or 20 cms. above for observation of the surface of separation between liquid and vapour, and leaving at the bottom of the tube 20 or 30 cms. for the pressure-measuring appliance.

This appliance would be on the same general principle as that adopted by Prof. Tait in his tests of the *Challenger* thermometers under great pressure (*Proceedings*, Royal Soc. Edin., 1880); a principle which I have myself used in a form of depth-gauge for deep-sea soundings; in which the pressure is measured, not by the compression of air, but by the flexure or other strain produced in brass or glass or other elastic solid.

ABNORMAL VARIATIONS OF BAROMETRIC PRESSURE IN THE TROPICS, AND THEIR RELATION TO SUN-SPOTS, RAINFALL, AND FAMINES

IN the first part of his work on the Meteorology of the Bombay Presidency, which was submitted to Government in August, 1875, Mr. Charles Chambers pointed out that the variation of the yearly mean barometric pressure at Bombay shows a periodicity nearly corresponding in duration with the decennial sun-spot period (see "Meteorology of the Bombay Presidency," § 26, p. 12), and in August, 1878, in a letter to NATURE, vol. xviii. p. 567, I drew special attention to this relation, pointing out that the observations of the winter and summer half-years, separately as well as conjointly, show that the pressure is low when the sun-spot area is great, and *vice versâ*, but that the pressure curve *lags behind* the sun-spot curve.

In November of the same year the eminent physicist, the late Mr. John Allan Broun, regarding the relation thus established between the variations of barometric pressure and sun-spots as one of very great importance, in that it gave a probability to the existence of similar laws in the variations of other meteorological elements which he believed was previously wanting, communicated to the same periodical (NATURE, vol. xix. p. 6) an article in which he showed, from the observations recorded at Singapore, Trevandrum, Madras, and Bombay, that the years of greatest and least mean barometric pressure are probably the same for all India, and from this he inferred that the relation to the decennial sun-spot period found for Bombay holds for all India.

In December, 1878, Mr. S. A. Hill supplemented and confirmed Mr. Broun's communication by giving similar data for Calcutta (NATURE, vol. xix. p. 432).

In May, 1879, Mr. E. D. Archibald communicated to NATURE, vol. xx. p. 28, the fact (brought to his notice by Mr. S. A. Hill) that at St. Petersburg the mean annual barometric pressure is high when the sun-spots are numerous, low when they are few, but that the pressure epochs lag behind the sun-spot epochs.

In December of the same year Mr. Blanford presented to the Asiatic Society of Bengal a paper (*Journal* of the Asiatic Society of Bengal, vol. xlix. part ii. 1880, p. 70) in which it was shown that the barometric observations recorded at Batavia from 1866 to 1878, at Akyab, Chittagong, and Darjeeling from 1867 to 1878, at Port Blair from 1868 to 1878, and at Singapore from 1869 to 1878, afford more or less confirmation of the results previously obtained for other stations in India.[1] And in the same paper Mr. Blanford brought forward the observations recorded at the Russian observatories at Ekaterinburg, Slatoust, Bogolowsk, and Barnaul from 1847 to 1877, and showed that at the two former stations during the whole period, and at the two latter during the first half of it, the barometric variations were similar to those previously obtained by Mr. Hill for St. Petersburg.

In a subsequent letter to NATURE, published in March, 1880, Mr. Blanford discussed the same observations in greater detail, dealing with the summer and winter observations separately, as well as conjointly, and showed that the decennial variation of the barometric pressure found for St. Petersburg was exhibited only by the observations of the winter months. He also obtained similar results for Ekaterinburg and Barnaul, but he appears to have overlooked the very important facts that the range of the winter curves rapidly decreases in passing from St. Petersburg, through Ekaterinburg to Barnauland, that the summer curves for the two latter stations are, on the whole, of the *same* character as the summer curves of the Indian stations, as may be seen by comparing the dotted curves for Ekaterinburg and Barnaul, given in NATURE, vol. xxi. p. 48, with the summer curve for Bombay, given in vol. xviii. p. 568 of the same periodical. He also showed that the barometric curves for Batavia, Singapore, and Port Blair were, as at other Indian stations, of the same character both in winter and summer.

In 1873 and 1874 (see British Association Reports for those years) Mr. Meldrum showed that there was strong evidence of a connection between sun-spots and rainfall, and he has recently (see *Monthly Notice* of the Meteorological Society of Mauritius for December 1878) put this question beyond all reasonable doubt by showing that the mean yearly rainfall of Great Britain, the continent of Europe, America, India, and the Southern Hemisphere, varies in the same way as the sun-spots, being on the average great when they are numerous, small when they are few.

In my "Brief Sketch of the Meteorology of the Bombay Presidency"[2] in 1876, I pointed out that the abnormal variations of the monthly mean barometric pressure in that year were mainly variations in the intensity of the usual seasonal movements, although at least some portion of the variations influenced a wider area than the Indian monsoon region, and in the Sketch for 1877 I attributed the uniformly high barometric pressure and the deficient rainfall of that year to a weak development of the equatorial belt of minimum pressure, probably induced by a diminution of the solar heat.

In the Report on the Meteorology of India in 1877 Mr. Eliot showed that the high pressure of that year was a characteristic of the whole Indian area and also of Australia.

In my meteorological sketch for 1878 I showed that the abnormal barometric movements observed at Zi-ka-wei in China and at Manilla in 1878 were similar to those recorded in Western India; that the latter largely influenced the rainfall of the Bombay Presidency; and that in former years of deficient rainfall at Bombay the barometer had been relatively high, not only at Bombay, but also at Mauritius and Batavia.

In the paper (*Journal* of the Asiatic Society of Bengal, vol. xlix. part ii., 1880, p. 70) already quoted, Mr. Blanford has confirmed the fact that the excessive pressure observed in the Indian area in the years 1876 to 1878 extended to China and Australia, and he has also shown that it affected Western Siberia also.

In my sketch for the year 1879 I have shown that these uniform variations of barometric pressure are accompanied by a nearly uniform variation of the percentage rainfall of all portions

[1] During the first half of these periods the results for Singapore, Akyab, Chittagong, and Darjeeling differ so much from each other and from the remarkably accordant results obtained from the more widely separated stations of Bombay, Calcutta, Port Blair, and Batavia as to suggest that the former are of doubtful validity during the earlier years.

[2] These sketches are submitted annually to Government in August of the year following that to which they refer. See notices in NATURE, vol. xviii. pp. 199 and 619, vol. xxi. p. 384. The sketch for 1879, containing some further important conclusions with reference to the variations of rainfall and barometric pressure, has recently been submitted to Government.

of the Bombay Presidency, and that the proportionate increase or decrease of the abnormal rainfall, corresponding to a fall or rise in the abnormal pressure of a tenth of an inch of mercury, amounts to more than *one hundred per cent.* of the normall fall; but that the variations of the ordinary monsoon gradients produce very different effects on the rainfall of different districts, depending on the geographical peculiarities of the particular locality.

From all these facts it is clear that there is some intimate relation between the variations of sun-spots, barometric pressure, and rainfall; and as famines in general are induced by a deficiency of rain, it is probable that they also may be added to the above list of connected phenomena. What is required in order to gain an insight into the causal relation of these variations is that they should each and all be studied in greater detail than has hitherto been attempted. Accordingly I commenced, more than a year ago, a detailed investigation into the nature of the abnormal variations of barometric pressure, and have been led to the discovery of some new facts which appear to me to be of sufficient importance to render it desirable that they should be published in anticipation of the theoretical conclusions deducible therefrom.

Commencing with the daily abnormal barometric variations observed at several stations in Western India, it was soon found that as the time over which an abnormal barometric fluctuation extended became longer and longer, the range of the fluctuation became more and more uniform at the various stations, thus leading to the conclusion that the abnormal variations of long



duration affect a *very wide area*. To test this inference it became necessary to compare the observations recorded at Bombay with those of some distant tropical station. Batavia was chosen, and on curving the daily observations side by side with those of Bombay, the degree of accordance between them was found to be truly surprising, considering how far the two stations are apart. The next step was to compare the monthly abnormal variations of these two stations, and finding that they presented many similar features, as well as some differences, to smooth the variations by taking three-monthly means. The degree of accordance was now found to be still greater, many of the discordances having been eliminated in the process of smoothing; but as some differences were still observable the process was repeated, giving nine-monthly means of abnormal pressure corresponding to the middle of the months January, April, July, and October of each year. The curves obtained in this way for Bombay and Batavia were then found to be *almost identical in form*, but with this very remarkable difference: *the curve for Batavia was seen to lag very persistently about one month behind the Bombay curve.* Similar results were then worked out from all the available data for the following tropical stations: St. Helena, Mauritius, Madras, Calcutta, and Zi-ka-wei, and for comparison with them the monthly sun-spot areas[1] were treated in exactly the same manner. The results are given in the fol lowing table, and graphically represented by the continuous curves on the annexed plate:—

[1] Taken from the paper by Messrs. De La Rue, Stewart, and Loewy, published in the *Philosophical Transactions* for 1870, p. 122.

TABLE I.

Nine-Monthly Means of Solar Spotted Area and Abnormal Barometric Pressure

Year.		Solar spotted area in millionths of visible hemisphere.	Abnormal barometric pressure in thousandths of an inch.					
			St. Helena.	Bombay.	Madras.	Calcutta.	Batavia.	Zi-ka-wie.
1841	1	473	+ 5					
	2	354	+ 8					
	3	359	- 12		- 1			
	4	285	- 14		- 7			
1842	1	241	- 11		- 18			
	2	207	- 3		- 23			
	3	236	+ 1		- 14			
	4	209	+ 3		- 2			
1843	1	188	+ 2		+ 4			
	2	116	+ 2		+ 3			
	3	107	+ 5		+ 2			
	4	102	+ 2		+ 8			
1844	1	130	- 5		+ 1			
	2	177	- 7		- 5			
	3	178	- 8		- 1			
	4	265	+ 2		+ 11			
1845	1	374	+ 10		+ 14			
	2	423	+ 17		+ 8			
	3	360	+ 21		+ 13			
	4	407	+ 16		+ 25			
1846	1	556	+ 11		+ 30			
	2	657	+ 3		+ 23			
	3	611	- 1		+ 7			
	4	664	- 3		- 6			
1847	1	719	- 1		- 7			
	2	841			- 4			
	3	1110		- 10	- 2			
	4	1295		- 12	- 10			
1848	1	1251		- 16	- 13			
	2	1053		- 12	- 11			
	3	969		- 3	- 11			
	4	1144		+ 4	- 13			
1849	1	1096		0	- 26			
	2	962		- 8	- 24			
	3	761		- 12	- 22			
	4	672		- 14	- 20			
1850	1	618		- 6	- 12			
	2	526		0	- 9			
	3	492		+ 2	- 4			
	4	588		0	- 6			
1851	1	671		- 5	- 3			
	2	669		- 10	0			
	3	633		- 19	- 13			
	4	627		- 15	- 13			
1852	1	659		- 10	- 5			
	2	566		- 3	+ 10			
	3	510		- 1	+ 12			
	4	456		- 2	+ 4			
			Mauritius.					
1853	1	474		0	+ 14			
	2	448		+ 3	+ 11			
	3	412	- 19	+ 8	+ 16	- 12		
	4	323	- 21	+ 10	+ 6	- 10		
1854	1	213	- 12	+ 8	+ 7	- 7		
	2	123	- 11	+ 6	+ 7	- 3		
	3	155	- 14	- 7	+ 1	- 3		
	4	202	- 16	- 7	+ 3	+ 7		
1855	1	175	- 15	- 1	+ 6	+ 9		
	2	100	- 2	+ 13	+ 12	+ 4		
	3	17	+ 3	+ 17	+ 20	+ 3		
	4	16	+ 12	+ 19		+ 6		
1856	1	16	- 2	+ 6		+ 7		
	2	30	- 15	- 5		+ 1		
	3	26	- 27	- 9		- 9		
	4	45	- 31	- 7		- 11		

Year.		Solar spotted area in millionths of visible hemisphere.	Abnormal barometric pressure in thousandths of an inch.					
			Mauritius.	Bombay.	Madras.	Calcutta.	Batavia.	Zi-ka-wie.
1857	1	86	- 21	- 8	- 3	- 19		
	2	130	- 17	- 16	- 1	- 24		
	3	234	- 12	- 1	+ 9	- 6		
	4	369	- 11	+ 12	+ 18	+ 5		
1858	1	510	0	+ 7	+ 16	+ 8		
	2	581	- 7	+ 6	+ 15	- 7		
	3	798	- 7	+ 2	+ 13	+ 2		
	4	1046	+ 7	+ 13	- 19	+ 11		
1859	1	1137	+ 32	+ 10	+ 21	+ 27		
	2	1222	+ 35	+ 8	+ 22	+ 22		
	3	1436	+ 20	+ 4	+ 15	+ 21		
	4	1519	- 6	- 3	+ 8	+ 3		
1860	1	1340	- 21	- 1	- 3	- 13		
	2	1231	- 25	0	- 5	- 15		
	3	1266	- 14	- 2	- 8	- 18		
	4	1405	- 21	- 11	- 8	- 18		
1861	1	1365	- 18	- 19	- 19	- 28		
	2	1416	- 18	- 16	- 14	- 18		
	3	1343	- 6	- 11	- 16	- 18		
	4	1238	- 18	- 8		- 13		
1862	1	1063	- 14	- 2		- 8		
	2	1275	- 23	- 9		- 6		
	3	1254	- 24	- 22		- 10		
	4	1267	- 41	- 34		- 23		
1863	1	913	- 31	- 37		- 26		
	2	684	- 23	- 26		- 28		
	3	508	- 12	- 21		- 32		
	4	652	0	- 7		- 23		
1864	1	757	0	+ 14		- 14		
	2	985	+ 16	+ 24		- 7		
	3	783	+ 17	+ 29		+ 8		
	4	838	+ 24	+ 20		+ 20		
1865	1	598	+ 16	+ 14		+ 32		
	2	511	+ 18	+ 2		+ 28		
	3	377	+ 19	+ 1		+ 18		
	4	541	+ 19	+ 1		+ 11		
1866	1	517	+ 5	+ 9		+ 1		
	2	406	+ 4	+ 9		+ 2		
	3	174	+ 12	+ 12		- 1	+ 6	
	4	101	+ 31	+ 15		+ 14	+ 11	
1867	1	74	+ 31	+ 14		+ 20	+ 11	
	2	70	+ 18	+ 13		+ 25	+ 10	
	3	209	+ 1	+ 11		+ 20	+ 4	
	4	261	0	+ 15		+ 22	+ 4	
1868	1	415	- 7	+ 24		+ 33	+ 16	
	2		- 8	+ 29		+ 31	+ 22	
	3		- 10	+ 33	+ 11	+ 25	+ 28	
	4		+ 14	+ 31	+ 9	+ 16	+ 30	
1869	1		+ 26	+ 27	- 1	+ 14	+ 27	
	2		+ 31	+ 19	- 11	+ 14	+ 20	
	3		+ 22	+ 5	- 24	+ 9	+ 10	
	4		+ 16	- 15	- 44	- 6	- 6	
1870	1		+ 13	- 19	- 49	- 17	- 16	
	2		+ 8	- 15	- 43	- 16	- 24	
	3		+ 5	- 6	- 24	- 3	- 14	
	4		+ 12	- 11	- 16	- 3	- 13	
1871	1		+ 27	- 9	- 9	- 4	- 7	
	2		+ 42	- 1	- 4	- 5	- 5	
	3		+ 39	+ 2	- 4	- 2	- 2	
	4		+ 33	0	- 8	- 2	- 4	
1872	1		+ 27	- 6	- 10	- 2	- 7	
	2		+ 9	- 7	- 6	+ 7	- 9	
	3		- 3	- 12	- 16	+ 11	- 17	
	4		- 20	- 18	- 23	- 1	- 24	
1873	1		- 15	- 15	- 19	- 4	- 26	
	2		+ 7	- 8	- 11	- 17	- 17	
	3		+ 18	+ 6	- 2	- 1	- 4	+ 2
	4		+ 34	+ 15	- 1	+ 2	+ 10	0
1874	1		+ 2	+ 12	- 3	+ 2	+ 12	- 6
	2		0	+ 5	- 1	+ 8	+ 5	- 8
	3		- 2	- 7	- 15	+ 12	- 4	0
	4			- 6	- 16	+ 16	- 11	- 4

TABLE I. (*Continued*)—

Year.		Solar spotted area in millionths of visible hemisphere.	Abnormal barometric pressure in thousandths of an inch.					
			Mauritius.	Bombay.	Madras.	Calcutta.	Batavia.	Zi-ka-wie.
1875	1			− 5	−22	+ 2	−11	0
	2			+ 1	−11	−10	− 7	−18
	3			+ 2	− 4	− 3	− 1	−16
	4			+ 1	− 1	− 9	− 5	−12
1876	1			− 3	−16	−14	−11	−13
	2			− 1	−18	−19	−10	− 8
	3			+ 9	−13	− 3	+ 1	−12
	4			+21	+12	+27	+22	+ 8
1877	1			+29	+30	+49	+28	+ 4
	2			+43	+46	+48	+46	+11
	3			+43	+55	+43	+47	+12
	4			+38		+32	+49	+29
1878	1			+24		+51	+34	+39
	2			+13		+55	+17	+34
	3			−15		+33	− 1	+16
	4			−33		0		− 4
1879	1			−40		−26		−10
	2			−15		− 2		− 7
	3			− 4		+ 4		− 3
	4			− 1		− 2		− 8
1880	1			− 8		−14		

Comparison of Abnormal Barometric Movements at Different Stations.—The general resemblance of all these curves to each other is very remarkable; indeed if the Mauritius curve for the years 1867 and 1868 be excluded, there is scarcely a single prominent feature in any one of the curves which is not reproduced in the others. To show this the corresponding points of the different curves have been marked with the same small letters. It will be seen, however, that there is strong evidence of a want of exact simultaneity in the barometric movements at different stations, and that as a rule the changes take place at the more westerly stations *several months earlier* than at the more easterly ones. This is particularly noticeable in the curves for St. Helena and Madras from 1841 to 1846, when the latter sometimes lagged behind the former by as much as six months; in those for Mauritius and Calcutta from 1855 to 1866, when the latter persistently lagged several months behind the former; in those for Bombay and Calcutta from 1862 to 1866, when the difference in time often amounted to *upwards of six months;* in those for Bombay and Batavia from 1867 to 1878, when (as already remarked) the latter lagged behind the former at an average interval of about one month; and in those for Bombay and Ti-ka-wei from 1876 to 1878, when the latter lagged upwards of six months behind the former. *It appears then that these long atmospheric waves* (*if such they may be called*) *travel at a very slow and variable rate round the earth from west to east, like the cyclones of the extra tropical latitudes.*

Bombay FRED. CHAMBERS

(*To be continued.*)

DR. SIEMENS'S NEW CURE FOR SMOKE

FROM among a number of letters which have been sent us on this subject we have selected the following for publication; to these Dr. Siemens has been good enough to append some important remarks.

IN NATURE, vol. xxiii. p. 25, I read with interest an article by Dr. Siemens describing an ingenious gas and coke fire which he suggests as a cure for the smoke nuisance. But although the darkening of the atmosphere or fog will certainly be prevented by its use, I am afraid the *gases from the coke*, especially the carbonic oxide, will make the fogs at least as poisonous and injurious to health as the open coal fires at present in use.

In these circumstances a description of an "Asbestos gas fire" free from this objection, which we have had in use in our smoking room for the last three years, and which, after a few alterations, has proved perfectly satisfactory, may perhaps interest your readers.

A ½-inch gas-pipe furnished with four Bunsen burners is laid on the hearthstone under the grate and parallel to the ribs, so arranged that the tops of the burners (which are made elliptical to pass through the bars) are flush with the upper surface of the grate, and two inches back from the line of the ribs. The fireplace is loosely filled with a preparation of asbestos in pieces about the size of a hen's egg.

This fire not only evolves a large amount of heat, but has a very cheerful appearance, similar to that of a bright coke fire, and to insure this it is essential that the burners should be placed close to the ribs, as stated above, and not in the centre of the grate. If this is not attended to the asbestos in the centre of the fire will be raised to a high temperature, but will not be sufficient to heat those portions in front, which will then not only be of no use as radiators in themselves, but act as screens to the light and heat generated in the centre. I suspect this was the cause of the failure of Dr. Siemens' pumice gas fire.

The cost of maintaining this fire is simply that of the amount of gas burned, as the asbestos is not consumed, and its prime cost is trifling. I have only further to add that there is not the slightest trace of fumes or smell from the fire two minutes after it is lighted. D. A. STEVENSON

Edinburgh, November 15

DR. SIEMENS has described in your pages the form of coke-gas grate which he has fitted in his own house. As I had fitted a similar arrangement in this house before Dr. Siemens' letter appeared in the *Times* of November 3, and as it is simpler than Dr. Siemens' and succeeds even beyond my expectation, I send you a drawing and description of it. It varies, of course, according to the shape of the grate in which it is fitted; but for the sake of comparison I have copied Dr. Siemens' grate, and drawn my arrangement as fitted into it.

Instead of Dr. Siemens' arrangement for withdrawing the heat from the back of the fire and bringing it to the front, I merely line the whole grate—sides, back, and bottom—with fire-bricks. This obviates the necessity for the close-fitting ash-pan described by Dr. Siemens, which would be rather expensive to fit. I make the fire-brick in the bottom of the grate slope towards the front, and leave a space of one inch between the front of it and the perforated gaspipe down which space the ashes fall on to the hearth.

If my grate is not quite so economical in working as Dr. Siemens', it is very near it, and the first cost of fitting is considerably less. In fact, as most grates are lined with fire-brick at back and sides, nothing has to be done but fit a wedge-shaped fire-brick into the bottom, a half-inch iron gaspipe, perforated with holes in front, and connect it with the gas service, all of which can generally be done for a few shillings.

The saving of kindling-wood and of chimney-sweeping would pay for it in a year. In Dr. Siemens' grate the copper must cost about 1*l.* A grate fitted with this arrangement looks exactly the same as an ordinary grate, and there is nothing to prevent ordinary coal being burnt in it—in fact coal can be burnt in it with much less smoke than in an ordinary grate by turning on the gas for a few minutes when fresh coal is put on, when the dense black smoke emitted by the new coal is completely burnt up in the gas-flame. To people who object that a gas grate must produce a bad smell in the room I can only say, "Come and see." They will find that we have three grates with this arrangement in constant use in these chambers, and that they produce no smell and make a very pleasant fire. Any person who takes an interest in the subject is quite welcome to come in and look at them at any time. COSMO INNES

Adelphi Chambers, 7, John Street, Adelphi

HAVING been experimenting for some years in the direction referred to by Dr. Siemens in NATURE, vol. xxiii. p. 25, I must beg to differ with him most seriously in some of his conclusions. The gas-fire with coke which he describes has, so far as our experience goes, several practical objections which prevent its use in the place of an ordinary gas fire, whilst when compared with a *good* coal fire it fails seriously.

First, with regard to the objections to Dr. Siemens' fire. It requires about half an hour to become anything like warm, as against ten to fifteen minutes with a well-lighted coal fire. Second, it makes as much or more dust and dirt than a *good* coal fire. Third, the grate requires as much cleaning and care as with coal.

I am not surprised at the economy, comparing the coal fire as shown with gas and coke, but if the result had been taken in

comparison with a good Abbotsford grate with solid clay bottom, back and sides, the figures would have appeared seriously the other way.

In a room of exactly half the cubic area of the one referred to by Dr. Siemens we have an Abbotsford grate a little over ½rd cubic foot capacity, the actual measurement of the fire space being 5½ inches deep, 8 inches back to front, 14 inches wide. This is lighted at 7 o'clock every morning and at 10 o'clock the grate is filled (not piled high). This fire burns until 10 or 11 o'clock every night untouched, practically smokeless, making the room pleasantly warm all over in the severest weather, and without making a *handful of cinders in a month*. One ordinary boxful of coals lasts two days. We have five, sometimes six, fires going daily at an average cost for coal for the winter season of five shillings weekly, or less than twopence per day per fire. That Dr. Siemens is correct so far as the old style of fire-grate is concerned, I know to my cost, but taking any good grate with clay sides and back and a solid clay bottom, his fire at its best will not compare either for cleanliness, economy, or comfort.

Gas fires are wanted where absolutely no attention and dust can be permitted. Allowing either of these as possible, no substitute I know will approach a well-constructed open fire with a solid clay bottom and fire-box.

With regard to the waste heat, it is no greater than absolutely necessary to take away the products of combustion, as, with our grates, it is utilised for warming the upper rooms. At this moment, with five good fires, there is visible from the tops of our chimneys nothing except a clear transparent current of warm air; any one at a cursory glance would say there were no fires in the house.

It must be borne in mind when I refer to cost that we cook entirely by gas, and the price of good coal here is 14*s.* 2*d.* per ton, coke being about half this price. What is required in a gas fire is a perfectly clean source of radiant heat, without trouble, and quickly available: these conditions are not in any way fulfilled by Dr. Siemens' arrangement. With the exception of two or three minutes expended in lighting, all he has attained can be found in a more perfect form in many of the fire-grates which have been in common use for the last ten years. Amongst our many attempts at gas fires one, although not absolutely the same as Dr. Siemens', was practically so, and was condemned because it required as much trouble as our present fires, and was much slower in lighting. It would be both interesting and instructive if Dr. Siemens would test an Abbotsford grate under the same conditions as his coke-gas fire, and supplement his report with one from the individual who has to do the cleaning up and dusting, a department which it is more than probable he ignores.

Another important matter is that I believe the cost of making and fixing Dr. Siemens' grate would be not less than that of a good modern fire-grate.

THOS. FLETCHER

Warrington

THROUGH your courtesy I am enabled to reply to the objections raised by three correspondents against my proposed gas-coke grate, before they have actually appeared in your columns.

Mr. D. A. Stevenson considers that the use of coke is objectionable on account of the gases evolved in its combustion, and especially the carbonic oxide gas, which would poison the atmosphere. In reply I have to say that in burning coke with a supply of hot air, and in contact in front of the grate with the atmosphere, its entire combustion is insured, resulting in carbonic acid, which is a necessary constituent of our atmosphere. In obtaining the same amount of heat through the perfect combustion of gas, products of combustion at least equally objectionable from a sanitary point of view will be evolved.

The gas-asbestos grate which he describes appears to be judiciously contrived, but its power of heating the room depends entirely upon the combustion of gas unaided by hot air or solid fuel. Now 1000 cubic feet of gas weigh about 34 lbs., and the heat developed in the combustion cannot exceed $34 \times 22{,}000 = 748{,}000$ units of heat.

The heat units produced in burning a pound of coke may be taken at 13,400 (assuming it to contain about 8 per cent. of incombustible admixture, the heat equivalent of pure carbon being 14,500 units), and it requires $\frac{748{,}000}{13{,}400} = 56$ lbs., or just half a hundredweight of this coke, to produce the heating effect of 1000 cubic feet of gas.

Taking gas coke at 18*s.* per ton (which is an excessive price), the 56 lbs. of coke represent a cost of 5·4*d.*, as compared with 3*s.* 6*d.* for the 1000 cubic feet of gas producing the same amount of heat. This great difference of cost at once shows the advantage of making coke do as much of the work as possible. Without it a gas grate will consume 50 to 70 cubic feet of gas per hour, whereas my experiments prove that an average consumption of 8 cubic feet suffices to heat a large room when combined with a moderate consumption of coke, and with the use of the heating arrangement, to which I attach great importance. Another important consideration in favour of the joint use of coke and gas is that the existing gas companies produce both these constituents very much in the proportion in which they would be required, and could therefore provide the means of supplying an enormous number of coke-gas grates, whereas their plant and mains would be quite inadequate to supply a demand upon them for an extended application of purely gas stoves.

Mr. Cosmo Innes describes a gas grate of his construction, having the closed grate and single gas pipe behind the lower front bar which I advocate; he proposes to fill the grate with common coal, using the gas only as a means of kindling the fire. My objections to his proposal are that in using coal he must continue to make smoke, which we are desirous to prevent, and that the hot back to his fire means rapid distillation of the fuel up the chimney in the form of hydrocarbons and carbonic oxide. The gas arrangement as shown by him will be efficacious, no doubt, as a means of kindling a bright and cheerful fire, but he



would do better in that case to use a few logs of wood instead of coals. A bright but short-lived fire may thus be raised quickly at a cheap rate in a dining-room or in a parlour.

Mr. Thomas Fletcher admits that my grate has the advantage of economy over a common coal grate, but thinks the Abbotsford grate the best of all. This grate is according to him practically smokeless, and produces only a handful of cinders in a month, although common coal is used. Now I have no desire to detract from the merits of the Abbotsford grate, but I fail to see why it should be smokeless, considering that raw coal is used; and the extremely small production of ashes or cinder seems to imply that Mr. Fletcher uses an extremely pure and probably a smokeless coal, very different from the fuel we are usually supplied with in London.

He also objects to the cost of my arrangement, and his opinion in this respect, coming from a practical grate-builder, is entitled to every consideration. In first describing my plan I did not go into the question of cost of application; but having been since asked by grate-builders to advise them regarding the cheapest form of my grate and the easiest mode of applying it to existing fire-places, I have devised a form of application which leaves little to be desired, I think, as regards first cost.

The arrangement is shown by the accompanying sketch, and consists of two parts which are simply added to the existing

grate, viz. :—(1) the gas-pipe (*d*) with holes of about $\frac{1}{16}$ inch diameter, 1·5 inch apart along the upper side inclining inward, and (2) an angular plate (*a*) of either cast or wrought iron, with projecting ribs (*b*) extending from front to back on its underside, either cast with or riveted to the same, presenting a considerable area, and serving the double purpose of supporting the additional part on the existing grate, and of providing the heating-surface produced by the copper plate and frill-work in my first arrangement. In using iron instead of copper it is necessary however to increase the thickness of these plates and ribs in the inverse ratio of the conductivity of the two metals, or as regards the back plate, from $\frac{1}{2}$ inch to $\frac{3}{8}$ inch.

The arrangement will be rendered more perfect by the use of the bent plate fastened to the lower grate bar, which directs the incoming air upon the heating-surfaces.

The front edge of the horizontal plate has vandyked openings (*c*), so as to form a narrow grating, through which the small quan-



tity of ashes that will be produced by combustion of the coke and anthracite in the front part of the grate discharge themselves down the incline towards the back of the hearth, where an open ash-pan may be placed for their reception.

In adapting the arrangement to new grates, the horizontal grating had better be dispensed with, and the casting with its lower ribs extended downwards, so as to find its fixed support between the back of the fireplace and the inclined deflector plate.

Mr. Fletcher speaks of the large amount of ashes that would be produced, but this amount can surely not be as great as in the case of a coal fire, seeing that the consumption of solid fuel is reduced to less than one-half, of which nearly one-half is anthracite, a fuel remarkably free from ashes. Neither do I participate in Mr. Fletcher's fear regarding opposition on the part of housemaids, except it be from an apprehension on their part that, with Othello's and the chimney-sweeps', their "occupation be gone."

The tendency of grate-builders of the present day, and also of your correspondents, appears to be to look for economy to brick-linings, which no doubt have the effect of producing hot radiating surfaces. I maintain however that such radiation is obtained at too great a cost of fuel, and that superior economical results will, on the contrary, be attained by abstracting the heat from the back of the fire, and concentrating it upon the purely carbonaceous material in front of the same.

To illustrate my reasoning I may here refer to an experiment which can easily be made of throwing a shovelful of bituminous coal into a steel-melting furnace; the result is an instantaneous dispersion of the coal, accompanied with a powerful refrigerative action on the furnace. In constructing gas-producers I take advantage of hot walls to turn solid into gaseous fuel, and a fireplace with hot brick bottom and sides is very much in the condition of a good gas-producer, giving out radiant heat no doubt, but combined with rapid distillation of combustible gases into the chimney. This action is made apparent in placing on the fuel towards the back of such a grate when in full glow a piece of wood, which will be seen to dwindle away rapidly without giving rise to flame, the atmosphere immediately over the glowing fuel being essentially a reducing one.

In my grate the heat, on the contrary, is confined to the coke immediately behind the bars, in contact with the heating gas flames and with the air of the room flowing in towards the chimney, whereas the coke at the back of the grate remains comparatively cool and unconsumed throughout the day. The cold furnace-back also means a cold chimney, and it is rather remarkable to observe that in the case of the application at my office, a thermometer held high up into the chimney showed a temperature of only 130° F., while the front of the grate was in a high state of incandescence. These, I maintain, are conditions most favourable to economy combined with entire absence of smoke or deleterious gases. C. WILLIAM SIEMENS

12, Queen Anne's Gate, S.W., November 24

CURIOUS IMPRESSIONS IN CAMBRIAN SANDSTONE NEAR LOCH MAREE

IN course of the short excursion to Loch Maree and its neighbourhood, Mr. Walter Carruthers, of the *Inverness Courier*, happened, on June 13, to light upon an interesting portion of the Cambrian or Torridon Red Sandstone of the district, forming part of the bed of the burn, near Loch Maree Hotel, on which occur what have been called the Victoria Falls, so named from the fact that the Queen visited them. There an exposed surface of the rock about sixteen feet in length, nearly as much in breadth, and almost perfectly level, is marked by several double grooves quite discernible, and each divided by a very thin raised line. These traverse the whole length of the rock in a perfectly straight line, and on both sides of them are roughnesses which, if we could entertain the idea that the grooving had been caused by some living creatures, might be produced by footprints which have been to a great extent obliterated. The impressions were so striking that they immediately suggested a recollection of the footprints discovered in the sandstones of Morayshire and Tarbatness, though there was no other resemblance than their marked character on the broad, flat rock. Having heard that Mr. William Jolly, H.M. Inspector of Schools, was in the neighbourhood, Mr. Carruthers called his attention to the subject, and indicated where he should find the markings. Mr. Jolly was not slow to examine the spot, and he writes to Mr. Carruthers as follows, as given in the *Inverness Courier* of July 1 :—

"I found your curious lines without difficulty, guided by your accurate description of their locality. They are assuredly no 'mare's nest,' but *bonâ fide* ancient impressions of some kind, which should receive the attention of geologists, both on their own account and as existing in the second oldest geological formation in Britain, in which, as yet in Scotland, no evidences whatever of organic life have been discovered.

"The lines or bands in question occur in the chocolate-coloured Torridon sandstone, the Cambrian of Murchison and Geikie, which is so well developed around Loch Maree, and rises into the great dome of the Slioch, or the Spear Head, that guards its waters. The most distinct of the impressions consists of two continuous flat bands side by side, 1¼ to 1½ inch broad, and about a quarter of an inch deep, running quite straight across the flat layers of sandstone *in situ*, and perfectly distinct for sixteen feet, disappearing on the west side under the superincumbent rock, and broken only where portions of the sandstone have

been weathered out. In some places a third line runs alongside the two, but this is much less distinct and persistent. The double band resembles nothing more nearly than the hollow impression that would be left by double bars of iron placed closely together and neatly inserted in the rock for clasping some structure on it, if the iron were subsequently removed; or, as you suggest, the marks of a gouge driven by a carpenter across a board. The bands, when looked narrowly into, consist of very fine close hair-like lines, continuous and parallel to their sides, resembling very minute striæ left by glaciation, and look as if caused by some object drawn along the original red sand, before it became the present indurated rock.

"A similar double line runs parallel to this one, about two feet lower down, seven feet long, and a third parallel double line on the other or upper side, three feet long, both of the same breadth as the first. Besides those pointed out by you, which occur on the same flat of sandstone, other lines exist farther down, on the other side of the pool below this rocky flat, on a similar bed of sandstone, part of the same layer—one three feet in length, another six feet, running more or less parallel to those above. Indications of others may also be seen, and, no doubt, several more may be discovered on more careful examination.

"What they are I can scarcely even surmise, having seen nothing of the *same* kind elsewhere. They do suggest the possibility of their being the indentations of the caudal appendage of some huge creature, similar to the hollow tail-lines between the footprints on the sandstone at Tarbatness and along the shores of Morayshire—a suggestion strengthened by the fact of the existence, on both sides of the line, of numerous rounded hollow marks, very like the footprints on these reptiliferous rocks, occurring, as in them, at intervals. But the continuous even breadth and square section of the bands would seem to render this impossible. Then they might be the depressions left on the soft sand by the hinder portions of the shell of some large crustacean—a more likely cause, rendered more probable by the existence of very good ripple-marks on the same sandstone, in the same and neighbouring layers. The striæ-like lines of which the grooves consist would seem to point to some moving agent, organic or physical. They may, however, be the casts or impressions of some great land reed or sea fucoid, the hair-lines being the marks of the fine structure of its stem or the parallel veins of its leaves. It would be desirable to have the superincumbent layer of rock carefully removed where the bands in question disappear under the upper rock, which might shed some light on the nature of the strange marks. I was sorry I could not spend more time on their examination."

The impressions occur about 300 or 400 yards above the Victoria Falls, and immediately beside the last of three lesser waterfalls on the west side of the stream.

THE QUANTITIES OF WATER IN GERMAN RIVERS

AN attempt has recently been made by Herr Graeve (*Der Civil-Ingenieur*, 1879, p. 591) to determine the amount of water in German rivers and its apportionment in different seasons, a question very important for navigation, and also of much scientific interest. His research comprehends the chief rivers of Germany, excluding the Danube, which begins to be navigable only outside of Germany, and including the Vistula and the Memel. He first calculated, from the mean heights of water, the quantities of water flowing out per second, and he adds a table in which the amount of outflow is shown in relation to the extent of the corresponding river territory. When the amount of outflow per 100 sq. km. of the region of precipitation is calculated the following values are obtained:—(1) the Rhine at Coblentz above the Moselle mouth delivers per 100 sq. km. of land 1·070 cub. m. of water in a second; (2) the Weser at Minden, 0·826 cub. m.; (3) the Elbe at Sorgau, 0·579; (4) the Elbe at Barby, 0·554; (5) the Oder at Steinau, 0·460; (6) the Oder below the Warta mouth, 0·413; (7) the Warta near its mouth, 0·344; (8) the Vistula at Montau Spitz, 0·538; (9) the Memel at Tilsit, 0·600.

From these numbers it appears (*a*) that the average outflow of different rivers, from equal portions of their territory, differs much more than is usually thought, for in the Middle Rhine it is about three times, in the Middle Weser two and a half times, and in the Middle Elbe, as also in the Lower Vistula and Memel, more than one and a half times as much as in the Lower Warta. On the whole, it decreases from the Rhine to the Warta, and from the latter increases again to the Memel. (*b*) In one and the same river the quantity from equal portions of land seems as a rule to decrease down stream. (*c*) All calculations of quantity of outflow in streams, based merely on extent of the region of precipitation, must as a rule give incorrect results.

It was important to try and determine the relations of the quantity of outflow to the rainfall of the corresponding regions, and Herr Graeve, doing so by a method which he describes, obtained the following percentage numbers, corresponding to the above series of rivers:—(1) = 38·5 per cent.; (2) = 37 p.c.; (3) = 30 p.c.; (4) = 28·5 p.c.; (5) = 27·2 p.c.; (6) = 21·4 p.c.; (7) = 21 p.c.; (8) = 29 p.c.; (9) = 32·5 p.c.

From this the following conclusions (briefly) are drawn:—

(*a*) The percentage proportion of the amount of outflow to the rainfall differs very considerably in these several rivers, though far less than the amount of outflow from equally large regions of these rivers; hence the differences of the latter can be due only in part to differences in the rainfall.

(*b*) The percentage decreases from the Rhine to the Warta, and increases again from the latter to the Memel. In one and the same river a decrease is perceptible down the stream, at least so far as the phenomena in the Oder and the Elbe are general.

(*c*) Since in a mountainous region a greater part of the atmospheric precipitates is carried off by rivers than in the plain, the steady decrease in the percentage proportion of outflow to rainfall in the direction from the Rhine to the Warta must be primarily attributed to the increasing flatness of the region; so too must the decrease of the percentage down stream. The influence of more or less wood on the land could not be precisely determined.

(*d*) The marked increase of the percentage in the direction from the Warta to the Memel cannot be explained by the orographic conditions of the region of precipitation, because this region in the case of the Memel is not at all hilly, and in that of the Vistula only a little more hilly than that of the Warta, but since the amount of the evaporated part of atmospheric precipitates is considerably influenced by the mean temperature of the region of precipitation, and this in the region of the Vistula and the Memel is lower than in that of the Warta, the increase of percentage in question from the Warta to the Memel must mainly be attributed to climatic conditions.

(*e*) While the percentage in question must be chiefly governed by orographic and climatic conditions, there can be no doubt that other factors also act, *e.g.*, the relative amount of moisture in the air, which influences the degree of evaporation, and in general must decrease from the rainy Rhine region to the dry region of the Warta; further, the amount of plantation, which in the regions of the Vistula and Memel is larger than in those of all other German rivers; lastly, the nature of the ground, allowing more or less passage to the precipitates; the influence of all these factors, however, cannot be proved with the same certainty as the orographic and climatic conditions.

A comparison of the amounts of outflow in different years shows that in individual rivers more important differences occur than are generally supposed, that these differences in rivers of different character and unequal force are very different in amount, and that in the same river they decrease down stream.

With regard to the difference in amount of outflow in the various seasons and months, the following average values were obtained. The amount of outflow in winter (from the beginning of November to the end of April) is to that of summer, at the parts of the stream examined, in the Rhine as 1 : 0·922, in the Weser as 1 : 0·434, in the Elbe as 1 : 0·467, in the Oder as 1 : 0·525, and further down stream as 1 : 0·522, in the Vistula as 1 : 0·486, and in the Memel as 1 : 0·389. A better idea of the regularity of the quantities of outflow is given by the relations of these for the driest and the wettest month of the year; in the case of the Rhine this ratio is 1 : 1·458, in the Weser 1 : 4, in the Elbe 1 : 5·238, in the Oder 1 : 4·5, and further down 1 : 3·68; in the Vistula 1 : 4·19, and in the Memel 1 : 4·51.

The causes of the difference in the ratio of the largest and least monthly amounts of outflow must chiefly be sought in the presence or absence of collecting basins, as also in the orographic and climatic conditions. In the Rhine all those factors combine which affect the regularity of outflow. It possesses in the Swiss lakes large reservoirs; its river-region comprises mountains of various height, and plains, so that the

melting of the snow must occur at very different times of the year. The Memel also possesses reservoirs in its marshes, and its region is perhaps better wooded than that of the other streams of Germany, but the long and hard winters cause an accumulation of large masses of ice and snow which melt suddenly and almost simultaneously in the whole region.

Herr Graeve takes up various other points, which have a practical bearing on navigation, but for these we must refer the reader to his memoir. He remarks in concluding on the desirability of comparing the conditions of outflow of German rivers with corresponding data for other European rivers, though at present the scanty and incomplete character of the data at hand render such inquiry scarcely practicable.

SCIENTIFIC SERIALS

THE *Journal of the Russian Physical and Chemical Society*, vol. xii. fascicules 5 and 6, contain, besides the minutes of meetings of the Society, the following papers:—In fascicule 5: On the dosage of chromium, by M. Th. Willm.—On the composition of the hydrate of peroxide of barium, by M. E. Schöne.—On the distribution of naphtha on the peninsula of Apsheron, by M. S. Goulichambaroff.—On the oxidation of ketones, by M. Goldstein.—On the products of oxidation of erythrite, by M. S. Przibytek.—A necrology of Prof. Nicolas Zinin, by MM. Borodin and Boutleroff.—On the magnetisation of liquids, by M. Ziloff.—On hail, by M. Schwedoff.—Notes by M. Latchinoff on specific heat, on a new dynamometer, and on electrical light.—In fascicule 6: On chlorocamphoric oxide, by M. Latchinoff.—On the action of heat on phosphorites, by M. Beletzky.—On tetrolic acid, by M. Lagermark.—On the solidification and evaporation of drops of liquid, by M. Sloughinoff.—On the dosage of mercury and arsenic in corpses; and an analysis of the artesian wells of Staraya Rousia.

Revue internationale des Sciences biologiques, July, 1880.—J. L. de Lanessan, on the protozoa (a chapter with illustrations from the author's forthcoming "Manuel d'Histoire Naturelle médicale).—A. Hovelacque, on the inferior races of mankind.—M. Debierre, man before and on the threshold of history.—Proceedings of the Academies of Paris, Belgium, and Amsterdam.

August.—J. L. de Lanessan, the coloration and the colouring-matters in plants.—M. Moniez, on the cysticers of Tænia.—M. Debierre, man before and on the threshold of history.—Proceedings of the Academies of Paris, Belgium, and Amsterdam.

September.—M. Vulpian, physiological study of poisons: curare.—M. J. L. de Lanessan, the saccharomycetes and the fermentations caused by them.—Prof. W. H. Flower, on the comparative anatomy of man (translated from NATURE).—M. R. Moniez, on cestoid worms and helminthologists.—Proceedings of the Academy of Paris.

SOCIETIES AND ACADEMIES

LONDON

Chemical Society, November 18.—Prof. H. E. Roscoe, president, in the chair.—It was announced that a ballot for the election of Fellows would take place at the next meeting (December 2).—The following papers were read:—Notes on the oxides of manganese, by Spencer Pickering. Various samples of oxides were procured and heated to various temperatures, until their weight was constant; in some cases they lost weight, in others they gained, whilst in some the weight remained constant.—On aluminium alcohols, by J. H. Gladstone and A. Tribe. When aluminium foil and iodine are heated with alcohol the latter is decomposed, two new organic aluminic compounds being formed, aluminic iodoethylate $(C_2H_5O)_3I_3Al_2$, and aluminic ethylate $Al_2(C_2H_5O)_6$. The authors have applied this reaction to other alcohols, and have thus prepared aluminic methylate, ethylate, propylate (isopropylate could not be obtained), isobutylate, amylate, cetylate, phenylate, cresylate, and thymolate.—Mr. W. H. Perkin then gave an account of the artificial production of indigo by A. Baeyer, and prepared some before the Society. The steps in the process are: toluene C_7H_8O, dichloride of benzyl $C_6H_5CHCl_2$, cinnamic acid $C_9H_8O_2$, orthonitrocinnamic acid $C_9H_7(NO_2)O_2$, orthonitrodibromhydrocinnamic acid $C_9H_7Br_2O_2(NO_2)$; by the action of caustic potash orthonitrophenylpropiolic acid $C_9H_5(No_2)O_2$ is formed, which on reduction in alkaline solution with grape sugar furnishes indigo $C_{16}H_{10}N_2O_2$.—On the synthetical production of new acids of the pyruvic series, by E. Moritz.—On the old alum well at Harrogate, by R. H. Davis. The author gives an analysis of the mineral constituents in the residue.—On the absorption spectrum of ozone, by W. N. Hartley.—On the probable absorption of the solar rays by atmospheric ozone, by W. N. Hartley. The author has photographed and measured the absorption spectrum of ozone; he suggests that the shortening of the solar spectrum at the violet end is due to the presence of ozone in the atmosphere, also that the blue colour of the sky may be ascribed to the same cause.—On peppermint camphor, by M. Moriya of Tokiô. The author has studied carefully the physical characters of this substance; he has also investigated the action of chromic acid, nitric acid, and bromine thereon.

Zoological Society, November 16.—Prof. Huxley, F.R.S., vice-president, in the chair.—Mr. W. K. Parker, F.R.S., read a paper on the development of the skull in the Urodele Batrachians. Mr. Parker described the skull of the adult Gigantic Salamander (*Sieboldia maxima*), the Siren and the Menopoma, and compared their structure with that of the various stages of the skull of the common newt.—Mr. G. E. Dobson, C.M.Z.S., exhibited and made remarks on the head of a partridge (*Perdix cinerea*) with an extraordinary prolongation of the intermaxillary bones.—Mr. W. A. Forbes, F.Z.S., made some remarks on the shedding of the horns of the Prong-buck (*Antilocapra americana*), as recently observed in the specimen living in the Society's Gardens.—Mr. Harting, F.Z.S., exhibited a specimen of Bartram's Sandpiper, recently killed in Lincolnshire.—Mr. Sclater exhibited the skin of the Guinea Fowl, lately described in the Society's *Proceedings* as *Numida Ellioti*. Further investigation had induced him to believe that this bird was the same as *Numida pucherani* of Hartlaub, the inaccurate colouring of the head in Mr. Elliot's figure of that species having prevented its identification.—Mr. G. A. Boulenger read a paper on the Palæarctic and Æthiopian species of *Bufo*, of which he recognised ten species: four in the Palæarctic, five in the Æthiopian region, and one found in both regions.—A communication was read from Dr. Otto Finsch, C.M.Z.S., in which he gave a list of the birds of the Island of Ruk, in the Central Carolines.—A second communication from Dr. Finsch contained the descriptions of some new or little-known species of pigeons from the Caroline Islands.—A communication was read from Mr. Edgar A. Smith, containing an account of the shells of the genus *Myodora* of Gray.—A communication was read from Mr. Martin Jacoby, in which he gave the descriptions of a collection of Phytophagous Coleoptera made by Mr. Buckley at Eastern Ecuador. The collection contained a good many new and interesting species, of which a great part were not alone inhabitants of Ecuador, but had been found either in Peru or the Amazonian region.—A paper by Messrs. F. D. Godman and O. Salvin was read, in which they gave the descriptions of some supposed new species of butterflies collected by Mr. Andrew Goldie in the interior of the district of Port Moresby, New Guinea.

Physical Society, November 13.—Prof. W. G. Adams in the chair.—Mr. Bosanquet, of St. John's College Physical Laboratory, Cambridge, read a paper on the nature of the sounds which occur in the beats of consonance. From mistimed octaves and twelfths he found that when the beats of the harmonics are cleared away each beat consists entirely of variations in the intensity of the lower notes. He gave the mathematical theory of these beats, and likewise of the curves given by the harmonograph. He also described an ear-tube for using in connection with a resonator. It is difficult to get definite results with a resonator unless the passage from the latter to the ear is closed to sound. The ear tube consists of a copper pipe bent into a sickle shape to gird the face, so that the ends may enter the ears, into which they are screwed, plugging them close. The sound is led from the resonator to the middle of the bent pipe by a flexible india-rubber tube, and thence to the ears.—Mr. Brown read a paper on action at a distance. He drew attention to the fact that though Newton disbelieved in action at a distance, he did not pronounce whether the medium was material or immaterial. Mr. Brown showed that the hypothesis of a material medium was encumbered with difficulties, since, among other reasons, direct contact could not explain gravity, projection of small particles from one body to another could not explain attraction, and Lesage's theory of corpuscles (as modified by Mr. Tolver Preston) required an enormous degree of porosity in masses of matter. The nature of magnetism and vibrations was also discussed by the author.—Mr. J. Macfarlane Gray read a paper on the mechanical nature of the forces called attraction, and gave grounds for attributing them to the pressures of a universal material ether of a gaseous nature. The paper was long, and had to be in part left unread. The hypothesis held by Mr. Gray

is remarkably confirmed by numerical results obtained by him.—Prof. Cottrell threw some doubts on Mr. Gray's results on the score that numerical coincidences were not always safe ground for basing theoretical deductions on. Mr. Gray stated that in the parts of the paper which had to be skipped Prof. Cottrell's objections were answered. He also pointed out that Mr. Brown in his criticism of the gasiform ether had not taken into account the important condition that the particles of ether have volume.—Professors Perry and Ayrton read a note on the contact-theory of Herr Exner recently brought before the Academy of Sciences of Vienna. They showed that Exner's experimental results disagreed with the concordant results of several independent experimenters, namely, Kohlrausch, Hankner, and Ayrton and Perry. They concluded that Herr Exner's experiments were inaccurate. They further argued that Exner's second and later paper, so far from being a disproof of the contact theory of electromotive force as now received, is in reality a proof of it. Dr. Wright stated that he will read a paper on this subject soon; and Prof. Reinhold said that Herr Exner had since corrected some of the results of his early papers on contact electricity.—Prof. Minchin of Cooper's Hill Engineering College exhibited a new photo-electric cell. This consists of a vessel of water containing a little acid, carbonate of calcium, and two tinfoil plates. When a beam of lime light was allowed to fall on one of the plates, a powerful current was set up in the cell, as seen by the deflection of a galvanometer connected in circuit with the plates. When a red glass screen intercepted the beam, the effect was very slight. Prof. Minchin had begun his experiments with fluorescence, but found "hard" water containing this salt of lime do equally well. The cell possesses this advantage: that the current it gives soon decreases in the light. When first the light falls on it, the exposed plate is positive, but it soon changes to negative. Prof. Minchin had tried the cell in place of a selenium one in the photophone, but with unsatisfactory results.

Anthropological Institute, November 9.—Edward B. Tylor, D.C.L., F.R.S., president, in the chair.—A paper was read on anthropological colour phenomena in Belgium and elsewhere, by J. Beddoe, M.D., F.R.S. Within the last few years the numerical method had been extensively applied to the determination of ethnological colour-types, the Anthropometric Committee of the British Association having set the example. The Continental nations were, however, now far ahead of us. In Germany Prof. Virchow had procured the tabulation as to the colour of the eyes and hair of all the school population, with the exception of Hamburg. In Switzerland Dr. Guillaume, of Neuchâtel, had obtained school statistics. For Belgium an elaborate monograph had been written on the subject by Prof. Vander Kindere, who, by the aid of the National Geographical Society, had induced the Minister of Public Instruction to include questions on the colour of the children's eyes and hair in the educational census. The results obtained have been of considerable importance, and bring out a remarkable contrast between the Flemish and Walloon provinces of Belgium.—Mr. J. F. Rowbotham read a paper on different stages in the development of the art of music in prehistoric times. Musical instruments, though their varieties may be counted by hundreds, are yet readily reducible under three distinct types: 1. The drum type. 2. The pipe type. 3. The lyre type. And these three types are representative of three distinct stages of development through which prehistoric music has passed. Moreover, the stages occur in the order named. That is to say, the first stage in the development of instrumental music was the drum stage, in which drums, and drums alone, were used by man. The second stage was the pipe stage, in which pipes as well as drums were used. The third stage was the lyre stage, in which stringed instruments were added to the stock. The three stages answer respectively to rhythm, melody, and harmony. And as in the geological history of the globe the chalk is never found below the oolite, nor the oolite below the coal, so in the musical history of mankind is the lyre stage never found to precede the pipe stage, nor the pipe stage to precede the drum stage.—A paper was read on neolithic implements in Russia, by Prince Paul Poutiatine. From the evidence of certain finds on his estate the author came to the conclusion: 1. That the Selave-Scythians existed there in the stone period. 2. That they possessed instruments resembling those of the Celt-Scythians, and burned their dead. 3. That the old iron period of that neighbourhood was a continuation of the stone period. 4. That they supported themselves partly by hunting. 5. That they understood corn-growing.

Meteorological Society, November 17.—Mr. G. J. Symons, F.R.S., president, in the chair.—The following gentlemen were elected Fellows: G. Corden, E. T. Dowson, F. Hepburn, B.A., C. M. Hepworth, J. Mulvany, M.D., R.N., F. H. G. Newton, Capt. M. Parry, E. P. Phillips, and H. L. Roth.—The papers read were: Table of relative humidity, by Edward E. Dymond, F.M.S.—Rainfall in South Africa, by John G. Gamble, M.A., M. Inst. C.E., F.M.S. The author gives the monthly totals of rainfall from 103 stations for the thirteen months, December 1878 to December 1879, and also the monthly means from all stations in South Africa from which a record of five years or upwards could be obtained. It is shown that the Cape Peninsula, the South-West and the West Coast, have winter rains with a dry summer, characteristics of what is called the subtropical region, the rains coming with the north-west wind or anti-trade; while Natal, Aliwal north, and in a less degree Queenstown, have the tropical features of a wet summer and dry winter. On the South Coast the rainfall appears to be more equally distributed throughout the year, though there seems to be an October maximum at Port Elizabeth and Uitenhage. In the Central and Northern Karroo the maximum of the very scanty rainfall occurs in February and March. These rains generally fall in thunderstorms; each storm seems to come from a westerly direction, but it is a more or less well-ascertained fact that these rains do not fall up country until the south-easters have set in on the South and South-West Coasts. In the south-east of the colony the transition towards tropical features may be noticed, both Grahamstown and King Williamstown showing a winter minimum in June.—On the meteorology of Mackay, Queensland, by Henry L. Roth.—Thermometrical observations on board ship, by Capt. W. F. Caborne, F.M.S.

VIENNA

Imperial Academy of Sciences, November 18.—Contributions to general nerve and muscle physiology, by Dr. Biedermann.—On rhythmic contractions of striped muscles, produced by chemical stimulation, by the same.—On some platino-cyanide compounds, by Herr Scholz.—On resorcin colouring matters, by Drs. Wesselskyund and Benedikt.—On the formation of carboxylnatron acid from Brenz, catechin, and the constitutional formula of benzol, by Prof. v. Barth.—Note on mononitro-pyrogallol, by the same.—The distribution of rainfall over Austria in the period August 11-15, 1880, and its relation to distribution of air-pressure, by Herr Hann.

CONTENTS

	PAGE
SULPHURIC ACID AND ALKALI. By Prof. H. E. ROSCOE, F.R.S.	73
THE FLORA OF PLYMOUTH	74
OUR BOOK SHELF:—	
Reiss and Stübel's "Peruvian Antiquities"	75
"Exposé Historique concernant le Cours des Machines, dans l'Enseignement de l'École Polytechnique"	75
LETTERS TO THE EDITOR:—	
Fertilisation of Yucca.—Lord WALSINGHAM	76
Skin Furrows of the Hand.—Sir W. J. HERSCHEL	76
The Aurora of the 3rd Instant.—J. RAND CAPRON	76
Temperature of the Breath.—Dr. R. E. DUDGEON; F. J. M. P.	76
Coral Reefs and Islands.—JOSEPH LECONTE	77
Vox Angelica.—GEORGE RAYLEIGH VICARS	77
Fascination (?)—ARTHUR NICOLS	77
Soaring of Birds.—W. LARDEN	77
The Photophone.—A. R. MOLISON	78
Salts of Zinc.—S.; W. BOTT	78
THE WORKS OF CARL VON NÄGELI. By SYDNEY H. VINES	78
PROF. TAIT ON THE FORMULA OF EVOLUTION	80
COMET-FINDERS (*With Diagram*)	82
NOTES	83
OUR ASTRONOMICAL COLUMN:—	
The Third Comet of 1869	85
The Star Lalande 1013-4	85
CHEMICAL NOTES	85
PHYSICAL NOTES	86
GEOGRAPHICAL NOTES	87
UNIVERSITY AND EDUCATIONAL INTELLIGENCE	87
ON A METHOD OF DETERMINING THE CRITICAL TEMPERATURE FOR ANY LIQUID AND ITS VAPOUR WITHOUT MECHANISM. By Sir WILLIAM THOMSON, F.R.S.	87
ABNORMAL VARIATIONS OF BAROMETRIC PRESSURE IN THE TROPICS, AND THEIR RELATION TO SUN-SPOTS, RAINFALL, AND FAMINES. By FRED. CHAMBERS (*With Diagram*)	88
DR. SIEMENS' NEW CURE FOR SMOKE. By D. A. STEVENSON; COSMO INNES; THOS. FLETCHER; Dr. C. WILLIAM SIEMENS, F.R.S. (*With Diagrams*)	91
CURIOUS IMPRESSIONS IN CAMBRIAN SANDSTONES NEAR LOCH MAREE	93
THE QUANTITIES OF WATER IN GERMAN RIVERS	94
SCIENTIFIC SERIALS	95
SOCIETIES AND ACADEMIES	9

SUBSCRIPTIONS TO NATURE

Yearly . . . . . 28*s.*
Half-yearly . . . . . 14*s.* 6*d.*
Quarterly . . . . . 7*s.* 6*d.*

To the Colonies, United States, the Continent, and all places within the Postal Union :—

Yearly . . . . . 30*s.* 6*d.*
Half-yearly . . . . . 15*s.* 6*d.*
Quarterly . . . . . 8*s.*

Office: 29, Bedford Street, Strand.

DIARY OF SOCIETIES.

LONDON

THURSDAY, NOVEMBER 25.

ROYAL SOCIETY, at 4.30.—On the Chemical Composition of Aleurone Grains, II.: S. H. Vines.—On the Ossification of the Terminal Phalanges of the Digits: F. A. Dixey.—On a Sun-spot observed August 21, 1880: J. N Lockyer, F.R.S.—On Methods of Preparing Selenium and other Sub stances for Photophonic Experiments: Prof. Graham Bell.

FRIDAY, NOVEMBER 26.

QUEKETT MICROSCOPICAL CLUB, at 8.

SATURDAY, NOVEMBER 27.

PHYSICAL SOCIETY, at 3.—On Refraction Equivalents: Dr. J. H. Gladstone, F.R.S.—On the Rate of Loss of Light from Phosphorescent Surfaces: Lieut. L. Darwin, R.E.—On Minor Applications of Electromotors: W. H. Coffin.—The Photophone: Prof. A. Graham Bell.

MONDAY, NOVEMBER 29.

SOCIETY OF ARTS, at 8.—Scientific and Artistic Aspects of Pottery: Prof. Church.

INSTITUTE OF ACTUARIES, at 7.—President's Address: A. H. Bailey.

TUESDAY, NOVEMBER 30.

ZOOLOGICAL SOCIETY, at 8.30.—On a Collection of Land and Fresh Water Shells from the Transvaal and Orange Free State in South Africa, with Descriptions of Nine New Species: Alfred E. Craven.—Description of Three New Species of Land Shells from Cape Colony and Natal: Alfred E. Craven.—On a Collection of Reptiles and Amphibians from Baluchistan, made by Dr. C. Duke: Prof. A. A. W. Hubrecht. Communicated by Surgeon Francis Day.

WEDNESDAY, DECEMBER 1.

GEOLOGICAL SOCIETY, at 8.—On Remains of a Small Lizard from the Neocomian Rocks of the Island of Lisina in Dalmatia, preserved in the Geological Museum of the University of Vienna: Prof. H. G. Seeley, F.R.S.—On the Beds at Headon Hill and Colwell Bay in the Isle of Wight: H. Keeping and E. B. Tawney, M.A.

ENTOMOLOGICAL SOCIETY, at 7.

SOCIETY OF ARTS, at 8.—Modern Gold Mining: A. G. Lock.

THURSDAY, DECEMBER 2.

LINNEAN SOCIETY, at 8.—On an *Erythræa* new to England: Frederick Townsend.—The Conifers of Japan: Dr. Maxwell Masters.

FRIDAY, DECEMBER 3.

GEOLOGISTS' ASSOCIATION, at 8.—Pre-Cambrian Rocks in British Isles: Dr. H. Hicks.

NOTICE OF REMOVAL.

JAMES HOW & CO.,

SCIENTIFIC INSTRUMENT MAKERS,

73, FARRINGDON ST., LONDON

(LATE OF 5, ST. BRIDE ST., AND 2, FOSTER LANE).

HOW'S STUDENT'S MICROSCOPE. HOW'S MICROSCOPE LAMP.

Rock Sections and other Objects for the Microscope.

R. W. NEEVES,
PHILOSOPHICAL INSTRUMENT
AND
INTENSITY COIL MAKER.
PRICE LIST, FOUR STAMPS.

55, SIDMOUTH STREET, LONDON, W.C.

EAGLE INSURANCE COMPANY,
79, PALL MALL.
FOR LIVES ONLY. ESTABLISHED 1807.

Accumulated Funds £3,043,542
Also a Subscribed Capital of more than £1,500,000
Reports, Prospectuses, and Forms may be had at the Office, or from any of the Company's Agents, post free.
GEORGE HUMPHREYS, Actuary and Secretary.

NEW SMOKELESS FIRE
IN AN OPEN GRATE
ON DR. SIEMENS'S PRINCIPLE
MAY BE SEEN IN ACTION, AND PRICES AND PARTICULARS HAD, ON APPLICATION TO
FRANCIS HAMMOND
5, Chandos Street, Charing Cross,
LONDON, W.C.

LIGHTNING CONDUCTORS.
Experience, accumulated since the time of Benjamin Franklin, proves conclusively that a Conductor made of Copper of adequate size is the best of all appliances for the protection of every description of building from the destructive effects of lightning.

NEWALL & CO.'S
PATENT COPPER LIGHTNING CONDUCTOR,
As applied to all kinds of Buildings and Shipping in all parts of the wor'd with unvarying success; is the most Trustworthy, most Effective, and also the Cheapest Conductor ever offered to the public.
It is simple in its application, no insulators being required, and it costs only one shilling per foot for the standard size, which ensures safety in any storm.
R. S. NEWALL & CO., 130, STRAND, W.C.
36, WATERLOO ROAD, LIVERPOOL.
68, ANDERSTON QUAY, GLASGOW.
MANUFACTORY—GATESHEAD-ON-TYNE.

NOW READY,
SECOND EDITION,
GRIFFIN'S
CHEMICAL HANDICRAFT.
PRICE 4*s.* 7*d.* POST FREE.
A CATALOGUE OF CHEMICAL APPARATUS:
ILLUSTRATED, CLASSIFIED, DESCRIPTIVE.
Demy 8vo, 480 pp., Illustrated with 1,600 Woodcuts.
Most Complete and Cheapest List of Apparatus.
JOHN J. GRIFFIN AND SONS, 22, GARRICK STREET, LONDON, W.C.

ASTRONOMICAL TELESCOPE.
BATEMAN'S
WONDERFUL £5 5*s.* INSTRUMENT
Is the finest ever yet attempted. 3-inch Achromatic Object Lenses. Entirely constructed of polished brass; total length, 4 feet 10 inches; very highly finished with Altitude and Azimuth Movements, Rackwork, fine Adjustment, one Terrestrial and one Huyghenian Astronomical Eyepiece; will show Jupiter's Belts, Crescent Form of Venus, resolve many Nebulæ and Clusters, and divide many Double Stars, &c., &c. Prospectus post free.
J. BATEMAN,
29, CHEAPSIDE; 104, STRAND; ROYAL POLYTECHNIC, 309, REGENT STREET, AND 131, HIGH HOLBORN, LONDON.

S. C. TISLEY & Co.,
OPTICIANS,
172, BROMPTON ROAD, S.W.
(Close to South Kensington Museum).
THE PHONEIDOSCOPE
An Instrument for Observing the Colour-Figures of Liquid Films under the action of Sonorous Vibrations.
Being a visible demonstration of the Vibratory and Molecular Motion of a Telephone Plate.
The PHONEIDOSCOPE, with 3 Discs, Bottle of Solution, Descriptive Pamphlet, &c., in Cardboard Box, 10*s.* 6*d.*
MANUFACTURED AND SOLD WHOLESALE AND RETAIL BY
S. C. TISLEY & CO., 172, BROMPTON ROAD, LONDON, S.W.
TELEPHONIC ELECTRICITY. All Materials supplied for experimental purposes.
Price Lists of Electrical and Acoustic Apparatus, with Drawings and Description of the Harmonograph, Post Free, 2d.

W. LADD & CO.,

SCIENTIFIC INSTRUMENT MANUFACTURERS,

(By Appointment to the Royal Institution of Great Britain),

11 AND 12, BEAK STREET, REGENT STREET, W.

IMPROVED HOLTZ ELECTRICAL MACHINES. GRAMME'S MAGNETO-ELECTRIC MACHINE for Laboratory use.

PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3s. per oz.

Physical Apparatus of every Description.

ILLUSTRATED CATALOGUE, SIXPENCE.

PATERSON'S NEW CATALOGUE OF PHYSICAL APPARATUS.

LANTERN SLIDES for SCIENTIFIC LECTURES. Season 1880-1. Post free 6 Stamps.
Complete Sets of Physical Apparatus for Science Primers and all the Physical Text-books in use in Schools and Colleges.
Siemens and Gramme Dynamo Machines and Lamps for hire.
Schools supplied with Apparatus as per Science and Art Departments' Requirements in the Sections of Light, Heat, Sound, and Electricity.
Electric Signals for Houses, Hotels, &c., Colliery Signals, Lightning Conductors. The Gower-Bell Loud-speaking Telephone.

EDWARD PATERSON, Electrical Engineer.

SHOW ROOMS AND STEAM WORKS:—76, LITTLE BRITAIN, E.C. (late 3, Bedford Court, W.C.).

MOLISON'S HARMONOGRAPH; executes the Harmonic Curves in the most perfect manner. 15s. and 20s.

Illustrated Catalogue of Electrical Apparatus, Part 1, *post free,* 6 *Stamps. Ditto, Electric Signals, Part* 2, 6 *Stamps.*

With 112 Engravings and 5 Maps of the Stars.

POPULAR ASTRONOMY.

BY

PROFESSOR S. NEWCOMB, LL.D.

8vo, cloth, price 18s.

"As affording a thoroughly reliable foundation for more advanced reading, Prof Newcomb's 'Popular Astronomy' is deserving of strong recommendation."—*Nature.*

"When we take up a book written by one of the foremost astronomers, mathematically and practically, of the day, we need not fear that, however popular, it will be inexact in its language or evasive in its descriptions. Nor are we disappointed in the book before us. Throughout the whole of it we are struck by the total absence of the defects so common in popular writings. . . . It is unlike anything else of its kind, and will be of more use in circulating a knowledge of astronomy than nine-tenths of the books which have appeared on this subject of late years."—*Saturday Review.*

MACMILLAN & CO., LONDON.

NEW WORK BY LIONEL S. BEALE.

Now ready, pp. 230, *demy* 8vo, 5s.

SLIGHT AILMENTS:

THEIR NATURE AND TREATMENT.

By LIONEL S. BEALE, M.B., F.R.S., F.R.C.P.,

Professor of the Principles and Practice of Medicine in King's College, London.

J. & A. CHURCHILL, New Burlington Street.

"The leading Farmers' paper."—CLARE SEWELL READ, ESQ., M.P.

THE CHAMBER OF AGRICULTURE JOURNAL

AND FARMERS' CHRONICLE

(PRICE 3*d.* WEEKLY).

The representative organ of the Central and Provincial Chambers of Agriculture; *gives fuller reports of the discussions and proceedings* of this extensive organisation than any other agricultural paper. It devotes *special attention to the treatment of Agricultural Questions by Parliament,* besides containing ample Reports of the LATEST LONDON and COUNTRY CORN, CATTLE, HOP, PROVISION, and other Markets, with Original Articles on Practical Farming, the Dairy, Herd and Flock News, Horticulture, &c., &c. It is despatched every Monday evening in time for the country post.

Terms of Subscription, payable in advance, post free:—3 months, 3s. 9½*d.*; 6 months, 7s. 7*d.*; 12 months, 15s. 2*d.*

Published by W. PICKERING, 21, Arundel Street, Strand, London, W.C.

FRY'S COCOA

GOLD MEDAL, PARIS EXHIBITION.

In Packets and Tins. Pure Cocoa only, with the superfluous oil extracted.

"If properly prepared, there is no nicer or more wholesome preparation of cocoa."—*Food, Water, and Air, edited by Dr. Hassall.*

EXTRACT

J. S. FRY & SONS, Bristol and London.

HOLLOWAY'S PILLS

THIS MEDICINE

Is a Certain Cure for all Disorders of the LIVER, STOMACH AND BOWELS. A Great PURIFIER of the BLOOD; a Powerful Invigorator of the System, in cases of WEAKNESS AND DEBILITY, and is unequalled in Female Complaints

FLETCHER'S PERFECTED SOLID FLAME GAS COOKING AND HEATING BURNER.

[PATENT, 3,203.]

The only perfect Burner for Cooking, Boiling, and Dirty Laboratory Work. Free from Smell, the most powerful Burner known, and not damaged by the roughest dirtiest work. This Burner is a valuable improvement on Fletcher's well-known Solid Flame Burner, of which Thousands are in daily use. The Gauze is done away with and replaced by a Loose Perforated Dome of Solid Copper, which can be taken off and Cleaned when Choked with Dirt. The Stand is Broad and Firm, supporting Large or Small Vessels safely and steadily.



PRICE, Japanned, 6s. 6d.; Nickel-Plated, 8s. 6d.

A SMALLER SIZE IN PREPARATION.

ORIGINAL SOLID FLAME BURNER.

PRICE, with Gauze, 4s.; or Nickel-Plated, 5s.

These Burners are the same power, and will with equal ease boil an Egg, cook a Chop, boil a Kettle, or melt half a hundredweight of Lead in an Iron Pot. They will boil half a gallon of Water in a Flat Copper Kettle in Six Minutes, and work equally well with Air, Gas, or Coal-Gas.

Complete Illustrated List, Price 3*d.*, of Gas Furnaces for Crucibles, Muffles, Ladles, Porcelain Painting, &c.; Hot and Cold Blast Blowpipes; Foot, Hand, and Automatic Blowers, Ingot Moulds, &c.; with Reprint of Mr. Fletcher's Lecture to the Society of Arts *On the Application of Gaseous Fuel to Laboratory Work,* for which he was awarded the Society's Silver Medal in June, 1880.

THOS. FLETCHER,

4 & 6, *MUSEUM STREET, WARRINGTON.*

Extra fcap. 8vo, 3s. 6d.

METALS and their CHIEF INDUSTRIAL APPLICATIONS.

By C. ALDER WRIGHT, D.Sc., Lecturer on Chemistry in St. Mary's Hospital Medical School. With Illustrations.

MACMILLAN & CO., LONDON.

Messrs. MACMILLAN & CO.'S PUBLICATIONS.

ETCHING AND ETCHERS. By P. G. HAMERTON. New Edition, Revised, with 48 New Plates. Columbier 8vo.

The text of the new Edition has been thoroughly revised, and increased by one-fifth. Several new Chapters and a new Preface have been added, whilst matter which had become unnecessary or disproportionate has been removed, to make room for studies of more importance. *[Immediately.*

The Edition is limited to 1000 copies, nearly all of which have been subscribed for. The price is now raised to £7 7*s*

LIFE OF WILLIAM BLAKE. With Selections from his Poems and other Writings. By ALEXANDER GILCHRIST. A New and Enlarged Edition, Illustrated from BLAKE's own Works, with Additional Letters and a Memoir of the Author. Printed on hand-made paper, the Illustrations on India paper, and mounted in the text. 2 vols., cloth gilt, elegant, with designs after BLAKE by FREDK. J. SHIELDS. Medium 8vo. £2 2*s*.

Several new Illustrations have been added to this work; among others the following may be named:—The Phillips Portrait of Blake; two new Portraits by Blake of his Wife; a new plate from the *Jerusalem*; a newly-discovered design to *Hamlet*; and a drawing of *Blake's Cottage at Felpham*. New Photogravures of the *Inventions to the Book of Job* are given. Some thirty additional letters are included in the Biographical portion of the work, forming a new link in the already interesting life of Blake. And Mr. W. M. Rossetti has revised, enlarged, and perfected the annotated catalogue of Blake's works that appeared in the first edition of the work.

[Immediately.

ISLAND LIFE; or, the Phenomena of Insular Faunas and Floras, with their Causes, including an entire revision of the Problem of Geological Climates. By ALFRED RUSSEL WALLACE, Author of "The Malay Archipelago," "The Geographical Distribution of Animals," &c. Medium 8vo, with Illustrations and Maps. 18*s*.

"The work throughout abounds with interest."—*Athenæum.*

"Whoever reads his book must be charmed with it."—*St. James's Gazette.*

"We have said enough to show that Mr. Wallace is led to discuss subjects of great interest to speculative minds."—*Pall Mall Gazette.*

A VISIT TO WAZAN, THE SACRED CITY of MOROCCO. By ROBERT SPENCE WATSON. 8vo, with Map and Illustrations. 10*s*. 6*d*.

"The result is one of the most delightful narratives we have had the good fortune to meet with for a very long time . . . In conclusion it remains to be said that Mr. Watson writes in a vigorous, scholarly style, manly and unaffected, oftentimes picturesque, but never descending to mere word-painting."—*Examiner.*

A DICTIONARY OF MUSIC AND MUSICIANS (A.D. 1450—1878). By Eminent Artists, English and Foreign. With Illustrations and Woodcuts. Edited by GEORGE GROVE, D.C.L. In three Volumes. Vols. I. and II., cloth. 21*s*. each.

Vol. I. A to Impromptu. Vol. II. Improperia to Plain Song.

IDEAL CHEMISTRY. By Sir BENJAMIN BRODIE, Bart., F.R.S. Crown 8vo. 2*s*.

FOOD FOR THE INVALID, THE CONVALESCENT, THE DYSPEPTIC, AND THE GOUTY. By J. MILNER FOTHERGILL, M.D., Author of "The Practitioner's Handbook," &c. Crown 8vo. 3*s*. 6*d*.

STUDIES IN DEDUCTIVE LOGIC. By W. STANLEY JEVONS, LL.D., F.R.S., Professor of Political Economy in University College, London. Crown 8vo. 6*s*.

"Besides these answers to questions which greatly increase the value of the book, and make it almost an independent manual of the subject, Professor Jevons has taken occasion to supplement his previous works in various directions. It is indispensable to the many students of the higher logic."—*Athenæum.*

GUIDE TO THE STUDY OF POLITICAL ECONOMY. By Dr. LUIGI COSSA. Professor of Political Economy in the University of Pavia. Translated from the Second Italian Edition. With a Preface by W. STANLEY JEVONS, F.R.S. Crown 8vo. 4*s*. 6*d*.

THE IRISH LAND LAW. By ALEXANDER G. RICHEY, Q.C., LL.D., Deputy Regius Professor of Feudal and English Law in the University of Dublin. Crown 8vo. 3*s*. 6*d*.

THE ARYAN VILLAGE. Modern Village Life in Bengal.—The Agricultural Community in Ceylon.—Supposed Rise and Growth of the Indo-Aryan Village System and Social Grades. By Sir JOHN PHEAR. Crown 8vo. 7*s*. 6*d*.

With Twenty-five Illustrations by WALTER CRANE.

THE NECKLACE OF PRINCESS FIORIMONDE: and other Stories. By MARY DE MORGAN. Extra fcap. 8vo. 6*s*.

ALSO AN EDITION, Printed by Messrs. R. and R. Clark, on hand-made paper. The Plates, initial letters, head and tail pieces being printed on India paper and mounted in the text.

The Edition is limited to ONE HUNDRED COPIES. Fcap. 4to.

"The stories display considerable originality, and Mr. Crane's characteristic illustrations combine with Miss de Morgan's pretty fancies to form a charming gift-book."—*Graphic.*

ENGLISH MEN OF LETTERS. Edited by JOHN MORLEY. Crown 8vo. 2*s*. 6*d*. (New Volumes.)

WORDSWORTH. By F. W. MYERS. *[On December* 12.

LOCKE. By Professor FOWLER.

"In the case of Locke's biographer we venture to say that Mr. Morley has been exceptionally fortunate. A pen more competent than Professor Fowler's for this particular work might have been sought, and sought in vain."—*Examiner.*

A CHRISTMAS CHILD: a Sketch of a Boy-life. By MRS. MOLESWORTH, Author of "Carrots," "The Cuckoo Clock," &c. Illustrated by WALTER CRANE. Globe 8vo. 4*s*. 6*d*.

PANSIE'S FLOUR BIN. By the Author of "When I was a Little Girl," &c. Illustrated by ADRIAN STOKES. Globe 8vo. 4*s*. 6*d*.

"Worthy to be classed with 'Alice in Wonderland,' and in some respects is better adapted to juvenile comprehension."—*Morning Post.*

CICERO'S LIFE AND LETTERS. Being a Translation of the Letters in Mr. WATSON'S Selection, with Historical and Critical Notes, by the Rev. G. E. JEANS, M.A. 8vo. 10*s*. 6*d*

"The style . . . . is life-like, and shows literary power, nor is it superfluous to add that it is for the most part really English and idiomatic."—*Academy.*

HISTORY OF THE ENGLISH PEOPLE. By JOHN RICHARD GREEN. Vol. IV. THE REVOLUTION, 1683—1760. MODERN ENGLAND, 1760—1815. 8vo, with 3 Maps and Index, 16*s*. (Vols. I. to III. 16*s*. each.) *[Concluding Volume.*

"A work that most students of history may turn to with advantage, and that will be almost sure to take rank among the great classics of our literature."—*Globe.*

READINGS FROM ENGLISH HISTORY. Selected and Edited by JOHN RICHARD GREEN. In Three Parts, each 1*s*. 6*d*.

"We cannot imagine a better reading-book for the highest standard of our elementary schools, but it is a book which will have great charms also for the most cultivated readers."—*Guardian.*

FIRST LESSONS IN GREEK. Adapted to Goodwin's "Greek Grammar," and designed as an Introduction to the "Anabasis" of Xenophon. By JOHN WILLIAMS WHITE, Ph.D., Assistant Professor of Greek in Harvard University. Crown 8vo. 4*s*. 6*d*.

XENOPHON'S ANABASIS. Books I.—IV. Edited by Professors W. W. GOODWIN and J. W. WHITE, of Harvard University. Fcap. 8vo. 5*s*. [Macmillan's Classical Series.

LIVY.—SCENES FROM THE HANNIBALIAN WAR. Adapted for the use of Beginners by G. C. MACAULAY, M.A., Assistant-Master at Rugby. Post 8vo. 1*s*. 6*d*. [Macmillan's Elementary Classics.

THE STORY OF ACHILLES, FROM HOMER'S ILIAD. Edited, with Notes and Introduction, by the late J. H. PRATT, M.A., Fellow of Trinity College, Cambridge, Assistant Master at Harrow; and WALTER LEAF, M.A., Fellow of Trinity College, Cambridge. Fcap. 8vo. 6*s*. [Macmillan's Classical Series.

MACMILLAN'S PROGRESSIVE FRENCH COURSE. By EUGENE-FASNACHT, Author of "Progressive German Course," &c. Third year, containing:—Systematic Syntax and Lessons in Composition Fcap. 8vo. 2*s*. 6*d*.

MACMILLAN AND CO., LONDON.

MR. MURRAY'S LIST.

THE POWER OF MOVEMENT IN PLANTS. By CHARLES DARWIN, F.R.S., assisted by FRANCIS DARWIN. With Woodcuts, crown 8vo, 15*s.*

SIBERIA IN EUROPE. A NATURALIST'S VISIT TO THE VALLEY OF THE PETCHORA IN NORTH-EAST RUSSIA. With Notices of Birds and their Migrations. By HENRY SEEBOHM, F.R.G.S. With Map and Illustrations, crown 8vo, 14*s.*

A POPULAR ACCOUNT OF PERUVIAN BARK, AND ITS INTRODUCTION INTO BRITISH INDIA, CEYLON, &C., AND THE PROGRESS AND EXTENT OF ITS CULTIVATION. By CLEMENTS R. MARKHAM, C.B. With Maps and Woodcuts, post 8vo, 14*s.*

A HISTORY OF GREEK SCULPTURE. From the EARLIEST TIMES down to the AGE of PHEIDIAS. By A. S. MURRAY, of the British Museum. With Illustrations, royal 8vo, 21*s.*

JAPAN: ITS HISTORY, TRADITIONS, and RELIGIONS. With the NARRATIVE of a VISIT to JAPAN in 1879. By SIR EDWARD J. REED, K.C.B. With Map and Illustrations, 2 vols., 8vo, 28*s.*

ILIOS: A COMPLETE HISTORY of the CITY and COUNTRY of the TROJANS, including all RECENT DISCOVERIES and RESEARCHES made on the SITE of TROY and the TROAD in 1871–3 and 1878–9. With an AUTOBIOGRAPHY of the AUTHOR. By DR. SCHLIEMANN, Author of "Mycenæ and Tiryns." With nearly 2000 Illustrations, imperial 8vo, 50*s.*

UNBEATEN TRACKS IN JAPAN. TRAVELS of a LADY in the INTERIOR, including VISITS to the ABORIGINES of YEZO and the SHRINE of NIKKO and ISÉ. By ISABELLA BIRD, Author of "A Lady's Life in the Rocky Mountains," &c. With Map and Illustrations, 2 vols., crown 8vo, 24*s.*

MEMOIRS OF THE PERSONAL LIFE of DAVID LIVINGSTONE, LL.D., from his UNPUBLISHED JOURNALS and CORRESPONDENCE. By W. G. BLAIKIE, D.D. With Portrait and Map, 8vo, 15*s.*

THE GARDENS OF THE SUN: Or, a NATURALIST'S JOURNAL on the MOUNTAINS and in the FORESTS and SWAMPS of BORNEO and the SULU ARCHIPELAGO. By F. W. BURBIDGE. With Illustrations, crown 8vo, 14*s.*

RAMBLES AMONG THE HILLS IN THE PEAK OF DERBYSHIRE, and on the SOUTH DOWNS, with Sketches of People by the Way. By LOUIS J. JENNINGS, Author of "Field Paths and Green Lanes in Sussex." With Illustrations, post 8vo, 12*s.*

A SMALLER MANUAL of MODERN GEOGRAPHY. For SCHOOLS and YOUNG PERSONS. By JOHN RICHARDSON, M.A., Diocesan Inspector of Schools, and Author of "A School Manual of Modern Geography." Post 8vo, 2*s.* 6*d.*

HANDBOOK TO THE MEDITERRANEAN. Describing the principal CITIES, SEAPORTS, HARBOURS, and BORDER LANDS, the Coasts of AFRICA, SPAIN, ITALY, DALMATIA, GREECE, ASIA MINOR. Forming a Guide to Corsica, Sardinia, Sicily, Malta, the Balearic Islands, Crete, Rhodes, Cyprus, &c. By COL. R. L. PLAYFAIR. With nearly 50 Maps, Plans, &c., post 8vo.

JOHN MURRAY, Albemarle Street.

Now publishing, in Crown 8vo. Price 2*s.* 6*d.* each.

ENGLISH MEN OF LETTERS.

Edited by JOHN MORLEY.

*** Upwards of 150,000 Vols. of this series have been issued.

LOCKE. By Prof. FOWLER.
"In the case of Locke's biographer we venture to say that Mr. Morley has been exceptionally fortunate. A pen more competent than Prof. Fowler's for this particular work might have been sought, and sought in vain."—*Examiner.*

BYRON. By Prof. NICHOL.
"Decidedly one of the most careful and valuable of the whole series. When a book is so good as Prof. Nichol's, there is little to be said about it except to recommend it as widely as may be."—*Athenæum.*

POPE. By LESLIE STEPHEN.
"The writer's eminent qualities as a critic, his judgment, his wit, his abundant knowledge of eighteenth-century literature, and his keen enjoyment of literary form, have equipped him handsomely for the task he has undertaken."—*St. James's Gazette.*

COWPER. By GOLDWIN SMITH.
"Mr. Goldwin Smith has sketched, in a few decisive touches, the genius of the poet and weakness of the man."—*Daily News.*

CHAUCER. By Prof. A. W. WARD.
"Far away the best connected account of Chaucer and his works to be found in English."—*Academy.*

BUNYAN. By J. A. FROUDE.
"He has given us a real study of Bunyan's life and character, and at the same time a real study of his books."—*Athenæum.*

SOUTHEY. By Prof. DOWDEN.
"A truly scholarly and delightful monograph."—*Examiner.*

HAWTHORNE. By HENRY JAMES, JUN.
"He has made a careful, conscientious, and even vivid literary portrait, such as few of our own writers could have made."—*New York Nation.*

MILTON. By MARK PATTISON.
"Mr. Pattison's achievement is deserving of high praise. He has put life into old facts, he has taken an impartial estimate of a great man whose name is too often used for purposes of poetry."—*Spectator.*

JOHNSON. By LESLIE STEPHEN.
"The new series opens well with Mr. Leslie Stephen's sketch of Dr. Johnson. It could hardly have been done better, and it will convey to the readers for whom it is intended a juster estimate of Johnson than either of the two essays of Lord Macaulay."—*Pall Mall Gazette.*

SCOTT. By R. H. HUTTON.
"We could not wish for a more suggestive introduction to Scott and his poems and novels."—*Examiner.*

GIBBON. By J. C. MORISON.
"As a clear, thoughtful, and attractive record of the life and works of the greatest among the world's historians, it deserves the highest praise."—*Examiner.*

SHELLEY. By J. A. SYMONDS.
"The lovers of this great poet are to be congratulated at having at their command so fresh, clear, and intelligent a presentment of the subject, written by a man of adequate and wide culture."—*Athenæum.*

HUME. By Prof. HUXLEY, F.R.S.
"It may fairly be said that no one now living could have expounded Hume with more sympathy or with equal perspicuity."—*Athenæum.*

GOLDSMITH. By WILLIAM BLACK.
"Mr. Black brings a fine sympathy and taste to bear in his criticism of Goldsmith's writings, as well as his sketch of the incidents of his life."—*Athenæum.*

DEFOE. By W. MINTO.
"Mr. Minto's book is careful and accurate in all that is stated, and faithful in all that it suggests. It will repay reading more than once."—*Athenæum.*

BURNS. By Principal SHAIRP.
"It is impossible to desire fairer criticisms than Principal Shairp's on Burns's poetry. . . . None of the series has given a truer estimate either of character or of genius than this volume."—*Spectator.*

SPENSER. By the Very Rev. the DEAN OF ST. PAUL'S.
"Dr. Church is master of his subject, and writes always with good taste."—*Academy.*

THACKERAY. By ANTHONY TROLLOPE.
"Mr. Trollope's sketch is excellently adapted to fulfil the purpose of the series in which it appears."—*Athenæum.*

BURKE. By JOHN MORLEY.
"It is no disparagement to the literary studies already published in this admirable series to say that none of them have surpassed, while few have equalled, this volume on Burke."—*British Quarterly Review.*

Others in Preparation.

MACMILLAN AND CO., LONDON.

Printed by R. CLAY, SONS, AND TAYLOR, at 7 and 8, Bread Street Hill, Queen Victoria Street, in the City of London, and published by MACMILLAN AND CO., at the Office, 29 and 30, Bedford Street, Covent Garden.—THURSDAY, November 25, 1880.

NATURE

WEEKLY ILLUSTRATED JOURNAL OF SCIENCE

"*To the solid ground*
Of Nature trusts the mind which builds for aye."—WORDSWORTH

23] THURSDAY, DECEMBER 2, 1880 [PRICE SIXPENCE

per at the General Post Office.]

[All Rights are Reserved.

CHING for YOUNG CHIL-
leman or Lady to undertake this, living with thorough knowledge of the subject. Also, a ress *Mr. HERBERT*, Freshwater, Isle of Wight.

CHEMISTRY of GREAT N and IRELAND.
Chemistry in connection with the Institute February, 1881, and four following days. KINSON. Candidates are requested to y. Mr. CHARLES E. GROVES, Somerset

Y OF LONDON.
C AND 1ST M.B. EXAMINATIONS.
ets required for these Examinations will al Medical School early in JANUARY. rom the Secretary, Dr. GILCHRIST.

CHNIC.—CLASSES for
for University Examinations, under the VELING, D.Sc., F.L.S. London Uni- and B.Sc., Preliminary Scientific M.B., All the work practical.

MINERALOGY.
at low prices. Educational Collections specially arranged to illustrate the text- Hins, Davies, Skertchley, Dana, Page, School and College Museums are also Catalogues post free.
ETON, 913 SHEFFIELD.

ILS, 50 MINERALS,
ARRANGED IN A
D POLISHED, LOCK AND KEY.
LED AND CATALOGUED.
wards, £1 10s.
and Range of Deposition, &c.
of the Genera found in the most
for their known uses in the Arts and
acteristic.
alities guaranteed.
ING, Geologist, &c.,
ET, LONDON, E.C.
ures Free.

RUSSELL'S
TORY STORES,
ET, STRAND, W.C.
spect the Collections of British and Echinoderms,
Annelids, Crustacea,
roscopic Objects, &c. Card Trays,
Glass Capped Bones, Cork and Glue, and
, Canada Balsam, Marine Glue, and
croscopist.
Post Free.

BROWNING'S POCKET MICROSCOPE.

The New Pocket or Field Microscope, on Firm Folding Brass Tripod Stand, with fine Adjustment, 1-inch Objective, Large Field Eye-piece, Hand-pliers, &c.: height when set up, 10 inches; dimensions, packed in Morocco Case, 4½ inches long. Price £1 10s. 6d.

Or with 1-inch and ¼-inch Objectives, Stage, Forceps, Stage Plate, and Dipping Tube, £2 5s.

List of Microscopes sent free.

Illustrated Catalogue of Microscopes, with 41 Illustrations, 10 whole page Illustrations, sent for Six Stamps.

JOHN BROWNING,
Optical and Physical Instrument Maker to Her Majesty's Government, the Royal Society, the Royal Observatories of Greenwich, Edinburgh, &c., &c.
63, STRAND, LONDON, W.C.

SPECTACLES AND EYE-GLASSES
MOUNTED WITH
NEGRETTI & ZAMBRA'S
THERMOSCOPIC LENSES
OF THE FINEST
BRAZILIAN PEBBLES,
In Gold, Steel, or Tortoise-shell Frames.

NEGRETTI & ZAMBRA,
Opticians and Meteorological Instrument Makers
TO HER MAJESTY THE QUEEN.
HOLBORN VIADUCT,
45, CORNHILL, & 122, REGENT STREET, LONDON

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 48N, Tollington Road, Holloway, London, N.

GEOLOGY.—In the Preface to the STUDENT'S ELEMENTS of GEOLOGY, by Lyell, 1874, he says: "As it is impossible to enable the reader to recognise rocks and minerals at sight by aid of verbal descriptions or figures, he will do well to obtain a well-arranged collection of specimens, such as may be procured from Mr. TENNANT (149, Strand), Teacher of Mineralogy at King's College, London." These Collections are supplied on the following terms, in plain Mahogany Cabinets:—

100 Specimens, in Cabinet, with 3 Trays	£2	2	0
200 Specimens, in Cabinet, with 5 Trays	5	5	0
300 Specimens, in Cabinet, with 9 Drawers	10	10	0
400 Specimens, in Cabinet, with 13 Drawers	21	0	0

More extensive Collections at 50 to 5,000 Guineas each.

MINERALOGY AND GEOLOGY.

FINE SPECIMENS of ORANGITE, ENSTATITE, BREVICITE, EUXENITE, AUGITE, PYROSMALITE.

UNIQUE SPECIMENS of ADULARIASPHENE and SMOKY QUARTZ.

FINE CRYSTALLISED CROMFORDITES and MATLOCKITE, Derbyshire.

XENOTINE CRYSTALLISED, Valais; WOLLASTONITE CRYSTALLISED.

COLLECTIONS FOR STUDENTS, from £2 2s. COLLECTIONS FOR BEGINNERS, from 4s. BLOWPIPE CASES AND APPARATUS.

PRIVATE LESSONS AND EVENING CLASSES.

Catalogues free.

SAMUEL HENSON,

277 (*Late* 113*a*), STRAND, LONDON, W.C.

THIN GLASS FOR MICROSCOPIC MOUNTING, of best quality. Circles, 3s. 6d. per ounce: Squares, 4s. 9d.; post free 2d. extra; Ground edged Slips, 5s. per gross: also other Mounting Materials and Objects prepared for mounting.—CHAS. PETIT, 151, High Street, Stoke Newington, N.

ROCK SECTIONS & ROCK SPECIMENS.

Collections of Rock Specimens to illustrate Rutley's "Study of Rocks" specially prepared. 100 Small Specimens in Cabinet, One Guinea; 200 Specimens, Two Guineas. Extensive and choice Series of Rocks for selection. New List of Sections of Rocks for Microscope, and List of Collections, &c.

JAMES R. GREGORY'S

Extensive New Museum and Show Rooms,

88, CHARLOTTE STREET, FITZROY SQUARE.

"CHALLENGER" EXPEDITION,

MICROSCOPIC PREPARATIONS FROM,

Per Sir WYVILLE THOMSON.

24 Soundings correctly marked, Lat., Long., Depth, &c., in Box, 30s.

Also, 24 Injected Preparations illustrating Anatomy of the Monkey, in Box, 21s.

To be had of J. T. NORMAN, 178, City Road, E.C., about 100 yards north of Old Street.

A large variety of Specimens in all Branches of Microscopy.

YORK'S

SERIES of SCIENTIFIC OPTICAL LANTERN SLIDES

Comprise over 2,000 of the following subjects:—Electricity, Magnetism, Sound, Telephone, Microphone, Electric Light, Light, Spectrum Analysis, Astronomy, Mines and Miners, Heat, Mechanics, Hydrostatics, Pneumatics, Human Physiology. Sample Slide and Catalogue sent on receipt of 2s.

F. YORK, OPTICAL LANTERN SLIDE MANUFACTURER,

87, Lancaster Road, Notting Hill, London, W.

"The leading Farmers' paper."—CLARE SEWELL READ, ESQ., M.P.

THE CHAMBER OF AGRICULTURE JOURNAL AND FARMERS' CHRONICLE

(PRICE 3*d.* WEEKLY).

The representative organ of the Central and Provincial Chambers of Agriculture; *gives fuller reports of the discussions and proceedings* of this extensive organisation than any other agricultural paper. It devotes *special attention to the treatment of Agricultural Questions by Parliament*, besides containing ample Reports of the LATEST LONDON and COUNTRY CORN, CATTLE, HOP, PROVISION, and other Markets, with Original Articles on Practical Farming, the Dairy, Herd and Flock News, Horticulture, &c., &c. It is despatched every Monday evening in time for the country post.

Terms of Subscription, payable in advance, post free:—3 months, 3s. 9½*d.*; 6 months, 7s. 7*d.*; 12 months, 15s. 2*d.*

Published by W. PICKERING, 21, Arundel Street, Strand, London, W.C.

LIVING SPECIMENS FOR THE MICROSCOPE.

THOMAS BOLTON, NATURALISTS' and MICROSCOPISTS' STUDIO, 17, ANN STREET, BIRMINGHAM.

T. B. has last week sent to his subscribers the curious Larval Form or Trochosphere of the Marine Polyzoon *Alcyonidium*. He has also sent out an interesting gathering of Desmids and Diatoms, also *Clava squamata*, *Pedicellina cernua*, *Stephanoceros Eichhornii*, *Volvox globator*, &c.

Weekly announcements will be made in this place of organisms T. B. is supplying.

Specimen Tube, One Shilling, post-free.

Twenty-six Tubes in course of Six Months for Subscription of £1 1s.

Price List of Specimens on application, with stamped addressed envelope.

Portfolio of Drawings, No. 3, One Shilling.

E. FRIEDLÄNDER & SOHN,

BERLIN N.W., CARLSTRASSE 11.

NATURAL HISTORY & NATURAL SCIENCE BOOKSELLERS.

Established since 1827.

Largest Stock of the whole Literature of Natural History and the Exact Sciences.

Apply for Classified Catalogue in 25 Parts (each one Special Department of Science), price 6*d.* each.

Just published: Part IX., Entomology, 1: Scripta Miscellanea, Coleoptera, 40 pgs.—Part X., Entomology, 2: Lepidoptera, 22 pgs.—Part XI., Entomology, 3: Hymenoptera, Neuroptera, Orthoptera, Diptera, Hemiptera, Parasita, 30 pgs. These Catalogues comprise the Entomological Library of Prof. C. Stal of Stockholm.

NORTH BRITISH AGRICULTURIST

is the only Agricultural Journal in Scotland, and circulates extensively amongst Landed Proprietors, Factors, Farmers, Farm-bailiffs, and others interested in the management of landed property throughout Scotland and the Northern Counties of England.

The AGRICULTURIST has also a very considerable circulation on the Continent of Europe, America, Australia, and the Colonies.

The AGRICULTURIST is published every Wednesday afternoon in time for the evening mails, and contains Reports of all the principal British and Irish Markets of the week, besides Telegraphic Reports of those held on the day of publication.

The Veterinary Department is edited by one of the leading Veterinarians in the country, and is invaluable to the breeder and feeder as a guide to the rearing of animals, and their treatment when labouring under disease.

Full Reports are given of the Meetings o the Royal Agricultural Society of England, the Royal Agricultural Society of Ireland, the Highland and Agricultural Society of Scotland, the Scottish Chamber of Agriculture, and all the principal Agricultural Associations throughout Great Britain and Ireland.

For Advertisers addressing themselves to Farmers a better medium does not exist.

Price 3*d.* By post 3½*d.* Annual Subscription, payable in advance, 14s.

Office—377, High Street, Edinburgh.

Post-Office Orders payable to Charles Anderson, Jun., Edinburgh.

ESTABLISHED 1843.

THE ENTOMOLOGIST'S MONTHLY MAGAZINE.

Price Sixpence, Monthly, 24 pages 8vo, with occasional Illustrations.

Conducted by J. W. DOUGLAS, R. MCLACHLAN, F.R.S., E. C. RYE, F.Z.S. and H. T. STAINTON, F.R.S.

This Magazine, commenced in 1864, contains standard articles and notes on all subjects connected with Entomology, and especially on the Insects of the British Isles.

Subscription—Six Shillings per Volume, post free. The volumes commence with the June number in each year.

Vols. I. to V. (strongly bound in cloth) may be obtained by purchasers of the entire set to date, at the increased price of 10s. each; the succeeding vols. may be had separately or together, at 7s. each.

London: JOHN VAN VOORST, 1, Paternoster Row.

N.B.—Communications, &c., should be sent to the Editors at the above address.

On the 1st of every Month.

TRIMEN'S JOURNAL OF BOTANY, BRITISH AND FOREIGN.

New Series. Edited by JAMES BRITTEN, F.L.S., British Museum.

CONTENTS.—Original Articles by leading Botanists.—Extracts, and Notices of Books and Memoirs.—Articles in Journals.—Botanical News.—Proceedings of Societies.

Price 1s. 3*d.* Subscription for One Year, payable in advance, 12s.

London: WEST, NEWMAN, & CO., 54, Hatton Garden, E.C.

THE "HANSA"

Published since 1864 in Hamburg, is the only independent professional paper in Germany, dedicated exclusively to Maritime Objects. Essays, Critiques, Reviews, Reports, Advertisements. Strict eye kept upon the development of Maritime Affairs in every respect. Every second Sunday one Number in 4to at least; frequent supplements and drawings. Subscription at any time; preceding numbers of the year furnished subsequently. Price 12s. for twelve months. Advertisements 4*d.* a line, widely spread by this paper; considerable abatement for 3, 6, 12 months' insertion. Business Office: Aug. Meyer and Dieckmann, Hamburg, Alterwall, 28. Edited by W. v. FREEDEN, M.R., Hamburg, Alexander Street, 8.

THE BREWERS' GUARDIAN:

A Fortnightly Paper devoted to the Protection of Brewers' Interests, Licensing, Legal, and Parliamentary Matters.

REVIEW OF THE MALT AND HOP TRADES; AND WINE AND SPIRIT TRADE RECORD.

The Organ of the Country Brewers.

"The Brewers' Guardian" is published on the evenings of every alternate Tuesday, and is the only journal officially connected with brewing interests, Subscription, 16s. 6d. per annum, post free, dating from any quarter-day. Single Copies 1s. each. Registered for transmission abroad.

Offices—5, Bond Court, Walbrook, London, E.C.

On the 1st of every Month, price Sixpence.

THE ENTOMOLOGIST:

AN ILLUSTRATED JOURNAL OF BRITISH ENTOMOLOGY.

Edited by JOHN T. CARRINGTON,

With the Assistance of

FREDERICK BOND, F.Z.S. | JOHN A. POWER, M.D.
EDWARD A. FITCH, F.L.S. | J. JENNER WEIR, F.L.S.
F. BUCHANAN WHITE, M.D.

Contains Articles by well-known Entomologists on all branches of the Science; on Insects injurious or beneficial to Farm or Garden; Notes on Habits, Life-Histories; occurrence of Rarities, &c.; there are monthly lists of Duplicates and Desiderata.

Numerous WOODCUT ILLUSTRATIONS, to the printing of which especial attention is given, and occasional LITHOGRAPHED and CHROMO-LITHOGRAPHED PLATES.

SIMPKIN, MARSHALL, & CO., Stationers' Hall Court.

On the 1st of every Month, price One Shilling.

THE ZOOLOGIST:

A MONTHLY MAGAZINE OF NATURAL HISTORY.

Third Series. Edited by J. E. HARTING, F.L.S., F.Z.S., Member of the British Ornithologists' Union; contains—

Original articles by well-known naturalists in every branch of zoology; habits of animals; arrival and departure of migratory birds; occurrence of rare birds; distribution and migration of British fresh-water fish; new or rare marine fish; local aquaria; British reptiles, British land and fresh-water mollusca, with remarks on the haunts and habits of the species; and other matters of general interest to those who delight in natural history. Reports of the Linnean, Zoological, and Entomological Societies. Reviews of natural history books. Occasional translations from foreign zoological journals of important and interesting articles in various branches of zoology. There are occasional woodcuts.

JOHN VAN VOORST, 1, Paternoster Row.

LA SEMAINE FRANÇAISE: a Weekly

Newspaper and Review in the French Language. Politics, Literature, Science, Art, Varieties, Notes. Price 3d., through booksellers, and at the railway bookstalls. Office, 37, Southampton Street Strand, W.C.

LA SEMAINE FRANÇAISE: Journal Française pour l'Angleterre: Politique, Littérature, Sciences, Arts, Variétés, Nouvelles, et Notes. Un exemplaire par la poste, 3½d., en timbres poste Abonnement franco par la poste—un an, 15s. 2d.; six mois, 7s. 7d. Prix 3d., chez tous les libraires et aux gares des chemins de fer. On s'abonne aux bureaux, 37, Southampton Street, Strand, Londres, W.C.

LA SEMAINE FRANÇAISE.—"'La Semaine Française' has been brought out in London for the benefit of those English readers who may wish to study contemporary French from all points of view, instead of confining their reading to one particular Gallic print. It certainly merits success."—*Graphic.*

LA SEMAINE FRANÇAISE.—"The numbers before us are full of good things. . . . . It will be far better for most than any one of the best papers published in Paris itself. We are much pleased with the character of it, and believe it will be highly valued in all those many households where French is cultivated. The printing is very well done."—*Queen.*

TERMS OF SUBSCRIPTION:—

	s.	d.
Three months	3	10
Six "	7	7
Twelve "	15	2

P.O.O. payable to T. SPANSWICK, at King Street, Covent Garden, W.C.

Publishing Office, 37, Southampton Street, Strand, W.C.

5me ANNÉE **L'ÉLECTRICITÉ** 5me ANNÉE

Paris. — 16, rue du Croissant. — Paris

Revue spéciale populaire, illustrée, bi-mensuelle contenant 24 pages grand in-8° à deux colonnes, formant chaque année un magnifique volume de 400 pages orné de plus de 200 gravures.

Rédacteur en chef: **W. DE FONVIELLE**

Directeur: **E. de Clisson**

Envoi gratis de numéro spécimen sur demande

Un numéro **75** *centimes*

Paris et Départements: Un an..... 12 fr.
Etranger. — Union postale: Un an..... 14 fr.

Les Abonnements partent du 5 et du 20 de chaque mois.

With Coloured Diagram of the Spectra of the Metals of the Alkalies and Alkaline Earth, and Illustrations.

BLOWPIPE ANALYSIS:

By J. LANDAUER.

Extra Foolscap 8vo, price 4s. 6d.

Authorised English Edition by JAMES TAYLOR and WILLIAM E. KAY, of the Owens College, Manchester.

The present English Translation contains the Author's latest Corrections and Additions, and has been printed under his personal supervision. Amongst the additions will be found the Author's Systematic Course of Analysis, an extended description of Bunsen's Flame Reactions, and the Reactions with Aluminium Plate proposed by Ross as a substitute for Charcoal.

CONTENTS.

Preface.
Examples for Practice.
Apparatus and Reagents.
The Operations of Blowpipe Analysis.
Bunsen's Flame Reactions.
Special Examination for Certain Elements in Combination.
Systematic Examination of Compound Inorganic Substances.
Condensed View of the Blowpipe Reactions.
Tabular View of the Behaviour of the Earth, Alkalis, and Metallic Oxides, alone and with Reagents, before the Blowpipe.
Index.

MACMILLAN & CO., LONDON.

MACMILLAN'S COPY-BOOKS.

In Two Sizes, viz.: Large post 4to, 4d. each, and post oblong, 2d. each.

1. Initiatory Exercises and Short Letters.
2. Words consisting of Short Letters.
3. Long Letters, with Words containing Long Letters. Figures.
4. Words containing Long Letters.
4a. Practising and Revising Copy-Book for Nos. 1 to 4.
5. Capitals and Short Half-text. Words beginning with a Capital.
6. Half-text Words beginning with a Capital. Figures.
7. Small-hand and Half-text, with Capitals and Figures.
8. Small-hand and Half-text, with Capitals and Figures.
8a. Practising and Revising Copy-Book for Nos. 5 to 8.
9. Small-hand Single Head Lines. Figures.
10. Small-hand Single Head Lines. Figures.
11. Small-hand Double Head Lines.
12. Commercial and Arithmetical Examples, &c
12a. Practising and Revising Copy-Books for Nos. 8 to 12.

Nos. 1 to 9, and 11, may be had with Goodman's Patent Sliding Copies. Large post 4to, price 6d. each.

By a simple device the copies, which are printed upon separate slips, are arranged with a movable attachment, by which they are adjusted so as to be directly before the eye of the pupil at all points of his progress. It enables him also to keep his own faults concealed, with perfect models constantly in view for imitation. Every experienced teacher knows the advantage of the slip copy, but its practical application has never before been successfully accomplished. This feature is secured exclusively to Macmillan's Copy-books under Goodman's patent.

An inspection of books written on the old plan, with copies at the head of the page, will show that the lines last written at the bottom are almost invariably the poorest. The copy has been too far from the pupil's eye to be of any practical use, and the result is a repetition and exaggeration of his errors.

MACMILLAN & CO., LONDON.

WANTED, Clean Copies of NATURE, No. 472, for November 14, 1878. Address—Office of NATURE, 29, Bedford Street, Strand.

In fcap. 8vo, price 3s. 6d.

SOUND: ELEMENTARY LESSONS ON.

By Dr. W. H. STONE, Lecturer on Physics at St. Thomas's Hospital. With numerous Illustrations.

"This is an excellent little text-book, well adapted for students of the Science and Art Classes, but also of considerable value to those who desire to do something more than cram. The student of acoustics will find it a very acceptable help, and a stepping-stone to the more elaborate works on the subject, while the musician will find in its pages information which may be of great assistance to him in the acquisition of his art."—*English Mechanic.*

MACMILLAN & CO., LONDON.

In Memoriam: W. J. Macquorn Rankine.

On DECEMBER 4th, price 31s. 6d., cloth.

MISCELLANEOUS SCIENTIFIC PAPERS.

By W. J. MACQUORN RANKINE, LL.D., F.R.S.,

Late Regius Professor of Civil Engineering in the University of Glasgow.

With MEMOIR by P. G. TAIT, M.A., Professor of Natural Philosophy in the University of Edinburgh.

Edited by W. J. MILLAR, C.E., Secretary to the Institute of Engineers and Shipbuilders in Scotland.

In 1 vol., royal 8vo, with fine Portrait on Steel, Plates, and Diagrams.

WORKS BY PROFESSOR RANKINE.

In crown 8vo, cloth.

I. A MANUAL of APPLIED MECHANICS. Ninth Edition. 12s. 6d.
II. A MANUAL of CIVIL ENGINEERING. Thirteenth Edition. 16s.
III. A MANUAL of MACHINERY and MILL-WORK. Fourth Edition. 12s. 6d.
IV. A MANUAL of the STEAM-ENGINE and other PRIME MOVERS. Ninth Edition. 12s. 6d.
V. A MANUAL of USEFUL RULES and TABLES for ENGINEERS, ARCHITECTS, BUILDERS, &c. Fifth Edition. 9s.
VI. A MECHANICAL TEXT-BOOK. By Prof. MACQUORN RANKINE and E. F. BAMBER, C.E. Second Edition. 9s.

*** The MECHANICAL TEXT-BOOK forms an INTRODUCTION to Prof. RANKINE'S SERIES of MANUALS.

London: CHARLES GRIFFIN AND COMPANY, Stationers' Hall Court.

Now ready.

EXERCISES in PRACTICAL CHEMISTRY. Vol. I. (ELEMENTARY EXERCISES). By A. G. VERNON HARCOURT, M.A., F.R.S., Senior Student of Christ Church, and Lee's Reader in Chemistry; and H. G. MADAN, M.A., Fellow of Queen's College, Oxford. Third Edition, Revised and considerably Enlarged, crown 8vo, cloth, 9s.

London: HENRY FROWDE, Clarendon Press Warehouse, 7, Paternoster Row.

NOW READY, in 4to, cloth, price 6s.

ELASTICITY AND HEAT.

BY

SIR WILLIAM THOMSON,

Professor of Natural Philosophy in the University of Glasgow.

Reprinted from the "Encyclopædia Britannica."

Edinburgh: ADAM & CHARLES BLACK.

To secure Insertion, Advertisements must be forwarded at once.

TWENTY-SECOND YEAR.

Price 1s., per Post 1s. 3d.

On the 20th December will be published the

YEAR-BOOK OF PHOTOGRAPHY AND PHOTOGRAPHIC NEWS ALMANAC FOR 1881. Edited by BADEN PRITCHARD, F.C.S. It will contain—

A Photograph of Daguerre, reproduced from a Daguerreotype, and entirely untouched.—The Gelatine Process in a Nutshell; being a digest of the most recent Improvements during the year.—Standard Formulæ and Processes, drawn from the most trustworthy sources.—Every-day Experiences of Experienced Men.—A List of all the Photographic Societies and Photographic Journals in the World.—Original Articles on all subjects by the most eminent Photographers of the day.

Owing to the increased popularity of the "Year-Book," a much larger edition will this year be issued than on any previous occasion.

To secure insertion, Advertisements must be forwarded at once.

Photographic News Office,

PIPER & CARTER, 5, Castle Street, Holborn.

EXPERIMENTS ON ANIMALS.—Fifth Annual Report of SOCIETY TOTAL ABOLITION VIVISECTION.—British Association.—Hunterian Society.—Prof. Owen.—Dr. Pye Smith.—The Rev. J. G. Wood.—Lewes Studentship.—Licences granted, and Experiments performed, under "Cruelty to Animals Act."—Hibbert Lectures.—Ernest Rénan.—The Royal Society Prevention Cruelty to Animals.—Earlham Temperance Series.—Ovariotomy.—Dr. Clay and Mr. Spencer Wells, F.R.C.S.—Canon Duckworth.—Bishop of Peterborough.—Earl of Pembroke, &c.—8vo, pp. 148, price 1s. 6d. PICKERING & Co., 196, Piccadilly, London, W.; and Mr. GEORGE R. JESSE, Honorary Secretary and Treasurer, Henbury, near Macclesfield, Cheshire.

Now Ready, in demy 8vo, pp. 720, price 24s.

AN INTRODUCTION TO THE STUDY OF FISHES.

By ALBERT C. L. G. GÜNTHER, F.R.S., &c.,

Keeper of the Zoological Department in the British Museum.

Contents.

1. HISTORY and LITERATURE.
2. EXTERNAL PARTS.
3. The SKELETON.
4. MYOLOGY.
5. NEUROLOGY.
6. The ORGANS.
7. GROWTH and VARIATION.
8. PALÆONTOLOGY.
9. DISTRIBUTION.
10. CLASSIFICATION.
11. COLLECTING and PRESERVING.
12. INDEX.

Illustrated with 320 Wood Engravings.

Edinburgh: A. & C. BLACK.

EDITED BY HENRY WATTS, B.A., F.R.S.,

Editor of the *Journal* of the Chemical Society

FOWNES' PHYSICAL and INORGANIC CHMISTRY. Twelfth Edition, with Coloured Plate and 154 Engravings, crown 8vo. 8s. 6d.

Also,

FOWNES' CHEMISTRY OF CARBON COMPOUNDS; or, ORGANIC CHEMISTRY. Twelfth Edition, with Engravings, crown 8vo. 10s.

London: J. & A. CHURCHILL.

Recently Published,

Demy 4to, with 18 Plates (5 printed in Colours), 207 pages, cloth, £2 2s.

AURORÆ:

THEIR CHARACTERS AND SPECTRA.

By J. RAND CAPRON, F.R.A.S.

Part I.—THE AURORA AND ITS CHARACTERS.
Part II.—THE SPECTRUM OF THE AURORA.
Part III.—MAGNETO-ELECTRIC EXPERIMENTS IN CONNECTION WITH THE AURORA.

By the same Author.

Demy 8vo, with 37 Plates, cloth, 30s.

PHOTOGRAPHED SPECTRA.

One Hundred and Thirty-Six Photographs of Metallic, Gaseous, and other Spectra, printed by the Permanent Autotype Process, with Introduction, Description of Plates, and Index, and with an Extra Plate of the Solar Spectrum (showing bright lines) compared with the Air Spectrum.

London: E. & F. N. SPON, 16, Charing Cross.

THURSDAY, DECEMBER 2, 1880

POLITICAL ECONOMY

Guide to the Study of Political Economy. By Dr. Luigi Cossa, Professor of Political Economy in the University of Pavia. Translated from the second Italian edition. With a Preface by W. Stanley Jevons, F.R.S. (London: Macmillan and Co., 1880.)

THE translator of Prof. Cossa's "Guide" has conferred a great boon upon the English student of political economy. The present condition of economic science generally, and especially in this country, cannot be regarded as satisfactory. The doctrines once regarded as firmly established, and the limits of discussion apparently viewed as fixed by the nature of the facts, have been subjected to criticism from the most varied grounds, and the process of disintegration, not yet completed, has not led to any general agreement with respect to the scope and principles of the science. The system of political economy, which with some justice we designate as the English, has been revised or attacked on two grounds mainly. In the first place, the fundamental notions upon which it proceeded have been criticised as too narrow and limited, as referring solely to one economic condition and as leading to results of an abstract and isolated character. The "Economic Studies" of the late Mr. Bagehot represent fairly this phase of opinion, while the excellent little compendium by Prof. and Mrs. Marshall, the "Economics of Industry," is a specimen of the mode in which the older theorems require to be restated in the light of more general principles. In the second place, the great advance in what we may call social science, and the application of the historic method to the study of the various orders of social facts, have led, on the part of many modern writers, to an almost total rejection of the whole system of doctrines grouped together under the title of Political Economy. The fundamental principles, the methods of reasoning from them, and the conclusions arrived at, have all been questioned, while a perfectly chaotic state of opinion appears to exist regarding the nature and method of that which is to take the place of the formerly accepted doctrine.

The present work supplies most timely aid in the discussion of these complicated problems. The first part (pp. 1–84), which treats in a thoughtful and judicious manner the province of political economy, its method, and its bearing upon social facts generally, brings into due prominence the immense extent and variety of the inquiries which, in an unsystematic fashion, have come to be included in one body of doctrine, and fairly warrants the conclusion that in future we must regard political economy as a complex of different sciences, with distinct aims and requiring distinct methods of treatment. The second part (pp. 85-227), containing a brief sketch of the history of the science, which we may without hesitation pronounce as unrivalled of its kind, leads by another path to the same result. The English student will learn from this history of the development of the science, more especially from the admirable account of recent German and Italian works, the nature of the various general principles which have been accepted as furnishing the foundation of economics and its allied branches, and will be enabled to discover in what respects mainly the peculiar doctrines of the older system require revision and amendment.

Prof. Cossa would doubtless be the first to admit that the brief treatment here given of so complex a problem as the determination of the province and logical character of political economy cannot be expected to furnish a final solution. His remarks on the essential nature of pure or theoretical political economy, which he regards as the science of the *social* laws of wealth, are at least instructive and helpful, while the sections on the relation of economics to the various branches of legislative science leave little to be desired. At the same time it may be doubted whether there is really any place for the art of political economy here alluded to, and it may be questioned whether the mode the author adopts for separating economics from technology on the one hand, and from economic legislation on the other, is satisfactory in itself, or so clear as what we find, *e.g.*, in Hermann and Wagner. The chapter on Method in Political Economy contains little more than a judicious reproduction of Cairnes' well-known essay, and the remarks on the historical method, though acute and sensible, do not seem to us to go to the root of the matter.

The historical sketch, the main feature of the work, deserves every praise that can be given for breadth and exactitude of knowledge, for fairness and acuteness of criticism. Particularly valuable are the sections on the Political Economy of the Greeks and Romans, and on the Physiocratic school. One recognises with satisfaction the cordial appreciation extended by the author to certain great works of modern Continental economists which are scarcely known, even by name, in this country, but which must be pronounced absolutely indispensable to the student. Such *e.g.* are v. Hermann's "Staatswirthschaftliche Untersuchungen," the first section of which is certainly the best treatment of the fundamental notions of pure economics, v. Mangoldt's "Volkswirthschaftslehre," Knies' "Geld und Credit," Courcelle-Seneuil's "Traité," and Cherbuliez' "Précis." As text-books of the subject, v. Mangoldt's "Grundriss" and Cherbuliez' "Précis" are unsurpassed.

Naturally one cannot always assent to the critical opinions expressed on detached doctrines or authors. Thus it seems to us that the author ought not to have included Codillac without further mention as a follower of Quesnay; that his estimate of the merits of Storch's "Cours" is much too low; that he is hardly fair to von Thünen's acute speculations on interest and wages; and that he is quite mistaken regarding the nature of v. Mangoldt's theory of profit. What Prof. Cossa, in this connection, stigmatises as "an equivocation" (p. 200) is in fact a misunderstanding of his own.

In a brief sketch covering so wide a literature as that of political economy, absolute completeness is not to be expected, and probably the author has good reasons for omitting various names which occur to one as having a place in the history of the science. Still one is surprised to find a studious omission of the whole school of economical writers to which the vague term *socialist* has been applied. Proudhon, we think, is mentioned once; Fourier, St. Simon, and Karl Marx are not mentioned at all. So

too, American writers are dismissed without notice, save a passing allusion to F. A. Walker. Carey's theories are occasionally referred to in connection with other names, but no specific account is given of them, nor are other American authors, orthodox or heterodox, better treated. Even a general history ought not, one would think, to have omitted notice of such writers as Lord Lauderdale (whose treatment of Demand and of the Functions of Capital has not received the attention it deserves), R. Jones (whose essay on the Early English Economists might also have been noted in its proper place), Jacob, Stirling (the translator of Bastiat and author of an excellent but well-nigh forgotten work, "Philosophy of Commerce"), Bernhardi (the author of a remarkable treatise on Large and Small Landed Properties), Hübner, H. Thornton, Baumstark, Skarbek, Cieskowski, Saint-Chamans, Esmenard de Mazet, Louis Say, Schön, Canard, and Carcanx. Dureau de la Malle's work might have been noted in connection with the political economy of the Romans, and De Tracy's name should not have passed without reference to his commentary on Montesquieu.

The translation appears to us generally excellent, and the translator, who is evidently well acquainted with the subject, deserves much credit for the clear and concise English into which she has rendered Prof. Cossa's work.

OUR BOOK SHELF

Avis préliminaire d'une nouvelle Classification de la Famille des Dytiscidæ. Par D. Sharp. (Extrait des *Comptes rendus* de la Société Entomologique de Belgique, Séance du 4 septembre, 1880.)

DR. SHARP is well known to have been long occupied on a work on the water-beetles of the world (at any rate on those of this particular family). The author announces it as ready for the press, and has forwarded to the Belgian Entomological Society a sketch of his ideas of the limits of the family and its classification, from which we learn that about 80 genera are recognised. One of the most important characters, as separating true *Dytiscidæ* from *Carabidæ* and from all other *Coleoptera*, appears to consist of the condition of the metathoracic episternum in connection with the intermediate cotyloid cavities. The family as a whole is divided into two great divisions, termed "*fragmentati*" and "*completi*," the latter being headed by the anomalous genus *Amphizoa*, the position assigned to which will perhaps not find universal favour. No one can doubt that the book, when it appears, will mark an era in this department of entomology. It is a great pity therefore that Dr. Sharp should throw himself open to the shafts of ridicule in his choice of terms wherewith to designate some of his new genera. We need only allude here to such terms as *Hunchhydrus* (presumably a misprint for *Hutchyhydrus*), *Darwinhydrus*, and *Tyndallhydrus!!!* We all honour the names that form the prefixes, and fail to realise the watery connection suggested.

Aid to the Identification of Insects. Edited by Charles Owen Waterhouse. Lithographs by Edwin Wilson. Small 4to, Part I. (London: E. W. Janson, 35, Little Russell Street, W.C.)

MR. WATERHOUSE, whose duties in the zoological department of the British Museum have probably continually caused him to feel the want of some such work as that which he now commences under the above title, has conceived the idea of issuing, at intervals of a month or six weeks, a series of hand-coloured drawings of insects of all orders not previously figured. Every working naturalist knows that a good pictorial representation conveys a more accurate and ready perception of a species than the most elaborate verbal description; and we can imagine no more ready way of widely disseminating a knowledge of the arcana of science than this. Each part is to contain eight or nine plates, each representing a single species, with its generic and specific names, the name of its describer, and a reference to its locality and place of description. The plates can be classified on the completion of a volume (twelve parts), when a title-page and index will be issued.

The first part, just issued, contains some well-executed figures of *Coleoptera*, *Hemiptera*, and *Lepidoptera*. The whole idea is unconsciously a repetition of Prof. McCoy's "Prodromus of the Zoology of Victoria," but with no Government money to back it up.

LETTERS TO THE EDITOR

[The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts. No notice is taken of anonymous communications.]

The Editor urgently requests correspondents to keep their letters as short as possible. The pressure on his space is so great that it is impossible otherwise to ensure the appearance even of communications containing interesting and novel facts.]

Geological Climates

I HAVE read with much interest Mr. Starkie Gardner's letter in NATURE, vol. xxiii. p. 53.

It is not necessary for me to discuss the question whether I am right in requiring an increase of 20° F. mean annual temperature at Bournemouth in Eocene times, or whether he is right in demanding an increase of only 14° F. to 15°, for I am able to show that the one increase is as *impossible* as the other, on the principles held by Lyell and his followers.

Mr. Starkie Gardner's ideas on the subject of oceanic circulation and its effects upon climate are expressed in the following words:—

"The general cooling effect of incessant oceanic circulation between the North Pole and the Tropics is, I think, scarcely taken into sufficient account; and although it may be contended that conversely the northerly flow of the Gulf Stream mitigates climate, I think that its action in Europe is chiefly in fending off the ice-laden currents from our coasts," &c., &c.

This statement, to my mind, involves so complete a misapprehension not only of the physical causes of oceanic circulation, but also of the whole problem of geological climate, that I shall ask your permission to lay down a few elementary propositions on the subject, which are capable of demonstration.

1. The Gulf Stream of the North Atlantic, so far from acting the part of a policeman in "fending off" imaginary cold water streams from the Polar regions, is the *cause of their existence*. If there were no Gulf Stream there could be no Labrador current of cold water running south. The same statement is true of the Kuro-Siwo of the North Pacific, of the Brazilian current of the South Atlantic, and of the Mozambique current of the Indian Ocean.

2. If the globe were covered with water, or in the condition of an archipelago pretty uniformly distributed, there would be no exchange of currents between the Tropics and the Poles, and consequently no effect upon climate. Within the Tropics there would be a broad, slow current of warm water moving from east to west, and producing no effect upon climate. In the temperate zones there would be in the northern hemisphere a feeble interchange of south-westerly and north-easterly currents, and in the southern hemisphere a similar interchange of north-westerly and south-easterly currents, both incapable of affecting climate to any sensible degree.

3. If a north and south barrier be constructed to the westward of a locality like the West of Europe; such a barrier as North and South America affords, a gulf stream is, at once, formed, and a corresponding Labrador current running in the opposite direction.[1] The effect of the Gulf Stream is to raise the temperature of the West of Europe to its *maximum*, and the effect of the Labrador current is to depress the temperature of the east coast of North America to its *minimum*.

4. It is *impossible* to suggest any rearrangement of land and water which shall sensibly *raise the temperature of the West of*

[1] The earth's rotation compels the Gulf Stream to impinge on the west coast of Europe, and the Polar current on the east coast of North America.

Europe, or sensibly *depress the temperature of the east of North America*.

Mr. Gardner makes the following hypothetical redistribution of land and water :—

"Supposing, as all evidence tends to prove,[1] that Northern Europe and America were connected by continuous land in Eocene time, would not the mere fact of shutting off the Arctic seas cause a general and perhaps sufficient rise of temperature?"

My answer to this is that such an arrangement of land and water in the North Atlantic would raise considerably the present *minimum* temperature of the east coast of North America, but would produce little or no effect in raising the already *maximum* temperature of West Europe, which already receives the full benefit of the Gulf Stream, and suffers none of the injuries of the Labrador current.

It seems to me not possible to raise the mean annual temperature of Bournemouth 15° F. or 20° F. without supposing an *increased Gulf Stream*; in other words, an *an increased sun-heat*, which is contrary to the ideas of Lyell and his followers.

I must again ask Mr. Duncan to name the *species* of bamboo that flourishes so luxuriantly at Cooper's Hill under the disadvantageous conditions he has so well described.

If he decline to do so I have no other remedy than to go to the Indian Engineering College on my next visit to London, and inspect and report on the bamboo myself.

Trin. Coll. Dub., November 23 SAML. HAUGHTON

"Sulphuric Acid and Alkali"

MR. MACTEAR informs me that the statements contained in my review of Prof. Lunge's second volume, which appeared in your columns last week, require amendment, and I beg, in justice to Mr. Mactear, to make the following remarks :—

1. It appears that the direct object of Mr. Mactear's process is to reduce the amount of limestone to the least possible amount. Hence the words "in excess of that usually worked" are to be omitted in the sentence referring to this subject.

2. With regard to the statement that many thousands of pounds have been gained in a single works by the adoption of Mr. Mactear's process, that gentleman has placed in my hands the proof that this fact is correct.

There remains however no doubt that, in the Lancashire district at least, the liming process is not now so generally adopted as Dr. Lunge implies; but this may be explained by the fact that Mactear's process greatly reduces the quantity of caustic soda, and this does not suit the Lancashire plan of working. H. E. ROSCOE

A General Theorem in Kinematics

PROF. MINCHIN has been anticipated in his discovery of the theorem on uniplanar motion given in NATURE, vol. xxiii. p. 62. It was published some six years ago by Prof. W. Schell of the Polytechnikum, Carlsruhe, in the *Zeitschrift für Mathematik und Physik*, xix. 3. The paper containing it is entitled "Ueber den Beschleunigung zustand des ebenen unveränderlichen, in der Ebene beweglichen Systems," and commences at p. 185. The two parts of the theorem will be found in leaded type at pp. 190 and 192. The paper (which is an admirable specimen of clear writing) is purely kinematical, and treats only of motion *in plano*. The dynamical consequences pointed out by Prof. Minchin are accordingly not to be found in it; nor the analogous theorem for the general motion of a rigid body obtained by Prof. Wolstenholme. The following quaternion proof of the latter theorem may interest some of your readers.

The velocity $\dot\rho$ of the particle at vector distance ρ from a fixed origin is— $\dot\rho = \alpha + V\beta\rho$,

α being the velocity at the origin, and β the angular velocity.

The acceleration is therefore—

$$\ddot\rho = \dot\alpha + V\dot\beta\rho + V\beta(\alpha + V\beta\rho),$$

and will be zero for one definite value of ρ.

Taking the point of no acceleration for origin, the constant terms in the expresssion for the acceleration must vanish, and the expression will be reduced to—

$$\ddot\rho = V\dot\beta\rho + V\beta V\beta\rho,$$

which is identical with Prof. Wolstenholme's result.

Malone Road, Belfast, November 22 J. D. EVERETT

Phosphorescent Centipedes

ON September 28 last I was walking in my garden here at eight o'clock in the evening with a friend, when we were simultaneously attracted by a bright light about twenty paces in front of us. The light was so bright that in the distance it looked like moonlight through the trees; and had the moon been shining we should probably not again have thought about the light until we came upon it. But it was a dark night, though warm and even sultry, and still. The light was so bright that, taking a letter out of my pocket, I could read it. It resembled an electric light, and proceeded from the bodies of two centipedes and their two trails. The centipedes were about four inches apart. The light illumined the entire body of the animal, and seemed to increase its diameter three times. It flashed along both sides of the creature in sections; there being about six sections from head to tail, between which the light played. The light behaved precisely like the electric light, moving as it were perpetually in two streams, one on each side, and yet lighting up the whole body. In the trail there was no movement, but light only. The trail extended 1½ foot from each centipede over the grass and the gravel-walk, and it had the appearance of illuminated mucus.

Having observed these creatures for several minutes, I picked one of them up and lodged it in a box which had been procured from the house, for further observation. On touching the centipede the light in both animals, as well as in both trails, was instantly extinguished. Later in the evening we found another centipede, and this also emitted light in the same manner, both from body and trail as I have described. My gardener then informed me that he had observed these creatures during the previous three or four evenings, both in the garden and in the stableyard.

On the following day I took the centipede to Prof. Flower, who, with the assistance of the authorities of the British Museum, has identified the species as *Geophilus subterraneus*.

The published descriptions of the luminous properties of the British centipedes differ considerably from what I observed in this instance.

The best, so far as I know, is given in Shaw's "General Zoology," vol. vi. After describing the animal, it proceeds thus: "It is possessed of a high degree of phosphoric splendour, which, however, seems to be only excited when the animal is pressed or suddenly disturbed, when it diffuses a beautiful smaragdine light, so powerful as not to be obliterated by the light of two candles on the same table."

I may observe that I was never able to induce my centipede to shine whilst in captivity. It may also be worthy of note that the atmosphere was exceptionally dry and the barometer remarkably high at the time of the observation.

B. E. BRODHURST

Grange Court, Chigwell, November 22

The Yang-tse, the Yellow River, and the Pei-ho.

ALTHOUGH the conclusions at which Dr. Woeikof has arrived (NATURE, vol. xxiii. p. 9) with regard to my estimations of the discharge of water and sediment of the Yang-tse and Pei-ho may militate against their being accepted as generally typical of these two rivers, I would urge that another series of observations would be of more service in either correcting or in corroborating my estimations.

In the case of the Yang-tse it will have been seen that, according to the estimate of Capt. Blakiston at I-chang and of my own at Hankow—500,000 and 650,000 cubic feet of water per second respectively,—this river increases its discharge by 150,000 cubic feet in the 360 miles that intervene between these two places of observation. In this portion of its course the Yang-tse not only receives the waters of the Han, but is also the recipient of those of the Tung-ting Lake; and the increase it receives from these two important tributaries—an amount exceeding the water-discharge of the Nile[1]—is not such as would support the conclusion that my estimate for the Yang-tse at Hankow is under the usual average.

My observations on the Pei-ho, referring as they do to only a portion of the year, are more open to correction; and a series of observations throughout the entire twelve months are certainly to be preferred.

In conclusion I may state that, although my various estimations are open to criticism, my object will have been gained if, by inviting further inquiry into the hydrological features of the great river system of China, an accurate knowledge of them is obtained. H. B. GUPPY

[1] I entirely deny this, but will not now turn aside from my present purpose to discuss it.

[1] 130,000 cubic feet per second.

Aurora observed at Ovoca, Co. Wicklow, November 3.—Observations from 5.30 p.m. to Midnight

At 5.30 p.m. yellow lights tinged with red were coming up all round the horizon; these at intervals formed indistinct columns to the south-west and north-west. At 6.30 there were faint reddish lights forming fans at different points; these were succeeded by red and orange lights that rose forming glows, columns, and pencils; while at 7.30 a bright silver-white arch appeared to the north—the horns from this arch were pencils of white, which seemed to cross the arch; they were very numerous, appearing and disappearing nearly instantaneously; from about four to seven appeared at one time. Some of them were very long, shooting up to the zenith. After the arch had dissolved away, brilliant narrow, well-defined, thin columns of silver light shot up, the most marked coming up to the north-west at 7.40; this darted up suddenly, and moved gradually southward, and when about due west, close to the church tower, it disappeared at 7.45.

These silver lights solely occurred between the west and north-east, while all round the horizon red and orange lights were rising; these sometimes congregated at the zenith in a mass. At 7.50 two brilliant silver pencils rose to the north-north-east, but disappeared nearly instantaneously.

From 8 p.m. to 8.50 there were orange and red glows of light sometimes in indistinct columns; but at the latter hour there appeared to the north-west a vivid display of silver light that lasted about five minutes; this was succeeded by a deep orange cloud that travelled up to the zenith. From 9 to 10.30 there was an orange to red glow round the horizon, while at intervals from the north-west rose pencils of silver light, five very brilliant ones rising at 10.30. They were succeeded by a bright silver glow over the whole of the western heaven, across which at intervals passed glows of red and orange light; columns also rose, while at times horizontal streaks of brilliant silver lights appeared and disappeared in a flash. At 11 there was an orange glow round the horizon; this, with spurts of light coming up between the south-west and north-east, were all that was observed up to midnight. G. H. KINAHAN

MR. SPENCER AND PROF. TAIT

WHEN, in NATURE for July 17th, 1879, while reviewing Sir Edmund Beckett's book, Prof. Tait lugged in Mr. Kirkman's travesty of the definition of Evolution, most readers probably failed to see why he made this not very relevant quotation. But those who remembered a controversy which occurred some years previously, possibly divined the feeling which prompted him thus to go out of his way.

At the time I said nothing; but having recently had to prepare a new edition of "First Principles," and thinking it well to take some notice of books, and parts of books, that have been written in refutation of that work, I decided to deal also with Mr. Kirkman's implied criticism, in which Prof. Tait so heartily concurred; and by way of gauging Prof. Tait's judgment on this matter, I thought it not amiss to give some samples of his judgment on matters falling within his own department. To make it accessible to those possessing previous editions of "First Principles," the Appendix containing these replies to critics was published as a pamphlet.

In the inaugural lecture of this session, recently given to his students, part of which is published in the last number of NATURE, Prof. Tait first of all recalls a passage from the preceding controversy. From this he quotes, or rather describes, a clause which, standing by itself, appears sufficiently absurd; and he marks the absurdity by a double note of admiration. Whether when taken with its context it is absurd, the reader will be able to judge on reading the passage to which it belongs.

In disproof of certain conclusions of mine, there had been quoted against me the *dictum* of Prof. Tait concerning the laws of motion, which is that—"as the properties of matter might have been such as to render a totally different set of laws axiomatic, these laws must be considered as resting on convictions drawn from observation and experiment and not on intuitive perception." Not urging minor objections to this *dictum*, I went on to say:—"It will suffice if I examine the nature of this proposition that 'the properties of matter *might have been*' other than they are. Does it express an experimentally-ascertained truth? If so, I invite Prof. Tait to describe the experiments? Is it an intuition? If so, then along with doubt of an intuitive belief concerning things *as they are*, there goes confidence in an intuitive belief concerning things *as they are not*. Is it an hypothesis? If so, the implication is that a cognition of which the negation is inconceivable (for an axiom is such) may be discredited by inference from that which is not a cognition at all, but simply a supposition. . . . I shall take it as unquestionable that nothing concluded can have a warrant higher than that from which it is concluded, though it may have a lower. Now the elements of the proposition before us are these:—*As* 'the properties of matter might have been such as to render a totally different set of laws axiomatic' [*therefore*] 'these laws [now in force] must be considered as resting . . . not on intuitive perception:' that is, the intuitions in which these laws are recognised, must not be held authoritative. Here the cognition posited as premiss, is that the properties of matter might have been other than they are; and the conclusion is that our intuitions relative to existing properties are uncertain. Hence, if this conclusion is valid, it is valid because the cognition or intuition respecting what might have been, is more trustworthy than the cognition or intuition respecting what is!"

From which it is manifest that, when asking (of course ironically) whether this alleged truth was an experimentally-ascertained one, my purpose was partly to ennumerate and test all imaginable suppositions respecting the nature of Prof. Tait's proposition, and partly to show that he had affirmed something concerning the properties of matter which cannot be experimentally verified, and therefore which, by his own showing, he has no right to affirm.

The first example which, in my recent replies to criticisms, I have given of Prof. Tait's way of thinking, is disclosed by a comparison of his views concerning our knowledge of the universe as visible to us, and our knowledge of an alleged invisible universe. This comparison shows that:—

"He thinks that while no validity can be claimed for our judgments respecting perceived forces, save as experimentally justified, some validity can be claimed for our judgments respecting unperceived forces, where no experimental justification is possible."

Part of Prof. Tait's answer is that "the theory there developed [in the "Unseen Universe"] was not put forward as probable, its purpose was attained when it was shown to be conceivable." To which I rejoin that whereas Prof. Tait said he found in this theory a support for certain theological beliefs, he now confesses that he found none; for if no probability is alleged, no support can be derived. The other part of his answer concerns the main issue. After pointing out that the argument of this work, "carried on in pursuance of physical laws established by converse with the universe we know, extends them to the universe we do not know," I had urged that if we have "no warrant for asserting a physical axiom save as a generalisation of results of experiments—if, consequently, where no observation or experiment is possible, reasoning after physical methods can have no place; then there can be no basis for any conclusion respecting the physical relations of the seen and the unseen universes," "since, by the definition of it, one term of the relation is absent." Prof. Tait's explanation is extremely startling. When following the discussion in the "Unseen Universe," throughout which the law of the Conservation of Energy and the Principle of Continuity are extended from the tangible and visible matter and motion around us to an

unknown form of existence with which they are supposed to be connected, readers little thought that Prof Tait meant by this unknown form of existence his own mind. Yet this is all that he now names as the missing term of the relation between the seen universe and the unseen universe.

The second sample which I gave of Prof. Tait's views on matters pertaining to his own subject, concerned the nature of inertia, which he describes by implication as a positive force. Here I quoted Prof. Clerk Maxwell. To repeat his criticism in full would cause me to trespass on the pages of NATURE even more unduly than I must do. If, however, any reader turns to NATURE, July 3rd, 1879, and reads the passage in question, he will be able to judge whether it is, or is not, a joke, and if a joke, at whose expense. Meanwhile, the essential question remains. Prof. Tait says that matter has "an innate power of resisting external influences." I, contrariwise, say that the assertion of such a power is at variance with established physical principles.

One further illustration of Prof. Tait's way of thinking was added. Quoting from a lecture given by him at Glasgow, for the purpose of dispelling "the widespread ignorance as to some of the most important elementary principles of physics," I compared two different definitions of force it contained. In a passage from Newton, emphatically approved by Prof. Tait, force is implied to be that which changes the state of a body, or, in modern language, does work upon it. Later on in the lecture, Prof. Tait says—"force is the rate at which an agent does work per unit of length." I contended that these definitions are irreconcilable with one another; and I do not see that Prof. Tait has done anything to reconcile them. True, he has given us some mathematics, by which he considers the reconciliation to be effected; and, possibly, some readers, awed by his equations, and forgetting that in symbolic operations, carried on no matter how rigourously, the worth of what comes out depends wholly on what is put in, will suppose that Prof. Tait must be right. If, however, his mathematics prove that while force is an agent which does work, it is also the rate at which an agent does work, then I say—so much the worse for his mathematics.

From these several tests of Prof. Tait's judgment, in respect to which I fail to see that he has disposed of my allegations, I pass now to his implied judgment on the formula, or definition, of Evolution. And here I have first to ask him some questions. He says that because he has used the word "definition" instead of "formula," he has incurred my "sore displeasure and grave censure." In what place have I expressed or implied displeasure or censure in relation to this substitution of terms? Alleging that I have an obvious motive for calling it a "formula," he says I am "indignant at its being called a *definition*." I wish to see the words in which I have expressed my indignation; and shall be glad if Prof. Tait will quote them. He says—"It seems I should have called him the *discoverer of the formula!*" instead of "the inventor of the definition." Will he oblige me by pointing out where I have used either the one phrase or the other? These assertions of Prof. Tait are to me utterly incomprehensible. I have nowhere either said or implied any of the things which he here specifies. So far am I from consciously preferring one of these words to the other, that, until I read this passage in Prof. Tait's lecture, I did not even know that I was in the habit of saying "formula" rather than "definition." The whole of these statements are fictions, pure and absolute.

My intentional use of the one word rather than the other, is alleged by him *à propos* of an incidental comparison I have made. To a critic who had said that the formula or definition of Evolution "seems at best rather the blank form for a universe than anything corresponding to the actual world about us," I had replied that it might similarly be "remarked that the formula—'bodies attract one another directly as their masses and inversely as the squares of their distances,' was at best but a blank form for solar systems and sidereal clusters." Whereupon Prof. Tait assumes that I put the "Formula of Evolution alongside of the Law of Gravitation," in respect to the definiteness of the previsions they severally enable us to make; and he proceeds to twit me with inability to predict what will be the condition of Europe four years hence, as astronomers "predict the positions of known celestial bodies four years beforehand." Here we have another example of Prof. Tait's peculiarity of thought. Because two abstract generalisations are compared as both being utterly unlike the groups of concrete facts interpreted by them, *therefore* they are compared in respect to their other characters.

But now I am not unwilling to deal with the contrast Prof. Tait draws; and am prepared to show that when the conditions are analogous, the contrast disappears. It seems strange that I should have to point out to a scientific man in his position, that an alleged law may be perfectly true, and that yet, where the elements of a problem to be dealt with under it are numerous, no specific deduction can be drawn. Does not Prof. Tait from time to time teach his students that in proportion as the number of factors concerned in the production of any phenomenon becomes great, and also in proportion as those factors admit of less exact measurement, any prediction made concerning the phenomenon becomes less definite; and that where the factors are multitudinous and not measurable, nothing but some general result can be foreseen, and often not even that? Prof. Tait ignores the fact that the positions of planets and satellites admit of definite prevision, only because the forces which appreciably affect them are few; and he ignores the fact that where further such forces, not easily measured, come into play, the previsions are imperfect and often wholly wrong, as in the case of comets; and he ignores the fact that where the number of bodies affecting one another by mutual gravitation is great, no definite prevision of their positions is possible. If Prof. Tait were living in one of the globular star-clusters, does he think that after observations duly taken, calculations based on the law of gravitation would enable him to predict the positions of the component stars four years hence? By an intelligence immeasurably transcending the human, with a mathematics to match, such prevision would doubtless be possible; but considered from the human standpoint, the law of gravitation, even when uncomplicated by other laws, can yield under such conditions only general and not special results. And if Prof. Tait will deign to look into "First Principles," which he apparently prides himself on not having done, he will there find a sufficient number of illustrations showing that not only other orders of changes, but even social changes, are predictable in respect to their general, if not in respect to their special, characters.

There remains only to notice the opinion which Prof. Tait seems still to hold, that the verbal transformation which Mr. Kirkman has made in the formula or definition of Evolution, suffices to show its hollowness. Here I may be excused for repeating what I have already said elsewhere, namely, that "We may conveniently observe the nature of Mr. Kirkman's belief, by listening to an imaginary addition to that address before the Literary and Philosophical Society of Liverpool, in which he first set forth the leading ideas of his volume; and we may fitly, in this imaginary addition, adopt the manner in which he delights.

"Observe, gentlemen," we may suppose him saying, "I have here the yolk of an egg. The evolutionists, using their jargon, say that one of its characters is 'homogeneity'; and if you do not examine your thoughts, perhaps you may think that the word conveys some idea. But now if I translate it into plain English, and say that

one of the characters of this yolk is 'all-alikeness,' you at once perceive how nonsensical is their statement. You see that the substance of the yolk is not all-alike, and that therefore all-alikeness cannot be one of its attributes. Similarly with the other pretentious term 'heterogeneity,' which, according to them, describes the state things are brought to by what they call evolution. It is mere empty sound, as is manifest if I do but transform it, as I did the other, and say instead 'not-all-alikeness.' For on showing you this chick into which the yolk of the egg turns, you will see that 'not-all-alikeness' is a character which cannot be claimed for it. How can any one say that the parts of the chick are not-all-alike? Again, in their blatant language we are told that evolution is carried on by continuous 'differentiations'; and they would have us believe that this word expresses some fact. But if we put instead of it 'somethingelseifications' the delusion they try to practise on us becomes clear. How can they say that while the parts have been forming themselves the heart has been becoming something else than the stomach, and the leg something else than the wing, and the head something else than the tail? The like manifestly happens when for 'integrations' we read 'sticktogetherations': what sense the term might seem to have, becomes obvious nonsense when the substituted word is used. For nobody dares assert that the parts of the chick stick together any more than do the parts of the yolk. I need hardly show you that now when I take a portion of the yolk between my fingers and pull, and now when I take any part of the chick, as the leg, and pull, the first resists just as much as the last—the last does not stick together any more than the first; so that there has been no progress in 'stick-togetherations.' And thus, gentlemen, you perceive that these big words which, to the disgrace of the Royal Society, appear even in papers published by it, are mere empty bladders which these would-be philosophers use to buoy up their ridiculous doctrines."

But though it is here, I think, made apparent enough that even when disguised in Mr. Kirkman's grotesque words, the definition of Evolution continues truly to express the facts, Prof. Tait shows no sign of changing his original opinion that Mr. Kirkman has made "an exquisite translation" of the definition. Nay, so charmed does he appear to be with Mr. Kirkman's feats of this nature, that he gives us another of them. One of two conclusions must be drawn. Prof. Tait either thinks that fallacies are disclosed by the aid of these cacophonous long words, or else the clatter of curious syllabic compounds greatly excites his sense of humour. In the last case we may infer that had he been one of that "Twelfth Night" party in which the Clown exclaims—"I did impeticos thy gratillity," he would have joined in Sir Andrew Ague-cheek's applause. HERBERT SPENCER

NOTES ON THE GEOLOGY OF EAST-CENTRAL AFRICA

THOUGH many travellers have now penetrated almost every part of Central Africa, and described the main geographical features, yet their accounts have been singularly barren in any reliable geological details. The Geographical Society, in its late expedition to the lake region, sought to remedy this want, and I, as a student of that science, had the honour of being selected as geologist and assistant to Mr. Keith Johnston, the leader of the expedition.

After the lamentable death of Mr. Johnston, almost at the commencement of our journey, the entire work of the expedition fell into my inexperienced hands, and to perform that work conscientiously precluded all hope of anything but the most superficial geological research. The difficulties in the way were, as in all tropical countries, much increased by the luxuriance of the vegetation, which seldom leaves a rock uncovered and exposed to view. Notwithstanding these obstacles to geological investigation, however, glimpses of the internal structure of the country traversed were here and there obtained, which I think may fairly be considered as shadowing forth the main general features of the geology of the Great Lake Region.

Let me briefly point these out in the order of their occurrence along our route to Nyassa and Tanganyika. The comparatively unbroken stretch of low-lying country which so markedly borders the East Coast of Africa is formed of two, if not three, raised beaches, elevated in recent times above the sea. They consist chiefly of brick-red sands and clays overlying coral rock. The former have been derived by denudation from the coast ranges, which, consisting of hornblende rocks and others containing a large amount of iron, easily account for the deep-red colour characterising these deposits. The sands are of value as containing the gum copal, of which our best varnishes are made. As the tree from which this gum has been derived is now almost extinct, it would seem that a considerable lapse of time has occurred since these deposits have been formed; but geologically they must be recent, as among the many insects that have been found imbedded in the copal none, as far as I am aware, are extinct. The Msandarusi, or gum copal tree, has evidently been restricted to the sea-coast, as neither it nor the gum has ever been found as yet in the interior.

In passing from these sands and clays we step over an immense gap in the geological record, of which no trace remains, as the rocks we next reach are evidently of carboniferous age. These occupy a variable strip along the base of the mountains, here and there rising into small hills and ranges.

They are found stretching from at least Mozambique to the Equator. On the Rovuma coal-beds are found. In the Rufigi valley there are red liver-coloured sandstones with pebbled beds and with interbedded lavas which in one curiously-shaped mountain near Behobeho produce a remarkable step-like appearance. These beds are horizontal, but beneath them are sandstones tilted by the intrusion of eruptive basalts, producing an unconformability which however is probably only local. Further north on the Unyanyembe road from Bogamoyo, and at the base of the mountain I observed on my return march compact beds of fossiliferous limestones, together with shales, &c.

At Umba, a place north of Pangani, I also discovered limestone, which I believe is now being burnt by the Universities Mission Agents. The young geologist, Thornton, the companion of Baron von der Decken, observed this same formation around Mombas, which he noted as being exactly similar to the coal formation of the Zambesi. As no rocks of a later date have been found along the whole of the east coast from Mozambique to the Equator, we may safely infer that this part of the continent has been above water since Carboniferous times, and this inference is strengthened by natural history evidence.

We have now reached the base of the mountains, and again we are brought face to face with another great break in the series of events. From the Carboniferous sandstones and limestones we pass abruptly to highly metamorphosed rocks whose exact place in the geological series is as yet extremely problematical. These consist of the schists, gneiss, and hornblende rocks which form the mountain range that flanks the great Central Plateau extending from Abyssinia to the Cape.

In crossing this range we rose to a height of 7000 feet. We found the strike of the rocks to be north and south. They present every intermediate grade of variation from the most coarsely crystalline to those with the bedding still traceable. Indeed it would be somewhat difficult to point out any sharply-defined line of demarcation between the granites, which seem to predominate

in the plateau, and the less metamorphosed rocks. It seems to me that this range suggests a line of weakness during the elevation of the continent, owing to which the neighbouring rocks were more easily folded up and raised above the line of greatest pressure, which has turned the main mass of the continent into granite. There is however some hope that more definite light will be thrown upon the question of the age of this range, as on my way back to the coast I discovered in the Usagara Mountains some much metamorphosed rocks with imperfectly pre-



Section of Rocks between Dar-es-salaam and Lake Nyassa. 1, Red sandy clays; 2, Carboniferous (?) sandstones with intrusive rocks; 3, Carboniferous sandstones with interbedded lavas; 4, Schists, gneiss, and other highly metamorphosed rocks; 5, Granite forming main mass of the interior; 6, Intrusive rocks and probable line of fault; 7, Clay slates with occasional felspathic rocks; 8, Volcanic porphyrites, tuffs, and agglomerates.

served fossils. A careful search would probably be rewarded by the discovery of fossils which would determine the age of these rocks.

Leaving the metamorphic rocks of the flanking range, we next pass over a great stretch of granitoid rocks. This tract, extending to near the lakes, is marked by undulating hills and valleys, with wide areas comparatively level, where the Kaffir-like semi-nomadic tribes of the Wabena, Warori, Wahehi, Wagogo, and Masai herd their cattle, hunt, and live in a constant state of warfare.

Section between Lakes Nyassa & Tanganyika E. & W.



1, Volcanic porphyrites and tuffs; 2 2, Clay-slates, schists, and gneiss; 3, Intrusive granite; 4, Variegated sandstones slightly metamorphosed.

The influence which the character of the country has upon the habits and manners of savage tribes is here well illustrated.

The soil formed by the degradation of this granite tract is either a stiff red clay as occurs in Ubena and Urori, sandy as in Ugogo, or grey clay as in Unyamwesi. The vegetation varies greatly according to the nature of the soil. The whole of this granitoid region is marked by the occurrence of monstrous blocks, generally rounded, and strewing the whole surface as if some great eruption

Section from S. to N. along west side of Tanganyika.



(1) Variegated sandstones; (2) Intruded rocks and probable line of fault; (3) Sandstones smashed and tilted; (4 4) Felspathic rocks; (5 5) Fine grained brick-red sandstones with quartz pebbles; (6 6 6) Greywacke and other metamorphic rocks.

had smashed the underlying rocks. Their presence, however, is not due to any such cause, the main agent having been rain and carbonic acid, assisted by rapid radiation acting along the joints and cracks.

It may be noted that at a number of points both in Ubena and Ugogo evidences of rocks erupted through the granites were obtained.

Continuing our route to Nyassa over this plateau at a general height of about 5000 feet above the sea we are confronted by a sudden rise in the ground, which forms

apparently a second and higher plateau. The abrupt change of level, together with the alteration in the internal structure and the presence of intrusive rocks at the base of the mountain seem to point to the existence of a fault of considerable magnitude, which probably is the eastward extension of a great fault to be described further on.

The rocks composing this high tract of country consist mainly of clay-slates with the original bedding still very distinct. What may be their exact relations to the granites which they probably overlie, or to the metamorphic rocks of the coast-range, we have as yet no means of ascertaining. Careful research will be required before anything definite can be said about them. The mountains cut out of these rocks by denudation are rounded in form, smooth, and by no means picturesque. They are devoid of trees, but covered with grass.

As we approach Lake Nyassa we observe evidence of much disturbance, till at a distance of about ten miles from the Lake we come upon the ancient pipe of a volcano, and five miles further on enter amongst a series of volcanic porphyrites, tuffs, and agglomerates forming mountains several thousands of feet in height, and which extend round the north end of the Lake. Along with this marked change of internal structure we have as decided a change in the scenery. The rounded mountains with smooth, grassy, and uncut sides give place to jagged peaks, serrated ridges, sharp yawning valleys, and irregular, rocky, notched sides, forming a landscape of no ordinary description.

The extraordinary series of volcanic rocks which form the magnificent mountains round the north end of Lake Nyassa probably belong to the same period as a similar series which characterise the Cape geology. The latter have been assigned to the Trias, and doubtless the immense development of volcanic rocks in Abyssinia described by Blandford is of the same age. Indeed we might almost say we have connecting links between the two places, as on my return march through Ugogo I observed evidence of volcanic outbursts, and it is well known that Kilimanjaro, further north, is of volcanic origin. It seems then that in Triassic times a great line of volcanic action stretched from the Cape by Nyassa, Ugogo, and Kilimanjaro, to Abyssinia.

But at the north-west corner of Nyassa we have evidence of later volcanic activity. In a niche cut out of the surrounding plateau and on a comparatively level plain, through which the River Jumbaka winds to the lake, a number of beautifully isolated cones rise to a height of about 300 feet. On examination these prove to be perfect volcanic craters, so entire and symmetrical as to appear almost artificial. One crater which I examined forms a beautifully bowl-shaped hollow, descending to the level of the plain, the bottom being a charming circular pond, where a number of hippopotamuses live.

It is clear from the perfect shapes of these cones, and from the fact that the surface features of the surrounding country have remained unchanged since their origin, that they must have arisen in comparatively recent times. Besides these cones there are two pretty circular lakes, which also appear to have been originally volcanic craters.

On leaving this interesting country and proceeding on our way to Tanganyika we rise once more to the top of the plateau, cross over mountains 8000 feet in height, and then descend to a general level of from 4000 to 6000 feet. We pass over clay slates and schists whose relative positions could not be determined with intrusive masses of granite. At one point an interesting section was revealed, showing the granite completely inclosing a mass of greenstone.

On nearing the south end of Lake Tanganyika we pass abruptly from these ancient rocks to red and variegated sandstones much hardened and broken, but preserving their original horizontal bedding. Rounding the end of the lake and continuing our march northward along its western side, we come to almost a sheer precipice, suddenly lowering the altitude from nearly 5000 feet to less than 3000. Running east and west along the precipice there occur intruded rocks, while on the northern or lower side of the precipice the sandstones almost disappear, being only represented by a small extent of crushed and tilted beds. Such a condition of things clearly indicates the existence of a great fault. This theory is strengthened by a similar abrupt change of rocks on the eastern side of the lake; and it will be remembered that we have already noticed among a different series of rocks still further east a sudden change of level almost on the same parallel of latitude.

The sandstones thus abruptly brought to a finish in their extension northward are succeeded by felspathic rocks which form huge mountain masses both on the east and west sides of the lake. Near the middle of the lake on its western side there occurs a curious apparently isolated area of fine red sandstones, surrounded on all sides except the east by mountains of metamorphic and felspathic rocks. These sandstones would seem to have been deposited in a small lake eight miles in diameter. Mount Malumbi, figured in Stanley's "Dark Continent," belongs to the same formation.

Still proceeding along the lake we cross a high mountain range named Tchansa, formed of metamorphic rocks with felspathic rock in the centre. We regain the sandstones once more in the country of Uguha. The sandstones here, unlike those of the south end, are very red in colour, extremely friable, and marked by the abundance of quartz pebbles. Through this formation the Lukuga River finds its way to the Congo, its course determined not by any great convulsion as some travellers have been inclined to believe, but by the long-continued action of streams wearing down the soft and friable barrier which hemmed in the lake at this point. These sandstones have an extension over a large area. They are found away towards Manyema and up the Congo Valley as far as Lake Moero, probably turning round and joining the strata we have noticed at the south end of Tanganyika. On the east side they are found from Kaboga to the north of Ujiji, though here shales are not uncommon and the strata much curved.

The absence of all fossils leaves the question of the age of these rocks in some mystery. A reference to Cape geology may, however, as in the case of the volcanic rocks, throw some light on this subject. The Tanganyika sandstones have evidently been formed in an enormous inland lake, beside which the present African lakes would look insignificant.

In Cape Colony a similar series of rocks occur of a lacustrine origin, and which have been assigned to a period not later than the Trias, and probably they belong to Palæozoic times. In the absence of anything but lithological evidence we cannot do better than place the Tanganyika sandstones in the same era as the Cape series, an era which would seem to have been emphatically characterised by the presence of great lakes.

JOSEPH THOMSON

INCANDESCENT ELECTRIC LIGHTS

THE recent experiments of Mr. J. W. Swan of Newcastle-on-Tyne have gone far towards demonstrating the practicabilty of a system of electric lighting based upon the so-called principle of incandescence. As the solution of the whole question of the possible domestic application of electric lighting depends in all probability uppon the successful application of this method, these experiments have claimed already a considerable share of public attention, though no panic has yet arisen like

that created two years ago by the far less formidable experiments of Mr. Edison in the same direction.

The material which Mr. Swan proposes to render incandescent by means of an electric current is a "wire" of prepared carbon of extraordinary density and elasticity. Twenty years ago he prepared carbon filaments for the very same purpose from calcined cardboard, inclosing them in a glass vessel from which the air was withdrawn as perfectly as the imperfect air-pumps of that date permitted. In October 1877, or one year before Mr. Edison had begun to attempt the construction of lamps with carbonised paper, Mr. Swan had some prepared carbons mounted in glass globes and exhausted by the Sprengel air-pump by Mr. Stearn of Birkenhead. This enabled Mr. Swan to discover that when the carbon was properly fixed and heated during exhaustion so that the occluded gases might be expelled, there was an end of the causes that hitherto had seemed to defeat all attempts to utilise this method of procuring an incandescent electric light; for when these conditions were observed there was none of the disintegration of the carbon rods, nor of the blackening of the globes that with less perfect vacua had proved the ruin of carbon lamps. The filaments of carbon now produced by Mr. Swan indeed resemble steel wire rather than carbon, so extraordinary is their tenacity and texture. The secret of their manufacture has not yet been made known, being the essential point of the patent rights which Mr. Swan has just secured. Each filament is about three inches long, and not more than the hundredth of an inch in diameter, and is so slight as only to weigh from one-fifteenth to one-twentieth of a grain. The durability of these filaments is remarkable. In the course of a lecture delivered on November 25 last before the Society of Telegraph Engineers, Mr. Swan stated that he had had lamps lighted continuously since August 30, with an intermission of three weeks only, and that this seemed to be far from the actual limits of durability. When the currents employed are not too strong, the lamps will last longer. The light yielded by these lamps varies, according to circumstances, from thirty to fifty standard candles. On the occasion of Mr. Swan's lecture thirty-six of these tiny lamps were exhibited working by the current of a dynamo-electric machine requiring four horse-power to drive it. In the debate which followed Mr. Swan's communication, the remarks made by Prof. Tyndall, Dr. Hopkinson, Mr. Alexander Siemens, and others, showed the real value of the advance made by Mr. Swan. The question however of the economy of the system remains yet to be decided by the practical test of durability. At a previous lecture at Newcastle-on-Tyne Mr. Swan exhibited twenty lamps fed by a current generated by a gas-engine consuming 160 cubic feet of gas per hour. The light obtained exceeded that of the seventy gas-jets which usually supplied the same room, and which consumed 280 feet per hour. Mr. Swan proposes to connect these lamps in series of fifty or a hundred in one circuit, using automatic circuit-closers to close the circuit in the rare case of the failure of a lamp. He considers his method of arranging the system to be superior to that proposed by Mr. Edison, whose method of placing the separate lamps in single branches of a divided circuit would involve the use of very heavy and costly conducting-wires without any counterbalancing advantage. With this important difference Mr. Swan's further proposal to erect central stations from which to supply currents of electricity over large areas resembles that suggested by Mr. Edison. Should the anticipations of the inventor and the present promise of the new lamps be fulfilled, domestic electric lights will certainly become a fact at no distant date.

Meantime Mr. Edison has not been idle. It is stated that he is at present laying down a service of about seven miles in length upon which to test the success or failure of his system upon a large scale. He has developed several ideas since his last appearance before public notice. He now makes his dynamo-electric generators of a much larger pattern than any heretofore attempted. He has abandoned charred cardboard in favour of a filament of carbon prepared from a cultivated variety of the Japanese bamboo. We shall hear before long whether his indomitable perseverance has been rewarded with final success. In spite of being in point of date behind Mr. Swan, he has the enormous advantages of a unique workshop and laboratory under his own direction, of a wealthy company at his back, and of the extraordinary prestige won by his previous inventions. If Mr. Swan appears to be nearer to a genuine success, Mr. Edison has a popular reputation that of itself will win a hearing for the most trivial of his inventions. Whichever of the rival systems succeeds science and mankind are the gainers. But up to the present point it seems to us that beyond question Mr. Swan is nearer the goal of practical results than his famous rival.

It may interest our readers to know that Mr. Edison's first carbon lamp is now on view along with his original phonograph and his earliest tasimeter in the Patent Museum at South Kensington.

SUBTERRANEAN FOREST IN INDIA

THE accompanying notes and illustrations on the underground forest recently discovered in excavating the Prince's Dock, Bombay, were forwarded by Col. C. J. Merriman, R.E., C.S.I., Member of the Legislative Council, and Secretary to Government (Public Works Department), Bombay.

The trees were generally found in a dark loamy soil composed of underlying rock disintegrated. The upper



FIG. 1.—Dock.

portion of the trunks stopped at the soft black clay, which is silt. A few went a little way beyond; but as far as they protruded into the silt they were completely



FIG. 2.—Section in line of trees B to F. Scale $\frac{1}{16}$ inch to 1 foot.

riddled by the teredo, the nearer the root the bigger the hole, showing that the boring began from the top.

The roots of the highest tree found were at 72·20 on T.H. datum, or close on Low Water extreme springs, about six feet under the surface of the mud. The lowest root was

at 55·93, or say sixteen feet under L.W. extreme springs, twenty-two feet under the surface of the mud.

Inside the dock altogether were 382 trees, 223 standing, the remainder flat. The largest tree was forty-six feet long, and 4′ 6″ girth; it was flat. None of the trees would girth over 4′ 6″. The soil in which many of them stood was only 6″ to 9″ thick over the rock. The wood is apparently black wood. The roots presented a peculiar appearance, being nearly at right angles to the trunks.

The forest seems to have stopped at the gates, as very few trees were brought up in the dredging operations.



FIG. 3.—Section No. 1. Scale—Vertical 15 feet to ½ inch, horizontal 150 feet to ½ inch.



FIG. 4.—Section No. 2.

The mixture of different kinds of stone is curious. In small patches we find trap, which gives way to moorum, and then a sort of pudding-stone mixed up with black and red stuff so hard that it cuts the divers' hands as with a knife.

NOTES

PROF. HELMHOLTZ has been appointed Faraday Lecturer for 1881; the lecture will be given early in April.

WE greatly regret to announce the death of Sir Benjamin C. Brodie, Bart., F.R.S., the eminent chemist and late Professor of Chemistry in the University of Oxford. He died on Wednesday, last week, at Torquay, in the sixty-fourth year of his age. We hope to be able to give a detailed notice of Sir Benjamin's life and work in a future number.

THE death, on Sunday, is announced of Mr. Mark Firth, at Sheffield, in the sixty-second year of his age. Mr. Firth was eminent for his discriminating liberality, and will be specially known to our readers as the founder of the well-known Firth College, Sheffield, opened by Prince Leopold last year.

PROF. J. CHARLES D'ALMEIDA, whose sudden death at Paris we mentioned a fortnight since, was one of the prominent leaders in the scientific circles of the French capital. Formerly a Professor of Physics in the Lyceum of Henry IV., he had occupied for some years past the important and responsible position of Inspector-General of Public Instruction. A strong Liberal in matters of education, he exercised a marked influence in the late reorganisation of the French educational system. It was almost entirely owing to his efforts that the Société Française de Physique owes its creation, and since its origin he has occupied the post of secretary. As an investigator D'Almeida is best known by his valuable researches on the phenomena of electrolysis, on galvanic batteries, on capillary phenomena, &c. One of the most remarkable services he has rendered was the invention of the photographic despatches by means of which, during the siege of Paris, the inhabitants of the city were enabled to avail themselves so extensively of the otherwise limited services of the "pigeon post."

A SHORT time ago we alluded to the severe loss to chemical and technical literature by the death of Prof. von Wagner, who for twenty-five years past has conducted so ably his admirable *Jahresbericht für die chemische Technologie*. The difficult question of finding a successor in the editorship of this important annual has been happily solved by the choice of Dr. Ferd. Fisher, Professor of Technology at the Polytechnic of Hanover. For a long time past Prof. Fisher has rendered valuable literary services in editing *Dingler's Polytechnisches Journal*, the most important technical publication on the Continent. As an investigator he is also well known by his elaborate researches on water in its technical and physiological relations, on pyrometry, and on numerous other chemical and technical questions. Under the new auspices the *Jahresbericht* has every reason to look forward to a continuance of its successful career.

M. CHARCOT reopened last week his course of botany at Salpetrière, where he exhibited last year the curious phenomena of female patients suffering from neuro-mental affections. New instances will be produced of cures analogous to the troubles regarded in mediæval times as produced by demoniacal agency or cured by witchcraft.

IN a lecture on earthquakes delivered in Vienna on the 22nd inst., Prof. v. Hochstetter designated the Agram earthquake (affecting elliptically a region of 60 to 80 German miles diameter, and having its larger axis directed south-south-west to north-north-east) as a tectonic or dislocation-earthquake—a name which originated with the Austrian geologist Prof. Hörnes. Prof. Süss expressed a similar opinion in a lecture on November 24, "On Earthquakes in the Alps."

ON Sunday evening, about six o'clock, slight shocks of earthquake were felt at two different places in Scotland—one being Callander, in Perthshire, and the other Inverary, in Argyllshire. The two districts affected are about forty miles apart, in a line due east and west. The shock was also felt at Rothesay and Stornoway. In the north of Ireland during Sunday evening and also the earlier hours of yesterday morning several decided shocks of earthquake were felt, especially in Londonderry and its vicinity. The disturbance was more particularly felt at Innishowen, and it seemed to travel across the bed of the River Foyle to the County Derry side, where the effects were felt strongly.

AT DORTMUND there was a slight shock of earthquake on November 25, and a smart one on the 27th.

MR. MUNDELLA has been speaking on education again, repeating essentially the old story, that our country must lose in the race unless, as in other countries, education in science is made an imperative part of elementary education. We have many natural and traditional advantages over other countries, but all these must in the long run succumb to scientific training.

A MAGNIFICENT lacustrine find has been made in the marshes of Corcelletes, near Consise, in Canton Vaud. It consists of a

fine canoe in a perfect state of preservation, 11 metres 16 centimetres long, and slightly more than a metre broad. It was dug out and drawn from the marsh by sixty men and eight oxen, under the superintendence of the director of the Museum of Lausanne, and has been placed in the court of the Lausanne Academy, where it is destined to remain.

We have before us the reports for last year of the two clubs which have for their object the furtherance of the special study of British plants and their distribution over the surface of the islands. The Botanical Exchange Club has been in existence about twenty-five years, and was a continuation of the London Botanical Society. The Secretary sends out each spring a list of the plants that are wanted, and the members, who are about thirty in number, at Christmas send in their parcels and lists of desiderata. All doubtful specimens are submitted to competent referees, and after the distribution is made a report is published on critical forms and extensions of distribution. The most interesting find noticed this year is the discovery of *Herniaria hirsuta*, a plant spread widely through the southern half of Europe, by Mr. Fred. Townsend at Christchurch, in Hampshire. Dr. Boswell identifies the prickly comfrey, which has been so much talked about lately as a forage plant, with the *Symphytum uplandicum* of Nyman. Probably it is really a hybrid between *S. officinale* and *S. asperrimum*, as was suggested lately when it was figured by Sir Joseph Hooker in the *Botanical Magazine*. Some curious observations have been made lately tending to show that our wild docks hybridise naturally not unfrequently, like verbascums, geums, primulas, thistles, and epilobia. There is a curious form of *Ophioglossum* (*O. vulgatum*, var. *ambiguum* of Cosson and Germain), which till now has been known in Britain only in the Orkney and Scilly Islands. This year Mr. Chas. Bailey has found it on the Welsh coast between Harlech and Barmouth. The Botanical Record Club has for its object the filling up of the blanks left by Mr. Watson when he traced out in detail the home-distribution of British plants in his "Cybele Britannica." In the report for this year detailed lists are given for Cardiganshire and Peeblesshire, and the only counties for which lists of flowering plants now remain to be drawn up are Flintshire, Wigtonshire, and West Ross. Fourteen pages of the present report are occupied by fresh records for counties already worked up, and the Club is now turning its attention to the distribution of the lower cryptogamia, especially mosses. The registration of flowering plants is in the hands of Dr. F. A. Lees of Wetherby, and of mosses in that of Mr. H. Boswell of Oxford; and the Secretary of both the Clubs is Mr. Chas. Bailey, F.L.S., of Manchester.

Mr. Brian Houghton Hodgson, F.R.S., has just presented to the Anthropological Institute a valuable portfolio of drawings illustrative of the Eastern Himalayas and Tibet. The drawings have been made by the same Nepalese draughtsman as delineated the zoological drawings which have been presented to the Zoological Society, and this ethnological series comprises and contains in all 521 subjects, including duplicates. A series of crania have been drawn by aid of the camera, Mr. Hodgson remarking "native patience, hand and eye being peculiarly fitted to work that instrument."

Etienne Mulsant, one of the most prominent of French entomologists, and librarian to the city of Lyons, died on November 4 at the great age of eighty-four. His earliest publication was the "Lettres à Julie sur l'Entomologie (en prose et en verse)," published in 1830, but for the most part consisting of real love-letters to the lady he afterwards married, and written before he was out of his teens. His writings are most voluminous; but he was best known as the author of a work extending over nearly forty years, on the *Coleoptera* of France, and published (chiefly) in the *Annales* of the Linnean Society of Lyons. He was also the author of a magnificently illustrated work on Humming Birds, in connection with which he visited London about five years ago.

We learn that Messrs. Williams and Norgate are about to issue an important work on the Fishes of Great Britain and Ireland by Dr. Francis Day, late Inspector-General of the Fisheries of India. This work deals with their economic uses, modes of capture, diseases, breeding, life-history, &c., with an introduction on the structure of fishes generally, their functions and geographical distribution. The first part appears this month, and is illustrated by twenty-seven plates. The whole will form a work of 700 pages royal octavo, with over 200 plates.

The exploration of the remains of prehistoric man is being actively carried out in Russia. We have already briefly noticed a contribution to this subject by M. Mereshkovsky, published in the *Izvestia* of the Russian Geographical Society (vol. xvi. No. 2), being a report upon the exploration of caverns and rock-shelters in the Crimea, in the neighbourhood of the Tchatyrdagh Mountain. A great cavern, 145 feet wide and 58 feet deep, was explored close by the Suren town, and M. Mereshkovsky found there the remains of a prehistoric workshop for the manufacture of stone implements, the whole belonging to two distinct periods. The paper by M. Mereshkovsky, published in the *Izvestia*, is accompanied with four tables of drawings of stone implements.

We notice the following interesting communications which were made at the last meeting of the St. Petersburg Geological Society:—On the motion of downs near Sestroretsk, by M. Sokoloff. The velocity of these downs is about one foot per month.—On the excavations made by water in rivers and springs of Northern Esthonia, especially by the waterfalls near Reval, Yagowal, and Fal; and on the Devonian clays discovered by Prof. Inostrantseff in the cuttings of the new Ladoga canal. The upper parts of the beds of these clays are bent by the action of the ice of the ice period, as has been observed at many places in Great Britain; the peats which cover the glacial formations are full of remains of prehistoric man.

We can state that the Observatory of Algiers will not remain longer without an astronomical observer. M. Tripier, who has been appointed director, as has been announced in the French papers, will leave in time for installation at the meeting of the French Association for the Progress of Science in April, 1881.

The purchaser of the French Siemens patent is preparing to send a tender for establishing an electric railway from the Exhibition to the central parts of Paris.

ABNORMAL VARIATIONS OF BAROMETRIC PRESSURE IN THE TROPICS, AND THEIR RELATION TO SUN-SPOTS, RAINFALL, AND FAMINES[1]

II.

Comparison of the Abnormal Barometric Variations with the Sun-Spots

A GLANCE at the barometric and sun-spot curves is sufficient to show that the irregular and frequent fluctuations of pressure are relatively much larger than those of the sun-spots. In order therefore to compare the general course of the barometric curves with that of the sun-spot curve the numbers of Table I. have been further smoothed by taking the means of every nine consecutive quarterly values of the nine-monthly means. The results of this operation are given in the following table, and graphically represented by the dotted curves which are drawn through the continuous ones. All these dotted barometer curves closely resemble each other, except that portion of the Mauritius curve after the year 1865 which shows a tendency to assume an opposite character. They are also very similar to the sun-spot curve, but all of them lag very persistently behind the latter, as will be seen by comparing the points marked with the same capital letters:—

[1] Continued from p. 91.

TABLE II.

Means of every Nine Consecutive Quarterly Values of the Nine-Monthly Means of Solar Spotted Area and Abnormal Barometric Pressure

Year.		Solar spotted area in millionths of visible hemisphere.	Abnormal barometric pressure in thousandths of an inch. St. Helena.	Bombay.	Madras.	Calcutta.	Batavia.	Zi-ka-wie.
	1							
1841	2	396						
	3	359						
	4	316						
	1	284	− 5					
1842	2	244	− 4					
	3	216	− 3		− 6			
	4	188	− 1		− 5			
	1	171	0		− 4			
1843	2	164	0		− 3			
	3	161	− 1		0			
	4	164	− 1		+ 2			
	1	182	0		+ 4			
1844	2	208	+ 2		+ 5			
	3	235	+ 4		+ 6			
	4	268	+ 5		+ 8			
	1	319	+ 6		+11			
1845	2	378	+ 7		+13			
	3	426	+ 8		+14			
	4	480	+ 8		+14			
	1	530	+ 8		+12			
1846	2	582			+10			
	3	658			+ 9			
	4	762			+ 6			
	1	856			+ 2			
1847	2	911			− 3			
	3	946			− 6			
	4	1005			− 9			
	1	1053			−11			
1848	2	1080			−13			
	3	1071		− 7	−15			
	4	1022		− 8	−17			
	1	947		− 7	−17			
1849	2	866		− 6	−16			
	3	804		− 4	−16			
	4	762		− 4	−15			
	1	709		− 4	−14			
1850	2	662		− 5	−11			
	3	626		− 6	−10			
	4	611		− 7	− 8			
	1	610		− 6	− 6			
1851	2	604		− 6	− 5			
	3	602		− 6	− 2			
	4	598		− 7	− 1			
	1	585		− 7	+ 1			
1852	2	560		− 6	+ 2			
	3	532		− 5	+ 4			
	4	498		− 1	+ 6			
			Mauritius.					
	1	452		+ 1	+ 8			
1853	2	392		+ 3	+ 9			
	3	346		+ 3	+ 8			
	4	312		+ 2	+ 7			
	1	281		+ 2	+ 8			
1854	2	239		+ 4	+ 7			
	3	191	−12	+ 5	+ 8	− 1		
	4	147	− 8	+ 6		+ 1		
	1	113	− 6	+ 6		+ 3		
1855	2	93	− 7	+ 5		+ 3		
	3	82	− 8	+ 3		+ 3		
	4	70	−10	+ 3		+ 2		
	1	57	−11	+ 3		− 1		
1856	2	52	−11	+ 1		− 5		
	3	67	−12	0		− 6		
	4	106	−14	− 1		− 6		

Year.		Solar spotted area in millionths of visible hemisphere.	Abnormal barometric pressure in thousandths of an inch. Mauritius.	Bombay.	Madras.	Calcutta.	Batavia.	Zi-ka-wie.
1857	1	161	−15	− 2		− 5		
	2	224	−16	− 2		− 7		
	3	309	−15	− 2		− 7		
	4	422	−11	+ 1		− 5		
1858	1	543	− 4	+ 3	+12	0		
	2	669	+ 3	+ 5	+15	+ 4		
	3	814	+ 6	+ 7	+16	+ 9		
	4	957	+ 7	+ 7	+16	+10		
1859	1	1065	+ 6	+ 5	+14	+ 8		
	2	1145	+ 3	+ 4	+12	+ 6		
	3	1221	+ 2	+ 4	+ 9	+ 4		
	4	1289	+ 1	+ 2	+ 7	+ 2		
1860	1	1325	− 2	− 1	+ 2	− 1		
	2	1356	− 7	− 4	− 5	− 7		
	3	1369	−12	− 6	− 6	−12		
	4	1347	−16	− 8		−15		
1861	1	1296	−17	− 8		−17		
	2	1289	−17	− 9		−16		
	3	1292	−17	−11		−15		
	4	1292	−20	−15		−16		
1862	1	1237	−21	−18		−17		
	2	1161	−22	−18		−17		
	3	1060	−21	−19		−18		
	4	983	−21	−18		−19		
1863	1	930	−19	−16		−19		
	2	922	−15	−15		−18		
	3	867	−11	− 9		−17		
	4	821	− 5	− 4		−14		
1864	1	747	+ 1	+ 1		− 8		
	2	702	+ 6	+ 5		− 2		
	3	668	+11	+ 8		+ 3		
	4	672	+14	+11		+ 8		
1865	1	657	+15	+13		+11		
	2	618	+15	+12		+13		
	3	528	+15	+11		+13		
	4	452	+16	+ 9		+14		
1866	1	367	+17	+ 8		+14		
	2	308	+17	+ 8		+13		
	3	274	+16	+ 9		+12		
	4	262	+13	+11		+13		
1867	1	248	+11	+14		+15		
	2		+ 9	+16		+19		
	3		+ 8	+18		+21	+12	
	4		+ 8	+21		+23	+15	
1868	1		+ 7	+22		+23	+17	
	2		+ 7	+22		+22	+18	
	3		+ 8	+22		+20	+18	
	4		+ 9	+19		+18	+17	
1869	1		+11	+15		+13	+15	
	2		+12	+10		+ 8	+10	
	3		+14	+ 7		+ 4	+ 6	
	4		+16	+ 2		+ 1	+ 2	
1870	1		+18	− 3		− 1	− 3	
	2		+20	− 6		− 3	− 6	
	3		+20	− 8		− 5	− 8	
	4		+22	− 8		− 6	−10	
1871	1		+23	− 7		− 6	−10	
	2		+22	− 6		− 3	− 9	
	3		+21	− 5		0	− 9	
	4		+19	− 7		0	−10	
1872	1		+16	− 7	−11	0	−11	
	2		+13	− 7	−11	− 2	−12	
	3		+11	− 6	−11	− 1	−12	
	4		+10	− 5	−10	− 1	−11	
1873	1		+ 6	− 4	−10	0	− 9	
	2		+ 4	− 2	− 9	+ 1	− 8	
	3		+ 2	− 2	−10	+ 1	− 7	
	4			− 2	−10	+ 2	− 7	
1874	1			0	−10	+ 2	− 5	
	2			+ 1	− 9	+ 2	− 3	
	3			+ 2	− 8	+ 3	− 1	− 5
	4			+ 2	− 8	+ 2	− 3	− 7

TABLE II. (*Continued*)—

Year.		Solar spotted area in millionths of visible hemisphere.	Abnormal barometric pressure in thousandths of an inch.					
			Mauritius.	Bombay.	Madras.	Calcutta.	Batavia.	Zi-ka-wie.
1875	1			0	−10	0	− 4	− 8
	2			− 1	−12	− 2	− 6	− 9
	3			− 1	−13	− 3	− 7	− 9
	4			+ 2	−10	− 1	− 4	− 8
1876	1			+ 6	− 5	+ 2	+ 1	− 7
	2			+13	+ 3	+ 7	+ 7	− 6
	3			+16	+10	+13	+13	− 3
	4			+20		+17	+18	+ 2
1877	1			+23		+24	+23	+ 8
	2			+25		+31	+26	+13
	3			+23		+37	+26	+16
	4			+18		+38		+16
1878	1			+11		+32		+14
	2			+ 7		+26		+13
	3			+ 1		+21		+12
	4			− 4		+16		+ 9
1879	1			− 9		+11		
	2							
	3							
	4							

The epochs of maximum and minimum barometric pressure and of minimum and maximum sun-spot area, as determined from the dotted curves by the graphic method, are given in the following table :—

Epochs of Maximum and Minimum Barometric Pressure and Solar Spotted Area

Solar spotted area.	Barometric pressure.						
	St. Helena.	Mauritius.	Bombay.	Madras.	Calcutta.	Batavia.	Zi-ka-wei.
Min. in July 1843.	Max. in Nov. 1845.	—	—	Max. in Aug. 1845.	—	—	—
Max. in May 1848.	—	—	Min. in Sept. 1848.	Min. in Dec. 1848.	—	—	—
Min. in April 1856.	—	Max. in Oct. 1858.	Max. in Aug. 1858.	Max. in Aug. 1858.	Max. in Sept. 1858.	—	—
Max. in June 1860.	—	Min. in April 1862.	Min. in Aug. 1862.	—	Min. in Jan. 1863.	—	—
Min. in February 1867.	—	?	Max. in May 1868.	—	Max. in Nov. 1867.	Max. in May 1868.	—
—	—	?	Min. in Sept. 1870.	—	Min. in Nov. 1870.	Min. in Dec. 1870.	—
—	—	—	Max. in April 1877.	—	Max. in Sept. 1877.	Max. in May 1877.	Max. in Sept. 1877.

The mean epochs are given below and compared with those of the solar spotted area.

Mean Epochs of Barometric Pressure compared with the Corresponding Epochs of Solar Spotted Area[1]

Solar spotted area. *a.*			Barometric pressure. *b.*			Difference. *b−a.*		
	Year.	Month.		Year.	Month.		Year.	Month.
Min.	1843	7·5	Max.	1845	10·0		+ 2	2·5
Max.	1848	5·5	Min.	1848	11·0		+ 0	5·5
Min.	1856	4·5	Max.	1858	9·2		+ 2	4·7
Max.	1860	6·5	Min.	1862	8·8		+ 2	2·3
Min.	1867	2·5	Max.	1868	3·5		+ 1	1·0
				Mean			+ 1	8·0

From this comparison it appears that the epochs of maximum and minimum barometric pressure lagged behind the corresponding epochs of minimum and maximum solar spotted area at an interval varyiug from above six months to nearly two and a half years, or at an average interval of about one year and eight months.

Making use of this result and comparing points of the pressure curves with points of the solar curve several months earlier, it will be seen that even the minor peculiarities of the pressure curves from 1863 to 1868 do bear some resemblance to the subordinate features of the sun-spot curve from 1862 to 1867. What appear to be corresponding points have been marked with corresponding letters. It is remarkable that this part of the sun-spot curve is the very portion which has been most accurately determined by means of the Kew photoheliograph.

Comparison of the Abnormal Barometric Variations with Past Famines.—According to the Report of the Famine Commission the famine of 1876-78 in Southern India was *the most widespread and severe* of any which have occurred in India during the present century, and on reference to the curves it will be seen that the abnormal barometric pressure during those years was the *highest on record.* In the year 1878 a famine occurred in the North-West Provinces also, in consequence of a deficiency of rain in the previous year.

The famine next in severity to that of 1876–78, and of even greater extent, was the one of 1868–69, which affected Rajputana and the North-West Provinces. The curves show that this also was accompanied or immediately preceded by a *wave of high barometric pressure*, which reached its maximum near the middle of the year 1868.

The next on the list of severe famines is that which occurred in Orissa in the years 1865–66, and it will be seen that this also was attended by a *wave of high pressure* which slowly passed over India in the years 1864–65.

The less extensive Behar famine of 1873-74 was also accompanied by a small wave of high pressure, which, judging from the curves for Mauritius, Bombay, Madras, and Batavia, reached its maximum height towards the end of 1873.

The famine of 1860-61 in the North-West Provinces was also preceded by a wave of high pressure in the year 1859, although the failure of the rains which induced this famine did not occur till the following year.

The above-mentioned famines include *all* the severe ones that have occurred in India since 1841, the year from which barometric data exist; and the waves of high barometric pressure which have been mentioned in connection with them include *all* that have been observed except two, viz. the one in 1855 and the one in 1845, both of which, though not immediately followed by actual famine, were nevertheless accompanied by deficient rainfall both at Madras and Bombay, the fall at the former station being 67 and 78 per cent. of the average in 1855 and 1845 respectively, and at the latter station 58 and 77 per cent. in the same years. Between the years 1832 and 1840, during which the solar spotted area was accurately observed, but for which period I have no barometric data, two other severe famines occurred, viz. the Gantur famine of 1833, and the famine of 1837-38 in Northern India; and it is worthy of note that the first of these occurred soon after the sun-spots had somewhat suddenly fallen to a minimum in 1832, and when, therefore, the barometric pressure would assumably be high, the second soon after the great and sudden diminution of spots which took place early in the year 1837. This last occurrence was very similar to the great decrease of spots observed in 1863, on which occasion

[1] The numbers 1, 2, 3, &c., under the heading "Month," refer to the months January, February, March, &c., respectively, and the decimals of a month are reckoned from the beginning of the respective months.

the decrease was followed by the wave of high pressure which preceded the Orissa famine.

Hence it appears that widespread and severe famines are generally accompanied or immediately preceded by waves of high barometric pressure.

Means whereby future famines may possibly be foreseen.—If the conclusions arrived at from the above comparisons of abnormal barometric variations, sun-spots, and past famines be admitted, it is clear that they at once present the means whereby future famines may possibly be foreseen. The conclusions are briefly:—

1. That variations of the solar spotted area are *succeeded many months afterwards* by corresponding abnormal barometric variations.

2. That abnormal barometric variations in the tropics travel at a very slow rate round the earth from west to east, arriving at westerly stations *several months before* they reach more easterly ones.

3. That famines follow in the wake of waves of high barometric pressure.

Hence it follows that there are two methods by which early intimation of the approach of those meteorological disturbances which are attended by famines may possibly be obtained—

1. By regular observation of the solar spotted area, and early reduction of the observations, so as to obtain early information of current changes going on in the sun.

2. By barometric observations at stations differing widely in longitude, and the early communication of the results to stations situated to the westward.

With regard to the first of these methods it is sufficient to state that the whole subject of solar observations is now being investigated by a committee of scientific gentlemen in London, and we may therefore hope that the all-important information which solar observations are capable of affording will ere long be at our disposal; but with regard to the second method, viz., that of barometric observations at stations differing widely in longitude, it is to be regretted that no observatories of long standing situated in suitable localities to the *westward* of Bombay at present exist, except possibly at the very distant station of Havanna in Cuba. The observatory at St. Helena appears to have been closed in the year 1847, after working continuously for about seven years.

The most suitable localities for barometric observations for the purpose in view are insular stations far removed from the disturbing influences of the large continents and near the equator, such as the Seychelles, St. Helena, and Ascension, but these appear to be at present unoccupied by permanent observatories, while the wide expanse of the Pacific, which is probably the most suitable portion of the earth's surface for investigations of this kind, appears to be entirely unrepresented by any fixed observatory on any of its numerous islands, such as the Galapagos, Sandwich, and Fiji Islands. An observatory has however lately been established at Zanzibar on the East Coast of Africa, from which very valuable observations may be expected if it should continue at work for any great length of time; and another has, I believe, been started at Aden; but as these stations are both situated on the borders of extensive continents, they are not so suitably located as the stations previously mentioned.

It would therefore be necessary, in order to utilise to the fullest extent the second method of foreseeing the approach of a meteorological disturbance of the kind which would probably be attended by famine, that special arrangements should be made for the registration of the needful observations at some, if not all, of the stations that have been referred to; and that the information thus afforded should be rapidly communicated from the more westerly to the more easterly stations.

F. CHAMBERS,
Meteorological Reporter for
Western India

Bombay, September 4

POSTSCRIPT.—In order to determine numerically the intervals of time at which the barometric variations of one station have lagged behind those of another, and behind corresponding minor variations of the sun spots, the times at which the continuous curves cross the dotted ones have been marked off by the graphic method for corresponding crossing points of the different curves, giving the first set of times and intervals in each of the following tables. The same thing has been done with regard to the times at which the continuous curves cross the respective zero lines, giving the second set of times and intervals in each of the tables. As the average pressures for Batavia and Bombay have not been calculated from the observations of the same years, and as the zero line of the Batavia curve is on this account relatively displaced by '004 of an inch in the upward direction, a new zero line has been drawn so as to make the times at which the continuous curve crosses the zero line comparable with those for Bombay. The approximate longitudes of the stations and their differences are also given in the tables.

Station ...	St. Helena.		Madras.		Madras minus St. Helena.
Longitude	5° 44' W.		80° 14' E.		+ 85° 58'.
	Year.	Month.	Year.	Month.	Month.
First Set.	1842	4·1	1843	9·7	+ 5·6
	1843	11·6	1843	12·8	+ 1·2
	1840	3·2	1846	7·1	+ 3·9
Second Set.	1842	6·8	1842	11·5	+ 4·7
	1843	11·4	1844	1·9	+ 2·5
	1846	6·7	1846	9·1	+ 2·4
				Mean	+ 3·38

Station ...	Mauritius.		Calcutta.		Calcutta minus Mauritius.
Longitude	57° 31' E.		88° 23' E.		+ 30° 54'.
	Year.	Month.	Year.	Month.	Month.
First Set.	1856	3·6	1856	6·5	+ 2·9
	1857	5·2	1857	7·3	+ 2·1
	1858	10·5	1858	10·1	− 0·4
	1859	9·1	1860	1·0	+ 3·9
	1861	4·7	1861	9·0	+ 4·3
	1862	4·1	1862	9·5	+ 5·4
	1863	8·0	1864	6·0	+ 10·0
Second Set.	1856	1·1	1856	4·7	+ 3·6
	1858	9·0	1858	6·8	− 2·2
	1859	9·8	1859	11·0	+ 1·2
	1863	10·5	1864	5·9	+ 7·4
				Mean	+ 3·47

Station ...	Bombay.		Calcutta.		Calcutta minus Bombay.
Longitude	72° 48' E.		88° 23' E.		+ 15° 35'.
	Year.	Month.	Year.	Month.	Month.
First Set.	1856	2·5	1856	6·5	+ 4·0
	1857	7·2	1857	7·3	+ 0·1
	1858	5·0	1858	2·8	− 2·2
	1858	8·9	1858	10·1	+ 1·2
	1859	7·5	1859	10·7	+ 3·2
	1861	7·5	1861	9·0	+ 1·5
	1862	6·7	1862	9·5	+ 2·8
	1863	11·1	1864	6·0	+ 6·9
	1865	1·8	1865	9·3	+ 7·5
	1866	1·1	1866	10·2	+ 9·1
	1867	1·5	1867	7·0	+ 5·5
	1867	12·8	1867	10·8	− 2·0
	1869	6·9	1869	8·7	+ 1·8
	1870	6·9	1870	7·1	+ 0·2
	1876	10·1	1876	9·3	− 0·8
	1878	5·4	1878	8·8	+ 3·4

Second Set.	1856	3·1	1856	4·7	+ 1·6
	1857	7·8	1857	9·1	+ 1·3
	1859	9·2	1859	11·0	+ 1·8
	1863	11·5	1864	5·9	+ 6·4
	1869	8·2	1869	9·2	+ 1·0
	1876	4·8	1876	7·8	+ 3·0
	1878	5·9	1878	10·5	+ 4·6
				Mean	+ 2·69

Station ...	Bombay.		Batavia.		Batavia minus Bombay.
Longitude.	72° 48′ E.		106° 50′ E.		+ 34° 2′.
	Year.	Month.	Year.	Month.	Month.
First Set.	1867	12·8	1868	2·1	+ 1·3
	1869	6·9	1869	8·5	+ 1·6
	1872	4·5	1872	5·6	+ 1·1
	1873	5·8	1873	6·8	+ 1·0
	1874	5·4	1874	6·7	+ 1·3
	1875	3·7	1875	4·9	+ 1·2
	1875	9·7	1875	10·0	+ 0·3
	1876	10·2	1876	9·8	− 0·4
Second Set.	1869	8·1	1869	10·0	+ 1·9
	1873	6·2	1873	7·5	+ 1·3
	1874	5·7	1874	7·5	+ 1·8
	1875	4·0	1875	6·0	+ 2·0
	1875	11·2	1875	9·7	− 1·5
	1876	4·9	1876	6·1	+ 1·2
	1878	5·9	1878	7·9	+ 2·0
				Mean	+ 1·07

	Solar spotted area.		Bombay barometer.		
	Year.	Month.	Year.	Month.	Month.
First Set.	1862	3·4	1862	6·7	+ 3·3
	1863	1·3	1863	11·1	+ 9·8
	1863	11·7	1865	1·8	+ 14·1
	1864	12·7	1866	1·1	+ 12·4
	1865	9·4	1867	1·5	+ 16·1
	1866	6·0	1867	12·8	+ 18·8
				Mean	+ 12·4

	Solar spotted area.		Madras barometer.		
	Year.	Month.	Year.	Month.	Month.
First Set.	1849	6·7	1849	12·8	+ 6·1
	1850	11·2	1851	5·4	+ 6·2
				Mean	+ 6·1

It will be seen that in the great majority of cases the barometric waves reach the westerly station several months before they arrive at the more easterly one, but that the rate of progression of these waves across the Indian Peninsula appears to be much slower than across the open ocean to the southward.

F. C.

THE ROYAL SOCIETY—ADDRESS OF THE PRESIDENT[1]

DR. SPOTTISWOODE began by referring to the losses which the Society has sustained by death during the past year:—Prof. Miller, Dr. Sharpey, Mr. Lassell, Prof. Ansted, Lord Belper, Mr. E. W. Cooke, and Sir Benjamin Collins Brodie.

The Society's finances generally are, as the balance-sheet will show, in a healthy condition, and appear to justify the hope that they will suffice for the large claims upon them for printing our publications. The address then proceeds:—

Although we are more concerned, Dr. Spottiswoode said, with the quality than with the quantity of communications made to the Society, it may not be without interest to observe that the number of papers received this year has been in excess of that in any previous year, at all events since 1872, inclusive. The following is a table of the numbers during the last nine years:—

1872	... ...	99 papers	received.
1873	... ...	92 ,,	,,
1874	... ...	98 ,,	,,
1875	... ...	88 ,,	,,
1876	... ...	113 ,,	,,
1877	... ...	97 ,,	,,
1878	... ...	110 ,,	,,
1879	... ...	118 ,,	,,
1880	... ...	123 ,,	,,

and we may conclude that these have contained good matter from the fact that of the *Philosophical Transactions* for the current year Parts i. and ii., already published, contain no less than 900 pages and thirty-three plates.

Dr. Spottiswoode then referred to the satisfactory results of the change of time of meeting of the Society, and went on to speak of the death of Mr. Henry White, who for many years was chief assistant in the compilation of the great Catalogue of Scientific Papers. At an earlier stage of the work, Dr. Spottiswoode went on to say, his loss would have been still more serious; but in a long course of training he succeeded so well in imparting his own careful and methodical mode of work to those under him, that the Council felt justified in making trial of his son to take his place. With the result of this trial, as shown in continuing the preparation of a new edition of the catalogue of the Society's Library, the Council has reason to be satisfied. Of this new edition, the first portion, 220 pages, containing our large collection of *Transactions* and *Proceedings* of Academies and Societies, and other scientific periodicals is in type, and will shortly be printed off. The verification of titles of our scientific books generally is so far advanced as to warrant the expectation that a large instalment of this portion of the catalogue will soon be in the printer's hands; after which we anticipate no further delay.

In regard to the Library, a question has arisen as to how far purely literary works, which occupy much space, should be retained. Among them there are doubtless some which add neither to the utility nor to the scientific importance of our Library, but there are also some early printed books, bibliographical treasures, which are worthy of a place in any collection. It is proposed to have these carefully put in order, and to place them in a case by themselves. Among these, there may be mentioned:—

Caxton's Chaucer, 1480.
Pynson's Chaucer, 1492.
Speght's Folio Chaucer, 1598.
Ciceronis Officia et paradoxa, Fust, 1466, vellum.
The generall historie of Virginia, Lond. 1632.
Bonifacius. Sextus decretalium liber. Ven. 1566-7
Plautus, 1482. Seneca, 1490.
Ovid, 1485. Statius, 1490.
Plutarch, 1485. Herodotus, 1494.
Homer, 1488.

For bringing into prominence these as well as other features of our miscellaneous, *i.e.* non-scientific, books, we are greatly indebted to the care and knowledge brought to bear on the subject by Mr. Tomlinson, and by our treasurer.

Although it is doubtless undesirable to propose, without sufficient cause, alterations in our statutes, or even in our practice, it is still often worth while from time to time to discuss questions involving such alterations in order that we may be prepared for a

[1] Address of William Spottiswoode, D.C.L., LL.D., the President, delivered at the Anniversary Meeting of the Royal Society on Tuesday, November 30, 1880

deliberate judgment whenever occasion may arise. Among such subjects there is one upon which I have often heard opinion expressed, and upon which opinion has always weighed in the same direction: I allude to the period of office of those elected to serve on the Council of the Society. By the terms of our charter ten of the ordinary members retire every year; and as it is our custom to remove six according to seniority and four in respect of least attendance, it rarely happens, although the contrary is possible, that any Fellow, except those holding the posts of President, Treasurer, or Secretary, should remain in office more than two years. Experience, however, appears to show, that for a member serving on the Council for the first time, there is so much to learn, so many heads of business which do not in general come before the Fellows at large, that his first year is occupied quite as much in ascertaining his duties as in actively performing them. This objection is in some degree met by selecting for the ten incoming members five who have served before, and five who have not so served; but, nevertheless, there is usually an interval of several years between two periods of office, and as a matter of fact we often lose a member of Council at the moment when his advice is becoming most valuable to our body.

I am aware of the great convenience attaching to our present impersonal mode of selecting the members to retire in each year, and am not at present prepared to suggest any specific alteration. But the great confidence which the Society has, especially of late years, placed in its more permanent officers, and the power which naturally accrues to them from the comparatively short tenure of office by the other Members of Council, appear to me to be points of which the Society should not lose sight. On the part of the officers I think it right to state that we are very sensible both of the honour which is thus done to us and of the responsibility which is thereby entailed, and that we hope never to discredit the one nor to abuse the other. And having said so much, we are quite willing to leave the matter in the hands of the Society to be taken up whenever they see reason so to do.

It will be in the recollection of the Fellows that the position of the Royal Society in respect of the Government Fund of 4000*l.* per annum is different from that in relation to the Government Grant of 1000*l.* per annum. In the latter case the sum is placed unreservedly in the hands of the Society for promoting scientific investigation, subject only to an annual report to the Treasury of the disposal of it; and, in administering it, the Society has in no case applied it to the personal remuneration of the applicant. In the former case the Society has been requested to advise the Science and Art Department as to the distribution of the grant, not only for the direct expenses of investigations, but also for personal remuneration for the time expended on them, whenever the circumstances and wishes of the applicant appeared to render this desirable. The responsibility of this advice lies with a Committee similar to that of the Government Grant, but with the addition of the presidents of certain learned bodies and societies, nominated for that purpose by the Government.

The recommendations made by the Committee each year are annually published in the *Proceedings*, so that the public will have had full information as to the distribution of the grant; while the Fellows have the opportunity of seeing the nature of applications made, and the extent to which it has been found practicable to meet them, as recorded in the minutes of the Council of the Society.

One of the points which is perhaps beset with the greatest difficulty is that of the so-called "personal" grants. On the one hand it has been argued that it is desirable to enable the man of small means to devote to research a part of his time which he could not otherwise afford to give; but, on the other, the question has been raised whether it be wise, even in the interests of science, to encourage any one not yet of independent income to interrupt the main business of his life. It is too often assumed that a profession or a business may be worked at half-speed, or may be laid down and taken up again, whenever we like. But this is not so, and a profession temporarily or even partially laid aside, may prove irrecoverable; and the temptation to diverge from the dull and laborious path of business may prove to have been a snare. Without proposing to exclude from possible aid in some shape or other those cases where personal assistance may be safely offered, it has been suggested that many such cases may be practically met by grants for the employment of an assistant, instead of grants to the applicant himself.

There is another fundamental difference between the position of the Government Grant of 1000*l.* per annum and the Government Fund of 4000*l.* per annum, which appears to me to be of material importance in the interests of science. The former is an absolute grant from the Treasury made to the Society for scientific purposes. It may be used wholly, or in part, during the year in which it is made, and the balance, if any, may be carried over by the Society to the next or even to succeeding years. The latter is a vote to the Science and Art Department, on the disposal of which the Society is consulted. Like all other similar votes, any unused balance reverts to the Treasury, and is to that extent lost to the purpose for which it was intended. I cannot help thinking that, if any such balances could be reserved and kept in hand, provision might be made for some larger purposes than those to which the fund has hitherto been devoted. And, even if having this end in view, the Committee should not see its way to recommend some of the smaller applications, it may be fairly questioned whether the smaller grants might not find a more appropriate place among those of the Donation Fund of this Society, or of the British Association, or among some of those separate funds which, through the liberality of individuals, are now growing up among the special societies.

I am glad to record the fact that, upon the recommendation of men of science, Her Majesty has been pleased to grant pensions on the Civil List to the widows of two of our late Fellows, viz., to Mrs. John Allan Broun and to Mrs. Clifford.

Last year two volumes containing a collection of the late Prof. Clifford's general lectures and essays were brought out. It is hoped that during the present winter a collection of his mathematical papers will be published. The contributions to science by the late Prof. Rankin have recently been placed in the hands of the public. While very sensible of the obligations under which the scientific world is placed by these posthumous publications, I cannot refrain from alluding to our obligations, even greater if possible, to those who during their lifetime are willing to re-issue their own scientific memoirs, and to give us thereby not only the convenience of ready access, but also the advantage of their own subsequent reflections on the subjects of which they have treated. And at this particular moment I desire to mention more particularly the mathematical and physical papers of our Senior Secretary, Prof. G. G. Stokes; and, while expressing our gratitude for the volume which has already appeared, I would express also our sincere hope that another instalment from the same source may shortly follow.

Among the subjects which at one period of the late session of Parliament engaged the attention of the Government was that of the law relating to vaccination; and a Bill was introduced intended to remove some of the practical difficulties in carrying out the existing law. While fully admitting the difficulties in question, the remedy proposed appeared to trench so closely upon the application at least of a scientific principle, and at the same time to be so important in its practical aspect, that I ventured (although the Council was not sitting) to consult the Presidents of the Colleges of Physicians and of Surgeons, and that of the Medical Council, about addressing the Government on the subject. This resulted in a joint deputation to the President of the Local Government Board, in which I took part as President of the Royal Society. I reported this matter to the Council at their first meeting after the recess, and received their approbation. The Bill in question was withdrawn.

The Royal Commission on Accidents in Coal Mines, the appointment of which I mentioned in my address of last year, has been occupied principally in bringing together a body of valuable evidence on the causes and prevention of accidents in mines generally. The Commission has also visited a number of mines in which serious accidents by explosion have taken place, or in which certain phenomena connected with the occurrence of fire-damp were to be studied. They have also instituted a series of experiments on the behaviour of various safety lamps in mixtures of natural fire-damp and air. These experiments they are about to renew during the winter. They also contemplate carrying out experiments in blasting rock and coal by methods which will check the production of flame, and which are thereby calculated to obviate the danger of igniting fire-damp.

The report of the voyage of H.M.S. *Challenger*, to which the scientific world has been looking forward with so much interest, is now so far advanced that one volume of the "Zoological Memoirs" will appear immediately. In addition to this a second volume may be expected within a year. The first volume of the whole work, "containing a short narrative of the voyage, with all necessary hydrographical details, an account of the appliances and methods of observation, a running

outline of the results of the different observations; and a chapter epitomising the general results of the voyage," together with the second volume containing the meteorological, magnetic, and hydrographic observations, will probably be published within the same period. "The general report on the zoology of the expedition will consist of about fifty distinct memoirs, which will occupy from ten to twelve volumes." It has been arranged "to print the Zoological Reports as they are prepared, and to publish them as soon as a sufficient bulk of memoirs is ready to form a volume. Copies of each memoir may also be had separately, in order that working naturalists may have them in their hands at the earliest possible date." Two more volumes on the geology and petrology, and one on the general chemical and physical results, will probably complete the series. Into the details of the zoological results I am not competent to enter; but the greatest interest attaches to the fact that notwithstanding the pressure and absence of light, there is no depth-limit to animal life.

As the Council of the Meteorological Office is nominated by the Council of the Royal Society, and as the Annual Report of the Office is submitted to the Royal Society, I think it right to mention a few points connected with the work of that department during the past year.

1. A method of recording the duration of bright sunshine by the charring of an object placed in the focus of a glass sphere, freely exposed to the rays of the sun, was devised by Mr. J. F. Campbell of Islay in 1856; and instruments, being modified forms of that originally proposed, have been employed for some time at Greenwich, at Kew, and at a few private observatories. Certain difficulties in adjusting the paper about to be charred to the path of the burning spot, which had hitherto prevented the adoption of Mr. Campbell's invention as a part of the ordinary equipment of a meteorological observing station, have been at last successfully overcome by an arrangement designed by Prof. Stokes; and thirty stations in the British Isles have now been supplied with instruments of the pattern proposed by him. We may thus hope to obtain in future a sufficient record of a meterological element, which is of primary importance in its relations to agricul.ure, and to the public health, but which has hitherto been very imperfectly registered.

2. The climatology of the Arctic regions, in addition to its importance as a part of the general physics of the globe, possesses a special interest in connection with geographical exploration. As a contribution to our knowledge of this subject, the Meteorological Office has entrusted to Mr. R. Strachan the task of bringing together, and discussing on an uniform plan, the results of the observations taken at intervals during the last sixty years, in the region extending from the meridian of 45° W. to that of 120° W., and from the parallel of 60° to that of 80°, either at land stations or at the winter quarters of British and American expeditions. A considerable portion of this discussion has been already published; the remainder may be expected in the course of next year.

3. Another publication of the Meteorological Office may be mentioned as serving to mark the advance in meteorological theory, which has been achieved during the last fifteen years. The old "Barometer Manual and Weather Guide" of the Board of Trade has been replaced, so far as it relates to the weather of the British Isles, by a work entitled "Aids to the Study and Forecast of Weather," prepared under the direction of the Meteorological Office by the Rev. W. Clement Ley. Though some of the views put forward in the later work may, perhaps, be regarded as not sufficiently established by observation, yet a comparison of the two works cannot fail to leave upon the reader's mind the impression that in the interval between their respective dates of publication, some real progress has been made in meteorology. Perhaps this is most conspicuous in the enlarged ideas that are now entertained concerning the conditions upon which the changes of weather depend. Local weather was first discovered to be contingent upon travelling areas of disturbance, each of which averaged many hundreds of miles in diameter, while, at the present time, the relation of these areas to one another, as parts of a single terrestrial system, has become a prominent topic of inquiry. If meteorology has thus been, to a certain extent, rescued from the ever-accumulating chaos of numerical tabulations, which threatened to engulf the whole science, the improvement is mainly due to the development in recent times of the synoptic study of weather over large regions of the earth's surface, to which so great an impetus has been given by the extended facilities of telegraphic communication.

4. Balloon ascents, with a view to military purposes, are now systematically carried on under the direction of the War Office; and the endeavour has been made to take advantage of these ascents for observations of the thickness of the aërial current which causes our winds, and of the peculiarities of the currents above it in the upper strata of the atmosphere. The military authorities have offered their co-operation in the most cordial manner; but the attention of an aëronaut is often so much engrossed by the operations necessary for working his balloon, that he has but little leisure for taking systematic records. Nevertheless, observations of considerable interest have already been obtained, relating especially to the velocity and direction of the upper air currents; and there can be no doubt that a continuance of such observations affords the best prospect at present open to us of adding to the very scanty knowledge which we possess of the movements of the atmosphere, even at a moderate height above the earth's surface.

Among the various duties which the President of the Royal Society is called upon to fulfil, there are those of a Trustee of the British Museum; and, as an operation of great importance to science, namely the removal of the natural history collections to the new building at South Kensington, is now going on, the Fellows may be interested to hear what progress has been made in the work.

The plans for the new building were approved as long ago as April, 1868: but the works were not commenced until the early part of 1873. Their progress was retarded by difficulties in the supply of the terra cotta with which the building is faced within and without, and in which the mouldings of arches and other ornamental features are executed.

The building was finally handed over to the Trustees in the month of June of the present year. It contains cases for three only of the departments for which it is intended, namely, Mineralogy, Geology, and Botany; the necessary funds for the Zoological Department not having yet been voted. As the latter collections are equal in bulk to the other three collectively, it follows that only half the new building can at present be actually occupied. The removal of the collections for which cases had been provided, commenced in the last week of July, and was virtually completed by the end of September.

Geology, which was very inadequately displayed in the old building, is now more commodiously accommodated. It now occupies a gallery 280 feet in length by 52 in breadth, forming the ground floor of the east wing of the new museum, together with eight other galleries covering an area of 200 × 170 feet at the back, and admirably adapted for the exhibition of the specimens. One of these galleries will be devoted to the illustration of stratification.

The principal part of the Minerals has been moved and replaced in the cases in which they were arranged in the old building. The collection now occupies the first floor of the east wing of the new museum, and the space devoted to it is 280 × 50 feet in area. It is already arranged for exhibition.

The Botanical collections are placed in the gallery over the minerals, where the space for exhibition and the conveniences for study are much greater than in their old quarters.

The construction of the cases for the Zoological specimens, and the ultimate removal of these collections, must depend upon the amount of the Parliamentary vote for the purpose; but under the most favourable conditions it can hardly be hoped that this department can be open to the public or to students for two years from the present time.

The "Index Museum," designed by Professor Owen, will form a prominent feature in the new museum. The object of it, in his words, is "to show the type characters of the principal groups of organised beings;" and "to convey to the great majority of visitors, who are not naturalists, as much information and general notions of its aim as the hall they will first enter and survey could be made to afford."

One of the principal difficulties attending the transfer of the Natural History Departments to a separate building consists in the provision of books for the use of the keepers and their staff, as well as for students who may visit the museum. Hitherto the separate collections of books, known as departmental libraries, supplemented as occasion might require from the main library of the museum, have sufficed for all purposes. But now, when the departmental libraries have to stand by themselves, it is impracticable to carry on even the current work of arrangement without additional resources. For an adequate supply of the necessary works a very large outlay would be required, sup-

posing that the works were in the market. But many of them are out of print and have become scarce; and a large grant of public money would perhaps raise the market price almost in proportion to its magnitude. This being so, it has been thought best, on the whole, by the Government to make an annual grant to be expended from time to time as favourable opportunities for purchase may offer. If it should prove possible, and on other grounds desirable, to allow the Banks' Library to follow the collections with which it has always been practically connected, the wants of the Natural History Departments would (so far as books up to the date of its bequeathment are concerned) be in a great measure supplied.

Another of the duties which falls officially on your President is to take part in the organisation of technical education as promoted by the City and Guilds of London Institute, which is now incorporated under the Companies Acts, 1862-80, as a registered association, and of which the Presidents of the Royal Society, the Chemical Society, the Institute of Civil Engineers, and the Chairman of the Council of the Society of Arts, are members. In the Memorandum and Articles of Association of the Institute, its objects are fully set forth. They may be summarised under the following heads:—

1. The establishment of a central technical institution for instruction in the application of science and art to productive industry.

2. The establishment of trade and technical schools in London and in the country.

3. The development of technical education by means of examinations held at the Central Institution, or at other places.

4. To assist by means of grants existing institutions in which technical education is being promoted.

5. To accept gifts, bequests, and endowments for the purposes of the Institute.

The Institute is supported by subscriptions from sixteen of the City Companies, of which the largest contributors are the Mercers, Drapers, Fishmongers, Goldsmiths, and Clothworkers.

The Institute has been in active operation not much more than a year, and during the last six months the work of the Institute has developed considerably in each of its several departments. These may be considered under the following heads:—

1. Technical Instruction.
2. Examinations in Technology.
3. Asssistance to other Institutions.

1. Since November last courses of lectures and laboratory instruction have been given in the temporary class-rooms of the Institute, at the Cowper Street Schools, under the direction of Prof. Armstrong, F.R.S., and of Prof. Ayrton. The subjects of instruction have included Inorganic and Organic Chemistry, with special reference to their industrial applications; Fuel, Electro-depositions of Metals, and Photographic Chemistry; General Physics, Steam, Electrical Engineering, Electrical Instrument Making, Electric Lighting, Weighing Appliances, and Motor Machinery.

During the term ending July last the number of tickets issued to students, most of whom belonged to the artisan class, exceeded three hundred. A considerable accession of students is expected as soon as the building in Tabernacle Row, the plans of which are already settled, shall be erected. This building, which is estimated to cost £20,000*l.*, will provide accommodation for schools of Technical Physics, Technical Chemistry and Applied Mechanics. Many of the day students at these classes are pupils of the Cowper Street Schools, and it is expected that, by adapting the course of technical instruction to be given in the College to the wants of these boys, a very complete technical school for the children of artisans will have been established.

The evening lectures and laboratory instruction, which are more advanced and more special, are attended very largely by external students, for whom the present temporary accommodation is already too limited.

At Kensington, schools have been established in which practical instruction is given in various art subjects, such as Painting and Drawing, Modelling, Designing, and Wood Engraving. These schools are attended by both sexes, and are under the immediate direction of Mr. Sparkes. The numbers in attendance last term were as follows:—

Wood Engraving . . .	8 Students,	3 Men,	5 Women.
Modelling	28 ,,	26 ,,	2 ,,
Drawing and Painting from Life	42 ,,	19 ,,	23 ,,
Designing	33 ,,	3 ,,	30 ,,

The Central Institution for instruction in the application of the higher branches of science to industrial pursuits is about to be erected on a plot of ground in Exhibition Road, granted by the Commissioners of 1851. The construction of this building, which, when completed, will cost 50,000*l.*, has been entrusted to Mr. Alfred Waterhouse, who is now engaged in the preparation of plans.

2. In the year 1879, the examinations in Technology, which had been initiated by the Society of Arts, were transferred to this Institute. Various changes where introduced into the regulations. New subjects were added, and in order to stimulate the teaching of Technology throughout the country, the principle of payment to teachers on the results of the examinations was adopted. The encouragement thus afforded to teachers gave a great impetus to the formation of classes throughout the country in technological subjects. Last year the number of candidates for examination was 202, while at the recent examination, held in May, 816 candidates presented themselves, of whom 515 satisfied the Examiners. During the last few months the number of classes throughout the country, in which technical instruction is being given, has considerably increased, and, judging from the returns already received, there is reason to believe that the number of candidates, who will present themselves for examination next May will be much greater than in either of the preceding years. The new programme, which is just issued, contains a syllabus of each subject of examination, and every effort has been made, short of testing the candidates' practical skill, to make the examinations as efficient as possible. To obtain the Institute's full certificate, each candidate is required to give evidence of having obtained some preliminary scientific knowledge.

3. In order to take advantage of efforts that are already being made to advance technical education, the Institute has given sums of money for specific objects to several institutions in which technical instruction is provided. The schools, colleges, and other bodies which have received grants from this Institute, are University College and King's College, London, the School of Art, Wood Carving, and Mining Association of Devon and Cornwall, the Nottingham Trade and Science Schools, the Artisans' Institute, the Birkbeck Institute, the Lancashire and Cheshire Union, and the Horological Institute.

The Artisans' Institute gives practical instruction in several of the humbler crafts in which artisans are engaged, such as carpentry, zinc work, and plumbers' work; and corresponds, therefore, to some slight extent with the apprenticeship schools of the Continent, from which, however, it differs in many important particulars. A similar experiment is being tried at the Horological Institute, where, at the expense of the Guilds, classes have been organised, in which apprentices receive practical instruction in the various branches of the watch-making trade.

It is found that the demand for technical instruction in London and throughout the provinces is very great, and the efforts that have been so far made by the City and Guilds of London Institute have been received with considerable satisfaction by artisans and others engaged in industrial pursuits, and promise, when further extended, to be of the utmost service in the development of technical education in this country. Turning now more particularly to the progress and the applications of science, I venture to make mention of a few topics which have come under my own observation.

(*To be continued.*)

OUR ASTRONOMICAL COLUMN

LUNAR ECLIPSES, 1880-84.—The total eclipse of the moon is only partly visible in this country, the middle occurring at 3h. 39m. Greenwich time, and the moon not rising until seven minutes later; the end of the total phase takes place at 4h. 24m., and the last contact with the earth's shadow at 5h. 33m. In Australia the whole eclipse may be witnessed to advantage. On December 5, 1881, there will occur an almost total eclipse (magnitude 0·97), again only partly visible here; the first contact with the shadow at 3h. 28m., and the moon rising at 3h. 50m.; greatest phase at 5h. 8m. In 1882 there will be no lunar eclipse. On October 16, 1883, a partial eclipse is barely visible here; first contact with the shadow at 5h. 59m. a.m., the moon setting at 6h. 25m. The next favourably-circumstanced lunar eclipse, as regards observation in this country, will take place on the evening of October 4, 1884; first contact with shadow at 8h. 15m., beginning of total phase at 9h. 16m., middle of the eclipse

at 10h. 2m., ending of total phase at 10h. 48m., and last contact with shadow at 11h. 49m.

A PROBABLE VARIABLE STAR.—On November 25 Swift's comet was compared with the star No. 4339 of Lalande, by Mr. Talmage at Mr. Barclay's Observatory, Leyton, the magnitude of the star being estimated 8, as it was also by Lalande. Argelander, in the *Durchmusterung*, gives it 6·4, and Heis made it a naked-eye star (6·7), but errroneously identifies it with Lalande 4359. It escaped observation in the Bonn Zones, and may be worth occasional examination as likely to prove an addition to our variable star list.

FAYE'S COMET.—In the *Berliner atsronomisches Jahrbuch* for 1882, Prof. Axel Möller, of Lund, has given an ephemeris of Faye's comet extending to the end of March next. On comparing the theoretical intensity of light appended to the ephemeris with that corresponding to particular epochs in other appearances, it will be found that there is a probability of observing the comet for some weeks from this time without difficulty if the larger instruments be employed. Thus at the beginning of January the calculated degree of brightness is more than twice that appertaining to the dates when the comet was first and last observed with the Northumberland telescope at Cambridge, during the return of 1850-51, and the geocentric position is favourable for observation; a month later the intensity of light is still equal to that at the time of the first observation with the Copenhagen refractor in 1865, and even at the close of Prof. Axel-Möller's ephemeris it is equal to that at the first and last Cambridge observations above alluded to; the comet's place, however, will then be drawing into the evening twilight. We have already remarked that the magnitude of the planetary perturbations of the comet's motion during the revolution 1873-1881 is greater than in any other revolution since the comet's discovery in 1843, and the success which has again attended his prediction of its apparent track in the heavens must have excited the admiration of those who have any experience or knowledge of such investigations, and the immense amount of skilled application involved in them.

SWIFT'S COMET.—The following elements depend upon Mr. Chandler's observation on October 25, one at Strassburg on November 9, and a third at Mr. J. G. Barclay's Observatory, Leyton, on November 25:—

Perihelion passage 1880, November 8·3691 Greenwich M.T.

	°	′
Longitude of perihelion	42	15·2
,, ascending node	294	46·6
Inclination	7	21·3
Log. perihelion distance	0·04188	

Motion—direct.

The close resemblance to the orbit of the third comet of 1869, it will be seen, is maintained. The elements give these positions for Greenwich midnight:—

		R.A. h. m.		Decl. ° ′		Log. distance from Earth.		Sun.		$\frac{1}{r^2.\Delta^2}$
Dec.	2	3 44·1	...	+50 57	...	9·3188	...	0·0680	...	16·8
	3	3 53·6	...	50 10						
	4	4 2·5	...	49 21	...	9·3366	...	0·0721	...	15·2
	5	4 10·7	...	48 32						
	6	4 18·5	...	47 41	...	9·3556	...	0·0765	...	13·7
	7	4 25·6	...	46 50						
	8	4 32·3	...	+45 59	...	9·3756	...	0·0811	...	12·2

UNIVERSITY AND EDUCATIONAL INTELLIGENCE

OXFORD.—No further regulations have been issued by the University Commissioners for the Professoriate. Opinion is much divided in the University itself as to the operation of the new rules. There have been several memorials to the Commissioners got up, some praying that no alterations be made, others approving the new Councils of the Faculties. There seems to be a general feeling against insisting on the professors examining their classes every term, and against making attendance at their lectures compulsory. The Councils of Faculties are regarded by many with favour as a means of bringing the tutors and lecturers of the various colleges who are engaged in teaching the same branch of learning into closer relationship, and enabling them better to divide the work among them.

At Balliol College an extra scholarship on the Brakenbury Foundation has been awarded to Mr. A. D. Hall of Manchester Grammar School, for Natural Science.

A MEETING of the Convocation of Victoria University was held at Owens College, Manchester, on Friday, Dr. Greenwood presiding. A resolution was received from the Associates of the College expressing their gratification at the creation of the University, and pledging themselves to perform their part in maintaining the welfare, dignity, and fame of the University, and promoting its objects. Standing orders for the regulation of the proceedings of Convocation were adopted, and the Rev. C. J. Poynting was appointed clerk.

THE recently-presented budget of Prussia shows that, despite the financial straits of the kingdom, no considerations of economy are allowed to hamper the growth of its scientific and educational system. First on the list come the nine universities with an allotment of 7,050,000 marks (352,500*l.*). Berlin receives the lion's share, 1,378,348 marks, an increase of about 37,000 marks on its last annual subvention. Bonn and Königsberg each have 740,000 marks, Breslau 600,000, Kiel 404,000, Marburg and Halle each 430,000, Göttingen 201,000, and Greifswald 136,000. Of the above-mentioned sum about 1,306,000 marks are appropriated for extraordinary expenses in connection with the construction of university buildings, and of this amount Berlin absorbs over one-half, viz., 766,000 marks. The other chief items in the Budget of Public Instruction are: Gymnasia and Realschulen, 5,000,000 marks; primary schools, 14,500,000; orphanages, schools for the blind, deaf and dumb, &c., 300,000; technical schools, and for the general furtherance of science and art, 3,000,000 marks.

THE number of pupils of Lycées and Colleges in the French Republic is 87,000 (46,500 for Lycées and 40,500 for Colleges). Last year it was only 84,700. These establishments may be considered as analogous to the English grammar-schools.

SCIENTIFIC SERIALS

Journal of the Franklin Institute, November.—The metric system: is it wise to introduce it into our machine-shops? by C. Sellers.—The weakening of steam boilers by cutting holes in the shell for domes and necks, by W. B. Le Van.—Observations in Brazil, by W. M. Roberts.

Rivista Scientifico-Industriale, October 31.—*Résumé* of solar observations at Palermo Observatory in the third quarter of 1880, by Prof. Ricco.—Experimental researches on the action of light on transpiration of plants, by Dr. Comes.—Dynamometric break with circulation of water, by Prof. Ricco.

Journal de Physique, November.—On the combination of phosphuretted hydrogen with hydrochloric acid, by M. Ogier.—An amplifying barometer, by M. Debrun.

SOCIETIES AND ACADEMIES

LONDON

Linnean Society, November 18.—Robt. McLachlan, F.R.S., in the chair.—Dr. Geo. E. Dobson exhibited a remarkable parasitic worm from the intestine of *Megaderma frons*, from the Gold Coast. It appears allied to *Pterygodermatites plagiostoma*, Wedl, from the Long-eared Hedgehog, though on first hasty examination he (Dr. Dobson) had been disposed to regard it as a new genus, *Metabdella*. Dr. McDonald further drew attention to its peculiar anatomical structure and relationships. Dr. Cobbold agreed to the importance of the observations as verifying previous discoveries, with addition of novel structural details. He considered the worm as identical with the *Ophiostomum* of Rudolphi and Willemoes Suhm, with *Pterygodermatitis* of Wedl, and with *Rictularia* of Froelich, and he regarded it as an aberrant member of the Ophiostomidæ, whereas Wedl thought it came nearest the Cheiracanthidea.—Dr. Cobbold also exhibited specimens of *Distoma crassum*, Busk (previously in 1875 shown to the Society), from a Chinese missionary who, on return to China with his wife and daughter, were again all attacked by the parasite, and obliged to return to England.—A paper was read on a proliferous condition of *Verbascum nigrum*, by the Rev. G. Henslow. The upper part was very diffuse with leafy axes produced from the centres of the flowers, while the lower part had flowers with very large ovaries adherent within to arrested proliferous branches. These differences may be attributed to the general tendency of

the sap to run to the extremities and thus cause an excess of development above with simultaneous arrested condition below.—A paper on the classification of the Gasteropoda (part 2) was read by Dr. J. Dennis McDonald. In this communication the author gives further data in support of his mode of arranging the group dependent on anatomical characters.—"Novitates Capenses" was the title of a paper by Messrs. P. MacOwan and H. Bolus, in which, among other novelties described of South African plants, were *Ranunculus Baurii*, *Ericinella passerimoides*, *Orthosiphon ambiguens*, and *Herpolirion capensis*, the last a representative of a form hitherto known only from Australia.—A communication from the Rev. M. J. Berkeley, on Australian fungi (part 2), principally received from Baron F. von Müller, was taken as read.—Lieut.-Col. H. Godwin-Austin was elected a Fellow of the Society.

Entomological Society, November 3.—Sir Jno. Lubbock, Bart., vice-president, in the chair.—Mr. E. Meyrick of Hungerford, Wilts, and Capt. Thos. Broun of Auckland, New Zealand, were elected as Ordinary Members, and Dr. J. E. Brandt, president of the Russian Entomological Society, was elected as a Foreign Member of the Society.—Mr. Waterhouse exhibited, on behalf of Mr. Sydney Olliffe, a pair of dwarfed specimens of *Epione vespertaria*, taken at Arundel.—Mr. McLachlan exhibited some curious galls on a broad-leaved *Eucalyptus* from Australia, which were stated to be made by a lepidopterous larva, and also mentioned that in a letter he had received from Mr. Rutherford, dated from Camaroons, West Africa, the writer stated that he had taken *Papilio merope* and *Papilio cenea* in copula. Mr. Trimen doubted that the butterfly referred to by Mr. Rutherford was *P. cenea*, Stoll, which, to the best of his knowledge, was a form of the female confined to South Africa, and was more probably either *Hippocoon*, Fab., or one of the other prevalent West African forms.—Prof. Westwood exhibited a globular gall on the surface of a sallow leaf made by a species of *Tenthredinidæ*, and also a dipterous larva (Syrphus) found closely adhering to the stem of a pelargonium.—Mr. Kirby exhibited a remarkable variety of *Epunda lutulenta*, and also a remarkable form of *Apatura*, stated to have been taken by Mr. Ralfe in Pinner Wood.—Sir Jno. Lubbock exhibited some interesting larvæ which Mr. Culvert had forwarded to him from the Troad through Sir Joseph Hooker. He stated that these larvæ had recently appeared there in great numbers, and were likely to prove most useful, as they fed on the eggs of locusts. These larvæ were probably coleopterous, and Sir Jno. Lubbock suggested that if the species does not exist in Cyprus it might be worth while to introduce it there.—Mr. Trimen exhibited a wingless female specimen of the Hymenoptera, which he had strong grounds for believing was the female of the well-known *Dorylus helvolus*, Linn.—Mr. Trimen also exhibited six cases fabricated by a South African lepidopterous larva, of which the outer covering consisted of particles of sand and fragments of stone, which gave them a most peculiar aspect, resembling in general appearance a myriapod.—Sir Sydney Saunders read a paper on the habits and affinities of the hymenopterous genus *Scleroderma*, with descriptions of new species.—Mr. Edward Saunders read a paper entitled a synopsis of British *Heterogyna* and fossorial *Hymenoptera*.—Prof. Westwood read a paper containing descriptions of new species of exotic diptera, with a supplement containing descriptions of species formerly described by the author in somewhat inaccessible publications.

PARIS

Academy of Sciences, November 15.—M. Edm. Becquerel in the chair.—Researches in isomerism, benzine, and dipropargyl, by MM. Berthelot and Ogier.—On papaïne; new contribution to the study of soluble ferments, by M. Wurtz. In one experiment 0·05 gr. of papaïne fluidified about two thousand times its weight of moist fibrine. It seems that it begins by fixing on the fibrine, and the insoluble product gives, by action of water, soluble products of hydratation of fibrine, while the ferment, becoming free again, may act on a new portion of fibrine. The action is thus related to that of chemical agents, *e.g.* sulphuric acid.—Enrichment of plumbic earths by a current of compressed air, by M. Delesse. The apparatus, called *trieur à soufflet*, effects a sorting of pulverulent matters, which cannot be separated by water. Earths of very fine grain cannot well be treated with it, and unfortunately it is they that contain most lead. The lead-dust produced is unhealthy for the workmen.—Observations of M. de Quatrefages on the Marquis de Nadaillac's work, "Les premiers Hommes et les Temps préhistoriques." M. de Quatrefages thinks that man probably existed in Portugal in the Tertiary epoch.—Observations on the publication of Dr. Guérin's works, by M. de Quatrefages.—On the arrangement of the cervical vertebræ in the Chelonians, by M. Vaillant.—Experimental researches on the heat of man during movement, by M. Bonnal. *Inter alia*, all muscular exercise raises the rectal temperature. The increase is not directly related either to duration of the exercise or to apparent fatigue. The altitude, state of the atmosphere, energy of movements, and nature of clothing affect the increase. All rapid exercise diminishes the peripheral temperature (in mouth, armpit, or groin). The rectal heat may reach 39·5°. In rapid climbing it is in the first half hour that the rectal temperature is most raised, it may then become stationary or fall. In general, a rigorous application of the laws of mechanics to the human system is not warranted.—Studies on the habits of phylloxera during August to November 1880, by M. Fabre. The young insects showed (in the author's experiments) a strong liking for light. The present year seems very unfavourable to the parasite.—On some linear differential equations, by M. Brioschi.—On the equilibrium of flexible and inextensible surfaces, by M. Lecornu.—On the compressibility of oxygen and the action of this gas on mercury when put in contact with it, by M. Amagat. Oxygen and mercury (pure and dry) he found to remain indefinitely long in contact without absorption. He operated at 50° and 100°, and with pressures from 110 to 420 atm. The compressibility of oxygen follows the laws he gave in his memoir of August 30. MM. Chevreul and Dumas made remarks on the subject.—On the liquefaction of ozone in presence of carbonic acid, and on its colour in the liquid state, by MM. Hautefeuille and Chappuis. Gradual compression of a mixture of ozonised oxygen and carbonic acid at − 23° gives a blue liquid of the same shade as the gas above. The products of decomposition of carbonic acid by the effluve are proved (by the blue colour on compressing) to contain a large proportion of ozone.—On malleable iron, by M. Forquignon. It seems to be intermediate between steel and grey pig-iron, differing from the latter by the special nature of its amorphous graphite and its greater tenacity; from steel, by its small elongations and its large proportion of graphite.—On the presence of phosphorus in the rocks of Brittany, by M. Lechartier.—On the composition of petroleums of the Caucasus, by MM. Schützenberger and Ionine.—On the temperatures of inflammation of gaseous mixtures, by MM. Mallard and Le Chatelier. Among other results, mixtures of protocarburetted hydrogen not only enter into slow combustion, but, when submitted to a certain temperature, may be inflamed after a variable time (which is longer the lower the temperature).—On the secondary wave of muscle, by M. Richet. A second contraction occurs, without fresh stimulation.—On the contagion of boils, by M. Trastour.—On the use of boring machines without use of explosive matter, by M. Biver. The advantages of Mr. Brunton's system are indicated.

CONTENTS

	Page
Political Economy	97
Our Book Shelf:—	
Sharp's "Avis préliminaire d'une nouvelle Classification de la Famille des Dytiscidæ"	98
"Aid to the Identification of Insects"	98
Letters to the Editor:—	
Geological Climates.—Prof. Saml. Haughton, F.R.S.	98
"Sulphuric Acid and Alkali."—Prof. H. E. Roscoe, F.R.S.	99
A General Theorem in Kinematics.—Prof. J. D. Everett, F.R.S.	99
Phosphorescent Centipedes.—B. E. Brodhurst	99
The Yang-tse, the Yellow River, and the Pei-ho.—Surgeon H. B. Guppy	99
Aurora observed at Ovoca, Co. Wicklow, November 3—Observations from 5.30 p.m. to Midnight.—G. H. Kinahan	100
Mr. Spencer and Prof. Tait. By Herbert Spencer	100
Notes on the Geology of East-Central Africa. By Joseph Thomson (*With Diagrams*)	102
Incandescent Electric Lights	104
Subterranean Forest in India (*With Diagrams*)	105
Notes	106
Abnormal Variations of Barometric Pressure in the Tropics, and their Relation to Sun-Spots, Rainfall, and Famines. By Fred. Chambers	107
The Royal Society—Address of the President. By William Spottiswoode, D.C.L., LL.D.	111
Our Astronomical Column:—	
Lunar Eclipses, 1880-84	114
A Probable Variable Star	115
Faye's Comet	115
Swift's Comet	115
University and Educational Intelligence	115
Scientific Serials	115
Societies and Academies	115

SUBSCRIPTIONS TO NATURE

Yearly . . . . . 28*s.*
Half-yearly . . . . . 14*s.* 6*d.*
Quarterly . . . . . 7*s.* 6*d.*

To the Colonies, United States, the Continent, and all places within the Postal Union :—

Yearly . . . . . 30*s.* 6*d.*
Half-yearly . . . . . 15*s.* 6*d.*
Quarterly . . . . . 8*s.*

Office: 29, Bedford Street, Strand.

DIARY OF SOCIETIES.

LONDON

THURSDAY, DECEMBER 2.

LINNEAN SOCIETY, at 8.—On an *Erythræa* new to England: Frederick Townsend.—The Conifers of Japan: Dr. Maxwell Masters.

CHEMICAL SOCIETY, at 8.—Communication from the Laboratory of the University College, Bristol: W. Ramsey.—On the Specific Volume of Chloral: Laura Mauda Passavant.—On the Formation of Carbon Tetrabromide in the Manufacture of Bromine: J. W. Hamilton.—Ballot for the Election of Fellows.

FRIDAY, DECEMBER 3.

GEOLOGISTS' ASSOCIATION, at 8.—Pre-Cambrian Rocks in British Isles: Dr. H. Hicks.

MONDAY, DECEMBER 6.

ROYAL INSTITUTION, at 5.—General Monthly Meeting.

SOCIETY OF ARTS, at 8.—Pottery and Porcelain: Prof. A. H. Church.

ARISTOTELIAN SOCIETY, at 8.—Hobbes: E. Clarkson.

VICTORIA INSTITUTE, at 8.—The Modern Science of Religion: Rev. G. Blencorne.

LONDON INSTITUTION, at 5.—Morality and Literature: Leslie Stephen.

WEDNESDAY, DECEMBER 8.

TELEGRAPH ENGINEERS, at 8 —Annual Meeting.

ROYAL MICROSCOPICAL SOCIETY, at 8.—*Floscularia trifolium*, n.sp.: Dr. Hudson.—Some Structural Features of Echinometridæ: C. Stewart.—Notes on the Movements of Diatoms, the Construction of Object-Glasses, Swinging Sub-stages, &c.

SOCIETY OF ARTS, at 8.—London Fogs: Dr. A. Carpenter.

THURSDAY, DECEMBER 9.

ROYAL SOCIETY, at 4.30.

MATHEMATICAL SOCIETY, at 8.—Note sur Dérivation des Déterminants: Prof. Taixeira (Coimbra, Portugal).—On the Solution of the Inverse Logical Problem: W. B. Grove.—Motion of a Viscous Fluid: T. Craig, U.S. Coast Survey.

LONDON INSTITUTION, at 7.—Germination and Propagation of Disease: Dr. L. S. Beale.

FRIDAY, DECEMBER 10.

ROYAL ASTRONOMICAL SOCIETY, at 8.

QUEKETT MICROSCOPICAL CLUB, at 8.

SATURDAY, DECEMBER 11.

PHYSICAL SOCIETY, at 3.—On the Rate of loss of Light from Phosphorescent Surfaces: Lieut. L. Darwin, R.E.—On the Determination of Chemical Affinity in terms of Electromotive Force: Dr. Alder Wright.

NOW READY,
SECOND EDITION,
GRIFFIN'S
CHEMICAL HANDICRAFT.
PRICE 4*s.* 7*d.* POST FREE.
A CATALOGUE OF CHEMICAL APPARATUS:
ILLUSTRATED, CLASSIFIED, DESCRIPTIVE.
Demy 8vo, 480 pp., Illustrated with 1,600 Woodcuts.
Most Complete and Cheapest List of Apparatus.
JOHN J. GRIFFIN AND SONS, 22, GARRICK STREET, LONDON, W.C.

ASTRONOMICAL TELESCOPE.
BATEMAN'S
WONDERFUL £5 5*s.* INSTRUMENT
Is the finest ever yet attempted. 3-inch Achromatic Object Lenses. Entirely constructed of polished brass; total length, 4 feet 10 inches; very highly finished with Altitude and Azimuth Movements, Rackwork, fine Adjustment, one Terrestrial and one Huyghenian Astronomical Eyepiece; will show Jupiter's Belts, Crescent Form of Venus, resolve many Nebulæ and Clusters, and divide many Double Stars, &c., &c. Prospectus post free.
J. BATEMAN,
29, CHEAPSIDE; 104, STRAND; ROYAL POLYTECHNIC, 309, REGENT STREET, AND 131, HIGH HOLBORN, LONDON.

BRYCE-WRIGHT'S LATEST ARRIVALS.
MINERALS. — Crystallised Hessite, Crystallised Golds, Krennerite, Crystallised Atacamites, Malacone, Euclase, Edingtonite, Suzannite, Chanarcillite, Proustite, &c.
METEORITES.—Specimens of the following Falls:—Wold Cottage, Yorkshire; Java; Orvinio, Italy; Amana, Ohio; Tipperary, Ireland; Java; Orvinio, Italy; Estherville; Hainholz; Grosnagy, Russia; Borkut; Carthago Co.; Bates Co.; Sierra di Chaco; Ashville Co.; Bates Co.; Pallas; Ashville Co., &c., &c.
BRYCE-WRIGHT, F.R.G.S., &c.,
Mineralogist and Expert in Gems and Precious Stones,
90, GREAT RUSSELL STREET, BLOOMSBURY, LONDON, W.C.

NEW SMOKELESS FIRE
IN AN OPEN GRATE
ON DR. SIEMENS'S PRINCIPLE
MAY BE SEEN IN ACTION, AND PRICES AND PARTICULARS HAD, ON APPLICATION TO
FRANCIS HAMMOND
5, Chandos Street, Charing Cross,
LONDON, W.C.

Liberal Terms to Science Teachers and the Trade.
THOMAS CRAMPTON & CO.,
ELECTRICIANS, OPTICIANS,
AND
PHILOSOPHICAL INSTRUMENT MAKERS:
Electric Bells, new metallic base pattern; Constant Batteries, Indicators for use with Electric Bells, Thief and Fire Alarms, and Automatic Switches. Induction and Medical Coils, or Specialities. Hughes' Sonometers and Microphones of every form. Batteries, Magnets, and Insulated Wires of every description. Microscopic and Optical Materials. Telescopes, Opera Glasses, Microscopes, Aneroid Barometers, Electric Machines and Lime-light Apparatus.
Illustrated Catalogue, Two Stamps.
THOMAS CRAMPTON & CO., 251, HIGH HOLBORN, LONDON, W.C.
Catalogue of Lowest Trade Prices on application.

£5 5s. ASTRONOMICAL TELESCOPE.
CRAMPTON & CO.'S IMPROVED TELESCOPE is of the highest workmanship and finish, combined with great power and clearness of definition. 3-inch Achromatic Object Lens, entirely constructed of polished brass, with Altitude and Azimuth Movements, Rackwork and Fine Adjustment, &c., &c.
THOMAS CRAMPTON & CO., 251, HIGH HOLBORN, LONDON, W.C.

NOTICE OF REMOVAL.
JAMES HOW & CO.,
SCIENTIFIC INSTRUMENT MAKERS,
73, FARRINGDON ST., LONDON
(LATE OF 5, ST. BRIDE ST., AND 2, FOSTER LANE).
HOW'S STUDENT'S MICROSCOPE. HOW'S MICROSCOPE LAMP.
Rock Sections and other Objects for the Microscope.

R. W. NEEVES,
PHILOSOPHICAL INSTRUMENT
AND
INTENSITY COIL MAKER.
PRICE LIST, FOUR STAMPS.
55, SIDMOUTH STREET, LONDON, W.C.

W. LADD & CO.,

SCIENTIFIC INSTRUMENT MANUFACTURERS,

(By Appointment to the Royal Institution of Great Britain),

11 AND 12, BEAK STREET, REGENT STREET, W.

IMPROVED HOLTZ ELECTRICAL MACHINES. GRAMME'S MAGNETO-ELECTRIC MACHINE for Laboratory use.

PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3s. per oz.

Physical Apparatus of every Description.

ILLUSTRATED CATALOGUE, SIXPENCE.

PATERSON'S NEW CATALOGUE OF PHYSICAL APPARATUS.

LANTERN SLIDES for SCIENTIFIC LECTURES. Season 1880–1. Post free 6 Stamps.
Complete Sets of Physical Apparatus for Science Primers and all the Physical Text-books in use in Schools and Colleges.
Siemens and Gramme Dynamo Machines and Lamps for hire.
Schools supplied with Apparatus as per Science and Art Departments' Requirements in the Sections of Light, Heat, Sound, and Electricity.
Electric Signals for Houses, Hotels, &c., Colliery Signals, Lightning Conductors. The Gower-Bell Loud-speaking Telephone.

EDWARD PATERSON, Electrical Engineer.

SHOW ROOMS AND STEAM WORKS:—76, LITTLE BRITAIN, E.C. (late 3, Bedford Court, W.C.).

MOLISON'S HARMONOGRAPH; executes the Harmonic Curves in the most perfect manner. 15s. and 20s.

Illustrated Catalogue of Electrical Apparatus, Part 1, post free, 6 Stamps. Ditto, Electric Signals, Part 2, 6 Stamps.

Now ready, post quarto, cloth gilt, 272 pages. Price 16s.

LIGHTNING CONDUCTORS:

THEIR

HISTORY, NATURE, AND MODE OF APPLICATION.

By RICHARD ANDERSON, F.C.S., F.G.S.,
Member of the Society of Telegraph Engineers; Assoc. Inst. C.E.

With numerous Illustrations.

"The book is one to be commended to the builders of, or dwellers in, lofty houses, to the deans of our cathedrals, to the parsons of churches with lofty spires or towers, and to all owners, constructors, or occupiers of buildings which, from their height or situation, are exposed to danger from lightning."—*The Athenæum.*

"The book is clearly and sensibly written, and sufficiently illustrated, and is the work of a practical man who thoroughly understands what he is talking about."—*The Academy.*

London: E. & F. N. SPON, 46, Charing Cross.
New York: 446, Broome Street. 1880.

THE NEW BIOLOGICAL JOURNAL.

ARCHIVES DE BIOLOGIE.

Edited by Professors EDOUARD VAN BENEDEN of Liège, and VAN BAMBEKE of Ghent.

This Journal is devoted to the publication of original Memoirs on the Embryology, Histology, Physiology, and Comparative Anatomy of Plants and Animals. Each number is illustrated with numerous Coloured Plates, and appears at the commencement of the Quarter.

Price:—A Single Number, Six Shillings and Sixpence. Annual Subscription: Twenty-five Shillings, or Twenty-seven Shillings post free.

Orders received by Messrs. WILLIAMS & NORGATE, 14, Henrietta Street, Covent Garden, London.

In the first two numbers have appeared:—

VAN BENEDEN: On the Embryology of the Mammalia.
VAN BAMBEKE: On the Cleavage of the Egg in Batrachia.
FOR HINGER: On the Termination of Nerves in the Muscles of Insects.
FREDERIQUE AND VANDEVELDE: On the Physiology of the Muscles and Nerves of the Lobster.
MACLEOD: On the Harderian Gland of the Duck, &c., &c.

S. C. TISLEY & Co.,

OPTICIANS,

172, BROMPTON ROAD, S.W.

(Close to South Kensington Museum).

THE PHONEIDOSCOPE

An Instrument for Observing the Colour-Figures of Liquid Films under the action of Sonorous Vibrations.

Being a visible demonstration of the Vibratory and Molecular Motion of a Telephone Plate.

The PHONEIDOSCOPE, with 3 Discs, Bottle of Solution, Descriptive Pamphlet, &c., in Cardboard Box, 10s. 6d.

MANUFACTURED AND SOLD WHOLESALE AND RETAIL BY

S. C. TISLEY & CO., 172, BROMPTON ROAD, LONDON, S.W.

TELEPHONIC ELECTRICITY. All Materials supplied for experimental purposes.

Price Lists of Electrical and Acoustic Apparatus, with Drawings and Description of the Harmonograph, Post Free, 2d.

EAGLE INSURANCE COMPANY,

79, PALL MALL.

FOR LIVES ONLY. ESTABLISHED 1807.

Accumulated Funds £3,043,542
Also a Subscribed Capital of more than £1,500,000

Reports, Prospectuses, and Forms may be had at the Office, or from any of the Company's Agents, post free.

GEORGE HUMPHREYS, Actuary and Secretary.

J. ORME & CO.,

(Late M. JACKSON & CO.)

MANUFACTURERS AND IMPORTERS OF

SCIENTIFIC APPARATUS AND CHEMICALS.

SOLE AGENTS FOR HICKLEY'S PATENT TELEPHONES,

Price 50s. per Pair, Cash with Order.

Price Lists sent on receipt of Three Stamps for Postage.

For Trade Terms inclose Business Card.

65, BARBICAN, LONDON, E.C.

New Edition, very much enlarged. 21s.

HOW TO WORK WITH THE MICROSCOPE.

By LIONEL S. BEALE, F.R.S.,
President of the Royal Microscopical Society.

THE FIFTH EDITION,

Strongly bound and enlarged to 530 Pages, with 100 Plates, some of which are Coloured, is now ready.

HARRISON & SONS, Pall Mall.

DRAPER'S INK (DICHROIC).

THE NEW BLACK INK

DIFFERING FROM ANYTHING ELSE EVER PRODUCED.

Writing becomes a pleasure when this Ink is used. It has been adopted by the principal Banks, Public Offices, and Railway Companies throughout Ireland.

It writes almost instantly Full Black. | Flows easily from the Pen.
Does not corrode Steel Pens. | Blotting-paper may be applied at the moment of writing.
Is cleanly to use, and not liable to Blot.

Can be obtained in London, through Messrs. BARCLAY & SONS, Farringdon Street; W. EDWARDS, Old Change; F. NEWBERY & SONS, Newgate Street; WM. MATHER, London and Manchester; J. AUSTIN & Co., Duke Street, Liverpool; and STACY & COOK, Paternoster Row; and to be had of all Stationers.

BEWLEY & DRAPER (Limited), Dublin.

HOLLOWAYS OINTMENT

A CERTAIN REMEDY

For BAD BREASTS, OLD WOUNDS, and SORES. If effectually rubbed on the Neck and Chest, it cures SORE THROATS, BRONCHITIS, COUGHS and COLDS; and for GOUT, RHEUMATISM, and all Skin Diseases it is unequalled.

Messrs. MACMILLAN & CO.'S PUBLICATIONS.

ETCHING AND ETCHERS. By P. G. HAMERTON. New Edition, Revised, with 48 New Plates. Columbier 8vo.

The text of the new Edition has been thoroughly revised, and increased by one-fifth. Several new Chapters and a new Preface have been added, whilst matter which had become unnecessary or disproportionate has been removed, to make room for studies of more importance. [*Immediately.*

The Edition is limited to 1000 copies, all of which have been subscribed for; particulars as to price, &c., may be obtained from any bookseller.

LIFE OF WILLIAM BLAKE. With Selections from his Poems and other Writings. By ALEXANDER GILCHRIST. A New and Enlarged Edition, Illustrated from BLAKE's own Works, with Additional Letters and a Memoir of the Author. Printed on hand-made paper, the Illustrations on India paper, and mounted in the text. 2 vols., cloth gilt, elegant, with designs after BLAKE by FREDK. J. SHIELDS. Medium 8vo. £2 2*s.*

Several new Illustrations have been added to this work; among others the following may be named:—The Phillips Portrait of Blake; two new Portraits by Blake of his Wife; a new plate from the *Jerusalem*; a newly-discovered design to *Hamlet*; and a drawing of *Blake's Cottage at Felpham*. New Photogravures of the *Inventions to the Book of Job* are given. Some thirty additional letters are included in the Biographical portion of the work, forming a new link in the already interesting life of Blake. And Mr. W. M. Rossetti has revised, enlarged, and perfected the annotated catalogue of Blake's works that appeared in the first edition of the work.

[*Immediately.*

ISLAND LIFE; or, the Phenomena and Causes of Insular Faunas and Floras, including a revision and attempted solution of the Problem of Geological Climates. By ALFRED RUSSEL WALLACE, Author of "The Malay Archipelago," "The Geographical Distribution of Animals," &c. Medium 8vo, with Illustrations and Maps. 18*s.*

"The work throughout abounds with interest."—*Athenæum.*

"Whoever reads his book must be charmed with it."—*St. James's Gazette.*

"We have said enough to show that Mr. Wallace is led to discuss subjects of great interest to speculative minds."—*Pall Mall Gazette.*

A VISIT TO WAZAN, THE SACRED CITY of MOROCCO. By ROBERT SPENCE WATSON. 8vo, with Map and Illustrations. 10*s.* 6*d.*

"The result is one of the most delightful narratives we have had the good fortune to meet with for a very long time . . . . In conclusion it remains to be said that Mr. Watson writes in a vigorous, scholarly style, manly and unaffected, oftentimes picturesque, but never descending to mere word-painting."—*Examiner.*

A DICTIONARY OF MUSIC AND MUSICIANS (A.D. 1450—1878). By Eminent Artists, English and Foreign. With Illustrations and Woodcuts. Edited by GEORGE GROVE, D.C.L. In three Volumes. Vols. I. and II., cloth. 21*s.* each.

Vol. I. A to Impromptu. Vol. II. Improperia to Plain Song.

IDEAL CHEMISTRY. By Sir BENJAMIN BRODIE, Bart., F.R.S. Crown 8vo. 2*s.*

FOOD FOR THE INVALID, THE CONVALESCENT, THE DYSPEPTIC, AND THE GOUTY. By J. MILNER FOTHERGILL, M.D., Author of "The Practitioner's Handbook," &c. Crown 8vo. 3*s.* 6*d.*

STUDIES IN DEDUCTIVE LOGIC. By W. STANLEY JEVONS, LL.D., F.R.S., Professor of Political Economy in University College, London. Crown 8vo. 6*s.*

"Besides these answers to questions which greatly increase the value of the book, and make it almost an independent manual of the subject, Professor Jevons has taken occasion to supplement his previous works in various directions. It is indispensable to the many students of the higher logic."—*Athenæum.*

GUIDE TO THE STUDY OF POLITICAL ECONOMY. By Dr. LUIGI COSSA, Professor of Political Economy in the University of Pavia. Translated from the Second Italian Edition. With a Preface by W. STANLEY JEVONS, F.R.S. Crown 8vo. 4*s.* 6*d.*

THE ARYAN VILLAGE IN INDIA AND CEYLON By SIR JOHN B. PHEAR. Crown 8vo, 7*s.* 6*d.*

THE IRISH LAND LAWS. By ALEXANDER G. RICHEY, Q.C., LL.D., Deputy Regius Professor of Feudal and English Law in the University of Dublin. Crown 8vo. 3*s.* 6*d.*

With Twenty-five Illustrations by WALTER CRANE.

THE NECKLACE OF PRINCESS FIORIMONDE: and other Stories. By MARY DE MORGAN. Extra fcap. 8vo. 6*s.*

ALSO AN EDITION, Printed by Messrs. R. and R. Clark, on hand-made paper. The Plates, initial letters, head and tail pieces being printed on India paper and mounted in the text.

The Edition is limited to ONE HUNDRED COPIES. Fcap. 4to.

"The stories display considerable originality, and Mr. Crane's characteristic illustrations combine with Miss de Morgan's pretty fancies to form a charming gift-book."—*Graphic.*

ENGLISH MEN OF LETTERS. Edited by JOHN MORLEY. Crown 8vo. 2*s.* 6*d.* (New Volumes.)

WORDSWORTH. By F. W. H. MYERS.

LOCKE. By Professor FOWLER.

"In the case of Locke's biographer we venture to say that Mr. Morley has been exceptionally fortunate. A pen more competent than Professor Fowler's for this particular work might have been sought, and sought in vain."—*Examiner.*

A CHRISTMAS CHILD: a Sketch of a Boy-life. By MRS. MOLESWORTH, Author of "Carrots," "The Cuckoo Clock," &c. Illustrated by WALTER CRANE. Globe 8vo. 4*s.* 6*d.*

THE WHITE RAT, AND SOME OTHER STORIES. By LADY BARKER. Illustrated by W. J. HENNESSY. Globe 8vo. 4*s.* 6*d.*

PANSIE'S FLOUR BIN. By the Author of "When I was a Little Girl," &c. Illustrated by ADRIAN STOKES. Globe 8vo. 4*s.* 6*d.*

"Worthy to be classed with 'Alice in Wonderland,' and in some respects is better adapted to juvenile comprehension."—*Morning Post.*

HISTORY OF THE ENGLISH PEOPLE. By JOHN RICHARD GREEN. Vol IV. THE REVOLUTION, 1683—1760. MODERN ENGLAND, 1760—1815. 8vo, with 3 Maps and Index, 16*s.* (Vols. I. to III. 16*s.* each.) [*Concluding Volume.*

"A work that most students of history may turn to with advantage, and that will be almost sure to take rank among the great classics of our literature."—*Globe.*

READINGS FROM ENGLISH HISTORY. Selected and Edited by JOHN RICHARD GREEN, M.A., LL.D. In Three Parts, each 1*s.* 6*d.*

"We cannot imagine a better reading-book for the highest standard of our elementary schools, but it is a book which will have great charms also for the most cultivated readers."—*Guardian.*

FIRST LESSONS IN GREEK. Adapted to Goodwin's "Greek Grammar," and designed as an Introduction to the "Anabasis" of Xenophon. By JOHN WILLIAMS WHITE, Ph.D., Assistant Professor of Greek in Harvard University. Crown 8vo. 4*s.* 6*d.*

XENOPHON'S ANABASIS. Books I.—IV. Edited by Professors W. W. GOODWIN and J. W. WHITE, of Harvard University. Fcap. 8vo. 5*s.* [Macmillan's Classical Series.

LIVY.—SCENES FROM THE HANNIBALIAN WAR. Adapted for the use of Beginners by G. C. MACAULAY, M.A., Assistant-Master at Rugby. Post 8vo. 1*s.* 6*d.*

[Macmillan's Elementary Classics.

THE STORY OF ACHILLES, FROM HOMER'S ILIAD. Edited, with Notes and Introduction, by the late J. H. PRATT, M.A., Fellow of Trinity College, Cambridge, Assistant Master at Harrow; and WALTER LEAF, M.A., Fellow of Trinity College, Cambridge. Fcap. 8vo. 6*s.* [Macmillan's Classical Series.

MACMILLAN'S PROGRESSIVE FRENCH COURSE. By EUGÈNE-FASNACHT, Author of "Progressive German Course," &c. Third year, containing:—Systematic Syntax and Lessons in Composition. Fcap. 8vo. 2*s.* 6*d.*

MACMILLAN AND CO., LONDON.

Selections from New & Standard Works published by CASSELL, PETTER, GALPIN, & CO.,

SUITABLE FOR CHRISTMAS AND NEW YEAR'S GIFTS, &c.

PICTURESQUE EUROPE. Complete in Five Volumes, with nearly 1000 Original Illustrations. Cloth gilt, £2 2s. each; morocco, £5 5s. each.

"Nothing on so grand a scale has been planned before, nor anything, so far as we know, so well executed."—*Spectator.*

THE MAGAZINE OF ART. Vol. III., with upwards of 300 Illustrations. Cloth, gilt edges, 10s. 6d.

THE TIMES of Nov. 30th, 1880, says—

"Messrs. Cassell, Petter, Galpin & Co. publish the third volume of their 'Magazine of Art.' The title is no misnomer, for the book, within a convenient compass, contains a very storehouse of art. The illustrations are, of course, numerous, ranging from the freest of etchings and woodcuts up to the most elaborate engravings, the frontispiece containing a particularly good etching after Bonnat. The letterpress is particularly good and varied, being designed to suit all tastes, from the most to the least artistic."

N.B.—The price of Vols. I. and II. of the MAGAZINE OF ART, *each containing about* 200 ILLUSTRATIONS, *has been raised from* 7s. 6d. *to* 10s. 6d. *each.*

OUR OWN COUNTRY. Vols. I. and II., with upwards of 200 Original Illustrations, and Steel Frontispiece in each. 7s. 6d. each.

"The beautiful work which Messrs. Cassell & Co. are publishing under the above title appeals to a very wide circle of readers. The treatment is full and comprehensive, embracing architecture, scenery, history and antiquities, industry and art, physical geography, and natural history. The work is creditable to author, draughtsman, and engraver."—*The Times.*

THE INTERNATIONAL PORTRAIT GALLERY. Vol. II. With 20 Portraits in Colours, and Biographies from Authentic Sources. Demy 4to, 12s. 6d.

FAMILIAR GARDEN FLOWERS. First Series. By SHIRLEY HIBBERD. With 40 Coloured Plates by F. E. HULME, F.L.S., F.S.A. 12s. 6d.

FAMILIAR WILD FLOWERS. Second Series. By F. E. HULME, F.L.S., F.S.A. Containing 40 full-page Coloured Plates. 12s. 6d.

MOROCCO: ITS PEOPLE AND PLACES. With Original Illustrations. 4to, cloth, 21s.

PLEASANT SPOTS AROUND OXFORD. By ALFRED RIMMER. With 72 Original Woodcuts. Extra fcap. 4to, cloth gilt, 21s.

CHARACTER SKETCHES FROM DICKENS. Consisting of Six *Fac-simile* reproductions, in large folio size, of Drawings by FRED. BARNARD. 21s.

SCIENCE FOR ALL. Yearly Volume for 1880. With about 350 Illustrations and Diagrams. 9s.

"Whatever branch of science a man may happen to be studying, he is sure to find something to his taste in turning over the pages of this work. After looking through the work we are disposed to think that, on the whole, each volume is an advance upon its predecessors, both in the character of the articles and in the excellence of the illustrations."—*The Athenæum.*

THE COUNTRIES OF THE WORLD. By ROBERT BROWN, F.R.G.S. Five Vols. Illustrated, 7s. 6d. each.

NEW NATURAL HISTORY. Edited by Prof. P. MARTIN DUNCAN, M.B., F.R.S. Four Vols. Illustrated throughout. 9s. each.

SEVENTEENTH THOUSAND.

THE LIFE AND WORK OF ST. PAUL. By the Rev. CANON FARRAR, D.D., F.R.S. Two Vols. cloth, 24s.; morocco, £2 2s.

TWENTY-EIGHTH EDITION.

CANON FARRAR'S LIFE OF CHRIST. Illustrated Edition. Cloth, 21s.; morocco, £2 2s. Library Edition, Two Vols., 8vo, cloth, 24s.; morocco, £2 2s.

A HISTORY OF MODERN EUROPE. By C. A. FYFFE, M.A., Fellow of University College, Oxford. Vol. I. From the Outbreak of the Revolutionary War in 1792 to the Accession of Louis XVIII. in 1814. Price 12s.

YOUNG IRELAND. By the Hon. Sir CHARLES GAVAN DUFFY, K.C.M.G. Second Edition. Price 21s.

THE LEOPOLD SHAKSPERE. With about 400 Illustrations. 10s. 6d.

ENGLISH LITERATURE, DICTIONARY OF. By W. DAVENPORT ADAMS. Cheap Edition. 10s. 6d.

PHRASE AND FABLE, DICTIONARY OF. By the Rev. Dr. BREWER. Cheap Edition. 3s. 6d.

LIFE OF RIGHT HON. W. E. GLADSTONE. By G. BARNETT SMITH. With Two Portraits on Steel. Seventh and Cheap Edition. 5s.

ESCOTT'S ENGLAND: ITS PEOPLE, POLITY, AND PURSUITS. By T. H. S. ESCOTT. Second Edition. Two Vols. 24s.

MEMORIES OF MY EXILE. By LOUIS KOSSUTH. 10s. 6d.

RUSSIA. By D. MACKENZIE WALLACE, M.A. Eighth and Cheap Edition. 10s. 6d.

HEROES OF BRITAIN IN PEACE AND WAR. By EDWIN HODDER. With about 300 Original Illustrations. Two Vols. 7s. 6d. each.

THE SEA: ITS STIRRING STORY OF ADVENTURE, PERIL, AND HEROISM. By F. WHYMPER. Four Vols. With 400 Original Illustrations. 7s. 6d. each.

WHAT GIRLS CAN DO. A Book for Mothers and Daughters. By PHILLIS BROWNE, Author of "A Year's Cookery," &c. 5s.

A YEAR'S COOKERY. Giving Dishes for Breakfast, Luncheon, and Dinner for every Day in the Year, with Practical Instructions for their Preparation. By PHILLIS BROWNE. Seventh Thousand. 5s.

THE FAMILY PHYSICIAN. A Modern Manual of Domestic Medicine. By PHYSICIANS and SURGEONS of the Principal London Hospitals. 21s.

HOUSEHOLD GUIDE, CASSELL'S. Revised Edition. Four Vols. 6s. each.

JANE AUSTEN AND HER WORKS. By SARAH TYTLER. 5s.

BETTER THAN GOOD. A Story for Girls. By ANNIE E. RIDLEY. With Illustrations. 5s.

FOR CHILDREN AND YOUNG PEOPLE.

TIM TRUMBLE'S "LITTLE MOTHER." By C. L. MATÉAUX. With Eighteen Illustrations by GIACOMELLI. Fcap. 4to. 5s.

FAMILIAR FRIENDS. By OLIVE PATCH. Illustrated throughout. Crown 4to, cloth gilt. 5s.

THE FAVOURITE ALBUM OF FUN AND FANCY. Illustrated by ERNEST GRISET. 3s. 6d.

☞ **CHRISTMAS AND NEW YEAR'S GIFTS, PRIZES, REWARDS, &c.**

COMPLETE CATALOGUES *of* **Cassell, Petter, Galpin & Co.'s Publications,** *containing a List of* **Several Hundred VOLUMES, consisting of Bibles and Religious Works, Fine Art Volumes, Children's Books, Dictionaries, Educational Works, History, Natural History, Household and Domestic Treatises, Handbooks and Guides, Science, Travels, &c. &c., together with a Synopsis of their numerous Illustrated Serial Publications, sent post free on application to CASSELL, PETTER, GALPIN & CO., Ludgate Hill, London.**

Printed by R. CLAY, SONS, AND TAYLOR, at 7 and 8, Bread Street Hill, Queen Victoria Street, in the City of London, and published by MACMILLAN AND CO., at the Office, 29 and 30, Bedford Street, Covent Garden.—THURSDAY, December 2, 1880.

NATURE

A WEEKLY ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
Of Nature trusts the mind which builds for aye."—WORDSWORTH

No. 580, VOL. 23] THURSDAY, DECEMBER 9, 1880 [PRICE SIXPENCE

Registered as a Newspaper at the General Post Office.]

[All Rights are Reserved.

UNVERSITY OF LONDON.

The following are the Dates at which the several EXAMINATIONS in the University of London for the year 1881 will commence :—

MATRICULATION.—Monday, January 10, and Monday, June 20.
BACHELOR OF ARTS.—First B.A., Monday July 18.
Second B.A., Monday, October 24.
MASTER OF ARTS.—Branch I., Monday, June 6; Branch II., Monday, June 13; Branch III., Monday, June 20.
DOCTOR OF LITERATURE.—First D.Lit., Monday, June 6.
Second D.Lit., Tuesday, December 6.
SCRIPTURAL EXAMINATIONS.—Tuesday, November 22.
BACHELOR OF SCIENCE.—First B.Sc., Monday, July 18.
Second B.Sc., Monday, October 17.
DOCTOR OF SCIENCE.—Within the first twenty-one days of June.
BACHELOR OF LAWS.—First LL.B. } Monday, January 3.
Second LL.B. }
DOCTOR OF LAWS.—Thursday, January 13.
BACHELOR OF MEDICINE.—Preliminary Scientific, Monday, July 18.
First M.B., Monday, July 25.
Second M.B., Monday, November 7.
BACHELOR OF SURGERY.—Tuesday, November 29.
MASTER IN SURGERY.—Monday, November 28.
DOCTOR OF MEDICINE.—Monday, November 28.
SUBJECTS RELATING TO PUBLIC HEALTH.—Monday, December 12.
BACHELOR OF MUSIC.—First B.Mus., Monday, December 12.
Second B.Mus., Monday, December 19.
DOCTOR OF MUSIC.—First D.Mus., Monday, December 12.

The Regulations relating to the above Examinations and Degrees may be obtained on application to "The Registrar of the University of London, Burlington Gardens, London, W."

ARTHUR MILMAN, M.A., Registrar.

December 4, 1880.

Microscopes and other Scientific Apparatus

C. BAKER,

244 & 245, HIGH HOLBORN,

Begs to call the attention of the Scientific to his Extensive Stock of Instruments at the lowest possible prices, *viz.* :—

ACHROMATIC MICROSCOPES: the Largest Assortment in London can be selected from, from £3 3*s*.
ASTRONOMICAL TELESCOPES from £5 5*s*.
FIELD GLASSES in Leather Sling Cases, from 20*s*.
OPERA GLASSES in Ivory, Leather, Metal, &c., from 12*s*. 6*d*.
GOLD SPECTACLES of every kind from 15*s*.
THE BEST LONDON-MADE PEBBLES IN STEEL FRAMES, 10*s*. 6*d*.
PLAIN STEEL DITTO, from 3*s*. 6*d*.
FOLDING HAND SPECTACLES IN TORTOISESHELL, STEEL, &c., from 3*s*. 6*d*.
DISSOLVING VIEW APPARATUS, complete from £6 10*s*.
MAGIC LANTERNS, from 6*s*. 6*d*.; Slides, all kinds, from 1*s*. 3*d*.

CATALOGUES FREE BY POST.

Second Hand Scientific Instruments.

C. BAKER'S new Catalogue of Scientific Instruments is now out; Selections can be made from a very large stock, comprising MICROSCOPES, ASTRONOMICAL TELESCOPES, TRANSIT INSTRUMENTS, REGULATORS, SPECTROSCOPES, METEOROLOGICAL and ELECTRICAL APPARATUS, DISSOLVING VIEWS, &c. All at the very lowest prices.

Catalogues of same Free by Post. *Instruments taken in exchange.*
ESTABLISHED 1765.

BROWNING'S INDUCTION COILS.

The adoption of an improved method of winding Induction Coils has increased their efficiency and reduced their cost. Every Coil is guaranteed to give the length of spark named.

Induction Coil, to give an ¼ in. spark, 18*s*. 6*d*.; to give a ½ in. spark, £1 10*s*.; to give a ¾ in. spark, £3 5*s*.; to give a 1 in. spark, £5 10*s*.; to give a 1½ in. spark, £6 15*s*.; to give a 2½ in. spark, £10; to give a 3½ in. spark, £12 15*s*.; to give a 4½ in. spark, £16; to give a 6 in. spark, £22; to give a 9 in. spark, £36; to give a 12 in. spark, £45.

List of Electric Lamps and Lanterns and Galvanic Batteries sent free.

JOHN BROWNING,
OPTICAL AND PHYSICAL INSTRUMENT MAKER TO H.M. GOVERNMENT,
63, STRAND, LONDON, W.C.



SPECTACLES AND EYE-GLASSES

MOUNTED WITH

NEGRETTI & ZAMBRA'S

THERMOSCOPIC LENSES

OR THE FINEST

BRAZILIAN PEBBLES,

In Gold, Steel, or Tortoise-shell Frames.

NEGRETTI & ZAMBRA,

Opticians and Meteorological Instrument Makers

TO HER MAJESTY THE QUEEN,

HOLBORN VIADUCT,
45, CORNHILL, & 122, REGENT STREET, LONDON.

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 48N, Tollington Road, Holloway, London, N.

ROYAL INSTITUTION OF GREAT BRITAIN,

ALBEMARLE STREET, PICCADILLY, W.

Lecture Arrangements before Easter, 1881 (*Corrected*).

LECTURE HOUR, 3 O'CLOCK P.M.

CHRISTMAS LECTURES.

Prof. DEWAR, M.A., F.R.S.—Six Lectures (adapted to a Juvenile Audience) on "Atoms;" on December 28 (Tuesday), December 30; January 1, 4, 6, 8, 1881. One Guinea; Persons under 16, Half-a-Guinea.

Prof. EDWARD A. SCHÄFER, F.R.S., Fullerian Professor of Physiology, R.I.—Twelve Lectures on "The Blood;" on Tuesdays, January 18 to April 5. One Guinea.

FRANCIS HUEFFER, Esq.—Four Lectures on "The Troubadours;" on Thursdays, January 20 to February 10. Half-a-Guinea.

Prof. ERNST PAUER.—Two Lectures on "The History of Drawing-room Music;" on Thursdays, February 17 and 24. Half-a-Guinea.

Rev. WILLIAM HOUGHTON, M.A., F.L.S., Rector of Preston-on-the-Weald Moors, Shropshire.—Two Lectures on "The Picture Origin of the Cuneiform Characters;" on Thursdays, March 3, 10. Half-a-Guinea.

H. H. STATHAM, Esq.—Four Lectures on "Ornament, Historically and Critically Considered;" on Thursdays, March 17, 24, 31, and April 7. Half-a-Guinea.

SIDNEY COLVIN, Esq., M.A., Slade Professor of Fine Art, Cambridge.—Four Lectures on "The Amazons: A Chapter in the Study of Greek Art and Mythology;" on Saturdays, January 22 to February 12.

REGINALD STUART POOLE, Esq.—Four Lectures on "Ancient Egypt in its Comparative Relations;" on Saturdays, February 19, 26, and March 5, 12. Half-a-Guinea.

Rev. H. R. HAWEIS, M.A.—Four Lectures on "American Humorists;" on Saturdays, March 19, 26, and April 2, 9. Half-a-Guinea.

Professors TYNDALL and DEWAR will give Courses after Easter.

Subscription (to Non-Members) to all the Courses during the Season, Two Guineas. Tickets issued daily.

Now being Issued.

PHILOSOPHICAL CLASSICS FOR ENGLISH READERS.

Edited by WILLIAM KNIGHT, LL.D.,

Professor of Moral Philosophy, University of St. Andrews.

In crown 8vo, cloth boards, with Portraits, price 3*s.* 6*d.* each.

This Day is Published.

Vol. I.—DESCARTES.

By Prof. MAHAFFY.

With Portrait, crown 8vo, 3*s* 6*d.*

The following Volmues are in preparation for this Series, and will be published at short intervals:—

BUTLER, by Rev. Canon Collins, M.A. (*in January*).—BERKELEY, by Prof. Fraser, Edinburgh (*in February*).—FICHTE, by Prof. Adamson, Owens College, Manchester.—HAMILTON, by Prof. Veitch, Glasgow.—HUME, by the Editor.—BACON, by Prof. Nichol, Glasgow.—HEGEL, by Prof. Edward Caird, Glasgow.—HOBBES, by Prof. Croom Robertson, London.—KANT, by William Wallace, Merton College, Oxford.—SPINOZA, by Dr. Martineau, Principal of Manchester New College.—VICO, by Prof. Flint, Edinburgh.

Succeeding Volumes will include LOCKE, LEIBNITZ, COMTE, &c.

WILLIAM BLACKWOOD & SONS, Edinburgh and London.

CIVIL SERVICE COMMISSION.—Open

Competition in London, Edinburgh, and Dublin, for One Situation as SECOND ASSISTANT ASTRONOMER in the Royal Observatory, Edinburgh, January 18. Age, 17-33.—For Regulations and Forms of Application address the SECRETARY, London, S.W.

UNIVERSITY OF LONDON.

PRELIMINARY SCIENTIFIC AND 1ST M.B. EXAMINATIONS.

Special Classes in all the Subjects required for these Examinations will commence at St. Thomas's Hospital Medical School early in JANUARY. Full particulars may be obtained from the Secretary, Dr. GILLESPIE.

SCIENCE TEACHING for YOUNG CHILDREN.

—Wanted, Gentleman or Lady to undertake this, living with the Family. Must have thorough knowledge of the subject. Also, if possible, Drawing.—Address Mr. HERBERT, Freshwater, Isle of Wight.

TO MUSEUMS, PUBLIC INSTITUTIONS, &c.

—Highly-coloured Diagrams of Insects suitable for exhibition in a Public Museum. Being facsimiles of the 38 Drawings of Coleoptera drawn by the late Mr. Murray, and now exhibited in the Science and Art Museum, Bethnal Green.—Apply, W. REDAWAY, 39, Robert Street, Hampstead Road, N.W.

ROYAL ASIATIC SOCIETY.

MONDAY, December 20, at 4 p.m., a Paper will be read, contributed by Prof. DOWSON, entitled "The Invention of the Indian Alphabet."

W. S. W. VAUX, Secretary R.A.S.

LIVING SPECIMENS FOR THE MICROSCOPE.

THOMAS BOLTON, NATURALISTS' and MICROSCOPISTS' STUDIO, 17, ANN STREET, BIRMINGHAM.

T. B. has last week sent to his subscribers the Infusorian, *Spirostomum teres* of Claparède and Lachman, with drawing. He has also sent out a very clean gathering of Desmids and Diatoms, including *Closterium lunula, didymotocum*, and *striolatum*, *Micrasterias denticulata*, *Tetmemorus granulatus*, and *Euastrum didelta*, with drawing of same.

Weekly announcements will be made in this place of organisms T. B. is supplying.

Specimen Tube, One Shilling, post-free.

Twenty-six Tubes in course of Six Months for Subscription of £1 1s.

Price List of Specimens on application, with stamped addressed envelope.

Portfolio of Drawings, No. 3, One Shilling.

ROYAL POLYTECHNIC.—CLASSES for

the preparation of Students for University Examinations, under the direction of EDWARD B. AVELING, D.Sc., F.L.S. London University Matriculation, 1st and 2nd B.Sc., Preliminary Scientific M.B., Botany, Physiology, Chemistry. All the work practical.

50 ROCKS, 50 FOSSILS, 50 MINERALS,

NEATLY ARRANGED IN A

DEAL CABINET, STAINED AND POLISHED, LOCK AND KEY.

EACH SPECIMEN LABELLED AND CATALOGUED.

Price complete, £1 10s.

THE ROCKS illustrate the Order and Range of Deposition, &c.

THE FOSSILS are representative of the Genera found in the most important Deposits.

THE MINERALS are selected for their known uses in the Arts and Manufactures, and are extremely characteristic.

Names and Localities guaranteed.

THOMAS J. DOWNING, Geologist, &c.,

38, WHISKIN STREET, LONDON, E.C.

Catalogues Free.

MINERALOGY AND GEOLOGY.

MR. HENSON, who has just returned from Cornwall, has procured some VERY FINE CORNISH MINERALS, including some most splendid LARGE CRYSTALS of LIBETHENITE, and CHALCOSIDERITE, recently found.

FINE CRYSTALLISED CASSITERITE, LIROCONITE, BRILLIANT CUPRITE; also VERY GOOD CHALCOTRICHITE, BISMUTHINE, COPPER MICA, and HENWOODITE.

From Derbyshire, large Crystals of PHOSGENITE and MATLOCKITE.

From Sweden, VERY FINE AUGITE and AVANTURINE.

COLLECTIONS FOR STUDENTS, from £2 2*s.* COLLECTIONS FOR BEGINNERS, from 4*s.* BLOWPIPE CASES AND APPARATUS.

PRIVATE LESSONS AND EVENING CLASSES.

Catalogues free.

SAMUEL HENSON,

277 (*Late* 113*a*), STRAND, LONDON, W.C.

GEOLOGY AND MINERALOGY.

JOHN TYM has ready for Sale, at low prices, Educational Collections of Fossils, Rocks, and Minerals, specially arranged to illustrate the text-books of Lyell, Geikie, Bonney, Collins, Davies, Skertchley, Dana, Page, Jukes, &c. Series of Specimens for School and College Museums are also supplied at very reasonable prices. Catalogues post free.

Postal Address:—CASTLETON, *via* SHEFFIELD.

GEOLOGY.—In the Preface to the STUDENT'S ELEMENTS of GEOLOGY, by Lyell, 1874, he says: "As it is impossible to enable the reader to recognise rocks and minerals at sight by aid of verbal descriptions or figures, he will do well to obtain a well-arranged collection of specimens, such as may be procured from Mr. TENNANT (149, Strand), Teacher of Mineralogy at King's College, London." These Collections are supplied on the following terms, in plain Mahogany Cabinets:—

100 Specimens, in Cabinet, with 3 Trays	£2	2	0
200 Specimens, in Cabinet, with 5 Trays	5	5	0
300 Specimens, in Cabinet, with 9 Drawers	10	10	0
400 Specimens, in Cabinet, with 13 Drawers	21	0	0

More extensive Collections at 50 to 5,000 Guineas each.

ROCK SECTIONS & ROCK SPECIMENS.

Collections of Rock Specimens to illustrate Rutley's "Study of Rocks" specially prepared. 100 Small Specimens in Cabinet, One Guinea; 200 Specimens, Two Guineas. Extensive and choice Series of Rocks for selection. New List of Sections of Rocks for Microscope, and List of Collections, &c.

JAMES R. GREGORY'S

Extensive New Museum and Show Rooms,

88, CHARLOTTE STREET, FITZROY SQUARE.

MUSEUMS AND COLLECTORS.

MR. DAMON, of WEYMOUTH, will forward an abridged Catalogue of his Collections in Natural History Objects, including RECENT SHELLS (Foreign and British), FOSSIL REMAINS, MINERALS, ROCKS, MARINE ZOOLOGY, &c., &c., &c.

SCIENTIFIC PRESENTS.

1.

Facsimiles of 28 of the most celebrated White and Coloured Diamonds, wrought in Crystal Glass, of great lustre.

2.

Models of Natural Crystals of Diamonds, with other Models of Crystals of Coloured Precious Stones.

Each Set in handsome Morocco Case with Descriptive Catalogue.
Obtained the Bronze Medal, Paris Exhibition of 1878.
Address—Mr. R. DAMON, Weymouth.

THIN GLASS FOR MICROSCOPIC

MOUNTING, of best quality. Circles, 3*s.* 6*d.* per ounce; Squares, 2*s.* 9*d.*; post free 2*d.* extra; Ground edged Slips, 5*s.* per gross: also other Mounting Materials and Objects prepared for mounting.—CHAS. PETIT, 151, High Street, Stoke Newington, N.

THOMAS D. RUSSELL'S

NATURAL HISTORY STORES,

48, ESSEX STREET, STRAND, W.C.

Students and others are invited to inspect the Collections of British and Foreign Shells, Corals, Zoophytes, Annelids, Crustacea, Echinoderms, Minerals, Fossils, Rock Specimens, Microscopic Objects, &c.

Cabinets, Geologist's Hammers, Glass Capped Boxes, Card Trays, Tablets, Glass Slips, Micro-Thin Glass, Canada Balsam, Marine Glue, and other requisites for the Geologist and Microscopist.

Catalogues Post Free.

On the 1st of every Month.

TRIMEN'S JOURNAL OF BOTANY,

BRITISH AND FOREIGN.

New Series. Edited by JAMES BRITTEN, F.L.S., British Museum.

CONTENTS.—Original Articles by leading Botanists.—Extracts, and Notices of Books and Memoirs.—Articles in Journals.—Botanical News.—Proceedings of Societies.

Price 1*s.* 3*d.* Subscription for One Year, payable in advance, 12*s.*
London: WEST, NEWMAN, & CO., 54, Hatton Garden, E.C.

"The leading Farmers' paper."—CLARE SEWELL READ, ESQ., M.P.

THE CHAMBER OF AGRICULTURE JOURNAL

AND FARMERS' CHRONICLE

(PRICE 3*d.* WEEKLY).

The representative organ of the Central and Provincial Chambers of Agriculture; *gives fuller reports of the discussions and proceedings* of this extensive organisation than any other agricultural paper. It devotes *special attention to the treatment of Agricultural Questions by Parliament*, besides containing ample Reports of the LATEST LONDON and COUNTRY CORN, CATTLE, HOP, PROVISION, and other Markets, with Original Articles on Practical Farming, the Dairy, Herd and Flock News, Horticulture, &c., &c. It is despatched every Monday evening in time for the country post.

Terms of Subscription, payable in advance, post free:—3 months, 3*s.* 9½*d.*; 6 months, 7*s.* 7*d.*; 12 months, 15*s.* 2*d.*
Published by W. PICKERING, 21, Arundel Street, Strand, London, W.C.

NORTH BRITISH AGRICULTURIST

is the only Agricultural Journal in Scotland, and circulates extensively amongst Landed Proprietors, Factors, Farmers, Farm-bailiffs, and others interested in the management of landed property throughout Scotland and the Northern Counties of England.

The AGRICULTURIST has also a very considerable circulation on the Continent of Europe, America, Australia, and the Colonies.

The AGRICULTURIST is published every Wednesday afternoon in time for the evening mails, and contains Reports of all the principal British and Irish Markets of the week, besides Telegraphic Reports of those held on the day of publication.

The Veterinary Department is edited by one of the leading Veterinarians in the country, and is invaluable to the breeder and feeder as a guide to the rearing of animals, and their treatment when labouring under disease.

Full Reports are given of the Meetings of the Royal Agricultural Society of England, the Royal Agricultural Society of Ireland, the Highland and Agricultural Society of Scotland, the Scottish Chamber of Agriculture, and all the principal Agricultural Associations throughout Great Britain and Ireland.

For Advertisers addressing themselves to Farmers a better medium does not exist.

Price 3*d.* By post 3½*d.* Annual Subscription, payable in advance, 14*s.*
Office—377, High Street, Edinburgh.
Post-Office Orders payable to Charles Anderson, Jun., Edinburgh.

ESTABLISHED 1843.

THE ENTOMOLOGIST'S MONTHLY MAGAZINE.

Price Sixpence, Monthly, 24 pages 8vo, with occasional Illustrations.
Conducted by J. W. DOUGLAS, R. MCLACHLAN, F.R.S., E. C. RYE, F.Z.S. and H. T. STAINTON, F.R.S.

This Magazine, commenced in 1864, contains standard articles and notes on all subjects connected with Entomology, and especially on the Insects of the British Isles.

Subscription—Six Shillings per Volume, post free. The volumes commence with the June number in each year.

Vols. I. to V. (strongly bound in cloth) may be obtained by purchasers of the entire set to date, at the increased price of 10*s.* each; the succeeding vols. may be had separately or together, at 7*s.* each.

London: JOHN VAN VOORST, 1, Paternoster Row.

N.B.—Communications, &c., should be sent to the Editors at the above address.

On the 1st of every Month, price One Shilling.

THE ZOOLOGIST:

A MONTHLY MAGAZINE OF NATURAL HISTORY.

Third Series. Edited by J. E. HARTING, F.L.S., F.Z.S., Member of the British Ornithologists' Union; contains—

Original articles by well-known naturalists in every branch of zoology; habits of animals; arrival and departure of migratory birds; occurrence of rare birds; distribution and migration of British fresh-water fish; new or rare marine fish; local aquaria; British reptiles, British land and fresh-water mollusca, with remarks on the haunts and habits of the species; and other matters of general interest to those who delight in natural history. Reports of the Linnean, Zoological, and Entomological Societies. Reviews of natural history books. Occasional translations from foreign zoological journals of important and interesting articles in various branches of zoology. There are occasional woodcuts.

JOHN VAN VOORST, 1, Paternoster Row.

LA SEMAINE FRANÇAISE: a Weekly

Newspaper and Review in the French Language. Politics, Literature, Science, Art, Varieties, Notes. Price 3*d.*, through booksellers, and at the railway bookstalls. Office, 37, Southampton Street, Strand, W.C.

LA SEMAINE FRANÇAISE: Journal Française pour l'Angleterre: Politique, Littérature, Sciences, Arts, Variétés, Nouvelles, et Notes. Un exemplaire par la poste, 3½*d.*, en timbres poste. Abonnement franco par la poste—un an, 15*s.* 2*d.*; six mois, 7*s.* 7*d.* Prix 3*d.*, chez tous les libraires et aux gares des chemins de fer. On s'abonne aux bureaux, 37, Southampton Street, Strand, Londres, W.C.

LA SEMAINE FRANÇAISE.—"'La Semaine Française' has been brought out in London for the benefit of those English readers who may wish to study contemporary French from all points of view, instead of confining their reading to one particular Gallic print. It certainly merits success."—*Graphic.*

LA SEMAINE FRANÇAISE.—"The numbers before us are full of good things. . . . . It will be far better for most than any one of the best papers published in Paris itself. We are much pleased with the character of it, and believe it will be highly valued in all those many households where French is cultivated. The printing is very well done."—*Queen.*

TERMS OF SUBSCRIPTION:—	*s.*	*d.*
Three months	3	10
Six ,,	7	7
Twelve ,,	15	2

P.O.O. payable to T. SPANSWICK, at King Street, Covent Garden, W.C.
Publishing Office, 37, Southampton Street, Strand, W.C.

THE BREWERS' GUARDIAN:

A Fortnightly Paper devoted to the Protection of Brewers' Interests, Licensing, Legal, and Parliamentary Matters.

REVIEW OF THE MALT AND HOP TRADES; AND WINE AND SPIRIT TRADE RECORD.

The Organ of the Country Brewers.

"The Brewers' Guardian" is published on the evenings of every alternate Tuesday, and is the only journal officially connected with brewing interests.
Subscription, 16*s.* 6*d.* per annum, post free, dating from any quarter-day.
Single Copies 1*s.* each. Registered for transmission abroad.
Offices—5, Bond Court, Walbrook, London, E.C.

On the 1st of every Month, price Sixpence.

THE ENTOMOLOGIST:

AN ILLUSTRATED JOURNAL OF BRITISH ENTOMOLOGY.

Edited by JOHN T. CARRINGTON,

With the Assistance of

FREDERICK BOND, F.Z.S. | JOHN A. POWER, M.D.
EDWARD A. FITCH, F.L.S. | J. JENNER WEIR, F.L.S.
F. BUCHANAN WHITE, M.D.

Contains Articles by well-known Entomologists on all branches of the Science; on Insects injurious or beneficial to Farm or Garden; Notes on Habits, Life-Histories; occurrence of Rarities, &c.; there are monthly lists of Duplicates and Desiderata.

Numerous WOODCUT ILLUSTRATIONS, to the printing of which especial attention is given, and occasional LITHOGRAPHED and CHROMO-LITHOGRAPHED PLATES.

SIMPKIN, MARSHALL, & CO., Stationers' Hall Court.

5me ANNÉE **L'ÉLECTRICITÉ** 5me ANNÉE

Paris. — 16, *rue du Croissant.* — *Paris*

Revue spéciale populaire, illustrée, bi-mensuelle contenant 24 pages grand in-8° à deux colonnes, formant chaque année un magnifique volume de 400 pages orné de plus de 200 gravures.

Rédacteur en chef: **W. DE FONVIELLE**
Directeur: **E. de Clisson**

Envoi gratis de numéro spécimen sur demande

Un numéro **75** *centimes*

Paris et Départements: Un an..... **12 fr.**
Etranger. — Union postale: Un an..... **14 fr.**

Les Abonnements partent du 5 et du 20 de chaque mois.

Demy 8vo, 1s.

LONDON FOGS. By the Hon. R. Russell, F.M.S.

London: EDWARD STANFORD, 55, Charing Cross, S.W.

NEW WORK BY LIONEL S. BEALE.

Now ready, pp. 230, demy 8vo, 5s.

SLIGHT AILMENTS:

THEIR NATURE AND TREATMENT.

By LIONEL S. BEALE, M.B., F.R.S., F.R.C.P., Professor of the Principles and Practice of Medicine in King's College, London.

J. & A. CHURCHILL, New Burlington Street.

NOW READY, in 4to, cloth, price 6s.

ELASTICITY AND HEAT.

BY

SIR WILLIAM THOMSON,

Professor of Natural Philosophy in the University of Glasgow.

Reprinted from the "Encyclopædia Britannica."

Edinburgh: ADAM & CHARLES BLACK.

Now ready.

EXERCISES in PRACTICAL CHEMISTRY. Vol. I. (ELEMENTARY EXERCISES). By A. G. VERNON HARCOURT, M.A., F.R.S., Senior Student of Christ Church, and Lee's Reader in Chemistry; and H. G. MADAN, M.A., Fellow of Queen's College, Oxford. Third Edition, Revised and considerably Enlarged, crown 8vo, cloth, 9s.

London: HENRY FROWDE, Clarendon Press Warehouse, 7, Paternoster Row.

EDITED BY HENRY WATTS, B.A., F.R.S., Editor of the *Journal* of the Chemical Society

FOWNES' PHYSICAL and INORGANIC CHMISTRY. Twelfth Edition, with Coloured Plate and 154 Engravings, crown 8vo. 8s. 6d.

Also,

FOWNES' CHEMISTRY OF CARBON COMPOUNDS; or, ORGANIC CHEMISTRY. Twelfth Edition, with Engravings, crown 8vo. 10s.

London: J. & A. CHURCHILL.

EXPERIMENTS ON ANIMALS.—Fifth Annual Report of SOCIETY TOTAL ABOLITION VIVISECTION.—British Association.—Hunterian Society.—Prof. Owen.—Dr. Pye Smith.—The Rev. J. G. Wood.—Lewes Studentship.—Licences granted, and Experiments performed, under "Cruelty to Animals Act."—Hibbert Lectures.—Ernest Rénan.—The Royal Society Prevention Cruelty to Animals.—Earlham Temperance Series.—Ovariotomy.—Dr. Clay and Mr. Spencer Wells, F.R.C.S.—Canon Duckworth.—Bishop of Peterborough.—Earl of Pembroke, &c.—8vo, pp. 148, price 1s. 6d. PICKERING & Co., 196, Piccadilly, London, W.; and Mr. GEORGE R. JESSE, Honorary Secretary and Treasurer, Henbury, near Macclesfield. Cheshire.

E. FRIEDLÄNDER & SOHN,

BERLIN N.W., CARLSTRASSE 11.

NATURAL HISTORY & NATURAL SCIENCE BOOKSELLERS,

Established since 1827.

Largest Stock of the whole Literature of Natural History and the Exact Sciences.

Apply for Classified Catalogue in 25 Parts (each one Special Department of Science), price 6d. each.

Just published: Part IX., Entomology, 1: Scripta Miscellanea, Coleoptera, 40 pgs.—Part X., Entomology, 2: Lepidoptera, 22 pgs.—Part XI., Entomology, 3: Hymenoptera, Neuroptera, Orthoptera, Diptera, Hemiptera, Parasita, 30 pgs. These Catalogues comprise the Entomological Library of Prof. C. Stal of Stockholm.

Second Edition, with Maps, price 10s. 6d., pp. 447.

EPIDEMIOLOGY; or, The Cause of Epidemic Disease, of Murrains, of Blight, of Hurricanes, and of Abnormal Atmospherical Vicissitudes. With a History of Epidemic Diseases, and of the Phenomena that accompanied them. By JOHN PARKIN, M.D.

DAVID BOGUE, St. Martin's Place, London, W.C.

BRYCE-WRIGHT'S LATEST ARRIVALS.

MINERALS. — Crystallised Hessite, Crystallised Golds, Krennerite, Crystallised Atacamites, Malacone, Euclase, Edingtonite, Suzannite, Chanarcillite, Proustite, &c.

METEORITES.—Specimens of the following Falls:—Wold Cottage, Yorkshire; Java; Orvinio, Italy; Amana, Ohio; Tipperary, Ireland; Java; Orvinio, Italy; Estherville; Hainholz; Grosnagy, Russia; Borkut; Carthago Co.; Bates Co.; Sierra di Chaco; Ashville Co.; Bates Co.; Pallas; Ashville Co., &c., &c.

BRYCE-WRIGHT, F.R.G.S., &c.,

Mineralogist and Expert in Gems and Precious Stones,

90, GREAT RUSSELL STREET, BLOOMSBURY, LONDON, W.C.

With Illustrations and Maps, medium 8vo, 18s.

ISLAND LIFE:

OR, THE PHENOMENA AND CAUSES OF INSULAR FAUNAS AND FLORAS, INCLUDING A REVISION AND ATTEMPTED SOLUTION OF THE PROBLEM OF GEOLOGICAL CLIMATES. By ALFRED RUSSEL WALLACE, Author of "The Malay Archipelago," "The Geographical Distribution of Animals," &c.

"Mr. Wallace has long devoted himself to these problems of geographical distribution; and his new volume gives us the cream of his latest thinking in a pleasant and eminently readable form. No other living naturalist has the same union of high literary excellence with profound scientific knowledge. His wonderful grasp of detail, depth of insight, and breadth of view remind one at every turn of Darwin, with whom he shares the honours of discovery in the theory of natural selection; but beyond this he has a lightness of touch, a beauty of style, and an ingenuity in unravelling intricate difficulties which are all his own. . . . 'Island Life' is a work to be accepted almost without reservation from beginning to end. . . . Whoever reads his book must be charmed with it."—*St. James's Gazette.*

"The present volume, though in some respects intended as a popularisation of Mr. Wallace's previous works on the distribution of animals, yet contains an immense amount of new and important matter for the man of science, as well as much delightful reading for the less instructed public. It is, in fact, the final outcome of the author's most mature thought and research on the special subject which he has made most peculiarly his own. . . . The work throughout abounds with interest. . . . It may be read with equal pleasure by those who are already acquainted with the general principles of distribution and by those who wish for the first time to learn something about modern biological geography."—*Athenæum.*

"We have said enough to show that Mr. Wallace is led to discuss subjects of great interest to speculative minds. With its numerous special maps 'Island Life' ought to prove as interesting as it is instructive."—*Pall Mall Gazette.*

"Four years additional thought and research upon the lines laid down in that suggestive work 'The Geographical Distribution of Animals,' have brought to a conclusion the general scheme of inquiry which he from the first proposed to himself, and he now propounds, as a clear and definite theory, the results of investigations which might at first sight appear fragmentary and disconnected. Mr. Wallace has entitled himself to be called the father of the new science of zoological geography, showing that we have in the present distribution of living things over the earth's surface a key to the problems of the most ancient relations of land and water. . . . Mr. Wallace's survey of the widely-separated island system of the globe sets upon a solid basis his views of the wonderful powers of dispersion and modificati n existing in the organic world. . . . In his theory of local geographical changes modifying the general stability of continents we have perhaps a key to the most difficult and complex problems involved in the phenomena of the variation and distribution of living forms."—*Saturday Review.*

MACMILLAN AND CO., LONDON.

THURSDAY, DECEMBER 9, 1880

BRITISH EARTHQUAKES

ON Sunday evening last week (28th Nov.) the northern parts of the British Isles were slightly shaken by an earthquake. The recent disastrous earthquake shocks in Croatia have called renewed attention to this still mysterious geological phenomenon, and now, while the subject is still fresh and under discussion, a milder visitation of the same nature reminds us that our islands are not wholly exempt from their share in the pulsations of the terrestrial crust. Save the vague and inexact newspaper paragraphs which chronicle the impressions of different observers, we have no information as to the direction of propagation of the earthquake wave of last week, its duration, relative intensity, and angle of emergence at different localities. It appears to have been one of the usual type of earth-tremors experienced in this country, and to have affected the region which, during the present century at least, has been most subject to such movements. It is reported as having been felt at many points in the central valley of Scotland and in the north-east of Ireland, also along the west coast as far north as the further end of the Long Island. Its effects appear to have been most marked over the area occupied by the crystalline schists. In Bute the house-bells rang. At Oban a portion of the plaster was detached from the ceiling of the parish church during the service of the Sunday-school. At Inverary also some plaster was loosened, and a sensation of nausea and giddiness is even said to have been experienced. At Blair Athole the oil in the table-lamps was thrown into undulations, which rose over half an inch up the side of the glass. Over the Lowland belt the effects were less perceptible, though they are alleged to have been distinctly felt as far as Edinburgh. By some observers the duration of the shock was estimated at two, by others at ten seconds. In some places the movement was thought to be from the north-west, in others, from the south-west. One of the phenomena duly chronicled in most of the narratives is the jingling and creaking made by crockery and furniture. Such is the usual meagre kind of detail out of which an explanation of the cause of earth quake movements in Britain is in truth hardly possible.

If we look back into the history of the subject numerous references to earthquake shocks will be found in the annals of the last seven or eight centuries in this country. And if the chroniclers are to be believed, some of these were of exceptional severity. According to the list compiled by Sir John Prestwich, shocks seem to have been specially numerous and severe in the twelfth century. Thus on the 2nd of August, 1134, England was shaken by an earthquake just at the very time that Henry I. was about to take ship for Normandy; "flames of fire burst forth with great violence out of certain riffs of the earth." On another occasion, in the same century, the bed of the Thames was laid bare at London. We read, too, of churches and other buildings having been from time to time thrown down, and of open rents having been left in the ground after the passage of the shock.

In the contemporary records of these phenomena the geologist vainly searches for particulars that may serve to elucidate their origin. He finds much that is doubtfully correct, not a little that is obviously fabulous. Naturally the events were considered merely in their relations to the human population of the country, and those aspects of them were noted that bore special interest in that respect. Most frequently they were regarded in the light of divine judgments, and were connected with some real or imputed delinquency on the part of the inhabitants. We read, for instance, that on the 8th November, 1608, a rather smart shock of earthquake passed over Scotland. In the southern counties it was looked upon as a result of "the extraordinar drouth in the summer and winter before." But the more orthodox worthies in the farther north took a higher view of it. The kirk-session of Aberdeen met, and accepting the earthquake as "a document that God is angry against this land and against this city in particular for the manifold sins of the people," appointed a solemn fast for next day. On further reflection they came to recognise one sin in particular as having doubtless called down the judgment. For more than 150 years, in virtue of a bull granted by Pope Nicolas V., the proprietors on the banks of the River Dee had been accustomed to fish salmon on Sunday. These Sabbath-breakers were accordingly now summoned before the session and rebuked. Some of them agreed to give up their custom, but "some plainly refusit anyway to forbear." Again on 20th October, 1580, an earthquake occurred that particularly affected the house of the Master of Gray. The boy king, James VI. asking Fergusson, the minister of Dunfermline, "What he thought it could mean, that that house alone should shake and totter," was grimly answered by the divine: "Sir, why should not the devil rock his awn bairns?"

Doubtless many of the events chronicled in former centuries as earthquakes may not have been of that nature. Landslips and violent storms would account for some of the phenomena recorded. In looking over the lists of reputed earthquakes we cannot fail to notice that some districts of the country have been specially liable to the visitation. One of these has been the south-west of England, embracing the lower basin of the Severn with Somerset, Gloucester, Worcester, Cornwall, and the adjoining counties. Another notable area for a hundred years past has been the southern highlands of Perthshire.

After making every allowance for the vast multiplication of the means of recording passing events afforded by the extension of newspapers and the consequent increasing minuteness of detail in our domestic annals, there seems no reason to doubt that the number of earthquake shocks has increased during the present century, though possibly none may have reached the severity of some recorded in earlier periods. During the four years subsequent to September, 1839, upwards of 200 shocks were felt in Perthshire, some of which extended over nearly the whole of Scotland.

In searching for a possible solution of the problem presented by these terrestrial commotions one or two circumstances should be specially considered. In the great majority of cases where details of any kind have been preserved of the nature of the earthquakes, reference is made to noises that immediately preceded the actual

shock. In not a few instances these seem to have been the most alarming part of the phenomena. They are variously likened to the sound of a rushing wind, the roll of waggons, the muttering of thunder, or the rattle of cannon. With these aërial vibrations there are also recorded sounds as of a sudden snap or blow, or explosion in the earth underneath. Another feature of the earthquake-register is the persistence with which a relation is believed to exist between the commotion in the ground and the state of the atmosphere above. In some cases, indeed, the barometer is said to have suddenly fallen, and then to have risen after the shock had passed. Warm, damp, moist weather, heavy rain, thunder, strange electrical discharges, fire-balls, and other meteoric phenomena are chronicled as the concomitants of earthquakes. It may be said, of course, that the occurrence of these events together is only of the nature of a coincidence, and cannot conceivably be anything else. There can be no doubt, however, that in Britain, as on the Continent, earthquakes have been more numerous in the winter than in the summer half of the year. Of the fifty-nine earthquakes in Sir John Prestwich's list, as Prof. Prestwich has pointed out, eleven occurred in winter, eleven in spring, seven in summer, and eight in autumn. Out of 139 earthquakes recorded as having happened in Scotland up to September, 1839, eighty-nine occurred in the winter half of the year and fifty in the summer half. We cannot suppose that any variation in the meteorological condition of the atmosphere can directly give rise to an earthquake. Nevertheless it is conceivable that where the crust of the earth is in a condition of tension, rapid and extensive changes of atmospheric pressure may destroy an equilibrium that has previously been barely maintained. The observed relation between a low barometer and the more copious escape of fire-damp within coal-mines may possibly be of wider application.

It is evident, moreover, that the source of disturbance must be at no great depth from the surface. This is shown by the markedly local character of the phenomena. A shock of considerable violence which rends walls, overturns chimney-pots, rings bells, shakes furniture, and fills with alarm the inhabitants of a few parishes, but is quite unperceived in the districts around, cannot have a deep-seated origin. In looking at the districts specially liable to such visitations we notice in some degree a connection with geological structure. The earthquake area in the south-west of England embraces within its borders the ranges of the Malvern and Mendip Hills, which, with the surrounding country, point to a long succession of geological disturbances, while the hot springs that still rise there furnish additional indications of a connection between the heated interior and the surface. The most remarkable earthquake district in these islands at present is undoubtedly that of Comrie in Perthshire; where in the month of October, 1839, no fewer than sixty-six shocks were felt, the severest being perceived as far north as Dingwall, and as far south as Coldstream. During the last forty years the British Association has appointed two Committees to investigate the nature of the shocks so frequently experienced there. But their labours cannot be said to have as yet thrown much light on the subject. They have erected seismometers of approved construction and sensitiveness, but in many cases shocks that have been distinctly perceptible to the inhabitants have not been registered by the instruments. Much speculation has been offered as to the cause that earth-tremors should be specially abundant in that district. Reference has been made by different observers to protrusions of granite and dykes of basalt which traverse the rocks, as if these igneous masses supplied a clue to the source of movement. But neither the granite bosses nor the dykes are specially conspicuous in the Comrie district. On the contrary, they are there small in area and few in number compared with their occurrence in other tracts where earthquake shocks are rare. A geological structure at Comrie, however, which so far as we are aware has not been dwelt upon in this connection, is the occurrence there of the great fracture by which the southern edge of the Scottish Highlands is bounded. The Old Red Sandstone with its associated volcanic bands has been thrown on end against the crystalline schists. Of the extent of the dislocation no precise measurements have yet been made; probably the amount of upthrow varies along the line. At the north-eastern end of the fracture the sandstones and conglomerates have been placed on their ends for about two miles back from the fault. The line of dislocation can be traced across the island from sea to sea and across the island of Arran, whence it points for Ireland. It is probably one of the largest, as it certainly is the longest, fracture within the British area. On its north-western side lie the crumpled schists of the Highlands; on its south-eastern boundary are the dislocated, curved, and even inverted strata of the Old Red Sandstone. Two series of rocks of very different structure and elasticity are here brought abruptly together along a vertical or at least steeply inclined face, which must descend for several thousand feet from the surface. So far therefore as geological structure can be supposed to govern the origin and effects of earthquakes there does not appear to be within these islands any line or district where terrestrial disturbances should be so readily felt as along the flanks of the Scottish Highlands. Shocks coming from the Lowlands will recoil against the crystalline wall of the Highland schists, and be consequently more perceptible there than over the more homogeneous formations lying to the south. Another area in which earthquakes have been frequently observed is that of the Great Glen. This longest, straightest, and deepest of British valleys has from early geological times been a line of weakness.

There seems every probability in the supposition that some at least of our earthquakes result from the sudden collapse of rocks that have been under great strain. Their occurrence along lines of powerful fault suggests that the rocks on one or both sides of these dislocations are still subject to great tension, and that occasional relief is obtained by a snap which is powerful enough to generate an earthquake, though it gives rise to no change of level at the surface. When we reflect upon the constant strain on the terrestrial crust as it settles down upon the more rapidly contracting nucleus, we may be allowed to be grateful that earthquakes are not everywhere more numerous and destructive.

THE ENCYCLOPÆDIA BRITANNICA

The Encyclopædia Britannica. Ninth Edition. Vols. x. and xi. (Edinburgh: A. and C. Black.)

THESE two volumes of the *Encyclopædia Britannica* fully sustain the high character of the earlier volumes. The articles dealing with branches of physical and natural science are conspicuous by their high quality and number. In geographical science this volume is particularly strong. Dr. Rae contributes an article on "Greece," several specialists contribute the article on "Germany," and General Strachey of the Indian Civil Service has produced a very striking and valuable essay on the "Himalayas." Besides these there are shorter articles on "Greenland," "Grisons," "Guiana," the "Hawaiian Islands," and "Heligoland," all worthy of attention and replete with information. In medical science we note particularly the articles on "Gout," contributed by Dr. Affleck, and on "Heart Diseases" by Dr. G. W. Balfour. In the department of natural history the articles are almost exclusively on subjects of a specific or technical character; Prof. Newton writes on "Grouse," and Mr. John Gibson on the "Hare" and the "Hippopotamus." Prof. Church contributes brief articles on "Hemp" and "Guano," and Dr. Trimen has a good descriptive paper on "Grasses." The article "Herbarium," contributed by Mr. E. M. Holmes, is a remarkably useful and practical handling of a subject on which most botanical writers have usually very little to say; and the summary of information as to the character of the principal herbaria in existence will be found acceptable for reference. The contributions to the physical sciences are numerous and of great interest. Dr. Ball's article on "Gravitation" is at once simple and masterly. The article on "Harmonic Analysis" by the late Prof. Clerk Maxwell is all too short, but admirable in its way. Amongst technical subjects we may single out the articles on "Gunpowder" and "Gun-cotton" by Major Wardell and Prof. Abel respectively, on "Heating" by Capt. D. Galton, two long and very fully illustrated papers by Col. Maitland on "Gunmaking" and "Gunnery," and one on "Harbours" by Mr. T. Stevenson, which is accompanied by several capital plates. Mr. J. Blyth contributes two valuable articles on the "Gyroscope" and on "Graduation." From the latter we miss one or two points that might well have been added. There is no account of the dividing-machine employed by Messrs. Cooke and Sons of York in graduating the circles of the great Newall telescope; nor of the still more recent dividing engine constructed by the Waltham Watch Company. The biographical articles are numerous and excellent. Those on the two "Herschels" are from the pen of Prof. Pritchard. That on "Sir W. Hamilton" is contributed by Miss E. Hamilton. The biographical notice of "Sir W. Rowan Hamilton" is by Prof. Tait, than whom no one is more competent to write of the great mathematician; though somehow we miss in this thoughtful and appreciative article the peculiar characteristics of Prof. Tait's trenchant style. We propose to notice at greater length the important articles on "Geometry," "Geology," and "Heat."

The editor did well, we think, when he intrusted the compilation of the article upon such an important subject as "Pure Geometry" to so accomplished a geometer as Prof. Henrici. We can fancy what such an article would have been in the hands of the generality of English mathematicians trained at our conservative Universities, meek followers, for the most part, of one master: "There is but one Geometry, and Euclid is its exponent." We ourselves entertain a very high regard for Euclid: indeed our indebtedness to him for what ability we may have in geometrical science is as great as that of Cicero to Archias for eloquence; but we cannot help feeling that we might have had a far greater mastery over modern methods had our masters been acquainted with these methods themselves. "This book," says one who has recently left us, a consummate master of modern methods, "has been for nearly twenty-two centuries the encouragement and guide of scientific thought. . . . The encouragement, for it contained a body of knowledge that was really known and could be relied on, and that, moreover, was growing in extent and application. . . . the guide, for the aim of every scientific student of every subject was to bring his knowledge of that subject into a form as perfect as that which geometry had attained." In our author we have one who,

"Nullius addictus jurare in verba magistri,"

can ungrudgingly acknowledge the many good points of the old-world geometer, whilst, with keen-cutting scalpel, he boldly lays bare his numerous defects. The present generation, perhaps, will not see Euclid superseded in our schools; but when his warmest defender makes him admit that his proofs might be abridged and improved, that alternative proofs may with advantage be appended to his, and that new problems and theorems might be interpolated, we may expect that a time will come, quickly if only the Universities would not handicap their favourite so heavily, when his order and numbering of propositions may be abolished, and his treatment of parallels shelved. In the meanwhile we must work in hope, and the article under notice will possibly pave the way for an improved mode of studying the science. As is well known, Prof. Henrici has long been engaged in writing a Geometry: to this work we must refer readers for his views on the subject. In the *book* we see him as the teacher, laying his foundations deep and strong and broad enough for the vast superstructure—all pure geometry—they have to bear: in the *article*, he treats his subject at first rather as the historian and critic, though subsequently he takes up the *rôle* of teacher again ("use doth breed such a habit in a man"), and rapidly but most deftly sketches a beautiful outline—in parts filled in—of the "higher" geometry. In a long, but far from tedious, sketch of sixty-four columns he treats pure geometry in two sections: the first, in twenty-five and a half columns, gives an account of the Elementary, or Euclidian, Geometry: the second is devoted to the Higher, or Projective, Geometry. In section 1 we have a running commentary on Euclid's text, which does at greater length, though somewhat in the same style, what De Morgan did some years since in the "Companion to the British Almanac" (1849). The axioms which lie at the basis of the subject are well discussed, and their foundation upon experience established: it is pointed out that the connection between these axioms has only been shown "within the last twenty years

through the researches of Riemann and Helmholtz, although Grassmann had already published, in 1844, his classical but long-neglected 'Ausdehnungslehre.'" In this connexion we can merely refer to the admirable lecture by Clifford, "The Postulates of the Science of Space." There is a good statement of Euclid's assumptions, but we shall refer only to that which is made in I. 4, thus enunciated by De Morgan: "Any figure may be removed from place to place without alteration of form, and a plane figure may be turned round on the plane." This is employed by Prof. Henrici, as it has been by many others, to prove I. 5, with this difference, that he does it after Mr. Dodgson has made Euclid say there is "too much of the Irish Bull about it, and that it reminds one too vividly of the man who walked down his own throat, to deserve a place in a strictly philosophical treatise." But the difference between these two writers is a radical one, and is not confined to the above solitary instance. The treatment of Book I. (the remarks on axiom xii. in connection with I. 28, 29 are valuable) calls for no special comment. In Book II. we have the propositions discussed symbolically and proved by the aid of laws investigated by Sir W. Rowan Hamilton and Grassmann: laws familiar to more advanced students, but which are here put in a manner within the grasp, we think, of junior students. The book is one, however, to which this class never take very kindly, and requires patience and illustration on the part of the teacher. We can, from the outline here given, guess how Prof. Henrici will treat this part of geometry in his forthcoming second volume. The remarks upon the Fourth Book conclude with a "few theorems not given by Euclid," but they are readily derived from (if not explicitly stated in) Euclid's constructions. Of Book V. there is a careful sketch, and our author shows "Why the usual algebraical treatment of proportion is not really sound." (Here we may refer also to Mr. A. J. Ellis's "Euclid's Conception of Ratio and Proportion" in his "Algebra identified with Geometry," and in a simpler form in a lecture at the College of Preceptors.) Books VI., XI., XII. need not delay us. We come now to the Projective Geometry, which we should much like to see reproduced in pamphlet form for use in colleges or schools. We notice Prof. Henrici states, "In Euclid's *Elements* almost all] propositions refer to the *magnitude* of lines, angles, areas, or volumes, and therefore to measurement." This, too, is our own view, and we presume it is what Mr. Wilson intended when he says: "Every theorem may be shown to be a means of indirectly measuring some magnitude"; whether it be so or not, at any rate Mr. Dodgson cannot impugn the Professor's more guarded statement. Those properties of figures which do not alter by projection are projective properties: there is a slight omission in the illustrations given, an exception should, we think, have been made in the case when the plane of projection is perpendicular to the plane upon which the quadrilateral, or circle, or other figure is projected. The points of difference between the two sciences are well put. "In Euclid each proposition stands by itself; its connection with others is never indicated; the leading ideas contained in its proof are not stated; general principles do not exist. In the modern methods, on the other hand, the greatest importance is attached to the leading thoughts which pervade the whole; and general principles, which bring whole groups of theorems under one aspect, are given rather than separate propositions. The whole tendency is to generalisation." Euclid, it is open to remark, throughout his work, avoids the *infinite*, whereas the modern geometry, like a good Samaritan, takes the most tender care of it. The systems adopted by Prof. Henrici are principally the methods of projection and correspondence—as handled by Von Staudt in the "Geometrie der Lage," and by Grassman in his above-cited work. We should like to analyse this sketch in detail, but we must forbear. For curves of two dimensions it is quite too delicious for us to mar it by such scant and imperfect treatment as we could here give it, and we must content ourselves with giving the heads of the several sub-sections. After the statement of definitions and preliminary explanations, we have segments of a line, projection and cross-ratios (Clifford's name for the anharmonic ratios of Chasles), correspondence, curves and cones of second order or second class, pole and polar, diameters and axes of conics, involution, involution determined by a conic on a line—foci, pencil of conics. The conclusion of the essay on the conics is that we arrive at the definitions from which our English text-books usually start. So the mode of treatment will be seen to be novel to the majority of English students. The concluding sections (six columns) on ruled quadric surfaces, but more especially on twisted cubics, seem to us to bear on their faces tokens of having been somewhat hurriedly written, so are not quite up to the high standard of the previous work. At the close Prof. Henrici refers his readers to Reye's "Geometrie der Lage" for "a more exhaustive treatment of the subject." "Scarcely any use has been made of algebra, and it would have been even possible to avoid this little, as is done by Reye." Prof. Clerk Maxwell, in a note to us, commended, in his own quaint way, this work of Reye. A short list of references is appended.

We could have wished that the "Analytical Geometry" had also been intrusted to Prof. Henrici, more especially that we might have seen how he would have connected the two together, and also that we might have had the subject discussed from a Continental point of view. We have sufficiently comprehensive and good treatises already by English writers, some of which are adorned with much of Prof. Cayley's work, and we feel, too, that had our author had *carte blanche* for space, he would have done his work well; whereas in attempting to pack much matter into a small space we think he has assumed much which is not familiar to some, and yet at the same time which is elementary to others who are advanced students. Nor does the article, to our mind, thoroughly serve for purposes of reference, though, no doubt, it goes some way to this end. The secret may be that "Pure Geometry" is more limited in its range, has, on one side, to do with a book known to almost all, and, on the other side, even does not reach, for the generality, beyond the conic sections; "Analytical Geometry," on the other hand, has to do with everything that relates to curves and surfaces, of whatever sort they may be. Prof. Cayley takes the line of analytical geometry "as a method," and confines himself, in his twenty-four and a half columns, to the consideration of the applications of Cartesian co-ordinates

almost exclusively. The article is divided into the two sections of plane and solid geometry. At the commencement the student is recommended by the weight of Prof. Cayley's advice to trace a number of curves, and he draws a few simple ones, so drawing attention to a point upon which Mr. Frost, in his "Curve-Tracing," strongly insists. Prof. Clifford, too, we believe, had it in his mind to publish an account of some methods which "are exceedingly simple and easy of application; they partake more of the nature of a manual craft than of a purely intellectual occupation, and may so be used as a rest from severer studies; and, as we can only imagine things of which we have seen the like by appealing directly to the senses, they extend those powers of concrete realisation which the growing complication of modern analysis renders daily more desirable." The methods he alluded to are "Projection, a process by which no alteration is made in the order, the class, nor in any other purely descriptive property of a curve;" then "those modifications of form which leave the *order* of a curve unaltered;" then "those changes which exercise no effect upon the class." In the last two cases he proposed to use a process which he used to call "the *composition of curves*, by which a curve of any order or class may be built up out of the simplest elements." We fear that we have lost this proposed sketch, with the many other sketches he had outlined and lived not long enough to endue with a vitality he could so well have given them. After the illustrations referred to Prof. Cayley discusses shortly the metrical theory, and obtains the several familiar equations both in plane and solid geometry. In short paragraphs polar, trilinear, point, and line co-ordinates are described, but not applied. We have noted scarcely any misprints in the first article, but in the second there are several, all of which are easily detected. The figures are very well done.

We would draw attention to the article on Geodesy by Col. Clarke, which we have read with much pleasure. It is well illustrated, and the eighteen columns treat of the following matters:—Horizontal angles, astronomical observations, calculation of triangulation, irregularities of the earth's surface, altitudes, longitude. These are as fully discussed as need be in a sketch of the subject, and we shall expect that Col. Clarke's more extended work on Geodesy, referred to in NATURE, vol. xxi. p. 423, will take its place as a standard work for some time to come.

Geology occupies at the present day so important a position in the circle of the sciences that it deserves to be treated, in any modern cyclopædia, with no niggard hand. A slender essay, confined to a survey of the broad features of geology, would have been sadly disappointing in such a work as the "Encyclopædia Britannica." It is therefore satisfactory to observe that Prof. Geikie, to whom the editor entrusted this article, has put a liberal interpretation upon his trust. He has treated his subject with a fulness worthy of a great and growing science, and worthy too of the noble plan upon which the Encyclopædia has been projected. The masterly article which he has contributed to the new edition stretches over more than 320 columns, and is thus longer than most of the kindred articles, such as those on "Astronomy" and "Chemistry." Possibly it might have borne, here and there, a little condensation, but on the whole it is admirably fitted for its place. It stands forth as a solid and comprehensive monograph which, if reprinted from the Cyclopædia, would form one of the most substantial treatises in our geological literature. But the article is not only substantial, it is, like all Prof. Geikie's writings, eminently readable. The cardina virtues of an encyclopædist are accuracy and conciseness of expression, and he usually finds but little scope for the play of literary graces. Prof. Geikie, however, is far too polished an author to write upon any subject in an unattractive style; and the present article is sufficient to prove—were proof needed—that his graceful pen does not fail him, even when discoursing on the knottiest point in geology. The comprehensive nature of this article, and the originality with which the subject is treated, may be best shown by explaining the seven-fold division adopted by the author. First he deals with the *Cosmical Aspects of Geology*, and not only discusses the shape and the motions of the earth, but stretches his survey to the probable history of the solar system. Then he inquires into the nature of the materials of the earth's substance—an inquiry which falls under the head of *Geognosy*. In the early part of the article the author may seem to trench a little upon subjects which are treated in other articles, but this is almost inevitable in any cyclopædia. It is not to be expected that the several essays shall just touch each other without overlap, like the pieces of a neatly-jointed mosaic. The geognostic division of the article is followed by a section on *Dynamical Geology*, and this in turn by one on *Structural Geology*, or the architecture of the earth. Under the head of *Palæontological Geology* Prof. Geikie sketches the history of life as revealed by the fossiliferous deposits, while in the following section on *Stratigraphical Geology* he traces the chronological succession of events in the history of the stratified rocks. Finally a chapter is devoted to *Physiographical Geology*, or a discussion of the origin of the physical features of the earth's surface.

To see for the first time a great actor play the part of a familiar character is a treat; but the pleasure is seldom quite free from a mixture of disappointment. His reading of the part is usually not our pet and peculiar one, and we are, as it were, bullied into contentment by the great power of the performer. We felt something akin to it when we read the article "Heat" by Sir William Thomson, though the feeling was of course unreasonable. It often happens when for the second time we see a great actor play a great part we yield ourselves to his charm without a trace of intellectual reserve; so it will most likely be when next we read the article "Heat." At all events, the readers of NATURE may be assured that there is little in this article that they can justly find fault with, whatever they may miss to find that they expected. Could it be otherwise, when the author is the pupil of Regnault, the colleague of Joule, one of the patriarchs of the modern science of thermodynamics, the greatest living authority on the theory of heat in Britain? We shall therefore most modestly discharge our function by pointing out to our readers what they will find in Sir William Thomson's article; and by slightly indicating some points on which, to our regret, he has withheld his opinion.

The article opens with a discussion of the sense of heat, and of the distinction between heat and temperature. We are thus introduced to the conception of latent heat, which is explained at some length. The two leading methods of calorimetry, viz. calorimetry by latent heat, and thermometric calorimetry, are then discussed in general terms; and the results of the comparison of the different calorimetric units by Regnault and others are given. Then follows a full account of the origin of the modern theory of heat, which regards it as energy, and measures it by the equivalent amount of work. We thus have a third method of calorimetry, which is called dynamical calorimetry. Of the thirty-five pages occupied by the whole article eighteen are devoted to thermometry. This is the most important, and certainly the most interesting part of the article. After discussing a theoretical (and to some extent practical) system of thermometry by mixtures of hot and cold water, the thermoscope being the sense of heat in the hand, the author gives an elaborate classification of the different possible kinds of thermoscopes. Then comes an extremely interesting discussion of the merits of the different kinds of thermometers with arbitrary scales. The defects of the mercury-in-glass thermometer, and the advantages which led Regnault to prefer the (constant volume) air-thermometer are fully explained. We do not remember to have anywhere seen so full, and, it is needless to say, so philosophical an account of Regnault's results of the comparison of the different thermometric scales. The rest of the part devoted to thermometry is more or less speculative. The absolute thermodynamic scale of temperature, invented by the author himself, is defined; and its great advantage pointed out, viz., that it gives us a definition of temperature "such that, if a thermometer were graduated according to it from observation of one class of thermal effects in any one particular substance, it would agree with a thermometer graduated according to the same thermodynamic law from the same class of effects in any other substance."

Thermodynamic formulæ are investigated in a variety of cases for graduating thermometers, according to the absolute scale, from experimental data concerning the thermometric substance. A number of instruments are described in detail which are intended to realise these cases in practice. We are thus introduced to the water steam, mercury steam, and sulphurous acid steam thermometers, and the constant pressure hydrogen thermometer. These instruments are mostly new as to their details, and all of them are new in the sense that they have not been practically used hitherto. Nevertheless a great future is predicted for them. It would appear that Sir William Thomson has himself constructed models of them all; but whether he has used any of them in practical work he does not say. It has doubtless occurred to many of our readers, as it has to us, to have doubts and difficulties about thermometric measurements. Nowhere could we find better reasons for our scepticism than in the earlier part of Sir William Thomson's discussion of the systems of thermometry at present in use; we shall look, therefore, with all the greater interest for some farther account of the practical working of these new instruments. Their success, were it even but partial, would be an immense gain to thermal science.

Thermal capacity and specific heat are next defined; and a brief account of the leading features of the results of different experimenters is given, without detail as to the methods employed in obtaining them. For further information we are referred to the articles on "Thermodynamics," "Matter," "Liquid," "Steam." The remaining five pages of the article deal with the transference of heat. Radiation is explained and distinguished from other modes of transference; but to our great regret is dismissed very briefly. A criticism of the work of the various experimenters in this department from an authority like Sir William Thomson would have been most interesting. There is still much doubt and difficulty hanging over the subject of the diathermancy of gases, for instance; we need scarcely mention as an illustration the famous controversy which has raged over water vapour. It may be however that these and kindred matters are to be treated under "Radiation" or "Light"; although we are not referred to these articles. The general principles of the theory of the conduction or diffusion of heat, as laid down by Fourier, are explained; and a most interesting critical account is given of the earlier attempts to measure conductivity. The explanation of the causes of the failure of Clément and Péclet in measuring high conductivities, such as that of copper, is very instructive, and should be closely studied by those engaged in like researches. Of the methods in use for measuring the thermal conductivity (or diffusivity as the case may be) of solids, Sir William Thomson prefers that of Ångström, and recommends along with it the use of thermoelectric methods for determining the temperatures along the experimental bar. The mathematical theory of this method is given, and its connection with the researches of Forbes and Thomson on underground temperatures pointed out. The method of Forbes for measuring the conductivities of metals in absolute measure is described in general terms; and the results obtained with it by Tait are given, and compared with those of Ångström and Thalèn. We regret that no mention is made of the recent attempts to measure the conductivities of liquids and gases. The only result given is that of Bottomley for water, and no description of the method accompanies it. It is quite true that the success of many of these attempts has been somewhat doubtful; but, for that very reason, a criticism of the methods by a competent and impartial authority would have been most opportune, and useful as a guide to future experimenters. Appended to the article are a series of ten tables of thermal constants, and a reasoned synopsis of the principal mathematical formulæ that occur in the theory of diffusion. This last is a most valuable part of the article; for it could be given only by a master of the subject, and it is likely to be extremely useful to many physicists, who have sufficient knowledge to enable them to use such formulæ, but not sufficient mathematical power to find them for themselves, or sufficient time to hunt them up from ponderous treatises and half-forgotten memoirs when they want them.

We sincerely congratulate the editor and publishers of the *Encyclopædia* on the high degree of success which continues to attend their great undertaking.

OUR BOOK SHELF

Life and Her Children: Glimpses of Animal Life from the Amœba to the Insects. By Arabella B. Buckley. (London: Edward Stanford, 1880.)

AFTER light came life, and with that life there came its two great functions—growth and development. With the simplest as with the most complex forms there is the same eager race to be run, to increase in size, to multiply, and thus replenishing this earth, to die. "Life and Her Children" is a praiseworthy and admirable attempt to tell us something of the Children that Life sends forth, and of their history. Its main object is to acquaint young people with the structure and habits of the lower forms of life; but in our deliberate judgment it will do a great deal more. None will read its introductory chapter without advantage, and few will read the volume through without enjoyment. Within its narrow limits of 300 small pages no candid reader would expect to find all the details that might be wished for, or all the illustrations that might be desired. What constitutes the book's chief charm is the marvellously simple yet quite scientific style which runs through it, the food for thought and future study which it affords, and the truly philosophic glow which lights up its every page. The volume gives a general account of Life's Simplest Children, the Protozoa. The word "slime" does not seem to us quite a happy term by which to designate the living protoplasm of these creatures; this word conveys the idea of a something adhesive or glutinous, or of a something thrown off a living organism—a something without a structure (sordies, eluvies)—and there seems somewhat of a "contempt for nature," a thought certainly never present in the author's mind, in the use of such a word. Jelly would seem a more appropriate word, as conveying the idea of the consistency requisite for life, and would have the sanction of use. Thus the Noctilucæ, called in this volume "tiny bags of slime," were described, if we mistake not, by their discoverer as "tiny spherical gelatinous bodies," and Prof. Huxley says, "Noctiluca may be described as 'a gelatinous transparent body about the one-sixtieth of an inch in diameter.'"

The chapter on "How Star-fish Walk and Sea-Urchins Grow" is excellent. The story of how the five curious little oval jelly bodies swimming about by their jelly lashes in the depths of the smooth water in some English bay—ended in becoming respectively a lily star, a brittle star, a starfish, a sea-urchin, and a sea-cucumber, is well told, and woodcuts, though they make one see as in a glass darkly, help in their own way to make the meaning plain. In the "Outcasts of Animal Life" a difficult problem is treated of. It need not surprise one that it is not solved. The last four chapters tell of "the Snare-Weavers and their Hunting Relations (spiders)"; the Insects which change their coats but not their bodies, and those which remodel their bodies within cover of their coats; "the Intelligent Insects with Helpless Children, as illustrated by the Ants." This volume thus tells of the greater part of the living invertebrate animals as they are spread over the earth to fight the battle of life. "Though in many places the battle is fierce and each one must fight remorselessly for himself and his little ones, yet the struggle consists chiefly in all the members of the various brigades doing their work in life to the best of their power, so that all while they live may lead a healthy, active existence. The little bird is fighting his battle when he builds his nest and seeks food for his mate and his little ones; and though in doing this he must kill the worm, and may perhaps by and by fall a victim himself to the hungry hawk, yet the worm heeds nothing of its danger till its life comes to an end; and the bird trills his merry song after his breakfast, and enjoys his life without thinking of perils to come. So Life sends her Children forth; and it remains for us to learn something of their history. If we could but know it all, and the thousands of different ways in which the beings around us struggle and live, we should be overwhelmed with wonder. Even as it is, we may perhaps hope to gain such a glimpse of the labours of this great multitude as may lead us to wish to fight our own battle bravely and to work and strive and bear patiently, if only that we may be worthy to stand at the head of the vast family of Life's Children."

The work forms a charming introduction to the study of zoology—the science of living things—which we trust will find its way into many hands. E. P. W.

LETTERS TO THE EDITOR

[*The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts. No notice is taken of anonymous communications.*]

The Editor urgently requests correspondents to keep their letters as short as possible. The pressure on his space is so great that it is impossible otherwise to ensure the appearance even of communications containing interesting and novel facts.]

Prof. Tait and Mr. H. Spencer

As Mr. Spencer has already got the length of calling some of my statements "fictions, pure and absolute," it is time that this discussion should cease. But it is necessary that I should at least show my reasons for having made the statements in question. They will be found ample.

Mr. Spencer's pamphlet, which originated this discussion, and in which I am the first subject brought up for vivisection, bears on the title-page that it deals with *Criticisms*.

The only passages of mine which Mr. Spencer quotes, which can possibly have the slightest reference to himself, and which can in any way be construed into criticisms, are but two in number. In these, or in one of them, the cause of his attack on me must be sought.

The first is mainly a verbal transcription from Mr. Kirkman, and as such it is none of mine; but in introducing it I inadvertently (though correctly) spoke of the "Formula of Evolution" as a *definition*.

The second is a passage *from a different part* of my article on Sir E. Beckett's book, and its application is to materialists and agnostics in general.

This latter passage did not appear to me capable of having roused the vivisection-instincts of so calm a philosopher as Mr. Spencer, especially as it was not applied to any one in particular. Of course, then, I at once assumed that the former passage contained the offence which was to be expiated; and I was confirmed in this idea by the way in which Mr. Spencer put his *formula* alongside of the Law of Gravitation. I could not have ventured to suppose that Mr. Spencer "*did not even know that he was in the habit of saying formula rather than definition.*" This *naïve* confession cannot but be correct. Had it been made in Mr. Spencer's pamphlet, I should not have thought it necessary to say a word. It explains at once his frequent entire misapprehensions of my meaning. So I give up my plausible theory of the origin of Mr. Spencer's attack on me; and shall, henceforth, ascribe that attack to my having made a singularly apt and telling quotation from Shakespeare!

With regard to the other parts of the discussion, I feel that I need not add anything to what I have already said; except on one point, an important one.

Mr. Spencer has employed an old remark of Prof. Huxley as to what mathematics can, and cannot, do; but he has not employed it happily, for the question at issue is really this:—Is it correct to speak, at one time, of force as an agent which changes a body's state of rest or of motion, and again to speak of it as the time-rate at which momentum changes or as the space-rate at which energy is transformed?

I answer that there is not the slightest inconvenience here; except, perhaps, in the eyes of those metaphysicians (if there be any) who fancy they know *what* force *is*. Such phrases as "the wind blows," or "the sun rises," though used by the most accurate even of scientific writers, would otherwise (on account of their anthropomorphism) have to be regarded as absolute nonsense. P. G. TAIT

Geological Climates

IT was with great surprise I read Prof. Haughton's unqualified statement in last week's NATURE, that—"It is *impossible* to suggest any rearrangement of land and water which shall sensibly *raise the temperature of the West of Europe*,"—since I had, as I thought, in my recently-published volume—"Island Life"—not only "suggested" such a rearrangement, but also adduced much evidence to show that it had actually occurred throughout the periods when both the West of Europe and the Arctic regions enjoyed a much higher temperature than they do now. I will now briefly re-state my "suggestion," and will also make a few remarks on the general causes of difference of temperature, which may serve to render the subject more intelligible.

It is now well known that places in the temperate zones owe their temperature at different seasons only partially to the amount of direct sun-heat they receive, but very largely to the amounts of heat brought to them by currents of air. Thus we explain, not only the mild winter climate of our islands as due to the prevalence of westerly and south-westerly winds which have become warmed by passing over the Atlantic, but also the wonderful inequality of temperature at different seasons of the year. When we have warm spring-like days in mid-winter, it is because these warm currents of air are passing steadily over our islands; while continued hard frosts are as clearly due to masses of cold air from the north or north-east which drift down to us, often with no perceptible wind. Again, when in April and May we have days as cold as those of December and January, they can always be traced to northerly or easterly currents of air, and are probably often connected with the southern drift of the icebergs at that season. It is clear then, that if south-westerly winds were to continue throughout the winter, the severity of that season would be entirely abolished; and the same effect would be produced if by any means the winds from the north and east lost their severity.

Now the source of the constant warmth of our westerly winds is admitted to be the influx of warm water into the North Atlantic—chiefly by the Gulf Stream; and this warm northward flow of tropical water, being primarily due to the trade-winds, is not confined to the Atlantic, but is equally present in the other great oceans, and similar effects are produced in them, though nowhere to so great a degree as in our islands, owing to our insular position and the great extent to which Europe to the east of us is permeated by water as compared with North America or Asia. The North Pacific, with its great Japan current, is probably quite as warm as the North Atlantic; but Vancouver's Island, though further south than London, has not so mild a climate; and this can be clearly traced to the great mass of land to the east and north of it, the lofty snow-clad mountains, and the absence of those deep gulfs and inland seas which do so much to ameliorate the climate of Europe.

Prof. Haughton states, in his "Lectures on Physical Geography," that the Kuro Siwo, or great Pacific current, is two and a half times as large as the Gulf Stream, while the Mozambique current, which forms the outflow of the warm waters of the Indian Ocean, is one and a half times as much, so that these two currents have together four times the bulk and heating power of the Gulf Stream. If therefore these two currents at any time obtained an entrance into the Arctic Ocean, it is difficult to over-estimate their effect on its climate. The Gulf Stream, of which probably not half passes northwards of our islands, gives to Iceland the same winter temperature as Philadelphia, and keeps the North Cape (far within the Arctic circle) permanently free from ice, and this, notwithstanding the powerful counteracting influences of the lofty Scandinavian mountains on the one side, and the huge ice-clad plateau of Greenland on the other. Suppose that only an equal proportion of the Kuro Siwo entered the Arctic Ocean, is it not probable that no sea-ice at all would form there? While, if Greenland were less elevated and thus ceased to be an accumulator of ice, the combined effect might be to render the whole Polar area free of icebergs. This would at once do away with the chief source of winter cold to all north temperate lands, and ameliorate the climate of America as much, proportionately, as that of Europe.

But we have yet to consider a still more powerful agent in ameliorating the climate of Western Europe in Secondary and early Tertiary times. The heated waters of the Indian Ocean have now no northern outlet, and only penetrate the continent in the sub-tropical Red Sea and Persian Gulf. Now if we suppose the waters of the Bay of Bengal and the Arabian Sea to have had northward outlets through the heart of the Euro-Asiatic continent, penetrating in two or more directions into the then much more extensive Arctic Ocean, we should have an agency at work which would render the presence of any permanent ice in the North Polar area as impossible as it is now in Scotland. The cooling agency of ice being once abolished, the comparatively small area of the Polar as compared with the Tropical seas (about one-tenth) would facilitate the raising of the temperature of the former to perhaps 15° or 20° F. above the freezing point, and this would not only give the Arctic lowlands a climate quite sufficient for the vegetation which we know they supported, but, by doing away with the only source of our winter cold, would give our islands a perfect immunity from frosts and render them capable of supporting the vegetation now characteristic of sub-tropical lands.

That the modifications of land and sea here indicated *did* exist throughout a considerable portion of past geological ages, and that the existing consolidation of the great northern continents, to which the possibility of our present Arctic climates is mainly due, is a comparatively recent and abnormal phenomenon, I have endeavoured to prove in the work already referred to. At present I have only undertaken to show, that a "suggested" rearrangement of land and water adequate to raise the temperature of Western Europe to a very sensible, or even to a very large extent, *is* "possible." ALFRED R. WALLACE

Photophonic Music

I HAVE not yet met with any reference to the capabilities of the photophone for giving musical harmonies. Might not some curious effects be got in some such way as this:—Suppose a disk perforated with holes in four concentric circles corresponding to the notes of a chord; a beam of light to be sent through each circle to a lens and disk of rubber with tube (as Prof. Bell has described), the four tubes debouching in a cup-shaped cavity to be applied to the ear; lastly, the disk to be rotated variably by means of a small windmill or otherwise. Another arrangement might be to make the beams of light pass through the holes to selenium cells in four telephone circuits, the four telephones being placed in one frame, against which the listener's ear would be put, or coupled in pairs, one pair put to either ear. Again, might not harmonised tunes be obtained thus:—Suppose a broad open drum of wood or cardboard rotated uniformly on a screw forming a vertical axis. The drum is perforated in a spiral band of four lines of holes (for the light), corresponding to the notes of the harmonised air to be produced. This spiral band passes before four rubber disks or selenium cells (as in the former system), but arranged vertically and placed within the drum, at the lower part. The drum, it will be understood, works gradually down the axis, presenting a continuous four-line series of holes before the receiving apparatus. Again, a long continuous strip of cardboard, with four rows of holes, might be passed before the receiver in any convenient way. M.

The "Philosophy of Language"

THOUGH it is my principle never to answer any criticism of my writings, I find myself obliged to deviate for once from this rule by the character of your highly esteemed review, and by the desire to find a discerning appreciation from your readers, whose judgment has for me the greater value, as it is the main aim of all my works to restore the relations between the science of mind and natural philosophy. Therefore you would oblige me very much by publishing the following short remarks:—

The critic of my *brochure* ("Max Müller and the Philosophy of Language,") says, ". . . Nor is speech the deliberate product of a conscious will." Now it is the real aim of all my works on the philosophy of language to show how the human will—before dark and unconscious—grows to consciousness *by language* and human activity intimately connected with it. Can there be the least doubt of this, even if I refer only to the motto of my "Origin of Language,"—"Language has created reason, before language man was without reason"?

Your critic has made me say *just the contrary of what I really have said.* Besides, it would have been only fair if the critic had pointed to the following little passage of my *brochure*:—

"Max Müller has since expressed *his full assent* to this view," (viz., my theory of the origin of language).

Mayence, November 11 LUDWIG NOIRÉ

[I gladly accept the author's assurance that he adheres to the view that "language has created reason." At the same time his

express words as well as the general bent of his argument seemed to point in the opposite direction. Thus at p. 81 he writes :—"Language is a product of *association*. . . . Language is a product of an active, not of a passive, process; it is the child of *will*, not of sensation." The statement that language is "the child of will" seems to me practically identical with the assertion that "speech is the deliberate product of a conscious will," because the will here spoken of, being "an active process," is necessarily conscious.—A. H. KEANE.]

Notes on the Mode of Flight of the Albatross

WHEN watching the albatross one is struck with the fact that the bird gets up to windward without appearing to use his wings to a degree sufficient to account for the same. The sailors are satisfied with the explanation that he beats to windward. The conditions are of course not analogous to those of a ship sailing to windward. If the wind be very light, or if there be a calm, occasional powerful and obvious flapping of the wings occurs. If there is no wind, the birds often settle on the water round the ship. In very heavy weather the birds disappear altogether, probably settling on the water. Except that for breeding they resort to the islands, I believe they frequent the open ocean, where the surface is seldom without more or less swell.

On watching the flight of the albatross, one observes that in order to rise from the water violent and obvious flapping of the wings is necessary, which is continued some time after the wings cease to strike the water. After a start has thus been effected, if there is a fresh breeze, the wings are kept almost motionless. Sometimes the bird goes some distance with the impetus derived from the flapping of the wings at the start, but sooner or later he turns so as to expose the plane surface of his wings full to the force of the wind, rising at the same time some height above the water, and drifts off to leeward, thus soon acquiring the velocity of the wind; then swooping down into the hollow between two swells, he turns his head to windward, and keeping close to the surface of the water, sails along more or less against the wind for a surprising distance; finally, rising over the crest of a wave comparatively high into the air, and turning with his wings as before, so as to catch the wind to the fullest extent, he again lets himself drift off to leeward.

Thus the manœuvre he performs seems to consist in drifting with the wind in such a way as to attain its velocity very soon, and then turning round so as to make use of this velocity to carry him in the contrary direction.

Of course if he still remained exposed to the wind which had imparted to him its velocity he would not travel far against it before he came to a standstill, and he would certainly make no progress to windward; but by keeping close to the surface of the water, and as much as possible in the hollows between the waves, he is almost out of the wind; and in this comparatively calm region the impetus derived from the wind will carry him a long distance in exactly the opposite direction to that of the wind itself.

This manœuvre appears to be an important factor. No doubt the almost imperceptible movement of the wings may assist, though that this alone is insufficient to account for the progress to windward appears evident from the powerful efforts made with the wings in rising from the water and in calm weather. I have never had an opportunity to observe the albatross flying over land or over level water. If the manœuvre above described be an important factor, the birds then would have to use their wings much as they do in very light winds on the ocean. If very strong winds were blowing, they would have to settle on the land or in the water in order to remain at the locality. ARTHUR W. BATEMAN

A General Theorem in Kinematics

PROF. EVERETT (*ante*, p. 99) has overlooked in the introductory paragraphs of Prof. Schell's paper, to which he refers for the original statement of the theorem re-discovered by Prof. Minchin, the acknowledgment: "Der Mittelpunkt der Beschleunigungen und jene beiden Kreise wurden bereits 1853 von BRESSE gefunden." The reference is to the *Journal de l'École Polytechnique*, tom. xx., "Mémoire sur un Théorème nouveau concernant les Mouvements Plans, etc." By means of the "two circles" Bresse determines the point c (J) "qui aura une accélération totale nulle" (p. 82), and then by very ingenious application of kinematic principles deduces those relations to it which any arbitrary point (P) has, as given by Prof. Minchin. Bresse names c "second centre instantané de rotation."

University Hall, December 4 J. J. WALKER

Geometrical Optics

YOUR correspondent "P. C." (NATURE, vol. xxii. p. 607) asks information concerning a work, in English or French, on geometrical optics, thoroughly explaining the optical construction of telescopes and microscopes. I am not aware of any such publication these last forty years, but deem it possible that it may interest your correspondent to know of the existence of such a work in German by von Littrow, entitled "Dioptrik, oder Anleitung zur Verfertigung der Fernröhre." It was published, I believe, in Vienna about 1838. W. G. LOGEMAN

High Burghal School, Haarlem, Holland, November 17

[Littrow's "Dioptrik" was published at Vienna in 1830 in 8vo.—ED.]

Ozone

IF a slip of the prepared paper, used for testing for atmospheric ozone, be carefully moistened on one side with alcohol, using a clean camel-hair brush, on burning off the spirit and immersing the slip of paper in water the paper changes to a deep purple colour, as deep as No. 8 in Negretti and Zambra's scale of colours for ozone.

Is this due to the development of ozone? as, according to Schönbein, heat destroys ozone. J. P.

Leicester, December 5

PLANTS OF MADAGASCAR

DURING the present year no less than four separate collections of plants have been received at Kew from Madagascar, including in the aggregate about a thousand species, represented by specimens complete enough to be botanically determinable. As the hills of the interior of the island attain an elevation of 10,000 feet, its range of climate is considerable. We now know not less than two thousand Madagascar flowering-plants, and probably have almost exhausted its ferns, to which the collectors have paid special attention, and which are about 250 in number, so that we may consider ourselves in a position to draw broad general conclusions as to the botany of the island.

Amongst the tropical types there are a considerable number of endemic genera. The lemurs find their parallel in the vegetable kingdom in the *Chlænaceæ*, a natural order whose nearest affinities are with *Tiliaceæ*, *Dipterocarpeæ*, and *Ternstromiaceæ*, which is strictly confined to Madagascar, and comprises four genera and about twice as many species, to which the Rev. R. Baron, in these new collections, has added a well-marked novelty in a second species of *Leptolæna*. Altogether there are certainly not less than fifty genera confined to the island, some of them very curious types, as *Dicoryphia* in *Hamamelideæ*, *Ouvirandra* in *Naiadaceæ*, *Asteropeia* (placed in the "Genera Plantarum" in *Samydaceæ*, but which Mr. Baron's excellent new specimens will most likely have to be removed to *Linaceæ*), *Macarisia* in *Rhizophoreæ*, *Deidamia* and *Physena* in *Passifloreæ*, *Hydrotriche* in *Scrophulariaceæ*, *Canctia*, *Tannodia* and *Sphærostylis* in *Euphorbiaceæ*, *Pachnotrophe* in *Moreæ*, *Calantica* in *Samydaceæ*, and several each in the orders *Rubiaceæ*, *Melastomaceæ*, and *Compositæ*. To these endemic types the new collections add at last three, *Kitchingia*, a fine new genus of *Crassulaceæ* allied to *Bryophyllum*, with five or six species named after the collector of the first of the four parcels, *Rhodocodon*, a monotypic genus of gamophyllous *Liliaceæ* allied to *Hyacinthus*, and *Micronychia*, in *Anacardiaceæ*, also monotypic, figured lately in Hooker's Icones. Besides these the tropical flora of the island contains a large proportion: first, of endemic species of genera known elsewhere; second, of species

common to Madagascar, Mauritius and Bourbon, but not elsewhere known, such as *Pitlosporum Senacia, Aphloia mauritiana, Gouania mauritiana, Nesæa triflora, Lobelia serpens*, and *Buddleia madagascariensis;* thirdly, of species that spread across Tropical Africa, such as *Haronga paniculata, Desmodium mauritianum* and *oxybracteum, Gynura cernua, Brehmia spinosa*, and *Mussoenda arcuata;* fourthly, of species spread universally through the tropics of the Old World, but not reaching America, such as *Crotalaria stricta, Oxalis sensitiva, Nymphæa stellata, Trichodesma zeylanica, Indigofera enneaphylla, Avicennia officinalis*, and *Rhizophora mucronata;* and fifthly, of species spread universally through the tropical zone of both hemispheres, such as *Eleusine indica Tephrosia purpurea, Drymaria cordata, Elephantopus scaber, Teramnus labialis, Zornia dephylla, Waltheria americana, Sida rhombifolia*, and *Nephrodium molle*. In Mauritius and the Seychelles there are 145 species which occur also both in Asia and Africa, in addition to 225 which are spread all round the world in the tropical zone, and nearly all these 370 species are now known in Madagascar also. A small proportion of the Madagascar genera and species are Asiatic but not African, and these present collections add to the island flora *Lagerstromia, Buchanania*, and *Strongylodon*, three well-marked Indian types.

But perhaps still more interesting, in the light that it throws on the past history of the island, is the relationship of the comparatively limited flora of the mountains of the interior to that of other parts of the world. A certain number of the plants, especially the ferns and fern-allies, are widely-spread temperate species, which now have their head-quarters in the temperate regions of the northern hemisphere; we have instances of this in *Nephrodium Filix-mas, Aspidium aculeatum, Osmunda regalis, Lycopodium claratum, L. complanatum, Sanicula europæa, Potamogeton oblongus, Sonchus asper, S. oleraceus, Polygonum minus*. Most of the characteristic types of the Cape flora are represented on the Madagascar mountains, but nearly always by species which are distinct from those which are now found in the extra-tropical regions of the main continent: for instance, the Aloes by a couple of species of *Eualoe;* the Heaths by several species of *Philippia* and *Ericinella;* the bulbous Iridaceæ by species of *Gladiolus, Geissorhiza* and *Aristea;* the saprophytic *Scrophulariaceæ* by *Harveya obtusifolia;* the special Cape ferns by *Mohria caffrorum, Cheilanthes hirta, Pellæa hastata*, and *P. calomelanos;* the Proteaceæ by the curious genus *Dilobeia* (which Du Petit Thouars found at the beginning of the century, and of which Dr. Parker has now sent home the first specimens which have been seen in England); and the *Selaginea* by *Selago muralis* of Bentham, which grows in the grounds of the Queen's palace at Antananarivo. But perhaps the most interesting feature of all is the occurrence of several striking cases of specific identity between plants of the Madagascar mountains and those of the tropical zone of the African continent. The only Madagascar violet (*Viola emirnensis*, Bojer, = *V. abyssinica*, Steud.) only occurs elsewhere high up amongst the mountains of Abyssinia, at 7000 feet above sea-level in the Camaroons, and at 10,000 feet above sea-level at Fernando Po. The only Madagascar Geranium (*G. emirnense*, H. B. = *G. compar*, R. Br. = *G. simense, latistipulatum* and *frigidum*, Hochst.) has a precisely similar area of distribution. *Caucalis melanantha* of Bentham is only known in Madagascar and amongst the mountains of Abyssinia. The Madagascar *Drosera* (*D. madagascariensis*, D.C. = *D. ramentacea*, Burch.) reappears at the Cape and the mountains of Angola and the west tropical coast; *Agauria salicifolia*, Hook. fil., which we noted lately as having been gathered by Mr. Thomson on the high plateaux of Lake Nyassa, is found in the Cameroons and on the mountains of Madagascar, Mauritius, and Bourbon; *Crotalaria spinosa* reappears in Nubia, Abyssinia, Angola, and Zambesi-land; *Asplenium Mannii*, Hook., on the mountains of Zambesi-land, the Cameroons, and Fernando Po. As a whole, it would seem that the flora of the Madagascar mountains corresponds closely with that of the great ranges of the tropical zone of the main African continent.

J. G. BAKER

BENJAMIN COLLINS BRODIE, BART., F.R.S., D.C.L.

ON Wednesday, November 24 last, died Benjamin Collins Brodie the younger, a worthy son of a distinguished sire. Born to affluence, but early imbued with the liberal and high-minded views of the great surgeon, he determined to devote his life and energies to the prosecution of science for its own sake, and well has he done his work. Brodie was born in London in 1817, and educated first at Harrow under Longley, and afterwards at Balliol, taking his Master's degree in 1842. In those days it was absolutely impossible to carry out original chemical work at Oxford, and Brodie naturally betook himself to Giessen, where Liebig's name drew students from all parts of the world. There in the summer of 1845 Brodie, at Liebig's suggestion, carried out analyses of certain waxes obtained by Gundlach by feeding bees on different kinds of sugar. The results thus obtained led him to continue his examination of bees'-wax on his return to England, and from his private laboratory in the Albert Road now came forth his well-known researches on the Chemical Nature of Wax (*Phil. Trans.* 1848, 147-170; 1849, 91-108), for which in 1850 he received the well-merited reward of the Royal Medal. These researches will always remain not only remarkable as having given a successful solution of a difficult problem, but as having proved, by careful preparation and exact analysis, the existence in wax of solid bodies which play the part of alcohols, and of which common spirit of wine is a direct lineal descendant. This unexpected discovery of solid alcohols containing respectively twenty-seven and thirty atoms of carbon in the molecule completely confirmed the truth of the views concerning the existence of an homologous series of alcohols first enunciated by Schiel and Gerhardt, and thus placed in firm position one of the chief pillars of the organic portion of our science.

Brodie's next work was not inferior either in importance or in workmanship to his first. In 1850 he published his memoir "On the Condition of certain Elements at the Moment of Chemical Change" (*Phil. Trans.*, 1850, 750-804), in which he carefully investigates the remarkable reducing action exerted by peroxide of hydrogen. Not only does this body lose half its oxygen when brought in contact with oxide of silver, but reduces this oxide to metal. This anomalous action was satisfactorily explained by Brodie, who pointed out that the second atom of oxygen in these peroxides is not only retained in an unstable state of combination, but that when brought into contact with silver oxide a true synthesis of oxygen occurs, two atoms of this element uniting to form one molecule of free oxygen. That this reaction really takes place was shown by Brodie to be the case by careful experiment. These results led him to consider the constitution of the alcohol radicals (*Chem. Soc. Journ.* iii. 405), and to assert in 1851 the important fact, now universally admitted, that the molecule of the radical ethyl contains four atoms of carbon. To him too we owe the prediction of the possibility of the existence of the mixed radicals, a prediction so soon afterwards experimentally verified by Wurtz. Next we find him active as secretary of the Society of which he afterwards became president, viz. the Chemical Society of London; also in lecturing at the Royal Institution on the allotropic changes of certain elements, on the formation of hydrogen and its homologues, in which

he clearly brings forward his views concerning the union of atoms to form the molecule.

In 1853 he published his interesting observations on the conversion of yellow phosphorus into the red modification by heating it to 200° in presence of mere traces of iodine (*Chem. Soc. Journ.* v. 289). Another very important and difficult investigation which occupied much of his attention about this time was the question of the purification (*Ann. de Chimie*, 45, 351) of graphite, and the determination of its "atomic weight" (*Phil. Trans.* 1859, 249). By heating graphite with strong nitric acid and chlorate of potash, Brodie showed that, unlike all the other modifications of carbon, graphite yields a remarkable crystalline acid, to which he gave the name of graphitic acid, having the formula $C_{11}H_4O_5$. The existence of this interesting body led Brodie to the conclusion that graphite may be considered as a peculiar radical, to which he gave the name of graphon. In the year 1855 Brodie was appointed Waynflete Professor of Chemistry in the University of Oxford, a position which enabled him to throw all his influence into forcing the recognition of chemical science as a proper object of academic training. Under his fostering care the science which had hitherto been so long neglected put out distinct signs of life: new laboratories and lecture-rooms were built, to which students flocked in numbers, and Oxford saw the unwonted sight of her professor of chemistry busily engaged in original investigation, as well as in the tutorial duties of his chair. The discovery of those singular and dangerous bodies, the peroxides of the organic radicals (*Proc.* Roy. Soc. ix. 361, *Phil. Trans.* 1863, 407), was made in the laboratory of the New Museum. The same laboratory soon afterwards saw the minute and careful investigation on ozone (*Phil. Trans.* 1872, 432), which proved beyond doubt or cavil that the supposition that the molecule of ozone is represented by the formula O_3 is both necessary and sufficient to explain all the observed phenomena.

Next we find him experimenting on the synthetic production of the hydrocarbon methane, as well as of formic acid, by the direct union of hydrogen and carbon monoxide under the influence of the electric spark. Then he examines the effect of an induced electric current upon pure and dry carbonic acid, and proves that this gas is partially decomposed with formation of carbon monoxide and oxygen, the latter gas being converted into ozone. And he then proceeds to ask whether the ozone thus produced is identical with that obtained from ordinary oxygen, and by a series of careful quantitative experiments demonstrates the identity of the ozone from these two sources.

This was Brodie's last experimental investigation. Ere long he resigned the Chair of Chemistry at Oxford, regretted by the whole University. He retired to his charming seat on the summit of Box Hill. Neither his own scientific activity nor his deep interest in the scientific work of others ceased on his withdrawal from professional life. Before his retirement he had put forward (*Phil. Trans.* 1866, 781-860) in his "Calculus of Chemical Operations," views altogether novel respecting the nature of chemical change. In place of the usual mode of considering this as due to a change in the relative positions of the atoms of which matter is composed, Brodie founds his theory of the constitution of chemical elements and compounds on the simple volume-relations discovered by Gay-Lussac to exist between these substances in the gaseous state. To hydrogen Brodie gives a simple symbol, because the unit of hydrogen can, as he expresses it, be conceived as made at once by one operation, whilst to oxygen he gives a double symbol, because it cannot, according to him, be made by less than two operations. The element chlorine is supposed to be made up of three operations, and a treble symbol is given to this body. Concerning the probable or possible decomposition of the elements Brodie naturally speculates. His analysis had led him to suspect that "chemical substances are really composed of a primitive system of elemental bodies analogous in their general nature to our present elements, some of which we possess, but of which we possess only a few" ("Ideal Chemistry," p. 54). But no experimental evidence of this fact was offered by him, and none of a satisfactory character was otherwise forthcoming, until Victor Meyer announced his belief that chlorine was capable of undergoing decomposition at high temperatures.

Here was a proof of the truth of Brodie's complex symbol! Sad to say, further experiment has not corroborated this conclusion. No substance differing essentially from chlorine has yet been got from this body. Even the change of density at a white-heat appears in the case of chlorine to be, to say the least, doubtful. So we are left for the present, and the author of the "Calculus of Operations" is left for ever, without the experimental confirmation of his conclusions which he so much desired. Whatever may be the verdict of the future as to the value of Brodie's Calculus, there is no doubt that science is indebted to him for an altogether new view of chemical combination obtained by a systematic analytical process.

This occasion is not a fitting one to enlarge upon the high personal character of the late Sir Benjamin Brodie. Suffice it to say that in all relations in life, in the domestic circle as in society, in the chair at Burlington House as in that at Oxford, he displayed all those qualities of heart and head which alone give dignity and sweetness to life, the possession of which ensures for his memory a lasting place in the minds of all those who were fortunate enough to count him amongst their friends. H. E. R.

THE PHYLLOXERA IN FRANCE

THE new vine-disease, due to the *Phylloxera vastatrix* Planchon, has already caused much damage to the French vineyards and wine-production. From the taxes arising from that national industry France derives a considerable part of her revenue; and this subject has consequently occasioned innumerable publications and investigations. Of the latter some have been empirical and without result; others, which were conducted scientifically, have alone been of any use. It was moreover absolutely necessary to have an unswerving confidence in exact observations, in order to persevere in making experiments which are often disturbed and rendered apparently self-contradictory by the secondary and ever-varying conditions of cultivation. These experiments have at last been crowned with success, and now there are decidedly good grounds for hope. For the last two years the public have shown a steadily increasing confidence in scientific methods.

One of the most distinguished chemists, a man of whom France is proud, and with whom readers of NATURE are well acquainted, especially as they were lately presented with his portrait and biography, M. Dumas, applied himself to the study of the Phylloxera, and pursued his task from day to day with keen determination, notwithstanding the attacks of some and the discouraging advice of others. It is his well-intentioned and unceasing diligence that we must thank for never having lost heart; it is to him that those results are due which are presently to be indicated. When the pébrine-disease was raging on silkworms in the South of France, it was by his personal suggestion and repeated encouragement that M. Pasteur agreed to devote himself to that difficult study; and it is the same gentle influence and guidance that have directed the present writer, together with several others, especially MM. Balbiani, Duclaux, and Mouillefert.

Henceforward the principal problems raised by the study of vine diseases are solved. They were solved one after another in regular order, as fresh light appeared and the ends to be aimed at became more definite. It cannot

be too frequently repeated that that is due, not to a happy hit or to guess-work, but to an unceasing and skilfully conducted struggle which was kept up with indomitable persistence in the midst of obstacles caused by many selfish interests. Times are greatly changed since M. Dumas[1] protested, in discreet but unmistakable language,



FIG. 1.—Map showing the spread of Phylloxera in France from 1865 to 1872. (See NATURE, vol. x. p. 504.)

against the indifference of a French Minister of Agriculture who tried to beat down a grant of 10,000 francs necessary for continuing the scientific investigation. On the same occasion he drew attention to the praiseworthy initiation taken by the railway companies and by various private gentlemen. M. Tirard, the present Minister of Agricul-

[1] Académie des Sciences, February 23, 1874.

ture, has obtained several large grants,[1] and proposes to ask still much larger ones for the approaching campaign, being anxious to assist in every way the laborious struggle. M. Tisserand, the new Director at the Office of Agriculture, a man of great energy and ability, has resolved to back up all his efforts, and has instituted a special central staff to take charge of all documents and operations. The Higher Phylloxera Commission, formed by order of the Minister, has also shown activity: it has adopted a general legislative scheme in order to supply the Government with the arms necessary to defend the threatened territory.

Switzerland and Germany soon adopted similar measures; and with reference to England we must remark that the Phylloxera question may soon become something different from a mere matter of curiosity. Are there no important vineyards in England? We are told that at Liverpool alone, in the "Vineries," there are forty hectares of vines grown under glass. The Phylloxera was observed by Mr. Westwood before it was known in France. It is still found here and there in Ireland, in Scotland, and not far from London itself. By the admirable cultivation under glass, in which English vine-growers are unrivalled, it is kept within narrow limits, but it might


OCEAN
ESPAGNE
SUISSE
ITALIE
Districts in which only a few points were assailed by Phylloxera
Districts more gravely assailed, but in which the introduction of foreign vines, or vines from districts in which Phylloxera have appeared, is not authorized
Districts completely invaded in which the introduction of foreign vines, or vines from districts in which Phylloxera have appeared is authorized

FIG. 2.—Map showing the spread of Phylloxera in France up to 1880.

be communicated to other places. In Switzerland one single parcel of plants is reported to have brought the parasite to Geneva, Schafthausen, and Neuchâtel. In any case, should an international convention be instituted, the enforced examination at the frontiers would hamper the trade in those magnificent English grapes. The rigorous measures taken against the cattle-disease suffice to show what may be necessary in order to defend the leaf or shoots of the vine.

Extent of the Disease.—The increase of the disease is considerable; thus at the beginning of 1877 there were only twenty-eight departments attacked, whereas at the beginning of 1879, according to the official statistics, there were thirty-nine. Those in the previous year, in order of date,[1] were Loir-et-Cher, Haute-Garonne, Gers, and Corrèze. In 1878 Aude, Pyrénées-Orientales, Haute-Loire, Vienne, Indre, Côte-d'or, and Savoie. In 1879, Haute-Savoie, Jura, Arriège, and Tarn. A special inquiry enables us to determine what area had been invaded in the end of 1879:—the invaded vineyards which had not yet succumbed were 319,760 hectares in

[1] One of 300,000 francs, which has since been doubled.

[1] "Le Phylloxéra, &c.; Rapports publ. par le Ministère de l'Agric." 8 fasc., p. 9. (Paris: Masson, 1879.)

extent, or 76,722 more than the preceding year; the vineyards destroyed, 474,760; or 101,317 more than the preceding year (1878).

There is unfortunately reason to fear that the isolated points may join each other and the affected patches unite. The patches, whether distinct or uniting, increase about 15 kilometres every year; and since the increase in any direction is proportional to the time, the increase of area is as the square of the time. In other words, after 2, 3, 4, 5 years, the evil is increased 4, 9, 16, 25 times. By merely looking at a map showing the extent of the plague, one can form an idea of the invading march of the terrible insect.

Yet there are actually men of science in France who join in depreciating those who are employed to battle with this fatal disease. It is sad to see the reception met with by those who have sacrificed their time, health, and scientific reputation to undertake duties so beneficial to their country. "They are merely wasting their time," say they; "much better not have left their personal duties;" and, true enough, those of whom this is said have cruelly felt its truth. M. Dumas, however, is not one of those.

Several years ago a prize of 300,000 francs was instituted to encourage investigations as to the best remedy against the phylloxera. Much ingenuity was wasted, many absurd remedies proposed, and it is curious to note the substances which were lauded by the inventors. They were for the most part the same, mixed in different proportions—tars, sulphur, lime, soot, urine, phenic acid, and salts of copper or iron. Patient research and scientific study have alone produced certain results.

These results, however, were not accepted and acknowledged without difficulty. Objections were accumulated and many instances of partial failure were brought together, ill-will and inertia playing an important part in the business. Local influences, political opinions, and other extraordinary considerations, one after another, opposed or favoured the results which were gained. At present the question has once for all entered upon a better path, the charlatans and pretended vine-doctors having entirely lost their credit. We are in possession of four modes of treatment which are really efficacious, though they vary in their effects in different cases. The struggle therefore should be maintained.

The various conditions of application and the entirely different principles which the application follows explain the divergence of opinions and methods. The scientific remedy is given: practice will decide which of the four methods is at the same time most efficacious and most economical. This happy result must mainly be attributed to the Commission of the Academy of Sciences, which was presided over by M. Dumas, who was the very soul of it. This Commission sent "delegates," who severally studied special clearly-defined questions, like officers sent by a general to make a reconnaissance in a country.

The commissions instituted in the departments did much good work, especially that of Hérault, which contained several distinguished members, both vine-growers and scientists: MM. Marès and Planchon, Members of the Institute of France; M. Bazille, Senator; M. Vialla, &c. We must also notice particularly the Viticultural Station at Cognac, which was established by private subscription, after the English manner,—a thing of rare occurrence in France. It was M. Lecoq de Boisbaudran, now Member of the Institute, the discoverer of the metal *Gallium*, who first started the idea, and triumphantly realised it in his native town. The principal houses in the trade made it a point of honour to subscribe, and the expenses in four years reached a sum not less than 32,000 francs. It was there that the general experiments as to "insecticides" were made, in accordance with the simple method proposed by M. Cornu, Director of the Viticultural Station, in order to determine definitively what substances are powerless. This work of "clearing the way" necessarily occupied several years, the practical part being energetically carried out by M. Mouillefert, of the National School of Agriculture at Grignon, near Paris, sub-director of the Viticultural Station. Towards the end of the first year they began to distinguish clearly the small group of substances which alone should be utilised. Amongst them was carbon disulphide (CS_2), which had been indicated by Baron Thénard, abandoned and then eagerly resumed by the enthusiastic M. Monestier, and at last rejected in a general manner in the end of 1873 and during 1874.

The carbon disulphide by itself appearing too dangerous to human life, M. Dumas happily started the idea of using it in combination with sulphide of potassium, forming the sulpho-carbonate of potassium ($KSCS_2$), which is both a powerful "insecticide" and an energetic manure.

The conclusions reached by the experiments made at Cognac were published towards the end of 1874 in the Report of the Academy of Sciences (last quarter), and the author can still defend every one of them as they were then deduced, a rare circumstance in connection with the phylloxera.

Under the happy influence of the Minister of Agriculture, the vine-growers were grouped into "vigilance-committees" for watching, and "syndicates" for treating, the vines. Thus the indifference of some and unreasoning excitement of others were followed by energetic preparation for the struggle. At the end of 1878 there were sixty committees instituted in fifty-six departments, and now there are 221, embracing sixty-one departments. Some of them have obtained decidedly successful results, and thus furnished a powerful incentive for the others to persevere.

The expense of the applications is still considerable, but in any case the most valuable vines are now out of danger. The more common vines will at first cost a good deal, but we are confident that scientific skill will supply sulphate of carbon either free or in combination at a cheaper rate, and that practical experience will render its application more easy and less expensive. France will thus continue to produce her wines, and have the pleasure of offering them to her friends and neighbours. This, though apparently a mere wish, is an actual statement of fact.

MAXIME CORNU,
Delegate of the Academy of Sciences, and formerly Director of the Viticultural Station at Cognac

NOTES

THE following are the arrangements for the Friday evening meetings of the Royal Institution of Great Britain before Easter, 1881:—January 21, Warren De La Rue, D.C.L., F.R.S., Sec. R.I., The Phenomena of the Electric Discharge with 14,400 Chloride of Silver Cells; January 28, Dr. Andrew Wilson, F.R.S.E., The Origin of Colonial Organisms; February 4, Dr. Arthur Schuster, F.R.S., The Teachings of Modern Spectroscopy; February 11, Robert S. Ball, LL.D., F.R.S., The Distances of the Stars; February 18, Sir John Lubbock, Bart., M.P., D.C.L., F.R.S., M.R.I., Fruits and Seeds; February 25, Dr. J. S. Burdon-Sanderson, LL.D., F.R.S., Excitability in Plants and Animals; March 4, Sir William Thomson, LL.D., F.R.S., Elasticity viewed as Possibly a Mode of Motion; March 11, uncertain; March 18, Wm. H. Stone, M.D., Musical Pitch and its Determination; March 25, Alexander Buchan, M.A., F.R.S.E., Sec. Met. Soc. Scot., The Weather and Health of London; April 1, uncertain; April 8, Prof. Tyndall, D.C.L., F.R.S., M.R.I.

THERE is nothing that will tend to keep our learned societies in so wholesome a condition as healthy public opinion; it is

therefore a matter for congratulation when we see a paper like the *Times* taking an interest in the organisation and work of the Royal Society, and giving its opinion on these, even when the justice of that opinion is questioned by many. From a leading article in the *Times* of Thursday last, on Mr. Spottiswoode's address, we take the following passage:—"The election to the vacancies in its ranks has of late years been too manifestly governed by a tendency to set up as an idol something which it is technically fashionable to call 'research,' and to ignore the far higher mental effort which is required for successful ratiocination. A man sets to work with a microscope and a test-tube, performs a number of curious experiments, and announces an interesting discovery which can neither be confirmed nor refuted by any one who does not follow precisely in his tracks. Such an experimenter, before now, has been rewarded by the privilege of placing the letters F.R.S. after his name; although, when the privilege had been conferred beyond recall, it may have been shown that his 'research' was undermined by the neglect of some essential precaution, and that his conclusion was erroneous. On the other hand, the man who gathers up the scattered facts ascertained by others, and founds upon them a weighty and important generalisation, is not on that account thought worthy of the Fellowship; and if he desires to obtain it is almost compelled to engage in some colourable 'research' as a means of gratifying his wishes. The principle thus acted upon is as much a mistake as it would be to glorify a carpenter or a mason and to ignore an architect; and it points to a narrowness of view which might profitably give place to a more accurate sense of relative proportion. The award of a medal to Prof. Lister, notwithstanding the great and direct utility of his work, is possibly an indication that better counsels may in time be expected to prevail."

We understand that the Rev. Osmond Fisher has in the press, and will shortly publish, a new work entitled "Physics of the Earth's Crust." The volume will contain selected and revised portions of papers which have appeared at various times in the *Transactions* of the Cambridge Philosophical Society and other scientific publications, together with new matter. Mr. Fisher will in some chapters apply mathematical methods, but there will be found much matter calculated to interest those readers who do not care for that mode of reasoning.

The meeting of the British Medical Association for the year 1881 will be held at Ryde, in the Isle of Wight, to which locality the Association has received a cordial invitation from nearly the whole of the medical profession in the island. Mr. Benjamin Barrow, an old and much-respected practitioner in Ryde, has been appointed president-elect. The Council of the Town of Ryde have passed a unanimous resolution that the whole of the Corporation Buildings, which are numerous and spacious, shall be placed at the disposal of the Reception Committee. There is every reason to believe that the many beautiful private grounds in the Isle of Wight will be thrown open to the Association. The president will give a garden party to the members and residents in the island. A *soirée* will be held in the Town Hall and adjoining buildings. The address in medicine will be given by Dr. John Syer Bristowe, London, of St. Thomas's Hospital; the address in surgery will be given by Mr. William Dalla Husband of Bournemouth, Consulting Surgeon to the York County Hospital; and an address in obstetric medicine by Dr. John G. Sinclair Colhill of Ventnor. Such has been the spirit with which the movement has been taken up by the Members of the Association and profession in the Isle of Wight and Ryde that the meeting bids fair to rival any previous meeting both in science and pleasure.—The following grants in aid of scientific investigation for the year were made, viz.:—Dr. McKendrick and Committee, Glasgow, for a continued investigation on anæsthetics, 25*l.*; Dr. Gerald Yeo, London, on the efficacy of the antiseptic method in injuries of the brain, 50*l.*; Dr. Shin, London, for a continued investigation on parasitic skin diseases, 25*l.*; Mr. W. North, London, for a continued investigation on the relations which exist between nitrogenous egesta and muscular work, 50*l.*; Dr. D. J. Hamilton, Edinburgh, an investigation on the pathology of the brain, 30*l.*; Mr. Watson Cheyne, London, an investigation on the relation of organisms of septic disease, 25*l.*; Dr. Augustus Waller, London, an investigation on the time and relations of muscular contractions in the human body in health and disease, 20*l.*; Dr. Alexander Ogston, Aberdeen, a continued investigation on the relation between bacteria and surgical disease, 10*l.*; Dr. Newman, Glasgow, a renewed grant in aid of an investigation on the functions of the kidney, 10*l.*; Drs. Braidwood and Vacher, Birkenhead, to illustrate the third and final report on the life history of contagium, 20*l.*

In the Vienna Gewerbeverein, Herr F. Siemens has been lecturing on his "regenerative gas-burner," in which the departing heat of the flame serves for pre-heating the air and the gas to be consumed. The products of combustion of the flame, collected in a short chimney, flow away cold, either into the room or to the open air. The light, according to measurements, has twice to three times the illuminating power of the best-known gas-burners, and is remarkably white and steady.

The death is announced of Dr. Lauder Lindsay, F.R.S.E. F.L.S., at Edinburgh, on November 24, at the age of fifty. Dr. Lindsay's name must be known to our readers as an occasional contributor to our columns. Dr. Lindsay did some good work in botany and geology, and took special interest in the subject of intelligence in the lower animals. In 1870 he published a "History of British Lichens," and quite recently we reviewed his work on "Mind in the Lower Animals," published last year.

On Monday a deputation, consisting of Mr. Ernest Hart, Prof. Chandler Roberts, F.R.S., Col. Festing, the Rev. H. V. Le Bas, the Rev. S. A. Barnett, Mr. S. Hadley, Mr. W. R. E. Coles, and others, had an interview with the Lord Mayor at the Mansion House, to interest him in the efforts now being made by the joint committees of the National Health and Kyrle Societies to reduce the mischief arising from the present excessive production of smoke in the metropolis. Mr. Ernest Hart said the Societies thought that a very great deal might be practically done to make the atmosphere in London as pure as that in Paris. It was proposed to conduct trials of the various kinds of fuel and to promote competitive testing of the appliances available at present, or which might become available, for the purpose of lessening the production of smoke. The smoke proceeding from the fires of private houses might be materially lessened by the use of improved apparatus, and that from factories might be abated with little interference with the manufacturing interests if the employers would only co-operate with the Societies towards that end. There was about to be an exhibition at South Kensington of the different kinds of apparatus and fuel, which would be practically tested. They now asked the Lord Mayor to let them bring the matter before the notice and attention of the citizens by means of a meeting at the Mansion House on the subject. The Lord Mayor thought it a matter well deserving the public attention, and he would gladly allow a conference in the Long Parlour of the Mansion House on Friday, January 7.

In connection with the subject of Incandescent Electric lighting it is of interest to notice in the New York *Times* an account of an experiment in this direction. At a reception given on the evening of November 17 by Prof. Henry Draper to the members of the National Academy of Sciences, a part of his house was

lighted by the Maxim light. The laboratory was lighted by eight Maxim electric lamps, which were screwed into the chandeliers in place of the ordinary gas burners. The large laboratory, it is stated, was as light as the open fields at noonday, and there was no flickering or unsteadiness in the light. In shape the lamps are precisely similar to those used by Edison, but H. S. Maxim, who holds the patent on them, claims to have improved on Edison's plan, by making his lamps more permanent. Like Edison, he uses a carbonised fibre, in the form of a horseshoe, but unlike him, does not inclose this fibre in a vacuum, and considers that his lamp is complete. An atmosphere of gasoline vapour is introduced into the glass globe which holds the carbonised fibre, and in this atmosphere the fibre is gradually heated by the electric current. As soon as the heat reaches a sufficient intensity it begins to decompose the hydrocarbon of which gasoline vapour is composed, and if there are any weak spots in the filament the freed carbon is deposited there and strengthens the fibre. A current of increasing intensity is thus carried through the carbonised fibre, which constantly grows at the expense of the gasoline vapour, and finally becomes of a uniform power of resistance throughout its whole length. The gasoline vapour is then pumped out of the globe and the lamp is ready for use. The Maxim lamps are said to give a larger amount of light than any incandescent lamp hitherto constructed. According to experiments made by Prof. Morton, of the Stevens Institute, it appears that the lamps have produced light at the rate of 600 candles per horse-power of current. Each of the eight lights in Prof. Draper's laboratory had an illuminating power of about fifty candles. The electric current for the lamps was furnished by a Maxim dynamo machine, which was driven by a gas-engine of four-horse power, located in the laboratory. The Maxim machine has an armature something like that of the Gramme machine, while its field magnets resemble those of the Siemens machine.

THE recent importations into this country of cinchona bark from Jamaica and the high prices realised have been the means of causing a considerable amount of attention to be drawn to this new source of supply. From a document recently drawn up by Mr. Morris, Director of Public Gardens and Plantations in Jamaica, it seems that the results of the cinchona sales for the year 1879-80 have been as follows:—Quantity of bark shipped 27,399 lb., gross amount realised £5380 9*s.* 6*d.*, net sum realised £5146 8*s.* 7*d.* Without going into details it will suffice to show the superiority of Jamaica bark over that from Ceylon by saying that for red "root bark" the highest price for Jamaica produce was 4*s.* 8*d.* per pound for "good root" as against 2*s.* 6*d.* for "good root" from Ceylon, thus showing an advantage in favour of Jamaica root bark to the extent of 2*s.* 2*d.* per pound. Thus again for "twig and small ordinary" bark of *C. succirubra* Ceylon produce obtained from 2½*d.* to 1*s.* per pound as against 10½*d.* to 1*s.* 6*d.* per pound for similar bark from Jamaica. From this, together with the fact that an enormous number of plants are now in stock in Jamaica, the future of cinchona cultivation in that island seems to be ensured.

IT is stated in an American contemporary devoted to electrical topics that a call has lately been made on the shareholders of the Edison Electric Light Company to the amount of sixty dollars per share. The object of the call was "to meet the expense of recent experiments."

IMPORTANT trials have been made lately on the Rhine, in order that navigation may be carried on at night by means of the electric light. It is hoped that soon satisfactory results will follow, which will probably develop an entirely new phase in river navigation.

IN the neighbourhood of Agram, at the mountainous places St. Simon and Remete, some shocks (of slight importance) were felt up till December 1. At Dortmund, on November 27, a considerable shock occurred at 5.50 a.m. It lasted several seconds, and the direction was south-south-east, barometer 756, temperature 7° R. A rather smart shock of earthquake, accompanied by a loud subterranean noise, was felt at Schaffhausen on Wednesday night last week. The Rev. Dr. Dixon of Beragh, near Omagh, writes that a slight earthquake shock was distinctly felt there on the afternoon of Sunday, November 28, at about half-past five. The peculiar character of the shock was most marked. It appeared to travel from south-west to north-east.

IN the course of his experiences as a medical missionary among the Mongols the Rev. James Gilmour has gathered some interesting information regarding their inner life, but perhaps the most curious item is that Mongol doctors are not entirely unacquainted with the properties of galvanism. It is said that they are in the habit of prescribing the loadstone ore, reduced to powder, as efficacious when applied to sores, and Mr. Gilmour states that one man hard of hearing had been recommended by a lama to put a piece of loadstone into each ear and chew a piece of iron in his mouth!

THE French Great Western Company instituted last year a competition in the large hall of St. Lazare Station, between the Jablochkoff and Lontin light and the gas company. The conclusions were in favour of the electric light, but the gas company having declared that they would abolish entirely the special price charged on the Great Western Company if they declared in favour of gas, the gas lamps have been restored.

Les Mondes gives the following old recipe for testing the age of eggs, which, it thinks, seems to have been forgotten. Dissolve 120 grammes of common salt in a litre of water. An egg put in this solution on the day it is laid will sink to the bottom; one a day old will not reach quite to the bottom of the vessel; an egg three days old will swim in the liquid; while one more than three days old will swim on the surface.

THE *Launceston Examiner* (Tasmania) of October 6 contains some account of a shaft that had been sunk for a well at a brewery at Launceston, near the river. Little water was met with, but some interesting observations were made. The shaft had been sunk to a depth of ninety-eight feet. The strata passed through are of a very interesting character. For a little over thirty feet strong clay was met with, then deep beds of compact sand separated by bands a few inches thick of fine quartz conglomerate. About forty feet from the surface considerable quantities of partially carbonised wood were found, extending thence to the bottom of the shaft. The wood is evidently pine, and appears to be identical with that found in the shaft of the Working Miners Company at Brandy Creek, at a similar depth below the river. The grain of the wood is perfectly distinguishable, but the transverse fracture is black and lustrous like jet. The trees must have been of a large size and very abundant, and the great mass of earth that has accumulated above their remains enables one to form some idea of the vast period that has elapsed since they flourished. The great depth of the stratum in which this fossil wood occurs proves that its deposition must have proceeded without material interruption through vast periods of time. It is a little curious that though vegetable remains occur so profusely in the freshwater deposits of the Windmill Hill, and at considerable depths both here and at Beaconsfield, no trace has yet been found of contemporaneous animal life.

THE *Cape Argus* for November 6 contains a full report of a paper read at the Cape Philosophical Society by Mr. J. G. Gambie, containing many useful suggestions as to important problems, especially in meteorology and geology, that await solution in South Africa. Residents and travellers in South Africa would no doubt find the paper suggestive.

PHYSICAL NOTES

MR. J. E. H. GORDON has lately patented a method of producing light from electricity based upon Mr. Spottiswoode's suggestion to apply the alternating-current magnetoelectric machine of De Méritens to the induction-coil. Mr. Gordon arranges small balls of platinum or iridium, or of an alloy of these metals, at the ends of fine platinum rods in pairs in the middle of a suitable globe, and causes to pass between them a rapid succession of sparks whereby they are raised to incandescence. There is no consumption of carbon or any other substance, and the lamps may be connected either in series or in parallel branched arcs. The principal remaining disadvantage is the noise attendant on the rapid sparks. A mechanical contrivance is added to bring the knobs near together when no current is passing in the primary coil. The induction-coils used are of comparatively small size.

M. TERQUEM (*Jour. de Phys.*, October) prepares, for the receivers of air-pumps, brass plates with a circular groove, in which is put a mastic fusing about 60°. The plate is placed over a vessel of heated water, and when the mastic is fused the receiver is brought down into the groove. When cool, the plate adheres to the jar. These receivers are tubulated, and a caoutchouc stopper in the tubule holds a tube bent at a right angle and provided with a stopcock like those used by M. Carré in his air-pump. For experiments with the air-pump several receivers with their plates can be easily prepared beforehand.

M. LIPPMANN points out (*Jour. de Phys.*, October) that full justice has hardly been done to Carnot with reference to his law (in thermodynamics). It seems to have been forgotten that he verified the law directly by experiment; and did not merely (as is found stated in excellent treatises) furnish a demonstration *à priori* based on the indestructibility of heat. This is doubtless due to the fact that Carnot's original work has long been exhausted and unobtainable. M. Lippmann considers that work a mine imperfectly explored.

EXPERIMENTS have been made by M. Hesehus of the St Petersburg Physical Society, as to the variations of volume and coefficient of elasticity of palladium and its alloys under the influence of hydrogen absorbed. The alloys contained 25 per cent. of gold, silver, and platinum. Wires 500 mm. long and 0·4 mm. diameter served successively as cathode in electrolysis of dilute sulphuric acid in a long vertical glass tube, where they were stretched by weights so that their length could be measured directly with a cathetometer. The alloy containing silver showed the greatest increase of length, 11·7 mm.; palladium-platinum 6·14 mm.; pure palladium 5 mm.; and palladium-gold only 0·9 mm. With a current of six bichromate elements, the elongation, very rapid at first, reached its maximum after nearly an hour. The shortening after breaking the current proceeded in a similar way, but less rapidly; *e.g.* for palladium wire it was only 2·6 mm. after twenty-four hours. Some experiments were made with the aid of a recording apparatus, and they also proved that, contrarily to Graham's opinion, the absorption of hydrogen takes place more quickly than the reverse action, and even when electrolytic oxygen is made to act on the wire (used as anode). M. Hesehus made a special delicate apparatus for measuring small variations in the length of wires. With this it was proved, that during the first day the shortening of the wire charged with hydrogen decreases very quickly, about the third day it becomes constant; it again decreases rapidly about the seventh day, then approaches zero asymptotically. This agrees with MM. Troost and Hautefeuille's experiments on the tension of hydrogen of palladium.

A PLUVIOMETER which registers the quantity of rain, and the duration and hour of the fall, is described by S. Grimaldi in *Rivista Scientifico-Industriale* for October 15.

IN a recent note to the Vienna Academy, on the relation of the daily and yearly variation of temperature to the eleven-years sun-spot period, Herr Liznar first compares observations of the daily variation at thirteen places (including St. Petersburg, Calcutta, and Hobarton), and finds for all some correspondence with the sun-spot curve. The curve from data for Vienna, Prague, Caslan, Brünn, and Trieste from 1857–70, brought to an average, shows, for the minima of this variation in 1859–60 and in 1870–71, a very good agreement with the corresponding maxima of the sun-spot curve; while the maximum of the variation precedes the minimum of the spots by about two years. With regard to the yearly variation of temperature, Dr. Hahn's results for Leipzig are fully confirmed by data from eight other places in Europe, the variation showing a maximum and minimum corresponding to the maximum and minimum of spots.

THE combinations formed by phosphuretted hydrogen with hydrobromic and hydriodic acids have been long known. Its combination with hydrochloric acid has lately been effected by M. Ogier (*Jour. de Phys.*, November) by compressing equal volumes of the gases in M. Cailletet's apparatus. Compressing about 20 atm. at + 14°, small yellowish bright crystals appear, and with sufficient pressure the two gases disappear entirely (if the mixture have been well made), the tube being covered with a crystalline coat without trace of liquid. If the upper part of the tube be heated with tepid water (+ 20°), the compression produces a liquid layer. If the tube be slowly cooled, and 60 or 70 atm. maintained, so as to get only a small layer of liquid, the combination forms slowly in crystalline state. Sudden compression, without external heating, will also produce the liquid. On the other hand, if before there is any deposit of crystals the pressure be relaxed (from 25 atm. *e.g.*) one perceives not a mist, but small, light, solid flocks, which slowly go down the sides of the tube and disappear. The combination can also be produced under cold without pressure; crystals are formed about − 30°. If the compound exist in the gaseous state, it is almost wholly dissociated at ordinary temperature and pressure.

AN amplifying barometer has been invented by M. Debrun (*Jour. de Phys.*, November). Suppose a Fortin barometer, in the tube of which the mercury is kept at a constant height. The cistern has two other vertical tubes open to the atmosphere, one rising out of the mercury, the other from water over the mercury. The variations of the water in the latter are read with the aid of a scale, and they are thirteen and a half times greater than those of the mercury in the other open tube.

RECENT experiments in capillarity by Herr Volkmann (*Ann. der Phys.*, No. 10) have led him to the following results:—1. The influence (affirmed by Wilhelmj) of curvature of the wall on constants of capillarity cannot be maintained, and is explicable by the supposition of a faulty determination of specific gravity. (The arrangement of the index is also objectionable.) 2. Observation of the height of rise between parallel plates warrants the assumption of a constant wall-layer, on which the liquid rises. 3. The thickness of the wall-layer in the case of neat's-foot oil and alcohol is found constant for plates and tubes at 0·004 mm. 4. In so far as the results with neat's-foot oil and alcohol may be extended to other wetting liquids, no influence of curvature of the wall on constants of capillarity is demonstrable.

PROF. SILOW of Moscow has studied the magnetism of iron chloride solution by the method of induced currents (*Ann. der Phys.* No. 10), and finds that the coefficient of magnetisation is not a constant, but a function of the force of separation. As the latter gradually increases, the former at first increases too, and pretty quickly, but reaches a maximum and then decreases, first quickly, then slowly. The liquid is therefore relegated to the same class of magnetic bodies as iron, steel, or nickel, and the author considers that probably all magnetic bodies show this rising and sinking of the coefficient.

IN a paper which appears in the *Ann. der Phys.* (No. 10), Herr Hankel gives the chief results of his study of the photo- and thermo-electric properties of fluor-spar. He states, *inter alia*, that the middles of the cube-faces become, in light, negative, the tension decreasing towards the edges, and especially the angles, which often show the opposite polarity. It is the chemical rays that act. The carbon electric light does better than sunlight. Sparks between two Leyden jars give the effects, but the light of Geissler tubes does not. Green Weardale crystals were the most excitable (of the specimens tried). The intensity of the effect generally grows with the depth of the colouring. The tensions produced by light do not change to those of opposite sign when the crystal is put and kept in the dark. Crystals long exposed to light are weakened in excitability. A moderate heating (to 130° to 150° C.) exalts the photoelectric effect. As to thermoelectricity, rise of temperature produces tensions of the same sign as illumination does. In cooling, the opposite electricities appear. In many crystals weakly excitable by light, the thermoelectric tensions are greater than the photoelectric (especially in the case of brown-red or brown-violet crystals).

GEOGRAPHICAL NOTES

SOME time back it was publicly stated that Commander Cheyne and his friends intended to apply to the Geographical Society for countenance and support to their plans of Arctic exploration. A deputation accordingly waited on Lord Aberdare, the president, on October 12, and, in pursuance of a suggestion he then made, a statement of Commander Cheyne's plans was lately drawn up by a committee for submission to the Council of the Society. This has been considered, and in reply the President and Council regret that the scheme, as explained by the statement, does not commend itself to them as one containing the elements of success and of usefulness, and that, even if it were feasible, the means proposed to be adopted for encountering the great dangers and difficulties necessarily attendant upon such an enterprise, do not appear to them sufficient. We believe the Geographical Society is to take up the subject of Arctic exploration this session. An Arctic Committee will be appointed to bring together all that has been done since the last English expedition, to enable the Society to decide what steps they should take.

THE post of honour in this month's issue of the Geographical Society's *Proceedings* is naturally assigned to Mr. J. Thomson's report of the journey of the East African Expedition, of which we have already given a *résumé*. It is illustrated by a map showing his route, constructed from the explorer's original map and other sources. There is also a useful little map of a route from Kagéi to Tabora, by the Rev. C. T. Wilson of the Church Missionary Society's Nyanza Mission. Capt. A. H. Markham's "Visit to the Galapagos Islands in 1880" follows, with some observations by Mr. Osbert Salvin on recent additions to our knowledge of the fauna of the group. From the geographical notes we learn that medals and other rewards are to be presented to Mr. Thomson's native followers, and that Dr. Kirk is to receive the formal thanks of the Society for the important services he rendered to the East African Expedition. Some interesting extracts from Capt. Carter's diary on his fatal march from Karema are next given, with a summary of recent news respecting African exploration. The remaining notes deal with M. Mushketof's ascent of the Zarafshan glacier, Russian explorations in Eastern and Western Siberia, surveys in Turkey, and an attempt to explore the affluents of the Rio Purûs.

MR. J. BANTING ROGERS has devised and published a game which is likely to be of service not only as a really interesting amusement, but also as a means of acquiring a considerable knowledge of navigation and meteorology. It is entitled the game of a "Voyage Round the World," and is played on a large board representing the ocean, suitably divided for counting by knots, and with hazards in the shape of cyclones, collisions, &c., which add excitement to the game. The game is played by means of a number of small models of ships of various kinds, and cards in which the number of knots is marked within which the players may move. Logs are kept, watches appointed, and a captain of the watch to record distances, &c. Altogether it will be seen that in Mr. Rogers's ingeniously devised game there are great possibilities both of amusement and instruction.

TWO Danish Expeditions which have been carrying on scientific exploration in Greenland have returned to Copenhagen. One of them, under Lieut. Hammer, has been continuing the investigations into the movement of the mainland ice into the fjörds and the formation of icebergs. In the course of the summer several previously unknown fjörds were visited, and the western part of the island of Disko surveyed and mapped. The other expedition, under Lieut. Holm, was to explore several of the large ruins of former settlements in the district of Julianhaab and to obtain information on the population and condition of the east coast. Several extensive ruins were found, which must have been left quite 100 years ago, and of which the present natives know nothing. Among these ruins many objects of ethnological interest were found. The weather during the whole summer was rainy and cloudy; indeed people who have been many years in Greenland never knew of so rainy a summer.

WE believe there is some prospect of Mr. Joseph Thomson being engaged to lead an expedition from Sierra Leone towards Timbuctoo, mainly to establish trading relations between the English Colonies and the interior. It would be a pity should Mr. Thomson be compelled to become a mere trading-caravan leader.

MAJOR SERPA PINTO'S account of his remarkable journey, which is still unpublished, is to be called "How I crossed Africa," instead of "The King's Rifle."

THE following telegram has been received in St. Petersburg from Col. Prejevalsky:—"Have finished my travel. Rich collections: 2000 birds, many mammals, 1300 species of plants. Will be in St. Petersburg at the beginning of January."

AT the last meeting (November 17) of the Russian Geographical Society, Dr. Piasetzky read an interesting paper on China. He has very closely studied the character of the Chinese, their life, their moral principles, and the education of children. Dr. Piasetzky, who has travelled during several years in China, is the author of a very interesting Russian work in two volumes on that country: the work is illustrated with very good drawings, which represent "types" of Chinese towns, streets, dwellings, market-places, &c. At the same meeting the Society resolved to take part in the next Geographical Congress and Exhibition at Venice.

BEFORE proceeding to Paris, as we mentioned last week, MM. Verminck, Zweifel, and Moustier were present at an enthusiastic meeting of the Marseilles Geographical Society, when the President, M. Rabaud, after a eulogistic address, presented them with medals for the part they respectively took in the expedition to the sources of the Niger.

LIEUT. E. W. PETLEY, of the Marine Survey of India, has lately drawn up some interesting notes on Marmagao (Goa), Portuguese India.

THE new *Bulletin* of the Antwerp Geographical Society contains an account of Mr. Andrew Goldie's last journey in New Guinea, and some observations on artesian wells in the Sandwich Islands.

MR. TODD, the Government Astronomer at Adelaide, is to proceed next May to Port Darwin, in the Northern Territory, to determine by telegraph the difference of longitude between that place and Greenwich.

A RECENT telegram from the Austrian traveller Oscar Lenz states that he had reached Medina, Senegal, on November 2. Oscar Lenz penetrated to Timbuctoo from the north, and went thence by Bassikonon, Sokolo, Goumbon, Nioro, and Konniakany to Medina.

HERR STIER, director of the Gymnasium in Zerbst, found, a short time ago, a detailed account of Vasco da Gama's second voyage to India. It is drawn up by a Dutchman (who accompanied Vasco da Gama), and in his own tongue. Herr Stier has now published a German translation of it.

MR. MUNDELLA ON EDUCATION IN SCIENCE

ON Friday last the Textile and Dyeing Departments of the Yorkshire College, Leeds, were formally opened, and at the dinner which followed the Right Hon. A. J. Mundella, M.P., Vice-President of the Council, proposed the toast of the occasion:—"Success to Yorkshire College." His remarks in connection therewith are so significant, coming from our *de facto* Minister of Education, that we give them in full.

There had not, he commenced by saying, been a more gratified spectator of the proceedings of that day than he was. There had been no one amongst them who had enjoyed more, if so much, the sense of satisfaction—he had almost said of triumph—that he had enjoyed that day. Sixteen years ago when he was, like many of those present, a captain in the ranks of industry, he took some interest in the question of the application of science to the industries of this country. His attention had been called to it by the advantages he possessed of seeing what was being done in other countries. He saw the infancy of technical education abroad, and now he stood by its cradle at home. The School of Arts et Métiers in Paris was not by any means a new school, and it had done great things for French industry. There was no one who was acquainted with that school who would not endorse his remarks when he said that it had done marvellous things for French manufactures, and he had learned since he came to Leeds that we had some of its most distinguished scholars in this town. He witnessed the beginning of technical instruction in Germany with the erection of the Polytechnic School of Zurich; and when he went to the members of the Chamber of Commerce of which he was

president, and told them what he had seen, the answer was that they had great doubts about the success of the experiment. It was thought then that the practical place to give technical instruction and teach the application of science to industry was in the workshops. They had now satisfied themselves, however, that whilst they could not dispense with the practical experience of the workshops, there was something that gave value to that experience. Let them take the art of dyeing for example. What was the old system of training in regard to it? The dyer did not then ascertain the properties of the articles with which he had to deal with that skill and accuracy with which the young men of Leeds were ascertaining them to-day. It used to be a bucketful of this, a shovelful of that, and a handful of the other. But the days of the old rule of thumb were numbered; and on standing at the cradle of the Yorkshire College he stood by the grave of the rule of thumb. He had been greatly encouraged this week by his visit to Yorkshire. He came to it somewhat in a state of despondency: not however with reference to elementary instruction, for the people of Yorkshire were doing wonders in that way, and in a few years hence this county would compare favourably in that respect with any part of the globe. But he had been examining recently, not for the first but the tenth time, what was being done on the Continent in the way of technical education. They had opened a good school in Leeds, but they must not flatter themselves. They must not believe that the 25,000*l.* which his friend Mr. Denison had indicated was the sum wanted to complete the work. He had stood in an industrial town of 70,000 inhabitants, in which a single building that had been erected within the past three years solely for teaching science, as applied to industry, had cost 100,000*l.* He had stood in three or four such towns. He had examined technical institutions in France, in Switzerland, and in the south and north and centre of Germany, and all he could say was, that not having examined these institutions critically for five years, he stood amazed and almost aghast at what he beheld. He came home feeling that in the countries he had mentioned they had found the weak place in our armour, and had wounded us in our tender part; but what he had seen in Yorkshire within the last week had given him renewed confidence and courage. He found, in addition to this splendid institution which had been opened to-day, that in the little town of Keighley—a very splendid little place—they were going to spend 5000*l.* in a weaving-school; that the Clothworkers' Company of London were going to assist Bradford also; and he was told that in Huddersfield they had got 15,000*l.* or 16,000*l.*; that they had no longer to teach elementary instruction in their night-classes, but wanted to give scientific and technical instruction to their workmen, and wanted a school for Huddersfield. Yesterday he stood by the grave of an eminent Yorkshireman who had done noble service to the teaching of science in Yorkshire—his friend Mr. Mark Firth. Would they not see that Yorkshire had many as worthy sons as Mr. Firth? Surely he was not the last man that would endow a college for science teaching. There were men, he hoped, within the sound of his voice who would perpetuate their memory, and show some gratitude to the industry that had made them wealthy by endowing another wing of the College like the one they had seen to-day. They must not believe that this was mere amateur work. This was not science teaching merely for the sake of scientific research, for arriving at scientific truth, or for giving intellectual culture. Those nations on the Continent who had produced such magnificent buildings, machinery, and apparatus to conduct this work were not doing so from sentimental reasons. They were not doing it with the object simply of endowing scientific research, or to make great progress in any particular branch of science. Their object was a very prosaic and a very practical one, and very full of self-interest. What they meant was to get industrial strength, which they believed was the real source of the wealth of their nation. The Yorkshire College was founded to supply instruction in those sciences which were applicable to the industrial arts. He might say as the result of his recent observations that France and Germany were conducting as active a competition with each other in this matter of arming for the industrial fight as any of the nations of the Continent of Europe were in their military armaments with a view to any catastrophe in future. But this was not a case in which Englishmen could look on with benevolent neutrality, because after all in this international fight they could not stand aloof, they could not remain neutral, for the blow, whenever it fell, would fall upon them. Rely upon it the success of the Science College of Yorkshire meant the success of Yorkshire itself. They possessed great natural resources for which their Continental neighbours envied them. They had in their immediate neighbourhood, in the mine, the coal and iron; they had in their people great vigour, great energy, and great inventive capacity; and they had also their old prestige. They had amongst them men of great wealth. There was his friend Mr. Denison ready to provide them capital very freely—at a very moderate rate. England, after all, was the great emporium as a depôt market for nearly all the raw material of the world. To London came that Australian wool so many thousand bales of which were exported to their neighbours on the other side of the water, and then came back to them in a finished state for the consumption of their own population. He was speaking from actual knowledge when he said that there was an enormous increase in the manufacture of dressed goods that could be well made in Yorkshire, that could be produced and sold in Yorkshire, and that were yet made abroad, but ought to be made at home. He believed the step they were taking that day in opening the College was the very way to create that employment at home which at present was too much done abroad. It had been said that the country gentlemen ought to assist in this movement. Lord Frederick Cavendish had come from a great and honourable house, and they all rejoiced in the wealth, ability, business capacity, sagacity, and liberality of that house. But what was it that had made these great houses and England wealthy? Was it not the value which had been added to the land by the success of the great manufactures? The success of the great houses of England was bound up in the success of the Yorkshire College and of other colleges like it. Thus to the success of their manufactures they must look for the continued greatness of England in its dealings with nations in the future. Why, they had but the same area of land now as they had when their population was only 10,000,000. They had 25,000,000 of people in England and Wales now, and they were multiplying at a rate which would soon double this number. What was it that was to feed all these people but the success of their manufactures? If they were to hold their own they must not lose a point; they must not neglect a single opportunity; they must not rest content on their old prestige; but they must, as Englishmen, look the difficulty in the face, and, where weakness existed, strengthen themselves, and this weakness was to be found entirely in the question of education, which they had too long neglected. In asking them to drink success to the Yorkshire College, he was asking them practically to drink to themselves. If they wished perfect freedom to carry on this work, he was quite of the opinion of Lord Frederick Cavendish that they must adopt the newest methods—to be untrammelled in their efforts, to carry on the College by themselves, and in that way in which Englishmen had been accustomed to do their work.

THE ROYAL SOCIETY—ADDRESS OF THE PRESIDENT[1]

II.

THE aspect of spectrum analysis has become much complicated by two sets of facts. First, the increased dispersion, the improved definition, the enlarged electrical power at our command, and, above all, the substitution of photography for eye observations, have revealed to us an almost overwhelming array of lines belonging to each substance. And, secondly, the same means have shown that many substances present different spectra when in different molecular states. These complications have led spectroscopists to seek some relief in theories of simplification. Lecoq de Boisbaudran, Stoney, Soret, and others have suggested that many of the lines, or groups of lines, may be regarded as the harmonics of a fundamental vibration; and they have shown that in certain cases this view will account for the phenomena observed. Professors Liveing and Dewar have contributed largely to the subject by their observations on the reversed lines. Looking in another direction, Mr. Lockyer considers that in increased temperature we have the means not only of resolving compound bodies into their elements, but even of dissociating bodies hitherto regarded as elementary into still more simple substances. There still remain serious difficulties connected with Mr. Lockyer's views; but it is to be hoped that his indefatigable energy will in some way or other ultimately overcome them.

The outlying parts of the spectrum, beyond the visible range,

[1] Address of William Spottiswoode, D.C.L., LL.D., the President, delivered at the Anniversary Meeting of the Royal Society on Tuesday, November 30, 1880. Continued from p. 114.

must always be a subject of interest; and while MM. Cornu and Mascart, and others, have extended our knowledge of the ultra-violet end, Major Abney has opened out to us a new region beyond the red. Lord Rayleigh and others before him have however proved that there must be a limit at the least refrangible end of the spectrum. Prof. Stokes, long since, noticed the difference in length between the spectrum of the sun and that of the electric arc; and M. Cornu has recently shown by observations at elevated stations that the great rapidity of atmospheric absorption must preclude the hope of any great extension of the solar spectrum toward the more refrangible end.

The striking advances made in electricity during the last few years, and marked by, amongst other things, the inventions of the telephone and the microphone, have been followed by a step not less daring in its conception, nor less successful in its execution; I allude, of course, to the photophone, the result of the researches of Mr. Graham Bell and Mr. Sumner Tainter. The principle of this instrument is already known. A powerful beam of light is first thrown upon a flexible mirror, the curvature of which is modified through vibrations set up in it by the human voice. The reflected beam is then received by a selenium "cell" forming part of an electric circuit. The intensity of the light so received, and with it the resistance in the circuit due to the selenium, varies with the varying curvature of the flexible mirror. A large parabolic mirror is used at the distant station to concentrate the light on the selenium "cell"; and a telephone in the circuit reproduces the variations in the form of sound.

Mr. Bell has however also shown that rays from the sun, or an electric lamp, when rendered intermittent by any convenient means, will set up in a plate of almost any substance vibrations corresponding to the intermittence. The substances as yet tried are: metals of various kinds, wood, india-rubber, ebonite, &c., and among them zinc appears to be one of the best suited for the purpose. This result, which is independent of any electric action, is perhaps due to heat rather than to light.

In these, as in many other issues of scientific research, we can hardly fail to be impressed by the almost inexhaustible resources which lie ready to hand, if we only knew how to use them, for the interpretation of nature or for the practical purposes of mankind.

During the past year Prof. Hughes employed his induction balance for the detection of very minute impurities in small masses of gold. Mr. Preece also has shown how slight increments of temperature in fine wires transmitting telephonic currents of electricity will suffice to reproduce sonorous vibrations, and even articulate speech, at a distant station by their influence on thin platinum wires only six inches in length.

Mr. Stroh has shown that, at the point of contact of two metals carrying strong electric currents, adhesion takes place, varying with the nature of the surfaces in contact; and that many of the effects at points of contact, previously attributed to induction, may be due to the peculiar action now for the first time brought under notice.

It is worthy of record that two Atlantic cables have been successfully laid during the present year; but that the operation has become so much a matter of course, that its occurrence has attracted little public attention. Two cables, each of more than 500 miles in length, have been laid across the Mediterranean; and the Cape Colony has been placed in telegraphic communication with this country by a cable of not less than 4400 miles.

Constant attention is paid in the General Post Office to the introduction of improved methods for the furtherance of the telegraphic communication throughout the country.

Steady progress has been made in bringing the electric light into practical use. The illumination of the Albert Dock of the London and St. Katherine's Dock Company, the Liverpool Street Station of the Great Eastern Railway, the St. Enoch's Station of the Glasgow and South-Western Railway, and last, but not least, that of the reading-room of the British Museum, have become accomplished facts; while the City authorities have decided to extend the use of this light over various thoroughfares under their control. The subdivision of the light for domestic purposes is a problem which appears to have found a solution in the incandescent carbon lamp of Mr. Swan. Besides this, Mr. J. H. Gordon has devised, for the same purpose, a very ingenious application of rapid sparks from alternating machines, such as that of De Méritens, to produce incandescence in refractory metals. Lamps constructed on this principle completely fulfil the conditions of subdivision, but some difficulties of detail still retard their adoption for general use. There is, however, every reason to hope that the experience already gained, and the intelligence at present brought to bear upon it, will before long supply us with more than one form of domestic light.

The chief question of interest which has occupied the attention of the Iron and Steel Institute has been the adaptation of the "basic" process to the production of steel from pig metal containing a considerable percentage of phosphorus. Hitherto, only pure hæmatite and spathic ironstones have been used for the production of steel; but it has now been shown that, by the employment of basic linings and basic slags, the metal is almost completely cleared of its phosphorus, and that steel of good quality may be produced from inferior ore.

The Conference on Lightning-Conductors, composed of delegates from the Royal Institute of British Architects, the Society of Telegraph Engineers, the Physical Society, and the Meteorological Council, is steadily pursuing its labours. A large mass of facts has been accumulated; several leading questions have been decided; and it is hoped that, in the course of the coming year, the Report of the Conference will be issued.

One of the most interesting, and at the same time useful, applications of the dynamo-machines, is that of transmitting mechanical power to spots, or under circumstances, where the ordinary appliances cannot be conveniently used. Their principle will doubtless by degrees extend itself over a wide range of industry; especially in localities where water-power is abundant. A very remarkable instance of such adaptations will be found in Dr. Werner Siemens's propulsion of railway carriages in Berlin.

Our Fellow, Dr. C. W. Siemens in London, and M. De Méritens in Paris, have demonstrated the use of the high temperature of the electric arc in fusing refractory metals. The method of operation, while peculiarly convenient for laboratory purposes, and for demonstration, promises to be capable of extension, even to the large demands of commerce and manufacture.

I should not, moreover, omit mention of the very beautiful experiments by Dr. C. W. Siemens on the effect of the electric light on the growth of plants, on the opening of flowers, and on the ripening of fruit. On this subject we hope to hear more hereafter. He has already commenced a fresh series of experiments, and contemplates continuing them during the coming winter.

I am not sure how far the fact is known to the Fellows of the Royal Society that the Society of Telegraph Engineers has thrown open to the scientific world a remarkable collection of books on electrical science, collected by our late Fellow, Sir Francis Ronalds, and bequeathed by him to that Society. The catalogue, compiled by the collector, is a monument of concentrated and well-directed labour.

As regards the Transit of Venus in 1874, the printing of the observations is complete for the two groups of stations in the Sandwich Islands and Egypt, and that for others is in progress.

Preparations are already being made with a view to the observation of the Transit of Venus in 1882. As a preliminary step for this operation, as well as for general purposes, it had been decided that the longitude of the Cape Observatory should be definitively determined by telegraphic connection with Aden, which place is already telegraphically referred to Greenwich; and, notwithstanding a temporary interruption on the land line, Capetown-Durban, it may be hoped that the connection will be effected at no distant period. Mr. Gill is prepared to undertake the main share of the work. With the same objects in view, on the urgent representation of the Astronomer-Royal, it has also been determined to connect one of the Australian Observatories with Greenwich, through Madras, the longitude of which is well known; and this operation will be very much facilitated by the share which Mr. Todd, Government Astronomer and Superintendent of Telegraphs at Adelaide, would be prepared to take in it under the auspices of his Government. The eastern boundary of the Colony having been defined by Imperial Act as the 141st meridian, a wish has been expressed officially for the accurate connection of Adelaide with Greenwich, independently of the Transit of Venus.

The Astronomer-Royal has explained in detail the preparations which he considers necessary, so far at least as this country is concerned, for the effective observati[illegible]it, and he has introduced several alterations in the [illegible] had formerly

suggested. The experience of the transit of 1874 points to the desirability of sacrificing something in the magnitude of the parallax-factor for the sake of securing a higher elevation of the sun; thus, for retarded ingress, Sir George Airy had at first proposed to refer principally to the coasts of the Canadian Dominion and the United States of North America, where the sun's elevation is from 15° to 18°; he now proposes to substitute for this the whole chain of West India Islands, from the eastern extremity of Cuba to Barbadoes, or stations on the neighbouring continent of Central America. Bermuda is also included as a favourable point for observation. Most, if not all, of the longitudes required have been determined with great precision by the Hydrographic Department of the United States. For ingress accelerated, Sir George Airy relies entirely upon stations in the Cape Colony. For the accelerated egress, all the stations suggested for ingress retarded will be available. For egress retarded, although the fixed Observatories at Melbourne and Sydney will contribute to the observation of the phenomenon, they will have the sun at a somewhat low elevation (10—14°); it is thereby proposed to rely mainly upon New Zealand, with which we are in telegraphic communication *viâ* Sydney. Considerable correspondence has taken place on the subject of Australian longitude, and it is expected that the necessary steps to effect the connection of one of the Observatories, probably Adelaide, with Madras, will be taken early in the ensuing year.

Sir G. B. Airy has completed the laborious calculations in his Numerical Lunar Theory, from which the corrections to the coefficients of Delaunay's Lunar Theory are to be deduced; and in connection with this work he has made an investigation of the value of the Moon's Secular Acceleration, for which he finally obtained the value 5″·477, thus confirming the results obtained by Prof. Adams, and subsequently by Mr. Delaunay. On this important question, Prof. Adams has also published an investigation (*Monthly Notices*, vol. xl. Nos. 6, 7, 8 and 9).

A new determination of the Physical Libration of the Moon from a large number of lunar photographs taken with the De La Rue reflector at the Oxford University Observatory has been recently made by Prof. Pritchard, the result being to indicate the existence of a small rotational inequality.

Messrs. J. Campbell and Neison have made use of the Greenwich Observations, 1862 to 1876, to determine the Lunar Parallactic Inequality, from which they deduce for the value of the Solar Parallax, 8″·778, or 8″·848, according as the existence of a forty-five year inequality, apparently indicated by the observations, is admitted or not (*Monthly Notices*, vol. xl. Nos. 7 and 8). The Sun's Parallax has also been determined by Mr. Downing, from N.P.D. observations of Mars at Leyden and Melbourne, in 1877. The value thus found is 8″·96 (*Astronomische Nachrichten*, No. 2288).

In continuation of his researches on tidal retardation from the action of a satellite on a viscous planet, Mr. G. H. Darwin has investigated the secular changes in the orbit of a satellite, deducing the early history of the earth and moon from the time when they were initially in contact, each revolving in the same period of from two to four hours. This leads to the suggestion that the moon was produced by the rupture of the primæval planet. In another memoir, Mr. G. H. Darwin gives analytical expressions for the history of a planet and a single satellite. (*Phil. Trans.*, 1879, *Proc.* Roy. Soc., Nos. 200 and 202.)

An important work in connexion with the United States Northern Boundary Commission has been published by Mr. Lewis Boss, on the Declination of Fixed Stars. The systematic corrections to some seventy catalogues have been discussed, and, from the mean of the whole, standard declinations of 500 stars have been deduced.

Dr. Gould's "Uranometria Argentina" and M. Houzeau's "Uranométrie Générale," are of especial value as giving important information on the brightness and distribution of the stars in the southern hemisphere.

Interesting results as to the diameters of satellites have been obtained by Prof. Pickering from photometric observations, on the assumption that their albedos do not differ greatly from those of their respective primaries. (*Annals*, Harvard College Observatory, vol. xi.) He has further investigated, on somewhat similar principles, the dimensions of the fixed stars, with especial reference to binaries and variables of the Algol type. (*Proc.* Amer. Acad., vol. xvi.) Prof. Pickering has also commenced a photometric survey of the heavens, in which the brightness of every star visible to the naked eye is to be determined. He has further undertaken a search for planetary nebulæ by a new method, in which, by the use of a direct-vision prism in front of the eyepiece, the nebula is at once detected by its monochromatic spectrum, focussing a point of light instead of a coloured line as in the case of a star. About a hundred thousand stars have been examined, and four new planetary nebulæ have been detected. (*American Journal of Science*, October, 1880.)

From the grouping of the aphelia of certain periodic comets Prof. G. Forbes has inferred the existence of two ultra-Neptunian planets, and has indicated their approximate positions. (*Trans.* Roy. Soc., Edinburgh.) Mr. D. P. Todd has deduced from the perturbation of Uranus a position for an ultra-Neptunian planet closely agreeing with that found by Prof. G. Forbes. So far, the search for the hypothetical planet with the 26-inch Washington refractor has been unsuccessful. (*American Journal of Science*, September, 1880.)

Prof. Bredichin's researches on the tails of comets have led him to the classification of these appendages according to the value of the solar repulsive force which would have generated them. Having discussed the forms of the tails of thirty-three comets, he finds that they belong to three types, corresponding respectively to repulsive forces 11, 1·4 and 0·3 (the sun's gravitation being taken as 1); and adopting Zöllner's hypothesis of a repulsive force, due to electricity and inversely proportional to the specific gravity, he infers that the tails of the three types are composed respectively of hydrogen, carbon, and iron. In the case of the second and third types other elements of nearly the same atomic weight may replace or be mixed with the carbon and iron, and in such a comet as Donati's a number of substances may be mixed in the tail, which will consequently spread out in the plane of the orbit. The first type composed of hydrogen will always remain separated from the others. (*Annales* de l'Observatoire de Moscou, vols. iii-vi.)

The appearance, at the beginning of this year, of a great comet in the southern hemisphere, recalling by the length of its tail and the smallness of its head the remarkable comet of 1843, has excited great interest, more especially as it was found that the orbits of the two comets were sensibly the same. The observations of the comet of 1843, however, do not appear to be compatible with so short a period as thirty-seven years, and Prof. Oppolzer has shown that the action of a resisting medium would not meet the case. (*Astronomische Nachrichten*, Nos. 2314, 2315.) Under these circumstances Prof. D. Kirkwood has suggested that the two bodies may be fragments of one original comet, viz., that of 370 B.C., which is said to have separated into two parts like Biela's comet (*Observatory*, No. 43.) Five other comets (including Faye's periodical comet) have been discovered this year, but two of them were lost through cloudy weather before a second observation could be obtained.

In astronomical physics Mr. Huggins has obtained photographs of stellar spectra, which establish the existence of a remarkable group of nine bands in the ultra-violet, probably due to hydrogen, and further lead him to an arrangement of the stars in a continuous series according to the breadth and marginal difference of the typical lines, particularly of the K line. Mr. Lockyer continues his researches on dissociation, as indicated in solar outbursts, and in connection with this work is engaged on a systematic observation of the spectra of sun-spots. At the request of the Committee on Solar Physics, corresponding observations are being made at Greenwich.

From the series of Greenwich photographs of the sun, 1874—1879, the mean heliographic latitude of spots and mean distance from the sun's equator, have been deduced for each rotation and for each year ("Greenwich Spectroscopic and Photographic Results," 1879).

A fine 36-inch silver-on-glass reflector has been recently constructed by Mr. Common, and with this instrument he has obtained photographs of Jupiter, showing the red spot, and of the satellites (*Observatory*, No. 34).

At the outset of an undertaking one figures to oneself in imagination what may be done; towards the close of it one sees in actual fact what has been done. In commencing this address I had hoped to say something of the progress of mathematics; before bringing it to a conclusion I find my space filled and my time exhausted. How far the good intentions of this year may be realised in the next, cannot yet be seen; but the difficulties of a task do not always diminish the fascination of making an attempt.

THE ROYAL SOCIETY MEDALS

AT the conclusion of his anniversary address on Tuesday last week, the President, Mr. Spottiswoode, delivered the medals which have been awarded this year, and in doing so spoke as follows :—

The Copley Medal has been awarded to Prof. James Joseph Sylvester, F.R.S. His extensive and profound researches in pure mathematics, especially his contributions to the Theory of Invariants and Covariants, to the Theory of Numbers, and to Modern Geometry, may be regarded as fully establishing Mr. Sylvester's claim to the award of the Copley Medal.

One Royal Medal has been awarded to Prof. Joseph Lister, F.R.S. Mr. Lister's claims to the honour of a Royal Medal are based upon his numerous and valuable contributions to physiological and biological science during the last thirty years.

By permission of its author, the Fellow of the Society best qualified, by his own extensive researches on the germ theory, to form a judgment, I quote the following account of Prof. Lister's work and achievements :—

"In 1836 and 1837 it was proved independently by Cagniard de la Tour and Schwann, that vinous fermentation was due to the growth and multiplication of a microscopic plant. At the same time Schwann described experiments which illustrated and explained the conditions, now well known, by which flesh may be preserved from putrefaction. But Schwann's researches were overshadowed by the views of accepted authorities, and they continued so up to the publication of Pasteur's investigations. From this point forward the view gained ground that putrefaction is the work of floating microscopic organisms; and that if air be thoroughly cleansed of its suspended particles, neither its oxygen, nor any other gaseous constituent, is competent to provoke either fermentation or putrefaction.

"Condensed into a single sentence, the merit of Mr. Lister consists in the generalisation, to living matter, of the results obtained by Schwann and Pasteur with dead matter. He began with cases of compound fracture and with abscesses. In simple fracture the wound is internal, the uninjured skin forming a protecting envelope. Here nature works the cure after the proper setting of the injured parts. In compound fracture, on the other hand, the wound extends to the surface, where it comes in contact with the air; and here the operator can never be sure that the most consummate skill will not be neutralised by subsequent putrefaction.

"In the earliest of his published communications Mr. Lister clearly enunciates, and illustrates by cases of a very impressive character, the scientific principles upon which the antiseptic system rests. He refers to the researches of Pasteur, and shows their bearing upon surgery. He points to the representative fact, then known but unexplained, that when a lung is wounded by a fractured rib, though the blood is copiously mixed with air, no inflammatory disturbance supervenes; while an external wound penetrating the chest, if it remains open, infallibly causes dangerous suppurative pleurisy. In the latter case the blood and serum are decomposed by the microscopic progeny of the germs which enter with the air; in the former case the air is filtered in the bronchial tubes, and all solid particles are arrested. Three years subsequently this inference of Prof. Lister was shown to be capable of experimental demonstration.

"After enunciating the theoretic views which guided him, he thus expresses himself in his first paper :—

"'Applying these principles to the treatment of compound fracture; bearing in mind that it is from the vitality of the atmospheric particles that all the mischief arises, it appears that all that is requisite is to dress the wound with some material capable of killing these septic germs, provided that any substance can be found reliable for this purpose, yet not too potent as a caustic.'

"This is the thesis to the illustration and defence of which Prof. Lister has devoted himself for the last thirteen years. His thoughts and practice during this time have been in a state of growth. His insight has been progressive; and the improvement of experimental methods founded on that insight incessant. By contributions of a purely scientific character, which stamp their author as an accomplished experimenter, he has materially augmented our knowledge of the most minute forms of life. The titles of his papers indicate the direction of his labours from time to time; but they give no notion of the difficulties which he has encountered, and successfully overcome. He performs, without dread of evil consequences, the most dangerous operations. He ventures fearlessly upon treatment which, prior to the introduction of his system, would have been regarded as no less than criminal. In the Glasgow Royal Infirmary, when wards adjacent to his had to be abandoned, he operated with success in an atmosphere of deadly infectiveness. Vividly realising the character and habits of the 'invisible enemy' with which he has to cope, his precautions are minute and severe. This demand for exactitude of manipulation has rendered the acceptance of the Antiseptic System slower than it would otherwise have been; but a clear theoretic conception has this value among others: it renders pleasant a minuteness of precaution which would be intolerable were its reasons unknown.

"The operative surgeons of our day have raised their art to the highest pitch of efficiency. Their skill and daring are alike marvellous. Mr. Lister urges an extension of this skill from the operation to the subsequent treatment, contending that every surgeon ought to be so convinced of the greatness of the benefits within his reach as to be induced to devote to the dressing of wounds the same kind of thought and pains which he now devotes to the planning and execution of an operation. His impressive earnestness; his clearness of exposition; his philosophic grasp of the principles on which his practice is founded—above all his demonstrated success—have borne their natural fruit in securing for him the recognition and esteem of the best intellects of the age.

"In a letter addressed to the writer on the 29th of September, 1880, Prof. Helmholtz expresses himself thus :—

"'Prof. Lister ist als einer der hervorragendsten Wohlthäter der Menschheit zu betrachten, und als eines der glänzendsten Beispiele, wie segensreich scheinbar minutiöse und abstruse wissenschaftliche Untersuchungen, wie die über di Erzeugung mikroskopischer Organismen, werden können, wenn sie von einem Manne von umfassendem geistigen Gesichtskreise aufgenommen werden.'"

"In a letter dated October 1st, 1880, Prof. Du Bois Raymond writes :—

"'The period of bloody warfare through which we passed not long ago, just when Prof. Lister's methods were matured enough to be freely used even on the battlefield, has of course contributed to render his name popular throughout Germany; nay, to make it a household word in many homes. We use the word 'listern' as a verb to designate the use of the carbol-spray while bandaging a wound. I do not hesitate to proclaim Lister the greatest benefactor of mankind since Jenner's wonderful discovery—far superior, indeed, to Jackson and Simpson; because, whatever may be the dread of pain and the blessing of being spared it, in Lister's invention health and life itself are concerned, as in hardly any other medical discovery except vaccination. Moreover, the general ideas which have led to Prof. Lister's conception stamp his work with a peculiarly scientific character.'

"In a letter dated from Vevey on the 10th of this month, Prof. Klebs of Prague, himself a distinguished worker in this field, expresses in the strongest terms his admiration of the profound philosophical intuition and practical success of Mr. Lister, as having not only reformed the whole art of surgery, but given a new impulse to medical science generally. Prof. Klebs's interpretation of the opposition encountered for a time by Mr. Lister is worthy of mention. He ascribes it to the high standard attained by British surgery before the time of Lister. 'The operators,' he says, 'that work under the best hygienic conditions will not feel so acutely as others do the necessity of disinfecting wounds. But the good results of the former British surgery are now surpassed by the new method, which is accepted at the present time by the whole world.'

"Such testimonies might be multiplied to any extent. The foregoing are the answers received from the only three gentlemen who have been requested to express an opinion as to the merits of Mr. Lister."

The second Royal Medal has been awarded to Capt. Andrew Noble, late R.A., F.R.S. Capt. Noble is joint author with Prof. Abel of the "Researches on Explosives," *Phil. Trans.*, 1875, which, in combination with other labours in the same field, procured for Prof. Abel the honour of the Royal Medal in 1879. To Prof. Abel is due mainly the chemical part of these investigations; to Capt. No[illegible]hanical and mathematical part. Each is a comple[illegible]her, but it

may be safely affirmed that they could not have been presented to the world in the form in which they appear without the co-operation of his remarkable union of technical knowledge and mastery of mathematical analysis with the chemical science of Prof. Abel. His beautiful invention of the Chronoscope, an instrument constructed by him at great cost, by which intervals of time as small as the one-millionth part of a second can be measured, has been of indispensable value in these researches. He is the author of papers which have been translated into most European languages on subjects of gunnery and gunpowder; he is perhaps the highest authority we possess on the higher branches of artillery science, and the best known on the Continent. His great talents and attainments are not more conspicuous than his singular modesty and his indefatigable industry. He has been engaged on these subjects about twenty years, having published the first experiments in this country with Navez' electroballistic apparatus, in 1862.

The Rumford Medal has been awarded to Dr. William Huggins, F.R.S. In 1866 a Royal Medal was awarded to Dr. Huggins for his important researches. Since that time he has been continually engaged in prosecuting the subject of celestial spectroscopy, both in the departments in which he had already done so much, and in others of its branches. One subject of Dr. Huggins' researches relates to the determination of the radial component of the velocity of the heavenly bodies relatively to our earth, by means of the alteration of the refrangibility of certain definite kinds of light which they emit, or which are stopped by their atmospheres. The smallness of the alteration corresponding to a relative velocity comparable with the velocity of the earth in its orbit makes the determination a matter of extreme delicacy. But as early as 1868 he had obtained such trustworthy determinations that he was able to announce before the Royal Society in that year that Sirius was receding from our solar system with a velocity of about 29·94 miles per second.

In a paper presented to the Royal Society in 1872 he has given the results obtained for a large number of stars, and has shown that some are receding and some approaching, and that there seems to be a balance of recession in those parts of the heavens, from which we have reason, from the observed proper motions, which of course can only be transversal, to conclude that the solar system is receding, and a balance in favour of approach in the opposite direction; while yet it does not appear that the motion of the solar system would alone account for the whole of the proper motions of the stars in a radial direction.

The same inquiry was extended to the nebulæ, the spectrum of which consists of bright lines, and in this case it presented greater difficulties. As those nebular lines which appear pretty certainly to be identifiable with hydrogen are too faint to be employed in the investigation, and the others are not at present identified with those of any known element or compound, he was obliged to avail himself of a coincidence between the brightest nebular line and a line of lead. But as the coincidence is probably merely fortuitous, the results give only the *differences* of approach or recess of different nebulæ. The observations seem to show that, so far as has been observed, the nebulæ are objects of greater fixity as regards motion in space, than the stars.

The other subject to which Dr. Huggins has more particularly devoted himself of late, is the mapping of the photographic spectra of stars. This was a research of great delicacy, partly on account of the small quantity of light at the disposal of the observer, partly from the great accuracy with which the comparison had to be made with the spectra of known substances, in order that satisfactory conclusions should be deducible as to the presence or absence of such or such substances in the stars. The results obtained led to a remarkable division of the stars into two great classes, naturally with transition cases, namely, white stars, which showed a group of twelve dark lines belonging, apparently, to the same substance, probably hydrogen, and the group of stars, of which our own sun may be taken as a type.

Besides the researches already mentioned, other papers have been presented by Dr. Huggins to the Royal Society, on the spectra of comets, on the spectrum of Uranus; and in particular one in which he showed that it was possible to detect the heat of the stars, and has given the results obtained for several.

The Davy Medal has been awarded to Prof. Charles Friedel, Member of the Institute of France.

From 1856 to the present time the investigations of M. Charles Friedel, ranging over widely-remote fields of chemical inquiry, have been continuous, numerous, and important. Mineralogical, theoretical, and general chemistry are indebted to him for many valuable contributions; but it is in the department of so-called organic chemistry that he has more especially laboured; and herein he has done much to assist in breaking down the barriers at one time regarded as impassably isolating the chemistry of carbon compounds.

Among the subjects of M. Friedel's successful work may be mentioned more particularly the chemistry of the 3-carbon family of organic bodies, to which belong propionic acid, lactic acid, glycerine, propylene, and acetone. The establishment of the constitution of lactic acid and of acetone, with the determination of the relationships to one another of the various, and in many cases isomeric, members of this large family, constituted for a long time one of the most fiercely-contested, as it was, and is, one of the most fundamental problems of organic chemistry. In the labours effecting the satisfactory solution of this problem M. Friedel bore a large share.

Passing to another branch of investigation, M. Friedel, partly by himself, but largely in conjunction in some parts of the work with Mr. J. M. Crafts, and in other parts with M. A. Ladenburg, made out, or confirmed in a very striking manner, the analogy subsisting between the modes of combination of carbon and of silicon, the most characteristic elements of the organic and inorganic kingdoms respectively.

To mention but one more subject of M. Friedel's research, he has, in conjunction with Mr. J. M. Crafts, made out and defined a simple method of wide application for effecting the synthesis of organic compounds. This method consists in bringing together a hydrocarbon and an organic chloride in presence of chloride of aluminum, whereby the residues of the two compounds enter into combination to form a more complex, frequently a highly complex, body. Independently of its utility, this process of synthesis is of remarkable interest from the part taken in it by the chloride of aluminum, which, though essential to the reaction, is found unaltered at the end, and seems to act by suffering continuously, little by little, a correlative transformation and regeneration.

UNIVERSITY AND EDUCATIONAL INTELLIGENCE

OXFORD.—The statutes made by the new Commissioners for the different colleges are appearing in their final shape. The statutes of six colleges are already printed and in the hands of Members of Convocation. They resemble each other closely in several respects. Ordinary Fellows are to be elected by examination, all the branches of learning recognised in the final schools of the University being taken from time to time as the subject of examination. These Fellowships are tenable for seven years. Tutorial Fellows are elected without examination, but the colleges may require two years' college work from an ordinary Fellow, having given notice of such requirement before the examination. The colleges may elect persons distinguished in literary or scientific work to Fellowships tenable for a term of years, during which the Fellows shall devote themselves to a definite research specified in the resolution appointing them.

Several meetings of the Professors and College Tutors engaged in teaching different branches of Physics in the University have been held during the last fortnight at the instance of Prof. Clifton. The object was to prepare a scheme of lectures for next term, such that the lecturers would cover most of the ground without clashing with each other or with the lecturers in other branches of science. It may be mentioned that this is the first time such an arrangement has been arrived at in the Natural Science School at Oxford. The following plan of lectures has been agreed upon for next Lent Term:—

Optics (treated Mathematically), Prof. Price, Tuesday, Thursday, and Saturday, at 12; Magnetism (treated experimentally), Prof. Clifton, Wednesday and Saturday, at 12; Practical Physics, Prof. Clifton, Mr. Stocker, Mr. Jones, daily, 11 a.m. to 4 p.m. Thermodynamics and Electrodynamics (treated mathematically), Mr. Baynes, Monday, Wednesday, and Friday, at 10; Electrostatics (treated mathematically), Mr. Hayes, Saturday at 11; Elementary Mechanics (treated experimentally), Mr. Stocker, Monday and Wednesday, at 10; Problems in Elementary Mechanics and Physics, Mr. Jones, Friday, at 10; Elementary Physics (treated experimentally), Mr. Dixon, Monday, Wednes-

day, and Friday, at 11. The last three courses of lectures are intended to meet the requirements of candidates for the Preliminary Honour Examination.

SOCIETIES AND ACADEMIES

LONDON

Geological Society, November 17.—Robert Etheridge, F.R.S., president, in the chair.—Prof. Joseph Henry Thompson, Auckland, New Zealand, was elected a Fellow of the Society.—The President called attention to the portrait of Dr. William Smith, presented to the Society by his grand-nephew, Mr. W. Smith of Cheltenham, which was then suspended behind the chair, and expressed his great satisfaction at this most interesting picture being in possession of the Society. Mr. W. W. Smyth expressed the satisfaction which all must feel in possessing a genuine relic of this eminent stratigraphical geologist. Now this one, which had been so liberally presented to the Society, was a most indubitable portrait of the most conspicuous founder of English geology. That portrait was painted by M. Fourau in 1837, and was certainly an admirable likeness. The Society was deeply indebted to the donor, Mr. W. Smith, the cousin of the valued Prof. Phillips. The portrait now hanging on the wall was engraved in Prof. Phillips' "Life" of his uncle. He proposed a hearty vote of thanks to the donor. Mr. Evans rose with great pleasure to second the vote of thanks proposed by Mr. Warington Smyth. The portrait was indeed replete with interest, not only to English geologists, but to all geologists in the world. An additional interest attaching to the portrait was that we had the whole history of it from Dr. Smith's own hand, an extract from which Mr. Evans read. The portrait was an admirable one. He hoped that in the future Mr. Smith's example would be followed, and that we should see many other portraits of eminent geologists on the Society's walls. The Society was also deeply indebted to the president for the interest which he had taken in the matter. The vote of thanks was carried by acclamation.—The following communications were read:—On abnormal geological deposits in the Bristol district, by Charles Moore, F.G.S.—Interglacial deposits of West Cumberland and North Lancashire, by J. D. Kendall, C.E., F.G.S.

Royal Microscopical Society, November 10.—Dr. Beale, F.R.S., president, in the chair.—Photographs of *P. angulatum* and *Frustulia saxonica* were exhibited by Herr O. Brandt; the Tolles-Blackham and eight other microscopes by Mr. Crisp; "Calotte" diaphragms by Mr. Swift; Hyde's illuminator by Mr. J. Mayall, jun.; and Dr. Carpenter, C.B., described Wale's "working microscope" with Iris diaphragm, which he highly commended as combining many novel and excellent points for a student's microscope.—Mr. Lettsom described Abbe's "stereoscopic ocular," and Dr. Maddox his apparatus for collecting particles from the air.—Notes were read on monobromide of naphthaline (for mounting diatoms to increase their "index of visibility").—On ebonite for microscopical appliances, and on aperture exceeding 180° in air; also papers by Mr. Stewart on the echinometridæ, and by Dr. Royston Pigott on testing object-glasses.

PARIS

Academy of Sciences, November 22.—M. Edm. Becquerel in the chair.—The following papers were read:—Meridian observations of small planets at the Greenwich and Paris Observatories, communicated by M. Mouchez.—The thermal springs of the coast chain of Venezuela (South America), by M. Boussingault. The most important are those of Onoto (alt. 696 m.), Mariara (533m.), and Trincheras, near Nueva Valencia (300 to 350m.). The respective temperatures are 44°·5, 64°·0, and 96°·9, showing an increase proportional to the decrease in altitude, 1° for a difference of level of 6m. to 7m. After the springs of Urijino, Japan (100°), those of Trincheras are probably the hottest. The author gives an analysis of their water; also general descriptions of the others.—*Reconnaissance* of the Napo (Equatorial America), by M. de Lesseps. This important affluent of the Amazon has been scientifically explored by M. Wiener, who in seven months has crossed South America in its greatest width, Quito to Para. The river is navigable a thousand miles from its entrance to the Amazon. He indicates a region larger than France well suited for colonisation.—On the treatment of vines with sulphide of carbon, by M. de Lafitte.—On the simultaneous reduction of a quadratic form and of a linear form, by M. Poincaré.—On Leverrier's tables of the motion of Saturn, by M. Gaillot.—On a property of the polynômes X_R of Legendre, by M. Laguerre.—New tables for calculating heights by means of barometric observations, by M. Angot. These tables give directly the height of each station above the level where the pressure is 760mm.; this is near the true altitude, an idea of which may thus be had without comparing results from two stations. The exactness is at least as great as with the best formulæ proposed. The heights calculated differ always from the real height in a sense that can be known *à priori*.—Researches on sulphide of nitrogen, by M. Demarcay.—On phytolaccic acid, by M. Terreil. This new organic acid exists in the state of a salt of potash in the fruit of *Phytolacca Kæmpferi*. (Its properties are described.)—Measurement of the toxical dose of carbonic oxide in different animals, by M. Gréhant. Great differences were observed: a mixture of $\frac{1}{100}$ strength was the poisonous dose for one dog, $\frac{1}{150}$ for another (the animals being made to breathe 200 litres). A rabbit required $\frac{1}{60}$ (breathing 50 litres). The smallest sufficing dose was that for a sparrow, $\frac{1}{100}$.—On a new species of *Poroxylon*, by M. Renault. This plant is named *P. Edwardsii*. The *Poroxyla* are found in the Upper Coal and Permian formations.—Transformation of a fructiferous ramification, resulting from fertilisation, into a prothalliform vegetation, by M. Sirodot. This was observed in *Batrachospermum vagum* (Roth).—Influence of light on the respiration of seeds during germination, by M. Pauchon. These experiments were made on the castor-oil plant (as being oleaginous and albuminous) and on the haricot bean (feculent and without albumen). As in previous experiments, a good deal more O was observed in light than in darkness. The castor-oil seeds exhale slightly more CO_2 in darkness than in light, but the opposite was the case with the seed of *Phaseolus*. In darkness the ratio of CO_2 to O was for the haricot at least $\frac{1}{3}$ superior to that for the castor-oil plant, but prolongation of the experiment tends to bring the relation equal to unity, whatever the original value. For a given quantity of oxygen absorbed the seed placed in darkness exhales more CO_2 than that kept in light. While in light there is always less CO_2 exhaled than O absorbed, the contrary occurs in darkness. These facts explain the transformation of legumin into asparagin.—Observations on the *rôle* attributed to maize, used as food, in the production of pellagra, by M. Fua. He considers M. Faye's opinion, that pellagra may be caused by the large use of unfermented maize, to be in contradiction with facts. Maize is always eaten in the unfermented state. It forms the chief food of a large population in Central Africa, where pellagra does not occur; and similarly in Naples and in Hungary. He refers to certain alterations of maize (by fungi and oxidation).

VIENNA

Imperial Academy of Sciences, December 2. Dr. L. A. Fitzinger in the chair.—On the theory of so-called electric expansion or electrostriction; Part ii., by Dr. Boltzmann.—Calculation of the absolute value and determination of the general equation of electrostriction, by the same.—On some properties of bromide of ammonium, by Dr. Eder.—Observations on contact-electricity (sealed packet), by Herr Schulze-Berge.—Results of an investigation of the identity of the comets 1880 *e* and 1869 III., by Herr Zelber and Dr. Hepperger.—On graphic formulæ of hydrocarbons with condensed benzol-nuclei, by Herr Wegscheider.

CONTENTS

	PAGE
BRITISH EARTHQUAKES	117
THE ENCYCLOPÆDIA BRITANNICA	119
OUR BOOK SHELF:—	
Buckley's "Life and her Children: Glimpses of Animal Life from the Amœba to the Insects"	123
LETTERS TO THE EDITOR:—	
Prof. Tait and Mr. H. Spencer.—PROF. P. G. TAIT	123
Geological Climates.—ALFRED R. WALLACE	124
Photophonic Music.—M.	124
The "Philosophy of Language."—LUDWIG NOIRÉ	124
Notes on the Mode of Flight of the Albatross.—ARTHUR W. BATEMAN	125
A General Theorem in Kinematics.—J. J. WALKER	125
Geometrical Optics.—W. G. LOGEMAN	125
Ozone.—J. P.	125
PLANTS OF MADAGASCAR. By J. G. BAKER	125
BENJAMIN COLLINS BRODIE, BART., F.R.S., D.C.L.	126
THE PHYLLOXERA IN FRANCE. By MAXIME CORNU (*With Maps*)	127
NOTES	130
PHYSICAL NOTES	133
GEOGRAPHICAL NOTES	134
MR. MUNDELLA ON EDUCATION IN SCIENCE	134
THE ROYAL SOCIETY—ADDRESS OF THE PRESIDENT, II. By WILLIAM SPOTTISWOODE, D.C.L., LL.D.	135
THE ROYAL SOCIETY MEDALS	138
UNIVERSITY AND EDUCATIONAL INTELLIGENCE	139
SOCIETIES AND ACADEMIES	140

SUBSCRIPTIONS TO NATURE

Yearly . . . . . 28*s.*
Half-yearly . . . . . 14*s.* 6*d.*
Quarterly . . . . . 7*s.* 6*d.*

To the Colonies, United States, the Continent, and all places within the Postal Union :—

Yearly . . . . . 30*s.* 6*d.*
Half-yearly . . . . . 15*s.* 6*d.*
Quarterly . . . . . 8*s.*

Office: 29, Bedford Street, Strand.

DIARY OF SOCIETIES.

LONDON

THURSDAY, DECEMBER 9.

ROYAL SOCIETY, at 4.30.—On a Simplified Form of the Torsion Gravimeters of Broun and Babinet: Major Herschel, F.R.S.—Note on the Microscopic Examination of some Fossil Wood from the Mackenzie River: C. Schröter.—Electrostatic Capacity of Glass, II.: Dr. Hopkinson, F.R.S.—The Cochlea of the *Ornithorhyncus platypus* compared with that of ordinary Mammals and of Birds: Dr. Urban Pritchard.

MATHEMATICAL SOCIETY, at 8.—Note sur Dérivation des Déterminants: Prof. Teixeira (Coimbra, Portugal).—On the Solution of the Inverse Logical Problem: W. B. Grove.—Motion of a Viscous Fluid: T. Craig, U.S. Coast Survey.—On the Solution of the Binomial Equation $x^p - 1 = 0$. Quinquisection: Prof. Cayley, F.R.S.—A General Theorem in Kinematics: Prof. G. M. Minchin.—On the Electrical Capacity of a Conductor bounded by Two Spherical Surfaces Cutting at any Angle: W. W. D. Niven.

LONDON INSTITUTION, at 7.—Germination and Propagation of Disease: Dr. L. S. Beale.

FRIDAY, DECEMBER 10

ROYAL ASTRONOMICAL SOCIETY, at 8.

QUEKETT MICROSCOPICAL CLUB, at 8.

SATURDAY, DECEMBER 11.

PHYSICAL SOCIETY, at 3.—On the Rate of loss of Light from Phosphorescent Surfaces: Lieut. L. Darwin, R.E.—On the Determination of Chemical Affinity in terms of Electromotive Force: Dr. Alder Wright.

MONDAY, DECEMBER 13.

GEOGRAPHICAL SOCIETY, at 8.30.—Geographical Results of the Afghan Campaign: Capt. T. H. Holditch, R.E.

SOCIETY OF ARTS, at 8.—Pottery and Porcelain: Prof. A. H. Church.

LONDON INSTITUTION, at 5.—The Kings of the Hittites: W. St. Chad Boscawen.

TUESDAY, DECEMBER 14.

ZOOLOGICAL SOCIETY, at 8.30.—On Additions to the Society's Menagerie during the Month of November: The Secretary.—On the Application of the Laws of Evolution to the Arrangement of the Vertebrata, and more particularly of the Mammalia: Prof. T. H. Huxley, F.R.S.—On the Animal of *Fernssacia gronoviana*, Risso, from Mentone, concluding with a Classification of the above Genus of Risso and its Allies by Geoffroy Neville, C.M.Z.S.: Lieut.-Col. H. H. Godwin-Austen, F.R.S.—On a Second Collection of Lepidoptera made in Formosa by H. E. Hobson: Arthur G. Butler.

ANTHROPOLOGICAL INSTITUTE, at 8.—Hittite Civilisation: W. St. Chad Boscawen.—Notes on Two Stone Circles in Shropshire: A. L. Lewis.

WEST LONDON SCIENTIFIC ASSOCIATION, at 8.—Shooting Stars and Meteors: Dr. J. H. Gladstone, F.R.S.

HORTICULTURAL SOCIETY, at 1.—Scientific Committee.

PHOTOGRAPHIC SOCIETY, at 8.

WEDNESDAY, DECEMBER 15.

GEOLOGICAL SOCIETY, at 8.—On the Constitution and History of Grits and Sandstones: John Arthur Phillips.—On the Coralliferous Series of Sind, and its connection with the last Upheaval of the Himalayas: Prof. P. M. Duncan, F.R.S.—On a New Species of *Trigonia* from the Purbeck Beds of the Vale of Wardour: R. Etheridge, F.R.S.; with a Note on the Strata by the Rev. W. R. Andrews, M.A.

METEOROLOGICAL SOCIETY, at 7.—Report on the Phenological Observations for 1880: Rev. T. A. Preston, M.A.—On the Variations of Relative Humidity and Thermometric Dryness of the Air, with changes of Barometric Pressure at the Kew Observatory: G. M. Whipple, F.R.A.S.—On the Relative Frequency of given Heights of the Barometer Readings at the Kew Observatory during the Ten Years 1870-79: G. M. Whipple, F.R.A.S.

SOCIETY OF ARTS, at 8.—The Use of Sound for Signals: E. Price Edwards.

CROYDON MICROSCOPICAL CLUB, at 8.30.

THURSDAY, DECEMBER 16.

ROYAL SOCIETY, at 4.30.

LINNEAN SOCIETY, at 8.—On the Theory of the Growth of Cuttings; Illustrated by Observations on the Bramble: Francis Darwin.—On the Genus *Durgella*, and its Anatomy: Lieut.-Col. H. Godwin-Austen.—On the means by which Leaves place themselves at Right Angles to the direction of Incident Light: Francis Darwin.—A Revision of the Genus *Vibrissea*: William Phillips.

LONDON INSTITUTION, at 7.—Electricity and Light: Dr. O. J. Lodge.

NUMISMATIC SOCIETY, at 7.

YORK'S

SERIES of SCIENTIFIC OPTICAL LANTERN SLIDES

Comprise over 2,000 of the following subjects:—Electricity, Magnetism, Sound, Telephone, Microphone, Electric Light, Light, Spectrum Analysis, Astronomy, Mines and Miners, Heat, Mechanics, Hydrostatics, Pneumatics, Human Physiology. Sample Slide and Catalogue sent on receipt of 2*s.*

F. YORK, OPTICAL LANTERN SLIDE MANUFACTURER,
87, Lancaster Road, Notting Hill, London, W.

LIGHTNING CONDUCTORS.

Experience, accumulated since the time of Benjamin Franklin, proves conclusively that a Conductor made of Copper of adequate size is the best of all appliances for the protection of every description of building from the destructive effects of lightning.

NEWALL & CO.'S
PATENT COPPER LIGHTNING CONDUCTOR,

As applied to all kinds of Buildings and Shipping in all parts of the world with unvarying success; is the most Trustworthy, most Effective, and also the Cheapest Conductor ever offered to the public.

It is simple in its application, no insulators being required, and it costs only one shilling per foot for the standard size, which ensures safety in any storm.

R. S. NEWALL & CO., 130, STRAND, W.C.
36, WATERLOO ROAD, LIVERPOOL.
68, ANDERSTON QUAY, GLASGOW.
MANUFACTORY—GATESHEAD-ON-TYNE.

NEW SMOKELESS FIRE
IN AN OPEN GRATE
ON DR. SIEMENS'S PRINCIPLE
MAY BE SEEN IN ACTION, AND PRICES AND PARTICULARS HAD, ON APPLICATION TO
FRANCIS HAMMOND
5, Chandos Street, Charing Cross,
LONDON, W.C.

Liberal Terms to Science Teachers and the Trade.
THOMAS CRAMPTON & CO.,
ELECTRICIANS, OPTICIANS,
AND
PHILOSOPHICAL INSTRUMENT MAKERS.

Electric Bells, new metallic base pattern; Constant Batteries, Indicators for use with Electric Bells, Thief and Fire Alarms, and Automatic Switches. Induction and Medical Coils, or Specialities. Hughes' Sonometers and Microphones of every form. Batteries, Magnets, and Insulated Wires of every description. Microscopic and Optical Materials. Telescopes, Opera Glasses, Microscopes, Aneroid Barometers, Electric Machines and Lime-light Apparatus.

Illustrated Catalogue, Two Stamps.

THOMAS CRAMPTON & CO., 251, HIGH HOLBORN, LONDON, W.C
Catalogue of Lowest Trade Prices on application.

£5 5*s.* ASTRONOMICAL TELESCOPE.

CRAMPTON & CO.'S IMPROVED TELESCOPE is of the highest workmanship and finish, combined with great power and clearness of definition. 3-inch Achromatic Object Lens, entirely constructed of polished brass, with Altitude and Azimuth Movements, Rackwork and Fine Adjustment, &c., &c.

THOMAS CRAMPTON & CO., 251, HIGH HOLBORN, LONDON, W.C.

ELECTRICAL AND SCIENTIFIC APPARATUS.

Wholesale Manufacturers of Electric Bells, Electric Reversing Indicators, and Constant Manganese Batteries, Telephone Switches and Transmitters. Induction Coils and Vacuum Tubes, Terminals, Carbons, Wire and all Materials. Instruments made, repaired, or altered on the premises.

Illustrated Bell List free. Complete Catalogue Two Stamps. Special Quotations to the Trade.

HENRY J. DALE, MANUFACTURING ELECTRICIAN, 4, Little Britain, London, E.C.

NOW READY,
SECOND EDITION,
GRIFFIN'S
CHEMICAL HANDICRAFT.

PRICE 4*s.* 7*d.* POST FREE.

A CATALOGUE OF CHEMICAL APPARATUS:
ILLUSTRATED, CLASSIFIED, DESCRIPTIVE.
Demy 8vo, 480 pp., Illustrated with 1,600 Woodcuts.
Most Complete and Cheapest List of Apparatus.
JOHN J. GRIFFIN AND SONS, 22, GARRICK STREET, LONDON, W.C.

ASTRONOMICAL TELESCOPE.

BATEMAN'S

WONDERFUL £5 5s. INSTRUMENT

Is the finest ever yet attempted. 3-inch Achromatic Object Lenses. Entirely constructed of polished brass; total length, 4 feet 10 inches; very highly finished with Altitude and Azimuth Movements, Rackwork, fine Adjustment, one Terrestrial and one Huyghenian Astronomical Eyepiece: will show Jupiter's Belts, Crescent Form of Venus, resolve many Nebulæ and Clusters, and divide many Double Stars, &c., &c. Prospectus post free.

J. BATEMAN,

29, CHEAPSIDE; 104, STRAND; ROYAL POLYTECHNIC, 309, REGENT STREET, AND 131, HIGH HOLBORN, LONDON.

EAGLE INSURANCE COMPANY,

79, PALL MALL.

FOR LIVES ONLY. ESTABLISHED 1807.

Accumulated Funds £3,043,542
Also a Subscribed Capital of more than £1,500,000

Reports, Prospectuses, and Forms may be had at the Office, or from any of the Company's Agents, post free.

GEORGE HUMPHREYS, Actuary and Secretary.

NOTICE OF REMOVAL.

JAMES HOW & CO.,

SCIENTIFIC INSTRUMENT MAKERS,

73, FARRINGDON ST., LONDON

(LATE OF 5, ST. BRIDE ST., AND 2, FOSTER LANE).

HOW'S STUDENT'S MICROSCOPE. HOW'S MICROSCOPE LAMP.

Rock Sections and other Objects for the Microscope.

R. W. NEEVES,

PHILOSOPHICAL INSTRUMENT

AND

INTENSITY COIL MAKER.

PRICE LIST, FOUR STAMPS.

55, SIDMOUTH STREET, LONDON, W.C.

S. C. TISLEY & Co.,

OPTICIANS,

172, BROMPTON ROAD, S.W.

(Close to South Kensington Museum).

THE PHONEIDOSCOPE

An Instrument for Observing the Colour-Figures of Liquid Films under the action of Sonorous Vibrations.

Being a visible demonstration of the Vibratory and Molecular Motion of a Telephone Plate.

The PHONEIDOSCOPE, with 3 Discs, Bottle of Solution, Descriptive Pamphlet, &c., in Cardboard Box, 10s. 6d.

MANUFACTURED AND SOLD WHOLESALE AND RETAIL BY

S. C. TISLEY & CO., 172, BROMPTON ROAD, LONDON, S.W.

TELEPHONIC ELECTRICITY. All Materials supplied for experimental purposes.

Price Lists of Electrical and Acoustic Apparatus, with Drawings and Description of the Harmonograph, Post Free, 2d.

FRY'S COCOA EXTRACT

GOLD MEDAL, PARIS EXHIBITION.

In Packets and Tins. Pure Cocoa only, with the superfluous oil extracted.

"If properly prepared, there is no nicer or more wholesome preparation of cocoa."—*Food, Water, and Air, edited by Dr. Hassall.*

J. S. FRY & SONS, Bristol and London.

HOLLOWAY'S PILLS

THIS MEDICINE

Is a Certain Cure for all Disorders of the LIVER, STOMACH AND BOWELS. A Great PURIFIER of the BLOOD; a Powerful Invigorator of the System, in cases of WEAKNESS AND DEBILITY, and is unequalled in Female Complaints

FLETCHER'S PERFECTED SOLID FLAME GAS COOKING AND HEATING BURNER.

[PATENT, 3,203.]

The only perfect Burner for Cooking, Boiling, and Dirty Laboratory Work. Free from Smell, the most powerful Burner known, and not damaged by the roughest dirtiest work. This Burner is a valuable improvement on Fletcher's well-known Solid Flame Burner, of which Thousands are in daily use. The Gauze is done away with and replaced by a Loose Perforated Dome of Solid Copper, which can be taken off and Cleaned when Choked with Dirt. The Stand is Broad and Firm, supporting Large or Small Vessels safely and steadily.



PRICE, Japanned, 6s. 6d.; Nickel-Plated, 8s. 6d.

A SMALLER SIZE IN PREPARATION.

ORIGINAL SOLID FLAME BURNER.

PRICE, with Gauze, 4s.; or Nickel-Plated, 5s.

These Burners are the same power, and will with equal ease boil an Egg, cook a Chop, boil a Kettle, or melt half a hundredweight of Lead in an Iron Pot. They will boil half a gallon of Water in a Flat Copper Kettle in Six Minutes, and work equally well with Air, Gas, or Coal-Gas.

Complete Illustrated List, Price 3d., of Gas Furnaces for Crucibles, Muffles, Ladles, Porcelain Painting, &c.; Hot and Cold Blast Blowpipes; Foot, Hand, and Automatic Blowers, Ingot Moulds, &c.; with Reprint of Mr. Fletcher's Lecture to the Society of Arts *On the Application of Gaseous Fuel to Laboratory Work*, for which he was awarded the Society's Silver Medal in June, 1880.

THOS. FLETCHER,

4 & 6, *MUSEUM STREET, WARRINGTON.*

Extra fcap. 8vo, 3s. 6d.

METALS and their CHIEF INDUSTRIAL

APPLICATIONS. By C. ALDER WRIGHT, D.Sc., Lecturer on Chemistry in St. Mary's Hospital Medical School. With Illustrations.

MACMILLAN & CO., LONDON.

With 112 Engravings and 5 Maps of the Stars.

POPULAR ASTRONOMY.

BY

PROFESSOR S. NEWCOMB, LL.D.

8vo, cloth, price 18s.

"As affording a thoroughly reliable foundation for more advanced reading, Prof Newcomb's 'Popular Astronomy' is deserving of strong recommendation."—*Nature.*

"When we take up a book written by one of the foremost astronomers, mathematically and practically, of the day, we need not fear that, however popular, it will be inexact in its language or evasive in its descriptions. Nor are we disappointed in the book before us. Throughout the whole of it we are struck by the total absence of the defects so common in popular writings. . . . It is unlike anything else of its kind, and will be of more use in circulating a knowledge of astronomy than nine-tenths of the books which have appeared on this subject of late years."—*Saturday Review.*

MACMILLAN & CO., LONDON

THE "HANSA"

Published since 1864 in Hamburg, is the only independent professional paper in Germany, dedicated exclusively to Maritime Objects. Essays, Critiques, Reviews, Reports, Advertisements. Strict eye kept upon the development of Maritime Affairs in every respect. Every second Sunday one Number in 4to at least; frequent supplements and drawings. Subscription at any time; preceding numbers of the year furnished subsequently. Price 12s. for twelve months. Advertisements 4d. a line, widely spread by this paper; considerable abatement for 3, 6, 12 months' insertion. Business Office: Aug. Meyer and Dieckmann, Hamburg, Alterwall. 28. Edited by W. v. FREEDEN, M.R., Hamburg, Alexander Street, 8.

Messrs. MACMILLAN & CO.'S PUBLICATIONS.

ETCHING AND ETCHERS. By P. G. HAMERTON. New Edition, Revised, with 48 New Plates. Columbier 8vo.

The text of the new Edition has been thoroughly revised, and increased by one-fifth. Several new Chapters and a new Preface have been added, whilst matter which had become unnecessary or disproportionate has been removed, to make room for studies of more importance. [*Immediately.*

The Edition is limited to 1000 copies, all of which have been subscribed for; particulars as to price, &c., may be obtained from any bookseller.

LIFE OF WILLIAM BLAKE. With Selections from his Poems and other Writings. Illustrated from BLAKE's own Works. By ALEXANDER GILCHRIST. A New and Enlarged Edition, with Additional Letters and a Memoir of the Author Printed on hand-made paper, the Illustrations on India paper, and mounted in the text. 2 vols., cloth gilt, elegant, with designs after BLAKE by FREDK. J. SHIELDS. Medium 8vo. £2 2s.

Several new Illustrations have been added to this work, which has long since taken its position as the standard authority on its subject; among others the following may be named:—The Phillips Portrait of Blake; two new Portraits by Blake of his Wife; a new plate from the *Jerusalem;* a newly-discovered design to *Hamlet;* and a drawing of *Blake's Cottage at Felpham.* New Photogravures of the *Inventions to the Book of Job* are given. Some thirty additional letters are included in the Biographical portion of the work, forming a new link in the already interesting life of Blake. And Mr. W. M. Rossetti has revised, enlarged, and perfected the annotated catalogue of Blake's works that appeared in the first edition of the work.

ISLAND LIFE; or, the Phenomena and Causes of Insular Faunas and Floras, including a revision and attempted solution of the Problem of Geological Climates. By ALFRED RUSSEL WALLACE, Author of "The Malay Archipelago," "The Geographical Distribution of Animals," &c. Medium 8vo, with Illustrations and Maps. 18s.

"The work throughout abounds with interest."—*Athenæum.*

"Whoever reads his book must be charmed with it."—*St. James's Gazette.*

"We have said enough to show that Mr. Wallace is led to discuss subjects of great interest to speculative minds."—*Pall Mall Gazette.*

"He takes his subject matter from all the sciences, and he builds it into a new harmonious whole."—*Fortnightly Review.*

PHYSICS OF THE EARTH'S CRUST. By Rev. O. FISHER, M.A., F.G S., Rector of Harlton, &c. 8vo. [*Shortly.*

A DICTIONARY OF MUSIC AND MUSICIANS (A.D. 1450—1878). By Eminent Artists, English and Foreign. With Illustrations and Woodcuts. Edited by GEORGE GROVE, D.C.L. In three Volumes. Parts I. to XVI. 3s. 6d. each. Vols. I. and II., cloth. 21s. each.

Vol. I. A to Impromptu. Vol. II. Improperia to Plain Song.

"Dr. Grove's Dictionary will be a boon to every intelligent lover of music."—*Saturday Review.*

IDEAL CHEMISTRY. By Sir BENJAMIN BRODIE, Bart., F.R.S. Crown 8vo. 2s.

FOOD FOR THE INVALID, THE CONVALESCENT, THE DYSPEPTIC, AND THE GOUTY. By J. MILNER FOTHERGILL, M.D., Author of "The Practitioner's Handbook," &c. Crown 8vo. 3s. 6d.

STUDIES IN DEDUCTIVE LOGIC. By W. STANLEY JEVONS, LL.D., F.R.S., Professor of Political Economy in University College, London. Crown 8vo. 6s.

"Besides these answers to questions which greatly increase the value of the book, and make it almost an independent manual of the subject, Professor Jevons has taken occasion to supplement his previous works in various directions. . . It is indispensable to the many students of the higher logic."—*Athenæum.*

GUIDE TO THE STUDY OF POLITICAL ECONOMY. By Dr. LUIGI COSSA, Professor of Political Economy in the University of Pavia. Translated from the Second Italian Edition. With a Preface by W. STANLEY JEVONS, F.R.S. Crown 8vo. 4s. 6d.

"It would be impossible to find a more compact and better-written sketch of the history of Political Economy and its latest developments. . . It is an admirable compendium and will, we hope, be widely circulated, as it will prove to many for the first time that the study of political economy is even more actively pursued on the Continent, than in England."—*Notes and Queries.*

THE ARYAN VILLAGE IN INDIA AND CEYLON. By SIR JOHN B. PHEAR. Crown 8vo, 7s. 6d.

THE IRISH LAND LAWS. By ALEXANDER G. RICHEY, Q.C., LL.D., Deputy Regius Professor of Feudal and English Law in the University of Dublin. Crown 8vo. 3s. 6d.

"To all who, either as legislators or publicists are called on to take part in the present controversy, the book will prove invaluable. The relation of the work to the discussions which now occupy so much attention is well expressed . . . . It would be difficult to find any series of legislative problems stated with greater clearness, sequence, and precision. We can recommend this little book to all who speak, write, or seriously think upon this question in or out of Parliament."—*The Times.*

With Twenty-five Illustrations by WALTER CRANE.

THE NECKLACE OF PRINCESS FIORIMONDE: and other Stories. By MARY DE MORGAN. Extra fcap. 8vo. 6s.

ALSO AN EDITION, Printed by Messrs. R. and R. Clark, on hand-made paper. The Plates, initial letters, head and tail pieces being printed on India paper and mounted in the text.

The Edition is limited to ONE HUNDRED COPIES. Fcap. 4to.

"The stories display considerable originality, and Mr. Crane's characteristic illustrations combine with Miss de Morgan's pretty fancies to form a charming gift-book."—*Graphic.*

"A real gem."—*Punch.*

ENGLISH MEN OF LETTERS. Edited by JOHN MORLEY. Crown 8vo. 2s. 6d. (New Volumes.)

WORDSWORTH. By F. W. H. MYERS.

LOCKE. By Professor FOWLER.

"This is an exceedingly good little book."—*St. James's Gazette.*

A CHRISTMAS CHILD: a Sketch of a Boy-life. By MRS. MOLESWORTH, Author of "Carrots," "The Cuckoo Clock," &c. Illustrated by WALTER CRANE. Globe 8vo. 4s. 6d.

"A very sweet and tenderly drawn sketch with life and reality manifest throughout. Very few can rival Mrs. Molesworth in the power of making us see the children of fancy, and in this 'Christmas Child' something has given to her pen a special power."—*Pall Mall Gazette.*

THE WHITE RAT, AND SOME OTHER STORIES. By LADY BARKER. Illustrated by W. J. HENNESSY. Globe 8vo. 4s. 6d.

PANSIE'S FLOUR BIN. By the Author of "When I was a Little Girl," &c. Illustrated by ADRIAN STOKES. Globe 8vo. 4s. 6d.

"Worthy to be classed with 'Alice in Wonderland,' and in some respects is better adapted to juvenile comprehension."—*Morning Post.*

FIRST LESSONS IN GREEK. Adapted to Goodwin's "Greek Grammar," and designed as an Introduction to the "Anabasis" of Xenophon. By JOHN WILLIAMS WHITE, Ph.D., Assistant Professor of Greek in Harvard University. Crown 8vo. 4s. 6d.

XENOPHON'S ANABASIS. Books I.—IV. Edited by Professors W. W. GOODWIN and J. W. WHITE, of Harvard University. Fcap. 8vo. 5s. [Macmillan's Classical Series.

"This is an excellent school-book . . . . There are many editions of the Anabasis or its parts, but we are inclined to think that this is the best for a young scholar who is bent on making himself a good one."—*Dublin Evening Mail.*

THE STORY OF ACHILLES, FROM HOMER'S ILIAD. Edited, with Notes and Introduction, by the late J. H. PRATT, M.A., Fellow of Trinity College, Cambridge, Assistant-Master at Harrow; and WALTER LEAF, M.A., Fellow of Trinity College, Cambridge. Fcap. 8vo. 6s. [Macmillan's Classical Series.

LIVY.—SCENES FROM THE HANNIBALIAN WAR. Adapted for the use of Beginners by G. C. MACAULAY, M.A., Assistant-Master at Rugby. 18mo. 1s. 6d. [Macmillan's Elementary Classics.

"This is an adaptation of Livy's difficult text to the wants of beginners, the peculiarities of Livy's beautiful style being carefully, and most ingeniously preserved, while its difficulties are entirely removed . . . We heartily recommend this little book for use in schools. There could be no better introduction to Livy nor to the art of Latin Prose Composition."—*Dublin Evening Mail.*

MACMILLAN'S PROGRESSIVE FRENCH COURSE. By EUGÈNE-FASNACHT, Author of "Progressive German Course," &c. Third year, containing:—Systematic Syntax and Lessons in Composition. Fcap. 8vo. 2s. 6d.

MACMILLAN AND CO., LONDON.

STANDARD AND OBSERVATORY TIMEKEEPERS.

TRADE DENT MARK MANUFACTURED BY E. DENT & CO. TRADE DENT MARK

	Guineas.
Standard Clock, suitable for Private Residences in Town or Country, or Public Institutions, beating seconds and going eight days with once winding; in carved and decorated oak or mahogany case ... ... from	35
(*a*) The same, but going one month with once winding ... ... from	40
Standard Observatory Mean-time Clock	80
(*a*) The same, but furnished with electrical contact apparatus with eccentric screw adjustments for dropping a time ball, or transmitting hourly signals	92
Standard Observatory Sidereal Clock	80
(*a*) The same, but furnished with electrical contact apparatus with fine vertical and horizontal screw adjustments for transmitting seconds, currents for controlling other clocks, &c.	95
(*b*) The same, but arranged to omit the current at every 60th second, for pricking on chronograph barrel, &c.	97
Standard Observatory Clock, of the most refined construction, with barometric compensation, &c. ...	160
(*a*) The same, with Sir Geo. Airy's escapement ...	170
(*b*) The same, with M. Leverrier's electrical contact system	200

The New Standard Clock (the primary standard timekeeper of the United Kingdom) of the Royal Observatory, Greenwich, was constructed by E. Dent & Co., and precisely similar instruments are now being made for the Royal Observatories of Spain and Belgium. Standard Clocks of less refined construction for the Observatories of Edinburgh (Royal), Dunsink (Royal Irish), Oxford (University), Pulkowa (Russian Imperial), Geneva (National Swiss); and many others, Foreign and Colonial, have been manufactured.

Galvanic Chronographic Apparatus, for registering the time of occurrence of transits and other astronomical phenomena ... ... from 120

The Great Galvanic Chronograph of the Royal Observatory, Greenwich, and the still more powerful Apparatus for the Royal Observatory, Brussels, and other smaller ones for other Observatories were constructed by E. Dent & Co.

E. DENT & CO.,

WATCH, CLOCK, AND CHRONOMETER MAKERS,

61, STRAND, & 34, ROYAL EXCHANGE. FACTORY, GERARD STREET, LONDON.

MICROSCOPIC SPECIALITIES.

		£	s	d
Series	I.—24 Medical Pathological Preparations, in Case	2	2	0
,,	II.—24 Physiological Preparations, in Case	2	2	0
,,	III.—24 Educational ,, ,,	2	2	0
,,	IV.—48 Physiological ,, ,,	4	4	0
Series	V.—24 Preparations from the Frog, in Case	2	2	0
,,	VI.—24 Surgical Pathological Preparations	2	2	0
,,	A.—48 Diatomaceæ (selected)	2	10	0
,,	B.—24 ,, (very rare)	1	11	6

Pathological and Physiological Preparations in great and constantly increasing variety, and of most valuable descriptions. 15s. to 30s. per doz.

Descriptive Lists and full particulars on application to

ARTHUR C. COLE & SON,

ST. DOMINGO HOUSE, OXFORD GARDENS, NOTTING HILL, LONDON, W.

LATE OF 62, ST. DOMINGO VALE, EVERTON, LIVERPOOL.

W. LADD & CO.,

SCIENTIFIC INSTRUMENT MANUFACTURERS,

(By Appointment to the Royal Institution of Great Britain),

11 AND 12, BEAK STREET, REGENT STREET, W.

IMPROVED HOLTZ ELECTRICAL MACHINES. GRAMME'S MAGNETO-ELECTRIC MACHINE for Laboratory use.

PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3s. per oz.

Physical Apparatus of every Description.

ILLUSTRATED CATALOGUE, SIXPENCE.

PATERSON'S NEW CATALOGUE OF PHYSICAL APPARATUS.

LANTERN SLIDES for SCIENTIFIC LECTURES. Season 1880-1. Post free 6 Stamps.

Complete Sets of Physical Apparatus for Science Primers and all the Physical Text-books in use in Schools and Colleges.

Siemens and Gramme Dynamo Machines and Lamps for hire.

Schools supplied with Apparatus as per Science and Art Departments' Requirements in the Sections of Light, Heat, Sound, and Electricity.

Electric Signals for Houses, Hotels, &c., Colliery Signals, Lightning Conductors. The Gower-Bell Loud-speaking Telephone.

EDWARD PATERSON, Electrical Engineer.

SHOW ROOMS AND STEAM WORKS:—76, LITTLE BRITAIN, E.C. (late 3, Bedford Court, W.C.).

MOLISON'S HARMONOGRAPH; executes the Harmonic Curves in the most perfect manner. 15s. and 20s.

Illustrated Catalogue of Electrical Apparatus, Part 1, post free, 6 Stamps. Bells, Electric Signals, Part 2, 6 Stamps.

Printed by R. CLAY, SONS, AND TAYLOR, at the [illegible] and 8, Bread Street Hill, Queen Victoria Street, in the City of London, and published by MACMILLAN AND CO., at their Office [illegible] and in Bedford Street, Covent Garden.—THURSDAY, December 9, 1880.

NATURE

A WEEKLY ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
Of Nature trusts the mind which builds for aye."—WORDSWORTH

No. 581, Vol. 23] THURSDAY, DECEMBER 16, 1880 [Price Sixpence

Registered as a Newspaper at the General Post Office.]

[All Rights are Reserved.

TRADE DENT MARK

61, STRAND, and 34, ROYAL EXCHANGE, LONDON.

MANUFACTURERS OF

CHRONOGRAPH WATCHES,

POCKET CHRONOMETERS,

INDEPENDENT & STOP-CENTRE SECONDS WATCHES.

MANUFACTURERS OF

GALVANIC CHRONOGRAPHS

AND STANDARD ASTRONOMICAL CLOCKS

FOR OBSERVATORIES

(The Standard Clocks and Great Standard Galvanic Chronographs of the Royal Observatory, Greenwich, and the Japanese and Brussels Observatories are manufactured by E. DENT AND CO.)

DENT'S CATALOGUE, New Edition, containing some hundreds of varieties of Watches, Clocks, &c., sent free on application to 61, STRAND, or 34, ROYAL EXCHANGE, LONDON.

MAGIC LANTERNS AND DISSOLVING VIEWS.

The Cheapest and best House in London for Phantasmagoria Lanterns and Dissolving Views.

C. BAKER'S, 244 & 245, HIGH HOLBORN.



A first-class Set of DISSOLVING VIEW APPARATUS, complete, that will fill a Disc 10 feet in Diameter, **£7**.

Ditto, ditto, with OXYHYDROGEN APPARATUS complete, from **£10 10s.**

MAGIC LANTERNS, with 3½-INCH CONDENSER, GIVING A 10-FOOT DISC, **£2 10s.**

A LARGE ASSORTMENT OF SMALLER SIZES, WITH SETS OF SLIDES, from 6*s.* 6*d.*

An extensive Stock of first-class PHOTOGRAPHS, Coloured and Plain, from 1*s.* 3*d.* each.

BEAUTIFULLY-PAINTED SLIDES in every variety of subject.

A Collection of Lanterns and Views, specially kept for Hire. Catalogues free by post.

BROWNING'S ELECTRIC LAMPS.

Electric Regulator Automatic.

This Lamp will give a powerful and steady light with from 10 to 20-quart size Grove or Bunsen's Cells,

£2 5s. 0d.

Illustrated List Free.

JOHN BROWNING,

Optical and Physical Instrument Maker to Her Majesty's Government,

68, STRAND, LONDON, W.C.

Factory—
Southampton Street and Exeter Street, London.

Prize Medal, 1862.

ESTABLISHED 100 YEARS.



STANDARD METEOROLOGICAL INSTRUMENTS



ILLUSTRATED PRICE LISTS FREE BY POST.

NEGRETTI & ZAMBRA,

Opticians and Scientific Instrument Makers

TO HER MAJESTY THE QUEEN,

HOLBORN VIADUCT,

45, CORNHILL, & 122, REGENT STREET, LONDON.

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 48N, Tollington Road, Holloway, London, N.

CIVIL SERVICE COMMISSION.—Open

Competition in London, Edinburgh, and Dublin, for One Situation as SECOND ASSISTANT ASTRONOMER in the Royal Observatory, Edinburgh, January 18. Age, 17–33.—For Regulations and Forms of Application address the SECRETARY, London, S.W.

UNIVERSITY OF LONDON.

PRELIMINARY SCIENTIFIC AND 1ST M.B. EXAMINATIONS.

Special Classes in all the Subjects required for these Examinations will commence at St. Thomas's Hospital Medical School early in JANUARY. Full particulars may be obtained from the Secretary, Dr. GILLESPIE.

ROYAL SOCIETY OF LITERATURE.—

Mr. WALTER DE GRAY BIRCH will read a Paper on WEDNESDAY, December 22, at 8 p.m., entitled "Pictures from the Life of Saint Guthlac, a Twelfth Century Roll in the British Museum."

W. S. W. VAUX, Sec. R.S.

ROYAL AGRICULTURAL SOCIETY OF ENGLAND.

ESSAY PRIZE.

A Prize of £20 has been offered by the Countess de Noailles for the best Essay "On the Benefit to Flocks and Herds which would accrue from giving them Access to Running Water to drink in place of the Water of Stagnant Ponds."

Competing Essays must be sent in before FEBRUARY 1st. Other conditions may be obtained on application to H. M. JENKINS, Secretary.

12, Hanover Square, London.

A GENTLEMAN who has a thorough

knowledge of English, French, and German will be glad to undertake Scientific and other Translations.—"N.," 21, Pyrland Road, N.

A 6½-inch ALTAZIMUTH TELESCOPE,

with Portable Stand on Wheel, Door in Tube, Solar and Day Eye-pieces by Browning, For Sale, nearly new.—For Price and Order to View, apply to J. WILLSON LANGFORD, Brixton Rise.

SCIENTIFIC PRESENTS.

1.

Facsimiles of 28 of the most celebrated White and Coloured Diamonds, wrought in Crystal Glass, of great lustre, £12 12s.

2.

Models of Natural Crystals of Diamonds, with other Models of Crystals of Coloured Precious Stones. £6 6s.

Each Set in handsome Morocco Case with Descriptive Catalogue.

Obtained the Bronze Medal, Paris Exhibition of 1878.

Address—Mr. R. DAMON, Weymouth.

CHRISTMAS PRESENTS.—The Popular

SCIENTIFIC POCKET CABINET SERIES. (SECOND EDITION.)

20 Specimens of Rocks, Fossils, and Minerals to illustrate Prof. Geikie's Geology Primer.

25 Minerals, Rocks, and Fossils to illustrate Bonney's Geology.

25 British Rocks. 25 British Fossils. 25 Earthy Minerals. 25 Metalliferous Minerals. 25 Metals and Alloys. 25 Recent Shells. 20 Rough Gems and Stones.

Each Collection complete in itself, price 2s. 6d.

*** The Specimens are sufficiently large for recognition of the Species, and are contained in Small Cabinets suitably adapted for carrying in the Pocket.

THOMAS J. DOWNING, Geologist, &c., 38, WHISKIN STREET, LONDON, E.C. N.B.—Post Office Order or Cheque must invariably accompany all Orders, with an additional Fourpence on each set for free delivery.

MARINE AQUARIA.

Animals and Plants, microscopic or otherwise, supplied in large or small quantities.

W. SHRUBSOLE, JUN., Sheerness-on Sea.

NEW GAME—"A VOYAGE ROUND the

WORLD." Amusement and Instruction (*vide* Press opinions). Price 21s. To be had at Fancy Repositories, or from J. B. ROGERS, St. Clement's House, Lombard Street.

THOMAS D. RUSSELL'S

NATURAL HISTORY STORES,

48, ESSEX STREET, STRAND, W.C.

Students and others are invited to inspect the Collections of British and Foreign Shells, Corals, Zoophytes, Annelids, Crustacea, Echinoderms, Minerals, Fossils, Rock Specimens, Microscopic Objects, &c.

Cabinets, Geologist's Hammers, Glass Capped Boxes, Card Trays, Tablets, Glass Slips, Micro-Thin Glass, Canada Balsam, Marine Glue, and other requisites for the Geologist and Microscopist.

Catalogues Post Free.

LIVING SPECIMENS FOR THE MICROSCOPE.

THOMAS BOLTON, NATURALISTS' and MICROSCOPISTS' STUDIO, 17, ANN STREET, BIRMINGHAM.

T. B. has last week sent to his subscribers the Infusorian, *Distygmæ Proteus*, with sketch and description. He has also sent out Marine Polyzoa and Hydrozoa; also Hydra, Cordylophora, Stephanoceros, Floscularia, Volvox; Desmids, Diatoms, Nitella, Amœba, Difflugia, Arcella, &c.

Weekly announcements will be made in this place of organisms T. B. is supplying.

Specimen Tube, One Shilling, post-free.

Twenty-six Tubes in course of Six Months for Subscription of £1 1s.

Price List of Specimens on application, with stamped addressed envelope.

Portfolio of Drawings, No. 3, One Shilling.

BRYCE-WRIGHT'S LATEST ARRIVALS.

MINERALS.—Crystallised Hessite, Crystallised Golds, Krennerite, Crystallised Atacamites, Malacone, Euclase, Edingtonite, Suzannite, Chanarcillite, Proustite, &c.

METEORITES.—Specimens of the following Falls:—Wold Cottage, Yorkshire; Java; Orvinio, Italy; Amana, Ohio; Tipperary, Ireland; Java; Orvinio, Italy; Estherville; Hainholz; Grosnagy, Russia; Borkut; Carthago Co.; Bates Co.; Sierra di Chaco; Ashville Co.; Bates Co.; Pallas; Ashville Co., &c., &c.

BRYCE-WRIGHT, F.R.G.S., &c.,

Mineralogist and Expert in Gems and Precious Stones,

90, GREAT RUSSELL STREET, BLOOMSBURY, LONDON, W.C.

MINERALOGY AND GEOLOGY.

MR. HENSON, who has just returned from Cornwall, has procured some VERY FINE CORNISH MINERALS, including some most splendid LARGE CRYSTALS of LIBETHENITE, and CHALCOSIDERITE, recently found.

FINE CRYSTALLISED CASSITERITE, LIROCONITE, BRILLIANT CUPRITE; also VERY GOOD CHALCOTRICHITE, BISMUTHINE, COPPER MICA, and HENWOODITE.

From Derbyshire, large Crystals of PHOSGENITE and MATLOCKITE.

From Sweden, VERY FINE AUGITE and AVANTURINE.

COLLECTIONS FOR STUDENTS, from £2 2s. COLLECTIONS FOR BEGINNERS, from 4s. BLOWPIPE CASES AND APPARATUS.

PRIVATE LESSONS AND EVENING CLASSES.

Catalogues free.

SAMUEL HENSON,

277 (*Late* 113*a*), STRAND, LONDON, W.C.

"NATURE," Nov. 7, 1878.—One Shilling

each will be paid for Copies of this number.—Address Publishers of NATURE, 29, Bedford Street, Strand, W.C.

YORK'S

SERIES of SCIENTIFIC OPTICAL LANTERN SLIDES

Comprise over 2,000 of the following subjects:—Electricity, Magnetism, Sound, Telephone, Microphone, Electric Light, Light, Spectrum Analysis, Astronomy, Mines and Miners, Heat, Mechanics, Hydrostatics, Pneumatics, Human Physiology. Sample Slide and Catalogue sent on receipt of 2s.

F. YORK, OPTICAL LANTERN SLIDE MANUFACTURER,

87, Lancaster Road, Notting Hill, London, W.

GEOLOGY AND MINERALOGY.

JOHN TYM has ready for Sale, at low prices, Educational Collections of Fossils, Rocks, and Minerals, specially arranged to illustrate the text-books of Lyell, Geikie, Bonney, Collins, Davies, Skertchley, Dana, Page, Jukes, &c. Series of Specimens for School and College Museums are also supplied at very reasonable prices. Catalogues post free.

Postal Address:—CASTLETON, *vid* SHEFFIELD.

GEOLOGY.—In the Preface to the STU-

DENT'S ELEMENTS of GEOLOGY, by Lyell, 1874, he says: "As it is impossible to enable the reader to recognise rocks and minerals at sight by aid of verbal descriptions or figures, he will do well to obtain a well-arranged collection of specimens, such as may be procured from Mr. TENNANT (149, Strand), Teacher of Mineralogy at King's College, London." These Collections are supplied on the following terms, in plain Mahogany Cabinets:—

100 Specimens, in Cabinet, with 3 Trays	£2	2	0
200 Specimens, in Cabinet, with 5 Trays	5	5	0
300 Specimens, in Cabinet, with 9 Drawers	10	10	0
400 Specimens, in Cabinet, with 13 Drawers	21	0	0

More extensive Collections at 50 to 5,000 Guineas each.

ROCK SECTIONS & ROCK SPECIMENS.

Collections of Rock Specimens to illustrate Rutley's "Study of Rocks" specially prepared. 100 Small Specimens in Cabinet, One Guinea: 200 Specimens, Two Guineas. Extensive and choice Series of Rocks for selection. New List of Sections of Rocks for Microscope, and List of Collections, &c.

JAMES R. GREGORY'S

Extensive New Museum and Show Rooms,

88, CHARLOTTE STREET, FITZROY SQUARE.

LA SEMAINE FRANÇAISE: a Weekly Newspaper and Review in the French Language. Politics, Literature, Science, Art, Varieties, Notes. Price 3*d.*, through booksellers, and at the railway bookstalls. Office, 37, Southampton Street. Strand, W.C.

LA SEMAINE FRANÇAISE: Journal Française pour l'Angleterre: Politique, Littérature, Sciences, Arts, Variétés, Nouvelles, et Notes. Un exemplaire par la poste, 3½*d.*, en timbres poste. Abonnement franco par la poste—un an, 15*s.* 2*d.*; six mois, 7*s.* 7*d.* Prix 3*d.*, chez tous les libraires et aux gares des chemins de fer. On s'abonne aux bureaux, 37, Southampton Street, Strand, Londres, W.C.

LA SEMAINE FRANÇAISE.—"'La Semaine Française' has been brought out in London for the benefit of those English readers who may wish to study contemporary French from all points of view, instead of confining their reading to one particular Gallic print. It certainly merits success."—*Graphic.*

LA SEMAINE FRANÇAISE.—"The numbers before us are full of good things. . . . . It will be far better for most than any one of the best papers published in Paris itself. We are much pleased with the character of it, and believe it will be highly valued in all those many households where French is cultivated. The printing is very well done."—*Queen.*

TERMS OF SUBSCRIPTION:—

	s.	d.
Three months	3	10
Six ,,	7	7
Twelve ,,	15	2

P.O.O. payable to T. SPANSWICK, at King Street, Covent Garden, W.C.
Publishing Office, 37, Southampton Street, Strand, W.C.

5me ANNÉE **L'ÉLECTRICITÉ** 5me ANNÉE

Paris. — 16, *rue du Croissant.* — *Paris*

Revue spéciale populaire, illustrée, bi-mensuelle contenant 24 pages grand in-8° à deux colonnes, formant chaque année un magnifique volume de 400 pages orné de plus de 200 gravures.

Rédacteur en chef : **W. DE FONVIELLE**
Directeur : **E. de Clisson**

Envoi gratis de numéro spécimen sur demande

Un numéro 75 centimes

Paris et Départements : Un an..... 12 fr.
Etranger. — Union postale : Un an..... 14 fr.

Les Abonnements partent du 5 et du 20 de chaque mois.

Now ready, post quarto, cloth gilt, 272 pages. Price 16*s.*

LIGHTNING
CONDUCTORS:
THEIR
HISTORY, NATURE, AND MODE OF APPLICATION.

By RICHARD ANDERSON, F.C.S., F.G.S.,
Member of the Society of Telegraph Engineers; Assoc. Inst. C.E.

With numerous Illustrations.

"The book is one to be commended to the builders of, or dwellers in, lofty houses, to the deans of our cathedrals, to the parsons of churches with lofty spires or towers, and to all owners, constructors, or occupiers of buildings which, from their height or situation, are exposed to danger from lightning."—*The Athenæum.*

"The book is clearly and sensibly written, and sufficiently illustrated, and is the work of a practical man who thoroughly understands what he is talking about."—*The Academy.*

London: E. & F. N. SPON, 46, Charing Cross.
New York: 446, Broome Street. 1880.

EDITED BY HENRY WATTS, B.A., F.R.S.,
Editor of the *Journal* of the Chemical Society

FOWNES' PHYSICAL and INORGANIC CHMISTRY. Twelfth Edition, with Coloured Plate and 154 Engravings, crown 8vo. 8*s.* 6*d.*

Also,

FOWNES' CHEMISTRY OF CARBON COMPOUNDS; or, ORGANIC CHEMISTRY. Twelfth Edition, with Engravings, crown 8vo. 10*s.*

London: J. & A. CHURCHILL.

New Edition, very much enlarged, 21*s.*

HOW TO WORK WITH THE MICROSCOPE.

By LIONEL S. BEALE, F.R.S.,
President of the Royal Microscopical Society.

THE FIFTH EDITION,
Strongly bound and enlarged to 530 Pages, with 100 Plates, some of which are Coloured, is now ready.

HARRISON & SONS, Pall Mall.

THE NEW BIOLOGICAL JOURNAL.

ARCHIVES DE BIOLOGIE.

Edited by Professors EDOUARD VAN BENEDEN of Liège, and VAN BAMBEKE of Ghent.

This Journal is devoted to the publication of original Memoirs on the Embryology, Histology, Physiology, and Comparative Anatomy of Plants and Animals. Each number is illustrated with numerous Coloured Plates, and appears at the commencement of the Quarter.

Price:—A Single Number, Six Shillings and Sixpence. Annual Subscription: Twenty-five Shillings, or Twenty-seven Shillings post free.

Orders received by Messrs. WILLIAMS & NORGATE, 14, Henrietta Street, Covent Garden, London.

In the first two numbers have appeared:—
VAN BENEDEN: On the Embryology of the Mammalia.
VAN BAMBEKE: On the Cleavage of the Egg in Batrachia.
FOL HINGER: On the Termination of Nerves in the Muscles of Insects.
FREDERIQUE AND VANDEVELDE: On the Physiology of the Muscles and Nerves of the Lobster.
MACLEOD: On the Harderian Gland of the Duck, &c., &c.

On the 1st of every Month, price One Shilling.

THE ZOOLOGIST:

A MONTHLY MAGAZINE OF NATURAL HISTORY.

Third Series. Edited by J. E. HARTING, F.L.S., F.Z.S., Member of the British Ornithologists' Union; contains—

Original articles by well-known naturalists in every branch of zoology; habits of animals; arrival and departure of migratory birds; occurrence of rare birds; distribution and migration of British fresh-water fish; new or rare marine fish; local aquaria; British reptiles, British land and fresh-water mollusca, with remarks on the haunts and habits of the species; and other matters of general interest to those who delight in natural history. Reports of the Linnean, Zoological, and Entomological Societies. Reviews of natural history books. Occasional translations from foreign zoological journals of important and interesting articles in various branches of zoology. There are occasional woodcuts.

JOHN VAN VOORST, 1, Paternoster Row.

THE BREWERS' GUARDIAN:

A Fortnightly Paper devoted to the Protection of Brewers' Interests, Licensing, Legal, and Parliamentary Matters.

REVIEW OF THE MALT AND HOP TRADES; AND WINE AND SPIRIT TRADE RECORD.

The Organ of the Country Brewers.

"The Brewers' Guardian" is published on the evenings of every alternate Tuesday, and is the only journal officially connected with brewing interests. Subscription, 16*s.* 6*d.* per annum, post free, dating from any quarter-day. Single Copies 1*s.* each. Registered for transmission abroad.

Offices—5, Bond Court, Walbrook, London, E.C.

Now completed, by the publication of the Third Volume,

A THEORETICAL and PRACTICAL TREATISE on the MANUFACTURE of SULPHURIC ACID and ALKALI, with the Collateral Branches. By GEORGE LUNGE, Ph.D., F.C.S., Professor of Technical Chemistry at the Federal Polytechnic Schools, Zurich; formerly Manager of the Tyne Alkali Works.

Vol. 1. 658 pages, 309 Illustrations, £1 16*s.*
Vol. 2. 708 ,, 267 ,, £1 16*s.*
Vol. 3. 438 ,, 135 ,, £1 4*s.*

JOHN VAN VOORST, 1, Paternoster Row.

Now ready.

EXERCISES in PRACTICAL CHEMISTRY. Vol. I. (ELEMENTARY EXERCISES). By A. G. VERNON HARCOURT, M.A., F.R.S., Senior Student of Christ Church, and Lee's Reader in Chemistry; and H. G. MADAN, M.A., Fellow of Queen's College, Oxford. Third Edition, Revised and considerably Enlarged, crown 8vo, cloth, 9*s.*

London: HENRY FROWDE, Clarendon Press Warehouse, 7, Paternoster Row.

MR. JENNINGS' RAMBLES.

Just out, with 23 Illustrations, post 8vo, 12*s.*

RAMBLES AMONG the HILLS in the PEAK of DERBYSHIRE and in the SOUTH DOWNS; including Visits to Chatsworth, Bolsover, Hardwicke, Ashopton, the Woodlands, Castleton, the Kinderscout, and Sherwood Forest. Also Walks in the South Downs, from Petersfield to Beachy Head, Ashburnham, Wiston, &c.; and Sketches of Old Houses, Churches, and People by the Way. By LOUIS J. JENNINGS.

Also, by the same Author.

FIELD PATHS and GREEN LANES. An Account of Country Walks, chiefly in Surrey and Sussex. With 8 Illustrations from Sketches made on the spot by J. W. WHYMPER, and Photographs. Post 8vo. 10*s.* 6*d.*

JOHN MURRAY, Albemarle Street.

Just published, royal 8vo, with Three Coloured Plates, 5*s.*

PTEROPHORIDÆ of CALIFORNIA and OREGON. By Lord WALSINGHAM.
JOHN VAN VOORST, 1, Paternoster Row.

Now publishing, in 4to vols., cloth, price 30s.; or bound in half russia, 36s.

THE

ENCYCLOPÆDIA BRITANNICA.

NINTH EDITION.

EDITED BY

PROFESSOR T. SPENCER BAYNES, LL.D.

Assisted by 500 Contributors.

VOLUME I.—(A—Ana).	VOLUME V.—(Can—Cle).	VOLUME IX.—(Fal—Fyz).
VOLUME II.—(Ana—Ath).	VOLUME VI.—(Cli—Day).	VOLUME X.—(G—Got).
VOLUME III.—(Ath—Boi).	VOLUME VII.—(Dea—Eld).	VOLUME XI.—(Goû—Hip).
VOLUME IV.—(Bok—Can).	VOLUME VIII.—(Ele—Fak).	VOLUME XII.—(*in the press*).

*** *A Prospectus, with specimen pages and other details, will be forwarded on Application.*

Edinburgh: ADAM & CHARLES BLACK.

COMPLETION OF THE ATLAS OF HISTOLOGY

Now Ready, Royal 4to, with 48 Coloured Plates, bound in Half Leather, price 4l. 4s., or in 13 Parts, price 6s. each.

ATLAS OF HISTOLOGY.

By E. KLEIN, M.D., F.R.S.,

Lecturer on Histology at St. Bartholomew's Hospital Medical School; and

E. NOBLE SMITH, L.R.C.P., M.R.C.S.,

Formerly Senior House Surgeon to St. Mary's Hospital.

The Illustrations by Mr. Noble Smith, from Preparations by Dr. Klein; the Text by Dr. Klein.

London: SMITH, ELDER, & CO., 15, Waterloo Place.

JUST PUBLISHED, Crown 8vo, cloth.

CONSCIOUS MATTER;

OR,

THE PHYSICAL and the PSYCHICAL UNIVERSALLY IN CAUSAL CONNECTIONS.

By H. STEWART DUNCAN.

London: DAVID BOGUE, 3, St. Martin's Place, W.C.

THE SCIENTIFIC RESULTS OF THE VOYAGE OF H.M.S. "CHALLENGER."

Now ready, Copiously Illustrated, in royal 4to, price 37s. 6d.

REPORT on the SCIENTIFIC RESULTS

of the VOYAGE of H.M.S. "CHALLENGER" during the YEARS 1873-6, under the Command of Capt. G. S. NARES, R.N., F.R.S., and Capt. F. T. THOMSON, R.N. Prepared under the Superintendence of Sir C. WYVILLE THOMSON, Knt., F.R.S., &c. (Provisional Title) ZOOLOGY—Vol. I. (containing a Provisional Introduction to the Zoological Section by Sir C. WYVILLE THOMSON, and Six Memoirs).

*** This Volume may be had also in Six Separate Parts as follows:—

PART I. *Brachiopoda.* (THOMAS DAVIDSON, F.R.S., &c.) Price 2s. 6d.
,, II. *Pennatulida.* (Prof. ALBERT KÖLLIKER, F.M.R.S., &c.) Price 4s.
,, III. *Ostracoda.* (G. STEWARDSON BRADY, M.D., &c.) Price 15s.
,, IV. *Bones of Cetacea.* (WM. TURNER, M.B. Lond., &c.) Price 2s.
,, V. *Development of the Green Turtle.* (WM. KITCHEN PARKER, F.R.S.) Price 4s. 6d.
,, VI. *The Shore Fishes.* (ALBERT GÜNTHER, M.A., &c.) Price 10s.

*** Published by Order of H.M. Government, and Printed for H.M. Stationery Office.

ZOOLOGY—Vol. II., containing Memoirs on certain Hydroid, Alcyonarian, and Madreporarian Corals, and on the Birds, is nearly ready.

London: LONGMANS & CO., JOHN MURRAY, MACMILLAN & CO., SIMPKIN, MARSHALL, & CO., TRÜBNER & CO., E. STANFORD, J. D. POTTER, and C. KEGAN PAUL & CO. Edinburgh: A. & C. BLACK and DOUGLAS & FOULIS. Dublin: A. THOM & CO., and HODGES, FOSTER, & FIGGIS.

Recently Published,

Demy 4to, with 18 Plates (5 printed in Colours), 207 pages, cloth, £2 2s.

AURORÆ:

THEIR CHARACTERS AND SPECTRA.

By J. RAND CAPRON, F.R.A.S.

Part I.—THE AURORA AND ITS CHARACTERS.
Part II.—THE SPECTRUM OF THE AURORA.
Part III.—MAGNETO-ELECTRIC EXPERIMENTS IN CONNECTION WITH THE AURORA.

By the same Author.

Demy 8vo, with 37 Plates, cloth, 30s.

PHOTOGRAPHED SPECTRA.

One Hundred and Thirty-Six Photographs of Metallic, Gaseous, and other Spectra, printed by the Permanent Autotype Process, with Introduction, Description of Plates, and Index, and with an Extra Plate of the Solar Spectrum (showing bright lines) compared with the Air Spectrum.

London: E. & F. N. SPON, 16, Charing Cross.

FOREIGN BOOKS AT FOREIGN PRICES.

WILLIAMS & NORGATE'S SCIENTIFIC BOOK CIRCULAR, No. 39. Post free, One Stamp. (Natural History, Physics, Astronomy, Chemistry, Medicine, and Surgery.)

14, Henrietta Street, Covent Garden, London; and 20, South Frederick Street, Edinburgh.

THURSDAY, DECEMBER 16, 1880

THE CHEMISTRY OF THE FUTURE

Ideal Chemistry. By Sir B. C. Brodie, Bart., D.C.L., F.R.S. A Reprint of a Lecture delivered before the Chemical Society on June 6, 1867. (London: Macmillan and Co., 1880.)

CHEMISTS who wish to study the "Calculus of Chemical Operations" will value this reprint of the lecture delivered by Sir Benjamin Brodie shortly after presenting his first memoir on the subject to the Royal Society, as it is in the main devoted to the description and explanation of the special symbols employed in the Calculus.

Even if this were the time and place, I should not venture to submit Sir Benjamin Brodie's views to that exhaustive analysis, which I believe has hitherto never been accorded to them, but which they must ere long receive at the hands of chemists. As yet only portions of the Calculus have been published, viz., Part I. "On the Construction of Chemical Symbols," and Part II. "On the Analysis of Chemical Events," although a valuable supplementary explanation of certain features was recently elicited by Naquet's criticisms. We have still to learn how the author proposed to treat of isomerism, by far the most intricate and difficult problem yet to be solved in chemistry, and let us hope that his departure from amongst us, which we now deeply lament, may not involve the suspension of judgment on this point he asked for but a short time ago being for ever.

I cannot refrain from devoting this notice to specially directing attention to what appears to me to be the topic of fundamental importance in the lecture, viz. the suggestion, made the author believes for the first time excepting in a few words at the conclusion of his first Memoir in the *Philosophical Transactions*, of the possible decomposition at the elevated temperature of the sun of certain chemical elements.

The fundamental hypothesis of the Calculus is to express the symbol of the unit of hydrogen by one letter, a. Hydrogen is to be regarded as constructed at once, by one operation. But while hydrogen is conceived of as the product of a single operation, the hypothesis indicates that oxygen, ξ^2, cannot be conceived of as made by less than two operations; while chlorine, $a\chi^2$, and nitrogen, $a\nu^2$, for example, are each to be conceived of as made by three operations, one operation in each case being that by which hydrogen is made. In short, the hypothesis involves the conclusion that there are several distinct classes—three at least—of "elements," of which hydrogen, oxygen and chlorine are the types, formed respectively by a single operation, by two similar operations, and by several operations not all similar. In other words, to quote the author, "we are led to a certain physical hypothesis as to the origin and causes of chemical phenomena." He then continues:—

"Now what I am going to suggest you must consider to be put before you with reservation, but we may conceive that in remote time, or in remote space, there did exist formerly, or do exist now, certain simpler forms of matter than we find on the surface of our globe—a, χ, ξ, ν, and so on—I say we may at least conceive of, or imagine, the existence in time and space of these simpler forms of being, of which we have some records remaining to us in such elements as hydrogen and mercury. We may consider that in remote ages the temperature of matter was much higher than it is now, and that these other things existed then in the state of perfect gases—separable existences—uncombined. This is the farthest barrier to which in the way of analysis theory can reach. Beyond all is conjecture. There may be something further, but if so, we have no suspicion of it from the facts of the science. We may then conceive that the temperature began to fall and these things to combine with one another and to enter into new forms of existence, appropriate to the circumstances in which they were placed. We may suppose that at this time water ($a\xi$), hydrochloric acid ($a\chi$), and many other bodies began to exist. We may further consider that as the temperature went on falling, certain forms of matter became more permanent and more stable, to the exclusion of other forms. We have evidence on the surface of our globe of the permanence of certain forms of matter to the exclusion of others. We may conceive of this process of the lowering of temperature going on so that these substances, $a\chi^2$ and $a\nu^2$, when once formed, could never be decomposed—in fact, that the resolution of these bodies into their component elements could never occur again. You would then have something of our present system of things."

We have here a most distinct prior statement by Sir Benjamin Brodie of views almost identical with those which have been so persistently urged for several years past by Mr. Lockyer, whose arguments, however, have hitherto met with but little sympathy from chemists, mainly perhaps on account of the unwonted character of the evidence. In his paper read before the Royal Society in December 1878, Mr. Lockyer adduced two lines of evidence in support of his hypothesis of elemental dissociation at high temperatures: The existence of lines common to several spectra—so-called basic lines—and the progressive alteration in the character of the spectra of the stars with temperature. Neither of these lines of argument has, I believe, yet been impugned, and the criticisms launched against the hypothesis have been on side issues of no real importance to the main question under discussion. More recently additional evidence in the same direction has been obtained by the comparison of the observations of Tacchini and others on solar storms. It appears that whereas at certain times lines which are admittedly all iron lines are visible, at other times certain of these lines are wanting from the spectrum, new lines appearing in their place: fluctuations of this kind taking place at frequent intervals, but evidently in accordance with some well-defined law. Facts such as these may after all meet with some other interpretation than that furnished by the "dissociation" hypothesis, although at present this affords by far the simplest explanation of them. A communication of Mr. Lockyer's, read at the last meeting but one of the Royal Society, however, adduces evidence which if confirmed must, it would seem, be regarded as final. It is well known that the velocity of uprush or downrush of vapours at the sun may be determined by observations of the amount of displacement from their normal position of the lines in the spectrum of the vapours, and obviously if all the lines in a given spectrum—that of iron, for instance—are lines due to one substance, it must be a matter of indifference by which of the lines the velocity is measured. Whereas, on the other hand, if this be not the case, and the simpler substances into which the body

is split up be of different degrees of volatility—of different molecular weight—we may expect that measurements of the displacement of different lines will not all furnish the same results. Mr. Lockyer states that in an observation of a sun-spot on August 31 of this year, when the iron line at λ 5207·6 was doubly contorted, indicating an ascending and descending velocity of about fifteen miles a second, the two adjacent iron lines at λ 5203·7 and 5201·6, visible in the same field of view, were perfectly steady. Observations of this kind are necessarily very difficult, and the communication is made with all reserve; but it is to be hoped that observers elsewhere will co-operate in at once putting this observation to the test.

It is difficult to exaggerate the importance of the question to the chemistry of the future, for should it once be proved that the dissociation of the so-called elements is taking place in the sun and still hotter stars, it will be within the power of the physicist with the aid of the telespectroscope to build up a theory of elemental evolution not inferior in interest to the doctrine of organic evolution. For my part, I have no fear of the result, for apart from Sir Benjamin Brodie's hypothesis and apart from spectroscopic evidence, I believe that in the relations of the "elements" to each other when arranged more or less in accordance with the now well-known periodic law of Mendeljeff we have distinct proof of progressive development, but of this I hope to say more on another occasion.

Sir B. Brodie points out in his lecture that if the symbol a'^2 were assigned to hydrogen, instead of the symbol a, a different symbolic system analogous in its form to the system in vogue amongst chemists would result In the second part of the Calculus he has fully explained his reasons for adopting the hypothesis a, notwithstanding that it leads to conclusions so entirely different from those ordinarily accepted, the chief reason being that this hypothesis satisfies the so-called law of even numbers—the law that the sum of all the units of affinity in a compound is an even number. The recent remarkable discovery—probably one of the most important theoretically ever made by chemists—of the behaviour of the halogens at high temperatures would appear to furnish an opportunity of experimentally ascertaining whether Sir B. Brodie's hypothesis a is admissible, for this hypothesis would not admit of a simple resolution of the diatomic molecules of chlorine, bromine and iodine into monatomic molecules which has been regarded as the more probable explanation of the results obtained by Victor Meyer and by Meier and Crafts. Two well-established exceptions to the law of even numbers exist, nitric oxide, NO, and nitric peroxide, NO_2, but as is well known, Sir B. Brodie has suggested that in these we may not be dealing with homogeneous gases, but that each is constituted of two gases which, taken together, are made up of oxygen and nitrogen, but which separately are not so made up: hypothesis a would lead to similar conclusions regarding the constitution of chlorine, bromine and iodine at high temperatures.

At present all that is *established*, however, regarding the halogens is that iodine begins to undergo dissociation at a temperature between 600° and 700°, and that its vapour gradually diminishes in density until at a white heat it attains not far short of half the "normal" value. Whatever the nature of the dissociation products, the occurrence of dissociation must be regarded as *placed beyond doubt*, for Victor Meyer's results have been in the main confirmed not only by Meier and Crafts, but also by Deville and Troost, who had previously obtained normal results. Bromine does not undergo dissociation so readily as iodine, the ratio of the observed to the theoretical "normal" density being, according to Meier and Crafts, ·8 for bromine when it is ·66 for iodine. In a recent communication, Victor Meyer has stated that the results of his earlier experiments with chlorine would appear to have been vitiated by some as yet undiscovered source of error; this gas probably is not dissociated except at extremely high temperatures, and it is doubtful whether there is any difference in behaviour between free and nascent chlorine.

HENRY E. ARMSTRONG

HANDBOOK OF BOTANY

Handbuch der allgemeinen Botanik. Von Prof. Dr. N. J. C. Müller. Zweiter Theil. Allgemeine Morphologie und Entwickelungslehre der Gewächse. Pp. 482, Figs. 277. (Heidelberg, 1880: Carl Winter's Universitätsbuchhandlung.)

THIS is the second instalment of a work by a single author which is to treat of all the different departments of botanical science. The first volume, which is devoted to the consideration of the Physiology and General Anatomy of Plants, was reviewed in NATURE, vol. xxi. p. 589. It is impossible to pass a more favourable verdict upon this volume than upon its predecessor. It is characterised by the same failing, namely, a want of clearness and definiteness in the statement of important facts and fundamental principles. The first section of the book is devoted to a discussion of the theory of descent, the origin of species, and the occurrence of varieties and monstrosities, with the object, presumably, of making the reader acquainted with some, at least, of the influences which determine the forms of living organisms. The account of the morphology of plants begins at p. 38, and after ten pages of general considerations the subject is actually grappled with. Prof. Müller commences with the Thallophytes, though he does not call them so, for his first section on them is headed "Der Algenstamm." It is not easy to understand what he means by the suffix "stamm"; does he mean to describe the thallus of the Alga as being a "stem," or does he use the word in the sense of "tribe"? Whichever be the true interpretation, it still remains unexplained why this word should appear as the heading of a section which treats not only of Algæ, but of Fungi as well. The prospectus of the work sets forth that the Classification of Plants is to form the subject of a subsequent volume, and there is therefore some hope that Prof. Müller will there give a classification of the Algæ which is more in accordance with facts and with reason than the one which he now follows. It is impossible to imagine on what grounds the Palmelleæ, the Protococcæ, and the Volvocineæ should be united together to form the Order Palmellaceæ, and yet this is done on p. 51 of this work, although the author is evidently aware of the fact that in Volvox reproduction is effected by means of sexually produced oospores, as his acc t plant, a singularly inaccurate one be it said ifies.

His account of the Lichens is not more trustworthy than that which he gives of Volvox. He appears to be halting between two opinions with regard to the burning question of the nature of these organisms, for although he states on p. 69 that the germinating spore gives rise to both gonidia and hyphæ, thereby implying that those cells of the thallus which do not contain chlorophyll and those which do have a common origin, yet he admits (p. 74) that the gonidia may escape from the thallus and lead an independent existence, and further (p. 84), that he has observed the formation of a lichen-thallus by the combination of algal and fungal forms which were originally distinct.

His treatment of the Cormophytes is also disappointing. If the student, anxious to become acquainted with the most recent views as to such important points as the gymnosperms of the Conifers and the morphological significance of the embryo-sac and its contents in Flowering Plants, turns to the sections of this book which profess to treat of them, he will find only a few dogmatic statements with regard to the former point, and none at all with regard to the latter. Perhaps these points may have been thought too recondite for discussion in a work which professes to be a handbook for learners of the science, but many pages are devoted to the consideration of subjects, such as the more complicated forms of phyllotaxis, which have principally a mathematical interest. Again, the morphology of the stem, of the leaf, and especially of the root, is dismissed far too summarily. It is to be hoped that these organs, as well as inflorescences, flowers, and fruits, will have justice done to them in the volume on the Classification of Flowering Plants. One further shortcoming must yet be mentioned, namely, the scantiness of the account given of the embryology of plants. This is a subject which has been much studied in recent years, and, from the title of this book, it might naturally be expected that it would give a satisfactory account of the results which have been attained. This is, unfortunately, by no means the case. Some of the facts are mentioned, it is true, but they are stated too briefly to be very intelligible, and no attempt seems to have been made to connect them together and to explain their significance.

It must be admitted that the book contains a considerable amount of information scattered through its pages, but the purely theoretical principles upon which this information has been arranged render it difficult of acquirement, and for this reason, if for no other, the book is not one which can be recommended for the use of students.

OUR BOOK SHELF

The Gardens of the Sun; or, A Naturalist's Journal on the Mountains and in the Forests and Swamps of Borneo and the Sulu Archipelago. By F. W. Burbidge. (London: John Murray, 1880.)

THIS book is the itinerary of a competent and enthusiastic botanist, whose main object was "the collection and introduction of beautiful new plants to the Veitchian collection at Chelsea," in which he so far succeeded as to add about fifty ferns to the list of those already collected in Borneo, about twenty being also new to science, and to introduce alive the giant pitcher-plant of Kina Balu (*Nepenthes Rajah*, Hook. f.). But these alone by no means show the floral riches which have induced the author to use the by no means exaggerated term "Gardens of the Sun." Amongst epiphytal orchids which here growing in mid-air "screened from the sun by a leafy canopy, deluged with rains for half the year or more at least, and fanned by the cool sea-breezes or monsoons," is found the beautiful *Phalænopsis grandiflora;* nor in the mountain vegetation are like floral riches absent; at 5000 feet the curious pitcher-plant, *Nepenthes Lowi*, was found epiphytal on mossy trunks and branches, and higher still a "large-flowered rhododendron, bearing rich orange flowers two inches in diameter, and twenty flowers in a cluster." The forests and gardens of Borneo are equally rich in native and naturalised kinds of edible fruits, the mango, pine-apple, durian, rambutan, &c., being all alike plentiful and luxuriant, and, as Mr. Burbidge remarks, in some favoured districts in Malaya the forests almost become orchards on a large scale, so plentifully are they stocked.

Zoology was naturally less followed than botany, but still a collection of birds was made, notices of which, contributed by Mr. Sharpe to the Zoological Society, are appended to the volume. We however regret to find the word "alligator" still constantly occurring, whilst the word "boa" is equally misleading. Crocodile and python are words which do not seem to find a home in the East, nor moreover in many books of Eastern travel. It is also quite erroneous to say that Borneo "is the only habitat of the wild elephant in the Malay Archipelago"; certainly so, at least, if we are not to exclude Sumatra from that region.

Many ethnological facts are scattered about the volume; the account of the Jakuns of Johore is taken and fully acknowledged from Maclay's memoir on the subject in the "Journal of Eastern Asia"; but the author contributes an interesting account of the method pursued by the Kadyans in playing the game of football. No one but the student of games knows how difficult it is to find much or any information on this point in most books of travel.

Tasmanian Friends and Foes: Feathered, Furred, and Finned. By Louisa Anne Meredith, Author of "My Home in Tasmania," &c. With Coloured Plates from Drawings by the Author, and other Illustrations. (London: Marcus Ward and Co., 1880.)

IT will probably be granted that there is developed in most people a fondness for certain of what we are pleased to call the lower forms of animals. Such are made pets of for various reasons: the sweetness of their song, the brightness of their plumage, the splendour of their scales —these phenomena act as causes that attract the senses. Their sometimes fond and gentle ways make of some, prime favourites, while a sense of their usefulness makes again of others indispensable companions to man.

Most of man's dumb companions have been taken from groups of animals with a more or less world-wide distribution; and it will no doubt be new to some of our readers to learn that in Australia—a country where the aborigines, for want of native pets, had to import at some time or another a dog—that there, such forms as brush kangaroos, wombats, bandicoots, and even great forest kangaroos—animals only known in these parts—can also become nice, quite gentle, mannerly things, doing a little damage now and then, it is true, by leaving long dirty tracks to bother the housemaid, like a boy home at Christmas time, or pulling up tulip-bulbs, or, worst of all, getting into the children's beds because they are comfortable. The beautifully got-up volume whose title heads this notice is written by a well-known and respected lady who has often before written pleasantly about her Tasmanian home and the bush friends she found or made there. In the present volume she writes an able defence of some of her dumb "marsupial" acquaintances, showing that

they too have intelligence, and that they exhibit at times a very respectable amount of common sense. The stories about them are strictly true, and from their very nature strictly new. But the volume tells also of many a two-footed friend, and the last few chapters almost exclusively treat of the fishes of the coast. There is much in this portion of the volume of interest to the scientific worker; there is much in every part of it to make it of value to those who care to learn something of the habits of Tasmanian beasts, birds, and fishes. One feature of the volume must be specially noticed—the eight coloured drawings, excellently chromolithographed from the water-colour drawings of the author. From a personal knowledge of the splendid colouring often present in freshly-caught tropical fishes, these plates are, we should say, by no means too brilliant. Four are devoted to some of the strange, wondrously-coloured fishes, and four to flowers, fruits, and insects.

This volume would be an excellent and not over-expensive Christmas present, which may lie on any table however select, and be read by any person however critical.

LETTERS TO THE EDITOR

[*The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts. No notice is taken of anonymous communications.*]

The Editor urgently requests correspondents to keep their letters as short as possible. The pressure on his space is so great that it is impossible otherwise to ensure the appearance even of communications containing interesting and novel facts.]

Mr. Spencer and Prof. Tait

PROF. TAIT'S explanation itself shows that the word commonly applied to products of imagination, was applicable to his statements; for the only justification he assigns is that he "assumed," that is to say, imagined, that his substitution of "definition" for "formula" must have been the ground of offence. How inadequate a plea this is, will be seen on re-reading the questions I put, which were these:—

"He [Prof. Tait] says that because he has used the word 'definition' instead of 'formula,' he has incurred my 'sore displeasure and grave censure.' In what place have I expressed or implied displeasure or censure in relation to this substitution of terms? Alleging that I have an obvious motive for calling it a 'formula,' he says I am 'indignant at its being called a *definition*.' I wish to see the words in which I have expressed my indignation; and shall be glad if Prof. Tait will quote them. He says:—'It seems I should have called him the *discoverer of the formula!*' instead of 'the inventor of the definition.' Will he oblige me by pointing out where I have used either the one phrase or the other?"

Every reader would infer that, for these specific statements made by Prof. Tait, there are specific foundations, which could be named when asked for. He does not name them, for the sufficient reason that they do not exist. Unable, as he says, to see in the passages I quoted from him, anything else to call for "censure" (a strange inability!), he "of course" assumed that this change of terms was the ground of censure. And the assumption thus made, is the only warrant he assigns for these positive assertions.

This is not all, however. Prof. Tait says:—"I could not have ventured to suppose that Mr. Spencer '*did not even know that he was in the habit of saying formula rather than definition.*' This *naïve* confession cannot but be correct." Of Prof. Tait's motive for putting this statement of mine in italics and calling it *naïve*, the reader may judge for himself. How entirely correct it is, and how well Prof. Tait might have "ventured to suppose" it, will quickly appear. For there is proof that I am *not* in the habit of always saying formula rather than definition; and Prof. Tait had the proof before him. In the note on page 565 of the Appendix forming the pamphlet in question—a page which Prof. Tait must have read, since it concerns Mr. Kirkman and himself—I have used the word "definition." So that not only had Prof. Tait no evidence on which to base his distinct statements, but there was under his eyes positive evidence which negatived them.

Very possibly it will be said that the question about my uses of these words is a trivial one. But this is not the question. The question is whether it is allowable to make an opponent look absurd by ascribing to him, in a quite positive way, things which he has neither said nor implied; and that, too, when he has implied the contrary. HERBERT SPENCER

Criterion of Reality

WILL you kindly allow a learner to ask for the criterion according to which Kinetic Energy and Work are real things, while Momentum and Force are unreal? Prof. Tait says $\frac{1}{2}mv^2$ and *wh* express real things, but *mv* and *wt* unrealities (NATURE, vol. xxiii. p. 82).

If *wt* be "as unreal as is the product of a quart into an acre," how is it that *wh* is real? The illustration of quart and acre is as applicable or inapplicable to the one as to the other. In both cases we take the product of two numbers, not two concrete magnitudes, which of course it would be absurd to speak of multiplying together. In one case the product is the number of units of Momentum, in the other case it is the number of units of Kinetic Energy. If it be said that a thing is real if its quantity cannot be altered, and *vice versâ*, why is mv^2 said to be real, and *mv* unreal? They vanish together. When Prof. Tait asserts "there is no such *thing* as Force," "it is merely a convenient expression for a certain *rate*" (NATURE, vol. xiv. p. 459), he seems, if I may venture to say so, to confound the measure of Force with Force itself, and to lay himself open to Mr. Spencer's comment that "a relation changes the state of a body." Certainly *mv* is not a *thing*, but neither is mv^2 a thing: yet the latter is the measure of something which Prof. Tait asserts to be "as real as matter itself": why is not that of which the former is the measure equally real? E. G.

Bardsea

[What Prof. Tait asserts may be correct or not, but it is self-consistent. He asserts in his lecture on "Force" (NATURE, vol. xiv. p. 462) that matter and energy must be looked on as real things, *because we cannot change the amount of either*. Such expressions as $\frac{1}{2}mv^2$, and *wh*, are to be considered as *wholes*, not as products of two or more factors. This separation into factors (where one is *mv*, or *w*, for instance) he asserts to be a relic of the old erroneous belief in the trustworthiness of the impressions made on the "muscular" sense.—ED.]

Landslips

IN NATURE, vol. xxii. p. 560, I pointed out that landslips often occurred in the Salt Districts. I did not then expect that I should so soon be able to refer again to the subject; but on December 6, at an early hour in the morning, one of the largest subsidences and landslips ever known in Cheshire occurred. I pointed out that whenever fresh water reaches the rock salt it dissolves it. In certain districts in the immediate neighbourhood of Northwich the ground is completely honeycombed with rock-salt mines that had been worked out and abandoned. Into many of these fresh water had penetrated, and had become by solution strong brine. This brine has of late been extensively pumped up, and many of these extensive cavities had become nearly empty. The thin crust of rock salt forming the roof of these old mines had become gradually thinner, owing to its solution by water, and on Monday morning the roof of one pit gave way, and let the superincumbent earth down into the mine, rifting and opening the ground to the surface. The surface rift passed across the bed of a large brook, and the water of the brook ran through the crevice into the mines below. In a short time the water made a more extensive cavity, and as the brook was cut in two about 200 yards above its entrance into a large lake that was drained by the Weaver River, the water in the lower portion of the brook and of the lake, as well as of the Weaver, commenced to return and run down the enlarged cavity. For four or five hours this return stream increased in velocity, pouring down the crater-like hole. Notwithstanding the water of the brook and the return water, as well as a large body of water from another small lake entering this cavity, the water standing in the funnel-shaped hole gradually lowered. The velocity of both portions of the brook increased, and such was the force of the water that the bottom of the brook for 100 yards was scooped out from 2 feet in depth to 10 feet, and the banks were washed away,

making the brook from 30 to 40 feet wide instead of 20 as at first.

The quantity of water thus rushing down for twelve hours from the commencement would be fully 600,000 tons. The water in one direction over a surface of 160 acres was lowered one foot in the space of three hours. Shortly after this water commenced to rush below it made its way through a weak portion of a barrier wall into a rock salt mine that was being worked. This mine, extending over fifteen acres, and having a worked-out depth of eighteen feet, was completely filled and all the tools, materials, waggons, tramways, &c., entirely lost. It will be quite impossible ever to pump out the water. Besides this mine, all the old abandoned mines were filled, and the brine, which stood at 100 yards from the surface on the Sunday, stood at 24 yards on Monday night. The water being fresh, great damage was expected by the solution of the salt. This soon occurred, for an old mine that fell in forty-two years ago, and the cavity of which had been filled with water, gave way, and suddenly the whole land over a circle of about 500 feet in diameter sank, and a large portion of water escaped into neighbouring pits. The ground cracked and rifted and subsided, and a length of road of 160 yards was destroyed, as also pipes conveying brine to the salt works. A large reservoir holding brine was split across and all the brine let out; the rending of the earth passed through two kilns of bricks, dropping one-half of the kilns at least 2 feet. On the Monday afternoon a tall chimney 90 feet in height became affected, and in a few hours fell with a great crash. The air that had filled the cavities below was forced out by the inrush of water, and caused all the pits and brooks near to bubble and boil violently, whilst in some of the rifts where water occurred miniature mud geysirs were formed, throwing up mud 10 or 12 feet high. These appearances extended over a district between two brooks for the space of 2000 feet. On Wednesday night a large hole 30 yards in diameter and 30 yards deep fell in, and more subsidences are daily expected, as the fresh water will eat away the pillars supporting the roofs of the abandoned mines.

The cavity formed on Monday is full of water, and the brook now runs through it. Some idea may be formed of it when I mention that it is crater-like, and of about 200 feet in diameter. On sounding it on Wednesday I found a depth of 78 feet of water in the centre, and various depths from 70 to 60, 50, and so on to about 12 feet at the margin. On Sunday, on the spot which is now 78 feet, there was a sandbank with its surface above the water.

Serious injury has been done to one set of salt works, and five sets are stopped for want of brine, the pipes being broken and the road destroyed.

As the salt trade increases these enormous sinkings keep increasing, and become more alarming in their character.

Brookfield House, Northwich THOS. WARD

The Geology of East-Central Africa and the Subterranean Forest in Bombay

IN Mr. J. Thomson's very interesting "Notes on the Geology of East-Central Africa" (NATURE, vol. xxiii. p. 104) he remarks that doubtless the immense development of volcanic rocks described by myself (and I may add by several previous explorers) in Abyssinia is of the same age as the volcanic rocks at the Cape of Good Hope, assigned to the Trias.

Mr. Thomson has, I think, overlooked the circumstance that whatever may be the age of the Cape volcanic rocks, the teaks of Abyssinia cannot be older than Jurassic. As I have shown (*Quart. Jour. Geol. Soc.*, 1869, pp. 403, &c., and "Geology and Zoology of Abyssinia," pp. 184, &c.), there are in the Abyssinian highlands two groups of bedded dolerites and trachytes, the upper of which rests unconformably on the lower, while the latter overlies limestone with Jurassic (Middle Jurassic) fossils.

I trust that Mr. Thomson will pardon my suggesting the possibility of the Tanganyika sandstones being river valley deposits, like the Gondwana series of India, rather than lacustrine. I may be mistaken, but the description appears to me to indicate beds coarser than those usually deposited in an extensive lake basin.

In the same number of NATURE, p. 105, is a brief notice of a "Subterranean Forest in India." As I understand the account given, the forest should perhaps rather be termed submarine than subterranean. My object in calling attention to this notice however is to point out that a previous description of the same formation was published in the *Records* of the Geological Survey of India for 1878, vol. xi. p. 302. This account is by Mr. G. E. Ormiston, Resident Engineer, and agrees in all essential particulars with the note in NATURE. I appended a few remarks on the geological bearing of the discovery. The "forest" has clearly been depressed, whilst neighbouring tracts in Bombay island appear to have been elevated in comparatively recent times.

W. T. BLANFORD

Dr. Siemens's Gas-Grate

HAVING endeavoured for some years past to heat my study by gas appliances, and having utterly failed in obtaining a comfortable temperature of 60°, as a last effort to accomplish my object I had fitted into an ordinary grate Dr. Siemens's arrangement of copper and iron, the construction of which was communicated to the public in the pages of NATURE, vol. xxiii. p. 25. Before giving the results of the trial of Dr. Siemens's gas-grate I may mention in what way my former gas-stoves failed. My first gas-fire consisted of gas and asbestos, but this gave out fumes which were quite intolerable; my second trial was with a gas-stove reflecting heat from a copper lining; this not only failed to warm the room, but was a cheerless and grim apology for a fire, and to obtain even a moderate degree of temperature a constant and expensive consumption of gas was necessary. With Dr. Siemens's gas-grate all that is required to produce a good cheerful fire radiating heat to all parts of the room, and maintaining a temperature from 60° to 62°, is to turn on the gas full for about twenty minutes, and as soon as the lower stratum of coke becomes incandescent, the gas may be quite turned off, the fuel, whether coke or anthracite, continuing to burn for five or six hours without any further expenditure of either gas or fuel.

If the fire is required for a longer time, or if at any time a more rapid combustion is wanted, it is only necessary to turn on the gas again for a few minutes and add more fuel. This is my experience of Dr. Siemens's gas-grate, and I consider it a great boon to householders who desire well-warmed rooms combined with economy. After the lucid description of the gas-grate given by Dr. Siemens in NATURE, it would be presumption in me to discuss the scientific explanation of its action; I shall only, in conclusion, venture to claim for it the following advantages which I believe it to possess over every other kind of gas-stove yet invented:—

1. It gives a clear, smokeless, cheerful fire.
2. It is most economical, and very soon pays the cost of the construction.
3. Being absolutely smokeless, contributes nothing to that constituent of our London fogs which renders them injurious in so many ways.

This last advantage, if multiplied by every householder at an outlay of 25*s.*, adopting a cheaper modification than the copper and iron gas-grate, we should before very long observe a marked change for the better in our London atmosphere; and the darkness, dirt, and destruction of property with which we Londoners are annually afflicted, would be things of the past.

December 13 R. DOUGLAS HALE

Geological Climates

I HAVE just read Mr. A. R. Wallace's letter in NATURE, vol. xxiii. p. 124, but as I have not yet seen his book, "Island Life," although my bookseller had promised it, I shall defer my reply in NATURE until I shall have made myself master of his ideas.

For the present I shall only say:—1. That Mr. Wallace's proposal would benefit the Polar regions but not Bournemouth. 2. Mr. Wallace omits all mention of the *return cold currents* which the admission of two new Gulf Streams into the Arctic regions would produce. These currents would seriously lower the temperature of China and Japan; and also of the Ural Mountains and east of Europe.

SAMUEL HAUGHTON

Trinity College, Dublin, December 10

SOME weeks since the Rev. Prof. Haughton took exception to a brief letter of mine, in which I suggested that as a bamboo flourishes in Cooper's Hill College garden, in a northern aspect winter after winter, it could be used effectually in an argument relating to geological climates. The bamboo being found in torrid India now, that at Cooper's Hill, if found in a future period, would, according to some geologists, indicate that the valley of the Thames was tropical formerly. My letter was

written because the Rev. Professor had written a very long one, in which he applied this kind of bad reasoning in relation to a bit of a leafy part of a tree found at Bournemouth in an Eocene deposit. The leaves of his bit resemble those of *Araucaria Cunninghami* squashed; nevertheless a thermometric virtue is given to the fossil because this Araucaria is native in districts in Eastern Australia.

Self-satisfied with his recognition of the similarity of the leaves, the Rev. Professor coolly assumes that he has made out his species, and therefore demands the name of mine, giving me a scolding before I could possibly let him have it.

It is curious that the Rev. Professor should not have seen the point of my letter, and the only explanation is that he was so taken up with the incomparable value of his delicate "self-registering plant thermometer." I did not believe in his discovery, and my bamboo—never mind whence it came—was quite as good in the method of argument as his so-called Araucaria. No botanist would feel satisfied with the coneless evidence of the Rev. Professor, and his genus is in doubt as well as his species. With regard to this, Lindley stated years since that *Araucaria Cunninghami* is a "supposed species" in relation to the Norfolk Island *C. excelsa*. So the "self-registering thermometer" has neither bulb nor stem, and the spirit or the mercury represents the Rev. Professor's genius. He bids me plant the bamboo in the sunny south-west. Not so; it is the damp soil and the shade which have permitted the stems to grow up to 10 feet 6 inches. He tells me that the bamboo grows in China: that fact I had heard of before, and it has been strikingly impressed on many generations of Celestials. Last week, but too late for my purpose of immediate publication in NATURE, I learned that the bamboo is of the sub-genus *Arundinacea*, and the species is *falcata*. Its natural habitat is in the temperate Himalayas, where frosts, fogs, and north-east winds, such as plague the Thames Valley, are unknown.

Finally I believe that the so-called *A. Cunninghami* has grown of late years in the south of England.

December 9 P. MARTIN DUNCAN

Hailstorm in Dorsetshire

AT about 1.30 on the 25th of last November, with a strong wind from the south-west, this place was visited by a hailstorm which lasted about five minutes, accompanied by rain and violent gusts of wind, and by a single vivid flash of lightning which was followed with scarcely more than an appreciable interval by the thunder.

The character of the hailstones which fell on the occasion, and which I examined before they could have undergone any important change induced by the higher temperature of the surrounding air, may be worth noting; for though they were not of very unusual size, and in most respects scarcely departed from what may be regarded as the typical condition of hailstones, they exhibited some features not generally met with in so well-marked a form.

In their simplest condition their shape was that of a sphere, and in every such case they consisted of a spherical nucleus of



opaque white ice enveloped by a concentric shell of ice perfectly transparent and homogeneous, showing none of the radial striæ often met with in hailstones (Fig. 1). The largest measured about half an inch in diameter, the nucleus having a diameter of about a quarter of an inch. The appearance of the opaque white nucleus surrounded by its thick crystal-clear envelope was very striking and beautiful.

In many cases two such hailstones were united firmly to one another, doubtless by a process of regelation after contact. In some of these the transparent envelope was continuous around each of the nuclei in the plane of contact (Fig. 2). In others it was here deficient, and the two nuclei were then in immediate contact with one another (Fig. 3). The difference thus presented is not without significance as affording evidence that there are two distinct conditions under which the union of hailstones by regelation may occur; for it is probable that in the former case the contact and regelation had taken place directly between the nuclei while as yet free from the investing shell of clear ice which had afterwards formed around the twin nuclei; while in the latter case the envelope had already existed before the contact and regelation of the hailstones.

Another frequent occurrence was the presence of one or two little piriform offsets, which projected from the surface of the hailstone, and were, like the envelope itself, formed of clear homogeneous ice (Fig. 4). In a paper published in the *Proc.* Asiatic Society for June, 1880, to which my attention has been called by Mr. Scott of the Meteorological Office, very similar club-shaped projections of transparent ice are described by Mr. Blanford in large hailstones figured by Col. Godwin-Austen as having fallen at Calcutta in March, 1877.

It is possible that in these cases the projections had originally the form of crystals, and that their faces and angles had been rounded off in passing through a warmer region of the atmosphere, such radiating crystals of ice not being unknown. In a memoir by Abich ("Ueber Kugel Hagel im Unterem Kaukasus," Vienna, 1879), for a knowledge of which I am also indebted to Mr. Scott, an account is given of certain very large hailstones which fell at Tiflis in Georgia, and had large ice crystals radiating from the surface. GEO. J. ALLMAN

Ardmore, Parkstone, Dorset, December 11

Sargassum

I FIND in NATURE, vol. xxiii. p. 70, a short report on my paper, "Revision von Sargassum," with several objections, which I believe to be erroneous. It is said that the fragments occurring sometimes on the open sea, the so-called *Sargassum bacciferum*, should have a bright yellow colour. Not long ago I received fresh samples thereof from the Sargasso Sea, which are not yellow at all; these fragments are never bright yellow, but of the same brown, varying to yellowish colour as decaying *Fucus vesiculosus*. I observed the latter, for instance, in this condition in several fjörds of Norway, where I found broken Fucus in greater quantities than ever I did Sargassum in the open sea between England and the West Indies.

Macrocystis pyrifera shows always stem and leaves entangled in a ball, if broken and swimming in the open sea (*vide* p. 235 of my treatise), and the Sargasso fragments of the open sea are also often entangled in compact balls, as Sir Wyville Thomson states ("The Atlantic," i. 194), and as it may be seen on my phototypic table, Fig. 1.

If the floating Sargassum should have no reproductive organs, this would be no difficulty, but rather a confirmation of my views on the fragmentary nature of swimming Sargassum, for a particular pelagic species could not be without reproductive organs. Besides there have been found "with certainty" sometimes samples in the open sea with reproductive organs, and I gave an explanation of their seldom occurrence by want or breaking off of the air-vesicles. The writer on my paper is mistaken in comparing Macrocystis and Fucus with Sargassum, for the air-vesicles and reproductive organs of Sargassum are separate from the leaves and isolated on thin stalks, which break off easily, while those of Fucus and Macrocystis are never separate, but in the middle of the leaf or on the base, or on the broad end of the leaf or thallus. Therefore swimming Sargassum is found often without reproductive organs, and its air-vesicles are often broken off, whilst on Macrocystis and Fucus such a separation is not possible. Having refuted those objections, and having also brought in my paper many more arguments against the existence and vegetation of *Sargassum bacciferum* than there are mentioned in the short report, I hope that my results on Sargassum will now generally be accepted.

Leipzig-Eutritzsch, December 4 OTTO KUNTZE

Note on an Acoustical Constant

THE number of vibrations executed in a second by a stretched string is generally represented in the text-books by a formula expressing the method of its variation with the determining circumstances, such as—

$$n \propto \frac{1}{dl}\sqrt{\frac{T}{s}},$$

where d is the diameter, l the length, s the specific gravity of the string, and T the tension or stretching force, but the absolute number of vibrations is not generally given by the formula.

Now if we write instead of the above—

$$n = \frac{k}{d\,l}\sqrt{\frac{T}{s}},$$

where k is some constant, it is evident that k will not depend on the nature of the string but solely on the system of units employed to express d, l, and T.

If C.G.S. units be employed, we have, as stated in Prof. Everett's translation of Deschanel—

$$n = \frac{1}{2\,l}\sqrt{\frac{T}{m}},$$

where m is the mass of unit length; and as we may write instead of m, $\pi r^2 s$, r being the radius of the wire, we shall have—

$$n = \frac{1}{\sqrt{\pi}} \cdot \frac{1}{2rl} \cdot \sqrt{\frac{T}{s}}, \text{ or } \frac{1}{\sqrt{\pi}} \cdot \frac{1}{d\,l} \cdot \sqrt{\frac{T}{s}},$$

so that here $k = \frac{1}{\sqrt{\pi}} = \cdot 5642$ approximately.

With any other system of units we may of course determine k from the value just given, by multiplying or dividing by the ratios of the new to the C.G.S. units; for example, if d be expressed in millimetres, l in metres, and T in kilogrammes, our new constant would be—

$$k = \frac{1}{\sqrt{\pi}} \cdot \frac{10}{1} \cdot \frac{1}{100} \cdot \sqrt{981000}$$

$$= \frac{99\cdot 04}{\sqrt{\pi}} = 55\cdot 87.$$

But we may also determine k directly for any system of units in the following manner:—If, in the formula—

$$n = \frac{k}{d\,l}\sqrt{\frac{T}{s}},$$

we make d, l, T, s, each unity, we shall have—

$$n = k.$$

Imagine then a wire of water, 1 mm. diam., 1 metre long, stretched by a weight of 1 kilo.: its weight would be ·7854 grm., and H, the "tension length," or length which would be equal in weight to the stretching weight, would be $\frac{1000}{\cdot 7854}$ = 1273·2 metres. The velocity v of transmission of a pulse along the wire would be $\sqrt{gH} = \sqrt{9\cdot 81 \times 1273\cdot 2} = 111\cdot 76$ metres per second, and the number of vibrations per second—

$$n = \frac{v}{2\,l} = \frac{111\cdot 76}{2} = 55\cdot 88 = k,$$

the same figure as that obtained above.

If the units in which d, l, and T are expressed are respectively the tenth of an inch, the foot, and the pound, k becomes 48·66.

In the later editions of Ganot's "Physics" we find the formula—

$$n = 9\cdot 8257\sqrt{\frac{c}{l}}$$

given, where c is the "tension length," and l the length of the string, both expressed in inches. This formula would of course be of more easy application than those given above when we know the weight per foot of the string, but does not directly show the relation of n to the diameter and specific gravity.

W. J. GREY
Newcastle-on-Tyne J. T. DUNN

The U.S. Weather Charts

I SHOULD be much obliged if you would inform me whether the United States Monthly Charts of Meteorological Data, in continuation of the series published in NATURE, can be procured in London, and if so where. H. M.

6, Charles Street, Grosvenor Square, December 7

Climate of Vancouver Island

MR. ALFRED R. WALLACE asserts in his letter published in NATURE, vol. xxiii. p. 124, that the climate of Vancouver Island is not so mild as that of London.

For three years I commanded a gunboat on those shores; speaking from recollection, and not from recorded observations, and with great deference to so distinguished a naturalist as Mr. Wallace, I should have said that the climate of Vancouver Island was a good deal milder than that of London.

EDMUND H. VERNEY

Travellers' Club, Pall Mall, S.W., December 11

Meteors

ON the evening of November 20 at about 8 p.m. my attention was attracted by a number of meteors appearing as often as once per minute in different quarters of the heavens, but pursuing courses apparently radiating from a point near the constellation Andromeda. M. A. VEEDER

Lyons, New York, November 22

THE PROBABILITY OF PHYLLOXERA CROSSING THE TROPICS

MUCH alarm has been felt by the wine-growers of South Africa at the possibility of the phylloxera being introduced into the Cape vineyards. Very stringent regulations have been framed in consequence, prohibiting the importation of living plants or vegetables in any form; and so rigidly have these regulations been carried out that it is stated that, in accordance with them, a cargo of potatoes from New Zealand was destroyed on its reaching Capetown.

It is generally conceded by the experts who have been consulted that the importation of vines, on the tissues of which the phylloxera would be able to live in transit, must be prohibited. The phylloxera can however, it is admitted, feed on no other plant but the vine, and the important question for the South African Government to decide is whether it is really needful to exclude other plants or vegetables besides the vine. In order to obtain the best opinion upon this point, Dr. Maxime Cornu was consulted. He accordingly drew up several reports, in which he expresses the opinion that, though extremely unlikely, it is still theoretically possible that the phylloxera should be conveyed from Europe to South Africa by means of other vegetable products than the vine, and he therefore supports the prohibitive action taken by the Cape Government.

The inconvenience to the community which such a policy involves is necessarily considerable. The grounds of Dr. Maxime Cornu's decision have therefore been carefully considered by an entomologist who has studied the subject and who has drawn up the following notes. The question is of great importance to all wine-growing countries in the southern hemisphere, and as these doubtless contain many readers of NATURE, I think the publication of these notes in its columns will give them the best opportunity of being fairly considered.

W. T. T. D.

Notes on Dr. Cornu's Reports on the Phylloxera, and on the Protective Measures against its Introduction.

Among the "truths" laid down in the first report, No. I. is, "The *Phylloxera vastatrix* lives only upon the vine." This is emphasised in the third report ("Memorandum on Laws of Protection, &c."), Paragraph No. IV., stating, "they (the insects) can, moreover, subsist only upon the vine."

Notwithstanding these unreserved statements of this fundamental fact in the life history of phylloxera, the same "Memorandum on Laws of Protection, &c.," proceeds (in its "General Conclusion") to recommend, "if such a course were possible," the imitation of "the example set by Algeria, and to forbid the introduction of all vegetable products whatever, with the exception of those which are absolutely required for consumption."

It may well be asked on what ground such a recommendation is based. After stating (Third Report, Paragraph IV.) that the phylloxera cannot live when dissociated from the vine for more than four or five days, and requires protection from dessication in any case, Dr.

Cornu proceeds (Paragraph V.) to sketch "the most favourable conditions for the introduction of the insect" as follows:—"A phylloxera is removed in the soil, say a pregnant mother, which survives for a period of five days; it lays an egg before dying; the egg takes fifteen days to hatch (at the mean temperature of 59 deg. Fahr.), and the young insect which is produced five days to die. This makes in all twenty-five days." That is to say, that the maternal phylloxera, when in *articulo mortis* at the end of her five days' dessication and starvation, is to lay an egg; that this egg, produced under such extraordinary conditions, is to hatch in due course, and, after undergoing total starvation from its birth, is to live out the normal term of five days allotted to the mother (presumably well fed until she started on the dolorous voyage), and after all this is to land at the Cape and propagate its species in the nearest vineyard at hand! If these are "the most favourable conditions" under which the phylloxera would be introduced, we may surely say with Dr. Cornu in another part of the same report (Paragraph VII. *a*) that "it would require a concatenation of circumstances which it is difficult to imagine to bring about the misfortune of the insect's introduction." It is as well also to note that the writer expressly states (Paragraph V.) that the egg's hatching is accelerated when the temperature exceeds 59 deg. Fahr., so that in the supposed case, if the starveling progeny ever did see the light on the voyage, it would probably emerge in a tropical temperature long before the normal fifteen days allowed, and so resign its life of total abstinence before reaching the promised land of plenty at the Cape.

Let us now turn to the "winter egg," which, as Dr. Cornu states (Paragraph VI.), "is particularly to be dreaded." This is the rarest condition of the insect, each female of the generation which includes both sexes laying only one egg (Paragraph VI.).

"It is to this egg alone that the introduction of the phylloxera in packing-cases, straw, &c., could be attributed; this would however require confirmation; in fact I am not aware of any well-authenticated instance of the introduction of the phylloxera resulting from the transmission of the winter egg" (Paragraph VII.).

This admission on the writer's part seems to reduce any apprehension about the winter egg to infinitesimal proportions, especially when it is noted that the "winter egg," as its title implies, is a state limited to cold weather, and "commences to develop at the return of the fine weather" (Paragraph VI.). If a specimen of this rare *œuf d'hiver* did by any chance (in the absence of the vine-stems or branches upon which it is laid) start on a voyage for South Africa, we may be very sure that in its passage through the whole extent of both tropics it would very speedily cease to merit its title, and become a miserable *phylloxèra d'été*, only to share the fate of its luckless relative, produced from the last dying egg of the *mère pondeuse*. It does not mend matters to find Dr. Cornu stating in italics (Paragraph VII.), "Such introduction is nevertheless possible from a scientific point of view." Impossibility can with accuracy be predicated of but very few propositions; as a rule it is safer to say of most matters apparently incredible that it is next to impossible, and this may very certainly be said in the present case; and when all known facts and conditions place every probability against a bare possibility, wise men will know how to act.

As long as vines and all parts of vines from abroad are kept out of the Cape, the requirements of the wine industry are fully met. This prohibition was put in force by the late Government, by Proclamation No. 88, of November 30, 1876, and has been in force ever since that date. As late as the 4th December last, attention was specially directed to this Proclamation, with the intimation that its provisions would be strictly enforced (in Government Notice, No. 1288, of 1879). The present superfluous and vexatious restrictions were added by Proclamation No. 14, of January, 1880, and all the facts adduced by Dr. Cornu point to their futility.

SONGS OF THE SCIENCES—I. ZOOLOGY

WE must regard it as a noteworthy sign that science has begun to percolate so through society generally that it has reached the pages of *Punch*. Almost every week we find a bit of more or less telling waggery, and last week the first of a series of "Songs of the Sciences" appeared, which we reproduce:—

Oh! merry is the Madrepore that sits beside the sea,
The cheery little Coralline hath many charms for me;
I love the fine Echinoderms of azure, green, and grey,
That handled roughly fling their arms impulsively away:
Then bring me here the microscope and let me see the cells,
Wherein the little Zoophite like garden floweret dwells.

We'll take the fair Anemone from off its rocky seat,
Since Rondeletius has said when fried 'tis good to eat;
Dyspeptics from Sea-Cucumbers a lesson well may win,
They blithely take their organs out and then put fresh ones in.
The Rotifer in whirling round may surely bear the bell,
With Oceanic Hydrozoids that Huxley knows so well.

You've heard of the Octopus, 'tis a pleasant thing to know,
He has a ganglion makes him blush not red, but white as snow:
And why the strange Cercaria, to go a long way back,
Wears ever, as some ladies do, a fashionable "sac":
And how the Prawn has parasites that on his head make holes,
Ask Dr. Cobbold and he'll say they're just like tiny soles.

Then study well zoology, and add unto your store,
The tales of Biogenesis and Protoplasmic lore:
As Paley neatly has observed, when into life they burst,
The frog and the philosopher are just the same at first.
But what's the origin of life remains a puzzle still,
Let Tyndall, Haeckel, Bastian go wrangle as they will.

THE AUGUST AURORAS

AS I had the pleasure of witnessing to great advantage at Christiania the superb aurora of August 12 last, as well as that of the 13th, it is possible that some account of these displays as seen in Norway may be useful for comparison with accounts of their appearance in England.

My attention was first drawn to the aurora on going into the open air at 11 p.m. At 10.30 p.m. a friend had remarked that the night seemed unusually dark, and that the stars were shining brightly. When first seen by me the aurora consisted of a wide arch of diffused light, the centre of which was about 30° in height. A few broad streamers were then beginning to appear. I walked as quickly as possible to a hill whence a good view could be obtained, but I had hardly got there before the aurora had already reached, about 11.10 p.m., its maximum splendour. Broad streamers had by this time covered almost the whole of the northern half of the heavens, converging to a point considerably south of the zenith, forming a grand corona. The arch was still highly luminous, and from its upper margin coruscations or waves of white light shot up every two or three seconds towards the zenith. At this time also there suddenly appeared to the east of magnetic north a splendid sheaf of rays proceeding from the horizon altogether beyond the auroral arch, and apparently in complete independence of it. These rays, through bright, attained an elevation of only some 35°, and belonged apparently to a distinct auroral discharge. At 11.15 the arch had already begun to fade, but a mass of rays shone out brightly near its eastern termination. Throughout the display I was struck by the tendency to the formation of compact bodies of streamers which seemed to flank each end of the arch. As the arch faded the pulsations of

light increased in frequency and brilliancy, and at 11.25 they might be described as broad flashes overspreading a large part of the northern half of the sky, always travelling upwards, and sometimes passing the zenith. The main body of streamers had by this time mostly faded, after going through an extraordinary series of changes which I found it quite impossible to record. Every minute or two new rays would strike up to the zenith, or sometimes beyond, and every now and then a portion of an older ray would suddenly shine out with a kind of phosphoric light.

The display now rapidly faded, and though at 11.35 and again about 11.45 there were minor reappearances of rays, the aurora seemed to be near its end, and I returned home.

The brightness of the phenomenon was somewhat delusive; for when a superb corona of rays covered the northern sky, I could only just read my watch by its light, and could not read what I endeavoured to write down on paper. The light was either white or of a greenish yellow tinge. There was no trace of the redness or other colours seen on other occasions.

By very good fortune I was able to watch the aurora of the next night (August 13) under the most favourable possible circumstances, namely, while steaming down the Christiania Fyord, in the steamship *Angelo*, during a beautiful calm evening. The aurora began at 10.20 p.m. with a very faint uniform arch, or rather line of white light, appearing 8° or 10° above the horizon, with difficulty distinguished from the twilight. This soon faded away entirely; but at 10.35 reappeared as a very distinct luminous arch, separated by a dark space from the twilight. Some slight signs of rays now also appeared.

At 10.45 the arch seemed to be rising somewhat, without ever attaining a height of more than about 15°. The lower edge became indented by ray-like notches. There was a tendency to the formation of streamers at the flanks. At 10.50 a fine single ray shot up from the horizon right through the arch, at 10° to west of true north. Streamers also began to appear above the arch, and especially at its eastern end; but the streamers were in no way comparable to those of the previous night. The arch now began to lose its previous regular form, and to go through a remarkable series of gradual changes and contortions, which it is impossible to describe. By degrees the eastern end became incurved in the manner of a folded curtain (like the pictures of auroras in the Polar regions which we see in books), and a few fragments of rays tended to form an inferior arch.

For more than an hour the light of this aurora was steady; but about 11.30 p.m. pulsations first began to appear faintly, soon increasing in frequency and width. As the pulsations grew the arch almost insensibly disappeared, but patches of light and fragments of rays occupied the sky above where the arch had been, and were every instant lighted up, as it were, by the passing coruscations. These flashes of light became more and more frequent, following each other every second, or even several times in a second, so as to produce at last a kind of rustling or dancing appearance. They were most intense upon the rays and patches, but were not confined to them. At 12.30 the display was failing, the waves being less frequent. At 1 a.m. there remained only a few irregular patches of faint, steady light, with occasional flashing waves. The light was again white, or greenish yellow. On neither occasion did the aurora seem to have the slightest relation to the ordinary vaporous clouds of the atmosphere, nor did the dark space beneath the arch seem to be more than might be explained as the effect of contrast.

Mr. Thomas Bennett, who is well known to all Norwegian travellers, and has resided many years in Christiania, informed me that the aurora of the 12th was probably the finest he had ever seen among the many grand displays which occur in Norway. Though I have witnessed several fine auroras, including some of those seen in the United States in August and September, 1859, and two fine displays of the Aurora Australis (September 14 and 16, 1854), I cannot call to mind that I ever saw coruscations or waves of electric light at all approaching those seen at Christiania on this occasion. The books say comparatively little about these coruscations, nor do the letters in NATURE, vol. xxii. p. 361, mention them as seen in England. Yet they probably represent the most important part of the phenomenon, the active discharge of electric energy.

I neither saw nor heard anything in Norway of an aurora on the night of August 11. About the dates I give there can be no possible mistake, because the steamboat from Christiania to Hull departed as usual on Friday evening (August 13). The times mentioned are the local times by the public clock at the Christiania University Buildings. W. STANLEY JEVONS

P.S.—The above account was mostly written a few days after my return to London, according to notes taken at the time. I print it now for what it may be worth. After thinking the matter over for three months, and comparing the auroral coruscations above described with the exquisite discoveries of Mr. Crookes, taking into account also some remarks in the article on auroras in the new edition of the "Encyclopædia Britannica," I venture to make the suggestion that these coruscations arise from highly tenuous matter (in what Mr. Crookes calls the *radiant state*) projected through the higher parts of the atmosphere. It is not possible by words to give an impression of such a phenomenon in the least degree approaching to that naturally acquired by watching it under favourable circumstances for several hours. My belief is, that during the auroras described, *puffs*, as it were, of radiant matter were discharged at a great elevation above the earth's surface, and the luminosity of these puffs perhaps arises from conflicts between the projected molecules and those already spread about the almost vacuous space. The arch and most of the streamers probably belong to a lower, though still a very high part of the earth's atmosphere, but certain of the streamers, as well as patches of luminous matter seen on the night of the 13th, certainly exist in the lofty regions through which the radiant matter is projected. The explanation of the streamers must probably be approached through that of the coruscations, but they are effects of a very different kind. W. S. J.

November 22

THE INFLUENCE OF A TUNING-FORK ON THE GARDEN SPIDER

HAVING made some observations on the garden spider which are I believe new, I send a short account of them in the hope that they may be of interest to the readers of NATURE.

Last autumn, while watching some spiders spinning their beautiful geometrical webs, it occurred to me to try what effect a tuning-fork would have upon them. On sounding an A fork and lightly touching with it any leaf or other support of the web or any portion of the web itself, I found that the spider, if at the centre of the web, rapidly slews round so as to face the direction of the fork, feeling with its fore feet along which radial thread the vibration travels. Having become satisfied on this point, it next darts along that thread till it reaches either the fork itself or a junction of two or more threads, the right one of which it instantly determines as before. If the fork is not removed when the spider has arrived it seems to have the same charm as any fly: for the spider seizes it, embraces it, and runs about on the legs of the fork as often as it is made to sound, never seeming to learn

by experience that other things may buzz besides its natural food.

If the spider is not at the centre of the web at the time that the fork is applied, it cannot tell which way to go until it has been to the centre to ascertain which radial thread is vibrating, unless of course it should happen to be on that particular thread or on a stretched supporting thread in contact with the fork.

If when a spider has been enticed to the edge of the web the fork is withdrawn and then gradually brought near, the spider is aware of its presence and of its direction, and reaches out as far as possible in the direction of the fork; but if a sounding fork is gradually brought near a spider that has not been disturbed, but which is waiting as usual in the middle of the web, then instead of reaching out towards the fork the spider instantly drops—at the end of a thread of course. If under these conditions the fork is made to touch any part of the web, the spider is aware of the fact and climbs the thread and reaches the fork with marvellous rapidity. The spider never leaves the centre of the web without a thread along which to travel back. If after enticing a spider out we cut this thread with a pair of scissors, the spider seems to be unable to get back without doing considerable damage to the web, generally gumming together the sticky parallel threads in groups of three and four.

By means of a tuning-fork a spider may be made to eat what it would otherwise avoid. I took a fly that had been drowned in paraffin and put it into a spider's web and then attracted the spider by touching the fly with a fork. When the spider had come to the conclusion that it was not suitable food and was leaving it, I touched the fly again. This had the same effect as before, and as often as the spider began to leave the fly I again touched it, and by this means compelled the spider to eat a large portion of the fly.

The few house-spiders that I have found do not seem to appreciate the tuning-fork, but retreat into their hiding-places as when frightened; yet the supposed fondness of spiders for music must surely have some connection with these observations, and when they come out to listen is it not that they cannot tell which way to proceed?

The few observations that I have made are necessarily imperfect, but I send them, as they afford a method which might lead a naturalist to notice habits otherwise difficult to observe, and so to arrive at conclusions which I in my ignorance of natural history must leave to others.

C. V. Boys

Physical Laboratory, South Kensington

THE MINERALOGICAL SOCIETY OF GREAT BRITAIN AND IRELAND

THERE was a time, now almost beyond the memory even of the oldest inhabitant, when the stillness of our learned halls was unbroken by the wrangle of contending geologists, when the science of geology could not be said yet to exist, when those who occupied themselves with stones found a congenial atmosphere of solemnity in the quiet domain of crystallography, whence with the boldness of adventurers they made little excursions into the more open and dangerous waters of chemistry. Days of slumberous peace as they now seem to one who turns over the ponderous dusty pages in which their records are duly chronicled! To the mineralogist of those days the interest and importance of rock-masses was measured by their richness or poorness in mineral specimens. Surrounded by his cases of minerals—the reward of years of patient toil and judicious expenditure, with what tender interest would he survey his treasures! We knew him in old times, yea and loved him. Enthusiastically would he describe how he had contrived to secure that priceless unique crystal; how day after day he had searched the rocks in vain, till at last one lucky stroke of the hammer laid open that magnificent druse; how he had bought that matchless group from a sailor who used it to keep down the lid of his tobacco box. Kindly too he was, and all the more if you took interest in his favourite pursuit. Ask him to tell you the difference between two resembling minerals, and he would launch out with evident relish into his "external characters." Lovingly would he handle the specimens, as if they were the children of his old age. Eagerly would he descant upon the difference between "lamellar distinct concretions"; how some were "indeterminate curved lamellar," others were "fortifications-wise bent." And then would follow the whole string of characters—"semi-hard," "not particularly difficultly frangible," "supernatant," "pretty cold," "not particularly heavy," between "aurora-red" and "hyacinth-red," or between "mountain-green" and "celandine-green." Such jargon it seemed to youthful ears! One could not but admire indeed its methodical precision, but the questions ever forced themselves on one's mind—What is the living truth underlying it all? Were minerals really created merely as a basis for our old friend's systems of classification? Or can they not be made to yield up some intelligible record of their own history and of the planet of which they form a part?

When the discoveries of William Smith drew off the attention of students to the marvels revealed by stratigraphical geology, mineralogy rapidly sank into neglect in this country. By a curious revulsion of opinion rocks were now appraised as of importance in proportion as mere mineral specimens were absent from them, for where these occurred organic remains were usually not to be looked for; and organic remains now took the place of minerals. Men who would formerly have trudged cheerfully a whole day with a 14-lb. hammer on their shoulders to secure a few minerals were now to be seen as enthusiastically hunting for ammonites, gryphaeas, belemnites, echini, fossil fishes, and other buried treasures of the stratified formations. Unmeasured was the scorn of the veteran mineralogist for this new-fangled pursuit. To neglect such attractive objects as minerals, with their exquisite forms and colours, for the dingy and fragmentary relics of extinct whelks, lobsters, and other pre-adamite vermin seemed to him an utterly unaccountable form of madness. And so his beloved cabinet became dearer to him than ever. In its quiet retreat he lived with his specimens in the past, and allowed the strong rising tide of palæontology to rush and roar past him unheeded.

But cycles appear in scientific as in political opinion. For some years past there has been a growing conviction that palæontology has had a long enough monopoly of power in the geological commonwealth, and that the mineralogical side of the science has in this country been unduly neglected and discouraged. The attention now bestowed among us upon petrographical research is a pleasing proof of the reality and steady progress of this reaction. Another token of the same change is supplied by the foundation and encouraging growth of the Mineralogical Society of Great Britain and Ireland. This society was instituted in the early part of the year 1876. It counts among its members a large and increasing number of the best geologists in the three kingdoms. But its operations are carried on so quietly and unostentatiously that its work and aims are probably not yet so widely known as they deserve to be. A body gathered under the leadership of Sorby and Heddle is one which may count on support from all to whom the advancement of mineralogy and mineralogical geology among us is an object of interest. As a rule our scientific societies are bodies with a local habitation, gathering most of their effective members from the district in which their rooms are placed. But the Mineralogical Society, as its name denotes, embraces the whole United Kingdom. It has no buildings of its own nor any one special home. Its meetings, like those of the British Association on a large scale, are

held from time to time in different towns throughout the country, its object being to form a bond of union among those who cultivate mineralogy or who wish to see this science restored to the place which it ought to hold in a land where so much sound geological work is being done. The Society publishes a "Mineralogical Magazine," of which three volumes and part of a fourth have already appeared. This publication contains numerous papers by Dr. Heddle and the indefatigable secretary, Mr. Collins, also some by Mr. Sorby, the late Mr. J. C. Ward, Prof. Bonney, and other well-known writers. No one need fear to encounter in its pages the resuscitated ghosts of the old mineralogical "Dryasdusts." Peace to their manes! They did good though limited work in their day, which deserves our respect for its thoroughness. But, with affectionate reverence for these early masters and their crabbed lingo, we breathe a more open breezy atmosphere now. The mineralogist's ken sweeps far beyond the limits of his cabinet and laboratory. Hand-in-hand with the geologist and palæontologist, being elder brother to both, he takes his share in the task of unravelling the structure and history of the earth. Towards the attainment of this union the Mineralogical Society aims, and it deserves the heartiest wishes for its success.

ARCH. GEIKIE

SMOKELESS LONDON

I WRITE for the purpose of expounding a scheme which, if adopted, would make London a smokeless city.

When taking upon myself to explain a subject in a few minutes which has taken many years to develop in my own mind, there is a great temptation to put the reader in possession of the steps which led to the conclusion. The conclusion itself however has so much to recommend it that I will confine myself to the results of my reasoning only. It is enough to say that they were arrived at to a great extent by an exhaustive exclusion of less feasible plans.

First then I propose to take advantage of the existing plant of the gas companies. I find they are amply sufficient for the purpose.

Instead of taking 10,000 cubic feet of gas per ton from the coal, I propose to take 3333 cubic feet, and to pass three times the quantity through the retorts, or any other proportion that may be found most convenient. The result of doing so is startling.

The companies will have double the quantity of by-products they have at present in the shape of tar and ammoniacal liquids; the community will have 24-candle gas instead of 16-candle gas; the fuel resulting from the process will light readily, and it will make a cheerful fire that gives out 20 per cent. more heat than common coal; London would become a smokeless city.

In dealing with the figures I shall take them roughly, but in such a way that by including a few outlying corporations they could be made absolutely correct.

I take the total annual consumption of coal in London to be 6,000,000 tons. Of this I take 2,000,000 tons to be the annual consumption of the gas companies. The total quantity of fuel used for general purposes I take to be 4,000,000 tons of coal and 1,000,000 tons of coke sold by the gas companies.

We shall now see what would be the result if we treat the whole of the 6,000,000 tons in the retorts on an extraction of less than three hours, instead of the six hours at present prevailing.

The total quantity of 16-candle gas consumed in London may be taken at 20,000,000,000 cubic feet. This would be at the rate of 3333 cubic feet per ton upon 6,000,000 tons, the total quantity of coal consumed in London. The residual smokeless fuel would amount to 5,100,000 tons. Of this 1,000,000 tons would be required for the extraction of the gas, leaving 4,100,000 available for the general uses of the community. This has to be compared with the 4,000,000 tons of coal and the 1,000,000 tons of coke already referred to as consumed at present. Now the smokeless fuel which results from an extraction of 3333 cubic feet of gas per ton has a heating capacity fully 20 per cent. greater than common coal, and 10 per cent. greater than coke. This gives us the exact equivalents of the 5,000,000 tons of fuel at present in use.

So far the account as regards the fuel available for the community balances. We may now deal with the difference in value between 16 and 24-candle gas. As the value of the gas varies directly as its illuminating power, the calculation is very simple. If we take the average price of 16-candle-gas to be 3*s.* 6*d.* per thousand cubic feet we shall find the total value of the 20,000,000,000 consumed in London to be 3,500,000*l.*, but as we have by my scheme the same quantity of 24-candle-gas, the value will be increased to 5,250,000*l.*; here then we have an annual sum of 1,750,000*l.* to place to the credit of the system.

Turning now to the by-products: seeing the gas companies by the new arrangements would subject three times the quantity of coal to the heat of their retorts during the period when the tar and ammoniacal liquors pass off most rapidly, I do not think I am wrong in estimating the yield at double its present amount. Taking this upon the tar and ammonia to yield 3*s.* 9*d.* per ton of coal, we find the total value of these by-products to be, at present, on the supposed consumption by the gas companies of 2,000,000 tons of coal per annum, 375,000*l.* This being doubled under my scheme, an additional sum of 375,000*l.* must be placed to its credit.

But the basis upon which we have hitherto been arguing is that the gas companies under the proposed scheme are getting their coal for nothing. We have been supposing that the community become the purchasers of 6,000,000 tons of coal and hand it to the gas companies. At present London only pays for its general consumption on 4,000,000 tons of coal and 1,000,000 tons of coke. Let us now suppose that the companies pay the same sum annually that they do at present for their coals; if so, they would pay upon 2,000,000 tons, or an annual amount of 1,600,000*l.*, if their coals cost 16*s.* per ton. From this falls to be deducted the money they at present draw from their sales of coke, which, when taken at 6*s.* yer ton of coal carbonised under the existing system, still leaves a sum of 1,000,000*l.*, which they could afford to pay per annum for the use of the 6,000,000 tons of fuel as proposed in my scheme. We will now take the total payments of the community for their coal to be upon 6,000,000 tons, for which we will further suppose they pay at the rate of 16*s* per ton first cost. This would amount to 4,800,000*l.* per annum. From this falls to be deducted the 1,000,000*l.* contributed by the gas companies for the use of the fuel, also the 1,750,000*l.* charged on the difference between the 16- and 24-candle gas already referred to, also the sum of 375,000*l.* of additional income from the by-products. This would leave a net sum paid by the community for its fuel under my scheme of 1,675,000*l.* Under the present system they have to pay, say 16*s.* per ton on 4,000,000 tons of coal, and say 12*s.* per ton on 1,000,000 tons of coke. This makes in all the sum of 3,800,000 per annum. Here then we have a balance in favour of my scheme of 2,125,000*l.* annually. This may be taken as the yearly value of London smoke, which I propose to convert into useful products by *the plant at present in use.*

I have only in conclusion to say one or two words about the efficiency of the scheme as regards the fuel. It lights easily, it gives off no smoke, it makes a cheerful fire, it gives out more heat than either coal or coke, it will be cheaper per heat-unit than the coal at present in use, London would become a smokeless city, and all that would fall to be deducted from the sum of 2,125,000*l.* per annum would be confined to a few items, such as the cost

of additional workmen employed in charging the retorts, interest upon additional capital required for transit appliances, and the terms to be made with the gas companies for carrying out the scheme.[1]

I cannot close without acknowledging the help I have received from Mr. Wallace, the gas manager at Woolwich Arsenal, and the valuable information obtained from Mr. Field's tabulated accounts of the London gas companies. So far as I am aware my contributions to the *Builder* and elsewhere are the only writing on the subject of my scheme that has ever been made public.

W. D. SCOTT MONCRIEFF

Westminster, December 13

NEW GUINEA[2]

OF the few travellers who have attempted to explore the great island of New Guinea, Signor D'Albertis must undoubtedly be considered the chief, since he alone has made extensive and repeated journeys both in the north-western and the south-eastern parts of the island, and has thus been able to examine and compare some of the most distinct tribes or races which inhabit the country. The narrative of his travels has therefore been looked for with some interest, for though several of his journeys have been more or less fully described in newspapers and magazines, it was felt that much must remain to be told, and that so energetic a traveller would probably be able to throw some fuller light on the hitherto doubtful affinities and relations of the Papuan races.

Leaving Genoa in November, 1871, in company with the well-known traveller and botanist Dr. Beccari, and making short excursions in Java and the Moluccas, our travellers hired a small schooner at Amboyna in March, 1872, to take them to Outanata, on the south coast of New Guinea; and after some delays at Goram seeking a pilot and interpreter, on April 9 D'Albertis records in his journal: "A memorable day! At last I tread the mysterious land. At last, leaping on shore this morning, I exclaimed, 'We are in New Guinea!'"



FIG. 1.—Mount Yule Range, seen from Yule Island.

Finding no safe or convenient place to stay at on the south coast, they proceeded to Sidwati and fixed their abode for some time at Sorong, a small island close to the north-western extremity of the main land of Papuas. From this point they made excursions into the interior, and D'Albertis resided some time at the inland village of Samoi, where he was near dying of dropsy and fever. They then went in a native vessel to Dorey Harbour, where they arrived in August, and settled themselves at Andai Village, where a German missionary resides. Here they had a house built, which was their headquarters till November, and D'Albertis succeeded in spending some weeks at Hatam, a village on Mount Arfak, about 3500 feet above the sea, and in the midst of the forests inhabited by the finest and rarest of the birds of paradise. On the very day after his arrival here he shot both the shielded and the six-shafted paradise-birds (*Lophorina atra* and *Paradisea sexpennis*), two species which had certainly never before been seen alive or freshly killed by any European; and before he left this spot he obtained many other rare species, besides an altogether new and beautiful kind, which has been named *Drepanornis albertisii*.

Constant attacks of fever and dropsy, however, reduced him to such a state of weakness that it was absolutely necessary to seek a change of climate, and returning to

[1] By experiment I find that the annular leakage I speak of (the loss in expense of the gas) is more than makes up for the saving which takes place on account of the more frequent recording of the meters.

[2] "New Guinea: What I Did and What I Saw." By L. M. D'Albertis, Officer of the Order of the Crown of Italy, &c. &c. In two volumes. (London: Sampson Low, Marston, Searle and Rivington, 1880.)

taken by an Italian man-of-war to
ne stay at the Aru Islands and Somba
ien on the way. Thence he went
Sandwich Islands, San Francisco
hing Europe in April, 1874, and thus
voyage to the far east.
rey in the end of 1872 he had deter-
e north coast and to penetrate further
ountains, but the subsequent journeys
hich he heard at Sydney, and Dr.
return to the same district, induced
ention to the south, where he had
natives the skin of a new bird of
he lofty ranges of Mount Yule and
d the prospect of an equally rich
exploring ground. Accordingly, in
reached Somerset (Cape York) by
h the intention of settling at Yule
l before fixed upon as convenient
xploration of Southern New Guinea,
nd delay he reached the island on
ng the natives friendly obtained
some land and build a house.
vember, having with him a young
, and five Polynesians; making
tural history, exploring the island
mainland, but being quite un-
pts to reach even the foot of the
interior.
rst volume, which contains by far
tter both to the naturalist and to
e second volume is devoted to a
e successive voyages up the Fly
missionary steamer *Ellengowan*,
hall steam-launch, the *Vera*, lent
of New South Wales. Of th
sful of these voyages D'Alberti
ntre of the great southern inla
g the hilly country but not the
ountains, of which a few glimpses
lerable distance.
oduced by the careful perusal o
gnor D'Albertis has all the ha
—enthusiasm, boldness, and
nature, great humanity, and an
s savages which enables him to
appreciate the good qualities
the character of a scientific
m, and those who expect to find
from the results of his observa-
lity be disappointed. Let us,
ples and illustrative passages
for himself.
village of Kamali he became
as besides almost starving, for
m nothing, neither would they
able him to return to Somba
to die there without an effort
ies to speak to him, and then
ver assured them that unless
nce to assist him to leave the
ould quit his hut alive. This
allowed to go and fetch the
s hostages, and the revolver
baggage was all on board the
the travellers were on their
crew were very insolent, and
ached their own country they
ion. D'Albertis, hearing this
ed to repeat it, and on his
im by the throat and pitched
f course, on board again in a
ed a bamboo to attack not
their revolvers; and so cowed
the whole crew that they became quiet and amenable for the rest of the voyage. An admirable portrait of one of these Motu Papuans (Kanaloa) is given, and the present writer can almost believe that he recognises in it one of his own acquaintance at Motu Motu in 1858.

More amusing was the way in which Signor D'Albertis made use of the aneroid on his journey to Hatam. His porters, who had agreed to take him there for a fixed payment, stopped at a village to rest; and on being told to go on, said, "This is Hatam; pay us our wages." He knew however, both by the distance and elevation, that they were deceiving him, and told them so, but they again said, "This is Hatam; pay us. How do you know that this is not Hatam?" He then took his aneroid out of his pocket, and laying his finger on a point of the scale, said, "Here is Hatam; this thing tells me where it is;" and then explained that when they got higher up the mountain the index would move, and when they reached Hatam it would come to the point he had marked. This astonished them greatly, but they would not believe it without

—London Stereoscopic Company.

proof. . . to be one of the . . . Arfaiuk to the top of a small hill near, when they saw that the index had moved, and on coming down that it moved back again. This quite satisfied them. They acknowledged that the white man knew where he was going, and could not be deceived, so they at once said, "Let us rest to-day; to-morrow we will go to Hatam." Of course every man and woman in the village wanted to see the little thing that told the stranger where he was. A remote village of the forests; and thus the traveller . . . influence was increased, and perhaps his personal safety secured.

In his second journey he revisited some of his old haunts and rockets, which were very essential in frightening the savages and saving him several times from them. At Yule Island he was also enabled to . . . on whom he conferred some . . . absence on an exploration his house was entered and a large quantity of goods stolen. By a . . . firmly re-establishing his power and influence he obtained great ingenuity. Aiding the chiefs and other native-

[illegible] all pretended great regret at his loss, though the robbery must have been effected with their connivance. He told them that he was determined to have his property back, and that if it was not brought in twenty-four hours, he would fire at every native who came within range of his house, which fortunately commanded a great extent of native paths, as well as the narrow strait between the island and the main land. He then made his preparations for a desperate defence in case he was attacked, loaded some Orsini shells and mined the paths leading to his house, so that with a long switch he could blow them up without exposing himself. At the end of the twenty-four hours, nothing having been brought, he commenced operations by exploding five dynamite cartridges, which made a roar like that of a cannonade, the echoes resounding for several seconds. He then let off rockets in the direction of the native houses, and illuminated his own house with Bengal fire. All this caused terrible consternation; and the next morning the chief arrived with five men, bringing a considerable portion of the stolen goods, and trembling with fear to such an extent that some of them could not articulate a word. He insisted however that the rest of the goods should be brought back; and the next day, to show that he was in earnest, fired at the chief himself, as he was passing at a distance of 300 yards, being careful not to hurt, but only to frighten him. A canoe was also turned back by a bullet striking a rock close by it. The effect of this was seen next morning in another visit from the chief, with five complete suits of clothes, axes, knives, beads, and other stolen articles. Much more, however, remained, and D'Albertis took the opportunity of impressing them thoroughly with his power. He first asked them to try to pierce a strong piece of zinc with their spears, which were

Fig. 1.—Type of Village on the Mukeyapapua.

blunted by the attempt, while he riddled it through and through with shot from his gun. He also sent bullets into the trunk of a small tree a hundred yards distant, showing that a man could not escape him. They had been seated on a large stone near his house, which he had mined. He now called them away, and having secretly lighted the match, told them to look at the stone. A tremendous explosion soon came, and the stone disappeared. The natives were too frightened to move, and begged him to have pity on them, promising to restore everything. A great hole was seen where the stone had stood, while some of its fragments were found a long way off. For twelve days more he kept up a state of siege, turning back all travellers and many canoes by rifle-balls in front of them, but never hurting any one. Then another large instalment of his goods was brought, leaving little of importance, and ultimately he recovered almost everything. During the whole of this time he never hurt a single person or did any damage to their property, but succeeded in getting back his own by impressing them with his, to them, superhuman power. The result was that after eight months' residence he parted from these people on the best of terms. They all embraced him, and most of them shed tears, while their last words were: "*Maria ora! Maria ora!*" "Return, Maria! Return, Maria!"—that being his second name, by which they had found it most easy to call him.

As a fearless capturer of snakes Signor D'Albertis rivals, if he does not surpass, the celebrated Waterton; indeed he seems to like them rather than otherwise. At Yule Island the natives had found a large snake under a tree, and all ran away from it, crying out, and this is his account of what happened:—

"At last I went to the natives and tried to ascertain

conduct, and they made me under-
ıd fled. I then returned to see the
ı in fact I did, although two-thirds of
den in a hole in the earth. His size
oncluded he could not be poisonous,
ped him by the tail. While dragging
with my two hands I was prepared to
lose to his head with one foot the
ed, so that he should not have the
r moving. My plan succeeded per-
e snake's head was imprisoned under
d his body with my hands, and, as
quished a terrible monster, turned
with an air of triumph. They, struck
ooked on at the scene from a safe
confess that the snake offered little
h it writhed and twisted itself round
it so tightly as to stop the circulation,
l black. I remained however in pos-
and soon secured it firmly to a long
brought with me. I then gave the
to carry home." Waterton caught
whereas the one Waterton caught
but ten feet, though it might have
ful. This snake was kept alive and
and when the natives saw D'Albertis
t it coil round his legs they howled
ıd admiration. Six weeks after the
"My snake continues to do well; it
skin, is well-behaved and tame, and
escape, even when I put it in the sun
and when I go to bring it in, it comes
ord. It never attempts to bite, even
ase it. While I am working I often
where it remains for hours; some-
ad, and licks my face with its forked
true friend and companion to me.
bother me it is useful in putting
ey are much afraid of it; it is quite
let my snake loose to make them fly
ept this serpent for nearly six months,
r of the same species with it, till at
ınd he mourns their loss as of dear
or I loved them and they loved me,
a long time together."
a long time together."
ge on the mainland visited by D'Al-
re he lived five days, and of which
ising account. It is about 1500 feet
ı very short distance from the coast.
ounded by a strong double stockade,
ar to be good specimens of the supe-
ı race. By the aid of these people it
have been difficult to penetrate to the
nterior, but our traveller was drawn
unity of exploring the Fly River, and
ration of this grand mountain range
treasures for some future explorer
r. Having thus sketched the outline
is eastern voyages and indicated his
s as a traveller and an author, let us
s as a traveller and an author, let us
tell us about the people among whom

ALFRED R. WALLACE

(To be continued)

OF. J. C. WATSON

ve to record the death of Prof. Watson,
ears director of the Observatory of
gan, and later of the new Observatory
ison, Wisconsin, under the auspices of
ie.

James Craig Watson was born on January 28, 1838, in Elgin County, Canada West, of American parents who were residing in Canada at the time of his birth. While he was still a boy they removed to Ann Arbor, where at fifteen years of age he entered the University as a classical student, but his mathematical bias soon became evident. He studied astronomy under Prof. Brunnow, who was then in charge of the Ann Arbor Observatory, and Professor of Astronomy in the University, and while the latter was director of the Dudley Observatory at Albany, Watson occupied his place at Ann Arbor. In 1860, when Prof Brunnow returned there, he was transferred to the Chair of Physics, which position he held until Prof. Brunnow finally severed his connection with Ann Arbor in 1863, when Watson was again appointed director of the Observatory. From this time his attention was chiefly directed to the discovery of minor planets, with which view he formed charts of very small stars; he had also in view the possible detection of an ultra-Neptunian planet, and it has been stated that latterly he had been more particularly working with this object, and had removed from Ann Arbor to Madison, to avail himself of the more powerful instrumental means at the latter place, where the refractor has an aperture of 16 inches, that of the Ann Arbor telescope being 12½. Watson added twenty-three members to the group of small planets, his first discovery being that of Eurynome in September, 1863.

In 1870 Watson proceeded to Sicily at the head of a Commission appointed by the United States Government to observe the total eclipse of the sun on December 22, and in 1874 he went to Pekin in charge of a similar Commission for the observation of the transit of Venus. While at Pekin he discovered No. 139 of the minor planet group, and it was stated at the time that the discovery was effected entirely through Watson's extraordinary recollection of the configuration of the small stars in the neighbourhood where the planet was situated (R.A. 9h. 58m. 13s., Decl. + 10° 44'). A member of the Imperial family who had been asked to name the planet, called it the "Hope of China"; *Juewa*, the name by which it has since been known, being an Anglicisation of the Chinese term.

Watson's observations of two objects during the totality of the eclipse of July 29, 1878, which he considered to be intra-Mercurial planets, will be fresh in the recollection of the reader: there is no doubt that whatever opinion may have been entertained by other astronomers, he was himself convinced that he had met with planetary bodies, and he stoutly defended his opinion against the doubts raised in his own country.

Watson was the author of a valuable work upon Theoretical Astronomy, published in 1867, upon which his reputation as an author mainly depends. He was a member of the principal scientific institutions of the United States, and his merits were acknowledged by several of the European Academies; he received the Lalande Medal of the Paris Academy of Sciences in 1870 for his numerous planetary discoveries.

The death of Prof. Watson took place somewhat suddenly, on the morning of November 23, at his residence on Observatory Hill, Madison, Wisconsin, and is attributed to intestinal inflammation following upon a prolonged to intestinal inflammation following upon a severe cold, in an over-strained condition of body; he had been working hard as usual at night, while superintending the completion of the Observatory buildings by the day. He was buried at Ann Arbor on November 26; memorial services were held in the University hall, and were attended by a body of between seven and eight hundred students and a large concourse of the general public, addresses being delivered by the President and several Professors of the University, of which the Ann Arbor and Detroit papers publish lengthy reports.

NOTES

THE subscription opened by the Paris Academy of Sciences for raising a statue to M. Becquerel, the celebrated electrician, is almost closed, having produced 15,000 francs; only 1500 francs more are required. Those wishing to subscribe should send their contributions to M. Mauduit, at the Academy of Sciences, as early as possible.

LAST week M. Moll, the doyen of the Professors of the Conservatoire des Arts et Métiers, died in Paris. He was the oldest teacher of agriculture and one of the first, having been one of the staff of the celebrated Roville *ferme-école*, established about sixty years ago.

THE Norse of German bryologists, Prof. Ernst Hampe, died at Helmstedt on November 23 at the age of eighty-five years.

ON Nov. 23 the first section of the St. Petersburg Academy of Sciences (physico-mathematical sciences) had to choose a member in chemistry, and an influentially-signed presentation recommended Prof. Mendeléjef to the choice of the Academy. The Academy would certainly have done itself honour in choosing a man of such eminence in science, but we regret that Prof. Mendeléjef was not elected. This is held locally to show that the Academy is influenced in its selection by other reasons than the value of a candidate's scientific work. The impression on the public in general, we believe, is very unfavourable to the Academy; not a day passes, we are informed, that Prof. Mendeléjef does not receive letters and telegrams from men eminent in science expressing admiration for his works. Many scientific societies have made him an honorary member, and only the other day the University of Moscow did the same.

AN interesting collection is being made by M. Pumas of medals commemorative either of scientific men or scientific discoveries. The number already collected is far greater than had been expected.

JULIUS PAYER, one of the leaders of the Austrian North Polar Expedition of 1872-74, has settled at Munich with the intention of devoting himself exclusively to the art of painting.

THE central committee for the erection of a Spinoza monument at the Hague have, before their dissolution, resolved to utilise the remaining balance of funds in their hands for publishing a new and handsome edition of the complete works of the great philosopher. Dozents J. van Vloten and J. P. N. Land have been commissioned to prepare the new edition. In the interest of the laudable undertaking the friendly request is now addressed to all librarians and possessors of autographs to communicate with the superintendent regarding any autographs of Spinoza which may be in their possession in order to render the edition as complete as possible. Communications are to be addressed to the publishing firm of Martinus Nijhoff at the Hague.

A SEVERE shock of earthquake was felt at Wellington on the night of the 5th instant, at eleven o'clock. The shock was directed from north to south. A rolling subterranean noise preceded it, and a violent wind of short duration followed. Another shock is reported from Masony. A fresh violent shock, lasting two seconds, occurred at Agram at twenty seven minutes after midnight of the 7th. Subterranean rumblings followed the shock and continued to be heard throughout the night. As on the last occasion the shock was accompanied by distant sounds and preceded by a slight vibration. On Wednesday night last week there was a strong earthquake shock at Agram which lasted six seconds. It was preceded by a loud rumbling. On the day previous the earth trembled for an hour together. That of Wednesday night was the strongest shock since the first. Two walls fell in and the houses shook. On Thursday evening last six slight shocks were felt at Vienna. At Agram there were two violent shocks at half-past two and half-past three o'clock in the morning. A shock of earthquake was felt at Brescia on the afternoon of the 10th, accompanied with a rumbling noise.

PROF. RUDOLPH FALB gave a lecture in the Vienna Gewerbe Museum on November 27, in which he said that earthquakes are subterranean volcanic outbreaks, produced by the cooling action of the hot liquid interior of the earth and the attraction of the sun and moon. In support of this view he urged that most earthquakes occur at the time when the sun is nearest us, viz. in January, fewest in June; also the number of earthquakes increases in the months of April and October, because of the stronger attraction of the sun on March 21 and September 23. He said further that in the period December 16-30 this year fresh earthquakes might occur at Agram.

A NEW and somewhat bold hypothesis as to the cause of earthquakes has been propounded by Dr. Novak in Pesth. He considers that, besides the rotation of the earth on its axis and its revolution round the sun, a multiplicity of motions of the earth appear in space, in virtue of which the earth's axis, and with it the equator, shift their position. This causes a variation of the forces influencing the earth's form (centrifugal and centripetal force), and the earth has the tendency to adapt itself to this change. He also considers a change of form of the earth to occur through the shifting of the pole and the equator, and that this may have effect some time afterwards, when the earth's crust is weak.

WE are requested by the Sunday Society to announce the following arrangements for the Sunday opening of the Winter Exhibition of Oil Paintings at the Hanover Gallery, New Bond Street, by permission of the proprietor, Mr. Weil. On Sunday, December 26, the Gallery will be open to the Members of the Society, and on the two following Sundays the public will be admitted by free tickets, which will be issued to those applying by letter and sending a stamped and addressed envelope to the Honorary Secretary, 8, Park Place Villas, W. On each Sunday ticket-holders will be admitted from 4 o'clock till 7.30 p.m., and the gallery will be closed at 8 o'clock. On the re-assembling of Parliament the Society will press its claims upon both Houses of the Legislature by bringing forward the following resolution:—"That inasmuch as all opposition to the action of Her Majesty's Government in opening on Sundays the National Museums and Galleries in the suburban districts of London and in Dublin has entirely ceased, owing to the good results which have followed such opening, this House is of opinion that the time has now arrived for extending this action to all institutions of a like character, it having been most conclusively shown that large numbers of the people rejoice in every opportunity that is afforded them of spending Sunday intelligently and with due regard for its preservation as a day of rest and exemption from ordinary work and amusement."

SOME information regarding the observatory at Nice, now in course of construction through the munificence of M. Bischoffsheim, is given by M. Trouvelot in *La Nature*. Some 35 hectares of ground have been acquired. The situation is a few kilometres north-east of Nice, near the road from Cimiez over the Mont des Mignons (or Mont Gros), and 375 m. above the sea. There are to be two 16.50 dwelling houses for astronomers and for accommodation of visitors. One is already finished, and M. Thollon has merged and runs excellent work in spectroscopy. More than 250 workmen are at present busy on the buildings. Some of the instruments will shortly be ready. The whole is being organised on the principles of the Bureau des Longitudes.

comprise at first two equatorials, one accessory instrument. One of the ly be the largest astronomical appar focal distance will be 18 metres, and its cupola will have a diameter of no less action of the object-glass is entrusted to Henry of the Paris Observatory. The st about 250,000 francs, and the cupola expensive. The total cost of the Ob million francs.

ollet on the subject of the introduction of ofication has been published by Dr. Lippstadt (Bonn, Strauss). Dr. Muller and in reply to Prof. Virchow, whose Hackel on this subject some years ago

l matter in the "British Almanac and is a summary of the science of the past in, which is good so far as it goes, but very far. There is also an article on g," by Mr. R. H. Scott, and a "Sketch Royal Observatory, Greenwich," by Mr.

Morris, the Director of Public Gardens jaica, on the financial results of the last ona barks sent to the London market, is inasmuch as it shows the superiority of rise of Ceylon, as indicated by the prices nment referred to in the present Report e bales, in which the several species under sented, crown bark from *C. officinalis*, and *Pahudiana* forming by far the largest propo nt realised for these eighty-one bales was all the different kinds, whether "quill," "twig" bark, the prices realised were in ed for the same kinds of Ceylon barks, t ne cases of 2s. 9d. per pound. Mr. Morris e fact that from the recent sales the relative incipal species under cultivation, namely, bark (*C. officinalis*) and the red bark (*C.* come very distinctly marked. The first vered to be a most valuable product, and d fluctuations may ultimately take place in tensive cultivation of Cinchona in different high-class bark of this nature must always remunerative prices. The conclusion arrived ons of soil and climate of certain parts of iently favourable to the production of the se valuable products, and as large tracts of ary labour are now available, there only capital and energy to overcome the initial nterprise."

Second Vegetation in Paris which was occasioned by the frosty weather in the beginning of ew vegetable phenomenon has been going on the owing to the exceptional heat which prevailing leaves have been observed on a few trees, and the date of our most recent observations.

g to the forthcoming exhibition of electric ig presented to the Chamber. M. Cochery a for 600,000 francs=£24,000 for the exhibition and ongress and experiments. A guarantee fund of signed by fifty persons.

ophlet on Bedroom Ventilation (2d.; Hodge Lawson Tait of Birmingham.

THE *American Entomologist* has been incorporated with the *American Naturalist*.

THE rare phenomenon of an inverted rainbow was observed at Innsbruck on November 25 at 8.45 a.m. The end points of the semicircle, the centre of which was the sun, rose and moved towards with the latter for some thirty minutes. The phenomenon then vanished.

A VALUABLE discovery has been made at Jochenstein, near Ohrenzell (Bavaria). A farmer of Jochenstein had frequently noticed a stone plate, of some 12 metres square, in the centre of a wood belonging to him. He had the plate raised recently, and under it were found six bead-rings, four spiral bracelets, each showing nine twists, and two battleaxes. All the objects are of bronze and carefully preserved.

THE second part of "The Scientific English Reader" (Leipzig, Brockhaus), edited by Dr. F. J. Wershoven, the first part of which we have already referred to, contains extracts relating to machinery and mechanical technology.

THE fourth part of Dr. Dodel Port's excellent "Atlas of Physiological Botany" has just been published. The six plates it contains are in every respect equal to those of the former numbers. They comprise (1) *Lupinus mutabilis*, germ-history of the embryo (the plate forms the supplement of the *Lupinus gladiator* plate in part 1); 2) *Equisetum Telmateja*, sporangia and spores; plate in part 1); 2) *Equisetum Telmateja*, sporangia and spores; (3) *Oscillaria insidiae* and *O. viridi-atrata*; (4) *Nitella indivisa*, with macro and microsporangia, macro- and microspores; (5) *Chara crinita*, male and female plants, macrofruit and its anatomy, spores and germinating spores; (6) *Marchantia polymorpha*, seed bud in longitudinal section at the time of fertilization. These drawings are made according to the latest researches on the fertilization of phanerogamic plants. Parts 3, 5 of the same author's "Illustrirten Pflanzenleben" will also shortly be published.

Among the special papers in the *Annuaire* of the Brussels Observatory for 1884 are the following:—"What is the Climate most favourable to the development of Civilisation?" "Physical Phenomena accompanying the Transits of Mercury," by M. Niesten. "Nomenclature of existing Public Observatories," by M. Niesten. "Memoir on the Theory of the Libration of Venus," by M. Stroobant.

THE Ice Committee are continuing their correspondence regarding the Greely party observed by Maughan, which therefore is becoming very decisive as to the date of the sighting. The specimens of seal sent to Mr. Wood Mason, deputy superintendent of the Indian Museum, have been identified by him as belonging to the Phoca Mitchellii and as related to the Harbour fly which destroys a great deal of seal on the whole coast of the United States. This species has never before been found in India, and Mr. Mason says, has never before been found in Asia, and he proposes to call the species *Cervicornis typus*, on the ground that it is likely to prove a very formidable pest, and because it is commonly that the Indian species is more numerous than the European and carefully watched its progress.

A LIMITED number of the Royal Geographical Society's Fellows, desiring that some further attempt should be made to obtain information of the fate of Lieutenant Greely and his party, have subscribed a sum of 100*l*. for the purpose, and have requested the Council to take such steps as they may think fit. The Council have accordingly decided to send out a vessel to Smith Sound, to search for traces of the party, and to bring back any survivors who may be found. The vessel will be commanded by Mr. A. H. Markham, who was in command of the Arctic expedition of 1875-76, and will be provided with a crew of twenty-five men, all of whom have had experience in Arctic navigation. The vessel will be provided with a steam launch, and with sledges and boats, and will be supplied with provisions for two years. She will leave Dundee in the middle of May next, and will proceed direct to Smith Sound. The organisation of the whole expedition will be under the direction of a special committee, consisting of Admiral Sir Leopold M'Clintock, Admiral Richards, Captain Sherard Osborn, Captain Nares, Mr. Clements Markham, Mr. Gilbert, and Mr. Keltie, with power to add to their number. Mr. Markham will be the executive officer of the committee, and Mr. Keltie will act as secretary. The committee will meet at the Royal Geographical Society's rooms on Thursday next, when the instructions to be given to Mr. Markham will be considered. Subscriptions will be received by the Secretary of the Society, Mr. Keltie, at the Society's rooms, 1 Savile Row, Burlington Gardens.

A Rhenish Fishery Society has just been founded at Cologne. It will direct its attention not only to the Rhine fisheries, but its programme is a most universal one, comprising even the furtherance and support of ichthyological research as well as the establishment of ichthyological stations in various countries.

Mr. Baller of the China Inland Mission has lately made a journey in the little-known province of Kweichow at the time when the people were engaged on their opium harvest, and he thus describes the process:—A small three-bladed knife is used to make an incision in the poppy-head as soon as the petals fall off. The drop or two of milky juice that oozes out is after a little while scraped off with a small curved knife into a bamboo tube, and a fresh incision made. The process is repeated until the supply is exhausted. The juice thus collected is dried in the sun, when it turns jet black, and is then ready for the market.

OUR ASTRONOMICAL COLUMN

The Comets of Hartwig and Swift.—MM. Schulhof and Bossert have investigated the elements of comets 1880 *d* and *e*, discovered respectively by Dr. Hartwig at Strasburg on September 29, and Mr. Lewis Swift at Rochester, New York, on October 11. Prof. Winnecke had conjectured that Hartwig's comet might have been identical with the comets of the years 1382, 1444, 1506, and 1569, with a period of revolution of 62½ years. MM. Schulhof and Bossert formed six normal positions between September 30 and November 29 from observations at Paris, Strasburg, Berlin, Leipsic, Kiel, Kremsmünster, Lund, Florence, Marseilles, O'Gyalla, Clinton, and Washington, and on varying the distances from the earth at the first and fifth place until the other normals were represented as closely as possible, arrived at an elliptical orbit, but with a period of 1280 years: this result is necessarily uncertain under the circumstances, but it nevertheless appears to render so short a revolution as 62½ years in the highest degree improbable.

With respect to Swift's comet, taking as the fundamental data the Odessa observation on October 31, a mean of Dunecht, Paris, and Strasburg on November 9, and an observation at Paris on November 27, it is found that, assuming only one revolution to have been accomplished between 1869 and 1880, or that the period is 10·00 years, the middle place cannot be represented with sufficient precision; when the error is diminished in longitude, it is increased in latitude. On the hypothesis that the period is 5½ years, or that two revolutions are included in the above interval, the error in latitude is greatly diminished, but still exceeds thirty seconds of arc. This, while indicating that the second hypothesis is more probable than the first, is regarded by MM. Schulhof and Bossert as rendering so short a period as 5½ years possible, though it is admitted that it may well be due to errors of observation. It must be borne in mind that the comet has always presented itself as a faint diffused object, without that degree of condensation necessary to insure precise observation. The following is the elliptic set of 5½ years' period:—

Perihelion passage, 1880, November 8·00011 G.M.T.

Longitude of perihelion	43 4 33	M. Ep. 1880·0
,, ascending node	296 51 33	
Inclination	5 23 32	
Angle of excentricity	41 3 55	
Logarithm of semi-axis major	0·492684	

With these elements the perihelion distance will be found to be 1·0671, and the aphelion distance 5·1518, and the heliocentric latitude at aphelion = + 6°·6, whence we find the distance from the orbit of Jupiter to be 0·53.

MM. Schulhof and Bossert propose to continue their investigation when further observations are available: meanwhile it may be remarked that their ellipse of five and a half years is likely to afford positions sufficiently near the truth to insure the observation of the comet as long as it is within reach of our telescopes, and it may be suggested to those who are in possession of powerful instruments that they will render an important service in determining places of this comet as long and as accurately as practicable.

The November Meteors.—Notwithstanding much interference from clouds the observers at Moncalieri, who watched for meteors during the nights of November 12-14, consider that they obtained evidence of the increasing density of the Leonid-stream, thus confirming observations made last year in England and the United States. One of these meteors appeared larger than the planet Jupiter, with an intense blue light, and a bright train of the same colour. It is added: "La lumiere zodiacale d'opposition etait tres brillante vers l'orient, sur le fond pur de ciel, s'elevait jusqu'au dela de la queue de Lion."

Near Apulse of Jupiter to a Fixed Star.—On the evening of November 20 Jupiter must have approached very near to the star B.D. + 2° No. 67, rated 7·7 in the *Durchmusterung*, and 7·9 on December 17, 1856, when it was observed on the meridian at Bonn, indeed the resulting place of the star would bring it almost into contact with the limit of the planet about the time of conjunction in right ascension (9h. 4m.), but small errors of the star's position and tables of Jupiter may have combined to leave it at an appreciable distance from the limb; perhaps some reader of Nature may have determined micrometrically the nearest approach. The apparent place of the star on November 20 was in R.A. 0h. 38m. 49·44s., Decl. + 2° 32′ 59″·9.

BIOLOGICAL NOTES

Anabena living in Botrydium.—It is now well known that many plants belonging to the group of the Nostocs flourish within the cells of other plants. Thus they are to be found in the petioles of the leaves of Gunnera, in Lemna, in Anthoceros, in Blasia, and in Azolla; and it was to be expected that they would equally find themselves at home in the cells of even more lowly organised plants. An instance of this latter, not without interest, has been noticed by Dr. L. Marchand, who recently collected a Botrydium at Montmorency, which, on being examined under the microscope, was found, instead of containing the usual mass of granular chlorophyll, to be filled with a chain of moniliform filaments, presenting all the characters of the chaplets of a Nostoc or Anabena. These filaments were composed of cells, some oblong with yellowish heterocysts, and they did not fill the entire cavity of the Botrydium cell, but seemed to adhere to its inner walls. The Botrydia plants were perfect; the root-like prolongations, as well as the rest of the plant, were perfectly closed. How then did these foreign bodies get in? This is not a question easy to answer, but it is one well worthy of being investigated. Dr. Marchand calls attention to the remarkable figure of Mr. E. Parfitt in "Greville's" (vol. i. p. 103, pl. viii.), in which there is now little doubt, with the light thrown on the subject by Dr. Marchand's specimens, that there is represented our common species of Botrydium with a para-site, or better, an endophytic Anabena. No doubt the cells of the Anabena in Parfitt's figure are badly represented, but the observation made in Parfitt's paper would seem now not to be without a special interest of its own.

Mesembrianthemum not Mesembryanthemum.—Prof. Asa Gray, in the *Botanical Gazette* (Indiana), vol. v. Nos. 8 and 9, p. 80, thus writes:—This word is properly written Mesembrianthemum, by Jacob Breyne, who made the name, and by Dillenius, who took it up, both giving the derivation from *Mesembria*, mid-day, alluding to the time in which the blossoms open. But both Breyne and Dillenius themselves very often wrote it Mesembryanthemum; Linnæus, adopting this latter, became consistent by making a wrong and far-fetched derivation to match the orthography. Among systematic writers Sprengel almost alone keeps to the correct orthography, but Webb insists on it. The younger Breyne, in his edition of his father's "Prodromus," has a note about it (p. 81). He mentions an excuse for changing the orthography, namely, "that some species do not open their blossoms at noontide," but intimates that Linnæus' derivation from the insertion of the corolla around the middle of the germ is open to the same objection. Prof. Asa Gray adds, "if heeded, this kind of objection would be fatal to very many generic names."

Chlorophyll in the Epidermis of Plants.—Adolf Stohr contributes to the *Schultz Proceedings* of the Vienna Academy a very interesting paper on the occurrence of chlorophyll in the epidermal tissue system of the leaves of flowering plants. He sums up a detailed account as follows:—While the epidermis of the aquatic submerged Phanerogams is usually regarded as containing chlorophyll, the epidermis of the green organs of the terrestrial Phanerogams is, on the contrary, considered to be

GEOGRAPHICAL NOTES

At a meeting of the Geological Society on Monday evening, Capt. St. H. Heath, R.E., of the Survey of India, read a very interesting paper on the geological results of the Afghan campaign 1878-80, after giving a brief sketch of the nature of the country, its mineral resources, &c. Only about 1000 square miles, or the 1/300th part of the whole area, had been surveyed geologically, but in the last year of the campaign 25,000 square miles were added to the known area. The rocks are very complicated, and their strike runs in every direction. Some of the most important fossiliferous rocks are the Lower Silurian, and the Carboniferous limestone, which yielded a rich fauna. Some of the coal seams can be made to yield the purest coke, with which powder is manufactured. Capt. Holdich's paper, read by the Secretary, Mr. Medlicott, dealt with the Mekran coast, which, according to Capt. Holdich, now, for the first time, has been surveyed from Cape Monze to Gwadur. The Hingol River, which, according to Arrian, was navigable for 200 miles, and also to Alexander's army, which passed along its banks, is now found to be only navigable for a few miles from the sea. The Hingol, Purali, and Kej rivers, which, according to Capt. Holdich, flow through a country which, according to Arrian, was a desert, are now found to be fringed with cultivation, and to flow through a country which, according to Capt. Holdich, is capable of supporting a large population. The Mekran coast, which, according to Arrian, was a desert, is now found to be fringed with cultivation, and to flow through a country which, according to Capt. Holdich, is capable of supporting a large population. The Mekran coast, which, according to Arrian, was a desert, is now found to be fringed with cultivation, and to flow through a country which, according to Capt. Holdich, is capable of supporting a large population.

Survey of India, made some valuable observations on certain groups of mineral species from Central Asia.

Under the title of "Die geographische Verbreitung der chiroptera." Dr. Dobson has published a volume of 320 pages, containing a brief but full sketch of the progress of African exploration from the earliest times down to the present day. Its special value consists in the excellent bibliography of the subject contained in the footnotes on every page, which must be of the greatest service to the students of African exploration and geography. There are occasional slips as when Mr. Monteiro's book on "Angola and the River Congo" is entered under "Monteiro," as published in New York in 1875, and again under "J. John," as published in London in 1876. But such blunders are wonderfully few. About 1500 names are referred to altogether.

DR. LENZ, on November 22, was at St. Louis, whence he was going to Tangier.

AS a memorial of the work performed in the Year, a "Jubilee Fund" has been raised by subscription in Sweden to encourage further geographical research. The sum raised is 35,000 crowns, which will be intrusted to the Swedish Academy of Sciences, and the interest either employed at once or be allowed to accumulate for a term of years. Only natives of Sweden, Norway, Denmark, and Finland will be entitled to receive the benefit of the fund.

TWO important expeditions are soon to be sent into Central Africa, under the auspices of the Algerian Missionary Society, which already has stations at the northern ends of Lake Tanganyika and the Victoria Nyanza. One will go from Zanzibar, and the other will ascend the Congo.

THE INFLUENCE OF PRESSURE AND TEMPERATURE ON THE SPECTRA OF VAPOURS AND GASES[1]

IN the course of my inquiry last year into the homology of the spectral lines of chemically-related elements I incidentally made the observation that the two strongly-marked red lines which I ascribed to the third-state give, when the pressure is reduced, to be likewise-related-radiation group very feeble or entirely disappear in the spectrum of the attenuated vapour in the Geissler tubes, while other lines not previously seen become visible. It appeared to me of interest to inquire more particularly into the changes of the spectrum of one and the same element, as these changes are naturally of the greatest importance in the comparison of chemically-related elements; and with this view I addressed myself to the problem of the changes of spectra at higher pressures.

Among many well-known experiments, a highly-attenuated with the three permanent gases, hydrogen, oxygen, and nitrogen, the spectral lines of the former under great disorder with higher pressure, and at the same time a continuously illuminated background to be observed. This phenomenon, however, presented even at the three permanent elements the greatest difference. Thus, while the lines in the hydrogen spectrum become easily resolved even under moderate pressure, those in the spectrum of nitrogen do not expand. There arose accordingly to me that a comparative investigation, which would extend to as many elements as possible, would be desirable, as such as it encouraged the hope that by this means one could arrive at a law, perhaps even at an explanation, of these phenomena.

I now venture to present to the Academy a report of my experiments as far as they have gone, reserving a full account till their completion.

In my experiments I have treated the most volatile of the metalloids, and among the metals have included cadmium and sodium. I will in due time give a full account of the apparatus and methods which I employed in my experiments, but at present I must confine myself to a statement of the results already ascertained.

The spectrum of the three halogens, at higher pressures, exhibits in each case the same peculiarities. The lines have the appearance of merging into each other, and without showing an expanded line-band, they become more readily resolvable bundles. There is a steadily illuminated background which becomes brighter when the pressure is increased, and which is often more intense than the lines themselves. This latter circumstance I frequently note in the case of iodine, where the continuous spectrum nearly covers all the rest. In the case of chlorine and bromine single lines are always distinguishable from the emitting as non-emitting light. The appearance of certain lines in the red field in chlorine and bromine which always preserve their pencil-like and definite is worth mentioning.

The changes in the intensity of the spectral lines as exhibited under different pressures are very interesting. If you compare the spectral lines of the halogens with each other, in order to ascertain their homology, and in doing so only employ the spectra of rarefied vapours in Geissler tubes, you meet considerable difficulties, for you can only compare the lines in groups, and these lines present frequently in each of the three elements such differences of intensity that you may be left in doubt as to the existence of a homology of their lines. But the apparent differences arise in reality out of the variation of intensity and the number of the lines with the pressure. By appropriate change in the density of the gas or vapour you can always produce spectra which exhibit the perfect homology of the lines. Thus, in the case of iodine you must employ that tension which iodine-vapour has at 50° or 60° C., while in the case of chlorine and bromine atmospheric pressure is required.

The spectrum of sulphur does not change at all at higher pressure, the lines maintaining their perfect sharpness, while in the red field a continuously illuminated background appears.

Phosphor and arsenic do not give any reaction, and even the continuous spectrum does not appear. With arsenic I observed what I think has hitherto been overlooked, namely, that it gives at a moderate pressure, and without the interposition of a Leyden jar, *a fraction of the first order*. It is almost continuous, and with increase of pressure or interposition of the jar it gives to the spectrum of lines the spectrum of the second order.

Great is the difference between the metalloids of which we have hitherto been speaking and the metals; they have no expansion of their lines whatever, while the continuous light takes a low pressure place. In conclusion, for the lowness especially of the gases and vapours in my experiments.

With sodium I have only noticed the great width of the lines when they appeared complete, for I could only examine the light from a flame through a layer of sodium vapour. Sodium gave at high pressures a continuously illuminated spectrum over the Fraunhofer lines, which, however, did not go into absorption, but which I suppose to be continuously over the whole illuminated part of the field.

[1] By G. Gassiot in Ad. Ann. der k. Akad. der Wiss. Vienna, Second Band, V. Heft.

UNIVERSITY AND EDUCATIONAL INTELLIGENCE

CAMBRIDGE.—Prof. Stuart finds the progress of his School of Mechanism and Engineering again compel enlargement. Some pupils are now reading small engines, and require more space for erecting them. A room for mechanical drawing is needed, and also an enlarged store. The Museums and Lecture-rooms Syndicate think of best in the present condition of University funds to erect a new temporary building 40 feet long by 20 feet wide, adjacent to the present workshop, and this, with other rooms which can be added, will supply present necessities for about 3000*l*.

The balance of 821*l*., being the debt on the last two years of the Museums Maintenance Fund, has been granted as an extra payment from the University Chest, and in future years 3000*l*. will be granted annually for the Museums and Lecture-rooms Maintenance Fund.

Prof. Stuart is to have the services of a Demonstrator in Mechanism and Applied Mechanics.

Clare College announces a scholarship of 60*l*. a year in chemistry and chemical physics, botany and geology, to be competed for on March 29 next, without limit of age. Jesus and Magdalene Colleges examine to offer no inducements to natural science.

BY a Royal decree, published last month, a museum will shortly be opened at Palermo on the plan of the one founded in Rome in 1874, with the object of making known the best scho-

est didactic methods adopted with success
l and civilised nations. This museum is
Museum, and will have its seat in the Royal
Museum, and will have its seat in the Royal
s to collect, with a view to their recognis-
objects and publications connected with
t in elementary schools, and in general all
ppliances which are being successively
er efficiency and progress in the arts of
n. All that has till now been collected
zoogy in the present Museum of Palermo
s the new institution, which is dependent
Instruction.

TIFIC SERIALS

Journal of Physiology, November.—Dr. C.
October, contains:—Dr. C.
art 1, of tuberculosis in man, identical
form of tuberculosis in man, identical
plates 1 to 6.—Dr. W. Allen, on a
plates 1 to 6.—Dr. W. Allen, on a
the human subject, plate 7.—Dr. J.
the histology of cirrhosis of the liver,
the histology of cirrhosis of the liver,
a contribution to the pathological
a contribution to the pathological
s, plate 9.—Dr. G. S. Middleton,
s, plate 9.—Dr. G. S. Middleton,
bia and in other diseases characterised
bia and in other diseases characterised
e 10.—Dr. D. Macphail, an other per-
e 10.—Dr. D. Macphail, an other per-
ical or pathological laboratories, plate
ical or pathological laboratories, plate
comparative value of chloroform
comparative value of chloroform
ne-diuretic agents.—Dr. R. Pinkerton,
ne-diuretic agents.—Dr. R. Pinkerton,
ture of the healthy human body in
ture of the healthy human body in
rge Hoggan and Dr. F. Elizabeth
rge Hoggan and Dr. F. Elizabeth
artilage and of the perichondrium.—
artilage and of the perichondrium.—
e branch from the middle meningeal
e branch from the middle meningeal
ar anomalies.

Journal of Botany, vol. iii. No. 5, October.
ture and function of the scale-leaves
ture and function of the scale-leaves
Edward F. Greene (the late), on daylight
Edward F. Greene (the late), on daylight
irror, an appendix to Part I. of the
irror, an appendix to Part I. of the
paratus.—W. Webb, on an im-
paratus.—W. Webb, on an im-
s by R. B. Tolles.—The record of
s by R. B. Tolles.—The record of
invertebrata, cryptogamia, micro-

November.—F. M. Endlich, the
November.—F. M. Endlich, the
ation, the Sand-hill Crane.—W.
ation, the Sand-hill Crane.—W.
ical characters contained in plants
ical characters contained in plants
n the origin of the flora (regards it as
n the origin of the flora (regards it as
Edward F. Greene, botanizing on
Edward F. Greene, botanizing on
tor's table: on the obligations of
tor's table: on the obligations of
ution.

Zeitschrift für Zoologie, Band 34, Heft 4,
Zeitschrift für Zoologie, Band 34, Heft 4,
borate memoir by Dr. Ferdinand
borate memoir by Dr. Ferdinand
he anatomy of the liver-fluke,
he anatomy of the liver-fluke,
40-646, with six plates; also by
40-646, with six plates; also by
the nervous system of Unio,
the nervous system of Unio,
val, bifid, and imago condition
val, bifid, and imago condition
plates.

Annals of Botany, October 15, con-
Annals of Botany, October 15, con-
ological study of pollen, with
ological study of pollen, with
n, Protoplasm considered in the
n, Protoplasm considered in the
fe; intercellular.—M. Scott on
fe; intercellular.—M. Scott on
ies of a germine.—M. L. Forbes,
ies of a germine.—M. L. Forbes,
ne.—G. Thurlet, contributions
ne.—G. Thurlet, contributions
l Chemical Properties of amino

Bihang till Svenska Vet.-Akad. Handl.—Three
Bihang till Svenska Vet.-Akad. Handl.—Three
ned to the entomologists. These
ned to the entomologists. These
the distinct, pp. 1-48. On the
the distinct, pp. 1-48. On the
pp. 1-10. On the lepidopters,
pp. 1-10. On the lepidopters,
These papers seem well put
These papers seem well put
deserve every support from the
deserve every support from the
rict and others.

ED ACADEMIES

NDON

ecember 9.—Mr. Samuel Roberts
ecember 9.—Mr. Samuel Roberts
r.—Mr. William Ralph Roberts
r.—Mr. William Ralph Roberts
rts were elected Members.—The

following communications were made:—Note sur la Dérivation des Déterminants, Prof. Teixeira (Coimbra, Portugal).—Solution of the equation $x^4 - 1 = 0$; quintic equation, Prof. Cayley, F.R.S.—A general theorem in kinematics, Prof. Münchin.—On the solution of the inverse logical problem, Mr. W. B. Grove.—Motion of a viscous fluid, Mr. T. Craig.—On the electrical capacity of a conductor bounded by two spherical surfaces cutting at any angle, Mr. W. D. Niven.

Chemical Society, December 2.—Dr. Gilbert, Vice-president, in the chair.—The following papers were read:—On the volumes of sodium and bromine at their boiling-points, by W. Ramsay.—On the volume of phosphorus at its boiling-point, by D. O. Masson and W. Ramsay. The authors have determined the atomic volume (the atomic volume = the specific volume × atomic weight) of the following elements in the free state: Bromine 27·135, sulphur 21·03, phosphorus 20·91, sodium 31·00. The authors discuss the formula of oxygen chloride of phosphorus, and conclude that in that substance phosphorus is quinquivalent, and that the constitution of that substance is $O=P\overset{Cl}{\underset{Cl}{\overset{Cl}{\underset{Cl}{}}}}Cl$. The atomic volume of phosphorus in this compound is therefore 21·1.—On the specific volume of chloral, by Laura Maude Dassovant. Great care was taken in purifying the chloral: the specific volume, determined according to the method of Thorpe, was found to be 107·37.—Note on the formation of carbon tetrabromide in the manufacture of bromine, by J. C. Hamilton. A quantity of a white crystalline substance was obtained as a residue, after distilling a quantity of commercial bromine, it melted at 90°, and contained 97 per cent. of bromine.—Researches on the relation between the molecular structure of carbon compounds and their absorption-spectra, by W. N. Hartley. Part I.—General conclusions as to the nature of actinic absorption exerted by various carbon compounds. Part II.—Experiments which prove the diactinic character of substances constituted on an open chain of carbon compounds. Part III.—The actinic absorption exerted by various closed chains of carbon atoms. Part IV.—The absorption-spectra of condensed benzen nuclei. Part V.—The cause of absorption-bands in the spectra transmitted by benzene and its derivatives.

Geological Society, December 1.—Robert Fliteroft, F.R.S., president, in the chair.—Wm. Hugh Hall, Wm. Jackson, Peregrine Prospert Lyon, William Tilbury, jun., D.Sc., New York, Peregrine Prospert Lyon, William Tilbury, jun., D.Sc., New York, U.S.A.; David Morgan Llewellin, John Marshall, Cyril Jersey

Nilgheris.—Mr. W. A. Forbes, F.Z.S., read a paper on the external characters and anatomy of the Red Cinkati Monkey (*Semnopithecus rubicundus*), describing more particularly the liver and brain, and made remarks on the other species of that genus and their distribution.

Anthropological Institute, November 23.—Allen Thomson, M.D., F.R.S., vice-president, in the chair.—The election of W. R. Huggild was announced.—A paper by Dr. Paul Topinard, entitled observations upon the methods and processes of anthropometry, was read. Anthropometry means the measurement of the entire human body with the view to determine the respective proportion of its parts:—1. At different ages, in order to throw light on the law of relative growth of the parts. 2. In the races, so as to distinguish them and establish their relations to each other. 3. In all the conditions of surrounding circumstances, in order to find out their influence upon the variations ascertained. The number of skeletons at disposal for this purpose being small, all our efforts should tend to make perfect the methods of operating upon the living, and to simplify them, so as to render them accessible to all, to travellers, officers of the navy, recruiting agents, schoolmasters, &c.; hence the number of measurement; should be reduced to those strictly necessary, and only those insisted on which are really useful and lead to the knowledge of one of the natural morphological divisions of the body. Heights above the ground, breadths, some circumferences, and perhaps the facial angle—to these we ought to limit our demands. The dimensions to be obtained directly, or by the method of subtraction, relate to:—1. The trunk. 2. The head and the neck taken separately. 3. The lower limb as a whole. 4. The upper limb as a whole. 5. Each of the segments of the limbs, the hand, the forearm, and the arm in the one case; the foot, the leg, and the thigh in the other. 6. The intrinsic proportions of the head, of the trunk, of the foot, and of the hand. Three fundamental principles to be duly observed, determination and marking the reference points—*viz.* taking the measurements quickly, and the possession of good instruments. The choice of reference points is matter of great importance, and the author explained his views upon this subject.—A paper by Mr. C. Staniland Wake on the origin of the Malagasy was read.

Physical Society, November 27.—Prof. W. G. Adams in the chair.—New Member, H. C. Jones, F.C.S.—Prof. Graham Bell exhibited his photophone, and explained the apparatus employed by Mr. Simons Tainter and himself for transmitting speech by a beam of light. The form in use consists of a metal plate or mirror vibrated by the sound and reflecting a beam of light to a distance, where it is received on a selenium cell in circuit with a telephone and battery. The light undulates in intensity with the vibrations of sound, and alters the resistance of the selenium in accordance with the vibrations, thereby reproducing the sound in the telephone. The electric light used was first employed to give a regular supply; but by means of a reading with just loud sound as was with before the light could be regulated to such a minute degree as to fix in the telephone. Indeed a number of receivers have described, some of which have not yet been tried. One of these consisted in varying the position of the plane of polarisation of the reflected beam. A plan for transmitting the beam consists in making (or at will) alternately vary the supply of gas to a jet of manganese nitrate. The author's present receiver has been found by experiment to be best; but theoretically it should operate better the greater the distance between the mirror and selenium. A receiver, consisting of a sheet of hard rubber in the ray, the invisible rays of which thereby is changed the sounds in a lower degree, and sounds can be heard by replacing the selenium receiver by sheets of different materials, such as hard rubber, metals, &c., and simply listening to them. All substances speak before the passage of incoming rays under the influence of varying light. Hard rubber, platinum-foil, coke, give the best results; paper, glass, carbon, the worst. Even tobacco-smoke in a glass tube held in the beam emitted a noise, as also did crystals of sulphate of copper. When hard rubber was skilfully made into the form of an ear-tube and held in the beam, the audible effect was also produced, and in fact when the beam was focussed on the ear it was heard without any other appliance whatever, a 16 foot sound could be perceived.—Prof. Adams thanked Prof. Bell in the name of the Society, and called on Mr. Sheffield Bidwell, who exhibited a lecture photophone, in which the reflector for receiving the light was discarded and the beam focussed on the selenium by a lens. The two lenses used cost only 25*s.*, and the beam was sent fourteen feet. The selenium cell was made by spreading melted selenium over sheets of mica, and then crystallising it by heat. For mica Prof. Bell recommended microscope glass. The resistance of the cell was 14,000 ohms in the dark, and 6500 in the light. Speech was distinctly transmitted by this apparatus. Mr. J. Spiller thought that since selenium probably alloyed with brass and the baser metals, it would be better to use gold and silver for the cells; but Prof. Bell said that he preferred brass, since perhaps for the reason that Mr. Spiller gave it yielded the best results.—Dr. J. H. Gladstone read a paper on the specific refraction and dispersion of isomeric bodies—an extension of his paper of last June. He concluded that the dispersion of a body containing carbon of the higher refraction is very much greater than that of a body containing carbon of the normal refraction 5, and that isomeric bodies which coincide in specific refraction coincide also in specific dispersion.

Entomological Society, December 1.—Sir John Lubbock, F.R.S., president, in the chair.—Mr. Pascoe exhibited a large series of *Arsinoe hilaris* from Peru, to show the extreme variability of the elytral markings in this species.—Mr. Killaby exhibited four species of *Psammobius* new to British, viz., *P. Mulleri*, *P. porcinus*, *P. intermedius*, *P. laevicollis*, and also exhibited twenty species of Coleoptera found in a small parcel of corn refuse. The president exhibited two specimens in alcohol of a species of *Philaenus* forwarded by a correspondent in St. Vincent.—Mr. Considine exhibited a specimen of *Thelcteria ignorabilis*, a species of *Tenthredo*, new to Britain; he also exhibited a remarkable variety of *Chilocorus renipustulatus*.—Mr. J. Scott communicated a paper on a collection of Hemiptera from Japan.—Mr. C. O. Waterhouse read a paper entitled description of a new species of the accumulans genus *Polystrates*, and exhibited a diagram illustrating the structure of this insect.

Royal Asiatic Society, November 15.—Sir H. C. Rawlinson, K.C.B., F.R.S., president, in the chair.—Sir W. E. Robinson, E.C.S.I., S. S. Thothaum, Capt. R. Gill, R.E., and the Rev. Marsham Argles, M.A., were elected Resident Members; and the Bishop of Lahore, Lieut. H. B. McCallum, R.E., S. W. Bushell, M.D., and Abd-er-rahman Mudvie Syed, barrister-at-law, Non-resident Members.—Prof. Monier Williams, C.I.E., read a paper on Indian theistic reformers, in which, after showing that Monotheism was not of recent growth in India, he traced the development of the modern Theistic churches there, from Rammohun Roy, who formulated a system which may be described as Unitarianism based on Brahmanism, through his successor, Debendra Nath, who improved on Rammohun Roy's work by founding the Adi Brahmo Samaj, to Keshub Chunder Sen, who threw off altogether both Brahmanism and caste, and founded his own progressive Brahmo Samaj in 1866. In his present eclectic form of Theism, composed of Hindu-ism, Mahomedanism, and Christianity, he teaches the worship of God under the character of a Supreme Mother. Some of his followers, attended with him, closely imitating marrying his daughter before she was fourteen to the Maharaja of Kuch-Behar, here recently set up a new Theistic Church called the Sadharan Brahmo Samaj, or Catholic Church of God. There are now more than 150 Theistic churches in different parts of India.

Royal Microscopical Society, December 8.—Mr. J. Gladstone, F.R.S., in the chair.—Eight new Fellows were elected.—Mr. Wills exhibited a new rotating substage; Mr. Morgan his form of spiral diaphragm, and Tuffen West's mechanical finger of ivory (stipples), and Mr. Crisp Crouch's histological microscope; Forbes's demonstrating microscope, Hibbert's compressorium, and Atwood's rubber-cell.—A paper by Dr. Hudson was read, on a new *Cricotus* (*Cricotus gracilis*), and a new *Floscularia* (*F. ringens*) found by Mr. Hood of Dundee in Loch Lomond. The tactile area of the former formed a link between that of *Melicerta* and *Conochilus*. The latter was remarkable in having only three lobes, and being much larger than any Floscularia hitherto known. Mr. Stewart explained some peculiar structural features of the Echinorhinidæ, illustrated by specimens and drawings.

Institution of Civil Engineers, November 9.—Mr. W. H. Barlow, F.R.S., president, in the chair.—The paper read was on machinery for sheet-making by the Bessemer and the Siemens processes, by Mr. Benjamin Walker, M. Inst. C.E.

December 7.—Mr. W. H. Barlow, F.R.S., president, in the chair.—The paper read was on the different modes of erecting iron bridges, by Mr. Theophilus Seyrig, M. Inst. C.E., of Paris.

Literature, November 24.—Mr. Charles
, in the chair.—Sir Hardinge Stanley
undra Ghose, Mr. Henry Allpass, Mr.
Capt. W. Deane Seymour, Dr. Altschul,
.—Mr. F. G. Fleay read a paper entitled
ish spelling reform now found in history
object of Mr. Fleay's paper was to show
pelling reform are principally founded on
of the amount of change required. This
aised by the revolutionary proposals of
o neglected the history of our language
ds of its orthography in favour of phili
Mr. Fleay, on the other hand, proposed
eveloped in two forms, one perfectly
purposes, the other differing from this
of the accents and the one new type
He showed that even in the vowel
ld need alteration, while in the case of
ion required would of course be much

, November 9.—J. Glaisher, F.R.S.,
ajor Waterhouse, Bengal Staff Corps,
ethod of obtaining "gram" in photo
alluded to was to squeeze into the
and- or glass-paper, previously waxed
ntraction of the paper while drying
bstance into the relief more strongly
ght-, and thus a discriminating grain
Abney, R.E., F.R.S., read a paper,
ess." The point insisted upon was
e some time before being fairly
ceness would be the result; another
uld be prevented by the same long
that with emulsions where silver
hyposulphite of soda would long

BRIDGE
November 8.—Prof. Newton, pre
owing communications were made
angement for sensitive flames, by
gas from a pin-hole burner im
cavity from which the jet is ex
pass tube a few inches long, and
e open. The front wall of the
embrane of tissue paper, through
the burner. The principle is
the flame described by Tyndall. In
me described the sensitive agent,
f the jet is the sensitive agent,
r. Harry's flame may be made
ght. A few years since Mr.
jet in a tube and side at the
arrival at the top of the tube,
vibrations have very nearly
he jet, and when they reach it
ing but little motion can arise
he arrangement was exhibited
ativeness to sound and upon
higher pressure than
the extreme of sensitiveness
re must be adjusted until
sound. The
Prof. Stuart's workshops. As
exactly at the middle of the
some advantage is gained by
the place of nodes. Lord
ns upon a suspended disk
ent by determining the unit of
and mirror are mechanically
end of a tube the ends of which
Under these circumstances a
the finger-nail upon the box
th the sensitive
dinary degree.
ations within the box, acting upon
at body, like a current of fluid in
any steady current of that sort
may fairly suppose that an current
ow from an alternating current
the box the air inside is made to
rably executes several vibrations

While these vibrations last the mirror is subject to a twisting force tending to set it at right angles to the direction of the vibration. The whole action being over in a time very small compared with that of the free vibrations of the magnet and mirror, the observed effect is as if an impulse had been given to the suspended parts. The experiment shown is intended to illustrate this effect. A small disk of paper, about the size of a sixpence, is hung by a fine silk fibre across the mouth of a resonator of pitch 128. When a sound of this pitch is excited, there is a powerful rush of air in and out of the resonator, and the disk sets itself promptly across the passage. A fork of pitch 128 may be held near the resonator, but it is better to use a second resonator at a little distance, in order to avoid any possible disturbance due to the neighbourhood of the vibrating prong.

PARIS

Academy of Sciences, November 20.—M. Edm. Becquerel in the chair.—MM. E. and J. Bourgeat presented a work on the silicified fossil seeds of strata of Autun and Saint Etienne, to which their father had devoted the closing years of his life. These researches led, among other things, to observation of a pollinic chamber in some living as well as in fossil species of seed.—Note relating to a memoir on vision of material colours in rotation, and velocities estimated in figures by means of the turning-plate apparatus of General Morin, for observation of the laws of motion, by M. Chevreul.—On the spontaneous oxidation of mercury and of metals, by M. Berthelot. He concludes from experiment that mercury, like iron, zinc, cadmium, lead, copper, and tin, undergoes, in contact with air, a superficial oxidation, very slight, indeed, and limited by the difficulty of renewal of the surfaces and the absence of contact resulting from commenced oxidation. This agrees with thermic data. The oxidation of mercury liberates per equivalent of fixed oxygen + 21·4 cal. (from 31°), in 329, &c.). Spontaneous oxidation is not appreciable in metals whose heat of oxidation is very small, e.g. silver (– 3·5 cal.). The greater rapidity of the reaction where an agent intervenes, which is capable of combining (with liberation of heat) with the substance produced, *e.g.* an acid, is shown to be in agreement with thermic theory.—On the propagation of light, by M. Gouy. He examines the case in which the rays have a constant direction, but vary in intensity, the source undergoing variations or being eclipsed by a moving screen. There is not, for a given homogeneous source, a determinate velocity of light, independent of the manner in which the amplitude is varied. But in every realizable experiment all variation is effected in a gradual and very slow manner relatively to the vibratory periods; here the formulæ are simplified and the amplitude is first carried to zero in a progressive medium for which it is shown to be in agreement with thermic theory.—On the velocity which is created by formed it. The index of refraction connected with the velocity of light for a relation of the condition.—On linear differential equations with periodic coefficients, by M. Floquet.—On a new electric property of selenium, by M. Hurmuzescu.—On the existence of tribo-electric currents, properly so called, and on the existence of tribo-electric currents properly so called, by M. Hurmuzescu. To one pole of a capillary electrometer a platinum wire is attached wall a platinum wire; to the other pole a platinum plate. If the platinum be brought into contact (insulating handle) into contact with the platinum the electrometer remains at zero; but on bringing the electron against the platinum a strong deflection occurs. Lippmann had found that an opposite direction to that of the current in question followed the platinum-platinum contact. It is shown that the platinum-platinum contact is the cause of the current in question, and that the platinum-platinum contact is the cause of the current in question.—On the action of phosphoric acid on hydrate and hydrofluoric acid.—Action of phosphoric acid on hydrate and hydrofluoric acid, by M. Painvin.—On Wolfberg, by M. Tamiel. The author gives the analysis of the crystals of wolfberg, which are found in the Cordilleras. The composition of the crystals is represented by the formula $3WO_3 + 2FeO$. The physical and chemical properties of wolfberg are described.—Insect analysis of peat; the chemical formula of peat, by M. Grimaud. The substance in question is a product of carbonization of the Somme Valley, formed under certain conditions of moisture and of time. Treated with water it yields resin and gas; treated with alcohol it gives resin, alcohol, and gas; treated with alcohol it gives resin, alcohol, and a little sulphate of lime. Alcohol at 90° produces a clear green solution, from which vegetable wax is easy to separate. The green matter has all the characters of chlorophyll. The

presence of *glucosides* can also be proved. Part at least of the total nitrogen of the peat (amounting to 3 per cent.) enters into the composition of the brown matters.—On the geology of the Northern Sahara, by M. Rolle. *Inter alia*, he found in the middle of the Great Erg, south of Ouargla, a broad plane region about 250 km. long, covered only with isolated parallel dunes lying along the magnetic meridian; an important feature for the Trans-Saharan railway. All the strata of the Northern Sahara are nearly horizontal.—On some phenomena of optics and vision, by M. Trève. Looking at a lamp-flame through a fine slit as a grid, the brightness and the diffraction effects vary much, according as the slit is vertical or horizontal.—M. Maumené in a note attributes the difference of experimenters as to absorption of oxygen by mercury to more or less silver contained by the mercury.—M. Dufrénoy announced the discovery of a prehistoric grotto in the Department of Landes.

December 6.—M. Edm. Becquerel in the chair.—The following papers were read:—On the development of any function of the radius-vector in elliptic motion, by M. Tisserand.—Spectral reaction of chlorine and bromine, by M. Lecoq de Boisbaudran. For detecting minute traces he fuses on the curved lower end of a platinum wire some pure carbonate of baryta; places in the bend a drop of the liquid to be examined; then evaporates, heating momentarily to a nascent red (with partial fusion); another platinum wire is then brought near the liquid from below, and the induction spark gives a spectrum with lines of $BaCl_2$ or $BaBr_2$. The $\frac{1}{20}$ mg. of chlorine or bromine may be thus detected.—M. Brioschi was elected correspondent in geometry in room of the late M. Borchardt.—On the action of water in applications of sulphide of carbon to the vine, method of using, by M. Cattel. He shows the injurious action of excessive humidity. The sulphide need not be in the liquid state if the air and be quite saturated with water.—On the swarming of phylloxera in 1880, by M. de Lafitte. Thickets been small, almost nil in some parts. The phenomenon is probably periodic, with a two years' period.—On nucleus, *Dictyocysta elegans Cienkowsky*, Berk and Curt., by M. Cornu. The nucleus will soon, perhaps next year, have special uses all Europe; and it is still almost unknown in region where it prevails. The grape is not directly attacked, but the plant is injured, often disastrously.—New process for destruction of larvæ of fig (*Cynips caricæ*, Fig.), by M. Grimaldis. The insects may be got rid of by making a number of incisions on the trunk and branches, causing the plant to emit a large quantity of latex.—Observation of comet *f* 1880 (Hartwig) at Paris Observatory, by M. Bigourdan.—On the same comet and on Swift's comet (1880), by MM. Schulhof and Bossert. He obtains for the former a revolution of 1250 years (uncertain); for the latter, 23 years.—On the method employed by Arbuthnot in 1810 for measurement of geodetic bases, by M. Laussedat. This is, in substance, the same as the method now recommended exclusively by the International Geodetic Commission.—On the calculation of heights by means of barometric observations, by M. Angot. He gives some rules for its application in the absence of certain data.—On the distribution of temperature on the lower strata of the atmosphere, by M. Angot. From observations on the north of south slopes of Mont Ventoux (1909 m. in height) he infers that on the same vertical the distribution of temperature up to a certain height is peculiarly independent, though it and solid. the extreme limits compared one another. The mean of temperature is a larger relation by the factors of both and how produced.—On radiophony, by M. Mercadier. Four means be given for the phenomenon, Tainter and Bell, by Prof. Bell. He knows reasons for thinking it is not a case of the action of the vibrating plate sometimes as a whole. May the agency of the molecules of the experimental mass in the of aggregation do not seem to have a predominant in the nature of the sound produced. These sound the number and the principally to direct action of calorific radiations on the surface of the receiver. The use the vibrating plate was inevitable with all as in the case of Prof. Bell.—On the existence of particular combinations, by M. Lecq. Four acts in presence of oxygenated water may like a different acid, though, of little stability; perhaps acid.—On cold-motion by M. Pouillard.—Researches on the comparative anatomy of the nervous system in the different orders of the class of insects, by M. Brandt. He gives the results of his own observations on Coleoptera, Lepidoptera, Diptera, and Hymenoptera.—On a new form of vesicular worm, with enormous cysts, by M. Villot. This is named *Cysticercus proliferus*, is a parasite of *Glomeris limbata*, and has the peculiarity of living in the same host in different degrees of development; in the vesicular state proper, in the visceral cavity; in the state of scoles, encysted in adipose tissue. Buds are successively formed (containing 2 scoles) and detached.—Habits of a fish of the family of Silurs, the *Callichthys fuscatus*, Cuvier, by M. Carbonnier. Its mode of reproduction is peculiar.—New researches on cirripedes; applications of their products to the arts and to therapeutics; experiments on their cultivation, by MM. Garreau and Machelart. Attention is called to a new substance, *bergenin*, obtained from the stocks; in the free and crystalline state it is represented by $C_{14}H_8O_9$. It is a strong neuro-sthenic tonic (between quinine and salicine). The tannin and feculæ also obtainable, further recommend the cultivation of saxifrages.—On a process of meat-preservation by means of dextrine, by M. Senre. Meat dried and preserved with dextrine has remained unaltered twenty months, exposed to air.—The meteors of November 14, 1880, observed at Moncalieri (Italy), by M. Denza. Four observers counted thirty-seven in three-quarters of an hour. More than a third belonged to the stream of the Leonides, and they were the most beautiful.

VIENNA

Imperial Academy of Sciences, December 9. Dr. Flitzinger in the chair.—Researches on Liverworts: 6, Marchantieæ, by Herr Leitgeb.—On the watercourses of middle Europe, and the importance of regulation of the Danube, with special reference to the stretch between Theben and Gönyö (Hungary), by Herr Lauffgaucuil.—On the formation of germinal layers in the hen's egg, by Herr Eidler.—On combinations of chloride of calcium with fatty acids, by Herr Lieber.

Imperial Institute of Geology, December 7.—Geological map of the environs of Teplitz, by Herr Hannes.—On a new mineral, *schmidtite*, by Herr Brezina.—Tectonics of the Alpine carpinoy rocks of Schwaben (Tyrol), by Herr Tolle.—Geological state of Gratlay, by Herr Trajnochn.—On Pleistocene, by Herr Roger.

CONTENTS

THE CHEMISTRY OF THE PLANT . . . By Prof. HUGO E. ADOLPH . . . 165
ELECTRICITY OF DISEASE . . . 167
OUR BOOK SHELF:—
Barbosa: "Exploration du Congo" . . . 168
Dresser: "Illustrations of Extinct and Fossil Feathered Animals" . . . 168
LETTERS TO THE EDITOR:—
Mr. Spencer and Prof. Tait.—HERBERT SPENCER . . . 168
Cyclone Centres.—W. [illegible] . . . 169
Local Specialties, Malaria . . . 169
Dr. Lloyd on the Central Physiological Solid Nervous System in Birds.—W. [illegible] . . . 169
The Meteoric Theory.—H. [illegible] . . . 169
Colour Illustrations from Rabbit's Blood.—Dr. [illegible] . . . 170
Mental Physiology.—Dr. [illegible] . . . 170
Hail-stones in Devonshire.—Rev. F. [illegible] . . . 170
The Weather in Ireland.—W. [illegible] . . . 170
Note on Aërolites.—W. J. Udward . . . 170
The Weather in Ireland.—W. [illegible] . . . 171
The Climate of Lancashire Inland.—[illegible] . . . 171
Shadows.—M. A. Veeder . . . 171
[illegible] . . . 171
[illegible] . . . 172
[illegible] . . . 172
[illegible] . . . 172

RIPTIONS TO NATURE
ly . . . . . 28s.
yearly . . . . . 14s. 6d.
terly . . . . . 7s. 6d.
onies, United States, the Continent, and
in the Postal Union :—
y . . . . . 30s. 6d.
yearly . . . . . 15s. 6d.
erly . . . . . 8s.
ce: 29, Bedford Street, Strand.

ARY OF SOCIETIES.
LONDON

E OF REMOVAL.
IES HOW & CO.,
INSTRUMENT MAKERS,
INGDON ST., LONDON
ET, BRIDGE ST., AND 2, FOUNTAIN LANE.
HICROSCOPE, HOW'S MICROSCOPE LAMP,
and other Objects for the Microscope.

V. NEEVES,
HICAL INSTRUMENT
AND
TY COIL MAKER.
LIST, FOUR STAMPS.
I STREET, LONDON, W.C.

SURANCE COMPANY,
PALL MALL.
70. ONLY. ESTABLISHED 1797.
ICES ... LOSSES PAID ... £2,000,000.
SLOE ... may be had at the ...
Forms may be had at the ...
Free.
H. HUMPHREYS, Actuary and Secretary.

INK (DICHROIC).
BLACK INK
EW
NYTHING ELSE EVER PRODUCED.
Which this Ink is used. It has been adopted
the Customs, and Railway Companies
Ireland.
Black. | Flows easily from the Pen.
Blotting-paper may be applied at once
moment of writing.
tc. Bfor. | Sample Bottle, 1s. 6d.
ough Messrs. Barclay & Sons, Farringdon
Street; Bourne & Sons, Newgate Street;
Manchester; J. Allen & Co., Finsbury
Square; and Manchester Row; and to be had of
Cook, Paternoster Row; and to be had of
& DRAPER (Limited), Dublin.

J. ORME & CO.,
(Late M. JACKSON & CO.)
MANUFACTURERS AND IMPORTERS OF
SCIENTIFIC APPARATUS
AND
CHEMICALS.
SOLE AGENTS FOR HUGHES'S PATENT TELEPHONES,
Price 50s. per Pair, Cash with Order.
Price List sent on receipt of Three Stamps for Postage.
For Trade Terms inclose Business Card.
65, BARBICAN, LONDON, E.C.

ASTRONOMICAL TELESCOPE.
BATEMAN'S
WONDERFUL £5 5s. INSTRUMENT
J. BATEMAN,
20, CHEAPSIDE; 168, STRAND; ROYAL POLYTECHNIC, 309,
REGENT STREET; AND 121, HIGH HOLBORN, LONDON.

THOMAS CRAMPTON & CO.,
ELECTRICIANS, OPTICIANS,
AND
PHILOSOPHICAL INSTRUMENT MAKERS,

£5 5s. ASTRONOMICAL TELESCOPE.

ELECTRICAL AND SCIENTIFIC
APPARATUS.

NOW READY,
SECOND EDITION,
GRIFFIN'S
CHEMICAL HANDICRAFT.
PRICE 6s. 6d. POST FREE.
A CATALOGUE OF CHEMICAL APPARATUS,
ILLUSTRATED, CLASSIFIED, DESCRIPTIVE,
Demy 8vo, 480 pp., Illustrated with 1500 Woodcuts,
Most Complete and Compact List of Apparatus
JOHN J. GRIFFIN AND SONS, 22, GARRICK STREET,
LONDON, W.C.

ROYAL POLYTECHNIC.—CLASSES for
the preparation of Students for University Examinations, under the
direction of EDWARD B. AVELING, D.Sc., F.L.S., London
versity Matriculation, 1st and 2nd B.Sc., Preliminary Scientific, Mecha
Botany, Physiology, Chemistry. All the work practical.

W. LADD & CO.,

SCIENTIFIC INSTRUMENT MANUFACTURERS,

(By Appointment to the Royal Institution of Great Britain),

11 AND 12, BEAK STREET, REGENT STREET, W.

IMPROVED HOLTZ ELECTRICAL MACHINES. GRAMME'S MAGNETO-ELECTRIC MACHINE for Laboratory use.
PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3s. per oz.

Physical Apparatus of every Description.

ILLUSTRATED CATALOGUE, SIXPENCE.

PATERSON'S NEW CATALOGUE OF PHYSICAL APPARATUS.

LANTERN SLIDES for SCIENTIFIC LECTURES. Season 1880-1. Post free 6 Stamps.
Complete Sets of Physical Apparatus for Science Primers and all the Physical Text-books in use in Schools and Colleges.
Sonorous and Granular Dynamo Machines and Lamps for hire.
Schools supplied with Apparatus as per Science and Art Departments' Requirements in the Section of Light, Heat, Sound, and Electricity.
Electric Signals for Houses, Hotels, &c., Colliery Signals, Lightning Conductors. The Gower-Bell Loudspeaking Telephone.

EDWARD PATERSON, Electrical Engineer,

SHOW ROOMS AND STEAM WORKS:—76, LITTLE BRITAIN, E.C. (late 7, Bedford Court, W.C.).

MOLISON'S HARMONOGRAPH; executes the Harmonic Curves in the most perfect manner. 15s. and 21s.

Illustrated Catalogue of Electrical Apparatus, Part 1, post free, 6 Stamps. Ditto, Electric Signals, Part 2, 6 Stamps.

S. C. TISLEY & Co.,

OPTICIANS,

172, BROMPTON ROAD, S.W.

(Close to South Kensington Museum).

THE PHONEIDOSCOPE

An Instrument for Observing the Colour-Figures of Liquid Films under the action of Sonorous Vibrations.

Being a visible demonstration of the Vibratory and Molecular Motion of a Telephone Plate.

The PHONEIDOSCOPE, with 3 Discs, Bottle of Solution, Descriptive Pamphlet, &c., in Cardboard Box, 12s. 6d.

MANUFACTURED AND SOLD WHOLESALE AND RETAIL BY

S. C. TISLEY & CO., 172, BROMPTON ROAD, LONDON, S.W.

TELEPHONIC ELECTRICITY. All Materials supplied for experimental purposes.

Price Lists of Electrical and Acoustic Apparatus, with Drawings and Description of the Harmonograph, Post Free, 2d.

THIN GLASS FOR MICROSCOPIC MOUNTING, of best quality, Circles 1s. 6d. per ounce; Squares, 2s. 9d.; post free 2s. extra; Spread-eagle Slips, 5s. per gross; also other Mounting Materials and Objects prepared for mounting.—CHAS. PETIT, 152, High Street, Stoke Newington, N.

On the 1st of every Month.

TRIMEN'S JOURNAL OF BOTANY,

BRITISH AND FOREIGN.

New Series. Edited by James Britten, F.L.S., British Museum.

CONTENTS.—Original Articles, by leading Botanists.—Extracts, and Reviews of Books and Memoirs.—Articles in Journals.—Botanical Notes.—Proceedings of Societies.

Price 1s. 6d. Subscription for one Year, payable in advance, 15s.

London: WILLIAMS, NEWMAN, & CO., 34, Hatton Garden, E.C.

"The leading Farmers' paper."—Right Hon. Sir Stafford Northcote, Bart., M.P.

THE CHAMBER OF AGRICULTURE JOURNAL AND FARMERS' CHRONICLE

(PRICE 2d. WEEKLY).

"The representative organ of the Central and Provincial Chambers of Agriculture, gives fuller reports of the discussions and proceedings of these executive organisations than any other agricultural paper. It devotes special attention to the treatment of Agricultural Questions in Parliament, including contents & topic Reports of the LATEST DEBATES, and COUNTRY CORN, CATTLE, WOOL, PROVISION, and other Markets, with Original Articles on Practical Farming, the Dairy, Herd and Flock Notes, Horticulture, &c., &c. It is so printed every Monday evening in time for the country post."

Terms of Subscription, payable in advance; post free:—3 months, 3s. 3d.; 6 months, 6s. 6d.; 12 months, 13s. 6d.

Published by W. FFRENCH, 21, Arundel Street, Strand, London, W.C.

HOLLOWAY'S OINTMENT A CERTAIN REMEDY

For BAD BREASTS, OLD WOUNDS, and SORES. If effectually rubbed on the Neck and Chest, it cures SORE THROATS, BRONCHITIS, COUGHS and COLDS; and for GOUT, RHEUMATISM, and all Skin Diseases it is unequalled.

NORTH BRITISH AGRICULTURIST

is the only Agricultural Journal in Scotland, and circulates extensively amongst Landed Proprietors, Factors, Farmers, Farmholders, and others interested in the management of landed property in Scotland and the Northern Counties of England.

The AGRICULTURIST has also a very considerable circulation on the Continent of Europe, America, Australia, and the Colonies.

The AGRICULTURIST is published every Wednesday afternoon in time for the evening mails, and contains Reports of all the principal British and Irish Markets of the week, besides Telegraphic Reports of those held on the day of publication.

The Veterinary Department is edited by one of the leading Veterinarians in the country, and is invaluable to the breeder and feeder as a guide to the treatment of animals, and their treatment when labouring under disease.

Full Reports are given of the Meetings of the Royal Agricultural Society of England, the Royal Agricultural Society of Ireland, the Highland and Agricultural Society of Scotland, the Scotch Chamber of Agriculture, and all the principal Agricultural Associations throughout Great Britain and Ireland.

For Advertisers addressing themselves to Farmers a better medium does not exist.

Price 3d. By post 3½d. Annual Subscription, payable in advance, 14s.

Offices—127, High Street, Edinburgh.

Post-Office orders payable to Charles Anderson, Jun., Edinburgh.

ESTABLISHED 1843.

THE ENTOMOLOGIST'S MONTHLY MAGAZINE.

Price Sixpence. Monthly, 64 pages 8vo, with occasional Illustrations.

Conducted by J. W. DOUGLAS, F. Mel Ent Soc., F.E.S., C. G. Ros, F.L.S. and H. T. STAINTON, F.R.S.

This Magazine, commenced in 1864, contains standard articles and notes on all subjects connected with Entomology, and especially on the Insects of the British Isles.

Subscription—Six Shillings per Volume, post free. The volumes commence with the June number in each year.

Vols. I. to V. (originally issued at 10 shillings) may be obtained by subscribers to the entire set to date, at the increased price of 12s. each; the publication of Vol. VI. may be had complete, 7s. 6d. or together, at 19s. each.

London: JOHN VAN VOORST, 1, Paternoster Row.

N.B.—Communications, &c., should be sent to the Editor at the above address.

On the 1st of every Month, price Sixpence.

THE ENTOMOLOGIST:

AN ILLUSTRATED JOURNAL OF BRITISH ENTOMOLOGY.

Edited by JOHN T. CARRINGTON.

With the Assistance of

FREDERICK POLLOCK, F.Z.S. | JOHN A. POWER, M.P.
EDWARD A. FITCH, F.L.S. | J. JOSEPH WEIR, F.L.S.
F. P. HORDEN-WHITE, M.D.

Contains Articles by well-known Entomologists on all branches of the Science; on Insects injurious or beneficial to Farm or Garden; Notices of Habits, Life-histories, occurrences of Rarities, &c.; Reviews kindly but Discriminating and Descriptive.

Numerous Woodcut Illustrations, in the printing of which especial attention is given, and occasional Lithographic and Chromo-Lithographic Plates.

SIMPKIN, MARSHALL, & CO., Stationers' Hall Court.

THE "HANSA"

Published since 1861 in Hamburg, is the only independent professional paper in Germany, dedicated exclusively to Maritime objects. Essays, Critiques, Reviews, Reports, Advertisements. Strict principles in the development of Maritime Affairs in every respect. Every second Sunday the Number in 4to at least 2; frequent 4-sp. Inserts and drawings. Subscription at any time; preceding numbers of the year furnished, when possible. Price per year for twelve months. Advertisements 4d. a line, widely spread by the paper; considerable abatement for 3, 6, 12 months insertion. Business Office: Aug. Meyer and Diedrichsen, Hamburg. Address of Editor: W. v. Freeden, Mr. Hugh [illegible]

MACMILLAN & Co.'s PRIMERS.

OF ONE MILLION OF THESE PRIMERS HAVE BEEN SOLD.

SCIENCE PRIMERS.

UNDER THE JOINT EDITORSHIP OF

S HUXLEY, ROSCOE, AND BALFOUR STEWART.

In 18mo, cloth, with Illustrations, price 1s. each.

CTORY PRIMER. By Professor HUXLEY, F.R.S.

By H. E. ROSCOE, hemistry, the Victoria University, the ter. With Questions.

BALFOUR STEWART, ral Philosophy, the Victoria Uni- s, Manchester. With Questions.

ARCHIBALD GEIKIE, gy, Edinburgh.

RAPHY. By Prof. ns.

PHYSIOLOGY. By MICHAEL FOSTER, M.D., F.R.S.

ASTRONOMY. By J. N. LOCKYER, F.R.S.

BOTANY. By SIR J. D. HOOKER, K.C.S.I., C.B., F.R.S.

LOGIC. By W. STANLEY JEVONS, LL.D., M.A., F.R.S.

POLITICAL ECONOMY. By W. STANLEY JEVONS, M.A., LL.D., F.R.S.

*** Others in preparation.*

AND LITERATURE PRIMERS.

EDITED BY

HN RICHARD GREEN, M.A., LL.D.,

Author of "A Short History of the English People"

In Ordinary Cloth, price 1s. each.

ight Hon. W. E. CLASSICAL GEOGRAPHY. By H. F. TOZER, M.A.

AR. By the Rev. GEOGRAPHY. By GEORGE GROVE, D.C.L., F.R.G.S. With Map.

. M. CREIGHTON, CHILDREN'S TREASURY of LYRICAL POETRY. By F. T. PALGRAVE. In Two Parts, each 1s.

YFFE, M.A. With SHAKSPERE. By Prof. DOWDEN.

PURIE. By Prof. PHILOLOGY. By J. PEILE, M.A.

FREEMAN, D.C.L., GREEK LITERATURE. By Prof. JEBB, M.A., LL.D.

ENGLISH GRAMMAR EXERCISES. By R. MORRIS, LL.D., and H. C. BOWEN, M.A.

TIES. By J. P. ENGLISH COMPOSITION. By Prof. NICHOL.

al.

TIES. By Prof. FRANCE. By CHARLOTTE M. YONGE. With Maps.

*** Others in preparation.*

AN & CO., BEDFORD STREET, STRAND, W.C.

Messrs. MACMILLAN & CO.'S PUBLICATIONS.

ETCHING AND ETCHERS. By P. G. HAMERTON. New Edition, Revised, with a New Plate by Calcidius Sec.

"The text of the new Edition has been thoroughly revised and increased by one-fifth. Several new Chapters and a new Preface have been added, while matter which had become unnecessary or disproportionate has been removed, to make room for additional and more important matter. *Immediately.*

The Edition is limited to 1000 copies, all of which have been subscribed for. Particulars as to price, &c., may be obtained from any bookseller.

LIFE OF WILLIAM BLAKE. With Selections from his Poems and other Writings. Illustrated from Blake's own Works. By ALEXANDER GILCHRIST. A New and Enlarged Edition, with Additional Letters and a Memoir of the Author. Printed on hand-made paper, the Illustrations on India paper, and mounted in the text. 2 vols., cloth gilt, elegant, with designs after BLAKE by FREDK. J. SHIELDS. Medium 8vo. *In the Autumn.*

Several new Illustrations have been added to this work, which has long since taken its position as the standard authority on its subject. Among others the following may be named:—The Phillips Portrait of Blake; two new Portraits by Blake of his Wife; a new plate from the *Jerusalem*; a newly-discovered design to *Hamlet*; and a drawing of *Blake's Cottage at Felpham*. New Prophecies of the *Invention to the Book of Job* are given. Some thirty additional letters are included in the Biographical portion of the work, forming a new link in the already interesting Life of Blake. And Mr. W. M. Rossetti has revised, enlarged, and perfected the annotated catalogue of Blake's works that appeared in the first edition of the work.

"One of the most beautiful and interesting books of the season."—*Daily News.*

ISLAND LIFE; or, the Phenomena and Causes of Insular Faunas and Floras, including a revision and extension of the Problem of Geological Climates. By ALFRED RUSSEL WALLACE, Author of "The Malay Archipelago," "The Geographical Distribution of Animals," &c. Medium 8vo, with Illustrations and Maps. 15*s.*

"The work throughout abounds with interest."—*Athenæum.*

"He takes his subject matter from all the sciences, and he builds it into a new harmony as a whole."—*Geographical Record.*

PHYSICS OF THE EARTH'S CRUST. By Rev. O. FISHER, M.A., F.G.S., Rector of Harlton, &c. 8vo. 15*s. nearly ready.*

A DICTIONARY OF MUSIC AND MUSICIANS (A.D. 1450—1880). By Eminent Artists, English and Foreign. With Illustrations and Woodcuts. Edited by GEORGE GROVE, D.C.L. In three Volumes. Parts I. to XII. 6*d.* each. Vols. I. and II. cloth, 12*s.* each.

Vol. I. A to Impromptu. Vol. II. Impresario to Pleyel Sainz.

"Dr. Grove's Dictionary will be a boon to every intelligent lover of music."—*Saturday Review.*

ENGLISH MEN OF LETTERS. Edited by JOHN MORLEY. Crown 8vo. 2*s.* 6*d.* each. [New Volume.]

WORDSWORTH. By F. W. H. MYERS.

GILBERT WHITE'S NATURAL HISTORY AND ANTIQUITIES OF SELBORNE. New Edition, with a Portion of Letters never before published. Edited, with Notes and Memoir, by JAMES BUCKLAND, Author of "Log-Book of a Naturalist," &c. SELBORNE, and the Garden Kalendar. With Original Illustrations from Drawings by Professor DELAMOTTE, taken on Selborne, and from various other sources. Reproduced by the Autotype Chromo Edition. Crown 8vo. 10*s.* 6*d.*

STUDIES IN DEDUCTIVE LOGIC. By W. STANLEY JEVONS, LL.D., M.A., F.R.S. Crown 8vo. 7*s.* 6*d.*

"Besides these answers to questions which scarcely increase the value of the book, and make it all but an indispensable manual of the subject, Professor Jevons has taken occasion to supplement his previous works in various directions. . . . It is indispensable to university students."—*The Academy.*

"Athenæum.

GUIDE TO THE STUDY OF POLITICAL ECONOMY. By Dr. LUIGI COSSA, Professor of Political Economy in the University of Pavia. Translated from the Second Italian Edition. With a Preface by W. STANLEY JEVONS, F.R.S. Crown 8vo. 4*s.* 6*d.*

"It would be impossible to find a more compact and better written sketch of the history of Political Economy and its latest developments. . . . It is an admirable compendium and will, we hope, be widely circulated, as it will prove to many for the first time that the study of Political Economy is even more actively pursued on the Continent, than in England."—*Academy and Queries.*

THE LIFE'S WORK IN IRELAND OF A LANDLORD WHO TRIED TO DO HIS DUTY. By W. BENCE JONES of Lisheen. Crown 8vo. 6*s.* [*Immediately.*

NEW VIEWS ON IRELAND: IRISH LAND GRIEVANCES AND REMEDIES. By CHARLES RUSSELL, Q.C., M.P. Crown 8vo. 2*s.* 6*d.* [*Immediately.*

THE IRISH LAND LAWS. By ALEXANDER G. RICHEY, Q.C., LL.D., Deputy Regius Professor of Feudal and English Law in the University of Dublin. Crown 8vo. 3*s.* 6*d.*

"To all who, either as legislators or publicists are called on to take part in the present controversy, the book will prove invaluable. The relation of the work to the discussions which now occupy so much attention is well expressed. . . . It would be difficult to find any series of legislative problems stated with greater clearness, sequence, and precision. We can recommend this little book to all who speak, write, or seriously think about this question in or out of Parliament."—*The Times.*

THE NECKLACE OF PRINCESS FIORIMONDE and other Stories. By MARY DE MORGAN. With Twenty-four Illustrations by WALTER CRANE. Extra fcap. 8vo. 6*s.*

ALSO AN EDITION, Printed by Messrs. R. and R. Clark, on hand-made paper. The Plates, inital letters, head and tail pieces being printed on India paper and mounted in the text.

The Edition is limited to ONE HUNDRED COPIES. Fcap. 4to.

"The stories display considerable originality, and Mr. Crane's characteristic illustrations combine with Miss de Morgan's pretty fancies to form a charming gift-book."—*Graphic.*

"A real gem."—*Punch.*

A CHRISTMAS CHILD: a Sketch of a Boy-life. By MRS. MOLESWORTH, Author of "Carrots," "The Cuckoo Clock," &c. Illustrated by WALTER CRANE. Globe 8vo. 4*s.* 6*d.*

"A very sweet and tenderly drawn sketch with life and reality manifest throughout. . . . Very few can rival Mrs. Molesworth in the power of making us see the children of Fancy, and in this 'Christmas Child' something has given to her pen a special power."—*Pall Mall Gazette.*

THE WHITE RAT, AND SOME OTHER STORIES. By LADY BARKER. Illustrated by W. J. HENNESSY. Globe 8vo. 6*s.* 6*d.*

"A pleasant little volume. It is pretty outside and pleasant in."—*Morning Post.*

PANSIE'S FLOUR BIN. By the Author of "When I was a Little Girl," &c. Illustrated by ADRIAN STOKES. Globe 8vo. 2*s.* 6*d.*

"Worthy to be classed with 'Alice in Wonderland,' and in some respects is better adapted to juvenile comprehension."—*Morning Post.*

XENOPHON'S ANABASIS. Books I.—IV. Edited by Professors W. W. GOODWIN and J. W. WHITE, of Harvard University. Fcap. 8vo. 3*s.* [Macmillan's Classical Series.

"This is an excellent school-book. . . . There are many editions of the Anabasis or its parts, but we are inclined to think that this is the best for a young scholar who is beginning himself a good one."—*Dublin Evening Mail.*

THE STORY OF ACHILLES, FROM HOMER'S ILIAD. Edited, with Notes and Introduction, by the late J. H. PRATT, M.A., Fellow of Trinity College, Cambridge. Assistant-Master at Harrow; and WALTER LEAF, M.A., Fellow of Trinity College, Cambridge. Fcap. 8vo. 6*s.* [Macmillan's Classical Series.

LIVY.—SCENES FROM THE HANNIBALIAN WAR. Adapted for the use of Beginners by G. C. MACAULAY, M.A., Assistant-Master at Rugby. 18mo. 2*s.* 6*d.* [Macmillan's Elementary Classics.

"Here is an adaptation of Livy's difficult text to the wants of beginners, the peculiarities of Livy's beautiful style being carefully and most ingeniously preserved, while its difficulties are entirely removed. . . . We heartily recommend this little book for use in schools. There could be no better introduction to Livy now to the art of Latin Prose Composition."—*Dublin Evening Mail.*

MACMILLAN'S FRENCH READER. Second year, containing Fiction in Prose and Verse, Historical and Descriptive Extracts, Essays, Letters, and Dialogues, &c. By EUGÈNE FASNACHT, Author of Macmillan's Progressive French and German Courses, &c. Extra fcap. 2*s.* 6*d.*

MACMILLAN AND CO., LONDON.

Printed by R. CLAY, SONS, AND TAYLOR, at 7 and 8 Bread Street Hill, Queen Victoria Street, in the City of London, and published by MACMILLAN AND CO., at the Office, 4 and 5 Bedford Street, in the County of London.—THURSDAY, December 16, 1880.

NATURE

WEEKLY ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
Of Nature trusts the mind which builds for aye."—WORDSWORTH

3] THURSDAY, DECEMBER 23, 1880 [PRICE SIXPENCE

[All Rights are Reserved.

at the General Post Office.]

61, STRAND, and
4, ROYAL EXCHANGE,
LONDON.

FACTURERS OF
APH WATCHES.
HRONOMETERS,
CENTRE SECONDS WATCHES.
ACTURERS OF
CHRONOGRAPHS
STRONOMICAL CLOCKS
ERVATORIES
reat Standard Galvanic Chrono-
ory, Greenwich, and the Japanese
re manufactured by E. DENT

ew Edition, containing some
Clocks, Sent free on application
Chester Terrace

D DISSOLVING VIEWS.

in London for Phantasmagoria
ssolving Views.

15, HIGH HOLBORN.

et of DISSOLVING VIEW
, complete, that will fill a Disc
eet in Diameter, £7.
ith OXYHYDROGEN APPA-
complete, from £10 10s.
TERNS, with 3½-INCH CON-
IVING A 10-FOOT DISC,
£2 10s.
SMALLER SIZES, WITH
ES, from 6s. 6d.
PHOTOGRAPHS, Coloured
om 1s. 3d. each.
SLIDES in every variety of
ject.
Views, specially kept for Hire,
free by post.

BROWNING'S
IMPROVED LANTERNS
FOR ELECTRIC LAMPS.

For Demonstrations in Physics, and Screen Experiments of all Kinds in Spectrum Analysis, Microscopy, &c., &c.,

£7 10s., £11 10s., and £16 10s.

ILLUSTRATED CIRCULAR FREE.

JOHN BROWNING,

Optical and Physical Instrument Makers to H.M. Government, the Royal Society, the Royal Observatories of Greenwich, Edinburgh, &c., &c.

63, STRAND, LONDON, W.C.

Factory—Southampton Street and Exeter Street, London.
PRIZE MEDAL, 1862. ESTABLISHED 100 YEARS.
Telescopes Speedily Repaired, Opera Glasses, Clocks &c.

STANDARD METEOROLOGICAL INSTRUMENTS

ILLUSTRATED PRICE LISTS FREE BY POST.

NEGRETTI & ZAMBRA,
Opticians and Scientific Instrument Makers
TO HER MAJESTY THE QUEEN.
HOLBORN VIADUCT,
45, CORNHILL, & 122, REGENT STREET, LONDON.

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 180, Tollington Road, Holloway, London, N.

CHRISTMAS LECTURES.

ROYAL INSTITUTION OF GREAT BRITAIN,

ALBEMARLE STREET, PICCADILLY, W.

Prof. DEWAR, M.A., F.R.S., will deliver a course of Six Lectures (adapted to Juvenile Audiences) on "Actinism," commencing on Tuesday next, December 28, at 3 o'clock; to be continued on December 30, 31, and January 4, 6, 7, 1881. Subscription to Members of the Course, One Guinea; Juvenile Members under 16 years of age, Half a Guinea. Tickets for the Course to Non-Members may now be obtained at the Institution.

CHEMICAL & PHYSICAL RESEARCH.

—A Gentleman of Youth (now at Cambridge) is open to receive a few Pupils, to read Chemistry, Physics, &c., with H.M. Inspector of Science Schools.—Address, Rev. T. H. Hall, Caius College, Cambridge.

UNIVERSITY OF LONDON.

PRELIMINARY SCIENTIFIC and the M.B. EXAMINATIONS.—Special Classes are now forming for these Examinations.—Apply personally or by letter to Dr. Hewlett, Medical Tutor, 3 Hanover Square, W.

INSTRUCTION IN MATHEMATICS.—

Youth of 18, who intended to take Wrangler's or Scholarship Rank, by a M.A. of Cambridge. Unexceptionable references given and required.—Address, by letter, to F., 8 Duke Street, Grosvenor Square.

MARINE AQUARIA.

Artificial Fresh and Salt Water for Marine Aquaria, in Bottles or Casks, 5s. per gallon.

W. SHARP & CO., [illegible]

THOMAS J. RUSSELL'S

NATURAL HISTORY STORES,

21, LYME STREET, STRAND, W.C.

Students and Others are invited to examine the Collections of Continental Foreign Shells, Corals, Zoophytes, Annelida, Crustacea, Recent Sponges, Minerals, Fossils, &c. Specimens, Store-cases, Glass Cases, &c.

Cabinets, Geological Hammers, Blow Pipes, Forceps, Reagents, Coal Tinted Labels, Glass Slips, Micro. Thin Glass, Canada Balsam, Marine Glues, and other requisites for the Use, Field and Microscopical.

Catalogues sent Post Free.

GEOLOGY AND MINERALOGY.

JOHN TYM has ready for Sale a Large and Valuable Collection of Fossils, Rocks, and Minerals, specially arranged to illustrate Text-books by Lyell, Geikie, Ramsay, Page, Phillips, Nicholas, Dana, Jukes &c. Series of Specimens for Class and Lecture Rooms arranged at very reasonable prices.—Catalogues post free.

Postal Address—CASTLETON, [illegible] DERBYSHIRE.

ROCK SECTIONS & ROCK SPECIMENS.

Cells, Forceps, Brass Turntables, Glass Slips, Rotating "Study of Rocks" [illegible] Small Collection of Rock Specimens for Schools. Nos. 1, 2, 3, F.R.S.E. Microscopes, and Thin Fly Microscopes.

JAMES SWIFT & SON,

[illegible] New Microscopes and Objectives,

CHARLOTTE STREET, PENTON VILLE.

BRYCE-WRIGHT'S LATEST ARRIVALS.

MINERALS.—Crystallised Heavite, Crystallised Goslarite, Kremnerite, Crystallised Arsenolite, Meloconite, Tincalconite, Edingtonite, Sulvanite, Chiastolite, Prosopite, &c.

METEORITES.—Specimens of the following Falls:—Wold Cottage, York Shire; Jowa; Orvinio, Italy; Ancona, Ohio; Tipperary, Ireland; Jowa; Orvinio, Italy; Bethanville; Thirlmere; Limerick, Ireland; Dundee; Carthage, Ohio; Bates Co.; Sierra di Chaco; Asheville Co.; Bates Co.; Pallas; Asheville Co.; &c.

BRYCE-WRIGHT, F.R.G.S., &c.,

Mineralogist and Expert in Gems and Precious Stones,

90, GREAT RUSSELL STREET, BLOOMSBURY, LONDON, W.C.

THIN GLASS FOR MICROSCOPIC

MOUNTING, of best quality. Circles, 1s. 6d. per ounce: Squares, 1s. 9d.; post free 2d. extra: Oblong edged Slips, 2s. per gross; also 4s. 6

BRITISH AGRICULTURIST

gricultural Journal in Scotland, and circulates extensively ded Prospects, Factors, Farmers, Farmsteadings, and others the management of landed property throughout Southland hern Counties of England.

AURIST has also a very considerable circulation in the ge, America, Australia, and the Colonies.

LURIST is published every Wednesday afternoon in 32 pages, and contains Reports of all the principal Fairs of the week, besides Telegraphic Reports of those held

Department is edited by one of the leading Veterinarians

s involved in the breeding and treatment of, and to the and their treatment when labouring under disease, agents of the Members of the Royal Agricultural Society, Royal Agricultural Society of Ireland, the Highland Society of Scotland, the Yorkshire, Cheshire, and National Agricultural Societies, and other Provincial Agricultural

addressing the Office as to Farming Literature, Advertisements, &c.

ed. Annual Subscription, payable in advance, 14s. 6d. 25, Street, Strand, W.C.

ts payable to A. Galt & Co., Aberdeen, James Edmonston, Edinburgh, or Duncan Lothian, 13, Johnston Terrace, Edinburgh.

ESTABLISHED 1843.

L'ÉLECTRICITÉ 5me ANNÉE

— 16, *rue du Croissant*, — *Paris*

ale populaire, illustrée, la mieux

24 pages grand in-8° à deux colonnes. Volume

Chaque année un nouveau volume

ous serez au plus tôt au courant.

Rédacteur en chef : W. DE FONVIELLE

Directeur : E. de Clisson

Un numéro, 75 centimes

Un numéro spécimen sera donné à

Prix de numéro spécimen sera donné à

artements. Un an..... 12 fr.

Un an..... 14 fr.

Un an..... 26 de chaque mois

Les parties du 1er et du 26 de chaque mois

NE FRANÇAISE : a Weekly

Review in the French Language. Politics, Literature, Series, Notes. Price 2d., through booksellers and stalls. Office, 32, Southampton Street Strand, W.C.

FRANÇAISE : Journal Française pour

FRANÇAISE, Arts, Variétés, Nouvelles, time, Littérature, Sciences, Modes, Théâtres, Musique, mplaire partout, 32 pages grand in-8°. Prix 25 c. par poste—un an, 10 francs. On s'abonne aux Faux Gates des principaux libraires de Paris, Londres, W.C. ampton Street, Strand, Londres, W.C.

FRANÇAISE.—"La Semaine Fran-

ought out in London for the benefit of those English wish to study contemporary French from all points of nforming their reading to one particular Gallic publi- success."—*Graphic*.—"The numbers before FRANÇAISE. It will be far better for most than any things. We are much pleased ers published in Paris itself. We shall be highly valued in Paris of it, and believe it will be highly valued in Paris here French is cultivated. The printing is very well

TERMS OF SUBSCRIPTION—	£	s.
— — — — — —	3	10
— — — — — —	7	7
— — — — — —	1	2
— — — — — —	1	5

SUBSCRIBE, at King Street, Covent Garden, W.C. 37, Southampton Street, Strand, W.C.

On the 1st of every Month,

JOURNAL OF BOTANY,

BRITISH AND FOREIGN. By [illegible], F.L.S., British Museum. ed by JAMES BRITTEN, F.L.S. Botanical Society. Contents.—Articles by [illegible]—Extracts, and Letters, &c., by leading Botanists.—Botanical News.—Literature.—Articles in Journals.—Botanical Appointments, &c.

Subscription for One Year, payable in advance, 10s. TRÜBNER & CO., 57, Ludgate Hill, E.C.

INSURANCE COMPANY,

72, PALL MALL.

LIVES ONLY. ESTABLISHED 1807.

Capital of more than £1,500,000

Forms may be had at the Office, or from any Agent.

HUMPHREYS, Actuary and Secretary.

POLYTECHNIC.—CLASSES for

Students, for University Examinations, under the R. D. BAVELING, D.Sc., F.L.S., London Univ. Matriculation and B.Sc., Preliminary Scientific M.B. Chemistry. All the work practical.

FLETCHER'S PATENT SOLID FLAME BURNERS.

The Safest, Cheapest, Purest, and most convenient. Improved Patent, with Pat. Cocks, gives 12 to 14 candle power each.

PRICE, Japanned, 6s. 6d.; Nickel-Plated, 8s. 6d.

Japanned, 4s.; Nickel-Plated, 5s. 6d.

THOS. FLETCHER,

[illegible] STREET, [illegible].

THE "HANSA"

[illegible] to Hamburg, in the centre of the City, close to the Exchange, the Custom House, Post Office, Banks, Consulates, Theatres, Museums, &c. Table d'hôte at 1 o'clock. Moderate charges. Pension terms may be had by the week or month. Apartments [illegible] Proprietor.

TO BOTANISTS AND HORTICULTURISTS.

ELWES (H. J.) MONOGRAPH OF THE

CLARKE (C. B., Superintendent of the Cal

BOOTT (F.), ILLUSTRATIONS OF THE

BERNARD QUARITCH, 15, Piccadilly.

*** A Catalogue [illegible]

MR. MURRAY'S LIST.

SIBERIA IN EUROPE. A NATURALIST'S VISIT TO THE VALLEY OF THE PETCHORA IN NORTH-EAST RUSSIA. With Descriptions of Birds and their Migrations. By HENRY SEEBOHM. With Illustrations, crown 8vo, 14s.

THE GARDENS OF THE SUN: A NATURALIST'S JOURNAL ON THE MOUNTAINS and in the FORESTS and SWAMPS of BORNEO and the SULU ARCHIPELAGO. By F. W. BURBIDGE, Trinity College, Botanical Gardens, Dublin. With Illustrations, crown 8vo, 14s.

A POPULAR ACCOUNT OF THE INTRODUCTION OF CINCHONA CULTIVATION into BRITISH INDIA, 1860-80. By CLEMENTS R. MARKHAM, C.B., F.R.S. With Maps and Woodcuts, post 8vo, 14s.

THE POWER OF MOVEMENT IN PLANTS. By CHARLES DARWIN, LL.D., F.R.S., assisted by FRANCIS DARWIN. With Woodcuts, crown 8vo, 15s.

RAMBLES AMONG THE HILLS. A Series of Walks chiefly in the PEAK OF DERBYSHIRE, and the SOUTH DOWNS, from PRESTON-FIELD to BEACHY HEAD. With Descriptions and Sketches of Old Houses, Churches, and People by the Way. By LOUIS J. JENNINGS. With Illustrations, post 8vo, 12s.

A SMALLER MANUAL of MODERN GEOGRAPHY. For SCHOOLS and YOUNG PERSONS. By JOHN RICHARDSON, M.A., Author of "A School Manual of Modern Geography." 16mo, 2s. 6d.

JOHN MURRAY, Albemarle Street.

JUST PUBLISHED, Crown 8vo, cloth, 5s.

CONSCIOUS MATTER;

OR,

THE PHYSICAL and the PSYCHICAL UNIVERSALLY IN CAUSAL CONNECTION.

By W. STEWART DUNCAN.

London: DAVID BOGUE, 3, St. Martin's Place, Trafalgar Square, W.C.

DR. SMILES'S WORKS.

Now Ready, 20th THOUSAND.

DUTY; with Illustrations of Courage, Patience, and Endurance. Price 5s.

SELF-HELP; with Illustrations of Conduct and Perseverance. 5s.

CHARACTER: A Book of Noble Characters. 5s.

THRIFT: A Book of Domestic Counsel. 5s.

INDUSTRIAL BIOGRAPHY: Iron Workers and Tool Makers. 5s.

LIVES OF THE ENGINEERS. 5 Vols. 5s. 6d. each.

THE HUGUENOTS: their Settlements, Churches, and Industries in England and Ireland. 7s. 6d.

JOHN MURRAY, Albemarle Street.

Now ready,

EXERCISES in PRACTICAL CHEMISTRY. Vol. I. (ELEMENTARY EXERCISES). By A. G. VERNON HARCOURT, M.A., F.R.S., Senior Student of Christ Church, and LEV. Reader in Chemistry, and H. G. MADAN, M.A., Fellow of Queen's College, Oxford. Third Edition, Revised and with Solubility Introduced, crown 8vo, cloth, 9s.

London: HENRY FROWDE, Clarendon Press Warehouse, 7, Paternoster Row, E.C.

EDITED BY HENRY WATTS, B.A., F.R.S.,

Editor of the "Journal of the Chemical Society."

FOWNES' PHYSICAL and INORGANIC CHEMISTRY. Twelfth Edition, with Coloured Plates and 165 Engravings, crown 8vo, 12s. 6d.

Also,

FOWNES' CHEMISTRY OF CARBON COMPOUNDS; or, ORGANIC CHEMISTRY. Twelfth Edition, with Engravings, crown 8vo, 12s.

London: J. & A. CHURCHILL.

"NATURE," Nov. 7, 1878.—One Shilling each will be paid for Copies of the number.—Address Publishers of NATURE, 20, Bedford Street, Strand, W.C.

THE SCIENTIFIC RESULTS OF THE VOYAGE OF H.M.S. "CHALLENGER."

Now ready, Crown 4to, with 9 Plates, price 12s. 6d.

REPORT on the SCIENTIFIC RESULTS of the VOYAGE of H.M.S. "CHALLENGER" during the YEARS 1873-76, under the Command of Capt. GEORGE S. NARES, R.S., F.R.S., and Capt. F. TURNER, R.N. Prepared under the Superintendence of Sir C. WYVILLE THOMSON, Knt., F.R.S., &c. (Provisional Edition). By the Staff of the Civilian Scientific Expedition in Professional Duty attached to the Zoological Station, by Sir C. WYVILLE THOMSON, and his Assistants.

**** This Volume is one of a Series of Separate Reports as follows:—

Part I. Introductory. By CHARLES DARWIN, F.R.S., &c. Price 2s. 6d.

" II. Preliminary. By C. WYVILLE THOMSON, F.R.S., &c. Price 2s. 6d.

" III. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 5s.

" IV. Deep-Sea Soundings. By JOHN MURRAY, LL.D., &c. Price 1s.

" V. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. (With Additional Papers). Price 5s.

" VI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" VII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" VIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" IX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" X. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XXI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XXII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XXIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XXIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XXV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XXVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XXVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XXVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XXIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XXX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XXXI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XXXII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XXXIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XXXIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XXXV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XXXVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XXXVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XXXVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XXXIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XL. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XLI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XLII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XLIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XLIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XLV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XLVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XLVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XLVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XLIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" L. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXXI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXXII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXXIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXXIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXXV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXXVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXXVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXXVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXXIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXXX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXXXI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXXXII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXXXIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXXXIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXXXV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXXXVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXXXVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXXXVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" LXXXIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XC. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XCI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XCII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XCIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XCIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XCV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XCVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XCVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XCVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" XCIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" C. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXXI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXXII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXXIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXXIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXXV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXXVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXXVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXXVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXXIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXXX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXXXI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXXXII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXXXIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXXXIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXXXV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXXXVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXXXVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXXXVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXXXIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXL. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXLI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXLII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXLIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXLIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXLV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXLVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXLVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXLVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXLIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CL. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXXI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXXII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXXIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXXIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXXV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXXVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXXVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXXVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXXIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXXX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXXXI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXXXII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXXXIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXXXIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXXXV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXXXVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXXXVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXXXVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CLXXXIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXC. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXCI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXCII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXCIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXCIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXCV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXCVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXCVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXCVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CXCIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CC. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXXI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXXII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXXIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXXIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXXV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXXVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXXVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXXVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXXIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXXX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXXXI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXXXII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXXXIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXXXIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXXXV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXXXVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXXXVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXXXVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXXXIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXL. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXLI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXLII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXLIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXLIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXLV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXLVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXLVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXLVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXLIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCL. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXXI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXXII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXXIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXXIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXXV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXXVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXXVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXXVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXXIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXXX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXXXI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXXXII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXXXIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXXXIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXXXV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXXXVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXXXVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXXXVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCLXXXIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXC. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXCI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXCII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXCIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXCIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXCV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXCVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXCVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXCVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCXCIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCC. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCCI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCCII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCCIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCCIV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCCV. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCCVI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCCVII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCCVIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCCIX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCCX. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCCXI. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCCXII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCCXIII. Deep-Sea Deposits. By JOHN MURRAY, LL.D., &c. Price 10s.

" CCCXIV. Deep-Sea Deposits. By J

RSDAY, DECEMBER 23, 1880

THE FOGS OF LONDON

k Mr. Scott Monerieff described in our
s a method of all but entirely eliminating
he atmosphere of London, and thus abolish-
venerable of our institutions—Fog. And
mber Dr. Siemens showed how our existing
e made to give out a maximum of heat at a
xpense and an entire absence of smoke. It
be of some interest to inquire briefly into
ries as to the causes and consequences of
incubus which renders residence in London
many.

posed to form a constituent part of the clima-
itish Islands from which there is no escape;
trictly local climatologies, such as that of
the aggregation of human beings is alto-
lented, they now and again acquire an
tensity and persistency, and are attended
ces so disastrous and fatal as to press
ament the necessity of legislation towards
the evil.

of this, reference may be made to the
mortality of London exercised by the
iled there from November, 1879, to
which was so remarkable both for it
otractedness, as to constitute it one of
ble fogs on record. The question has
by Dr. Arthur Mitchell, and the result
in the *Journal* of the Scottish Meteoro

the death-rate was truly enormous, as
g the whole mortality for each of the
February 21, show—1734, 1730, 1906,
1,2016; in other words, several thousand
to the disastrous fatality of this great
tion of the figures in the Registrar-
hows that no approach to so large an
ath-rate showed itself in any of the
towns, and in none of these did fog o
ever occur. Of all diseases, rather
influenced in its fatality by the fog
the fog increased was that the death-
s the fog abated, rose at once
d the death-rate instantly fell. Thus
to 220 per cent. above the average
dense-t fog, but as the fog gave way
> 40 per cent. below the average
fat, pleurisy, and other lung diseases
n enormously increased fatality, and
hitis rising during the week when the
o 331 per cent. above its average. In
ases however the relief did not come
the cessation of the fog, but some
t nature appear to have been over-
death-rate at a high figure for some
ed finally disappeared. Whooping-
characteristics in even a still more

The pernicious effects of the fog
in the system; so that while the
- 582

mortality rose during the worst week of the fog to 182 per cent. above the average, four weeks thereafter it had fallen no lower than 74 per cent. above the normal mortality of whooping-cough. It is singular, and particularly to the medical profession profoundly interesting, that deaths from croup, diphtheria, and rheumatism did not show any distinct relation to the fog. As regards the other diseases, the deaths from which are registered, they equally did not appear to show any steady connection with the fog's varying denseness and persistency.

This pernicious and deadly character of fog on persons suffering from these diseases is not due to fog as such, but to the noxious qualities imparted to it by our large towns. Dr. Angus Smith has shown that the air of Manchester during an extremely dense fog contained 20·85 per cent. of oxygen, or one-tenth per cent. less than the normal quantity. The pernicious character of fog however is to be traced not so much to this slight diminution of atmospheric oxygen as to the presence of positively deleterious substances.

The smoke which issues from our dwelling-houses contains, in addition to solid soot, also gaseous carbonic acid, sulphurous acid, carbon monoxide, sulphide of ammonia, and sometimes minute traces of arsenic. Moreover the soot does not consist of particles of carbon only, but carbon saturated with tarry matters, sulphur and ammoniac compounds, &c. Smoke from manufactories is usually more completely burned than that from dwelling-houses, and is therefore less deleterious. In many cases however manufactories pour out into the air their own specific bad gases. Of these gases the more pernicious are muriatic acid, especially sulphuric and hydrochloric acids, sulphuretted hydrogen, sulphur dioxide, and oxides of arsenic. Gases rising from decaying animal and vegetable matter in waste heaps and in faulty sewers also lend their aid in the contamination of the atmosphere of towns. In the neighbourhood of various manufactories special nuisances exceed the unpleasantness of fog, as above restricted to them, with an accompanying increase of fatality to the inhabitants.

In February last we drew attention (NATURE, vol. xxi. p. 353) to the heat of fog and the general atmospheric [illegible] when they are generated, when the [illegible] causing the question of fog of a certain [illegible] accompanying an [illegible] and the accompaniments [illegible] Indeed it is to the [illegible] that we [illegible] [illegible] [illegible]

relation to the vast quantities of deleterious matters which are vomited into the atmosphere from the chimneys of London. The horizontal movement of the air is at a minimum, and thus altogether insufficient to sweep these noxious matters out into the surrounding country. The impurities therefore ascend into the air over London; and when no longer buoyed up by the warmer air with which they began the ascent, they fall under the influence of the general downward movement of the atmosphere; and this downward movement is accelerated by the solid impurities becoming saturated with condensed aqueous vapour, coal-oil, and tarry substances. Hence the specially noxious fogs of large towns settle near the surface, are no more than a few fathoms in depth, and are at the maximum where chimneys are planted thickest, the situation low-lying and confined, and where consequently the horizontal circulation of the air is absolutely arrested.

If we would then overcome, or in any way mitigate, the terribly fatal effects of our city fogs, it can be done in no other way than by Parliament interposing with a legislation which will not only effectually stop the emanation of deleterious exhalations from manufactories, but also compel the combustion of the smoke arising from ordinary fires in dwelling-houses. As regards the latter, where the real difficulty in legislating lies, it may be stated that we already have appliances for thoroughly burning coal, the use of which would be attended with an immense saving of money to the community, as well as the prevention of the painful recurrence of periods of such widespread sickness and mortality as London passed through in the beginning of the present year. But it is of little use in science showing how this terrible evil may be cured if the authorities make no attempt to put her hardly obtained results into practice; it would cost little to give both Dr. Siemens's and Mr. Moncrieff's methods a fair trial on something more than a miniature scale. But what are some of the obstacles to such a practical course may be seen from our correspondence columns to-day.

WHAT IS CIVILISATION?

The Past in the Present. What is Civilisation? By Arthur Mitchell, M.D., LL.D. 8vo. pp. xvi. and 354. (Edinburgh: David Douglas, 1880.)

THIS interesting volume, as may be inferred from the title, embraces two cognate but at the same time somewhat diverse subjects—the one the survival, or possibly the reintroduction, of objects and customs, which are usually regarded as primitive, among the civilised nations of the present day; the other the nature and origin of civilisation.

As Rhind Lecturer on Archæology Dr. Arthur Mitchell selected these two subjects as the topics on which to enlarge, and devoted six of his lectures to the first and four to the second; and these lectures, illustrated by nearly 150 excellent illustrations, form the body of his book, to which is added a long appendix and a detailed analytical table of contents.

The facts brought forward in the first portion of the work, though for the greater part by no means new to most archæologists, are of considerable general interest, and will appear sufficiently striking to the ordinary reader. The peregrinations of the author in the remoter districts of Scotland and the neighbouring groups of islands have brought him in frequent contact with those among whom ancient customs are most likely to have survived, whose domestic appliances are often of the same simple character as were those of their ancestors generations and generations ago, and whose ordinary life has also been but little affected by the advance in material civilisation of their fellow-countrymen. To these objects and customs so persistently surviving from the Past into the Present the term "neo-archaic" has been applied by Prof. Rolleston; and it is precisely these objects that a practised archæologist declines to regard as ancient, unless the circumstances of their finding justify him in so doing. Foremost among them is placed the whorl and spindle, an appliance for spinning still in use in parts of Scotland, as it is throughout the whole of the continent of Europe; and which indeed is never likely to be entirely supplanted by the spinning-wheel or other machinery, so long as the use of the spindle can be combined with an out-of-doors occupation, such as tending sheep or cows. All will agree with Dr. Mitchell that the mental power of those Scotch women who still use the spindle and whorl need not be a whit inferior to that of those who do not use it, and some will go farther, and place the shepherdess who spins in a higher rank than the one whose hands are idle all the day long. That a spindle should be made of a form to do without a whorl, or that a potato should be substituted for the latter, are regarded by the author as signs of the art of spinning by hand having reached a state of degradation; but if producing the greatest effect with the least possible trouble is any sign of progress, such an opinion is questionable.

In all such cases the external circumstances of a family or group of families must be taken into consideration; and if it be cheaper or more easy to employ articles of the simplest and rudest character than to purchase, it may be from a distance, the appliances of modern art, the simple methods and appliances will survive. Netting and knitting by hand will thrive by the side of netting and knitting by machinery, as the long hours of a winter's evening, which might otherwise be wasted, can thus be utilised at practically no cost; and it seems more remarkable that the simple form of narrow loom for webbing, of which Dr. Mitchell gives a figure, should have become almost extinct, than that it should have survived.

A flint for striking a light may be cheaper and in some respects more convenient than lucifers; and the "knockin'-stane" and mallet are not less effective for their purpose than the most expensive pestle and mortar. The earthenware "craggans" are as cheap and as well adapted for the ends they serve as pots thrown on the wheel; and in countries where carriage is difficult or extensive water power scarce, the quern or hand-mill and the little Norse-mill may still hold their own; as they did in St. Alban's in the fourteenth century, when they competed with the high charges for multure at the Abbey mills. The survival of the black houses and beehive houses in the Hebrides may also probably be reduced to a question of cost. Perforated or grooved stones are cheaper than plummets of lead as sinkers for nets and lines; and for working in water a pivot and socket of

stone is probably both cheaper and more durable than one of metal. The existence of sockets and other working parts formed of stone in our best clocks and watches can hardly be regarded as an instance of low civilisation, or of those who use them being in the Stone Age.

In all these remarks Dr. Mitchell will perhaps agree, and if the object of his lectures were merely to inculcate caution in accepting such objects as those he describes as belonging of necessity to any remote antiquity or to an absolutely rude and barbarous people, most archæologists would fully endorse his views. But there is throughout these lectures a more or less evident intention that they should apply not to any minor questions of archæological classification, but to the far greater question of the progress of the human race. Though accepting the ordinary division of antiquities into those of the Stone Age, of the Bronze Age, and of the Iron Age, he does not regard the use of stone, bronze, or iron as in any way indicative of the culture and capacity of those who used them. No doubt many of those who use iron and steel are mentally barbarians, and certainly the instances the author brings forward of the superstitious beliefs still prevalent in Scotland show how deeply rooted are such relics of early beliefs, and how little material civilisation has done to elevate the mental culture of the mass of the population. The distinction Dr. Mitchell draws between culture and civilisation is one which is well illustrated by the continued existence of such low forms of belief; and all his readers will agree with him that it is an error to suppose that in this or any other civilised country the mass of the people can be spoken of as highly cultured. Civilisation he defines to be nothing more than a complicated outcome of a war waged with Nature by man in society to prevent her from putting into execution in his case her law of Natural Selection.

Such a view of mankind being to a certain extent exempt from the operation of that law has already been held by many; but even if accepted does not appear to contradict the opinion that the human race may have been evolved from some lower form of mammalian life. For on such an assumption it is, as Dr. Mitchell insists, impossible that man in isolation could become civilised, while, on the other hand, it is evident that until he had become sufficiently intelligent or cultured to enter into association with his fellow men, he would remain subject to the law of Natural Selection in the same manner as any members of the brute creation. Nor even when the stage of association was reached can we expect that there should have been at once any great development of mental power; for there is a long interval between the banding together of a certain number of human units, and any one of them being in that position of ease and leisure which is so necessary for mental culture.

It is perfectly true that so far as osteological evidence is concerned there appears to be no tangible difference between the earliest known remains of man and the human frame of the present day. But it is by no means certain that all the skulls which have been attributed to the Quaternary Period actually belong to so remote an antiquity; and it is worth while to remember that among the coolies of China and some of the Pelew islanders, while the weight of the brain is singularly great, it is balanced by a marked deficiency in the number and depth of the secondary convolutions and by a want of depth in the grey matter.

Dr. Mitchell's view, though we believe nowhere clearly expressed, appears to be that during the whole period of the existence of the human race there was in some part of the world a state of civilisation in existence, which would imply that those among whom it prevailed were possessed of the same average mental capacity as any people or nation of the present day. "May it not happen," he says, "that dealing with the human race as a whole, there never has been a time in its history when there did not occur among men states both of high and of low civilisation? Is it not also possible that there may have never existed a time in the history of mankind as a whole when there were not among those composing it persons potentially as good—persons exhibiting as high a capacity—as any among those who now go to make up mankind?" Were the history of our race confined to the last five or six thousand years it might be hard to answer these questions otherwise than in the affirmative; but who that appreciates the vast antiquity of man as established by recent geological discoveries will admit that such a term forms more than a small fractional portion of the period of man's existence upon the earth, or that there is any parity of reasoning between the circumstances of the beginning of the human period and of the comparatively recent times of Egyptian or Assyrian civilisation?

Granted even that the potential mental capacity existed, of what use could it have been to those who were daily on the brink of starvation, who were unacquainted with writing, and with metal, and had not even succeeded in domesticating any of those animals which now seem almost necessary for human existence?

This however is not the place to enter into a long discussion as to the origin and progress of civilisation. Those, and they are many, who are interested in this subject will do well to read Dr. Mitchell's book, and even should they not agree with all his conclusions, will feel that his cause has not suffered from the treatment it has received at his hands.

They will also find in his Appendix much valuable matter extracted from the writings of Mr. Alfred R. Wallace, Mr. Herbert Spencer, and Mr. Bancroft. To the antiquary pure and simple the illustrations of the "neo-archaic" objects still in use in Scotland will be attractive and valuable; and should some stray politician take up the volume some of the reflections on the dangers to civilisation which may arise from over-legislation, as set forth in the last of the lectures, may profitably be studied.

AUSTRIAN MYRIOPODS

Die Myriopoden der österreichisch-ungarischen Monarchie. Von Dr. Robert Latzel. Erste Hälfte: Die Chilopoden. 8vo. pp. xv. and 228, plates i-x. (Wien: Alfred Hölder, 1880.)

THE centipedes, millipeds, and their allies have hitherto not only been neglected by English naturalists, but practically by Continental workers, until the present generation. Our countryman, Newport, indeed (of whom it may be said with justice, that he touched nothing that he did not elucidate and adorn), has secured a permanent

place in the annals of the class referred to; but it is to the brothers Koch, Meinert, and the Italians Fanzago and Fedrizzi, with the Bohemian naturalist Rosický, and some few other writers of less importance, that we have had to look in recent times for anything approaching serious or continued work upon these creatures. In America, Wood and A. S. Packard, jun., have also done good service. The writer of the book now under notice (Professor of Natural Sciences in the Imperial Franz-Joseph Gymnasium at Vienna) has by this sterling treatise at once assumed a place in the front rank of authorities. We are not aware of any prior writings of his on the subject, beyond one or two of trifling local interest; but, from his five years' study and collection of material in various parts of Austria and in Western Hungary, it is clear that he is qualified for the task of monographing the species of his country, especially as he has examined nearly all the exponents in Austrian collections and museums. As he says, no work on the *Myriopoda* of Europe, or even of Germany and the Austro-Hungarian Empire, exists; so it is to be hoped that the present instalment towards such a desideratum may be from time to time succeeded by others of more extended area.

As regards the preparation, &c., of specimens, Dr. Latzel recommends the use of small well-corked glass tubes, containing spirits of wine. Pinned examples are of no use.

Adopting the *Myriopoda* as a separate class (Packard seems alone nowadays in uniting them with the *Insecta*), the following classification is proposed: Orders I. CHILOPODA; II. SYMPHYLA, Ryder (for the *Scolopendrellidæ*); III. DIPLOPODA, with sub-orders *Chilognatha*, *Colobognatha* (for the *Polyzoniidæ*), and *Heterognatha* (for the *Pauropodidæ*); IV. MALACOPODA (*Peripatidæ*).

The present part discusses the *Chilopoda* only, the flat centipedes, with large sternum, and whose first pair of thoracic feet is transformed into foot-jaws. The common thin yellow *Geophilus*, which sometimes gives out a phosphoric light, is a type of the order. Thirty-one genera are recognised, whereof fifteen are European, one American (*Notiphilides*), and one European (*Stigmatogaster*) being described as new, and *Opisthemega*, Wood, renamed *Megopisthus*. Sixty-seven Austrian species are described (*Lithobius*, the largest, with thirty-seven), including many new ones.

It is not within our scope to analyse the specific characters of such a work; Dr. Latzel seems to have performed his task conscientiously and exhaustively, giving the varied stages of development in each case where known ("juvenis," "adolescens," "pullus," and "fetus"), and combining biological and anatomical aspects with the purely descriptive accounts.

The *Myriopoda* have always afforded material for the comparative anatomist, as evidenced quite recently by MacLeod's researches upon the poison-bearing glands of various Chilopods (in the *Bulletin* of the Belgian Academy of Sciences, 2nd series, vol. xlv. p. 781 *et seq.*), and Voges's scheme for the classification of *Tracheata* (in Siebold and Kölliker's *Zeitschrift für wissenschaftlische Zoologie*, vol. xxxi. p. 143), &c. Dr. Latzel recognises the importance of this element, and gives some remarkably well-executed lithographs (from his own designs) of such organs as are of general morphological importance, in addition to details illustrative of specific structure. Were it not for the general excellence of Continental work in such matters, we should congratulate Messrs. Hölder upon the result of their part in this matter.

OUR BOOK SHELF

Die Ethnographisch-Anthropologische Abtheilung des Museum Godeffroy in Hamburg. Ein Beitrag zur Kunde der Südsee-Völker. Von J. D. E. Schmeltz und Dr. med. R. Krause. (Hamburg: L. Friederichsen and Co. 1881.)

THIS catalogue of the anthropological section of the Museum Godeffroy in Hamburg is a model of its kind, and from the exhaustive manner in which it is treated the publishers are quite justified in calling the publication as they do in their prospectus a "Handbook of Ethnography and Ethnology of the South Sea Tribes." The Godeffroy collection is probably unique and unrivalled as representing the area to which it is confined, and is another example of what private munificence can accomplish for scientific ends; and though the great merchant house may no longer have their collectors scattered throughout the South Seas, the town of Hamburg now possesses by their exertions the anthropological material which this somewhat bulky volume of 687 pages with 46 plates is found not too large to enumerate. However, this catalogue is not merely an enumeration, but contains much valuable geographical information, and some most useful bibliographical notes, which, in the present absence of any anthropological record compiled in the method and way of our zoological work, is, if not perfect, much to be commended, and not too critically received. The arrangement is geographical, and therefore ethnological in its true sense, as followed in most large museums, the Pitt-Rivers collection being of course a brilliant exception, which is rather designed to exhibit evolution in culture.

The first part, "Ethnographische Abtheilung," is written by Dr. Schmeltz, and naturally occupies the largest portion of the volume. Australia is treated first, and then "Oceanien," commencing at New Guinea and terminating with the Sandwich Isles, including not only so large and well known an area as New Zealand, but also amongst others the smaller and much less known Exchequer Isles and Futuna. Of the last-named we are told incidentally that the fauna and flora is allied to that of Samoa. The Gilbert, Marshall, and Caroline Islands are then dealt with, the last very fully. This ethnographical portion concludes with Alaska and a few other various localities, thus showing that in the most special of museums the usual few outside elements *obtrude*.

The second part, "Anthropologische Abtheilung," is the joint production of Messrs. Schmeltz and Krause, the first author treating the photographs and original drawings, whilst Dr. Krause enumerates and describes the osteological specimens. The cranial measurements are most desired by physical anthropologists, and it is to be hoped that some of our own provincial museums which are still behind in that respect, though possibly containing but few crania, will yet, where such can be authentically localised, have the same at once properly measured, and for a method, the lately-published Catalogue by Prof. Flower will supply all that anthropological science requires. Such Catalogues as the one under notice, taken with those of Prof. Flower and General Pitt-Rivers, are in themselves real manuals of anthropology.

W. L. D.

On the Digestive Ferments and on the Preparation and Use of Artificially Digested Food. By Wm. Roberts, M.D., F.R.S. (London: Smith, Elder, and Co., 1880.)

THIS little volume contains the three Lumleian Lectures delivered before the College of Physicians, London, for the present year. The subject is treated in a manner worthy of the reputation of the author. He gives a summary of what is known on the subject of digestion as a function common to animals and plants, treats of the general characters and properties of the digestive juices and their ferments, with an account of the action of each on food material. After many trials the author adopts three solutions for the preservation of his solution of animal ferment, full details of the preparation of which are given. The researches of Musculus and O'Sullivan as to the transformation of starch are given, with the very recent researches on the same subject by Brown and Heron. The subject of the digestion of starch is excellently handled, and any dyspeptic reader would do well to consider the facts and reasonings here so well and clearly given. The second lecture chiefly relates to pepsin and the digestion of proteids; digestive proteolysis; the milk-curdling ferment. The third lecture is devoted to the effects of cooking on food, preparation of artificially-digested food, peptonised materials, the clinical experience of the use of peptonised food, and on the use of pancreatic extract as an addition to food shortly before food is taken. These lectures, though at times technical, may be understood by the ordinary reader, who would often derive advantage from a general knowledge of their contents. As long as man must live on food so long will the proper digestion of that food be of extreme importance to him.

The Niger and the Benueh: Travels in Central Africa. By Adolphe Burdo. From the French by Mrs. George Sturge. (London: Bentley, 1880.)

THERE is a good deal that is interesting in M. Burdo's lively story of his voyage up the Niger and Benueh, partly in the company of Bishop Crowther. He gives many details of the various towns and villages he visited on the banks of the two rivers, and of the appearance and habits of the people he met with, all welcome information in a region on which our information is even yet comparatively meagre. M. Burdo's journey was made in 1878.

LETTERS TO THE EDITOR

[*The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts. No notice is taken of anonymous communications.*

The Editor urgently requests correspondents to keep their letters as short as possible. The pressure on his space is so great that it is impossible otherwise to ensure the appearance even of communications containing interesting and novel facts.]

Smokeless London

I HAVE read the letter of Mr. Scott Moncrieff in NATURE, vol. xxiii. p. 151, with much interest, and am satisfied that his data and conclusions are substantially accurate. This conviction is based on some experience in the commercial distillation of coal.

One difficulty will arise which should at once be foreseen and provided against, or it may be exaggerated into a big bugbear by that class of self-styled "practical" men who oppose to every innovation the inertia of their own self-sufficient stupidity. The semi-coke remaining in the retorts, when only one-third of the volatile constituents of the coal has been run off, will be highly inflammable, and display this property by a great outburst of lurid flame and dense smoke when the retort doors are opened for discharging, and unless the withdrawn charge is immediately quenched there will be a veritable Inferno where it falls. This is merely a matter of practical detail admitting of easy remedy where there is ability and willingness to grapple with it.

A more serious difficulty is likely to arise in London from the peculiar position of the gas companies. They are suffering from commercial congestion due to a plethora of prosperity, and receiving no stimulation from wholesome competition, they display very low commercial vitality. The public welfare is no business of theirs.

It is otherwise in those towns that are sufficiently advanced in civilisation and have abolished the gas and water joint-stock monopolies. There the public are helping themselves, and control the management of the Corporation gas works by their election of the members of the Corporation. Many of these towns are foggy and smoky enough for the experiment, and in these such a boon as that offered by Mr. Moncrieff will probably be appreciated, and, being appreciated by those most interested, will be at once practically tested. Birmingham, for instance, is likely to try it. I was there a few weeks ago and saw how they have eclipsed our electric lamps on the Embankment by the gas lamps around their town-hall.

If it succeeds in any one of these towns our companies will surely follow, or if not, so much the worse for the companies.

Stonebridge Park, Willesden, December 17 W. MATTIEU WILLIAMS

I HAVE read with great interest Mr. Scott Moncrieff's scheme for "Smokeless London" propounded in your last issue. I would ask however—Is he satisfied that the coke would be smokeless when only 3333 feet of gas per ton has been extracted from the coal? E. R. F.

London, December 20

Climates of Vancouver Island and Bournemouth

I THINK it very probable that your correspondent Capt. Verney is right about the climate of Vancouver's Island. My only sources of information were maps of isothermals in Keith Johnston's and Phillips' Atlases, which show the *mean* temperature about the same as that of the south of England, while the *winter* temperature is shown as being decidedly colder, and it was to this I more especially referred. The mainland of British Columbia is undoubtedly colder than that of Western Europe, but Vancouver's Island itself and the adjacent sea may be really milder; and if so it is another proof of the great power of the returning Japan current.

I shall be very glad of Prof. Haughton's criticisms on my hypothesis; and in the mean time will only say: 1. That unless Bournemouth is *never* cooled by north and north-east winds, any amelioration of the climate of the Polar regions would certainly benefit it. 2. That as by my hypothesis the entrance of two new gulf-streams into the Arctic Ocean would entirely prevent the formation of ice; the return currents that would undoubtedly be produced would *not be cold currents* in the sense in which they are now, as they would probably be always considerably above the freezing point. ALFRED R. WALLACE

Geological Climates

IN relation to the discussion as to the importance to be ascribed to the distribution of certain trees and plants in the determination of geological climates, it may interest Prof. Haughton and Mr. Duncan to know that a specimen of the Australian *Araucaria Cunninghami* is now growing on one of the slopes of the Marlstone Hills near Belvoir Castle, in North Leicestershire, a position it has occupied for upwards of forty years. It has attained a height of about thirty-five feet. Having survived (without other protection than that afforded by the wooded heights about it) the cold of the winters of 1860 and 1879, its capability to withstand a greater degree of cold than is ever experienced in our southern counties may be with confidence asserted.

Masses of a true and very characteristic bamboo, *Bambusa metaké*, are now growing vigorously and spreading rapidly on the same estate, the long elegant and slender canes and the delicate green foliage of this variety of bamboo not having suffered in the slightest degree from the severe frost of last winter or the early and equally trying severity of this. *Arundinaria falcata*, the bamboo found as high as the snow-line in the Himalayas, has also proved hardy at Belvoir, but it has been displaced as an ornamental plant by *B. metaké*. *Arundo donax*

often throws up clustering bunches of canes that reach a height of sixteen feet in one season. Associated with *Arundo conspicua* and *Gynecium argentum*, the above interesting and handsome plants give quite a tropical aspect to some of the hill-sides of this northern county. WILLIAM INGRAM

Belvoir, December 20

The Appulse of Jupiter to a Fixed Star on November 20

REFERRING to a request appearing in NATURE, vol. xxiii. p. 158, I may say that the approach of Jupiter to B.D. + 2°97 was well observed here, and I found that the star, when perpendicular to the belts, was 4″·05 distant from the northern limb. The definition was good, and the measure, I should say, pretty exact.

It was a strange and beautiful sight, Jupiter appearing with *five* satellites, though, at the same time, the different aspect of the star compared with that of the moons was very striking. The light of the former was however very sensibly affected by the glow of the great disk near it, and it looked no more than 10 magnitude. JOHN BIRMINGHAM

Millbrook, Tuam

British Earthquakes

MAY I ask leave to offer a few remarks on the leading article on British Earthquakes which appeared in NATURE, vol. xxiii. p. 117. The author brings out very strongly the apparent connection between great lines of jointing or faulting and earthquake movements, and points out the great fault which traverses Scotland from sea to sea as a case in point. Now I had this same question before the British Association this year, and exhibited a map illustrative thereof. I had further, following up a theory submitted by me to the Royal Irish Academy, on the Correlation of Coast-Line Directions, and published by that body, drawn up on a Geikie's Geological Map of Scotland certain of those correlated lines, and on a smaller map of the British Isles had indicated both the lines in question and the localities wherein earthquakes have been noticed in later times, more essentially since 1860. One of those lines crosses the district about Comrie, and at the moment (August, 1880) could hardly be pointed out as in any notable way supporting the connection sought to be established between coast-line directions and earthquake localities. But the recent earthquakes in the north of Ireland and in Scotland go far to do this, as the direction shown by me both agrees with the great fault mentioned by the author of the paper on British Earthquakes in direction, and also fairly shows the direction of the earthquake band or zone, which apparently extends from Londonderry across Scotland. This direction is exactly at 40° with the coast-line direction between Carnsore Point and Wicklow Head, as shown on the accompanying map.

I may add that having had occasion to examine Prof. Höfer's memoir on the "Erdbeben Kärntens und deren Stosilinien," and to compare his lines with those given on the map of Europe exhibited by me at the British Association meeting of this year, I find some very remarkable concordances as regards directions, which, having submitted to him, he quite recognised. I consider therefore that this memoir, Prof. Geikie's very remarkable article on the Volcanoes of North-Western Europe, and this late article on British Earthquakes, all point more and more distinctly to the importance of jointing and fissuring in connection with volcanic and earthquake action, and so far go in support of the theory submitted by me. J. P. O'REILLY

Royal College of Sciences, Dublin, December 14

A General Theorem in Kinematics

I AM very much obliged to Prof. Everett and Mr. J. J. Walker for having taken the trouble to point out that the theorem which I communicated to NATURE is, *so far as it relates to uniplanar motion*, already known. I am indebted to Prof. Unwin for more complete information on the subject. He tells me that the theorem (for the uniplanar case) has been employed by German engineers in the discussion of stresses produced in moving pieces —exactly the use of the theorem which naturally presents itself. Moreover, the theorem (for the uniplanar case) will be found in § 198 of Collignon's "Cinématique," as well as in other foreign books, but not, so far as my information goes, in the work of any English author. None of your correspondents or of mine are however able to say that the *general* case was previously known.

The simple method of proof given by Prof. Everett is that which I had used nearly a month ago in a paper which I wrote (and have since read) for the London Mathematical Society.

I may mention in connection with this subject a kinematical theorem which Mr. Kempe communicated to NATURE some time back. I find that this theorem comes properly under a general theorem which holds for the areas of roulettes. It can be easily proved that the areas of the most general kinds of roulettes follow exactly the law of circular transformation which Steiner proved to hold good for the areas of pedals. For this theorem of Steiner's see Williamson's "Integral Calculus," p. 202, third ed.

Mr. Kempe's theorem (as also Holditch's) is an immediate consequence, since every possible uniplanar displacement of a body can be produced by epicycloidal motion. Mr. Williamson, justly describing Mr. Kempe's as "a singularly elegant theorem" (*ibid.* p. 210), arrives at it quite differently.

GEORGE M. MINCHIN

Royal Engineering College, Cooper's Hill, December 13

A Correction

IN NATURE, vol. xxiii. p. 44, Prof. Young has published some experiments proving that the thermo-electric power of a platinum-iron couple is to be observed in vacuo as well as in air; this fact is said to be contradictory to the results given in my papers. I presume that some error has caused this statement, as I never and nowhere asserted that the thermo-electric power is dependent on the surrounding gases. I have, on the contrary, stated (*Phil. Mag.*, October 1880, p. 294) that no such influence has been hitherto observed. Thus the experiments of Prof. Young do in no way contradict my views.

University of Vienna FRANZ EXNER

Jelly Fish

ON November 3, in the B.I.S.N. Co.'s steamer *Arcot*, Capt. Stevenson, while in lat. 16° 50′ N., long. 55° 45′ E., with the Kuriyan-muriyan islands to the north, thirty to forty miles and three days out from Aden to Karachi, we passed through a vast quantity of brown anemones, the ordinary bell-shaped jelly-fish and strange worm-like (apparently) jelly-fish, floating on and just below the surface. These were first noticed about five in the afternoon, and we were still amongst them when we went below to dinner at six, the vessel steaming about eight knots. The anemones were only peculiar in that they appeared to be rounded at the base and without the ordinary flat surface for adhering to rock or stone; they were in vast numbers and had the feelers expanded. The worm-like or centipede-like jelly-fish were from six to eight feet long and as thick as a man's wrist. They appeared sometimes singly, sometimes many twisted together; they were in slow feeble snake-like motion. All agreed that they were ribbed in appearance; but there was a difference of opinion as to the colour. It was described by some as that of the sea, by others as violet, brown, or purple. Each apparent rib was divided from those next it by a bar of lighter colour.

At night the sea was bright with many phosphoric lights of many shapes, so we were perhaps still passing through the mass. There was a dead calm at the time.

The captain has read this account and stated it to be fairly correct. F. C. CONSTABLE

Karachi, Sind, November 8

MR. PLIMSOLL'S CURE FOR COLLIERY EXPLOSIONS

LET us suppose a person actuated by very powerful motives, who desires to solve the most difficult mathematical problem of the day, and who, after having neglected to acquire the most rudimentary knowledge of his subject, and after having contented himself with seeking the company of land surveyors, and trying to entrap civil engineers into conversations about it, suddenly startles the world with the cry of Eureka! Eureka! Eureka! should we, or should we not, be inclined to regard his solution with respect?

Mr. Plimsoll has done for the mining world exactly what our supposititious person would have accomplished for the mathematical one. In an article contained in the December

number of the *Nineteenth Century*, under the title of "Explosions in Collieries and their Cure," he lays before the readers of that magazine an account of the praiseworthy motives which impelled him to seek some means of preventing these horrible disasters; he tells them plainly that he knows little or nothing about the subject, and he recounts what steps he took for the purpose of supplying the want of that knowledge to some extent. He says:—"In my hope that the resources of chemistry might supply a solution of the problem which has so long perplexed everybody, I have made it my business from time to time to seek the society of practical chemists as well as of purely scientific men whose business it is to teach chemistry. I have seen several amongst the former who are engaged in calico-printing works, lead-works, &c., and have sought, by getting them to talk about chemistry, and by so to speak lying in wait myself for some hint in their conversation, for something which might supply the missing link."

Mr. Plimsoll then gives an account of how he travelled over the painfully disappointing road of trying to "unmask" the fire-damp, to "make it visible to the eye like smoke or steam," and to indicate its presence by means of a collodion balloon filled with the light carburetted hydrogen and put into a vertical recess glazed in front where it "would float upon the stratum of common air because filled with the lighter gas, but would remain at the bottom of the stratum of gas because kept down by the weight of the envelope inclosing it."

He says of the fire-damp indicator:—"A delicate instrument has been invented, constructed on the principle of the diffusion of gases; but as this would require the application and careful observation of anybody using it, and as all it shows can be equally ascertained by watching the elongation of the flame on the safety-lamp, I pass it by."

He next asks, "Can this gas be absorbed?" and gives an example of what he means by describing the strong affinity which quicklime has "for hydrogen in the form of water"; and lastly, he puts the question: "Supposing all these branches of inquiry to result unsatisfactorily, whether this gas should be loaded or neutralised in some manner that should render it non-explosive?"

We will pass over the incentives which our author brings forward with the view of stimulating men of science to undertake the work of discovery. That these incentives are strong enough in all conscience we who heard the dreadful sound of the explosion at the Naval Steam-Coal (Penygraig) Collieries as we lay awake shortly after midnight on Friday last can testify from experience. A few hours later we breathed the fatal after-damp in a sufficiently diluted form to produce only headache and nausea: we looked upon the blackened remains of the victims as they lay or knelt on the ground, some having been hurled from a distance and having nearly every bone in their bodies broken, others having their coats tightly drawn over their necks and mouths and their faces buried in the dust, and still others actually kneeling, having their knees drawn more or less closely up under them, their hands pressed on their mouths and their faces also in the dust. We saw nine fine horses that had been struck down where they stood in their stable never to rise again; one that had started off at a mad gallop, and been arrested in six yards by a fall of roof due to the blast which startled him, his legs and his whole body in an attitude of fierce action resting on the top of the fall, and his head laid gently on one side; two others lying on their backs with their legs in the air; another that had turned round in his shafts by some extraordinary convulsion, so that he faced the load he was drawing, while his body, with head erect, was twisted in between two props at the side of the road; and, lastly, a little donkey denuded of harness and tossed like a rag on to a heap of rubbish. We saw many of the bodies carried to the bottom of the shaft and sent to the surface, and others being carried from the pit to the homes where they lately dwelt; we heard the weeping of the bereaved ones; we saw one little knot of mourners from our very window, and since we began to write, as they gathered at the end of a row of houses, were joined by others bearing a coffin on their shoulders, and proceeded slowly down the road and out of sight, while the plaintive Welsh hymn that never fails to accompany such a procession rose and fell on the ear, and died away fitfully amongst the hills.

If any one can see and hear all this and more and remain unmoved, his natural affection is dead, and Mr. Plimsoll's appeal will be made to him in vain. Happily there are many whose hearts are wrung when they see or hear of the sufferings of their fellow-men, and who are always ready and willing to respond to such a cry.

We will now turn to the second part of Mr. Plimsoll's article, where we find his account of the manner in which he proposes to prevent "half, or it may happily prove even more than half, the number of explosions." He describes it in the following words:—"I do not propose to alter anything in existing arrangements in the suggestion I am about to offer, but only to supplement them. Let the present system of ventilation remain as it is in all its vigour, but in regard to the gas which escapes it, gets behind it, and accumulates in the upper and the waste portions of the pit, can we not go arm in arm with Nature in this matter, as we do in the others, and follow the gas whithersoever it goes and thus, in Lord Bacon's words, by obeying Nature learn how to conquer her?

"It goes to the highest part of the pit, therefore into the exhausted spaces. I would work with this tendency, and, as in the case of water, a large hole is dug called a 'sump,' to collect the water at the bottom of the pit and so facilitate its removal by the pumps, so I would make a hole or sump for the accommodation of the gas; but as the water is heavy and lies upon the floor, and has the sump for it made in the floor, so my hole or 'sump' to gather the gas should be in the roof of the mine, and that in the highest accessible places.

"If it were certain that the water will run into the hole or sump dug for it in the floor or the lowest part of the pit, then it is equally certain that the light carburetted hydrogen would rise in the 'sump' or hole dug for it in the highest part of the workings of the pit.

"I would then place a vertical tube with an open trumpet-shaped mouth, something like the funnel or chimney of a locomotive, in this place, and of such a length that the open mouth (which should be protected with a louvre covering or cap to keep out the dirt) should reach up very near to the roof; the bottom end of this pipe or tube I would continue to the bank of the pit; and as in the case of water you proceed to remove the accumulation by a water-pump, so in this case I would pump out the accumulation of light carburetted hydrogen by means of an air-pump; probably a small fan like that used in foundries would do as well, or even better.

"This air-pump or fan could easily be worked by a strap from the winding-engine, or by hand. It would require assistance during the daily drawing out of the pipe the atmospheric air which would fill it when the gas was exhausted from the mine. I ask your common sense, could you not as certainly in this way draw off every cubic foot of gas in the mine as you now can certainly remove the water from it?"

Mr. Plimsoll summarises in the following manner:—

"1. Is it not a fact that the light carburetted hydrogen does and will seek the highest place of refuge open to it in the pit? 2. Is it not a fact that at this moment there is scarcely a coal-mine which has not gas in its goaves and highest parts? And 3. Is it not clear that by thus tapping the highest places it can as surely be drawn off as water can be pumped out of a pit?"

It would be impossible to controvert all the statements that Mr. Plimsoll makes regarding the properties of fire-damp, its tendency to rise to the highest point, and so on; he has supplied himself with all the knowledge necessary to understand its behaviour when it is found in easily manageable quantities. But what are we to think of his proposal when we come to deal with such quantities as 1000 and 2000 cubic feet per minute? Two hours after the explosion at the Naval Steam-Coal (Penygraig) Colliery we estimated the amount of fire-damp coming up the upcast at 1100 cubic feet per minute, and this is doubtless the normal quantity when the colliery is at work. Dinas Colliery, which adjoins the last-named one, always produced about 1000 cubic feet per minute for some years before the explosion on January 13, 1879; Llwynypia Colliery, which adjoins the Naval Steam-Coal Colliery on the other side, produced 2000 cubic feet per minute for some years, but its output of coal is now less, and consequently its production of gas has decreased.

But where does this gas come from, and how is it disposed of? In following one of the subdivisions of the air-current from the point where it leaves the main intake air-current to the point where it returns to the main return air-current we observe the following phenomena. On reaching the first working place the air is still apparently as pure as it was when it left the surface; about the fifth or sixth place it begins to show the first symptoms of gas on the small flame of a glass safety-lamp (it is still invisible in a Davy lamp); at the tenth place the cap is quite apparent even to the unpractised eye; at the fifteenth place it is say $\frac{5}{16}$ of an inch in height, and at the twentieth place it is a $\frac{1}{4}$ of an inch. This is enough, and the current returns towards the upcast shaft without passing through any more places. At the point of its junction with the main return air-current its cap remains exactly the same as it was when it left the last face. We have ourselves verified these observations hundreds of times in different mines. The number of places through which the air must pass in order to obtain a given proportion of gas varies according to the rate at which gas is produced in the mine in question, and the volume of air passing along the faces.

In the most fiery mines we can generally follow the air-current from the surface, and return with it again to the surface after having passed along the working places without having seen the least accumulation of explosive gas. This is the rule; a cavity left by a fall of roof and containing explosive gas is the exception, and not only is no work allowed to be carried on near it, but means are taken to ventilate it as quickly as possible.

How then could Mr. Plimsoll's method be applied under these circumstances? Should we slacken the ventilation in order to give the gas time to rise to the roof, and after it got there to give it a chance of finding its way to a sump excavated for it somewhere or other? If so we should have streams of explosive gas travelling along the roof of the working places, and our dangers would be increased a thousandfold. We do not know what kind of mines those are in which Mr. Plimsoll has seen a stratum of explosive gas along the roof of the airways, but we should prefer not to have anything to do with them, even were his method applied for the purpose of drawing off the gas.

Let us take the explosion that has just occurred in the Rhondda Valley as an example. About ten months ago the two shafts, which are about 1111 yards apart, and over 400 yards deep, were connected together by an approximately straight heading, which is driven nearly level in coal from each shaft for say 520 yards, and descends the slope of a fault for 60 yards. The coal in one shaft is 30 yards below the level of that in the other shaft, and the surface of the ground at the top of the former shaft is 188 feet higher than at the latter. The fault forms a natural boundary between the workings of the two shafts, and, except for purposes of ventilation and communication, they were treated as distinct collieries. The workings are ranged on each side of the straight heading, there being four districts at the lower level (three on the right hand and one on the left, looking towards the higher shaft), and one district at the higher level (on the right hand side, looking in the same direction). The natural direction of the air-current is from the lower to the higher shaft. The natural air-current gives a volume of about 30,000 cubic feet of air per minute at the present moment, and we are informed that when the fan was at work the volume was between 60 and 80,000 cubic feet. The envelope of the fan was destroyed by the explosion, and the natural ventilation had to be depended on for the explorations so far as they have been carried.

Soon after midnight on the morning of Friday last there were somewhat over one hundred men and boys busily employed underground: five were at the bottom of the upper shaft, four at the bottom of the lower shaft; seventeen or so were on the straight heading about half-way between the fault and the upper shaft; twenty-four were in the left-hand workings of the lower shaft; several gangs of from three to six were in each of the other three small districts of the lower workings; fifteen or so were in the right-hand workings constituting the only district in the upper pit; some were cutting coal, others were blasting down roof, some were filling rubbish, others were *stowing* it into empty places, and here and there a horse and his driver were proceeding along the roadways with short trains of full or empty waggons.

No explosive accumulation of gas is said to have been found in the mine when it was examined a few hours previously, and two men, who came up only a few minutes before the explosion, had not heard of any unusual occurrence. The mine is a very dry one, and there is abundance of very fine coal-dust to be found everywhere on the roadways.

A sudden shock was felt; a veritable hurricane swept through every passage and every open space communicating with the air-ways; a "darkness that might be felt" ensued for an instant, then a gleam of brilliant light accompanied by a shower of molten and red-hot dust, then darkness again, and all was still.

During the interval between the raising of the dust and the passage of the flame some of the men, who evidently knew what had occurred, pulled their coats over their necks and mouths and staggered outwards, but fell after they had gone at most six or eight yards; others, as we have said, knelt down, covered their faces with their hands, and buried their mouths in the dust and small coal on the floor; the terrified horses made a few mad plunges, and then the Angel of Death breathed upon them all, and they remained transfixed in the positions they had assumed at that fatal moment. Only five men who were engaged in workings close to the downcast shaft escaped alive. They were rendered insensible by the after-damp, but recovered consciousness before the exploring parties reached them, having been revived by the fresh air which immediately flowed into the downcast shaft after the explosion was over.

We ask now where was the fire-damp accumulated that could produce so widespread an explosion, and at what part of the colliery would Mr. Plimsoll have placed his apparatus for the purpose of pumping it out?

The flame ramified into every district of workings both in the upper and lower pit, and left unmistakable tokens of its presence in the form of crusts of coked coal-dust on the timber, on the coal, and on some of the men's bodies.

It is evident that Mr. Plimsoll has remained unnecessarily ignorant that many men have been engaged in working out the problem he has attempted to solve. Let him go back to the many volumes of Parliamentary evi-

dence for information that will enable him to avoid all his useless work in trying to find means of "unmasking" or absorbing the gas; let him take up Faraday and Lyell's report on the Haswell Colliery explosion of 1844, and he will find his own proposal described in every essential detail, as well as a hint thrown out that coal-dust has much to do with explosions; let him peruse the copy of the report addressed to the United Committee of the Coal Trade by the Special Committee appointed to take into consideration Faraday and Lyell's report, and he will find the opinion expressed by the practical men of that day regarding the very plan he now brings forward as original.

But why should he labour through all that mass of reading and more than we have named, when he can find all that is of any value on the subject condensed in that most admirable dissertation, entitled "Rapport de M. Haton de la Goupillière (Ingenieur-en-chef des Mines, Professeur d'Exploitation des Mines à l'École des Mines), au nom de la Commission d'Étude des Moyens propre a prévenir les Explosions du grisou" (Paris: Dunod, Editeur, Quai des Augustins, No. 49, 1880). In that volume he will find an account of all his own plans and those of many others, as well as much valuable information that will prove of inestimable value to him if he should decide to pursue this subject to its legitimate conclusion, as we most earnestly hope he will.

Mr. Plimsoll wrongs the scientific and mining sections of the community when he charges them with so much indifference. In England, in France, and in Belgium there is at present a Government Commission considering the subject of his article, viz. "Explosions in Collieries and their Cure," and collecting evidence which will be of great value in enabling us to approach nearer to the mark we are all aiming at.

As usual the Royal Society travels in the van, and to our certain knowledge has given the sum of no less than 255*l.* within the last seven or eight years towards assisting in experiments which are being made with the view of throwing light upon the subject.

Similarly each of the Mining Institutes is eagerly canvassing every scrap of useful knowledge that may tend to lessen the risks of mining, and especially of explosions.

Lastly, in Germany we have also activity; and we can recommend a perusal of a pamphlet entitled "Die Verhüttung von Explosionen schlagender Wetter in Steinkohlenbergwerken," by Dr. Adolf Gurlt, Bergingenieur, Bonn: Verlag von Max Cohen und Sohn (Fr. Cohen), 1880. This pamphlet ends with the following words, in which it appeals to thoughtful miners. We would extend the same appeal to one and all:—

"So mögen denn alle denkenden Bergmänner ihre Kräfte vereinigen um dem verderblichen Feinde des Kohlenbergmannes, dem Grubengase, diesem Moloch, welcher noch fortwährend so viele frische Menschenleben verschlingt, in Zukunft seine Opfer nach Möglichkeit zu entreissen."

If really safe safety-lamps were introduced that could not under any circumstances ignite an explosive mixture of fire-damp and air; and if at the same time the use of an explosive or other agent that produced no flame were substituted for that of gunpowder or dynamite, we might be comparatively free from explosions.

Thus far however neither the one nor the other of these desirable consummations has been attained.

On the other hand, if we could entirely eliminate explosive accumulations of fire-damp and air from our mines we should expect, according to the most generally received opinions, to be able to use naked lights and to fire shots wherever we had a mind to do so. Naked lights we might use under these circumstances; but we should protest in the strongest terms against blasting in the presence of dry coal-dust alone. The *rôle* of that agent has not yet been officially recognised, at least to the extent of framing special regulations to assist in dealing with it; and until it is so recognised we venture to assert that explosions will continue, and that the same impossibility of explaining them, save by the assumption of simultaneous eruptions of fire-damp in different parts of the workings, will continue to be experienced.

That this is an illogical method of accounting for them may be gathered from the fact that the Risca explosion of July last required no less than three simultaneous eruptions to explain it. The Penygraig explosion would require one in each district; but we say this without prejudice to the evidence either direct or circumstantial that may yet be forthcoming to prove the existence of explosive accumulations in one or more places in the workings.

In conclusion we would say that the Penygraig explosion cannot be explained by the fire-damp hypothesis alone; explosive accumulations may have been accidentally ignited by a shot, or by a defective safety-lamp, and so have originated the explosion; but something else than fire-damp, something whose presence was entirely ignored, took up the flame, carried it to the innermost and to the most extreme limits of the workings, and was in all probability the cause of 90 per cent. or more of the deaths that ensued. Need we state our absolute conviction that that obscure agent was coal-dust?

W. GALLOWAY

COL. PRSHEVALSKYS' RECENT JOURNEY

THE new number of the *Izvestia* of the Russian Geographical Society contains the long-expected letters from Col. Prshevalsky on his adventurous journey on the frontier of Tibet. We have already referred to Col. Prshevalsky's work; the following further details will be of interest:—His last news were dated from Hami, whence he proposed to go south-east to Tsaïdam. But it was impossible to find a guide: a Chinese, given for this purpose by the Hami authorities, left the expedition some fifty miles from the town, after having led the travellers into a region full of great ravines. M. Prshevalsky, confident in his eleven companions, resolved to find his way himself by sending every day two men on horseback for distances of thirty and fifty miles round to discover the best direction. The advance was very slow, and the travellers spent one month and a half in the mountains south of Sa-djeou, discovering the high mountain-ranges to which they gave the names of Humboldt and Ritter. After a march of 190 miles they arrived at Kourlyk in the Tsaïdam, but here also they were badly received, and could not find guides, owing to the secret influence of the Chinese. Finally M. Prshevalsky told the chief of Kourlyk that he would take him as guide to Tibet if another guide could not be found, and on the following day the guide was found.

On September 24 the travellers left Tsaïdam. Again the guide led them into impracticable tracts near to the Blue River, so that M. Prshevalsky's expedition was compelled again to seek its own way. After having crossed the Blue River at its sources, they climbed the high plateau of Tan-la, after having crossed the 16,800 feet high pass across the border-range, which was covered with snow in October. On the passage they were attacked by the nomad tribe of Egrays, but the companions of M. Prshevalsky gave them a hot reception, and the Egrays fled, leaving four killed and several wounded.

Descending from the Tan-la ridge, the expedition continued its way to Lassa, but at the Nabchou settlement, 160 miles distant from the capital of the Dalaï-Lama, they were met by Tibetians, who declared that the expedition could not be allowed to go further without a permission from the Lassa authorities; a thousand soldiers were assembled at Nabchou. M. Prshevalsky gave his consent to await an answer from Lassa, and stayed at

Nabchou, buying food from the Tangoutes, who consider themselves as under the rule of the governor of Sining. Twently days later the answer arrived; a messenger from the Dalaï Lama, accompanied by seven officers, entreated M. Prshevalsky to return, saying that the whole population of Lassa was very excited against the strangers, as it was declared among the people that the expedition intended to steal the Dalaï-Lama himself and extirpate the Buddhist religion. A conflict with the inhabitants of Lassa being most probable, M. Prshevalsky was compelled to return. All December and January were spent on the road to Tsaïdam, the distance from Nabchou to Tsaïdam being 560 miles. Progress on this high plateau (14,000 to 16,000 feet) was very difficult; out of thirty-four camels twenty died, and the collections were conveyed on horseback; the men mostly went on foot. We need scarcely say that the scientific collections and observations are of a great value.

On March 20 M. Prshevalsky reached the Chinese town of Sining, close to Lake Koko-nor. After having received permission from the governor of the province to go to the Hoang-ho, however, without crossing it, M. Prshevalsky sent his collections to Alashan, and went east to the banks of the Yellow River, which are fifty-six miles distant from the town of Donkyr. He reached them at the Gomi settlement. The river, 450 feet wide, and 8000 feet above the sea-level, is rapid (5 feet in a second). Its valley cuts deeply into a great deposit of clay, gravel, and boulders, the abrupt walls of which, along the banks of the main river, being 1600 feet high, and no less than 1000 feet along the banks of numberless tributaries. The journey across these gigantic ravines with abrupt walls (quite like those of the loess in the lower parts of the Hoang-ho) was most difficult. After a journey of 130 miles up the Hoang-ho, M. Prshevalsky reached a lofty mountain-range, which is cut through by the river, and probably is a continuation of the Burkhan-buda range. Further advance along the banks was impossible, and M. Prshevalsky not having a guide for crossing the range was compelled to return and soon reached the town Gui-doni, situated on the left bank of the Hoang-ho, forty miles below Gomi. The natural history collections from the Upper Hoang-ho are very rich: 260 species of plants, many fishes, and 500 birds. The astronomical and barometrical observations are numerous. M. Prshevalsky did not reach the sources of the Yellow River, and he supposes that they cannot be reached otherwise than along the Tibetan plateau; he doubts however that the Upper Hoang-ho makes so great a bend as it is usually shown on our maps.

The last letter from M. Prshevalsky is dated Gui-ta-din, on the Upper Hoang-ho. As is known, he returned *viâ* Alashan, and is expected at St. Petersburg by the end of January.

MICHEL CHASLES

THE news of the death of Michel Chasles, perhaps the oldest and best-known mathematician in Europe, will be everywhere learned with deep regret. For the fifty-five years over which his writings extend he has devoted himself with persistent industry to the history of geometry and to the perfection of those geometrical methods with which his name will be always associated. The "Aperçu historique sur l'Origine et le Développement des Méthodes en Géométrie," which in fact forms an elaborate history of the subject from the time of Thales and Pythagoras to the beginning of the present century, is the best known of his works; it was first published in 1837, and a second edition appeared only a few years ago. His restoration of the Porisms of Euclid was published in 1860. The last great work of Chasles related to the investigation of the number of conics satisfying any five conditions: the special method which he invented for these researches, termed by him geometrical substitution, involved the consideration of the characteristics of systems of conics, *i.e.* of the numbers of conics satisfying four common conditions and (1) passing through an assumed point; (2) touching an assumed line.

In 1865 Chasles received the Copley medal of the Royal Society; this medal has, since its foundation in 1731, been given only five times for discoveries in pure mathematics, viz., in 1784 to Waring, in 1814 to Ivory, in 1841 to Sturm, in 1865 to Chasles, and in the present year to Sylvester.

In 1846 Chasles was appointed to fill the new Chair of Modern Geometry, founded by the Faculty of Sciences at Paris; and as a professor he exerted personal influence over the younger geometers of that time, which has since been apparent in their writings, although the effect of the geometrical methods to which he devoted his life is chiefly visible in the works of the Italian and German mathematicians. He was the inventor of the term "anharmonic ratio," but not of course of the ratio itself, which was known to the ancients. Chasles's memoirs on the attraction of ellipsoids are well known to English mathematicians and physicists; and a translation of his memoirs on Cones of the Second Order, and Spherical Conics, was published in Dublin in 1841 by Dr. Graves, now Bishop of Limerick.

Most of our readers will remember how in 1866 Chasles was deceived by M. Vrain Lucas by what were called the Pascal forgeries, and they will also remember how honourably he extricated himself from the matter, and did all in his power to repair the mischief done. The forger was convicted and sentenced to two years' imprisonment; and not a shadow of suspicion was ever thrown upon the honour or good faith of Chasles.

Scientific visitors to Paris will miss a well-known face at the Academy and a kind and hospitable friend. Till quite recently Chasles seemed as active as ever, both mentally and physically, and it was only last September that he issued a new edition of his "Géométrie supérieure." He was a Foreign Member of the Royal Society and of the Cambridge Philosophical Society.

THOMAS RYMER JONES, F.R.S.

THE late Professor of Comparative Anatomy at King's College, London, whose death is announced, was born about the year 1820. He studied for the medical profession at Guy's Hospital, and took the diploma of the Royal College of Surgeons, London, in 1833. A chronic deafness unfitting him for the active pursuit of his profession, he devoted his attention exclusively to comparative anatomy. Some of his earliest papers were on the dissections of a tiger (*Proc.* Zool. Soc. 1834) and of an agouti (*Proc.* Zool. Soc. 1834). He was the first Professor of Comparative Anatomy at King's College, and was Fullerian Professor of Physiology to the Royal Institution in 1840. He was Assistant-Secretary to the Section of Zoology and Botany during the eighth meeting of the British Association held at Newcastle-upon-Tyne in 1838, the president of the section being Sir W. Jardine, the secretaries J. Edward Gray, Richard Owen, and John Richardson. This meeting was marked by the presence of Christian Gottfried Ehrenberg, who laid before the section a copy of his famous work, "Ueber Infusionsthierchen," making at the same time a short statement as to his views of the alimentary canal of the polygastric infusoria. These views were, in the discussion which followed, criticised by Rymer Jones, who stood almost alone among the British naturalists in opposing them. In 1838 the first part of his "General Outline of the Animal Kingdom" was published by Mr. Van Voorst, happily still among us. It was completed in ten or twelve parts, and was illustrated

by really beautiful woodcuts. This work marked an era in the study of zoology and comparative anatomy in our country. True it is that the information of the author was mostly borrowed; true that he had no great familiarity with the work of the German naturalists of the time; true that the book will not bear to be appealed to now: but forty years ago it was the best book of its sort in England, and the generation has not as yet quite passed away which learnt from its pages. We have altered since then, both in the manner and the matter of our teaching of comparative anatomy, and for the better no doubt; but after another forty years our systems may too have seen their day. It may be conjectured that this book was in advance of its day, for an eminent writer, in reviewing it in 1839, objected to Rymer Jones' facts about the Infusoria, and declared he still placed confidence in Ehrenberg's observations, while he criticised his description of *Volvox globator*, and believed this "Infusorian" had nutritive organs, mouth, eyes, &c.

Prof. R. Jones was an extensive contributor to Todd's "Cyclopædia of Anatomy and Physiology," writing no less than twelve of the articles on comparative anatomy. He was the author of at least one work on popular natural history, called the "Aquarian Naturalist." He was an excellent lecturer, and though never rising to the highest rank as a biologist, well deserves this passing notice in our columns.

FRANK BUCKLAND

FRANCIS TREVELYAN BUCKLAND was born on Dec. 17, 1826. He was the eldest son of the Very Rev. Dr. Buckland, Dean of Westminster. As a boy he was a constant companion of his father in the latter's geological excursions; he was a scholar of Winchester College and a student of Christ Church, graduating M.A. of Oxford in 1848. About this date he entered St. George's Hospital as a student of medicine, taking the diploma of the Royal College of Surgeons, London, in 1851, becoming house surgeon to St. George's Hospital, and lastly receiving the appointment of assistant-surgeon to the 2nd Life Guards, a position he held until 1863. He seems to have been always well liked in his regiment, gaining the character of a pleasant, good-natured, sociable fellow. Although fond of all that pertained to natural science, he was in no sense of the word a profound naturalist; he could seize with alacrity the popular side of a scientific question, but he seldom went deeper. Perhaps the most scientific work he ever accomplished was the editing, in 1858, of his father's work on "Geology and Mineralogy," published as one of the Bridgewater treatises. He was the author of some pleasant volumes entitled "Curiosities of Natural History," was a constant writer in *Land and Water*, and an occasional contributor on subjects of economic zoology to the daily press. On the subjects of fish and fish-culture he was an authority, and it will be remembered that he had an interesting museum in connection with the subject at South Kensington. For his labours in this direction he received several honourable distinctions from France, and in 1869 he was appointed by the British Government one of the Inspectors of Salmon Fishing for England and Wales. He was also one of the Commissioners appointed to inquire into the Crab and Lobster Fisheries of this country, and the results of this Commission culminated in the useful Act regulating the oyster, crab, and lobster fisheries of the kingdom, which received the Royal assent in 1877.

One notable event of his life was the discovery he made in 1859 of John Hunter's coffin in the vaults of St. Martin's-in-the-Fields, which was re-interred at the expense of the Royal College of Surgeons in Westminster Abbey.

Familiarly known by a large circle of friends as Frank Buckland, he has left them while still in middl life, and it will be long ere they look upon the like of poor Frank again.

NEW GUINEA[1]

II.

THE various accounts of the natives given throughout these volumes leave an impression of vagueness that is very unsatisfactory. The mixture of races in various parts of New Guinea is no doubt great, but we cannot help thinking that there is a well-marked Papuan type, and that its head-quarters are in this great island. Signor D'Albertis seems to attach too much importance to minor peculiarities. He continually mentions small differences in the features, the hair, the form of the skull, or the stature, as implying a radical difference of race, forgetting that such differences are found among every people and in every country, and that on this principle we might establish a dozen different "races" in Europe. Taking the term Papuan in a broad sense as including all the dark-skinned woolly or crisp-haired tribes of the Western Pacific, it seems clear that New Guinea is very largely peopled by this race, and that its north-western peninsulas contain the most typical examples of it. In the south-east however another race is found which may be described as yellow-skinned and smooth-haired, and these are clearly Polynesians or "Mahori," that is of the same race as the natives of Samoa and New Zealand. In the Fly River and adjacent country both these occur, as well as a mixed race, which D'Albertis seems to think is destined to supplant them. He describes these races as follows:—

"The two varieties to which I allude may be defined thus: the yellow, and the black. The term yellow does not exactly express the first, nor does black the second, and those adjectives must be used comparatively only. The characteristics of the yellow variety are as follows:—hair curling or smooth—neither crisp nor woolly, black and shining, often almost of a chestnut hue; forehead large and flat; temples little, if at all depressed; eye orbits scarcely, if at all, prominent; cheek-bones rather high; round chin and round face; large brown eyes, with eyeballs of a bluish-white; the nose often aquiline, never flattened, and generally small; lips moderately full; and brachycephalous and round skull. These people are not prognathous. In colour they vary from brown to very light brownish yellow. In stature they are not generally inferior to the black race, and their forms are fuller and rounder.

"The black variety is distinguished by a narrow and retreating forehead, compressed temples, strongly-marked orbital arches, prominent cheek-bones, aquiline nose, pointed and narrow chin, long face, decidedly prognathous, an oblong skull. The eyes are small, either black or brown, the eyeball bloodshot or yellowish, and the men are tall and generally thin. The preponderating type exhibits every gradation that can result from these two varieties.

"We may therefore conclude that the present inhabitants of Hall Bay (opposite Yule Island) are a mixture of two races, one dark-skinned and crisp-haired, the other with lighter skin and smooth hair; and this is all that can be said from our present knowledge."

The light race—which we may call Papuan Mahoris—are far more civilised than the dark Papuans. D'Albertis says of them:—

"The most perfect harmony seems to reign in families, and rare indeed are cases of quarrel among members of one household. They live in communities, sometimes of more than a thousand inhabitants, in well-built villages,

[1] "New Guinea: What I Did and What I Saw." By L. M. D'Albertis, Officer of the Order of the Crown of Italy, &c., &c. In two volumes. (London: Sampson Low, Marston, Searle and Rivington, 188c.) Continued from p. 155.

worthy to be called small towns, both for their order and cleanliness. They are under the rule of the chiefs or land-owners. The chief is looked upon as father of the family. He is called Pacao, and his servant or subject is called Irine. From all I could learn, slavery does not exist, and the sale of human beings is unknown." After describing their daily avocations, amusements, dress, implements, and ornaments (a group of which are figured), he goes on: "Their natural disposition is gentle and placid. They like to spend their time in talking and games, in which men and women take an equal share. Playful and free of speech, they nevertheless do not transgress the bounds of modesty, either in word or deed. Women and children are included in every conversation, and often take part in public discussions, which are usually held in the evening. Women are always respected, and in some villages they enjoy a certain supremacy, although the government of the house belongs to the husband. Labour may be said to be fairly divided between the two sexes, and they are accustomed to work from their earliest childhood. . . . The material for civilisation is in them, but will the change make them better? Will they be the happier for

FIG. 4.—Durabi, a native of Kiwai Island, at the mouth of the Fly River.

it? This is a difficult problem, and one which cannot be solved until the experiment has been made. For my part I do not doubt that these, more readily than any other savages whom I know, would answer to the call of a civilised nation which, stretching out a paternal hand, would lead them towards our civilisation! To insure success, however, they should be treated as friends, not as slaves; they should be cherished, not destroyed."

Unfortunately our attempts at civilising savages have as yet in every case failed. Are we still, notwithstanding all our wretched failures, to go on in the old way, and allow these interesting and now happy people to be first ruined morally by the teaching of the dregs of our Australian and Pacific traders, and then physically deteriorated by the forced introduction of a form of civilisation utterly unsuited to them? Cannot either philanthropy, or religion, or Government protect these people from all such external influences as have been proved to be unsuited to their condition and stage of development, while aiding them to work out for themselves an indigenous civilisation? Here is perhaps the last chance we have to preserve one remnant of the better class of savages from being crushed under the Juggernaut car of our high-pressure civilisation and mad struggle for wealth.

The inhabitants of the lower part of the Fly River appear to be mostly dark Papuans, while further in the interior a mixed race was met with. Among the curious articles found in this part of the country were numbers of stone clubs, carved into various star-like shapes and forming terrific weapons in close combat. Stone axes are also largely used, closely resembling in form the neolithic celts of Europe.

Maino, chief of Moatta, a village at the mouth of the Fly, was a great friend of D'Albertis', and accompanied him on one of his voyages up the river. An elaborate study, both physical and mental, was made of this savage, and forms one of the best and most valuable passages in the book. A few extracts will show its character. After describing his person, our author goes on:—

"The above is a sketch of the animal Maino. I will now try to draw his portrait as a man, according to the moral sense of that definition. The opinion I have formed of him as a reasonable being is favourable. It is not however necessary to examine him very closely with European lenses, remembering that he is what we call a savage. He has sufficient intelligence for his position, and probably he is not capable of more. . . . He is friendly to the white man because he fears him, and because he knows he can gain by him. He is proud, and takes offence easily, without however showing that he is

FIG. 5.—Maino, Chief of Moatta.

irritated; only once during two months and a half did he display any anger. He is generally silent, and seems meditative. Sometimes he is lively and will laugh, but his laugh appears studied and forced, not natural or spontaneous. He is cruel rather from instinct than from education, and in a way that we Europeans can perhaps neither understand nor appreciate justly. His cruelty raises him in his own estimation and in that of his dependents—in the eyes of his friends and of his enemies. He considers men and women, if they are strangers to him, good for nothing but to have their heads cut off. Up to the present time his victims number thirty-three. A warrior who bravely attacked him, or a woman sleeping in the forest would be to him exactly the same thing. He would see in each a trophy, a victory; and what he would esteem would be their skulls. He likes to see blood, and it is with marked satisfaction he describes the *modus operandi* in cutting off a head, the instruments used in the operation, and the method of surprising an enemy by treachery, even if a woman or a child. . . . He is tender and affectionate towards his own family, and to his sons at least his temper may be said to be mild. . . . Maino is remarkably selfish. He would willingly let others die of hunger if to relieve them he would have to sacrifice some delicacy intended for himself. I experienced this during the voyage. . . . Notwithstanding certain traits which might make him appear a bad man in the eyes of Euro-

peans, I can testify that Maino is a good fellow, and was a good comrade to us all. His rank and his age prevented his being useful except as a pilot, but in that capacity he was most valuable."

Turning to the lighter race, one of the most interesting and novel facts we find recorded of them is their most ingenious mode of cultivation. Fields were observed in Yule Island so well and evenly tilled that they appeared as if they had been ploughed, but it was afterwards ascertained that all had been done by manual labour.

"The natives form gangs of eight or ten men, each man holding in either hand a very hard wooden pole, sharpened to a point, over six feet long and from an inch to an inch and a half thick. These men stand in a row, and at a given signal plant their rods in the ground, repeating the operation several times until they have penetrated to the required depth, which is generally about a foot. This done, they bear down on the other end of the poles, making them act as levers, and thus loosen a long piece of ground, ten to thirteen yards long, and from a foot to a foot and a half wide; then by alternate heaving up and bearing down, the large mass of earth is upturned, and as they take care to preserve the same measurements and distances, regularity like that of the action of a plough is produced."

On his way home, fresh from New Guinea, Signor D'Albertis suffered partial shipwreck in the Red Sea, and met a number of Somauli men and their families, and was much struck by their resemblance to Papuans. He says: "Who will believe that in these people I seemed to be renewing my acquaintance with the natives of New

FIG. 6.—Attacked by Canoes on the Fly River.

Guinea, especially those of Torres Straits! Such is the impression they made upon me. I observed the true negro type, which differs from them in several respects; but if several of these natives were transported to New Guinea they might be mistaken for aborigines of that country; those with the receding forehead, aquiline nose, and moderately thick lips—who have curly but not woolly hair. They belong to the type I called Arab when speaking of Moatta and Tawan—the type which, although not predominating, I have often found in New Guinea, and I discover them to-day on the shores of Ras Afun." Our traveller had two true Jamaica negroes with him in New Guinea, and these also closely resembled other types of Papuans, although there were certain minute characteristics of skin and hair by which they could be distinguished. Taken as a whole, and speaking broadly, the Papuan and African races would appear to belong to the same great type of mankind.

Our readers will now perceive that, as the journal of an enterprising and observant traveller, Signor D'Albertis' work is one of considerable merit. It is written in a simple unaffected style, and bears internal evidence of accuracy and absence of exaggeration, while it no less clearly shows that in all the best qualities of a traveller its writer has rarely been surpassed.

Living among some of the wildest of savages he overcame them by kindness, courage, and by exciting in them a dread of his vast powers of destruction and command over the forces of nature; and he never took away human life except when attacked by overwhelming forces—when the vessel committed to his charge as well as the lives of its crew were in imminent danger on the Fly River, and even then he beat back his enemies while doing them the smallest possible injury.

Turning now from the general character of the book and of its author, and considering it as an expensive and

somewhat pretentious work brought out by an English publisher, we feel bound to state that it is full of grave defects. This is due probably to the incompetence of the editor, or the total absence of any such necessary functionary; for the original was written in Italian, and we cannot believe that the author himself corrected or supervised the proofs. In the first place a considerable number of the illustrations seem to be thrown in at random, and are not referred to at all in the text. Such are the portraits at pp. 59, 140, and 151 in vol. i. Ornaments and implements from the Fly River are figured in the first instead of in the second volume. A cut of thirty-four separate articles (at vol. i. p. 416), though all numbered, has no reference to the numbers; while at vol. ii. p. 136, four elaborate spears or ornamental staves are described as "Baratus," which are said in the text to be "pieces of armour for war," and to be "worked in very hard stone"!



FIG. 7.—Imp'ements and Weapons. From the Fly River (upper set) and Hull Sound (lower set).

The misprints and misspellings are excessively numerous. At p. 4 we read of "temples excavated in the deserted roads" in Java. At p. 49 the traveller goes to the "source of the river" instead of to its mouth; and at p. 222 we have "stone nails" instead, probably, of stone clubs. The names of places and of plants and animals are rarely spelt correctly, and are often spelt differently in adjacent pages. The Italian mode of spelling scientific names has not been altered, and they are often almost unintelligible to an English reader, as *Oloturia* for *Holothuria*, *Stafilinus* for *Staphylinus*, and *Cicas* for *Cycas*. Orankaya (a village chief) is sometimes spelt Orankay and sometimes Oranhay. Waigiou is spelt Waigen, and immediately afterwards Waigeu. Battanta is spelt Battauta, and Daudai is spelt Dandai. At the end of the book four vocabularies of native languages are given, but as if to make these of as little use as possible, they consist of four different sets of words, all differently arranged, and none in alphabetical order; so that any comparison with each other or with vocabularies given elsewhere is practically impossible without the preliminary labour of rearranging them. Add to this that there is no index to the book and that the only map given is a poor and imperfect one, and it will be seen that the merits of Signor D'Albertis' work have not been enhanced by the manner in which it is presented to the reader.

The illustrations on the whole are good, the coloured plate of birds of paradise being excellent. But far too many skulls are figured, since these are of no possible interest to the general reader, while, as we have no guarantee for their accuracy, or that they are all figured on exactly the same scale, they will have little value for the man of science.

From the notices scattered through these volumes Signor D'Albertis appears to have made very large collections in natural history, especially of birds, reptiles, and insects. It is to be hoped that complete series of these have been kept together, and that, in conjunction with those collected by Dr. Beccari, they will be made the subject of some important works. The birds are being carefully elaborated by Prof. Salvadori; but the reptiles and the insects would probably throw even more light on the zoological relations and past history of this wonderful island.

ALFRED R. WALLACE

PHYSIOLOGY OF PLANTS

THE two papers[1] which we notice together under the above heading, though relating to different questions in the physiology of plants, have nevertheless something in common. Both of them bear on the relationship between the external and internal conditions of life, between external forces, such as light and gravitation, and the constitution of the organism on which these forces act. And both tend to show the importance of recognising in plants those specific forms of sensitiveness which may be said to determine the results which will follow external changes.

I. The behaviour of leaves in relation to light may be illustrated by the cotyledons of a seedling radish; if it is illuminated from above, the cotyledons are extended horizontally, and are thus at right angles to the direction of incident light. If the seedling is then placed at a window, so that it is lighted obliquely from above, and if the stem (hypocotyl) is prevented from bending, the cotyledons will accommodate themselves to the changed conditions by movements in a vertical plane. The cotyledon which points towards the light will sink, while the other will rise, and thus both will become once more at right angles to the incident light.

Two theories have been proposed to account for this

[1] I. "The Power possessed by Leaves of placing themselves at right angles to the direction of Incident Light." II. "The Theory of the Growth of Cuttings, illustrated by Observations on the Bramble, *Rubus fruticosus*." Read by Francis Darwin before the Linnean Society, December 16, 1880.

property of leaves: the first is that of Frank ("Die natürliche wagerechte Richtung von Pflanzentheilen," 1870), who ascribes to leaves and to some other organs a specific sensitiveness to light called "transversal-heliotropismus" or diaheliotropism ("Power of Movement in Plants," p. 438). Just as an ordinary heliotropic organ has an inherent tendency to become parallel to incident light, so a diaheliotropic organ has an inherent tendency to place itself at right angles to the direction of the light. The two classes of organs differ from each other exactly as some creeping rhizomes differ from ordinary stems; the rhizome tends to extend itself horizontally under ground, while the stem above the surface grows vertically upwards (see Elfving, in Sachs' "Arbeiten," 1879).

A different theory has been proposed by de Vries (Sachs' "Arbeiten," i. 1872), whose views are supported by Sachs ("Arbeiten," ii. 1879) with additions or modifications. According to these views it is not necessary to assume the existence of any special kind of heliotropism, since the phenomena might result from the ordinary forms of heliotropism and geotropism acting in concert. Thus in the case of the seedling radish illuminated from above, if the cotyledons were apheliotropic (negatively heliotropic) and apogeotropic (negatively geotropic) it is possible that they might be kept in equilibrium by these opposing tendencies. The tendency to move away from a vertical light will make the cotyledons curving downwards towards the earth, and the apogeotropism or tendency to move away from the centre of the earth may exactly balance the downward tendency, so that the cotyledons remain horizontal.

Besides the various geotropic and heliotropic tendencies there are other modes of growth which may enter into the combination. In some cases there is a natural preponderance of longitudinal tension or growth along the upper surfaces of the petiole, so that owing to impulses arising within the plant there is a tendency for the leaf to curve downwards, or more accurately in the direction in which the morphologically lower side of the petiole is directed; this tendency is called longitudinal epinasty, or simply epinasty; the opposite tendency is called hyponasty. According to the theories of de Vries and Sachs epinasty may be opposed by heliotropism, or by apogeotropism, while hyponasty will of course be opposed by apheliotropism and geotroprism, and all these opposing forces may combine in producing an equilibrium. The object of the present paper is to test the relative values of the two above described theories: that of Frank, and that of de Vries and Sachs.

The method employed was to fix the plants under observation to a horizontal spindle, which was kept in slow rotation by clockwork. This instrument (called the klinostat) has been employed by Sachs for the study of ordinary heliotropism; light is admitted parallel to the axis of rotation, and the plants are thus subjected to a constant lateral illumination, while they are freed from the disturbing influence of gravitation, for, owing to their being kept in constant slow rotation, there is no reason why they should bend apogeotropically in one direction more than another (see Sachs in his "Arbeiten," Bd. ii. 1879). On the same principle the behaviour of leaves which place themselves at right angles to the incident light has been studied. If a plant with horizontally-extended leaves, which has been illuminated from above, is fixed on a slowly-revolving, horizontal spindle, so that the axis of the plant is parallel both to the axis of rotation and to the direction of incident light, we shall have a means of testing the opposing theories above mentioned.

The plant's leaves will still be illuminated by light striking them at right angles; therefore if Frank's theory is the right one they ought to remain in this position. But if de Vries and Sachs are correct in their views, the leaves ought *not* to be able to remain at right angles to the incident-light, since apogeotropism has disappeared, which was one of the tendencies necessary to keep the leaves in a position of equilibrium.

A considerable number of experiments were made with the celandine, *Ranunculus ficaria*, the results of which are decidedly in favour of Frank's views. The leaves of the celandine are sometimes extremely epinastic, so that they press against the ground, and when a plant is dug up it often happens that, the leaves being released from the resistance of the soil, curve nearly vertically downwards. If such a plant is fixed on the klinostat in the position above described, the leaves will be pointing away from the light, so that if the leaves were apheliotropic, as might be expected according to de Vries' theory, the leaves would remain pointing away from the window. But this is not the case, they move forwards until they are approximately at right angles to the light, and then come to rest. Again, if a celandine is placed in the dark its leaves rise up so as to be highly inclined above the horizon, if the plant is then placed on the klinostat the leaves (which now of course point towards the light) again accommodate themselves by curving backwards until they are at right angles to the light. Thus the leaves cannot be called heliotropic or apheliotropic; we are forced to believe that under the stimulus of light they are able to move in either direction, which may be necessary to bring them into the plane at right angles to the light. The other experiments with *R. ficaria*, the details of which we omit, lead to the same general result.

Besides a few observations on Vicia, Cucurbita, and Plantago, a series of experiments were made on seedling-cherries, and these lead to a somewhat different result. A cherry-plant illuminated from above has its leaves approximately horizontal, and when placed on the klinostat, as above described, the leaves are unable to remain at right angles to the light, but curve backwards so as to become parallel to the stem of the plant. This movement can be shown to be due to epinasty, not to apheliotropism, and is the result of the loss of balance which follows when apogeotropism is removed. It is clear therefore that the horizontal position of the leaves of seedling-cherries growing normally must largely depend on the balance struck between epinasty and apogeotropism, in accordance with the views of de Vries and Sachs. But since these forces obviously cannot produce the power which the cherry possesses, of altering the position of its leaves in accordance with the direction of the light, we must assume that some kind of heliotropism enters into the combination. The view to which the present research lends most probability is that dia-heliotropism (transverse-heliotropism) is the really important influence at work. In the case of the celandine we have seen that the sensitiveness to light is strong enough to determine the position of the leaves—although the natural balance is disturbed by the annihilation of apogeotropism. It seems probable that an essentially similar state of things holds good in the case of the cherry. When the plant is growing normally it trusts to epinasty and apogeotropism to produce an approximate balance, the final result being determined by the stimulus of light. But when the balance is disturbed by placing the plant on the klinostat, the light-stimulus is not strong enough to produce a condition of equilibrium.

This view is the same as that given in "The Power of Movements in Plants," and is in accordance with the principle there given: that the chief movements in plants are due to modifications of the circumnutating motion.

II. When a cutting, for instance a piece of a willow-branch, is placed in circumstances favourable for growth, it produces roots at its lower end, while the buds at its upper end grow out into branches. The experiments of Vöchting ("Organbildung im Pflanzenreich," Bonn, 1878) on the growth of cuttings were made by suspending

pieces of stems, branches, &c., in large, darkened jars, the air in which was kept constantly moist by a lining of wet filter paper. The cuttings were suspended both in the normal position—that is with the upper end upwards—and also upside down. Vöchting found as a general result that there is a strong tendency for the roots to appear at the *basal* end,[1] and the branches to be developed at the *apical* end, whether the cutting had been hung apex upwards or downwards in the glass jar.

Vöchting believes that the growth of roots at the base and of branches at the apex of a cutting are determined chiefly by an innate, inherited, growth-tendency. When the knife divides a branch into two cuttings it separates a mass of identically-constituted cells into two sets, one which form part of the apex of the lower cutting, and another set which form part of the base of the upper cutting. And under appropriate circumstances one of these sets of cells might develop into roots, the other into adventitious buds. Vöcht holds that it is the morphological positions of these sets of cells (the fact of one being at the base and the other at the apex of a cutting) which chiefly determines the course of their subsequent development. The idea may be expressed somewhat familiarly by saying that each cutting into which a branch is divided is able to distinguish its base from its apex, and can tell where to produce roots and buds, by means of an internal impulse or morphological force which is independent[2] of the external forces, gravitation and light.

The theory which Sachs has brought forward in his paper on "Stoff und Form der Pflanzenorgane" ("Arbeiten des bot. Inst. Würzburg," 1880, p. 452) is entirely opposed to that of Vöchting. Sachs conceives that Vöchting's morphological force is not an innate hereditary impulse, but a tendency produced by the action of external forces during the growth of the formative cells. Thus Sachs believes that the force of gravity acting on the developing cells of an organ produces in it a "predisposition" or enduring impulse which manifests itself in the results which Vöchting ascribes to a hereditary force. The mode in which Sachs believes gravitation to act is interesting, not only in itself but also as a modification of a theory of Du Hamel's. It is assumed that difference of material is a necessary concomitant of difference of form, and that accordingly the materials from which roots are formed are chemically (used in a qualified sense) different from those which supply the branches. Sachs' theory supposes that the growth of roots or buds at a given place will be determined by the distribution of the root- and branch-forming materials, and that the distribution of these materials is regulated by the force of gravity. The root-material is in a certain sense geotropic and flows downwards, the branch-material having the opposite tendency. But they are not supposed to be *simply* geotropic, the tendency of the root-material to flow towards the base of a branch is continued after the branch has been made into a cutting and hung upside down, so that the root-material flows upwards towards the base of the cutting, because that end was originally downwards, and *vice versâ* with regard to the branch-forming matter.

The observations on the bramble, which form the subject of the present paper, were carried out with the object of deciding how far the natural growth of roots in the bramble agrees with Vöchting's or Sachs' theories on the growth of cuttings.

The long sterile shoots of the bramble are well known to possess the power of rooting at their ends. The terminal bud is thus protected during the winter, and the store of nutriment contained in the club-like thickened end of the branch forms a starting-point for new growth in the spring. It is commonly the long pendant branches growing vertically downwards which reach the ground and form roots. It might therefore be supposed that gravitation determines the growth of roots at the *lower* end of the branch, just as in a cutting made from an erect willow branch the roots grow at what was originally the lower end. But observations made on brambles under certain circumstances show that this is not the case. When brambles grow on a steep bank the majority of the branches grow down hill at once, or else straggle more or less horizontally along the bank and finally turn downwards. But a certain number of branches grow uphill, and some of these take root at the apex. When therefore we find on the same individual plant some branches forming roots at the physically lower, and others at the upper end, we may feel sure that the distribution of root growth in the bramble is not determined by gravitation. We mus believe that there is a morphologically directed impulse which tends to the production of roots at the apex of the branch, whether the direction of its growth has been upwards or downwards. It is true that in the observed cases the extreme end of the branches was bent so that from 1 to 9 inches was inclined at from 2° or 3° to 5° below the horizon, but it can hardly be imagined that this fact influences the growth of roots at the apex; and experiment shows that it is not necessary that even a single inch should be inclined below the horizon. A bramble branch was tied, apex upwards, to a vertical stick, and was surrounded by damp moss and covered with waterproof cloth; under these circumstances a plentiful crop of roots sprang from the terminal part of the branch. This result combined with the observations made with brambles growing on a steep bank seem to show that an internal impulse or morphological force regulates the growth of roots in the bramble.

When a cutting is made from a bramble the only development that takes place is the growth of the axillary buds at the apical end of the cutting. Under certain circumstances these side shoots take on a root-bearing function. They are stunted in growth, being, it may be, 10–12 mm. in length and 3 or 4 mm. or more in breadth; they assume a peculiar club-like form, being thicker at the apex than at the base, and are clothed with rudimentary scale-like leaves, from among which a number of relatively large roots spring forth.

In order to determine whether the production of this root-bearing type of root is determined by gravitation or by a "morphological force," cuttings were made from branches whose direction of growth was above the horizon. Such cuttings were hung apex upwards, and it was found that the most apical buds were capable of developing under these circumstances into the root-bearing type of branch. Similar rooting side-shoots are produced by cuttings made from branches which have grown beneath the horizon, it is therefore clear that gravitation is not the chief[1] determining force in this form of root production.

When the end of a branch is injured, which often occurs when a bramble grows along the ground near a pathway, the most apical bud or buds grow out into branches; these may be ordinary branches which ultimately take root. Under certain circumstances, the stunted club-shaped root-bearing side-shoots may be developed whose whole formation is devoted to the bearing of roots. It is therefore clear that the production of such rooting shoots in cuttings is the same process that occurs in branches injured in a state of nature; a process which enables the branch to perform the function, the normal performance of which had been interfered with. And this fact enables us to see in what way a

[1] The basal end is that end of a cutting nearest to the parent plant; the apical, is the opposite end.

[2] Vöchting states distinctly that gravitation and light do affect the positions in which organs are developed in cuttings, but he considers the internal impulse as the stronger determining cause.

[1] The experiments seem to show that gravitation has *some* influence on the growth of roots in the bramble.

morphological growth-impulse is better fitted for the requirements of the case than any possible dependence on gravitation as a guiding force. When the end of a branch is injured it is clear that if a side-shoot is to be developed to carry on the function of the injured apex, it will have the best chance of success if it starts from the position which the end of the original branch had already gained before it was injured. Therefore the bud which is nearest to the injured apex will be the most suitable one to be developed into a new branch. And thus it is advantageous to the plant that the place where the new development is to take place should be determined morphologically, not by gravitation.

Thus in the bramble the behaviour of cuttings is a repetition (cf. Vöchting, "Organbildung," p. 107) of the normal process of restoration of a deranged function in the plant; how far this is the case with other plants must remain at present undetermined.

NOTES

We are very glad to hear that Bedford College is taking a leading part in giving to women the opportunity of studying thoroughly physical science. It has this session opened a physical laboratory, under the able direction of Dr. Lodge. A chemical laboratory was added to the College some years ago, and has proved of great service to the students, several of whom have passed the science examination of the University of London.

The death is announced of M. Lécard, a promising French botanist, as the result of excessive fatigues during his late journey in Soudan. M. Lécard was formerly director of the Public Botanical Gardens at Saigon, in Cochin-China, and at Richard Toll in the colony of Senegal. During the past year he was intrusted by the French Minister of Public Instruction with the important mission of studying the flora of the Upper Niger, a question now of no slight interest in view of the probable construction of the Trans-Saharan Railway. Various difficulties prevented his reaching the Niger. At Kouridiam, however, the most distant point reached in his journey, where he was forced to pass the rainy season, he made the valuable discovery of five varieties of annual vines, the fruits of which so closely resemble our ordinary grapes that he regarded them as fully able to replace the grape in the production of raisins and wine. M. Lécard hoped also to find in his new discovery the means of satisfactorily combating the phylloxera, and inspired with this desire, sought to make extensive collections of the seeds of the vines to bring back to France. M. Lécard, in a letter recently read by Dumas before the French Academy of Sciences, expressed the fear of having lost his health by the privations incident to this journey—a prevision unfortunately too completely realised.

The death is reported of Dr. Wilhelm Heintz, Professor of Chemistry at Halle University, at the age of sixty-three years.

The death has taken place, on the 16th inst., at the age of ninety-one years, of Mdlle. de Montgolfier, daughter of Etienne de Montgolfier, the inventor of the balloon to which his name is attached.

Prof. Williamson, Graham's successor in the Chair of Chemistry at University College, London, has complied with the request of the committee of the Chemical Section of the Philosophical Society of Glasgow that he should act as adjudicator in the competition for the Graham Medal.

Prof. Tyndall, Prof. Haeckel, and Dr. Andrew Buchanan have been elected Honorary Members of the Philosophical Society of Glasgow.

Among the buildings which are to be erected on the new Observatory grounds in Paris when legally handed over to Admiral Mouchez will be the great dome for the large refracting telescope which is now building. This dome will measure twenty metres in diameter, and its weight will exceed sixty tons.

The credit of 300,000 francs asked by M. Cochéry for the forthcoming Exhibition of Electricity and Congress of Electricians at Paris has been voted by the Chamber of Deputies unanimously. The Bill has been sent to the Senate, which will probably have passed it by the time this number is published.

On December 12 took place at the Sorbonne the celebration of the fiftieth anniversary of the foundation of the Polytechnic Association for delivering scientific lectures all over France. This Society was established a few months after the Revolution of July, 1830, by a certain number of pupils of this celebrated school. The principal address was given by M. Gambetta, who praised science in magnificent style. M. Gambetta declared his conviction that Auguste Comte was the profoundest thinker of the whole century.

Frequent observations on the retrograde motion of glaciers have been made of late years. One of the most assiduous of observers is Herr W. Grömer, proprietor of the Hotel on the Schafberg. He reports that during September the retrograde motion was exceptionally large, larger indeed than he had ever seen during seventeen years. The Gosau glacier (Dachstein), the Hochalmspitze, and the Uebergossene Alp showed hardly any ice at all on September 12 last, so that with the telescope only *débris* of rocks could be seen. Herr Grömer ascribes this phenomenon to the unusually high temperature which reigned upon the Alps during last winter, as well as to the constant rain during the summer.

We are glad to receive a third edition of vol. i. of Harcourt and Madan's "Exercises in Practical Chemistry" (the Clarendon Press). Mr. Madan is the sole reviser of this edition, and we quote with approval the following passage from his preface:—"Practical chemistry seems in danger of being made far too much a study of a few reactions of salts, got up for the purpose of detecting them in the course of an analysis. This is of course due to the requirements of examiners, to satisfy which nearly all the very moderate time available for practical instruction in schools must at the present day be spent. Moreover analytical work (in the narrow, technical sense) entails, like Latin verses, less trouble to the teacher and less risk to the pupil than other kinds of practical work; while it undoubtedly affords, when intelligently used, a very excellent training in the application of logical methods. But it may well be doubted whether a more real and valuable advance in a scientific education is not made by the careful preparation and examination of the properties of such a substance as oxygen, or by an exact study of a few examples of oxidation and reduction, than by simply observing, for instance, that chlorides give a white precipitate with silver nitrate which is soluble in ammonia."

Mr. C. Schoesster, one of the Commissioners at the Melbourne Exhibition, we learn from the *Colonies and India*, has been visiting the Geelong vineyards, and reports that they are suffering from *Phylloxera* in the worst form, and ought to be totally destroyed.

Prof. Dewar will give the first of his Christmas Lectures (adapted to a juvenile audience) on Atoms, at the Royal Institution on Tuesday next, December 28, at three o'clock.

A botanical society for Northern Thuringia has been founded at Sondershausen by Prof. Leimbach. The new Society takes the title of "Irmischia," in memory of the celebrated botanist Irmisch, who died at Sondershausen last year. The immediate object of the Society, which has already a good

number of members, is the minute investigation of the Thuringian flora, and the making of botanical collections.

A GENERAL meeting of the Mineralogical Society of Great Britain and Ireland will be held at the Museum of Practical Geology, Jermyn Street, to-day, at 8 p.m. The following papers will be read:—"On Tyreeite," by Prof. M. F. Heddle, F.R.S.E.; "On Minerals New to Britain," by Prof. M. F. Heddle, F.R.S.E.; "Note on Gilbertite," by J. H. Collins, F.G.S.; "On Brochantite," by Wm. Semmons; "On a Remarkably Fine Crystal of Euclase," by M. Guyot; "On the Action of Organic Acids on Minerals," by Prof. H. C. Bolton, communicated by J. H. Collins; "On Strontium from Westphalia," by Joseph J. Acworth, F.C.S., communicated by F. W. Rudler, F.G.S.

UNDER the common name of "Guaco" many plants are known belonging to different natural families, which have a reputation for curing snake-bites. In a recent number of the *Pharmaceutical Journal* particular attention is drawn to one of these guaco-yielding plants, the *Mikania guaco*, a composite plant of South America. The paper referred to is the substance of a letter received at the Royal Gardens, Kew, from a correspondent at La Salada, New Grenada, in which the writer gives his personal testimony as to the value of the remedy, and says that it forms the basis of all the preparations of the snake-bite doctors of the district. Notwithstanding that there are several species of snakes in the country whose bite is considered mortal, some killing in a very few hours, it is asserted by the writer of the letter, who has resided in snake-infested regions for many years, that properly and promptly administered the guaco is a sure cure for the bite of the most venomous. An infusion or tincture of the leaves is used internally, and hot poultices of the bruised leaves and stem are applied externally.

THE Report on the Botanic Gardens, Georgetown, Demarara, for the half-year ending June 30 last has just been received. Its matter is mostly of local interest. We note however that Mr. Jenman, the superintendent, refers in one part of the Report to the rapid growth of some introduced plants. "This," he says, "is more particularly shown by the roses obtained from England. The hybrid perpetuals from average-sized nursery plants have in the three months which have elapsed since they were put out, grown into bushes from six to seven feet high, and the other hard-wooded things have hardly done less well; while herbaceous plants such as *Coleus, Alternanthera, Iresine, Amaranthus*, &c., appear to rush up to maturity in two or three weeks. Much of this luxuriance is due however to the very moist season experienced, as vegetation soon suffers and becomes stagnant with even a short period of drought in the stiff, tenacious soil of the coast land of the colony."

A PLANT recently introduced to Queensland by accident is reported to be giving some trouble in the colony in consequence of its poisonous effects upon cattle. The plant is *Xanthium strumarium*, and it is said to have been introduced along with cotton seed. From experiments made with the plant by administration of the extract to some animals it seems at first that no particular symptoms were apparent, but after a period of about half an hour the animal becomes torpid and unwilling to move about. "The torpidity gradually increases, and without notable struggling or excitement the breathing ceases, after which the heart's action becomes feeble and stops. In weaker doses recovery of the functions of life takes place, and the animal appears little the worse for the experiment. The animals poisoned retained their intelligence to the last. An extract prepared from the common Bathurst Burr, *Xanthium spinosum*, gave similar results, though the stubborn character of this plant does not offer a tempting food for cattle, and they are not therefore poisoned by it." Both species are found as casual weeds in this country, though they are not considered to be indigenous.

ON the 7th inst. the distinguished Vienna anatomist, Dr. Hyrtl, reached his seventieth birthday. He received numerous addresses from medical bodies in Austria, and congratulatory telegrams from all parts of the world.

IN Banjaluka (Bosnia) a distinct shock of earthquake was felt on the 6th inst. at 9.18 p.m., direction north-east to south-west, duration four seconds. In Agram, on the 11th, a violent shock was experienced about 5 a.m., and one less violent about 7.14 a.m. Since the 12th there have been no shocks there. The entire number of shocks at Agram during the earthquake period—November 9 to December 10—is (according to official data) fifty-nine. In Gurkfeld (Styria) shocks of brief duration were felt on the 11th inst. at 5 and 7.12 a.m., direction south-east to north-west.

A SLIGHT shock of earthquake was felt at Charleville, Ireland, on Saturday morning. It passed from the north-west to the south-east, and lasted for five seconds.

THE new "Year-book of Photography" contains a nice portrait of Daguerre, the father of photography, from a daguerrotype taken in 1846 by Mr. J. E. Mayall.

IN a moor of the Canton of Vaud (Switzerland) a well-preserved boat, dating from the age of pile-dwellings, has been found. It measures eleven metres in length and one metre in breadth, and has been conveyed to Lausanne.

THE ruins of a once magnificent bathing establishment have been recently discovered by Prof. Giuseppe Novi not far from Herculaneum. They are covered with a layer of ashes and lava of ten metres thickness. What has been brought to light up to the present is said to eclipse all previous discoveries of a similar nature both in Herculaneum and Pompeii. The fountains and tanks of these "Terme" are made of oriental granite and adorned with sculptures. The floors are of coloured glass mosaic; unfortunately it is but badly preserved. The walls of the various buildings are elegantly ornamented with paintings and stucco-work. The excavations are to be continued.

OUR ASTRONOMICAL COLUMN

SWIFT'S COMET.—The evidence in favour of a period of about 5½ years instead of about 11 years for this comet is apparently strengthened by an able note from Mr. S. C. Chandler, jun., which we find in an advance number of the Boston *Science Observer*. He brings the two periods to bear upon the representation of the observations of 1869. Starting with Prof. Bruhns' parabolic elements in *Ast. Nach.* No. 1788, he computed an ephemeris and compared therewith all the published observations, thirty-five in number, after taking into account parallax and aberration. The residuals were found to be considerable and systematic, and with the view to obtaining a nearer approximation to the orbit before proceeding with the determination of final elements, he formed three normals, using for the first all the observed places, six in number, from November 29 to December 1 inclusive; for the second all the places from December 8 to 10 inclusive, eleven in number; and for the third six observations between December 26 and 31: these observations were made at Hamburg, Königsberg, Kremsmunster, Leipsic, Manheim, and Vienna; he thus gets for the foundation of his subsequent work the following normal positions:—

Washington M.T.	App. R.A. h. m. s.	App. Decl. ° ′ ″
1869, November 29·82475 ...	23 1 5·20 ...	+ 15 51 57·7
December 8·81453 ...	0 3 37·28 ...	20 55 2·1
December 29·43628 ...	2 39 22·08 ...	+ 26 30 56·8

From these data Mr. Chandler calculates elements upon three different hypotheses: (1) that the orbit is a parabola; (2) that it is an ellipse with a period of 4006 days, or about 11 years (3) that it is an ellipse with a period of 2003 days, or about 5½

years, and he finds from these three orbits the following residual errors for the second normal place :—

	Longitude.	Latitude.
	″	″
Parabola	− 3·1	+ 25·7
11-year ellipse	− 0·6	+ 12·9
5½-year ellipse	− 0·3	+ 4·1

Mr. Chandler finds that an attempt to reduce these errors in latitude on the assumption of a parabolic orbit or an elliptic orbit of 11 years' period, will only lead to intolerable discordances in the longitudes, and he considers that for both these hypotheses the residuals are far in excess of the probable error of the normal position. For the shorter period, on the contrary, the residuals seem well within reasonable limits of error, and his conclusion therefore is that the comet will be found to revolve in about 5½ years. His ellipse with this assumed period is as follows, and will be found in close agreement with that obtained on a similar hypothesis from the observations of the present year, by MM. Schulhof and Bossert, which we gave last week :—

Perihelion passage, 1869, November 18·59702 Washington M.T.

Longitude of perihelion	° ′ ″ 42 58 53	M.Eq.
,, ascending node	296 46 2	1869·0
Inclination	5 23 44	
Excentricity	0·6581359	
Semi-axis major	3·10971	
Log. perihelion distance	0·0265728	

It appears that the comet was observed at Harvard College until January 3, 1870, or three days later than at any other observatory, and Prof. Pickering has had these late observations very carefully reduced.

At the actual appearance a communication from Mr. Lewis Boss, Director of the Dudley Observatory at Albany, N.Y., shows that the comet was micrometrically referred to a star, with the 13-inch refractor of that establishment, on the evening of October 11, but the declination of the comparison-star (B.D. + 17°·4611) needs further examination; it might be referred to Bessel's star 38s. following and about 6½′ north. If good observations can be obtained towards the end of the present month the elliptic orbit may admit of pretty close determination from the observations of 1880 alone. The following ephemeris is calculated from MM. Schulhof and Bossert's ellipse of 5½ years :—

At Greenwich midnight

	R.A	Decl. N.	Log. Δ.
	h. m. s.	° ′	
Dec. 23 ...	5 28 18 ...	35 3·4 ...	9·3514
24 ...	5 30 38 ...	34 28·9	
25 ...	5 32 51 ...	33 55·6 ...	9·3736
26 ...	5 34 58 ...	33 23·4	
27 ...	5 36 59 ...	32 52·5 ...	9·3957
28 ...	5 38 55 ...	32 22·6	
29 ...	5 40 47 ...	31 53·7 ...	9·4177
30 ...	5 42 35 ...	31 25·8	
31 ...	5 44 19 ...	30 58·9 ...	9·4828
Jan. 1 ...	5 45 59 ...	30 33·0	
2 ...	5 47 35 ...	30 8·0 ...	9·5041
3 ...	5 49 7 ...	29 44·1	
4 ...	5 50 34 ...	29 21·2 ...	9·5252
5 ...	5 51 56 ...	28 59·2	

A New Comet.—A small, pretty bright comet was discovered by Dr. Pechüle at Copenhagen on the evening of December 16, in R.A. 18h. 49m., Decl. + 10° 30′. Daily motion, + 5m. and + 40′.

Occultation (?) of 73 Piscium by Jupiter.—On February 3, 1881, according to Leverrier's Tables of the planet Jupiter and the position of the star 73 Piscium (rated 6·0m. in the *Durchmusterung*) brought up from the Greenwich Catalogue of 1872, the star should be occulted by the planet about 2h. 8m. G.M.T. Very small change however in the place or semi-diameter of the planet, might suffice to bring about merely an appulse. The facts of the case may be well ascertained in easterly longitudes, as at Madras, where the conjunction in Right Ascension appears to occur when the planet is 3h. 26m. past the meridian, about 7h. 29m. mean time. The apparent place of the star on February 3 is in R.A. 0h. 58m. 43·53s., Decl. + 5° 1′ 10″·2. The polar semi-diameter of the planet, according to the value of mean semi-diameter now adopted in the *Nautical Almanac*, will be 17″·2, and allowing for parallax, this seems to place the star a little over 2″ within the planet's northern limb.

METEOROLOGICAL NOTES

From an able and temperately-worded article in the New York *Nation* on the Signal-Service Succession, it is plain that meteorology is in a critical position in the United States at the present moment. The whole question of the future of meteorology in that country practically turns on the sort of man who is to be appointed to succeed the late lamented Gen. Myer. As regards the bearing of the question on the promotion of the great financial, commercial, and educational concerns of the country, the writer of the article well puts it when he states that "it depends altogether on the future management of the office whether its activity shall be confined to a lifeless routine without any attempt to make new discoveries or introduce improved methods, or whether it shall be animated by that progressive spirit which will not be satisfied until every man within reach can be informed of coming meteorological changes as long in advance as it is possible for them to be foreseen." To accomplish this end much more is needed than a most diligent discharge of the daily duties of the office, such as will put the public in possession of forecasts drawn up on the lines that have hitherto been followed in forecasting the weather. It was an essential feature of General Myer's procedure that in framing the forecasts in the office he confined himself simply to making the best use of what was already known of meteorology. But whilst this continued the practice of his office, he had the genius to see that if the system of forecasting weather is to make way it is absolutely indispensable to strike out entirely new lines of observation with the view of arriving at some positive knowledge of the great movements of the atmosphere and their determining causes. Hence his great scheme of International Meteorology, by which was secured one daily observation at the same physical instant, where possible, over the globe, and the regular publication of the monthly results in the U.S. Weather Maps, with which our readers are familiar. These admirable maps, together with the Weather Maps of the States themselves, published at intervals of eight hours through a period of ten years, now furnish a mass of material the value of which it is not possible to overestimate; and the adequate discussion of which, it may be very safely said, is the next great step to be taken by meteorology. This step it is in the power of the United States to take, and whether it be taken or not depends almost wholly on the character of the man who may be called to fill the place so suddenly left vacant by General Myer's premature decease. What, above all, is imperatively required, is a sympathy with science and workers in science, so strong and so decided that he will, without fail, enlist in the service of his country some of the best intellects who will give their time and their energies to work out the great problem of weather prognosis.

The American mails inform us that a frost of unusual severity for the season set in over Canada and the middle States on November 19. It came so suddenly and with such intensity that vessels of every description were frozen up and fixed, in many cases in mid-stream. The cold was greatest all along the St. Lawrence, where the thermometer ranged from zero to − 10°·0. Several ocean steamers, even, were placed in a very precarious position, and altogether it is estimated that 800 vessels laden with grain, potatoes, fruit, and other produce were frozen up; and many deaths have occurred in consequence of the frost. So early and intense a frost has not been experienced in Canada since 1873. Closely following it occurred a remarkable depression of temperature in the British Islands, which as regards certain districts in North Britain was unprecedented at so early a period in the winter months. It was an accompaniment of a wide-spread area of high pressure which appeared off the north-west of Scotland on the 20th as shown by the English and German daily weather maps. On this day temperatures fell low for the season, particularly along the west from Cornwall to Shetland. On the 21st the high-pressure area had advanced a considerable way towards the south-east, and under the clear skies and light winds which characterised it, the temperature fell in many places in Scotland to a degree which would have been noteworthy in the depth of winter. The protected thermometer fell at Aboyne Castle on Deeside to zero, and to 1°·0 at several places, viz., at Lanark in Clydesdale, at Stobo Castle near the head of the Tweed, and at Thirlestane Castle on the Leader. These low temperatures were approximated to at a considerable number of the other stations of the Scottish Meteorological Society situated in the larger valleys in in-

land situations. As on similar occasions, the influence of the sea in arresting the fall of temperature was strikingly seen. Thus the minimum temperatures on the 21st were 31°·7 at Portpatrick, 8°·3 at Drumlanrig Castle on the Nith, 1°·0 at Stobo Castle and Thirlestane Castle, 11°·7 at Milne Graden near Coldstream, and 17°·7 at Eyemouth on the East Coast. At Douglas Castle and Thirlestane Castle the unprotected thermometer fell to −6°·0.

MR. H. S. EATON has rendered a great service to meteorology by a paper on the average height of the barometer in London, which has just appeared in the *Journal* of the Meteorological Society for October. The great value of the paper consists not so much in the long period of 100 years for which the monthly averages of each year are given, as in this, combined with a careful and laborious elimination of instrumental errors and errors arising from breaks of one or more days in the observations of the months. The series is sufficiently extended as to entitle it to be considered one of the most valuable we possess in dealing with questions of secular meteorological variations. The mean atmospheric pressure at 32° and sea-level for London is 29·952 inches, the mean monthly maximum 29·996 inches occurring in June, and the minimum 29·900 inches in November, the mean for October being nearly as low, viz., 29·909 inches. In a discussion which followed the reading of the paper Mr. Strachan remarked that even another 100 years' observations would not alter the positions of these points of the London curve—a remark no doubt quite true for London. On advancing however to the south-west the means for June and July approach towards equality, and ultimately the July mean becomes the larger as we advance into the region of high pressure which occupies the Atlantic to the south-west during this month. On the other hand, as we proceed northward, the means for May and June approach towards equality till about the south of Scotland the mean for May becomes the maximum for the year, and the further north the more decidedly is May the maximum, till in Iceland it exceeds the mean of any other month by the tenth of an inch. Attention was drawn to the dips in the curve of pressure for April and July. These in all probability are permanent features in the London curve of pressure for March-April and July when drawn from a long average, since the former is connected with the east winds of spring and the latter with the great summer barometric depression which falls to the lowest point in July in the interior of the Europeo-Asiatic continent.

IN the same number Mr. Marriott gives a brief *résumé* of three years' observations made by Mr. F. E. Cobb at Stanley, in the Falkland Islands, which, from the geographical position of the place, possess some interest. The results show a mean annual pressure of 29·604 inches, the maximum occurring in winter, and the minimum in summer. A singular feature of the monthly means is their comparative steadiness from year to year, the highest being 29·819 inches for August 1876, and the lowest 29·342 inches for February of the same year. The difference of these two extremes is only 0·477 inch. It would be difficult to select from Mr. Eaton's 100 years mean pressures for London any consecutive three years which would show so small a variation between their two extreme monthly means as do these Falkland Islands' observations. The prominent features of pressure in those islands would appear to be its variability, the constant recurrence of rapid changes, and the comparative absence of protracted periods of very low, but especially very high pressures—occasioned in all likelihood by there being no great mass of land in that quarter of the globe. A like equableness from year to year characterises the temperature and rainfall of the climate. The rainfall is surprisingly small, amounting only to twenty inches in the year; but the falls, though not heavy, are frequent, there being 236 rainy days in the year. The lowest mean temperature of any of the thirty-six months was 35°·4, and the highest 52°·6. The climate is eminently a dripping one, and when the range of its temperature is taken into consideration, and its high winds, it is one of the most disagreeable climates of the globe.

GEOLOGICAL NOTES

NAINI TAL LANDSLIP.—In NATURE, vol. xxii. p. 505, attention was directed to landslips in connection with the catastrophe at Naini Tal on September 18. We have just received part 4 of vol. xiii. of the *Records* of the Geological Survey of India, containing a paper by Mr. R. D. Oldham, of the staff of that Survey, who was deputed to examine and report on the landslip to the Director. From this paper and a note appended to it by Mr. Medlicott, it appears that we were in error in supposing Naini Tal to stand upon Tertiary rocks. It lies just to the north of the younger formations, and is situated upon "more or less imperfectly-cleaved clay slates." These rocks are subject to a decomposition which penetrates deep into their mass, and it would seem to have been the cover of loose, decomposed detritus which, thoroughly saturated with water from the heavy rains, slid down the hill, and gave rise to the catastrophe.

THE "CHALLENGER" WORK.—Steady progress is being made in the investigation of the deep-sea deposits dredged up by the *Challenger* Expedition. M. Renard has established himself at Edinburgh, where, in concert with Mr. J. Murray, he is busily engaged in subjecting the various dredgings to chemical and microscopic analysis. In the first volume, devoted to an account of the bottom of the ocean, will be gathered together the facts amassed during this laborious study. It will avoid all speculation, but will contain such a body of data for the explication of the sedimentation and chemistry of the ocean abysses as has never before been available. In a subsequent volume the authors will develop the views to which their prolonged and minute investigations have led them. No part of the work of the *Challenger* promises to possess a profounder interest in geology.

GEOLOGICAL SURVEY OF BELGIUM.—The dual organisation for the Geological Map of Belgium is likely to lead to some curious reduplications and complications. Besides the staff under the direction of M. Dupont, there are other geologists independently at work under the Ministry of the Interior who are determined to lose no time in bringing out sheet after sheet of the geological map as surveyed by them. In particular the Baron O. Van Ertborn and M. Paul Cogels have been eminently energetic. The Baron made a convention with the Ministry towards the end of last year to complete six sheets with their explanatory texts before June 1 of the present year. He has been able to keep his engagement except as regards the Lubbeek sheet, for which he obtained a delay until the close of this year. We have just received the Boisschot and d'Aerschot sheets. Meanwhile M. Dupont makes no sign. Specimens of his map were seen at the Paris Exhibition in 1878, and also at the Dublin meeting of the British Association last year. But so far as we are aware, nothing has yet been issued. The Director is understood to be resolved to make his map the most perfect geological map that has ever been published. It is being chromolithographed at Leipzig. Considerable interest is naturally felt among geologists to see the first completed specimens of this long-expected work. We are curious also to know what will happen when the Official Survey and the free-lances meet on the same ground. Will the Government publish two different geological maps? The position reminds us of that which roused the activity of the Congress of the United States a few years ago, when it was discovered that the same Territory in the far West was sometimes independently surveyed by two or three different organisations, all paid out of the public purse. Only in Belgium things are worse, for the country is small, and the certainty of reduplication must have been foreseen from the beginning.

GEOGRAPHICAL NOTES

AT the meeting of the French Geographical Society on November 19, M. Henri Duveyrier read an important memorandum which he had drawn up on the subject of the sources of the Niger. After going carefully into the question of Major Laing's prior discovery and various matters relating to the hydrographic system of the Niger basin, he thinks it very doubtful if any other stream will ever be discovered having a right to be deemed the chief source of the river, than the Tembi-Kundu visited by MM. Zweifel and Moustier. M. Duveyrier's remarks will no doubt be published in an early number of the French Geographical Society's *Bulletin*, and it may be hoped that it will be illustrated by a large scale map. At the annual meeting of the Society last Friday, M. Maunoir read his usual report on the work of the Society and the progress of geographical knowledge. It was announced that the Society had now about 2100 members, being an increase of about 100 in the year.

HEFT 3 of vol. ii. of the *Mittheilungen* of the German African Society contains a brief report of the work of the year. The

most striking feature of the work is the successful journey of Dr. Lenz from Morocco to Timbuctoo and thence to St. Louis in Senegal. In the region to the south of the Congo some good work has been done. Dr. Buchner has probably got beyond the district known as the kingdom of Muata Yanvo, while Major von Mechow has reached the Coango from Malange by following down the valley of the Cambo, a tributary of that river. The navigation above the junction is obstructed by cataracts, but Major von Mechow did not expect to meet with any difficulty in sailing down the Coango to its mouth in the Congo. Dr. Pogge is on his way out to Portuguese West Africa to proceed to the interior to found a station at Mussumba, the chief town in Muata Yanvo's kingdom. Herr Flegel has been exploring the Niger in the *Henry Venn*, and expects shortly to reach Sokoto. Dr. J. Hann has a paper in this number on the meteorological and hypsometrical results of Rholfs' expedition to the Kufra Oasis. The Society have received instructions from the Imperial Government regarding the manner in which the 3750*l.* granted by the Reichstag is to be divided. Dr. Gerhard Rohlfs' expedition to Abyssinia will receive 1600*l.*, and 150*l.* is to form a reserve fund for this same undertaking. The expedition now being organised at Zanzibar under the leadership of Herr von Schöler will receive 800*l.*, and the remaining 1200*l.* are for Dr. Pogge, who is attempting to reach the capital of Muata Yanoo, in Central Africa, in order to found a station there. The Society has also granted 250*l.* to Herr R. E. Flegel, who ascended the Binuë River this year.

THE new number (No. 9 of vol. vii.) of the *Verhandlungen* of the Berlin Geographical Society contains papers by Herr Gustav Niederlein on some of the scientific results of an Argentine expedition to the Rio Negro in Patagonia, and by Dr. Nachtigal on the ethnological place of the Tubu and Kanuri.

THE December number of *Petermann's Mittheilungen* contains an interesting paper by Dr. Rholfs on the Libyan Desert, in which he shows that it is the eastern part of the Sahara, and not the western, that is the real desert, broken only here and there by oases. Indeed the extreme west of the Sahara, for a distance of from 400 to 500 kilometres from the coast, does not strictly belong to the desert at all; and even the eastern half, the more we know of it, the more numerous are its oases found to be. There is an eclectic article on the Liu-Kiu Islands, by Dr. v. Klöden; a paper on the New Volcano on Lake Ilopango; and a map of the South Coast of Franz Josef Land, based on Mr. Leigh Smith's recent discoveries. In the *Monatsbericht* some interesting details are given of Dr. Junker's journey to and his sojourn in the Niam-Niam country. A letter from Dr. Emin Bey, the Governor of the Egyptian Equatorial Province, informs us that Mtesa, King of Uganda, whom Mr. Stanley so whitewashed, is as tyrannical and bloodthirsty as ever, and does not intend to be either Christianised or Mohammedanised, but to adhere to the ways of his forefathers. Dr. Emin is anxious that explorers should turn their attention to the Equatorial Province, which forms a splendid field for botanists, zoologists, and other specialists.

NOTWITHSTANDING the belief in some quarters that the American Arctic steamer *Jeannette* has been lost with all hands, it is thought in San Francisco that Capt. De Long and his staff and crew may have only abandoned her, and be waiting succour at some point. An attempt is therefore being made to get a small schooner sent out next spring to search Wrangell Land.

EARLY in the present year Mr. W. H. Cornish, of the Surveyor-General's Department at Adelaide, was engaged for some two months in examining the country in the far interior for the extension of the trigonometrical survey and traverse of the Herbert River. In about lat. 30° 59′ near that river he crossed a piece of country which by his account almost baffles description; it was flood country of the Herbert, and was completely rotten. "Cracked ground," he reports, as a term is scarcely applicable, for there were yawning chasms from four to five feet deep, and even deeper, and eight to twelve inches wide at every few feet. The country indeed was so bad that it took the camels six hours to travel seven miles, and Mr. Cornish's difficulties were increased by the unusually intense heat of the weather. Mr. Cornish believes that before long the cattle-trade from the part of Queensland which he visited will go southwards to Australia as soon as the settlers who are beginning to open up the country on the Herbert, Diamantina, and Mulligan become sufficiently acquainted with the means of communication. During his journey Mr. Cornish did not see more than 300 natives, who were all friendly, but he believes there are large numbers in the region he travelled through, and that it would not be prudent to trust them.

DR. LAWS, the head of the Livingstonia station on Lake Nyassa, is actively engaged on linguistic work. He has translated various portions of the New Testament into Chinyanja, and the Laing trustees have agreed to publish his translation of St. Mark's Gospel. Dr. Laws has also begun the Yahitonga language spoken at Bandawi, and he has collected a short vocabulary of the Chungu dialect at the north end of the lake. The Livingstonia and Foreign Missions Committee of the Free Church of Scotland have recently agreed that, on the assurance that there will be no difficulty there as to civil government, owing to the presence of powerful chiefs, Bandawi shall be made the principal port of the mission on Lake Nyassa, while sanitary out-stations are to be sought on the neighbouring hills among the Angoni. As soon as possible however the east side of the lake is to be explored, in the hope of finding a better sanitarium on the so-called Livingstone Mountains.

MESSRS. GRIFFITH AND HUTLEY, who lately established the first mission station on the west side of Lake Tanganyika at Mtowa, near the mouth of the Lukuga Creek, have sent home to the London Missionary Society some information respecting the religious notions of the Waguha. There appears to be a marked difference on this point between the tribes on the opposite shores of the lake. Those on the east side have no images or idols, but on the west shore they have them in great numbers, and have certain beliefs connected with them. Mr. Griffith observes that the first thing which strikes the African traveller on entering the western half of the continent is an image at the entrance of every village, besides many others inside it. The image is in imitation of the human figure, and is called *Mkissi*, which is the same as the Mzimu of the Swahili, and means spirit.

THE new *Bulletin* of the Belgian Geographical Society contains reports relating to the International African Association's expeditions in East Africa, including tables of meteorological observations taken by M. Popelin. There is also a report on the "Conférence Géodésique Internationale de Munich," and an essay by Col. Verstraete on biological geography.

THE *Bulletin* of the Norman Geographical Society contains a paper by M. G. Gravier on M. Paul Soleillet's journey to Adrar between December, 1879, and May, 1880, as well as the continuation of M. Ch. Benner's journey from M'ruli to the capital of Unyoro.

THE Italian Expedition to the Antarctic Regions will not set out till 1882, but Lieut. Bove will shortly set out on board a whaling vessel to make a voyage of reconnaissance.

TWO Englishmen, with sixteen men belonging to an Indian convoy, are reported to have arrived at Yarkand from the direction of Tibet, whither they returned after visiting Kashgar.

M. RABOURDIN, who accompanied Col. Flatters on his survey for the proposed Trans-Saharan Railway, reports that he discovered numerous remains of cut flints, not less than eighteen manufactories being found in a length of 800 kilometres from Wargla. He also found remains of the great horned oxen which, according to Herodotus, were found in the country of the Garamantes.

DR. NACHTIGAL has furnished the *Tour du Monde* with a *résumé* of the concluding portion of the forthcoming volume of his "Reise in Afrika" in advance of publication, and it now appears in that periodical under the title of "Voyage du Bornou au Baguirmi," accompanied by a sketch-map and some very interesting illustrations.

WE hear that the Geographical Society of Marseilles have awarded their gold medal to Major Serpa Pinto for his journey across Africa.

ACCORDING to the *Echo du Japon* the King of Corea has been induced to make an offer of entering into treaties with foreign powers, through his fear of his kingdom being annexed by Russia, and he has despatched two envoys to open negotiations. Though the opening of Corea will hardly be of any great commercial importance, it will pave the way for interesting geographical researches in a country which is almost unknown, except from the imperfect accounts of Roman Catholic missionaries.

THE first volume of Löwenberg's "Geschichte der geographischen Entdeckungs- und Forschungsreisen," which treats

of voyages of discovery made during antiquity and the middle ages, as far as Magellan's first voyage round the globe, will be shortly published by Herr Spamer of Leipzig. It will contain some 100 illustrations, besides maps, charts, &c.

CRITICAL TEMPERATURE OF ETHYLENE

M. AMAGAT (*Compt. rend.*[1] [1879], lxxxix. p. 437, corrected *Beiblätter* [1880], iv. p. 19) has submitted hydrogen, oxygen, nitrogen, air, carbon monoxide, methane, and ethylene at temperatures from 18° to 22° to pressures ranging between 28 and 431 atmospheres, and finds that, except for hydrogen, the product pv first diminishes and then increases as p increases, the most marked case being that of ethylene, for which the values of pv at 31·58, 84·16, 398·71 atmospheres are proportional to 2·29, 1, 3·13 respectively. Dr. van der Waals deduced this general peculiarity theoretically in 1873, and showed that its markedness is the greater, the less the temperature of compression exceeds the critical temperature: concluding, therefore, that for ethylene the critical temperature is not far below 18°, as M. Amagat has also surmised, he has recently (*Meded. der k. Akad. van Wetenschappen in Amsterdam*, Mei 1880)[2] determined it directly by a Cailletet compression-apparatus, finding it to be 9°·2, and the critical pressure 58 atmospheres.

On p. 55 of his dissertation "Over de Continuiteit van den Gas- en Vloeistoftoestand" (Leiden, 1873), van der Waals finds the characteristic equation of a gas in the form—

$$\left(p + \frac{a}{v^2}\right)(v - b) = R(1 + \alpha t),$$

where a, b, R are constants and α the coefficient of expansion, and on p. 79 *et seq.* it is shown that at the critical temperature all three values of v given by this equation, which may be written

$$v^3 - \left\{ b + \frac{R(1 + \alpha t)}{p} \right\} v^2 + \frac{a}{p} v - \frac{ab}{p} = 0,$$

are equal: hence, if V is put for this common value of v, and T, P for the corresponding values of t, p, *i.e.* for the critical temperature and pressure, the theory of equations gives

$$3V = b + \frac{R(1 + \alpha T)}{P}, \quad 3V^2 = \frac{a}{P}, \quad V^3 = \frac{ab}{P},$$

whence

$$P = \frac{a}{27b^2}, \quad V = 3b, \quad PV = \frac{a}{9b}, \quad 1 + \alpha T = \frac{8a}{27bR},$$

and also

$$a = 3PV^2, \quad b = \tfrac{1}{3}V, \quad R = \tfrac{8}{3}\frac{PV}{1 + \alpha T}.$$

The minimum value of pv at any temperature t may be determined in the usual way by $\frac{d.pv}{dv}$ being equated to zero, and, if p', v' are written for the corresponding values of p, v, there result

$$v' = \frac{V}{3(1 - \tau)}, \quad p' = 27(1 - \tau)(2\tau - 1)P, \quad p'v' = 2(2\tau - 1)PV,$$

where

$$\tau^3 = \frac{bR(1 + \alpha t)}{a} = \tfrac{8}{27}\frac{1 + \alpha t}{1 + \alpha T}.$$

Thus a minimum value of pv exists only when

$$1 > \tau > \tfrac{1}{2},$$

i.e. only at temperatures that lie between

$$\frac{a}{bR\alpha} - \frac{1}{\alpha} \text{ and } \frac{a}{4bR\alpha} - \frac{1}{\alpha}.$$

If p_1 represents the pressure of the gas when occupying unit volume at t, then

$$(p_1 + a)(1 - b) = R(1 + \alpha t),$$

and, p_1 being the value of pv in this initial state, the markedness of the minimum value of pv is greater the less

$$\frac{p'v'}{p_1} \text{ or its equivalent } \frac{(1 - b)(2\tau - 1)}{\tau^2 - b(1 - b)},$$

that is, since the sign of the t-differential coefficient of this expression is the same as that of $(\tau - b)(1 - b - \tau)$, the less t, provided that

$$1 - b > \tau > b,$$

or that the temperatures lie between

$$\frac{a(1 - b)^2}{bR\alpha} - \frac{1}{\alpha} \text{ and } \frac{ab}{R\alpha} - \frac{1}{\alpha}.$$

If v represents the volume of the mass of gas which occupies unit volume at 0° under unit pressure, then

$$R = (1 + a)(1 - b),$$

as is taken in the following calculations.

In the case of ethylene van der Waals' experiments give $T = 9·2$ and $P = 58$: hence, by the above relations with $\alpha = 0·00367$,

$$\frac{a}{b(1 + a)(1 - b)} = 3·489, \quad \frac{a}{b^2} = 1566,$$

which lead to a cubic equation that gives

$$a = 0·00786, \quad b = 0·00224, \quad R = 1·0056,$$

so that the characteristic equation is

$$p = \frac{0·0037(272·5 + t)}{v - 0·00224} - \frac{0·00786}{v^2},$$

the pressure being reckoned in atmospheres; hence too $V = 0·0067$ and $PV = 0·39$. Further, when $t = 20$, the mean temperature in Amagat's experiments, $\tau = 0·5547$, and thus by calculation $p' = 76·25$, while Amagat's direct observations give $p' = 84$ approximately, so far justifying the the theory. The temperatures for which pv has a minimum value range from 678° to −35°.

The intimate agreement between Amagat's experiments and van der Waals' formula (which is entirely independent of them) is shown by the following table, wherein the first column contains the pressures (expressed in atmospheres) employed by Amagat, the second his experimental values of pv divided by 23500, and the third the values of pv calculated for $t = 20$ from the formula :—

p	pv observed.	pv calculated.
31·58	0·914	0·895
45·80	0·781	0·782
59·38	0·522*	0·624
72·86	0·416	0·387
84·16	0·399	0·392
94·53	0·413	0·414
110·47	0·454	0·456
133·26	0·520	0·520
176·01	0·643	0·642
233·58	0·807	0·805
282·21	0·941	0·940
329·14	1·067	1·067
398·71	1·248	1·254

The only serious discrepancy occurs for $p = 59·38$, and van der Waals accounts for this by supposing that in Amagat's table 12263 is misprinted for 15263, so that the asterisked number should be 0·650; for by experiment he finds that the ratio of the values of pv for $p = 45·80$ and $p = 59·38$ is 1·26 (the calculated ratio being 1·25), while Amagat's actual numbers give 1·50, but, when corrected, 1·20.

For methane the equation of van der Waals' form that best satisfies Amagat's experimental values has for constants $a = 10^6 \times 2·9$, $b = 53$, $R = 25525$, if $t = 20$, $\alpha = 0·00367$, pressures being measured in metres of mercury, and this gives $-99\frac{1}{2}°$ for the critical temperature and $50\frac{1}{2}$ atmospheres for the critical pressure. The constants have large values here, for, as calculation shows, the mass of the gas considered *is* about $24\frac{1}{2}$ grams, which would occupy, at 0° under one atmosphere, about 33518 c.c.

This discussion—with the numbers recalculated—by Dr. van der Waals of M. Amagat's experiments in connection with the critical temperature is here reproduced, together with the brief *résumé* of his theory (which has not hitherto appeared in an English dress), for ready application in other cases.

September 17 ROBERT E. BAYNES

[1] Since the following was written, M. Amagat has published further results, which do not however affect its main point.

[2] Mr. Dickson seems to have independently discovered (*Phil. Mag.* for July, 1880) the principles laid down by Dr. van der Waals in his above mentioned dissertation, pp. 79-93, which is not sufficiently known in England.

UNIVERSITY AND EDUCATIONAL INTELLIGENCE

CAMBRIDGE.—The Natural Science Tripos Class List has just been issued. There are eight names in the first class, eight in the second, and fifteen in the third. Of those in the first class three attain their first class for Physics and Chemistry, viz.: Fleming, St. John's (distinguished in Physics); S. L. Hart, St. John's, and Heycock, King's. Two attain their first class for

Botany: Hillhouse, Trinity, and Hoffmeister, Caius (distinguished); and three for Zoology, Anatomy, and Physiology: Caldwell, Caius; Pigeon, Christ's; and Shaw, Sidney.

Mr. J. A. Fleming, B.A., of St. John's, has been appointed to the new post of Demonstrator of Mechanism and Applied Mechanics; Mr. Fleming is a distinguished graduate of London University, as well as having attained distinction in Physics, with first class honours in the Natural Science Tripos of this year.

Mr. J. J. Lister, B.A., of St. John's College, has been appointed Demonstrator of Comparative Anatomy, in place of Mr. A. C. Haddon, who has been appointed to the Professorship of Zoology and Comparative Anatomy in the Royal College of Science, Dublin, vacated by Prof. Bridge.

Mr. A. H. Cooke, B.A., Fellow of King's College, has been appointed Curator of the Zoological Museum.

SCIENTIFIC SERIALS

Annalen der Physik und Chemie, No. 11.—Magnetic researches, by F. Auerbach.—New researches on magnetism, by C. Baur.—On so-called polar induction, by E. Riecke.—Determination of the absolute velocity of current electricity from Hall's phenomenon, by A. v. Ettingshausen.—Method of calibration of a wire for galvanic measurements, by W. Giese.—Action of gases and vapours on the optical properties of reflecting surfaces, by P. Glan.—On a new interference-photometer, by Fr. Fuchs.—Influence of the density of gases on their conduction of heat, by A. Winkelmann.—Currents of liquids resulting from unequal temperature within them, by A. Oberbeck.—Theory of the interference-phenomenon presented by dichroïtic crystal-plates cut at right angles to the axis, by E. Ketteler.—On the polarisation of diffracted light, by M. Rethy.—On changes produced in the spark and brush phenomena by coverings of the electrodes, by W. Holtz.—On atmospheric refraction of sound rays, by A. Kneser.—Double-acting mercury-pump without cock, by F. Neesen.—Alteration of Rüdorff's absorption-hydrometer, by the same.—Reply to a note by O. E. Meyer, by L. Boltzmann.—Remarks on U. Dühring's paper on the law of corresponding boiling temperatures, by A. Winkelmann.

SOCIETIES AND ACADEMIES

LONDON

Zoological Society, December 14.—Prof. W. H. Fowler, LL.D., F.R.S., president, in the chair.—Mr. Sclater exhibited and made remarks on a skin of a brown female of *Pauxis galeata*, formerly living in the aviary of the late Mr. G. Dawson Rowley, F.Z.S.—Dr. A. Günther, F.R.S., exhibited and made remarks on a skin of a new species of *Rhynchocyon* from Eastern Africa, discovered by Dr. Kirk.—Prof. T. H. Huxley, F.R.S., read a paper on the application of the laws of evolution to the arrangement of the Vertebrata, and more particularly of the Mammalia.—Lieut.-Col. H. H. Godwin-Austen, F.R.S., read a paper on the anatomy of *Ferussacia gronoviana*, Risso, from Mentone, pointing out its general relationship with *Lovea tornatellina*, Lowe, of Madeira, and with *Ferussacia follicula*, Gronov., from Algiers.—Mr. Arthur G. Butler read a paper on a second collection of Lepidoptera made in Formosa by Mr. H. E. Hobson. Thirty-three new species were found in this collection.—Mr. Oldfield Thomas, F.Z.S., read a paper containing the description of a new species of *Reithrodon*, obtained in Venezuela by the late Mr. D. Dyson, which was described as *Reithrodon alstoni*.—Dr. A. Günther read a paper containing notes on some rare reptiles and batrachians now or lately living in the Society's Gardens.

Physical Society, December 11.—Prof. W. G. Adams in the chair.—New Members: Mr. W. R. Brown, Mr. T. Mightson, C.E.—Lieut. L. Darwin read a paper on the rate of loss of light from phosphorescent substances. His experiments were made at Chatham on Balmain's luminous paint, by comparing the intensity of the phosphorescent light with the light of a sun-burner; the luminous surface being kept cool by placing ice and water near, as a slight increase of temperature in the surface considerably increases the quantity of light given off in a certain space of time. The supply of light was communicated to the paint from a mirror reflecting sunlight. A table and a curve exhibited to the meeting showed the rate of loss found by Lieut. Darwin. It is independent of the original intensity of of the illumination. According to the curve the light diminishes very nearly in proportion to the square of the intensity of the light. In a report on the use of Balmain's paint in mines, it had been stated that the phosphorescence became brighter a few minutes after exposure in the dark; but the curve showed this to be an error, due probably to the fact that the eye becomes more sensitive to light after being a few minutes in the dark. Mr. Pearsall emphasised the advantages of such a light in fiery mines. Prof. Guthrie inquired if the phosphorescent power grew weaker by time, and Lieut. Darwin instanced a specimen eighty years old to the contrary; but Dr. W. Crookes stated that these luminous substances give off sulphuretted hydrogen in damp air and deteriorate. If sealed in a vacuum they would not. Dr. Crookes remarked that in Balmain's patent it was stated that the phosphorescence died out sooner when exposed to a strong light for a short time than to a weak light for a longer time; but Lieut. Darwin thought this was explained by the slow decrease in the lower part of the curve when the phosphorescence became faint. Mr. R. J. Lecky mentioned that Evelyn in his Diary (1650) describes a phosphorescent powder as "bottling up" sunlight. Dr. Coffin inquired if short exposure to strong light was equivalent to long exposure to feeble light. Lieut. Darwin thought not.—Dr. C. R. Alder Wright read a full paper on the determination of chemical affinity in terms of electromotive force. He considered first the value of the B.A. unit of resistance, which from different experimenters might be taken as really 1·005 earth quadrants per second, or not more than half per cent. out. Clark's element when carefully prepared was practically correct at 1·457 volts, and it kept constant for three or four months after being made, but deteriorated thenceforth some 3 per cent. in about two years. The deterioration was assisted by air, which could not be well excluded by the paraffin cork, as it cracked. If sealed in a Sprengel vacuum the element lasted better. Joule's mechanical equivalent of heat (J) he estimated at 42×10^6, or not over 1 per cent. greater than Joule's water value. The chief result of Dr. Wright's researches was the conclusion that the action of a current in electrolysis is to decompose the electrolyte into "nascent" products which evolve heat in changing into ordinary products of electrolysis. These nascent products may be the ultimate atoms composing the molecules of the ordinary products, and the heat is given out in these atoms coming together to produce molecules, say of oxygen and hydrogen in the case of water. A number of deductions from this theorem are verified by experiment. One of these is that no gas battery can give a higher E.M.F. than 1·5 volts. A result, not before published, is that the E.M.F. of a Daniell cell is a function of the current and is a maximum when the current is indefinitely small. The variation may amount to 10 degrees. Therefore all methods of determining resistance by means of two currents of different strength are inaccurate. Dr. Wright's experiments also verified Faraday's law that conduction in an electrolyte is always accompanied by electrolysis. Prof. Adams inquired if Dr. Wright had seen the letter of Prof. Rowland's assistant to the effect that Dr. Wright's former estimate of the ohm was on the wrong side of unity. He had been too busy to see it. Prof. Foster thought that the variation of E.M.F. in a cell with the current was to be expected, and was probably due to the slowness of diffusion. Dr. Wright thought diffusion would account for it. Dr. Lodge said that there was no way of measuring the resistance of a cell except by employing two currents of different strength, and therefore it was necessary to know the law of variation of E.M.F. with current strength. Dr. Wright stated that he had found two methods of proceeding with currents of the same strength. With regard to the deduction of Dr. Wright that no current passes without producing electrolysis, Mr. Walenn inquired if the ordinary law of solution held when there was no evolution of hydrogen, and was answered in the affirmative.—Prof. Guthrie cited the experiments of Mr. C. V. Boys and himself on the conductivity of liquids as an instance of a current passing without electrolysis, or if there was decomposition it was followed by instant recomposition. Dr. Wright thought there must be electrolysis in Dr. Guthrie's experiments (which were conducted by rotating a glass vessel filled with the liquid between the poles of a magnet, after Arago's experiment), because some two parts of the rotating vessel would be at different potentials, and a current would be set up in the liquid.—The Society then adjourned till after Christmas.

PARIS

Academy of Sciences, December 13.—M. Edm. Becquerel in the chair.—The following papers were read:—Solid and

liquid products which continued issuing in April, 1880, from a crater of Dominica (English Antilles), by M. Daubrée. The lake of boiling water which filled the crater in January had shrunk to a boiling spring, the dark liquid from which joined a river. The weight of solid matter is nearly half the liquid, and mainly consists of silica and alumina; there is also iron oxide, with carbonate of lime, &c. Chloride of potassium abounds in the water.—Order of appearance of the spikelets in the ear of Lolium, by M. Trécul.—On the orbit described by a material point which is attracted by a spheroid, by M. Gyldén. —M. Abria was elected Correspondent in Physics in place of M. Lissajous.—Application of the theory of germs to parasitic champignons on plants, and especially to diseases of the vine, by M. Cornu. In some cases the diseased leaves may be variously utilised, after such treatment as will prevent the spores being disseminated when their time of vegetation comes. Other kinds of parasites do not allow of the leaves being used as food for cattle, compost, or litter. Their dormant spores are not killed by digestion or putrefaction of tissues; after prolonged burial they may produce new germs. The *débris* in that case should be burnt. Oidium and anthracnose exemplify the former; *peronospora* the latter.—On the discovery of the winter egg in the Eastern Pyrenees, by M. Campana. He found three in the end of September.—On a process of preparation of sulphide of carbon in the solid state for treatment of phylloxerised vines, by M. Lafaurie. He solidifies the sulphide by making an emulsion of it with a solution of algæ (Japanese moss does very well). The proportion of sulphide may be varied up to 80 per cent. It evaporates very slowly, so that vapours can be thus maintained a long time about the roots.—Swift's comet (*e* 1880), by MM. Schulhof and Bossert.—Influence of the slope of refringence on astronomical refraction, by M. Glasenapp. By this term he denotes the effect of atmospheric layers of equal density not being generally distributed in concentric surfaces on the earth's surface (as they are supposed to be in all theories of astronomical refraction). He proposes to investigate the influence of this phenomenon and its law of variation; to find whether it have an annual period, and if so, of what nature; to study the influence of this on the annual parallax of fixed stars and their aberration; also to study lateral refraction.—On the contact of conics and surfaces, by M. Darboux.—On a class of linear differential equations, by M. Appell.—On the integration of equations with partial derivatives of the first order, by M. Collet.—On linear differential equations of the second order, by M. Mittag-Leffler. —Reclamation of priority on the subject of the law of corresponding boiling temperatures, by M. Dühring.—On radiophony (second note), by M. Mercadier. The sounds may be got from oxyhydrogen lamps and gas lamps without concentrating lenses, if the lamps be brought very near the (glass) interrupting wheel, and the rays limited by a diaphragm with aperture. A copper disc (0·002 m. thick) was placed near the wheel, and heated on the side opposite to that of the wheel with an oxyhydrogen blowpipe. Sounds were heard when the disk still remained invisible in the dark (though louder when the disk was raised to a dark or bright red).—On new and economic methods of producing intermittent luminous signals, by M. Mercadier. Instead of using a diaphragm with a constant source of light, he varies the source; *e.g.* by introducing oxygen suddenly into a low flame. This is done by pressing a key, and so releasing from pressure a tube conveying the oxygen.—On the absorption-spectrum of ozone, by M. Chappuis. Eleven dark bands are observed in the visible spectrum, and several correspond with telluric bands of the solar spectrum.—Action of hydrochloric acid on metallic chlorides, by M. Ditte.—Action of hydrofluoric acid on bichromate of ammonia, by M. Varenne.—On chlorised derivatives of strychnine, by MM. Richet and Bouchardat. They have isolated three such compounds, retaining in different degrees the chemical properties of strychnine.—On the cause of spontaneous alteration of the raw sugar of cane, by M. Gayon. He gives reasons for thinking this process a true fermentation.—On the variations of luminous sensibility according to the extent of the retinal parts excited, by M. Charpentier. One region, seventeen to eighteen hundredths of a millimetre in diameter, and corresponding to the *fovea centralis*, requires a determinate quantity of light, independent of the extent of surface, to excite it. In other parts the minimum illumination is proportional to the surface.—Anatomic researches on *Onchidium*, Cuv. (*Oncidiella celtica*, Gray), by M. Joyeux Laffine. —Serpentines of Corsica; their age and origin, by M. Dieulafait. M. Hebert dissented from some of the results in this paper.

Vienna

Imperial Academy of Sciences, December 16.—Herr v. Burg in the chair.—Table of the most important relations of astronomy and geography, by Herr Letoschek.—Further researches on identity of the comets 1869 III. and 1880 *e*, by Herr Zelbr and Dr. Hepperger.—On leucæmia, by Herr Ludwig.—Fourth report of the Prehistoric Commission, containing (1) Szombathy on this year's prehistoric investigations and excavations at Kiritein and Mokrau in Moravia; (2) Luschau on several old burial-places in Bosnia and Dalmatia; (3) Heger on skeleton graves of Tlonic, grave-mounds at Tschemin (Bohemia) and at Wässering in Lower Austria, and tumuli at Mars in Hungary.—Theoretical researches on the displacements of the radiation-points of dissolved meteor-streams, by Herr v. Riessl.—Application of hyposulphate of soda to separation of copper from cadmium, by Herr Vortmann.—Some experiments on an earth-magnetic inductor, by Herr Stefan.

Berlin

Geographical Society, December 4.—Dr. Nachtigal in the chair.—It was stated *inter alia* that Herr Flegel, who is busy in the Niger region, had gone from Lukodja to the King of Nupe or Nife, seeking letters of introduction to the rulers of the Haussa States, so as to make a safe journey up the Niger, especially on the stretch between Tawa and Sai. He had a friendly reception, and wrote in good hopes (October 10). From Sai he means to go to Sokoto, the chief town of the Haussa States, and there to get letters for the ruler of Adamaua. A large collection of ethnological objects of the Niger region is looked for in Berlin.—Rumours of the death of Herr Hildebrandt in Madagascar prove false. A letter from him dated Krabé in Bessileo (Central Madagascar), September 2, 1880, states that he had made a journey, rich in results, from the West Coast to the Central Plateau; but his health broke down, when he was two hours' journey from the capital, to which however he was shortly brought by Herr Cousins and tended for a time in the Norwegian mission-house till able in July to visit the hot springs of Siralé (for health). He discovered in the moor at Siralé the skeleton of an extinct species of hippopotamus.—Dr. Kiepert gave details of Mr. Doughty's expeditions in Central Arabia, which have cleared up much of the physical geography of that region. —Dr. Holub spoke on the Maruthameich in southern interior Africa, north of the lower, and about the middle course of the Zambesi.

CONTENTS

	Page
The Fogs of London	165
What is Civilisation?	166
Austrian Myriopods	167
Our Book Shelf:—	
Schmeltz and Krause's "Die Ethnographisch-Anthropologische Abtheilung des Museum Godeffroy in Hamburg. Ein Beitrag zur Kunde der Südsee-Völker"	168
Roberts's "On the Digestive Ferments and on the Preparation and Use of Artificially-Digested Food"	169
Mrs. Sturge's "Niger and the Benueh"	169
Letters to the Editor:—	
Smokeless London.—W. Mattieu Williams; E. R. F.	169
Climates of Vancouver Island and Bournemouth.—Alfred R. Wallace	169
Geological Climates.—William Ingram	169
The Appulse of Jupiter to a Fixed Star on November 20.—John Birmingham	170
British Earthquakes.—Prof. J. P. O'Reilly	170
A General Theorem in Kinematics.—George M. Minchin	170
A Correction.—Prof. Franz Exner	170
Jelly Fish.—F. C. Constable	170
Mr. Plimsoll's Cure for Colliery Explosions. By W. Galloway	170
Col. Prshevalsky's Recent Journey	173
Michel Chasles	174
Thomas Rymer Jones, F.R.S.	174
Frank Buckland	175
New Guinea, II. By Alfred R. Wallace (*With Illustrations*)	175
Physiology of Plants. By Francis Darwin	178
Notes	181
Our Astronomical Column:—	
Swift's Comet	182
A New Comet	183
Occultation (?) of 73 Piscium by Jupiter	183
Meteorological Notes	183
Geological Notes:—	
Naini Tal Landslip	184
The *Challenger* Work	184
Geological Survey of Belgium	184
Geographical Notes	184
Critical Temperature of Ethylene. By Robert E. Baynes	186
University and Educational Intelligence	186
Scientific Serials	187
Societies and Academies	187

SUBSCRIPTIONS TO NATURE

Yearly . . . . . 28s.
Half-yearly . . . . . 14s. 6d.
Quarterly . . . . . 7s. 6d.

To the Colonies, United States, the Continent, and all places within the Postal Union :—

Yearly . . . . . 30s. 6d.
Half-yearly . . . . . 15s. 6d.
Quarterly . . . . . 8s.

Office: 29, Bedford Street, Strand.

DIARY OF SOCIETIES.

LONDON

THURSDAY, DECEMBER 23.

LONDON INSTITUTION, at 7.—A Story-telling: W. R. S. Ralston.

TUESDAY, DECEMBER 28.

ROYAL INSTITUTION, at 3.—Atoms: Prof. Dewar.
WEST LONDON SCIENTIFIC ASSOCIATION, at 8.

THURSDAY, DECEMBER 30.

ROYAL INSTITUTION, at 3.—Atoms: Prof. Dewar.
LONDON INSTITUTION, at 7.—The Study of the Beautiful: G. A. Storey.

SATURDAY, JANUARY 1.

ROYAL INSTITUTION, at 3.—Atoms: Prof. Dewar.

NOW READY,
SECOND EDITION,
GRIFFIN'S
CHEMICAL HANDICRAFT.
PRICE 4s. 7d. POST FREE.
A CATALOGUE OF CHEMICAL APPARATUS:
ILLUSTRATED, CLASSIFIED, DESCRIPTIVE.
Demy 8vo, 480 pp., Illustrated with 1,600 Woodcuts.
Most Complete and Cheapest List of Apparatus.
JOHN J. GRIFFIN AND SONS, 22, GARRICK STREET, LONDON, W.C.

R. W. NEEVES,
PHILOSOPHICAL INSTRUMENT
AND
INTENSITY COIL MAKER.
PRICE LIST, FOUR STAMPS.
55, SIDMOUTH STREET, LONDON, W.C.

In fcap. 8vo, price 3s. 6d.
SOUND: ELEMENTARY LESSONS ON.
By Dr. W. H. STONE, Lecturer on Physics at St. Thomas's Hospital. With numerous Illustrations.
"This is an excellent little text-book, well adapted for students of the Science and Art Classes, but also of considerable value to those who desire to do something more than cram. The student of acoustics will find it a very acceptable help, and a stepping-stone to the more elaborate works on the subject, while the musician will find in its pages information which may be of great assistance to him in the acquisition of his art."—*English Mechanic.*
MACMILLAN & CO., LONDON.

YORK'S
SERIES of SCIENTIFIC OPTICAL LANTERN SLIDES
Comprise over 2,000 of the following subjects:—Electricity, Magnetism, Sound, Telephone, Microphone, Electric Light, Light, Spectrum Analysis, Astronomy, Mines and Miners, Heat, Mechanics, Hydrostatics, Pneumatics, Human Physiology. Sample Slide and Catalogue sent on receipt of 2s.
F. YORK, OPTICAL LANTERN SLIDE MANUFACTURER,
87, Lancaster Road, Notting Hill, London, W.

HOLLOWAY'S PILLS THIS MEDICINE
Is a Certain Cure for all Disorders of the LIVER, STOMACH AND BOWELS. A Great PURIFIER of the BLOOD; a Powerful Invigorator of the System, in cases of WEAKNESS AND DEBILITY, and is unequalled in Female Complaints.

LIGHTNING CONDUCTORS.
Experience, accumulated since the time of Benjamin Franklin, proves conclusively that a Conductor made of Copper of adequate size is the best of all appliances for the protection of every description of building from the destructive effects of lightning.

NEWALL & CO.'S
PATENT COPPER LIGHTNING CONDUCTOR,
As applied to all kinds of Buildings and Shipping in all parts of the world with unvarying success; is the most Trustworthy, most Effective, and also the Cheapest Conductor ever offered to the public.
It is simple in its application, no insulators being required, and it costs only one shilling per foot for the standard size, which ensures safety in any storm.
R. S. NEWALL & CO., 130, STRAND, W.C.
36, WATERLOO ROAD, LIVERPOOL.
68, ANDERSTON QUAY, GLASGOW.
MANUFACTORY—GATESHEAD-ON-TYNE.

NOTICE OF REMOVAL.
JAMES HOW & CO.,
SCIENTIFIC INSTRUMENT MAKERS,
73, FARRINGDON ST., LONDON
(LATE OF 5, ST. BRIDE ST., AND 2, FOSTER LANE).
HOW'S STUDENT'S MICROSCOPE. HOW'S MICROSCOPE LAMP.
Rock Sections and other Objects for the Microscope.

S. C. TISLEY & Co.,
OPTICIANS,
172, BROMPTON ROAD, S.W.
(Close to South Kensington Museum).
THE PHONEIDOSCOPE
An Instrument for Observing the Colour-Figures of Liquid Films under the action of Sonorous Vibrations.
Being a visible demonstration of the Vibratory and Molecular Motion of a Telephone Plate.
The PHONEIDOSCOPE, with 3 Discs, Bottle of Solution, Descriptive Pamphlet, &c., in Cardboard Box, 10s. 6d.
MANUFACTURED AND SOLD WHOLESALE AND RETAIL BY
S. C. TISLEY & CO., 172, BROMPTON ROAD, LONDON, S.W.
TELEPHONIC ELECTRICITY. All Materials supplied for experimental purposes.
Price Lists of Electrical and Acoustic Apparatus, with Drawings and Description of the Harmonograph, Post Free, 2d.

DOLLOND,
1, Ludgate Hill, St. Paul's Churchyard.
ESTABLISHED 1750.
Manufacturer of Astronomical and Terrestrial
TELESCOPES.
THE "EDUCATIONAL" ASTRONOMICAL TELESCOPE,
With 3-inch clear aperture. Complete, £7 17s. 6d.
N.B.—These Telescopes have been introduced to meet the wants of those wishing to purchase Instruments of excellent quality optically, while the exterior is sound and good, without the cost of high finish.
The New Short-length Mercurial Barometer and Thermometer combined, price 15s., particulars of which will be sent post free on application.

ELECTRICAL AND SCIENTIFIC APPARATUS.
Wholesale Manufacturer of Metallic Base Electric Bells, Electric Reversing Indicators, and Constant Manganese Batteries, Telephone Switches and Transmitters, Induction Coils and Vacuum Tubes, Terminals, Carbons, Wire and all Materials. Instruments made, repaired, or altered on the premises.
Illustrated Bell List free. Complete Catalogue Two Stamps. Special Quotations to the Trade.
HENRY J. DALE, MANUFACTURING ELECTRICIAN and OPTICIAN,
4, Little Britain, London, E.C.

FRY'S COCOA
GOLD MEDAL, PARIS EXHIBITION.
In Packets and Tins. Pure Cocoa only, with the superfluous oil extracted.
"If properly prepared, there is no nicer or more wholesome preparation of cocoa."—*Food, Water, and Air, edited by Dr. Hassall.*
EXTRACT
J. S. FRY & SONS, Bristol and London.

WESLEY COLLEGE, SHEFFIELD.

(*Affiliated to the London University*, 1844.)

Governor and Chaplain, Rev. W. H. DALLINGER, F.R.S. Head Master, H. M. SHERA, Esq., M.A., LL.D.
Second Master, R. SHINDLER, Esq., M.A. (Lond.).
And Eighteen Assistant Masters and Professors.

The object aimed at in this Institution is a sound and comprehensive mental training. The course of study is fully adapted to the requirements of the present time and to the prospective wants of the pupils, who, whether in preparation for the Universities, training for scientific pursuits, or for professional or commercial life, are provided with the most efficient aids.

BIOLOGY, PHYSICS, and CHEMISTRY, the Modern Languages of Europe, Hebrew and Syriac, Vocal and Instrumental Music, and Drawing, are taught by accomplished Professors.

The Rev. W. H. DALLINGER, F.R.S., has undertaken the Professorship of NATURAL SCIENCE, and gives Weekly Lectures and Class Instruction in Practical Zoology, Botany, &c.

Physics and Chemistry are taught by A. H. ALLEN, Esq., F.C.S.

Scholarships are awarded, worth in the aggregate 300*l.* a year.

Prospectuses may be had by application to the GOVERNOR or HEAD MASTER.

W. LADD & CO.,

SCIENTIFIC INSTRUMENT MANUFACTURERS,

(*By Appointment to the Royal Institution of Great Britain*),

11 AND 12, BEAK STREET, REGENT STREET, W.

IMPROVED HOLTZ ELECTRICAL MACHINES. GRAMME'S MAGNETO-ELECTRIC MACHINE for Laboratory use.

PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3*s.* per oz.

Physical Apparatus of every Description.

ILLUSTRATED CATALOGUE, SIXPENCE.

PATERSON'S NEW CATALOGUE OF PHYSICAL APPARATUS.

LANTERN SLIDES for SCIENTIFIC LECTURES. Season 1880–1. Post free 6 Stamps.
Complete Sets of Physical Apparatus for Science Primers and all the Physical Text-books in use in Schools and Colleges.
Siemens and Gramme Dynamo Machines and Lamps for hire.
Schools supplied with Apparatus as per Science and Art Departments' Requirements in the Sections of Light, Heat, Sound, and Electricity.
Electric Signals for Houses, Hotels, &c., Colliery Signals, Lightning Conductors. The Gower-Bell Loud-speaking Telephone.

EDWARD PATERSON, Electrical Engineer.

SHOW ROOMS AND STEAM WORKS:—76, LITTLE BRITAIN, E.C. (late 3, Bedford Court, W.C.).

MOLISON'S HARMONOGRAPH: executes the Harmonic Curves in the most perfect manner. 15*s.* and 20*s.*

Illustrated Catalogue of Electrical Apparatus, Part 1, *post free*, 6 *Stamps. Ditto, Electric Signals, Part* 2, 6 *Stamps.*

A HANDBOOK OF DOUBLE STARS.

With a Catalogue of Twelve Hundred Double Stars, and extensive Lists of Measures. With additional Notes bringing the Measures up to 1879. For the use of Amateurs. By EDWARD CROSSLEY, F.R.A.S., JOSEPH GLEDHILL, F.R.A.S., and JAMES M. WILSON, M.A., F.R.A.S. With Illustrations. 8vo. 21*s.*

Just ready. 44 pages 8vo. 1*s.*

CORRECTIONS, TOGETHER WITH NOTES, CRITICISMS, RECENT MEASURES AND DISCOVERIES, &c., &c., TO THE HANDBOOK OF DOUBLE STARS.

THE BIBLIOGRAPHY HAS ALSO BEEN BROUGHT UP TO DATE.

"The volume is one which may be expected to find its way to the shelves of most amateurs and students of astronomy."—*Nature.*

"This is a truly delightful work, and one which will admirably supply a want. Into the hands of abler, more impartial and painstaking observers and compilers than the authors' its preparation could not have fallen."—*The Astronomical Register.*

"Will be welcomed by all who take an interest in the subject of double stars."—*Academy.*

"The names of the authors, noted authorities on the subject treated of, will lead the reader to open this volume with the feeling that in it he has a treasure of lore on the knowledge brought to light in the last hundred years respecting the relative motions of physically connected stars, nor will he be disappointed."—*Athenæum.*

"One of the most valuable additions to the library of the amateur astronomer that has been made for many years. It is full of information of perennial interest to the student and the practical observer, and assuredly ought to be upon the table of every single observatory in the United Kingdom, and of all those in other parts of the world where the language in which it is written is intelligible."—*The English Mechanic.*

"The book is well and clearly printed, and we heartily recommend it to our readers as a most valuable contribution to the literature of double-star astronomy."—*The Observatory.*

MACMILLAN AND CO., LONDON.

In Medium 8vo, price 18*s.* Vol. I.

A TREATISE ON

COMPARATIVE EMBRYOLOGY.

By F. M. BALFOUR, M.A., F.R.S., Fellow and Lecturer of Trinity College, Cambridge. In Two Vols. Illustrated.

"It is scarcely possible to exaggerate the expressions of gratitude which are due from zoologists to Mr. Balfour for the execution of the great task which some three or four years ago he set himself. . . . Zoologists have to be thankful to him for the admirable style in which he has carried out his work."—*Nature.*

MACMILLAN AND CO., LONDON.

Messrs. MACMILLAN & Co.'s PRIMERS.

UPWARDS OF **ONE MILLION** *OF THESE PRIMERS HAVE BEEN SOLD.*

SCIENCE PRIMERS.

UNDER THE JOINT EDITORSHIP OF

PROFESSORS HUXLEY, ROSCOE, AND BALFOUR STEWART.

In 18mo, cloth, with Illustrations, price 1*s.* each.

INTRODUCTORY PRIMER. By Professor HUXLEY, F.R.S.

CHEMISTRY. By H. E. ROSCOE, F.R.S., Professor of Chemistry, the Victoria University, the Owens College, Manchester. With Questions.

PHYSICS. By BALFOUR STEWART, F.R.S., Professor of Natural Philosophy, the Victoria University, the Owens College, Manchester. With Questions.

GEOLOGY. By ARCHIBALD GEIKIE, F.R.S., Professor of Geology, Edinburgh.

PHYSICAL GEOGRAPHY. By Prof. GEIKIE, F.R.S. With Questions.

PHYSIOLOGY. By MICHAEL FOSTER, M.D., F.R.S.

ASTRONOMY. By J. N. LOCKYER, F.R.S.

BOTANY. By SIR J. D. HOOKER, K.C.S.I., C.B., F.R.S.

LOGIC. By W. STANLEY JEVONS, LL.D., M.A., F.R.S.

POLITICAL ECONOMY. By W STANLEY JEVONS, M.A., LL.D., F.R.S.

*** *Others in preparation.*

HISTORY AND LITERATURE PRIMERS.

EDITED BY

JOHN RICHARD GREEN, M.A., LL.D.,

AUTHOR OF "A SHORT HISTORY OF THE ENGLISH PEOPLE."

In 18mo, cloth, price 1*s.* each.

HOMER. By the Right Hon. W. E. GLADSTONE, M.P.

ENGLISH GRAMMAR. By the Rev. R. MORRIS, LL.D.

ROME. By the Rev. M. CREIGHTON, M.A. With Maps.

GREECE. By C. A. FYFFE, M.A. With Maps.

ENGLISH LITERATURE. By STOPFORD BROOKE, M.A.

EUROPE. By E. A. FREEMAN, D.C.L., LL.D., M.A. With Maps.

GREEK ANTIQUITIES. By J. P. MAHAFFY, M.A. Illustrated.

ROMAN ANTIQUITIES. By Prof. A. S. WILKINS. Illustrated.

CLASSICAL GEOGRAPHY. By H. F. TOZER, M.A.

GEOGRAPHY. By GEORGE GROVE, D.C.L., F.R.G.S. With Maps.

CHILDREN'S TREASURY of LYRICAL POETRY. By F. T. PALGRAVE. In Two Parts, each, 1*s.*

SHAKSPERE. By Prof. DOWDEN.

PHILOLOGY. By J. PEILE, M.A.

GREEK LITERATURE. By Prof. JEBB, M.A., LL.D.

ENGLISH GRAMMAR EXERCISES. By R. MORRIS, LL.D., and H. C. BOWEN, M.A.

ENGLISH COMPOSITION. By Prof. NICHOL.

FRANCE. By CHARLOTTE M. YONGE. With Maps.

*** *Others in preparation.*

MACMILLAN & CO., BEDFORD STREET, STRAND, W.C.

Messrs. MACMILLAN & CO.'S PUBLICATIONS.

NEW BOOKS ON IRELAND.

NEW VIEWS ON IRELAND; or, Irish Land Grievances and Remedies. By CHARLES RUSSELL, Q.C., M.P. Crown 8vo. 2s. 6d.

THE LIFE'S WORK IN IRELAND OF A LANDLORD WHO TRIED TO DO HIS DUTY. By W. BENCE JONES of Lisselan. Crown 8vo. 6s.

THE IRISH LAND LAWS. By ALEXANDER G. RICHEY, Q.C., LL.D., Deputy Regius Professor of Feudal and English Law in the University of Dublin. Crown 8vo. 3s. 6d.

"To all who, either as legislators or publicists, are called on to take part in the present controversy, the book will prove invaluable."—*The Times.*
"This book cannot fail to do good."—*St. James's Gazette.*

LIFE OF WILLIAM BLAKE. With Selections from his Poems and other Writings. Illustrated from BLAKE's own Works. By ALEXANDER GILCHRIST. A New and Enlarged Edition, with Additional Letters and a Memoir of the Author. 2 vols., cloth elegant, gilt, with designs after BLAKE by FREDK. J. SHIELDS. Medium 8vo. 42s.

Several new Illustrations have been added to this work, which has long since taken its position as the standard authority on its subject. Among others the following may be mentioned:—The Phillips Portrait of Blake; two new Portraits by Blake of his Wife; a new Plate from the *Jerusalem;* a newly-discovered Design to *Hamlet;* and a Drawing of *Blake's Cottage at Felpham.* New Photogravures of the *Inventions to the Book of Job* are given. Some thirty additional Letters are included in the Biographical portion of the work, forming a new link to the already interesting life of Blake. Mr. W. M. Rossetti has revised, enlarged, and perfected the *Annotated Catalogue of Blake's Works* that appeared in the First Edition of the book.

"One of the most beautiful and interesting books of the season..... Thus Blake, more than Thoreau, and infinitely more than Rousseau, is a shining example of a man who chose and secured a simple and sufficient measure of happiness. There is no higher philosophy."—*Daily News.*

THE ABBOTT'S FARM; or, Practice with Science. By HENRY TANNER, M.R.A.C., F.C.S., Professor of the Principles of Agriculture in the Royal Agricultural College, Author of "First Principles of Agriculture." Extra feap. 3s. 6d.

ISLAND LIFE; or, the Phenomena and Causes of Insular Faunas and Floras, including a revision and attempted solution of the Problem of Geological Climates. By ALFRED RUSSEL WALLACE, Author of "The Malay Archipelago," "The Geographical Distribution of Animals," &c. Medium 8vo, with Illustrations and Maps. 18s.

"The work throughout abounds with interest."—*Athenæum.*
"He takes his subject matter from all the sciences, and he builds it into a new harmonious whole."—*Fortnightly Review.*

GILBERT WHITE'S NATURAL HISTORY AND ANTIQUITIES OF SELBORNE. New Edition, with a Poem and Letters never before published. Edited, with Notes and Memoir, by FRANK BUCKLAND; a chapter on Antiquities by Lord SELBORNE; and the Garden Kalendar. With Illustrations by Prof. DELAMOTTE. Cheap Edition. Crown 8vo. 6s.

PHYSICS OF THE EARTH'S CRUST. By Rev. O. FISHER, M.A., F.G.S., Rector of Harlton, &c. 8vo. [*Shortly.*

STUDIES IN DEDUCTIVE LOGIC. By W. STANLEY JEVONS, LL.D., M.A., F.R.S. Crown 8vo. 6s.

"It is indispensable to the many students of the higher logic."—*Athenæum.*

GUIDE TO THE STUDY OF POLITICAL ECONOMY. By Dr. LUIGI COSSA, Professor of Political Economy in the University of Pavia. Translated from the Second Italian Edition. With a Preface by W. STANLEY JEVONS, F.R.S. Crown 8vo. 4s. 6d.

"It would be impossible to find a more compact and better-written sketch of the history of Political Economy and its latest developments. . . It is an admirable compendium, and will, we hope, be widely circulated, as it will prove to many for the first time that the study of political economy is even more actively pursued on the Continent, than in England."—*Notes and Queries.*

THE WHITE RAT, AND SOME OTHER STORIES. By LADY BARKER. Illustrated by W. J. HENNESSY. Globe 8vo. 4s. 6d.

"A pleasant little volume. It is pretty outside, and pleasant in."—*Morning Post.*

GOLDEN TREASURY SERIES.—NEW VOLUME.

ESSAYS OF JOSEPH ADDISON. Chosen and Edited by JOHN RICHARD GREEN, M.A., LL.D. 18mo. 4s. 6d.

DICTIONARY OF MUSIC AND MUSICIANS (A.D. 1450—1878). By eminent Writers, English and Foreign. Edited by GEORGE GROVE, D.C.L. Three Vols., 8vo, with Illustrations and Woodcuts. Parts I. to XII. each 3s. 6d. Vols. I. and II. 8vo, cloth, each 21s.

Vol. I. A to Impromptu. Vol. II. Improperia to Plain Song.

"This work promises to be for music what the best encyclopædias are to general literature and science."—*Guardian.*

ENGLISH POETS: Selections, with Critical Introductions by various Writers, and a General Introduction by MATTHEW ARNOLD. Edited by T. H. WARD, M.A. 4 vols. crown 8vo, each 7s. 6d.

Vol. I. CHAUCER to DONNE.
Vol. II. BEN JONSON to DRYDEN.
Vol. III. ADDISON to BLAKE.
Vol. IV. WORDSWORTH to SYDNEY DOBELL.

"An excellent design admirably executed."—*Pall Mall Gazette.*

ENGLISH MEN OF LETTERS. Edited by JOHN MORLEY. Crown 8vo. 2s. 6d. (New Volume)

WORDSWORTH. By F. W. H. MYERS.

THE YEAR'S ART: A Concise Epitome of all matters relating to the Arts of PAINTING, SCULPTURE, and ARCHITECTURE, which have occurred during the Year, together with information respecting the events of the Year 1881. Compiled by MARCUS B. HUISH, Crown 8vo. 2s. 6d.

THE NECKLACE OF PRINCESS FIORIMONDE; and other Stories. By MARY DE MORGAN. With Twenty-five Illustrations by WALTER CRANE. Fcap. 8vo. 6s.
Also an Edition of One Hundred Copies on large paper.

"The stories display considerable originality, and Mr. Crane's characteristic illustrations combine with Miss de Morgan's pretty fancies to form a charming gift-book."—*Graphic.*
"A real gem."—*Punch.*

A CHRISTMAS CHILD: a Sketch of a Boy-life. By MRS. MOLESWORTH, Author of "Carrots," "The Cuckoo Clock," &c. Illustrated by WALTER CRANE. Globe 8vo 4s. 6d.

"A very sweet and tenderly drawn sketch with life and reality manifest throughout. Very few can rival Mrs. Molesworth in the power of making us see the children of fancy, and in this 'Christmas Child' something has given to her pen a special power."—*Pall Mall Gazette.*

PANSIE'S FLOUR BIN. By the Author of "When I was a Little Girl," &c. Illustrated by ADRIAN STOKES. Globe 8vo. 4s. 6d.

"Worthy to be classed with 'Alice in Wonderland,' and in some respects is better adapted to juvenile comprehension."—*Morning Post.*

*** *Messrs. MACMILLAN & Co.'s Illustrated Catalogue of Gift and Presentation Books is now ready, and may be obtained on application.*

MACMILLAN & CO., BEDFORD STREET, STRAND, W.C.

Printed by R. CLAY, SONS, AND TAYLOR, at 7 and 8, Bread Street Hill, Queen Victoria Street, in the City of London, and published by MACMILLAN AND CO., at the Office, 29 and 30, Bedford Street, Covent Garden.—THURSDAY, December 23, 1880.

NATURE

A WEEKLY ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
Of Nature trusts the mind which builds for aye."—WORDSWORTH

No. 583, Vol. 23] THURSDAY, DECEMBER 30, 1880 [Price Sixpence

Registered as a Newspaper at the General Post Office.]

[All Rights are Reserved.

UNIVERSITY OF LONDON.

PRELIMINARY SCIENTIFIC AND 1ST M.B. EXAMINATIONS. Special Classes in all the Subjects required for these Examinations will commence at St. Thomas's Hospital Medical School early in JANUARY. Full particulars may be obtained from the Secretary, Dr. GILLESPIE.

OWENS COLLEGE, MANCHESTER.

The LENT TERM begins on TUESDAY, January 11. New Students will be admitted on Monday, the 10th, from 11 a.m. to 4 p.m. Candidates must not be under 14 years of age, and those under 16 will be required to present themselves on Tuesday, the 11th, at 10.30 a.m., for examination in English, Arithmetic, and the elements of Latin.

The Courses of Study are adapted to the requirements of Candidates for the Arts and Science Degrees of the University of London.

The Junior Classical Classes will commence after Christmas to read the books set for Matriculation in June, 1881

J. HOLME NICHOLSON, Registrar.

SAINT PAUL'S SCHOOLS.—About 12 Scholarships will be awarded next Term.—For information, address CLERK TO GOVERNORS, Mercers' Hall, E.C.

CHEMICAL & PHYSICAL RESEARCH.

—A Gentleman or Youth, desirous of pursuing it, may communicate with X., care of H. M Chichester, 97, Belgrave Road, S.W.

INSTRUCTION IN MATHEMATICS.—Youths or Adults attended at their Residence, on Reasonable Terms, by a M.A. of Cambridge. Unquestionable references if required.—Address, by letter, O. P., Post Office, Turnham Green.

MAGIC LANTERNS AND DISSOLVING VIEWS.

The Cheapest and best House in London for Phantasmagoria Lanterns and Dissolving Views.

C. BAKER'S, 244 & 245, HIGH HOLBORN.



A first-class Set of DISSOLVING VIEW APPARATUS, complete, that will fill a Disc 10 feet in Diameter, **£7.**

Ditto, ditto, with OXYHYDROGEN APPARATUS complete, from **£10 10s.**

MAGIC LANTERNS, with 3½-INCH CONDENSER, GIVING A 10-FOOT DISC, **£2 10s.**

A LARGE ASSORTMENT OF SMALLER SIZES, WITH SETS OF SLIDES, from 6*s.* 6*d.*

An extensive Stock of first-class PHOTOGRAPHS, Coloured and Plain, from 1*s.* 3*d.* each.

BEAUTIFULLY-PAINTED SLIDES in every variety of subject.

A Collection of Lanterns and Views, specially kept for Hire.
Catalogues free by post.

BROWNING'S LANTERNS.



THE NEW

THREE-WICK LANTERN.

PRICE

£4 7s. 6d.

New Illustrated Catalogue of Electric Lanterns, Magic Lanterns, Slides, and Diagrams, Sixpence.

Illustrated List of Instruments, for Presents or School Prizes, at Prices from 5*s.* to £10, sent free.

JOHN BROWNING,

63, STRAND, LONDON, W.C.

STANDARD METEOROLOGICAL INSTRUMENTS



ILLUSTRATED PRICE LISTS FREE BY POST.

NEGRETTI & ZAMBRA,

Opticians and Scientific Instrument Makers

To HER MAJESTY THE QUEEN,

HOLBORN VIADUCT,

45, CORNHILL, & 122, REGENT STREET, LONDON.

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 48N, Tollington Road, Holloway, London, N.

EVENING LECTURES TO WORKING MEN.

ROYAL SCHOOL OF MINES, JERMYN STREET.

The Second Course of the Session, consisting of Six Lectures on Minerals, by Mr. WARINGTHN W. SMYTH, M.A., F.R.S., will be commenced on MONDAY, January 10th, 1881, at 8 o'clock. Tickets may be had at the Museum in Jermyn Street (where the Lectures will be delivered), by Working Men only, on Monday evening, January 3rd, from 6 to 10 o'clock, on payment of 6*d*. Each applicant is requested to bring his name, address, and occupation written on paper, for which the Ticket will be exchanged.

F. W. RUDLER, Registrar.

JAWS or TEETH of LOWER TERTIARY

MAMMALS wanted, at reasonable price.—Address Mr. HERBERT, Freshwater, Isle of Wight.

ROYAL POLYTECHNIC.—CLASSES for

the preparation of Students for University Examinations, under the direction of EDWARD B. AVELING, D.Sc., F.L.S. London University Matriculation, 1st and 2nd B.Sc., Preliminary Scientific M.B., Botany, Physiology, Chemistry. All the work practical.

GEOLOGY.—In the Preface to the STU-

DENT'S ELEMENTS of GEOLOGY, by Lyell, 1874, he says: "As it is impossible to enable the reader to recognise rocks and minerals at sight by aid of verbal descriptions or figures, he will do well to obtain a well-arranged collection of specimens, such as may be procured from Mr. TENNANT (149, Strand), Teacher of Mineralogy at King's College, London." These Collections are supplied on the following terms, in plain Mahogany Cabinets:—

100 Specimens, in Cabinet, with 3 Trays	£2	2	0
200 Specimens, in Cabinet, with 5 Trays	5	5	0
300 Specimens, in Cabinet, with 9 Drawers	10	10	0
400 Specimens, in Cabinet, with 13 Drawers	21	0	0

More extensive Collections at 50 to 5,000 Guineas each.

MINERALOGY AND GEOLOGY.

FINE CRYSTALLISED DANBURITES, the first Specimens received in England.

MAGNIFICENT CRYSTAL of MATLOCKITE from Derbyshire.

VERY BRILLIANT and FINELY CRYSTALLISED AUGITE, from Sweden.

VERY LARGE and FINE CRYSTALS of LIBETHENITE, CHALCOSIDERITE, CUPRITE, LIROCONITE, CASSITERITE, BISMUTHINE, HENWOODITE.

COLLECTIONS FOR STUDENTS, from £2 2*s*. COLLECTIONS FOR BEGINNERS, from 4*s*. BLOWPIPE CASES AND APPARATUS.

PRIVATE LESSONS AND EVENING CLASSES.

Catalogues free.

SAMUEL HENSON,

277 (*Late* 113*a*), STRAND, LONDON, W.C.

GEOLOGY AND MINERALOGY.

JOHN TYM has ready for Sale, at low prices, Educational Collections of Fossils, Rocks, and Minerals, specially arranged to illustrate the text-books of Lyell, Geikie, Bonney, Collins, Davies, Skertchley, Dana, Page, Jukes, &c. Series of Specimens for School and College Museums are also supplied at very reasonable prices. Catalogues post free.

Postal Address:—CASTLETON, *vid* SHEFFIELD.

ROCK SECTIONS & ROCK SPECIMENS.

Collections of Rock Specimens to illustrate Rutley's "Study of Rocks" specially prepared. 100 Small Specimens in Cabinet, One Guinea; 200 Specimens, Two Guineas. Extensive and choice Series of Rocks for selection. New List of Sections of Rocks for Microscope, and List of Collections, &c.

JAMES R. GREGORY'S

Extensive New Museum and Show Rooms,

88, CHARLOTTE STREET, FITZROY SQUARE.

CHRISTMAS PRESENTS.—The Popular

SCIENTIFIC POCKET CABINET SERIES. (SECOND EDITION.)

20 Specimens of Rocks, Fossils, and Minerals to illustrate Prof. Geikie's Geology Primer.

25 Minerals, Rocks, and Fossils to illustrate Bonney's Geology.

25 British Rocks. 25 British Fossils. 25 Earthy Minerals. 25 Metalliferous Minerals. 25 Metals and Alloys. 25 Recent Shells. 20 Rough Gems and Stones.

Each Collection complete in itself, price 2*s*. 6*d*.

*** The Specimens are sufficiently large for recognition of the Species, and are contained in Small Cabinets suitably adapted for carrying in the Pocket.

THOMAS J. DOWNING, Geologist, &c., 38, WHISKIN STREET, LONDON, E.C. N.B.—Post Office Order or Cheque must invariably accompany all Orders, with an additional Fourpence on each set for free delivery.

LIVING SPECIMENS FOR THE MICROSCOPE.

THOMAS BOLTON, NATURALISTS' and MICROSCOPISTS' STUDIO, 17, ANN STREET, BIRMINGHAM.

T. B. has last week sent to his subscribers an Eyed Ovum of American Trout, *Salmo fontinalis*, showing the action of the heart and the circulation of the blood in the inclosed embryo, and in the capillaries of the yelk sac.

Weekly announcements will be made in this place of organisms T. B. is supplying.

Specimen Tube, One Shilling, post-free.

Twenty-six Tubes in course of Six Months for Subscription of £1 1*s*.

Price List of Specimens on application, with stamped addressed envelope.

Portfolio of Drawings, No. 3, One Shilling.

BRYCE-WRIGHT'S LATEST ARRIVALS.

MINERALS.—Crystallised Hessite, Crystallised Golds, Krennerite, Crystallised Atacamites, Malacone, Euclase, Edingtonite, Suzannite, Chanarcillite, Proustite, &c.

METEORITES.—Specimens of the following Falls:—Wold Cottage, Yorkshire; Java; Orvinio, Italy; Amana, Ohio; Tipperary, Ireland; Java; Orvinio, Italy; Estherville; Hainholz; Grosnagy, Russia; Borkut; Carthago Co.; Bates Co.; Sierra di Chaco; Ashville Co.; Bates Co.; Pallas; Ashville Co., &c., &c.

BRYCE-WRIGHT, F.R.G.S., &c.,

Mineralogist and Expert in Gems and Precious Stones,

90, GREAT RUSSELL STREET, BLOOMSBURY, LONDON, W.C.

THIN GLASS FOR MICROSCOPIC

MOUNTING, of best quality. Circles, 3*s*. 6*d*. per ounce; Squares, 2*s*. 9*d*.; post free 2*d*. extra; Ground edged Slips, 5*s*. per gross; also other Mounting Materials and Objects prepared for mounting.—CHAS. PETIT, 151, High Street, Stok Newington, N.

THOMAS D. RUSSELL'S

NATURAL HISTORY STORES,

48, ESSEX STREET, STRAND, W.C.

Students and others are invited to inspect the Collections of British and Foreign Shells, Corals, Zoophytes, Annelids, Crustacea, Echinoderms, Minerals, Fossils, Rock Specimens, Microscopic Objects, &c.

Cabinets, Geologist's Hammers, Glass Capped Boxes, Card Trays, Tablets, Glass Slips, Micro-Thin Glass, Canada Balsam, Marine Glue, and other requisites for the Geologist and Microscopist.

Catalogues Post Free.

NORTH BRITISH AGRICULTURIST

is the only Agricultural Journal in Scotland, and circulates extensively amongst Landed Proprietors, Factors, Farmers, Farm-bailiffs, and others interested in the management of landed property throughout Scotland and the Northern Counties of England.

The AGRICULTURIST has also a very considerable circulation on the Continent of Europe, America, Australia, and the Colonies.

The AGRICULTURIST is published every Wednesday afternoon in time for the evening mails, and contains Reports of all the principal British and Irish Markets of the week, besides Telegraphic Reports of those held on the day of publication.

The Veterinary Department is edited by one of the leading Veterinarians in the country, and is invaluable to the breeder and feeder as a guide to the rearing of animals, and their treatment when labouring under disease.

Full Reports are given of the Meetings of the Royal Agricultural Society of England, the Royal Agricultural Society of Ireland, the Highland and Agricultural Society of Scotland, the Scottish Chamber of Agriculture, and all the principal Agricultural Associations throughout Great Britain and Ireland.

For Advertisers addressing themselves to Farmers a better medium does not exist

Price 3*d*. By post 3½*d*. Annual Subscription, payable in advance, 14*s*.

Office—377, High Street, Edinburgh.

Post-Office Orders payable to Charles Anderson, Jun., Edinburgh.

ESTABLISHED 1843.

5me ANNÉE L'ÉLECTRICITÉ 5me ANNÉE

Paris. — 16, *rue du Croissant.* — *Paris*

Revue spéciale populaire, illustrée, bi-mensuelle contenant 24 pages grand in-8° à deux colonnes, formant chaque année un magnifique volume de 400 pages orné de plus de 200 gravures.

Rédacteur en chef: W. DE FONVIELLE

Directeur: E. de Clisson

Envoi gratis de numéro spécimen sur demande

Un numéro 75 centimes

Paris et Départements: Un an..... 12 fr.

Étranger. — Union postale: Un an..... 14 fr.

Les Abonnements partent du 5 et du 20 de chaque mois.

WESLEY COLLEGE, SHEFFIELD.

(*Affiliated to the London University*, 1844.)

Governor and Chaplain, Rev. W. H. DALLINGER, F.R.S. Head Master, H. M. SHERA, Esq., M.A., LL.D.
Second Master, R. SHINDLER, Esq., M.A. (Lond.).
And Eighteen Assistant Masters and Professors.

The object aimed at in this Institution is a sound and comprehensive mental training. The course of study is fully adapted to the requirements of the present time and to the prospective wants of the pupils, who, whether in preparation for the Universities, training for scientific pursuits, or for professional or commercial life, are provided with the most efficient aids.

BIOLOGY, PHYSICS, and CHEMISTRY, the Modern Languages of Europe, Hebrew and Syriac, Vocal and Instrumental Music, and Drawing, are taught by accomplished Professors.

The Rev. W. H. DALLINGER, F.R.S., has undertaken the Professorship of NATURAL SCIENCE, and gives Weekly Lectures and Class Instruction in Practical Zoology, Botany, &c.

Physics and Chemistry are taught by A. H. ALLEN, Esq., F.C.S.

Scholarships are awarded, worth in the aggregate 300*l.* a year.

Prospectuses may be had by application to the GOVERNOR or HEAD MASTER.

"The leading Farmers' paper."—CLARE SEWELL READ, ESQ., M.P.

THE CHAMBER OF AGRICULTURE JOURNAL AND FARMERS' CHRONICLE

(PRICE 3*d.* WEEKLY).

The representative organ of the Central and Provincial Chambers of Agriculture; *gives fuller reports of the discussions and proceedings* of this extensive organisation than any other agricultural paper. It devotes *special attention to the treatment of Agricultural Questions by Parliament*, besides containing ample Reports of the LATEST LONDON and COUNTRY CORN, CATTLE, HOP, PROVISION, and other Markets, with Original Articles on Practical Farming, the Dairy, Herd and Flock News, Horticulture, &c., &c. It is despatched every Monday evening in time for the country post.

Terms of Subscription, payable in advance, post free:—3 months, 3*s.* 9½*d.*; 6 months, 7*s.* 7*d.*; 12 months, 15*s.* 2*d.*

Published by W. PICKERING, 21, Arundel Street, Strand, London, W.C.

THE ENTOMOLOGIST'S MONTHLY MAGAZINE.

Price Sixpence, Monthly, 24 pages 8vo, with occasional Illustrations.
Conducted by J. W. DOUGLAS, R. MCLACHLAN, F.R.S., E. C. RYE, F.Z.S. and H. T. STAINTON, F.R.S.

This Magazine, commenced in 1864, contains standard articles and notes on all subjects connected with Entomology, and especially on the Insects of the British Isles.

Subscription—Six Shillings per Volume, post free. The volumes commence with the June number in each year.

Vols. I. to V. (strongly bound in cloth) may be obtained by purchasers of the entire set to date, at the increased price of 10*s.* each; the succeeding vols. may be had separately or together, at 7*s.* each.

London: JOHN VAN VOORST, 1, Paternoster Row

N.B.—Communications, &c., should be sent to the Editors at the above address.

LA SEMAINE FRANÇAISE: a Weekly

Newspaper and Review in the French Language. Politics, Literature, Science, Art, Varieties, Notes. Price 3*d.*, through booksellers, and at the railway bookstalls Office, 37, Southampton Street Strand, W.C.

LA SEMAINE FRANÇAISE: Journal Française pour l'Angleterre: Politique, Littérature, Sciences, Arts, Variétés, Nouvelles, et Notes. Un exemplaire par la poste, 3½*d.*, en timbres poste Abonnement franco par la poste—un an, 15*s.* 2*d.*; six mois, 7*s.* 7*d.* Prix 3*d.*, chez tous les libraires et aux gares des chemins de fer. On s'abonne aux bureaux, 37, Southampton Street, Strand, Londres, W.C.

LA SEMAINE FRANÇAISE.—"'La Semaine Française' has been brought out in London for the benefit of those English readers who may wish to study contemporary French from all points of view, instead of confining their reading to one particular Gallic print. It certainly merits success."—*Graphic.*

LA SEMAINE FRANÇAISE.—"The numbers before us are full of good things. . . . . It will be far better for most than any one of the best papers published in Paris itself. We are much pleased with the character of it, and believe it will be highly valued in all those many households where French is cultivated. The printing is very well done."—*Queen.*

TERMS OF SUBSCRIPTION:—							s.	d.
Three months	...	...	...	...	...	...	3	10
Six "	...	...	...	...	...	...	7	7
Twelve "	...	...	...	...	...	...	15	2

P.O.O. payable to T. SPANSWICK, at King Street, Covent Garden, W.C.
Publishing Office, 37, Southampton Street, Strand, W.C.

THE "HANSA"

Published since 1864 in Hamburg, is the only independent professional paper in Germany, dedicated exclusively to Maritime Objects. Essays, Critiques, Reviews, Reports, Advertisements. Strict eye kept upon the development of Maritime Affairs in every respect. Every second Sunday one Number in 4to at least; frequent supplements and drawings. Subscription at any time; preceding numbers of the year furnished subsequently. Price 12*s.* for twelve months. Advertisements 4*d.* a line, widely spread by this paper; considerable abatement for 3, 6, 12 months' insertion. Business Office: Aug. Meyer and Dieckmann, Hamburg, Alterwall. 28. Edited by W. v. FREEDEN, M.R., Hamburg, Alexander Street, 8.

THE NEW BIOLOGICAL JOURNAL.

ARCHIVES DE BIOLOGIE.

Edited by Professors EDOUARD VAN BENEDEN of Liège, and VAN BAMBEKE of Ghent.

This Journal is devoted to the publication of original Memoirs on the Embryology, Histology, Physiology, and Comparative Anatomy of Plants and Animals. Each number is illustrated with numerous Coloured Plates, and appears at the commencement of the Quarter.

Price:—A Single Number, Six Shillings and Sixpence. Annual Subscription: Twenty-five Shillings, or Twenty-seven Shillings post free.

Orders received by Messrs. WILLIAMS & NORGATE, 14, Henrietta Street, Covent Garden, London.

In the first two numbers have appeared:—

VAN BENEDEN: On the Embryology of the Mammalia.
VAN BAMBEKE: On the Cleavage of the Egg in Batrachia.
FOR HINGER: On the Termination of Nerves in the Muscles of Insects.
FREDERIQUE AND VANDEVELDE: On the Physiology of the Muscles and Nerves of the Lobster.
MACLEOD: On the Harderian Gland of the Duck, &c., &c.

On the 1st of every Month, price One Shilling.

THE ZOOLOGIST:

A MONTHLY MAGAZINE OF NATURAL HISTORY.
Third Series. Edited by J. E. HARTING, F.L.S., F.Z.S., Member of the British Ornithologists' Union; contains—

Original articles by well-known naturalists in every branch of zoology; habits of animals; arrival and departure of migratory birds; occurrence of rare birds; distribution and migration of British fresh-water fish; new or rare marine fish; local aquaria; British reptiles, British land and fresh-water mollusca, with remarks on the haunts and habits of the species; and other matters of general interest to those who delight in natural history. Reports of the Linnean, Zoological, and Entomological Societies. Reviews of natural history books. Occasional translations from foreign zoological journals of important and interesting articles in various branches of zoology. There are occasional woodcuts.

JOHN VAN VOORST, 1, Paternoster Row.

THE BREWERS' GUARDIAN:

A Fortnightly Paper devoted to the Protection of Brewers' Interests, Licensing, Legal, and Parliamentary Matters.
REVIEW OF THE MALT AND HOP TRADES; AND WINE AND SPIRIT TRADE RECORD.
The Organ of the Country Brewers.

"The Brewers' Guardian" is published on the evenings of every alternate Tuesday, and is the only journal officially connected with brewing interests.

Subscription, 16*s.* 6*d.* per annum, post free, dating from any quarter-day. Single Copies 1*s.* each. Registered for transmission abroad.

Offices—5, Bond Court, Walbrook, London, E.C.

On the 1st of every Month, price Sixpence

THE ENTOMOLOGIST:

AN ILLUSTRATED JOURNAL OF BRITISH ENTOMOLOGY.
Edited by JOHN T. CARRINGTON,
With the Assistance of
FREDERICK BOND, F.Z.S. | JOHN A. POWER, M.D.
EDWARD A. FITCH, F.L.S. | J. JENNER WEIR, F.L.S.
F. BUCHANAN WHITE, M.D.

Contains Articles by well-known Entomologists on all branches of the Science; on Insects injurious or beneficial to Farm or Garden; Notes on Habits, Life-Histories; occurrence of Rarities, &c.; there are monthly lists of Duplicates and Desiderata.

Numerous WOODCUT ILLUSTRATIONS, to the printing of which especial attention is given, and occasional LITHOGRAPHED and CHROMO-LITHOGRAPHED PLATES.

SIMPKIN, MARSHALL, & CO., Stationers' Hall Court.

On the 1st of every Month.

TRIMEN'S JOURNAL OF BOTANY,

BRITISH AND FOREIGN.
New Series. Edited by JAMES BRITTEN, F.L.S., British Museum.

CONTENTS.—Original Articles by leading Botanists.—Extracts, and Notices of Books and Memoirs.—Articles in Journals.—Botanical News.—Proceedings of Societies

Price 1*s.* 3*d.* Subscription for One Year, payable in advance, 12*s.*
London: WEST, NEWMAN, & CO., 54, Hatton Garden, E.C.

JUST PUBLISHED, Crown 8vo, cloth. 5s.

CONSCIOUS MATTER;

OR,

THE PHYSICAL and the PSYCHICAL UNIVERSALLY IN CAUSAL CONNECTION.

By W. STEWART DUNCAN.

London: DAVID BOGUE, 3, St. Martin's Place, Trafalgar Square, W.C.

Now ready.

EXERCISES in PRACTICAL CHEMISTRY. Vol. I. (ELEMENTARY EXERCISES). By A. G. VERNON HARCOURT, M.A., F.R.S., Senior Student of Christ Church, and Lee's Reader in Chemistry; and H. G. MADAN, M.A., Fellow of Queen's College, Oxford. Third Edition, Revised and considerably Enlarged, crown 8vo, cloth, 9s.

London: HENRY FROWDE, Clarendon Press Warehouse, 7, Paternoster Row.

EDITED BY HENRY WATTS, B.A., F.R.S.,

Editor of the *Journal* of the Chemical Society

FOWNES' PHYSICAL and INORGANIC CHEMISTRY. Twelfth Edition, with Coloured Plate and 154 Engravings, crown 8vo. 8s. 6d.

Also,

FOWNES' CHEMISTRY OF CARBON COMPOUNDS; or, ORGANIC CHEMISTRY. Twelfth Edition, with Engravings, crown 8vo. 10s.

London: J. & A. CHURCHILL.

DR. SMILES'S WORKS.

Now Ready, 20TH THOUSAND.

DUTY; with Illustrations of Courage, Patience, and Endurance. Post 8vo. 6s.

ALSO

SELF-HELP; with Illustrations of Conduct and Perseverance. 6s.

CHARACTER: A Book of Noble Characteristics. 6s.

THRIFT: A Book of Domestic Counsel. 6s.

INDUSTRIAL BIOGRAPHY: Iron Workers and Tool Makers. 6s.

LIVES OF THE ENGINEERS. 5 Vols. 7s. 6d. each.

THE HUGUENOTS: their Settlements, Churches, and Industries in England and Ireland. 7s. 6d.

JOHN MURRAY, Albemarle Street.

BRITISH ASSOCIATION FOR THE ADVANCEMENT OF SCIENCE,

22, ALBEMARLE STREET, LONDON, W.

The REPORT for 1880 (Swansea Meeting) is NOW READY, and will be supplied as follows:—

To Members, gratis and carriage paid.

To Associates at the Swansea Meeting, 16s.; if sent by post, 1s. additional.

To the Public, through Mr. John Murray or any Bookseller, 24s.

J. E. H. GORDON,
Assistant Secretary.

NEW WORK BY SIR RICHARD TEMPLE.

Now Ready, One Volume (544), 8vo, 16s.

INDIA IN 1880. By Sir Richard Temple, Bart., G.C.S.I., C.I.E., D.C.L., late Governor of Bombay, Lieutenant-Governor of Bengal, and Finance Minister of India.

CONTENTS.

Claims of India on the Continuous Attention of England.
Objects of Beauty in Nature and Art.
European Classes, Official and Non-official.
Native States.
Material Progress of the Natives.
Mental and Moral Progress of the Natives.
National Education.
Religious Establishments and Missions.
Law and Legislation.
Crime, Police, and Prisons.
Land Tax and Landed Tenures.
Revenues.
Canals and Irrigation.
Railways and Electric Telegraphs.
Roads and Embankments.
Products, Natural, Agricultural, and Industrial.
Commerce, Internal and External.
Public Health and Sanitation.
Famine.
Learned Research.
Physical Science.
Wild Animals and Sports.
Navy and Marine.
The Army.
Foreign Relations.
Finance.
Statistical Summary.
Conclusion.

JOHN MURRAY, Albemarle Street.

Now ready, post quarto, cloth gilt, 272 pages. Price 16s.

LIGHTNING

CONDUCTORS:

THEIR

HISTORY, NATURE, AND MODE OF APPLICATION.

By RICHARD ANDERSON, F.C.S., F.G.S.,
Member of the Society of Telegraph Engineers; Assoc. Inst. C.E.

With numerous Illustrations.

"The book is one to be commended to the builders of, or dwellers in, lofty houses, to the deans of our cathedrals, to the parsons of churches with lofty spires or towers, and to all owners, constructors, or occupiers of buildings which, from their height or situation, are exposed to danger from lightning."—*The Athenæum.*

"The book is clearly and sensibly written, and sufficiently illustrated, and is the work of a practical man who thoroughly understands what he is talking about."—*The Academy.*

London: E. & F. N. SPON, 46, Charing Cross.
New York: 446, Broome Street. 1880.

New Edition, very much enlarged, 21s.

HOW TO WORK WITH THE MICROSCOPE.

By LIONEL S. BEALE, F.R.S.,
President of the Royal Microscopical Society.

THE FIFTH EDITION,

Strongly bound and enlarged to 530 Pages, with 100 Plates, some of which are Coloured, is now ready.

HARRISON & SONS, Pall Mall.

Just Published, Part I., 64 pp., 27 Plates, imp. 8vo, price 12s.

The FISHES of GREAT BRITAIN and IRELAND: being a Natural History of such as are known to inhabit the Seas and Fresh Waters of the British Isles, including Remarks on their Economic Uses and various Modes of Capture. With an Introduction upon Fishes generally.

By FRANCIS DAY, F.L.S. & F.Z.S.

To be completed in 9 Parts of about 25 Plates, each Part, 12s. Prospectus on application.

WILLIAMS & NORGATE, 14, Henrietta Street, Covent Garden, London; and 20, South Frederick Street, Edinburgh.

Recently Published,

Demy 4to, with 18 Plates (5 printed in Colours), 207 pages, cloth, £2 2s.

AURORÆ:

THEIR CHARACTERS AND SPECTRA.

By J. RAND CAPRON, F.R.A.S.

Part I.—THE AURORA AND ITS CHARACTERS.
Part II.—THE SPECTRUM OF THE AURORA.
Part III.—MAGNETO-ELECTRIC EXPERIMENTS IN CONNECTION WITH THE AURORA.

By the same Author.

Demy 8vo, with 37 Plates, cloth, 30s.

PHOTOGRAPHED SPECTRA.

One Hundred and Thirty-Six Photographs of Metallic, Gaseous, and other Spectra, printed by the Permanent Autotype Process, with Introduction, Description of Plates, and Index, and with an Extra Plate of the Solar Spectrum (showing bright lines) compared with the Air Spectrum.

London: E. & F. N. SPON, 16, Charing Cross.

In fcap. 8vo, price 3s. 6d.

SOUND: ELEMENTARY LESSONS ON.

By Dr. W. H. STONE, Lecturer on Physics at St. Thomas's Hospital. With numerous Illustrations.

"This is an excellent little text-book, well adapted for students of the Science and Art Classes, but also of considerable value to those who desire to do something more than cram. The student of acoustics will find it a very acceptable help, and a stepping-stone to the more elaborate works on the subject, while the musician will find in its pages information which may be of great assistance to him in the acquisition of his art."—*English Mechanic.*

MACMILLAN & CO., LONDON.

THURSDAY, DECEMBER 30, 1880

PERUVIAN BARK

Peruvian Bark: a Popular Account of the Introduction of Chinchona Cultivation into British India. By Clements R. Markham, C.B., F.R.S. 1860–1880. (London: John Murray, 1880.)

"THE enterprise undertaken by me in 1859 of introducing the cultivation of Peruvian bark trees into British India and Ceylon is now an assured success." With these words Mr. Markham begins his preface, and a perusal of the convenient history he has put together of the gradual steps by which during the past twenty years this success has been reached, enables us to fully share the satisfaction with which they must have been written. Not merely has a cheap supply of febrifuge alkaloids been brought within reach of the fever-haunted population of India, but a new and highly-profitable industry has been opened to the planters of our tropical colonies, and the yield of an inestimable drug placed beyond risk of exhaustion.

Enthusiasm is in most enterprises essential to success. If a certain tinge of impracticability often accompanies it a moderate experience of human nature disposes us to regard this with a good deal of toleration. We may as well confess at once therefore that the pleasure with which we have studied Mr. Markham's pages would have been greater but for his insistance throughout on two grievances, in neither of which do we find ourselves in any way persuaded by his advocacy. One of these—the other is more serious, and must be adverted to further on—is irritating in inverse proportion to its importance. The names of genera employed in systematic botany are Latinised forms, very arbitrary, and often, it must be allowed, unscholarly in their construction. But they are symbols or dockets under which scientific information can be arranged. If there is one thing about which botanists, of whatever nationality, are agreed, it is that the docket, having once been promulgated and brought into use, shall not be meddled with. It may be abolished or merged in some other, but being a mere symbol it cannot be tampered with without disturbing all kinds of mechanical aids to study, such as indexes and catalogues, and so adding to the worry of life. From a literary point of view the correction of *Cinchona* into *Chinchona* may be desirable, but the trouble of having two spellings in circulation is too great a price to pay for the mere satisfaction of literary propriety. It cannot be said therefore that this is merely a literary question like such spellings as those of diocess and chymistry affected by the *Times*, while from a technical point of view it has been already discussed and conclusively decided against Mr. Markham in the pages of this journal.

The genus *Cinchona*—as we must still beg leave to call it—includes all the plants at present known to yield quinine and allied alkaloids. It has rather more than thirty species, some of which however are medicinally valueless, while the rest vary individually in the amount and character of the alkaloids they yield. The native habitat of the genus is very restricted; it is only found on the Andes between 10° N. and 19° S. lat., and between 2500 and 9000 feet of elevation. Besides this the several species are closely limited to particular portions of the general area.

The native inhabitants seem to have set little store on the febrifugal properties of the cinchonas, and indeed to have been little aware of them except in the neighbourhood of Loxa, where a Jesuit was cured in 1600 of a fever at Malacotas by Peruvian bark, and to this day the local prejudice against its use is very strong. In 1638, however, the Countess of Chinchon, wife of the Viceroy of Peru, was cured of intermittent fever by bark sent by the Corregidor of Loxa. The remedy, whose reputation was now established, was carried by her to Spain in 1640, and became known as *Pulvis comitissæ*. In 1670 it was sent to Rome by the Jesuits and distributed to members of that order throughout Europe. Hence it came to be called Jesuit's bark, and it is interesting to find that its merits became accordingly a party question between Protestants and Catholics.

For more than a century (till 1776) the only bark met with in commerce was that brought from the neighbourhood of Loxa. This was called Quinquina, from the Indian name *quina-quina*, *quina* meaning bark, and the reduplication the possession of medicinal properties. The plant producing the bark was described by Linnæus under the name of *Cinchona officinalis*, to be rechristened afterwards by Humboldt and Bonpland *Cinchona condaminea*, a change correctly rejected by Mr. Markham, following Sir Joseph Hooker, and, be it remarked, on precisely the same grounds as those on which the rechristening of the genus as *Chinchona* must also be rejected.

As early as 1735 Ulloa represented to the Spanish Government that the Loxa forests could not long survive the reckless treatment to which even then they were subjected. And this was in spite of the intelligent efforts of the Jesuits, who endeavoured to enforce replanting as a religious duty. The Loxa bark, eventually distinguished as Crown bark from being reserved, when other kinds became known, for use in the Royal Pharmacy at Madrid, is represented in old collections of Materia Medica, such as that of the College of Physicians, by massive fragments which must have been detached from very old trees. Mr. Markham tells us that it is now only found in commerce in the minutest quills. As the Loxa bark became scarce the search after other supplies of cinchona bark was stimulated. The botanical expedition of Ruiz and Pavon sent by the Spanish Government in 1777 resulted in the discovery of seven species of *Cinchona*, yielding gre bark, near Huanuco in Northern Peru. Mutis, another Spanish botanist, believed that he first detected a *Cinchona* in Columbia in 1772, though a resident in Bogota challenged his claim to priority.

The well-known "red bark" of the slopes of Chimborazo seems to have been known early in the last century, and later to have found its way into European markets, though it was not till 1857 that the plant yielding it was clearly identified by Dr. Klotzsch. The yellow or Calisaya barks of Bolivia, first discovered by Haenke in 1776, did not become of commercial importance till 1820, when quinine, the most important active principle of Peruvian bark having been isolated by the French chemists, Pelletier and Caventou, yellow bark was recognised as richer in it than any other kind.

It is not necessary to follow in detail the interesting account given by Mr. Markham of the recklessness with which the natural supplies of Cinchona bark were drawn upon. The inconvenience of a precarious dependence upon the South American forests has for at least forty years occupied the attention of scientific men in Europe. Royle, in 1839, urged the introduction of Cinchonas into India, and pointed out the Nilgiri Hills as a suitable locality. The Dutch botanists had been no less urgent that the experiment should be made in Java, and Hasskarl was commissioned to proceed to Peru in 1852 to obtain seeds. In this he succeeded, but the bulk of the seeds eventually proved to belong to a species worthless medicinally, which was afterwards named *C. Pahudiana*. He also obtained, by the aid of a Bolivian named Henriquez, 400 plants of the yellow bark, *C. Calisaya*, only two of which unfortunately survived in Java. The mishaps of the Dutch enterprise cannot be followed here, instructive as they are to any one interested in the cultivation. A happy accident, to be presently alluded to, was a kind and well-deserved turn of fortune in its favour, and a greater measure of success than could ever have been hoped for now seems assured to it.

The Government of India in 1852 first proposed the introduction of cinchona into that country, and several abortive attempts to effect it were made with the aid of the Foreign Office, but without success. In 1859 Mr. Markham was officially employed by the present Lord Derby, who was then Secretary of State for India, to undertake a mission to South America for the purpose. His previous travels in the Cinchona region, though for ethnological and not for botanical inquiry, and his knowledge of the Spanish and Quichua languages singularly fitted him for the task. The plan laid down by him was extremely comprehensive, and has at last been fully carried out, or nearly so. It was nothing less than the introduction into India of all the species of *Cinchona* yielding bark of known commercial value. This plan was adopted as it was *à priori* uncertain which kinds would turn out best adapted for Indian cultivation, and it was desirable that all should be tried; it involved no less than five distinct expeditions to the different districts of the Andes already mentioned.

Mr. Markham visited himself in 1860 the yellow bark region in Southern Peru and Bolivia, accompanied by a young gardener named John Weir, recommended by Messrs. Veitch. The plants collected reached England in fifteen Wardian cases, but the heat of the Red Sea was fatal to them and they all eventually died. A supply of seed which Mr. Markham had arranged for at Caravaya arrived in India in 1865 and germinated satisfactorily.

Mr. Pritchett, who had travelled in the Huanuco district, was employed to make a collection of the grey bark plants, and to these also the Red Sea was fatal, but the loss again was retrieved by the safe transmission to India of seed which grew well. The red bark region was visited, at the suggestion of Sir William Hooker, by the well-known botanical traveller, Dr. Spruce, who was residing in South America at the time, and he was accompanied by Robert Cross, a Scotch gardener, recommended by the Kew authorities. The plants collected by Dr. Spruce were more fortunate, and reached India in good condition in 1861 under Mr. Cross's charge. This skilful collector then returned to South America and obtained the seed of the crown bark from the Loxa forests, which reached India in 1862 and germinated abundantly. Before returning to Europe he visited the Columbian forests in 1863 and secured seed of Pitayo bark (*C. Pitayensis*), which however had lost its vitality before it arrived in India. He was therefore sent again in 1868, and this time secured both plants and seeds, which were transmitted to India in a living state. The only remaining kinds of importance which had not been introduced into India were the Calisaya de Santa Fé, yielding soft Columbian bark, and *Cinchona cordifolia*, yielding hard Carthagena bark; to procure these Mr. Cross was despatched on another mission, from which he returned in 1878, bringing cuttings of both kinds, and these were successfully propagated at Kew, which had indeed in every case been made the depôt for the receipt of the successive consignments and their despatch to India. The Carthagena bark is now well established in India, Jamaica, and it is hoped in Ceylon. But the fate of the Calisaya de Santa Fé is still doubtful, as one consignment succumbed to the heat of the Red Sea, which is so great an obstacle to the transport of plants, intolerant of great heat, and no news as to the second instalment taken out in charge of Mr. Cross has yet reached this country.

We must but very briefly hurry over the interesting pages in which Mr. Markham describes what has been done in India. Red bark has everywhere taken the lead. Next to this, in the Nilgiris, crown bark has succeeded best; the other kinds have made but little progress. Unfortunately little care seems of late to have been taken in Southern India to keep the different kinds distinct, and as the species hybridise very freely it is not easy to say what some of the plants actually in cultivation precisely are. In the Himalayas, however, besides red and crown bark-plants, *C. Calisaya* (yellow bark) and *C. micrantha* (one of the species yielding grey bark) also do well.

The share taken by Kew in this important enterprise enabled the advantages secured by the Indian Government to be extended to other tropical possessions in the Empire. Sir William Hooker was allowed to transmit a share of the seeds and plants to Ceylon, Jamaica, Trinidad, Mauritius, and St. Helena. In the three latter islands the cultivation has made but little progress; in the first it is now one of the staple resources of the planters; while in Jamaica the crown and red bark bring in an annual revenue to the Government, which leaves an ample surplus after paying the whole expenses of the botanical department.

One of the most singular incidents in the whole story has still to be told. Mr. Charles Ledger, who had long resided in South America, hearing of Mr. Markham's enterprise, employed a native servant, Manuel Mamani, to collect seed of the best Calisaya or yellow bark tree. Four years elapsed before he succeeded, as each year the blossom of the trees was destroyed by frost. These seeds were transmitted to London to the care of Mr. Ledger's brother, and it is believed were offered to the Indian Government, who refused to purchase them. Half was eventually sold to the Dutch Government and half to Mr. Money, a planter on the Nilgiris. This fortunate purchase has put quite a

new face upon the cultivation in Java. The bark of some of the trees has yielded as much as 10 per cent. of quinine; and the news of this remarkable result has produced much the same effect on Cinchona planters in Ceylon and Southern India as the discovery of a gold-field on the inhabitants of an Australian city. The Java officials have however behaved with singular liberality in the matter, and in the course of a few years it cannot be doubted that Ceylon will be abundantly supplied with this valuable kind, which, there seems reason to think, may prove to be a distinct species. Part of the seed sent in the first instance to the Nilgiris seems to have found its way to Sikkim, and the Government plantations there are believed to be in possession of a strain of Calisaya, little if at all inferior to that possessed by the Dutch.

The Government of Bengal have effected an enormous saving by using, in hospitals and dispensaries, instead of quinine imported from Europe, the febrifuge manufactured at the Sikkim plantations. The Government estimated that in consequence, by the end of 1879, "the plantations will have cleared off the entire capital that has been invested in them."

And this leads us to what is really the painful feature in Mr. Markham's book. He complains in repeated and in bitter terms of the want of justice which has been shown to those whom he employed in the business of collecting. "Those who did the work have not received fair recompense for most valuable services." It is rather singular to find that he adduces in support of this statement the case of Mr. Ledger, who was not even in any way commissioned to do what he did. But the remuneration which his actual agents received was the ground of no complaint on their part, and was in point of fact liberal compared with that which is given to the collectors who are constantly employed by the great nurserymen, and who too often lose their lives in their arduous pursuits without the satisfaction of feeling that they are doing so in an enterprise like this of lasting utility. But we fear that if Mr. Markham's assistants have reason to complain the blame must, on his own showing, be laid at his own door. He tells us (p. 271): "The system I adopted was . . . to include very slight remuneration in the original agreements. *Thus the loss to Government would be insignificant if the work was not executed satisfactorily.* If, on the other hand, the arduous tasks were successfully performed . . . I anticipated no difficulty in obtaining fitting recognition for such distinguished services." We leave our readers to judge of the probability of such a scheme answering Mr. Markham's expectations. We may go further, and ask how the claims would have stood if, notwithstanding all the pains that were taken, the cultivation of Cinchonas had fared in India—as might even have happened—no better than it at first did in Java.

But there are many other things pleasanter than this which we should like to touch upon if this review had not already run to an inordinate length. So many Englishmen are now in one way or other interested in colonial industries that it will be strange if this interesting book does not find as many readers as it deserves. Besides a complete history of the Cinchona enterprise in the Old World, it gives, in an appendix, accounts of some other South American vegetable products, notably india-rubber. The steps taken at Mr. Markham's instance for the introduction into India of the most important rubber-yielding plants of the New World have been from time to time recorded in our pages. We have only to repair one inadvertent omission on Mr. Markham's part, and point out that the transmission of the Para rubber plant to India was secured by the exertions of Mr. Wickham, as recorded in the Kew Report for 1876, p. 8.

PRACTICAL BLOWPIPE ASSAYING

Practical Blowpipe Assaying. By George Attwood. With Seventy-four Woodcuts. (London: Sampson Low, Marston, Searle, and Rivington, 1880.)

THIS book shows many signs of carelessness on the part of the author. At the very outset, in the Introduction, we meet with strange statements. Mr. Attwood divides the elements into those which are of commercial value and those which are of no commercial value. In the latter class we find Uranium and Tungsten; surely the author does not intend to deny the value of pitchblende and wolfram. He classifies zirconium among the non-metallic elements.

The first part of the work describes the reagents and apparatus; the second, we are told, contains the modes of determining any one of the sixty-four well-recognised elements, and in the third part we have the methods adopted by the author for making quantitative assays by the blowpipe. Finally, Part IV. contains some tables showing the English and American values of gold according to its fineness, and the value of gold coins in the United States.

The apparatus employed is much the same as that recommended by Plattner. Like Neumann, Mr. Attwood very wisely uses riders with his balance instead of the very small weights supplied by some of the other Freiberg opticians; but the balance would be improved by the addition of a movable arm for shifting these riders. The steelyard devised by the author will probably be of use to explorers. From practical experience with the batea I can fully endorse all that is said in its favour, but why are the merits of the iron pan ignored? It has the advantage that it will stand rougher usage than the batea. Again, for washing a sample of tin ore nothing will beat the Cornish vanning shovel.

I regret to see no mention of the useful little pastilles and crucibles made out of charcoal powder, proposed by Griffin thirty or forty years ago and adopted by Plattner. Col. Ross's aluminium plate for sublimates seems also to have escaped Mr. Attwood's notice.

With reference to the list of reagents I must remark that the author does not name all the reagents which his tests require, whilst others are inserted which he does not appear to put to any use. I should be glad to know what he means by inserting "nitrous acid" among his reagents. This is not a misprint for "nitric acid," because that acid has been already named.

The plan of the second part of the work is not one which I should recommend. It simply contains a list of tests for the various elements, but gives no systematic scheme for making the examination of an unknown substance. I fear that the "direct" method advocated by Mr. Attwood will often prove a very tedious one. Many of the tests themselves are not so complete as they

ought to be. In describing the tests for barium it is said that the bead "can be flamed," but no explanation is given of the process of flaming. The capital test for bismuth with potassium iodide and sulphur is entirely ignored.

I now come to the third part, which treats of quantitative assays. Mr. Attwood's plan of making a check assay in every case with a small quantity of the pure metal is certainly calculated to give the operator confidence in his results. The author adopts 1½ grain as the amount of ore to be taken for an assay. I think he would have done better to have followed Plattner and used the French weights, because there is less chance of making errors where each milligramme means 1 per cent.

For the silver assay Mr. Attwood employs pieces of ordinary charcoal instead of the far more convenient and portable charcoal crucibles designed by Plattner. He also describes a crucible assay for silver ores, which does not appear to possess any advantage over Plattner's scorification method.

There is one most unfortunate error in the book to which I feel bound to call attention. Mr. Attwood gives some tables for calculating the number of ounces of gold or silver per ton from the results of assays of 1½ grain of the ore. In an unlucky moment he forgot that gold and silver are weighed by *troy* weight, and calculated his tables for *avoirdupois* ounces. The consequence is that these tables are not only valueless, but also highly misleading. Let us take one case as an example. Suppose that 1½ grain of ore had yielded 0·01 grain of fine metal. We look down the table (p. 117), and find, according to Mr. Attwood, that the yield would be 238·93 oz. per ton; in reality the yield should be 217·77 oz.

Some neat little retorts have been designed by the author for distilling ores of mercury and amalgam, but he does not mention Küstel's assay.

On coming to the tin assay we have the peculiar statement that silica may be separated from tin ore by boiling t with hydrochloric acid. "The assay being finely powdered, the silica is dissolved." "The dissolved silica is decanted off" (p. 158). Cornish mine agents will be surprised when they are told that, in order to obtain correct results, it is necessary to wash or van as much as *5 lbs.* of an ordinary tin ore (p. 159).

Under the head of nickel no mention is made of the valuable ores from New Caledonia.

Small mistakes are numerous. The size of a box is said to be "twelve inches square" (p. 3); we note also: "*a* most useful addend*a*" (p. 24); "chloride of ammoni*a*" (p. 33); "manganate" instead of manganate (p. 53), and permanganate (p. 54). The term "raw iron" is used frequently instead of "pig iron," and shows that the author has copied Cornwall's translation blindly. Coal, anthracite, and graphite are said to "volatilise" when heated in the platinum spoon (p. 82). Sieves are made with 2000 holes per "linear" inch (pp. 100 and 137). In the description of cupellation (p. 106) we read: "The lead parts with portions of its oxygen to the copper and other base metals."

In conclusion I think that the value of the book would be increased if a list of *errata et corrigenda* were inserted, correcting some of the errors which, I regret to say, impair its general usefulness. C. LE NEVE FOSTER

OUR BOOK SHELF

Über die von den Trichopterenlarven der Provinz Santa Catharina verfertigen Gehäuse. Von Dr. Fritz Müller. *Archivos de Museu national.* Vol. iii. pp. 99-134, and 209-214. Rio de Janeiro, 1880. (Aus dem Portugieischen übersetzt von dem Bruder des Verfassers, Dr. Hermann Müller in Lippstadt.)

DR. FRITZ MULLER has for some years been engaged upon an investigation of the habits of the Caddis-flies of Santa Catharina, and has shown extraordinary skill in breeding these insects, a matter always difficult, and especially in the case of those that inhabit running water. The results of his researches were foreshadowed in various notes published in the *Zoologischer Anzeiger* and in the *Transactions* of the Entomological Society of London for 1879. But it was well known that the extended information and figures would be given in the Rio de Janeiro *Archivos*. As this publication is somewhat difficult to obtain, and as most of us are not familiar with Portuguese, Dr. Hermann Müller has conferred a great boon by publishing a translation of the paper (accompanied by the two folded plates) in the *Zeitschrift für wissenschaftliche Zoologie* for the present year (pp. 47-87, plates iv. and v.). It is needless to state that the details are of the greatest interest, and we have here the most important contribution to the natural history of *Trichoptera* that has appeared since the publication of Pictet's "Recherches" on the species of Geneva, and worked out in a far superior manner. We cannot here even allude to most of the many marvels of insect-architecture and habits that Dr. Fritz Müller has revealed. Some of the most interesting are the numerous forms of *Helicopsyche*, which build little sand-cases so like shells that they have been described as such; those *Dentalium*-like cases, originally noticed by Aug. St. Hilaire as *Grumicha*, which name our author retains; those instances of parasitism (or worse) in which a larva of one species dispossesses that of another of its house and converts it to its own purposes; those very numerous forms of *Hydroptilidæ*, the most minute of all *Trichoptera*, with cases of the most varied and wonderful structure; above all, that most interesting fact that the rain-water which collects at the bases of the leaves of some *Bromeliaceæ* has a special fauna of its own, including at least one Caddis-worm. The descriptions of these and many others will be read with delight by every biological student; and we hope Dr. Müller will follow up the paper by records of further discoveries, for here, as in all his works, the evidences of superior powers of observation strike one on every page.

The plates are excellent, and aid much in a realisation of the descriptive portion. Dr. Müller's artistic powers are so marked that we cannot but regret he has not furnished details of the form and structure of the perfect insects also, which would have greatly aided systematists; in fact the perfect insects are only alluded to in a casual manner.

Voyages of the Elizabethan Seamen to America. Thirteen Original Narratives from the Collection of Hakluyt, Selected and Edited, with Historical Notices, by E. J. Payne, M.A. (London: De La Rue and Co., 1880.)

WE do not quite understand Mr. Payne's reason for publishing this selection from Hakluyt's classical collection of voyages. The selection is, however, judicious, and cannot fail to be interesting, and at the same time instructive, to those who desire to become familiar with the first beginnings of English conquest in America. Mr. Payne's familiarity with the subject of British colonisation, as exemplified in his excellent little "History of European Colonies," specially qualifies him for making such a selection as the present. His brief Historical Introduction enables the reader to understand the special significance of the voyages contained in this volume. He

shows the various causes in operation at the time to instigate such voyages, causes mainly political and commercial. Other influences were however at work, not the least of which was "the total transformation which astronomy and geography had undergone" during the sixteenth century. The narratives here given are those of Hawkins's and Frobisher's three voyages, Drake's voyages of 1577 and 1585, Gilbert's voyage of 1583, Amadas and Barlow's voyage, 1584; Cavendish's first and last voyages, and Raleigh's voyage to Guiana. Prefixed to each narrative is a short historical introduction.

LETTERS TO THE EDITOR

[*The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts. No notice is taken of anonymous communications.*

The Editor urgently requests correspondents to keep their letters as short as possible. The pressure on his space is so great that it is impossible otherwise to ensure the appearance even of communications containing interesting and novel facts.]

Black Sheep

THE following extract of a letter from Mr. Sanderson of Chislehurst, who permits me to publish it, seems worth placing on record. It relates to the former frequent appearance of spotted or black sheep in the Australian flocks, as long as animals thus coloured were of use to man, although they were never, as far as Mr. Sanderson knows, separately bred from, and certainly not in his own case. On the other hand, as soon as coloured sheep ceased to be of use they were no longer allowed to grow up, and their numbers rapidly decreased. I have elsewhere assigned reasons for the belief that the occasional appearance of dark-coloured or piebald sheep is due to reversion to the primeval colouring of the species. This tendency to reversion appears to be most difficult quite to eradicate, and quickly to gain in strength if there is no selection. Mr. Sanderson writes:—"In the early days before fences were erected and when shepherds had charge of very large flocks (occasionally 4000 or 5000) it was important to have a few sheep easily noticed amongst the rest; and hence the value of a certain number of black or partly black sheep, so that coloured lambs were then carefully preserved. It was easy to count ten or a dozen such sheep in a flock, and when one was missing it was pretty safe to conclude that a good many had strayed with it, so that the shepherd really kept count of his flock by counting his speckled sheep. As fences were erected the flocks were made smaller, and the necessity for having these spotted sheep passed away. Their wool also being of small value the practice soon grew of killing them off as lambs, or so young that they had small chance of breeding, and it surprised me how at the end of my sheep-farming experience of about eight years the percentage of coloured lambs produced was so much smaller than at the beginning. As the quantity of coloured wool from Australia seems to have much diminished, the above experience would appear to be general." CHARLES DARWIN

The Nature of the Chemical Elements

DR. ARMSTRONG'S article in NATURE, vol. xxiii. p. 141, has brought to my mind some calculations I made more than a year ago to test a theory I had long previously entertained. Most of us who have paid much attention to the subject are agreed that the elements are capable, under exceptional circumstances, of profound chemical change. Mr. Lockyer is searching, with success as it appears, for contemporary evidence of this by examining the condition of the solar surface. The other line of evidence is historical, and turns mainly on the classification of the numerical values of chemical symbols. It is of course only with the latter that I have to deal.

The classifications proposed by Newlands and Mendelejeff are comprehensions of much similar preceding work. They appear to me to be faulty in two ways: (1) on account of the seriously large number of elements they wholly fail to include, and (2) because of the strong stress they lay upon arithmetical series of a rough *per saltum* character. As I do not know of any real case of *per saltum* chemical change, I do not think the elements should be classified on such a basis. What is wanted is a system capable of including—with exactness and not mere approximation—the whole of the elementary numbers; that system to be represented in the mathematical symbols of ordinary chemical change, and therefore free from a *per saltum* character. I have to a great extent succeeded in finding such a system, and the results of testing it at many points are as follow:—1. There is probably only one fundamental form of matter; and this, as has been previously supposed, yields our ordinary elements and many others by ordinary polymerisation. 2. Almost all the elementary numbers have been tried, and, with the exception of H and Cl, which are a little troublesome, they fall into order very exactly. 3. This order exhibits no discontinuity, and is similar to a case of ordinary chemical change. 4. There is clearly an upper limit to this order; in other words, elementary numbers of more than a certain magnitude appear to be impossible.

Sir B. C. Brodie's method is really a classificatory one; and I with others had been very desirous to read the Third Part of the Calculus, in which it was promised ampler play. It will be a matter for much regret if his premature death should have prevented this. But what he did publish was sound and sure: the first real symbols chemistry has yet enjoyed, and the only ones hitherto proposed whereby the process and the results of chemical change admit of unitary as well as kinetical representation.

EDMUND J. MILLS

Smokeless London

AS I hope soon to have an opportunity of reading a paper on this subject before a scientific audience I need not occupy your valuable space by replying to your correspondents of last week in detail. I may say however that the scheme has been carried out in practice at a gas-work to which I shall afterwards refer. When it was found that the apparatus for making gas on an extraction of six hours was insufficient for supplying the wants of the long winter evenings the distillation was stopped when gas had been removed to the extent of 5000 cubic feet per ton. The larger quantities obtained from the coal per unit of time and the superior illuminating power obtained per unit of volume tided over the difficulty and rendered the existing plant sufficient. No practical obstacles were discovered in discharging the retorts. I do not think the difference between an extraction of 5000 and 3333 cubic feet per ton would make a material change in this respect. Mr. Mattieu Williams points out a much more serious obstruction in the plethoric indifference of the gas companies. In reply to E. R. F. I may say that the fuel resulting from a uniform extraction of 3333 cubic feet per ton is practically smokeless if it is taken hot from the retorts and immediately quenched with water.

Westminster, December 27 W. D. SCOTT-MONCRIEFF

Colliery Explosions and Coal-Dust

ACCEPTING Mr. Galloway's view that in many mines the extent and destructiveness of colliery explosions are due to the distribution of coal-dust in the air, may I suggest the possibility of preventing the explosion from spreading beyond the sphere of the fire-damp by sprinkling the floors throughout, at certain regular intervals, with mineral oil? A shady road, with one such sprinkling, may be kept free from dust for several weeks during the summer, and the corridors of a mine, not being open to wind and rain, would of course remain wet for a longer period. A saucer filled with dust and treated with mineral oil will retain the oil for months even when exposed to sun and rain. The mixture of coal-dust and oil is quite uninflammable. The experiment may perhaps be worth trying in one of the drier coal-mines.

December 27 R. RUSSELL

Geological Climates

PROF. DUNCAN is under the impression that the claim of *Araucaria Cunninghami* to have flourished at Bournemouth during the Eocene, rests on "a bit of a leafy part of a tree," and that this bit is "squashed." The foliage is however abundant there, occurring almost wherever vegetable remains are found, from the east of Bournemouth Pier to half a mile beyond Boscombe. In one place, where a bluff is literally full of it, the disarticulated branchlets are perfect, and not in the least degree compressed. Again, the determination was not made by Prof. Haughton, but rests upon my statement that this foliage and that of *A. Cunninghami* cannot be distinguished one from the other. That it is Araucarian foliage I am perfectly satisfied; but whether the existing Australian species is identical and unmodified, must remain doubtful until other

organs besides foliage are found, it being by no means absolutely certain that because the foliage is identical the species are so. The discussion raised by Prof. Haughton, and continued by Prof. Duncan and Mr. Wallace, seems therefore hardly worth prolonging, since it is based upon an assumption that is only probably correct. But even if the identity were proved, a single species is not satisfactory evidence of former temperature.

I am indebted to Mr. Winslow Jones for the only information that I have yet obtained about the growth of either species in England. He recollects a small tree of *A. excelsa*, growing near the water's edge in a garden on the upper portion of Falmouth Harbour, which he believes died three years ago. He has seen flourishing trees at Naples, Cintra, Malta, and Algiers, but even Northern Italy seems beyond the range of successful cultivation. Of the two *A. Cunninghami* seems the more tender, though possibly its less symmetric growth may have excluded it from many gardens. In Madeira it grows generally best close to the sea and in sheltered places.

Lindley was mistaken in regarding the two species as one. All the needle-leaved (Eutacta) section of Araucaria are certainly closely allied, for the species, however distinct in other respects, possess two kinds of foliage, that of the young plants being identical in all: yet otherwise the species are clearly and distinctly marked off from each other.

With further regard to the identification of the Bournemouth foliage with Araucaria, I find that Massalongo[1] gives an excellent photograph of the same foliage from Chiavon, in North Italy, and of an immature cone consisting of 250 scales. Although existing Sequoias have cones with from 16 to 20 scales, Schimper says: "Il est sans aucun doute un *Sequoia* et peut-être identique au *S. Sternbergii*. Les cônes ont la plus grande ressemblance avec ceux du *S. gigantea*" (Pal. Végétale," vol. iii. p. 573). I am beginning to lose all faith in the so-called science of palæo-botany as worked out by our Teutonic brethren. Not only is the above quotation an absurdity, for which Heer is responsible, but I fail to see any good evidence to support the change made by Heer from *Araucaria*[2] *Sternbergii* to *Sequoia Sternbergii*. The foliage is more Araucaria-like than Sequoia-like, and has been found associated with an Araucaria cone, but never with any Sequoia cones. It has nothing to do with the Icelandic foliage, neither with the Upper Miocene foliage from Turin, nor that from Bilin nor Oeningen. The true *Araucaria Sternbergii* characterises a well-marked horizon, that of the Newer Eocene or Oligocene in Central Europe, and has been found at Barton in Hampshire; it differs from the Middle Eocene form (*A. venetus*, Mass.) of England and Italy in the needle-like leaves hugging more closely to the branchlet, as the latter differs in its turn from the Araucaria of the Grès du Soissonnais, which has needles very widely opened out. This progressive change may have taken place *pari passu* with the changing climate. At Sheppey, where foliage is plentiful, I have met with a beautifully-preserved axis of an Araucaria cone with the basal scales attached, exactly as we find them in the existing species.

Now with regard to Mr. Wallace's letter, I pointed out in NATURE, vol. xix. p. 126, that the Tertiary fossil plants, even of the Eocene, require at most an increase in temperature of 20°, and that the land connection between Europe, Greenland, and America, which there is reason to suppose existed then, would, by shutting out Arctic currents, have produced more than the required increment. If this theory appeared for the first time in my article, however clumsily I may have worded it, and if it has been of use to Mr. Wallace, it is only fair that the fact should be acknowledged, while if it has escaped his notice he will perhaps pardon my now drawing his attention to it. At the same time the publication of the Tertiary flora of North-East Siberia, which I had not then seen, and of Saghalien, has modified the views I put forward in a manner which I trust I may shortly find time to explain.

J. STARKIE GARDNER

Chalk

MR. WALLACE'S theory that chalk was deposited in comparatively shallow water requires careful examination before it is accepted by geologists. I do not think he has given sufficient evidence to bear out his views which are necessary to his theory of continents.

Mr. Wallace cites the resemblance between chalk and Globigerina-ooze, namely—

The similarity of the minute organisms found to compose a considerable portion of both deposits; several species of Globigerina appearing to be identical in the chalk and the modern Atlantic mud; the presence of Coccoliths and Discoliths in both formations; the abundance of Sponges in both; the presence of *Porifera vitrea*, the nearest representative of the Ventriculites of the white chalk; the resemblance of the forms of Echinoderms; and without attempting to reconcile these with a shallow sea-deposit, he proceeds to state the case on the other side. This consists of the difference in analysis between chalk and Globigerina-ooze, the former containing more carbonate of lime and less alumina, the presence of silica in the Globigerina-ooze being perhaps counterbalanced by the flints in the chalk. The greater proportion of alumina certainly points to different conditions, which Mr. Wallace considers to be that chalk is the very fine mud produced by the disintegration of coral-reefs, and mentions a deposit resembling chalk at Oahu in the Sandwich Islands and the deposit in several growing reefs, without however attempting to show that there is any probability that the remains found in these would bear any resemblance to the Sponges and Echinoderms of the chalk, or why we find no remains of these Cretaceous coral-reefs.

Mr. Wallace does not state in what the greater resemblance between chalk and Globigerina-ooze of shallow over deep water consists, but he looks on it as "weighty evidence."

Mr. Gwyn Jeffries, he says, finds all the Mollusca of the chalk to be shallow-water forms, many living at forty to fifty fathoms, some confined to still shallower waters, while deep-sea forms are absent. The late Dr. S. P. Woodward considered that Ammonites probably lived in water not over thirty fathoms; and these facts are as difficult to reconcile with Mr. Wallace's views that chalk was deposited in a sea of not over a few thousand feet as in a deeper sea.

The rareness of corals and absence of coralline beds of the age of the Lower or Upper Chalk is an important objection to the theory that chalk was deposited similarly to the Oahu chalk, the beds of Maestricht and Faxoe being above the chalk, and the former are not even conformable with it.

The point I think is still an open one, whether we shall accept Mr. Wallace's views that chalk was deposited in a comparatively shallow sea and not very far from land, or in a deep sea, the immense break between the chalk and Eocene beds giving ample time for very considerable alteration to have taken place in the disposition of land in the interval. I send this letter in the hope that a discussion on the point may elicit new facts bearing on the subject.

S. N. CARVALHO, JUN.

8, Inverness Terrace, Kensington Gardens, W.

On Estimating the Height of Clouds by Photography and the Stereoscope

THE great practical value of meteorological science and the desirability of extending its usefulness by the collection of data relating to atmospheric current will perhaps be sufficient excuse for asking attention to anything likely to promote this end.

In studying the currents and other peculiarities of the atmosphere a method of estimating the height, motion, and character, as also the position with respect to each other, of each stratum of cloud, is a requirement of almost paramount importance, the value of the means employed being proportional to the number of particulars provided in its record, and the facility with which any set of observations can be compared to another at any future period. With such ever-changing subjects as clouds in constant motion, and having no strongly-defined marks, the use of theodolites is almost out of the question, and the sextant and mirror process for similar reasons would be a very tedious operation.

These considerations have induced me to endeavour to make use of photography and the stereoscope, the former to secure a couple of simultaneously-exposed photographs at the extremities of a base line, and the latter to observe them reproduced apparently solid for the respective distances of the points composing the picture to be measured when superimposed on a scale of distances and placed in it. The base line is thus practically reduced to the width of the eyes, and the difficulties arising from motion eliminated.

The recording apparatus consists of a base 50 or 100 feet long, constructed of wood and turning on a pivot at the centre of its length, its extremities being suitably supported by a framework of wood or other material upon which they could easily roll. The small cameras for the ends of this are each to be hinged at the back of its base to a second board having a graduated quadrant and rackwork erected from one of its sides for adjusting

[1] "Specimen photographicum." Verona, 1859. Plate xxi.

[2] Actually described as Araucarites, a useless modification in this instance.

the camera to any degree of altitude. These supplementary boards are then pivoted at the centre of part of a divided circle, previously inlaid in the wood at the extremities of the base line, in such a manner that a line passing through the axis of the lenses would cut the pivots. The cameras thus furnished can be adjusted with ease to any vertical or horizontal angle. These angular adjustments of the two instruments must always coincide, with the slight exception that the horizontal ones must make internal angles with the base included between them, or, in other words, the lenses of both require to be directed to a point opposite to the centre of the base line.

The cameras also require their rapid exposing shutters to be electrically connected, to ensure the pair of sensitive plates being impressed at the same instant, and each dark slide employed to have a fine wire strained at its centre from top to bottom immediately in front of the prepared plate, and as close as possible to it without touching. The transparent lines produced in the developed negatives by these wires will constitute the zero of distance of any pair, and during the operation of reading off must be made to agree with similar ones on the scale of measurements obtained as follows:—

Upon a large cardboard rule a number of squares in fine black lines, one inside the other, and each one slightly out of the centre of its predecessor to the right hand, the outside square being then divided with a line at a tenth part of its diameter to the left of its centre. This line will indicate the zero of the scale. After placing a distinguishing mark or number in the corner of every square for purposes of identification, the cardboard will be ready to be photographed and reduced at the same time to the intended size of the cloud negatives. Two transparent positives copied from this and observed when placed side by side in a suitable stereoscope with the edges representing the left-hand one of the cardboard together, will appear in that instrument with the lines composing the zero only a few inches away, and the squares as a succession of vertical planes commencing some distance from that and receding from the eye in the order of greater to less, each one representing its own distance in space.

To find the value of these distances it will be necessary to focus the two cameras upon some terrestrial objects whose distances can be measured by any of the known methods, and negatives taken. The two resulting landscapes, when placed in the stereoscope, each superimposed face to face upon its respective scale, and the fine vertical lines of the whole made to occupy one apparent distance, an operation offering but little difficulty, every object or point of the landscape will be found to stand out in the vertical plane suited to its own distance, the relation between them being noted for the values found by measurement of the one to be marked upon the other. As a scale prepared thus would be of no value for any other angle at which the cameras might be placed, it would be most convenient to make use of two or three angles only, more being quite unnecessary, and prepare a scale for each, or one with a reference table of values for the respective angles would suffice. Again, in respect of altitudes. As the terrestrial measurements would only be absolutely accurate for those of clouds in the zenith, or of them, if it were possible, from the earth's centre in any direction, the tables of reference would have to include calculated corrections for altitude, or the graduations could be valued for the most useful degrees by experimental means.

It will be gathered from the above that the constancy of length of the base line can be ascertained, and corrected if necessary, by taking a couple of views of the same landscape for comparison with the preceding pair; slight fluctuations of length would not however be of much consequence in dealing with the comparatively coarse measurements of thick masses of cloud floating in so short a distance as the few miles of atmosphere capable of forming them consists.

To ascertain the height of clouds photograph a pair of negatives, and place these in the stereoscope with a pair of scale plates agreeing with the angle at which they were taken, and adjust as for the landscapes described above. The data required may then be read off by noting the vertical plane each stratum occupies.

Prints of these negatives should afterwards be made for the particulars of height, direction of motion of the respective layers, point of compass, wind rate, state of barometer, thermometer, and general remarks upon the weather, to be recorded upon them for comparison or circulation.

Meteorological observatories fitted with such an addition to their present splendid collection of instruments would have their powers of dealing with the atmosphere and weather changes greatly reinforced.

JOHN HARMER

Wick, near Arundel

Correction of an Error in "Island Life"

MY friend Dr. Günther has kindly called my attention to an extraordinary error at p. 322–323 of my "Island Life," where I state that the Loch Killin Charr (*Salmo Killinensis*) inhabits a lake in Mayo County, Ireland; instead of a small lake in Inverness-shire, 2000 feet above the level of the sea, as given in Dr. Günther's original description in the *Proceedings* of the Zoological Society, 1865, p. 698. On referring to my MSS. notes for this part of my work, I find that the habitat was first correctly given, but subsequently scored out and altered to the erroneous Irish locality! Why this was done I cannot now discover; and I can only regret that I should have fallen into so palpable an error, and request such of the readers of NATURE as possess my book to make the necessary alterations.

ALFRED R. WALLACE

Natural Science for Women

WILL you allow me to supplement your kindly reference to the instruction in physical science given to women in Bedford College, London, by the statements that for the last two sessions a class in biology has been conducted there by Mr. Charles Stewart of St. Thomas's Hospital Medical School. The course of study is in every sense a practical one, with special reference to the Preliminary Scientific and First B.Sc. examinations at the University of London, and the best testimonial to the excellence of the instruction in these various subjects is furnished by the remarkable success during the present year of the Bedford College pupils at the University examinations, a success not less marked in the Science than in the Arts examinations.

ALFRED W. BENNETT

Movements of Leaves

A YEAR ago we had in our conservatory a healthy young plant of *Acacia mollissima*. It bore no flowers, but consisted of a simple axis adorned with the soft feathery leaves of its genus, which closed up at night. Our gardener however thought it would improve in appearance if it could be made to bear a few branches; and with that view he cut it back. His end was achieved: a new stem shot up from the section, and graceful limbs were thrown out in turn by it. But along with this a strange result followed: the fresh leaves borne by the new stem and by the branches now closed at night, while the old leaves below the section ceased to do so. These lower leaves have long since fallen off, but the upper ones kept to their habit, and at the present time all fold up at dusk save a few of the very oldest, which only partially shut, or, in one case, do not shut at all. When our plant was cut back it stood three feet high; now it stands seven: which shows that the vigour of the plant as a whole in no wise diminished by the operation.

Chislehurst, December 23 M. L. ROUSE

ON DUST, FOGS, AND CLOUDS[1]

DUST, fogs, and clouds seem to have but little connection with each other, and we might think they could be better treated of under two separate and distinct heads. Yet I think we shall presently see that they are more closely related than might at first sight appear, and that dust is the germ of which fogs and clouds are the developed phenomena.

This was illustrated by an experiment in which steam was mixed with air in two large glass receivers; the one receiver was filled with common air, the other with air which had been carefully passed through a cotton-wool filter and all dust removed from it. In the unfiltered air the steam gave the usual and well-known cloudy form of condensation, while in the filtered air no cloudiness whatever appeared. The air remained supersaturated and perfectly transparent.

The difference in the behaviour of the steam in these two cases was explained by corresponding phenomena,

[1] Abstract of a paper read to the Royal Society of Edinburgh, December 20, by Mr. John Aitken. Furnished to NATURE by the Council of the Society.

in freezing, melting, and boiling. It was shown that particles of water vapour do not combine with each other to form a cloud-particle, but the vapour must have some solid or liquid body on which to condense. Vapour in pure air therefore remains uncondensed or super-saturated, while dust-particles in ordinary air form the nuclei on which the vapour condenses and forms fog or cloud-particles.

This represents an extremely dusty condition of the air, as every fog and cloud-particle was formerly represented by a dust-particle, which vapour by condensing upon it has made visible. When there is much dust in the air but little vapour condenses on each particle, and they become but little heavier, and easily float in the air. If there are few dust specks each gets more vapour, is heavier, and falls more quickly.

These experiments were repeated with an air-pump, a little water being placed in the receiver to saturate the air. The air was then cooled by slightly reducing the pressure. When this is done with unfiltered air a dense cloudiness fills the receiver, but when with pure air no fogging whatever takes place, there being no nuclei on which the condensation can take place. In this experiment, and in the one with steam, the number of cloud-particles is always in proportion to the dust present. When the air is nearly pure and only a few dust-particles present, then only a few cloud-particles form, and they are heavy and fall like fine rain.

The conclusions drawn from these experiments are: (1) that whenever water vapour condenses in the atmosphere it always does so on some solid nucleus; (2) that dust-particles in the air form the nuclei on which the vapour condenses; (3) that if there was no dust there would be no fogs, no clouds, no mists, and probably no rain, and that the supersaturated air would convert every object on the surface of the earth into a condenser on which it would deposit; (4) our breath when it becomes visible on a cold morning, and every puff of steam as it escapes into the air, show the impure and dusty condition of our atmosphere.

The source of the fine atmospheric dust was then referred to, and it was shown that anything that broke up matter into minute parts would contribute a share. The spray from the ocean, when dried and converted into fine dust, was shown to be an important source. Meteoric matter also probably contributed a proportion. Attention was then directed to the power of heat and combustion as a source of this fine dust.

It was shown that if there is much dust then each particle only gets a little vapour condensed upon it, that when the particles are numerous they become but little heavier, and easily float in the air, and give rise to that close-packed but light form of condensation which constitutes a fog, and therefore whatever increases the amount of dust in the air tends to increase fogs, and that when the dust-particles are not so numerous the cloud-particles are larger and settle down more quickly.

It was shown that by simply heating any substance, such as a piece of glass, iron, brass, &c., a cloud of dust was driven off, which, when carried along with pure air into the experimental receiver, gave rise to a dense fog when mixed with steam. So delicate is this test for dust that if we heat the one-hundredth of a grain of iron wire the dust driven off from it will give a distinct cloudiness in the experimental receiver, and if we take the wire out of the apparatus and so much as touch it with our fingers and again replace it, it will again be active as a cloud-producer. Many different substances were tried, and all were found to be active fog-producers. Common salt is perhaps one of the most active.

Heat, it is well known, destroys the motes in the air, and it might be thought that flame and other forms of combustion ought to give rise to a purer air. Such however is not the case. Gas was burned in a glass receiver, and supplied with filtered air for combustion, and it was found that the products of combustion of pure air and dustless gas gave rise to an intensely fog-producing atmosphere. It may be mentioned here that the fog-producing air from the heated glass, metals, and burning gas were each passed through the cotton-wool filter, and the air was in all cases made pure, and did not give rise to cloudiness when mixed with steam

It will be seen that it is not the dust motes which are revealed to us by a beam of sunlight when shining into a darkened room, that form the nuclei of fog and cloud-particles, as these may be entirely removed by heat, and yet the air remain active as a cloud-producer. The heat would seem to break up the larger motes which reflect the light into smaller and invisible ones. When speaking of dust, it is to these infinitesimally small and invisible particles we refer. The larger motes which reflect the light will no doubt be active nuclei, but their number is too small to have any important effect.

It is suggested, and certain reasons are given for sup posing, that the blue colour of the sky is due to this fine dust.

Other experiments were made to test the fog-producing power of the air and gases from different sources. The air to be tested was introduced into the experimental receiver and mixed with steam, and the relative densities of the fog produced were noted. It was always found that the air of the laboratory where gas was burning gave a denser fog than the air outside, and that the air outside varied, giving less fog during wet than during dry weather. The products of combustion of gas burned in a Bunsen flame, a bright flame, and a smoky flame, were all tested and found to be about equally bad, and all much worse than the air in which they were burned. Products of combustion from a clear fire and from a smoky one gave about equal fogging, and both much worse than the air of the room.

Experiments were made by burning different substances. Common salt when burned in a fire or in alcohol flame gave an intensely fog-producing atmosphere, but burned sulphur was the most active substance experimented on. It gave rise to a fog so dense it was impossible to see through a thickness of 5 cm. of it.

The vapours of other substances than water were tested to see if they would condense in the cloud form without nuclei on which to deposit. All the substances experimented on, which included sulphuric acid, alcohol, benzole, and paraffin, only gave a cloudy condensation when mixed with ordinary unfiltered air, and remained perfectly clear when mixed with filtered air, all these acting like water vapour.

Before referring to fogs, which have now become so frequent and aggravated in our large towns, it was pointed out that caution was necessary in applying the results of the experiments.

The conditions of a laboratory experiment are so different, and on so small a scale, that it is not safe to carry their teaching to the utmost limits and apply them to the processes which go on in nature. We may, however, look to the experiments for facts from which to reason, and for processes which will enable us to understand the grander workings of nature.

It having been shown that vapour, by condensing on the dust-particles in the air, gives rise to a fogging, the density of which depends on the amount of fine dust in the air; the more dust the finer are the fog-particles, and the longer they remain suspended in the air. It having been also shown that all forms of combustion, perfect and imperfect, are producers of fog nuclei, it is concluded that it is hopeless to expect that, adopting more perfect forms of combustion than those at present in use, we shall thereby diminish the frequency, persistency, or density of our town fogs. More perfect combustion will, however, remove the pea-soup character from the fogs

and make them purer and whiter, by preventing the smoke which at present mixes with our town fogs and aggravates their character, and prevents them dissolving when they enter our rooms. Smoke descends during a fog, because the smoke particles are good radiators, and soon get cooled and form nuclei on which the water vapour condenses. The smoke thus becomes heavier and falls. This explains why falling smoke is often a sign of coming rain. It indicates a saturated condition of the atmosphere.

Sulphur when burned has been shown to be an intensely active fog-producer. Calculation shows that there are more than 200 tons of sulphur burned with the coal every winter day in London, a quantity so enormous as quite to account for the density of the London fogs. It is suggested that some restriction ought to be put on the amount of sulphur in the coal used in towns.

Before utterly condemning the smoke and the sulphur, it was pointed out that it would be necessary thoroughly to investigate and fully to consider the value of smoke as a deodoriser, and also the powerful antiseptic properties of the sulphurous acid formed by the burning sulphur. The air during fogs is still and stagnant. There is no current to clear away the foul smells and deadly germs that float in the air, which might be more deadly than they are, were it not for the suspended soot and burned sulphur. We must therefore be on our guard lest we substitute a great and hidden danger for an evident but less evil.

ON THE SPECTRUM OF CARBON

ALTHOUGH fifteen years have passed since the possibility of one substance possessing more than one spectrum was first suggested by Plücker and Hittorf, the question of the existence of double spectra cannot yet be considered as decided. One of the elements to which multiple spectra have been attributed is carbon, which was at one time supposed to possess four different spectra: of these one has been shown to be due to oxide of manganese, a second to oxides of carbon, the origin of a third (obtained only from oxides of carbon) has hardly been discussed (though it may prove to be one of the true carbon spectra), and the other "carbon" spectrum—the best known of all—is the one first attributed to carbon by Attfield, but ascribed to acetylene by Ångström.

In a paper read before the Royal Society, and of which an abstract is given in NATURE, vol. xxii. p. 620, Professors Liveing and Dewar describe experiments to prove that this spectrum is that of a hydrocarbon, and not of carbon itself; and also that certain blue bands, best seen in the flame-spectrum of cyanogen, are due to compounds of carbon and nitrogen, and not to carbon itself. They attribute to hydrocarbon (amongst others) the yellowish-green group, which we will call γ, of wave-lengths from about 5635 to 5478, and the emerald-green group, which we will call δ, of wave-lengths from about 5165 to 5082; and they attribute to nitro-carbon the two blue groups of wave-lengths 4600 to 4502 and 4220 to 4158, which we will call θ and ζ respectively.

As these result are directly opposed to my own experience, I have thought it necessary to repeat two of the experiments described in my paper on the carbon spectra in the *Philosophical Magazine* for October, 1869, under such conditions as to exclude (as far as lay in my power) all trace of hydrogen in the one case, and of nitrogen in the other.

The difficulty of supposing carbon to be present in the state of vapour at any temperature which we can command seems to be the chief reason why so many investigators think it necessary to attribute the spectrum in question (with experimental evidence or without it) to compounds of carbon. I am not aware that Ångström ever gave any experimental proof of his assertion that this spectrum was caused by acetylene.

On the other hand, the evidence that the spectrum is due to carbon is that first stated by Attfield, that if these lines "are absent in flames in which carbon is absent, and present in flames in which carbon is present," if they are "observable equally in the flame of the oxide, sulphide, and nitride as well as in the hydride of carbon," and if "present whether the incandescence be produced by the chemical force, as in burning jets of the gases in the open air or by the electric force, as when hermetically-sealed tubes of the gases are exposed to the discharge of a powerful induction-coil," then they "must be due to incandescent carbon vapour"; and if this is borne out by experiment the conclusion that the lines are due to carbon (as gas, liquid or solid) cannot be resisted, whatever may be the apparent impossibility of volatilising or even liquifying carbon, even by the most powerful current of electricity directed through it.

We must bear in mind how very small a quantity of a gas is often sufficient to give us a spectrum, and when the carbon spectrum is obtained by the decomposition of olefiant gas or cyanogen by passing sparks through the gas, the carbon certainly exists as gas in the compound which is decomposed, and before the liberated atoms unite together to form the molecules of the solid, there is surely no impossibility in their existing for the moment as gas—as gaseous carbon.

On an examination of Professors Liveing and Dewar's paper to ascertain the experimental evidence upon which the bands γ and δ are attributed to hydrocarbon and not to carbon itself, we find it stated that "the green and blue bands characteristic of the hydrocarbon flame seem to be always present in the arcs, whatever the atmosphere. This is what we should expect if they be due, as Angström and Thalèn suppose, to acetylene, for the carbon electrodes always contain, even when they have been long heated in chlorine, a notable quantity of hydrogen."

Since then it is impossible to completely expel hydrogen from the carbon-poles, we must reject all the experiments in which the electric arc was observed in atmospheres of different gases, although "the green and blue hydrocarbon bands were seen more or less in all of them."

Turning then to other methods of producing the spectrum, we find it stated that in the flame of carefully-dried cyanogen "the hydrocarbon bands were almost entirely absent" (they should have been *entirely* absent); "only the brightest green band was seen, and that faintly." Hence we are to infer, I suppose, that the bands γ and δ, so brilliant in the flame of cyanogen in air or oxygen, are due to the accidental presence of hydrogen (see the extract from Morren's paper, NATURE, vol. xxii. p. 7. Dibbits also speaks of this spectrum as "by far the most magnificent" he has seen).

Next we have the experiment of burning hydrocyanic acid, in which, as we have hydrogen present, we expect to find the hydrocarbon bands brilliantly developed. But we find the result stated as "very much the same as that of cyanogen." The flames of hydrogen and sulphide of carbon, and of hydrogen and carbonic oxide, do not give the hydrocarbon bands (their spectra being continuous); a mixture of hydrogen and carbon tetrachloride gives them faintly, and a mixture of hydrogen and chloroform gives them strongly.

In all this we have no *proof* of the point in question, nor even any special probability that the bands are due to hydrocarbon; and yet, in the face of experiments in which the spectrum is obtained from cyanogen, when care has been taken to exclude hydrogen, we are asked to attribute the bands to the hydrocarbon formed by combination with some trace of hydrogen (as water or otherwise), supposed to be present as impurity. In the same way the presence of the bands θ and ζ obtained under circumstances when nitrogen has been intentionally excluded, is to be explained by "the extreme difficulty of

removing the last traces of air." So that in the case of cyanogen with a trace of hydrogen present, the spark persists in giving us the spectrum of hydrocarbon; and when we have naphthalin with a trace of nitrogen present, it gives us the spectrum of nitrocarbon!

Attfield states that the spectrum in question is obtained from *pure dry* cyanogen. "The ignition of the gases having been effected in air, it was conceivable that hydrogen, nitrogen, or oxygen had influenced the phenomena. To eliminate this possible source of error the experiments were repeated out of contact with air. A thin glass tube one inch in diameter and three inches long, with platinum wires fused into its sides and its ends prolonged by glass quills having a capillary bore, was filled with *pure dry* cyanogen, and the greater portion of this gas then removed by a good air-pump. Another tube was similarly prepared with olefiant gas. The platinum wires in these tubes were then so connected with each other that the electric discharge from a powerful induction-coil could pass through both at the same time. On now observing the spectra of these two lights in the simultaneous manner previously described, the



characteristic lines of the hydrocarbon spectrum were found to be rigidly continued in that of the nitrocarbon. Moreover, by the same method of simultaneous observation the spectrum of each of these electric flames, as they may be termed, was compared with the corresponding chemical flames, that is with the oxyhydrocarbon and oxynitrocarbon jets of gas burning in air. The characteristic lines were present in every case."

"The spectrum under investigation having then been obtained in one case when only carbon and hydrogen were present, and in another when all elements but carbon and nitrogen were absent, furnishes to my mind sufficient evidence that the spectrum is that of carbon."

Morren also adopted this method of producing the spectrum by taking the spark of an induction coil in a sufficiently rapid current of pure cyanogen at atmospheric pressure.

I have again repeated this experiment with cyanogen under conditions which would seem to ensure that the gas should be dry (see also *Phil. Mag.*, 1875).

The cyanogen was prepared by heating pure cyanide of mercury, which was finely powdered and placed in a piece of combustion-tubing (*a*) drawn out at both ends. In this it was repeatedly heated to the temperature of incipient decomposition whilst a current of dry air was drawn over it. One end of the tube was then closed by fusion at the point *g*, and the other bent round and fitted, as shown in the figure, to a U-tube (*b*) containing phosphoric anhydride—the discharge-tube *c* was interposed between this U-tube and a second U-tube *d* also containing phosphoric anhydride, the other branch of which was connected to one end of a vertical tube *e* of more than thirty inches in length, the lower end of which passed into mercury contained in the bottle *f*, the upper portion of which could be exhausted by means of the air-pump. The connections with the U-tube were made by means of perforated india-rubber stoppers, and the joints were surrounded during the experiment by melted paraffin.

The apparatus having been exhausted, the mercuric cyanide was heated till the apparatus was filled with cyanogen at atmospheric pressure; it was then again exhausted and again filled with cyanogen. After having been thus exhausted and re-filled five or six times, the spectrum of the spark between the wires at *c* was examined at various pressures. The spectrum figured in my paper in the *Philosophical Magazine* for October, 1869, was obtained, the groups γ and δ, with which alone we are at present concerned, being the brightest in the whole spectrum. Next careful search was made for the red hydrogen line. The cross-wires of a one-prism spectroscope were accurately adjusted to the red line, as seen in a hydrogen vacuum tube, and the spectroscope was then directed upon the spark in the cyanogen. No trace of the line could be observed.

A second experiment was devoted to the examination of the spark in an atmosphere of naphthalin vapour, from which nitrogen had been excluded as far as possible, in order to ascertain whether the bands ζ and θ, which Professors Liveing and Dewar attribute to cyanogen, would be produced. Professors Liveing and Dewar are somewhat in error in saying that I laid much stress on the occurrence of these bands in carbonic oxide. They were never obtained very brilliantly from carbonic oxide (except under pressure), but they are obtained brilliantly from a naphthalin vacuum tube. I have obtained them also from a vacuum tube containing pure marsh-gas (my note-book remarks "θ very bright"), and as confirmation by an independent observer, I would remark that Plücker maps them in the spectrum of a vacuum tube containing *methyl*.

The vacuum tube in this second experiment contained pure solid naphthalin fused on the sides of the tube; this was placed in position so that the upper end passed through one hole in an india-rubber stopper into a flask filled with carbon dioxide; a vertical tube of thirty inches length passed through the second hole in the stopper of the flask, and its lower end dipped below mercury. The whole of the vacuum tube except the lowest portion was surrounded by a wider tube containing melted paraffin.

When the apparatus had been arranged, the experiment was commenced by passing a rapid current of carbonic acid through the vacuum tube, so as to fill the flask and escape through the mercury. After passing the gas for a considerable time, the lower end of the tube was closed by fusion, the naphthalin all melted down into this end, where it was made to boil violently, while the paraffin was maintained at a temperature of about 220° C. After the current of naphthalin vapour had lasted some time, the upper end of the tube was closed by fusion, the tube removed and cooled, and its spectrum examined. It gave a spectrum in which the groups ζ and θ were plainly seen.

It is to be hoped that some independent observer will repeat these [illegible]s. so as finally to settle the question of the [illegible] bands of what I must still call the "c

W. M. WATTS

THE INDO-CHINESE AND OCEANIC RACES—TYPES AND AFFINITIES

I.

THE ethnological area here under consideration comprises the south-eastern corner of the Asiatic mainland, and nearly the whole of the Indian and Pacific Oceans. Of the three great divisions of the human family—the black, yellow, and fair—the two former alone are usually supposed to be represented in this region, the black by the Australians, extinct Tasmanians, Melanesians or Papûans, and Negritos, the yellow by the Indo-Chinese (Annamese, Siamese, Burmese, &c.), of the mainland, and the so-called "Malayo-Polynesians" of Oceanica. But it will be one of the main objects of these papers to show that room must here be henceforth made for the third also, and that most of the difficulties associated with the mutual classification of the other two are due to the omission or neglect of this third factor in the problem. It has long been an accepted doctrine of ethnologists that this fair or Caucasian type, using the term "Caucasian" in Blumenbach's sense, is limited by some mysterious law of nature or providential arrangement to the western portion of Asia, to the northern section of its African, and to nearly the whole of its European peninsula. But anthropology is a very young science, and as facts accumulate and knowledge expands, many of its conclusions too hastily arrived at will have to be modified or abandoned. The time seems to have already arrived for very materially modifying the views hitherto entertained regarding the geographical limits of the Caucasian species, which, instead of being confined to a western corner of the Old World, will be found to have been diffused in prehistoric times eastwards to within 2,500 miles of the American continent.

But the acceptance or rejection of this new doctrine will of course depend largely on the various senses in which the terms type, species, race, are understood by the different monogenist and polygenist schools. For the orthodox monogenist these words can obviously have but a relative meaning, for if all are necessarily sprung of one created pair, all have also necessarily become differentiated into the now existing types, these types thus sinking to the category of mere varieties. But to polygenists of all shades such expressions may naturally convey an absolute sense, the fundamental species now existing having presumably been evolved in so many independent centres, and for these the only question will be in *how many* centres? Yet even they cannot consistently base their theory on the eternal fixity of species, for they are all of them otherwise, and necessarily believers in evolution. They must therefore admit the abstract possibility of such comparatively slight transformism as the development of the dark from the yellow, the fair from either, lank from woolly hair, dolichocephaly from brachycephaly, the tall stature of the Tehuelch Patagonian from the pygmy Akka, or the reverse of all these processes. They may say that, assuming independent development from various anthropoids, such transformism is unnecessary to account for the present state of things; but they can never deny its inherent possibility, for it still remains a very trivial modification compared with the evolution of any given human from any given anthropoid type. Nor will they deny that in general differentiations of this sort are far more easy and explicable than independent growths, which involve so much more fundamentally radical changes. Consequently unorthodox monogenism, that is monogenism not starting from a created pair, but from one evolutionary centre, seems more rational and philosophic than any conceivable form of polygenism. This view seems in other respects to harmonise best with the actual conditions, and an effort has accordingly been made to give it expression in the subjoined definition of species, which differs in some important respects from those hitherto proposed: *Species is an aggregate of units resembling each other in all salient points, producing offspring of the same type in the same surroundings, or of continuously modified type in continuously modified surroundings, and themselves evolved of previous species similarly modified indefinitely.* Thus any given species or race (terms practically identical when used with scientific precision) exists only for the time being, is not and cannot be permanent, for it has become what it is by slow modification under slowly modified outward conditions, has had a beginning, may have an end. The best vindication of this truth is the geological record, which can only be explained either with Cuvier by the unwarranted assumption of successive fresh creations, or with common sense by regarding type or species as relative, not absolute concepts. Between the two views there seems to be no logical middle term.

It is therefore in this relative sense only that race or species are here to be understood, and in this sense it will be seen that all the three most fundamental types of mankind have existed from the remotest times in the wide area above defined. With their diverse modifications and intercrossings these three types form altogether seven main groups, which it will be convenient to take *seriatim* in the order adopted in the subjoined

General Scheme of Indo-Chinese and Oceanic Races

A.—DARK TYPES

I. NEGRITOS: Aetas; Andamanese; Samangs; Kalangs; Karons.

II. PAPÛANS: Central branch—Papûans Proper. Western branch—Sub Papûans West (so-called "Alfuros"). Eastern branch—Sub-Papûans East (Melanesians).

III. AUSTRAL: Australians; Tasmanians (?)

B.—CAUCASIAN TYPE (Fair and Brown)

IV. CONTINENTAL BRANCH: Khmêr or Cambojan Group.

V. OCEANIC BRANCH: Indonesian and Sawaiori or Eastern Polynesian Groups.

C.—MONGOLIAN TYPE (Yellow and Olive Brown)

VI. CONTINENTAL BRANCH: Indo-Chinese Group.

VII. OCEANIC BRANCH: Malayan Groups.

A—DARK TYPES

I. THE NEGRITOS: *Aetas; Andamanese; Samangs; Kalangs; Karons*

Of the three divisions of this type shown in our scheme the Negrito is probably the most primitive. It seems to have formed the aboriginal element in South-East Asia and Malaysia at a time when the Archipelago was still connected with the mainland; but it is now represented only in a fragmentary way by the wild tribes in the Philippines collectively known as Aetas, Aitas, or Itas, the so-called "Mincopies" of the Andaman Islands, the little-known Samangs of Malacca, probably the Karus or Karons[1] of the Arfak Hills behind Geelvink Bay, New Guinea, and a few surviving members of the Kalangs of East Java. From a number of specimens recently brought to Europe, the osteology of the Aetas and Andamanese has been carefully studied, the former by Virchow in Germany, the latter by Prof. Flower in England, with parallel and in many respects identical results. Virchow[2] describes the Aetas as "a brachycephalous race differing altogether from the Papuans and Australian Negroes, and no less so from the African Negroes." He adds that they are "strongly prognathous," the profile of some

[1] Described by M. Raffray ("Tour du Monde," April 26, 1879) as essentially distinct from the Papûans. "Ce ne sont pas des Papous, mais bien des Negritos, plus semblables aux sauvages aborigènes des Philippines qu'aux Papous Mélanésiens qui les entourent."

[2] In "Correspondenz-Blatt der deutschen Gesellschaft für Anthropologie," &c., 1872, p. 58.

crania consequently presenting an almost "orang-utan physiognomy." So also Prof. Flower[1] tells us that the Andamanese cranium is "as distinct as possible" from the Melanesian, and on all the available evidence he seems disposed to regard these islanders as "representing an infantile, undeveloped or primitive form of the type from which the African Negroes on the one hand, and the Melanesians on the other . . . . may have sprung." The relations of the Negritos to the Papûans, long a vexed question in anthropology, may thus be regarded as finally settled by the most competent authorities. One

Fig. 1.—Ape-like Type, Java. Ardi of Buitenzorg.

doubtless, originally, they must now be regarded as two distinct species in the relative sense involved in our definition of that term. C. Staniland Wake also points out another important feature in which the two races differ. The Papûans proper, and especially the Melanesians of Fiji, New Caledonians and Solomon Islanders, are frequently furnished with well-developed beards, whereas the Andamanese and all other true Negritos, are absolutely beardless. "The absence of the beard seems to be characteristic of all the Negrito peoples, and this trait may in my opinion be safely added to the conclusions of de Quatrefages touching the small black races of the Archipelago."[2]

Fig. 2.—Andamanese Type. Mourning Head-dress.

Fig. 3.—Australian Type. Woman in Mourning.

The ape-like appearance of the Aetas, already spoken of by de la Gironnière, and now insisted on by Virchow, receives a startling illustration from the accompanying portrait (Fig. 1) of a Javanese Kalang named Ardi,

[1] In paper "On the Osteology and Affinities of the Natives of the Andamanese Islands," in *Journal* of Anthropological Institute, November, 1879, pp. 132-3.

[2] *La barbe considérée comme caractère de races*, in *Rev. d'Anthrop.*, an. 13, 1880.

recently if not still employed as a workman in the famous Buitenzorg (Sans-Souci) Botanic Gardens near Batavia. Here he was seen by C. B. H. von Rosenberg in 1871, and reproduced at p. 569, vol. iii. of that naturalist's work on the "Malay Archipelago" from an original photograph by van Musschenbroek, which has also been

Fig. 4.—Full-blood Papûan Type. North-west Coast New Guinea.

figured on an enlarged scale in Dr. A. B. Meyer's monograph on the "Kalangs of Java." Notwithstanding its startling ape-like appearance all doubt as to the correctness of the portrait is removed by the independent testimony of von Rosenberg and van Musschenbroek, the latter of whom informs me through Prof. Veth of Leyden

Fig. 5.—Full-blood Papûan Type. North-west Coast New Guinea.

(Letter, October 16, 1880), that "he has met with the same type in other parts of Java, though not so pronounced, and that it could always be traced to a Kalang origin." He adds that "this race is fading away and that the intermixture with Common Javanese has become

such that in most instances only faint traces of the peculiar type have been left." Meyer agrees with van Musschenbroek in regarding the Kalangs as a remnant of the aborigines of Java, possibly allied to the other

FIGS. 6, 7.—Malayo-Papûan Mixed Types. Body-guard of the Sultan of Ternate.

Negrito peoples of the Archipelago, and "occupying Java before it was peopled by the Malays." Ardi had come from the eastern parts of the island, where a few still linger no longer as a distinct tribe, but dispersed, like Ardi himself, amongst the general population. Hence

FIG. 8.—Melanesian Type. Vanikoro Chief.

the reader will doubtless be glad to have this authentic specimen of perhaps the very lowest type of mankind, now all but extinct.

Our next illustration (Fig. 2) is that of an Andamanese Negrito in a mourning head-dress, from a photograph sent to Europe by Mr. Man, and originally published in the *Anthropological Journal*, vol. vii. (1877) p. 416. It presents a singular resemblance to an Australian woman (Fig. 3) also in mourning, reproduced in the same place

FIG. 9.—A Motu Youth.

from a picture in Angus' "South Australia Illustrated" (plate 51).

The Negrito and Hottentot hair is usually described as growing in separate woolly tufts, or, as Topinard puts it, "in little peppercorn masses, separated by bald spaces." In his "Genealogical Classification of the Human

FIG. 10.—Maori Type.

Races and Languages" Venzel Krizhek revives the well-known classification of Friedrich Müller which makes this feature the basis of one of the main divisions of mankind, including the Hottentots, Papûans, and Negritos. Yet the phenomenon has absolutely no existence in nature. But such is the tenacity of errors of this sort that

it seems impossible to dispel the delusion, although, as Prof. Flower well remarks, "the report of a committee of the Paris Anthropological Society on the growth of the hair of a Negro in one of the hospitals of that city, published last year (1879) in the *Bulletin* of the Society, ought to set the question at rest for ever." It is curious that evolutionists should have discovered in man a trait which is characteristic of none of the anthropoids.

The Negritos, whether those described by Jagor and Meyer in the Philippines, or those visited by E. H. Man in the Andaman group, are all alike socially on the lowest level. They are all nomadic, though not pastoral, moving about from hill to hill, from coast to river-bank, in search of food or shelter from the weather or their enemies. They live on the fruits and roots of the tropical woodlands, on wild honey, snakes, frogs, fish, or such game as their feeble weapons (mostly spear and bow and arrow) are able to procure them. Yet, although indolent and incapable of providing for the future, they do not lack intelligence, for their brain capacity (index No. 74) is still immensely greater than that of the highest anthropoid ape. The Aetas often acquire a knowledge of the neighbouring Tagalog and Bisayan (Malayan) dialects, and the speech of the Andamanese seems from Man's specimens to belong to a highly agglutinating type. They appear to have no shrines or idols of any sort, in this greatly differing from the Papuans, and their religious thought is limited to a blind awe or fear of the powers of nature, for them doubtless supernatural manifestations. But our knowledge of their inner life is still far too restricted to pronounce very positively on these points. The Negritos are not generally suspected of cannibalism; but the Karons of New Guinea are certainly addicted to the practice. One of them, although quite a youth, admitted to M. Achille Raffray that he had already eaten fifteen men, treating it as quite a matter of course. They appear, however, to confine themselves to the bodies of their enemies slain in battle, and do not regard every stranger as so much "meat," like the Negroes of the Lualaba-Congo.

II. THE PAPÛANS: *Papûans proper; Sub-Papûans West ("Alfuros"); Sub-Papûans East (Melanesians)*

The Papûan domain is entirely oceanic, stretching in its widest sense from the island of Floris, Malaysia, eastwards to Fiji (120° – 180° E. long.), and from about the equator southwards to New Caledonia, at this point approaching the Tropic of Capricorn. In our scheme are shown three branches, a central, western, and eastern, which grouping has the convenience of being at once geographical, and to a large extent ethnical. The type itself, so named from the Malay word (*papûwah* = frizzly), denoting one of its most striking characteristics, retains everywhere a considerable degree of uniformity in all essentials. But it is largely mixed with two distinct elements, the Malay in the west, the brown Polynesian or Sawaiori in the east. No doubt there are mixtures in New Guinea or the central region also, and notably on the south-east coast, to which the brown Polynesians seem to have penetrated in more recent times. But on the whole the bulk of the New Guinea people, including the adjacent Aru, Waigiu, Salwatty, Mysol, and Ké islanders, may be taken as the most typical branch of the race. The western division, composed of Malayo-Papûans, and often vaguely spoken of as "Alfuros," but whom I name Sub-Papûans West, comprises the Malaysian islands of Floris, Jilolo, Ceram, Buro, Goram, Timor, Wetter, Timor Laut, and neighbouring islets, without prejudice to the question of Papûan blood in Borneo and Celêbes. The eastern division, composed mainly of Sawaiori-Papûans, and whom I name Sub-Papûans East, comprises all the South Pacific Islands grouped as Melanesia. This term, Melanesia, referring to the prevailing black colour of the natives, is in every way convenient, so that Sub-Papûan East and Melanesian may be taken as practically synonymous. Here the chief groups are the Admiralty, New Britain, New Ireland, Solomon, New Hebrides, New Caledonia, Fiji, and it is to be noted that there are some, possibly many, Melanesians who betray no trace of mixture with the brown Polynesians, and who must consequently be regarded as pure Papûans. Such are the Vanicoro and Mallicolo people in the New Hebrides, and especially the Kai Colos of Viti Levu in Fiji, some specimens of whose crania Prof. Flower has recently shown to be absolutely the most dolichocephalous on the globe. As brachycephaly is a distinctive mark of the Negrito, so dolichocephaly is of the Papûan type. Consequently on this easternmost verge of the Papûan area we would seem to have, as far as is known, the very purest specimen of the race. This harmonises with the view I have ventured elsewhere to express, that the type was developed in a now submerged South Pacific Continent, moving westwards with the gradual subsidence of the land. For a long way east of New Guinea and North-East Australia, in fact quite as far as Samoa, the water is very shallow, averaging probably not more than 500 fathoms.

The accompanying illustrations may be taken as typical specimens of the three great divisions of the Papûan family. Characteristic full-blood Papûan types are those of two members of the Wosaoni tribe, North-West Coast of New Guinea (Figs. 4 and 5), from portraits by M. Raffray, originally figured in the *Tour du Monde*, for April, 1879. p. 267. In Figs. 6 and 7 we have good specimens of the so-called "Alfuros," or mixed Malayo-Papûans of the Archipelago, from sketches by M. Rosenberg, reproduced in his "Malay Archipelago," vol. ii. p. 401. The Vanikoro chief (Fig. 8), from Stanford's "Australasia," p. 476, represents a pure Melanesian head, extremely narrow and high, with long straight, but somewhat broad (platyrhine) nose and frizzly hair. In this front view the prognathism and dolichocephaly are of course not so perceptible as they would be in profile. The Motu youth (Fig. 9), from Stone's work, "A Few Months in New Guinea" (Sampson Low and Co.), illustrates the sub-Papûan East type, the moppy head being thoroughly Papûan, while the broad face, implying brachycephaly, must be referred to Sawaiori influences. The Motu people occupy a strip of about sixty miles on the south-east coast of New Guinea about Port Moresby, and speak a language of the Sawaiori type, apparently more allied to Samoan than to Malay. O. C. Stone's statement that they reckon up to one million must be received with caution, for the Samoans themselves cannot get beyond 10,000, while the Malays draw the line at 100,000. The familiar Maori (New Zealand) head (Fig. 10), from Stanford's "Australasia," p. 565, seems to support the now generally accepted view that the Maoris are not pure brown Polynesians, but a mixture of Rarotongans (Sawaiori stock) and Melanesians, the former predominating. According to some of their traditions on their arrival, probably some 600 years ago, they found the islands occupied by an aboriginal people, who must have been Melanesians, and who were partly exterminated and partly absorbed.

In point of culture the Papûans take a far higher place not only than the Negritoes and Australians, but even than most of the African Negroes. They build houses preferably on piles, cultivate the land with great care and intelligence, are everywhere settled in fixed tribal communities governed by well-understood usages. Alfred R. Wallace, a careful observer of this race, ranks them intellectually higher even than the Malays, accounting for their social inferiority by their less favourable surroundings and remoteness from the civilising influences of more highly-cultured peoples. A very pleasing account is given by Cook of his visit to the New Caledonians, who are generally regarded as an unfavourable branch of the

family. He describes the land about the villages as "finely cultivated, being laid out in sugar-canes, plantations, yams, and other roots, and watered by little rills conducted by art from the main stream, whose source was in the hills. . . . Some roots were baking on a fire in an earthern jar which would have held six or eight gallons; nor did we doubt its being their own manufacture." And further on: "The plantations were laid out out with great judgment, and cultivated with much labour." The reference to earthenware is curious, because the Polynesians are generally supposed to be ignorant of the potter's art. But a taste for art in general, and especially for decoration, is one of the most distinguishing features of the Papûans. Their arms, idols, houses, boats, and other objects are often adorned with very tasteful and elaborate designs, and some of their tatooing presents extremely elegant patterns. They have domesticated the pig, dog, and poultry, and they cultivate the yam, sweet potato, banana, sugar-cane, taro, bread-fruit, and mango. Amongst their arms, besides the spear and bow, are the bamboo blowpipe, and flint knives and axes like those of the neolithic age in Europe. Cannibalism seems to be extremely rare in the West and in New Guinea, but until suppressed was universal in New Zealand and Fiji, and is still prevalent in New Britain and many other parts of Melanesia. From this division of the family it seems to have passed to the brown Polynesians, many of whom were formerly addicted to the practice. It reached its climax in Fiji when, shortly before the annexation of these islands to Great Britain, a whole tribe was condemned to be roasted alive and eaten. As they were too numerous to be consumed at one meal, it was arranged that at the annual taro harvest one family should be baked and eaten with that esculent, and the arrangement was scrupulously carried out until the annexation seasonably intervened to save a remnant of the tribe (*De Rici*).

A. H. KEANE

(*To be continued.*)

PROF. HUXLEY ON EVOLUTION

AT the meeting of the Zoological Society on December 14, among the papers read was one by Prof. Huxley on the application of the laws of evolution to the arrangement of the vertebrata, and more particularly of the mammalia.

We take the following report of the paper from the *Times*:—

Prof. Huxley began by saying:—There is evidence, the value of which has not been disputed, and which, in my judgment, amounts to proof, that, between the commencement of the Tertiary epoch and the present time, the group of the Equidæ has been represented by a series of forms, of which the oldest is that which departs least from the general type of structure of the higher mammalia, while the latest is that which most widely differs from that type. In fact, the earliest known equine animal possesses four complete sub-equal digits on the fore-foot, three on the hind-foot; the ulna is complete and distinct from the radius; the fibula is complete and distinct from the tibia; there are forty-four teeth, the full number of canines being present, and the cheek-teeth having short crowns with simple patterns and early-formed roots. The latest, on the other hand, has only one complete digit on each foot, the rest being represented by rudiments; the ulna is reduced and partially ankylosed with the radius; the fibula is still more reduced and partially ankylosed with the tibia; the canine teeth are partially or completely suppressed in the females; the first cheek-teeth usually remain undeveloped, and when they appear are very small; the other cheek-teeth have long crowns, with highly complicated patterns and late-formed roots. The Equidæ of intermediate ages exhibit intermediate characters. With respect to the interpretation of these facts, two hypotheses, and only two, appear to be imaginable. The one assumes that these successive forms of equine animals have come into existence independently of one another. The other assumes that they are the result of the gradual modification undergone by the successive members of a continuous line of ancestry. As I am not aware that any zoologist maintains the first hypothesis, I do not feel called upon to discuss it. The adoption of the second, however, is equivalent to the acceptance of the doctrine of evolution so far as horses are concerned, and, in the absence of evidence to the contrary, I shall suppose that it is accepted.

Since the commencement of the Eocene epoch, the animals which constitute the family of the Equidæ have undergone processes of modification of three kinds: (1) there has been an excess of development of one part of the oldest form over another; (2) certain parts have undergone complete or partial suppression; (3) parts originally distinct have coalesced. Employing the term "law" simply in the sense of a general statement of facts ascertained by observation, I shall speak of these three processes by which the Eohippus form has passed into Equus as the expression of a three-fold law of evolution. It is of profound interest to remark that this law, or generalised statement of the nature of the ancestral evolution of the horse, is precisely the same as that which formulates the process of individual development in animals generally, from the period at which the broad characters of the group to which an animal belongs are discernible onwards. After a mammalian embryo, for example, has taken on its general mammalian characters, its further progress towards its special form is effected by the excessive growth of one part in relation to another, by the arrest or suppression of parts already formed, and by the coalescence of parts primarily distinct. This coincidence of the laws of ancestral and individual development, creates a strong confidence in the general validity of the former, and a belief that we may safely employ it in reasoning deductively from the known to the unknown. The astronomer who has determined three places of a new planet calculates its place at any epoch, however remote; and, if the law of evolution is to be depended upon, the zoologist who knows a certain length of the course of that evolution in any given case, may with equal justice reason backwards to the earlier, but unknown stages. Applying this method to the case of the horse, I do not see that there is any reason to doubt that the Eocene Equidæ were preceded by Mesozoic forms, which differed from Eohippus in the same way as Eohippus differs from Equus. And thus we are ultimately led to conceive of a first form of the equine series, which, if the law is of general validity, must need have been provided with five sub-equal digits on each plantigrade foot, with complete, sub-equal antebrachial and crural bones, with clavicles, and with, at fewest, forty-four teeth, the cheek-teeth having short crowns and simple-ridged or tuberculated patterns. Moreover, since Marsh's investigations have shown that the older forms of any given mammalian group have less-developed cerebral hemispheres than the later, there is a *primâ facie* probability that this primordial hippoid had a low form of brain. Further, since the existing horse has a diffuse allantoic placentation, the primary form could not have presented a higher, and may have possessed a lower, condition of the various modes by which the fœtus derives nourishment from the parent. Such an animal as this, however, would find no place in any of our systems of classification of the mammalia. It would come nearest to the Lemuroidea and the Insectivora, though the non-prehensile pes would separate it from the former, and the placentation from the latter group.

A natural classification is one which associates together all those forms which are closely allied, and separates them from the rest. But, whether in the ordinary sense of the word "alliance," or in its purely morphological sense, it is impossible to imagine a group of animals more closely

allied than our primordial hippoids are with their descendants. Yet, according to existing arrangements, the ancestors would have to be placed in one order of the class of mammalia and their descendants in another. It may be suggested that it might be as well to wait until the primordial hippoid is discovered before discussing the difficulties which will be created by its appearance. But the truth is that that problem is already pressing in another shape. Numerous "lemurs," with marked ungulate characters, are being discovered in the older Tertiaries of the United States and elsewhere; and no one can study the more ancient mammals with which we are already acquainted without being constantly struck with the insectivorous characters which they present. In fact, there is nothing in the definition of either Primates, Carnivores, or Ungulates, which affords any means of deciding whether a given fossil skeleton, with skull, teeth, and limbs almost complete, ought to be ranged with the Lemurs, the Insectivores, the Carnivores, or the Ungulates.

In whatever order of mammals a sufficiently long series of forms has come to light, they illustrate the three-fold law of evolution as clearly, though perhaps not so strikingly, as the equine series does. Carnivores, Artiodactyles, and Persso-sodactyles all tend, as we trace them back through the Tertiary epoch, towards less modified forms which will fit into none of the recognised orders, but come closer to the Insectivora than to any other. It would, however, be most inconvenient and misleading to term these primordial forms Insectivora, the mammals so-called being themselves more or less specialised modifications of the same common type, and only, in a partial and limited sense, representatives of that type. The root of the matter appears to me to be that the palæontological facts which have come to light in the course of the last ten or fifteen years have completely broken down existing taxonomical conceptions, and that the attempts to construct fresh classifications upon the old model are necesssarily futile. The Cuvieran method, which all modern classifiers have followed, has been of immense value in leading to the close investigation and the clear statement of the anatomical characters of animals. But its principle, the association into sharp logical categories defined by such characters, was sapped when Von Baer showed that, in estimating the likenesses and unlikenesses of animals, development must be fully taken into account; and if the importance of individual development is admitted, that of ancestral development necessarily follows. If the end of all zoological classification is a clear and concise expression of the morphological resemblances and differences of animals, then all such resemblances must have a taxonomic value. But they fall under three heads: (1) those of adult individuals; (2) those of successive stages of embryological development or individual evolution; (3) those of successive stages of the evolution of the species, or ancestral evolution. An arrangement is "natural," that is, logically justifiable, exactly in so far as it expresses the relations of likenesses and unlikenesses enumerated under these heads. Hence, in attempting to classify the Mammalia, we must take into account not only their adult and embryogenetic characters, but their morphological relations, in so far as the several forms represent different stages of evolution. And thus, just as the persistent antagonism of Cuvier and his school to the essence of Lamark's teachings (imperfect and objectionable as these often were in their accidents) turns out to have been a reactionary mistake, so Cuvier's no less definite repudiation of the principle of Bonnet's "*échelle des êtres*" was no less unfortunate. The existence of a "scala animantium," is a necessary consequence of the doctrine of evolution, and its establishment constitutes, I believe, the foundation of scientific taxonomy. Many years ago, in my lectures at the Royal College of Surgeons, I particularly insisted on the central position of the Insectivora among the higher Mammalia; and further study of this order and of the Rodentia has only strengthened my conviction that any one who is acquainted with the range of variation of structure in these groups possesses the key to every peculiarity which is met with in the Primates, the Carnivora, and the Ungulata. Given the common plan of the Insectivora and of the Rodentia, and granting that the modifications of the structure of the limbs, of the brain, and of the alimentary and reproductive viscera which occur among them may exist and accumulate elsewhere, and the derivation of all Eutheria from animals which, except for their diffuse placentation, would be Insectivores, is a simple deduction from the law of evolution. I venture to express a confident expectation that investigation into the mammalian fauna of the Mesozoic epoch will, sooner or later, fill up the blanks which at present exist in the "scala mammalium." Prof. Huxley proceeded to give details on which his conclusions were based, and dwelt on the fact that much further careful work is needed to clear up problems before us.

NOTES

We are enabled through the courtesy of the Council of the Royal Society of Edinburgh to present our readers with an abstract of a remarkable paper by Mr. John Aitken, on Dust, Fog and Mist. The paper opens up new lines of inquiry, and indeed a new future, to what has hitherto been one of the most difficult branches of meteorology, viz. the investigation of the vapour of the atmosphere, which we may safely predict meteorologists will not be slow in following up. Mr. Aitken continues the prosecution of the inquiry, and we learn that last week he has experimented with temperatures as low as 14°·0 F. with the result that equally as at higher temperatures, there is no cloudy condensation when there is no dust; but, when there is dust, cloudy condensation takes place on the dust nuclei, the amount of cloudiness being of course relatively small at such low temperatures on account of the small amount of vapour present. Taken along with Prof. Lister's experiments, in which it was shown that a single drop of rain developed organisms in sensitive solutions which would otherwise have remained for months unaltered, it shows that germ-producing matter, or germs themselves, form at least a part of the cloud- and fog-producing dust. Hence a cotton-wool respirator may prove a protection against disease. We have said enough to show that the paper is one of interest, not only to the physicist and the meteorologist, but also (and perhaps even specially) to the physiologist and the sanitarian.

We are pleased to learn that Dr. W. De La Rue, F.R.S., has been chosen a Corresponding Member of the Paris Academy of Sciences in the Section of Astronomy.

Baron de Chaudoir, Mr. McLachlan, and Baron C. R. Osten-Sacken have been elected honorary members of the Entomological Society of Belgium, filling the vacancies in the list caused by the deaths of Dr. Boisduval, M. Mulsant, and Dr. Snellen van Vollenhoven.

It is proposed to hold a meeting of the Association for the Improvement of Geometrical Teaching on Friday, January 7, in the Botanical Theatre of University College, Gower Street, at 11 a.m. The sub-committees appointed January 11, 1878, have prepared, and circulated amongst the members, draft syllabuses of solid geometry, higher plane geometry, and geometrical conics, and will present their Reports at the meeting. All persons interested in the elementary teaching of geometry are invited to attend.

According to a resolution of the St. Petersburg Society of Naturalists, the work of Prof. Wagner on "Meduse and

Hydroids of the White Sea," will be published in German and French, with fifty tables of engravings.

THE Peabody Academy of Science (Salem, Massachusetts, U.S.A.), after a forced suspension of its publications for six years, announces that the *Memoirs* will be resumed at an early date.

DR. HOEK of Leiden writes us that a first part of the Zoological Results of the Dutch Arctic Cruises with the 60-ton Schooner *Willem Barents* will shortly be published. These results—a preliminary report of which Mr. D'Urban has given in the October number of the *Ann. and Mag. of Nat. Hist.*—will be published as an extra volume of the *Niederländisches Archiv. für Zoologie* (Leiden, E. T. Brill). The different articles will be written in English, French, or German, and the distribution of the material has been as follows:—Sponges, Dr. G. C. J. Vosmaer; Echinoderms, Prof. C. K. Hoffmann; Hydroids and Polyzoa, Dr. W. J. Vigelius; Nemertineans, Dr. A. A. W. Hubrecht; other Worms, Dr. R. Horst; Pycnogonids and Crustaceans, Dr. P. P. C. Hoek; Lamellibranchiate Mollusks, Mr. D. van Haren Noman; Gastropodous Mollusks, Mr. Th. W. van Lidth de Jeude; Fishes, Dr. A. A. W. Hubrecht; Birds, Prof. H. Schlegel. The first part contains the Worms, the Pycnogonids, the Lamellibranchiate Mollusks, the Fishes, and a description of the only mammal captured, and will be issued before the end of January.

THE death is announced of Prof. Karl B. Heller of the K.K. Theresianum at Vienna, a naturalist well known by his numerous writings.

REPORTS from Honolulu describe an eruption of the Mauna Loa Volcano (Hawai) as the grandest which has ever been observed. It began on November 5 at some nine kilometres distance from the summit of the crater. The eruption of lava was accompanied by terrible explosions.

EARTHQUAKES are reported (1) from Brescia, where a shock was observed on December 10 in the afternoon; (2) from Schloss Trakostyan and environs (in the mountains of Northern Croatia), where three violent shocks occurred in the night of December 10–11; (3) from Smyrna, where, on December 12 at 9.40 p.m., a tolerably powerful shock was noticed. On the 23rd inst., about 5 p.m., a shock of earthquake was felt at Bucharest, Rustchuk, Kustendje, Galatz, Berlad, and Jassy. In the night of December 16–17 two earthquake shocks were felt in Agram, in close succession, about 11 p m. About the same hour shocks were observed in various parts of Carniola and Styria, *e.g.* in Gurkfeld at 11.4 and 11.9 p.m., in Grossontag, near Friedau, three quickly-successive shocks; in Pragerhof two pretty sharp shocks; in Peltau and in Marburg one strong shock each. In Csakathurn (Hungary) and neighbourhood strong earthquake motions were likewise observed the same night about 11.20 p.m. In the night of December 21-22 shocks were again felt in Agram, of which one about 1 a.m. was pretty violent. In the environs of Agram slight earth-vibrations are still constantly being experienced. At about ten minutes past five o'clock p.m. on December 25 two rather severe shocks of earthquake occurred at Odessa within a very short interval of each other. They appear to have come from the direction of the Middle Danube, and, passing through Roumania and Bessarabia, spent themselves here on the shores of the Black Sea in South Russia. They seem to have been most strongly felt at the Bessarabian towns of Bieletz, Kishineff, and Tiraspol, for the walls of some of the houses were cracked in consequence. At Odessa the effects were limited to buildings and furniture being more or less roughly shaken, or light articles such as vases, bottles, and glasses, being thrown down. The weather was extremely mild and calm at the time, and the sky but very partially clouded.

FALB's theory is gaining in favour with the population, especially as he predicted fresh earthquakes in the Agram region from December 15 to 31. Falb has enunciated his theory in a newly-published popular work entitled "Die Umwälzungen im Weltall" (Revolutions in the Universe). These are treated under three heads: (1) in the star regions; (2) in the region of clouds; and (3) in the depths of the earth.

THE tomb of Immanuel Kant at Königsberg will soon be decorated in a worthy manner. Upon a suitable pedestal a marble bust of the great philosopher will be placed. The bust is the work of Prof. Siemering.

"ALLERLEI gesammelte ornithologische Beobachtungen" is the title of a new book from the pen of Rudolf, Crown Prince of Austria, just published in a limited number of copies, which have been presented by the author to his friends.

A MONUMENT of the celebrated ornithologist Naumann was recently unveiled in the Schlossgarten at Köthen upon the occasion of the centenary of Naumann's birth.

THE German Fisheries Union have, according to the proposal of Prof. Nitsche of Tharand, resolved to offer a prize of 500 marks (25*l.*) for the best treatise on the following subject:—Of the ova of fish which are sown out for breeding, and particularly of the ova of the Salmonidæ, a large percentage is completely destroyed by fungi, well-known to pisciculturists as byssus or "mould," and belonging partly to the family of Schizomycetæ and partly to that of Saprolegniaceæ. A detailed botanical description of the respective genera and species, their biology and propagation, as well as an account of the manner of their introduction into the piscicultural apparatus, of the conditions which favour their development and of the way in which they destroy the ovum, is now required. At the same time the questions are to be discussed whether and by what means it would be possible to prevent their introduction, and what measures would best stop a continued spreading of the evil when once introduced into a breeding place. The treatises are to be sent, under the usual formalities, to the office of the German Fisheries Union, 9, Leipziger Platz, Berlin. The competition for the prize is to be an international one, and the treatises may be written in German, English, or French. The final term is October 1, 1882.

WE have received specimens of the diaries published by Messrs. De La Rue. While their beauty and convenience commend them to everybody, they ought to be of special value to lovers of science, as they contain so many scientific data. Their get-up and general utility are beyond praise.

THE *Comptes rendus* of the Paris Academy of Sciences for December 20 is entirely occupied with the discourses pronounced at the funeral of M. Michel Chasles by representatives of the various bodies with which the deceased member was connected—MM. J. Bertrand, Bouquet, Laussedat, Dumas, and Rolland.

AT the last meeting of the St. Petersburg Society of Gardening M. Grigorieff made an interesting communication on Japanese gardens. The Japanese are most passionate lovers of gardening, which is carried on by all classes of society, from the great palaces to the most humble houses. Gardening, as well as the art of making bouquets, is taught in schools, and nowhere else in Europe are there so many gardens as in Japan. The species cultivated in the small private gardens are mostly miniature representatives of great trees. All new species and varieties of garden flowers and trees are sold at high prices and become known throughout the country with great rapidity. M. Grigorieff exhibited during his lecture a most interesting collection of photographs of Japanese gardens.

THE Russian scientific bodies continue to express their sympathy with Prof. Mendeleeff on the occasion of the refusal

by the Academy of Sciences to admit him as Member of that body. The Russian Chemical and Physical Society, while electing him Honorary Member, has presented him with an address in which it is stated that the Society considers him "to be a chemist who has no equal among Russian chemists." Many scientific bodies, as the University of Kieff, the Society of Hygiene, &c., have elected him Honorary Member or President. A public subscription has been opened for the institution of a prize bearing his name, and a great dinner was given in his honour by the St. Petersburg *savants*, among whom we notice the most eminent Russian Members of the Academy of Sciences. It is worthy of notice that Professors Korkin and Setchenoff, as well as the late M. Hilferding, the Panslavist explorer of Slavonian literature, met at the hands of the Academy of Sciences the same fate as M. Mendeleeff.

THE law for the isolation of the French National Library has been adopted by both Houses of the French Parliament, and the necessary expropriation for the great work will begin immediately.

AT a recent sitting the Municipal Council of Paris voted a sum of 400*l*. for the establishment of a School of Chemistry. It will be opened free to the pupils of the several Municipal schools who are desirous of practice in chemical industries.

THE French Government is to establish in Egypt a school of Egyptology, which will be directed by M. Maspero, now Professor of Egyptology to the College of France. This creation will be the third school established abroad at the expense of the French Budget. The two others are one at Rome and the other at Athens.

THE Thirteenth Annual Report of the Eastbourne Natural History Society testifies to the Society's continued prosperity. At the meeting of November 19 Dr. Royston Pigott read an interesting paper on "The Limits of Human Vision."

THE *Proceedings* of the Belfast Natural History and Philosophical Society for 1878–80 contains, besides several general papers, a few natural history papers of local interest, including one (with illustrations) on Irish Spiders, by Mr. Thomas Workman.

A BALNEOLOGICAL and a patent-protection exhibition will be held at Frankfort-on-the-Main in 1881.

OUR ASTRONOMICAL COLUMN

VARIABLE STARS.—Amongst the stars which, from a comparison of the various catalogues, exhibit more or less strongly signs of variability, may be mentioned the following, which we take in order of right ascension; the positions are for the year 1880:—

1. Lalande 2037-8. R.A. 1h. 3m. 24s., N.P.D. 38° 30′·5. On September 29, 1790, Lalande rated this star 10m., and on December 27 following, 8·9; the B.D. (by which letters we refer to the Bonn *Durchmusterung*) has 7·0. Harding marks it a ninth.

2. 40 Cassiopeæ. R.A. 1h. 28m. 57s., N.P.D. Lalande calls this star 4m. in September, 1789, and 6 i 1790. In Argelander's zone No. 167 on January 1 , 1843, i was estimated 7, yet in the B.D. it is 5·2. In the first Radcliffe catalogue, where great attention was given to the magnitudes, it is 4·7; Piazzi has 6, Groombridge 5·6, and Heis the same.

3. Lalande 4864·5. R.A. 2h. 32m. 15s., N.P.D. 40° 57′·4. Estimated 9 in September, 1790, and 7½ in January following; but it has since been discerned with the naked eye, Heis calling it 6·7. The B.D. has 6·7. It is not in Houzeau.

4. Bradley 396. R.A. 2h. 53m. 13s., N.P.D. 8° 59′·8. Lalande rated this star 4·5 in November, 1789, and 7 in March, 1790. Groombridge, who made six observations for position, estimated it 7, Heis and Carrington 6, while it is 5·5 in the B.D.

5. 35 Camelopardi. We have already referred to the marked discordances in the estimates of the magnitude of this star in the various catalogues. Dembowski has directed attention to the probable variability of the principal component, and the star certainly deserves more regular attention at the hands of observers than it has yet received. R.A. 5h. 54m. 58s., N.P.D. 38° 25′·5. The estimated magnitudes vary from 5·5 to 8.

6. Attention may be once more directed to the star which Rümker compared with Encke's comet at Paramatta, N.S.W., on June 19, 1822, and which he rated at the time 4·5. Whether it really attains this degree of brightness is not yet certain; it is however 6·0 in the *Uranometria Argentina*, and was observed as low as 8m. in 1873. The B.D. says 6·5. Its light is a full yellow. R.A. 7h. 23m. 15s., N.P.D. 91° 39′·5.

7. 65 b^2 Geminorum. R.A. 7h. 22m. 21s., N.P.D. 61° 50′·3. Lalande rated this star as low as 8½ in March, 1794, but calls it 5½ in February following. Bessel estimated it 7; all other observers say 5 or 5·6.

8. 16 Leonis Minoris. R.A. 9h. 42m. 51s., N.P.D. 49° 48′·7. D'Agelet has 5 and 7·8, Lalande 6½, Piazzi 8, the first Radcliffe Catalogue 6·6, Bessel, Taylor, and the B.D. 7, Houzeau 5·6, but neither Argelander nor Heis included it amongst the stars visible to the naked eye.

9. Lalande 19034. R.A. 9h. 34m. 49s., N.P.D. 113° 2′·7. It appears strange that a star isolated as this is should not have been more frequently observed on the meridian, if always as bright as say 5m. D'Agelet and Piazzi have not got it; Lalande calls it 4½ on March 21, 1797; Argelander has 6 on March 6, 1850, 4 on February 16, 1851, and 5 on March 8, 1852; Heis and Houzeau call it 5, and Gould 5·2.

If we may rely upon the observations of Kirch early in the last century there would appear to be sensible changes in the relative brightness of β and δ Scorpii; on January 17, 1704, he writes: "β und δ erschienen fast im gleicher Grösse, jedoch δ ein wenig heller (jetzt ist β 2, δ 3 grösse)," while on April 1 following he records "δ merklich grösser als β." Argelander and Heis estimate β and δ respectively 2 and 2·3; Gould has no sensible difference.

10. Lalande 38405. R.A. 20h. 0m. 16s., N.P.D. 94° 45′·4. This star was rated 6 on July 15, 1794, 7 on August 15, 8 on August 20, and 7½ on August 30 of the following year. It is 8 in Bessel, 7 in Wolfer's map, one of the series of the Berlin Academy, and 6·7 in Heis and Houzeau. Gould does not give it. It might be inferred from Lalande's observations that the period is not very long.

11. 33 Capricorni. Chacornac says of this star: "Observée tantot plus brillante, tantot moins qu'une étoile de 7me grandeur dont elle est voisine:" the seventh magnitude alluded to being, it may be presumed, O.A. 21386, which follows 2m. 12s., 9′·4 to the south. 33 Capricorni is 5·6 in Argelander, 6·5 in Heis and Behrmann, and 5·7 in Gould; it is one of Chacornac's red stars, Gould also calls it red. The evidence of variability in this case seems to rest with Chacornac. R.A. 21h. 17m. 21s., N.P.D. 111° 21′·5.

12. 17 *i* Andromedæ, a star previously noted in this column as variable. In the "British Catalogue" it is rated 4; Bradley and Piazzi call it 7; Lalande's three estimates are 5, 5 and 4; D'Agelet has 3·4 and 6; the first Radcliffe catalogue 3·9, and the B.D. 4·2; estimates from 4 to 7 are therefore sufficiently confirmed: the variation may be slow, but the star certainly deserves attention. R.A. 23h. 32m. 15s., N.P.D. 47° 24′·1.

THE COMET 1873 VII.—The comet discovered by Coggia at Marseilles on November 10 and by Winnecke on November 11 was soon lost in Europe from its rapid southerly motion; indeed the observations extend over less than a week. The elements exhibited a similarity to those which had been assigned to a comet detected by Pons in February, 1818, but very imperfectly observed, and Prof. Weiss, the present director of the Imperial Observatory at Vienna, was at the trouble of examining the question of possible identity as closely as the data permitted. He formed three normal positions from the small number of observations—for November 11, 13, and 15—and under the condition that the first and third normals should be exactly represented he ascertained how the second one was represented on the assumption (1) that the orbit was parabolic; (2) that the period of revolution corresponded to the interval between the perihelion-passages in 1818 and 1873, or 55·82 years; and (3) that the comet had completed eight revolutions in this interval, or that the period extends only to 6·977 years. As a matter of figures the agreement was found to be slightly closer for hypothesis (3) than for the other two, the parabola showing the largest differ-

ence. Hence so far as the paucity of data in 1873 enabled any judgment to be formed, the preference appeared to belong to the revolution in 6·977 years. On this supposition there would be a very near approach to the orbit of Jupiter near the ascending node, which would render possible an amount of perturbation at some past time, that might have fixed the comet in an orbit of such limited dimensions.

If the comet were really revolving in an elliptical orbit with this period of revolution, neglecting perturbations, which might however be sensible since 1873, it would be again due at perihelion about November 24 in the present year, in which case its track in the heavens would not be very different from that followed in 1873. We are not aware if any search has been made for the comet. It would have been possible to have decided in 1873 if a short period were admissible could observations have been obtained in the southern hemisphere: this was not done, and the identity of the comets of 1818 and 1873 remains therefore open to conjecture; but it must be borne in mind that the data in the former year are in a high degree uncertain.

PECHÜLE'S COMET.—Elements computed by the discoverer from observations at Copenhagen on December 16, 17, and 20, have a general resemblance to those of the comet of 1807, so elaborately discussed by Bessel, but after his resulting period of many centuries, and considering the position of the orbit in the system, there can be of course no question of identity of these bodies. At Greenwich noon on January 1 the comet's position will be, by Pechüle's elements, in R.A. 20h. 1·9m., N.P.D. 70° 24′, and on January 5 in R.A. 20h. 19·6m., N.P.D. 68° 30′.

CHEMICAL NOTES

MM. HAUTEFEUILLE AND CHAPPUIS, in continuing their investigation of the conditions under which oxygen is transformed into ozone, have shown in *Compt. rend.* that the character of the electric discharge to which the oxygen is subjected largely influences the quantity of ozone produced. If the discharge assume the character of a luminous shower the maximum amount of ozone is produced, the temperature of such a discharge being lower than that of the ordinary *effluve*. The production of this special form of discharge is ensured by mixing with the oxygen a small quantity of a foreign gas whose physical properties are dissimilar from those of oxygen; of the gases experimented with silicon fluoride has given the best results. If nitrogen be the foreign gas the transformation into ozone is greater than when pure oxygen is employed, but the discharge is not altogether luminous. Hydrogen is more effective than nitrogen. The presence of carbon dioxide also insures a large amount of ozonation. In their earlier experiments on the liquefaction of ozone the authors only succeeded in obtaining a mist in the Cailletet tube when the pressure was suddenly withdrawn. They now find that if a mixture of carbon dioxide and oxygen which has been ozonised at a low temperature be submitted to the action of the silent discharge at − 23°, and be slightly compressed, the gas acquires a deep blue colour, and after a time a blue liquid is produced. At − 88° the liquid is very dark blue. When carbon dioxide is decomposed by the electric spark at − 23° a blue gas is produced, and at a certain pressure (exact pressure is not mentioned) the undecomposed carbon dioxide condenses to a blue coloured liquid. By this experiment the authors think they have proved that ozone is one of the products of the decomposition, by the spark, of carbon dioxide.

THE heat of formation of benzene has recently been measured by Thomsen (*Berliner Berichte*) and by Berthelot (*Compt. rend.*). The results show considerable differences: but from the accounts of the experiments, Thomsen's number seems the more trustworthy. For the heat of combustion of gaseous benzene Thomsen finds the number 805,800 heat units; Berthelot the number 776,000. For the heat of formation of gaseous benzene, at constant volume, from amorphous carbon and hydrogen, Thomsen finds − 20,120 heat units; Berthelot, on the other hand, finds + 5800. Berthelot does not state whether this number is calculated for constant volume or constant pressure. Thomsen makes certain theoretical deductions from the value which he has found for the heat of formation of benzene, basing these on his calculations for the heat of formation of "singly- and doubly-linked" carbon atoms (see NATURE, vol. xxii. p. 608): he concludes that the generally accepted hexagon formula for benzene is probably incorrect, and that a formula in which each carbon atom is "singly linked" to three others is to be preferred.

BERTHELOT finds the heat of formation of gaseous dipropargyl—C_6H_6—a metamer of benzene—from amorphous carbon to be − 64,800 heat units. The instability and easy polymerisation of this body are explained by the great absorption of heat which occurs in its formation. Attempts to transform dipropargyl into benzene were unsuccessful. Berthelot has also determined the heats of formation of various hydrocarbons, and finds certain constant differences between the successive members of homologous series.

HERR V. MEYER describes in the *Berliner Berichte* a very elegant modification of his method of determining vapour densities, whereby the specific gravities of permanent gases may be readily measured at very high temperatures. At the highest temperature of a Schlösing's furnace (about 1400°) the density of hydrogen vapour was normal. It has now been shown that the coefficients of expansion of the following gases are not changed at very high temperatures: tellurium, sulphur, nitrogen, oxygen, hydrogen, mercury, carbon dioxide, hydrochloric acid, arsenious oxide.

THE following numbers for the vapour densities of tellurium and selenium have been recently obtained by Deville and Troost (*Compt. rend.*):—Selenium at 1420° = 5·68 (calculated = 5·54), tellurium at 1440° = 9·0, at 1390° = 9·08 (calculated = 8·93).

IN the *Wien. Acad. Berichte* Herr Ofler describes the results of experiments which he thinks show that Guthrie's cryohydrates are merely mixtures of various salts and ice: alcohol dissolves the ice, leaving a "skeleton" of undissolved salt; cold water dissolves the salt, and leaves the ice with the form of the cryohydrate. Solution of a cryohydrate is attended with the same thermal change as solution of the salt and ice separately.

THE connection which exists between the opium and cinchona alkaloïds, and between both of these groups of compounds and pyridine, has been recently made more apparent by the work of Herr E. v. Gerichten (*Berliner Berichte*), who has shown that the so-called apophyllenic acid—obtained by oxidising the opium alkaloïd cotarnine—is really the acid methyl salt of pyridine dicarboxylic acid, which acid is obtained from the cinchona alkaloïd cinchonine, and which when heated with lime yields pyridine.

WHEN an aqueous solution of potassium, sodium, or lithium chloride, or potassium nitrate is kept for some time in a vertical tube, the upper part of which is maintained at a considerably higher temperature than the lower part, diffusion of the salt from the hotter to the colder part occurs, according to M. C. Soret (*Naturforscher*). The amount of diffusion in a given time depends upon the original concentration of the solution, and is also connected with the molecular weight of the salt used.

M. DUFET stated some little time since that the refractive index of a mixture of isomorphous salts in solution is equal to the mean of the indices of the components. Herr Fock (in *Zeitschrift für Crystallographie*) concludes, from measurements of the refractive indices of solutions of thallium and potassium alums, of lead and strontium thiosulphate, and of magnesium chromate and sulphate, that Dufet's statement does not hold good in all cases: for the second pair of salts mentioned above it is approximately correct. In *Compt. rend.* Dufet gives numbers showing that his statement applies to a mixture of magnesium and zinc sulphates.

In *Compt. rend.* M. Demarcay describes two new compounds containing sulphur, nitrogen, and chlorine, viz., SNCl and $(SN)_3Cl$: the former prepared by passing chlorine into a solution of nitrogen sulphide in chloroform, and the latter by adding nitrogen sulphide to a solution, in chloroform, of the compound SNCl. SNCl is partly decomposed by heat, in accordance with the equation $2SNCl = N_2 + S_2Cl_2$.

THE relation between the total energy developed in the chemical reactions which occur in various kinds of galvanic batteries and the energy which appears in the form of current electricity, has been recently studied by Thomsen (*Wiedemann's Annalen*) using a thermal method of measuring the total energy. He finds that the whole of the energy developed in the chemical change appears as electric energy in Daniell's battery (with closed circuit), and in those forms of batteries in which the metallic surface of the negative electrode is not changed by the electrolytic process; when nitric acid is used as electrolyte the same total conversion of one into another form of energy is

nearly realised, but the gradual absorption, by the liquid, of reduction products, tends to cause a deviation from this result.

BERTHELOT has recently studied (*Compt. rend.*) the action of air and of hydrochloric acid in presence of air, on pure mercury. He confirms the generally accepted fact that pure mercury is very slowly and superficially oxidised by the action of air at ordinary temperatures. If gaseous hydrochloric acid is shaken with mercury in presence of air mercurous chloride and water are produced. This reaction ($Hg_2 + 2HCl + O = Hg_2Cl_2 + H_2O$) is attended with the evolution of 53,400 thermal units, whereas the oxidation of mercury ($Hg + O = HgO$) is attended with the evolution of only 21,100 units. The action of hydrochloric acid in presence of air on copper ($Cu_2 + 2HCl + O = Cu_2Cl_2 + H_2O$) is accompanied by the evolution of 26,500 thermal units, hydrochloric acid in absence of air is, as is well known, almost without action on metallic copper.

IN the course of his investigation into the action of phosphorus on hydriodic acid, Damoiseau (*Compt. rend.*) describes a method for preparing phosphonium iodide in a state sufficiently pure for general use. Ten parts ordinary phosphorus in small pieces are allowed to react for some time on twenty-two parts of an aqueous solution of hydriodic acid (saturated in the cold); two parts iodine are added, and the phosphorous acid which is produced is separated from the crystals of phosphonium iodide by washing with aqueous hydriodic acid.

A SERIES of compounds, derived from monohydric alcohols, in which the "hydroxylic hydrogen" of the alcohol is replaced by aluminium, is described (*Chem. News*) by Gladstone and Tribe. These bodies are prepared by the action of aluminium in presence of aluminium iodide on the alcohol. The new substances are solids, melting to clear liquids which do not solidify at temperatures much below the melting points of the solids; they are decomposed by water with formation of aluminium hydrate and the corresponding alcohol.

THE sulphides of vanadium have been investigated by Kay (*Chem. Soc. Journ.*). The compounds obtained by Berzelius by the action of sulphuretted hydrogen on solutions of vanadium salts are shown to contain oxygen in addition to vanadium and sulphur, but no definite formula can be assigned to any of these bodies. Vanadium trisulphide V_2S_3 is obtained by the action of dry sulphuretted hydrogen on heated vanadium trioxide, as described by Berzelius. When this compound is heated to bright redness in hydrogen, it is reduced to the disulphide V_2S_2, and when heated with sulphur to 400° it is converted into the pentasulphide V_2S_5.

IN the *Chem. Soc. Journ.* Kingzett describes experiments on the atmospheric oxidation of phosphorus which seem to prove that ozone and hydrogen peroxide are simultaneously produced when air is drawn over phosphorus partially immersed in water.

MANY so-called basic sulphates of iron have been from time to time described: of the fifteen which are generally recognised as probably existing it would appear from Pickering's experiments (*Chem. Soc. Journ.*) that only one, viz. $2Fe_2O_3 . SO_3$, actually exists.

DR. SYDNEY MARSDEN has recently experimented on the action of boron on various metals at high temperatures. He finds (*Proc.* R. S. Edin. and *Chem. Soc. Journ.*) that silver dissolves amorphous boron, and that on cooling, pure boron is obtained partly in the graphitoidal, partly in the adamantine form. Copper combines with boron to form the compound B_2Cu_3.

PROF. BELLATI has published in pamphlet form, under the title "Proprietà termiche notevoli di alcuni Ioduri doppi," an extended and careful series of observations of the specific gravities, specific heats, thermal expansions, and thermal changes which accompany changes of colour and structure, of several double iodides of mercury, more especially of the three salts $HgI_2 . 2AgI$, $HgI_2 . 3AgI$, and $HgI_2 . Cu_2I_2$.

HERR HAASS describes in the *Berliner Berichte* a simple method of illustrating the existence of the so-called "critical pressure" described in this journal by Carnelley. A small piece of mercuric chloride is placed in a glass tube which is closed at one end, and communicates at the other with a Bunsen pump. So long as the manometer registers less than about 400 mm. pressure it is not possible to melt the mercuric chloride by heating it; the salt passes at once from the solid to the gaseous state. But immediately the pressure rises above about 420 mm. the mercuric chloride melts.

IN studying the condensation products of aldehyde Prof. Lieben has obtained (*Wied. Akad. Ber.*) a new alcohol belonging to the same series as glycerin, viz. $C_4H_7(OH)_3$. The new compound, called butenyl glycerin by Lieben, is a syrupy, sweet-tasting liquid, soluble in water, boiling at 172°–175° under a pressure of 27 mm. It forms a triacetin analogous in properties to the natural fats; when heated with oxalic acid its behaviour is similar to that of glycerin: formic acid is produced along with an oily, strongly-smelling substance which has not as yet been fully examined.

PHYSICAL NOTES

MONS. A. ANGOT proposes a new formula for calculating altitudes from barometric observations, based upon that given originally by Laplace. The existing method of calculation from observed monthly or annual means is found, as Plantamour has shown, to be defective, since its results exhibit an uncertainty that varies with the season, an elevated station appearing to be higher by day and in summer than at night or in winter. As an example, when the height of the Great St. Bernard is measured by comparison of barometer observations between that place and Geneva, it would appear that the height of the Great St. Bernard exhibits a diurnal variation of 17 metres in winter and of more than 47 metres in summer; while the mean of the June observations gives a height of 25 metres higher than that found from the January numbers! These anomalies M. Angot explains by the facts that the mean temperature between the stations is not exactly equal to the half sum of the two temperatures, and that the weight of the air between the two stations is on the other hand greater when the mean temperature is low. The rather complicated formula proposed by M. Angot gives the difference in altitude by calculating directly the height of each station above an imaginary plane at which the barometric pressure is equal to 760 millims. No empirical coefficients are needed in this case, the standard constants of Regnault and others for air and aqueous vapour being taken. M. Angot has recalculated from his formula a new set of tables, involving all the corrections that must be applied to the older tables of the Bureau des Longitudes.

IN a recent number of the *Journal de Genève* M. Colladon has pointed out that a poplar or other tall tree may, if its roots strike into damp soil, serve as a lightning-conductor to protect a house; and he thinks he has verified this conjecture by examination of a number of individual cases of lightning-stroke. In the case however where the house stands between the tree and a piece of water, a pond or a stream, the shortest path for the lightning from the tree to the wet conductor may be through the house!

YVON ZOCH has described a new kind of electric dust-figures, which he regards as having an important bearing upon the theory of discharges in vacua, being in opposition to the views of Crookes. Tubes of 1 to 3 centims. diameter, and from 10 to 30 centims. in length, were closed at both ends by corks pierced to receive copper wires. In the tubes were placed various powders, bronze powder being chiefly used in preference to others, which being lighter adhered to the sides of the tube. One wire was then connected with the positive conductor of an electric machine; from the other the repelled electricity dissipated itself into the air. In other cases the discharges of Leyden jars were employed. The experiments were all conducted at atmospheric pressure. When thus treated the bronze powder arranged itself in beautifully-marked ridges or strata, varying in regularity according to the original distribution of the powder. A space free from all traces of powder was observed to surround the positive pole. Uusually there was a corresponding accumulation about the negative pole. These ridges or striations may be compared to the stratifications observable in Geissler-tubes; and Herr Zoch shows that variations in the strength of the electric discharges, in the width of the tubes, &c., produce upo- similar effects to those they produce on the lum icuous tubes. In this present case a mechanical r ticles lying near the poles undoubtedly takes pl of this research believes that the presence o the Geissler tube may be similarly accou inous regions are those the bronze powder the inference is tha idual gas has a gr

any other part. The stratifications produced by electric discharges through flames may be similarly explained; and these researches have an obvious bearing on the structure of Lichtenberg's well-known figures.

MONS. MERCADIER has been devoting some attention to the subject of the photophone, and more particularly to the production of sounds by the simpler forms of the instrument, in which a selenium receiver with its electrical connections is dispensed with. The musical photophone—or, as M. Mercadier chooses to style it, the radiophone—may be described as a sort of optical siren, in which a rotating disk pierced with holes is interposed in the path of a period of rays of light, causing intermittences of regular period varying with the speed of the disk. Our readers will remember that such a beam falling on a simple disk of metal or of hard rubber throws it into vibration, and it emits a note corresponding in pitch with the frequency of the intermittences of the light. In Prof. Bell's actual instrument this "siren" was a heavy disk of brass pierced with holes. M. Mercadier prefers a disk of black paper gummed upon a glass disk in order to get rid of the whistling sounds which even a gentle current of air produces on the brass disk. It may be noted in passing that M. Duboscq has independently constructed similar disks. The receiving disks were fixed in a suitable holder at the end of a short india-rubber hearing-tube. M. Mercadier finds that when opaque disks of zinc, copper, and other substances are employed to receive the beams, very little difference in the loudness of the sounds can be perceived, whether the disks are polished or not. But the thickness of the disks is of great importance, thin ones answering much better than those a little thicker. With transparent laminæ such as glass and quartz, M. Mercadier obtains strong effects, whereas Prof. Bell found only feeble results with these substances. The degree of polish is here unimportant also; but a film of smoke or white paint, or of metallic silver on the front of the disk, diminishes its powers, while, on the contrary, the loudness is augmented by blackening the back of the disk. M. Mercadier employed as sources of light the lime-light and flames of petroleum fed with oxygen.

HERR F. KLOCKE has lately discovered an anomalous property in hyposulphite of lead in respect of its action on polarised light. This substance usually exhibits circularly polarised light: but Klocke has found that plates cut perpendicularly to the optic axis, when viewed in the field of a polariscope by parallel rays of light, appear unequally bright, being divided by dark bands into six sectors, of which opposite pairs are equally bright. In convergent light, moreover, the ordinary ring-figure of a uniaxial crystal is not seen, but instead there appears in each sector a figure of the form characteristic of the ordinary biaxial crystal, and having the plane of the optic axes perpendicular to the neighbouring edge of the crystal. The explanation of this curious phenomenon appears to be that there is some anomaly in the molecular structure of the crystals, by virtue of which the six portions are compressed equally each in direction perpendicular to the neighbouring face of the prism.

IN the Vienna *Berichte* for June, 1880, Victor von Lang describes a form of dichroïscope, in which a small improvement upon the common form has been made. Usually the small square aperture through which light is admitted to the rhomb of spar is fixed rigidly to the tubular holder of the latter. In the new form the square aperture is cut in a diaphragm fastened to an outer tube, which can be rotated round the inner. The advantages gained in permitting the rhomb of spar to be turned independently of the aperture are obvious. A plano-convex lens of small magnifying power is added as usual as an eyepiece at the other end of the rhomb.

M. AMAGAT has experimented on the compressibility of oxygen gas in an apparatus in which the working fluid for transmitting the pressure was mercury. Since the experiments of Regnault it has been commonly assumed that the absorption of the gas by mercury at high pressures and temperatures rendered inexact any such experiments. M. Amagat however finds that the absorption is almost insensible, an oxygen manometer and a nitrogen manometer giving identical indications for several days, even with temperatures varying up to 100°.

MM. HAUTEFEUILLE AND CHAPPUIS have continued their researches on the liquefaction of ozone, which they have lately liquefied in the presence of carbonic acid. They believe the [illegible] of liquefaction of ozone to be very near that of carbonic acid; and on mixing ozonised oxygen with carbonic acid and submitting it in a capillary tube to a slow pressure at a temperature of − 23° (obtained by the evaporation of methylic chloride), they obtained a liquid separated by a distinct meniscus from the gas. This liquid was of a clear blue tint, as was the compressed gas above it. If the substance is then allowed to expand gently and immediately compressed, the liquid becomes much more blue, owing to the greater proportion of liquefied ozone. The blue tint thus characteristic of ozone under pressure proves it to be present in the gases which result when the silent electric discharge is passed through carbonic acid gas for some hours.

EDISON has lately patented a "*webermeter*." This is an instrument for measuring the amount of electric current flowing through a circuit, or in other words a *meter* for electric currents to tell the number of webers that have been supplied. The name is at least in accordance with the inventor's usual abundant ingeniosity.

IN the *Comptes rendus* M. Gouy publishes an extract from a memoir presented by him to the Académie des Sciences, on the propagation of light. In this memoir he proposes to examine the particular case of propagation of luminiferous waves, in which, while the direction of the propagation of the movement is constant, the intensity of the waves or of the source of light varies. This problem, which has doubtless been suggested to the author by considerations derived from the photophone, affects the whole question of the measurement of the velocity of light, whether by the methods of occultations of Rœmer and Fizeau, or by that of aberrations (in the rotating mirror), as devised by Foucault. The former case only is treated of in M. Gouy's paper. Setting aside at first the case of dispersive media, and restricting the question to isotropic media, M. Gouy investigates mathematically whether the velocity of propagation of the amplitude is the same as that of the wave, and finds that this is the case only for those waves for which the differential equations contain no terms beyond those of the second order—those in which the vibration has virtually attained to the steady condition. For such waves moreover in dispersive media the amplitude is not propagated with the same velocity as the waves themselves, but the amplitude itself varies according to a complex function of the wave-length according to an ascertainable periodic law. If we remember rightly, a similar hydrodynamic investigation of the rate of propagation of waves in water was made some years ago by Prof. Osborne Reynolds, with the result that the effective wave-front only travelled at half the velocity of the steady waves. The inference is that that which physicists usually term "the velocity of light" is only the rate of propagation of the wave-front, which is slower than the true velocity, the retardation being greatest for the vibrations of greatest wave-length.

ANOTHER new property of selenium is claimed as the discovery of M. Blondlot. He states that when selenium is rubbed upon platinum, each metal being connected with a terminal of a capillary electrometer, a current is observed. This current, which is observed to pass through the electrometer from the platinum to the selenium, appears therefore to differ from the tribo-electric currents discovered by Becquerel, and which were always in the same direction as the thermo-electric currents which would have been produced had the surfaces of friction been directly heated. The true thermo-electric current of a selenium-platinum pair is, according to M. Blondlot, from selenium to platinum through the heated junction. One curious point stated by M. Blondlot is that no indication whatever is obtained upon the capillary electrometer by friction between two metals, or between two insulators, or between a metal and an insulator. The electrometer in the selenium experiment indicated a difference of potential about equal to that of one Daniell's cell.

MAGNUS AND TYNDALL found carbonic acid to have a considerable absorbent action on radiant heat. Dr. Lecher (*Wien. Acad. Ans.*) has lately made new observations, especially as to absorption of solar radiation by the carbonic acid in the atmosphere. Experiments with a gas-lamp and glass cylinder first showed that carbonic acid in a length of 214 mm. gave passage to 94·8 per cent. of the radiation; 536 mm. 93·8 per cent.; 917 mm. 89·0 per cent. At Greifenstein, outside of Vienna (chosen for pure air), the sun's rays also were proved to undergo considerable weakening in passage through carbonic acid gas. A layer of this gas one metre thick absorbed about 13 per cent. when the sun had an altitude of 59°; the number however diminished in proportion as the sun got lower. This shows that the absorption of solar radiation by carbonic acid is selective, and that the

absorbable wave-lengths become more rare the greater the atmospheric layer the rays have already traversed. The author calculates from his experiments the proportion of carbonic acid in the atmosphere, finding it 3·27 in 10,000 parts by volume; a number agreeing so well with results of chemical analysis as to indicate that this is a good way of determining the carbonic acid in the atmosphere and its variations, applicable, too, at heights where direct measurements are impossible.

HERR WINKELMANN proves by experiment (*Wied. Ann.* No. 11) that the heat-conduction of ethylene decreases somewhat with increased pressure. The pressure was varied from 10 to 740 mm. (Comparative experiments with air showed no influence of pressure.) The author explains the phenomenon by the divergence of ethylene from Boyle's law. The action of cohesion-forces between the molecules is indicated by that fact; and this will cause, at each collision, a temporary retardation of the straight movements, which effect will occur oftener the greater the number of collisions (*i.e.* the greater the density). Hence this retardation will increasingly affect the velocity with which two contiguous layers of different temperature exchange the energy of their motions.

A REMARKABLE fall of rain in Austria and neighbouring parts on August 11-15 this year, has been closely investigated by Dr. Hann (*Wien. Akad. Anz.*), on the basis of data from 260 stations in Austria-Hungary, Bavaria, Switzerland, and Saxony. This fall caused the Danube at Vienna to reach (on the 18th) its highest summer level in this century. The rain began in Siebenburgen and south-east Hungary on the 11th, and in general went from east to west. It was most extensive on the 12th, and the heaviest fall was in Salzkammergut and neighbourhood. The rain-area is found to lie on the west and north-west side of the area of lowest air-pressure, and to stretch westwards far over the border of the minimum region. Near the centre of lowest pressure the precipitation was much less than in several parts distant from it. The non-existence of a minimum-producing power of rainfall (contrary to common views), and the incapability of so great rainfall as that in the present case attracting a minimum and influencing its propagation, are noteworthy. The general conclusion arrived at is that no relation is demonstrable between barometric variation and rainfall; the fall of the barometer does not primarily depend on the rainfall, and is not perceptibly influenced by it. Dr. Hann finds this confirmed by an examination of several other heavy rainfalls in their relation to distribution of air-pressure.

THE salt and the ice in cryohydrates have been regarded by Prof. Guthrie as in chemical combination. In 1877 Herr Pfaundler expressed the view that cryohydrates were merely mixtures of salt and ice. This view is also maintained by Herr Offer, who in a recent paper to the Vienna Academy raises various objections to the existence of cryohydrates as chemical compounds. The numbers expressing the quantities in which the water unites with the salts in various cryohydrates, indicate no stoichiometric law, and tell much rather in favour of chemical mixtures. No cryohydrate forms a clear and pure crystal, but always an opaque confused crystalline mass. The phenomena which occur when cryohydrates are brought into alcohol and into water are considered to be against Prof. Guthrie's view. The heat-absorption of cryohydrates in dissolving, as compared with that of the salt and ice separately, only presents differences which lie within the errors of observation. Further, Herr Offer compared the specific gravity of several cryohydrates with those of their constituents, and found pretty close agreement.

FROM recent magnetic researches Herr Auerbach (*Wied. Ann.* No. 11) finds the temporary magnetism of cylindrical bodies, *ceteris paribus*, proportional to the mass; greater the greater the length; the less the thickness; the greater the density; dependent only on form, not on size; in the case of nickel, according to density and force, a quarter to half as much as in iron. It increases with magnetising force, first proportionally, then (except with very small density) more quickly, and at last more slowly. The quick increase is greater the denser the body. The turning point is, for the same density, at the same place, but with stronger forces the greater the density; for magnetic saturation of powders extremely strong forces are necessary. Herr Auerbach theorises on these results.

ANOTHER paper on magnetism in these *Annalen* is by Herr Baur, and deals with the "function of magnetisation" for very small magnetising forces; the influence of temperature on it; the magnetisability of iron at very high temperatures; Gore's phenomenon; and the function for varieties of iron. Among other results, the smaller the magnetising force the greater is the influence of temperature on the function in question. Up to a certain force the function increases with increase in temperature, but beyond that it decreases. With weak forces the temporary magnetic moment rises quickly (with rise of temperature) to a maximum at red glow, then sinks quickly to *nil*; with strong forces it gradually sinks, with rise of temperature, to a very low value at red glow. With increased magnetic force Gore's phenomenon becomes more intense and prolonged, and it occurs at a higher glow. In ordinary iron the function of magnetisation reaches its maximum very quickly, in iron filings later, and in electrolytic iron very late.

GEOGRAPHICAL NOTES

THE glacier of the Byelookher Mountain, the chief summit of the Siberian or Great Altay, which has not been visited by men of science during the last fifty years, was recently explored by an expedition engaged in the study of the life of the West Siberian natives. After having crossed the 9000 feet high Alps of the Tchouya, the explorers descended into the pretty and wealthy broad valley of the Tchouya, whence, following the Arkhyt River, they soon reached the foot of the mighty Berel glacier. The glacier, which forms in its lower parts a *mer de glace* two miles long and 2800 feet wide, was accurately explored and surveyed during a week by the expedition from its lower end to a great ice-fall, where the travellers were compelled to stop their work before a moving wall of ice, while mighty masses of snow fell, one after the other, on the glacier from the neighbouring mountains. After having surveyed the glacier and made several drawings of the severe scenery which it affords, the travellers returned to the valley of Ouimon, and thence to the civilised towns.

THE astronomical determinations of positions which were made by M. Pyevtsoff during his journey from Khobdo through Mongolia to Kalgan, and from Ourga to Kosh-agatch, are published by Col. Scharnhorst in the last number of the *Izvestia* of the Russian Geographical Society. They are most welcome, as they come from a country where exact determinations are very scanty. —The same fascicule of the *Izvestia* contains M. Larionoff's catalogue of seventy-five determinations of heights in the northern and eastern parts of the province of Kouldja and in the mountains which border it north and east; and M. Severtsoff's map of his route on the Pamir Rang-koul, south-east of the Lake Kara-koul.

THE Russian travellers who have been engaged in the exploration of Central Asia are now returning to St. Petersburg. Col. Prshevalsky is expected every day, and the Russian Geographical Society, at its last meeting (December 15), elected the indefatigable traveller an Honorary Member. M. Potanin is already at St. Petersburg, and will soon give a lecture on his journey to Western Mongolia, as also M. Pyevtsoff, who travelled with merchants from Biysk to Khou-khou-khoto, and who during his journey collected much material for the correction of the map of Mongolia. M. Mushketoff, who has explored the glacier of Zarafshan (NATURE, vol. xxiii. p. 44), gave a lecture at the last meeting of the Russian Geographical Society on his excursion. This traveller, contrary to M. Severtsoff's experience, did not find in the Thian-Shan any traces of the glacial period.

THE *Kouban News* announces the appearance, in the Sea of Azoff, of a new little island, some 150 feet in diameter, and 10 feet above the level of the water. Its appearance was accompanied with a kind of marine eruption. It is 150 brasses distant from the shore, where a crevice has appeared.

THE organisation of the Polar meteorological station on the Lena is being actively carried out by Prof. Lentz. The director of the station will be M. Yurgens.

PROF. NORDENSKJÖLD is again thinking of fresh enterprises. At present a ship is being built at the Lena estuary, in which he intends to start on a new Arctic expedition in the summer of 1882.

PRINCE BORGHESE, the Italian African traveller, has arrived near Tripolis from Wadai. This is the first time that a traveller from Darfur has reached the Mediterranean by way of Wadai and Bornu.

THE Leipzig publishing firm of Ferd. Hirt and Son announce that Major Serpa Pinto's great African work of travel will be published in January, 1881.

UNIVERSITY AND EDUCATIONAL INTELLIGENCE

ALFRED C. HADDON, B.A., Scholar of Christ's College, Demonstrator of Comparative Anatomy, and Curator of Zoology in the University of Cambridge, has been appointed Professor of Zoology at the Royal College of Science, Dublin.

THE movement to found a college at Dundee has been revived, and at a meeting last week it was announced by Dr. Baxter, the Procurator-Fiscal, that he was in a position to place 125,000*l.* at the head of a subscription for the purpose. Owens College, Manchester, is proposed as the model of the Dundee Institution.

DURING recent years much has been done in Russia by private initiative for primary education in natural science. Now we notice the creation at St. Petersburg of a special institution, the aim of which is to devise and collect apparatus and drawings for the teaching of natural science in primary schools. A special collection of objects intended for the illustration of science will be sent from school to school by the Committee, and lectures will be given in each school on the subject.

THE building of the new Siberian University is being briskly carried on. It will contain twenty large rooms for lectures, as well as spacious halls for the museum and library. The building for anatomy, as well as the hospital for clinical medicine, will be erected in accordance with the latest hygienic principles. A special building will be appropriated for the physical cabinet and the astronomical observatory.

THE Moscow University is closed for an indeterminate time because of the disturbances among medical students, and three hundred students are incarcerated in the town prison.

SCIENTIFIC SERIALS

Journal of the Franklin Institute, December.—Boiler experiments, by Mr. Isherwood.—New electric motor, by Mr. Griscom.—The Sawyer electric light.—Proceedings of Institute, &c.

Bulletin de l'Academie Royale des Sciences de Belgique, Nos. 9 and 10.—Influence of liquids on the sound of sonorous bells which contain them or which are immersed in them, by M. Montigny.—On the chemical composition of the epidote of Quenast, by M. Renard.—On Caels and De Bennie, by M. Mailly.

No. 11.—On the compensation of a chain of geodetic triangles, by M. Adan.—Excretory apparatus of Trematodes and Cestode (3rd paper), by M. Fraipont.

Rivista Scientifico-Industriale, No. 21, November 15.—On spherohedry in crystallisation, by Prof. Bombicci.—On beats, the third sound of Tartini, &c. (concluded), by Dr. Crotti.

No. 22, November 30.—On some singular phenomena of geometrical optics, by Prof. Cassani.

Reale Istituto Lombardo di Scienze e Lettere. Rendiconti, vol. xiii. fasc. xvii., November 11.—On *Peronospora viticola* and the cryptogamic laboratory, by Prof. Garovaglio.—On measurement of the thermo-luminous radiations of the sun, by Dr. Chistoni.—Fourth series of researches and studies on the pelagic fauna of the Italian lakes (short *résumé*), by Prof. Pavesi.—The leprosy of Ancient Italy, especially of Comacchio, by Prof. Sangalli.

Kosmos, September 1880, contains:—Theodor Vuy, on the rehabilitation of shattered authorities; considerations on the education of the future.—Dr. Ernst Krause, sketch of the development history of the history of development, No. 3.—Dr. H. Müller, on the variability of alpine flowers.—Leopold Einstein, apprehension and comprehension, a study in the philosophy of language.—Short notices and extracts from journals. Literary and critical notices.

October.—Prof. Fritz Schultze, the transformation of human fundamental conceptions on the threshold of modern times.—Prof. Dr. Hörnes, on phacops and dalmanites, genera of trilobites and their probable genetic connection.—George Potonié, on the purport of the stony particles to be found in the flesh of the pear and generally in the Pomaceæ.—Dr. Fritz Müller, *Paltostoma torrentium*, a gnat with two forms of females, one with a mouth for honey-sucking the other with a mouth for blood-sucking (with illustration).—Short notices and extracts from journals. Literary and critical notices.

SOCIETIES AND ACADEMIES

LONDON

Chemical Society, December 16.—Prof. H. E. Roscoe, president, in the chair.—The following communications, &c., were made:—On the estimation of nitrogen by combustion, including the nitro-compounds, by J. Ruffle. The author recommends the use of the following mixture instead of soda-lime in the process of Will and Varrentrapp:—Two molecules of sodium hydrate, one molecule of pure lime, and one molecule of sodium hyposulphite; the substance before burning being mixed with about its own weight of a mixture of sulphur and wood charcoal. By this process good results were obtained with sodium nitrate, picric acid, &c.—Dr. Carnelly then showed some experiments as to the effect of pressure in raising the melting-points of ice, camphor, and mercuric chloride. By suspending a cylinder of ice (formed round the bulb of a thermometer) in a Torricellian vacuum and condensing the aqueous vapour by a freezing mixture, so as to keep the vacuum perfect, the author has raised ice to 180° C. before it melted. In the experiment shown, through an accident, the temperature only rose to 30° C. before the cylinder fell off the thermometer. Camphor which was boiling in a tube solidified when the pressure was diminished, though the heating was continued. Mercuric chloride, which under diminished pressure had been raised considerably above its melting-point, melted and boiled as soon as it was exposed to atmospheric pressure.—On some naphthalene derivatives, by Dr. Armstrong and Mr. Graham.

Geological Society, December 15.—Robert Etheridge, F.R.S., president, in the chair.—William Elijah Benton, Rev. George Clements, J. Kerr Gulland, Francis T. S. Houghton, George Bingley Luke, and William Mansell MacCulloch, M.D., were elected Fellows; and Prof. Luigi Bellardi of Turin, and Dr. M. Neumayr of Vienna, Foreign Correspondents of the Society. The following communications were read:—On the constitution and history of grits and sandstones, by John Arthur Phillips, F.G.S. In the first part of this paper the author described the microscopic and chemical structure of a large series of grits, sandstones, and in some cases quartzites, of various geological ages, noticing finally several sands of more or less recent date. The cementing material in the harder varieties is commonly, to a large extent, siliceous. The grains vary considerably in form and in the nature of their inclosures, cavities of various kinds and minute crystals of schorl or rutile not being rare. The author drew attention to the evidence of the deposition of secondary quartz upon the original grains, so as to continue its crystal structure, which sometimes exhibits externally a crystal form. This is frequently observable in sandstone of Carboniferous, Permian, and Triassic age. Felspar grains are not unfrequently present, with scales of mica and minute chlorite and epidote. Chemical analyses of some varieties were also given. The author then considered the effect of flowing water upon transported particles of sand or gravel. It results from his investigations that fragments of quartz or schorl less than one-fiftieth of an inch in diameter retain their angularity for a very long period indeed, remaining, under ordinary circumstances, unrounded; but they are much more rapidly rounded by the action of wind. It is thus probable that rounded grains of this kind in some of the older rocks, as, for example, certain of the Triassic sandstones, may be the result of Æolian action.—The chair was then taken by J. W. Hulke, F.R.S., V.P.G.S.—On a new species of *Trigonia* from the Purbeck beds of the Vale of Wardour, by R. Etheridge, F.R.S., president; with a note on the stratigraphical position of the fossil by the Rev. W. R. Andrews. In this paper the author described a species of *Trigonia* discovered by the Rev. W. R. Andrews in the "cinder-bed" of the Middle Purbeck series in the Vale of Wardour. The specimens were found in the railway-cutting one mile west of Dinton Station. The shell was referred to d'Orbigny's section "Glabræ" of the genus *Trigonia*, and named *Trigonia densinoda*. In its ornamentation it closely resembles *T. tenuitexta*, Lyc., of the Portland oolite, but is more depressed and lengthened posteriorly, and destitute of the antecarinal space which occurs in all known Jurassic "Glabræ." The escutcheon is remarkably large, and possesses transverse rugæ, as in the Neocomian "Quadratæ." The author regarded the species as a transition form connecting the two groups of *Trigoniæ* above-mentioned. The description of the new species was accompanied by a note on the Purbeck strata of the Vale of Wardour by the Rev. W. R. Andrews.

Meteorological Society, December 15.—Mr. G. J. Symons, F.R.S., president, in the chair.—J. Coventry, J. W. Moore,

M.D., W. T. Paulin, J. Porter, and Capt. W. C. Smith were elected Fellows.—The following papers were read:—Report on the phenological observations for the year 1880, by the Rev. T. A. Preston, M.A., F.M.S. Agriculturally speaking the year may be considered as disappointing. Till June the weather was such as has rarely been experienced for farm operations. The severe cold of the winter broke up and mellowed the soil, and the dry open weather enabled farmers to clean their land from the excessive growth of weeds caused by the damp of the year before. The dry May was not favourable for the hay, which suffered severely in some places, but still a crop with far more real nourishment in it than would be obtained from a rank growth would have been secured had it not been for the terrible floods of July in the Midland Counties, which not only seriously injured the crop, so that it was frequently not worth the trouble of removing off the land, but also carried it entirely away in low-lying districts. The corn again, which was looking most promising till July, suffered much during that damp period, and had it not been for the subsequent fine weather would have been ruined. But the unfavourable season of 1879 produced very serious effects on vegetation, especially on trees and shrubs and their produce. The young wood of the trees was not ripened, and as a natural consequence the severe winter killed an enormous quantity of some kinds, and greatly injured others. "Laurustinus" was generally killed to the ground, and in some districts the destruction of other shrubs was severely felt. The evergreens in many cases lost large quantities of their leaves. Hollies especially are mentioned by several observers, and privet-hedges were sometimes quite leafless. With respect to fruit-trees, apples and pears in some localities (but not all) were hardly able to put forth any bloom, and the crops were consequently extremely poor. Wall-fruit was also a general failure, but this was partially owing to severe weather when the trees were in bloom, for in some instances the show of bloom was splendid. Gooseberries and currants produced enormous crops, and strawberries were very fine, but they lasted an unusually short time. Seeds generally ripened with difficulty; much of the corn could not be ground, and a great deal was mixed up with roughly-ground Indian corn and flavoured to induce the cattle to eat it. The crop of ordinary garden seeds was also far below its usual quality, and some of the favourite garden flowers were consequently very poor. Among the *special* features of the year may be mentioned the great quantity of certain insects. "Aphis" was in astonishing numbers in the early part of the year. The apple-shoots, before the leaves expanded, were in almost every case covered with the "green fly," and among wild plants the Mealy Guelder-rose was especially attacked by them. "Wasps," again, have been in extraordinary numbers, and dreadful accounts of them have been sent to the various entomological periodicals; their numbers appear to have exceeded all previous experience. The larvæ of the gooseberry moth and of the gooseberry saw-fly have also been extremely destructive; and finally, as an undoubted result of the wet season of 1879, the larvæ of the crane-fly have been a perfect plague in some localities, and sheep-licks in others. The scarcity of small birds has been universally noticed; some, no doubt, perished from the cold, but vast numbers had migrated. The enormous numbers of larks which hastened to the Eastern Counties on the outbreak of cold weather was astonishing.—On the variations of relative humidity and thermometric dryness of the air, with changes of barometric pressure at the Kew Observatory, by G. M. Whipple, B.Sc., F.R.A.S.—On the relative frequency of given heights of the barometer readings at the Kew Observatory during the ten years 1870-79, by G. M. Whipple, B.Sc., F.R.A.S.

Mineralogical Society of Great Britain and Ireland, December 23.—Prof. M. Forster Heddle, F.R.S.E., president, in the chair.—Prof. F. J. Wiik of Helsingfors was elected a corresponding member, and Messrs. Baxter, Gray, James Cunningham, R. Shaw Simpson, H. B. Guppy, and Stephen Vivian as ordinary members.—The following papers were read and discussed:—On Tyrceite, by the President.—On minerals new to Britain, by the President.—Note on Gilbertite, and on tin pseudomorphs from Belowda Mine, by J. H. Collins.—On Brochantite and its allies, by William Lemmons.—On a remarkably fine crystal of Euclase, by L. Guyot.—On the action of organic acids on minerals, by Prof. H. C. Bolton.—Note on artificial Gay-Lussite, by C. Rammelsberg.—Note on a peculiar carbonaceous substance from the Maesymarchog Colliery, by James S. Merry.

Anthropological Institute, December 14.—Edward B. Tylor, F.R.S., president, in the chair.—The election of the Rev. R. A. Bullen as a member of the Institute was announced.—Mr. W. St. Chad Boscawen read a paper on "Hittite Civilisation."

Institution of Civil Engineers, December 21.—W. H. Barlow, F.R.S., president, in the chair.—The scrutineers reported that the following gentlemen had been duly elected to fill the several offices in the Council for the ensuing year:—Mr. James Ab rnethy, president; Sir W. G. Armstrong, C.B., F.R.S., Sir J. W. Bazalgette, C.B., Mr. F. J. Bramwell, F.R.S., and Mr. J. Brunlees, vice-presidents; Mr. G. Berkley, Mr. G. B. Bruce, Sir John Coode, Mr. E. A. Cowper, Mr. A. Giles, Sir Charles A. Hartley, Mr. H. Hayter, Dr. W. Pole, F.R.S., Mr. R. Rawlinson, C.B., Mr. A. M. Rendel, Dr. C. W. Siemens, F.R.S., Mr. D. Stevenson, Sir W. Thomson, F.R.S., Sir Joseph Whitworth, Bart., F.R.S., and Mr. E. Woods, other members of Council.

EDINBURGH

Royal Society, December 20.—Sir Wyville Thomson, vice-president, in the chair.—Mr. John Aitken read a paper on dust, fogs, and clouds, which we give on another page.—Mr. E. Sang communicated a note on the solar eclipse of December 31, 1880, which is visible in our islands.—Dr. Marsden, in a paper on the preparation of adamantine carbon, intimated that he had at length effected the crystallisation of carbon in the cubical form. The crystals he had obtained were however far too minute to be of any commercial value.—Prof. Blyth described an electric sonometer, consisting of a wire monochord, which, traversed by an interrupted electric current, was set into strong vibrations between the poles of a horse-shoe magnet. The notes given out were loudest when they were harmonics of the fundamental interrupted note which was sounded by a vibrating tuning-fork inserted in the circuit—Dr. Haycraft communicated an explanation of the amœboid motions of masses of protoplasm, illustrating his theory by an extremely simple mechanical contrivance. An india-rubber ball perforated with several small apertures was filled with coloured white of egg, and immersed in a solution of sugar of about the same density as the albumen. When a gentle pressure was applied, the albumen was forced out in long continuous processes; and when the pressure was relaxed the processes at once retracted inside the ball again, probably in virtue of the action of the viscosity and surface-tension of the gelatinous matter. Thus was explained the retraction of the amœboid processes, after they had been expelled by contraction of the internal muscular structure.

CONTENTS

	PAGE
PERUVIAN BARK	189
PRACTICAL BLOWPIPE ASSAYING. By Dr. C. LE NEVE FOSTER	191
OUR BOOK SHELF:—	
Müller's "Über die von den Triohopterenlarven der Provinz Santa Catharina verfertigen Gehäuse"	192
Payne's "Voyages of the Elizabethan Seamen to America"	192
LETTERS TO THE EDITOR:—	
Black Sheep.—CHARLES DARWIN, F.R.S.	193
The Nature of the Chemical Elements.—Dr. EDMUND J. MILLS, F.R.S.	193
Smokeless London.—W. D. SCOTT-MONCRIEFF	193
Colliery Explosions and Coal-Dust.—Hon. R. RUSSELL	193
Geological Climates.—J. STARKIE GARDNER	193
Chalk.—S. N. CARVALHO, Jun.	194
On Estimating the Height of Clouds by Photography and the Stereoscope.—JOHN HARMER	194
Correction of an Error in "Island Life."—ALFRED R. WALLACE	195
Natural Science for Women.—ALFRED W. BENNETT	195
Movements of Leaves.—M. L. ROUSE	195
ON DUST, FOGS, AND CLOUDS. By JOHN AITKEN	195
ON THE SPECTRUM OF CARBON. By W. M. WATTS (*With Diagram*)	197
THE INDO-CHINESE AND OCEANIC RACES—TYPES AND AFFINITIES. I. By A. H. KEANE (*With Illustrations*)	199
PROF. HUXLEY ON EVOLUTION	203
NOTES	204
OUR ASTRONOMICAL COLUMN:—	
Variable Stars	206
The Comet 1873 VII.	206
Pechüle's Comet	207
CHEMICAL NOTES	207
PHYSICAL NOTES	208
GEOGRAPHICAL NOTES	210
UNIVERSITY AND EDUCATIONAL INTELLIGENCE	211
SCIENTIFIC SERIALS	212
SOCIETIES AND ACADEMIES	212

SUBSCRIPTIONS TO NATURE

Yearly . . . . . 28*s.*
Half-yearly . . . . . 14*s.* 6*d.*
Quarterly . . . . . 7*s.* 6*d.*

To the Colonies, United States, the Continent, and all places within the Postal Union :—

Yearly . . . . . 30*s.* 6*d.*
Half-yearly . . . . . 15*s.* 6*d.*
Quarterly . . . . . 8*s.*

Office: 29, Bedford Street, Strand.

DIARY OF SOCIETIES.

LONDON

THURSDAY, DECEMBER 30.

ROYAL INSTITUTION, at 3.—Atoms: Prof. Dewar.
LONDON INSTITUTION, at 7.—The Study of the Beautiful: G. A. Storey.

SATURDAY, JANUARY 1.

ROYAL INSTITUTION, at 3.—Atoms: Prof. Dewar.

MONDAY, JANUARY 3.

LONDON INSTITUTION, at 5.—Cuttlefishes: Dr. A. Wilson.
VICTORIA INSTITUTE, at 8.—Early Destinies of Man: J. E. Howard.—Revelation and Science: Dr. S. Kinns.
INSTITUTE OF ACTUARIES, at 7.—On the Simultaneous Construction of Compound Interest and Annuity Tables: F. N. Newcome.

TUESDAY, JANUARY 4.

ROYAL INSTITUTION, at 3.—Atoms: Prof. Dewar.
ZOOLOGICAL SOCIETY, at 8.30.—Account of the Zoological Collection made during the Survey of H.M.S. *Alert* in the Straits of Magellan, and on the Coast of Patagonia: Dr. Albert Günther, F.R.S.—On the Sea Elephant: Prof. Flower.
EPPING FOREST FIELD CLUB, at 8.—The Natural History of Islands: A. R. Wallace.

WEDNESDAY, JANUARY 5.

GEOLOGICAL SOCIETY, at 8.—The Archæan Geology of Anglesey, by C Callaway, D.Sc., with a Note on the Microscopic Structure of some Anglesey Rocks: Prof. T. G. Bonney, F.R.S.—The Limestone of Durness and Assynt: C. Callaway, D.Sc.—On a Boulder of Hornblende Pikrite near Pen-y-Carniseog, Anglesey: Prof. T. G. Bonney, F.R.S.

THURSDAY, JANUARY 6.

ROYAL SOCIETY, at 4.30.
ROYAL INSTITUTION, at 3.—Atoms: Prof. Dewar.
LONDON INSTITUTION, at 7.—Our Living Dramatists: Prof. H. Morley.

FRIDAY, JANUARY 7.

GEOLOGISTS' ASSOCIATION, at 8.—The Zones of Chalk: Prof. Morris.

SATURDAY, JANUARY 8.

ROYAL INSTITUTION, at 3.—Atoms: Prof. Dewar.

YORK'S

SERIES of SCIENTIFIC OPTICAL LANTERN SLIDES

Comprise over 2,000 of the following subjects:—Electricity, Magnetism, Sound, Telephone, Microphone, Electric Light, Light, Spectrum Analysis, Astronomy, Mines and Miners, Heat, Mechanics, Hydrostatics, Pneumatics, Human Physiology. Sample Slide and Catalogue sent on receipt of 2*s.*

F. YORK, OPTICAL LANTERN SLIDE MANUFACTURER,
87, Lancaster Road, Notting Hill, London, W.

NOTICE OF REMOVAL.

JAMES HOW & CO.,
SCIENTIFIC INSTRUMENT MAKERS,
73, FARRINGDON ST., LONDON
(LATE OF 5, ST. BRIDE ST., AND 2, FOSTER LANE).
HOW'S STUDENT'S MICROSCOPE. HOW'S MICROSCOPE LAMP.
Rock Sections and other Objects for the Microscope.

S. C. TISLEY & Co.,

OPTICIANS,
172, BROMPTON ROAD, S.W.
(Close to South Kensington Museum).

THE PHONEIDOSCOPE

An Instrument for Observing the Colour-Figures of Liquid Films under the action of Sonorous Vibrations.
Being a visible demonstration of the Vibratory and Molecular Motion of a Telephone Plate.
The PHONEIDOSCOPE, with 3 Discs, Bottle of Solution, Descriptive Pamphlet, &c., in Cardboard Box, 10*s.* 6*d.*
MANUFACTURED AND SOLD WHOLESALE AND RETAIL BY
S. C. TISLEY & CO., 172, BROMPTON ROAD, LONDON, S.W.
TELEPHONIC ELECTRICITY. All Materials supplied for experimental purposes.
Price Lists of Electrical and Acoustic Apparatus, with Drawings and Description of the Harmonograph, Post Free, 2d.

"NATURE," Nov. 14, 1878, No. 472.—One Shilling each will be paid for Copies of this number,—Address Publishers of NATURE, 29, Bedford Street, Strand, W.C.

NOW READY,
SECOND EDITION,
GRIFFIN'S
CHEMICAL HANDICRAFT.

PRICE 4*s.* 7*d.* POST FREE.

A CATALOGUE OF CHEMICAL APPARATUS:
ILLUSTRATED, CLASSIFIED, DESCRIPTIVE.
Demy 8vo, 480 pp., Illustrated with 1,600 Woodcuts.
Most Complete and Cheapest List of Apparatus.
JOHN J. GRIFFIN AND SONS, 22, GARRICK STREET, LONDON, W.C.

R. W. NEEVES,
PHILOSOPHICAL INSTRUMENT
AND
INTENSITY COIL MAKER.
PRICE LIST, FOUR STAMPS.

55, SIDMOUTH STREET, LONDON, W.C.

DRAPER'S INK (DICHROIC).
THE NEW BLACK INK

DIFFERING FROM ANYTHING ELSE EVER PRODUCED.
Writing becomes a pleasure when this Ink is used. It has been adopted by the principal Banks, Public Offices, and Railway Companies throughout Ireland.

It writes almost instantly Full Black. | Flows easily from the Pen.
Does not corrode Steel Pens. | Blotting-paper may be applied at the moment of writing.
Is cleanly to use, and not liable to Blot.

Can be obtained in London, through Messrs. BARCLAY & SONS, Farringdon Street; W. EDWARDS, Old Change; F. NEWBERY & SONS, Newgate Street; WM. MATHER, London and Manchester; J. AUSTIN & Co., Duke Street, Liverpool; and STACY & COOK, Paternoster Row; and to be had of all Stationers.
BEWLEY & DRAPER (Limited), Dublin.

J. ORME & CO.,
(Late M. JACKSON & CO.)
MANUFACTURERS AND IMPORTERS OF
SCIENTIFIC APPARATUS
AND
CHEMICALS.
SOLE AGENTS FOR HICKLEY'S PATENT TELEPHONES,
Price 50*s.* per Pair, Cash with Order.
Price Lists sent on receipt of Three Stamps for Postage.
For Trade Terms inclose Business Card.

65, BARBICAN, LONDON, E.C.

EAGLE INSURANCE COMPANY,
79, PALL MALL.
FOR LIVES ONLY. ESTABLISHED 1807.
Accumulated Funds £3,043,542
Also a Subscribed Capital of more than £1,500,000
Reports, Prospectuses, and Forms may be had at the Office, or from any of the Company's Agents, post free.
GEORGE HUMPHREYS, Actuary and Secretary.

By JOHN FISKE, M.A., LL.B.
OUTLINES OF COSMIC PHILOSOPHY,
Based on the Doctrine of Evolution, with Criticisms on the Positive Philosophy. 2 vols., 8vo. 25*s.*
DARWINISM, AND OTHER ESSAYS.
Crown 8vo. 7*s.* 6*d.*
MACMILLAN & CO., London.

HOLLOWAY'S PILLS
THIS MEDICINE
Is a Certain Cure for all Disorders of the LIVER, STOMACH AND BOWELS. A Great PURIFIER of the BLOOD; a Powerful Invigorator of the System, in cases of WEAKNESS AND DEBILITY, and is unequalled in Female Complaints.

W. LADD & CO.,

SCIENTIFIC INSTRUMENT MANUFACTURERS,

(*By Appointment to the Royal Institution of Great Britain*),

11 AND 12, BEAK STREET, REGENT STREET, W.

IMPROVED HOLTZ ELECTRICAL MACHINES. GRAMME'S MAGNETO-ELECTRIC MACHINE for Laboratory use.

PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3*s.* per oz.

Physical Apparatus of every Description.

ILLUSTRATED CATALOGUE, SIXPENCE.

PATERSON'S NEW CATALOGUE OF PHYSICAL APPARATUS.

LANTERN SLIDES for SCIENTIFIC LECTURES. Season 1880–1. Post free 6 Stamps.
Complete Sets of Physical Apparatus for Science Primers and all the Physical Text-books in use in Schools and Colleges.
Siemens and Gramme Dynamo Machines and Lamps for hire.
Schools supplied with Apparatus as per Science and Art Departments' Requirements in the Sections of Light, Heat, Sound, and Electricity.
Electric Signals for Houses, Hotels, &c., Colliery Signals, Lightning Conductors. The Gower-Bell Loud-speaking Telephone.

EDWARD PATERSON, Electrical Engineer.

SHOW ROOMS AND STEAM WORKS:—76, LITTLE BRITAIN, E.C. (late 3, Bedford Court, W.C.).

MOLISON'S HARMONOGRAPH; executes the Harmonic Curves in the most perfect manner. 15*s.* and 20*s.*

Illustrated Catalogue of Electrical Apparatus, Part 1, *post free,* 6 *Stamps. Ditto, Electric Signals, Part* 2, 6 *Stamps.*

SCIENTIFIC WORTHIES.

ENGRAVED BY THE LATE C. H. JEENS.

The following is a list of the Portraits that have appeared in the above Series.

MICHAEL FARADAY.
THOMAS HENRY HUXLEY.
CHARLES DARWIN.
JOHN TYNDALL.
GEORGE GABRIEL STOKES.
SIR CHARLES LYELL.
SIR CHARLES WHEATSTONE.
JEAN BAPTISTE ANDRÉ DUMAS.
SIR WYVILLE THOMSON.
SIR WILLIAM THOMSON.
HERMANN L. F. HELMHOLTZ.
SIR JOSEPH DALTON HOOKER.
WILLIAM HARVEY.
SIR GEORGE B. AIRY.
J. LOUIS R. AGASSIZ.
RICHARD OWEN.

Proof impressions of these, printed on India paper, may be had from the Publishers, price 5*s. each, or the Set of* 16 *Portraits in a Handsome portfolio for* £4 5*s. carriage paid.*

THE PORTFOLIO MAY BE HAD SEPARATELY, PRICE 6*s.*

NOTE.—ONLY A VERY FEW COMPLETE SETS CAN BE MADE UP.

Cheques and P.O.Os payable to MACMILLAN & CO.,

OFFICE OF "NATURE," 29, BEDFORD STREET, STRAND.

A HANDBOOK OF DOUBLE STARS.

With a Catalogue of Twelve Hundred Double Stars, and extensive Lists of Measures. With additional Notes bringing the Measures up to 1879. For the use of Amateurs. By EDWARD CROSSLEY, F.R.A.S., JOSEPH GLEDHILL, F.R.A.S., and JAMES M. WILSON, M.A., F.R.A.S. With Illustrations. 8vo. 21*s.*

Just ready. 44 pages 8vo. 1*s.*

CORRECTIONS, TOGETHER WITH NOTES, CRITICISMS, RECENT MEASURES AND DISCOVERIES, &c., &c., TO THE HANDBOOK OF DOUBLE STARS.

THE BIBLIOGRAPHY HAS ALSO BEEN BROUGHT UP TO DATE.

"The volume is one which may be expected to find its way to the shelves of most amateurs and students of astronomy."—*Nature.*

"This is a truly delightful work, and one which will admirably supply a want. Into the hands of abler, more impartial and painstaking observers and compilers than the authors' its preparation could not have fallen."—*The Astronomical Register.*

"Will be welcomed by all who take an interest in the subject of double stars."—*Academy.*

"The names of the authors, noted authorities on the subject treated of, will lead the reader to open this volume with the feeling that in it he has a treasure of lore on the knowledge brought to light in the last hundred years respecting the relative motions of physically connected stars, nor will he be disappointed."—*Athenæum.*

"One of the most valuable additions to the library of the amateur astronomer that has been made for many years. It is full of information of perennial interest to the student and the practical observer, and assuredly ought to be upon the table of every single observatory in the United Kingdom, and of all those in other parts of the world where the language in which it is written is intelligible."—*The English Mechanic.*

"The book is well and clearly printed, and we heartily recommend it to our readers as a most valuable contribution to the literature of double-star astronomy."—*The Observatory.*

MACMILLAN AND CO., LONDON.

Messrs. MACMILLAN & CO.'S PUBLICATIONS.

NEW BOOKS ON IRELAND.

NEW VIEWS ON IRELAND; or, Irish Land Grievances and Remedies. By CHARLES RUSSELL, Q.C., M.P. Crown 8vo. *2s. 6d.*

THE LIFE'S WORK IN IRELAND OF A LANDLORD WHO TRIED TO DO HIS DUTY. By W. BENCE JONES of Lisselan. Crown 8vo. *6s.*

THE IRISH LAND LAWS. By ALEXANDER G. RICHEY, Q.C., LL.D., Deputy Regius Professor of Feudal and English Law in the University of Dublin. Crown 8vo. *3s. 6d.*

"To all who, either as legislators or publicists, are called on to take part in the present controversy, the book will prove invaluable."—*The Times.*

"This book cannot fail to do good."—*St. James's Gazette.*

LIFE OF WILLIAM BLAKE. With Selections from his Poems and other Writings. Illustrated from BLAKE's own Works. By ALEXANDER GILCHRIST. A New and Enlarged Edition, with Additional Letters and a Memoir of the Author. 2 vols. Printed on hand-made paper, the Illustrations on India paper, and mounted in the text. Cloth elegant, gilt, with designs after BLAKE by FREDK. J. SHIELDS. Medium 8vo. *42s.*

"One of the most beautiful and interesting books of the season.....Thus Blake, more than Thoreau, and infinitely more than Rousseau, is a shining example of a man who chose and secured a simple and sufficient measure of happiness. There is no higher philosophy."—*Daily News.*

THE ABBOTT'S FARM; or, Practice with Science. By HENRY TANNER, M.R.A.C., F.C.S., Professor of the Principles of Agriculture in the Royal Agricultural College, Author of "First Principles of Agriculture." Extra fcap. *3s. 6d.*

ISLAND LIFE; or, the Phenomena and Causes of Insular Faunas and Floras, including a revision and attempted solution of the Problem of Geological Climates. By ALFRED RUSSEL WALLACE, Author of "The Malay Archipelago," "The Geographical Distribution of Animals," &c. Medium 8vo, with Illustrations and Maps. *18s.*

"The work throughout abounds with interest."—*Athenæum.*

"He takes his subject matter from all the sciences, and he builds it into a new harmonious whole."—*Fortnightly Review.*

GILBERT WHITE'S NATURAL HISTORY AND ANTIQUITIES OF SELBORNE. New Edition, with a Poem and Letters never before published. Edited, with Notes and Memoir, by FRANK BUCKLAND; a chapter on Antiquities by Lord SELBORNE; and the Garden Kalendar. With Illustrations by Prof. DELAMOTTE. Cheap Edition. Crown 8vo. *6s.*

PHYSICS OF THE EARTH'S CRUST. By Rev. O. FISHER, M.A., F.G.S., Rector of Harlton, &c. 8vo. *[Shortly.*

STUDIES IN DEDUCTIVE LOGIC. By W. STANLEY JEVONS, LL.D., M.A., F.R.S. Crown 8vo. *6s.*

"It is indispensable to the many students of the higher logic."—*Athenæum.*

GUIDE TO THE STUDY OF POLITICAL ECONOMY. By Dr. LUIGI COSSA, Professor of Political Economy in the University of Pavia. Translated from the Second Italian Edition. With a Preface by W. STANLEY JEVONS, F.R.S. Crown 8vo. *4s. 6d.*

"It would be impossible to find a more compact and better-written sketch of the history of Political Economy and its latest developments. . . It is an admirable compendium, and will, we hope, be widely circulated, as it will prove to many for the first time that the study of political economy is even more actively pursued on the Continent, than in England."—*Notes and Queries.*

THE WHITE RAT, AND SOME OTHER STORIES. By LADY BARKER. Illustrated by W. J. HENNESSY. Globe 8vo. *4s. 6d.*

"A pleasant little volume. It is pretty outside, and pleasant in."—*Morning Post.*

GOLDEN TREASURY SERIES.—NEW VOLUME.

ESSAYS OF JOSEPH ADDISON. Chosen and Edited by JOHN RICHARD GREEN, M.A., LL.D. 18mo. *4s. 6d.*

DICTIONARY OF MUSIC AND MUSICIANS (A.D. 1450—1878). By eminent Writers, English and Foreign. Edited by GEORGE GROVE, D.C.L. Three Vols., 8vo, with Illustrations and Woodcuts. Parts I. to XII. each *3s 6d.* Vols. I. and II., 8vo, cloth, each *21s.*

Vol. I.—A to Impromptu. Vol. II. Improperia to Plain Song.

"This work promises to be for music what the best encyclopædias are to general literature and science."—*Guardian.*

ENGLISH POETS: Selections, with Critical Introductions by various Writers, and a General Introduction by MATTHEW ARNOLD. Edited by T. H. WARD, M.A. 4 vols., crown 8vo, each *7s. 6d.*

Vol. I. CHAUCER to DONNE.
Vol. II. BEN JONSON to DRYDEN.
Vol. III. ADDISON to BLAKE.
Vol. IV. WORDSWORTH to SYDNEY DOBELL.

"An excellent design admirably executed."—*Pall Mall Gazette.*

ENGLISH MEN OF LETTERS. Edited by JOHN MORLEY. Crown 8vo. *2s. 6d.* (New Volume)

WORDSWORTH. By F. W. H. MYERS.

THE YEAR'S ART: A Concise Epitome of all matters relating to the Arts of PAINTING, SCULPTURE, and ARCHITECTURE, which have occurred during the Year, together with information respecting the events of the Year 1881. Compiled by MARCUS B. HUISH, Crown 8vo. *2s. 6d.*

THE NECKLACE OF PRINCESS FIORIMONDE; and other Stories. By MARY DE MORGAN. With Twenty-five Illustrations by WALTER CRANE. Fcap. 8vo. *6s.*

Also an Edition of One Hundred Copies on large paper.

"The stories display considerable originality, and Mr. Crane's characteristic illustrations combine with Miss de Morgan's pretty fancies to form a charming gift-book."—*Graphic.*

"A real gem."—*Punch.*

A CHRISTMAS CHILD: a Sketch of a Boy-life. By MRS. MOLESWORTH, Author of "Carrots," "The Cuckoo Clock," &c. Illustrated by WALTER CRANE. Globe 8vo. *4s. 6d.*

"A very sweet and tenderly drawn sketch with life and reality manifest throughout. Very few can rival Mrs. Molesworth in the power of making us see the children of fancy, and in this 'Christmas Child' something has given to her pen a special power."—*Pall Mall Gazette.*

PANSIE'S FLOUR BIN. By the Author of "When I was a Little Girl," &c. Illustrated by ADRIAN STOKES. Globe 8vo. *4s. 6d.*

"Worthy to be classed with 'Alice in Wonderland,' and in some respects is better adapted to juvenile comprehension."—*Morning Post.*

*** *Messrs. MACMILLAN & Co.'s Illustrated Catalogue of Gift and Presentation Books is now ready, and may be obtained on application.*

MACMILLAN & CO., BEDFORD STREET, STRAND, W.C.

Now ready, PART 1, Price 7d.

The Royal Shakspere.

With numerous *FULL-PAGE ILLUSTRATIONS* on *STEEL* and WOOD, from Original Designs by F. DICKSEE, F. BARNARD, A. HOPKINS, J. D. WATSON, V. W. BROMLEY, C. GREEN, J. M'L. RALSTON, &c. &c.

The ROYAL SHAKSPERE will be a COMPLETE EDITION of the great dramatist's Plays and Poems, arranged in chronological order from the Text of the eminent Shaksperian scholar Professor DELIUS. "Edward III." and "The Two Noble Kinsmen" will be included. There will also be an Introduction and Life of Shakspere by Mr. F. J. FURNIVALL, Founder and Director of the New Shakspere Society, who shows the proper method of studying Shakspere, recounts the story of the poet's life, and presents a chronological arrangement of the Plays and Poems.

The Steel Plate *in PART* 1 *is engraved from FRANK DICKSEE'S charming Painting*, "BERTRAM and HELENA."

Cassell, Petter, Galpin & Co., Ludgate Hill, London.

Now ready. Price 9*s*.

SCIENCE FOR ALL. Vol. III. Edited by DR. ROBERT BROWN, M.A., F.L.S. Assisted by Eminent Scientific Writers. Illustrated throughout.

"Whatever branch of science a man may happen to be studying, he is sure to find something to his taste in turning over the pages of this work. After looking through the work we are disposed to think that, on the whole, each volume is an advance upon its predecessors, both in the character of the articles and in the excellence of the illustrations."—*Athenæum*.

Cassell, Petter, Galpin & Co., Ludgate Hill, London.

Now ready. Price 12*s*. 6*d*. each.

FAMILIAR WILD FLOWERS. First and Second Series. By F. E. HULME, F.L.S., F.S.A. Each series is complete in one volume, and contains FORTY Exquisite COLOURED PLATES, with descriptive text.

"An exquisite volume. . . It is illustrated with forty plates, which are among the most beautiful illustrations of plants which have appeared in any popular work."—*Westminster Review*.

Cassell, Petter, Galpin & Co., Ludgate Hill, London.

Now ready. Price 12*s*. 6*d*.

FAMILIAR GARDEN FLOWERS. First Series. Complete in One Volume. By SHIRLEY HIBBERD, with FORTY charming COLOURED PLATES from original paintings by F. E. HULME, F.L.S., F.S.A.

"It is got up in quite an elegant form, and is really handsome."—*Queen*.

"Refined in colouring and admirably true to Nature are Mr. Hulme's drawings."—*Graphic*.

Cassell, Petter, Galpin & Co., Ludgate Hill, London.

Now ready, PART I., price 1*s*., of the NEW SERIAL ISSUE of

THE ILLUSTRATED BOOK OF PIGEONS. By ROBERT FULTON, assisted by the most Eminent Fanciers. Edited and arranged by LEWIS WRIGHT. With FIFTY LIFE-LIKE COLOURED PLATES, painted expressly for this Work; and with numerous ENGRAVINGS ON WOOD.

Cassell, Petter, Galpin & Co., Ludgate Hill, London.

Now ready, price **1s.**; post free **1s. 3d.**

The Live Stock Journal Almanack for 1881,

With which is incorporated **The Farmer's Almanack.**

EVERY FRIDAY, PRICE **4d.**

The Live Stock Journal & Fancier's Gazette.

A CHRONICLE FOR COUNTRY GENTLEMEN, BREEDERS, AND EXHIBITORS.

THE LIVE STOCK JOURNAL AND FANCIER'S GAZETTE is the official organ of the ROYAL AGRICULTURAL, SHORTHORN, SMITHFIELD CLUB, BRITISH DAIRY FARMERS', ENGLISH CART HORSE, CLYDESDALE, and other ASSOCIATIONS, and now stands without a rival as a Chronicle for Country Gentlemen, Breeders, and Exhibitors. Amongst the Subjects which are fully treated in THE LIVE STOCK JOURNAL are—

Horses,	**Pigs,**	**Pigeons,**	**Rabbits,**	**Poultry Farming,**
Cattle,	**Dogs,**	**Aviary,**	**Pets,**	**Fish Culture,**
Sheep,	**Poultry,**	**Goats,**	**Dairy Farming,**	**Natural History,**

Notes and Queries, &c., &c., &c.

Terms of Subscription by Post—Three Months, **4s. 11d.**; *Six Months*, **9s. 9d.**; *Twelve Months*, **19s. 6d.**

Publishing Office and Office for Advertisements: LA BELLE SAUVAGE YARD, LUDGATE HILL, E.C.

Printed by R. CLAY, SONS, AND TAYLOR, at 7 and 8, Bread Street Hill, Queen Victoria Street, in the City of London, and published by MACMILLAN AND CO., at the Office, 29 and 30, Bedford Street, Covent Garden.—THURSDAY, December 30, 1880.

NATURE

A WEEKLY ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
Of Nature trusts the mind which builds for aye."—WORDSWORTH

No. 584, VOL. 23] THURSDAY, JANUARY 6, 1881 [PRICE SIXPENCE

Registered as a Newspaper at the General Post Office.]

[All Rights are Reserved.

PRELIMINARY SCIENTIFIC EXAMINATION.—UNIVERSITY OF LONDON.

A Class in all the Subjects (including Practical Work) for this Examination is held at St. Bartholomew's Hospital, continuing till the Examination in July The Class is open to Candidates who are not Students of the Hospital, as well as to Students, and will begin on TUESDAY, January 18th.

Botany—Rev. G. Henslow, M.A., Christ's Coll., Camb.; Lecturer on Botany to the Hospital.
Zoology—Norman Moore, M.D. St. Cath. Coll., Camb., Lecturer on Comparative Anatomy to the Hospital.
Chemistry—H. E. Armstroog, Ph.D., F.R.S., Demonstrator of Chemistry.
Physics—Donald McAlister, B.A., Fellow of St. John's Coll., Camb., Demonstrator of Physics.

Fee for the whole Course (including Chemicals) to Students of the Hospital, £8 8s.; to others, £10 10s.

Particulars may be ascertained on application, personally or by letter, to the WARDEN of the College, St. Bartholomew's Hospital, E.C. A Handbook forwarded on application.

UNIVERSITY OF LONDON.

PRELIMINARY SCIENTIFIC AND 1ST M.B. EXAMINATIONS.

Special Classes in all the Subjects required for these Examinations will commence at St. Thomas's Hospital Medical School early in JANUARY. Full particulars may be obtained from the Secretary, Dr. GILLESPIE.

SAINT PAUL'S SCHOOLS.—About 12

Scholarships will be awarded next Term.—For information, address CLERK TO GOVERNORS, Mercers' Hall, E.C.

Microscopes and other Scientific Apparatus

C. BAKER,

244 & 245, HIGH HOLBORN,

Begs to call the attention of the Scientific to his Extensive Stock of Instruments at the lowest possible prices, *viz.* :—

ACHROMATIC MICROSCOPES: the Largest Assortment in London can be selected from, from £3 3s.
ASTRONOMICAL TELESCOPES from £5 5s.
FIELD GLASSES in Leather Sling Cases, from 20s.
OPERA GLASSES in Ivory, Leather, Metal, &c., from 12s. 6d.
GOLD SPECTACLES of every kind from 15s.
THE BEST LONDON-MADE PEBBLES IN STEEL FRAMES, 10s. 6d.
PLAIN STEEL DITTO, from 3s. 6d.
FOLDING HAND SPECTACLES IN TORTOISESHELL, STEEL, &c., from 3s. 6d.
DISSOLVING VIEW APPARATUS, complete from £6 10s.
MAGIC LANTERNS, from 6s. 6d.; Slides, all kinds, from 1s. 3d.

CATALOGUES FREE BY POST.

Second Hand Scientific Instruments.

C. BAKER'S new Catalogue of Scientific Instruments is now out; Selections can be made from a very large stock, comprising MICROSCOPES, ASTRONOMICAL TELESCOPES, TRANSIT INSTRUMENTS, REGULATORS, SPECTROSCOPES, METEOROLOGICAL and ELECTRICAL APPARATUS, DISSOLVING VIEWS, &c. All at the very lowest prices.

Catalogues of same Free by Post. *Instruments taken in exchange.*
ESTABLISHED 1765.

The "EURYSCOPIC" Opera, in case, £2 2s.

For the Theatre, has the largest field of view, giving delightfully easy vision.

ILLUSTRATED CATALOGUE FREE BY POST.

JOHN BROWNING,

63, STRAND, LONDON, W.C.

ESTABLISHED ONE HUNDRED YEARS.

STANDARD METEOROLOGICAL INSTRUMENTS

Now ready, a New Edition of Negretti & Zambra's Encyclopædic Catalogue of Mathematical, Philosophical, Optical, and Standard Meteorological Instruments, containing numerous Comparative Tables of Reference, and Illustrated by Twelve Hundred Engravings.

Royal 8vo, cloth, gilt lettered, price 5s. 6d.

NEGRETTI & ZAMBRA,

Opticians and Scientific Instrument Makers

To HER MAJESTY THE QUEEN,

HOLBORN VIADUCT,

45, CORNHILL, & 122, REGENT STREET, LONDON.

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 48N, Tollington Road, Holloway, London, N.

INSTITUTE OF CHEMISTRY.

PRIZES.

DR. FRANKLAND has offered a Prize of £50 for the best Original Investigation involving Gas Analysis, and DR. C. MEYMOTT TIDY has also offered a Prize of £25 for the best Original Investigation on Special Reactions of the Alkaloids and their Separation from Organic Mixtures. These prizes will be open to Associates, and to all persons (except Fellows of the Institute) who shall, before the 31st of December next, have qualified for the Associateship in all respects, short of passing the prescribed practical examination; and successful competition for these prizes will be accepted in lieu of such practical examination.

Further information may be obtained on application to the Secretary, Mr. C. E. GROVES, Somerset House Terrace, W.C.

OWENS COLLEGE, MANCHESTER.

The LENT TERM begins on TUESDAY, January 11. New Students will be admitted on Monday, the 10th, from 11 a.m. to 4 p.m. Candidates must not be under 14 years of age, and those under 16 will be required to present themselves on Tuesday, the 11th, at 10.30 a.m., for examination in English, Arithmetic, and the elements of Latin.

The Courses of Study are adapted to the requirements of Candidates for the Arts and Science Degrees of the University of London.

The Junior Classical Classes will commence after Christmas to read the books set for Matriculation in June, 1881.

J. HOLME NICHOLSON, Registrar.

INSTRUCTION IN MATHEMATICS.—

Youths or Adults attended at their Residence, on Reasonable Terms, by a M.A. of Cambridge. Unquestionable references if required.—Address, by letter, O. P., Post Office, Turnham Green.

ROYAL POLYTECHNIC.—CLASSES for

the preparation of Students for University Examinations, under the direction of EDWARD B. AVELING, D.Sc., F.L.S. London University Matriculation, 1st and 2nd B.Sc., Preliminary Scientific M.B., Botany, Physiology, Chemistry. All the work practical.

JAWS or TEETH of LOWER TERTIARY

MAMMALS wanted, at reasonable price.—Address Mr. HERBERT, Freshwater, Isle of Wight

CHEMICAL & PHYSICAL RESEARCH.

—A Gentleman or Youth, desirous of pursuing it, may communicate with X., care of H. M Chichester, 97, Belgrave Road, S.W.

QUEENWOOD COLLEGE, near STOCK-

BRIDGE, HANTS. A High-Class School for Boys. The course of study is adapted to the pupils' requirements. For view of the College see *Graphic* of December 25th, 1880. The Spring Term begins Friday, January 21st. Applications to the Principal, C. WILLMORE.

GEOLOGY AND MINERALOGY.

JOHN TYM has ready for Sale, at low prices, Educational Collections of Fossils, Rocks, and Minerals, specially arranged to illustrate the text-books of Lyell, Geikie, Bonney, Collins, Davies, Skertchley, Dana, Page, Jukes, &c. Series of Specimens for School and College Museums are also supplied at very reasonable prices. Catalogues post free.

Postal Address:—CASTLETON, *viâ* SHEFFIELD.

ROCK SECTIONS & ROCK SPECIMENS.

Collections of Rock Specimens to illustrate Rutley's "Study of Rocks" specially prepared. 100 Small Specimens in Cabinet, One Guinea; 200 Specimens, Two Guineas. Extensive and choice Series of Rocks for selection. New List of Sections of Rocks for Microscope, and List of Collections, &c.

JAMES R. GREGORY'S

Extensive New Museum and Show Rooms,

88, CHARLOTTE STREET, FITZROY SQUARE.

GEOLOGY.—In the Preface to the STU-

DENT'S ELEMENTS of GEOLOGY, by Lyell, 1874, he says: "As it is impossible to enable the reader to recognise rocks and minerals at sight by aid of verbal descriptions or figures, he will do well to obtain a well-arranged collection of specimens, such as may be procured from Mr. TENNANT (149, Strand), Teacher of Mineralogy at King's College, London." These Collections are supplied on the following terms, in plain Mahogany Cabinets:—

100 Specimens, in Cabinet, with 3 Trays	...	...	£2 2 0
200 Specimens, in Cabinet, with 5 Trays	...	...	5 5 0
300 Specimens, in Cabinet, with 9 Drawers	...	...	10 10 0
400 Specimens, in Cabinet, with 13 Drawers	...	...	21 0 0

More extensive Collections at 50 to 5,000 Guineas each.

LIVING SPECIMENS FOR THE MICROSCOPE.

THOMAS BOLTON, NATURALISTS' and MICROSCOPISTS' STUDIO, 17, ANN STREET, BIRMINGHAM.

T. B. has last week sent to his subscribers a rare and interesting Infusorian, *Follicularia ampulla*, with drawing and description. It is described and figured in the "Micrographic Dictionary." He has also sent out *Corymo sessilis*, Trout Spawn, *Arellus vulgaris*, *Philodina roseola*, *Volvox globator*, &c.

Weekly announcements will be made in this place of organisms T. B. is supplying.

Specimen Tube, One Shilling, post-free.

Twenty-six Tubes in course of Six Months for Subscription of £1 1s.

Price List of Specimens on application, with stamped addressed envelope.

Portfolio of Drawings, No. 3, One Shilling.

MINERALOGY AND GEOLOGY.

FINE CRYSTALLISED DANBURITES, the first Specimens received in England.

MAGNIFICENT CRYSTAL of MATLOCKITE from Derbyshire.

VERY BRILLIANT and FINELY CRYSTALLISED AUGITE, from Sweden.

VERY LARGE and FINE CRYSTALS of LIBETHENITE, CHALCOSIDERITE, CUPRITE, LIROCONITE, CASSITERITE, BISMUTHINE, HENWOODITE.

COLLECTIONS FOR STUDENTS, from £2 2s. COLLECTIONS FOR BEGINNERS, from 4s. BLOWPIPE CASES AND APPARATUS.

PRIVATE LESSONS AND EVENING CLASSES.

Catalogues free.

SAMUEL HENSON,

277 (*Late* 113*a*), STRAND, LONDON, W.C.

CHRISTMAS PRESENTS.—The Popular

SCIENTIFIC POCKET CABINET SERIES. (SECOND EDITION.)

20 Specimens of Rocks, Fossils, and Minerals to illustrate Prof. Geikie's Geology Primer.

25 Minerals, Rocks, and Fossils to illustrate Bonney's Geology.

25 British Rocks. 25 British Fossils. 25 Earthy Minerals. 25 Metalliferous Minerals. 25 Metals and Alloys. 25 Recent Shells. 20 Rough Gems and Stones.

Each Collection complete in itself, price 2s. 6d.

*** The Specimens are sufficiently large for recognition of the Species, and are contained in Small Cabinets suitably adapted for carrying in the Pocket.

THOMAS J. DOWNING, Geologist, &c., 38, WHISKIN STREET, LONDON, E.C. N.B.—Post Office Order or Cheque must invariably accompany all Orders, with an additional Fourpence on each set for free delivery.

THOMAS D. RUSSELL'S

NATURAL HISTORY STORES,

48, ESSEX STREET, STRAND, W.C.

Students and others are invited to inspect the Collections of British and Foreign Shells, Corals, Zoophytes, Annelids, Crustacea, Echinoderms, Minerals, Fossils, Rock Specimens, Microscopic Objects, &c.

Cabinets, Geologist's Hammers, Glass Capped Boxes, Card Trays, Tablets, Glass Slips, Micro-Thin Glass, Canada Balsam, Marine Glue, and other requisites for the Geologist and Microscopist.

Catalogues Post Free.

On the 1st of every Month, price Sixpence.

THE ENTOMOLOGIST:

AN ILLUSTRATED JOURNAL OF BRITISH ENTOMOLOGY.

Edited by JOHN T. CARRINGTON,

With the Assistance of

FREDERICK BOND, F.Z.S. | JOHN A. POWER, M.D.
EDWARD A. FITCH, F.L.S. | J. JENNER WEIR, F.L.S.
F. BUCHANAN WHITE, M.D.

Contains Articles by well-known Entomologists on all branches of the Science; on Insects injurious or beneficial to Farm or Garden: Notes on Habits, Life-Histories; occurrence of Rarities, &c.; there are monthly lists of Duplicates and Desiderata.

Numerous WOODCUT ILLUSTRATIONS, to the printing of which especial attention is given, and occasional LITHOGRAPHED and CHROMO-LITHOGRAPHED PLATES.

SIMPKIN, MARSHALL, & CO., Stationers' Hall Court.

"The leading Farmers' paper."—CLARE SEWELL READ, ESQ., M.P.

THE CHAMBER OF AGRICULTURE JOURNAL

AND FARMERS' CHRONICLE

(PRICE 3*d.* WEEKLY).

The representative organ of the Central and Provincial Chambers of Agriculture; *gives fuller reports of the discussions and proceedings* of this extensive organisation than any other agricultural paper. It devotes *special attention to the treatment of Agricultural Questions by Parliament*, besides containing ample Reports of the LATEST LONDON and COUNTRY CORN, CATTLE, HOP, PROVISION, and other Markets, with Original Articles on Practical Farming, the Dairy, Herd and Flock News, Horticulture, &c., &c. It is despatched every Monday evening in time for the country post.

Terms of Subscription, payable in advance, post free:—3 months, 3s. 9½*d.*; 6 months, 7s. 7*d.*; 12 months, 15s. 2*d.*

Published by W. PICKERING, 21, Arundel Street, Strand, London, W.C.

Price 3s. Quarterly; Yearly, 12s., post free.

MIND: No. XXI.

I. Illusions of Introspection, by J. Sully.
II. Our Control of Space and Time, by J. Venn.
III. M. Renouvier's Logic, by S. H. Hodgson.
IV. The *Summum Bonum*, by D. G. Thompson.
V. Replies to Criticisms on "The Data of Ethics," by H. Spencer.
Notes, Critical Notices, &c., by G. S. Hall, Editor, Prof. Land, J. Collier, &c.

WILLIAMS & NORGATE, London and Edinburgh.

LA SEMAINE FRANÇAISE: a Weekly Newspaper and Review in the French Language. Politics, Literature, Science, Art, Varieties, Notes. Price 3*d.*, through booksellers, and at the railway bookstalls. Office, 37, Southampton Street Strand, W.C.

LA SEMAINE FRANÇAISE: Journal Française pour l'Angleterre: Politique, Littérature, Sciences, Arts, Variétés, Nouvelles, et Notes. Un exemplaire par la poste, 3½*d.*, en timbres poste Abonnement franco par la poste—un an, 15*s.* 2*d.*; six mois, 7*s.* 7*d.* Prix 3*d.*, chez tous les libraires et aux gares des chemins de fer. On s'abonne aux bureaux, 37, Southampton Street, Strand, Londres, W.C.

LA SEMAINE FRANÇAISE.—"'La Semaine Française' has been brought out in London for the benefit of those English readers who may wish to study contemporary French from all points of view, instead of confining their reading to one particular Gallic print. It certainly merits success."—*Graphic.*

LA SEMAINE FRANÇAISE.—"The numbers before us are full of good things. . . . . It will be far better for most than any one of the best papers published in Paris itself. We are much pleased with the character of it, and believe it will be highly valued in all those many households where French is cultivated. The printing is very well done."—*Queen.*

TERMS OF SUBSCRIPTION:—

	s.	d.
Three months	3	10
Six ,,	7	7
Twelve ,,	15	2

P.O.O. payable to T. SPANSWICK, at King Street, Covent Garden, W.C.
Publishing Office, 37, Southampton Street, Strand, W.C.

THE ENTOMOLOGIST'S MONTHLY MAGAZINE.

Price Sixpence, Monthly, 24 pages 8vo, with occasional Illustrations. Conducted by J. W. DOUGLAS, R. M'LACHLAN, F.R.S., E. C. RYE, F.Z.S. and H. T. STAINTON, F.R.S.

This Magazine, commenced in 1864, contains standard articles and notes on all subjects connected with Entomology, and especially on the Insects of the British Isles.

Subscription—Six Shillings per Volume, post free. The volumes commence with the June number in each year.

Vols. I. to V. (strongly bound in cloth) may be obtained by purchasers of the entire set to date, at the increased price of 10*s.* each; the succeeding vols. may be had separately or together, at 7*s.* each.

London: JOHN VAN VOORST, 1, Paternoster Row.

N.B.—Communications, &c., should be sent to the Editors at the above address.

NORTH BRITISH AGRICULTURIST is the only Agricultural Journal in Scotland, and circulates extensively amongst Landed Proprietors, Factors, Farmers, Farm-bailiffs, and others interested in the management of landed property throughout Scotland and the Northern Counties of England.

The AGRICULTURIST has also a very considerable circulation on the Continent of Europe, America, Australia, and the Colonies.

The AGRICULTURIST is published every Wednesday afternoon in time for the evening mails, and contains Reports of all the principal British and Irish Markets of the week, besides Telegraphic Reports of those held on the day of publication.

The Veterinary Department is edited by one of the leading Veterinarians in the country, and is invaluable to the breeder and feeder as a guide to the rearing of animals, and their treatment when labouring under disease.

Full Reports are given of the Meetings of the Royal Agricultural Society of England, the Royal Agricultural Society of Ireland, the Highland and Agricultural Society of Scotland, the Scottish Chamber of Agriculture, and all the principal Agricultural Associations throughout Great Britain and Ireland.

For Advertisers addressing themselves to Farmers a better medium does not exist

Price 3*d.* By post 3½*d.* Annual Subscription, payable in advance, 14*s.*
Office—377, High Street, Edinburgh.
Post-Office Orders payable to Charles Anderson, Jun., Edinburgh.
ESTABLISHED 1843.

On the 1st of every Month, price One Shilling.

THE ZOOLOGIST:

A MONTHLY MAGAZINE OF NATURAL HISTORY.

Third Series. Edited by J. E. HARTING, F.L.S., F.Z.S., Member of the British Ornithologists' Union; contains—

Original articles by well-known naturalists in every branch of zoology; habits of animals; arrival and departure of migratory birds; occurrence of rare birds; distribution and migration of British fresh-water fish; new or rare marine fish; local aquaria; British reptiles, British land and fresh-water mollusca, with remarks on the haunts and habits of the species; and other matters of general interest to those who delight in natural history. Reports of the Linnean, Zoological, and Entomological Societies. Reviews of natural history books. Occasional translations from foreign zoological journals of important and interesting articles in various branches of zoology. There are occasional woodcuts.

JOHN VAN VOORST, 1, Paternoster Row.

5me ANNÉE **L'ÉLECTRICITÉ** 5me ANNÉE

Paris. — 16, *rue du Croissant.* — *Paris*

Revue spéciale populaire, illustrée, bi-mensuelle contenant 24 pages grand in-8° à deux colonnes, formant chaque année un magnifique volume de 400 pages orné de plus de 200 gravures.

Rédacteur en chef: **W. DE FONVIELLE**
Directeur: **E. de Clisson**

Envoi gratis de numéro specimen sur demande

Un numéro 75 centimes

Paris et Départements: Un an..... 12 fr.
Etranger. — Union postale: Un an..... 14 fr.

Les Abonnements partent du 5 et du 20 de chaque mois.

THE "HANSA"

Published since 1864 in Hamburg, is the only independent professional paper in Germany, dedicated exclusively to Maritime Objects. Essays, Critiques, Reviews, Reports, Advertisements. Strict eye kept upon the development of Maritime Affairs in every respect. Every second Sunday one Number in 4to at least; frequent supplements and drawings. Subscription at any time; preceding numbers of the year furnished subsequently. Price 12*s.* for twelve months. Advertisements 4*d.* a line, widely spread by this paper; considerable abatement for 3, 6, 12 months' insertion. Business Office: Aug. Meyer and Dieckmann, Hamburg, Alterwall. 98. Edited by W. v. FREDEN, M.R., Hamburg, Alexander Street, 8.

On the 1st of every Month.

TRIMEN'S JOURNAL OF BOTANY,

BRITISH AND FOREIGN.

New Series. Edited by JAMES BRITTEN, F.L.S., British Museum.

CONTENTS.—Original Articles by leading Botanists.—Extracts, and Notices of Books and Memoirs.—Articles in Journals.—Botanical News.—Proceedings of Societies

Price 1*s.* 3*d.* Subscription for One Year, payable in advance, 12*s.*
London: WEST, NEWMAN, & CO., 54, Hatton Garden, E.C.

The PHOTO-CHEMISTRY of the RETINA and VISUAL PURPLE. Translated from the German of Dr. KÜHNE, and Edited, with Notes, by MICHAEL FOSTER, M.D., F.R.S. 8vo, price 3*s.* 6*d.*

A TEXT-BOOK of PHYSIOLOGY. By MICHAEL FOSTER, M.D. F.R.S. New Edition, Enlarged, with additional Plates. 8vo. 21*s.*

The ELEMENTS of EMBRYOLOGY. By MICHAEL FOSTER, M.D., F.R.S., and F. M. BALFOUR, M.A. Part I. Crown 8vo. 7*s.* 6*d.*

PRACTICAL PHYSIOLOGY: an ELEMENTARY COURSE of. By Dr. M. FOSTER, F.R.S., assisted by J. LANGLEY. Fourth Edition. Crown 8vo. 6*s.*

PHYSIOGRAPHY: an Introduction to the Study of Nature. By Professor HUXLEY, F.R.S. With Coloured Plates and Woodcuts. New and Cheaper Edition. Crown 8vo. 6*s.* [*Fourteenth Thousand.*

ELEMENTARY BIOLOGY: a Course of Practical Instruction in. By Prof. HUXLEY, F.R.S., and H. N. MARTIN, M.B., D.Sc. Third Edition. Crown 8vo. 6*s.*

The OSTEOLOGY of the MAMMALIA: a Series of Lectures. By Prof. W. H. FLOWER, F.R.S., F.R.C.S. With numerous Illustrations. New Edition, Enlarged. Crown 8vo. 10*s.* 6*d.*

MACMILLAN & CO., LONDON.

FRY'S COCOA

GOLD MEDAL, PARIS EXHIBITION.

In Packets and Tins. Pure Cocoa only, with the superfluous oil extracted.

"If properly prepared, there is no nicer or more wholesome preparation of cocoa."—*Food, Water, and Air, edited by Dr. Hassall.*

EXTRACT

J. S. FRY & SONS, Bristol and London.

HOLLOWAY'S PILLS

THIS MEDICINE

Is a Certain Cure for all Disorders of the LIVER, STOMACH AND BOWELS. A Great PURIFIER of the BLOOD; a Powerful Invigorator of the System, in cases of WEAKNESS AND DEBILITY, and is unequalled in Female Complaints.

JUST PUBLISHED.

With 2 Maps and 106 Woodcuts, Crown 8vo, Cloth, price 5s.

The Natural Conditions of Existence as they Affect Animal Life.

By KARL SEMPER.

*** Vol. XXXI. of "The International Scientific Series."

London: C. KEGAN PAUL & CO., 1, Paternoster Square.

JUST PUBLISHED, Crown 8vo, cloth. 5s.

CONSCIOUS MATTER;

OR,

THE PHYSICAL and the PSYCHICAL UNIVERSALLY IN CAUSAL CONNECTION.

By W. STEWART DUNCAN.

London: DAVID BOGUE, 3, St. Martin's Place, Trafalgar Square, W.C.

WESLEY COLLEGE, SHEFFIELD.

(*Affiliated to the London University*, 1844.)

Governor and Chaplain, Rev. W. H. DALLINGER, F.R.S. Head Master, H. M. SHERA, Esq., M.A., LL.D.
Second Master, R. SHINDLER, Esq., M.A. (Lond.).
And Eighteen Assistant Masters and Professors.

The object aimed at in this Institution is a sound and comprehensive mental training. The course of study is fully adapted to the requirements of the present time and to the prospective wants of the pupils, who, whether in preparation for the Universities, training for scientific pursuits, or for professional or commercial life, are provided with the most efficient aids.

BIOLOGY, PHYSICS, and CHEMISTRY, the Modern Languages of Europe, Hebrew and Syriac, Vocal and Instrumental Music, and Drawing, are taught by accomplished Professors.

The Rev. W. H. DALLINGER, F.R.S., has undertaken the Professorship of NATURAL SCIENCE, and gives Weekly Lectures and Class Instruction in Practical Zoology, Botany, &c.

Physics and Chemistry are taught by A. H. ALLEN, Esq., F.C.S.

Scholarships are awarded, worth in the aggregate 300*l.* a year.

Prospectuses may be had by application to the GOVERNOR or HEAD MASTER.

Just Published, free for One Stamp,

The NATURAL HISTORY and SCIENTIFIC BOOK CIRCULAR, No. 45.—New and Ancient Works in Astronomy, Botany, Chemistry, Conchology, Entomology, Ornithology, Physics, Zoology, and GEOLOGY AND PALÆONTOLOGY.

WM. WESLEY, 28, Essex Street, Strand, London.

EDITED BY HENRY WATTS, B.A., F.R.S.,
Editor of the *Journal* of the Chemical Society

FOWNES' PHYSICAL and INORGANIC CHEMISTRY. Twelfth Edition, with Coloured Plate and 154 Engravings, crown 8vo. 8s. 6d.

Also,

FOWNES' CHEMISTRY OF CARBON COMPOUNDS; or, ORGANIC CHEMISTRY. Twelfth Edition, with Engravings, crown 8vo. 10s.

London: J. & A. CHURCHILL.

METALS and their CHIEF INDUSTRIAL APPLICATIONS. By C. ALDER WRIGHT, D.Sc., Lecturer on Chemistry in St. Mary's Hospital Medical School. With Illustrations.

MACMILLAN & CO., LONDON.

With 112 Engravings and 5 Maps of the Stars

POPULAR ASTRONOMY.

BY

PROFESSOR S. NEWCOMB, LL.D.

8vo, cloth, price 18s.

"As affording a thoroughly reliable foundation for more advanced reading, Prof. Newcomb's 'Popular Astronomy' is deserving of strong recommendation."—*Nature.*

"When we take up a book written by one of the foremost astronomers, mathematically and practically, of the day, we need not fear that, however popular, it will be inexact in its language or evasive in its descriptions. Nor are we disappointed in the book before us. Throughout the whole of it we are struck by the total absence of the defects so common in popular writings. . . . It is unlike anything else of its kind, and will be of more use in circulating a knowledge of astronomy than nine-tenths of the books which have appeared on this subject of late years."—*Saturday Review.*

MACMILLAN & CO., LONDON

NEW WORK BY LIONEL S. BEALE.

Now ready, pp. 230, demy 8vo, 5s.

SLIGHT AILMENTS:
THEIR NATURE AND TREATMENT.

By LIONEL S. BEALE, M.B., F.R.S., F.R.C.P.,
Professor of the Principles and Practice of Medicine in King's College, London.

J. & A. CHURCHILL, New Burlington Street.

Now ready.

EXERCISES in PRACTICAL CHEMISTRY. Vol. I. (ELEMENTARY EXERCISES). By A. G. VERNON HARCOURT, M.A., F.R.S., Senior Student of Christ Church, and Lee's Reader in Chemistry; and H. G. MADAN, M.A., Fellow of Queen's College, Oxford. Third Edition, Revised and considerably Enlarged, crown 8vo, cloth, 9s.

London: HENRY FROWDE, Clarendon Press Warehouse, 7, Paternoster Row.

Second Edition, with Maps, price 10s. 6d., pp. 447.

EPIDEMIOLOGY; or, The Cause of Epidemic Disease, of Murrains, of Blight, of Hurricanes, and of Abnormal Atmospherical Vicissitudes. With a History of Epidemic Diseases, and of the Phenomena that accompanied them. By JOHN PARKIN, M.D.

DAVID BOGUE, St. Martin's Place, London, W.C.

BRYCE-WRIGHT'S LATEST ARRIVALS.

MINERALS.—Crystallised Hessite, Crystallised Golds, Krennerite, Crystallised Atacamites, Malacone, Euclase, Edingtonite, Suzannite, Chanarcillite, Proustite, &c.

METEORITES.—Specimens of the following Falls:—Wold Cottage, Yorkshire; Java; Orvinio, Italy; Amana, Ohio; Tipperary, Ireland; Java; Orvinio, Italy; Estherville; Hainholz; Grosnagy, Russia; Borkut; Carthago Co.; Bates Co.; Sierra di Chaco; Ashville Co.; Bates Co.; Pallas; Ashville Co., &c., &c.

BRYCE-WRIGHT, F.R.G.S., &c.,
Mineralogist and Expert in Gems and Precious Stones,
90, GREAT [illegible] STREET, BLOOMSBURY, W., W.C.

THURSDAY, JANUARY 6, 1881

DR. GÜNTHER ON FISHES

An Introduction to the Study of Fishes. By Albert C. L. G. Günther, M.A., M.D., Ph.D, F.R.S., Keeper of the Zoological Department in the British Museum. (Edinburgh: A. and C. Black, 1880.)

A GENERAL work on Fishes could not have been undertaken by a more thoroughly qualified writer than Dr. Günther. Twenty years ago and more he commenced studying the collection of this ever-interesting and most important group in the vaults of the British Museum, with what success let not only the present fine collection of fish in the National Museum declare, but also that truly wonderful work, to be the product of one man's labours, "The Catalogue of Fishes," in eight volumes, published by order of the Trustees of the British Museum. Fishes have always been a subject of great interest to mankind; their commercial value interests some, others, as keen sportsmen, could not exist without their finny prey; from the earliest times, and among the earliest records, we find them of importance as articles of food. To the man of science, be he or be he not a specialist, fishes are of an ever-increasing interest, placed at the very beginning of vertebrate life, and by their study we seem to see more clearly into the evolution of that life which culminated in the production of ourselves.

A book to tell us in carefully selected generalities all about fishes: such the English reader had no access to, until the publication of this volume. If it come not up to a perfect standard how could it be otherwise, for had not the history of the structure of fish, their habits, their distribution, their classification to be condensed within the limit of a few hundred pages, and the wonder is that so much will be found here given, not that a few things have been left unnoticed or but partially touched upon. We have looked over each page of the handsomely got-up, well-printed, and well-illustrated volume, and we feel certain that it must find a place on the shelf of all biologists, and that it will find a place in the libraries also of that vastly larger class, the intelligent general reader.

The first and slightly smaller half of the volume treats of fishes in general; the second half of fishes from a systematic and descriptive point of view. The work opens with an account of the history and literature of the subject beginning with Aristotle; who had a perfect knowledge of the general structure of fish, and who wrote about them some three and a half centuries before the Christian era; which account is continued to the most recent times; the work done by Ray, Artedi, Linneus, Bloch, Lacépède, Cuvier, Agassiz, Müller, being passed in review. The next twelve chapters treat of the external morphology of fish and of their internal structure. We would have liked more details about the recent researches into the modifications to be met with in fishes' tails; the description of the electrical organs to be met with in some fish is far too brief; the myology of fishes is dismissed with a little over a page, as if it were not a favourite subject with the author, and yet it is one worth working at and by no means deficient in promise. In the chapter on Respiration the subject of the temperature in fishes is scarcely alluded to; the chapter on the Reproductive Instincts of Fish is sure to interest the readers, some of whom may learn for the first time of female fishes taking care of their progeny, and more curious, of male fishes doing the same. The chapter on the Growth and Variation of Fishes is well illustrated by woodcuts of some remarkable changes of form in fish. The fourteenth chapter treats of domesticated and acclimatised fishes, on the artificial impregnation of ova, tenacity of life and reproduction of lost parts, hybernation in fishes (a misuse of this term), useful and poisonous fishes. The uses of fishes to man our author disposes of in twelve lines, and it would almost seem as if he would rather not have referred to such a subject at all in the scientific part of this treatise. In these twelve lines we find the following:—"In the Polar regions *especially* whole tribes are *entirely* dependent on this class for subsistence." Without venturing on criticism we would ask, Is this so? Do the inhabitants of the Polar regions support their life wholly on fish, or are they not indebted for a large portion of their heat-producing food to the flesh or blubber of mammals? and do not the inhabitants of tropical countries, on the contrary, manage often to support their existence almost entirely on fish food?

While the chapters concerning the distribution of fishes in time leave a good deal to be desired, those on the distribution of fishes in space are most excellent; that on the fishes of the deep sea contains a complete list of deep-sea forms with the depths as ascertained by the dredgings of the *Challenger*, which list contains apparently over 100 species. Before the voyage of the *Challenger* scarcely thirty deep-sea fishes were known. Though this number has been now so very much increased yet no new types of families have been discovered. Perfectly novel and very interesting modifications of certain organs have been met with, but nothing more than what might have been expected from our previous knowledge of the group. The greatest depth reached hitherto by a dredge in which fishes were inclosed is 2900 fathoms; but the specimens then obtained belong to a species (*Gonostoma microdon*), which would seem to be extremely abundant in the upper strata of the Atlantic and Pacific Oceans, and were very probably caught by the dredge in its ascent. The next greatest depth, 2750 fathoms, must be accepted as one at which fishes undoubtedly do live. The fish obtained at this depth in the Atlantic, *Bathyophis ferox*, showing by its whole habit that it is a form living on the bottom of the ocean.

"The fish fauna of the deep sea," writes Dr. Günther, "is composed chiefly of forms or modifications of forms which we find represented at the surface in the cold or temperate zones, or which appear as nocturnal pelagic forms." The Chondropterygians are few in number, not descending to a depth of more than 600 fathoms. The Acanthopterygians, which form the majority of the coast and surface faunas, are also scantily represented; genera identical with surface types are confined to the same inconsiderable depths as the Chondropterygians, while those Acanthopterygians which are so much specialised for the life in the deep sea as to deserve generic separation, range from 200 to 2400 fathoms. Three distinct families belong to the deep sea fauna, viz. Trachypteridæ, Lophotidæ, and Notacanthidæ; they

respectively consist of three, one, and two genera. Gadidæ, Ophidiidæ, and Macruridæ are very numerous, ranging through all depths; they constitute about one-fourth of the whole deep-sea fauna. Of Physostomi, the families of Sternoptychidæ, Scopelidæ, Stomiatidæ, Salmonidæ, Bathythrissidæ, Alepocephalidæ, Halosauridæ, and Murænidæ are represented. Of these the Scopeloids are the most numerous, constituting nearly another fourth of the fauna. Salmonidæ are scarce, with three small genera only. Bathythrissidæ includes one species only, which is probably confined in its vertical as well as horizontal range: it (*Bathythrissa dorsalis*) occurs at a depth of about 350 fathoms in the sea of Japan. The Alepocephalidæ and Halosauridæ, known before the *Challenger* Expedition from isolated examples only, prove to be true, widely spread, deep-sea types. Eels are well represented, and seem to descend to the greatest depths; Myxine has been obtained from a depth of 345 fathoms.

In the systematic portion Dr. Günther divides the class of fishes into four sub-classes—the first Palæichthyes, the second Teleostei, the third Cyclostomata, and the fourth Leptocardii. The description of each order, sub-order, and family is given. In addition we have the diagnosis of all the more important genera, and under these are given the names of the species of economic value or special scientific interest. We select the following account of two interesting genera as examples taken from the eighth family of the sharks, Spinacedæ:—

"ACANTHIAS.—Each dorsal fin with a spine. Teeth equal in both jaws, rather small; their point is so much turned aside that the inner margin of the tooth forms the cutting edge. Spiracles rather wide, immediately behind the eye.

"The two species of 'Spiny Dog Fishes,' *A. vulgaris* and *A. Blainvillii*, have a very remarkable distribution, being found in the temperate seas of the Northern and Southern Hemispheres, but not in the intermediate tropical zone. They are of small size, but occur at times in incredible numbers, as many as 20,000 having been taken in one season on the Cornish coast. They do much injury to the fishermen by cutting their lines and carrying off their hooks.

"CENTROPHORUS.—Each dorsal fin with a spine, which however is sometimes so small as to be hidden below the skin; mouth wide; teeth of the lower jaw with the point more or less inclined backwards and outwards; upper teeth erect, triangular, or narrow, lanceolate with a single cusp; spiracles wide, behind the eye.

"Eight species are known from the southern parts of the European seas and one from the Moluccas; they do not appear to exceed a length of five feet. According to the observations of E. P. Wright some of the species at least live at a considerable depth, perhaps at a greater depth than any of the other known sharks. The Portuguese fishermen fish for them in 400 to 500 fathoms with a line of some 600 fathoms in length. The sharks caught were specimens of *Centrophorus cœlolepis*, from three to four feet long; the sharks as they were hauled into the boat fell down into it like so many dead pigs, there was not the smallest motion of their bodies. There can be no reasonable doubt that they were inhabitants of the same great depth as Hyalonema; and that in fact they were killed by being dragged to the surface from the pressure of water under which they lived. The dermal productions of some of the species have a very peculiar form, being leaf-shaped, pedunculate, or ribbed or fronded with an impression."

One other quotation must suffice; the Clupeidæ forms the twenty-second family of the Physostomii, which is the fourth order of the second sub-class; after enumerating several genera, among them Engraulis, to which the Anchovy belongs, the hint being given that "lucrative fisheries of Anchovies might be established in Tasmania, where the same species occurs, in Chili, China, Japan, California, at Buenos Ayres, each of which countries possesses Anchovies by no means inferior to the Mediterranean species;" the author proceeds to give the particulars of the genus Clapea. After the scientific description he adds:—

"This genus comprises more than sixty different species The majority are of greater or less utility to man, but a few tropical species (*C. thrissa*, *C. venenosa*, and others) acquire probably from their food highly poisonous properties so as to endanger the life of persons eating them. The most noteworthy species are:—

"1. *C. harengus* (the 'Herring'). It is readily recognised by having an ovate patch of very small teeth on the vomer. Gill cover smooth without radiating ridges. It inhabits in incredible numbers the German Ocean, the northern parts of the Atlantic, and the seas north of Asia. The herring of the Atlantic coasts of North America is identical with that of Europe. A second species has been supposed to exist on the British coast (*C. Leachii*), but it comprises only individuals of a smaller size, the produce of a late or early spawn. Also the so-called 'Whitebait' is not a distinct species, but consists chiefly of the fry or the young of herrings, and is obtained 'in perfection' at localities where these small fishes find an abundance of food, as in the estuary of the Thames.

"2. *C. mirabilis*. The herring of the North Pacific.

"3. *C. sprattus*. The 'sprat,' without vomerine teeth. Gill cover smooth, without radiating ridges. Abundant on the Atlantic coasts of Europe.

"4. *C. thrissa*. One of the most common West Indian fishes, distinguished by the last dorsal ray being prolonged into a filament. Hyrtl has discovered a small accessory branchial organ in this species.

"5. *C. alosa*. The 'shad' or 'Allice shad,' with very fine and long gill-rakers, from sixty to eighty on the horizontal part of the outer branchial arch, and with one or more black lateral blotches. Coasts of Europe, ascending rivers.

"6. *C. finta*. The 'shad' or 'Twaite shad,' with stout osseous gill-rakers from twenty-one to twenty-seven on the horizontal part of the outer branchial arch, and spotted like the preceding species. Coasts of Europe, ascending rivers and found in abundance in the Nile.

"7. *C. menhaden*. The 'mossbanker,' common on the Atlantic coasts of the United States. The economic value of this fish is surpassed in America only by that of the Gadoids, and is derived chiefly from its use as bait for other fishes and from the oil extracted from it, the annual yield of the latter exceeding that of the whale (from American fisheries). The refuse of the oil factories supplies a material of much value for artificial manures.

"8. *C. sapidissima*. The American shad, abundant and an important food-fish on the Atlantic coasts of North America. Spawns in fresh water.

"9. *C. mattowocca*. The 'Gaspereau' or 'Ale-wife,' common on the Atlantic coasts of North America, ascending into fresh water in early spring and spawning in ponds and lakes.

"10. *C. pilchardus*. The 'Pilchard' or the 'Sardine,' equally abundant in the British Channel, on the coast of Portugal, and in the Mediterranean, and readily recognised by radiating ridges on the operculum, descending towards the sub-operculum.

"11. *C. sagax*. Representing the Pilchard in the Pacific, and found in equally large shoals on the coasts of California, Chili, New Zealand, and Japan.

"12. *C. toli.* The subject of a very extensive fishery on the coast of Sumatra for the sake of its roes, which are salted and exported to China, the dried fish themselves being sent into the interior of the island. The fish is called 'Trubu' by the Malays, is about eighteen inches long, and it is said that between fourteen and fifteen millions are caught annually.

"13. *C. scombrina.* The 'oil sardine' of the eastern coast of the Indian Peninsula."[1]

These quotations will show the value and importance as well as the interest of the systematic and descriptive part of this volume, not a page of which is without some



Toxotes jaculator.

lines of most instructive reading, in many cases sufficiently so as to tempt one to turn "Ichthyologist" on the spot. We strongly recommend the reader to turn at once to the pages on the Salmonidæ. This portion too is illustrated with many excellent figures, two of which, through the courtesy of the publishers, we are permitted to reproduce —the first is of a fish belonging to the genus Toxotes. Two species of this genus are known from the East Indies, one of which (*T. jaculator*) is the more common, and it ranges to the north coast of Australia. It has received its name from its habit of squirting a drop of water at an insect which it perceives close to the surface in order to



Skull of *Plagyodus ferox.*

make it fall into it. The Malays, who call it "Ikan sumpit," keep it in a bowl in order to witness this singular habit, which it continues even in captivity.

The second woodcut represents the bones of the head of one of the largest and most formidable of the deep-sea fishes. Of the genus Plagyodus but one species is known (*P. ferox*). It has been found off Madeira and in the sea off Tasmania. Other species have been noticed from Cuba and from the North Pacific, but it is doubtful if they differ specifically from *P. ferox*. The fish grows to a length of six feet, and from the stomach of one specimen have been taken several eight-armed cuttle-fish, Crustacea, Ascidians, a young brama, twelve young boar fishes, a horse-mackerel, and one young of its own species. The stomach is coëcal, the commencement of the intestine has extremely thick walls, its inner surface being cellular, like the lung of a reptile, it has no pyloric appendage. All the bones are extremely thin, light, and flexible, containing very little earthy matter. Very singular is the development of a system of abdominal ribs symmetrically arranged on both sides and extending the whole length of the abdomen. Perfect specimens are rarely obtained on account of the want of coherence of the muscular and osseous parts, caused by the diminution of pressure when the fish reaches the surface of the water. The exact depth at which *Plagyodus ferox* lives is not known; probably it never rises above a depth of 300 fathoms; but woe betide any rash intruder that dares to descend into the realms of its abyss.

The volume closes with some directions for collecting and preserving fishes—when practicable fishes when dead should be set to swim in spirit. But we must not quote any more, so leave the curious reader to find out the details of how, having caught his fish, he can cook it so as to make it of value for some national museum.

[1] In this quotation the fin formulæ and references to works on the Herring, &c., are omitted.

SULPHURIC ACID AND ALKALI

A Theoretical and Practical Treatise on the Manufacture of Sulphuric Acid and Alkali, with the Collateral Branches. By George Lunge, Ph.D., F.R.S.E., Professor of Technical Chemistry at the Federal Polytechnic School, Zurich (formerly manager of the Tyne Alkali Works, South Shields). Vol. III. (J. Van Voorst, 1880.)

THE publication of the third and concluding volume of Prof. Lunge's excellent work follows wonderfully soon on that of the first and second. This volume, which fully equals the other two in accuracy of description and clearness of style, is devoted to the subsidiary processes lying alongside of the main channel of Leblanc's great discovery. We first find a chapter on the ammoniacal soda process now rising, through Solvay's exertions, into well-merited and formidable competition with its older rival. The ash made by this theoretically beautifully simple and practically most original process is very pure, containing from 98 to 99 per cent. of Na_2CO_3, and free of course from the impurities common to Leblanc's ash of caustic soda and sulphide of sodium.

But this Solvay's ash is less dense than that made by the old plan, and both German and English manufacturers are now making a Leblanc ash of 98 per cent. free from sulphur and of a dense quality. The struggle, says Lunge, is not now one of purity, but merely of price, and so far Leblanc soda is holding its own. Here however the beneficial action of competition is seen: if Messrs. Brunner, Mond, and Co., of Northwich and Sandbach, were not turning out from 35 to 40 tons of Solvay ash *per diem*, I cannot help thinking that the Leblanc soda-makers might have felt inclined to rest content with their previous performances. There is of course no chance of this new process turning out the old-fashioned plan until the chlorine of the common salt can by this new method

be made available as a marketable article. At present it runs away as calcium chloride; but if Weldon's process for regenerating the chlorine were to prove as successful as his well-known plan (of world-wide application) for obtaining it from the ordinary chlorine-still liquor has proved (and this so far has not come to pass), it is pretty clear that all the old alkali works would have to be closed. Next come the chapters on Bleaching Powder and Chlorate of Potash. Here we find thirty-four pages of a practical treatise devoted to the theoretical consideration of the composition of bleaching powder, and even graphical formulæ may be detected on some of these pages, to say nothing of chemical equations of some complexity, involving the discussion of one of the most intricate of chemical problems. This is a pretty dish to set before our "typical practical man," who only knows the substance he makes under the names of "B.P." or "Chemic," and would be puzzled to say of what it consisted. It is however a species of nourishment which it will do him good inwardly to digest, for if he turns away from it in disgust and dismay, so much the worse for him and his manufacture. "The rule of thumb," as Mr. Mundella truly said at Leeds the other day, "is now over; we stand at its grave." Our manufacturers must all be thoroughly trained in the scientific principles which underlie their trades. Noble and great things have been done by Englishmen in the perfection and development of chemical industry, and still greater things remain for them to do; but whilst taking only proper credit for what England has done and is doing, let us not forget that the general scientific education of our manufacturers and managers is far below that of their Continental competitors. It is no doubt quite true that no German alkali work could exist were it not for their import duty on English soda; for even with all their care and scientific knowledge, the Germans are unable to compete on equal terms with us, thanks rather to the circumstances of our environment than to any special merits of our own.

But this artificial and economically unsound condition of Continental manufacture ought rather to urge us so to complete our system that we not only shall have the advantages which geographical position and geological good fortune places at our disposal, but also that thorough scientific training and the knowledge of what is being done elsewhere, without which all natural advantages become comparatively valueless. In this way and in this way only can we, as it seems to me, fight against the incubus of protective tariffs. On this necessity for our typical "practical man" to re-consider his position and to arm himself for the technical war with every appliance which science places at his disposal, Dr. Lunge speaks so forcibly and so well in the preface to his third volume that I take the liberty of giving his remarks *in extenso*.

I may however express my own doubts whether the British alkali-maker has, as Dr. Lunge maintains, in reality been distanced by any foreign manufacturer of alkali or sulphuric acid, except so far as regards the import of British goods into countries where inland production is artificially stimulated by protection. As regards other chemical industries, especially those such as the manufacture of colours, in which great delicacy and care in manipulation and an intimate knowledge of the highest developments of organic chemistry are essential, one must in sorrow confess that Dr. Lunge is perfectly right when he says that the English trade is rapidly passing into the hands of French and German houses.

"Other books aim at nothing but giving an accurate description of the present style of making sulphuric acid and alkali in England; and they leave the chemistry of the subject almost totally aside. My treatise differs from this in several respects. First it gives a detailed chemical description of the raw materials, intermediate and final products, of the modes of testing, and so forth, supplemented by numerous tables of solubilities, densities, &c.; and it also enters very fully into the theory of all the processes concerned, accurately citing all papers on the subject, so that the reader can go to these for further elucidation. I am quite aware that a treatment of this kind will appear lengthy and superfluous to some readers who look into this book merely for 'practical' hints. In this respect they will not, I trust, be disappointed either, but I make bold to say that they would do very well not to despise the scientific part, the purely chemical detail, of this work.

"After all, our subject belongs to the domain of *chemistry*, and the times are far behind us when, in the manufacture of chemical products, the practical man with his rule of thumb could look down upon the chemist in the laboratory—who in the former's idea was at best only good for testing the materials, but whose interference with the works would invariably cause mischief. That this was true to some extent, and still is so, where the chemist attempts to transfer his ideas into practice in a crude state without sufficient practical experience, nobody can possibly deny. But does the 'practical man' on his part make no mistakes?

"Have not untold sums been wasted in futile 'inventions' and 'improvements' merely because 'practical' inventors lacked a scientific knowledge of their subject? Probably very much larger sums have been lost in this way than by the deficiency in practical experience of 'theoretical' inventors, for the simple reason that the latter class of inventors generally have not so much means at command as the former. It is a mere truism that theory and practice should always go hand in hand; but it must nevertheless be inculcated over and over again, as would appear from the fact that several costly books on perhaps the most important branch of chemical industry have just been published with next to no chemistry in them. And to what consequences does this neglect of a scientific treatment of practical subjects lead? The author may be pardoned for illustrating this from his personal experience. A little more than sixteen years ago he left his native country for Great Britain, and he might justly hope to learn a great deal and find much more scope for himself in that country which he is proud to have made his second home. More particularly the manufacture of sulphuric acid, soda-ash, and bleaching-powder was at that time quite insignificant in Germany, and not very considerable in France as compared with Great Britain, nor could the technical appliances, the yields, or even the purity of the products in the two former countries vie with those of the latter. How different matters are now is a matter of notoriety. The manufacture of chemicals has made enormous strides forward, both in quantity and quality, in France, and even more so in Germany. Many of the chemicals of these countries outstrip those of English works in purity; and their plant and their processes are frequently superior to those used in the majority of English works. Everybody knows how this has come about. The foreign chemists and manufacturers have looked all round, not merely in their own countries, but wherever they could find improved methods and apparatus, and upon the practical knowledge thus gained

to bear the scientific training they had universities and polytechnic schools. ready, in many fields formerly remu- manufacturers, distanced the latter, ough these be by their long occupation y permanent natural advantages, such l and of freight, superior command of is is likely to go on to an increasing ish chemical manufacturers decline to ific study of their respective branches. excusable, as England for a time of old has of scientific chemistry, and can hold whole world in that respect."

I will only add that one of the best lvancement in the study of science so ermanent well-being of our manufa- nd well-thumbed copies of Dr. Lunge's nly on the so-called-owners' shelves, but ry manager, and on the table of every nufacturing districts.

H. E. ROSCOE.

NEW BOOKS SHELF

Supplément. Par D. Kuhlmann. (Zurich: Orell Fürster et Cie., 1880.)

supplement to the "Manuel du Voy- e author, noticed in these pages of the ware. The present volume may be tion of constants in all departments be of service to the straight traveller, dents, of many kinds. It contains a n geography, mathematics, physics, ogy, biology, and anthropology. It ted a list of works to be consulted on ects, numerous plates and maps. All of authors whose works are cited. ults to us well put together, the infor- ains to us well put together, the infor- t and, so far as we have tested, trust- t and, so far as we have tested, trust- lists of works are not always so com- lists of works are not always so com- t be; this can be easily amended in t be; this can be easily amended in s. To all interested in geography in s. To all interested in geography in s work must prove of great service. s work must prove of great service.

LETTERS TO THE EDITOR

[The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts intended for this or any other part of NATURE. No notice is taken of anonymous communications.]

Geological Climates

Temperature of the Breath

At the request of many friends, Mr. Gardiner's view is disagreeable to me; and I did not think it advisable to encumber the discussion of my own theory with more references of this kind than were absolutely necessary. I may add, that the extension of the Miocene Arctic flora to Grinnell Land since Mr. Gardiner's article appeared, renders his views still more untenable. Of course I here refer to my chapter on "Mid Arctic Climate" in "Island Life." In my letter to NATURE I entered myself briefly to the point raised by Prof. Haughton, which I did not consider had been adequately met by Mr. Gardiner's hypothesis.

ALFRED R. WALLACE.

To your correspondent, Mr. Ingram of Belvoir Castle, quite certain that he has not confused the *Anisoptera Cunninghamii* of Queensland with *Cunninghamia lanceolata* of China? The name is misleading.

H. KING.

Chilham, Petersfield.

At one time or other during the past few months letters on the temperature of the breath have appeared in NATURE, in which experiments have been referred to as to the cause of the high temperature produced by breathing on the fingers and pad of silk or other materials.

Can it be considered as proved that the high temperature does not exist sufficiently to account for the feeling of heat and moisture on the application to the hand of the breath? I believe it does not, by a comparison by Heidenhain; but it is well to see how far this is correct. In a letter to Nature of October 7 in the present year, I referred to the breath a temperature of about 98°, as deduced by the application of a calorimeter, and that by this—as well as by the rejection of all observations by means of the fingers—the true cause of the breath [illegible]

As to the [illegible] referred to NATURE of October 7 in the present year, I proved to be [illegible] and that [illegible] the [illegible] temperature of the breath [illegible] the high temperature produced in [illegible] by the breath [illegible] was not [illegible] by others, [illegible] to be [illegible] the same and to consist of the [illegible]

The [illegible] Physiological [illegible] Well [illegible] [illegible] [illegible]

covered thermometer rose rapidly till it nearly touched 94°, while the naked one remained stationary.

The conclusions to which these experiments point are too obvious to require demonstration. C. J. McNALLY

Madras, December 9, 1880

Selenium

THE use of selenium in the photophone has suggested to me the possibility of using it in two ways, which I shall now describe, thinking you may perhaps consider them of sufficient general interest to publish in NATURE.

Firstly, it seems probable that selenium might be used to obtain the automatic registration in a chronograph of such phenomena as star-transits. It possesses the property of being drawn into fine wire at a low temperature, but whether it can be drawn fine enough to represent mere wires in a telescope I do not know.

The arrangement would be as shown in the diagram, where A A, B B are parallel metal plates crossing the field of the telescope, and insulated from each other except by the selenium wires c c c c in one direction, and by a wire circuit passing through a battery, and a relay, R, in the other. The relay should be so adjusted that the increased force of the current passing through the circuit caused by the light of a star falling on each wire c c in succession, shall cause its armature to vibrate and pass on a signal to the chronograph.

The delicacy of the adjustment required for this purpose might be a greater difficulty than I am aware of; but it should be borne in mind that the length of selenium in the circuit would be very small, as the plates A A, B B need not be farther apart than sufficient to insure the star's falling between them without error to the accuracy of setting, say one-twentieth to one-tenth of an inch in a telescope of no considerable size. If necessary, it would be simple enough to give each wire c c its own distinct circuit. Should the brittleness of the wires prove a difficulty, they may be supported between the plates A A, B B in any convenient way which does not interfere with the insulation of these plates.

The second purpose would perhaps be of more practical use than the above, viz. to secure an automatic daily time-signal. Let a thin plate of selenium be placed between, and in firm contact with, two parallel plates of metal, which are connected with each other by a wire passing through a battery and a relay, as above, so that the selenium alone interrupts the circuit. Then if this plate be placed with its length in the meridian, and a lens adjusted above it, so as to throw the image of a star, or the sun, as it crosses the meridian exactly on the selenium, a signal will be returned from the relay as before, which in this case may be the ordinary tick of any other convenient sound.

An ordinary lens would require certain changes of adjustment if used for the sun, moon, or any body of sensible declination; but if the lens were the central zone cut out of a sphere by two small circles parallel to each other and equidistant from the centre, placed with its flat sides parallel to the meridian, while the selenium was placed in a curve concentric with it, the low, at the proper distance from its surface, and of such length—of course being accurately in the meridian—that the heavenly body of whatever declination—between certain limits—would throw its image on the selenium and affect the signal, if of sufficient brightness. The arrangement of a warning signal would be easy.

If this method proved practicable the objection would not apply to it having to apply a correction to obtain mean time, as it would probably prevent its being used for public purposes, as dropping time-balls or firing time-guns. It seems to me however that it might nevertheless prove very useful to many private individuals who require an accurate knowledge of time.

Poona, December 3, 1880 W. M.

Experiments with Vacuum Tubes

AT a meeting of the Philosophical Society of Glasgow on December 28, 1880, I gave a very brief preliminary account of some experiments that I have been making, along with Sir William Thomson, with vacuum tubes. We have called up both old and various glow-tubes with very high resistance, but without any electrodes, and have shown how remarkable luminous effects can be produced in them by means of electrostatic induction. Using an ordinary frictional electric machine, and keeping one end of the vacuum tube to the same conductor, while the other end of the tube is held in the hand, the tube becomes charged to a suitable [illegible] in the following way:—one end of the tube, that in the prime conductor,—outside negative, inside negative (the other end—also positive, outside negative). This can be shown by the gold-leaf electroscope. The charge seems to be very high after the glass is very frequently perforated. Indeed it is difficult to work with the electricity unless it is sufficiently powerful to perforate the glass. While this double Leyden jar is thus being charged by rotations, part by part, the charge from the outside of the tube, beautiful luminous effects are observed very different from those seen in the ordinary vacuum tubes. We have also obtained curious effects by heating the middle region of the tube so highly that it becomes a conductor. J. J. THOMSON

Physical Laboratory, University, Glasgow, December 29

Modern Use of Ancient Stone Implements

PERHAPS the following statement will interest some of your readers:—In an old volume, "Thomae Bartolini Acta Hafniensia," Ann. 1674, 1675, 1676, I find a paragraph signed by Olaus Borrichius, which clearly indicates that in the seventeenth century ancient stone implements, and probably many of them, were converted into flints for the use of the contemporaneous musquetry. The text runs thus:—"Silices Anbeldiai gubrice. In ala linea [Ambeli in the Kattegat] peraguntur in sedano, minuty illa spe lenses analogias amphi-ama infantis [illegible] quod ab ipso nomen habent. Inter classum scru infinitis reperiri olim negotiabar, varios, in schuli hinc separatos, ad sex transvers in digitos in longitudinem prof lapis digitum unum, minus. Frequentia sic et majora mis-ad aemulum, et lacvibus plerumque in illam actem ex in lenae curare pulmani cubris saxeis filiorum Israel ci eminent Imperatori. Nunc terreo hic negotio in alma vo Caesar mulleo enim in Imperio conficiendis divat selopes robustis opem prompte ministrare et fomitis incendiari fulmineis bellatorum tubis acquiantur." D. Bro

Rome, December 26, 1880

Pile Dwellings

In the connection between pile dwellings in the Swiss l the Swiss chalet, and the Malayan modern pile dwelli environment, a decided advance has been or will be ma geological archæology.

Pile dwellings are a very distinct characteristic of all the race—both ancient and modern, except those on the Kasia Hill ra and so far as I can see is a conspicuous distinction betwe Aryan and non-Aryan races here.

The persistence with which this custom is retained a tribes who have migrated, to new sites, where the need obvious, seems to offer a safe means of tracing to some c racial descent or relationship.

The "Meris" of Assam offer a case where part of the tr still in the hills, while the rest are more or less scattered the Brahmaputra in the level land of Assam, and build h these. The Ahoms, a Shan race who invaded and settl Assam in A.D. 1228, built pile dwellings, and the "Deodhai who are lineally descended from them, do so now. The I

, Abors, Mishmis, Singphus, and Nagas (all) dlings, as do the Kamtis.
uliarities are noteworthy, *i.e.* that the custom is confined to *hut rices*, and not seen in (hain rices;) that the invariable explanation offered to inquiry is that on the hill tops and spurs, where *alone* the villages are built, there is very little

that this form of house is a necessity among pigs and goats, which to any casual visitor is at

ible that this question may afford unexpected mined, I inclose sketch of a Naga "Morang,"

S. E. PEAL
A-sam

lips.—The Cheshire Subsidences

ndance of Mr. Thos. Higgin, F.L.S., and your h. Ward, I have just been examining the subs- been lately taking place in the neighbourhood To understand how they occur, it is necessary ere are two beds of rock salt in the Trassic er bed, 25 yards thick, is from 40 to 60 yards ut 10 yards of hard marl. The greater bulk of d in the form of brine pumped up from the lower bed is to a smaller extent worked as a these operations two classes of subsidence neral and gradual, due to the removal of salt salt of the upper bed by percolation of water which the surface of the ground into the er, sudden falling in of the ground into the rater like lake. It is to these I wish to call s fortunate enough to see one below it had all do, partially filled with water. I fought out 70 feet deep, 150 feet diameter at the top at the foot on, where a little water was lying. accurate, for is how such an inverted cone of Leather-clay and drift could apparently through six small a hole. The explanation is by percolation of water the roof of the mine give way and fall into the mine, gradually the surface, where it first appears in the form he size of a well. The cavity will no doubt orm, the base being at the roof of the mine. ormed, the surface ground begins to slip to ually enlarging the orifice, the material sli- mine below. This continues until the natural le sides of the crater attain the angle of le thing will occur in a night. The subsidence very remarkable appearance to see the "pene- cular or elliptical form and funnel under like ent such subsidences could not happen except ditions, such as are provided by salt-mining. ese Keuper marls.

J. MACLAREN ROSE
Lumbellsands, Liverpool, December 22, 1880

Animal Reasoning

I LEND an account of a singular act of animal intelligence which may not be uninteresting to the readers of NATURE. A lady, a friend of mine, was also the manager of a hospital for poor women and children which was maintained by subscription. One of the inmates was a little girl who was there not as a patient, but temporarily till a home could be found for her. She had learned to feel herself, and at most times was very unwilling her dinner was placed on her knee or she sat on a comfortable chair for her special convenience in her bed. One day while she was eating the patient of the establishment placed herself [illegible] on the girl and bolted long and gave her, so exceedingly that the matron, seeing the animal meditated some mischief to the girl, took her out of the room. Again the next day, at the same hour, the rat entered the room, but this time walked openly to the girl's side, seized herself on her hind legs, and wickedly, steadily reached at her tray to the plate, [illegible] and [illegible] flood her, and, silently as [illegible] of [illegible] enjoyed her [illegible] meal. The girl never noticed [illegible] but [illegible] [illegible] [illegible]

THE INDO-CHINESE AND OCEANIC RACES—TYPES AND AFFINITIES[1]

II.

A BELIEF in sorcery is very general, especially amongst the Melanesians, and some of the practices associated with it often resemble those prevalent amongst the Australians and African Negroes, and even in mediæval times in Europe. In Tanna, New Hebrides group, Dr. G. Turner tells us that the real gods "may be said to be the disease-makers. It is surprising how these men are dreaded, and how firm the belief is that they have in their hands the power of life and death. There are rain-makers and thunder-makers, and fly- and mosquito-makers, and a host of other 'sacred men'; but the disease-makers are the most dreaded. It is believed that these men can create disease and death by burning what is called *nahak*. Nahak means rubbish, but principally refuse of food. Everything of the kind they burn or throw into the sea lest the disease-makers should get hold of it. These fellows are always about, and consider it their special business to pick up and burn, with certain formalities, anything in the nahak line that comes in their way. If a disease-maker sees the skin of a banana, for instance, he picks it up, wraps it in a leaf, and wears it all day hanging round his neck. The people aware as they see him go along, and say to each other, 'He has got something; he will do for somebody by and by at night.' In the evening he scrapes the bark off a tree, moxes it with the banana skin, rolls up tightly in a leaf in the form of a cigar, and then puts the one end close enough to the fire to cause it to singe, and smoulder and burn away gradually. Presently he hears a shell blowing. 'There,' he says to his friends, 'there is the man whose rubbish I am now burning; he is ill. Let us stop burning, and see what they bring in the morning.'

"When a person is taken ill he believes it is occasioned by some one burning his rubbish. Instead of thinking about medicine he calls some one to blow a shell, who is, when perforated and blown, can be heard two or three miles off. The meaning of this is to implore the person who is supposed to be burning the sick man's rubbish and causing all the pain to stop burning; and it is a promise as well that a present will be sent in the morning. The greater the pain, the more they blow the shell, and when the pain abates they cease, supposing that the disease-maker has been induced enough to stop burning. Then the friends of the sick man arrange about a present to be taken in the morning. Pigs, mats, knives, hatchets, beads, whales' teeth, &c., are the sort of thing taken. Some of these diseases or any state are always ready to receive the presents and themselves the parts of it they will do their best to prevent the rubbish from being again burnt. If the poor man less another attack it might be thinks nobody is even burning. The shell is again blown, and swiftly go off, and if both the friends lay it all down to the disease-makers, and having got a-head with the presents taken and so buying him off, punish to the end. The disease-maker, if he could foresee the person dies." (J. Sunderland, "Four Years in Polynesia") Substitute for the nahak a piece of fetish of the ethnographer, and you have in these accounts a very fair parallel to the belief in the power of witchcraft to produce disease and death, as held in all times in Europe.

"Devoted heretic, mine incantations shall fetch
To torment thee in fiercest anguish."
(Faust, Part I.)

But this merely shows how little reliance can be placed on similarity of manners and customs in tracing the affinities of races. The mind of man having sprung, as seems most probable, from one original centre, it everywhere very much the same in the infantile or undeveloped stage. Hence, like practices under like conditions may very well arise independently in diverse places without implying any ethnical relationship or even any necessary social contact. The most extravagant theorist would scarcely venture to suggest any direct relationship of any sort between the Papuans, for instance, and the Basques; yet among the young girls of both races the extraordinary taste for making pets of little pigs prevails. At least the practice is spoken of by recent explorers as common in New Guinea, while Mdme. d'Aulnoy ("Relation du Voyage d'Espagne," Paris, 1691) was greatly surprised to find the young Basque ladies of Bayonne indulging in the same habit when she visited the place in 1679. "Some of those who came to see me had a little sucking-pig tucked under their arms, just as we carry our little lap-dogs. Several had ribbons of different colours tied round their necks as collars. But when the ladies joined in the dance they were obliged to let the horrid beasts loose in the room, where they made more noise than so many imps." The "corycade" is another remarkable custom attributed both to the Basques and to the Bura Islanders, East Archipelago, in common with many other peoples ancient and modern in the Old and New World. But M. Julien Vinson (*Revue Linguistique Française*, January 10, 1877) has shown that, at least so far as regards the Basques, there is little or no ground for the statement. We all know what astonishing conclusions as to ethnical affinities certain ethnologists have drawn from the assumed common prevalence of this eccentric fashion amongst the most widely-dispersed nations. Yet even if it did exist among them such conclusions would be utterly inadmissible.

It may be mentioned that the missionaries have been for some years at work amongst the Malay people and the kindred of Dorey, into whose language they have translated several treatises and portions of Scripture. Here is a specimen from Genesis i. 1 ("In the beginning," &c.): "Dop neia kabut mon-eren allah ibekadi nanggi ma dawa. Dinya ikambo ma dro beri, ma imprep (or bo) wor ro manseren allah ikedi arioh ro bo wäre." The Malay, or rather Arabic words, *allah*, God, *ibekadi* oath, *dro* for *roh*, spirit, are of course borrowed by the translators; but the structure of the language is entirely different, being highly agglutinating and employing both pre- and post-positives. Like other Papuan dialects, in other respects the Papuan and Melanesian tongues differ so profoundly from each other that it is impossible to group them in one linguistic family. As a rule they possess absolutely nothing in common beyond a certain uniformity of structure and such verbal resemblance as is due to Malay and Sawaiori influences. These influences are very widely spread, as shown especially in the numerals which the dark races have almost everywhere borrowed from their brown and olive neighbours. But they do not retain the old agglut-ystem at one time common to Indo-China and Malaysia, but in the Oceanic area have generally replaced by the decimal. Thus in the Duke of York Islands, Dalrymple, New Britain and New Ireland the five first cardinals only are taken from the Sawaiori or Eastern Polynesians, the numbers beyond five being expressed by addition, as in Cambojan and several Malayan and Western Papuan dialects. Hence for instance, 6 = *sigi-tahi*, 7 = *sigi-rua*, 10 = *lima-lima*, we have *lima-tahi* = 5 + 1, *lima-rua* = 5 + 2, *lima-lima* = 5 + 5, where *lima* = 5 from the Samoan or Eastern Polynesian *lima* = 5. In an adjacent province the numerous Sawaiori words have found their way especially into the Eastern Papuan dialects are always compelled to conform to the agglutinating principle of Papuan grammar. Thus the Fijian Duke of York *tuvei* = brother, apparently answering to the Samoan *tuaa* = boy, assume the pronominal prefixes *au* = my, &c., peculiar to those groups, the Fijian *tuvei* and Duke of York *tuvaqu* being equivalent to Samoan *toku tuaa* = my brother or my boy. Here

[1] Continued from p. 203.

ow entirely the structure of the Papuan differs
the Sawaiori tongues, and how constant is
languages of different systems may borrow
of words from each other, while each in its
its own grammatical genius. Hence, where
ixed Papuan, Malayan, and Sawaiori tongue
ns the expression is always to be understood
o the vocabularies only, never to the gram-
ure of those languages. In philology there
enomenon than mixed grammatical systems
ps it might be premature to deny the possi-
y of such mixture.

SPECIAL FACTS: *Australians, Tasmanians*.—
cupied by this division of the dark races is
e Australian continent and neighbouring
smania. Here we enter an entirely new
d, for, although the extinct Tasmanians
doubtful affinities to the Melanesians, the
and quite apart. They are usually tall,
ck, straight-haired, dolichocephalous, and
But this generalisation can pretend to no
races, and in any case it is so remotely doubt-
ey can be regarded as all belonging to one
Papuans, who has devoted great atten-
subject, recognises at least two distinct
s, the history of which reaches into the
above described, and who are essentially
y be said to consist in the combination of
negroid features with straight hair. The
race, found mainly on the Kowrey coast
ing Georges Sound, in the middle of the
s described as of short stature, with
u-, with woolly or at least frizzly hair; the
ner race, occupying the interior, and
north-eastern highlands, are much taller,
ir, with straight or wavy hair, and slight

standing these discrepancies, it would
at "throughout Australia there is considerable
ormity to one pattern in its customs, imple-
ental characters. A very accurate
torial would be to represent Australia
ants of hair fixed permanently in the
Sound. It would be surely absurd to
s." This common racial character is
ps on the least instructive customs,
nical among a people to whom even
ght far and wide by Europeans, and
others in Polynesia. Even in appar-
of the arguments adduced in support
Indian relationship is to be found
lance of the theory in the
e Australians women to
with [illegible]. The Aborigines
some thought into the practice
safety to deny the affinity in this respect
concerning with that of the Andamanese
the first under most circumstances. The
to believe to the women
port of the Australian tribes
an crooked back. Similarly
an resemblance between the Australian
esistible of danger [illegible]
an dress and a mode of wearing
hour the South American girl
rmer [illegible]
ers, we [illegible]
[illegible]
racter of this sort,
a sound mind in a sound body,
a language, which, with considerable
able uniformity of structure and with
nitient, have often been noted with
y-am- and other [illegible]

results, except where the unscientific method has been adopted. Thus *murry*, great, is compared with the Keltic *mor*, or the English *moor*; *cobbon*, head, with the Spanish *cabeza*, quite a modern formation; *gatter*, rock, with the first syllable of *djebel*, of which the true Arabic form is *jebl*; *bo kunna*, shield, with the Anglo-Saxon *helian* or *helan*, to cover, or with the English *helmet*, which the ingenious etymologists are careful to tell us is "a little shield for the head"; *cunna*, good, with the French *bon*; *kan*, hand, with the Latin *canis*; *kirdi*, wizard, with the Greek *κηρύσσω*, to utter, with the Latin *vates*; *kattin*, eating, with the English *take in* (why not *suck in*?); *mooto*, blooming, with *mortis*, beyond which it would be difficult to carry etymological eccentricity. Many of these languages are highly agglutinating, some even verging on the inflectional; but scarcely any have distinct names for the numerals beyond 1 and 2, after which 3 = 2 + 1, 4 = 2 + 2, and so on.

This common feature alone should be sufficient to reject any semitic, Aryan, or Dravidian affinities, for if the Australians came of any of those stocks, it is not to be believed that all the tribes would have agreed to forget their inherited arithmetical system, and stop short precisely at the most eminently convenient number 2. At the same time it is conceivable that at an extremely remote age, while yet the old broad part of the Asiatic mainland, tribes resembling the Koromkus, Mussulas, Toda, and other aboriginal people of the Deccan, may have spread southwards, and have mingled with others of a Papuan type from Melanesia. The result of such an intermingling might be a race not far from the present average Australian in form, but exhibiting in the present day more or less dolichocephalous and with wavy or glossy hair intermediate between the frizzly and straight. But these migrations cannot have taken place since the embedding of the land, because none of the races in question are negroes, although some of the Negro tribes have records bearing the art from the Malays. As to the other hand the resemblance of the people to which such arrangements must be referred is no objection, for Australia has been peopled for many ages, as is evident from the axe-flakes hitherto found on the coasts, and some of these have already been used as arrows by the white settlers.

The contrast in the intellect [illegible] formed by Mr Wallace and other ethnologists seems at first sight somewhat extreme and one-sided even over the least favourable specimens of the Australian race, as described by such competent observers as Mr Oldfield, who says that the race "is not without some peculiarly redeeming traits, and has been more calumniated than any other race of men." Many testimonies are given of their mental capacity, especially for which was their evident pleasure in acquiring the English language, and exercising themselves [illegible] capable of receiving and [illegible] as the children of [illegible] (see p. 256). [illegible] Bramble, it was [illegible] more than any other [illegible]

[illegible] Mr Taplin [illegible] Lake Alexandrina [illegible] Mr Taplin [illegible] Mr Taplin [illegible] Mr Taplin

above the brow. The men could make twine, the woman a rush basket (*op. cit.*, p. 191).

Cannibalism has also been prevalent, even amongst some tribes a very revolting form.

Unfortunately, but few of the Aborigines are left to benefit by the existing kind and humane system of treatment lately introduced by the local administrations. There are probably not 20,000 left in all Australia: even those of Victoria, who are best cared for, are dying out except in a few favoured localities, and "Lalla Rookh," the last of the pure blood Tasmanian women, died in June, 1876. The Tasmanians differed in many important respects from the Australians. They were of darker colour and somewhat less dolichocephalous, with decidedly frizzly hair, that latter feature bringing them into close connection with the Melanesians. In point of culture they stood nearer to the lowest level, possessing no fixed abodes, wearing no clothes, never cultivating the land, unacquainted with the rudest art, possessing neither domestic animals, pottery, nor the boomerang or bows and arrows of the Australians. They were divided into a great number of tribes, speaking as many as nine quite distinct languages, but so little developed that the sense was largely eked out with the aid of gesture and signs. Yet their cranial capacity seems to have been slightly greater than that of their neighbours, index 80 as compared with 78½ while they were nearly as orthognathous as Europeans. These contradictions constitute the Tasmanian a type *sui generis*, allied partly to the Australian, partly to the Melanesian and Polynesian, with some special features which may perhaps be due to their long isolation from other races.

B. CAUCASIAN TYPE.

IV. CONTINENTAL BRANCH.—*Khmer or Cambodian Group.*

In Further India, with one exception, all the settled peoples, forming recognised nationalities, that is, the Burmese, Thai or Siamese, and Annamese, are physically of Mongolian stock, and all speak languages of the monosyllabic or isolating class. The same is largely true of the Mishmis, Khasias, Kukis, Nagas, Khyengs, Karens, and other wild tribes in the west and north west, as well as of the Shans, Muosos, and many Miao-tsi tribes in the north. Hence the universal assumption that, excluding Malacca, all the inhabitants of the peninsula constitute one ethnical and linguistic group allied to the Chinese in the north and to the Tibeto-Himalayan races of the north-west, and with them forming collectively the great South-Eastern division of the Mongolian family. This comfortable theory was first shaken by the revelations of the Mekong Exploration Commission of 1866-8 up the Me-Khong River, since when the writings of Mr. Thorel, Francis Garnier, F. Aymonier, A. R. Colquhoun, Dr. Harmand, and other French naturalists have made it abundantly evident that there is in this region an important non-Mongolian element, which can henceforth be taken into account. Yet a deep-rooted scientific truth makes its way against long-established errors, that the fact has scarcely yet been to general or any comprehensive treatise on ethnology or its students. In a paper prepared for the meeting of the French Association at Montpellier in 1879, and since published in separate form,[1] I endeavoured to determine the true nature of this non-Mongolian element, and to point out its essential importance in connection with the classification of all the Indo-Chinese and Oceanic races. It was there shown that the Khmer or Cambodgian nation, the exception above referred to, together with a large number of kindred peoples inhabiting the Lower Mekhong basin and the region between that river and the Coast range running from Cape St. James northwards to the Chinese frontier, form a distinct racial and linguistic group, of the physical type as the Mediterranean or Caucasian of the west, and closely akin to the brown Oceanic of Malaysia and the Pacific.

The arguments brought forward in support of this need not here be formally repeated, and it will be cient to vindicate the use of the term "Caucasian thus extended to the remotest Polynesian island has been objected that there are no Aryan lang in the far east, and that the Eastern Polynesians brown race, consequently that the word Caucasian here apply. But those who so argue seem scar realise the nature of the problem. Caucasian is linguistic, but an ethnical expression; hence al the Aryan, Basque, Semitic, and many languages Caucasus have no conceivable relationship wit other, we do not hesitate to regard those who spea languages as of one stock because their physical substantially the same. This type we conventiona Caucasian or Mediterranean, which terms must to apply wherever the physical features implied are found, irrespective altogether of the languag tion. Why speech and type should not corres another problem, which admits of an obvious but which cannot here detain us.

The objection based on colour, though more point, is scarcely more forcible. The brown Poly are not supposed to spring directly from the fa peans, but to have gradually spread from Ind through Malaysia to their present homes; and it presently seen that there are peoples in Indo-Chin enough to suit the Polynesian taste, and fair en clum-kinship with the western nations. Besi question of colour must anthropologically be rega altogether of secondary importance. There are Caucasians in Abyssinia, deep brown Caucasians Ganges Valley, dusky or swarthy Hamites and S also Caucasians, in North Africa and Arabia; and w there not be brown Caucasians in Polynesia? Su evolutionist, who does not hesitate to accept the d ment of the *genus homo* from some anthropoid ap not scruple about the relationship of the human because of such a secondary matter as colour. Sc furth tells us that albinism is common among negroes of the Nile basin, and there is at the moment a clear case of melanosis in London. It be regarded as morbid symptoms, they are often dutory, and it has not yet been shown that they m be cases of atavism, such as the reappearance of th on the pigeon's wing, however far removed fro original blue-rock type. *Nimium ne crede colori*, said Linnæus, speaking of plants, and the rem equally applicable to the animal kingdom. Obs that the black pigmon does not make its appearan the Negroes of Loango, West Coast of Africa, unti birth, the Berlin anthropologist Falkenstein su that it may be due to the action of the solar rays. what becomes of colour as a fundamental charact at all?

Besides the civilised Khmers, forming the bulk present kingdom of Cambodia and neighbouring Si provinces of Ongkar and Battambang, the chief C sian peoples of Indo-China are the Chams, Cha Bulovins, Stodings, Sui, Nong, Cedangs, Khoedeh, hars, Samrè, Lemets, and Kiays, the last of whom looked on by the Cambodians as the primitive K stock; hence are called by them *Khmer dom*, or " nal Khmers." In the paper above referred to the ph characteristics of these tribes are thus summed up m from Thorel:—"A fine, vigorous race, with symme and well-set frames; stature rather above the middle straight profile, oval face, dolichocephalous head, forehead, retreating very slightly, black hair, often in ing to brown, straight or wavy and elliptical in sec

[1] "On the Relations of the Indo-Chinese and Indo-Oceanic Races and Languages." (London, 1879.)

-s well furnished and always frizzled, eyes perfectly straight and horizontal, arly prominent, but nearly always r flattened at the root, cheek-bones rominent, mouth of medium size and ith moderately thick lips but no trace nplexion mainly of a bister or brown g from fair and even white to light hough never so dark as that of the

given by a scientific observer, is the he Mongolian, and corresponds in all rdinary Caucasian or Western Asi nce it is not surprising to find recent ely applying to these peoples such asique," "Indo-European," "blanc," vaux calls the Chaires "white savages " Thorel connects the northern tribes an race, or more correctly with the oples." Dr. Harmand gives us a eautiful Khang woman, dwelling pa aquiline nose, large eyes, thin lips, and other points of a European cha evens of Bassac he describes as of and taller than the surrounding Laos es, with sub-dolichocephalous head,

he Laos is decidedly handsomer, nger are remarkably beautiful in the ith large straight eyes, regular features than yellow complexion. The woman s is often described as darker than nese and Laos neighbours; but Dr. nt that this is due to the deep-seated aos, who habitually sports shoes a gh often fewer than the Laos them ntial difference between the two races precisely what we should expect, the yellow, the Khas, or Caucasian gir Thus red or ruddy tinge was also Mantse amongst the Barbars, and the d to have wavy brick hair with a tinge occurring in any pure branch of the

n tribes seem to be the true Aborigi where they have been mostly expe to the impenetrable forests and fast h-east by the intruding Mongol races e valleys of the great rivers from the Still one branch, the Khmers, re powerful and numerous enough to l in the lower Mekhong Valley, where influences, they established a flourishing empire and erected monuments 2000 years ago, whose stupendous ruins rival those in Java and India itself in archæological and artistic interest. Indeed it may be doubted whether there is anything in the whole world

more wonderful in its way than the magnificent temple of Angkor Vath, on the northern shores of Lake Toulé-sap. It is noteworthy that the bas-reliefs and other figures on these monuments are of the same type as the present Cambodian race, with the same regular features, full beard,

and even the very dress, arms, and musical instruments. Traditions of this early civilisation still linger amongst the surrounding Khmer tribes, many of whom, such as the Stiengs, Kings, and Chaires, possess natural endow-

ments of a high order, cultivate their lands with great intelligence, are skilful workers in metals, and betray extreme taste in their decorative art. In the *Tour du Monde* for May 15, 1880, Dr. Harmand figures two native pipes and a quiver of a Stieng tribe, whose forms and arabesque designs are supremely beautiful (see Figs. 11, 12, and 13). "Their artistic instincts," this observer remarks, "are more developed and especially more original [than those of their Laos neighbours]. From them I have procured various objects betraying a refined taste, and woven fabrics with simple designs and well-harmonised colours." Amongst them there is prevalent a curious system of writing, at first sight somewhat suggestive of the Irish Ogham, but of a far more primitive character. It consists of a series of notches, varying in size and number, cut on both edges of a bamboo planchette, which is generally set up as a sort of public notice at the entrance to the villages. Thus a row made up of eight large, eleven medium-sized, and nine small notches was explained to mean: "Our village contains eight men, eleven women, and nine children." It is evident that in a system of this sort as wide a scope must be left to the imagination as in the hypothetical primitive speech, in which broken utterances are largely supplemented by signs and gesture. A. H. KEANE.

(*To be continued*.)

GEOLOGY OF BOSNIA AND HERZEGOVINA

AMID the conflict of political parties, the jealousies of rival powers, the rumours of renewed dispeace among the nations, and the smouldering embers of war that seem ready at any moment to burst forth into renewed conflagration, it is a relief to turn to a volume in which the Austrian Government has just shown to the world one of the first uses to which she has put her new acquisitions in the East. Nothing could have been more quietly and unostentatiously done, and nothing could show a more enlightened and humanising policy than the action which is modestly described in the volume before us. The story is briefly told by the Ritter von Hauer in an introductory note. It appears that immediately after the pacification of the occupied provinces of Bosnia and Herzegovina the Director of the Geological Institute at Vienna addressed to the Minister of Public Worship and Instruction (under whom the Geological Institute is placed) a letter in which he pointed out the desirability of expanding the pacific mission on which the country had entered in these provinces by organising a geological survey of them under the guidance of the Geological Institute. His representations were seconded by, and on March 9, 1879, he received instructions to commence a geological reconnaissance of the provinces with detailed investigation of such localities as might be found of economical importance. The work was to be undertaken conjointly by the Geological Institutes in Vienna and Buda-pest. The Director was requested as soon as possible to submit a plan of survey with proposals as to the number of geologists to be detailed and the individuals most competent for the execution of the duties required; and he was further instructed to put himself in direct relations with the Hungarian Geological Institute with a view to a proper subdivision of the work. Ritter von Hauer had no difficulty with one part of his instructions. Two of his staff, Dr. E. von Mojsisovics and Dr. E. Tietze, had already signified their wish to undertake the work, and Dr. Bittner expressed his desire to share in it. After some delay the Hungarian Institute made known its inability, from want of a sufficient staff, to take part in the intended survey. At last, on March 23, Director Von Hauer was able to announce to the Ministry that he was ready to begin operations, and proposed that as the work would naturally fall into two sections, (1) the preparation of a geological sketch of the whole occupied Provinces, and (2) a special detailed investigation of localities affording indications of salt, coal, or ores, it would be desirable to arrange that officers employed into two divisions. For the preparation of the map he suggested that four geologists should be employed, which, estimating the area to be surveyed at 1030 square German miles, would give 250 square miles to each surveyor. He recommended for this task the three gentlemen above-named, and added the name of Prof. Hörnes of Graz as the fourth, should the Hungarian Geological Institute have no other to propose. It was of course impossible that these officers, intrusted with the task of rapidly traversing the country and seizing on its salient features of its geological structure, should have time to halt anywhere long enough to make detailed investigations for useful minerals. This part of their duties however was one in which the services of the Hungarian Geological Institute might be especially useful, seeing that the distribution of ores in the Hungarian territory bore the closest analogy to that in Bosnia. The name of Herr F. Herlich of Klausenberg was accordingly suggested as one of the most competent persons to be intrusted with this part of the survey. It was also represented that the interesting and important district of salt-spring region of Dolnji-Tuzla would be most carefully explored by Herr Bergrath K. M. Paul, well known for his intimate acquaintance with the mineral region of Slavonia, Croatia, and the northern slopes of the Bosnian Mountains. Some further suggestions as to additional assistants were made. At last on May 1, 1879, the scheme of operations received the sanction of the Minister of Public Worship and Instruction.

By the beginning of May Herr Paul had broken ground in Bosnia. Before the end of the same month Drs. von Mojsisovics, Tietze, and Bittner were likewise in the field, and each betook by themselves the whole length of the map. In about three months the traverses for the construction of the map were completed, and the general structure of a hitherto unexplored region of 1000 square German miles was added to our knowledge of the geology of Europe. One is at a loss whether most to admire the breadth of view which conceived and executed this first utilisation of an annexed territory, or the rapidity with which so rapidly carried out and completed the conception.

The *Jahrbuch der k. k. Geologischen Reichsanstalt* is one of the best-known and most useful geological periodicals in existence. The present number considerably exceeds the usual size of the periodical, since it is expressly containing the reports of the geologists upon the results of the survey of Bosnia-Herzegovina. Drs. von Mojsisovics, West Bosnia and Turkish Croatia. In his report he gives acknowledging assistance received in the course of his examination, the literature of the subject, in which his work in the veteran Ami Boué stands in the first place, the author proceeds to give a general outline of the topography and geology of the region examined. Most of the survey was done on horseback. He describes various traverses of the country, noting down by the way his observations upon the general map of Europe on the scale of 1:2,000,000 published by the Military Geographical Institute of Vienna. The first section of his report is devoted to geological topography, and includes much interesting information regarding what has been known as the "oriental fixed land"—an ancient island or group of islands round which, in the Balkan Peninsula, the Lias and the more recent formations have been ranged. The second section treats of the geological formations in stratigraphical order, the more important being Triassic, Jurassic, Cretaceous, and Flysch, the last-named belonging partly to the Cre-

Continued after the Geological ... Reichsanstalt, Band xxx. Heft 1. (Vienna: Hof- und Staatsdruckerei, 1880.) Contributions zur Geologie von Bosnien und Herzegovina. Published by the Director of the Geological Institute, Dr. E. Tietze, and Drs. E. von Mojsisovics, Dr. E. Tietze, and Dr. M. Neumayr and K. V. Hauer. Vienna, 1880. The work is also published separately by Holder of Vienna, with a preface by Ritter ... Hauer.

Eocene system. Among the younger
uthor devotes a couple of pages to sub-
ncluding the results of the superficial
ks and the formation of "eluvial" accu-
third section describes the geological
ent traverses of the country, and locali-
interest, while a supplement contains
he mineral resources of the ground re-

cribes in a similar methodical way the
Bosnia, while Dr. Bittner takes the
the south-east part of Bosnia. These
of interest, especially in relation to the
Tertiary geology of the east of Europe.
questions discussed in them we may
r occasion. Though the geologists in
es had little time to collect specimens
found opportunity to carry off some
which were found of sufficient importance
alline rocks of the Provinces, including
gne base rocks, younger diabases, diorites,
s from the Flysch, gabbros, serpentines,
trachytic and andesitic lavas. Dr.
es a series of brackish-water shells from
ations of the Provinces.
Institute of Vienna may be congratulated
rise. Rarely has so compendious a body
nation in geology been so rapidly accu-
mptly published. Bittner von Haues

March 1, 1880—that is within a year
en his proposal for the Survey was first
man Government. These few months
work, for the elaboration of the reports,
ration of the map and engraving. The
volume of 333 closely-printed octavo
is issued in one sheet on the scale of
ty-nine colours.

ARCH. GEIKIE

ARCHIT. CHASLES

Oct. 15, 1793, *Prof. Decaisne reads a paper*

not that there is a prince and a
en this day?" might well have been the
resident Bonaparte when he appointed
on the 20th all that Chasles could
n who had surpassed in the highest
by eleven. Lagrange by some Laplace
ime, and Newton by no contemporary
en," had set a "minor" only
the present generation could consider
a prince of geometers, and it has since
as a surprise to hear that he was still
king in our midst. A few years ago
t hint from Boston conveyed to us the
pressing the hope that the illustrious
ight see the close of the year of
he would have suppressed the words, for
gth of days is not always a boon, but
de sa vieillesse," and he lived to be
e might say, without end. Indeed, Bulwer
ence uttered in "Le vie de M. Chasles a
simple: il a trouvé dans la Science
ables jouets que plus tard nous immortels
attentions et ses soins dans des travaux
commits par les gens de lettres, qui
s leur respectueuse déférence en toute
em-ulation de ses vieilles."
non Lavoisier-Leroy, he entered the Ecole
y 1812. At this early date he would cross
idents in the rival college, the pre-famous
the week, adding at recess the questions
ir masters: "Dans cet échange de mots

par le jeune lycéen, on peut croire aisément que le futur
géomètre avait souvent la meilleure part." After taking
his place in the defence of Paris in 1814 he passed out in
engineering, but he re-entered the school in 1815. And
this is the reason. Chasles was on the point of leaving
for Chartres to show his uniform and to bid farewell to
his mother before going to Metz, when he was waited on
by the father of one of his comrades. "Mon fils," said
the father, "est le premier des élèves qui n'ont pas
obtenu de place; vous avez hésité, je le sais, à accepter
l'épaulette: votre refus aurait assuré à votre camarade
une carrière qui lui plaît et pour laquelle j'ai fait les
derniers sacrifices; il m'est impossible de les continuer
pour lui en préparer une autre." Chasles made no reply:
he went to Chartres; on his arrival his choice was made,
and he told his mother he would stay with her. The
army lost him as an officer, the world gained him as a
geometer. On finally leaving the establishment, in spite
of the high position he held amongst his companions, he
voluntarily renounced public employment (Carnot-se states
however: "Fut agent de change et plus tard aux affaires
pour les sciences") and went to Chartres, where he spent
some ten years. He was working quietly, however:
"Toujours passionné pour la géométrie, il résolvait de
beaux problèmes, comme au collège, trouvait chaque jour
d'élégants théorèmes, inventait des méthodes générales et
féondes sans attirer l'attention des maîtres de la science
et sans y prétendre. 'Que de talent perdu!' disaient
les plus bienveillants, sans songer même à traiter d'égal
ce jeune homme obstiné à approfondir les théories déjà
centenaires et qui bientôt peut-être devait, par elles, s'élever
bien au-dessus d'eux." Elected a Corresponding Member
of the Academy in 1839 (decorated the same year), he
was made "Professeur de Machines et de Géodésie" at
the École Polytechnique in succession to Savary in 1841.
This chair he occupied for ten years, when, in conse-
quence of some altercations "profondes et très regret-
tables" (), he sent in his resignation, and ever afterwards
did all in his power to combat these, as he thought,
dangerous reforms. His attention however continued
unabated: "C'est ainsi qu'il accepta avec tout l'empres-
sement la présidence du Comité de la Société annuale des
Anciens Élèves: 'c'est ainsi qu'il entra au conseil de
perfectionnement et que, sans augmenter encore, malgré
son droit acquis, il accepta le renouvellement de son
mandat avec le désir avoué de continuer jusqu'à son
dernier souffle à contribuer par le travail, l'honneur
et le désintéressement au progrès." With the notice which so
distinguished him Mr. Chasles had undertaken to write a
history of the chair and extract from this history he
recently published "Aperçu historique concernant la
Chaire de Machines dans l'Enseignement de l'École
Polytechnique" (see notice in NATURE, vol. xxii. p. 751).
Mr. Lupton informs us that the veteran's work is in
good part attained, and that it was with great pleasure
Charles Lupton learnt before his death that the Council
of the Royal Society had determined that the re-
mainder of the manuscript should be published. It was
the last ambition of France that gave light to
Pascal. Pour nous, en cette triste circonstance
chair should be appointed for the Master for several
and the Chair was vacant. On the 6th of December
1841 he was elected a Member of the Academy, and in
1846 he was elected a Member of the Academy, and in
the same year, almost on the same day, he was elected
a Fellow of the Royal Society. In 1855 he was elected a Foreign
Member of the Royal Society, in 1865 he was awarded the Copley
Medal, and in April, 1870, he was elected the first Foreign
Associate of the Royal Society of London.

Mathematical Society. His honours of membership were numerous, and are printed on the title-pages of his works. The Pascal-Newton controversy has already been alluded to in these pages, and we willingly leave it here untouched.

"M. Chasles a poursuivi son œuvre sans interruption depuis sa sortie du Lycée jusqu'à l'âge de quatre-vingt-sept ans. Soixante-huit années séparent la première note de l'élève Chasles, insérée dans la *Correspondance sur l'École Polytechnique*, du dernier mémoire présenté à l'Académie des Sciences. Tous les géomètres, sans distinction de nationalité ni d'école, se sont inclinés devant ce vénérable vieillard; tous ont admiré sa puissance d'invention, sa fécondité, que l'âge semblait rajeunir, son ardeur, et son zèle, continués jusqu'aux derniers jours."

A mere recital of the titles of M. Chasles' numerous papers would fill several columns. In the "Catalogue of Scientific Papers" will be found the titles of 177, and from the slight examination we have been able to make we have little doubt that the number published since 1873 would bring the total to nearly 240. The subjects range over curves and surfaces of the second and of any degree, geometry, mechanics (and attractions), history, and astronomy. Amongst his earliest papers are those which were translated by the present Bishop of Limerick in 1841, under the title "Two Geometrical Memoirs on the General Properties of Cones of the Second Degree, and on the Spherical Conics." "These possess strong claims on the attention of mathematicians, whether they are considered merely as exercises of pure geometry, exhibiting its elegance and power in a remarkable degree, or as a rich and early contribution to the theory of spherical curves."

Chasles himself remarks in his *Rapport*[1] (which perhaps furnishes the best key to his writings), "On peut s'étonner que, jusque vers la fin du premier tiers de ce siècle, on n'ait eu l'idée d'étudier ni les propriétés des cônes du second ordre qui servent à engendrer les coniques, ni celles des courbes qui tiennent sur la sphère le rang des coniques sur le plan" (p. 73).

In reply to the question, "On demande un examen philosophique des différentes méthodes employées dans la géométrie récente et particulièrement de la méthode des polaires réciproques," was written, "Mémoire de Géométrie sur deux Principes généraux de la Science, la Dualité, et l'Homographie" (January, 1830, to the Académie Royale of Brussels), preceded by some historical researches. This work subsequently took the form of the famous "Aperçu historique sur l'origine et le Développement des Méthodes en Géométrie . . . suivi d'un Mémoire . . . sur deux Principes généraux . . . et l'Homographie." This work appeared in 1837, and having become exceedingly scarce, was reprinted verbatim in 1875, with the addition of a short preface giving a brief historical account of the book. In the *Rapport* (p. 80) we are told "c'est cette troisième partie" (the memoir on Duality and Homography, "qui a donné lieu à la composition de l'ouvrage. La théorie des figures homologiques et celle des polaires réciproques qui sont la base des beaux travaux de l'illustre Général Poncelet donnèrent une heureuse impulsion aux recherches de pure géométrie." These two methods were susceptible, he says, of generalisation, and the progress of the science demanded it. The *Aperçu*, which has been translated into German (except the third part) by Sohncke, is a perfect mine of geometrical facts, and is to the present day a high authority on the subject of which it treats. In some places too great reliance on Montucla (see Dr. Allman on "Greek Geometry from Thales to Euclid," p. 171, cf. also p. 202), and in others non-acquaintance with German ("nous éprouvons un vif regret de ne pouvoir citer ici leurs ouvrages, qui nous sont inconnues, par suite de notre ignorance de la langue dans laquelle ... sont écrits," p. 215) may slightly detract from its merit; but after all deductions it exhibits a vast amount of research and originality, and well merits the title of *ouvrage classique*.[2]

The appointment to the Chair of Modern Geometry necessitated a course (or courses) of lectures, and in 18[illegible] these were embodied in the "Traité de Géométrie supérieure," "an elaborate and masterly treatise," which in late years has been rarely attainable, and only at a very high price. M. Chasles, hardly two months before his death, had the satisfaction of seeing a second edition accompanying which is (pp. 547-585) the excellent "Discours d'Inauguration" (referred to above). The three fundamental principles of this work are "Anharmonic Ratio of Four Points," "Homographic Divisions," and "Involution" (*Rapport*, p. 220).

In 1865 appeared the first volume of the "Traité des Sections coniques, faisant suite au Traité de Géométrie supérieure." As its title indicates, constant application is made in it of the principles of pure geometry unfolded in the earlier work. It thus differs considerably not only from analytical treatises, but from geometrical treatises also: "Ces trois théories primordiales s'appliquent avec une extrême facilité à toutes les recherches concernant les sections coniques" (*Rapport*, pp. 266 9).

Mathematicians have long looked for a second volume, materials for which have appeared in the *Comptes rendus*. In the *Rapport* (pp. 257-266) will be found an account of the method of *geometrical substitution* and a definition of the *elements* (or *characteristics*) of a system of conics (*Comptes rendus*, 1864-7). Numerous applications are made of this remarkable theory (for further accounts the English student may refer to Dr. Salmon's "Higher Plane Curves," pp. 369, &c., and "Conics," p. 368; see also later papers in the *Comptes rendus*, vol. lxxviii.[3] p. 5 &c., vol. lxxiv. p. 362, pp. 460-6).

We must now go back to the year 1863, when Chasles published his "Les trois Livres de Porismes d'Euclide, rétablis pour la première Fois, d'après la Notice et les Lemmes de Pappus, et conformément au Sentiment de R. Simson, sur la Forme des Énoncés de ces Propositions." In 1838 he had contributed a paper, "Sur la Doctrine des Porismes d'Euclide," to Quetelet's *Corresp. Math.* x. (1-23). We must content ourselves with referring to the *Rapport*, pp. 155, 233-42; the *Aperçu*, pp. 39, &c. Chasles cites Montucla as to the profoundness of the Porisms, gives high praise to Simson, and shows that there is in Pappus's Lemmas what is in effect the projective property of the anharmonic ratio of four points). The publication of this work led to a short controversy with M. Breton ("Question des Porismes—notices sur les débats de priorité auxquels a donné lieu l'ouvrage de M. Chasles sur les porismes d'Euclide," Paris, 1805; and a second part, Paris, 1866). M. Chasles comments on these in the *Rapport* (cf. ref. above).

We have now for a moment to the subject of attraction. "La question de l'attraction présentait-elle à l'auteur ses plusieurs points de vue, qui donnèrent lieu à divers mémoires et s'étendirent même au problème général de l'attraction d'un corps de forme quelconque" (*Rapport*, p. 101); on p. 103 he gives a history of Maclaurin's theorem (of which Todhunter—"History of the Theory of Attraction," &c., vol. i. 260, writes: "Chasles is correct"; on p. 105 we read: "Mais il restait toujours à désirer une démonstration directe et rigoureuse du théorème de Maclaurin;" and he cites an extract from Poinsot's report on his paper (*Mémoires* par divers Savants, t. ix. 1846): "Ce mémoire remarquable ne offre un nouvel exemple de l'élégance et de la clarté que la géométrie peut répandre sur les questions les plus

[1] Pp. 72-121, 222-282, contain an account of the author's own contributions to geometry.

[2] Mr. Morgan says, "A work of great importance in the historical point of view."

[3] "Considération sur le caractère propre du principe de correspondance" "s'applique avec une très grande facilité, à une infinité de questions."

es plus difficiles" (*Comptes rendus*, t. vi. -812).

rst *synthetic* solution (of General Sabine's resenting the Copley Medal) was published, not, in 1837. M. Bertrand, in his *éloge* of ry 28, 1878, *Mémoires* de l'Académie des s "M. Chasles obtenait, en la transportant si souvent étudiée de l'attraction des s démonstrations et des résultats admirés dèle d'élégance et de généralité."

space left, having perhaps already dwelt etail upon the complete works, to give an e numerous papers we referred to above. ss necessary as the results of many are orated in the larger works. We must however ntion the important mechanical principle the proposition "quand deux polygones cés d'une manière quelconque dans un plan, urs un point du plane qui est également ix sommets homologues quelconques des es, le point est semblablement placé par ux polygones."

tions of this, under Poncelet's form of e fully treated of by Richard in his "Note i principe de cinématique sur son emploi ème de M. Chasles" (Paris, 1856).

g lines of the *Rapport* M. Chasles indicates the modern system which has for its mmediate object *desapplications pratiques* caractérisée suffisamment par Dalembert

These remarks we pass over, but gladly to a wish which he strongly expresses, viz. ould be remedied by the creation of two "Géométrie infinitésimale et analytique," for "Analyse transcendante." If these ow exist, it would be a fitting compliment to establish one or both. The other wish a we repeat, and that is, following the ime, that a collected edition of his papers it present they are scattered over a very

we are indebted to the funeral speeches r M. Chasles's grave (*Comptes rendus*, Oct. nber 20, 1880) which, and M. Chasles's own ve freely cited in their original languages, g conciseness of expression.

wever linger no longer by the grass, but ng present," after repeating M. Dumas's lieu. Chasles, adieu!

R. TUCKER

HUXLEY ON EVOLUTION

II.

mmalia are the results of a process of nalogous to that which has taken place in e Equidæ, and if they exhibit different rocess, then a natural classification will the first instance, according to the place n the scale of evolution of the mam- py in the "sixth main particular ring of the determination of nch they stand. The determination of occupied by any group must, I think, be deductive application of the laws of evolu- o say, those groups which approach the Vertebrata most closely, present least evelopment, least suppression, and least the fundamental parts of the type, must stages of evolution; while those which rary characters must appertain to later

Judged from this point of view, there can be no doubt that the Monotremes embody that type of structure which constitutes the earliest stage of mammalian organisation:—

1. The mammary glands are devoid of teats; and thus the essential feature of the mammal could hardly be presented under a simpler form.

2. There is a complete and deep cloaca, as in Vertebrata lower in the scale.

3. The openings of the ureters are *hypocystic*—that is to say, they open, not into the bladder of these animals, but behind it, into the dorsal wall of the genito-urinary passage. As this answers to the neck of the allantois, the ureters of the Monotremes retain their primitive embryonic position.

4. There is no vagina apart from the genito-urinary passage, and the oviducts are not differentiated into distinct uterine and Fallopian regions.

5. The penis and the clitoris are attached to the ventral wall of the cloaca.

6. The epiphyses of the vertebræ are but slightly, or not at all developed.

7. The malleus is relatively very large, and the "processus gracilis," which is singularly long and strong, passes between the tympanic and the periotic bones to the pterygoid, with which it is firmly united. Thus the palato-pterygoid apparatus is directly connected by a "suspensorium" with the periotic, as in the Amphibia and Sauropsida. As in these, the representative of the incus is extremely small and that of the stapes columelliform.

8. The coracoid is complete, distinct, and articulates with the sternum.

9. The hip-girdle is provided with large epipubes, and the iliac axis is inclined at a large angle to the sacral axis.

10. The corpus callosum is very small.

11. There appears to be no allantoic placenta, though, from the obvious remains of the ductus arteriosus and of the hypogastric arteries, there can be little doubt that the fœtus has a large respiratory allantois. It is quite possible that, with a large umbilical sac, there may be an imperfect "umbilical" placentation.

But, while the *Ornithorhynchus* and the *Echidna* are thus the representatives of the lowest stage of the evolution of the Mammalia, I conceive it to be equally unquestionable that, as Haeckel has already suggested, they are greatly modified forms of that stage. *Echidna*, on the wholly, representing a greater, and *Ornithorhynchus* a less, departure from the general type. The absence of true teeth in both genera is an obvious sign of extreme modification. The long tongue, extraordinary external auditory passages, and relatively large convoluted brain of *Echidna*, and the cheek-pouches and horny mouth-plates of *Ornithorhynchus*, are other indications of the same kind.

Hence, the primary mammals which were less modified, and the existence of which is necessarily postulated in the conception of the evolution of the group, cannot, without risk of confusion, be called Monotremata or Ornithodelphia, since in all probability they were as widely different from *Ornithorhynchus* and *Echidna* as the Insectivora are from the Edentata, or the Ungulata from *Cetacea*. It will therefore be convenient to have a distinct name. *Prototheria* for the group which includes these, at present, hypothetical embodiments of the lowest stage of the mammalian type, or which the existing Monotremes are the only known representatives.

A similar reasoning applies to the Marsupialia. In their essential and fundamental characters they occupy an

intermediate position between the Prototheria and the higher mammals.

1. The mammary glands are provided with teats.

2. The cloaca is so greatly reduced that it is often said to have disappeared.

3. The openings of the ureters are *entoptic*—that is to say, the ureters open into what is called the "base" of the bladder in front of the narrowed "neck" by which it passes into the tubular "urethra." This means, I conceive, that, morphologically, the bladder of the Marsupial represents the bladder of the Monotreme + the anterior part of the genito-urinary passage; the so-called "trigonum," if not more, of the bladder of the Marsupial, being the homologue of that anterior segment of the genito-urinary passage of the Monotreme.

4. There is a distinct and long vagina, quite separated from the cystic urethra, in the female; and the oviducts are differentiated into uterine and Fallopian portions.

5. The penis is large, and the corpora cavernosa are connected by fibrous tissue and muscles with the pelvis. The spongy body has a large bifurcated bulb, and Cowper's glands are very largely developed.

6. The vertebræ have distinct epiphyses.

7. The malleus is small, and its connections are similar to those which it possesses in the higher mammals. The incus is relatively larger, and the stapes more or less stirrup-shaped.

8. The coracoid is short, does not articulate with the sternum, and becomes ankylosed with the scapula.

9. The hip-girdle is provided with epipubes, usually of large size and well ossified; and the iliac axis is inclined at a small angle to the sacral axis.

10. The corpus callosum is small.

11. In the few forms of which the fœtus is known there is no allantoic placenta; while the umbilical sac is so large that the possibility of the existence of a non-hilary umbilical placentation must be taken into account.

It will be observed that in the characters 1, 2, 3, 4, 5, 6, 7, 8, and the latter part of the 9th, the Marsupials agree with the higher mammals; while in the former part of the 9th, the 10th, and the 11th, they present Prototherian characters. So far, therefore, they constitute an intermediate type between that of the Prototheria and that of the higher mammals, which may be termed that of the *Metatheria*. And if there were any known animals which combined these characters, with a complete double dentition, unmodified pentadactyle manus and pes, and normal introgestation, they would furnish us the exact transition between the Prototheria and the higher mammals, which must have existed if the law of evolution is trustworthy.

No known Marsupial, however, possesses these additional characters. None has more than a single successional tooth on each side of each jaw; and, as Prof. Flower (to whom we owe the highly important demonstration of this fact) has pointed out, the question arises whether we have here a primary dentition with only one secondary tooth, or a secondary dentition with only one tooth of the primary set left. I have no doubt that the answer given to this question by Prof. Flower is correct, and that it is the milk-dentition of which only a vestige is left in the Marsupialia. Among existing Rodents, in fact, all conditions of the milk-dentition exist, from a number equal to that of the permanent incisors and premolars (as in the Rabbit[1]) to none at all.

The same thing is observed in the Insectivora, where the Hedgehog, and probably *Centetes*, have a full set of milk-teeth, while none have yet been found in the Shrews.

[1] The dentition is molars and the anterior deciduous upper teeth of the Rabbit have been long known. But I have recently found that in the Rabbit is present an additional, two anterior upper and two lower deciduous incisors. Both are simple conical teeth, the size of which one-tenth of an inch high, the lower rather larger. It would be interesting to examine fœtal Guinea-pigs in relation to this point; at present they are known to possess only the last deciduous molars, so far agreeing with the Marsupialia.

In these cases, it is obvious that the milk-dentition h gradually been suppressed in the more modified forms and I think that there can be no reasonable doubt th the existing Marsupials have undergone a like suppre sion of the deciduous teeth, in the course of their deriva tion from ancestors which possessed a full set.

Again, no existing Marsupial possesses an unmodifie pentadactyle pes. If the hallux is present, it presents a extensive movement in adduction and abduction; i fact, the pes is prehensile. This is the case in th *Phascolomyidæ*, *Phalangistidæ*, *Phascolarctidæ*, and *Didelphidæ*. The *Ponyarine* present the same type of pe with the hallux reduced or suppressed. Hence, conside ing the relations of the *Macropodidæ* and the *Peramelidæ* with the Phalangers, it seems likely that the hind fo in these groups is also a reduced prehensile pes; i which case this special modification of the foot woul characterise the whole of the existing *Marsupialia*.

Thirdly, the most marked peculiarities of the re productive organs and processes in the Marsupial a in no wise transitional, but are singularly specialise characters. The suspension of the scrotum in front the root of the penis is unlike any arrangement in th higher mammals; and the development of the bulb an of Cowper's glands is in excess of anything observable i them. In the female, the cystic urethra is as completel separated from the vagina as it is in the higher mammals while the doubling of the vagina must, in my opinion, als be considered as a special peculiarity which leads from rather than toward-, the higher mammals. In a Mono treme, in fact, the anterior end of the genito-urinar passage exhibits two very short dilatations or cornu one on each side. In the middle line, a little distanc behind these, the ureters open on a prominent ridge-like papilla. The opening of the bladder lies in front o and below the genital cornua. Now, if we compare thi arrangement with that which obtains in the lower form of the higher Mammalia, we find that the ureteric papilla have separated laterally and moved forwards, in such a manner as to occupy the base of the bladder, and the genital cornua come to lie behind and somewhat dorsad of them. At the same time a longitudinal separation has taken place between what may be called the "ureteric" region of the genito-urinary passage and the "genital" region. The first is taken into the bladder and becomes connected by a longer or shorter "cystic urethra" with the latter, which is converted into the longer or shorter vagina. In the Marsupial the same general modification has taken place; but the "genital cornua" become immensely elongated, and give rise to the so-called "double" vagina.

Lastly, the marsupium, where it exists, is a no less special feature of the Marsupialia, and, like the peculiarities of the female genital organs, appears to be related with the abnormally early birth of the fœtus. Among the higher Mammalia, it is well known that the fœtus is born in a relatively much earlier state in some cases than in others, even among closely allied species. Thus Rabbits are born hairless and blind, while Hares are born hairy and with their eyes open. I think it probable, from the characters of the pes, that the primitive forms, whence the existing Marsupialia have been derived, were arboreal animals; and it is not difficult, I conceive, to see that with such habits it may have been highly advantageous to an animal to get rid of its young from the interior of its body at as early a period of development as possible, and to supply it with nourishment rather than through an imperfect form of placenta.

However this may be, the characters of the existing Marsupialia leave no doubt on my mind that they are greatly modified members of the metatherial type; and I suspect that most, if not all, of the Australian forms are of comparatively late origin. I think it probable that the

Metatheria, of which I doubt not a
shortly be discovered in Mesozoic
widely from our existing Marsupials;
pouch, as do some existing "Mar-
ng undivided vagina, and probably
young, not earlier than exist-
nts do, the nutrition of the fœtus
station being provided for, in all
bilical placental apparatus, and its
dacental allantois.
group of the Mammalia, hitherto
ner Mammalia":—
hands are provided with teats.
usually disappeared. Sometimes,
ths), a shallow cloaca is present.
e.
he ureters are always entering
s greatly, from close to the neck
ior end of the bladder (e.g. *Hyrax*),
r vagina, which is almost always
ts are differentiated into uterine

y large, the built sinuous or partly
cavernous almost always directly

epiphyses
ually small, the ilium relatively
shipped.
most always much reduced, and
gula.
es at small angle with the post-
ligaments or ends in bone be-

m and the upper commissure
ius as *Ornithorhynchus* and *Echidna*
mmike.
ted with the uterus of the mare
uterus with *Lepus* and *Hyrax*.
the umbilical cord
ius with *Lepus* and *Hyrax*.
ches placenta.

ese respects we have no
all these respects, as have no
ner stage of evolution than the
rth and the Metatheria in the
s have run in lines more

principles of development
the placental Mammalia
ne Metatheria
ne Eutheria
ne Metatheria
ne Eutheria
ne Metatheria
ne Eutheria

Thus I regard the Amphibian type as the representative of the next lower stage of vertebrate evolution; and it is extremely interesting to observe that even the existing Amphibia present us with almost every degree of modification of the type, from such forms as the oviparous, branchiate, small-lunged *Siredon* and *Menobranchus*, which stand in the same relation to it as *Gymnura* to the Eutheria, to the exclusively air-breathing Salamanders and Frogs, in which the period of intraovular development, either within the uterus itself or in special receptacles, may be as much prolonged as it is in the Mammalia.

A careful study, on full materials, of the development of the young of such forms as *Hylodes* will probably throw great light on the nature of the changes which ended in the suppression of the branchiæ, and the development of the amnion and of the extra-abdominal part of the allantois in the fœtus of the higher Vertebrata.

The recent researches of Boas[1] on the structure of the heart and the origin of the pulmonary arteries of *Ceratodus* fell into my hands when I happened to be working afresh at the subject, and had arrived, so far as the heart is concerned, at results which are entirely confirmatory of his. This wonderful creature seems contrived for the illustration of the doctrine of evolution. Equally good arguments might be adduced for the assertion that it is an amphibian or a fish, or both, or neither—the reason of this being that, as it appears to me, *Ceratodus* is an extraordinarily little modified representative of that particular stage of vertebrate evolution of which both the typical Fishes and the typical Amphibia are special modifications. I think it will be convenient to have a name for the representatives of this stage, and I propose that of *Herpetichthyes*.

If we were to take away from *Ceratodus* the membrane-bones of the heart and the pneumatocœle, and slightly simplify the structure of the heart, the result would be an animal which would undoubtedly be classed among the *Chimeroidei*; and if, in such a Chimæroid, the lamellar septa of the branchiæ were not reduced, as they are in the *Chimæroidei*, while the opercular fold remained undeveloped, the product would be a little modified representative of the Selachian group, to which, among actually known forms, *Heptanchus* and *Cestracion* present the nearest approximations. Vertebrated animals in this stage of evolution may be termed *Chondrichthyes*.



Suppose the limbs and the genital ducts of the *Chondrichthyes*-stage to be undeveloped, and let the two nasal sacs be represented by a partially divided sac with a single external aperture, the result will be a still lower grade of vertebrate life, which may be termed *Myzichthyes*, represented only by the greatly modified Lampreys and Hags of the existing fauna.

Finally, let the head retain its primitive segmentation, and the heart its primitive character of a contractile tube, and we reach, in the *Hypichthyes*, a stage of simplification of the vertebrate type, from which it would be difficult to remove any essential feature without reaching a point at which it is questionable whether an animal should be called "vertebrate." This stage is at present represented only by a singularly modified form, the living *Amphioxus*.

Thus, in the order of evolution all the Vertebrata hitherto considered may be arranged in nine stages:—1, that of the *Hypichthyes*; 2, that of the *Myzichthyes*; 3, that of the *Chondrichthyes*; 4, that of the *Herpetichthyes*; 5, that of the *Amphibia*; 6, that of the *Hypotheria*; 7, that of the *Prototheria*; 8, that of the *Metatheria*; and, 9, that of the *Eutheria*. All these stages, except that of the *Hypotheria*, are represented by existing groups of vertebrated animals, which, in most cases, are composed of greatly modified forms of the type to which they belong, only the Amphibia and the Eutheria exhibiting near approximations to the unmodified type in some of their existing members.

It will be observed that I have omitted to mention the Ganoid and the Teleostean Fishes and the Sauropsida. I have done so because they appear to me to lie off the main line of evolution—to represent, as it were, side tracks starting from certain points of that line. The Ganoidei and the Teleostei I conceive to stand in this relation to the stage of the Herpetichthyes, and the Sauropsida to the stage of the Amphibia.

There is nothing, so far as I can see, in the organization of the Ganoid and Teleostean fishes which is not readily explicable by the application of the law of evolution to the Herpetichthyes. They may be interpreted as effects of the excessive development, reduction, or coalescence of the parts of a Herpetichthyan.[1]

[1] "Ueber Herz und Arterienbogen bei *Ceratodus* und *Protopterus*," *Morph. Jahrbuch*, 1880.

[1] That the heart of *Butirinus* characteristically Ganoid and recently been proved by Boas (*Mo* transition between the teostean heart, has re- Thus the last remnant of the supposed hiatus betw teostean vanishes.

Similarly, the suppression of the branchiæ, the development of an amnion, and of a respiratory extra-abdominal allantois, and that enlargment of the basioccipital relatively to the exoccipitals which gives rise to a single skull-condyle, is all the change required to convert an Urodele amphibian into a Lizard. It is needless to recapitulate the evidence of the transition from the Reptilian to the Bird type, which the study of extinct animal-remains has brought to light.

The scheme of arrangement of the Vertebrata which naturally flows from the considerations now brought forward will stand thus:—

Stages of Evolution.	Representative Groups.			
9. *Eutheria*.....	*Monodelphia.*			
	O			
8. *Metatheria*.....	*Marsupiala.*			
	O			
7. *Prototheria*.....	*Monotremata.*			
	O			
6. *Hypotheria*.....	×	*Sauropsida* O	*Aves.* / *Reptilia.*	
5. *Amphibia*	*Amphibia*.....	×		
	O			
4. *Herpetichthyes*.	*Dipnoi*	×	... *Osteichthyes* O	*Ganoidei.* / *Teleostei.*
	O			
3. *Chondrichthyes*.	*Chimæroidei*	×	... ×	
	O			
	Selachii.	×	... ×	
	O			
2. *Myzichthyes* ...	*Marsipobranchii*...	×	... ×	
	O			
1. *Hypichthyes* ...	*Pharyngobranchii.*	×	... ×	
	O			

It appears to me that everything which is at present known respecting the Vertebrata of past epochs agrees with the assumption that the law which expresses the process of ancestral evolution of the higher Mammalia is of general application to all the Vertebrata. If this is admitted, I think it necessarily follows that the Vertebrata must have passed successively through the stages here indicated, and that the progress of discovery, while it will obliterate the lines of demarcation between these stages, and convert them into a continuous series of small differentiations, will yield no vertebrate form for which a place does not exist in the general scheme.

NOTES

DR. JOHN STENHOUSE, F.R.S., died on December 31, in the seventy-second year of his age. He was a native of Glasgow, where he was educated and long resided. A pupil of Graham and of Liebig, he devoted all his time to research work in the domain of organic chemistry. He was a Royal Medallist of the Royal Society, LL.D. of Aberdeen, and one of the founders of the Chemical Society. On removing to London he was appointed Lecturer on Chemistry in St. Bartholomew's Hospital, London, but was obliged to resign in 1857, owing to a severe attack of paralysis. This however did not deter him from continuing his scientific studies, which were a labour of love to him. He was the inventor of the charcoal respirator, of the charcoal ventilator for sewers, and of a process for rendering fabrics waterproof by means of paraffin. In 1865 he succeeded Dr. Hofmann as non-resident assayer to the Royal Mint, but was deprived of the appointment when the office was abolished by Mr. Lowe in 1870.

ON the 3rd inst. Mr. John Thomas Towson died at his residence in Liverpool, in his seventy-seventh year. Mr. Towson was connected with the early history of photography, but in 1846 he devoted his thoughts to navigation, especially to determining the quickest routes across the ocean to distant countries. With this object he constructed a set of tables for facilitating the practice of great circle sailing, and at the British Association in 1854 Mr. Towson aided Dr. Scoresby in directing the attention of the scientific section to the importance of investigating more fully the subject of the deviation of the compasses on board iron ships. The result of this discussion was the formation of the Liverpool Compass Committee. The observations and the deductions resulting from them were embodied in three reports, "presented to both Houses of Parliament by command of Her Majesty." In 1863 Mr. Towson was instructed by the Board of Trade to prepare a manual on the deviation of the compass, which was subsequently published at the expense of the Board, under the title of "Practical Information on the Deviation of the Compass; for the use of Masters and Mates of Iron Ships."

WE are glad to learn that Prof. MacOwan, late of Gill College, Somerset East, has accepted the post of Director of the Botanic Garden, Cape Town. He will also lecture at the South African College. The appointment of a man whose long and enthusiastic devotion to South African botany has earned him a wide reputation is to the credit of the Cape Government, and is of good omen for the scientific future of the Cape Botanic Garden. This has never yet attained the position which it would naturally derive from the resources of one of the most interesting floras in the world.

DR. W. FEDDERSEN of Leipzig is preparing a supplement to Poggendorff's well-known biographical dictionary. Many of our readers will receive during the next few days circulars asking them to answer a few questions as to their scientific life and labours. As the great utility of such a work lies in the completeness of the information it supplies, we trust that every one will fill up the answers to the questions as completely as is in his power, and that neither false modesty nor carelessness will create a gap in the work.

PROF. CORFIELD's lectures on Health to ladies will commence to-day, January 6, by an Introductory Lecture at 3 p.m., and will be continued on Tuesdays and Thursdays at the same hour. Ladies are admitted free to the Introductory Lecture.

HERR ROBERT OPPENHEIM of Berlin announces the forthcoming publication of a "Grundriss der Anatomie des Menschen," by Prof. Ad. Pansch of Kiel.

THE Reale Istituto Lombardo has awarded two sums of 1500 lire, on the Brambilla foundation, (1) to the Milanese Committee of Animal Vaccination for founding a vaccinogenic establishment in Milan; and (2) to S. Bassolini for establishing in Milan a manufactory of white-lead colours and varnishes. On the Fossati foundation a sum of 2000 lire has been awarded to Dr. Golgi for studies on the fine anatomy of central organs of the nervous system; and 1000 lire to Drs. Tenchini and Staurenghi for researches in the anatomy of the cerebellum, the Pons Tarini, &c. A list of prizes now open to competition will be found in the *Rendiconti* of the Institute, vol. xiii. fasc. xviii. The subjects have nearly all been previously published. (We note that one is "Studies on the Telephone.") The prizes vary in value from 500 to 4000 lire. Foreigners may compete, and memoirs must be written in Italian, French, or Latin.

THE Transit of Venus Commission has already met at the French Academy of Sciences, as usual under the presidency of M. Dumas, but no resolution was come to. A number of scientific men have already offered themselves as observers.

BARON NORDENSKJÖLD arrived at St. Petersburg on Saturday, and was received at the station by the Swedish Ambassador and delegates from the Russian societies. In the course of the day he was received at the Foreign Office, and is to be *fêted* by the Municipality and the learned societies.

THE dates for some of the papers which will be read at the Society of Arts before Easter next have been announced. The following are set down for the ordinary meetings (Wednesday evenings):—January 12: A Sanitary Protection Association for London, by W. Fleeming Jenkin, F.R.S. (On this evening Prof. Huxley will preside.) January 19: Causes of Success and Failure in Modern Gold-Mining, by A. G. Lock. February 23: Recent Advances in Electric Lighting, by W. H. Preece. March 2: Flashing Signals for Lighthouses, by Sir William Thomson, F.R.S. March 9: Improvements in the Treatment of Esparto for the Manufacture of Paper, by William Arnot, F.C.S. March 16: The Manufacture of Aërated Waters, by T. P. Bruce Warren. In the Indian Section (Friday evenings), the following will be read:—January 21: Forest Conservancy in India, by Sir Richard Temple, Bart., G.C.S.I. February 11: The Gold-Fields of India, by Hyde Clarke. March 4: The Results of British Rule in India, by J. M. Maclean. March 25: The Tenure and Cultivation of Land in India, by Sir George Campbell, K.C.S.I., M.P. The dates and Papers for the Foreign and Colonial Section (Tuesday evenings) will be:—February 1: The Industrial Products of South Africa, by the Right Hon. Sir Henry Bartle Edward Frere, Bart., G.C.B., &c. February 22: The Languages of South Africa, by Robert Cust. March 15: The Loo Choo Islands, by Consul John A. Gubbins. April 5: Trade Relations between Great Britain and her Dependencies, by William Westgarth. For the Applied Chemistry and Physics Section (Thursday evenings) the arrangements are as follows:—January 27: A New Mechanical Furnace, and a Continuous System of Manufacturing Sulphate of Soda, by James Mactear. February 24; Deep-Sea Investigation, and the Apparatus used in it, by J. G. Buchanan, F.R.S.E., F.C.S. March 24: The Future Development of Electrical Appliances, by Prof. John Perry.

VARIOUS earthquake shocks in Roumania, Transylvania, Hungary, &c., in the latter days of December, are reported; in Bucharest, on the 23rd of that month at 11.20 a.m., and on the 25th at 5.45 p.m.; in Tultscha also, on the 25th, at 5.25 p.m. (direction north-west to south-east); in Fokschau, at 5.5 p.m., pretty strong, duration 8 sec.; in Tecuciu at 4.51 p.m., two strong shocks, the first lasting 2 sec.; the second 4 sec.; in Washui (near Tassy), a very violent undulatory shock; in Silistria (Bulgaria), at 3.22 p.m., 20 shocks lasting 1m. 20s.; in Homorod (Hungary), at 4.18 p.m., duration 5s., direction west to east; in Földvar (Hungary), at 4.20 p.m., direction north-west to south-east. At the same time shocks were felt at various places in the south-east of Transylvania.

IT may be useful to some of our readers to know that the Library of the Society of Telegraph Engineers and of Electricians is open to members of all scientific bodies, and (on application to the librarian) to the public generally. The library is open daily between the hours of 11.0 a.m. and 8.0 p.m., except on Thursdays and on Saturdays, when it closes at 2.0 p.m.

"WHITAKER'S ALMANAC" is undoubtedly a most useful publication; but in the larger edition there is a supplement of miscellaneous information which seems to us to require looking after. Among other things there is a variety of items more or less connected with science. There is a "Scientific Summary" consisting of nine lines of introduction (in which the only geological fact mentioned is the discovery of some fossil remains in Essex), followed by selected subjects of general interest, including such items as "Steam Power in Germany," "Forests in Russia," "The World's Gold and Silver," "American Railroad Progress," all looking like so many random newspaper cuttings; but no mention of perhaps the most brilliant scientific event of the year—Mr. Graham Bell's "Photophone." In another part of the supplement we have two pages on the "Progress of Astronomical Science"; why this is not included in the "Scientific Summary" the editor perhaps knows. A page is devoted to "Radiant Points of Shooting Stars," two to the "Year's Weather," three to "Earthquakes and Volcanic Eruptions," and three to "Geographical Discovery." The writer of the last-mentioned actually places Mr. Leigh Smith's yacht voyage to Franz Josef Land as "the most remarkable geographical event" of a year which witnessed the successful conclusion of Mr. Joseph Thomson's remarkable African Expedition, because he thinks it opens up "a new and apparently feasible route for future Polar research:" does he not mean *search*? Evidently the supplement to this "Almanac" stands in need of editing, and as the whole work is to be reset for next year, perhaps this part will be brought up to the level of the rest of the work.

THE *Annuaire* of the Bureau des Longitudes for 1881 has been issued by Gauthier-Villars. As usual, it is full of information on a great variety of subjects more or less connected with science.

Land and Water states that the late Mr. Frank Buckland has bequeathed his valuable Museum of Economic Fish Culture to the nation; and on the decease of Mrs. Buckland a sum of 5000*l.* will revert to the nation, to be applied for the purpose of founding a professorship of economic pisciculture in connection with the Buckland Museum and the Science and Art Department at South Kensington.

A SCOTCH Fisheries Improvement Association has been formed for the purpose of making an effort to improve by various means the fisheries of the Scotch rivers, which have in recent years considerably deteriorated. The president is the Duke of Sutherland, and the chairman of the provisional committee Mr. David Milne Home.

WE have received a copy of the regulations issued by the French Minister of Posts and Telegraphs for the International Congress and Exhibition of Electricity, to be opened at Paris next September. Those interested in the Congress should apply to M. le Commissaire Général de l'Exposition Internationale d'Electricité, at the Palace of the Champs Élysées, porte No. IV., Paris.

MR. INNES ROGERS, in a letter to us, calls attention to a list of bamboos published in vol. i. of the *Garden*, which are found to be hardy under cultivation, and to the fact that several kinds, chiefly from China and Japan, grow in Battersea Park, Kew Gardens, &c. He further instances as hardy plants a Cactus from the Rocky Mountains, Begonia from the Andes, the well-known *Chamærops excelsa*, *Ficus repens*, and a Mesembryanthemum acclimatised at Scilly, and believes that the fixity of continents through long geological periods would cause tropical species in spreading to adapt themselves to temperate conditions. He thinks that the Gulf Stream may have brought tropical seeds to Bournemouth, and that a most trifling change of climate would have made them thrive there.

A NEW illustrated archæological review will soon be published at Naples by MM. Augusto Mele and Enrico Abeniacco. It will be in French, and its title will be "Pompeii." The object of the new publication is to excite in wider circles a vivid interest for the excavations at Pompeii, Herculaneum, &c., as well as for archæology generally.

IN the Austrian "Engineers and Architects Union" at Vienna, a new aëronautical department has been created, with the object of discussing and solving aëronautical problems and questions both theoretically and in practice, as well as making the necessary experiments. The application of aëronautics to meteorological science forms a special study of the department.

To the October number of *Symons's Monthly Meteorological Magazine* Col. Foster Ward writes describing some remarkable hailstones that fell during a slight thunderstorm at Partenkirchen, Bavaria, at 6 p.m. on August 21. He was on a mountain about 3000 feet above the village, and saw the cloud (a small one) pass over the valley below. There were several peals of thunder, but there was no visible lightning, owing, he concludes, to the sun's brightness. "On arriving near home, I met a friend who told me it had been hailing 'tadpoles' and 'acidulated drops.' There had been little or no rain and no visible lightning, and



the hailstones fell at intervals and about six feet apart. There were very few of them, my family only picking up twenty in a space occupied by a full-sized lawn tennis court. My son made a sketch of their shape and size, which I inclose. The greater part were of the 'tadpole' shape and were clear as glass, perfectly round, the five knobs being at equal distance from one another. The flat stones had more or less a slight nucleus of snow in the convex portion of the stone. My wife and three daughters, and two ladies staying with us, say that the stones looked just like a lady's hand looking-glass, with a knob at the top and on either

side for ornament. More than twenty, perhaps thirty, were picked up of this shape. Of these about two-thirds were studded, the rest plain, with only the tail or handle, the thinnest part of it being near the body of the stone, as in sketch. The studs were all symmetrically placed. There were from three to five in each stone besides the handle. When there were less than five they occupied the same positions as if the five had been complete. In some cases the handle appeared to have been knocked off. The drops were more numerous, were *all* of same shape, convex at the top, the bottom being concave (like a small china painting palette)."

THE total completion of the St. Gothard tunnel will very likely take place in July of this year; the railway is to be opened on July 1, 1882. The mail-bags are even now carried through the tunnel by messengers when rough weather prevails upon the mountain. On December 21 the first mail-bag was so carried through the tunnel, and it took four hours to convey it from Œrschenen to Airolo.

GEOGRAPHICAL NOTES

AT the Second International Polar Conference at Berne all the leading nations of Europe were represented except England. The leading stations have been definitely decided on. Austria undertakes to establish a station in northern Novaya Zemlya, at the expense of Count Wilczek; Denmark has selected Upernivik; Germany New Georgia for the Antarctic, and Jan Mayen or East Greenland for the Arctic regions; Norway, Bossekop in Finmark; Holland the south-east coast of Novaya Zemlya, or the coast of Siberia, between the mouth of the Yenissei and Cape Taimyr; Russia has selected two stations, the mouth of the Lena and the New Siberian Islands. Even Switzerland, which has not even a sea-board, hopes to take part in the international movement, by establishing a station at Mossel Bay, in Spitzbergen. The expedition to be sent out by Italy to the Antarctic region under Lieut. Bove is to some extent connected with this scheme, and no doubt France will ultimately be compelled to take her part. As to England, there has hitherto been no sign that as a nation she is even interested in a scheme so full of important issues for science and navigation.

IN a recent paper to the R. Accademia dei Lincei, Signor Guido Cora, a member of the International Polar Committee, urges the importance of the enterprise under consideration, and of Italy sharing in it. He considers the Antarctic zone as the more suitable one for Italy, as being nearer regions where Italians form a large portion of the population and conduct an extensive commerce; moreover the south has a brilliant record of geographical exploration by Italians in the sixteenth century, and the recent project of an Antarctic exploring expedition has drawn enthusiastic attention. For the temporary scientific observatory which the Italian Government is recommended to plant in 1882 (in harmony with the large scheme), S. Cora suggests one or other of three places:—1. Port Spence, on the east coast of Coronation Island in the Southern Orkneys, at about 60° 50′ S. lat., and 45° 45′ W. long. 2. Cape Look-out, on the south coast of Elephant Island, in the north-east part of the Southern Shetland group, at about 61° 17′ S. lat. and 55° 15′ W. long. (a station at either place would serve well as a base of operations for the Italian Exploring Expedition). 3. In the case of means being inadequate for a station at either of the two places named, S. Guido recommends some one of the islands close to Cape Horn. Supposing that the transport would be by a Government vessel destined to the naval station

in South America, it is calculated that the cost of the observatory would amount to 70,000 or 80,000 lire, of which 10,000 would be for instruments, and the remainder would provide three dwelling-houses, salaries of four scientists, two assistants, and two servants, food, &c. This is calculated for an absence of sixteen months, twelve of which would be occupied in observations.

THE Geographical Society's *Proceedings* this month contains three papers relating to Africa, the first of which is Sir Bartle Frere's, on Temperate South Africa. This, as now printed, embodies some useful statistical information and is illustrated by a general map of South Africa. The other two papers bring some additions to our knowledge of the geography of West Africa, Mr. Comber giving a short sketch of his recent journeys in the interior of Congo, and Mr. Milum an account of his travels in the Niger region. The former is accompanied by an excellent map of the neighbourhood of San Salvador and of the course of the River Congo from Stanley Pool to the sea. The final report of the Executive Committee of the African Exploration Fund is published, together with a statement of receipts and expenditure. In the Geographical Notes extracts are given from a letter by Mr. Hore of Ujiji, on the long-continued rise of the waters of Lake Tanganyika, which he seems to connect with earthquake-movements. Mr. Hore is shortly about to return to England, so that we shall probably hear more on this subject before long. Among the other notes we may call attention to those on the River Okavango, the survey of Eastern Palestine, and the United States' Survey operations in the neighbourhood of Behring Strait. Increased attention, we note, is being paid to the proceedings of foreign geographical Societies, those of the French Society being very fully reported.

M. VOSSION, who, it will be remembered, spent some time in Burmah, and not long since read papers on that country before the French Geographical Societies, has lately gone to Egypt to take up the Vice-Consulship of Khartum. During his stay there he is to pay special attention to the slave trade, and to the best means of opening up commercial relations with the Sudan.

CAPT. SERRA-CARRACIOLI left Naples on November 23, 1880, for the Bay of Assab, having undertaken a mission, under the auspices of the Club Africano, to inquire into the possibility of developing commerce there and with the natives of the interior. The Club Africano is desirous of establishing pearl, mother-of-pearl, and sponge fisheries in the Bay of Assab. While funds are being raised for more extensive operations, this expedition is sent out to make a careful survey of the region, to form a depôt for further expeditions, whether commercial or scientific, and to make other preparations. The expense is expected not to exceed 600*l*. It is also stated that the Italian Geographical Society have made arrangements for the establishment of a meteorological station at the Bay of Assab. The October part of the *Bolletino* of the Italian Geographical Society contains a long and valuable memoir by Signor C. de Amezaga on Assab.

AT the last meeting of the Lyons Geographical Society M. Coillard gave an interesting account of his twenty years' experiences in South Africa. He was engaged for some time on a missionary expedition in the Upper Zambesi region, and was probably the means of saving Major Serpa Pinto's life, afterwards accompanying him in some of his explorations. As no particulars have yet been published of M. Coillard's geographical work in this region, it is to be hoped that his paper will be given in full in the Lyons Society's *Bulletin*.

IN last week's *Missions Catholiques* we have the concluding instalment of some interesting and useful papers by the Bishop of Vancouver, entitled "Une Visite Pastorale dans le Territoire d'Alaska." Père Montiton's notes on the traditions and customs of the Sandwich Islands are also continued.

THE January number of *Good Words* contains the first of a series of papers by Mr. Joseph Thomson on his experiences during his recent journey in East Central Africa. The present instalment deals with the preparatory journey which he made with Mr Keith Johnston to Usambara, and furnishes interesting notes on the country traversed.

THE Alexandria Correspondent of the *Daily News* tells us that M. Chower, formerly a newspaper correspondent in Turkey, Kurdistan, Armenia, and Albania, started on December 31, "to explore Africa from north to south, from Alexandria to the Cape of Good Hope." *Bon voyage*.

THE death is announced of Dr. Fr. Mook, the well-known African traveller, who accompanied Dr. E. Riebeck on his expedition, which started in August last for the East. Dr. Mook died at Jaffa shortly before Christmas.

WE have received parts 17 to 22 of the new edition of Stieler's Hand-Atlas, with three supplementary parts containing in eight sheets a very fine map of the Basin of the Mediterranean Sea.

THE Dutch Committee, which arranged the North Polar Expeditions of the last few years, held a general meeting at the Hague a short time ago, when the resolution was passed to collect funds for the organisation of a fourth Arctic expedition. In the meantime the Committee will endeavour to have a steamer built for this purpose.

ON HEAT CONDUCTION IN HIGHLY RAREFIED AIR[1]

THE transfer of heat across air of different densities has been examined by various experimentalists, the general result being that heat conduction is almost independent of pressure. Winkelmann (*Pogg. Ann.* 1875, 76) measured the velocity of cooling of a thermometer in a vessel filled with the gas to be examined. The difficulty of these experiments lies in the circumstance that the cooling is caused not only by the conduction of the gas which surrounds the cooling body, but that also the currents of the gas and, above all, radiation play an important part. Winkelmann eliminated the action of currents by altering the pressure of the gas between 760 and 1 millim. (with decreasing pressure the action of gas currents becomes less); and he obtained data for eliminating the action of radiation by varying the dimensions of the outer vessel. He found that, whereas a lowering of the pressure from 760 to 91·4 millims. there was a change of only 1·4 per cent. in the value for the velocity of cooling, on further diminution of the pressure to 4·7 millims. there was a further decrease of 11 per cent., and this decrease continued when the pressure was further lowered to 1·92 millim.

About the same time Kundt and Warburg (*Pogg. Ann.* 1874, 5) carried out similar experiments, increasing the exhaustion to much higher points, but without giving measurements of the pressure below 1 millim. They inclosed a thermometer in a glass bulb connected with a mercury pump, and heated it to a higher temperature than the highest point at which observations were to be taken; then left it to itself, and noted the time it took to fall through a certain number of degrees. They found that between 10 millims. and 1 millim. the time of cooling from 60° to 20° was independent of the pressure; on the contrary, at 150 millims. pressure the rate was one-and-a-half times as great as at 750 millims. Many precautions were taken to secure accuracy, but no measurements of higher exhaustions being given the results lack quantitative value.

It appears, therefore, that a thermometer cools slower in a so-called vacuum than in air of atmospheric pressure. In dense air convection currents have a considerable share in the action, but the law of cooling in vacua so high that we may neglect convection has not to my knowledge been determined. Some years ago Prof. Stokes suggested to me to examine this point, but finding that Kundt and Warburg were working in the same direction it was not thought worth going over the same ground, and the experiments were only tried up to a certain point, and then set aside. The data which these experiments would have given are now required for the discussion of some results on the viscosity of gases, which I hope to lay before the Society in the course of a few weeks; I have therefore completed them so as to embody the results in the form of a short paper.

An accurate thermometer with pretty open scale was inclosed in a 1½ inch glass globe, the bulb of the thermometer being in the centre, and the stem being inclosed in the tube leading from the glass globe to the pump.

Experiments were tried in two ways:—

I. The glass globe (at the various exhaustions) was immersed in nearly boiling water, and when the temperature was stationary it was taken out, wiped dry, and allowed to cool in the air, the number of seconds occupied for each sink of 5° being noted.

II. The globe was first brought to a uniform temperature in a vessel of water at 25°, and was then suddenly plunged into a large vessel of water at 65°. The bulk of hot water was such that the temperature remained sensibly the same during the continuance of each experiment. The number of seconds required for the thermometer to rise from [illegible] to 50° was registered as in the first case.

[1] Abstract of a Paper read before [illegible]ciety by William Crookes, F.R.S., December 16, 1880.

It was found that the second form of experiment gave the most uniform results; the method by cooling being less accurate, owing to currents of air in the room, &c.

The results are embodied in the following Table:—

(Rate of Heating from 25° to 50°)

TABLE I.

Pressure.	Temperature.	Seconds occupied in rising each 5°.	Total number of seconds occupied.
760 millims.	25°	0	0
	25 to 30	15	15
	30 to 35	18	33
	35 to 40	22	55
	40 to 45	27	82
	45 to 50	39	121
1 millim.	25°	0	0
	25 to 30	20	20
	30 to 35	23	43
	35 to 40	25	68
	40 to 45	34	102
	45 to 50	48	150
620 M.[1]	25°	0	0
	25 to 30	20	20
	30 to 35	23	43
	35 to 40	29	72
	40 to 45	37	109
	45 to 50	53	162
117 M.	25°	0	0
	25 to 30	23	23
	30 to 35	23	46
	35 to 40	32	78
	40 to 45	44	122
	45 to 50	61	183
59 M.	25°	0	0
	25 to 30	25	25
	30 to 35	30	55
	35 to 40	36	91
	40 to 45	45	136
	45 to 50	67	203
23 M.	25°	0	0
	25 to 30	28	28
	30 to 35	33	61
	35 to 40	41	102
	40 to 45	55	157
	45 to 50	70	227
12 M.	25°	0	0
	25 to 30	30	30
	30 to 35	37	67
	35 to 40	41	108
	40 to 45	58	166
	45 to 50	86	252
5 M.	25°	0	0
	25 to 30	38	38
	30 to 35	43	81
	35 to 40	54	135
	40 to 45	71	206
	45 to 50	116	322
2 M.	25°	0	0
	25 to 30	41	41
	30 to 35	51	92
	35 to 40	65	157
	40 to 45	90	247
	45 to 50	165	412

There are two ways in which heat can get from the glass globe to the thermometer—(1) By radiation across the intervening space; (2) by communicating an increase of motion to the molecules of the gas, which carry it to the thermometer. It is quite conceivable that a considerable part, especially in the case of heat of low refrangibility, may be transferred by "carriage," as I will call it to distinguish it from convection which is different, and yet that we should not perceive much diminution of transference, and consequently much diminution of rate of rise with increased exhaustion, so long as we work with ordinary exhaustions up to 1 millim. or so. For if, on the one hand, there are fewer molecules impinging on the warm body (which is adverse to the carriage of heat), yet on the other the mean length of path between collisions is increased, so that the augmented motion is carried further. The number of steps by which the temperature passes from the warmer to the cooler body is diminished, and accordingly the value of each step is increased. Hence the increase in the difference of velocity before and after impact may make up for the diminution in the number of molecules impinging. It is therefore conceivable that it may not be till such high exhaustions are reached that the mean length of path between collisions becomes comparable with the diameter of the case, that further exhaustion produces a notable fall in the rate at which heat is conveyed from the case to the thermometer.

[1] M = millionth of an atmosphere.

The above experiments show that there *is* a notable fall, a reduction of pressure from 5 M. to 2 M. producing twice as much fall in the rate as is obtained by the whole exhaustion from 760 millims. to 1 millim. We may legitimately infer that each additional diminution of a millionth would produce a still greater retardation of cooling, so that in such vacua as exist in planetary space the loss of heat—which in that case would only take place by radiation—would be exceedingly slow.

SCIENTIFIC SERIALS

Journal de Physique, December, 1880.—Note on magic mirrors, by M. Bertin.—On some applications of articulated systems, by M. Robin.—Experiments on the discharge in rarefied gases, by M. Righi.—Notice on the life and works of M. Almeida.

Archives des Sciences Physiques et Naturelles, November 15.—Meteorological *résumé* of the year 1879 for Geneva and the Great St. Bernard, by M. Plantamour.—Disinfection of vehicles, plants, collections of natural history, and various objects with anhydrous sulphurous acid, by Dr. Fatio.—Observations on a memoir of M. Schönn, by M. Soret.—On the phenomenon of hydration in peptonisation of albuminoid substances, by Dr. Danilewsky.—Notes on the winds of mountains, by M. Pittier.—Case of diplopia, by Prof. Wartmann, &c.

Reale Istituto Lombardo di Scienze e Lettere. Rendiconti. vol. xiii. fasc. xviii., November, 1880.—This number contains lists of prizes awarded and offered.

Atti della R. Accademia dei Lincei, vol. v. fasc. 1 (December 5, 1880).—New studies on the nature of malaria, by SS. Cuboni and Marchiafava.—Graphic determination of the elastic force relative to plane elements passing through a point, by S. Modigliano.—On the geological nature of strata met with in the tubular foundations of the new iron bridge built on the Tiber at Ripatta, and on the *Unio sinuatus*, Lamk., there found, by S. Meli.—On the structure of the envelope of the ova of some fishes, by S. Lepori.—On the preservation of man in countries of malaria, by S. Tommasi-Crudeli.—On bilinear ternary forms, by S. Battaglini.—On the projected stations for systematic physical observations in polar regions, by S. Cora.—On a cebocephalic caprine monster, by S. de Sanctis.—On the recent restoration of the scholastic and tomistic philosophy, by S. Ferri.

SOCIETIES AND ACADEMIES

LONDON

Photographic Society, December 14, 1880.—J. Glaisher, F.R.S., president, in the chair.—Papers were read by Prof. T. E. Thorpe, F.R.S., on a simple and expeditious method of preparing pyrogallol for dry plate development. The method proposed is to put dry gallic acid and glycerine into a flask, which is then heated to 200° on a sand tray, as long as bubbles of carbon dioxide are seen to be formed in the liquid. The gallic acid soon dissolves and is entirely converted into the theoretical quantity of pyrogallol, viz., 80 per cent.—By Capt. Abney, R.E., F.R.S., iodide and ammonia in gelatine emulsions. It was stated that iodides in gelatine bromide emulsion kept the silver salts from being deposited upon the shadows, as also that there is freedom from decomposition of the film, and tendency to red fog, and more light can be used in preparing and developing the plates.—And also by Capt. Abney on a photographic sunshine recorder. This consisted of a semi-cylindrical box with a flat lid, in the centre of which is a small hole; round the inside of the cylinder strips of sensitive paper are

fixed; the instrument is then so placed that the sun, the hole, and the centre line of the paper are in the same plane, so that as the sun moves its track will be recorded on the paper.

Victoria (Philosophical) Institute, January 3.—A paper on the early destinies of man was read by Mr. J. E. Howard, F.R.S., F.L.S., &c., in which he considered them in relation to science, to philosophy, and also to religion, and gave an analysis of the various known traditions in regard to the early history of man in all ages and in all countries.

MANCHESTER

Literary and Philosophical Society, December 14, 1880.—E. W. Binney, F.R.S., F.G.S., president, in the chair.—Boulder stones as grave stones. The president, when visiting Ashton-under-Lyne the other day, observed in the churchyard on the Manchester Road a greenstone boulder used as a tombstone over the grave of a son of an alderman of that borough. This is the first instance where he had seen a boulder stone used for such a purpose, and it is one where they may not only be preserved, but exhibited to the public.—The land subsidence at Northwich, by Thomas Ward.—Some endeavours to ascertain the nature of the insoluble form of soda existing in the residue left on causticising sodium carbonate solutions with lime (Part ii.), by Watson Smith, F.C.S., Assistant Lecturer on Chemistry in the Owens College, and W. T. Liddle. Communicated by Prof. C. Schorlemmer, F.R.S.

PARIS

Academy of Sciences, December 27, 1880.—M. Edm. Becquerel in the chair.—M. Faye presented the *Annuaire du Bureau des Longitudes* for 1881, and noted the improvements.—On the series of Fourier and other analytical representations of functions of a real variable, by M. Hermite.—On the velocity of propagation of light, by M. Cornu. He controverts M. Gouy's ideas.—On the chlorhydrates of metallic chlorides, and on the reduction of chlorides by hydrogen, by M. Berthelot. These chlorhydrates play an important part in chemical mechanics, by reason of their considerable heat of formation and their state of dissociation.—On an oxygenated base derived from aldol, by M. Wurtz.—Effects of tearing out the intracranial part of the glossopharyngeal nerve, by M. Vulpian. This action does not (in the cat) appreciably affect the influence of nerves which act as direct vaso-dilators on the mucous membrane of the buccal cavity, except as regards the effects of excitation of the nerve itself on the posterior region of the dorsal face of the tongue.—Observations on some animals of Madagascar, by M. Milne-Edwards. This relates to an important collection of mammalia and birds by M Humblot, sent to the Museum of Natural History They show the modifications of species well. M. Humblot has sent to the menagerie two living Aye-Ayes, two Makis, &c. (offering many points of interest).—Order of production of the first vessels in the ear of *Lolium* (first part), by M. Trécul.—M. Sella was elected Correspondent in Mineralogy in room of the late Prof. Miller, and Mr. Warren De La Rue in Astronomy in room of the late Mr. MacLear.—Observations on phylloxera, by M. Lichtenstein. He indicates ten or eleven animal parasites of phylloxera, but does not regard any of these hopefully as a means of stopping the disease. He is studying the effect of inoculation with cryptogams; the results are not yet decisive.—Determination of the time of rotation of Jupiter, by M. Cruls. From observations of the spot at Rio Observatory during 1083 rotations he obtains the number 9h. 55m. 36s. in mean solar time. Mr. Pratt, at Brighton, got the number 9h. 55s. 33·91, from 321 rotations. Thus the time of Jupiter's rotation seems to be known to within a second.—On Hartwig's comet (*d* 1880), by MM. Schulhof and Bossert. They consider the period 62⅔ years must be rigorously excluded.—Solar observations at the Royal Observatory of the Roman College during the third quarter of 1880, by P. Tacchini. There was increased activity. The number of spots was double that in the preceding quarter, and there was hardly a day without them. The number of faculæ in September was extraordinary. In the case of the protuberances (also more frequent) there was a maximum in each hemisphere between 50° and 60° and another between 20° and 40°.—Observations on Swift's comet (*e* 1880) at the Royal Observatory of the Roman College, by P. Tacchini.—On the contact of conics and surfaces, by M. Moutard.—On a new method of producing intermittent luminous signals, by M. Crova. M. Leverrier and he used in 1870-71 a very similar arrangement to M. Mercadier's. They found that they must use oxygen under weak pressure and give the pipe a wide orifice; also that the key must be pressed and released very suddenly.—On a new electrodynamic theorem, by M. Cabanellas.—Regulator of pressure for vapours, by M. D'Arsonval. The triple problem here solved is (1) keeping constant, in a boiler, the pressure of a given vapour whatever the discharge; (2) using the combustible gas only in proportion to the vapour expended; (3) making the instrument quite automatic without danger of explosion. There is a membrane of caoutchouc between two metallic rings; its lower surface is in contact with the vapour, and on its upper rests a metallic disk with rod and lever like that of a safety valve. At the upper surface of the disk debouches a tube which brings the gas; there is another tube above through which the gas goes to the boiler.—On a new derivative of sulphide of nitrogen, by M. Demarcay.—On a platinous hypophosphite, by M. Engel. This is got by action of phosphuretted hydrogen on tetrachloride of platinum.—On borotungstates of sodium, by M. Klein.—On some facts relative to the transformation of chloral into metachloral, by M. Bryasson.—On the products of oxidation of cholalic acid.—On the excretion by urine of sulphur incompletely oxidised, in various pathological states of the liver, by MM. Lépine and Flavard.—On visual sensibility and its relations with luminous and chromatic sensibility, by M. Charpentier. What he calls visual sensibility corresponds to visual acuteness, but while the latter is expressed by the smallest angle under which one can recognise as distinct two luminous points; the former is expressed by the smallest quantity of light which renders those two points distinct. The order of increasing complexity is, luminous sensibility, chromatic sensibility, visual sensibility.—On the distribution of light in the solar spectrum (spectrum of Daltonians), by MM. Macé and Nicati. These observations appear to give certain proof of the existence of two distinct kinds of Daltonians; also to support the Young-Helmholtz theory of colours, and to contradict Hering's.—Reactions of the motor-zone of the brain in animals paralysed by curare, by MM. Couty and De Lacerda.—On passage of red corpuscles into the lymphatic circulation, by M. Laulaine. This is effected by obliteration of veins. The effect appears in about twelve hours, and the number of corpuscles increases to about the fortieth hour.—On the internal and external sheaths of hairs, by M. Renaut.—New researches on the organs of touch, by M. Ranvier. By observing the tactile corpuscles in infants and children he has come to a better appreciation of their structure.—On the sensitive nerve-termination in the skin of some insects, by M. Viallanes. Examining larvæ of *Musca* and *Eristalis*, he finds under the hypodermis an extremely rich plexus of ganglionic cells, connected on one hand with the chief nerve-centres, and on the other with sensitive terminal nerve-branches.—On the sensorial cylinders of the internal antennæ of crustaceans, by M. Jourdain. While these have undoubtedly the characters of an organ of sense, they cannot (anatomically, and independently of all physiological experiment) be said to be affected with olfaction.—Marine mollusca living on the coasts of Campbell's Island, by M. Filhol.—Examination of the marine fauna of the upper sands of Pierrefitte near Etampes, by M. Meunier.—On the age of upheaval of the district of Bray, by M. Dollfus.—On the crystalline schists of Brazil and the red earths which cover them, by M. Gorceix.

CONTENTS

	PAGE
DR. GÜNTHER ON FISHES (*With Illustrations*)	213
SULPHURIC ACID AND ALKALI By Prof. H. E. ROSCOE, F.R.S.	215
OUR BOOK SHELF:—	
Kaltbrunner's "Aide-Mé noire du Voyageur"	217
LETTERS TO THE EDITOR:—	
Geological Climates.—ALFRED R. WALLACE; H. KING	217
Temperature of the Breath.—C. J. MCNALLY	217
Selenium.—W. M. C. (*With Diagram*)	218
Experiments with Vacuum Tubes.—J. T. BOTTOMLEY	218
Modern Use of Ancient Stone Implements.—D. BUDDE	218
Pile Dwellings.—S. E. PEAL (*With Illustration*)	218
Landslips.—The Cheshire Subsidences.—T. MELLARD READE	219
Animal Reasoning.—K. P.	219
Ozone.—J. RAND CAPRON	220
THE INDO-CHINESE AND OCEANIC RACES—TYPES AND AFFINITIES. II. By A. H. KEANE (*With Illustrations*)	220
GEOLOGY OF BOSNIA AND HERZEGOVINA. By Prof. ARCH. GEIKIE, F.R.S.	224
MICHEL CHASLES By R. TUCKER	225
PROF. HUXLEY ON EVOLUTION, II.	227
NOTES	231
GEOGRAPHICAL NOTES	233
ON HEAT CONDUCTION IN HIGHLY RAREFIED AIR. By WILLIAM CROOKES, F.R.S.	234
SCIENTIFIC SERIALS	235
SOCIETIES AND ACADEMIES	235

SUBSCRIPTIONS TO NATURE

Yearly . . . . . 28s.
Half-yearly . . . . . 14s. 6d.
Quarterly . . . . . 7s. 6d.

To the Colonies, United States, the Continent, and all places within the Postal Union :—

Yearly . . . . . 30s. 6d.
Half-yearly . . . . . 15s. 6d.
Quarterly . . . . . 8s.

Office: 29, Bedford Street, Strand.

DIARY OF SOCIETIES.

LONDON

THURSDAY, JANUARY 6.

ROYAL SOCIETY, at 4.30.—Researches on the Minute Structure of the Thyroid Gland: E. C. Baber.—Existence of Ice and other Bodies in the Solid State at Temperatures far above their ordinary Melting Points: Prof. T. Carnelley.—Phenomena of the Capillary Electróscope: G. Gore, F.R.S.—Electric Currents caused by Liquid Diffusion and Osmose: G. Gore, F.R.S.—Additional Note to a Paper on the Thermal Conductivity of Water: J. T. Bottomley.—And other Papers by G. F. Rodwell, Prof. Schäfer, F.R.S., and Dr. Thudichum.

ROYAL INSTITUTION, at 3.—Atoms: Prof. Dewar.

LONDON INSTITUTION, at 7.—Our Living Dramatists: Prof. H Morley.

FRIDAY, JANUARY 7.

GEOLOGISTS' ASSOCIATION, at 8.—The Zones of Chalk: Prof. Morris.

SATURDAY, JANUARY 8.

ROYAL INSTITUTION, at 3.—Atoms: Prof. Dewar.

SUNDAY, JANUARY 9

SUNDAY LECTURE SOCIETY, at 4.—Temperaments as a Practical Study: Dr. B. W. Richardson.

MONDAY, JANUARY 10.

LONDON INSTITUTION, at 5.—The French Revolution: Frederic Harrison.

TUESDAY, JANUARY 11.

ANTHROPOLOGICAL INSTITUTE, at 8.

PHOTOGRAPHIC SOCIETY, at 8.

WEST LONDON SCIENTIFIC ASSOCIATION, at 8.

WEDNESDAY, JANUARY 12.

ROYAL MICROSCOPICAL SOCIETY, at 8.—On Three Microspongiadæ belonging to the Hexactinellids from the Deep Sea: Prof. P. Martin Duncan, F.R.S.—On the Aperture Question: G. Shadbolt.—On the true Conditions of Stereoscopic and Pseudoscopic Effect in Microscopical Vision: Prof. E. Abbe.—On a Species of Acarus believed to be unrecorded: A. D. Michael.

SOCIETY OF ARTS, at 8.—A Sanitary Protection Association for London: Prof. Fleeming Jenkin.

THURSDAY, JANUARY 13.

ROYAL SOCIETY, at 4.30

MATHEMATICAL SOCIETY, at 8.—On an Apparently Paradoxical Relation of the Circle, Parabola, and Hyperbola: A. J. Ellis, F.R.S.—A Proof of the Differential Equation which is satisfied by the Hypergeometric Series: Rev. T. R. Terry.—On the Periodicity of Hyper-Elliptic Integrals of the First Class: W. R. Westropp Roberts.—On the Tangents drawn from a Point to a Nodal Cubic: R. A. Roberts.

LONDON INSTITUTION, at 7.—The Art of Popular Illustration: H. Blackburn.

FRIDAY, JANUARY 14.

ROYAL ASTRONOMICAL SOCIETY, at 8.

QUEKETT MICROSCOPICAL CLUB, at 8.

YORK'S

SERIES of SCIENTIFIC OPTICAL LANTERN SLIDES

Comprise over 2,000 of the following subjects:—Electricity, Magnetism, Sound, Telephone, Microphone, Electric Light, Light, Spectrum Analysis, Astronomy, Mines and Miners, Heat, Mechanics, Hydrostatics, Pneumatics, Human Physiology. Sample Slide and Catalogue sent on receipt of 2s.

F. YORK, OPTICAL LANTERN SLIDE MANUFACTURER,
87, Lancaster Road, Notting Hill, London, W.

NOTICE OF REMOVAL.

JAMES HOW & CO.,

SCIENTIFIC INSTRUMENT MAKERS,

73, FARRINGDON ST., LONDON

(LATE OF 5, ST. BRIDE ST., AND 2, FOSTER LANE)

HOW'S STUDENT'S MICROSCOPE. HOW'S MICROSCOPE LAMP.

Rock Sections and other Objects for the Microscope.

"CHALLENGER" EXPEDITION,

MICROSCOPIC PREPARATIONS FROM,

Per Sir WYVILLE THOMSON.

24 Soundings correctly marked, Lat., Long., Depth, &c., in Box, 30s.

Also, 24 Injected Preparations illustrating Anatomy of the Monkey, in Box, 21s

To be had of J. T. NORMAN, 178, City Road, E.C., about 100 yards north of Old Street.

A large variety of Specimens in all Branches of Microscopy.

LIGHTNING CONDUCTORS.

Experience, accumulated since the time of Benjamin Franklin, proves conclusively that a Conductor made of Copper of adequate size is the best of all appliances for the protection of every description of building from the destructive effects of lightning.

NEWALL & CO.'S

PATENT COPPER LIGHTNING CONDUCTOR,

As applied to all kinds of Buildings and Shipping in all parts of the world with unvarying success; is the most Trustworthy, most Effective, and also the Cheapest Conductor ever offered to the public.

It is simple in its application, no insulators being required, and it costs only one shilling per foot for the standard size, which ensures safety in any storm

R. S. NEWALL & CO., 130, STRAND, W.C.
36, WATERLOO ROAD, LIVERPOOL.
68, ANDERSTON QUAY GLASGOW.
MANUFACTORY—GATESHEAD-ON-TYNE.

NOW READY,

SECOND EDITION,

GRIFFIN'S

CHEMICAL HANDICRAFT.

PRICE 4s. 7d. POST FREE.

A CATALOGUE OF CHEMICAL APPARATUS:

ILLUSTRATED, CLASSIFIED DESCRIPTIVE

Demy 8vo, 480 pp., Illustrated with 1,600 Woodcuts.

Most Complete and Cheapest List of Apparatus.

JOHN J. GRIFFIN AND SONS, 22, GARRICK STREET, LONDON, W.C.

S. C. TISLEY & Co.,

OPTICIANS,

172, BROMPTON ROAD, S.W.

(Close to South Kensington Museum)

THE PHONEIDOSCOPE

An Instrument for Observing the Colour-Figures of Liquid Films under the action of Sonorous Vibrations.

Being a visible demonstration of the Vibratory and Molecular Motion of a Telephone Plate.

The PHONEIDOSCOPE, with 3 Discs, Bottle of Solution, Descriptive Pamphlet, &c., in Cardboard Box, 10s. 6d.

MANUFACTURED AND SOLD WHOLESALE AND RETAIL BY

S. C. TISLEY & CO., 172, BROMPTON ROAD, LONDON, S.W.

TELEPHONIC ELECTRICITY. All Materials supplied for experimental purposes.

Price Lists of Electrical and Acoustic Apparatus, with Drawings and Description of the Harmonograph, Post Free, 2d.

R. W. NEEVES,

PHILOSOPHICAL INSTRUMENT

AND

INTENSITY COIL MAKER.

PRICE LIST, FOUR STAMPS.

55, SIDMOUTH STREET, LONDON, W.C.

Liberal Terms to Science Teachers and the Trade.

THOMAS CRAMPTON & Co. (formerly of 4, Little Britain, London, E.C.), ELECTRICIANS, OPTICIANS, and PHILOSOPHICAL INSTRUMENT MAKERS. Electric Bells, New Metallic Base Pattern, Constant Batteries, Indicators, Thief and Fire Alarms, and Automatic Switches, Induction and Medical Coils, or Specialities. Insulated Wires of every description. Microscopic and Optical Materials. Telescopes, Opera Glasses, Microscopes, Aneroid Barometers, and Lime-light Apparatus. Illustrated Catalogue Three Stamps.

THOMAS CRAMPTON & CO., 251, HIGH HOLBORN, LONDON, W.C.

For Trade Terms send Card.

£5 5s. ASTRONOMICAL TELESCOPE.

CRAMPTON & CO.'S IMPROVED TELESCOPE is of the highest workmanship and finish, combined with great power and clearness of definition: is entirely constructed of polished brass, with 3-inch Achromatic Object Lens, Altitude and Azimuth Movements, Rackwork, and Fine Adjustment, &c., &c.

THOMAS CRAMPTON & CO., 251, HIGH HOLBORN, LONDON, W.C.

W. LADD & CO.,

SCIENTIFIC INSTRUMENT MANUFACTURERS,

(By Appointment to the Royal Institution of Great Britain),

11 AND 12, BEAK STREET, REGENT STREET, W.

IMPROVED HOLTZ ELECTRICAL MACHINES. GRAMME'S MAGNETO-ELECTRIC MACHINE for Laboratory use.

PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3*s.* per oz.

Physical Apparatus of every Description.

ILLUSTRATED CATALOGUE, SIXPENCE.

PATERSON'S NEW CATALOGUE OF PHYSICAL APPARATUS.

LANTERN SLIDES for SCIENTIFIC LECTURES. Season 1880–1. Post free 6 Stamps.
Complete Sets of Physical Apparatus for Science Primers and all the Physical Text-books in use in Schools and Colleges.
Siemens and Gramme Dynamo Machines and Lamps for hire.
Schools supplied with Apparatus as per Science and Art Departments' Requirements in the Sections of Light, Heat, Sound, and Electricity.
Electric Signals for Houses, Hotels, &c., Colliery Signals. Lightning Conductors. The Gower-Bell Loud-speaking Telephone.

EDWARD PATERSON, Electrical Engineer.

SHOW ROOMS AND STEAM WORKS:—76, LITTLE BRITAIN, E.C. (late 3, Bedford Court, W.C.).

MOLISON'S HARMONOGRAPH; executes the Harmonic Curves in the most perfect manner. 15*s.* and 20*s.*

Illustrated Catalogue of Electrical Apparatus, Part 1, *post free*, 6 *Stamps. Ditto, Electric Signals, Part* 2, 6 *Stamps.*

FLETCHER'S PATENT SOLID FLAME BURNERS.

The highest power Gas-heating Burners ever constructed. Improved Pattern, with Perforated Copper Dome, for dirty work.



PRICE, Japanned, 6s. 6d.; Nickel-Plated, 8s. 6d.

Will do any work of the smallest kind, or melt a hundredweight of Lead in an Iron Pot. Will boil 2 quarts of Water in a Flat Copper Kettle in 6 minutes.

‡ Smaller size, for general use, with a poor Gas supply, slightly under half the power.



Japanned, 4s.; Nickel-Plated, 5s. 6d.

Illustrated List of Gas Apparatus for domestic use (Cooking, &c.), free by post.

Illustrated List of Gas and Petroleum Heating Apparatus for Laboratory use. Furnaces, Foot and Automatic Blowers, Hot and Cold Blast Blowpipes, Ingot Moulds, &c., Price 2*d.*

THOS. FLETCHER,

4 & 6, *MUSEUM STREET, WARRINGTON.*

EAGLE INSURANCE COMPANY.

79, PALL MALL.

FOR LIVES ONLY. ESTABLISHED 1807

Accumulated Funds ... £3,043,548
Also a Subscribed Capital of more than ... £1,500,000

Reports, Prospectuses, and Forms may be had at the Office, or from any of the Company's Agents, post free.

GEORGE HUMPHREYS, Actuary and Secretary.

THIN GLASS FOR MICROSCOPIC

MOUNTING, of best quality. Circles, 3*s.* 6*d.* per ounce: Squares, 2*s.* 9*d.*; post free 2*d.* extra; Ground edged Slips, 5*s.* per gross; also other Mounting Materials and Objects prepared for mounting. CHAS. PETIT, 151, High Street, Stok Newington, N.

BROKEN!!

DAVY'S DIAMOND CEMENT

SECURELY AND NEATLY MENDS

CHINA, GLASS,

CABINET WORK,

AND

FANCY ARTICLES.

Of all Chemists in 1*s.* Bottles.

See the name "E. DAVY," the Original Inventor, is on the Label, and also that of

BARCLAY & SONS, 95, Farringdon Street, London.

MUSEUMS AND COLLECTORS.

MR. DAMON, of WEYMOUTH, will forward an abridged Catalogue of his Collections in Natural History Objects, including RECENT SHELLS (Foreign and British), FOSSIL REMAINS, MINERALS, ROCKS, MARINE ZOOLOGY, &c., &c., &c.

"NATURE," Nov. 14, 1878, No. 472.—One Shilling each will be paid for Copies of this number.—Address Publishers of NATURE, 29, Bedford Street, Strand, W.C.

MICROSCOPIC SPECIALITIES.

Series	I.—24 Medical Pathological Preparations, in Case	£2	2	0
,,	II.—24 Physiological Preparations, in Case	2	2	0
,,	III.—24 Educational ,, ,,	2	2	0
,,	IV.—48 Physiological ,, ,,	4	4	0
Series	V.—24 Preparations from the Frog, in Case	£2	2	0
,,	VI.—24 Surgical Pathological Preparations	2	2	0
,,	A.—48 Diatomaceæ (selected)	2	10	0
,,	B.—24 ,, (very rare)	1	11	6

Pathological and Physiological Preparations in great and constantly increasing variety, and of most valuable descriptions. 15*s.* to 30*s.* per doz.

Descriptive Lists and full particulars on application to

ARTHUR C. COLE & SON,

ST. DOMINGO HOUSE, OXFORD GARDENS, NOTTING HILL, LONDON, W.

LATE OF 62, ST. DOMINGO VALE, EVERTON, LIVERPOOL.

In medium 8vo, price 18s., Vol. I.

A TEXT-BOOK OF THE

PHYSIOLOGICAL CHEMISTRY OF THE ANIMAL BODY,

INCLUDING

AN ACCOUNT OF THE CHEMICAL CHANGES OCCURRING IN DISEASE.

By ARTHUR GAMGEE, M.D., F.R.S.,

Professor of Physiology in the Victoria University, the Owens College, Manchester.

LONDON: MACMILLAN AND CO.

This work, of which the first volume is now published, and of which the second and concluding volume will be published in 1881, aims at giving a more complete account of the present state of physiological and pathological chemistry than is to be found in any of the existing text-books. The special features of the work are the following:—

First.—Physiological Chemistry is treated of from the points of view of the physiologist and physician rather than from that of the pure chemist, although no chemical fact and even no chemical speculation is omitted which appears to throw any light upon a biological question. The classification adopted is, however, based upon physiological and pathological rather than chemical considerations.

Secondly.—It has been sought to combine a thoroughly systematic treatment of each subject with a full description of those methods of research which have in the past proved of the greatest value to the investigator. In the pursuit of this aim, detailed accounts are given of methods which have, in many cases, hitherto been only incidentally referred to by the systematic writer. It seemed the most important to do this in a work intended for the scientific worker, anxious not merely to learn what had been already acquired to science, but wishful himself to extend her boundaries. Methods of analysis are described with great care, so as to render the work a trustworthy laboratory guide for the student of physiological chemistry and the practical physician.

Thirdly.—The history of each subject treated of is dwelt upon with great thoroughness, a detailed account of all epoch-making researches being given, and the full titles of nearly all papers quoted being given.

Fourthly.—The work is copiously illustrated, the illustrations being in many cases original.

Fifthly.—Whereas in the first volume the chemical composition of and the chemical processes connected with the elementary tissues of the organism are mainly dwelt upon, the second volume will deal with the chemical history of the complex animal processes.

With Illustrations and Maps, medium 8vo, 18*s*.

ISLAND LIFE:

OR, THE PHENOMENA AND CAUSES OF INSULAR FAUNAS AND FLORAS, INCLUDING A REVISION AND ATTEMPTED SOLUTION OF THE PROBLEM OF GEOLOGICAL CLIMATES. By ALFRED RUSSEL WALLACE, Author of "The Malay Archipelago," "The Geographical Distribution of Animals," &c.

"Mr. Wallace has long devoted himself to these problems of geographical distribution; and his new volume gives us the cream of his latest thinking in a pleasant and eminently readable form. No other living naturalist has the same union of high literary excellence with profound scientific knowledge. His wonderful grasp of detail, depth of insight, and breadth of view remind one at every turn of Darwin, with whom he shares the honours of discovery in the theory of natural selection; but beyond this he has a lightness of touch, a beauty of style, and an ingenuity in unravelling intricate difficulties which are all his own. . . . 'Island Life' is a work to be accepted almost without reservation from beginning to end. . . . Whoever reads his book must be charmed with it."—*St. James's Gazette.*

"The present volume, though in some respects intended as a popularisation of Mr. Wallace's previous works on the distribution of animals, yet contains an immense amount of new and important matter for the man of science, as well as much delightful reading for the less instructed public. It is, in fact, the final outcome of the author's most mature thought and research on the special subject which he has made most peculiarly his own. . . . The work throughout abounds with interest. . . . It may be read with equal pleasure by those who are already acquainted with the general principles of distribution and by those who wish for the first time to learn something about modern biological geography."—*Athenæum.*

"We have said enough to show that Mr. Wallace is led to discuss subjects of great interest to speculative minds. With its numerous special maps 'Island Life' ought to prove as interesting as it is instructive."—*Pall Mall Gazette.*

"Four years additional thought and research upon the lines laid down in that suggestive work 'The Geographical Distribution of Animals,' have brought to a conclusion the general scheme of inquiry which he from the first proposed to himself, and he now propounds, as a clear and definite theory, the results of investigations which might at first sight appear fragmentary and disconnected. Mr. Wallace has entitled himself to be called the father of the new science of zoological geography, showing that we have in the present distribution of living things over the earth's surface a key to the problems of the most ancient relations of land and water. . . . Mr. Wallace's survey of the widely-separated island system of the globe sets upon a solid basis his views of the wonderful powers of dispersion and modificati .a existing in the organic world. . . . In his theory of local geographical changes modifying the general stability of continents we have perhaps a key to the most difficult and complex problems involved in the phenomena of the variation and distribution of living forms."—*Saturday Review.*

MACMILLAN AND CO., LONDON.

In Medium 8vo, price 18*s*. Vol. I.

A TREATISE ON

COMPARATIVE EMBRYOLOGY.

By F. M. BALFOUR, M.A., F.R.S., Fellow and Lecturer of Trinity College, Cambridge. In Two Vols. Illustrated.

"It is scarcely possible to exaggerate the expressions of gratitude which are due from zoologists to Mr. Balfour for the execution of the great task which some three or four years ago he set himself. . . . Zoologists have to be thankful to him for the admirable style in which he has carried out his work."—*Nature.*

MACMILLAN AND CO., LONDON.

Messrs. MACMILLAN & CO.'S PUBLICATIONS.

NEW BOOKS ON IRELAND.

New Views on Ireland, or Irish Land Grievances and Remedies. By CHARLES RUSSELL, Q.C., M.P. Crown 8vo, cloth, 2*s.* 6*d.*

"This should be studied by every one who desires to understand the existing crisis in Ireland."—*Spectator.*

The Life's Work in Ireland of a Landlord who Tried to do his DUTY. By W. BENCE JONES of Lisselan. Crown 8vo, 6*s.*

"Mr. Bence Jones has written an interesting and instructive little book; but not the least enlightening part of it is the Preface, dated December 12th, 1880. He had just been threatened with Boycotting, which he now undergoes."—*St. James's Gazette.*

The Irish Land Laws. By *Alexander G. Richey, Q.C., LL.D.,* Deputy Regius Professor of Feudal and English Law in the University of Dublin. Crown 8vo. 3*s.* 6*d.*

"To all who, either as legislators or publicists, are called on to take part in the present controversy, the book will prove invaluable. . . . We can recommend this little book to all who speak, write, or seriously think upon this question in or out of Parliament."—*Times.*

"This book cannot fail to do good. . . . Mr. Richey writes throughout fairly, and in no partisan or controversial spirit, and his book is a contribution of great value to the discussion in which we now find ourselves involved."—*St. James's Gazette.*

LIFE OF WILLIAM BLAKE. With Selections from his Poems and other Writings. Illustrated from BLAKE's own Works. By ALEXANDER GILCHRIST. A New and Enlarged Edition, with Additional Letters and a Memoir of the Author. 2 vols. Printed on hand-made paper, the Illustrations on India paper, and mounted in the text. Cloth elegant, gilt, with designs after BLAKE by FREDK. J. SHIELDS. Medium 8vo. 42*s.*

"One of the most beautiful and interesting books of the season.....Thus Blake, more than Thoreau, and infinitely more than Rousseau, is a shining example of a man who chose and secured a simple and sufficient measure of happiness. There is no higher philosophy."—*Daily News.*

GOLDEN TREASURY SERIES.—NEW VOLUME.

ESSAYS OF JOSEPH ADDISON. Chosen and Edited by JOHN RICHARD GREEN, M.A., LL.D. 18mo. 4*s.* 6*d.*

DICTIONARY OF MUSIC AND MUSICIANS (A.D. 1450—1878). By eminent Writers, English and Foreign. Edited by GEORGE GROVE, D.C.L. Three Vols., 8vo, with Illustrations and Woodcuts. Parts I. to XII. each 3*s.* 6*d.* Vols. I. and II., 8vo, cloth, each 21*s.*

Vol. I. A to Impromptu. Vol. II. Improperia to Plain Song.

"This work promises to be for music what the best encyclopædias are to general literature and science."—*Guardian.*

ENGLISH POETS: Selections, with Critical Introductions by various Writers, and a General Introduction by MATTHEW ARNOLD. Edited by T. H. WARD, M.A. 4 vols., crown 8vo, each 7*s.* 6*d.*

Vol. I. CHAUCER to DONNE.
Vol. II. BEN JONSON to DRYDEN.
Vol. III. ADDISON to BLAKE.
Vol. IV. WORDSWORTH to SYDNEY DOBELL.

"An excellent design admirably executed."—*Pall Mall Gazette.*

ENGLISH MEN OF LETTERS. Edited by JOHN MORLEY. Crown 8vo. 2*s.* 6*d.* (New Volume.)

WORDSWORTH. By F. W. H. MYERS.

"Mr. Myers gives us a picture of the man and an estimate of his work which is certainly not inferior to anything that has preceded it."—*Academy.*

THE YEAR'S ART: A Concise Epitome of all matters relating to the Arts of PAINTING, SCULPTURE, and ARCHITECTURE, which have occurred during the Year, together with information respecting the events of the Year 1881. Compiled by MARCUS B. HUISH. Crown 8vo. 2*s.* 6*d.*

THE ABBOTT'S FARM; or, Practice with Science. By HENRY TANNER, M.R.A.C., F.C.S., Professor of the Principles of Agriculture in the Royal Agricultural College, Author of "First Principles of Agriculture." Extra fcap. 3*s.* 6*d.*

ISLAND LIFE; or, the Phenomena and Causes of Insular Faunas and Floras, including a revision and attempted solution of the Problem of Geological Climates. By ALFRED RUSSEL WALLACE, Author of "The Malay Archipelago," "The Geographical Distribution of Animals," &c. Medium 8vo, with Illustrations and Maps. 18*s.*

"The work throughout abounds with interest."—*Athenæum.*

"He takes his subject matter from all the sciences, and he builds it into a new harmonious whole."—*Fortnightly Review.*

GILBERT WHITE'S NATURAL HISTORY AND ANTIQUITIES OF SELBORNE. New Edition, with a Poem and Letters never before published. Edited, with Notes and Memoir, by FRANK BUCKLAND; a chapter on Antiquities by Lord SELBORNE; and the Garden Kalendar. With Illustrations by Prof DELAMOTTE. Cheap Edition. Crown 8vo. 6*s.*

PHYSICS OF THE EARTH'S CRUST. By Rev. O. FISHER, M.A., F.G.S., Rector of Harlton, &c. 8vo. [*Shortly.*

STUDIES IN DEDUCTIVE LOGIC. By W. STANLEY JEVONS, LL.D., M.A., F.R.S. Crown 8vo. 6*s.*

"It is indispensable to the many students of the higher logic."—*Athenæum.*

GUIDE TO THE STUDY OF POLITICAL ECONOMY. By Dr. LUIGI COSSA, Professor of Political Economy in the University of Pavia. Translated from the Second Italian Edition. With a Preface by W. STANLEY JEVONS, F.R.S. Crown 8vo. 4*s.* 6*d.*

"It would be impossible to find a more compact and better-written sketch of the history of Political Economy and its latest developments. . . It is an admirable compendium, and will, we hope, be widely circulated, as it will prove to many for the first time that the study of political economy is even more actively pursued on the Continent, than in England."—*Notes and Queries.*

MACMILLAN & CO., LONDON.

Printed by R. CLAY, SONS, AND TAYLOR, at 7 and 8, Bread Street Hill, Queen Victoria Street, in the City of London, and published by MACMILLAN AND CO., at the Office, 29 and 30, Bedford Street, Covent Garden.—THURSDAY, January 1881.

NATURE

A WEEKLY ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
Of Nature trusts the mind which builds for aye."—WORDSWORTH

No. 585, Vol. 23] THURSDAY, JANUARY 13, 1881 [Price Sixpence

Registered as a Newspaper at the General Post Office.]

[All Rights are Reserved.

ROYAL INSTITUTION OF GREAT BRITAIN,

ALBEMARLE STREET, PICCADILLY, W.

CHANGES IN THE LECTURE ARRANGEMENTS.

Prof. EDWARD A. SCHÄFER, F.R.S.—First of Eleven Lectures on The Blood, on Tuesday, January 25 (instead of Tuesday, January 18), at 3 p.m. One Guinea the Course.

FRANCIS HUEFFER, Esq.—First of Four Lectures on The Troubadours, on Thursday, January 27 (instead of Thursday, January 20), at 3 p.m. Half-a-Guinea.

SIDNEY COLVIN, Esq., Slade Professor of Fine Art, Cambridge.—First of Four Lectures on The Amazons, a Chapter in the Study of Greek Art and Mythology, on Saturday, January 29 (instead of Saturday, January 22), at 3 p.m. Half-a-Guinea.

Subscription for all the Courses in the Season, Two Guineas.

Friday, January 21st, 8 p.m.—WARREN DE LA RUE, Esq., D.C.L., F.R.S., Sec. R.I., The Phenomena of the Electric Discharge with 14,400 Chloride of Silver Cells, 9 p.m.

To the Friday Evening Meetings Members and their Friends only are admitted.

ROYAL SCHOOL OF MINES.

Dr. FRANKLAND, D.C.L., F.R.S., will commence a Course of Thirty Lectures on Organic Chemistry at the Science Schools, South Kensington, on MONDAY next, the 17th inst., at 12 at noon, to be continued on each succeeding Wednesday, Friday, and Monday at the same hour. Fee, £3; or to those who have attended the Inorganic Course, £2.

F. W. RUDLER, Registrar.

Microscopes and other Scientific Apparatus

C. BAKER,

244 & 245, HIGH HOLBORN,

Begs to call the attention of the Scientific to his Extensive Stock of Instruments at the lowest possible prices, *viz.*:—

ACHROMATIC MICROSCOPES: the Largest Assortment in London can be selected from, from £3 3s.
ASTRONOMICAL TELESCOPES from £5 5s.
FIELD GLASSES in Leather Sling Cases, from 20s.
OPERA GLASSES in Ivory, Leather, Metal, &c., from 12s. 6d.
GOLD SPECTACLES of every kind from 15s.
THE BEST LONDON-MADE PEBBLES IN STEEL FRAMES, 10s. 6d.
PLAIN STEEL DITTO, from 3s. 6d.
FOLDING HAND SPECTACLES IN TORTOISESHELL, STEEL, &c., from 3s. 6d.
DISSOLVING VIEW APPARATUS, complete from £6 10s.
MAGIC LANTERNS, from 6s. 6d.; Slides, all kinds, from 1s. 3d.

CATALOGUES FREE BY POST.

Second Hand Scientific Instruments.

C. BAKER'S new Catalogue of Scientific Instruments is now out; Selections can be made from a very large stock, comprising Microscopes, Astronomical Telescopes, Transit Instruments, Regulators, Spectroscopes, Meteorological and Electrical Apparatus, Dissolving Views, &c. All at the very lowest prices.

Catalogues of same Free by Post *Instruments taken in exchange.*"
Established 1765.

BROWNING'S ASTRONOMICAL TELESCOPES.

Reduced List of Prices of these Telescopes Free.

The EDUCATIONAL REFLECTING TELESCOPE, with Silvered Glass Mirror 4½ in. diameter, 5 ft. focus, Mounted on a Parallactic Stand for following the Heavenly Bodies with one Motion by means of an endless Driving-screw and Hook's Joint, with Two Eyepieces.

PRICE £22 0s. 0d.

Powers can be used up to 400 diameters on many Stars with advantage.

JOHN BROWNING,

OPTICAL AND PHYSICAL INSTRUMENT MAKER TO H.M. GOVERNMENT.

63, STRAND, LONDON, W.C.

Microscopes, Spectroscopes, Spectacles, &c., &c.

STANDARD METEOROLOGICAL INSTRUMENTS



Now ready, a New Edition of Negretti & Zambra's Encyclopædic Catalogue of Mathematical, Philosophical, Optical, and Standard Meteorological Instruments, containing numerous Comparative Tables of Reference, and Illustrated by Twelve Hundred Engravings.
Royal 8vo, cloth, gilt lettered, price 5s. 6d.

NEGRETTI & ZAMBRA,

Opticians and Scientific Instrument Makers

To Her Majesty the Queen,

HOLBORN VIADUCT,

45, CORNHILL, & 122, REGENT STREET, LONDON.

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 48N, Tollington Road, Holloway, London, N.

ROYAL AGRICULTURAL COLLEGE, CIRENCESTER.

PROFESSORSHIP OF GENERAL AND AGRICULTURAL CHEMISTRY.

This Chair will be VACANT in MAY. Gentlemen duly qualified, especially in Agricultural Chemistry and Chemico-Agricultural Work, are invited to become Candidates. Salary, £400 with one Assistant, or £300 with two, without Board and Residence. Excellent Laboratory. Facilities for Private Work. The new Professor to enter on duties May 30th. Testimonials, &c., to be forwarded to the PRINCIPAL on or before Saturday, March 5th.

KING'S COLLEGE, LONDON.

Prof. W. G. ADAMS will deliver a Course of Lectures on Voltaic Electricity and Magnetism and their Applications to Cable-testing, Electric-lighting, &c., on Thursdays, beginning THURSDAY, January 20th, at 2 p.m.

For further particulars apply to

J. W. CUNNINGHAM, Secretary.

ROYAL ASIATIC SOCIETY,

MONDAY, JANUARY 24, 1881.

A Paper will be read by W. SIMPSON, Esq., F.R.G.S., "On the Identification of Nagara-hara in the Jellalabad Valley, with reference to the Travels of Hionen-Tsang."

W. S. W. VAUX, Sec. R.A.S.

PRELIMINARY SCIENTIFIC EXAMINATION.—UNIVERSITY OF LONDON.

A Class in all the Subjects (including Practical Work) for this Examination is held at St. Bartholomew's Hospital, continuing till the Examination in July. The Class is open to Candidates who are not Students of the Hospital, as well as to Students, and will begin on TUESDAY, January 18th.

Botany—Rev. G. Henslow, M.A., Christ's Coll., Camb., Lecturer on Botany to the Hospital.
Zoology—Norman Moore, M.D. St. Cath. Coll., Camb., Lecturer on Comparative Anatomy to the Hospital.
Chemistry—H. E. Armstrong, Ph.D., F.R.S., Demonstrator of Chemistry.
Physics—Donald McAlister, B.A., Fellow of St. John's Coll., Camb., Demonstrator of Physics.

Fee for the whole Course (including Chemicals) to Students of the Hospital, £8 8s.; to others, £10 10s.

Particulars may be ascertained on application, personally or by letter, to the WARDEN of the College, St. Bartholomew's Hospital, E.C. A Handbook forwarded on application.

UNIVERSITY OF LONDON.

PRELIMINARY SCIENTIFIC AND 1ST M.B. EXAMINATIONS.

Special Classes in all the Subjects required for these Examinations will commence at St. Thomas's Hospital Medical School early in JANUARY. Full particulars may be obtained from the Secretary, Dr. GILLESPIE.

SAINT PAUL'S SCHOOLS. —About 12

Scholarships will be awarded next Term.—For information, address CLERK TO GOVERNORS, Mercers' Hall, E.C.

CHEMICAL & PHYSICAL RESEARCH.

—A Gentleman or Youth, desirous of pursuing it, may communicate with X., care of H. M. Chichester, 97, Belgrave Road, S.W.

INSTRUCTION IN MATHEMATICS.—

Youths or Adults attended at their Residence, on Reasonable Terms, by a M.A. of Cambridge. Unquestionable references if required.—Address, by letter, O. P., Post Office, Turnham Green.

ROYAL POLYTECHNIC.—CLASSES for

the preparation of Students for University Examinations, under the direction of EDWARD B. AVELING, D.Sc., F.L.S. London University Matriculation, 1st and 2nd B.Sc., Preliminary Scientific M.B., Botany, Physiology, Chemistry. All the work practical.

GEOLOGY.—In the Preface to the STU-

DENT'S ELEMENTS of GEOLOGY, by Lyell, 1874, he says: "As it is impossible to enable the reader to recognise rocks and minerals at sight by aid of verbal descriptions or figures, he will do well to obtain a well-arranged collection of specimens, such as may be procured from Mr. TENNANT (149, Strand), Teacher of Mineralogy at King's College, London." These Collections are supplied on the following terms, in plain Mahogany Cabinets:—

100 Specimens, in Cabinet, with 3 Trays	£2	2	0
200 Specimens, in Cabinet, with 5 Trays	5	5	0
300 Specimens, in Cabinet, with 9 Drawers	10	10	0
400 Specimens, in Cabinet, with 13 Drawers	21	0	0

More extensive Collections at 50 to 5,000 Guineas each.

LIVING SPECIMENS FOR THE MICROSCOPE.

THOMAS BOLTON, NATURALISTS' and MICROSCOPISTS' STUDIO, 17, ANN STREET, BIRMINGHAM.

T. B. has last week sent to his subscribers the Infusorian, *Bursaria truncatella*, with drawing and description. He has also sent out the Fairy Shrimp, *Chirocephalus diaphanus*, *Diaptomus castor*, *Asellus vulgaris*, *Stephanoceros Eichhornii*.

Weekly announcements will be made in this place of organisms T. B. is supplying.

Specimen Tube, One Shilling, post-free.

Twenty-six Tubes in course of Six Months for Subscription of £1 1s.

Price List of Specimens on application, with stamped addressed envelope.

Portfolio of Drawings, No. 3, One Shilling.

MINERALOGY AND GEOLOGY.

FINE CRYSTALLISED DANBURITES, the first Specimens received in England.
MAGNIFICENT CRYSTAL of MATLOCKITE from Derbyshire.
VERY BRILLIANT and FINELY CRYSTALLISED AUGITE, from Sweden.
VERY LARGE and FINE CRYSTALS of LIBETHENITE, CHALCOSIDERITE, CUPRITE, LIROCONITE, CASSITERITE, BISMUTHINE, HENWOODITE.
COLLECTIONS FOR STUDENTS, from £2 2s. COLLECTIONS FOR BEGINNERS, from 4s. BLOWPIPE CASES AND APPARATUS.

PRIVATE LESSONS AND EVENING CLASSES.

Catalogues free.

SAMUEL HENSON,
277 (*Late* 113*a*), STRAND, LONDON, W.C.

CHRISTMAS PRESENTS.—The Popular

SCIENTIFIC POCKET CABINET SERIES. (SECOND EDITION.)

20 Specimens of Rocks, Fossils, and Minerals to illustrate Prof. Geikie's Geology Primer.

25 Minerals, Rocks, and Fossils to illustrate Bonney's Geology.

25 British Rocks. 25 British Fossils. 25 Earthy Minerals. 25 Metalliferous Minerals. 25 Metals and Alloys. 25 Recent Shells. 20 Rough Gems and Stones.

Each Collection complete in itself, price 2s. 6d.

*** The Specimens are sufficiently large for recognition of the Species, and are contained in Small Cabinets suitably adapted for carrying in the Pocket.

THOMAS J. DOWNING, Geologist, &c., 38, WHISKIN STREET, LONDON, E.C. N.B.—Post Office Order or Cheque must invariably accompany all Orders, with an additional Fourpence on each set for free delivery.

ROCK SECTIONS & ROCK SPECIMENS.

Collections of Rock Specimens to illustrate Rutley's "Study of Rocks" specially prepared. 100 Small Specimens in Cabinet, One Guinea; 200 Specimens, Two Guineas. Extensive and choice Series of Rocks for selection. New List of Sections of Rocks for Microscope, and List of Collections, &c.

JAMES R. GREGORY'S
Extensive New Museum and Show Rooms,
88, CHARLOTTE STREET, FITZROY SQUARE.

DIAMONDS IN MATRIX.

R. C. NOCKOLD, Diamond and Oriental Stone Cutter and Dealer, has for sale Specimens of the above; also Cut Precious Stones in all Colours.

Precious Stones valued and bought.

12, FRITH STREET, SOHO, W.

THIN GLASS FOR MICROSCOPIC

MOUNTING, of best quality. Circles, 3s. 6d. per ounce; Squares, 2s. 9d.; post free 2d. extra; Ground edged Slips, 5s. per gross; also other Mounting Materials and Objects prepared for mounting.—CHAS. PETIT, 151, High Street, Stoke Newington, N.

NORTH BRITISH AGRICULTURIST

is the only Agricultural Journal in Scotland, and circulates extensively amongst Landed Proprietors, Factors, Farmers, Farm-bailiffs, and others interested in the management of landed property throughout Scotland and the Northern Counties of England.

The AGRICULTURIST has also a very considerable circulation on the Continent of Europe, America, Australia, and the Colonies.

The AGRICULTURIST is published every Wednesday afternoon in time for the evening mails, and contains Reports of all the principal British and Irish Markets of the week, besides Telegraphic Reports of those held on the day of publication.

The Veterinary Department is edited by one of the leading Veterinarians in the country, and is invaluable to the breeder and feeder as a guide to the rearing of animals, and their treatment when labouring under disease.

Full Reports are given of the Meetings of the Royal Agricultural Society of England, the Royal Agricultural Society of Ireland, the Highland and Agricultural Society of Scotland, the Scottish Chamber of Agriculture, and all the principal Agricultural Associations throughout Great Britain and Ireland.

For Advertisers addressing themselves to Farmers a better medium does not exist

Price 3d. By post 3½d. Annual Subscription, payable in advance, 14s.

Office—377, High Street, Edinburgh.

Post-Office Orders payable to Charles Anderson, Jun., Edinburgh.

ESTABLISHED 1843.

Sale by Auction.

Natural History Specimens and Books.

MR. J. C. STEVENS will Sell by Auction, at his Great Rooms, 38, King Street, Covent Garden, on FRIDAY, January 14, at half-past 12 precisely, a Collection of Shells found in the Mauritius, a fine assortment of Corals, rare Fish, Echini, Star Fish, &c., from the same locality. The Collection of Shells formed by Dr. F. Farrer. Minerals, Fossils, Crustacea, Shells, Botanical Specimens, Diagrams, Cabinets, &c., the property of the late C. Johnson, Esq., who was for many years Professor of Botany at Guy's Hospital. Animal Skulls and Skins, Rare Birds from New Guinea, Exotic Butterflies, and various other Natural History Specimens, and about 60 Lots of Scientific Books.

On view after 2 o'clock the day prior and morning of Sale, and Catalogues had.

On the 1st of every Month, price Sixpence.

THE ENTOMOLOGIST:

AN ILLUSTRATED JOURNAL OF BRITISH ENTOMOLOGY.

Edited by JOHN T. CARRINGTON,

With the Assistance of

FREDERICK BOND, F.Z.S. | JOHN A. POWER, M.D.
EDWARD A. FITCH, F.L.S. | J. JENNER WEIR, F.L.S.
F. BUCHANAN WHITE, M.D.

Contains Articles by well-known Entomologists on all branches of the Science; on Insects injurious or beneficial to Farm or Garden; Notes on Habits, Life-Histories; occurrence of Rarities, &c.; there are monthly lists of Duplicates and Desiderata.

Numerous WOODCUT ILLUSTRATIONS, to the printing of which especial attention is given, and occasional LITHOGRAPHED and CHROMO-LITHOGRAPHED PLATES.

SIMPKIN, MARSHALL, & CO., Stationers' Hall Court.

"The leading Farmers' paper."—CLARE SEWELL READ, ESQ., M.P.

THE CHAMBER OF AGRICULTURE JOURNAL

AND FARMERS' CHRONICLE

(PRICE 3*d.* WEEKLY).

The representative organ of the Central and Provincial Chambers of Agriculture; *gives fuller reports of the discussions and proceedings* of this extensive organisation than any other agricultural paper. It devotes *special attention to the treatment of Agricultural Questions by Parliament*, besides containing ample Reports of the LATEST LONDON and COUNTRY CORN, CATTLE, HOP, PROVISION, and other Markets, with Original Articles on Practical Farming, the Dairy, Herd and Flock News, Horticulture, &c., &c. It is despatched every Monday evening in time for the country post.

Terms of Subscription, payable in advance, post free:—3 months, 3*s.* 9½*d.*; 6 months, 7*s.* 7*d.*; 12 months, 15*s.* 2*d.*

Published by W. PICKERING, 21, Arundel Street, Strand, London, W.C.

On the 1st of every Month.

TRIMEN'S JOURNAL OF BOTANY,

BRITISH AND FOREIGN.

New Series. Edited by JAMES BRITTEN, F.L.S., British Museum.

CONTENTS.—Original Articles by leading Botanists.—Extracts, and Notices of Books and Memoirs.—Articles in Journals.—Botanical News.—Proceedings of Societies

Price 1*s.* 3*d.* Subscription for One Year, payable in advance, 12*s.*

London: WEST, NEWMAN, & CO., 54, Hatton Garden, E.C.

Now ready, Price 6*s.*, Part II., Vol. XV., January, 1881.

THE JOURNAL OF ANATOMY AND PHYSIOLOGY,

NORMAL AND PATHOLOGICAL.

CONDUCTED BY

Profs. HUMPHRY, TURNER, M'KENDRICK, & Dr. CREIGHTON.

Contents.

1. Bones, Articulations, and Muscles of Rudimentary Hind-limb of Greenland Right-Whale. By J. Struthers, M.D. (Plates XIV.–XVII.)
2. Infective Form of Tuberculosis in Man identical with Bovine Tuberculosis. By C. Creighton, M.D.
3. Medullary Neuroma of Brain. By W. Osler, M.D. (Plate XVIII)
4. Dissection of Genito-Urinary Organs in Case of Fissure of Abdominal Walls. By A. Doran, F.R.C.S. (Plate XIX.)
5. Description of a Polygraph (with Figure). By D. Newman, M.B.
6. Remarks on Mechanism of Secretion of Sweat. By C. Handfield Jones, M.B.
7. Anomalous Growth-Bearing Pilose Skin in Pharynx of a Young Woman. By P. S. Abraham, M.A. (With Figure.)
8. Histology of Granular Kidney (with Figure). By R. Saundby, M.D.
9. Two Cases of Cerebellar Disease. By T. Oliver, M.D.
10. Colouring Matter of Jelly Fishes. By Prof. M'Kendrick.
11. Nerves of the Hind-Limb of the Thylacine and Cuscus. By D. J. Cunningham, M.D.
12. Pulse Dicrotism. By Wm. Jas. Fleming, M.D.
13. Anatomical Notices.

MACMILLAN & CO., London and Cambridge.

THE QUARTERLY REVIEW, No. 301,

Will be Published on SATURDAY, January 15th.

Contents.

I. LORD CAMPBELL'S MEMOIRS.
II. CALIFORNIAN SCENERY AND SOCIETY.
III. LORD BOLINGBROKE IN EXILE
IV. PROTECTION OF BRITISH BIRDS.
V. LORD BEACONSFIELD'S "ENDYMION."
VI. BELIEF AND UNBELIEF.
VII. McCARTHY'S HISTORY OF OUR OWN TIMES.
VIII. EMPLOYMENT OF WOMEN.
IX. THE RITUALISTS AND THE LAW.
X. THE TRUTH ABOUT IRELAND.

JOHN MURRAY, Albemarle Street.

THE NEW BIOLOGICAL JOURNAL.

ARCHIVES DE BIOLOGIE.

Edited by Professors EDOUARD VAN BENEDEN of Liège, and VAN BAMBEKE of Ghent.

This Journal is devoted to the publication of original Memoirs on the Embryology, Histology, Physiology, and Comparative Anatomy of Plants and Animals. Each number is illustrated with numerous Coloured Plates, and appears at the commencement of the Quarter.

Price:—A Single Number, Six Shillings and Sixpence. Annual Subscription: Twenty-five Shillings, or Twenty-seven Shillings post free.

Orders received by Messrs. WILLIAMS & NORGATE, 14, Henrietta Street, Covent Garden, London.

In the first two numbers have appeared:—

VAN BENEDEN: On the Embryology of the Mammalia.
VAN BAMBEKE: On the Cleavage of the Egg in Batrachia.
FOL HINGER: On the Termination of Nerves in the Muscles of Insects.
FREDERIQUE AND VANDEVELDE: On the Physiology of the Muscles and Nerves of the Lobster.
MACLEOD: On the Harderian Gland of the Duck, &c., &c.

Chaque Samedi 16 pages grand in-8°, 2 colonnes

REVUE HEBDOMADAIRE

Scientifique, illustrée, spéciale, seul journal tenant les lecteurs au courant de tous les détails de l'Exposition universelle d'électricité, organe indépendant des exposants

RÉDACTEUR EN CHEF : **W. de FONVIELLE**

E. de CLISSON : DIRECTEUR

Un numéro, **40** *centimes.* — *L'année*, **48** *francs.*
Union postale **20** *francs.*

PARIS, 16, rue du Croissant, PARIS

Envoi de numéros spécimens gratis sur demande

THE ENTOMOLOGIST'S MONTHLY MAGAZINE.

Price Sixpence, Monthly, 24 pages 8vo, with occasional Illustrations.

Conducted by J. W. DOUGLAS, R. MCLACHLAN, F.R.S., E. C. RYE, F.Z.S. and H. T. STAINTON, F.R.S.

This Magazine, commenced in 1864, contains standard articles and notes on all subjects connected with Entomology, and especially on the Insects of the British Isles.

Subscription—Six Shillings per Volume, post free. The volumes commence with the June number in each year.

Vols. I. to V. (strongly bound in cloth) may be obtained by purchasers of the entire set to date, at the increased price of 10*s.* each; the succeeding vols. may be had separately or together, at 7*s.* each.

London: JOHN VAN VOORST, 1, Paternoster Row

N.B.—Communications, &c., should be sent to the Editors at the above address.

On the 1st of every Month, price One Shilling.

THE ZOOLOGIST:

A MONTHLY MAGAZINE OF NATURAL HISTORY.

Third Series. Edited by J. E. HARTING, F.L.S., F.Z.S., Member of the British Ornithologists' Union; contains—

Original articles by well-known naturalists in every branch of zoology; habits of animals; arrival and departure of migratory birds; occurrence of rare birds; distribution and migration of British fresh-water fish; new or rare marine fish; local aquaria; British reptiles; British land and fresh-water mollusca, with remarks on the haunts and habits of the species; and other matters of general interest to those who delight in natural history. Reports of the Linnean, Zoological, and Entomological Societies. Reviews of natural history books. Occasional translations from foreign zoological journals of important and interesting articles in various branches of zoology. There are occasional woodcuts.

JOHN VAN VOORST, 1, Paternoster Row.

MR. MURRAY'S LIST.

MR. CHARLES DARWIN, ASSISTED BY FRANCIS DARWIN: THE POWER OF MOVEMENT IN PLANTS. With Woodcuts. Crown 8vo. 15s.

MR. H. SEEBOHM: SIBERIA IN EUROPE. A NATURALIST'S VISIT TO THE VALLEY OF THE PETCHORA IN NORTH-EAST RUSSIA. With Notices of Birds and their Migrations. With Map and Illustrations. Crown 8vo. 14s.

MR. CLEMENTS MARKHAM: A POPULAR ACCOUNT OF PERUVIAN BARK, AND ITS INTRODUCTION INTO BRITISH INDIA, CEYLON, &C., AND THE PROGRESS AND EXTENT OF ITS CULTIVATION. With Maps and Woodcuts. Post 8vo. 14s.

MR. A. S. MURRAY: A HISTORY OF GREEK SCULPTURE. From the EARLIEST TIMES down to the AGE of PHEIDIAS. With Illustrations. Royal 8vo. 21s.

MR. F. W. BURBIDGE: GARDENS OF THE SUN; or, a NATURALIST'S JOURNAL ON THE MOUNTAINS AND IN THE FORESTS AND SWAMPS OF BORNEO AND THE SULU ARCHIPELAGO. With Illustrations. Crown 8vo. 14s.

DR. BRUGSCH'S HISTORY OF EGYPT UNDER THE PHARAOHS. DERIVED ENTIRELY FROM THE MONUMENTS. With a MEMOIR on the EXODUS OF THE ISRAELITES and the EGYPTIAN MONUMENTS. *Second Edition, revised.* With New Preface and Notes by the Author. Maps. 2 vols. 8vo. 32s.

DR. SCHLIEMANN'S ILIOS: A COMPLETE HISTORY OF THE CITY AND COUNTRY OF THE TROJANS, including all RECENT DISCOVERIES and RESEARCHES on the site of TROY and the TROAD in 1871-3 and 1878-9. With nearly 2000 Illustrations. Imperial 8vo. 50s.

SIR RICHARD TEMPLE'S INDIA IN 1880. 8vo. 16s.

DR. PERCY'S METALLURGY; THE ART OF EXTRACTING METALS FROM THEIR ORES, and adapting them to various purposes of Manufacture.

SILVER AND GOLD. With Illustrations. 8vo. 30s.

FUEL. With Illustrations. 8vo. 30s.

LEAD. With Illustrations. 8vo. 30s.

MR. BUNBURY'S HISTORY OF ANCIENT GEOGRAPHY AMONG THE GREEKS AND ROMANS, FROM THE EARLIEST AGES TILL THE FALL OF THE ROMAN EMPIRE. Maps. 2 vols. 8vo. 42s.

MR. CRIPPS' OLD FRENCH PLATE. FURNISHING TABLES OF THE PARIS DATE-LETTERS AND FACSIMILES OF OTHER MARKS. A Handbook for the Collector. With Illustrations. 8vo. 8s. 6d.

REV. JOHN RICHARDSON: A SMALLER MANUAL OF MODERN GEOGRAPHY for SCHOOLS and YOUNG PERSONS. Post 8vo.

PROF. LEVI'S HISTORY OF BRITISH COMMERCE, AND THE ECONOMIC PROGRESS OF THE NATION, FROM 1763 TO 1878. *New Edition.* With Diagrams. 8vo. 18s.

DR. SOUTH'S HOUSEHOLD SURGERY; OR, HINTS FOR EMERGENCIES. *Fourth Edition.* With New Preface and Additions. Woodcuts. Fcap. 8vo. 3s. 6d.

JOHN MURRAY, Albemarle Street.

Now ready, post quarto, cloth gilt, 272 pages. Price 1£s.

LIGHTNING

CONDUCTORS:

THEIR

HISTORY, NATURE, AND MODE OF APPLICATION.

By RICHARD ANDERSON, F.C.S., F G.S.,

Member of the Society of Telegraph Engineers; Assoc. Inst. C.E.

With numerous Illustrations.

"The book is one to be commended to the builders of, or dwellers in, lofty houses, to the deans of our cathedrals, to the parsons of churches with lofty spires or towers, and to all owners, constructors, or occupiers of buildings which, from their height or situation, are exposed to danger from lightning."—*The Athenæum.*

"The book is clearly and sensibly written, and sufficiently illustrated, and is the work of a practical man who thoroughly understands what he is talking about."—*The Academy.*

London: E. & F. N. SPON, 46, Charing Cross.

New York: 446, Broome Street. 1880.

Recently Published.

Demy 4to, with 18 Plates (5 printed in Colours), 207 pages, cloth, £2 2s.

AURORÆ:

THEIR CHARACTERS AND SPECTRA.

By J. RAND CAPRON, F R.A.S.

Part I.—THE AURORA AND ITS CHARACTERS
Part II.—THE SPECTRUM OF THE AURORA
Part III.—MAGNETO-ELECTRIC EXPERIMENTS IN CONNECTION WITH THE AURORA.

By the same Author.

Demy 8vo, with 37 Plates, cloth. 30s.

PHOTOGRAPHED SPECTRA.

One Hundred and Thirty-Six Photographs of Metallic, Gaseous, and other Spectra, printed by the Permanent Autotype Process, with Introduction, Description of Plates, and Index, and with an Extra Plate of the Solar Spectrum (showing bright lines) compared with the Air Spectrum.

London: E. & F. N. SPON, 16, Charing Cross

EDITED BY HENRY WATTS, B.A., F.R.S.,

Editor of the *Journal* of the Chemical Society

FOWNES' PHYSICAL and INORGANIC

CHEMISTRY. Twelfth Edition, with Coloured Plate and 154 Engravings, crown 8vo. 8s. 6d.

Also,

FOWNES' CHEMISTRY OF CARBON

COMPOUNDS; or, ORGANIC CHEMISTRY. Twelfth Edition, with Engravings, crown 8vo. 10s.

London: J. & A. CHURCHILL.

THE "HANSA"

Published since 1864 in Hamburg, is the only independent professional paper in Germany, dedicated exclusively to Maritime Objects. Essays, Critiques, Reviews, Reports, Advertisements. Strict eye kept upon the development of Maritime Affairs in every respect. Every second Sunday one Number in 4to at least; frequent supplements and drawings. Subscription at any time; preceding numbers of the year furnished subsequently. Price 12s. for twelve months. Advertisements 4d. a line, widely spread by this paper; considerable abatement for 3, 6, 12 months' insertion. Business Office: Aug. Meyer and Dieckmann, Hamburg, Alterwall 28. Edited by W. v. FREEDEN, M.R., Hamburg, Alexander Street, 8.

THOMAS D. RUSSELL'S

NATURAL HISTORY STORES,

48, ESSEX STREET, STRAND, W.C.

Students and others are invited to inspect the Collections of British and Foreign Shells, Corals, Zoophytes, Annelids, Crustacea, Echinoderms, Minerals, Fossils, Rock Specimens, Microscopic Objects, &c.

Cabinets, Geologist's Hammers, Glass Capped Boxes, Card Trays, Tablets, Glass Slips, Micro-Thin Glass, Canada Balsam, Marine Glue, and other requisites for the Geologist and Microscopist.

Catalogues Post Free.

BRYCE-WRIGHT'S LATEST ARRIVALS.

MINERALS.—Crystallised Hessite, Crystallised Golds, Krennerite, Crystallised Atacamites, Malacone, Enclase, Edingtonite, Suzannite, Chanarcillite, Proustite, &c.

METEORITES.—Specimens of the following Falls:—Wold Cottage, Yorkshire; Java; Orvinio, Italy; Amana, Ohio; Tipperary, Ireland; Java; Orvinio, Italy; Estherville; Hainholz; Grosnagy, Russia; Borkut; Carthago Co.; Bates Co.; Sierra di Chaco; Ashville Co.; Bates Co.; Pallas; Ashville Co., &c., &c.

BRYCE-WRIGHT, F.R.G.S., &c.,

Mineralogist and Expert in Gems and Precious Stones,

90, GREAT RUSSELL STREET, BLOOMSBURY, LONDON, W.C.

THURSDAY, JANUARY 13, 1881

BAROMETRIC CYCLES

ABOUT twelve years ago Mr. Baxendell of Manchester gave evidence of a connection between the convection-currents of the earth and the state of the sun's surface, and the subject has since been much discussed by meteorologists from various points of view.

Amongst these Mr. Meldrum of the Mauritius Observatory has brought forward much evidence in favour of a connection between sun-spots on the one hand and rainfall and cyclones on the other. Still more recently the Indian meteorologists, including the names of Messrs. Archibald, Blanford, Broun, Charles and Frederick Chambers, Eliot, and Hill have studied with much success the abnormal variations of barometric pressure in the tropics. Of these the researches of Mr. F. Chambers are particularly interesting[1] as exhibiting a very close relation between such barometric fluctuations and the state of the sun's surface.

The chief principle underlying these investigations is sufficiently obvious. We know that the marked differences in barometric pressure which exist between various portions of the earth's surface must be due to the sun; if therefore the sun be in reality variable we should naturally expect these differences to vary likewise in such a way as to be strengthened when the sun is most powerful and weakened when he has least influence. In accordance with this way of regarding things, Mr. Chambers in 1876 pointed out that the abnormal variations of the monthly mean barometric pressure at Bombay in that year were mainly variations in the intensity of the usual seasonal movements, while in 1877 he attributed the uniformly high barometric pressure and the deficient rainfall of that year to a weak development of the equatorial belt of minimum pressure, probably induced by a diminution of the solar heat.

In a diagram attached to his first communication Mr. Chambers compares the curve of solar-spotted area with other curves denoting the barometric pressure at various widely-distributed tropical stations, from which we can clearly see that there is a very marked resemblance between the salient points of the various curves on the hypothesis that a large amount of sun-spots corresponds to a low barometer. But besides this it appears that the epochs of maximum and minimum barometric pressure lag considerably behind the corresponding epochs of minimum and maximum solar-spotted area, and that this lagging behind is greater for easterly than for westerly stations, or in other words the abnormal barometric variations in the tropics may be said to travel at a very slow rate round the earth from west to east.

Perhaps the subject of greatest practical importance in these communications is the discussion regarding Indian famines and their connection with sun-spot minima—a connection first brought to light by Dr. Hunter. Mr. Chambers sums up his conclusions on this point as follows:—

1. Variations of the solar-spotted area are succeeded months afterwards by corresponding abnormal barometric variations, a high barometer corresponding to a minimum of sun-spots.

2. Famines follow in the wake of curves of high barometric pressure.

Finally two methods are indicated by which early intimation of the approach of those meteorological disturbances which are attended by famines may possibly be obtained.

1. By regular observation of the solar-spotted area, and early reduction of the observations, so as to obtain early information of current changes going on in the sun.

2. By barometric observations at stations differing widely in longitude and the early communication of the results of stations situated to the westward.

While it thus appears that the evidence in favour of a connection between the state of the sun's surface and the meteorology of the earth is continually acccumulating it may not be amiss to review briefly the present position of the problem.

In the first place Mr. Meldrum, as already mentioned, has given evidence that in numerous stations the rainfall is greater about times of maximum than about times of minimum sun-spot frequency.

Secondly. Through his labours and those of M. Pöey we have reason to believe that there are more cyclones in the Indian Ocean and hurricanes near the West Indies during times of maximum than during times of minimum sun-spot frequency.

Thirdly. There is the connection between the barometric fluctuations of the tropics and the state of the sun's surface which has just been pointed out.

Fourthly. From investigations in which I have been recently engaged there is reason to suppose that sun-spot inequalities of short duration are followed by corresponding inequalities in the diurnal temperature range of Toronto in such a way that a large amount of sun-spots slightly precedes a large temperature range.

Fifthly. To go from meteorology to magnetism there is the well-known connection first observed by Sabine, in virtue of which the diurnal oscillations of the magnet are greatest about times of maximum sun-spots. And I may add that magnetic maxima lag behind sun-spot maxima, while there are also indications that magnetic weather, like meteorological weather, travels from west to east.

We thus perceive how strong the evidence is in favour of some connection between the state of the sun's surface and terrestrial meteorology, while at the same time it is unmistakably indicated by all elements that this connection is of such a nature as to imply that the sun is most powerful when there are most spots on his surface. Add to this that the spectroscopic observations of Lockyer and others tend in the same direction, as well as such actinometric results as we have been able to procure, chiefly through the labours of Mr. J. H. Hennessey at Dehra Dhoon and Mussoorie.

In fine this hypothesis is rapidly emerging, if indeed it has not already emerged, from the regions of mere conjecture.

But here it is necessary to bear in mind the following considerations. Prof. Stokes has pointed out that the problem before us really involves two questions, which may be stated as follows:—Firstly, do the changes which take place in the sun's surface correspond to changes in

[1] See NATURE, November 25 and December 2, 1880.

the meteorology and magnetism of the earth, and if so, does an increase of spotted area denote an increase of solar activity, or the reverse?

This question, I have already remarked, seems to be rapidly emerging from the realms of mere conjecture. But there is still another question, for we have to inquire whether these recognised solar inequalities bear all or any of the marks of a true periodicity. Now this is still *sub judice*, while at the same time it is a point of very great practical importance. For if the solar inequalities be found on investigation to present none of the marks of a true periodicity, we can hardly hope ever to be able to hazard a prediction regarding the state of the sun, and our knowledge of the eleven-yearly period, as it is called, will continue to remain very much the same as at present. But on the other hand, if we find that there are true solar periods and succeed in disentangling them, we may hope to arrive at some measure of predicting power. As I have said, this question is still unsettled, and will of course present itself in different ways to different observers. Meanwhile all we can do is to observe and register the actual state of the sun's surface, and inasmuch as the meteorological occurrences of greatest practical issue do not precede but follow solar phenomena by several months or more, we may thus arrive at a limited amount of practical prevision.

I do not however feel sure that the method of doing this which Mr. Chambers has indicated is in reality the best, for I should imagine that unexceptionable observations of the sun's intrinsic heat-giving power, if these could be obtained, would furnish a more trustworthy instrument of prevision than the sun-spot record.

Then with regard to indirect observations. No doubt those of the barometer are very immediately connected with the occurrences which we wish to foresee, but yet I think it possible that well-selected magnetic observations might ultimately be found to follow more quickly upon solar changes as well as to indicate with a less amount of local influence the true state of the sun.

These however are points that can only be settled by future research. Meanwhile it is extremely gratifying to all who take an interest in this subject to reflect that it is engrossing the attention of observers in all parts of the world.

BALFOUR STEWART

LIFE OF LIVINGSTONE

The Personal Life of David Livingstone, LL.D., D.C.L. Chiefly from his Unpublished Journals and Correspondence in the Possession of his Family. By William Garden Blaikie, D.D., LL.D., New College, Edinburgh. Portrait and Map. (London: Murray, 1880.)

WHEN the news of Livingstone's sad death on the swampy shore of Lake Bangweolo reached this country, and when his body was brought home by his faithful followers to be honoured as the nation honours its greatest and best; and again on the publication of his "Last Journals," we spoke in some detail of the great work he accomplished, and expressed our opinion as to the position which that work had earned for him. The years that have elapsed since Livingstone died at his post have only confirmed the judgment of the nation; and now that Dr. Blaikie's admirably-compiled "Personal Life" enables us to fill up the portrait, it will be seen that the man was as great as his work. Necessarily the missionary and religious side of Livingstone's character and work occupies a large place in this volume; this was to be expected from a writer who is a prominent leader in the Free Church of Scotland. But we do not think there is any excess in this direction; these were genuine and ever-present aspects of the character of the man, and Dr. Blaikie does not give them place at the expense of any other feature. He has honestly endeavoured to give us a complete portrait of his hero, and in this we think he has decidedly succeeded. Simplicity and transparency were marked features in Livingstone's character from first to last; delight in simple joys, a boyish love of fun, tenderness of heart and all-embracing charity, strong natural affection, the yearnings of which he could and did sacrifice to his still stronger sense of duty, the whole dominated by an all-conquering determination and perseverance in accomplishing the work which he believed was "given him to do." This is the impression which Dr. Blaikie's "Personal Life" gives, and in this it only confirms the impression which is conveyed by a study of Livingstone's own narratives.

Dr. Blaikie, however, tells us many things which must be new to most of those who knew Livingstone only through his works. We learn here how well qualified he was for the work which from early years he seems to have set before himself. Livingstone came of a good stock, which, though humble, knew of and had some pride in its ancestry. One ancestor fought at Culloden on the side of Prince Charlie, for on the mother's side he had some Highland blood in his veins. But the impulsive and sad temperament of the Celt was considerably modified by the practical and hopeful features of the Teutonic blood of his father. The latter was a type of the devout, rigidly honest, intelligent, and comparatively well-read, humble Scotchman, while the mother held the love and respect of her son to the end of her life. The family were poor, and all had to work hard; and early in life young Livingstone had to begin to earn his living in a cotton-mill at Blantyre, near Glasgow, where he was born March 19, 1813. With his first wages he bought a copy of Ruddiman's "Latin Rudiments," and thus early, it is evident, his aspirations went beyond the cotton-mill. His hours were long, but while attending to his "jenny," and till late at night, after his day's work was over, he conned his Ruddiman and other books to qualify himself for a University course. His thirst for reading was great, and he devoured all the books that came within his reach. Natural science also had its attractions for him, which he indulged by scouring the country when he had time in search of natural history specimens. Dr. Blaikie tells of Livingstone's "conversion" when he was a young man. This, in his case, means that what was instinctive action became thenceforth settled and conscious purpose. It was doubtless a proud day both for father and son when the former walked with the latter to Glasgow to see him settled in a humble lodging in order that he might attend the classes at Anderson's College. Livingstone never intended to be a clerical missionary; medicine was the subject of his study in Glasgow, and it was as a medical missionary he intended to accomplish the work of his life. It was only to please his friends and the

London Missionary Society he consented to "ordination." Chemistry seems to have been a favourite subject with him at college, and Dr. Blaikie narrates an interesting incident in which Livingstone and James and William (now Sir William) Thomson and Lyon Playfair met together at James Young's (now of Kelly) rooms, to witness some chemical experiment. Having been accepted by the London Missionary Society, Livingstone went to London to complete his medical studies, get some lessons in theology, and learn to preach. His failure in the latter accomplishment nearly led to his final rejection, and no doubt determined the Society to send him to the rough and humble field of Africa, instead of to China, on which his heart was set. The decision must be regarded as in every respect fortunate, though Livingstone had been some time in Africa ere he got over his disappointment. He went out to his work in Africa in 1841, and how anxious he was in every way to qualify himself for that work is shown by the fact that he got the captain of the ship in which he sailed to teach him the use of the quadrant and how to take lunars. With a few more lessons in taking observations from Sir Thomas Maclear at the Cape, he became an adept in this kind of work, and Sir Thomas afterwards expressed his astonishment at the almost perfect accuracy of Livingstone's observations in this department. He left the Cape as soon as he could and made for Moffat's station at Kuruman. Still further north he went, about 250 miles, and settled for some time among the Bechuanas, over whom, as over all other natives with whom he came into contact, he soon acquired great power and influence. His idea of a missionary's work was very practical, and rapidly developed and expanded, after he set foot in Africa. From the first he gave attention to geography, and his early letters are full of geographical details, illustrated by little sketch maps. How early his mind was attracted by the scientific questions connected with the geography of Africa will be seen from the following passage from the work before us:—

"The progress of medical and scientific work during this period is noted in a letter to Dr. Risdon Bennett, dated 30th June, 1843. In addition to full details of the missionary work, this letter enters largely into the state of disease in South Africa, and records some interesting cases, medical and surgical. Still more interesting, perhaps, is the evidence it affords of the place in Livingstone's attention which began to be occupied by three great subjects of which we shall hear much anon—Fever, Tsetse, and 'the Lake.' Fever he considered the greatest barrier to the evangelisation of Africa. Tsetse, an insect like a common fly, destroyed horses and oxen, so that many traders lost literally every ox in their team. As for the Lake, it lay somewhat beyond the outskirts of his new district, and was reported terrible for fever. He heard that Mr. Moffat intended to visit it, but he was somewhat alarmed lest his friend should suffer. It was not Moffat but Livingstone, however, that first braved the risks of that fever swamp.

"A subject of special scientific interest to the missionary during this period was—the desiccation of Africa. On this topic he addressed a long letter to Dr. Buckland in 1843, of which, considerably to his regret, no public notice appears to have been taken, and perhaps the letter never reached him. The substance of this paper may, however, be gathered from a communication subsequently made to the Royal Geographical Society (see *Journal*, vol. xxvii. p. 356) after his first impression had been confirmed by enlarged observation and discovery. Around and north of Kuruman, he had found many indications of a much larger supply of water in a former age. He ascribed the desiccation to the gradual elevation of the western part of the country. He found traces of a very large ancient river which flowed nearly north and south to a large lake, including the bed of the present Orange River; in fact he believed that the whole country south of Lake 'Ngami presented in ancient times very much the same appearance as the basin north of that lake does now, and that the southern lake disappeared when a fissure was made in the ridge through which the Orange River now proceeds to the sea. He could even indicate the spot where the river and the lake met, for some hills there had caused an eddy in which was found a mound of calcareous tufa and travertine, full of fossil bones. These fossils he was most eager to examine, in order to determine the time of the change; but on his first visit he had no time, and when he returned he was suddenly called away to visit a missionary's child, a hundred miles off. It happened that he was never in the same locality again, and had therefore no opportunity to complete his investigation."

It was not likely that a man whose mind was filled with such problems would be content to settle down to the dull routine of the work of a common missionary, and count his success by the tale of doubtful "conversions" he could send home to his constituents. He kept moving onward from one station to another, getting further and further into the interior, gaining the love of the natives and the hatred of the Boers. By his example more than by direct teaching he showed the people the beauty of right living, and taught them many industrial arts which some of them have not lost till this day. But his longing was ever northwards, and his eager desire to solve the mystery of Lake 'Ngami. It was not till 1849 however that he was able to visit the lake, and his account of the visit first brought him permanently into notice as a working geographer. This may be said to have ended the first stage of Livingstone's career, that in which the missionary was predominant. It seems to us, however, doubtful whether Livingstone ever intended definitely to settle down to the life of a missionary. Even from the beginning, we think, he must have had some vague idea of combining the function of missionary and explorer, always, however, with the one great object in view of bringing Africa under the influences of civilisation and Christianity. Shortly after the 'Ngami excursion he became a missionary at large. Returning to Cape Town, he sent home his wife and children, and prepared himself for the great work of exploring the Zambesi. Proceeding northwards to Linyanti in 1852, he set out on that ever memorable journey to Loanda and across the continent to Quilimane, which stamped him as one of the greatest explorers of all time. The story of this and of his subsequent work in the region of Lake Nyassa, and of his many years' wandering all over Central Africa, he has told himself, and Dr. Blaikie wisely refrains from introducing more of it than is really necessary to hold together the narrative of his Personal Life. All that Livingstone has done for Africa it is not easy to estimate. It is he more than any other explorer who has filled up the great white blank in the maps of our schoolboy days. His geographical instinct was surer than that of any other man; only once was it seemingly at fault, when he wandered away by Lake

Bangweolo seeking for the "fountains of the Nile"; and that one mistake cost him his life. Men like Sir Thomas Maclear, Prof. Owen, and Sir Roderick Murchison testify to the high value of his observations in various departments of science; and it is due to his example and initiative that Africa is now covered with an army of explorers. Livingstone was a man who was consumed with a definite and noble purpose, which he firmly believed it was his duty to carry out unto death. In doing so he was bound to give offence, and he did make enemies; and so must every man who is able to conceive a great purpose and possesses strength of will and energy of physique sufficient to carry it out. Had he been weakling enough to be swayed by the scruples of others he would never have left Cape Town. No great work was ever yet accomplished without sacrifice; and we have here mainly to do with the work which Livingstone accomplished for science. That work is the highest of its kind, and had Livingstone been either a Byron or a Napoleon in character, the value of that work would not have been less. Fortunately it is clear from Dr. Blaikie's pages—which consist largely of Livingstone's own journals and letters—what indeed was pretty clear before, that Livingstone was a pure and tender-hearted man, full of humanity and sympathy, simple-minded as a child, with a healthy ambition to do a great work for Africa and for science, and with energy and courage sufficient to carry it out. The motto of his life was the advice he gave to some children he addressed in a humble Scotch meeting-house when he returned from his first great journey and found himself a great man—"Fear God and work hard."

SALVADORI'S ORNITHOLOGY OF NEW GUINEA

Ornitologia della Papuasia e delle Molucche di Tommaso Salvadori. Parte prima. 1 vol. 4to. 540 pp. (Torino, 1880.)

IN the second volume of the Linnean Society's *Journal of Proceedings*, published in 1858, will be found an article by Mr. Sclater on the Birds of New Guinea, which gives in a few pages a summary of the then existing state of our acquaintance with this subject. The bulky quarto now before us, to be followed by three or four other similar volumes, is no bad evidence of the vast mass of additions that has been made to our knowledge of the Papuan avifauna since that period.

In 1857 the only modern authorities on the birds of New Guinea were the naturalists of the French circumnavigating expeditions, who had explored the vicinity of Havre Dorey in the northern peninsula of the island, and the collectors for the Leyden Museum, who had visited Lobo Bay and other points on the south coast. Although much is still wanting to complete our knowledge of the Papuan avifauna, much has been done since those days. In 1858 our famous countryman Mr. Wallace passed some months at Havre Dorey, and made excellent collections in every branch of zoology. Moreover in the neighbouring island of Batchian Mr. Wallace was fortunate enough to come across a new form of paradise bird—one of the few recent additions to this remarkable group—which was deservedly named after its discoverer, *Semioptera wallacii*. Mr. Wallace was also the first of modern explorers to visit the Arroo Islands—which belong strictly to the same fauna as New Guinea, and in his well-known work on his "Travels in the Malay Archipelago" has given us a most interesting account of the habits of the paradise birds as there observed, and of the manner in which the natives procure their specimens.

After Mr. Wallace the Italian travellers D'Albertis and Beccari were the next to visit New Guinea, and succeeded in carrying their investigations further into the unknown interior than it had been hitherto believed possible to penetrate. The ascent of the Arfak Mountains was first accomplished by D'Albertis in 1872, and Beccari succeeded in making the same dangerous journey some years later, besides visiting many localities on the north coast which had not been previously explored. Both these naturalists were active collectors of birds, and transmitted large collections to Europe. In 1875 and the following year D'Albertis turned his attention to the southern portion of New Guinea, and during his excursions up the Fly River made fresh additions to our knowledge of Papuan ornithology. In the meantime a German naturalist, Dr. A. B. Meyer of Dresden, was engaged on new explorations on the shores of the great Bay of Geelvinck, and did not fail to make considerable additions to the rich avifauna of that district.

While Prof. Salvadori has not neglected to consult every existing authority on Papuan ornithology, and, we believe, to visit every European museum which contains specimens from the Papuan region, it is mainly upon the large series accumulated by his countrymen D'Albertis and Beccari, to which must be added the numerous specimens obtained by the hunters of Heer A. A. Bruijn of Ternate, that his present labour is based. These collections, or at any rate all the important portions of them, have passed into the Museo Civico of Genoa, either through the liberality of the Marquis G. Doria, the founder of that institution, or through assistance given by the Italian Government. Their extent may be judged of from the fact, stated in the preface to the present volume, that they contained no less than 9539 specimens, which have thus come directly under Prof. Salvadori's observation, besides the examples examined in the Museums of Paris, London, Leyden, Bremen, Berlin, Dresden, and Vienna, which, as already stated, our author has visited for the purpose of preparing his work. It is evident therefore that materials did not lack, and Prof. Salvadori's well-known abilities as an ornithologist give us every confidence that these materials will have been well used.

Such indeed is doubtless the fact. If the succeeding volumes of the "Ornitologia della Papuasia" shall be executed in the same style as that in which the first volume has been prepared, there can be no question that a most important work will have been accomplished. Not only is every species fully and accurately described, but its complete synonymy is given, a detailed list of the specimens from various localities and remarks on their differences are added, and, in fine, every necessary particular is given that can contribute to a perfect history of the species. Would that other geographical works on ornithology were carried out with equal exactness and similar strict attention to details!

In conclusion we have only to express our thanks to

or the admirable way in which he has
aborious task, and to express our hope
it to a successful conclusion. In Mr.
k on the "Birds of New Guinea" we
nagnificent illustrations of all the more
of Papuan ornithology. Such a work
alvadori's was much wanted in order to
edge of the history and literature of this

UR BOOK SHELF

Treatise on the Integral Calculus, containing Applications to Plane Curves and Surfaces, with Numerous Examples. By B. Williamson, F.R.S. (Longmans, 1880.)

we need only remark that it is a carefully
e second, and point out the few improvements
t have been made. In the discussion
rem (§ 119), a simple shape of the formula
E. B. Elliott, is given, and reference
ides on multiple definite integrals by
ian (and by Mr. Leudesdorf) in the
(1875) and in the *Proceedings* of the
atical Society, 1876-7. A new article
of a simple character, by Zuluaga, of
agrange's series, § 147, contains a re-
n of Bolditch's theorem, due to Mr.
Math., February 1875, and § 147a
rly elegant" theorem discussed by Mr.
Hirchin's letter in Nature of December
he proves these theorems in another
various insertions of a similar character
e by more than twenty pages). A good
ent edition of an index of the curves

...Zeit. Herausgegeben von Dr. H.
Leipzig: Teubner, 1880.)

to record the completion of the first
ible serial of mathematics. The level of
the part of the college and the level of
ing of the public-school teaching to
ed every impediment in the
ublished in the academic series in the
pe, Great Britain, and America) such
been able to judge, the student could be
the great judgment and completeness
also not interfered. Applications
in Just's "Jahrbuch," the Journal
sible to anyone who desires to keep
artment of botanical science.

...ons on Illustrated Flowers. By Dr. H.
...Botany and Flower Lessons. By Dr.
enslow, M.A., F.L.S., &c. (London:
d, 1880.)

hat botany can be taught with pleasure
from books. No method of teaching
ted to the wants of junior students as
tion. A flower pulled to pieces by the
arts and their importance intelligently
eacher forms a lesson far more educative
ot from a text-book. With a few such
ons easily obtained flowers, as the
selves, most of the elementary facts
plants can be readily mastered, while
servation and the facility of dissecting
invaluable to the student. It is well
abit in teaching botany to make the student prepare a lesson from the text-book as if it were spelling or history. This is really what should be most carefully avoided, although there must be a great temptation to proceed with the book lesson when the plant is not obtainable. Mr. Henslow states in his preface: "The descriptions of flowers in this book are intended to form botanical reading-lessons, specimens of the flowers being at the same time placed in the hands of the pupils, who are required to dissect and examine them carefully, and be sure they see and understand each special part noticed in the text." When used in accordance with the directions laid down by the author, the book seems an excellent one, and calculated to serve its purpose well, although some very important types have been omitted for want of space. As we have known children to work out the structure of flowers for themselves by means of this little book and to enjoy the exercise, we believe the work will be deservedly popular. The illustrations are rather coarse, but on the whole characteristic and often give details of structure sometimes omitted from much larger works.

LETTERS TO THE EDITOR

[The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts. No notice is taken of anonymous communications.

The Editor requests that communications may be as short as possible. The pressure on his space is so great that it cannot find room even for extracts from letters, unless they contain information of unusual interest.]

Geological Climates

I am about to proceed to justify my statement, which has caused Mr. Wallace great surprise, viz.:—

"It is impossible to suggest any rearrangement of land and water which shall explain the phenomena of the warmth formerly so widely diffused over the temperate zone of the east of North America."

In order partially to do this I must premise, what the only fact I have to adduce is, that in three years in which I have been experiencing the climate of Scotland, I have had a very considerable [illegible] experiencing the climate of Scotland, I have had a very considerable [illegible] experiencing the climate of Scotland, I have had a very considerable [illegible]

temperature. From this it follows that the temperature of the air at the surface of the sea corresponds with the surface-temperature of the water. This has been fully confirmed by observations made in every latitude, which show that the difference of temperature between the air and sea is never more than one or two degrees Fahrenheit.

(*b*) *Gulf Stream.*—The temperature of the air above the Gulf Stream is:—

62° F. at latitude 40°			45° F. at latitude 60°
53 ,,	,,	50°	...	33 ,,	,, 70°

and the quantities of water contained in the Gulf Stream are:—

36 cubic miles per hour at latitude 50°			
36	,,	,,	,,	60°
24	,,	,,	,,	70°

The mean annual temperatures of the several latitudes, in the northern hemisphere, are, taken all round the globe—

29·3° F. at latitude 60°			4·5° F. at latitude 80°
14·4 ,,	,,	70°		0·0 ,,	,, 90°

From this it is evident that the Gulf Stream is inadequate to keep the temperature of the Polar cap, from the Pole to 60° lat., above the freezing point of water; so that if the heat and cold were uniformly distributed, the whole of this great area would be permanently frozen over, the thickness of the ice being greatest at the Pole, and least at lat. 60°.

This ideal ice-cap (on the supposition of uniformly distributed heat and cold) represents accurately the amount of heat that must be introduced into the Arctic regions before their temperature rises to that of the freezing point of water. Its southern limit is lat. 58° 51′, where the mean annual temperature all round the globe is 32° F.

The thickness of this ideal ice-cap at the Pole is unknown, but from what we know of the palæocrystic ice of Hall's Land and Grinnell Land must be measured by hundreds of feet; and its mean temperature must be at least 20° F. below the freezing point of water.

Mr. Wallace has put forward the supposition that the introduction of an equal proportion of the Kuro-siwo (to that of the Gulf Stream) would prevent the formation of sea-ice in the Arctic Sea. Before this could happen, the Kuro-siwo must first melt the ice-cap, and then keep it from freezing again.

To show how inadequate this supposition is, I shall calculate what the Gulf Stream has already done, and then show what the Kuro-siwo could do.

Let us suppose that the whole heat of the Gulf Stream, passing northwards through the parallel of 70° N., is employed in melting a supplementary ice-cap extending from the Pole to 70° N. and that this supplementary ice-cap is at the temperature of 32° F. only (*vide foot-note*); I find the thickness of ice melted is only 5·874 feet[1] yearly.

If therefore the Gulf Stream were cut off by a barrier at 70° N. lat., no old-world growth of ice at 32° F., less than 6 feet thick, might grow upon the area from the Pole to 70° N. lat.

Of course the Gulf Stream expends its heat in melting local ice in the Spitzbergen and Barentz Seas, and perhaps still further east in summer along the Siberian coast, and not in melting the supplementary ice-cap I have imagined; nevertheless the whole work done by it does not exceed the melting of the ice-cap from the Pole to 70° lat., and of a uniform thickness of 5·874 feet. In other words, the work done by the Gulf Stream north of 70° lat. is equivalent to the melting of 4382 cubic miles of ice at 32° F., which represents a delicate penalty of heat. It is however much eased to remove the ice-cap from the Pole to 70° lat., of 5·874 feet thick, than 4382 cubic miles of ice.

As the ice melted between the Pole and 70° lat. has a temperature of 6° F., instead of 32° F., it is easy to see that the thickness of ice-cap melted by the Gulf Stream is 4·813 feet instead of 5·874 feet.

(*c*) *The Kuro-siwo admitted through Behring's Strait.*—Mr. Wallace quotes me as stating that the volume of the Kuro-siwo is 2½ times the volume of the Gulf Stream: I believe it to be so, but in the present discussion shall consider it to be only twice as great; for at least one-fifth of its climate-partial entrance into Behring's Strait, and behaves like the Gulf Stream; as appears from the ice-set to-east of the climate of the Parry Islands, from the open water discovered by Collinson along the northern coast of America, and from the return cold current of the coast of China.

From the calculations I have just given it appears that the Kuro-siwo current admitted through a widened Behring's Strait would be competent to melt a thickness of ice-cap extending from the Pole to 70° lat., amounting to 9·626 feet.

I shall leave your readers to judge whether this amount of ice-melting justifies Mr. Wallace in asking "Suppose that only an equal proportion (to that of the Gulf Stream) of the Kuro-siwo entered the Arctic Ocean, is it not probable that no sea-ice at all would form there?"

To me this question appears like a proposal to Hercules to clean out the Augean stables with a teaspoon.

(*d*) Let us now add on the *Mozambique Current*, converted into a *Caspian depression Gulf Stream*. Of this current I cannot allow Mr. Wallace to appropriate more than half, unless he shows cause for a land barrier preventing the other *half* from continuing its pre-cent course into the southern hemisphere, there to aid in mitigating the climates of the Temperate and Antarctic zones.

The *Caspian Gulf Stream* will then cut off another slice of 3·609 feet in thickness from the ice-cap extending to 70° lat. Is this amount of ice-melting sufficient to perform the feat assigned to it by Mr. Wallace of "raising the former [the Polar sea] to perhaps 25° or 20° F. above the freezing point"?

(*e*) If there be any truth at all in the power of Gulf Streams to modify the climates of the Temperate and Polar zones, the southern hemisphere should be warmer than the northern hemisphere, as it receives three Gulf Streams instead of 1½ Gulf Streams (without discussing their relative volumes).

This is the actual fact, as is easily proved, notwithstanding the iterated parrot-like statements to the contrary copied from text-book to text-book.

I have shown that, taking the annual mean temperature at all longitudes, the cold of the northern hemisphere is represented by an ideal ice-cap which is thickest at the north pole and terminates in the latitude 58° 51′ N., where the mean annual temperature is 32° F.

In the southern hemisphere, the latitude at which the mean annual temperature for all longitudes is 32° F., is found at 62° 41′ S. This limit of the ideal southern ice-cap (measuring the Antarctic amount of cold) lies nearer to the South Pole by 3° 50′, or 230 geographical miles, than the *corresponding limit* of the northern ice-cap from the North Pole.

These limits of ideal ice cap at the North and South Poles are independent of the wholly different question as to which of the Poles has the largest volume of ice surrounding it, into which I shall not enter at present.

(*f*) From what I have proved above it is evident that the two return co-operating currents from the Arctic seas will still consist of ice-cold water, one of which, on the coast of Asia, of double the volume of the Labrador current, will reduce the climate of China and Northern Japan to a condition compared with which the present climate of Hudson's Bay would be a Garden of Eden; and the other would bring the Ural range and Eastern Europe into the present condition of Labrador. I think it is evident, under these latter conditions, that Bournemouth would suffer, and not gain, by Mr. Wallace's arrangements of land and water. The services rendered to the Arctic lands by the two new Gulf Streams would, in my opinion, be dearly purchased by the damage done by their compensating currents in the subtropical latitudes of Eastern Asia and Eastern Europe.

SAML. HAUGHTON.

Trinity College, Dublin, December 31, 1880

IN NATURE, vol. xxiii. p. 169, Mr. Ingram mentions the growth of *Eriobotrya mexicana* in Leicestershire. I have found large examples of loquats cultivated on a great scale in Northern Nippon, where the winter temperature is certainly much colder than in England. The northernmost place where I found them was the vicinity of Yo-odori, about 39° 12′ N., at a small distance (twenty-five miles) from the west coast. The nearest place to the south where observations were made is Niigata, 37° 55′, and to the north Hakodate, 41° 46′. The coldest month has a temperature respectively of 33°·0 and 27°·3 F. Yusuwa being situated about 450 feet high, and in the interior, the coldest month there must have not over 30°, and a heavy snowfall is the rule every winter. Again, on descending the dividing ridge

[1] I assume the following data:—Area from Pole to 70° lat. = 4,475,000 sq. m.; mean heat of sea-cold water = 111 F.; Gulf Stream = 24 cubic miles per hour (temperature = 35°).

a and Yone-awa, I first found large bamboos
e last place, about 1000 feet above sea-level, and
een here and Niigata the temperature of the
ed. This gives about 30° F. for Yone-awa, or
as at Yasawa. Now in Great Britain, the
iets excepted, the mean temperature of the
owhere lower than 36°.
December 19, 1880

A. WORTHY

vol. xxiii. p. 104) I inadvertently stated that
re composed of from 16 to 20 scales. I in-
to 80, which appears to be the maximum
f the existing species.

J. S. G.

Chalk

urged by Mr. S. N. Carvalho, jun. (vol. xxii.
e's explanation of the deposition of chalk, must
ery geological reader of "Island Life." There
er objections to it, and I tried to be specific
ithem in the leading article to which they are
y good-will to induce the readers of NATURE

J. S. G.

Height of Barometer in London

your "Meteorological Notes" a week or two
e paper by Mr. H. S. Eaton on the average
neter in London, that of the series he adopts
le is to be considered one of the most valu
ling with the mean of about 30·10 inches.

the same light I have thought it worth while
ertain method for discovering the existence
ertain, method for discovering the existence
the secular variation in the annual cycle.
1811-79 I find the following to be the

LONDON

Barometer—Hourly Means	Maximum variation in the year	Minimum variation in the year
9 A.M.	0·054	0·013
3 P.M.	·058	·014
9 P.M.	·060	·015
3 A.M.	·060	·015
Mean	·058	·014

f. Trees are, though not so regular as the
Dates relating to 1879, as far as I have
the anomalies are apparent in India,
ns stimulus on sap and the increase of growth
behind the cyclonic anomaly one spot. How-
the known annual cycle in the case which
the wise similar in relation to the mean of
The known annual cycle in the case which
the wise similar in relation to the mean of
Is it possible to trace the progress of
Can I reasonably suppose that the progress
communication between England and Australia
time? Atlantic records and coincidences

E. DOUGLAS ARCHIBALD

riments with Vacuum Tubes

H. Hertz in the last number of NATURE (vol.
e compared vacuum tubes without electro-

with a tube containing water. A tube was filled about nine-tenths full of water and then sealed hermetically. It was then applied to the prime conductor of the electric machine and electrified in the same way as the ordinary millikin electrodes, and it was found to behave precisely as they did. The water tube became charged as a double Leyden jar, positive outside and negative inside at the end next the prime conductor, and negative outside and positive inside at the other end. A great tendency to crumple of the glass was also required. So far as we have been able to see the best vacuum that I have been able to obtain with the Sprengel pump has behaved as to frictional electricity precisely as a perfect conductor such as water.

These experiments seem interesting in connection with the discoveries of Mr. Crookes as to the properties of a very perfect vacuum. No doubt it was known that Sabine can be obtained within vacuum tubes without wondering that the properties of a perfect vacuum as a repository of electricity has not been hitherto

J. T. BOTTOMLEY

Physical Laboratory, the University, Glasgow, January 8

Oxidation of Quinine, &c.

In the Chemical Society's Journal for December, 1880, there is an abstract of a paper by Hoogewerf and Van Dorp, which is to be found in Recueil des Travaux Chimiques, No. 4, 1881, in which the authors detail the experiments on the oxidation of quinine, cinnidine, cinchonine, and cinchonidine. A reference is made in this paper to our work upon the same subject in such a manner as to lead to the inference that we had copied Hoogewerf and Van Dorp, wishing to call our notice to the fact of publishing what the work as ours is existing in the interim.

In the Bulletin (vol. xxxvi. p. 481) for 1881, Hoogewerf and Van Dorp published a preliminary note on the oxidation of quinine, telling us that quinine and cinchonine yield the same next other products of oxidation of quinine a nitrogenous acid, to which they assigned little importance. Of cinchonidine they said no further account. At that time we were working at the same subject, and had come to some important conclusions.

As Hoogewerf and Van Dorp's results contained missing references to quinine which we worked out and discovered by them and ourselves many years ago, and as a reference that they were entitled to claim that priority of publication should be received for them. We sent an account of our work to the Chemical Society, before [illegible] 1879 (see also Berlin Berichte, vol. xii. p. 521). In this paper we claimed [illegible] and stated that [illegible] and [illegible] and [illegible] and

each confine himself to his own branch, at the same time recognising the importance of our discovery; and Herr Konig, in a paper published in the *Berichte*, xii. 97, referring to our first paper, says: "Es ist der erste glatte Uebergang der Chinaalkaloide in eine jedenfalls einfachere Substanz—das Pyridin."

WILLIAM RAMSAY
JAMES J. DOBBIE

Glasgow University

The Temperature of the Breath

DR. DRUMMOND'S first letter under this heading contained the suggestion of a friend that his computed thermometric readings were to be accounted for by the high temperature "caused by the condensation of the moisture of the breath by the cold hand-bright."

The discussion that followed has not only brought us back to this solution, but has also furnished us with an authoritative expression of opinion that the clinical thermometer is not sensitive to pressure. Dr. J. M. P. first hinted the curious proposition only to have it thrust aside by Dr. Dalgleish; this latter denial, neglected by Dr. Roberts, and finally discarded by himself for no other apparent reason than that aqueous vapour in condensing liberates heat. Yet I venture to assert that readings as high as any obtainable by Dr. Dalgleish's method, be it the pressure, can be obtained by a very similar mode of experimenting, without the developed heat at all. If the bulb of a thermometer, protected by paper or other non-conductor, be squeezed in an intermittent manner between finger and thumb, it will be found that the mercury can readily be made to dance up and down through about a degree on the scale with a celerity not attributable to changes of temperature. 2. If eighteen inches of cotton thread be tightly wound about the bulb, on immersing the thermometer in water it will exaggerate the temperature sometimes to as many as 12° F. 3. If a tube filled with cotton batting be substituted for the thermometer the latter beneath the thread will be longer in indicating than that in other portions of the tube, a result which I think proves that the high readings of experiment No. 2 are not temperature, but (in the light of No. 1) pressure readings.

My chief object in writing, is to protest on general grounds against the treatment accorded to P. J. M. P.'s suggestion, but at the same time I wish to express my opinion that Dr. Roberts's argument would have been strengthened by giving heed to it, for I see nothing in the account of the interrupted experiment not explainable on the pressure hypothesis at once, the descending series of readings being perchance due to a yielding of the wrappings under prolonged tension. On the other hand I have to thank the discussion on Dr. Roberts' part for having induced me to test the subject for myself, and that experience, in repeating his experiment, the rare pleasure of scientific surprise at seeing the index mount higher and higher above the level of my expectations under conditions which left no doubt as to the cause being a rise of temperature. Dr. Dalgleish has done good service by directing attention to a simple experiment which, properly interpreted, throws new light on the philosophy of clothes, and should prove a telling shot in the quiver of popular science.

WM. MCADAM

Islington, December 26, 1880

IN the number of NATURE which reached Malvas after the departure of the mail conveying my letter of the 9th inst. I was glad to read Dr. W. Roberts' abundantly full and lucid explanation of the heat produced by breathing on thermometers covered with hygroscopic substances. He has, by a very simple method, confirmed the view enforced in my communication in NATURE, vol. xxiii. p. 334.

That the effects of friction and of compression of the air are so slight that they may be disregarded, has been proved; and the rise has been clearly traced to the agency of aqueous vapour. It has yet to be determined how much of this heat may be accounted for by the reduction of aqueous vapour to the fluid state, and how much by capillary action and absorption of water, with or without chemical union, and to reduction to the solid state—all of which may be included in hygroscopic action. This determination would involve some intricate investigations which some scientific specialist may perhaps find leisure to undertake. That more than simple vapour condensation is concerned in the production of hygroscopic heat is shown by the rise of temperature on adding water to a non-saturated hygroscopic substance.

A scientific colleague has suggested to me that some cases of very high axillary temperatures may be explained by the clothing of patients being pressed into the axilla in contact with the thermometer. Thus, by folding a banian round a thermometer placed in the axilla, I registered a temperature above 100° F., while the temperature in the bare axilla was 98·3. It is evident that recently changed and dried clothing and clothing warmed by the body of a non-perspiring fever patient would have still more effect when pressed closely into a hot and moist axilla. Although this point is important mainly to physicians, I venture to draw attention to it through your columns on account of its connection with the subject of hygrometric heat.

C. J. MCNALLY

Madras, December 16, 1880

Distance of Clouds

I HAVE conveniently determined the distance of passing clouds by a method probably not new, but which I have not seen described.

It consists in ascertaining the velocity with which the shadow of a cloud traverses level ground, which is easily observed, and of course gives the velocity of the cloud itself.

The angular motion per second of clouds passing overhead is simultaneously observed by means of a coarse micrometer in a telescope, or with a theodolite.

The distance is thus obtained with fair approximation.

Distance $= \frac{v}{n} \frac{3438}{}$, v being the velocity in feet per second, and n the number of minutes of arc described in 1 seconds.

A distant mirror may be advantageously used in determining the velocity of the shadow.

EDWIN CLARK

Fluke in Calves

CAN any of your readers account for the following facts?—An examination of the liver of some six-weeks-old calves which had never touched any food but their mother's milk showed them to be infested with fully-developed Fluke (*Distoma hepaticum*). It is clear that the presence of these flukes does not admit of the usual explanation, viz., the ingestion with green food or water of mollusca bearing the larva in one of its earlier stages.

I should be grateful if any of your readers could suggest an explanation of the mode in which the flukes entered the liver of the calf. Is it possible that the larva may have passed into the milk of the mother, and so have entered the stomach of the calf?

It may interest some of your readers to know that traces of fluke were present in the livers of cattle lately killed when in high condition. The fluke had apparently been established in the host some considerable time previous to the slaughter of the animals, and not developed on their attaining to a state of high health and vigour.

A. B.

JOHN STENHOUSE, LL.D., F.R.S.

IN the early morning of the last day of the old year we lost one of the few surviving founders of the Chemical Society, Dr. John Stenhouse. He was born at Glasgow, October 21, 1809, the son of William Stenhouse of the well-known firm of calico-printers, John Stenhouse and Co. of Barrhead. He was educated first at the Grammar School and then at the University of Glasgow, and long resided in his native city. At an early age he turned his attention to chemistry, and diligently studied that science under Graham and Thomson, and subsequently with Liebig at the University of Giessen. When he removed to London, after the failure of the Western Bank of Scotland had deprived him of the fortune bequeathed to him by his father, he became Lecturer on Chemistry in St. Bartholomew's Hospital, London, but was obliged to resign that appointment in 1857 owing to a severe attack of paralysis. Even this affliction however did not discourage him, and after the lapse of a short time he renewed his scientific labours. In 1865 he succeeded Dr.

n-resident Assayer to the Royal Mint, but f the appointment by Mr. R. Lowe, who ffice in 1870.

raham and Liebig, he had all their en- ientific investigation, and devoted nearly s time to research work in the domain of ary; the eminence he attained in this nce is fully recognised, but his contribu- nical knowledge are not so well known. hor of many ingenious and useful inven- n to dyeing, sugar manufacture, tanning, atest and most permanent has been the charcoal for di-infecting and deodorising took the form of charcoal air-filters for of sewers, and the charcoal respirator, respirators, not only for preventing the cts of noxious gases in numerous manu- ations, but also for the protection of o bronchitis, asthma, and other similar

ble in our limited space to give even an numerous investigations which he published scientific career, extending as it did over e than forty years. The results are em- 100 papers, published in various scientific s and foreign; they relate in great part to he called "organic chemistry"—the che- compounds formed by organised bodies. was LL.D. of Aberdeen, a Fellow of ; was the Royal Medal ety, which awarded him; the Chemical Society; the founders of the Chemical Institute of Che- the recently-established Institute of Chy personal character those who knew him l never speak too highly; his death l mourned not only by his many per- but also by men of science throughout

WILHELM HEINTZ

recorded the death, at Halle on December 4, W. Heintz, one of the leading German day. He was born at Berlin, November 4, ier university studies were undertaken ecoming a pharmacist, but this intention d as the attractions of a more purely were offered to him. In 1844 he received gree at the Berlin University, and was s admitted as privat-docent in the philo- of the same university. In 1850 he to Halle as the successor of the well- nd; and here, after passing five years as professor, he was appointed in 1853 to orship of Chemistry, and the directorship it laboratory, posts which he occupied at leath.

ind as a guide to talents inclined towards rch, Prof. Heintz evinced more than y, and for a quarter of a century he has the reputation of Hallenser the leading rest in Germany. This reputation is due to his own personal contributions as a few chemists of our day have manifested energy and long-continued application, ss of work, accuracy of observation, and harity with fact and theory are evinced hold and diversified researches.

portion of his career was directed to the lems in physiological chemistry. Among ant researches in this direction may be e of those on the nature of the so-called on kreatin and kreatinin (1847), on lactic- atric juice (1849), on the composition of bones, and on cholesterin (1850), on the colouring matter of gall stones (1851), on urinary sediments (1862), and more especially on the animal and vegetable fats. This latter research, extending over a period of about seven years, includes exhaustive studies on the physical properties of the fats, methods of their separation, their chemical constitution and nature, the products of their decomposition, &c. His careful observations of the melting points and composition of the fatty acids in the pure state and when mixed with each other, form essentially the basis of our present knowledge on this subject, and enabled him at the time to show the composite character of various fats which preceding chemists had regarded as pure compounds.

In analytical chemistry Heintz devised a variety of methods and modifications of methods, amongst which mention may be made of his contributions on the estimation of sulphur in organic bodies, on the separation of magnesia from the alkalies, on the analysis of ashes (1847), on the determination of urea and uric acid, on the detection of gall (1848), on the determination of nitrogen (1851), on the estimation of phosphoric acid, and numerous analytical data.

In inorganic chemistry his researches were chiefly confined to studies on a variety of phosphates, on bismuth and uranium salts, on the preparation of caesium and rubidium compounds (1863), on the combustion of ammonia in oxygen (1864), on the silicates of the alkaline metals, and to the examination of the minerals margarite, stassfurtite, carnallite, adamite, and boracite, the latter of which he prepared artificially (1869).

It is however in the field of pure organic chemistry that Heintz's discoveries have been most numerous and important. They commence with his investigation on saccharic acid, begun in 1851 and resumed in 1858-1860, to which we owe a great deal of our knowledge of this acid, and especially of its salts and ethers. This was followed in 1856 by a study on the action of chloride of sulphur on the salts of organic acids, in which he recorded the interesting and well-marked formation of chlorides and sulphates of the organic salts. In 1859 he began his researches on glycollic acid, which occupied much of his time until 1872, by exposing mono-bromacetic acid to the action of various sodium alcoholates, obtaining thereby the different ethers of glycollic acid; thus with sodium ethylate:

$$CH_2Cl.COOH + NaOCH_2.CH_3 = NaCl + \begin{matrix} CH_2.OC_2H_5 \\ | \\ COOH \end{matrix}$$

By means of this double reaction he obtained a number of interesting derivatives of the acid in question. Closely allied to them were the acid ethers of glycollic acid, obtained by subjecting mono-bromacetic ethers to the action of salts, or by acting upon glycollic ethers with such bodies as phosgene or chloro-acetic ether. Among the other important compounds discovered by him in this group are glycol-ether, or di-glycollic acid, diglycollic acid, $C_4H_6O_5$ (1863), obtained by the action of sodium hydrate on monochloracetic acid, diglycol-diamide, diglycol-diamic acid, &c. During this same period he made noteworthy researches on the nitrile-amines, on sulphocyanacetic acid and its derivatives, on nitrate or ethyl-glycollic acid, on lactic acid and on the amidoacids obtained from chloropropionic and iodopropionic acids by the action of ammonia. With 1874 commences his first important research, that on the acetone bases, the simplest of which is derived from the action of ammonia on acetone. While poised between these manifold difficulties in the prosecution of this investigation, Heintz succeeded in establishing another of novel and important compounds, one very interesting from a theoretical point of view. The bodies here embraced in this new group are also ammines. Hexamine; the corresponding acetone base, the tetramethyl-diamine and

triacetonamine; benzaldiacetonamine; and lo-tri-methyl-oxylutyro-nitrile resulting from the action of prussic acid on diacetonamine; and amido-dimethyl-acetic acid, obtained by the oxidation of diacetonamine; while a paper published a few months since describes a new acetone base containing sulphur. Prof. Heintz's activity was maintained up to within a few months of his death. In addition to the paper just alluded to, his contributions to chemical literature during the year just closed include articles on triacetonamine, on the existence of aceto-nines, on two compounds of urea with chloride of gold, and on diethylene-diuramic acid.

Prof. Heintz was the recipient in 1862 of the honorary degree of M.D. from the University of Königsberg in recognition of his services to physiological chemistry. In 1870 he was elected an honorary member of the London Chemical Society.

T. H. N.

SMOKE ABATEMENT

A MEETING was held in the Egyptian Hall at the Mansion House on Friday last, under the presidency of the Lord Mayor, to consider the best means of remedying the evils arising from the present smoky condition of the atmosphere of London. Among those present were Mr. G. J. Shaw-Lefevre, M.P. (First Commissioner of Works), Mr. W. Spottiswoode (President of the Royal Society), Dean Stanley, Sir T. Kay-Shuttleworth, Dr. Farquharson, M.P., Mr. Ernest Hart (Chairman of the Joint committee of the Health and Kyrle Societies), Col. Festing, R.E., Dr. Alfred Carpenter, and Prof. Chandler Roberts.

Mr. Ernest Hart, in explaining the objects of this movement, said that some practical advance had already been made. It was not pretended that fogs could be prevented; but since smoke added appreciably and corrosive and other deleterious qualities to London fogs, much might be done to diminish the discomforts and evils we suffered from this cause. Having described the objects proposed to be attained by an exhibition of apparatus and smokeless fuel, he gave the results of some calculations in order to bring home to the minds of his hearers the enormous waste of money involved in the present arrangements for heating houses.

Mr. Spottiswoode stated that a committee of the Royal Society had been appointed to investigate the facts connected with the formation of fog; but while we looked to science to tell us what was wanted to improve our atmosphere, we looked to the legislature to carry out those objects by the enactment of every householder the best legislation could be turned to but little account. In conclusion he moved, "That it is the opinion of this meeting that the smoky condition of the atmosphere of London injuriously affects the health and happiness of the community, besides destroying public buildings, deteriorating perishable fabrics, and entailing in various ways unnecessary expenditure."

Sir Frederick Pollock seconded the resolution, and urged that much might be done if every one who had an old fire-grate to replace would provide one of an approved and really more economical pattern.

Mr. G. J. Shaw-Lefevre moved, "That in the further opinion of this meeting the injurious effects of fog are largely due to the quantities of smoke given forth from the chimneys of furnaces, manufactories, and steam-vessels, as well as dwelling-houses, and that the smoke in the metropolis might, without any considerable difficulty, be greatly lessened by the better enforcement of the existing law, by the introduction of amended legislation, and by the general use in all descriptions of premises, including dwelling-places, of proper smoke-preventing apparatus, improved household stoves and grates, or of smokeless fuel."

As the head of the public works of the responsible for the he need hardly assure those present that impressed with the importance of the cussion. The importance of pure water upon, but surely pure air was even more for years past, it must be admitted that had been getting worse, and fogs were longer duration than formerly, even in months. There could be no doubt that years ago London was famous for its roses impossible to get the rose to blossom here but impossible to get any of the coniferæ darkness of the London atmosphere. ever, deprecate any hasty attempts to might be done by the extension of the relating to the abatement of the nuisance and he thought Government might be right to give some additional facilities for enforcing those Acts. It was monstrous days so many factories should not be own smoke, and, since there was a great use of appliances which prevented this there was no hardship in enforcing the came to the question of the domestic thought it would not be wise to attempt by any legislation. They must rather trust to the extension and example and inducements. was in the introduction of some other heat country coal would be an advantage; but we the means of persuading the public to use holders to use the smokeless coal unless it could tinctly proved to them that there would be the change. He would suggest that it might while for the gas companies to turn their attention help thinking that the time was not very far distant production of gas for heating purposes. It was not only our streets and public buildings, but private houses, which might be lighted by electricity which could be made at a much less cost than present supplied for lighting. From a friend in America for heating, learnt that water-gas, which could be made at a much less cost than was used in many towns in America for heating, Every one could do something to help forward the work of abating smoke, and for himself he would to use his efforts in the department with which connected to diminish the nuisance from smoke. he mentioned that some 20,000 tons of coal were chased annually by the department, the meeting appreciate the extent to which the public offices added to the smoke. If the atmosphere of the metropolis. hoped the time would not be far distant when they would have restored the blossom to our London roses, and the blooming parity, the cheeks of our London children.

Dr. Alfred Carpenter urged that this was a question particularly affecting the middle class and the poor, the aware of that at present being deplorable. He moved, "That this meeting approves the proposal of the joint Committee of the National Health and Kyrle Societies to hold an exhibition, by permission of Her Majesty's Commissioners for the Exhibition of 1851 and the other authorities in buildings erected for the International Exhibition of 1862, of the various smokeless coals and other fuels, and of various appliances applicable to household and manufacturing purposes for the reduction of smoke, and to test the same, practically available to household information the means in order to demonstrate for the object. This meeting is of opinion that the exhibition and testing should precede any ment of the existing Smoke in regard to smoke

'INESE AND OCEANIC RACES—'ES AND AFFINITIES[1]

III.

nying series of illustrations the late King Fig. 14) and the Steing of the forest region hong, between 12–14° N. lat. (Fig. 15), ed, on the one hand, with the famous rous king, Bua Sivisi Miwong (Fig. 16), ilder of the temple of Ongkor-Vâht, and h the first King of Siam and his late and 18). Here the resemblance of Figs. European type and difference from the ese (17 and 18) is too obvious to need

For these illustrations from Mouhot, &c., I am indebted to the courtesy of les-rs. Murray, Albemarle Street.

element in Indo-China differs from the as much in speech as it does in other the Mongol races, as already stated, all nc toned languages; but the Cambojans les all speak polysyllabic untoned lan- reely yet recognised even by the best- gists. Taking the Khmer as the typical group, it will be convenient here to syllabic character, reserving the question ies till we come to the allied races of ynesia. The so-called monosyllabic or of languages Chinese, Tibetan, Anna- ns, Khasia, Shan, Burmese, Khyeng, Kuki, and most of the innumerable ts—must all be regarded as at present of profound phonetic decay. Whether were all essentially mono-syllabic, pos- Aryan, mots of one syllable only, it is y; but it seems certain that they were ed. In fact there can be no reasonable ios are a later development, worked out preserve distinctions between words that same form by loss of initial or final Chinese the final letters *m, n, ŋ, p* have e correct Mandarin dialect, causing roots *k, t, p* all to assume the form of *k*, toned *k* according to the sense.

which, combined with the absence of of modification, constitutes the very monosyllabic system, pervades the whole absolutely unknown in the Khmer group, whether monosyllables or polysyllables, ed without intonation, as in all other olysyllabic character was not recognised er, but it has been abundantly demon- vaux and Aymonnier, and will be made s. But because the Cambojans are of eir speech of polysyllabic type, it does not mbojan must be an Aryan language. As t, within the Cambojan group, which are tally distinct linguistic groups, which are ation. To attempt to affiliate Cambojan rist necessarily end in failure as did o include the "Malayo-Polynesian" in

It must always be remembered that a quaternary, if not a ternary, monosyl- t human speech is probably several years old. This period has been but more than perhaps three or four really types, but it has been long enough to ndreds of really distinct linguistic types, one lingering on in connected areas, several, like the Sorth of Eusatia and ues, actually dying out, some few, like sian, Spanish, and threatening to divide the the rest, and threatening to divide the

[1] Continued from p. 171.

B.—CAUCASIAN TYPE—(*Continued*).

V. OCEANIC BRANCH: *Indonesian and Saxonian, or Eastern Polynesian Groups.*

All the Oceanic peoples, other than the dark races of Class A, are commonly grouped together under the collective term "Malayo-Polynesian." By this name are consequently understood all the yellow, brown, or olive-brown inhabitants of Malaysia and the Indian and Pacific Oceans, that is to say, all varieties of Malays in Malacca and the Dutch East Indies, the Malagasy of Madagascar, the Philippine Islanders, the Micronesians, the natives of Formosa and the large brown Eastern Polynesians. The expression was originally proposed by William von Humboldt, merely in a linguistic sense, to designate the group of fundamentally connected languages, which really prevail amongst all these widely diffused peoples. But, like Aryan and so many other similar terms, it gradually acquired an ethnical meaning, and most ethnologists now take it for granted that there is a Malayo-Polynesian race, as there is a Malayo-Polynesian speech. But such is not the case, and as on the mainland, so in the Oceanic area, the presence of the two distinct Caucasian and Mongolian types must be recognised and carefully distinguished. It seems hopeless to do this as long as the misguiding expression Malayo-Polynesian continues to figure in scientific writings. While retaining Malay for the typical olive-brown Mongolian element in the Eastern Archipelago, I have elsewhere proposed *Indo-Pacific* for the brown Caucasian element in the Indian and Pacific Oceans, and *Saxonian* for the large brown Polynesians, constituting the eastern and most important branch of that element.

It has already been remarked that the Caucasians are the true autochthones of Indo-China. They seem to have also preceded the Mongol migration to the Archipelago, to which driven rather by the continual pressure of the Mongols advancing southwards and eastwards from High Asia. In the Archipelago they occupied chiefly the large islands of Sumatra, Borneo, Celebes, and Celebes, here probably exterminating the aboriginal Negrito tribes. But here also they were followed by the Mongols from the mainland, with whom some admixture resulted, producing the present mixed races of Western Malaysia, while others migrated eastwards to their present homes in the Eastern Pacific. Here they occupy almost exclusively all the islands east of a line running from Hawaii through Samoa to New Zealand, these groups included. West of that line they are found mostly blended with the Melanesians, as explained in Section II., but also in a pure state at a few isolated spots such as the Ellice and Phœnix Islands, Rotuma and Uvea in the Loyalty group. They are also found blended with the Malay and other elements in Micronesia.

That this large brown race reached the Pacific from the west there can be no reasonable doubt, and this view is now consequently held by Hale, Hovorth Whitmore, de Quatrefages, and most recent ethnologists. F. Müller and de Quatrefages believe we should derive the Polynesians, or Western Islanders, as the first, with *Nesos* or Malayans, which I am inclined to take as their probable starting-point. But from whatever place they set out, they seem to have settled first in Samoa, which may therefore be taken as their original point of dispersion. From this centre, and more particularly from the Island of Savaii, the principal of the group, their further migrations may be traced with some certainty from the traditions of the various groups. As those traditions [illegible]

FIG. 14.—Caucasian Type, Indo-China. King of Cambodia.

FIG. 15.—Caucasian Type, Indo-China. Strong Savage, Cochin China.

referred to under diverse forms as the original home of the race, or otherwise persists, as shown in the subjoined list, which will also serve to illustrate the permutation of letters in all these closely-connected dialects :—

SAVAIKI.—Organic Sawaiori form of the word.
SAVAII.—The Samoan form; here still the name of the island referred to in the Sawaiori traditions.
HAVAII.—The Tahitian form; here "the universe," "the world" in the national odes; also the old capital of Raiatea Island.
AVAIKI.—The Rarotonga form; here "the land under the wind."
HAWAIKI.—The Maori form; here the land whence came the first inhabitants of New Zealand.

FIG. 16.—Caucasian Type, Indo-China. Statue of the Leprous King, Founder of Angkor-Vâht, Cambodia.

HAVAIKI.—The Marquesas form; here "the lower regions of the dead." Over the victims in human sacrifices are uttered the words, "To fenua Havaiki" = Return to the land of thy forefathers.
HAWAII.—The Sandwich form; here still the chief island of the group.
HEAVAI.—The form in chart published by R. Forster in vol. v. of Cook's Second Voyage, and based on information furnished by Tapaia, a native of Tahiti, who had no personal knowledge of Samoa.
HEAWIJE.—The form given by Cook in his account of his first visit to New Zealand (1770).[1]

started from Java, they could not have carried its present name with them. I note that Prof. Sayce now identifies *Yanai* with the Etruscan *Avi*, accounting for the *Y* by association with *Janus* (*Academy*, August 21, 1880). But is not *Yanai* itself a derived form from *Yanu*, whence also *Yanuarius*?

[1] "Philology and Ethnology of the Inter-Oceanic Races," by A. H. Keane, in Stanford's "Australasia," 1879.

ven been assigned for these various migra-
are told that the Polynesians made their
he Marquesas Islands about the beginning
ury A.D., in Tahiti about 1100, in Raro-
o, in New Zealand about 1400, and so on.
epending on the oral genealogies of the
r equally unreliable data, must be regarded
re. More probable is the statement that
ed in Malaysia
d years before
urs of Malays in
the same time it
t assigning dates
historic events,
ct sequence of
ore concerned.
are one of the
mankind, Cau-
ntials, and with-
ongolian blood.
Cook to the
Challenger Ex-
animous in de-
as distinguished
mmetrical pro-
ature, handsome
ures. Cook gives
the Marquesas
"for fine shape
ures, surpass all
The Samoans
re very little in-
of the Tongans
ipelago) Lord
ell remarks:—
people in the
one at first so
Friendly Islan-
r, light copper-
kins, yellow and
-humoured and
their *tout en-*
a novel and
of the *noyau*
as physique and
they gave one
ression of being
o ours." Their
s five feet ten
in this respect
cleides of Para-
ve smooth but
otten curly and
Stanislaus Wake
en that, against
ceived opinion,
ally full, though
removed. Add
cheerful joyous
rank and truth-
d kindly nature,
a type as dif-
ossible to im-
Mongolian, and
m the true Malay. Yet the Sawerton
grouped together under the collective
"Malayo-Polynesians," as if they were
ties of a common stock. All they have
one or two cranial features, of no par-
racial tests, at least when taken apart,
of their language, which we shall see is
o racial test at all. The true affinities of
with the Caucasians of Indo-China, and
ent in Malaysia which Dr. Hamy proposes

to group as Indonesians, and whose relations to the Eastern Polynesians he has been one of the first to perceive. Noteworthy amongst these Indonesians, Pre-Malays, or Indo-Chinese Caucasians still unaffected by Mongol influences in the Archipelago are the Mentawey Islanders, who, though occupying the Pora Group some seventy miles off the west coast of Sumatra, are none the less closely related in physique, language, and customs, to the Eastern

Fig. [illegible].—Mentawey Islanders. Boy and Girl.

Polynesians. On this point the testimony of C. B. H. von Rosenberg is decisive. "On a closer inspection of the inhabitants the careful observer at once perceives that the Mentawey natives have but little in common with the peoples and tribes of the neighbouring islands, and thus as regards physical appearance, speech, customs, and usages they stand almost quite apart. They bear such a decided stamp of a Polynesian tribe that one feels far more inclined to compare them with the inhabitants of the South Sea Islands."

From this point of view it will be instructive to compare the native of Pora, Mentawey Group (Fig. 19), with the Battas of Pak-Pak, Sumatra (Figs. 20 and 21), all from von Rosenberg's "Malay Archipelago," vol. i. pp. 56 and 192. Owing to their splendid physique and "Caucasian features" Junghuhn and Van Leent take

FIG. 19.—Caucasian Type: Malayan. Mentawey Islander.

these Sumatran Battas as the typical unmixed or pre-Malay element in the Archipelago, whom they would accordingly group collectively as the Batta race. The form *Battak* often occurs, but this is simply the plural of Batta, so that to write *Battaks*, as many do, is a solecism. Compared with the Malays proper, the Battas are tall and muscular,

FIG. 20.—Caucasian Type: Sumatran. Native of Batta Land.

with regular features, less prominent cheek-bones, light brown complexion, with a ruddy tinge on the cheeks, finer hair, often brown and wavy, thicker beard. When in Jilolo in 1876 M. Achille Raffray met some so-called "Alfuros" of Dodinga, who might be taken as typical specimens of this Batta or Indonesian race (*Tour du Monde*, April 12, 1879, p. 234). We therefore separate this Batta, Indonesian or Pre-Malay element in the Archipelago from the Malay element proper, affiliating the former to the Indo-Chinese and Eastern Pacific Caucasians, the latter to the Indo-Chinese Mongolians. Whether the Caucasians are found in other parts of East

FIG. 21.—Caucasian Type: Malayan. Native of Pak Pak, Batta Land.

Asia is a question that cannot here be discussed, but it may be remarked that even the cautious Topinard ventures to include "the Ainos of Japan, the Miau-Tz' and the Lolos of Yunnan in the European group" ("Anthropology," p. 476).

C. MONGOLIAN TYPE.

VI. CONTINENTAL BRANCH: *Indo-Chinese Group.*

VII. OCEANIC BRANCH: *Malayan Group.*

The main features of the continental branch of this division are too well known to need special comment here. What we are more immediately concerned with is its relation to the Oceanic section, and this relation will come out the more clearly if both are treated together. To avoid misconception, it may be well to observe that a portion only of the Continental branch is comprised in the Indo-Chinese group; for there are many other groups, such as the Mongolian proper, the Manchurian, the Tatar or Turkic, the Japanese, the Corean, the Finns scattered over the greater part of Asia and penetrating westwards to the Baltic seaboard and Middle Danube basin. All these must be held, apart from the question of intergradation or belonging to one primeval stock, constituting the Yellow or Mongolian division of the human family. We recall familiar with its essential characteristics: flat and broad features, prominent cheek-bones, short broad and flat nose, black almond-shaped and oblique eyes, long black and lank hair nearly cylindrical in section, little or no beard, low stature averaging about 5 feet 4 inches, dirty yellow or tawny complexion, slightly prognathous and more or less brachycephalous head.

This description corresponds substantially with the ordinary Malay type, such as we see it in Java, Bali, Madura, many parts of Sumatra, round the coast of Borneo, and in the peninsula of Malacca. The true aborigines of this region, as shown in a previous section, were the Negritos; consequently the Malays, like the

...ese, or even Indonesians, are here intruders. ...n where? Obviously from where the type ...ighbouring Indo-Chinese peninsula. What ...s of the Malay as a primary division of ...ys such it can no longer be recognised in ...and must sink to the position of a mere ...Mongol type. The so-called true Malay ...lay is essentially a Mongolian, and the like...the two has not failed to strike all extend... "The Malayan race," says Wallace, "as a ...tedly very closely resembles the East Asian ...om Siam to Manchuria. I was much struck ...en in the Island of Bali I saw Chinese ...had adopted the costume of that country, ...n then hardly be distinguished from Malays. ...her hand I have seen natives of Java who, ...esigning was concerned, would pass very ...ese." Hence De Quatrefages rightly rejects ...he Malays to be regarded as a fundamental ...polymorphic," he remarks, "have recorded ...me of their *Banua ajoeng*, many modern ...considered them as one of the principal ...ed long ago that in reality they are only a ...in which white, black, and yellow elements ...

...use of this sentence gives the true solution ...em. "The inhabitants of Malaysia consist ...r even of three distinct races, but of three ...y intermingled, the yellow or Mongolian ...or Caucasian chiefly in the west, those two ...s or Papuan chiefly in the east. To the ...w, white, and black positives, the so-called ...ly, the fusion of yellow and white ...the east, or the fusion of yellow and black ...so-called Malays in the west. The more ...ssified Malays in the west, the more they ...ands the near relation the Malays approach ...ps, the more the white preponderates over ...each the Caucasian type, and in some ...seem to be no longer distinguishable from ...n others from the Caucasians. The ...taken for Chinese by Wallace, just as the ...ndians are taken for Savoyards or Italian ...s von Rosenberg. I infer that from ...at surprising that those who seek to study ...ld meet with nothing but confusion ...ld I meet with more elaborate discussions ...ments on the divergent characteristics ...the Malayan genus, in tracing the where...very great complexity in the characters of ...ir collections which are said to belong to ...must always be the case until we come ...ain, as to the meaning of the term Malay, ...is far more a national and linguistic than ...ession. Precisely the same remarks ...a common Malay type in existence ...a common Malay type in existence ...ult of the supposed astonishing result ...ed at the supposed astonishing result ...ent arrangements in Micronesia and Malaysia ...

Length of Skull in			
	68	73	5
	74	77	3
	75	76	1
			0·1
			1
			0·8
			0·4
			0·1
	79	80	1
	79	81	1
	82	82	0·1

Sumatrans is taken as a unit, although it is ... too much to say that a comparison of ... Palembang, Lingly, Siak, Menangkabau, ... Tulambadie, Lingly, Siak, Menangkabau, ... ng, Lampung, and other states from that ... would probably yield almost as many dis... crepancies as are revealed in this table. There is in fact less uniformity of type in Malaysia alone, with a population of some 25,000,000, than in the whole of China and Mongolia with a probable population of 400,000,000.

A. H. KEANE

(*To be continued.*)

A CHAPTER IN THE HISTORY OF THE CONIFERÆ.

II.

GINKGO (Linnæus)

THE perhaps better known name of this genus is Salisburia Smith), but the Linnæan name, adapted from the Chinese, has unfortunately priority. The genus contains only one existing species, the gigantic *Ginkgo biloba* of Northern China and Japan. It is classified with the Taxeæ, is dioicous, and the flabelliform leaves are deciduous, leathery, very variably lobed, and of all sizes up to an extreme of five inches across. The fruit, about an inch in diameter, is drupaceous, on a slender footstalk, composed externally of a fleshy layer, and internally of a hard light-coloured shell, and is somewhat unsymmetrical, owing to the abortion of one of the seeds. The foliage is like that of the maidenhair fern, but the petiole is short, often three inches long, and distinctly articulated at the base. An important characteristic in recognising the fossil leaf, besides the petiole, is that however irregularly they may be lobed, they are almost invariably primarily bilobed.

Though so restricted a genus now, its ancestry is perhaps more venerable than that of any other forest tree. The Carboniferous fruits Trigonocarpus and Noeggerathia are believed by both Hooker and Saporta to have belonged to some ancestral form, and even the foliage of the latter, Lesquereux's figure of Schimper, approaches nearly to that of Ginkgo. Baiera, beyond doubt a close ally, appears in the Permian, and Ginkgo in all probability in the bilobate Lanjouia of the Rhætic of Bayreuth, but the group did not reach its maximum until the Jurassics. A few species have been described in other works, but Heer's Jurassic flora of Eastern Siberia ("Flora fossilis Arctica," Vol. iv.) contains by far the most important contribution to their past history. Five genera are placed in the group: *Phænicopsis*, *Ginkgo*, *Baiera*, *Czekanowskia*, and *Stachyopitys*, but there is no special character uniting the latter to Ginkgo, although it is no doubt coniferous. The remains are clusters of occasionally forked acicular leaves, sheathing at the base in imbricated scales. The leaves widen in most specimens here and there into head-like expansions, interred to have been caused by some extinct type of parasitic fungus. It is thought by Heer that a detached stem bearing shortly petiolated double seeds or nuts may be their fruit. The inflorescence is a cluster of separate leaves, also sheathing in scales at the base, but forming a fine pinnate foliage, thought by Heer to unite Czekanowskia and Baiera, yet without any direct affinity with Ginkgo.

The most aberrant of the genera obviously belonging to the group is Trichopitys of Saporta. In this the leaves were smaller, with fewer veins, and the parenchyma reduced to a narrow expansion midrib, each vein. Although so extreme a modification of the normal type, *T. comosa* possesses the characteristic bilobation and petiole. Its affinity is best traced through *Stachyopitys*, which is similar, but with the segments of the leaves expanded to receive two or three veins each.

Czekanowskia and *Stachyopitys* are separated on trivial grounds not supported by the illustrations, and when ground through the cloak and most abnormal leaves in the mind through the cloak and most abnormal leaves in the deposit. These are rarely as large as in the existing species, but more frequently [illegible] of the vegetable

each segment. They have the venation, bilobation, and petiole of Ginkgo, yet approaching in their larger leaves to Baieria. Other similar species (?) diminishing in size are *G. schmidtiana*, with about six segments, *G. flabellata*, with fourteen or fifteen segments, and *G. pusilla*, with a less number, and barely an inch across the base. These three might probably be united into a single species. The remaining form from Siberia, *G. huttoni*, is less divided, having but four rounded segments, and is in that respect a nearer approach to the existing one.

The nearest, however, is *G. digitata* from the Jurassic of Spitzbergen, which, but for smaller size and thicker petiole, might be placed in the existing species. Leaves from Scarborough, said to be of the same species, are larger. *G. integriuscula* is evidently the smaller and less lobate leaf of the same species, and the author has besides taken the unnecessary care to establish five duly named and lettered varieties, thus clearly showing that he had formed no adequate conception of the extent to which the leaves of the existing tree may vary, even on the same branch. His species should be reduced, the excessive subdivision being a disadvantage and rendering the work unwieldy. The author also changes the classification of the Coniferæ between the second and third volumes, and the name for this genus between the third and fourth volumes, without explanation or notice, which, in a work addressed especially to geologists, is an inconvenience.

The third genus, Baieria, possesses a larger and more palm-like leaf, averaging nearly five inches in radius, primarily bilobed, each lobe forking either once or twice, the ultimate segments being of uniform width and possessing four parallel veins each. The leaf tapers to the petiole, which is not preserved in the engraved specimens. The bilobation and venation connect it sufficiently with Ginkgo, and the persistence of these characters throughout the whole group, which would hardly have been suspected to have a morphologic value, is peculiarly remarkable.

There is a marked diminution in the group in the Cretaceous. Baieria from the Komeschichten is limited to vestiges of stunted form placed among the ferns, while Ginkgo appears in a starved species with small leaves and short thick petiole, described as *Adiantum formosum*, and by fragments from the Upper Cretaceous Ataneschichten, inappropriately named *G. primordialis*.

In the Arctic Eocenes (Miocenes of Heer) Ginkgo has only, and that very sparingly, been met with in Greenland. This variety so resembled *G. adiantoides* of the Italian Miocenes, that Heer almost directly abandoned his specific name *primordialis*, and became doubtful even whether both should not be united with the existing species.

The small fragments figured in the Miocene Baltic flora are inconclusive, and we only again meet with it in the Miocenes as far south as Italy, the South of France, and the Mississippi.[1] It has been said to occur in English Eocenes by Heer, who wrote upon the tracing of an Adiantum from Bournemouth, "this is a Ginkgo," and by Ettingshausen, who considers four seeds from Sheppey to belong to it, although less than half the size of those of the present Ginkgo, and rather materially differing. Its absence otherwise in British and in French Eocenes, and in the Swiss and Austrian Tertiaries, is ascertained, for the occurrence of so distinctly-marked and easily-preserved a leaf could not well be overlooked.

The very strongly-marked and exceptional characters of Ginkgo, shared by the allied extinct genera, the remoteness of its origin in the Carboniferous, its extensive development in the Mesozoic, and persistence through so many ages, seems to render it desirable to separate them from the Taxeæ into a distinct tribe. Already dying out in the Cretaceous and lingering through the Tertiaries in a single species, its existence now is a mere survival.

[1] Since writing the above, Saporta informs me that the supposed Mississippi species is really a Lygodium.

Its home has been from time to time within the Arctic circle, yet it is scarcely proved, as Saporta says, that it actually originated there. The leaf of *G. digitata* from the Scarborough oolite, figured by Schimper, is far larger than any figured from Spitzbergen, and neither the foliage nor the fruit of the northern fossil Ginkgo, it appears, ever at any time approached those of the existing tree in its native habitats. It is now indigenous to the northern provinces of China, and must therefore be capable of withstanding a rigorous climate; yet the conditions in Western Europe do not appear to favour the ripening of its seed in higher latitudes than the South of France.

Its distribution during the Tertiaries is instructive, and Saporta's explanation, that it existed in the north during the warm Eocene and pre-Eocene times, and descended thence across Europe as the temperature decreased, on the approach of the Miocene time, is the only one that explains the facts. To suppose with Heer that the same species lived contemporaneously and at the same level in Italy and in Disco is absurd, and would presuppose a uniformity of climate such as no natural causes could have produced at so recent a geological period.

J. STARKIE GARDNER

NOTES

THE Roman Academy of Sciences has awarded half of the King Humbert Prize, now awarded for the first time, to the German astronomer, Dr. Wilhelm Tempel, director of the Acetri Observatory at Florence, for his observations on nebulæ.

DEATH is levying heavy contributions from the students of entomology in France, more especially as regards the oldest and best known. We very recently had occasion to notice the decease of Etienne Mulsant, at a ripe age. Now, we regret to have to announce the death of Achille Guenée of Châteaudun, whose name is probably more known in England than is that of any other French entomologist. He died on the 30th ult. (his colleague and fellow-worker, Dr. Boisduval, died on December 30, 1879), in his seventy-second year. Guenée was a lepidopterist. His publications are very numerous. The most important of all are the six volumes of the series termed the "Suites à Buffon" on some of the principal families of the *Lepidoptera* of the world, which appeared from 1852 to 1857. These volumes formed a basis for future students of *Lepidoptera*, and largely influenced those of them amongst our own countrymen. The town of Châteaudun occupies a not unimportant position in the history of the Franco-Prussian war. Guenée's house was occupied by the Prussian troops. He himself took refuge in Geneva, and, true to his predilections, studied the *Lepidoptera* in the collection of the museum of that city; the results of his investigations were published. We believe that when circumstances permitted his return, his own collections were found to have suffered very little damage at the hands of his unbidden guests. He was an officer of the French Academy. Our Entomological Society of London elected him one of its honorary members many years ago; and his friends amongst Englishmen were not few.

JOHN DUNCAN, a poor Aberdeenshire weaver, has presented to the University of Aberdeen his herbarium of nearly 1200 British plants, gathered by him all over the country from Northumberland to Banff, while acting as a harvest labourer. The story of Duncan was told in *Good Words* for 1878, by Mr. William Jolly, and now it would seem that the poor and intelligent weaver is so reduced in circumstances as to be compelled to accept parochial relief. Surely the University of Aberdeen ought to do something for him; and possibly some of our readers may care to send a trifle to John Duncan, Droughsburn, by Alford, Aberdeenshire.

t last to have a zoological garden. A number of
s form a company for the purpose of establishing
rden on an area of twenty acres, with conserva-
e civic authorities of Leipzig have given their
ointed out a suitable place in the immediate
city.

the Mont Cenis tunnel at the French entrance
in unmistakable signs of sinking that the Paris-Lyons
railway Company intend to have another entrance
ed, which is to be situated at about 1,181 metres
he present entrance, and is to reach the old
about 600 metres from its mouth. The work
e commenced.

he Brighton Aquarium will regret to hear of the
male sea-lion (*Otaria stelleri*), so long an inmate
—Mr. A. Crane sends us some details about
—"Jack's" very sudden death is attributed to
ie air. The left lung of that organ was found
a state of complete collapse. His female com-
good health. The first offspring of the pair, a
in the spring of 1877; the second, a dead
following year. Jack was probably about twelve
His death. His length was 8 feet 5 inches,
5 feet 3 inches; fore-feet 4 feet 2 inches and
inches; greatest circumference of the body
frontal 2 feet 2 inches, round the hinder
hes; weight of skin 1 cwt., of lungs 22 lbs.
will be preserved in the Institution, and
ally determine by means of the skull the exact
this male belonged. The cub born of this pair
ars old, a fine animal 6 feet long and much
mewhat diminutive and flat headed mother, to
he bears most resemblance, the extraordinary
he frontal bones of the skull characterising his
g as yet undeveloped. The male, Mr. Crane
excellent condition, and the growth of mane,
evelopment of invertebrate life generally is very
fact to a qualified biologist and entomologist
ld furnish ample material for a vacation, and
interesting results. Facilities for visits, we are
be willingly accorded by the Management.

KEEN'S *Corn Combine Incubator* stands in the
NESS. We have now before us the eighth issue
of this most useful botanical directory. In
United States the list of botanists, which I and
ery full and complete; and scarcely any quarter
n he named which is not represented by one or
very working botanist should have a copy of his

to 5 p.m. on January 5 a somewhat severe shock
as felt at Agram. It lasted about three seconds,
in wave-like curves as the shock passed over,
might two slight shocks were experienced.

ucharest correspondent, under date January 4,
almost correspondent, under date January 4,
as result following the recent earthquake which
t city. The soil of Bucharest is a rich loam,
e mould, very spongy under pressure, and
: in a street cause a strong vibration in the
"The Grand Hotel Boulevard, however, is
this general rule, and in the correspondent's
e principal street, on which there is a heavy
could feel any sensible effect from passing
ng the recent earthquake the windows and
massively constructed buildings rattled very
there was no audible sound produced in the
hotel mentioned. Since the earthquake shock, however, this state of things has changed entirely, and every vehicle passing the hotel causes vibration in the whole building. The singular part of this change consists in the fact that the effect produced by the vehicle is precisely the same as that accompanying the earthquake. It is not at all as previously produced in other buildings, but a swing motion similar to that described in the correspondent's telegram relating to the late shock of earthquake. The movement is so great as to cause pictures to sway backwards and forwards on the walls, and it is equally perceptible in the rear corner rooms farthest from the street. The hotel is of brick, covered outside with mastic, which would show at once any crack in the walls. He has carefully examined the exterior of the building and there is not a crack in it. Hence, he thinks, this change in the stability of the structure appears to be due to some effect produced in the earth underneath the building by the shock of earthquake.

THE *Daily Mail* Rangoon correspondent, writing on December 10, states that they felt another shock of an earthquake in Pegu nine days before the one shock on which Agram was revisited. In Rangoon it was not severe, but the trembling motion lasted for fully a minute and a half, and was sufficiently strong to set pictures swinging and rattling against the walls. Like those which preceded it, the shock travelled from south to north, and was felt more violently elsewhere, though in no case so intensely as to cause serious damage.

ON the 6th inst. at 4.30 a.m. Berlin time, a pretty strong shock of earthquake was felt at Rossdorf.

DR. KRUMME of 48, rue de la Bienfaisance, Paris, writes to ASK if any of our readers can give him information as to the causes of death in monkeys in a wild state.

THE appearance of the dogfaloera in the Crimea has been the subject of a communication by M. Puschnikoff to the St. Petersburg Imperial Geographical Society. It has appeared probably in consequence of vines having been imported from France, and has extended itself very slowly in small eccentric circles. As the vineyards are situated on the southern coast of the Crimea on the slopes of a mountain chain at the foot of the mountains, M. Puschnikoff thinks that the devastating insect will not cause much destruction. Should it appear on the Crimean steppes, especially among the grain-fields and vineyards of that country, it might soon begin to damage the whole of the vines in the valleys of the Kondol and Kara rivers.

MR. E. W. CLAYS has made a communication to the Essex Institute of peculiar interest on "The Kaweah Colonists of Southern California, as bearing on the origin of the Red Man in America." He called attention to the facts relating to the antiquity of man in the Pacific coast, and to the importance of the discovery in Calaveras County of human remains and of the works of man in the gravel under beds of volcanic material, where they were associated with the remains of extinct animals, and to the necessity of looking to this early race for much that is now otherwise impossible to account. He thought that what is called the "Chinese element" in the physical characters and arts of the southern Californians was very likely due to the inquiries from a primitive American stock, which is probably to be found now in the pure Comanche tribe. In the connection he dwelt upon the probability of rapid changes of type of man. In illustrating this argument he called attention to the distinctive characters in different tribes of Indians on the Pacific coast, and stated his belief that they had resulted from an admixture of the descendants of divergent stocks. The an adventure of the descendants of divergent stocks. The an adventure of the descendants of divergent stocks. The an adventure

was as likely autochthonous as of Asiatic origin, had stamped its impress on the people of California. The early men of America he believed were dolichocephali, and the short-headed people he thought were made up of a succession of intrusive tribes in a higher stage of development, which in time overran the greater part of both North and South America, conquering and absorbing the long-headed people, or driving them to the least desirable parts of the continent. He thought that the evidence was conclusive that California had been the meeting ground of several distinct branches of the widely-spread Mongoloid stock; for in no other way could he account for the remarkable commingling of customs, arts and languages, and the formation of the large number of tribes that existed in both Upper and Lower California when first known to the Spaniards. Mr. Putnam then gave a review of the arts of the Californians and the physical characters and customs of the people, showing that, notwithstanding the absence of pottery, the tribes, when first known, had passed through the several stages of savagery and had reached the lower status of barbarism of the "ethnical periods" given by Morgan.

PROF. SCHAFER's course of eleven lectures on the Blood at the Royal Institution will begin on the 25th instant instead of the 18th. Mr. Francis Hueffer's course of four lectures on the Troubadours will begin on the 27th instant instead of the 20th; and Prof. Sidney Colvin's course of four lectures on the Amazons will begin on the 29th instant instead of the 22nd.

PART 2 of vol. viii. of the "Natural History Transactions of Northumberland, Durham, and Newcastle-on-Tyne" has just been issued (Williams and Norgate). The part contains an interesting memoir of the late Mr. W. C. Hewitson, F.L.S., by Dr. Embleton, accompanied by a good photograph. There is a long paper by Mr. Hugh Miller on Tynedale Escarpments, their pre-glacial, glacial, and post-glacial features.

HERR E. REYER has published a little pamphlet containing some interesting notes on the history of tin.

AT the meeting of the Eastbourne Natural History Society of December 17, 1880, Mr. Charles Dixon read "Notes on some of the Beetles of the Cuckmere District."

THE Municipal Council of Paris has given authority to the Lontin Company to light the Place du Carrousel with electricity. A contract has been signed by the Lyons and Mediterranean Company for illuminating, by the Lontin light, all the principal railway stations on their system. Experiments have been tried at Marseilles and have been carried out successfully.

FROM January 1 *L'Electricité* and *La Lumière Électrique*, two French electrical papers, will appear every week instead of every fortnight.

THE German Society of Eastern Asia, having its headquarters at Yokohama, has sent us the first four parts of its *Mittheilungen*. This Society is evidently doing a very useful work in collecting information on a great variety of subjects connected especially with Japan. The present parts contain papers on such subjects as Japanese proverbs, diseases, origin, population statistics, mining, cremation, the "Go" game, coins, and the chalk formation of Yedo. Asher and Co. of Berlin are the European agents of the Society.

WE find in the *Journal de Genève* the following figures as to the very warm winter which is experienced during this year on the shores of Lake Leman, as compared with the unusually cold winter of the year 1879-80. In December, 1879, the maximum daily temperature at Geneva was only five times above zero, and the average was +0°4 Cels., whilst the average of the maximum temperatures of the remaining twenty-six days was +4°5 Cels. As to the minima they were only twice above zero, and their average was +2°9, whilst the average of the remaining twenty-nine minima was −9°7. In December, 1880, the thermometer was only six times below the melting-point, and the average of the cold minima was −0°7, whilst the average of the minima for the other twenty-five days was +3°8. As to the maxima they fell below zero, and their average is as high as +9°1. The greatest cold experienced during December, 1879, was −15° Cels., and only −1°5 in 1880; the warmest temperature observed during December, 1879, was +8°9, and +13° Cels. in 1880.

A TEA plantation was established last year by Count d'Amigo upon his estates, situated near Messina. The tea plant is said to thrive perfectly well there, and its leaves are said to be in no-wise inferior to those of the Chinese plant. In order to dry them in a rational manner and to prepare them for export as well as for home consumption, a Chinese expert is to become the manager of the Messina plantations.

THE Wissenschaftliche Centralverein at Berlin held its annual general meeting on December 13, 1880. The secretary, Dr. Max Hirsch, in his yearly report stated that the principal efforts of the Society had been directed towards furthering the progress of the Humboldt Academy, which was founded by the Society some two years ago, and which since that time shows a total of ninety-two courses of lectures, which were delivered before 3366 students and a still larger number of "hospitanten," *i.e.* casual students. Apart from these lecture-courses the Society has for this winter arranged for a number of single lectures by eminent men of science. The establishment of a large reading-room is also planned.

A SOCIETY for Home Study has been started in the United States. The aim of the Society is to guide and encourage young men desirous of systematic study and reading at home by opening to them, by means of correspondence, systematic courses in various subjects. Courses of reading and plans of work are arranged, from which men may select one or more, according to their taste and leisure, and aid is given them, from time to time, through directions and advice. The courses offered by the Society at present (more may be added as the demand for them becomes known) are: Course 1. American and English History. Course 2. English Literature. Course 3. German Literature. Course 4. Natural Science: Sec. 1, Botany; Sec. 2, Zoology; Sec. 3, Geology. Course 5. Mathematics. Mr. Samuel H. Scudder is head of the Natural Science Department.

THE smallest post-office in the world is in Magellan Straits, and has been established there for some years past. It consists of a small cask, which is chained to the rock of the extreme cape in the straits, opposite Tierra del Fuego. Each passing ship sends a boat to open the cask and to take letters out and place others into it. The post-office is self-acting therefore; it is under the protection of the navies of all nations, and up to the present there is not one case to report in which any abuse of the privilege it affords has taken place.

OUR ASTRONOMICAL COLUMN

WINNECKE'S COMET.—Reference has been already made in this column to the very unfavourable circumstances attending the actual return to perihelion of the short-period comet of Winnecke, and so far there is no information of its having been detected even with telescopes of the greatest optical capacity. Indeed, it will be seen from Prof. Oppolzer's communication in the *Astron. Nach.*, No. 2326, though he gave an accurately-computed ephemeris extending to January 24, he considered the chance of perceiving the comet a very remote one. The perihelion passage took place on December 4, and the intensity of light is now very small, not greater than half that at the date of the last observation in 1858. The comet rets less than 1h. 45m.

The later positions in Prof. Oppolzer's ephemeris

	12h. Berlin M.T. R.A.		N.P.D.		Log. Distance from Earth
	h. m.	s.			
3 ...	21 20	12 ...	109 41'4	...	0·2839
4 ...	21 38	18 ...	109 9·7	...	0·2875
5 ...	21 47	12 ...	108 36·9	...	0·2916
6 ...	21 55	54 ...	108 3·2	...	0·2963
7 ...	22 4	23 ...	107 28·6	...	0·3012

METEOR.—Mr. Common, with his reflector of three feet, at Ealing, has observed this comet for position as late as January 5, when it was not yet considered the appropriate instrument. Accurate observations were made by Prof. Hall at the Dudley Observatory, Albany, U.S., on January 4, and it was at the Dudley Observatory, Albany, U.S., on January 4, and it was hoped that there will be a favourable night after discovery, so that there will be a good observation upon which to determine the orbit with precision.

ALGOL.—The following epochs of geocentric minima of Algol are deduced from Prof. Schönfeld's elements, the slight perturbations which have taken place during the last few centuries have been allowed for in accordance with a comparison of these elements with the observations made by Prof. Julius Schmidt of Athens; thus the mean epochs of Prof. Schmidt are, for 1875·0 = 4ᵈ 8ʰ 20ᵐ 59·0ˢ + 1·9409 E, and for 1878·0 = 4ᵈ 8ʰ 20ᵐ 59·0ˢ + 1·9409 E, and for 1878·0 = 21 30. The star is well deserving of attention during the present year.

G.M.T.			G.M.T.
h. m.			h. m.
18 20	February 15	=	10 53
15 0	16	=	13 43
11 58	19	=	19 32
8 48	22	=	7 22
5 37			

VARIABLE IN CEPHEUS.—A series of minima of this star commences about January 13, when it is fainter than in Europe commences about January 13, when it is fainter than 7·8 magnitude. The period may be taken = 5ᵈ 8ʰ 47ᵐ 39·0ˢ + 0·0000134E. The period may be taken = 5ᵈ 8ʰ 47ᵐ 39·0ˢ + 0·0000134E. The epoch adopted by Prof. Schmidt is Oct. 18, 1880, 8ʰ 48ᵐ, and if we reckon from the second minimum adopted by Prof. Schmidt as 17ʰ 44m, G.M.T., January 18 at 17h. 44m. G.M.T., the minima on January 18 at 17h. 44m. G.M.T., the minima on January 18 at 17h. 44m. G.M.T., the minima on

difference in the result, if on experimenting with two ants one had access to a large treasure, the other only to a small one.

It also occurred to me that some light would be thrown on the question by compelling the ant who found the treasure to return empty handed. If she took nothing home and yet others returned with her, this must be by some communication having passed. It would be a case in which precept was better than example.

I selected therefore a specimen of *Atta barbara pilosa*, belonging to a nest which I had brought back with me from Algeria. She was out hunting about six feet from home, and I placed before her a large dead bluebottle fly, which she at once began to drag to the nest. I then pinned the fly to a piece of cork, in a small box, so that no ant could see the fly until she had climbed up the side of the box. The ant struggled, of course in vain, to move the fly. She pulled first in one direction and then in another, but, finding her efforts fruitless, she at length started off back to the nest empty-handed. At this time there were no ants coming out of the nest. Probably there were some few others out hunting, but for at least a quarter of an hour no ant had left the nest. My ant entered the nest but did not remain there; in less than a minute she emerged accompanied by seven friends. I never saw so many come out of that nest before. In her excitement the first ant soon distanced her companions, who took the matter with much *sang froid*, and had all the appearance of having come out reluctantly, or as if they had been asleep and were only half awake. The first ant ran on ahead, going straight to the fly. The others followed slowly and with many meanderings; so slowly, indeed, that for twenty minutes the first ant was alone at the fly, trying in every way to move it. Finding this still impossible, she again returned to the nest, not chancing to meet any of her friends by the way. Again she emerged in less than a minute with eight friends, and hurried on to the fly. They were even less energetic than the first party; and when they found they had lost sight of their guide they one and all returned to the nest. In the meantime several of the first detachment had found the fly, and one of them succeeded in detaching a leg, with which she returned in triumph to the nest, coming out again directly with four or five companions. These latter, with one exception, soon gave up the chase and returned to the nest. I do not think so much of this last case, because as the ant carried in a substantial piece of booty in the shape of the fly's leg, it is not surprising that her friends should some of them accompany her on her return; but surely the other two cases indicate a distinct power of communication.

Lest however it should be supposed that the result was accidental, I determined to try it again. Accordingly on the following day I put another large dead fly but one an ant belonging to the same nest, pinning it to a piece of cork as before. After trying in vain for ten minutes to move the fly, my ant started off home. At that time I could only see two other ants of that species outside the nest. Yet in a few seconds considerably less than a minute, she encouraged with no less than twelve friends. As in the previous case, she ran on ahead, and they followed very slowly and by no means directly, taking in fact nearly half an hour to reach the fly. The first ant, after vainly labouring for about a quarter of an hour to move the fly, started off again to the nest. Meeting one of her friends on the way she talked with her a little, then returned towards the nest, but after going about a foot, changed her mind, and returned with her friend to the fly. After some minutes, during which two or three other ants came up, one of them detached a leg, which she carried off to the nest, coming out again almost immediately with six friends, one of whom, curiously enough, seemed to lead the way, tracing it, I presume, by scent. I then removed the pin and they carried off the fly in triumph.

These and other experiments certainly seem to indicate the possession by ants of something approaching to language. It is impossible to doubt that the friends were brought out by the first ant; and as she returned empty-handed to the nest, the others cannot have been induced to follow her merely by observing her proceedings. I conclude, therefore, that they possess the power of requesting their friends to come and help them.

Recognition of Relations.—In my last paper (*Linn. Journ.*, vol. xiv. p. 611) I recorded some experiments made with pupæ, in order if possible to determine how ants recognised their nest companions. The general result was that pupæ tended by strangers of the same species, and then after they had arrived at maturity put into the nest from which these strangers had been taken, were invariably treated as interlopers and attacked. On the other hand, if they were tended by ants from their own nest, and then after arriving at maturity put back in their own nest, they were invariably recognised as friends; and lastly, if as pupæ put back in their own nest, they were generally received as friends. In all these experiments, however, the ants were taken from the nest as pupæ, and though I did not think the fact that they had passed their larval existence in the nest could affect the problem, still it might do so. I determined therefore to separate a nest before the young were born, or even the eggs laid, and then ascertain the result. Accordingly I took one of my nests, which I began watching on September 13, 1878, and which contained two queens, and on February 8, 1879, divided it into halves, which I will call A and B, so that there were approximately the same number of ants with a queen in each division. At this season, of course, the nest contained neither young nor even eggs. During April both queens began to lay eggs. On July 20 I took a number of pupæ from each division and placed each lot in a separate glass, with two ants from the same division. On August 30 I took four ants from the pupæ bred in B, and one from those in A (which were not quite so forward), and after marking them as usual with paint, put the B ants into nest A, and the A ant into nest B. They were received amicably and soon cleaned. Two, indeed, were once attacked for a few moments, but soon released. On the other hand, I put two strangers into nest A, but they were at once killed. For facility of observation I placed each nest in a closed box. On the 31st I carefully examined the nests and also the boxes in which I had placed them. I could only distinguish one of the marked ants, but there were no dead ants either in the nests or boxes, except the two strangers.

Some further experiments led to similar results.

These observations seem to me conclusive as far as they go, and they are very surprising. In my experiments of last year, though the results were similar, still the ants experimented with had been brought up in the nest, and were only removed after they had become pupæ. It might therefore be argued that the ants—having not of them as larvæ, recognised them when they came to maturity; and though this would certainly be in the highest degree improbable, it could not be said to be impossible. In the present case, however, the old ants had absolutely never seen the young ones until the moment when, some days after arriving at maturity, they were introduced into the nest; and yet in all ten cases they were undoubtedly recognised as belonging to the community.

It seems to me therefore to be established by these experiments that the recognition of ants is not personal and individual; that their harmony is not due to the fact that each ant is individually acquainted with every other member of the community.

At the same time the fact that they recognise their friends even when no attached, and that they know the young born in their own nest even when they have been brought out of the chrysalis by strangers, seems to indicate that the recognition is not effected by means of any eggs or pre-ment.

Working Breeding.—In my last paper I brought forward some strong evidence tending to show that when workers laid eggs they always produced males. This is, however, a physiological fact of so much interest that I have carefully watched my nests this year also, to see what further light they would throw on the subject. In six of those which continued no queen eggs were produced, which if some must necessarily have been laid by workers belonging to *Lasius niger*, *Formica cinerea*, *Formica fuscata*, *Tetramorium caespitum*.

The result was that in five of these nests males have been produced, and in not a single case has a worker laid eggs which have produced a female, either a queen or a worker. Perhaps I ought to add that workers are abundantly produced in those of my nests which possess a queen. Again, as in previous years, so this season again, while great numbers of workers and males have come to maturity in my nests, not a single queen has been produced. We have, I think, therefore, strong reason for concluding that, as in the case of bees, so also in ants, some special food is required to develop the female embryo into a queen.

Aids to Hearing and Experiments with Telephone.—In order to ascertain if possible whether ants made any sounds which were audible to one another, I thought I would try the telephone. Accordingly I looked for two ants' nests (*Lasius niger*) not far from one another, and then, after disturbing one of them, laid a telephone held just over it. I then held the second telephone close over the other nest, each telephone being

to two inches above the ground. If the disturbed
y sound which was transmitted by the telephone, the
her nest ought to have been thrown into confusion.
however, perceive that it made the slightest differ-

I tried the experiment three or four times, always
result.—I then put some syrup near a nest of *L.*
ien several hundred ants were feeding on the syrup,
e nest, which always disturbs them very much,
if in large numbers and run about in great excite-
held one end of the telephone over the nest, the
feeding ants, who, however, took not the slightest
not, however, look on these experiments as at all
cause it may well be that the plate of the telephone
set in vibration by any sounds which ants could

Amount of Aphides.—Our countryman Gould, who e
work on ants has hardly received the attention
serves that "the queen ant lies is speaking of
lays three different sorts of eggs: the slave,
utral. The two first are deposited in the spring,
y and part of August; or, if the summer be ex-
able, perhaps a little sooner. The female eggs
ith a thin black membrane, are oblong, and about
or seventeenth part of an inch in length. The
of a more brown complexion, and usually laid in

er our worthy countryman fell into an error; the
thus describes not being those of ants, but a-
ly observed, of Aphides." The error is the more
cause the ants treat these eggs exactly as if they
, guarding and tending them with the utmost care.
th them in February, 1876, and was much aston-
ing at that time aware of Huber's observations. I
ier had done before me, that the ants took the
f these eggs, carrying them out to the lower cham-
utmost haste when the nest was disturbed. I
home with me and put them near one of my own
e ants carried them inside. In 1877 I again pro-
y my observations further. In March I again
the same eggs, and offered them to my ants, who
into the nest, and in the course of March I had the
seeing them hatch into young Aphides. M.
er does not think these are quite ordinary eggs,
ry he agrees with Bonnet "that the insect in a
rfect, gains the body of it's mother in the evening
it from the cold in winter, and from the heat of
re, in the egg surrounded by a double membrane,
veloped and supported. It is nothing more than
which the Aphides bear at another season their
on the account some ants have been truly
a e sweets. The mothers are now more truly
e their young are almost as perfect as they ever
-asylum in which Nature has placed them."

ink, a mistake. This is not the opportunity to
nat many of the Aphides, but I may observe that I
l the female, and that these eggs, as in the
ll described by Huxley in other Aphides, and also
also myself observed in the eggs deposited in
rewer I have opened the eggs themselves are
ained with a
containing ordinary yolk. It enclosed within its
the germ-vesicle presently the whole
was unable to detect its
nearly perfect, and nearly ready to
rane, but limbs or internal organs
are indeed relatively of
ot develop) them until a little later.

Hatched I naturally thought that the Aphides
ne of the species usually found on the roots
ets of *Lasius flavus*. The specimens I found
atures inside the nest of that species, and
ere sometimes brought out by the ants. I offered
ed them with pots of gems, &c. from my own
nt of English Ants," by the Rev. W. Houghton, F.L.S.,
el from Mr. South, also shared their nest, and
He did not however disturb the

ral History of Ants." By M. F. Huber. 1820. 2 vols.
Species, vol. xviii.
of Entomology, 1860.

uneasily about, and eventually died. Moreover they did not in any way resemble the subterranean species. In 1878 I again attempted to rear these young Aphides; but though I hatched a great many eggs, I did not succeed. This year however I have been more fortunate. The eggs commenced to hatch the first week in March. Near one of my nests of *Lasius flavus*, in which I had placed some of the eggs in question, was a glass containing living specimens of several species of plant commonly found on or around ants' nests. To this some of the young Aphides were brought by the ants. Shortly afterwards I observed on a plant of daisy, in the axil of the leaves, some small Aphides very much resembling those from my nest, though we had not actually traced them coming only. They seemed thriving, and remained stationary on the daisy. Moreover, whether they had sprung from the black eggs or not, the ants evidently valued them, for they built up a wall of earth round and over them. So things remained throughout the summer; but on October 9 I found that the Aphides had laid some eggs exactly resembling those found in the ants' nests; and on examining daisy-plants from outside I found on many of them similar Aphides, and more or less of the same eggs.

I confess these observations surprised me very much. The statements of Huber have not indeed attracted so much notice as many of the other interesting facts which he has recorded; because if Aphides are kept by ants in their nests, it seems only natural that their eggs should also occur. The above case however is much more remarkable. Here are Aphides, not living in the ants' nests, but outside, on the leaf-stalks of plants. The eggs are laid early in October on the food-plant of the insect. They are of no direct use to the ants, yet they are not left where they are laid, where they would be exposed to the severity of the weather and to innumerable dangers, but brought into their nest by the ants, and tended by them with the utmost care through the long winter months until the following March, when the young ones are brought out and again placed on the young shoots of the daisy. This seems to me a most remarkable case of prudence. Our ants may not perhaps lay up food for the winter, but they do more, for they keep during six months the eggs which will enable them to procure food during the following summer.

No doubt the fact that our European ants do not generally store up food in the usual way is greatly due to the nature of their food. They live, as we know, partly on insects and other small animals which cannot be kept fresh; and they have not learnt the art of building vessels for their honey, probably because they are not kept in cells like those of the honey-bee, and their pupæ do not construct firm cocoons like those of the bumblebees.

Moreover it is the less necessary for them to do so, because if they obtain access to any liquid store of honey, that which they swallow is only digested by degrees and as it is required; so that, as the camel does with water, they carry all out with them in their crops to supply food which may last them a considerable time. They have moreover, as we know, the power of regurgitating this food at any time, and so supplying the larvæ or less fortunate friends. Even in our English ant the quantity of food which can be thus stored up is considerable in proportion to the size of the insect; and, if we watch, for instance, the little brown ant (*Lasius niger*, L.) ascending a tree to milk the Aphides, and compare them with those returning full of honey, we can see a marked difference in size.

We have, indeed, reason to suppose that in our English ants any particular individuals specially told off to serve as food-vessels do not exist. W. Wesmael, however, has described a remarkable genus (*Myrmecocystus*) which he thought to be established from Mexico, in which certain individuals in each nest serve as living honey-pots. Testimony to the existence among these ants of such individuals seems to be afforded by the fact that the Mexicans are said to receive the honey, ready stored, from the ants themselves, and not to have to procure it when required. They are said moreover to obtain it in considerable quantities. On examining, however, the internal organs of these ants, I could not find that the distension of the crop was much greater than in other species of the genus. Nevertheless the fact that the distension of the crop is visible externally in ordinary ants as in bees and certain true wasps, seems to me to render the existence of such individuals as those described by Wesmael not improbable. Similar statements have been made by MM. de Saussure and Wesmael for other ants, and by Belt and subsequent observers as to the habits of the Mexican honey-ant, *Myrmecocystus Mexicanus*, Wesm. For instances of such observations see Belt,* Darwin,† Lincecum,‡ Saunders,§ Edwards,‖ Blake,¶ Lowe,** and Mecook.††

* "The Naturalist in Nicaragua," p. 194.
† "Descent of Man," 2nd edition, p. 237.
‡ Trans. Entomological Society of London, 1862, p. 187.
§ Trans. Entomological Society of London, 1871, p. 311.
‖ Trans. Entomological Society of London, 1871, p. 311.
¶ Proceedings of the California Academy of Natural Sciences, vol. iv. part i. p. 1.
** Trans. Entomological Society of London, 1872, p. 189.
†† Proceedings of the Academy of Natural Sciences of Philadelphia, 1879, p. 295.

On one very important point, however, M. Wesmael was in error; he states that the abdomen of these abnormal individuals "ne contient aucun organe; ou plutôt, il n'est lui-même qu'un vaste sac stomacal." Blake even asserts that "the intestine of the insect is not continued beyond the thorax," which must surely be a misprint; and also that there is no connection "between the intestine and the cloaca"! These statements, however, are entirely erroneous; and, as M. Forel has shown, the abdomen does really contain the usual organs, which, however, are very easily overlooked by the side of the gigantic stomach.

I have now the honour of exhibiting to the Society a second species of ant, which has been sent me by Mr. Waller, in which a similar habit has been evolved and a similar modification has been produced. The two species, however, are very distinct, and the former is a native of Mexico, while the present comes from Adelaide in Australia. The two species, therefore, cannot be descended one from the other; and it seems inevitable that the modification has originated independently in the two species.

It is interesting that, although these specimens apparently never leave the nest, and have little use therefore for legs, mandibles, &c., the modifications which they have undergone seem almost confined to the abdominal portion of the digestive organs. The head and thorax, antennæ, jaws, legs, &c., differ but little from those of ordinary ants.

CAMPONOTUS INFLATUS, *n. sp.*

Operaria. Long. 15 mill. Nigra, tarsis palliditibus; subtiliter coriacea, setis cinereo-testaceis sparsis; antennis tibiisque haud pilosis; tarsis infra hirsutis; mandibulis punctatis, hirsutis, sexdentatis; clypeo non carinato, antice integro; petiolo squama mediocre incrassata, antice convexa, postice plana emarginata.

Hab. Australien.

The colour is black, the feet being somewhat paler. The body is sparsely covered with still cinereo-testaceous hairs, especially on the lower and anterior part of the head, the mandibles, and the posterior edge of the thorax. The head and thorax are finely coriaceous.

The antennæ are of moderate length, twelve-jointed; the scape about one-third as long as the terminal portion and somewhat bent. At the apex of the scape are a few short spines, bifurcated at the point. At the apex of each of the succeeding segments are a few much less conspicuous spines, which decrease in size from the basal segments outwards. The antennæ is also thickly clothed with short hairs, and especially towards the apex with leaf-shaped semi-hairs. The clypeus is rounded, with a slightly developed median lobe and a row of still hairs round the anterior border; it is not carinated. The mandibles have six teeth, those on one side being rather more developed and more pointed than those on the other. They decrease pretty regularly from the outside inwards. The maxillæ are formed on the usual type. The maxillary palpi are six-jointed, the third segment being but slightly longer than the second, fourth, or fifth; while in *Myrmecocystus* the third and fourth are greatly elongated. The segments of the palpi have on the inner side a number of curious curved blunt hairs besides the usual shorter ones. The labial palpi are four-jointed. The eyes are elliptical and of moderate size. The ocelli are not developed.

The thorax is arched, broadest in front, without any marked incision between the meso- and metanotum; the mesonotum itself is, when seen from above, very broadly oval, almost circular, rather broader in front and somewhat flattened behind. The legs are of moderate length, the hinder ones somewhat the longest. The scale or knot is heart-shaped, flat behind, slightly arched in front, and with a few stiff, slightly diverging hairs at the upper angles. The length is about two-thirds of an inch.

ON THE THERMIC AND OPTIC BEHAVIOUR OF GASES UNDER THE INFLUENCE OF THE ELECTRIC DISCHARGE[1]

PROF. E. WIEDEMANN has undertaken an exact calorimetric investigation of the electric discharge through gases, and in spite of the serious difficulties which he had to encounter, he has already obtained valuable and important results. As a source of electricity, Töpler's machine was used; but we must refer to the original paper for all details of experimentation.

Three series of observations were made. In the first the total heat generated in a given time in the whole vacuum tube was measured. In the second series the capillary part only was measured. In the third the thermal behaviour of the regions in the neighbourhood of the electrodes was investigated. The result of the first series is summed up as follows:—With decreasing pressure the total quantity of heat generated at first decreases, reaches a minimum, and then increases again. In hydrogen the amount of heat generated is smaller than in atmospheric air.

A smaller amount of heat developed corresponds to a larger number of discharges in a given time, and hence to a smaller potential at the moment the discharge begins to pass. The results of Prof. Wiedemann are therefore, as he points out, in accordance with those of Messrs. De La Rue and Hugo Müller, who found that the difference of potential necessary to cause a discharge passes through a minimum as the pressure decreases.

Somewhat more complicated results were obtained when an air-break was introduced into the circuit. In that case the air-break determines the difference of potential necessary to produce a discharge; but if the whole quantity of electricity would pass suddenly when that potential has been reached, and before it has had time to sink, the amount of heat generated would be independent of the pressure in the vacuum tube. This however is not the case; but the result is intermediate between that obtained when no air-break exists, and that which would be obtained on the above supposition.

The following results were obtained in the experiments in which the capillary part of a vacuum tube only was introduced into the calorimeter:—

1. The heating effect in capillary tubes at pressures above 1 mm. is almost independent of the quantity of electricity passing with each discharge, and nearly proportional to the total amount of electricity which passes.

2. The heating effect is almost the same whether the positive or negative electrode of the tube is connected with the machine (the other electrode being connected with the earth), although the number of discharges passing in a given time is different.

3. With decreasing pressure the heat generated decreases very rapidly without passing through a minimum.

4. The heating effect is independent of the shape of the electrodes. Some results obtained by Prof. G. Wiedemann, who had found that in tubes of different widths the same amount of heat is generated by the same current, were confirmed.

Calorimetric measurements made near the electrodes showed:

1. The heating effect near the positive electrode decreases with decreasing pressure rapidly. At very low pressures a small increase is sometimes observed.

2. The heating effect near the negative electrode decreases first with decreasing pressure, and then increases rapidly.

The heating effect near the positive electrode shows some anomalies when an air-break is introduced, the amount of heat generated being considerably increased.

Some measurements were reduced to an absolute scale, and showed that the total amount of heat generated is very large. Taking account of the number of discharges, and assuming that after each discharge the gas returns to its original state, the temperature in the capillary part of the tube must have been about 2,000° C. at 15 mm. pressure, and about 1,100° C. at 5 mm. pressure. If the width of the tube was increased ten times, the temperature would only be about 100° C., and this confirms the result obtained by Prof. Wiedemann on a former investigation, that gases may become luminous under the influence of the electric discharge at a comparatively low temperature.

In another part of the paper Prof. Wiedemann treats of a very important problem. When his tubes were filled with hydrogen, and an air-break was introduced in the circuit, the spectrum of the luminous gas changed suddenly at a given point. According to a now generally accepted hypothesis this change of spectrum is always accompanied by a change in the molecular constitution of the gas; and it is to be expected therefore that heat is either absorbed or given out by a gas when its spectrum changes. This heat Prof. Wiedemann has endeavoured to measure. Let us imagine, for instance, that the current has to do the work of decomposing the molecules of a gas. The moment the discharge has passed, recomposition will take place, and the heat then generated was measured by Prof. Wiedemann. Some of the suppositions on which the calculations are based might require further investigation, but the assumptions made are supported, and to a certain extent proved by the fact that the heat necessary to change the band-spectrum into the line-spectrum was found to be *independent of the pressure and cross-section of the tube.* It is

[1] By Eilhard Wiedemann. (*Wied. Ann.*, x. p. 202.)

main's line of investigation would all of the changes of spectra are really due to ey are now hypothetically referred by the It is however rather unfortunate that in e discussion the chemical origin of the been settled to the general satisfaction of many of them believe the spectrum to be and in that case Prof. Wiedemann would he heat of combustion of hydrogen and of Wiedemann will extend his measure- which the spectroscopic difficulties have settled.

also investigated some phenomena in have also been partly dealt with by other certain conditions more exactly investi- wede and Moulton, it is known that a tiswoode and Moulton have will deflect ty brought near a vacuum tube will deflect Wiedemann finds, as had already been Mr. Gabbett, that the point touched by like a negative electrode. It is known s for something from a negative electrode are at times, and do not turn round a corner, ver is mentioned by Prof. Wiedemann, in this subject seems to take place; but Prof. suggests the secondary phenomenon might result. Perhaps an explanation is to be ed by Mr. Gabbett, that when two tubes re fused together the joint of electro- ve electrode.

were made to show that the rays in passing ceas traverse the positive discharge also he presence is essential the shape of the influence on the number of discharges and ena streaming from.

would appear with some interesting qualifications- ds with some interesting qualifications the bright of electricity through gases but discharge only if his experimental give an account only of half the facts we al discussion would lead us to focus the count of other writers which have lately return to this part of the subject on another lent from the account we have given that had employed by Prof. Wiedemann have every material step towards the Constitution n, and we may hope for another series of ns.

ARTHUR SCHUSTER.

ITY AND EDUCATIONAL INTELLIGENCE

e Baxter Physical Scholarship of the University of Edinburgh, on the most has been awarded to Mr. D. Orme Masson as been awarded to Mr. D. Orme Masson y at University College, Bristol, to enable him a further experience in Berlin, in mathematics.

Ilowship in the Johns Hopkins University is ment. Twenty Fellowships, each of the value annually open to competition to the gra- n of Fellowship was instituted in the year ll Fellowship is open to any person who a young man of talent, to enable him to ue their studies in the Johns Hopkins ocation. Each of the Fellows is required tigation, or to perform such other duties ppointment has not been made to vacate y does not go out—and consequently is not in other words the Fellowship is not an ities have been used for post-graduate stu- ogress, and are not limited to those who They have not been offered to students g graduated in the University, but it has been ome, though such persons have been held in the competition, but have been held in n young men desirous of becoming teachers atures, or determined to devote their lives to learning which lie outside of the ordinary er, the physician, and the manufacturer. Every ed to submit his college diploma or other ency from the institution where he has been mendations from those who are qualified to

speak of his character and attainments. But this is only introductory. He must also submit, orally or in writing, such evidence of his past success in study and of his plans for the future, together with such examples of his literary or scientific work as will enable the professors to judge of his fitness for the post. The examination is indeed in a certain sense competitive; but it is with and on tests, not by formal questions and answers submitted to the candidates. First, the head of a given department considers, with such counsel as he may command, the applicant's record. The professors then collectively deliberate on the nominations made by individual members of their body. The list given when they agree, with the reasons for it, is finally submitted by the president of the University to the Executive Committee, and by them in the terms for full registration and appointment. By all these precautions the highest results which were anticipated have been secured. A company of most promising students has been brought together, and their ability as teachers and scholars has been recognised by the calls they have received to permanent and attractive posts in different parts of the country.

A SPECIAL feature of Russian universities is that the students usually belong to the lower classes, and that they earn the means of existence by teaching or by translating foreign works for the monthly reviews. Thus, at the same time as the Emperor Alexander I. founded the seven Universities of Russia, a university-stone of the scheme Tomsk was laid at Tomsk, a university-town was raised for the erection of a building in which gratuitous lectures might be given to students. The well-known explorer of Western Siberia, M. Valdemar, immediately after his return from his last journey, delivered a series of lectures on the scenery of Altai, to raise funds for that purpose.

THE new university at Tomsk will be most liberally endowed. Up to the time of laying the foundation-stone 354,000 roubles (about £35,000) had been received for the building, 100,000 roubles (£10,000) for the scientific utensils, and 31,000 roubles (£3000) for the library. A library of more than 35,000 volumes is ready, and only waiting the building of the necessary apartments to house it.

SCIENTIFIC SERIALS

Journal of Botany, October, 1880 (January, 1881.—Among the more valuable articles in the most recent numbers of this journal may be mentioned a [illegible] by H. Spencer.—An account of the Acanthaceæ of the Welwitschia Angolan herbarium, by S. Le M. Moore, with descriptions of a number of new species.—[illegible] Moore's account of the [illegible] collected by [illegible] in Madagascar, by J. G. Baker.—[illegible] a collection of Malagasy ferns by J. G. Baker.—[illegible] Dimock, a recent visit to [illegible] Dyason on the [illegible] Dyason on the genus [illegible] Lindley, of its result by H. A. Hunt, with a number of interesting botanical notes and articles.

[illegible] Journal, No. 6 [illegible] Transactions of the Society.—Charles Stewart, on [illegible] Sowerby.—[illegible] Dr. H. Stewart, on the [illegible] Army Medical Staff.—Dr. W. Ley on [illegible] Dr. Stewart, on the [illegible] Dr. Stewart, on the [illegible] Dr. Stewart, on the

Plantes, and possibly the first ever seen of which the parentage was certainly known, though an egg, also exhibited by Prof. Newton, had been for many years in the collection of Mr. H. F. Walter.—Dr. Albert Günther, F.R.S., read an account of the zoological collections made by Dr. R. W. Coppinger, R.N., during the survey of H.M.S. *Alert* in the Straits of Magellan and on the coast of Patagonia, and called attention to the most remarkable species represented in the various groups, which had been worked out by himself and his assistants in the Zoological Department of the British Museum. Dr. Günther also called attention to several interesting cases of the similarity of forms in these collections to known forms of the Arctic regions and of the Australian seas.—A communication was read from Prof. J. O. Westwood, containing the description of some new exotic species of moths of the genera *Ophiusa* and *Saturnia*.—A second paper by Prof. Westwood contained observations on two Indian butterflies—*Papilio castor* and *P. polias*.—Prof. W. H. Flower, F.R.S., described the skull of a very large elephant seal (*Macrorhinus leoninus*), lately received in the Museum of the College of Surgeons from the Falkland Islands, and discussed the question of infantile and systematic variation of this animal among the Pinnipeds. Prof. Flower arrived at the conclusion from an examination of its dental, cranial, and limb characters, and from various other points in its anatomy, that the elephant seal is the member of the group the farthest removed from the terrestrial carnivora and showing most obvious analogies. He also contended that at present there is no evidence of the existence of more than one species of the genus.—Dr. A. Günther read some notes on the species of insectivorous mammals belonging to the genus *Myogale* and *Urotrichus*, and described two new species of the former genus, proposed to be called *M. moschata* (from the Rovuma River), and *M. chrysogaster* (from the Mombuga River).

PARIS

Academy of Sciences, January 3.—M. Wurtz in the chair.—M. Jamin was elected Vice-President for 1881, and MM. Decaisne and Lalanne, Becquerel were elected Members of the Central Administrative Committee. M. Becquerel gave information as to the Academy's publications, and the changes among members and correspondents. Two members have died during the year, M. Charles and General Morin; and seven correspondents, MM. Borchardt, Peters, Liouville, Faye, Miller, Schimper, and Milbert.—The following papers were read:—On magnetic oxide of iron, by M. Berthelot. The heat liberated in fixation of oxygen by iron decreases (for a given quantity of oxygen) as we pass from the protoxide to the magnetic oxide, then to the peroxide.—Researches of M. Fournier on the fall of the barometer in cyclones, by M. Faye. M. Fournier gives a formula for the progress of the barometer, and shows its validity by observations at the Island of Reunion.—M. Gould was elected Correspondent in Astronomy, in room of the late M. Peters.—On observations of the satellites of Jupiter at Toulouse (Observatory in 1879, by M. Baillaud.—On a process of atmospherical observation for the use of voyagers, dispensing with the instrument of angles for determination of latitude and of sidereal time, by M. Rouget. This is by observing two stars that have at a given moment the same altitude (or nothing such observations in pairs, and noting the interval between the two phenomena, &c.—Determination of the lines of curvature of all the surfaces of the fourth class, correlatives of cyclides, which have the circle of infinity for double line, by M. Darboux.—Measurement of the electromotive force of ballatine, by M. Ledig. He uses a torsion balance having a long wire (2·70m.) of annealed silver, and a lever with balls of gilt copper at each end. Similar balls are fixed at the angles of a rectangle, and diagonal pairs are in communication with each other. The lever, placed at equal distance from the fixed balls, is connected through the torsion wire with the + pole of a battery, the other pole being to earth. One pole of the piles to be measured is connected with the fixed balls. The deflections are read by reflection of an illuminated glass scale. The apparatus is enclosed in a metallic case connected with the ground. A thick envelope of wood-shavings is used to exclude disturbances from heat.—On the velocity of light: reply to M. Cornu, by M. Gouy.—Study on spectrophotometers, by M. Crova. Two spectra from different sources may be easily compared by covering half the slit of a photometric spectroscope with a small rectangular prism, the edge of which cuts the slit normally into two equal parts: one half receives one of the lights directly, the other, by total reflection, the other light placed laterally. Aberration can be corrected with a cylindrical lens. The elliptic polarisation from total reflection may be suppressed, by replacing a simple prism by two total reflection prisms superposed in contact.—On a method of reproducing speech in electric condensers, and particularly in the singing condenser, by M. Dumond. He connects one pole of a battery with one end of the induced wire of the coil, the other pole with one armature of the condenser, while the second armature is attached to the other end of the induced wire. (In the circuit of the primary coil are a battery and carbon microphone). In this way speech may be reproduced with perfect distinctness. The condenser giving the best effects was 0·06m. in length of side; it contained thirty-six sheets of tin foil. For the auxiliary battery two or three (Leclanché) elements will give weak articulate sounds. The intensity increases with increase of the number of elements, but not proportionally. The current of the auxiliary coil does not traverse the condenser.—M. du Moncel made some remarks on the subject.—On the vapour-density of iodine, by MM. Crafts and Meier. They study the variation of the density with the tension and with the temperature. The facts agree with the hypothesis of progressive dissociation.—On the direct preparation of chlorised and bromised derivatives of the methylic series, and especially of chloroform and bromoform, by M. Damoiseau.—On the functions of the small oblique muscle of the eye in man, by M. Panas.—Facts for the study of formation of fogs, by M. Andre. This relates to a cave in which a high barometer was observed to sink suddenly (with rain), while a fog present disappeared; with slow rise of the barometer the fog reappeared.—New eruption of Mauna Loa (Hawaiian Islands), by Mr. Green. This was on November 9.—On the formation of a thin layer of ice on the sea observed at Smyrna during the winter of 1879, by M. Carpentin. A slight breeze seems to have driven the waters of the Guedyze against the quays of Smyrna, and there formed a thin layer on the surface, which froze in a complete calm on a clear night.—On a new use of electricity, by M. Grandi. The ex. propelling vessel. A steam-engine drives one or more electro-dynamic induction apparatuses; the current is sent through a voltameter; the gases are conducted to an orifice in the keel, and exploded by an induction spark, with propulsive effect.

CONTENTS

PAGE

BALFOURIAN CRITICISM. By Prof. BALFOUR STEWART . . . 257
LIGHT OF DISSOCIATION . . . 258
SALVATION'S ANTHROPOLOGY OF NEW GUINEA . . . 258
OUR BOOK SHELF . . . 259
Williams's "Elementary Treatise on the Integral Calculus, containing Applications to Plane Curves and Surfaces" . . . 259
"Notes on Roumania" . . . 260
"Rambosson's Copernicus" . . . 260
Hensley's "Botany for Children" and "Illustrated Elementary Text-Book for Junior Classes and Young Children" . . . 260
LETTERS TO THE EDITOR:—
Zoological Classification.—Prof. SAML. HAUGHTON, F.R.S.; Dr. A. WILLEY; J. S. G. . . . 260
Chloric Ether.—A. E. . . . 261
Average Height of Barometer in London.—G. HERBERT ARCHER . . . 261
Earthquakes slowly Seismic Pulses.—J. T. BOTTOMLEY . . . 261
Dissociation of Quinine, &c.—Dr. WILLIAM RAMSAY and JAMES J. HOTTER . . . 261
The Temperature of the Breath.—Dr. WM. MCLAUGHLIN, Dr. C. J. M'NALLY . . . 262
Diplacusis Classic.—ERWIN CLARK . . . 262
Fishing Cats.—A. E. . . . 262
JOHN SPOTTISWOODE, LL.D., F.R.S. . . . 262
WILLIAM HUGGINS, F.R.S. . . . 264
SCIENCE ACADEMIES . . . 265
THE INTERCHANGE AND ORGANIC RATES—TYPES AND APTITUDES. III. By A. H. KNIGHT (*With illustrations*) . . . 267
A CHAPTER IN THE HISTORY OF THE CENTIGRADE. II. By J. STATER-GLAISHER . . . 270
NOTES . . . 272
THE ASTRONOMICAL COLUMN:—
Winnecke's Comet . . . 274
Swift's Comet . . . 274
Minima of Algol . . . 274
Cornu's Variation in Coefficient of Aberration . . . 274
The Academy of Sciences, Paris . . . 275
GEOLOGICAL NOTES . . . 275
OBSERVATIONS ON ANTS, BEES, AND WASPS. By Sir JOHN LUBBOCK, Bart., F.R.S. . . . 276
ON THE THERMIC AND OPTIC BEHAVIOUR OF GASES UNDER THE INFLUENCE OF THE ELECTRIC DISCHARGE. By Dr. ARTHUR SCHUSTER, F.R.S. . . . 278
UNIVERSITY AND EDUCATIONAL INTELLIGENCE . . . 280
SCIENTIFIC SERIALS . . . 280
SOCIETIES AND ACADEMIES . . . 280

IPTIONS TO NATURE

. . . . . 28s.
early . . . . . 14s. 6d.
erly . . . . . 7s. 6d.
nies, United States, the Continent, and
in the Postal Union :—
. . . . . 30s. 6d.
early . . . . . 15s. 6d.
rly . . . . . 8s.
e: 20, Bedford Street, Strand.

ARY OF SOCIETIES.
London

W. NEEVES.
PHICAL INSTRUMENT
AND
SITY COIL MAKER.
LIST, &c., ON APPLICATION.
TH STREET, LONDON, W.C.

APPARATUS AND SCIENTIFIC INSTRUMENTS.
PURE CHEMICALS, &c.
IMPORTERS AND MANUFACTURERS.
AUG. BEL & CO.,
34, MAIDEN LANE, COVENT GARDEN, LONDON, W.C.

GIMINGHAM'S SPRENGEL AIR-PUMP,

CROOKES'S RADIANT MATTER TUBES,

T. CASELLA, 147, Holborn Bars, London, E.C.

THOMAS CRAMPTON & Co. (formerly of

CRAMPTON & CO.'S IMPROVED TELE

"NATURE," Nov. 14, 1878, No. 472.—One

YORK'S

NOTICE OF REMOVAL.
JAMES HOW & CO.,
SCIENTIFIC INSTRUMENT MAKERS,
73, FARRINGDON ST., LONDON.

J. ORME & CO.
SCIENTIFIC APPARATUS
AND
CHEMICALS.
65, BARBICAN, LONDON, E.C.

WESLEY COLLEGE, SHEFFIELD.

(*Affiliated to the London University*, 1844.)

Governor and Chaplain, Rev. W. H. DALLINGER, F.R.S. Head Master, H. M. SHERA, Esq., M.A., LL.D.
Second Master, E. SHINDLER, Esq., M.A. (Lond.).
And Eighteen Assistant Masters and Professors.

The object aimed at in this Institution is a sound and comprehensive mental training. The course of study is fully adapted to the requirements of the present time and to the prospective wants of the pupils, who, whether in preparation for the Universities, training for scientific pursuits, or for professional or commercial life, are provided with the most efficient aids.

BIOLOGY, PHYSICS, and CHEMISTRY, the Modern Languages of Europe, Hebrew and Syriac, Vocal and Instrumental Music, and Drawing, are taught by accomplished Professors.

The Rev. W. H. DALLINGER, F.R.S., has undertaken the Professorship of NATURAL SCIENCE, and gives Weekly Lectures and Class Instruction in Practical Zoology, Botany, &c.

Physics and Chemistry are taught by A. H. ALLEN, Esq., F.C.S.

Scholarships are awarded, worth in the aggregate 300*l.* a year.

Prospectuses may be had by application to the GOVERNOR or HEAD MASTER.

THE

British Pharmaceutical Conference.

SECRETARY WANTED.

The Executive Committee invite applications from gentlemen willing to act as SECRETARY. The duties will be to conduct the correspondence, collect subscriptions, keep the books, and carry on the general business of the Conference, under the direction of the Honorary Secretaries and Treasurer. The Secretary will also be required to assist in organising the Annual Meetings, and reside in London. Salary £100 per annum. Applications should be addressed without delay to the Hon. Secretaries, BRIT. PHARM. CONFERENCE, at 17, Bloomsbury Square, London, W.C.

F. RAJEN BENGER, } *Hon. Secs.*
MICHAEL CARTER-BELL, }

W. LADD & CO.,

SCIENTIFIC INSTRUMENT MANUFACTURERS,

(*By Appointment to the Royal Institution of Great Britain*),

13 AND 12, BEAK STREET, REGENT STREET, W.

IMPROVED HOLTZ ELECTRICAL MACHINES. GRAMME'S MAGNETO-ELECTRIC MACHINE for Laboratory use.
PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3*s.* per oz.

Physical Apparatus of every Description.

ILLUSTRATED CATALOGUE, SIXPENCE.

PATERSON'S NEW CATALOGUE OF PHYSICAL APPARATUS.

LANTERN SLIDES for SCIENTIFIC LECTURES. Sixteen stamps. Post free 6 Stamps.
Complete Sets of Physical Apparatus for Science Primers and all the Physical Textbooks in use in Schools and Colleges.
Siemens and Gramme Dynamo Machines and Lamps for hire.
Schools supplied with Apparatus as per Science and Art Department Requirements in the Sections of Light, Heat, Sound, and Electricity.
Electric Signals for Houses, Hotels, &c., Colliery Signals, Lightning Conductors. The Crown-Bell Loud-speaking Telephone.

EDWARD PATERSON, Electrical Engineer,

SHOW ROOMS AND STEAM WORKS—56B, LITTLE BRITAIN, E.C. (late 9, Bedford Court, W.C.).

MOLISON'S HARMONOGRAPH (executes the Harmonic Curves in the most perfect manner). 15*s.* and 20*s.*

Illustrated Catalogue of Electrical Apparatus, Part 1, *post free*, 6 *Stamps. Bells, Electric Signals, Part* 2, 6 *Stamps.*

S. C. TISLEY & Co.,

OPTICIANS,

172, BROMPTON ROAD, S.W.

(Close to South Kensington Museum).

THE PHONEIDOSCOPE.

An Instrument for Observing the Colour-Figures of Liquid Films under the action of Sonorous Vibrations.

Being a visible demonstration of the Vibratory and Molecular Motion of a Telephone Plate.

The PHONEIDOSCOPE, with 3 Discs, Bottle of Solution, Description Pamphlet, &c., in Cardboard Box, 10*s.* 6*d.*

MANUFACTURED AND SOLD WHOLESALE AND RETAIL BY

S. C. TISLEY & CO., 172, BROMPTON ROAD, LONDON, S.W.

TELEPHONIC ELECTRICITY. All Materials supplied for experimental purposes.

Price Lists of Electrical and Acoustic Apparatus, with Drawings and Descriptions of the Phoneidoscope, Post Free, 2d.

HOLLOWAY'S PILLS

THIS MEDICINE

Is a Certain Cure for all Disorders of the LIVER, STOMACH AND BOWELS. A Great PURIFIER of the BLOOD; a Powerful Invigorator of the System, in cases of WEAKNESS AND DEBILITY, and is unequalled in Female Complaints.

NOW READY.

SECOND EDITION,

GRIFFIN'S CHEMICAL HANDICRAFT.

PRICE 4*s.* 6*d.* POST FREE.

A CATALOGUE OF CHEMICAL APPARATUS:

ILLUSTRATED, CLASSIFIED, DESCRIPTIVE.

Containing 400 pp. Illustrated with 150 Woodcuts.

The Most Complete and Cheapest List of Apparatus.

JOHN J. GRIFFIN AND SONS, 22, GARRICK STREET, LONDON, W.C.

DRAPER'S INK (DICHROIC).

THE NEW BLACK INK

DIFFERING FROM ANYTHING ELSE EVER PRODUCED.

Writing becomes a pleasure when this Ink is used. It has been adopted by the principal Banks, Public Offices, and Railway Companies throughout Ireland.

It writes almost instantly Full Black.
Does not corrode Steel Pens.
Is cleanly to use, and not liable to Blot.
Flows easily from the Pen.
Blotting-paper may be applied at the moment of writing.

Can be obtained in London, through Messrs. BARCLAY & SONS, Farringdon Street; W. EDWARDS, Old Change; F. NEWBERY & SONS, Newgate Street; WM. MATHER, London and Manchester; J. ALLEN & Co., Dean Street, Liverpool; and STACY & COOK, Paternoster Row, and to be had of all Stationers.

BEWLEY & DRAPER, Limited, Dublin.

n Crown 8vo. Price 2*s.* 6*d.* each.

IEN OF LETTERS.

y JOHN MORLEY.

ooo Vols. of this series have been sold.

H. By F. W. H. MYERS.

of. FOWLER.

biographies we venture to say that Mr. Morley ...rpasses. A few more compared their Prof. ... work might have been more light, and sought in ...

of NICHOL.

... careful and valuable ... able ... Dictionary ...

H. STEPHEN.

... critic, as a critic, ... he is ... This will only ... literature, which has been ... ...ppeal him indifferently ... the rock by his ...

GOLDWIN SMITH.

... sketched, on a ... effective ... touches for ... ...ter one." —*Globe*, New ...

Prof. A. W. WARD.

... critical account of Chaucer ... the first ... ...

J. A. FROUDE.

... life of ... 3rd ... 2 vols. ... at the ...

Prof. DOWDEN.

... Robert ... Founder ...

... By HENRY JAMES, JUN.

... ...

MARK PATTISON.

... ...

LESLIE STEPHEN.

... work, Mr. ... ...

H. HUTTON.

... ...

... C. MORISON.

... ...

... J. A. SYMONDS.

... ...

... HERBERT, F.R.S.

... ...

By WILLIAM BLACK.

... ...

... MINTO.

... ...

Principal SHAIRP.

... ...

... the Very Rev. the DEAN OF ST. ...

... ...

... By ANTHONY TROLLOPE.

... ...

JOHN MORLEY.

... to the literary ... ...ready ... in the ... of time to ... them here. Suffice ... while few have ... ...ke."—*British Quarterly Review.*

* *Others in Preparation.*

LAN AND CO., LONDON.

NATURE SERIES.

THE SPECTROSCOPE AND ITS APPLICATIONS. By J. N. LOCKYER, F.R.S. With Illustrations. Second Edition. Crown 8vo. 3*s.* 6*d.*

THE ORIGIN AND METAMORPHOSES OF INSECTS. By Sir JOHN LUBBOCK, M.P., F.R.S. With Illustrations. Crown 8vo. 3*s.* 6*d.* Second Edition.

THE TRANSIT OF VENUS. By G. FORBES, B.A., Professor of Natural Philosophy in the Andersonian University, Glasgow. With numerous Illustrations. Crown 8vo. 3*s.* 6*d.*

THE COMMON FROG. By St. George MIVART, F.R.S. Illustrated. Crown 8vo. 3*s.* 6*d.*

POLARISATION OF LIGHT. By W. SPOTTISWOODE, LL.D., President of the Royal Society. Illustrated. Second Edition. Crown 8vo. 3*s.* 6*d.*

ON BRITISH WILD FLOWERS CONSIDERED IN RELATION TO INSECTS. By Sir JOHN LUBBOCK, M.P., F.R.S. Illustrated. Second Edition. Crown 8vo. 4*s.* 6*d.*

THE SCIENCE OF WEIGHING AND MEASURING. By H. W. CHISHOLM, Warden of the Standards. Illustrated. Crown 8vo. 3*s.* 6*d.*

HOW TO DRAW A STRAIGHT LINE; A Lecture on Linkages. By A. B. KEMPE, B.A. Illustrated. Crown 8vo. 1*s.* 6*d.*

LIGHT: A Series of Simple, Entertaining, and Useful Experiments in the Properties of Light for the Use of Students of every Age. By ALFRED M. MAYER and CHARLES BARNARD. Well Illustrated. Crown 8vo. 2*s.* 6*d.*

SOUND: A Series of Simple, Entertaining, and Useful Experiments in the Phenomena of Sound for the Use of Students of every Age. By A. M. MAYER, Professor of Physics in the Stevens Institute of Technology. Illustrated. Crown 8vo. 3*s.* 6*d.* With numerous Illustrations.

SEEING AND THINKING. By Prof. W. K. CLIFFORD, F.R.S. With Diagrams. Crown 8vo. 3*s.* 6*d.*

DEGENERATION: A Chapter in DARWINISM. By Prof. E. RAY LANKESTER, F.R.S. Illustrated. Crown 8vo. 3*s.* 6*d.*

[*Others in Preparation.*

MACMILLAN & CO., LONDON.

LA SEMAINE FRANÇAISE: a Weekly Newspaper and Review in the French Language. Politics, Literature, Science, Art, Varieties, Notes, Extracts from French Booksellers, and all the railway bookstalls. Offices, 37, Southampton Street, Strand, W.C.

A SEMAINE FRANÇAISE: Journal Français pour l'Angleterre. Politique, Littérature, Science, Art, Variétés, Nouvelle, etc., etc. Un exemplaire par la poste, 3*d.*, extérieur poste. Abonnements par la poste—un an, 13 fr. 20 c.; six mois, 7*s.* 6*d.* Puis de chez Londres, chez tous les libraires et aux gares des principales lignes de fer. On s'abonne aux bureaux, 37, Southampton Street, Strand, Londres, W.C.

LA SEMAINE FRANÇAISE.—"La Semaine Française" has been brought out in London for the benefit of those English readers who may wish to study, cursorily, easy French, in all points of view, instead of confining their reading to one particular feuille périodique."—*Athenæum.*

LA SEMAINE FRANÇAISE.—"The numbers before us are full of good things. . . . It will in fact better for us than any one of the best papers published in Paris itself. We are much pleased with the character of it, and believe it will be highly valued in all those homes where French is cultivated. The printing is very well done."—*Queen.*

TERMS OF SUBSCRIPTION—

	£	*s.*	*d.*
Three months			
Six			
Twelve			

P.O.O. payable to T. SPANSWICK, at King Street, Covent Garden, W.C.
Publishing Office, 37, Southampton Street, Strand, W.C.

EAGLE INSURANCE COMPANY.

... PALL MALL.

... ...

... ...

... ...

Messrs. MACMILLAN & CO.'S PUBLICATIONS.

NEW BOOKS ON IRELAND.

Disturbed Ireland, being the Letters Written during the Winter of 1880-81. By BERNARD H. BECKER, Special Commissioner of the *Daily News*. With Route Maps. Crown 8vo, 6s.

New Views on Ireland, or Irish Land Grievances and Remedies. By CHARLES RUSSELL, Q.C., M.P. Crown 8vo, cloth, 2s. 6d.

"This should be studied by every one who desires to understand the existing crisis in Ireland."—*Spectator.*

The Life's Work in Ireland of a Landlord who Tried to do his DUTY. By W. BENCE JONES of Lisselan. Crown 8vo, 6s.

"Mr. Bence Jones has written an interesting and instructive little book; but not the least enlightening part of it is the Preface, dated December 12th, 1880. He had just been threatened with Boycotting, which he now undergoes."—*St. James's Gazette.*

The Irish Land Laws. By Alexander G Richey, Q.C., LL.D., Deputy Regius Professor of Feudal and English Law in the University of Dublin. Crown 8vo. 3s. 6d.

"To all who, either as legislators or publicists, are called on to take part in the present controversy, the book will prove invaluable. . . . We can recommend this little book to all who speak, write, or seriously think upon this question in or out of Parliament."—*Times.*

"This book cannot fail to do good. . . . Mr. Richey writes through out fairly, and in no partisan or controversial spirit, and his book is a contribution of great value to the discussion in which we now find ourselves involved."—*St. James's Gazette.*

LIFE OF WILLIAM BLAKE. With Selections from his Poems and other Writings. Illustrated from Blake's own Works. By ALEXANDER GILCHRIST. A New and Enlarged Edition with Additional Letters and a Memoir of the Author, a vols. Printed on hand-made paper, the Illustrations in India paper, and mounted in the text. Cloth elegant, gilt, with design after BLAKE, by FREDK. J. SHIELDS. 30s. net.

"One of the most beautiful and interesting books of the season. . . . The Blake volume (both Rossetti and infinitely more than Rossetti, is a shining example of a man who chose and secured a single and sufficient measure of fortune. There is no higher philosophy."—*Daily News.*

THE YEAR'S ART: A Concise Epitome of all matters relating to the Arts of Painting, Sculpture, and Architecture, which have occurred during the Year (1880) with information respecting the events of the Year 1881. Compiled by MARCUS B. HUISH. Crown 8vo, 2s. 6d.

GOLDEN TREASURY SERIES.—NEW VOLUME.

ESSAYS OF JOSEPH ADDISON. Chosen and Edited by JOHN RICHARD GREEN, M.A., LL.D. 18mo. 4s. 6d.

DICTIONARY OF MUSIC AND MUSICIANS (A.D. 1450—1880). By eminent Writers, English and Foreign. Edited by GEORGE GROVE, D.C.L. Three Vols., 8vo, with Illustrations and Woodcuts. Price £2 2s. each. Vol. I. and II. Biographies, each 21s.

Vol. III. (Supplement). Vol. II. (Appendix to Vols. I. & II.)

"This work promises to be far more than what the best encyclopædia usually claim to be, general literature and science."—*Examiner.*

ENGLISH POETS: Selections, with Critical Introductions by various Writers, and a General Introduction by MATTHEW ARNOLD. Edited by T. H. WARD, M.A. 4 vols. crown 8vo, each 6s. 6d.

Vol. I. CHAUCER to DONNE. | Vol. III. ADDISON to BLAKE.
Vol. II. BEN JONSON to DRYDEN. | Vol. IV. WORDSWORTH to SYDNEY DOBELL.

"An excellent design admirably executed."—*Pall Mall Gazette.*

ENGLISH MEN OF LETTERS. Edited by JOHN MORLEY. Crown 8vo, 2s. 6d. (Now Volumes.)

WORDSWORTH. By F. W. H. MYERS

"Mr. Myers gives us a picture of the man and an estimate of his work which is certainly not inferior to anything that has preceded it."—*Academy.*

THE ABBOTT'S FARM; or, Practice with Principle. By HENRY TANNER, M.R.A.C., F.C.S., Professor of the Principles of Agriculture in the Royal Agricultural College, Author of "First Principles of Agriculture." Extra fcap. 3s. 6d.

ISLAND LIFE; or, the Phenomena and Causes of Insular Faunas and Floras, including a revision and attempted solution of the Problem of Geological Climates. By ALFRED RUSSEL WALLACE, Author of "The Malay Archipelago," "The Geographical Distribution of Animals," &c. With Illustrations and Maps. Medium 8vo. 14s.

"The work the richest alive in its ingenuity."—*Athenæum.*

"It takes for subject matter from all the sciences, and he builds it into a new harmonious whole."—*Pall Mall Gazette.*

GILBERT WHITE'S NATURAL HISTORY AND ANTIQUITIES OF SELBORNE. New Edition, with a Preface, and Letters never before published. Edited, with Notes and Memoir, by LEONARD JENYNS; a chapter on Antiquities by Lord SELBORNE; and the Garden Kalendar, by THOMAS BROWN, F.L.S. With Illustrations by Prof. T. MACKIE. Cheap Edition. Crown 8vo. 6s.

PHYSICS OF THE EARTH'S CRUST. By Rev. O. FISHER, M.A., F.G.S., Rector of Harlton, &c. 8vo. [*Shortly.*

STUDIES IN DEDUCTIVE LOGIC. By W. STANLEY JEVONS, LL.D., M.A., F.R.S. Crown 8vo. 6s.

"It is indispensable to the many students of the higher logic."—*Athenæum.*

GUIDE TO THE STUDY OF POLITICAL ECONOMY. By Dr. LUIGI COSSA, Professor of Political Economy in the University of Pavia. Translated from the Second Italian Edition. With a Preface by W. STANLEY JEVONS, F.R.S. Crown 8vo. 4s. 6d.

"It would be impossible to find a more compact and better-written sketch of the history of Political Economy and its latest developments. . . . It is an admirable compendium, and will, we hope, be widely circulated, as it will prove to many for the first time that the study of political economy is even more actively pursued on the Continent, than in England."—*Notes and Queries.*

MACMILLAN & CO., LONDON.

Printed by R. CLAY, SONS, AND TAYLOR, BREAD STREET HILL, Queen Victoria Street, in the City of London, and published by MACMILLAN AND CO., [illegible]

NATURE

A WEEKLY ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
Of Nature trusts the mind which builds for aye."—WORDSWORTH

No. 231 THURSDAY, JANUARY 29, 1880 [PRICE SIXPENCE

[All Rights are Reserved

ERSITY OF LONDON.
SCIENTIFIC M.B. EXAMINATION.

COLLEGE, LONDON.
J. W. CUNNINGHAM.

OD COLLEGE, near STOCK.

ION IN MATHEMATICS.—

CIETY OF LITERATURE—

and other Scientific Apparatus
BAKER.
245, HIGH HOL ORN,

ALOGUES FREE BY POST.
Hand Scientific Instruments.

BROWNING'S
NEW LANTERN MICROSCOPE.

This Apparatus has been devised to enable Lecturers or others to display ordinary Microscopic Slides with Oxyhydrogen or Electric Light Lantern on a Screen.

LIST SENT FREE ON APPLICATION.

Illustrated Catalogue of Lanterns sent free for Six Stamps

JOHN BROWNING,
OPTICAL AND PHYSICAL INSTRUMENT MAKER TO H.M. GOVERNMENT, THE ROYAL SOCIETY, &c.
63, STRAND, LONDON, W.C.

STANDARD METEOROLOGICAL INSTRUMENTS

NEGRETTI & ZAMBRA,
Opticians and Scientific Instrument Makers
To Her Majesty the Queen
HOLBORN VIADUCT,
45, CORNHILL, & 122, REGENT STREET, LONDON.

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 48a, Tollington Road, Holloway, London, N.

ROYAL INSTITUTION OF GREAT BRITAIN,

ALBEMARLE STREET, PICCADILLY, W.

LECTURE ARRANGEMENTS, NEXT WEEK.

Prof. EDWARD A. SCHÄFER, F.R.S.—First of Twelve Lectures on The Blood, on Tuesday next, January 25, at 3 p.m. One Guinea the Course.

FRANCIS HUEFFER, Esq.—First of Four Lectures on The Troubadours, on Thursday next, January 27, at 3 p.m. Half-a-Guinea.

SIDNEY COLVIN, Esq., Slade Professor of Fine Art, Cambridge.—First of Four Lectures on The Assassins, a Chapter in the Study of Greek Art and Mythology, on Saturday next, January 29, at 3 p.m. Half-a-Guinea.

Subscription for all the Courses in the Season, Two Guineas.

Friday, January 28th, 9 p.m.—Dr. ARTHUR SCHUSTER, F.R.S., The Teaching of Modern Spectroscopy, 1 lecture.

To the Friday Evening Meetings Members and their Friends only are admitted.

SCIENCE CLUB, 4, SAVILE ROW, W.

—The Club is OPEN for the use of Members. Gentlemen desirous of ascertaining the Conditions of Membership are communicate with the Hon. Sec. Entrance Fee, Five Guineas. Annual Subscription: Town Members, Four Guineas; Country Members, Three Guineas.

ROYAL POLYTECHNIC.—CLASSES for

the preparation of students for University Examinations, under the direction of EDWARD B. AVELING, D.Sc., F.L.S. London University Matriculation, 1st and 2nd B.Sc., Preliminary Scientific M.B., Botany, Physiology, Chemistry. All the work practical.

THOMAS D. RUSSELL'S

NATURAL HISTORY STORES,

45, ESSEX STREET, STRAND, W.C.

Students and others are invited to inspect the Collections of British and Foreign Shells, Corals, Zoophytes, Annelids, Crustacea, Echinodermata, Minerals, Fossils, Rock Specimens, Microscopic Objects, &c.

Cabinets, Geologists' Hammers, Glass Capped Boxes, Card Trays, Tablets, Glass Slips, Micro Thin Glass, Canada Balsam, Marine Glue, and other requisites for the Geologist and Microscopist.

Catalogues Post Free

GEOLOGY.—In the Preface to the STUDENT'S ELEMENTS of GEOLOGY, by Lyell, 1874, he says: "As it is impossible to enable the reader to recognise rocks and minerals at sight by aid of verbal descriptions or figures, he will do well to obtain a well-arranged collection of specimens, such as may be procured from Mr. TENNANT (149, Strand), Teacher of Mineralogy at King's College, London." These Collections are supplied on the following terms, in plain Mahogany Cabinets:—

100 Specimens, in Cabinet, with 5 Trays	...	...	£2 2 0
200 Specimens, in Cabinet, with 5 Trays	...	...	5 5 0
300 Specimens, in Cabinet, with 5 Drawers	...	...	10 10 0
400 Specimens, in Cabinet, with 15 Drawers	...	...	21 0 0

More extensive Collections at 50 l. 100 Guineas each.

ROCK SECTIONS & ROCK SPECIMENS.

Collections of Rock Specimens to illustrate Ridley's "Study of Rocks" specially prepared. 100 Small Specimens in Cabinet, One Guinea; 200 Specimens, Two Guineas. Extensive and choice Series of Rocks for selection. New List of Sections of Rocks for Microscope, and List of Collections, &c.

JAMES R. GREGORY'S

Extensive New Museum and 36 in Rooms,

88, CHARLOTTE STREET, FITZROY SQUARE.

MINERALOGY AND GEOLOGY.

Mr. HENSON having purchased an OLD COLLECTION formed in DERBYSHIRE, containing FINE SPECIMENS of ANGLESITE, CERUSSITE, FLUOR SPAR and CALC SPAR, DIOPHASE, EUCHROITE, and other RARE MINERALS, begs to offer the same singly or otherwise.

COLLECTIONS FOR STUDENTS, from £2 2s. COLLECTIONS FOR BEGINNERS, from 42s. BLOWPIPE CASES AND APPARATUS.

PRIVATE LESSONS AND EVENING CLASSES.

Catalogues free.

SAMUEL HENSON,

277 (*Late* 113a), STRAND, LONDON, W.C.

DIAMONDS IN MATRIX.

R. C. NOCKOLD, Diamond and Oriental Stone Cutter and Dealer, has for sale Specimens of the above; also Cut Precious Stones in all Colours.

Precious Stones valued and bought.

19, FRITH STREET, SOHO, W.

LIVING SPECIMENS FOR THE MICROSCOPE.

THOMAS BOLTON, NATURALISTS' and MICROSCOPISTS' STUDIO, 17, ANN STREET, BIRMINGHAM.

T. B. has last week sent to his subscribers the Marine Rotifer, *Pterodina elliptica*, with sketch and description. He has also sent out the young "Fry" of the American Trout, *Salmo fontinalis*, in the "Alevin" stage; also *Paludicella ehrenbergii*, *Stephanoceros Eichhornii*, *Melicerta ringens*, *Stephanoceros Eichhornii*, &c.

Weekly announcements will be made in this place of organisms T. B. is supplying.

Specimen Tube, One Shilling, post-free.

Twenty-six Tubes in course of Six Months for Subscription of £1 1s.

Price List of Specimens on application, with stamped addressed envelope.

Portfolio of Drawings, No. 3, One Shilling.

EVERY BOY A GEOLOGIST.

Now ready, and highly recommended, complete, price 7s. 6d.

This admirable little Work and most extraordinary Cabinet of wonderfully well selected Natural Specimens, together with other Geological Preparations, and a powerful Lens, are Established to start a boy thinking till he has mastered for himself an ordinary knowledge of the formation of the Earth's Crust.—THOMAS J. DOWNING, GEOLOGIST, &c., 38, Whitcher Street, London, E.C.—Catalogues free.

THE ENTOMOLOGIST'S MONTHLY MAGAZINE.

Price Sixpence, Monthly, 24 pages 8vo, with occasional Illustrations.

Conducted by C. G. BARRETT, J. W. DOUGLAS, R. M'LACHLAN, F.R.S., E. C. RYE, F.Z.S., E. SAUNDERS, F.L.S., and H. T. STAINTON, F.R.S.

This Magazine, commenced in 1864, contains standard articles and notes on all subjects connected with Entomology, and especially on the Insects of the British Isles.

Subscription—Six Shillings per Volume, post free. The volumes commence with the June number in each year.

Vols. I. to VI. (strongly bound in cloth) may be obtained by purchasers of the entire set to date, at the increased price of 10s. each; the succeeding vols. may be had separately or together, at 7s. each.

London: JOHN VAN VOORST, 1, Paternoster Row.

N.B.—Communications, &c., should be sent to the Editors at the above address.

"The leading Farmers' paper."—CLARE SEWELL READ, Esq., M.P.

THE CHAMBER OF AGRICULTURE JOURNAL AND FARMERS' CHRONICLE

(PRICE 3*d.* WEEKLY).

The representative organ of the Central and Provincial Chambers of Agriculture; gives fuller reports of the discussions and proceedings of this extensive organisation than any other agricultural paper. It also pays special attention to the treatment of agricultural questions in Parliament, besides containing ample Reports of the LATEST LONDON and COUNTRY CORN, CATTLE, WOOL, PROVISION, and other Markets, with Original Articles on Practical Farming, the Dairy, Herd and Flock, News, Horticulture, &c., &c. It is despatched every Monday morning in time for the country post.

Terms of Subscription, payable in advance, post free:—3 months, 1s. 6d.; 6 months, 3s. 3d.; 12 months, 13s. 6d.

Published by W. PICKERING, 21, Arundel Street, Strand, London, W.C., on the 1st of every Month.

TRIMEN'S JOURNAL OF BOTANY,

BRITISH AND FOREIGN.

New Series. Edited by JAMES BRITTEN, F.L.S., British Museum.

CONTENTS.—Original Articles by leading Botanists.—Extracts.—Notices of Books and Memoirs.—Articles in Journals.—Botanical News.—Proceedings of Societies.

Price 2s. 3d. Subscription for One Year, payable in advance, 27s.

London: WEST, NEWMAN, & CO., 54, Hatton Garden, E.C.



Chaque Samedi 16 pages grand in-8°. 2 colonnes

REVUE HEBDOMADAIRE

Scientifique, illustrée, spéciale, seul journal tenant les lecteurs au courant de tous les détails de l'Exposition universelle; illustrée, organe indépendant des exposants

RÉDACTEUR EN CHEF : W. de FONVIELLE

E. de CLISSON : DIRECTEUR

Un numéro, 40 *centimes*. — *L'année*, 18 *francs*. *Union postale* 20 *francs*.

PARIS, 16, rue du Croissant, PARIS

Envoi de numéros spécimens gratis sur demande

RTERLY REVIEW, No. 301,
Is Published THIS DAY.
Contents.
CAMPBELL'S MEMOIRS.
ORNAN SCENERY AND SOCIETY.
E HENRIETTE IN EXILE.
CLEON OF BRITISH BIRDS.
CEFIELD'S "ENDYMION."
BEACONSFIELD'S "ENDYMION."
FANSHAWE.
THYS HISTORY OF OUR OWN TIMES.
YMENT OF WOMEN.
THE ISLES AND THE LAW.
RUTH ABOUT IRELAND.
HN MURRAY, Albemarle Street.

NE FRANÇAISE: a Weekly
Review in the French Language, Politics, Literature,
Review in the French Language, Politics, Literature,
perties, Notes. Price 2d., through booksellers, and at
Office, 23, Southampton Street, Strand, W.C.
ffice, 23, Southampton Street, Strand, W.C.
FRANÇAISE: Journal Français pour
FRANÇAISE: Journal Français pour
Anglais. Littérature, Causeries, Arts, Variétés, Nouvelles
Anglais. Littérature, Causeries, Arts, Variétés, Nouvelles
composition par la poste, 5/6; ou à toutes les gares de
composition par la poste, 5/6; ou à toutes les gares de
Paris, 6/6. Un an, 25 fr. Prix d'abonnement

SOCIETY FOR PROMOTING CHRISTIAN KNOWLEDGE.

Just published.

NATURAL HISTORY OF BRITISH FISHES:

THEIR STRUCTURE, ECONOMIC USES, AND CAPTURE BY NET AND ROD.

Cultivation of Fish-ponds, Fish suited for Acclimatisation, Artificial Breeding of Salmon.

BY THE LATE FRANK BUCKLAND,

H.M. Inspector of Fisheries, &c.

With numerous Woodcuts. Crown 8vo, cloth boards, 5s.

NATURAL HISTORY RAMBLES:

A Series of Popular Handbooks of the Fauna and Flora of the British Isles.

Fcap. 8vo, cloth boards, 2s. 6d. each.

IN SEARCH OF MINERALS. By the late D. T. ANSTED, M.A., F.R.S., formerly Professor of Geology, King's College, &c. With numerous Woodcuts.

"It is probable there is no more entertaining companion with whom a country ramble can be taken than a search of minerals."—Athenæum.

PONDS AND DITCHES. By M. C. COOKE, M.A., LL.D., Author of "The Wayfarer." With numerous Woodcuts.

THE WOODLANDS. By M. C. COOKE, M.A., LL.D. With numerous Woodcuts.

"Wild flowers are never out of fashion, and the country may be made glorious [illegible] and flowers in it."—Saturday Review.

"These handy little volumes are well packed and contain very fully all we expect to find in [illegible] which should be familiar to our youth."—Nature.

LAKES AND RIVERS. By C. O. GROOM NAPIER, F.G.S. With numerous Woodcuts.

LANE AND FIELD. By the Rev. J. G. WOOD, M.A. With numerous Woodcuts.

MOUNTAIN AND MOOR. By J. E. TAYLOR, Esq., F.L.S., &c. With numerous Woodcuts.

THE SEASHORE. By Prof. P. MARTIN DUNCAN, M.B., F.R.S., F.G.S. With numerous Woodcuts.

UNDERGROUND. By J. E. TAYLOR, Esq., F.L.S., F.G.S. With numerous Woodcuts.

ASTRONOMY WITHOUT MATHEMATICS.

BY SIR EDMUND BECKETT, BART., LL.D., Q.C., F.R.A.S.,

Revised and Enlarged. Fcap. 8vo, cloth boards, 4s.

LONDON: NORTHUMBERLAND AVENUE, CHARING CROSS, S.W.; 43, QUEEN VICTORIA STREET, E.C.; and 48, PICCADILLY, W.

JUST PUBLISHED, Crown 8vo, cloth, 5s.

CONSCIOUS MATTER;

OR,

THE PHYSICAL and the PSYCHICAL UNIVERSALLY IN CAUSAL CONNECTION.

By W. STEWART DUNCAN.

London: DAVID BOGUE, 3, St. Martin's Place, Trafalgar Square, W.C.

Now Ready, in One Volume, demy 8vo, pp. xv-538, cloth, 14s.

British Animals Extinct Within Historic Times.

WITH AN ACCOUNT OF BRITISH WILD WHITE CATTLE.

By JAMES EDMUND HARTING, F.L.S., F.Z.S., &c.

With Illustrations by J. WOLF, C. WHYMPER, and others.

A few Copies printed on Large Paper, in Paper Boards, at 31s. 6d.

London: TRÜBNER & CO., Ludgate Hill.

PROF. HELMHOLTZ' SCIENTIFIC LECTURES.

In crown 8vo, with 15 Woodcuts, price 7s. 6d., cloth

POPULAR LECTURES on SCIENTIFIC SUBJECTS. By Prof. HELMHOLTZ, Prof. of Physics in the Univ. of Berlin. Translated by E. ATKINSON, Ph.D., F.C.S., Prof. of Experimental Science, Staff Coll. Hyde.

PROF. HELMHOLTZ' FIRST SERIES of LECTURES on SCIENTIFIC SUBJECTS. Translated by Prof. ATKINSON, with Introduction by Prof. TYNDALL. 8vo, cloth, London, with 52 Woodcuts, uniform with the Second Series, now ready, price 7s. 6d.

London: LONGMANS & CO.

BRYCE-WRIGHT'S LATEST ARRIVALS.

MINERALS.—Crystallised Hessite, Crystallised Gold, Krennerite, Crystallised Anatasites, Malaone, Enclase, Ellingtonite, Stromnite, Chamaeciite, Prunite, &c.

METEORITES.—Specimens of the following Falls—Wold Cottage, Yorkshire; Java; Ovinnic, Italy; Anum, Ohio; Tipperary, Ireland; Java; Ovinnio, Italy; Estherville; Hainholz; Grosnagy, Russia; Borkut; Carthage Co.; Bates Co.; Sierra di Chaco; Ashville Co.; Bates Co.; Pallas; Ashville Co., &c., &c.

BRYCE-WRIGHT, F.R.G.S., &c.,

Mineralogist and Expert in Gems and Precious Stones,

99, GREAT RUSSELL STREET, BLOOMSBURY, LONDON, W.C.

THURSDAY, JANUARY 29, 1881

NORTH AMERICAN PINNIPEDS

of the North American Pinnipeds: a Monograph of Walruses, Sea-Lions, Sea-Bears, and Seals of America. By J. A. Allen, Assistant in the Museum of Comparative Zoology at Cambridge, Mass. (Washington: Government Printing Office, 1880)

This bulky octavo volume forms No. 12 of the miscellaneous publications of the Department of the United States Geological and Geographical Survey of the Territories, which is under the charge of Dr. Hayden. It is a most important contribution to the history of the species of America Pinnipedia, for the zoologist as well as the merchant may well thank Mr. Hayden and Mr. Allen.

The author's task to satisfactorily set a closely-printed volume of 600 pages, but still we trust to be able to give our readers a notion of the general contents of this interesting work. Of the mammals, belonging to an essentially aquatic, finned and fin-footed group have always had a large and interest for mankind. The existing species constitute three very distinct families—the Walruses, the Eared Seals, and the Earless Seals—of which the two first are more nearly allied than either of the third. The Earless Seal is the lowest or lowest group. The Walruses are really little more than thick-skinned fat forms of the Eared Seal, enormously developed canine teeth, and modified so as to bear these. All the Pinnipeds have a high degree of brain development, and are easily tamed under favourable conditions; they manifest social and parental affections, and they defend their young with great courage. They are, almost without exception, mostly feeding on fish, mollusks, &c. While the Eared Seals are polygamous, greatly exceeding the females in size, the males of the Earless Seals are thought to be monogamous, and there is very little difference between the sexes. The polygamous species usually resort in large numbers to favourite breeding-grounds, the monogamous forms do not so uniformly resort to breeding-grounds on land, and they leave the land for short intervals. As a group the Pinnipeds are very distinctly characteristic of the Arctic and temperate portions of the globe; very few species are found in tropical waters, and only one species can be correctly tropical. While the Seals, Eared and Earless, are abundantly represented on both sides of the Atlantic, the Walruses are only to be found within the Walruses but two living species—the Walrus (Odobenus) are known, the one inhabiting the Atlantic Walrus; the other, the Pacific Walrus. The history of both species is here given. The first a full synonymy is given; then the history, accompanied by figures; then habits, and enemies. Among the figures given are those of the head of the Pacific species, which is the uncouth facial aspect and of the

[illegible] provided with, but it is a pity that none of Elliott's representations of an adult form were reproduced from his work on Alaska, published in 1875, and of which only one hundred and twenty-five copies were printed. Capt. Cook's description of this species is still one of the best extant, as species that may soon disappear if the annual slaughter of ten to twelve thousand animals is allowed to continue.

The number of genera and species among the group of the Eared Seals has fluctuated immensely even within the last ten years. The views of Gray and Peters have repeatedly changed on this subject, "great," the author writes, "in the nomenclature, out of proportion to the new material he had examined." In Peters' latest enumeration he gives thirteen species—five are Hair Seals, or Sea-lions, eight are Fur Seals or Sea-bears. Mr. Allen enumerates nineteen species. Five are Hair and four Fur Seals. A good deal of this discrepancy doubtless arose from writers not having it first to distinguish the sexes, and from their not making due allowance for the great changes in contour and density of structure that result in the skulls of these animals in passage. The most striking fact in respect of the distribution of the Eared Seals is their entire absence from the waters of the North Atlantic. The Fur and Hair Seals have nearly the same geographical distribution; but though commonly found frequenting the same shores, they generally live apart. They are about equally and abundantly represented on both sides of the equator, but are confined almost wholly to the temperate and colder latitudes. The Hair Seals have coarse hard fur only, and are wholly without soft under-fur, the abundant presence of which on the Fur Seals is that which invests their skins so valuable as articles of commerce.

The Eared Seals are all gregarious and polygamous. Their breeding-places have received the strangely appropriate name of "rookeries." The strongest males generally secure to their use from twelve to fifty females. During the breeding season the males remain wholly on land, and they will not even take food [illegible] from their chosen spot. Thus they remain for a period of several weeks in a continual fast. Steller's account, given nearly a century ago, applies still to nearly all the species. The "method" of the hunters is obtained from these Eared Seals with the [illegible]. Fortunately the destruction of the Fur Seals at the Aleutian Islands, where at one time these seals were killed at the rate of 30,000 a year, has now been placed under legal restrictions, and the same systematic protection ought to be all others to them at all their stations. In 1877 Mr. Elliott calculated that the number [illegible] to the Government monopoly of Seals on the Alaska Islands had been [illegible] to [illegible] breeding females, [illegible] added to the one male stock, and that the total number would not be much less than 1,000,000.

The description of the Earless Seals forms nearly one-half of the volume. The technical history of the group is given at length and in good [illegible]. The genus Phoca of Linnæus [illegible] four species now known in four distinct genera and in three [illegible]. Since Linnæus distinct specific and varietal names have been bestowed upon what our author considers as sixteen species. These are located in three sub-families and placed in

eleven genera. Copious synonymic details are given. Of the restricted genus Phoca, three—*P. vitulina*, *P. Groenlandica*, and *P. fœtida*—are marine, and frequent the northern oceans, never descending anywhere near to the equator. A fourth, *P. Caspica*, is found in the Aral and Caspian Seas, and a fifth, *P. Sibirica*, is from Lakes Baikel and Oron. *Monachus albiventer* occupies an intermediate position (Mediterranean, Madras, and Canary Islands) between these northern forms and the Antarctic species, such as *Macrorhinus leoninus*, *Ogmorrhinus leptonyx*, *Ommatophoca rossi*, and the like. All the species have strong social instincts, and are almost unsurpassed in their affection for their young. Most of them are gregarious; few of them are in the least ferocious; they are in general patient and submissive creatures, quite harmless to man. Fond of basking in sunshine, they spend a good deal of their time out of the water, on bank, rock, or ice. They are very voracious, eating fishes, or in lack of these, mollusks and crustacea. Strange though it may seem, the young seals take to the water reluctantly, and have to be actually taught to swim by their parents. The young of some species remain on the ice until they are from two to three weeks old, or until they have shed their first soft woolly coat of hair; their cry is more of a bark than a roar; that of the young is a kind of tender bleat, putting one in mind of the cry of a young child. Dr. Murie (*Proc.* Zool. Soc. London, 1870) has characterised three distinct modes of terrestrial locomotion among these Seals, from which it would appear that the Phocine Seals generally have considerable power of movement upon land.

The Seal-hunting districts are described at length; the oil and skins of these Seals having a large commercial importance. The Dundee sealers took in 1876 nearly 40,000*l.* worth. The habits of the various species form a most interesting portion of this division of the volume, and the author seems to have ransacked every treatise on the subject so as to make his own complete. This history of the North American Pinnipeds will long remain a perfect monograph of a valuable and important group of mammalia.

CATALOGUE OF NEWCASTLE LIBRARIES

Newcastle-upon-Tyne Public Libraries. Catalogue of the Books in the Central Lending Department. Compiled by W. John Haggeston, Chief Librarian. (Newcastle-upon-Tyne: 1880.)

NO portion of a book draws more heartfelt commendation or more earnest rebuke from a critic who has read it, not for the purpose of criticising, but for that of using its information, than the index. Only the reader who picks up a book for recreation and amusement feels at all independent of it; and even he appreciates its importance if any future reference is required. And if a good table of contents is so requisite in the case of a single book, how far more so must one be in a large library.

We have here a new catalogue of a new library, a selection of 20,000 volumes of books chosen for their readable value only (which perhaps justifies the omission of all dates of publication of the books, which would be a fault in a catalogue of most libraries), and consequently we may look to it as a model of what a catalogue should be. And we shall not be disappointed. It is drawn up on the same scientific principles worked out so fully in Dr. Billing's catalogue of the U.S. Surgeon-General's Office, which we noticed lately; and these so well worked out too, that really it is a table of contents of the library; the matter contained in the volumes of the latter as well as their titles are all laid before us. Each work is entered under the author's name, under the title, and, in cases where that title is compound, under each of the subjects it may include. Under the heading of each principal subject treated a reference is again given to the work with its library number, and so numerous are these cross references that on an average every volume throughout the library appears four times over. Indefinite titles are rectified by a summary being given, in a smaller type, of the matters discussed.

Catalogues which limit themselves rigidly to the contents of the title-page abandon all attempts at completeness, since many titles do not even pretend to express the subjects of the book (need we cite Mr. Ruskin's?), and many equally fail in the attempt. As the field of literature increases, and not even a librarian can keep himself acquainted with the ground gone over by all the books under his care, a subject-catalogue as well as an author- and title-catalogue becomes a necessity, and, if it is well drawn up, though it may cost both money and time, they will be well spent. Volumes that appear unattractive enough to the general reader, and are far too numerous for the ordinary student to search through, become suddenly, through a subject-catalogue, of the greatest value to both of them. The books in a library whose contents are thus laid open to its frequenters will be read with profit much greater than would a considerable fraction more books whose title-page was all the introduction their readers had to them.

And the saving of time when it is completed will be immense. It will save the time of the librarian by preventing hundreds of inquiries being made at all, and still more by strengthening the hands of his assistants, who will be capable of working his catalogue to the utmost and answering a very large proportion of such inquiries as are made by readers who may be awkward at it; it will save the time of the busy man, who wants his information at once; it will save the time of the student who wants the most recent information which he can get; and it will save the time of all by making fewer changes of books necessary.

All this is doubly important in a Free Library, because, as any one taking an interest in these institutions will have marked, those of its readers who do not confine themselves to novels seldom take out books for the mere pleasure of reading, as the higher classes do. Reading has not yet become a recreation to them, but they go to the library as to a great encyclopædia to get information on certain subjects, often of the most technical character; and a catalogue that directs them to the very book they want doubles and trebles the value of the library to them. They have no time to read all the *critiques* and *résumés* of new books with which the press teems, and which make the style and contents of many such works familiar to readers of periodicals who may never have seen the works

themselves. Where hundreds go in an evening for books it is impracticable to allow them access to the shelves of the library to select them; while in an ordinary bare list of titles it is impossible for them to judge which book in a column will be found the one most to their requirements.

Like Dr. Billings, our Newcastle librarian has fully worked out a most important branch of a subject-catalogue. Magazine literature in these days has become far too important to be treated by either a thrifty librarian or an inquiring student as "fugitive" and "ephemeral." All the newest science now appears first in journals, and all leaders of thought give their first expression of it in magazines and reviews. In this new catalogue therefore we are much pleased to see that not only is each volume of all important periodicals entered separately with its list of articles, but, as we have said, under the head of each subject a reference is given to all of such articles as bear upon it. By this means students who have read a standard work published a few years ago upon any subject will be not only guided but stimulated into reading the latest researches or theories which these publications contain. It is perhaps going beyond our subject, but we cannot help noticing how convenient for this important purpose a card-catalogue at a library is; in which cards containing the subject of each article down to the last number of all the magazines have been dropped into their places. Such an arrangement would make many students feel a printed catalogue to be ancient by the time it was published.

The selection of books as a whole is admirable—though of course few selections have been made under such favourable circumstances. We are rather surprised in so large a list to note the absence of books like Boyd Dawkins's "Cave-Hunting" and "Early Man in Britain," Clifford's "Lectures and Essays," Croll's "Climate and Time," Moseley's "Naturalist on board the *Challenger*," and Sir Wyville Thomson's book; Hæckel's "History of Creation" and "Evolution of Man"; Schliemann's "Troy" and Cesnola's "Cyprus"; Wallace's "Geographical Distribution of Animals," &c. And if some of these are so costly as to be confined to the Reference Library, as is probably the case here, still we are sorry to miss Wallace's "Tropical Nature," and R. Jefferies ("The Gamekeeper at Home") with his series of books teaching men to open their eyes as they move about the fields and lanes.

The printing is a credit to both printer and editor. It is almost as funny as the "Ingoldsby Legends" to read "Life and Remains of *Dean* Hook," by Barham! but it is plainly a slip, and the smallest errors are very scattered.

The Rules and Regulations are clumsy to enforce, which indeed will probably not be attempted, at any rate for long. The annoyance of having to get a guarantor practically shuts out many whose hitherto idle life might have taken a fresh start if books had been put into their hands freely. We have been very pleased to see that several large libraries have done away with this irritating system without any loss of property, and it seems a step backwards when a new institution like this starts with more rigid and inconvenient rules than many others. Indicators are capital things in libraries to which each reader goes for his own book as at a university, but only very few of the hundreds who exchange books every night at a flourishing Free Library are at all able to work with them. Children are the usual messengers, not high enough to consult an Indicator of 20,000 volumes. It is an unmerciful rule that borrowers should return their books personally, and a downright unreasonable one that every book must be returned in a fortnight (Rule 17), NOT to be re-issued the same day (Rule 16), although we are told (p. vi.) that three-volume works are issued complete. Few Free Library readers can get through 600 or 800 pages in a fortnight. And surely it was not necessary to threaten each person who consults the catalogue with imprisonment *with whipping* if he defaces a book! It may be necessary to make such Draconian laws, but they should be brought forward to intimidate gross offenders, not flourished in the face of all whom we wish to attract. Such severe rules repel sensitive people, while from their very familiarity they lose their effect on the careless.

OUR BOOK SHELF

Botanische Jahrbücher für Systematik Pflanzengeschichte und Pflanzengeographie. Herausgegeben von A. Engler. Erster Band, zweites Heft. (Leipzig: Wilhelm Engelmann, 1880.)

THIS part includes four papers. The first is by W. O. Focke, on the natural divisions and geographical distribution of the genus Rubus. The characters chiefly discussed are:—1. Mode of growth or habit. 2. Forms of leaf which are very numerous: the duration of the leaf being also variable. 3. Characters derived from the stipules, which are considered of great value. 4. Inflorescence; and 5. the Structure of the flower. The number and size of the parts of the calyx and corolla vary, as also the colour of the corolla. The stamens vary in closely allied species, and while most of the species are hermaphrodite, some are unisexual. The structure of the gynœcium is very varied, the number of carpels being five or six in some, as in *R. dalibarda*, or above 100, as in *R. rosæfolius*. The hairs (trichomes) on the different parts of the plant are very numerous and remarkable for the variety of structure shown; no other group, except perhaps some Solanaceæ, approaching the Rubi in this particular. In regard to the geographical distribution the most important points are:—1. The characteristic difference in the Rubi of Eastern Asia and Europe. 2. The predominance of European forms in the Atlantic, and of East Asian forms on the Pacific side of America. 3. The occurrence of south Chinese and north Indian types in Mexico and Peru. These peculiarities Focke would explain on geological grounds.

The second paper is by Franz Buchenau on the distribution of Juncaceæ over the world. The author gives a complete list of the species of the genera Juncus: Luzula, Rostkovia, Marsippospermum, Oxychloë, Distichia, and Prionium, and a table showing their distribution into regions nearly corresponding to those of Grisebach.

Koehne, in the third paper, gives the first portion of a monograph of the Lythraceæ, including a key to twenty-one genera. He admits and then describes thirty-one species with numerous varieties of Rotala (Ammânia, Linn., Benth., and Hooker).

The last paper is by Engler. Contributions to the knowledge of the Araceæ, in which he describes some new Araceæ from the Indian Archipelago and Madagascar, and also directs attention to the cultivation of *Zamioculcas Loddigesii* from the detached leaflets of the remarkable pinnate leaf of the plant. A swelling occurs at the base of the leaflet, and in a few days a small tuber is produced which develops two buds, below each of which roots are formed. The plant has been propagated in this way by Herr Hild of the Kiel Botanic Garden.

The Fishes of Great Britain and Ireland. By Dr. Francis Day, F.L.S., &c. (London: Williams and Norgate, 1880.)

THIS work is to be issued in nine parts, of which the first, containing sixty-four pages of text and twenty-seven plates, is now published. Waiting until the completion of the work for a more extended notice, we may for the present mention that in it the author purposes to give a natural history of the fishes known to inhabit the seas and fresh waters of the British Isles, with remarks on their economic uses and on the various modes of their capture, and that an introduction to the study of fishes in general is promised.

The synonymic lists of the species are given in great detail; the descriptive diagnoses treat of internal peculiarities as well as of external form; a good many interesting details appear under the headings of Habits, Means of Capture, Baits, Uses. The plates are from drawings by the author, and are very excellent.

A Manual of the Infusoria. By W. Saville Kent, F.L.S. (London: David Bogue, 1880.)

THIS sometime promised work has now advanced so far in its publication as the third part; when completed it will merit a somewhat lengthened notice, as the most important work on the subject which has issued from the British press. It is intended to include a description of all known flagellate, ciliate, and tentaculiferous Protozoa, British and foreign, and an account of the organisation and affinities of the Sponges. Each part (roy. 8vo in size) contains over 140 pages and eight plates. The general get-up of the work is magnificent, rather too much so for the poor student, already weighed down by the burden of the parts of Stein's "Infusionsthiere," but very pleasant for the book fancier, and forming an imposing shrine wherein to inclose the records of these early-life forms.

The first five chapters (pp. 1-194) are introductory, treating of the general history of the group: on the sub-kingdom Protozoa, on the nature and organisation of the Infusoria, on spontaneous generation, on the nature and affinities of the sponges. The sixth chapter treats of the systems of classifications of the Infusoria, adopted by various authorities, from the time of O. F. Müller to the present date. The seventh chapter commences the systematic description of the Flagellata. The third part, just published, carries the work as far as the 432nd page and to the twenty-fourth plate.

A Complete Course of Problems in Practical Plane Geometry . . . with an Introduction to Elementary Solid Geometry. A New, Revised, and Enlarged Edition. By J. W. Palliser. (London: Simpkin, Marshall, and Co., 1881.)

THIS is a cheap manual, the cost of which can be easily met by any artisan desirous of studying the subject, while at the same time its contents enable it to fully satisfy the wants of all examinees in first, second, and third grade and similar papers of the Science and Art Department Examinations. The figures are very clearly drawn, well showing given, constructional and required lines; the form of the page enables four propositions to be fully treated of with the accompanying figures in four spaces on each page. In the constructions we do not look for novelty, but we have conciseness and great clearness generally prevailing. Here and there elegance of expression is sacrificed to brevity ("for all the Government examinations, the requirements of which this is a text-book, the same rules will apply, with exception of Nos. 1 and 6"). We have detected only three points which call for our notice: in Prop. 12 it strikes us as being simpler to use the same radius throughout, thus doing away with the necessity of taking two cases, as Mr. Palliser does; in Prop. 37, *note*, it is necessary to add *how* the point is obtained; in Prop. 212 the letter E is made to do double duty in the proof. We can confidently recommend the book.

Bericht über die Thätigkeit der Botanischen Section der Schlesischen Gesellschaft im Jahr 1877. Erstattet von Prof. Dr. Ferdinand Cohn.

MOST of the papers in this part are in abstract; a few however are given at some length, and are of considerable interest. The additions to the phanerogamous Flora of Silesia and the record of new localities for rare plants occupy a considerable part of the pamphlet. Perhaps the most interesting paper is that on the Date-palm and Palm-forest at Elche in Spain, by General von Schweinitz. The palms there grow to a height of from seventy-five to eighty feet. The plants grow for about 100 years, then become stationary, and next decay. Each tree bears from the fifth year two to five bunches of fruit, each with from 500 to 600 dates, the weight of dates yielded by one tree being sometimes three centners. Many of the papers in this part are contributed by Goeppert and Cohn, and deal with all departments of botany. Dr. Thalheim describes a series of models of diatoms made in paraffin and glycerine soap, which exhibited the structure of all the chief groups of this order of plants.

LETTERS TO THE EDITOR

[*The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts. No notice is taken of anonymous communications.*

The Editor urgently requests correspondents to keep their letters as short as possible. The pressure on his space is so great that it is impossible otherwise to ensure the appearance even of communications containing interesting and novel facts.]

Dr. Carnelley's Hot Ice

THE remarkable observation made by Dr. Carnelley that ice in a vacuum is very permanent, even though surrounded by and apparently in contact with very hot bodies, has caused him to suppose and maintain that the ice itself is at a high temperature; a supposition which has been apparently confirmed by preliminary calorimetric determinations. This proposition has naturally met with a good deal of scepticism, and certainly requires ample and cautious verification; but I venture to think that there is nothing in it contradictory to our present knowledge of the properties of matter, though if verified (as, for the reasons to be stated, I fully believe it will be) it constitutes an important addition to that knowledge.

The notions which have occurred to me have made the essential part of the phenomenon so much clearer to myself that I fancy they will not be uninteresting to your readers.

By the term "vapour-tension" at a given temperature I mean, as I believe is usual, the pressure at which a liquid and a vapour can exist permanently together at that temperature, or the maximum pressure which the vapour is able to exert at that temperature, or the vapour pressure under which a liquid ceases to evaporate, or the total pressure at which it begins to boil. By the term "boiling-point" I mean the temperature of a liquid under a total pressure equal to its vapour-tension.

Now in order that a solid may sublime or pass directly into the vaporous condition without melting, it must be either at a temperature below the melting-point, so that no liquid attempts to form, or else at such a temperature that any liquid formed shall instantly evaporate; which it would certainly do if it were above the boiling-point, that is if the total pressure on it were less than the vapour tension.

A solid, under either of these circumstances, gives off vapour from its free surface at a rate depending on, but not necessarily proportional to, the supply of heat; for there is no definite subliming point for a solid, any more than there is a definite evaporating point for a liquid, so that the temperature of the solid need not remain constant. When a liquid is evaporating, the more you heat it the faster it evaporates, but not at a compensating rate, and the temperature rises as well: if this be true for a liquid, much more will it be true for a solid, whose

always more encumbered, partly, no doubt, aporating surface is a fixture.
of temperature of a liquid is its boiling, but nted it may get superheated; and, unless the ntegrate internally) it can become superheated The possibility of this internal disintegration we reetly, but at present we will consider it practi-

ien that a subliming solid always rises in tempe a sufficient rate, and Dr. Carnelley's proposition

that no liquid can exist at temperatures below bove its boiling point, on that if we wish to bility of its existence, we need only make the e side. This can always be done by diminishing the boiling-point of all substances is greatly es of pressure, while the freezing-point is only and even in the case of ice, in the opposite

the solid below its melting-point, and reduc till the boiling point coincides with or passe -point. There is now no region where liquid e solid must therefore be done by diminishing ume any temperature you please; and the more pressure may be brought to bear upon it to melt, for the pressure may be all-well ing short of the vapour-tension at the tem erated sufficiently, then the whole atmosphere st to, and ice melting will ensue. All that heat shall be supplied at a sufficient rate to rapid evaporation (which however will not the vacuum and so prevent the temperature ing point; for if it reached that point all ufy, and the whole fall to the freezing-point

re remark, the proposition that if, by the pr e boiling-point to coincide with the given te we must go to get the ice which temperature, it may be that 120° is the temperature; and that what 120° will be ll melt no matter how much pressure is ap prevent the melting. If it will not melt d to 100°, even with the greatest pressure and the whole will be at 0 centigrade, what rect, that the freezing-point of ice is lo

ne considered.

that if a solid is perfectly homogeneous its interior it would not melt, for it would r readily by application of pressure to the rid, such as would be required to take the determine a sufficient result. In fact, I experiment has indeed been previously p experiment of the same character as that ice, and in connexion with the latent heat ntly, such as would be required to take the rface is another thing altogether. Here the ature is not uniform throughout the mass, ature throughout the mass, and the pressure ly, the whole mass would be in a state of ow the solid, and above the vapour, the ange between temperature and pressure will after that to which corresponds the boiling- and the pressure exerted by the vapour at ce the pressure on the solid is equal to the ermined. There are still many questions very slowly, much more slowly in fact than ly way, such more slowly as that the ice is there artificially maintained.

is permitted the ice will cool the 12 to 0°; and these two—viz. that of any continuous ice below the boiling point, and liquefaction rapidly spreads, the ice is melting at the rate

ice in therefore will not occur while the tem at it will set in at a great pace if a body at 0

to become stationary or to fall, unless there be an utter absence of nuclei. If the temperature rise very high the pressure of the internal vapour will of course be great, and ultimately might even be able to burst the ice, but this would scarcely occur under several atmospheres.

It would be interesting if Dr. Carnelley would kindly try the following experiments:—

1. Heat ice *in vacuo* with a pressure gauge, and, till heating it, stop the passage to the condenser so that the pressure is allowed to accumulate, and note the pressure and temperature when collapse occurs.

2. Heat ice up to any temperature, and, still maintaining a good vacuum, remove the supply of heat, and see if the ice does not boil/rise.

3. Heat the ice up to 120°, and, still heating it, let in the atmosphere gently (but make the air move in though hot pipes, or it will melt the ice), and see if the ice does not rather longer than it would have done in the vacuum, because the evaporation will be more obstructed. But if the second experiment succeed, the temperature must never be allowed to fall much or to remain stationary long.

Finally, it is important to point out explicitly that the Carnelley experiment has nothing to do directly with pressure. Our knowledge on this point resembles what it was, viz. that the value of $\frac{dp}{dt}$ is not zero (centigrade) = 0·0071; that is to say, the melting-point is raised (all at once) 1° centigrade per atmosphere of pressure (not exactly so, but so nearly).

Of course this number is not absolutely constant, but its variation with pressure is very slight, and moreover has no bearing on the Carnelley experiments, as was mutually but erroneously supposed by Prof. Thomson in the *Proceedings* (18), and I believe also by Prof. Ayrton at the Chemical Society, though I had said the reverse of before.

OLIVER J. LODGE

University College, London

NOTE.—While referring to the above record experiment (that the melting-point of ice is not depressed) I ought to remark "that I thoroughly experimented with the vapour-tension of ice at the temperature of boiling water, by the use of water at the same temperature previously boiled to expel air, and found [illegible] to be that of water at the same temperature. See Phil. Trans. 1876, p. 168. I have also experimented on the vapour-tension of various mixtures of ice and salt, and found that the temperature of the mixture was not depressed while any ice remained unmelted, but as soon as the ice began to melt, the temperature fell at once. The vapour-tension of the mixture was found to be exactly that of water at the temperature of melting ice. I think the Carnelley experiments must be explained in some such way as this, but I have not yet had time to investigate the matter thoroughly."

O. J. L.

[illegible]

On the Spectrum of Carbon

I HAVE a great desire for the Watt [illegible] to continue the measurement of the spectrum of carbon, which I began in 1875, and which was published in the Phil. Trans. for that year. I made [illegible] expect that [illegible] I would [illegible] I would [illegible] I have long [illegible] I would [illegible] I would [illegible] I would

that even with joints all made by fusion of the glass it was well nigh impossible to get rid entirely of hydrogen. Mr. Crookes has, I believe, found that the last traces of moisture adhering to glass can only be expelled by heating to the softening point of the glass. This tallies with my own experience. In a series of experiments on the ultra-violet water spectrum I had occasion to photograph the spectra of sparks in sundry gases wet and dry, and found that in gases which had been passed through a tube full of phosphoric anhydride the water-spectrum still appeared strongly. Even when the gas had been passed very slowly through two tubes each half a meter long filled with calcium chloride, and then through a similar tube full of phosphoric anhydride, and the part of the tube where the wires were sealed had been heated strongly for a long time, while the current of gas was passing, traces of the water spectrum still often appeared. But Dr. Watts did not see the hydrogen lines in his tube. My difficulty has always been to avoid seeing them when the pressure of the gas was sufficiently reduced and a large condenser used with the induction coil. True: tubes if gas may not always show them even when hydrogen is known to be present. The spark takes a selected course of its own, and does not always light up all that is in the tube. Carbonic oxide does not generally show oxygen lines, and in tubes exhausted by a Sprengel pump the lines of mercury do not usually appear until the pumping has been carried far. A real test would be to see whether when the spark gives the line-spectrum of carbon the hydrogen lines do not also appear. The experiment with naphthaline Prof. Dewar and I have repeated and discussed elsewhere, so I will say no more on it than this, that purity in regard to chemicals is a relative rather than an absolute quality, and that it is only from a long series of experiments chosen with a view to eliminate the effects of accidents of all kinds that any safe induction in this kind of spectroscopy can be reached.

Cambridge, January 4 G. D. LIVEING

[To save time we submitted Prof. Liveing's letter to Mr. Watts, who sends the following reply.—ED.]

I SEE no reason why india-rubber stoppers may not be used in the construction of an apparatus to be filled with a gas *at atmospheric pressure*, or nearly so. The case would be altogether different if we were concerned with the construction of a vacuum tube, and I take it that most of these statements of the difficulty of getting rid of the last traces of moisture and of hydrocarbons adhering to the glass refer to cases where the pressure is to be only a few millimetres. But when a current of cyanogen at atmospheric pressure, made from dried mercuric cyanide, is passed through a U-tube filled with phosphoric anhydride, the gas is surely dry to all intents and purposes. I do not say that the glass would not give off traces of moisture, &c., if the pressure were to be reduced to an extreme point; at least there can be so little hydrogen present in the tube that to ascribe the spectrum given by the tube to the hydrogen present in it is to set up an extreme hypothesis, which must be supported by cogent experimental evidence before it can be accepted.

But if the defect of the experiment be in the use of india-rubber there can be no great difficulty in constructing the apparatus entirely of glass, and if we are to give up the view that the groups *h* 15165 to 50820 and 54938 to 54780 are due to carbon, it must be shown that they are not present in the spectrum of the spark in cyanogen at atmospheric pressure when sufficient precautions are taken to obtain the gas pure. I have never examined the spectrum of the spark in cyanogen without seeing them, and have every confidence that Prof. Liveing will still find them there after he has taken all the precautions he may think necessary.

But admitting, for the sake of argument the justice of Prof. Liveing's contention that the cyanogen in my experiment contained a trace of hydrogen and that the naphthalin contained a trace of nitrogen, then this seems to be the theory offered for our acceptance—that the spark in nitrocarbon gas containing a trace of hydrogen gives the lines of hydrocarbon, and that the spark in hydrocarb in gas containing a trace of nitrogen gives the lines of nitrocarbon. Does Prof. Liveing hold *both* of these hypotheses to be reasonable?

W. M. WATTS

Geological Climates

THE letter of Prof. Haughton in last week's NATURE so bristles with figures and calculations that some of your readers may feel a little puzzled and may be unable to detect the fallacies that lurk among them. The question is far too large a one to be fully discussed in your columns. I shall therefore confine myself to pointing out the erroneous assumptions and false inferences which vitiate all the learned Professor's calculations, having done which my own theory will remain, so far, intact.

The whole argument against me is based upon an "ideal ice-cap," extending from the Pole to lat. 60°. A considerable but unknown thickness is given to this imaginary field of ice, and it is then calculated that the three great ocean streams, even if admitted to the Arctic area in the manner I suggest, would not get rid of this mass of ice. There are however several important misconceptions and illogical deductions underlying the whole argument, and when these are exposed the results, however accurately worked out, become completely valueless.

We first have it stated that if heat and cold were uniformly distributed over the Polar regions the whole would be permanently frozen over, and an ice-cap be formed of great but varying thickness, diminishing from the Pole to about lat. 60°. But even this preliminary statement is open to serious doubt; for ice cannot be formed without an adequate supply of water, and over a large part of the Polar area no more snow falls than is annually melted by the sun and by warm southerly winds blowing over the heated land-surfaces of Asia and America. Admitting however that any such ice-cap could be formed, it would certainly not form in *one year* but by the accumulations of a long series of years; and any estimate of the *total* heat required to melt it has no bearing whatever on the *annual* amount that would be sufficient, since this depends solely on the average thickness of the ice *annually* formed, of which Prof. Haughton says nothing whatever.

The amount of rainfall in the Arctic regions (mostly in the form of snow) is certainly very small. It is estimated by Dr. Rink to be only twelve inches in Greenland, and this is probably far above the average. All that falls on the inland plains of Asia, Europe, and America is however melted or evaporated by the action of the sun and air far from the influence of the Gulf Stream. The thickness of ice formed annually over the whole area of the Arctic Ocean I have no means of estimating. In open water in very high latitudes it may be considerable, but perennial ice-fields can only increase very slowly. I should therefore very much doubt if the thickness of ice now formed annually over the whole Arctic area averages nearly so much as five feet: and Prof. Haughton himself calculates that our own Gulf Stream is now capable of melting this quantity.

The first assumption, therefore—that the amount of heat required to be introduced into the Arctic regions in order to raise their mean temperature above the freezing-point is "accurately measured" by the amount required to melt an "ice-cap" covering the whole area to a thickness of several hundred feet—is grossly erroneous; and it is so because it takes the hypothetical *accumulated* effects of *many years* Arctic cold under altogether impossible conditions, and then estimates the amount of heat required to melt this whole accumulation in *one year*!

But we find a second and equally important error, in the assumption (involved in all Prof. Haughton's arguments and figures) that all the ice of the alleged "ideal ice-cap" must be melted by that portion of the Gulf Stream which actually enters the Polar area, where its temperature is taken to be 35° F. or only 3° above the melting point of ice. A large quantity of the Arctic ice, however, even now floats southward to beyond lat. 50° in both the Atlantic and Pacific, and is melted by the warmer water and atmosphere and the hotter sun of these lower latitudes. Now, as it is a essential part of my theory that much of Northern Asia and North America were under water at those early periods when warm climates prevailed in the Arctic regions, it is clear that whatever Arctic ice was then formed would have a freer passage southwards, and as the south-flowing return currents would then have been more powerful and more extensive than at present, a much larger proportion of the ice would have been melted by the heat of temperate instead of by that of Arctic seas.

Prof. Haughton admits that the Kuro Siwo and the Mozambique currents together, if they entered the Polar seas, would be equal to the melting of a layer of ice more than thirteen feet thick over the whole area down to lat. 70°. But if our own Gulf Stream is sufficient to get rid of the whole of the ice that now forms annually—as Prof. Haughton's figures show that it would probably be, and as it would be still more certainly were Greenland depressed, thus ceasing to be the great Arctic refrigerator and ice-accumulator—then the heat of the other two currents would be employed in raising the temperature of the Arctic seas above

g-point: and if we take the area of the water a- l to that of the land, we shall have heat enough to hole Arctic ocean to a depth of full 180 feet more ., or to a mean temperature of 52° F., and as this ly a still higher surface temperature it is considerably *I require*.

herefore Prof. Haughton can prove that the amount forming *annually* in the Polar regions is *very much* n average of five feet thick over the whole area, his demonstrate my case for me, since they prove that the ent of land and sea which I have suggested would ermanent mild climate within the Arctic circle and lly raise the mean temperature of all north-temperate

summarise my present argument:—Prof. Haughton's *l error* consists in assuming that the true way of the amount of heat required in order to raise the of the Polar area a certain number of degrees by— pose an accumulation of ice indefinitely *greater* than sis, and then to demand heat enough to melt this *n annually*. The utmost *possible* accumulations of retic area, during an indefinite *number of years*, and ost *adverse physical conditions* imaginable, are to be *one year*; and the heat required to do this is said "accurate measure" of that required to raise the of the same area about 20°, at a time when there great accumulations of ice and when all the phys- *s adverse* to its *accumulation* and *favourable* to its e immensely more powerful than at present!

fundamental error is corrected, it will be seen that tion's calculations are not only quite compatible s, but actually lend them a strong support.

ALFRED R. WALLACE

---

rtesy of Mr. Ingram I am enabled to say that the ir supposed to be *Araucaria Cunninghamii* is in rnised by Capt. King, *Cunninghamia sinensis*, *hamii* is a native of Southern China, hence it duced into Japan. In this country it was origi- *ler glauca*, but, as the instance at Ickworth illus- it is not absolutely requisite. The tree is however ler, and so far as I know has never produced its ler, and so far as I know has never produced its country in the open air.

country, in this country it may be well to ambocks hardly in this country, it may be well to are not familiar with the plants not to expect to and rapidly growing trees that grow under this pies. Rarely indeed do they attain in this country even of the *Araucaria*, so familiar to travellers ccuracy of nomenclature is proved in this and the ice to be a matter of much moment, it may be the authority of the late General Munro that the nt commonly grown in gardens as *Pseudotsuga* correctly called *Abies douglasii*. The tree correctly called *Pseudotsuga Douglasii*. The tree of gardens is the true *Taxodium distichum*, and that the Japanese *Sequoia gigantea*, as, and that the Japanese *Sequoia gigantea*, as, and that the Japanese *Sequoia gigantea*, as

anthracite, ought not to rejoice in a pure and transparent atmosphere.

Similarly, the South Wales coal and iron districts would be centres of fog clouds and mist, like Birmingham and Newcastle. But they are as free from fog as the purely pastoral valleys of Wales.

Next, as to persistency. Early in the morning of January 31 last, in some districts of London the fog extended considerably above the tops of the houses, in others only about 10 or 20 feet from the ground in my immediate. Where the fog extended high the smoke mixed with it and produced a yellow fog, but where it remained low the smoke escaped into the upper air and drifted away, leaving a white fog below, so pure as to be a very unusual phenomenon at 10 A.M. in a London street. Now it was remarkable that wherever the white fog prevailed in the morning, the sun soon shattered the misery and dispelled it more or less, but in the smoke-charged districts a dark yellow fog continued throughout the day.

White fogs may doubtless be exceedingly dense. But will not an admixture of smoke increase its density?

A humid atmosphere is not necessary for the production of mist and fogs. The frequent long-continued prevalence of blue haze over the whole country, not excepting the east coasts, in the driest east winds of spring, would be a subject deserving investigation. They sometimes extend to a height much above the tops of our highest mountains. Experiments such as those of Mr. Aitken will, we may hope, ultimately solve this problem of meteorology.

R. RUSSELL

Low Temperature

THE reading of the thermometer last night, January 15, 16, was the lowest ever recorded at this observatory in the course of thirty-three years. The reading was 4°6 F., the previous minimum having occurred on December 24, 1860, when the mercury stood at 6°5 F.

S. J. TERRY

Stonyhurst Observatory, January 16

A "Natural" Experiment in Polarised Light

PLACE on a plate of ice and hold it between the eye and a pool of water. Its reflected image will show the brightest colours due to polarised light. The incident rays should come from a part of the sky about 90° from the sun, and reflection should take place at the surrounding angle for water, and the glare will probably require adjusting to bring out the tints in effect. Water, various oils, and liquids that mingle with water, crystal, and analyser. I do not remember to have read any account of this very simple experiment, for which Nature provides all the materials.

CHAS. T. WHITMELL

9, Beech Street, Hillsgrove, January 16

STATICS AND DYNAMICS OF SKATING

MANY years ago, when skating was but in its infancy, skates were made of bone, and if they could be made to stay on the feet they were considered to answer their purpose sufficiently well.

More recently iron runners with wooden heels came into use, and a contrivance of a fastenment on the toes, horizontally and longitudinally, was made easier by means of leather straps and screws passing into the heel of the boots; and these adjustments, made implements, were quite sufficient for the skating of those days, namely, forwards and curves.

Within the last dozen years, however, skating has made enormous strides, back skating becoming an essential qualification of a finished skater, and hence not only more perfect forms of skate are demanded from the maker, but also the adjustment of them on the foot becomes an important part of his duty.

There are three points to be attended to in the adjustment of the skate, besides the obvious one of placing the skate medially on the foot:

1. Height of turn of the ice where the greatest breadth of the sole of boot meets.
2. Height of foot on ice at the heel.
3. Position of the skate longitudinally or lengthwise on the foot.

First. The height of the foot from the ice should be such as will enable the skater to lean over sufficiently when on a curve, and such that he may be able to get a powerful enough stroke. If he is too low the edge of the boot will come in contact with the ice in leaning overt and also in taking a stroke: a fall ensuing in the first case, and a disagreeable and dangerous overstrain in the second. To avoid these the sole of the boot should subtend an angle at the bottom of the runner of about 96 deg. *i.e.* for a sole 3½ inches broad the edge of the runner should be 1⅛ inch from the sole, instead of varying from 1⅝ to 1¼ inch, which are the heights of skates commonly met with.

This angle of 96 deg. will be found to clear the ice in both striking and leaning over for most skaters, and any greater height than is given by this angle should not be used, as it is not necessary, and only throws an additional strain on the ankle.

Second. The height at the sole having been fixed, the next point is what should be the height at the heel? In fact is the foot to be parallel to the skate, or is it to rest on an incline?

Dove was the first person, in his "Skater's Monitor," published in Edinburgh in 1836, to write on the position of the skate on the foot, summing up his remarks by saying, "Level wards then are for shoes whose heels

and soles are equally prominent, but high heels must be sunk into the skate-wood." This was quite correct at that time, when back skating was little practised, and when the skate which was then worn was made very flat, in fact almost straight at and near the heel. Now, by universal consent for figure-skating, the iron is made a segment of a single circle from toe to heel, 7½ feet being the radius. Yet, notwithstanding these changes, Vandervell and Witham, as lately as January, 1880, in their "Figure Skating," recommend the very same parallelism of the foot to the skate instead of parallelism of the top of the blade to the ice, as it should be for modern skating, as I shall subsequently show.

In Fig. 1 is shown the result of adopting Dove's or Vandervell and Witham's position, *i.e.* no heel. It might be thought that a person standing on a curve would balance comfortably at the middle of the curve, but this cannot be, for a person standing naturally on a level surface does not distribute the weight of his body equally over the length of his foot, but by far the greater part comes on the heel, and therefore the centre of pressure of his body is nearer the heel than the toe, and consequently if he is standing on a curve the curve must roll up in front and down behind till the upward pressure of the ice just passes through the centre of pressure of his body. The point of contact of the skate on the ice will therefore not only be much behind the centre of the skate, but will be a little behind the centre of pressure of his body when standing on a level surface, as he now

an incline. Of course the footstocks of the
ing too low behind would produce the same
so low a heel to the boot, for throw the balance
ck.
hows the position the skate will have on the ice
is too high, *i.e.* the centre of pressure is thrown
ward, and consequently the skate must roll up
order to get the proper balance.
3 is shown a skate in the proper position on the
h the heel raised so high as to throw the centre
e on the centre of the foot and skate.
per height of the heel of the boot to obtain this
depend on whether the footstocks of the skates
is they ought to be, and the exact height will
different individuals, depending on whether
ally stoop or lean well back, and probably also
ots they are in the habit or walking in, and
an only be determined accurately by trial; but
heel is by no means too low for most purposes.
With regard to the adjustment of the skate
lly, Figs. 4 and 5 will show the advisable extremes
ng the skate properly on the foot: in Fig. 4 the
5 put too far forward, and in Fig. 5 too far

ow shown how to preserve the balance on any
t of the skate, it only remains to be shown
sition of the skate, with the balance on the
Fig. 5, is the proper one; and as the effects
us positions are most evident in skating turns
ing myself entirely to them, commencing by
heory of turns which I believe has never been
y explained.
sible in a few words to describe accurately
e forces which come into action in making a
y object will be attained by describing what
is the basis of the whole theory of turns, namely,
s not a twist round of the body made by the
e moment of the turn, but the turning round
e arrow *a* in Fig. 6, and being exerted at
is the result of a reaction of the ice on the
d by his putting his skate in rolling on to
set on in such a position as to make that jour
bite or grip the ice, producing a force oppo
not directly opposed to the direction of mo
allel to it. The direction of the reaction is
e arrow *a* in Fig. 6, and being exerted at
e from the body, it necessarily tends to turn
nd in the direction of the arrow. It will be
the greater the distance of the point of appli
force is from the curve the skater is describ
ater will be the force tending to turn round

r can be shown by means of a disk of lead,
h a light rod through it. If this be made to
e, and a force be applied to the rod at its
nger, the action of the hand will be at once shown.
skating it is found to make a big turn, and
better than about to make a big turn, and
ers near the beginning of his skate can do it
n only roll a very little further, and he is
wheel of his skate, the forward pressure of
arms to turn him round, will be almost nil.
ches being of the shape shown in Fig. 7,
ches shown in Fig. 6, and comes
ge of the skate shown in Fig. 5,
to turn round in time by mere pressure
e to turn round, which I consider more elegant,
round, which I consider more elegant,
ground accomplish. If the heavier pressure
trifle greater than are usually given by
of the forward turns are much larger than
hind hands during the turning to make
more difficult than is necessary, but even
more difficult than is necessary, but even
on the centre of the skate back turns will
than forward turns, as the tendency of
vents the bending arm of the first upon than
even with a hand on, whereas we can bend
easily.

With the influence of the centre of the skate back turns can be performed without any wrench or swing of the leg—a thing that is physically impossible if the balance is on the heel, as it must be in Dove's or Vandervell and Wilkinson's plates.

CHARLES ALEX. STEVENSON

JOHN DUNCAN, THE ALFORD WEAVER AND BOTANIST

ON the last day of 1880 the University of Aberdeen was presented with a herbarium of 1131 specimens of the British Flora, gathered, preserved, named, and mounted by one John Duncan, a weaver who lives near Alford in Aberdeenshire. He is no ordinary man, as the accumulation of such a botanical collection is alone sufficient to prove. It represents a portion only of the scientific labours of no less than forty years—for much of these have been destroyed by time and the moth. This remarkable man, who is now a pauper on the parish which it has been the work of his unextinguishable scientific enthusiasm should be better known to the scientific world, and a short sketch of his life and labours may not be unacceptable to the readers of NATURE.

John Duncan was born on December 24, 1794, so that he is now in his eighty-seventh year. His parents were very poor, and could afford him only the merest rudiments of even the three Rs as they taught, for his education had to be sacrificed to the pressure of penury. He learnt to read by laboriously spelling his way through the text at church; his writing has ever been very rude, but distinct, and his spelling is such an example of the phonetic as would delight Mr. Pitman. He was early sent to work and became a "customer weaver," making into cloth the thread and wool sent to his home by his neighbours, and such he has remained ever since. He married early in life, and had a son and two daughters; but his wife died more than thirty years ago, and all his family have gone, he remaining as the sole survivor. During the greater part of his long life he has dwelt in the valley of the Don, near Alford, and for nearly thirty years in the same cottage at Dunchestie, in the pleasant hollow of the Leochel, not far from Alford village. This cottage consists of a pair of dwellings, the other belonging to a farmer's family who prepare his simple meals. He occupies a single room, filled with the looms and other implements of his trade, even to the thatched roof, his bed is slung on some pegs laid across the rafters, and reached by means of a ladder. In this narrow space John Duncan has lived for twenty-eight years, a solitary man, as serene a saint as quiet, upright, and religious, workmen. Laboriously for an honest living, cheered only by the friendship of a few, by love of books, and his devotion to the study of botany, which he has prosecuted with a single-minded enthusiasm that is as rare as it is beautiful. I visited him about three years ago, and spent two days in his company, having come to consult him from what I look upon as his own town, his dearest friend and fellow student, Charles Cline. I found him in good health, working hard at his loom, a single, spare, and vigorous man, and perfectly well informed on the subjects about which he had corresponded with me. I found him, as I have found many others, a man who had made himself and the plants, which he gathered within a few miles of his home, the study of his life. He knew the habitat of nearly every plant which is found in the district, and the changes which have occurred in their history and distribution within recent years. He had also studied theology, and could talk on that subject with me for many hours, and was familiar with the writings of many divines, chiefly Scotch, and his intimacy with Charles, whose friendship he enjoyed almost from the date of his arrival at Alford, and with whom he corresponded and consulted for many years, was evidently regarded by him as the chief comfort of his life, and was cherished, nurtured, and fostered by him, the result of unwearied patience and wise contentment, the result of unwearied patience and wise contentment, by his life, character, influence, and wise counsels, and by his life, character, influence, and wise counsels, and

account I then gave of him. This account appeared in *Good Words* for April, May, and June, 1878, with pictures of himself and his cottage. It has recently been incorporated in whole into "Leaders of Men," by H. A. Page (Marshall, Japp, and Co., London); and he was visited by not a few kindly spirits whose open-handedness lightened somewhat the growing pressure of age and want. Since then he has worked at his loom, winning his daily bread with heroic struggle, till a short time ago, when decaying power and some paralytic touches, in his eighty-sixth year, compelled him reluctantly to give it up and remove from his small but honourable workshop and study to be kindly tended by the ditcher's widow. Many years ago his hard-won earnings—for he was always a most careful man—were dissipated through domestic causes over which he had no control attended with heavy griefs. Since then his growing age has barely enabled him to live more than from hand to mouth, and now for some time he has had to do what must be inexpressibly keen to an independent soul like his, to accept from the parish a pauper's portion.

From his earliest days, when he used to play upon the green cliffs of the high conglomerate coast of Kincardine, John Duncan had an intense love of plants, and long before he began their scientific study collected them for their medicinal uses, guided by Culpepper's "Herbal." It was not till he was forty years of age, when he was introduced in 1835 to Charles Black, that he commenced the study of botany as a science. Charles was a remarkable man, of great individuality and ability, and though twenty years his junior, at once gained over him an ascendency of the best kind, and inspired him with an ardent friendship that has been the sweetest solace of his long solitude. He still lives as the gardener he was then, a botanist, geologist, ornithologist, numismatist, scientific student, theologian, and omnivorous reader at Arbigland in Dumfries, near the mouth of the Nith. When these two men met, Charles was settled as gardener near Alford, and under his guidance John at once began the systematic study of botany. They soon conquered the flora of the Vale of Alford; the curious peak of Ben-a-chie, where they found at an early date the *Rubus chamæmorus*, or cloudberry, being a favourite haunt. John, having his time, as a home weaver, more at his own command, by and by extended his excursions to greater distances, and before very long did the most of the county. The enthusiasm with which these two humble men prosecuted their studies was wonderful, the morning light often surprising them at their work of classifying, drying, and arranging their accumulating treasures. The want of text-books of the science was sorely felt by them, and excited them to ingenious devices to supply it; a certain country inn, for example, being frequented by them, not for convivial purposes, but to obtain a sight of "Hooker," which had belonged to the innkeeper's dead son. The details of John's continued studies under poverty, difficulty, and trial are interesting and honourable, but these cannot be given here. In order to extend his knowledge of botany and the flora of Scotland he used to take harvest work in different parts of the country, studying in succession the plants of each district, till he had in this way traversed the most of the land from Northumberland to Banff, except some parts of the West and the Highlands; bringing home specimens living and dead, planting the one in his own neighbourhood, and adding the other to his rapidly-increasing herbarium. His knowledge of plants was minute and scientific, and the abundant technical terms were used with ease and intelligently understood by the help of a Latin dictionary he had purchased for the purpose; nor was it confined to mere technicalities, but extended to an unusual acquaintance with their habits, history, and uses. His collection of botanical works is surprisingly large and valuable, all purchased by his own hard-won earnings. His memory being as strong as his use of the pen was weak, he did not write down any details of the plants thus collected, but he could tell all these when asked with unerring precision, as well as relate the varied incidents, interesting, humorous, happy or hard, connected with their discovery. The names and localities have however been successfully obtained from him and written down, by the help of one of his disciples, Mr. J. M. B. Taylor, of Aberdeen, who prepared the herbarium for the University.

John kept his collection neatly laid down in volumes made by himself of newspapers of the period, of tea paper, which he thought a good protection against moths, and of other homely materials scented with camphor. Many of them of course decayed or were destroyed during the forty and more years they were in his possession, but even after discarding all imperfect specimens there remained 1131 plants now fully named, localised, and arranged by Mr. Taylor from John's unfailing memory. They are divided in four books, put together by John himself.

1. A general collection of some 500 specimens including ferns arranged according to the Linnæan system, 100 of which are described by Prof. Dickie, author of the "Flora of Aberdeen, Banff, and Kincardine," as rare or very rare.

2. An almost perfect collection of the flora of the Vale of Alford, many of the plants now uncommon.

3. Specimens of about 50 of the grasses from the Alford district.

4. Specimens of some 50 of the Cryptogamia of the district, chiefly mosses and lichens.

John never possessed above a few of *the very rarest* of our British plants, not having visited the higher mountains and outlying regions where only such are found, but had been fortunate in obtaining a large number of local and very local, rare and very rare species. They were mainly found along the eastern half of the country from Banff to Northumberland, excluding the Highlands.

Such is a very slight sketch of the life and labours of this remarkable weaver. The presentation of his herbarium has revealed the sad fact that, independent and toil-worn as he has ever been, even to nigh eighty-six, he has been lately compelled to bear the pain and shame of depending on the parish for his daily bread. His books are of value, and would alone fetch a considerable sum; but these, the dear companions of his life, he cannot bring himself to part with, though now unable to enjoy more than a sight of them. His beloved plants he would not barter for heaps of gold, and he has therefore presented them to Aberdeen University, there, it is to be hoped, not only to do good educational work, but to exercise an inspiring impulse over many generations of students privileged to examine these far-fetched treasures.

An appeal has recently been publicly made in favour of the aged botanist, to enable him to spend his few remaining days in comfort and independence, supported by the free-will offerings of the scientific and generous, which have been amply won by scientific work admirably achieved. Scientific societies throughout the country could not better aid research than by recognising his merit, and making a contribution for such a worthy object. Shortly after my account of him in *Good Words* the Largo Field Naturalists' Club elected John an Honorary Member, and the same has been recently done by the Inverness Scientific Society and Field Club, which also made a donation to him of 5*l*., examples that might be honourably followed by other societies. A lively interest has been excited in his case, and his been already substantially expressed. It is devoutly to be hoped that such a man will not be allowed to go down to his grave dishonoured and neglected.[1]

WILLIAM JOLLY

[1] Subscriptions may be sent to William Jolly, H.M. Inspector of Schools, Inverness.

'DO-CHINESE AND OCEANIC RACES—TYPES AND AFFINITIES[1]

IV.

are the Raja of Gorontalo, N. Celebes (Fig. 22), nief of Sendegeassi, S. Nias, West Coast Sumatra and two natives of Jilolo (Fig. 24), all sup- e more or less typical Malays whom it will be to compare with Figs. 19, 20, 21, representing sian pre-Malay or Indonesian element in the o. In Fig. 25 we have Mohamed-Yamdali- an of the Sulu Archipelago who was compelled Spanish supremacy in 1876. He is a pure ut thirty-four years old, like most of his sub- ating a fine type far superior to that of the Malacca. Yet the Mongoloid element is un- betrayed, especially in the high cheek-bones, such a striking contrast to the regular European the Indonesians (see Figs. 19, 20, and 21). The from a photograph forwarded to France by ano and Rey, and originally published in *Le* ril 3, 1880.

must speak with great hesitation and much re- mmon Malay type, we can speak all the more not only of a common Malay speech, but of a Malayo-Polynesian," and even of a common speech. Indeed the chief objection to the pression Malayo-Polynesian is that it is no ciently comprehen-ive. In the alternative , which, on the analogy of Indo-European, I ed as a substitute, the first component must two senses, so as to include both the Indian portion of Further India. When Fr. Muller much remains certain, and will never by the it and cogent reasonings be disproved: the nesians are connected with no Asiatic people," s mind not so much the "Malayo-Polynesian Malayo-Polynesian language. In this sense t was true enough according to his lights. In a other eminent philologists he entirely over- bojim, or from insufficient data probably s a monosyllabic-toned language allied to the family. He consequently considered it as y distinct from the Malayo-Polynesian group, nitedly polysyllabic and untoned. But we seen in Section IV. that Cambojan or a member of the Indo-Chinese family, and syllable and untoned, like all other known ech. In the above-named paper "On the and Inter-Oceanic Races and Languages" further show that the true affinities of Khmêr Malayo-Polynesian tongues, the whole st linguistic family stretching from Mada- ister Island, west and east, from Hawaii to north and south, and with its basis still Indo-Chinese peninsula, where it originated, has been diffused throughout the Oceanic migrations of the Mongolo-Caucasian races, ng reigned supreme, continually encroaching mingling, as in so many detached enclaves, rrito and Papuan tongues, but itself now extinction by the advancing Siamese and the mainland, and by the still more lish in Polynesia.

ecents establishing the intimate connection n and Malayan languages need not be that based on the principle of modifying attention, and is in itself so ected so much attention, and is in itself so ers of NATURE will perhaps be at the readers of NATURE will perhaps be re-united:—

ere re-united:—

the Khmêr and Malaysian tongues is peculiarly distinctive as of itself alone to establish their common origin. This identical infixes, which, though forming a marked characteristic of Khmêr, Malay, Javanese, Tagala, Malagasy, and other members of this group, has not yet been generally recognised. . . . The infixes in question are always the same, the liquids *m* and *n*, and even *mn*, with or without the connecting vowels *a*, *o* with *m*; *a*, *i* with *n*. Thus:—

IN KHMÊR: *m*, *am*, *om*, *mn*, *n*.

Slap, dead; samlap, to kill.
Srouch, pointed; sâmrouch, to point.
Thleak, to fall; tomleak, to throw down.
Roloun, to fall; romloun, to knock down.
Chereay, to know; chomreay, to do or, teach, make known.
Kar, to draw; kamnar, a design.
Srek, to cry; samrek, a shout.
Chlo, to chew; chomnoh, a part or portion.
Sauk, to corrupt; samnauk, a bribe.
Pram, to publish; hamram, a notice.
Pang, to wish; hamnang, a wish.
Kep, to confiscate; romkep, seizure, thing seized.
Ar, to saw; Anar, a saw.

IN MALAGASY: *in*, *om*.

Hanna, food; hopanna, to eat.
Tuly, to feed, a rope; lumdy, strong.
Taratra, glazing; tsinantra, transparent.
Sat-ina, overflowing; sonat-dra, bountiful.
Sany, likeness; somany, like.
Sify, spying; somify, spy—of distant object.
Vidy and sindy, to-day.
Valy and sivaly, broken.

IN MALAYSIAN: *um*, *im*, *in*.

Javanese.

Rayale, to bereave; rumaya, to be bereft.
Hurub, flame; humurub, to flame.
Tabuhan, a small drum; tinabuhan, a round gong.

Tagala.

Basa, to read; humasa, [-ma-] use of reading.
Kapatir, brother; kinapatir, brotherly.
Tapay, to knead; tinapay, bread.
Gunting, shears; ginunting, to cut with shears.

Malay.

Palu, to beat; pumalu, a stick.
Pakul, to subdue; kapukul, a hammer.
Sapit, to grasp; sumapit, to attack.
Padam, to extinguish; tumpadam, an extinguisher.
Pilih, to choose; pumilihan, choice (fig. 20 D).

This characteristic, of which nothing but the faintest echoes occur in any other linguistic system, is obviously one that is incapable of being borrowed. Hence it must be regarded as an original principle developed in the primitive speech before its differentiation into the various Oceanic branches, whose common origin seems thus to be established beyond question. The theory of such a remarkable feature being evolved independently at several points in this linguistic area and in no other cannot be seriously entertained.

Here therefore we have one type of speech everywhere common to two racial types, and the question arises, how all the Malayan peoples have come to speak exclusively polysyllabic untoned tongues, while their nearest kindred, the Mongoloid peoples of Indo-China, still speak exclusively mono-syllabic toned languages. To explain this phenomenon we must remember that, as already pointed out, the polysyllabic-speaking Caucasians preceded the monosyllabic-speaking Mongols both in Further India and in the Archipelago. Hence when the Mongols quitted the mainland they found the islands occupied by the Caucasians, with whom they amalgamated, and whose speech they adopted. Similar instances, though perhaps not on such a large scale, have occurred often enough elsewhere, even in historic times. Thus the Moorish Tatar Aimâ's and Hazaras of South Afghanistan now speak

[1] Continued from p. 250.

Persian; the Ugro-Finnic Bulgarians have been Slavonised in speech since the tenth century; the Northmen of the Lower Seine valley entirely forgot their Norse tongue within two generations, and many of the early English settlers in Ireland rapidly became "Hiberniores ipsis Hibernicis," more Irish than the "Irishry" themselves. Special causes, arising from the utterly antagonistic nature of toned and untoned languages, must have accelerated the process of assimilation in Malaysia, where nevertheless its universality still remains a remarkable circumstance. For it is undoubtedly surprising that not a single Malay community should have succeeded in retaining its original monosyllabic speech, and still more surprising to find that every trace of monosyllabism had already disappeared, at least from Java, Madura, and Bali some two thousand years ago. The old Kawi language current in those islands and reduced to writing by the Buddhists at that remote period is as genuine a polysyllabic tongue as its modern representatives, Javanese, Sundanese, Madurese, and Balinese.

FIG. 22.—Malayan Type: Celebes. King of Goa (Macassar).

The eastern or Sawaiori branch differs greatly from the western or Malayan, with which it has now really little in common beyond the fundamental elements. But these, after a separation of probably many thousand years, are still numerous enough to establish beyond all doubt their primeval unity. In this instance, however, as in so many others, community of speech in no way involves community of descent, for we have just seen that the language now spoken by the Malay races was in all probability imposed upon them by their Caucasian predecessors in the Archipelago. On the other hand there is no reason to suppose that the Eastern Polynesians ever spoke any other than their present language, its resemblance to the Malay being due not to their relationship with the Malay people, but with the Indonesian Caucasians, from whom the Malays borrowed their speech.

FIG. 23.—Malayan Type, Sumatra. Chief of Sendegeasel, Nias Island.

FIG. 24.—Malayan Types, Javanese.

Mueller and Forschhammer, Dodinga.

other members of the family Sawaiori is agglu-
but it occupies a very primitive or undeveloped
in that order of speech. Thus it betrays very
ces of the infix principle, but it possesses as a
same particle *mat*, which in Cambojan and its
n congeners appears as an infix. In Samoan,
nce, *fai* = to do, but *mafai* = to be able;
to spill, *masa'a* = spilt; *liligi* = to pour out,
to be poured out; *fasi* = to split, *mafasi* = to
off; *fati* = to break, *mafati* = to be easily
spread out; *fofola* = to spread out, *mafofola* =
read out; *gogau* = to shake,
= to be loose; *goto* = to sink,
to be sunk or waterlogged, and
nerally in an intransitive or passive

chief peculiarity of the Sawaiori
s their extremely simple phonetic
omprising no more than fifteen
e vowels and ten consonants, with
syllables or combinations of two
onsonants without an intervening
nce the strange forms assumed by
d other European words in the
the natives. When he visited
69 to observe the transit of Venus,
us that "after great pains they
tterly impossible to teach the
pronounce their names . . .
Capt. Cook, Tuote; Mr. Hicks,
incus they renounced in absolute
d called the master Bobu, from
n name Robert; Mr. Gore was
r. Solander, Torano; and Mr.
ane; Mr. Green, Eiree; Mr.
Parini; Mr. Sporing, Polini;
'terodero; and in this manner
w formed names for almost every
ship" (*First Voyage*).
ne; in the India-Chinese and
ions we have altogether five dis-
three dark (Negrito, Papuan,
with the doubtful Tasmanian,
(Mongolian, and one brown
These, with their various inter-
intermingles, give the seven
ns of our scheme, which may
ended and complemented so
e, for reasons fully specified,
erm "Malayo-Polynesian" the
Malays itself sinks to the position
of the Mongolian type. As
ed with the Oceanic branch of
it should be noted that the
occupy most of the peninsula
But they seem to be intruders
the true aborigines of which
Samangs, and in any case
ime in historic times is the
pelago.

A.—DARK TYPES

—Aeta- of the Philippines; Andamanese
ders; Samangs of Malacca; Kalangs of Java;
ons of New Guinea.

Central branch: Papuans proper of New
—1. *Central islands*: Mafors, Arfaks, Kobari,
ua and adjacent islands; Mysol, Ceram, &c.
ajua. Waigiu, Aru, Salwatty, Mysol, Ceram, &c.
2. *Sub-Papuan islands* (Melanesians),
reform Islands, New Britain, New Ireland,
rality Islands, New Hebrides, Loyalty, New
nian Isles. 3. *Western branch*: Sub-Papuan
lands: Flores, Ceram, Timor, Timor
Alfuros; Banda, Kissa, Savu, &c.
of Gilolo.

—Australians, Tasmanians (?).

B.—CAUCASIAN TYPES (Fair and Brown)

IV. CONTINENTAL BRANCH.—Khmêr or Cambojan Group: Khmers proper, Khmerdom, Charay, Stieng, Cham, Bashar, Xong, Khang, &c.

V. OCEANIC BRANCH.—Indonesian Group: Battas of Sumatra, Dyaks of Borneo and Celebes, some "Alfuros" of Ceram and Gilolo, Mentawey Islanders. Sawaiori or Eastern Polynesian Group: Samoa, Tonga, Tahiti, Marquesas, Tuamotu, Maori, Hawaii, Tokelau, Ellice.

(Map)—Malayo-Polynesian Hearth. The present Distribution

C.—MONGOLIAN TYPES (Yellow and Olive-brown)

VI. CONTINENTAL BRANCH.—Indo-Chinese-Chinese, Annamese, Tonquinese, Hue Islanders, Laos, Shan, Khamti, Khyen, Kayen, Karen, Jokia Naga, Abors, Miscos, Bhoks.

VII. OCEANIC BRANCH.—Malayan Group: Malays proper, Javanese, Sundanese, Madurese, Lampongs, Macassar, Bugi, Malagasy of Madagascar; Tagalo-Bisayans of Philippines; Formosan Islanders; Micronesians (Pelew, Carolines, Ladrones, Marshall, Gilbert Islands).

It thus appears that the three great divisions of mankind (A, B and C) are in possession of an ethnical region which some anthropologists have regarded as the

cradle of the human race. Observing that the anthropoid apes of equatorial Africa—gorilla and chimpanzee—are dolichocephalous, while those of Malaysia—orang-utan and gibbon—are brachycephalous, certain polygenists have suggested that the former may be the progenitors of the dolichocephalous Negroes, the latter of the brachycephalous Negritos. But we have seen that the Papûans of the extreme east (New Hebrides, Fiji, &c.) are also dolichocephalous, and even of a more pronounced type than the natives of Sudan. On the other hand, the Obongos, Akkas, and other pigmy tribes of Central Africa appear to be brachycephalous,[1] so that the theory fails at both extremes, Fiji and the Gaboon. Assuming however that mankind may have been evolved in the Eastern Archipelago or in some now submerged adjacent lands, and bearing in mind the relative value attached to the idea of race, as implied in our definition of species, the present conditions might still admit of explanation. In the Andamanese Islanders, whom Prof. Flower justly regards as of an "infantile type," and in the Javanese Kalong, whose features von Rosenberg describes as the most decidedly ape-like he had ever seen, we would have still *in situ* the earliest extant representatives of primeval man. Migrating westwards across a now lost "Lemuria," this primitive Negrito race may have reached equatorial Africa, where it is still represented by Du Chaillu's Obongo, Lenz's Abongo or Akoa, Schweinfurth's Akka, and where it may under more favourable conditions have become differentiated into the Negro of Sudan. Migrating eastwards across a continent of which the South Sea Islands are a remnant, the same Negritos may have similarly become slowly differentiated into the present Papûan or Melanesian peoples of those islands. Migrating northwards, before the severance of the Archipelago from the mainland, they reached Malacca and the Deccan, where they may still be represented by the Maravans and other low castes of that region. Moving thence over the Asiatic continent, they became under more temperate climes differentiated, first probably into the yellow Mongol, and then through it into the fair Caucasian type. But however this be, the subsequent migrations of the Mongols and Caucasians to the Archipelago, as above set forth, was probably, after all, but a return under new forms to their old homes. Here their mutual interminglings have again evolved fresh types and sub-types, producing a chaos of races whose true affinities I have endeavoured in these papers to elucidate, while fully sensible that in all such inquiries the last word still must be, *felix qui potuit rerum cognoscere causas.*

A. H. KEANE

[1] The Akkas certainly; but Lenz seems to think that the Abongos are dolichocephalous, so that this point remains still to be settled. Dr. Barnard Davis however in his *Thesaurus Craniorum* recognises brachycephaly in equatorial Africa, four out of eighteen skulls in his collection from this region being distinctly brachycephalous.

THE PHOTOPHONE

THE following calculation, made with the view of examining whether the remarkable phenomena recently discovered by Prof. Bell could be explained on recognised principles may interest the readers of NATURE. I refer to the *un-electrical* sounds produced by the simple impact of intermittent radiation upon thin plates of various substances.

It has been thought by some that in order that a body exposed to variable radiation may experience a sensible fluctuation of temperature its rate of cooling must be rapid. This however is a mistake. The variable radiation may be divided into two parts—a constant part, and a periodic part—and each of these act independently. Under the influence of the constant part the temperature of the body will rise until the loss of heat by radiation and conduction balances the steady inflow; but this is not appreciable by the ear, and may for the present purpose be left out of account. The question is as to what is the effect of the periodic part of the whole radiation, that is, of a periodic communication and *abstraction* of heat which leaves the mean temperature unaltered. It is not difficult to see that if the radiating power of the body were sufficiently high, the resulting fluctuation of temperature would diminish to any extent, and that what is wanted in order to obtain a considerable fluctuation of temperature is a *slow* rate of cooling in consequence of radiation or convection.

If θ denote the temperature at time t, reckoned from the mean temperature as zero, q be the rate of cooling, $E \cos p t$ the measure of the heating effect of the incident radiation, the equation regulating the fluctuation of temperature is—

$$\frac{d\theta}{dt} + q\theta = E \cos p t.$$

Thus—

$$\theta = \frac{E \cos (p t + \epsilon)}{\sqrt{\{p^2 + q^2\}}},$$

showing that if p and E be given, θ varies most when $q = 0$.

Let us suppose now that intermittent sunlight falls upon a plate of solid matter. If the plate be transparent, or absorb only a small fraction of the radiation, little sonorous effect will be produced, not merely because the radiation transmitted is lost, but because the heating due to the remainder is nearly uniform throughout the substance. In order that the plate may bend, as great a difference of temperature as possible must be established between its sides, and for this purpose the radiation should be absorbed within a distance of the order of half the thickness of the plate. If the absorption be still more rapid, it would appear that the thickness of the plate may be diminished with advantage, unless heat conduction in the plate itself interferes. The numerical calculation relates to a plate of iron of thickness d. It is supposed that q is negligible in comparison with p, *i.e.* that no sensible gain or loss of heat occurs in the period of the intermittence, due to the fluctuations of temperature themselves.

If the posterior surface remains unextended the extension of the anterior surface corresponding to a curvature ρ^{-1} is $\frac{d}{\rho}$, and the average extension is $\frac{d}{2\rho}$. Let us inquire what degree of curvature will be produced by the absorption of sunlight during a time t, on the supposition that the absorption is distributed throughout the substance of the plate, so as to give the right proportional extension to every stratum.

If Ht denote the heat received in time t per unit area, c the specific heat of the material per unit volume, e the linear extension of the material per degree centigrade, then

$$\frac{1}{\rho} = \frac{2eHt}{c.d^2}.$$

In the case of sunshine, which is said to be capable of melting 100 feet of ice per annum, we have approximately in $C.G.S$ measure

$$Ht = \cdot 008\, t.$$

Thus

$$\frac{1}{\rho} = .016 \frac{et}{cd^2}.$$

For iron $e = \cdot 000012$, $c = \cdot 86$.

Thus if $t = \frac{1}{8}$ (of a second), $d = \cdot 02$ cents.

$$\frac{1}{\rho} = 1 \cdot 12 \times 10^{-6}.$$

This estimate will apply roughly to a period of intermittence equal to $\frac{1}{11}$th of a second, *i.e.* to about the middle of the musical scale. If the plate be a disk of radius r, held at the circumference, the displacement at

the centre will be $\frac{r^2}{2\rho}$, or $\cdot 56 r^2 \times 10^{-6}$. In the case of a diameter of 6 centimetres this becomes $5\cdot0 \times 10^{-6}$.

Five-millionths of a centimetre is certainly a small amplitude, but it is probable that the sound would be audible. In an experiment (made, it is true, at a higher pitch) I found sound audible whose amplitude was less than a ten-millionth of a centimetre.[1] We may conclude, I think, that there is at present no reason for discarding the obvious explanation that the sounds in question are due to the bending of the plates under unequal heating.

January 13 RAYLEIGH

NOTES

We regret to learn of the death of the Rev. Humphrey Lloyd, D.D., Provost of Trinity College, Dublin, on the 17th inst., at the age of eighty-one years. Dr. Lloyd's contributions to scientific literature have been many and important, and to these and to his career generally we hope to refer at length in our next number.

Prof. Huxley has been appointed to the Inspectorship of Fisheries vacant by the death of Mr. Frank Buckland.

The Queen has been pleased to confer a pension of 200*l.* upon Mr. Alfred Russel Wallace.

The election of Dr. B. A. Gould of Cordoba in the place of the late Prof. C. A. F. Peters, director of the Observatory at Kiel, as Correspondent of the Academy of Sciences at Paris, completes the authorised number in the section of Astronomy.

York has already begun to make preparations for the 51st meeting of the British Association in that city on August 31 next. A meeting is to be held on the 26th inst. to appoint a reception committee and take other steps in connection with the approaching visit of the Association. The local secretaries are the Rev. Thomas Adams and Dr. Tempest Anderson.

The well-known collection of fossils formed by the late Mr. E. Wood of Richmond, Yorkshire, has been purchased by Mr. William Reed, F.G.S., of York, and by him presented to the Museum of the Yorkshire Philosophical Society, York. The collection consists of about 10,000 specimens, and is specially rich in fossils from the Carboniferous rocks.

The great *soirée* of the Paris Observatory will take place on February 5. One of the features of the display will be a series of vacuum tubes exhibiting the spectral peculiarities of the several gases inclosed.

Dr. Fritsch, Professor of Zoology at the University of Prague, has sent us a specimen of a cast, taken by the galvano-plastic process, of a skeleton of one of the extraordinary Labyrinthodont reptiles, described by him in his work, "Fauna der Gaskohle der Permformation Böhmens." As the matrix in which these skeletons are found contains much pyrites, it soon crumbles away on exposure to the air. By this process of Dr. Fritsch's the specimens however may be examined, even when magnified twenty-fold, and all little minutiæ of the skeleton can be seen. Complete sets of these galvano-plastic casts, representing all the more important reptile remains found, can be had on application to Prof. Fritsch.

In Siberia, a country so rich in gigantic fossils, the body of a colossal rhinoceros has been discovered in the Werchojanski district. It was found on the bank of a small tributary to the Jana River, and was laid bare by the action of the water. Similar to the mammoth washed ashore by the Lena River in 1799, it is remarkably well preserved, the skin being unbroken and covered with long hair. Unfortunately only the skull of this rare fossil has reached St. Petersburg, and a foot is said to be at Irkutsk, while the remainder was allowed to be washed away by the river soon after it had been discovered. The investigation of the skull gave the interesting result that this rhinoceros (*R. Merckii*) is a connecting form between the species now existing and the so-called *Rhinoceros tichorrhinus*, remains of which are not unfrequently found in the gravel strata of Eastern Prussia. It is supposed that *R. Merckii* is the now extinct inhabitant of the eastern part of Siberia.

Herr Julius Gillis, a wealthy merchant of St. Petersburg, offers a prize of 1000 florins for a popular work on "Kant's Views on the Ideality of Time and Space." Herr Gillis will not only pay the cost of publishing of the work which obtains the prize, but will also let the author have the profits its sale may realise. Details regarding this matter can be obtained from Last's Literary Institute at Vienna.

Mr. Warren De La Rue will, on Friday next, the 21st inst., deliver his discourse at the Royal Institution on "The Phenomena of the Electric Discharge with 14,400 Chloride of Silver Cells." Prof. Schäfer will give the first of a course of twelve lectures on the Blood, on Tuesday next (January 25); Mr. Francis Hueffer, the first of a course of four lectures on the Troubadours, on Thursday next (January 27); and Mr. Sidney Colvin the first of a course of four lectures on the Amazons, on Saturday next (January 29). The next Friday evening discourse will be given by Dr. Arthur Schuster, on the Teachings of Modern Spectroscopy, on January 28.

Mr. E. T. Sachs sends us some interesting notes from Batavia:—"Within the past month I have been so lucky as to make what I hope is a very interesting if not remarkable discovery. On the Island of Biliton, 200 miles from here, I found a fresh-water fish which produces its young *living from its mouth*. I am quite prepared for the cry of incredulity that will be raised; but I conducted my observations with living fish and closed doors, and what I assert is undeniable: the eggs are hatched in the lower portion of the head of the fish, and are projected out at the mouth and from nowhere else. I have secured several specimens, which I shall send to Dr. Günther, who will of course at once set the matter at rest. I also got on Biliton a butterfly, which is either a new Thecla or else it is the male of the pretty *Myrina nivea* peculiar to the island. I fancy it must be the latter. I was only three weeks on the island on other business, and was never two miles from the shore, so I have reason to be satisfied with my trip. I mean to go again next May or thereabouts, and go into the interior, and also try to get some living fish to breed from in Batavia. . . . There is a Dr. Schluyter here who is working hard at invertebrates. He is just busy on the tri-pang family, and will no doubt produce a fine monograph. He gets some fine crustaceans from the Straits of Sunda. I have shown him my fish, and he knows nothing of it."

On the subject of crickets Mr. Sachs writes:—"These are sold in the markets in Batavia, inclosed in small bamboos. There is not much superstition about it, as little ticklers (pieces of stick with a bunch of plants analogous to our broom tied on the end) are sold with it wherewith to stir up the unfortunate insect when it doesn't chirp. Only children buy them."

A sharp shock of earthquake was felt at Peshawur at 4 a.m. on December 10. The atmosphere was clear at the time; small drafts and eddies of cold wind followed the shock. The previous evening there had been a few drops of rain, the first for three months. The temperature was rather warmer than it had been, owing to the sky being more overcast. A smart shock was felt at the Bridge of Allan, near Stirling, on the morning of the 12th, about seven o'clock. There was a severe shock at Thurgau on the night of the 13th, accompanied by underground noises.

[1] *Proc.* Roy. Soc. 1877.

THE difficulties of the old Paris Municipal Council with the gas company were not adjusted before its dissolution. We believe that the new Municipal Council is sure to accept all the proposals coming from any gas company which has proved practically by some previous experiments the value of their system, and are willing to accept a remuneration proportional to the quantity of light produced on a scale similar to the Lontin agreement, viz. 10 deniers for each 120 or 130 sperm candles.

THE French Government has appointed an engineer of the Ponts et Chausées, M. de Villier du Terroge, to report on the possibility of establishing in Paris underground railways. The difficulty is in the length of the tunnels to be excavated, which will be greater than on the Metropolitan Railway, and the necessity of procuring smoke-consuming engines.

ON the 7th inst. a silver tea and coffee service was presented by the Mayor of Liverpool, in the name of a large number of subscribers, to Mr. A. Norman Tate for his disinterested efforts to promote scientific education in that city.

A GENERAL Horticultural Exhibition will be held at Frankfort-on-Main from May 1 to October 1 this year. Particulars may be obtained by applying to "Die Gartenbau-Gesellschaft" at Frankfort-on-Main.

THE Electric Railway, constructed by Siemens and Halske, between the Anhalter Station, in Berlin, and the suburban village of Lichtenfeld, has been satisfactorily completed, and will be opened to public traffic on the 1st of next month.

A NEW electric lamp has been brought out in Paris; it is a combination of the Werdermann with a perforated carbon filled by an insulating medium. It is said to work well.

AT a meeting of the Council of the Epping Forest Naturalists' Field Club, held on Saturday evening, January 8, the following resolution was passed on the motion of Mr. Francis George Heath, seconded by Mr. N. F. Robarts, F.G.S.—"That the Council of this Society, on behalf of the large section of the population of London interested in the pursuit of Natural History, desires to record an emphatic protest against the proposal of the Great Eastern Railway Company to carry a line across Epping Forest, believing that it is wholly unnecessary for the Railway to take the route projected, and that it would not fail to prejudicially affect the advantages secured by the Epping Forest Act, which directs that the forest is to be preserved as far as possible in its natural aspect."

OUR ASTRONOMICAL COLUMN

JANSON'S STAR OF 1600.—The so called *Nova* of 1600, which is 34 Cygni of Flamsteed, and P Cygni of Schönfeld's catalogues of variable stars, was discovered by Wilhelm Janson, a pupil of Tycho Brahe's, and entered upon his globe in that year. It has been erroneously stated in some astronomical works (as in Cassini's "Elements d'Astronomie) that Kepler was a co-discoverer of this star, of which he himself informs us to the contrary in his treatise, "De stella tertii honoris in Cygno, quæ ad annum MDC fuit incognita necdum extinguatur, Narratio astronomica"; this is appended to his well-known work, "De stella nova in pede Serpentarii," published at Prague in 1606. At p. 154 we read, "Cum mense Majo anni 1602 primùm literis monerer de novo Cygni phænomeno," &c., while at p. 164 Kepler says distinctly that Janson was the discoverer, "Primus est Gulielmus Jansonius, qui hanc novam a se primùm anno 1600, conspectam profitetur inscriptum in globum cælestem anno 1600 editum factâ." Kepler gave the position of the star for the end of 1600 in R.A. 300° 46′, Decl. + 36° 52′. He observed it during nineteen years, it became fainter in 1619, and disappeared in 1621, though Fortuni Liceti dates a reappearance in the same year. In 1655 Dominique Cassini observed it again; it increased during five years, until it attained the third magnitude, and afterwards diminished. On the testimony of Hevelius, it reappeared in November, 1665, it was again faint in the following year, but subsequently brightened without reaching the third magnitude, in 1677 and 1682, it was only of the sixth magnitude. Cassini says on June 24, 1715, a star of this magnitude was seen in the position of P (Bayer) equal to the three which are near that marked *b* in Cygnus by Bayer.

Edward Pigott was at some pains to elucidate the history of this star in a communication presented to the Royal Society in 1786 (*Philos. Trans.* vol. lxxvi. p. 189). He says he had minutely examined the observations made in the previous century with the following results as to the star's fluctuations:—

1. Continues at its full brightness for about five years.
2. Decreases rapidly during two years.
3 Invisible to the naked eye for four years.
4. Increases slowly during seven years.
5. All these changes, or its period, are completed in eighteen years.
6. It was at its *minimum* at the end of the year 1663.

It does not always increase to the same degree of brightness, being sometimes of the third, and at other times only of the sixth magnitude. He adds that he was entirely ignorant whether it were subject to the same changes since the beginning of the eighteenth century, as he had not met with any series of observations upon it.

It cannot be said that Pigott's conclusions (which Schönfeld appears to think are only indifferently supported by the observations upon which they are stated to be founded) have received any confirmation since his time. If in the absence of systematic series of observations we consult the catalogues of the present century, we have the following estimates of magnitude amongst others:—Piazzi, 5·6; Bessel, 6·7 (on September 14, 1825); Argelander's *Uranometria*, 5; and *Durchmusterung*, 5·3; Yarnall, 5·2; Radcliffe observations, 1870, 5·8. But in view of the undoubted variation in the brightness of this star in past times, more regular observation seems desirable. Has it ever been carefully examined under the spectroscope? Its light has a strong yellow cast. Mädler found no appreciable proper motion. The star occurs in the second Radcliffe catalogue, and in the Greenwich catalogue of 1864. The position carried back to Kepler's epoch from these authorities is in close accordance with that given in his treatise.

THE NEW CAPE CATALOGUE.—At the meeting of the Royal Astronomical Society on the 14th inst. the Radcliffe observer, Mr. E. J. Stone, laid upon the table the complete sheets of his great Catalogue of Southern Stars, observed during his superintendence of the Royal Observatory, Cape of Good Hope, which has been printed since his return to England. This very important work contains the places of between twelve and thirteen thousand stars, including, in addition to the stars observed by Lacaille, a considerable number of stars falling within similar limits of magnitude. "A stereographic projection, showing the distribution of the stars contained in the Cape Catalogue, 1880, between 110° and 180° N.P.D." has been lithographed by Mr. Stone. We believe a number of suspected cases of large proper motion amongst the southern stars disappear under the new determination of their positions at the Cape.

BIOLOGICAL NOTES

ARCHÆOPTERYX MACRURA.—A very able article on this strange-feathered animal by Prof. Carl Vogt was read before the Saint Gall Meeting of the Congress of Swiss Naturalists, and was published in the *Revue Scientifique* for September, 1879. This has been translated in the recently-published number of *Ibis*, with a photograph of Herr Häberlein's specimen. H. von Meyer, in 1861, described this species (under the specific name lithographica) from the impression of a "bird's" feather in the Solenhofen slate. Prof. Owen, on the discovery by Dr. Häberlein of a specimen (imperfect) described it "as he alone knows how to do." The head of this specimen was wanting. Dr. Häberlein's son, about 1875, succeeded in splitting a slab so skilfully as to have on one of its halves the whole animal, and on the other its impression. This specimen Herr Häberlein is anxious to dispose of, and it is the one described by Carl Vogt. The animal preserved in the slab is of the size of a ringdove. The remains described by Prof. Owen belong to the same species, but to an example greater by a fifth. It is entire; the head, neck, trunk, and hind-quarters are placed in profile, the head is bent backwards, so that its top nearly touches the back. The wings, united at the shoulder girdle, are

spread as if for flight. The head is small, pyramidal, nearly flat. The orbit is large, with the nostril in front of it. By means of a lens two little conical and sharp teeth are perceived at the end, planted in the upper jaw. On the lower surface there is a forked bone to be seen, but Prof. Vogt dare not say whether this is the lower jaw or a tongue bone; the bones of the head show clearly that it is a true reptile's head. Its shoulder-girdle proves also to be that of a reptile. In fact the head, the neck, the thorax, with the ribs, the tail, the shoulder-girdle, and the whole fore-limb, are plainly constructed as in reptiles. The pelvis has probably more agreement with that of reptiles than with that of birds. The hind-foot is that of a bird, therefore reptilian affinities prevail in the skeleton over all others. The feathers are those of a bird. The remiges of the wings are fixed to the ulnar edge of the arm and to the hand; they are covered for nearly half their length with a fine filiform down; none of them project beyond the others. It is possible that at the base of the neck there was a ruff like that of the condor. The tibia was clothed with feathers for the whole of its length. Archæopteryx thus wore breeches, as do our falcons All the other parts of the body were evidently naked. It would thus seem to take its rank neither among birds nor reptiles. It forms an intermediate type of the most marked kind, and confirms in a brilliant way the views of Prof. Huxley, who has united birds and reptiles—to form of them under the name of Suuropsids, a single great section of Vertebrates.

European and North American Birds.—The occurrence of North American birds in Europe has always been a subject of interest to ornithologists. In the April number (1880) of the *Proceedings* of the Royal Dublin Society there is a paper by Percy Evans Freke giving a comparative catalogue of the birds found in Europe and North America, in which the species of North American birds are arranged in columns side by side with the same species found at times in Europe. The geographical distribution of these species is also given, and the residents, which are probably breeders, are distinguished. This list seems worked out with a great deal of care. A paper on the same subject by Mr. J. J. Dalgleish appears also in the April number (1880) of the *Bulletin* of the Nuttall Ornithological Club, with a table giving a "List of Occurrences of North American Birds in Europe." Great care has evidently been taken in this memoir also to secure correctness. On comparison of the lists it would seem as if Evans had overlooked Gätke's paper on Heligoland Birds.

A Gnat with two kinds of Wives.—Dr. Fritz Müller describes in a late number of *Kosmos* (October) a very remarkable two-winged insect which he calls *Paltostoma torrentium*, and which he found at Itajah. The larvæ were found by him under stones and rocks in the little streams with which this province abounds. These larvæ were carefully watched and reared, and the perfect insects on their appearance were found to be males and females, but the latter of two well-marked and very different types. In the male gnat the eyes occupy nearly the whole side of the head, and leave not even room for the three ocelli, which are thus forced to the top of a peculiar stalk-like body. In one of the two forms of the female the eyes occupy the whole length of the head, but leave between them a broad belt, which in the second form of female is not half so wide or long. In the large-eyed females the parts of the mouth are formed after the type of those to be met with in the blood-sucking females of the mosquito or horse-fly. But in the small-eyed females and in the males this formidable development of the parts of the mouth, which enables the large eyed females to feed on blood, is wanting, and the former are honey-suckers, obtaining this food from the nectaries of several flowers. Along with this remarkable difference in the parts of the mouth there is a notable difference in the foot-joints, the honey-sucking wives having slender feet, with smaller claws than their honey-sucking husbands; while the blood-sucking wives have the last foot-joint short and wide, furnished on its under surface with a thick pad, from which arise strong curved hairs; the claws are also much longer. Thus the small-eyed honey-loving form has the more simple structure of foot, whereas the blood-seeker has not only the more complicated form of foot, but great eager eyes looking about for what they can get to devour.

The Function of Asparagine.—Boussingault's researches seemed to show that asparagine was a substance comparable to urea, the result, like it, of a transformation of albuminous matters, and that this substance made its appearance only in seeds during their germination; but from the discovery of this substance not only in bitter almonds when the embryo is not yet visible; in the same seeds when completely ripe; in the young seeds of the apricot, plum, and cherry, and even in the unopened inflorescences of the pear, M. L. Portes sees reason to doubt the propriety of ascribing to it this function. If, he says, Boussingault's experiments show the existence in leguminous plants of an asparagine concomitant with the act of germination—which might be called blastemic asparagine—there also exists in the almond tribe and pear-buds, another form apparently not having any physiological connection with the other, which may be referred to as ablastemic. In both cases the asparagine is a secondary product; its formation is in intimate connection with the production of new cells. Sweet and bitter almonds gathered in March in the middle of France were proved to contain neither sugar nor starch, but dextrine was present. Previous analysis allows one to affirm that neither sugar nor starch ever existed in them, nor as yet were they in the flowering stalk. May it not be admitted that the dextrine and glucose which speedily appear have at least in part an albuminoid origin? since the seed does not contain, nor will it for a long time contain, starch; since the young seed shows no sugar; and lastly, since there is a product of excretion representing the azote of the transformed protoplasmic matter. (*Revue Internationale des Sciences biologiques*, October 15.)

A Cause of the Motion of Diatoms.—According to one view diatoms move by means of strong osmotic processes, which, being more intense in one direction, cause impulsion in the other. Some observations by Herr Mereschkowsky supporting the latter view are described by him in the *Botanische Zeitung* (1880, p. 529). He examined two species of Navicula and one of Stauridium in sea-water containing many very small micrococci, which, near the diatoms, vibrated greatly, but at a distance were quite still. It was first evident that the movements of the diatoms consisted of a straightforward motion, then a backward, with a pause between, or of a turning round the axis. Then it was noticed that so long as the diatom remained still, all the actively vibrating micrococci were uniformly distributed, whereas, when the diatom moved, the micrococci vibrated with excessive activity at the hinder end, as if a strong water current entered behind the alga. At the fore end there was only a very slight motion of micrococci. When the still state was reached the vibration became again equally distributed, and on commencement of the backward motion a reverse distribution of the vibration was observed. These phenomena (observed also in rotation of diatoms) can only be explained, the author considers, by the hypothesis above stated.

Fungal Growths in the Animal Body.—By experiments on animals, Herr Grawitz (*Virchow's Archiv*, B. 81, p. 355), has recently proved the following:—1. The well-known mould-fungi *Eurotium* (*Aspergillus*) and *Penicillium* occur in two varieties, which are quite alike in form, but quite different physiologically; the one proving wholly indifferent in the blood-system of the higher animals, while the other has all the malignity of the worst pathogenic fungi known. 2. From any original form both varieties can be obtained by continued cultivation, and similarly from either of the two varieties the other may be got, in twelve to twenty generations, by systematic cultivation. 3. The principle of the cultivation is to habituate the fungi which live on solid, weakly acid, nutritive substances at a temperature of about 8° to 20° C., through a series of generations, to liquid alkaline albumen solutions, and a heat of 38° to 40° C. 4. The malignity of the pathogenic mould-fungi consists, in acute cases, in their spores, which on reaching the circulation of the higher mammals, there germinate, and passing into different parts of the body, multiply, and cause local neuroses, and death in about three days. In the subacute and chronic cases a reactive inflammation occurs in each of the numerous fungus-centres, which may cause the death of the hyphæ and lead to cure. 5. Most of the small mould-accumulations easily seen with the naked eye in the kidneys, liver, muscles, and retina, are microscopically distinguishable neither by size nor by histological characters from fungi of the same species, which have grown on their favourite substrata, except that they have only rudimentary fruit-stalks, and never attain to the separation of spores.

Brain-Weight.—The weight of the human brain, according to a recently-published work by the eminent Munich anatomist Prof. Bischoff, is on an average 1362 grammes for man and 1219 gr. for woman. The difference between the average brain-weight of man and woman thus amounts to 143 gr., or 10·50 per cent.

The brain-weight of man exceeds that of all animals except the elephant (4500 gr.) and the larger Cetaceæ (2500 gr.). The brain-weight of the largest apes is hardly a third of man's. Prof. Bischoff has worked with a considerable amount of material; his data comprise the weights of brain of 559 men and 347 women.

PHYSICAL NOTES

EXPERIMENTS have been made by Herr Glan (*Wied. Ann.* No. 11) as to the action of gases and vapours on the optical properties of reflecting surfaces. No such influence (expressed in alteration of phases in reflection) is found to exist if the gases and vapours do not act chemically on the surfaces, or are not precipitated in visible quantity (as when the temperature is below the dew point).

DR. FUCHS describes a new interference photometer (*Wied. Ann.* No. 11) in which no polarisation of the rays at right angles to each other is required. It consists simply of two similar isosceles glass prisms joined by their basal surfaces, which enclose an air layer variable in thickness by pressure. A diaphragm reaches out in prolongation of the surface of junction. The observer looks obliquely towards this surface and sees one illuminated surface directly through the double prism, the other by reflection at the air layer. One light-source is fixed, and the other is displaced till the interference bands disappear.

THE polar differences in luminous phenomena of the discharge of electricity through gases were considered by Wiedemann and Rühlmann as possibly due, in part at least, to a gas layer (more or less condensed) on one electrode. Supposing that other kinds of envelopes with like action would essentially affect the phenomena, Herr Holtz has been able (*Wied. Ann.* No. 11), by covering one electrode, *e.g.* with silk, or placing a stretched silk disk before it, to verify this, and almost quite obliterate, in some cases, the polar differences.

IN a recent publication describing electrical researches, by Herr Goldstein, in Berlin, that author investigates the phenomena which occur when, in a space so far evacuated that the green phosphorescent light occurs with the discharge from the cathode, there are, not one, but several cathodes. He has met with a new form of electrical repulsion, not to be classified either with the mechanical repulsion in collision of ponderable masses, or with electrostatic or electrodynamic repulsion. (An abstract of the memoir appears in *Wiedemann's Beiblätter*, No. 11.)

APPLYING his theory of the potential energy of liquid surfaces to great cycle-operations in nature, M. van der Mensbrugghe (*Bulletin* of Belg. Acad., 9 and 10) has lately calculated that if evaporation subdivides the liquid of seas into spherules of *e.g.* 1-10,000th mm. diameter, each kilogramme of water presents a collection of spherules whose total potential energy is equivalent to 450 kilogrammetres, *i.e.* more than a million times that of a sphere of compact water also weighing 1 kilogramme. This shows what prodigious quantities of work-units are carried virtually into the atmosphere by water vapour, and there is to be added the potential energy acquired by this vapour in virtue of its weight. The author applies his theory to the effects of condensation, to glazed frost, to phenomena of rivers and waterfalls, &c. He anticipates important verifications of it from the examination of the Gulf Stream in the Gulf of Mexico projected by the United States, and recent soundings have tended to confirm it.

M. MONTIGNY (*Bull.* Belg. Acad. 9 and 10) has lately studied the effects of making bells vibrate with liquids in them (water, ether, alcohol, sulphide of carbon), or when wholly immersed in liquids. He found that (1) the sound produced was always more grave than the natural sound; (2) that the lowering of tone was more marked in both cases the more dense the liquid (thus it is less with ether than with sulphide of carbon); (3) that with all the liquids tried the alteration in sound of a given bell was much more marked when the bell was wholly immersed than when merely filled with the liquid; and (4) that in both cases the lowering of tone was more marked for grave than for acute notes. The general inference is that the rapidity of vibrations of a sounding body is considerably diminished by a liquid with which its walls are in contact, and that this diminution is more sensible when the contact is established on both sides of the vibrating body than when only on one side. The mode of action is related not only to the density, but to the compressibility of the liquid. The lowering of sound is more sensible with water than with alcohol and ether; the latter being less dense and more compressible liquids. The form of the bell and the nature of its substance (that is its special elasticity and its density) are shown also to affect considerably the pitch of the sound produced in contact with liquids. M. Montigny is investigating whether air is a medium of too little density and too great compressibility to modify sensibly the duration of vibrations of sonorous bodies.

AT a recent meeting of the Franklin Institute (*Journal* for December), Mr. Griscom described his new electric motor, which, weighing about 2½ pounds, compares favourably with those of the old forms of fifteen times its weight. Its most essential advantage is in the field magnets; the shape of which is such that all the magnetic lines of force, including those nearest the neutral line, are brought into the best possible position for effecting the revolution of the armature. If a bar of soft iron is pivoted at one end to move in a horizontal plane, and a semicircular magnet is placed concentrically with the circle the bar can describe, then a given force is exerted on the bar at a much greater distance from the poles when the latter is within the semicircle than when it is without. Herein (it is stated) is the secret of the power of Mr. Griscom's motor. The battery is inclosed in a strong waterproof box, gives no odour, and very little trouble in renewing. It is calculated that it will suffice for the sewing of a small family for one year; a professional seamstress would exhaust it more rapidly, but always in proportion to the exact amount of work done.

A NEW microphone, made by M. Boudet in Paris (*La Nature*, No. 394), has the general shape of a telephone on a support. It comprises a mouthpiece, in which is an ebonite plate 1 mm. thick, with a short bar of copper penetrating from its middle a short way into a glass tube in which are six little balls of retort carbon in a row; a second mass of copper following the last, and resting on a small spiral spring in a case. The pressure can be varied by means of a screw. The instrument is worked with six Gaiffe elements (peroxide of manganese and chloride of zinc) mounted in tension, and a Bell telephone. It is said to transmit the voice very distinctly without altering its timbre and without disturbing sounds being produced.

IN a note to the Vienna Academy (*Ans.* December 16) Prof. Stefan describes experiments on the influence of terrestrial induction in development of an electric current, and the excitement of the telephone by currents from a rotating coil. The coil used was 56 mm. in external diameter, and 11 mm. in width. The earth's influence is best shown by so connecting the apparatus with a galvanometer that the circuit is closed during one half of the coil's rotation, and broken during the other half; if the completion of the circuit correspond to the positive maximum of the electromotive force of the earth's magnetism, and the interruption to the negative, the galvanometer is positively deflected. The deflection may be reduced to zero by displacing the contact, and from the displacement and the number of rotations the potential may be inferred in absolute measure. Next the telephone was so connected with the coil that the fall alternately opposite currents went uninterruptedly through the circuit. This gave a simple tone. With 100 rotations per second the horizontal component of the earth's magnetism did not suffice to excite an ordinary telephone, but it excited one having a horse-shoe magnet. (When the intensity of the field was doubled the ordinary telephone was also excited.) The tone corresponds to the number of rotations. When the coil was rotated 220 times in a second the ordinary telephone sounded. The telephone was shown to be less sensitive to currents whose intensity periodically changes than to interrupted currents (an ordinary telephone sounded with 100 rotations or fewer, when the circuit was closed only during a short time of each rotation).

GEOGRAPHICAL NOTES

AT the meeting of the Geographical Society on Monday evening a paper was read on the discoveries made by Mr. Leigh Smith last year on the coast of Franz Josef Land, including also a general sketch of the rest of his voyage in the *Eira*. Mr. Smith appears to have reached the southern shores of Franz Josef Land with comparative ease about the middle of August, and to have examined it and several islands along a coast-line of over 100 miles of previously unexplored ground. The new continent, as some would fain believe it to be, does not present an attractive appearance, for the coast-line is described as consisting

of glaciers with dark frowning and flat-topped cliffs, here and there reaching to a height of 1200 feet. It was after passing Barents' Hook that new ground was actually broken, and the exploration was continued westwards until Mr. Smith succeeded in rounding the western headland. The farthest point actually reached by the *Eira* was in N. lat. 82° 20′, E. long. 45°, and thence the land could be seen trending away to the north-west. During the voyage a meteorological record was kept, photographs taken, and various collections made, chiefly of botanical and geological specimens.

THE January number of *Petermann's Mittheilungen* contains an account of a journey from Dufilé to Lur, on the west shore of Lake Mwutan-Nzige, by Dr. Emin Bey, in the last months of 1879. Herr Clemens Denhardt brings together much valuable information on the East African region between Mombasa and the Victoria Nyanza, with special reference to the trade-routes, accompanied by an excellent map. An article of special scientific interest is contributed by Dr. H. Hoffmann on the Comparative Phænology of Central Europe. In a series of tables and in a map the average time of bloom is shown for a very large number of places, with reference to Giessen as a standard. There is a very interesting account by Baron Nordenskjöld of his visit to Behring Island, followed by some critical remarks on the vegetative region of the Serra da Estrella, by Dr. O. Drude.

Bulletin, No. 5, 1879, of the American Geographical Society contains a paper by General R. E. Colston on "Life in the Egyptian Deserts," and an amusing lecture by Lord Dunraven on "Moose and Cariboo Hunting."

THE French station of the African Association has been established by M. Savorgnan de Brazza at Nghimi, on the route from Machogo to Levumba, in the region of the sources of the Ogové, in 1° 30′ S., and about 11° E. from Paris.

THE publication in which the results of the determination of the South American longitudes by electricity have been tabulated by American observers has just arrived in Paris. All the positions determined by M. Mouchez on the Brazilian coast have proved correct within a difference of 1½ second of time. These determinations were taken by Admiral Mouchez when a subordinate officer in the French service twenty years ago, by lunar distances, occultations, and eclipses.

THE author of the summary of Geographical Discovery in *Whitaker's Almanac* writes to us in reference to the notice on p. 232, that it is not stated that Mr. Leigh Sr. ith's voyage is "the most remarkable geographical event of the year," to the depreciation of Mr. Thomson's African journey; "but that, in spite of the success of the latter, Mr. Smith's voyage would probably be considered by many as the most remarkable geographical event of 1880." We doubt if "many" would hold such an opinion, merely for the reason assigned in the *Almanac*. "May I be allowed to point out," he adds, "that the word 'research' means careful search or investigation? and that mere searching for the North Pole is not the sole object of Arctic voyages?" We are glad the writer is of this opinion, though we doubt if Mr. Leigh Smith's voyage has much bearing on Polar "research."

CHESAPEAKE ZOOLOGICAL LABORATORY

A REPORT of the third year's work at the Chesapeake Zoological Laboratory of the Johns Hopkins University has been addressed to the President of the University by Mr. W. K. Brooks, Director of the Laboratory. An advance copy of this has been sent us, from which we make some valuable extracts.

The laboratory was opened at Beaufort, North Carolina, on April 23, 1880, and closed on September 30, after a session of twenty-three weeks. It was supplied with working accommodations for six investigators, and the facilities which it afforded were used by the following six persons:—W. K. Brooks, Ph.D., Director; K. Mitsukuri, Ph.B., Fellow in Biology; E. B. Wilson, Ph.B., Fellow in Biology; F. W. King, A.M., Professor of Natural Science, Wisconsin State Normal School; H. C. Evarts, M.D., Academy of Natural Sciences, Philadelphia; H. F. Osborne, Ph.D., Fellow of the College of New Jersey.

Beaufort was selected for the third season's work because it is the nearest accessible town south of Baltimore which is favourably situated for zoological study. The scientific advantages of Beaufort are very great; the most important is the great difference between its fauna and that of the northern Atlantic coast.

"The configuration of our coastline," the Report goes on, "is such that Cape Hatteras, the most projecting point south of New York, deflects the warm water of the Gulf Stream away from the coast, and thus forms an abrupt barrier between a cold northern coast and a warm southern one. The fauna north of this barrier passes gradually into that of southern New England, while the fauna south of the barrier passes without any abrupt change into that of Florida, but the northern fauna is sharply separated by Cape Hatteras from the southern. As the laboratory of the U.S. Fish Commission and Mr. Agassiz's laboratory at Newport afford opportunities for work upon the northern fauna, it seemed best for us to select a point south of Cape Hatteras in order to study the southern fauna with the same advantages, and as Beaufort is the only town near the Cape which can be reached without difficulty, it was chosen as the best place for the laboratory. The situation of this town is exceptionally favourable for zoological work, for the surrounding waters present such a diversity of conditions that the fauna is unusually rich and varied."

After describing in detail the special characteristics of the locality Mr. Brooks goes on to say:

"The zoological resources of Beaufort have not escaped the attention of American naturalists, and there are few places upon our coast, outside of New England, where more zoological work has been done. In 1860 Drs. Stimpson and Gill spent a season in dredging and collecting in the vicinity of Beaufort, Cape Lookout, and Cape Hatteras, and an account of their work was published in the *American Journal of Science*. Dr. Coues, who was stationed at Fort Macon during the war, occupied himself for two years in collecting the animals which are found here, and he published a series of papers on the 'Natural History of Fort Macon and Vicinity' in the *Proceedings* of the Academy of Natural Sciences of Philadelphia. These papers, which were continued by Dr. Yarrow, contain copious and valuable notes on the habits and distribution of the animals which were observed, and we found them a great help to us. These two naturalists found 480 species of animals in the vicinity of Beaufort. Of these 480, 298 are vertebrates, and 182 are invertebrates. Of the vertebrates 24 are mammals, 133 are birds, 27 are reptiles, 6 batrachians, 97 fishes, and 11 selachians. Of the invertebrates 147 are mollusks, 21 are crustaceans. The list of vertebrates is very nearly exhaustive, and we made no additions to it; but the list of invertebrates is obviously very imperfect, and although we made no attempt to tabulate the species which we observed, there would be no difficulty in enlarging the list twenty or thirty fold.

"Among other naturalists who have spent more or less time at Beaufort I may mention Prof. L. Agassiz, Prof. E. S. Morse, Dr. A. S. Packard, Prof. Webster, and Prof. D. S. Jordan. Prof. Morse procured most of the material for his well-known paper on the Systematic Position of the Brachiopoda on the Sand-bars in Beaufort Inlet.

"I will now attempt to give a very short statement of some of the leading points in our own summer's work. Much of our time was spent in studying the development of the Crustacea, since this is one of the most important fields for original work upon our southern coast. The supply of material is almost inexhaustible, and would employ a number of students for many years. The life-history of the Crustacea is of great interest in itself, and the recent species are so numerous and diversified that there is no group of animals better adapted for studying the general laws of embryonic development in their relation to the evolution of the group. These considerations have led us to devote especial attention to this group during this and the preceding seasons. One of the published results of the first season's work was an illustrated account of the metamorphosis of Squilla, a representative of a somewhat aberrant group of Crustacea. During the second season a member of our party, Prof. Birge, made a very thorough study of the development of Panopæus, one of our crabs, and the account of his observations, with drawings, was ready for publication several months ago. At Beaufort we spent most of our time upon this subject, and figured more than 800 points in the development of various Crustacea.

"Among these I wish to call especial attention to our observations upon the development of the Sergestidæ; the least specialised of the stalk-eyed Crustacea. This very peculiar group was not known to occur upon our coast until we found a few

specimens of one genus at Fort Wool, and the same genus—Lucifer—in great abundance at Beaufort, associated with another genus which is also new to North America. As nothing whatever was known of the development of Lucifer, we made every effort to obtain the eggs and young, and after four months of almost fruitless labour we finally succeeded in finding all the stages of the metamorphosis, and figured them in a complete series of ninety-nine drawings. We also obtained a somewhat less complete series of figures of stages in the life history of the second Sergestid. Our only motive in this work was the desire to fill a gap in our knowledge of crustacean development by supplying the life-history of a very interesting group of animals, but the result was found to have a very unexpected value, since it contributes to the discussion of a number of problems in general embryology and morphology, and is the most significant crustacean life history which has ever been studied.

"The following are some of the more important points:—The egg undergoes total regular segmentation. There is no food-yolk, and cleavage goes quite through the egg. There is a true segmentation cavity. Segmentation is rhythmical. There is an invaginate gastrula. The larva leaves the egg as a Nauplius, and passes through a protozoea stage and a schizopod stage. The fifth thoracic segments and appendages are entirely wanting at all stages of development.

"Another interesting group which was studied is the Porcellanidæ; the least specialised of the true crabs. The adults of our American species are almost restricted to our southern waters, although the swimming larvæ are carried north by the Gulf Stream. Within the last two years two northern naturalists have studied these floating embryos upon the south coast of New England, but as they were working upon stragglers so far from home, their accounts are incomplete and somewhat contradictory. Our advantages at Beaufort enabled us to contribute towards the solution of this confused subject by raising one species of Porcellana from the egg. We also raised six other species of crabs from the egg, and made drawings of the more important stages of development. One of the species which was thus studied is the edible crab. Its metamorphosis has never been figured, and although it presents no unusual features, its economic importance gives value to exact knowledge of its life history. Mr. Wilson also studied the development of one s ecies of Pycnogonida, a group of very peculiar Arthropods distantly related to the spiders. As he has paid especial attention to the systematic study of this group, and is now engaged in describing the Pycnogonids collected in the Gulf Stream by Mr. Agassiz, the opportunity to study them alive in the laboratory has been a great advantage to him.

"Another important investigation is the study by Mr. Wilson of the embryology of the marine Annelids. Although the representatives of this large group are abundant and widely distributed, little was known of the early stages of their development until he procured the eggs of several species and studied them at Beaufort. This investigation has shown, among other things, that the accepted division of Annelids into two great groups, the Oligochæta and Polychæta, is not a natural method of classification. The work upon the development of marine Annelids was supplementary to an investigation which Mr. Wilson carried on last spring at Baltimore, and which he will continue this winter, upon the development of land- and fresh-water Annelids.

"As much time as possible was given this season to the study of the hydroids and jelly-fish of Beaufort. The life history of several of them were investigated, a thorough anatomical study of some of the most important forms was carried on, and nearly two hundred drawings was made. It is almost impossible to complete a study of this kind in a single season, but if one or two more summers can be given to the work, we have every reason to hope for valuable results, for although the North Carolina coast is the home of many species which are only found as stragglers upon our northern coast, and of other species which are not known to occur anywhere else, and of some genera and families which are new to the North American coast, this field has suffered almost total neglect.

"Nearly three months of the time of two members of our party, Mitsukuri and Wilson, were given to the study of the habits, anatomy, and development of Renilla, a compound Polyp very much like that which forms the precious coral, but soft and without a stony skeleton. The animals which form the community are so intimately bound together that the community as a whole has a well-marked individuality distinct from that of the separate animals which compose it. The compound individuality of Renilla is quite rudimentary as compared with that of a Siphonophore, and as there is no trace of it in the closely allied Gorgonias, it furnishes an excellent field for studying the incipient stages in the formation of a compound organism by the union and specialisation of a community of independent simple organisms. With this end in view the anatomy of the fully-developed community was carefully studied, and the formation of a community was traced by rearing a simple solitary embryo in an aquarium until a perfect community had been developed from it by budding. During the process of development the law of growth by which the characteristics of the compound organism are brought about was very clearly exhibited, and it is fully illustrated by nearly one hundred drawings.

"One of the most interesting results of our work is the explanation by Mr. Wilson of the origin of the metamorphosis of the larva of Phoronis, a small Gephyrean worm which lives in a tube. Several of the most noted embryologists of Europe have studied the development of Phoronis, and our knowledge of its life history is due to their combined labours. Last summer Mr. Wilson reviewed the subject, and added some important points, and during the present season he has shown by the comparison of a great number of allied forms that the very peculiar metamorphosis admits of an extremely simple explanation. The adult is sedentary and confined to its sand tube, while the larva is a swimming animal totally different in structure. The change from the larva to the adult is very rapid and violent. It occupies only a few minutes, and during the change the larva becomes turned wrong side out, so that what was internal is external. Mr. Wilson's comparison shows that Phoronis was originally a free animal, and that the structural peculiarities which fit the adult for sedentary life in a tube are of recent acquisition. The larva has however retained its ancestral adaptation to a swimming life in order to provide for the distribution of the species. There must have been a time, in the evolution of the species, when the adult was imperfectly adapted to a sedentary life, and also imperfectly adapted to a swimming life; and if the development of the individual were a perfect recapitulation of all the stages in the evolution of the species, we should have, between the swimming larva and the sedentary adult, a stage of development during which the adaptation is not quite perfect for either mode of life. It is clearly an advantage for the animal to pass through this stage as quickly as possible, or to escape it altogether. The peculiar metamorphosis enables the larva to remain perfectly adapted to a locomotor life until the occurrence of the sudden change which fits it for life in a tube; and Mr. Wilson has pointed out the manner in which the metamorphosis has been acquired in order to bridge over the period of imperfect specialisation. This explanation is somewhat similar to that which Lubbock has given of the origin of the metamorphosis of insects, and we may hope that the same method of investigation will throw light upon the significance of other remarkable instances of metamorphosis in the invertebrates.

"During the summer the following abstracts of some of the more important points in our work have been published in scientific journals:—

The Development of the Cephalopoda and the Homology of the Cephalopod Foot. By W. K. Brocks. *Amer. Journal of Science.*

The Development of Annelids. By E. B. Wilson. *Amer. Journal of Science.*

The Rhythmical Nature of Segmentation. By W. K. Brooks. *Amer. Journal of Science.*

The Origin of the Metamorphosis of Actinotrocha. By E. B. Wilson. *Amer. Assoc., Boston Meeting.*

Notes on the Medusæ of Beaufort. By W. K. Brooks. *Amer. Assoc., Boston Meeting.*

Budding in Free Medusæ. By W. K. Brooks. *Amer. Nat.*

Development of Marine Polychætous Annelids. By E. B. Wilson. *Zoölogischer Anzeiger.*

Embryology and Metamorphosis of Lucifer. By W. K. Brooks. *Zoölogischer Anzeiger.*

The Early Stages of Renilla. By E. B. Wilson. *Amer. Journal of Science.*

"Other abstracts are now in the press, and others are ready for publication.

"A paper, with four plates, on the 'Early Stages of the Squid,' is also in the press, and will soon be issued in the Memorial Volume of Memoirs of the Boston Society of Natural History."

ELASTICITY OF WIRES[1]

THE experiments described in this paper form a continuation of experiments undertaken in connection with the work of the Committee of the British Association for commencing secular experiments on the elasticity of wires.

Long-continued application of stretching force increases to a very great extent the tensile strength of soft iron wire. Thus in experiments described to the British Association in 1879 (see Report of the Committee just referred to), a particular very soft iron wire was shown to have a breaking weight 10 p.c. higher if the weight necessary to break it is applied half a pound at a time per day, than it has if the breaking weight is applied half a pound at a time at intervals of say two minutes. It was found also that this wire, quickly broken, extends before breaking by as much as 25 p.c. of its original length; whereas if the application of the stress is very slow, the extension is not more than 5 or 6, or perhaps 8 p.c. Further experiments have been undertaken on this subject, and are still in progress.

Using a continuous arrangement for applying the stretching weight and employing some very soft iron wire which had been specially prepared, and which was used in former experiments, the greatest weight which could be rapidly put on the wire without breaking it was determined. It was found that with a weight of 41 lbs. gradually applied in 6¼ minutes the wire stretched by 24·4 p.c. of its original length, and broke 18 minutes after the weight was put on. With the same weight, 41 lbs., applied in 6¾ minutes, the wire stretched 22·1 p.c. and broke in 24 minutes. With 41 lbs., however, applied in 7½ minutes, the wire stretched 18 p.c., and did not break. This weight, therefore, appeared to be just as much as the wire would bear with this method of applying the weight. Accordingly it was applied to a great number of wires for different lengths of time for the purpose of hardening them, and arrangements have been made for keeping a number of wires for very long times with this stretching force applied to them. The amount of extension produced by the application of the hardening stress was observed in each case.

After the hardening stress had been applied for a certain time the additional weight necessary to break the wire was determined, and also the additional elongation before breaking, which was in all cases almost insensible. The wires seemed permanently set in about forty minutes from the time when the hardening stress was applied. They did not alter in length till just before they broke, when they generally stretched 1 or 2 millimetres on a length of about 1,800 mm. The following table shows some of the results out of a great many that have already been obtained.

Length of wire used.	Hardening stress applied in pounds.	Time taken by continuous machine in applying the hardening stress in minutes.	Extension produced by application of hardening stress in p.c. of original length.	Duration of hardening stress in hours.	Total breaking weight after hardening.
150 cm.	41	6½	24·4	Broke with 41 lbs.	
,,	,,	6¾	22·1		
,,	,,	9½	18·7	24	47·44
,,	,,	7	17·2	27	47·5
,,	,,	8	17·3	117	48·13
,,	,,	7½	18·1	790	52·31

Curves have also been obtained and were exhibited to the Section showing the extension with gradually applied weights both of a number of wires and of the different parts of the same wire; also curves showing the extension at different intervals of time from the beginning of an experiment in which the wire is running down under a weight sufficient to break it finally.

The author acknowledged the great assistance that he had received from Mr. A. C. Crawford and other students the in Physical Laboratory of the University of Glasgow.

Similar experiments are in progress on wires of copper and tin, and it is intended to test gold wire very soon, as it will probably give interesting results, and results very different from those given by soft iron wires.

[1] Strength and Elasticity of Soft Iron Wires. Abstract of a Paper read at the British Association, by J. T. Bottomley, M.A., F.R.S.E.

SPECTROSCOPIC NOTES, 1879-80.

DOUBLE Reversal of Lines in Chromosphere Spectrum.—The magnesium lines of the *b* group, and the two D-lines of sodium have been seen several times (first on June 5, 1880) *doubly-reversed* in the spectrum at the base of a prominence.

A bright line first appears in the centre of the widened dark lines; then this bright line grows wider and hazy at the edge, and a thin dark line appears in its centre, as shown in the figure. The phenomenon lasts usually from ten minutes to an hour. It is evidently the exact correlative of the double reversal of the bright sodium lines, observable in the flame of a Bunsen burner or alcohol lamp under certain circumstances when the quantity and temperature of the sodium vapour in the flame are greatly increased.

The H-lines in the Chromosphere and Sun-spot Spectra.—In 1872 I found the H- and K-lines to be reversed in the spectra of prominences and sun-spots, as observed at Sherman, 8000 feet above the sea. Until recently I have not been able to verify the observation, except for a moment during the eclipse of 1878. During the past summer, however, I have succeeded in seeing them again, and with suitable precautions as to shade-glass, adjustment of slit to true focal plane for these special rays, and exclusion of extraneous light, I have no further difficulty with the observation. The spectroscope employed has collimator and view-telescope each of 1¼ inches aperture, and about 13 inches focal length, and a speculum-metal Rutherfurd grating with 17,300 lines to the inch. A shade of cobalt-blue glass greatly aids the observation. The solar image is 1¼ inches in diameter.

In the spectrum of the chromosphere, H and K are both *always* reversed. I have never failed to see them both when circumstances were such that *h*, the nearest of the hydrogen lines, could be seen.

Furthermore, H, in the chromosphere spectrum, is *always double:* that is, a fine bright line always accompanies the principal line, about one division of Ångström's scale below. The principal line seems to be exactly central in the wide dark shade, the other is well within the nebulosity. K on the other hand shows no signs of duplicity.

In the spectrum of a sun-spot H and K are also, both of them, generally, though not always, reversed; and the reversal is not confined to the spot, but covers often an area many times larger in its neighbourhood.

In the spot spectrum, however, H has never yet been seen double. The companion line of H is therefore probably due to some other substance than that which produces H and K; a substance prominent in the chromosphere, but not specially so in the neighbourhood of spots. In view of the recent observations of Vogel, Draper, and Huggins, it is natural to think that hydrogen is probably the element concerned. If so, it may be expected that H will be found doubled in the spectrum of a spot which reverses the hydrogen line *h*. I have not yet been able to test it in this way, as *h* is rarely seen reversed, though C and F occur pretty frequently.

[*Note.*—An observation made since my paper was written leads me to modify this opinion, that the companion of H is due to hydrogen, and satisfies me that in all probability both H and K must themselves be hydrogen-lines. At 11 A. M. on October 7, a bright horn appeared on the S.E. limb of the sun. When first seen it was about 3′ or 4′ in elevation, but it rapidly stretched up, and before noon reached a measured altitude of over 13′ (350,000 miles +) above the sun's limb. It faded away and disappeared about 12.30. It was brightest about 11.30 with an altitude of about 8′ and at this time both H and K were distinctly, and for them, brilliantly reversed in it clear to the summit. H was not double in it to any notable elevation, though the companion of H was visible at the base of the prominence. The H- and K-lines also showed evidence of violent cyclonic action, just as C did. *h* was only faintly visible in the prominence; F and the line near G were of course strong. But no other lines, either of sodium, magnesium, or anything else, could be traced more than a very few seconds of arc above the sun's limb. I am not able to say how long the H-lines continued visible, or to what elevation they extended afterwards, as I returned to the C-line to watch the termination of the eruption. If I remember rightly, this eruption reached a higher elevation than any before observed. There was (and is to-day) nothing on the sun's limb visible with the telescope which would account for it.—Princeton, October 8.]

Examination of Lines in the Solar Spectrum which are given in the Maps as common to Two or more Substances.—For this purpose a spectroscope of high dispersion has been constructed by combining the grating mentioned above, which has about 4 square inches of ruled surface, with a collimator and observing telescope each of 3 inches aperture and about 42 inches focal length, using magnifying powers ranging from 50 to 200. The apparatus is arranged upon a wooden frame-work, and when in use is strapped to the tube of the 12-feet equatorial of our observatory, so that it is kept by the driving-clock directed to the sun. An image of the sun is formed on the slit by an achromatic object-glass of 3 inches aperture, in order to increase the light and to avoid the widening of the lines due to the sun's rotation. A large prism of about 20° angle was sometimes placed in front of this object-glass (between it and the sun) to separate the colours before reaching the slit; and in examining the darker portions of the spectrum a concave cylindrical lens was sometimes used next the eye, like a shade glass, to reduce the apparent width of the spectrum and thus increase its brightness.

The grating is an admirable one, on the whole the best I have ever seen. But I have been greatly surprised at its excessive sensitiveness to distortion by pressure or inequalities of temperature. Although the plate is fully $\frac{3}{8}$ of an inch thick, and only $3\frac{1}{2}$ inches square, an abnormal pressure of less than a single ounce at one corner will materially modify its behaviour, and a quarter of a pound destroys the definition entirely. In fact the plate is not naturally exactly flat, and to get its best performance it is necessary to crowd a little wedge gently under one corner. When it is in good humour and condition, however, the performance is admirable; one could wish for nothing better, unless for a little more light in the violet portions of the spectrum.

With this instrument I have examined the 70 lines given on Ångström's map as common to two or more substances. Of the 70 lines, 56 are distinctly double or triple; 7 appear to be single; and as to the remaining 7, I am uncertain; in most cases, because I was unable to identify the lines satisfactorily on account of their falling upon spaces thickly covered with groups of fine lines, none of which are specially prominent.

As a general rule the double lines are pretty close, the distance being less than that of the components of the 1474 line. Generally also the components are unequal in width or darkness, or both, though in perhaps a quarter of the cases they are alike in appearance. The doubtful lines are the following, designated by their wave length on Ångström's map: 5489·2, 5425·0, 5396·1, 5265·8, 4271·5, 4253·9 and 4226·8. I strongly suspect 5396·1 and 5265·8 (which present no difficulty in identification) of being double, but could never fairly split either of them, and therefore leave them among the doubtfuls.

Those which show no signs of doubling, so far as could be seen, were: 6121·2, 6064·5, 5019·4, 4585·3, 4578·3, 4249·8, and 4237·5.

In respect to the lines 5019·4, 4585·3 and 4237·5 it is quite possible there may be some mistake as to the coincidence, since in his *tables* Thalén gives neither of them as due to iron. An accidental strengthening of the dotted line, which, on the map, leads up from the symbol of the element concerned, through the iron spectrum, would account for the matter, by making the line appear on the map as belonging to iron also.

As the facts stand, therefore, it is obvious that arguments which have been based upon the coincidence of lines in the spectra of different elements lose much of their force; it appears likely that the coincidences are in all cases only near approximations. At the same time this is certainly not yet demonstrated. The complete investigation of the matter requires that the bright line spectra of the metals in question should be confronted with each other and with the solar spectrum under enormous dispersive power, in order that we may be able to determine which of the components of each double line belongs to one, and which to the other element. If in this research it should be found that *both* of the components of a double line were represented in the spectra of two different metals, and the suspicion of impurity were excluded, we should then indeed have a most powerful argument in favour of some identity of material or architecture in the molecules of the two substances involved.

Distortion of Solar Prominences by a Diffraction Spectroscope.—Generally, in such an instrument, the forms seen through the opened slit are either disproportionately extended, or compressed along the line of dispersion. The reason is this: if the slit be illuminated by monochromatic light, the image of the slit, formed on each side of the simple reflected image in the focus of the view-telescope (which is supposed to have the same focal length as the collimator), will have the same width as the slit itself only in one special case, not usually realised with a reflecting grating.

If the angle, between the normal to the grating and the view-telescope, is *less* than that between the normal and the collimator, the slit-image will be *narrower* than the slit, and a prominence seen through it will be *compressed* in the plane of dispersion. If the relation of the angles be reversed, then of course the distortion will also be reversed, and we shall have extension instead of compression.

The mathematical theory is very simple. Suppose the collimator and telescope to be fixed at a constant angle, as in the now usual arrangement.

Let angle between telescope and collimator $= \alpha$.

Angle between telescope and normal to grating $= \tau$.

Then angle between collimator and normal $= \kappa = \alpha - \tau$.

Also, let space between adjacent lines of grating $= s$.

And the order of spectrum observed $= n$.

Then, by principles of spectrum formation, we have

$$\lambda = \frac{s}{n}\left\{\sin\tau - \sin\kappa\right\},$$

λ being the wave-length of the ray which is in the centre of the field of view:

whence $$\sin\tau = \frac{n\lambda}{s} + \sin\kappa.$$

Differentiating, we have at once

$$d\tau = \frac{\cos\kappa}{\cos\tau}d\kappa, \text{ or } \frac{\cos(\alpha-\tau)}{\cos\tau}d\kappa;$$

which reduces to, $d\tau = (\cos\alpha + \sin\alpha\tan\tau)\,d\kappa$. Distortion can only disappear in cases when this coefficient of $d\kappa$ reduces to unity. Special cases—

1. If $\tau = \kappa$ there is no distortion—but also no dispersion: it is the case of simple reflection.
2. If $\kappa = 0$, the grating being kept normal to the collimator, then $d\tau = \sec\alpha\, d\kappa$.
3. If $\tau = 0$, the grating being kept normal to the telescope (which in this case must be movable), then $d\tau = \cos\alpha\, d\kappa$.
4. If $\alpha = 90°$, $d\tau = \tan\tau\, d\kappa$.
5. If $\alpha = 0$, $d\tau = d\kappa$, and there is no distortion.

This is possible only by using the same tube and object-glass both for collimator and view-telescope, the grating being slightly inclined at right angles to the plane of dispersion. The principal difficulty in this form of instrument lies in the diffuse light reflected by the surfaces of the object-glass. It is hoped that this may be nearly obviated by a special construction of the lens which will throw the reflected light outside of the eyepiece. An instrument on this plan is being made for Prof. Brackett by the Clarks, for use in the physical laboratory at Princeton, and is now nearly completed.

Princeton, September 27, 1880 C. A. YOUNG

UNIVERSITY AND EDUCATIONAL INTELLIGENCE

DR. J. E. HARRIS (D.Sc. Lond.) has been appointed to the vacant Professorship of Natural Philosophy at Trinity College, London.

FROM the new Calendar of the University College of Wales we learn that the present number of students is fifty-seven. We see there are classes for most of the branches of science, only unfortunately they are all taught by one professor, which, to say the least, must be rather hard on him. We hope the college will soon be able to have separate teachers, at any rate for the physical and biological sciences.

THE new University Library at Halle has just been opened. It is built entirely on the French system, and special precautions have been taken with regard to fire. It now numbers some 200,000 volumes, but there is room for half a million. The cost of the building amounts to 400,000 marks (20,000*l.*).

SCIENTIFIC SERIALS

THE *American Naturalist* for December, 1880, contains:—D. Cope, on the extinct cats of America.—F. V. Hayden, Twin

lakes and Teocalli Mountain, Central Colorado, with remarks on the glacial phenomena of that region.—C. E. Bessey, sketch of the progress of botany in the United States in the year 1879.—C. S. Minot, sketch of comparative embryology, No. 5; on the general principle of development.—The Editor's Table.—Permanent exhibition of Philadelphia.—Recent literature.—A new edition of Packard's "Zoology" is announced.—General Notes. Scientific news. Proceedings of scientific societies.

Revue des Sciences Naturelles, December, 1880, contains: Herborisations of Strobelberger about Montpellier in 1620, translated, with notes, by M. Kieffer (a complete *exposé* of the extraordinary plagiarism of Strobelberger, who copied his work on the plants of Montpellier almost *verbatim* from the work of Lobel).—M. Doumet-Adanson, on an immense Calamary taken near Cette, January, 1880 (*Ommastrephes sagittata*). This specimen was nearly six feet in length, from the end of the body to the tops of the arms.—M. S. Jourdain, on the late development of scales in the eels.—E. Dubrueil, catalogue of testaceous mollusca collected from the French shores of the Mediterranean.—M. Reitsch, an analysis of Falkenberg's researches on the fecondation and alternation of generation in Cutleria.—F. Fontannes, on the stratigraphical position of the Pliocene group of Saint Aries, in the Western Bas-Dauphiné, and particularly in the environs of Hauterives (Drôme).—Scientific Reports and Bulletin.

Gegenbaur's morphologisches Jahrbuch, Band 6, Heft 4.—Dr. M. v. Davidoff, contribution to the comparative anatomy of the posterior limb masses in fishes, 2nd part (Plates 21, 23); Dr. W. Pfitzner, on the epidermis in the amphibia (Plates 24, 25); J. E. V. Boas, on the conus arteriosus in *Butirinus albula* and in other Teleostei (Plate 26); Dr. H. Rabl-Rückhard, on the mutual relations between the chorda, hypophysis and the middle ridge of the skull in the embryos of the sharks', &c., brains (with Plates 27, 28); Carl Rabl, on the "pedicle of invagination," &c., in Planorbis (Plate 29); Prof. R. Wiedersheim, on the duplication of the os centrale in the carpus and tarsus of Axolotl (Plate 30); Prof. C. Gegenbaur, critical remarks on polydactylism as atavism; short notices; W. Leche, on the morpology of the pelvic region in the Insectivora.

Archives des Sciences Physiques et Naturelles, December 15, 1880.—Tertiary man in Portugal, by M. Choffat,—Monograph of the ancient glaciers and the erratic formation of the middle part of the Rhone valley, by MM. Falsan and Chantre.—Organic dust of the atmosphere, by Dr. Yung.—On the question of lowering of the high waters of the Lake of Constance, by M. Achard.

SOCIETIES AND ACADEMIES

LONDON

Royal Society, January 6.—Observations on the Structure of the Immature Ovarian Ovum in the Bird and Rabbit, and on the Mode of Formation of the Discus Proligerus in the Rabbit and of the "Egg-Tubes" in the Dog. By E. A. Schäfer, F.R.S.

The first part of the paper is devoted to a minute description of the young ovarian ova of the bird as seen in sections of the ovary of a laying hen. The germinal spot is described as composed of two distinct substances, namely, a homogeneous matrix staining but slightly with logwood and a number of coarse granules imbedded in it, which become darkly stained. The germinal spot may often be seen to be connected with the wall of the germinal vesicle by a network of fine filaments (intranuclear network). Appearances are also described which indicate that two germinal vesicles may be originally present in one ovum (? formed by the fusion of two primitive ova), and that one of the two may afterwards disappear.

A network of filaments is also described as existing in the yolk, which in some ova shows peculiar condensations of vitelline substance, which simulate nuclei; but the origin and meaning of these are left in doubt. Other appearances, as of systems of striæ, are also mentioned as occurring in larger ovarian ova. With regard to the membranes of the ovum the author differs from Waldeyer and agrees with Balfour in regarding the *zona radiata* as a product of the protoplasm of the ovum, and not as derived from the cells of the follicular epithelium.

The ovarian ovum of the rabbit is next described, and is found to agree in most essential particulars with that of the bird. The *zona pellucida* is porous, and allows granules of food-material to pass from the epithelium cells of the Graafian follicle directly into the vitellus. But it is chiefly in this epithelium that the interest centres, for the inner layer of cells of the follicular epithelium appears to be formed in the peripheral layer of the vitellus of the ovum itself, making their appearance first of all as mere nuclei (derived in all probability from the nucleus of the ovum), around which part of the protoplasm or vitellus of the ovum becomes segmented off. This description is compared with that which Kuppfer gives of the formation of an inner layer of follicular epithelium from nuclei which make their appearance in the periphery of the vitellus of the ovum of *Ascidia canina*, and with the observations of Kleinenberg upon the formation of a layer of cells from the periphery of the ovum of *Hydra*.

Finally the gland-like nature of the ovarian tubes in the bitch's ovary is insisted upon in agreement with Pflüger and Waldeyer, and in opposition to the view taken by Foulis.

January 13.—"On the Forty-eight Co-ordinates of a Cubic Curve in Space," by William Spottiswoode, President R.S.

In a note published in the *Report* of the British Association for 1878 (Dublin), and in a fuller paper in the *Transactions* of the London Mathematical Society, 1879 (vol. x. No. 152), I have given the forms of the eighteen, or the twenty-one (as there explained), co-ordinates of a conic in space, corresponding, so far as correspondence subsists, with the six co-ordinates of a straight line in space. And in the same papers I have established the identical relations between these co-ordinates, whereby the number of independent quantities is reduced to eight, as it should be. In both cases, viz., the straight line and the cubic, the co-ordinates are to be obtained by eliminating the variables in turn from the two equations representing the line or the conic, and are, in fact, the coefficients of the equations resulting from the eliminations.

In the present paper I have followed the same procedure for the case of a cubic curve in space. Such a curve may, as is well known, be regarded as the intersection of two quadric surfaces having a generating line in common; and the result of the elimination of any one of the variables from two quadric equations satisfying this condition is of the third degree. The number of coefficients so arising is $4 \times 10 = 40$; but I have found that these forty quantities may very conveniently be replaced by forty-eight others, which are henceforward considered as the co-ordinates of the cubic curve in space.

The number of identical relations established in the present paper is thirty-four. But it will be observed that the equations are lineo-linear in each of two groups, say the U-co-ordinates and the U'-co-ordinates; and as we are concerned with the ratios only of the coefficients, and not with their absolute values, we are, in fact, concerned only with the ratios of the U-co-ordinates *inter se*, and the U'-co-ordinates *inter se*, and not with their absolute values. Hence the number of independent co-ordinates will be reduced to $48 - 34 - 2 = 12$, as it should be.

Mathematical Society, January 13.—S. Roberts, F.R.S., president, in the chair.—Miss C. A. Scott and Messrs. J. Parker Smith, O. H. Mitchell, Fellow of Johns Hopkins University, and T. Craig, U.S. Coast Survey Office, Washington, were elected members. Dr. Hirst, in drawing attention to the loss the Society had sustained by the death of M. Chasles, gave a rapid sketch of that distinguished geometer's career and work; in lightly touching upon his private life he mentioned how gratified M. Chasles had been by the fact that he was not only the first Foreign Member of the Society, but for a long time the only one. The following communications were made:—On an apparently paradoxical relation of the circle, parabola, and hyperbola, by A. J. Ellis, F.R.S.—A proof of the differential equation which is satisfied by the hypergeometric series, by the Rev. T. R. Terry.—On the periodicity of hyperelliptic integrals of the first class, by W. R. W. Roberts.—On the tangents drawn from a point to a nodal cubic, by R. A. Roberts.—Sur une propriété du paramètre de la transformée canonique des formes cubiques ternaires, by Signor Brioschi (Milan).—Note on a kinematical theorem connected with the rectilinear courses of two vessels sailing uniformly, by C. W. Merrifield, F.R.S.—A partition-problem connecting the angles of a triangle with the angles of the successive pedal triangles, by J. W. L. Glaisher, F.R.S.

PARIS

Academy of Sciences, January 10.—M. Wurtz in the chair.—The following papers were read:—On the conditions

relative to the theoretic expression of the velocity of light, by M. Cornu.—Crystalline substances produced from old medals immersed in the thermal waters of Baracci, commune of Olmeto (Corsica), by M. Daubrée. Some of these bronze medals had merely a dark patina resulting from superficial sulphuration. A few others had a thick crystalline crust, the substance being apparently a double sulphide of copper and tin (of which the nearest natural analogue would be stannine). The water, containing only 0·3 gr. of mineral matters per litre, has chloride of sodium, sulphate of soda, and silica in predominance.—On the star-fishes dredged in the deep regions of the Gulf of Mexico and the Carribean Sea by the American ship the *Blake*, by M. Perrier. The new collections raise the number of species from twenty-seven to seventy. A pretty large number are new generic types.—On a class of linear differential equations, the coefficients of which are algebraic functions of the independent variable, by M. Appell.—On the circulatory apparatus of isopod crustaceans, by M. Delage.—Phylloxera in California, by M. de Lavignon. The old vine-growers say they have always known it, and they do not regard it as introduced with plants from Bordelais. Its effects are the same in kind as in France, but its progress is very slow by reason of absence (apparently) of the winged insect, quality of the soil (rich and deep), and the existence of an acarian parasite (*Tyroglyphus longior*).—The Inspector-General of Navigation reported on the variations of the Seine at Paris in 1880. The highest water was on January 4, the lowest on February 3 and 4.—On a process of astronomical observation for use of voyagers, &c. (continued), by M. Ronget.—On the transformation of reciprocal directions, by M. Laguerre.—On the size and variations of Purkinje's images, by M. Crouillebois. It is proved that the mechanism of the adaptation consists in a simultaneous modification of the curvature of the two faces of the crystalline lens.—Thermo-regulator for high temperatures, by M. D'Arsonval. This is applicable up to 1200° at least. A regulator like that before described has its space under the membrane connected by means of a capillary tube with a short hollow stem which can be opened or closed with a screw and is connected by two tubes with a mercury manometer, and an air-reservoir (of glass or porcelain) to be put in the medium that is to be kept constant. For temperatures over 300° he opens the stem when 1 atm. has been reached, and so lets the manometer come back to zero before closing again. A new method of reading must then, of course, be adopted.—Investigation of gaseous compounds and study of some of their properties with the spectroscope, by MM. Hautefeuille and Chappuis. With the spectroscope one can follow the isomeric change of ozone into oxygen, and prove that its destruction does not give hyponitric acid. Electrification of a dry mixture of nitrogen and oxygen, containing at least one-seventh of the former, gives a substance not before observed, and having a remarkable absorption-spectrum. It is thought to be *pernitric acid*, analogous to M. Berthelot's *persulphuric acid*.—On bromides and iodides of phosphorus, by M. Ogier.—Rapid stoppage of the rhythmic contractions of the cardiac ventricles through occlusion of the coronary arteries, by MM. Sée, Bochefontaine, and Roussy.—On the application of anatomical examination of the blood to diagnosis of disease, by M. Hayem. He gives two methods: examination of pure blood, in a thin layer, of constant thickness; and examination of blood diluted with a special reagent. The phenomena in certain diseases are described.—On the quantity of light necessary to perceive the colour of objects of different surfaces, by M. Charpentier. For retinal surfaces $\frac{88}{1000}$ to $\frac{4400}{1000}$ mm. square the illumination necessary to make or perceive colour (once the luminous sensibility is obtained) was the same for each colour tried. It may, then, be said that for red, yellow, green, and blue the chromatic sensibility is independent of the retinal surface excited. Influence exerted by environment on the form, structure, and mode of reproduction of *Isoetes lacustris*, by M. Mer.—On the conservation of grain in closed reservoirs, by M. Muntz. With renewal of air he found about ten times more CO_2 produced than in a closed vessel. The volume of CO_2 found in contact with air is always less than that of O absorbed. The O is chiefly fixed by fatty matters. Too dry grain, not giving much of an asphyxiating atmosphere, is liable to the ravages of insects. The proportion of CO_2 increases rapidly with the degree of moisture. As the temperature is raised there is physiological combustion up to a point (about 50°), thereafter chemical. Anæsthetics, like sulphide of carbon, diminish, without stopping, the formation of CO_2.—On a simple means of bringing to life new-born infants in a state of apparent death, by M. Gozard. He describes a successful application of M. Le Bon's suggestion for young asphyxiated animals, immersing in a water-bath heated 45° to 50°.—M. Boutigny invited attention to the fact that boiling water projected on an incandescent surface instantly falls in temperature to 97°. He attributes this cooling to work done in production of the spheroidal state.

BERLIN

Geographical Society, January 8.—Dr. Nachtigal, president.—The President gave a sketch of the work of the Society's explorers for the past year. It was hoped that Dr. Lenz would have been present at the meeting, but he had been unable to leave St. Louis in Senegal, as yellow fever prevailed there. After a long interval letters had been received from Dr. Buchner, dated February, May, and July last. He had been for six months in Mussumba in Muatà Janvo's kingdom, carrying on topographical, photographic, and natural history work. After sending most of his papers and collections to Angola he proceeded northwards, writing on July 1 from Muene Chikambo. Dr. Nachtigal then referred to the East African Expedition, which, along with Capt. Ramseckers, has arrived at Tabora, and Dr. Rohlfs' party, who on December 12 were at Massowah.—Herr Buchter exhibited a large number of photographs and drawings from the Upper Nile.

VIENNA

Imperial Academy of Sciences, January 7.—On the quantitative relations of electric expansion in glass and caoutchouc, by G. Korteweg and V. A. Julius.—Preliminary note on decomposition of water, by C. Baudet.—Researches on fats, by D. G. Goldschmiedt and M. v. Schmidt.—On an uncrystallisable acid obtained from albumen by oxidation with permanganate of potash, by E. v. Bruecke.

CONTENTS

	Page
North American Pinnipeds	261
Catalogue of Newcastle Libraries	262
Our Book Shelf:—	
"Botanische Jahrbücher für Systematik Pflanzengeschichte und Pflanzengeographie"	263
Day's "Fishes of Great Britain and Ireland"	264
Kent's "Manual of the Infusoria"	264
Palliser's "Complete Course of Problems in Practical Plane Geometry"	264
"Bericht über die Thätigkeit der Botanischen Section der Schlesischen Gesellschaft im Jahre 1877"	264
Letters to the Editor:—	
Dr. Carnelley's Hot Ice.—Dr. Oliver J. Lodge	264
On the Spectrum of Carbon.—Prof. G. D. Liveing, F.R.S.; Dr. W. M. Watts	265
Geological Climates.—Alfred R. Wallace; Dr. Maxwell T. Masters	266
Climate of Vancouver Island.—Wm. Pengelly, F.R.S.	267
Dimorphic Leaves of Conifers.—Dr. Maxwell T. Masters	267
Dust and Fogs.—Hon. R. Russell	267
Low Temperature.—Rev. S. J. Perry, F.R.S.	268
A "Natural" Experiment in Polarised Light.—Chas. T. Whitmell	268
Statics and Dynamics of Skating. By Charles Alex. Stevenson (*With Diagrams*)	268
John Duncan, the Albord Weaver and Botanist. By William Jolly	269
The Indo-Chinese and Oceanic Races—Types and Affinities. IV. By A. H. Keane (*With Illustrations*)	271
The Photophone. By Lord Rayleigh, F.R.S.	274
Notes	275
Our Astronomical Column:—	
Janson's Star of 1600	276
The New Cape Catalogue	276
Biological Notes:—	
Archæopteryx macrura	276
European and North American Birds	277
A Gnat with Two Kinds of Wives	277
The Function of Asparagine	277
A Cause of the Motion of Diatoms	277
Fungal Growths in the Animal Body	277
Brain-Weight	277
Physical Notes	278
Geographical Notes	278
Chesapeake Zoological Laboratory	280
Elasticity of Wires. By J. T. Bottomley, M.A., F.R.S.E.	281
Spectroscopic Notes, 1879-80. By Prof. C. A. Young	281
University and Educational Intelligence	282
Scientific Serials	282
Societies and Academies	283

SUBSCRIPTIONS TO NATURE

Yearly . . . . . 28s.
Half-yearly . . . . . 14s. 6d.
Quarterly . . . . . 7s. 6d.

To the Colonies, United States, the Continent, and all places within the Postal Union :—

Yearly . . . . . 30s. 6d.
Half-yearly . . . . . 15s. 6d.
Quarterly . . . . . 8s.

Office : 29, Bedford Street, Strand.

DIARY OF SOCIETIES.

LONDON

THURSDAY, JANUARY 20.

ROYAL SOCIETY, at 4.30.—On Gravimeters, with special reference to the Torsion Gravimeter designed by the late J. A. Broun: Major Herschel, F.R.S.—Experimental Researches into Electric Distribution as manifested by that of the Radicles of Electrolytes: A. Tribe —On the Tidal Friction of a Planet attended by several Satellites, and on the Evolution of the Solar System: G. H Darwin, F.R.S.—On the Female Organs and Placentation of the Racoon (*Procyon lotor*): Prof. Watson.—Further Note on the Minute Anatomy of the Thymus: H. Watney.

LINNEAN SOCIETY, at 8.—On some Hybrid British Ferns: Edwd. J. Lowe.—A Revision of the Genus *Vibrissea*: Wm. Phillips.

CHEMICAL SOCIETY, at 8.—On some Hydrocarbons present in Resin Spirit: H. E. Armstrong, F R S —Determination of the Relative Weight of Single Molecules: E. Vogel.—On the Oxidation of Organic Matter in Water: Arthur Downes, M.D.—Analysis of Queensland Soils: Prof. Liversidge.

NUMISMATIC SOCIETY, at 7.

LONDON INSTITUTION, at 7.—The Production of Electricity: Prof. Ayrton.

FRIDAY, JANUARY 21.

ROYAL INSTITUTION, at 9. The Phenomena of the Electric Discharge with 14,400 Chloride of Silver Cells: Warren De La Rue.

SOCIETY OF ARTS, at 8.—Forest Conservancy in India: Sir Richard Temple.

SATURDAY, JANUARY 22.

PHYSICAL SOCIETY, at 3.—On the Measurement of Small Resistances, and on a Method of comparing the Capacities of Two Condensers: R. T. Glazebrook.—On the Density of Bismuth in the Molten State: W. Chandler Roberts and T Wrightson.

EPPING FOREST NATURALISTS' CLUB, at 7.—Annual General Meeting.

SUNDAY, JANUARY 23

SUNDAY LECTURE SOCIETY, at 4.—The Wandering Jew: Moncure D. Conway.

MONDAY, JANUARY 24.

LONDON INSTITUTION, at 5.—Problems in the History of Civilisation: Dr. E. B. Tylor.

TUESDAY, JANUARY 25.

ANTHROPOLOGICAL INSTITUTE, at 8.—Anniversary.

WEST LONDON SCIENTIFIC ASSOCIATION, at 8.

ROYAL INSTITUTION, at 3.—The Blood: Prof. Schäfer.

WEDNESDAY, JANUARY 26.

ROYAL SOCIETY OF LITERATURE, at 8.—On a Recent Tour in Spain, with Notices of Al-Hamra and of Spanish Customs: Robert N. Cust

SOCIETY OF ARTS, at 8.—Trades' Mark Registration: Edmund Johnson.

THURSDAY, JANUARY 27.

ROYAL SOCIETY, at 4.30.

LONDON INSTITUTION, at 7.—Manufacture of Indigo from Coal: Prof. Armstrong.

SOCIETY OF ARTS, at 8.—A New Mechanical Furnace, and a Continuous System of Manufacturing Sulphate of Soda: James Mactear.

ROYAL INSTITUTION, at 3.—The Troubadours: F. Hueffer.

FRIDAY, JANUARY 28.

QUEKETT MICROSCOPICAL CLUB, at 8.—On Sponges: B. W. Priest.—On *Filariæ*: Dr T. S. Cobbold.

ROYAL INSTITUTION, at 9.—Modern Spectroscopy: Dr. Schuster.

SATURDAY, JANUARY 29.

ROYAL INSTITUTION, at 3.—The Amazons: Prof. S. Colvin.

EAGLE INSURANCE COMPANY,

79, PALL MALL.

FOR LIVES ONLY. ESTABLISHED 1807.

Accumulated Funds £3,043,542
Also a Subscribed Capital of more than £1,500,000

Reports, Prospectuses, and Forms may be had at the Office, or from any of the Company's Agents, post free.

GEORGE HUMPHREYS, Actuary and Secretary.

On the 1st of every Month, price One Shilling.

THE ZOOLOGIST:

A MONTHLY MAGAZINE OF NATURAL HISTORY.

Third Series. Edited by J. E. HARTING, F.L.S., F.Z.S., Member of the British Ornithologists' Union; contains—

Original articles by well-known naturalists in every branch of zoology; habits of animals; arrival and departure of migratory birds; occurrence of rare birds; distribution and migration of British fresh-water fish; new or rare marine fish; local aquaria; British reptiles; British land and fresh-water mollusca, with remarks on the haunts and habits of the species; and other matters of general interest to those who delight in natural history. Reports of the Linnean, Zoological, and Entomological Societies. Reviews of natural history books. Occasional translations from foreign zoological journals of important and interesting articles in various branches of zoology. There are occasional woodcuts.

JOHN VAN VOORST, 1, Paternoster Row.

LIGHTNING CONDUCTORS.

Experience, accumulated since the time of Benjamin Franklin, proves conclusively that a Conductor made of Copper of adequate size is the best of all appliances for the protection of every description of building from the destructive effects of lightning.

NEWALL & CO.'S

PATENT COPPER LIGHTNING CONDUCTOR,

As applied to all kinds of Buildings and Shipping in all parts of the world with unvarying success; is the most Trustworthy, most Effective, and also the Cheapest Conductor ever offered to the public.

It is simple in its application, no insulators being required, and it costs only one shilling per foot for the standard size, which ensures safety in any storm.

R. S. NEWALL & CO., 130, STRAND, W.C.
36, WATERLOO ROAD, LIVERPOOL.
68, ANDERSTON QUAY, GLASGOW.
MANUFACTORY—GATESHEAD-ON-TYNE.

GIMINGHAM'S SPRENGEL AIR-PUMP,

with Multiple Fall Tubes and every recent improvement, including McLeod's Barometer Gauge, Radiometer, Terminals for testing non-conductivity of the Vacuum, &c., &c.

L. CASELLA having arranged with Mr. GIMINGHAM for the Sole Manufacture of these Pumps, as well as his Improved Forms of

CROOKES'S RADIANT MATTER TUBES,

Is prepared to supply them either in their simple form, or with any of their accessories.

Mr. GIMINGHAM has kindly engaged to examine each, in order that no Imperfect Instrument or Tubes may be sent away.

Also GIMINGHAM'S COMBINATION BLOWPIPE for Amateur and Professional Glass Work, the most simple and perfect in use.

L. CASELLA, 147, Holborn Bars, London, E.C.

NOW READY.

SECOND EDITION,

GRIFFIN'S

CHEMICAL HANDICRAFT.

PRICE 4s. 7d. POST FREE.

A CATALOGUE OF CHEMICAL APPARATUS:

ILLUSTRATED, CLASSIFIED, DESCRIPTIVE.

Demy 8vo, 480 pp., Illustrated with 1,600 Woodcuts.

Most Complete and Cheapest List of Apparatus.

JOHN J. GRIFFIN AND SONS, 22, GARRICK STREET, LONDON, W.C.

Liberal Terms to Science Teachers and the Trade.

THOMAS CRAMPTON & Co. (formerly of

4, Little Britain, London, E.C.), ELECTRICIANS, OPTICIANS, and PHILOSOPHICAL INSTRUMENT MAKERS. Electric Bells, New Metallic Base Pattern, Constant Batteries, Indicators, Thief and Fire Alarms, and Automatic Switches. Induction and Medical Coils, or Specialities. Insulated Wires of every description. Microscopic and Optical Materials. Telescopes, Opera Glasses, Microscopes, Aneroid Barometers, and Lime-light Apparatus. Illustrated Catalogue Three Stamps.

THOMAS CRAMPTON & CO., 251, HIGH HOLBORN, LONDON, W.C.

For Trade Terms send Card.

£5 5s. ASTRONOMICAL TELESCOPE.

CRAMPTON & CO.'S IMPROVED TELE-

SCOPE is of the highest workmanship and finish, combined with great power and clearness of definition; is entirely constructed of polished brass, with 3-inch Achromatic Object Lens, Altitude and Azimuth Movements, Rackwork, and Fine Adjustment, &c., &c.

THOMAS CRAMPTON & CO., 251, HIGH HOLBORN, LONDON, W.C.

NOTICE OF REMOVAL.

JAMES HOW & CO.,

SCIENTIFIC INSTRUMENT MAKERS,

73, FARRINGDON ST., LONDON

(LATE OF 5, ST. BRIDE ST., AND 2, FOSTER LANE).

HOW'S STUDENT'S MICROSCOPE. HOW'S MICROSCOPE LAMP.

Rock Sections and other Objects for the Microscope.

YORK'S

SERIES of SCIENTIFIC OPTICAL LANTERN SLIDES

Comprise over 2,000 of the following subjects:—Electricity, Magnetism, Sound, Telephone, Microphone, Electric Light, Light, Spectrum Analysis, Astronomy, Mines and Miners, Heat, Mechanics, Hydrostatics, Pneumatics, Human Physiology. Sample Slide and Catalogue sent on receipt of 2s.

F. YORK, OPTICAL LANTERN SLIDE MANUFACTURER,
87, Lancaster Road, Notting Hill, London, W.

W. LADD & CO.,

SCIENTIFIC INSTRUMENT MANUFACTURERS,

(By Appointment to the Royal Institution of Great Britain),

11 AND 12, BEAK STREET, REGENT STREET, W.

IMPROVED HOLTZ ELECTRICAL MACHINES. GRAMME'S MAGNETO-ELECTRIC MACHINE for Laboratory use.

PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3*s.* per oz.

Physical Apparatus of every Description.

ILLUSTRATED CATALOGUE, SIXPENCE.

PATERSON'S NEW CATALOGUE OF PHYSICAL APPARATUS.

LANTERN SLIDES for SCIENTIFIC LECTURES. Season 1880–1. Post free 6 Stamps.
Complete Sets of Physical Apparatus for Science Primers and all the Physical Text-books in use in Schools and Colleges.
Siemens and Gramme Dynamo Machines and Lamps for hire.
Schools supplied with Apparatus as per Science and Art Departments' Requirements in the Sections of Light, Heat, Sound, and Electricity.
Electric Signals for Houses, Hotels, &c., Colliery Signals, Lightning Conductors. The Gower-Bell Loud-speaking Telephone.

EDWARD PATERSON, Electrical Engineer.

SHOW ROOMS AND STEAM WORKS:—76, LITTLE BRITAIN, E.C. (late 3, Bedford Court, W.C.).

MOLISON'S HARMONOGRAPH; executes the Harmonic Curves in the most perfect manner. 15*s.* and 20*s.*

Illustrated Catalogue of Electrical Apparatus, Part 1, *post free,* 6 *Stamps. Ditto, Electric Signals, Part* 2, 6 *Stamps.*

FLETCHER'S
PATENT VENTILATED
HOT-AIR OVEN.

At a cost of less than one halfpenny per hour for gas this oven will grill, roast, toast, bake, warm dishes and plates; and with the assistance of Fletcher's Patent Solid Flame Boiling Burners will do everything possible with a first-rate open fire (except drying clothes on washing days).



It is unapproached by any oven for pastry, and is fully hot in one minute after the gas is lighted.

Fish, joint, and pastry can be cooked all at once, in the most perfect manner, without the slightest taint from one to the other. The cooking is always good and always alike.

It will roast joint and fowls both at once, at least as well as an open fire.

Complete illustrated list of gas cooking and labour-saving appliances free by post. List of Gas and Petroleum Laboratory Furnaces and Apparatus, price 2*d*

THOS. FLETCHER,
4 & 6, *MUSEUM STREET, WARRINGTON.*

HOLLOWAY'S PILLS THIS MEDICINE

Is a Certain Cure for all Disorders of the LIVER, STOMACH AND BOWELS. A Great PURIFIER of the BLOOD; a Powerful Invigorator of the System, in cases of WEAKNESS AND DEBILITY, and is unequalled in Female Complaints

BROKEN!!
DAVY'S DIAMOND CEMENT

SECURELY AND NEATLY MENDS
CHINA, GLASS,
CABINET WORK,
AND
FANCY ARTICLES.

Of all Chemists in 1*s.* Bottles.

See the name "E. DAVY," the Original Inventor, is on the Label, and also that of

BARCLAY & SONS, 95, Farringdon Street, London.

FRY'S COCOA EXTRACT

GOLD MEDAL,
PARIS EXHIBITION.

In Packets and Tins. Pure Cocoa only, with the superfluous oil extracted.

"If properly prepared, there is no nicer or more wholesome preparation of cocoa."—*Food, Water, and Air, edited by Dr. Hassall.*

J. S. FRY & SONS, Bristol and London.

R. W. NEEVES,
PHILOSOPHICAL INSTRUMENT
AND
INTENSITY COIL MAKER.

PRICE LIST, FOUR STAMPS.

55, SIDMOUTH STREET, LONDON, W.C.

THIN GLASS FOR MICROSCOPIC

MOUNTING, of best quality. Circles, 3*s.* 6*d.* per ounce; Squares, 2*s.* 9*d.*; post free 2*d.* extra; Ground edged Slips, 5*s.* per gross; also other Mounting Materials and Objects prepared for mounting.—CHAS. PETIT, 151, High Street, Stoke Newington, N.

S. C. TISLEY & Co.,
OPTICIANS,
172, BROMPTON ROAD, S.W.

(Close to South Kensington Museum)

THE PHONEIDOSCOPE

An Instrument for Observing the Colour-Figures of Liquid Films under the action of Sonorous Vibrations.

Being a visible demonstration of the Vibratory and Molecular Motion of a Telephone Plate.

The PHONEIDOSCOPE, with 3 Discs, Bottle of Solution, Descriptive Pamphlet, &c., in Cardboard Box, 10*s.* 6*d.*

MANUFACTURED AND SOLD WHOLESALE AND RETAIL BY
S. C. TISLEY & CO., 172, BROMPTON ROAD, LONDON, S.W.

TELEPHONIC ELECTRICITY. All Materials supplied for experimental purposes.

Price Lists of Electrical and Acoustic Apparatus, with Drawings and Description of the Harmonograph, Post Free 2d.

Messrs. MACMILLAN & CO.'S PUBLICATIONS.

NEW BOOKS ON IRELAND.

Disturbed Ireland, being the Letters Written during the Winter of 1880-81. By BERNARD H. BECKER, Special Commissioner of the *Daily News*. With Route Maps. Crown 8vo. 6*s*.

"Will be found one of the most trustworthy pictures of the sister island as it is . . . It has, especially at this moment, high political value."—*Examiner*.

The Life's Work in Ireland of a Landlord who Tried to do his Duty. By W. BENCE JONES of Lisselan. Crown 8vo. 6*s*.

"Mr. Bence Jones has written an interesting and instructive little book; but not the least enlightening part of it is the Preface, dated December 12th, 1880. He had just been threatened with Boycotting, which he now undergoes."—*St. James's Gazette*.

Life of William Blake. With Selections from his Poems and other Writings. Illustrated from BLAKE's own Works. By ALEXANDER GILCHRIST. A New and Enlarged Edition, with Additional Letters and a Memoir of the Author. 2 vols. Printed on hand-made paper, the Illustrations on India paper, and mounted in the text. Cloth elegant, gilt, with designs after BLAKE by FREDK. J. SHIELDS. Medium 8vo. 42*s*.

"One of the most beautiful and interesting books of the season."—*Daily News*.

"Without any reservation, it is undoubtedly one of the most tasteful and thorough editions of a fine art book which we ever remember to have seen."—*Notes and Queries*.

The Year's Art: A Concise Epitome of all matters relating to the Arts of PAINTING, SCULPTURE, and ARCHITECTURE, which have occurred during the Year, together with information respecting the events of the Year 1881. Compiled by MARCUS B. HUISH. Crown 8vo. 2*s*. 6*d*.

GOLDEN TREASURY SERIES.—NEW VOLUME.

Essays of Joseph Addison. Chosen and Edited by John Richard Green, M.A., LL.D. 18mo. 4*s*. 6*d*.

Dictionary of Music and Musicians (A.D. 1450—1878). *By Eminent* Writers, English and Foreign. Edited by GEORGE GROVE, D.C.L. Three Vols. 8vo, with Illustrations and Woodcuts. Parts I. to XII. each 3*s*. 6*d*. Vols. I. and II., 8vo, cloth, each 21*s*.

Vol. I. A to Impromptu. Vol. II. Improperia to Plain Song.

"This work promises to be for music what the best encyclopædias are to general literature and science."—*Guardian*.

English Poets: Selections, with Critical Introductions by various Writers, and a General Introduction by MATTHEW ARNOLD. Edited by T. H. WARD, M.A. 4 vols., crown 8vo, each 7*s*. 6*d*.

Vol. I. CHAUCER to DONNE.
Vol. II. BEN JONSON to DRYDEN.
Vol. III. ADDISON to BLAKE.
Vol. IV. WORDSWORTH to SYDNEY DOBELL.

"An excellent design admirably executed."—*Pall Mall Gazette*.

English Men of Letters. Edited by John Morley. Crown 8vo. 2s. 6d.

(New Volume.)

WORDSWORTH. By F. W. H. MYERS.

"Mr. Myers gives us a picture of the man and an estimate of his work which is certainly not inferior to anything that has preceded it."—*Academy*.

The Abbott's Farm; or, Practice with Science. By Henry Tanner, M.R.A.C., F.C.S., Professor of the Principles of Agriculture in the Royal Agricultural College, Author of "First Principles of Agriculture." Extra fcap. 3*s*. 6*d*.

Kamilaroi and Hurnai. Group-Marriage and Relationships, and Marriage by Elopement. Drawn chiefly from the usage of the Australian Aborigines: also the Kurnai tribe—their Customs in Peace and War. By LORIMER KINSON, M.A., and A. W. HOWITT, F.G.S. With an Introduction by LEWIS H. MORGAN, LL.D., Author of "System of Consanguinity," "Ancient Society," &c. Demy 8vo. 15*s*.

Gilbert White's Natural History and Antiquities of Selborne. New Edition, with a Poem and Letters never before published. Edited, with Notes and Memoir by FRANK BUCKLAND; a Chapter on Antiquities by Lord SELBORNE; and the Garden Kalendar. With Illustrations by Prof. DELAMOTTE. Cheap Edition. Crown 8vo. 6*s*.

Physics of the Earth's Crust. By Rev. O. Fisher, M.A., F.G.S., Rector of Harlton, &c. 8vo. [*Shortly*.

Studies in Deductive Logic. By W. Stanley Jevons, LL.D., M.A., F.R.S. Crown 8vo. 6*s*.

"It is indispensable to the many students of the higher logic."—*Athenæum*.

Guide to the Study of Political Economy. By Dr. Luigi Cossa, Professor of Political Economy in the University of Pavia. Translated from the Second Italian Edition. With a Preface by W. STANLEY JEVONS, F.R.S. Crown 8vo. 4*s*. 6*d*.

MACMILLAN AND CO., LONDON.

Now ready, Ninth Edition, Revised and Enlarged, with 3 Steel Plates and 377 Wood Engravings, 8vo. £1 11s. 6d.

CARPENTER'S HUMAN PHYSIOLOGY.

By HENRY POWER, M.B., Lond., F.R.C.S.,

Examiner in Anatomy and Physiology in the Royal College of Surgeons; Senior Ophthalmic Surgeon to St. Bartholomew's Hospital.

J. & A. CHURCHILL, New Burlington Street.

Now ready, Third Edition, containing 6 Plates, royal 4to, 12s.

DIAGRAMS OF THE NERVES OF THE HUMAN BODY,

Exhibiting their Origin, Divisions and Connections, with their Distribution to the various Regions of the Cutaneous Surface and to all the Muscles.

By Prof. FLOWER, F.R.S.,

Hunterian Professor of Comparative Anatomy, and Conservator of the Museum of the Royal College of Surgeons.

J. & A. CHURCHILL, New Burlington Street.

New Series No. LXXXI., January 1881, Price 7s. 6d.

THE QUARTERLY JOURNAL OF MICROSCOPICAL SCIENCE.

Edited by
E. RAY LANKESTER, M.A., F.R.S., F.L.S.,
Fellow of Exeter College, Oxford, and Professor of Zoology and Comparative Anatomy in University College, London;
With the co-operation of
F. M. BALFOUR, M.A., F.R.S., F.L.S.,
Fellow and Lecturer of Trinity College, Cambridge;
W. T. THISELTON DYER, M.A., F.R.S., F.L.S.,
Assistant Director of the Royal Gardens, Kew; and
E. KLEIN, M.D., F.R.S.,
Lecturer on Histology in St. Bartholomew's Hospital Medical School, London.

MEMOIRS.

Notes on a Peculiar Form of Polyzoa closely allied to Bugula (*Kinetoskias*, Kor. and Dan.). By GEORGE BUSK, F.R.S. (With Two Plates.)
On the Germination and Histology of the Seedling of Welwitschia mirabilis. By F. ORPEN BOWER, B.A., Camb. (With Two Plates.)
Notes on some of the Reticularian Rhizopoda of the "Challenger" Expedition. By HENRY B. BRADY, F.R.S.
On the Head Cavities and Associated Nerves of Elasmobranchs. By A. MILNES MARSHALL, D.Sc., M.A., Fellow of St. John's College, Cambridge, Professor of Zoology in Owen's College. (With Two Plates.)
Contributions to the Minute Anatomy of the Nasal Mucous Membrane. By E. KLEIN, M.D., F.R.S., Lecturer on Histology and Embryology in the Medical School of St. Bartholomew's Hospital. (With Plate.)
Histological Notes. By E. KLEIN, M.D., F.R.S., Lecturer on Histology and Embryology in the Medical School of St. Bartholomew's Hospital.
On the Intra-Cellular Digestion and Endoderm of Limnocodium. By E. RAY LANKESTER, M.A., F.R.S. (With Three Plates.)
On the Micrometric Numeration of the Blood-Corpuscles and the Estimation of their Hæmoglobin. By Mrs. ERNEST HART.
Preliminary Account of the Development of the Lampreys. By W. B. SCOTT, M.A., Assistant in Palæontology, Princeton.
On Some Appearances of the Red Blood-corpuscles of Man and other Vertebrata. By G. F. DOWDESWELL, B.A., Cantab., F.C.S., F.L.S.

NOTES AND MEMORANDA.

Medusæ and Hydroid Polyps living in Fresh Water.
Terminology of Reproductive Organs and Classification of Thallophytes.

J. & A. CHURCHILL, New Burlington Street.

Sixth Edition, in Two vols., 8vo, £2 2s.

COOLEY'S CYCLOPÆDIA OF

PRACTICAL RECEIPTS and Collateral Information in the Arts, Manufactures, Professions, and Trades, including Medicine, Pharmacy, Hygiene, and Domestic Economy; designed as a Comprehensive Supplement to the Pharmacopœia and General Book of Reference for the Manufacturer, Tradesman, Amateur, and Heads of Families. Edited by Prof. Tuson, F.C.S., assisted by several Scientific Contributors.

This Edition exceeds the last by some 600 pages, and contains a greatly-increased number of receipts culled from the most reliable English and foreign journals; numerous articles on Applied Chemistry, Pharmacy, Hygiene, Human and Veterinary Medicine, &c., have been added; many of the old articles are extended; and, where desirable, the text is illustrated by woodcuts.

"We cannot spare space to enumerate all the improvements. Those who have the old edition of this work will do well to supply themselves with its successor; those who have no copy of it will do still better if they purchase this edition."—*Chemist and Druggist.*

"It is a storehouse of scientific knowledge, and will be found valuable in every house."—*Lancet.*

*** *This Work can also be had in 16 Parts, at 2s. 6d. each.*

J. & A. CHURCHILL, New Burlington Street.

Third Edition, Revised and Enlarged, with Forty-eight Engravings. Post 8vo. 7s. 6d.

PRACTICAL AND ANALYTICAL

CHEMISTRY, Specially adapted for Schools and Colleges, and for Beginners. By FRANK CLOWES, D.Sc., Senior Science Master at the High School, Newcastle-under-Lyme.

J. & A. CHURCHILL, New Burlington Street.

Fourth Edition, with nearly Three Hundred Engravings, 8vo. 16s.

CHEMISTRY, INORGANIC AND

ORGANIC. WITH EXPERIMENTS. By CHARLES L. BLOXAM, Professor of Chemistry in King's College, London.

By the SAME AUTHOR. Fourth Edition, with 89 Engravings, crown 8vo. 5s. 6d.

LABORATORY TEACHING; or, Progressive

Exercises in Practical Chemistry.

J. & A. CHURCHILL, New Burlington Street.

Fifth Edition, 8vo, with Engravings. 7s. 6d.

VALENTIN'S QUALITATIVE CHEMI-

CAL ANALYSIS. Revised and Corrected by W. R. HODGKINSON, Ph.D., Demonstrator of Practical Chemistry in the Science Schools, South Kensington.

J. & A. CHURCHILL, New Burlington Street.

Eighty-eighth Thousand. Fcap. 8vo. 2s. 6d.

ADVICE TO A MOTHER ON THE

MANAGEMENT OF HER CHILDREN, and on the Treatment on the Moment of some of their more pressing Illnesses and Accidents. By PYE-CHAVASSE, F.R.C.S. With Notes and Annotations by Sir C. LOCOCK, Bart., M.D., F.R.S.

By the SAME AUTHOR. One Hundredth Thousand. Fcap. 8vo. 2s. 6d.

ADVICE TO A WIFE ON THE MAN-

AGEMENT of her own HEALTH, and on the Treatment of some of the Complaints incidental to Pregnancy, Labour, and Suckling. With an Introductory Chapter especially addressed to a Young Wife.

J. & A. CHURCHILL, New Burlington Street.

"The value of such information as is contained in this book, both to teachers and learners, can scarcely be overrated."—*Nature.*

Second Edition, Revised and Enlarged, Crown 8vo. With Engravings 6s. 6d.

PHYSIOLOGY AND HYGIENE OF THE

VOICE, with especial reference to its Cultivation and Preservation, for the Use of Speakers and Singers. By GORDON HOLMES, L.R.C.P.E., Physician to the Municipal Throat and Ear Infirmary.

"Will prove most valuable . . . In a truly scientific spirit."—*Athenæum.* "Admirably given."—*Nature.* "Well written."—*Lancet.* "Of great excellence."—*Dublin Medical Journal.* "Marked with sound sense."—*Saturday Review.* "A valuable book."—*Western Review.* "Much more clear and satisfactory than ordinary books of physiology."—*New York Medical Journal.* "Both classes will derive great benefit from studying it and following its precepts."—*Philadelphia Medical Times.*

J. & A. CHURCHILL, New Burlington Street.

8vo. 1500 pp. 12s.

THE MEDICAL DIRECTORY FOR 1881.

Giving the Names, Addresses, Qualifications, Appointments, Scientific Distinctions, Published Works, &c., of Medical Practitioners throughout the World possessing British Qualifications; with a List of Licentiates in Dental Surgery, and much General and Statistical Information relating to Medical Education and Medical Practice.

J. & A. CHURCHILL, New Burlington Street.

Printed by R. CLAY, SONS, AND TAYLOR, at 7 and 8, Bread Street Hill, Queen Victoria Street, in the City of London, and published by MACMILLAN AND CO., at the Office, 29 and 30, Bedford Street, Covent Garden.—THURSDAY, January 20, 1881.

NATURE

A WEEKLY ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
Of Nature trusts the mind which builds for aye."—WORDSWORTH

NO. 587, VOL. 23] THURSDAY, JANUARY 27, 1881 [PRICE SIXPENCE

Registered as a Newspaper at the General Post Office.]

[All Rights are Reserved.

SCIENCE and ART DEPARTMENT OF THE COMMITTEE OF COUNCIL ON EDUCATION.

EXAMINATIONS IN DRAWING IN ELEMENTARY DAY SCHOOLS.

The Science and Art Department will hold EXAMINATIONS in ELEMENTARY DRAWING through the agency of the Managers in Elementary Day Schools throughout the Kingdom.

These Examinations will take place on MONDAY, March 7th, in Elementary Schools at which Drawing is taught by persons certificated in Second Grade Drawing. Payments to the Managers and Prizes to the Children and Pupil Teachers are offered on the results of these Examinations.

Applications for Examination must be made before February 1st to the Secretary, Science and Art Department, London, S.W.

By Order of
THE COMMITTEE OF COUNCIL ON EDUCATION.

QUEENWOOD COLLEGE, near STOCKBRIDGE, HANTS. A High-Class School for Boys. The course of study is adapted to the pupils' requirements For view of the College see *Graphic* of December 25th, 1880. The Spring Term begins Friday, January 21st. Applications to the Principal, C. WILLMORE.

INSTRUCTION IN MATHEMATICS.—Youths or Adults attended at their Residence, on Reasonable Terms, by a M.A. of Cambridge. Unquestionable references if required.—Address, by letter, O. P., Post Office, Turnham Green.

Microscopes and other Scientific Apparatus

C. BAKER,

244 & 245, HIGH HOLBORN,

Begs to call the attention of the Scientific to his Extensive Stock of Instruments at the lowest possible prices, *viz.* :—

ACHROMATIC MICROSCOPES: the Largest Assortment in London can be selected from, from £3 3s.
ASTRONOMICAL TELESCOPES from £5 5s.
FIELD GLASSES in Leather Sling Cases, from 20s.
OPERA GLASSES in Ivory, Leather, Metal, &c., from 12s. 6d.
GOLD SPECTACLES of every kind from 15s.
THE BEST LONDON-MADE PEBBLES IN STEEL FRAMES, 10s. 6d.
PLAIN STEEL DITTO, from 3s. 6d.
FOLDING HAND SPECTACLES IN TORTOISESHELL, STEEL, &c., from 3s. 6d.
DISSOLVING VIEW APPARATUS, complete from £6 10s.
MAGIC LANTERNS, from 6s. 6d.; Slides, all kinds, from 1s. 3d.

CATALOGUES FREE BY POST.

Second Hand Scientific Instruments.

C. BAKER'S new Catalogue of Scientific Instruments is now out; Selections can be made from a very large stock, comprising MICROSCOPES, ASTRONOMICAL TELESCOPES, TRANSIT INSTRUMENTS, REGULATORS, SPECTROSCOPES, METEOROLOGICAL and ELECTRICAL APPARATUS, DISSOLVING VIEWS, &c. All at the very lowest prices.

Catalogues of same Free by Post. *Instruments taken in exchange.*
ESTABLISHED 1765.

BROWNING'S SPECTROSCOPES.

THE MINIATURE SPECTROSCOPE.

This Instrument will show many of Fraunhofer's lines, the bright lines of the metals and gases, and the absorption bands in coloured gases, crystals, or liquids.

Price, with Plain Slit, £1 2s.; ditto, with Adjustable Slit in Morocco Case, £1 15s.; ditto, with Achromatic Lenses, &c., &c., in Morocco Case, £2 6s.

An Illustrated Catalogue of Spectroscopes, Price Sixpence.

LIST OF SPECTROSCOPES SENT FREE.

JOHN BROWNING,

63, STRAND, LONDON, W.C.

STANDARD METEOROLOGICAL INSTRUMENTS



Now ready, a New Edition of Negretti & Zambra's Encyclopædic Catalogue of Mathematical, Philosophical, Optical, and Standard Meteorological Instruments, containing numerous Comparative Tables of Reference, and Illustrated by Twelve Hundred Engravings.
Royal 8vo, cloth, gilt lettered, price 5s. 6d.

NEGRETTI & ZAMBRA,

Opticians and Scientific Instrument Makers

To HER MAJESTY THE QUEEN,

HOLBORN VIADUCT,

45, CORNHILL, & 122, REGENT STREET, LONDON.

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 48N, Tollington Road, Holloway, London, N.

UNIVERSITY OF LONDON.

PRELIMINARY SCIENTIFIC M.B. EXAMINATION.

Instruction is given in all the Subjects of the above Examination at Guy's Hospital during the Winter and Summer Sessions. The Class is not confined to Students of the Hospital.—For further particulars apply to the DEAN, Guy's Hospital, Southwark, S.E.

FOR SALE, price £100.—A rapidly-growing

ANALYTICAL PRACTICE in the West of England. To be sold because the owner is leaving England.—Apply by letter, G. W. R., 52, Drury Lane, London, E.C.

ROYAL POLYTECHNIC.—CLASSES for

the Preparation of Students for University Examinations, under the direction of EDWARD B. AVELING, D.Sc., F.L.S. London University Matriculation, 1st and 2nd B.Sc., Preliminary Scientific M.B., Botany, Physiology, Chemistry. All the work practical.

MINERALOGY AND GEOLOGY.

Mr. HENSON having purchased an OLD COLLECTION formed in DERBYSHIRE, containing FINE SPECIMENS of ANGLESITE, CERUSSITE, FLUOR SPAR and CALC SPAR, DIOPTASE, EUCHROITE, and other RARE MINERALS, begs to offer the same singly or otherwise.

COLLECTIONS FOR STUDENTS, from £2 2s. COLLECTIONS FOR BEGINNERS, from 4s. BLOWPIPE CASES AND APPARATUS.

PRIVATE LESSONS AND EVENING CLASSES.

Catalogues free.

SAMUEL HENSON,

277 (*Late* 113*a*), STRAND, LONDON, W.C.

DIAMONDS IN MATRIX.

R. C. NOCKOLD, Diamond and Oriental Stone Cutter and Dealer, has for sale Specimens of the above; also Cut Precious Stones in all Colours.

Precious Stones valued and bought.

12, FRITH STREET, SOHO, W.

THOMAS D. RUSSELL'S

NATURAL HISTORY STORES,

48, ESSEX STREET, STRAND, W.C.

Students and others are invited to inspect the Collections of British and Foreign Shells, Corals, Zoophytes, Annelids, Crustacea, Echinoderms, Minerals, Fossils, Rock Specimens, Microscopic Objects, &c.

Cabinets, Geologist's Hammers, Glass Capped Boxes, Card Trays, Tablets, Glass Slips, Micro-Thin Glass, Canada Balsam, Marine Glue, and other requisites for the Geologist and Microscopist.

Catalogues Post Free.

GEOLOGY.—In the Preface to the STU-

DENT'S ELEMENTS of GEOLOGY, by Lyell, 1874, he says: "As it is impossible to enable the reader to recognise rocks and minerals at sight by aid of verbal descriptions or figures, he will do well to obtain a well-arranged collection of specimens, such as may be procured from Mr. TENNANT (149, Strand), Teacher of Mineralogy at King's College, London." These Collections are supplied on the following terms, in plain Mahogany Cabinets:—

100 Specimens, in Cabinet, with 3 Trays	£2	2	0
200 Specimens, in Cabinet, with 5 Trays	5	5	0
300 Specimens, in Cabinet, with 9 Drawers	10	10	0
400 Specimens, in Cabinet, with 13 Drawers	21	0	0

More extensive Collections at 50 to 5,000 Guineas each.

GEOLOGY AND MINERALOGY.

Special Collections for Teachers and Students, used with success by all Lecturers and Teachers of Geology in Great Britain. Obtained Gold and Bronze Medals at Sydney Exhibition, 1879, also in London, 1862, and Paris, 1807.

200 Specimens in Cabinet	£2	2	0
100 ditto ditto	1	1	0
50 ditto ditto	0	10	6

New Lists of Collections, Apparatus, &c., now ready, and free on application to

JAMES R. GREGORY'S

Geological Museum and Repository,

88, CHARLOTTE STREET, FITZROY SQUARE.

EVERY BOY A GEOLOGIST.

Now ready, and highly recommended, complete, price 7s. 6d.

This admirable little Work and most extraordinary Cabinet of wonderfully well-selected Natural Specimens, together with other Geological Preparations, and a powerful Lens, are calculated to start a boy thinking till he has mastered for himself no ordinary knowledge of the formation of the Earth's Crust.—THOMAS J. DOWNING, GEOLOGIST, &c., 38, Whiskin Street, London, E.C.—Catalogues free.

LIVING SPECIMENS FOR THE MICROSCOPE.

THOMAS BOLTON, NATURALISTS' and MICROSCOPISTS' STUDIO, 17, ANN STREET, BIRMINGHAM.

T. B. has last week sent to his subscribers *Spirorbis nautiloides*, with drawing and description. He has also sent out *Follicularia ampulla*, *Argulus foliaceus*, *Asellus vulgaris*, young American Trout, *Salmo fontinalis*, *Cordylophora lacustris*, &c.

Weekly announcements will be made in this place of organisms T. B. is supplying.

Specimen Tube, One Shilling, post-free.

Twenty-six Tubes in course of Six Months for Subscription of £1 1s.

Price List of Specimens on application, with stamped addressed envelope.

Portfolio of Drawings, No. 3, One Shilling.

THE QUARTERLY REVIEW, No. 301,

Is Published THIS DAY.

Contents.

I. LORD CAMPBELL'S MEMOIRS.
II. CALIFORNIAN SCENERY AND SOCIETY.
III. LORD BOLINGBROKE IN EXILE.
IV. PROTECTION OF BRITISH BIRDS.
V. LORD BEACONSFIELD'S "ENDYMION."
VI. BELIEF AND UNBELIEF.
VII. McCARTHY'S HISTORY OF OUR OWN TIMES.
VIII. EMPLOYMENT OF WOMEN.
IX. THE RITUALISTS AND THE LAW.
X. THE TRUTH ABOUT IRELAND.

JOHN MURRAY, Albemarle Street.

In unserem Verlage erscheint:

DER NATURFORSCHER.

Wochenblatt zur Verbreitung der Fortschritte in den Naturwissenschaften.

Herausgegeben von Dr. WILHELM SKLAREK.

Wöchentlich 1—1½ Bgn. in 4°.

Preis vierteljährlich 4 Mk.

Die nunmehr ihren XIV. Jahrgang beginnende Zeitschrift hat bei Allen, welche sich mit Naturwissenschaften beschäftigen, grossen Beifall gefunden.

Probenummern sind durch jede Buchhandlung zu erhalten.

Berlin, S.-W., 77, Charlottenstr.

FERD. DÜMMLER'S VERLAGSBUCHHANDLUNG.

(Harrwitz & Gossmann.)

THE ENTOMOLOGIST'S MONTHLY MAGAZINE.

Price Sixpence, Monthly, 24 pages 8vo, with occasional Illustrations.

Conducted by C. G. BARRETT, J. W. DOUGLAS, R. MCLACHLAN, F.R.S., E. C. RYE, F.Z.S., E. SAUNDERS, F.L.S., and H. T. STAINTON, F.R.S.

This Magazine, commenced in 1864, contains standard articles and notes on all subjects connected with Entomology, and especially on the Insects of the British Isles.

Subscription—Six Shillings per Volume, post free. The volumes commence with the June number in each year.

Vols. I. to VI. (strongly bound in cloth) may be obtained by purchasers of the entire set to date, at the increased price of 10s. each; the succeeding vols. may be had separately or together, at 7s. each.

London: JOHN VAN VOORST, 1, Paternoster Row.

N.B.—Communications, &c., should be sent to the Editors at the above address.

THE NEW BIOLOGICAL JOURNAL.

ARCHIVES DE BIOLOGIE.

Edited by Professors EDOUARD VAN BENEDEN of Liège, and VAN BAMBEKE of Ghent.

This Journal is devoted to the publication of original Memoirs on the Embryology, Histology, Physiology, and Comparative Anatomy of Plants and Animals. Each number is illustrated with numerous Coloured Plates, and appears at the commencement of the Quarter.

Price:—A Single Number, Six Shillings and Sixpence. Annual Subscription: Twenty-five Shillings, or Twenty-seven Shillings post free.

Orders received by Messrs. WILLIAMS & NORGATE, 14, Henrietta Street, Covent Garden, London.

In the first two numbers have appeared:—

VAN BENEDEN: On the Embryology of the Mammalia.

VAN BAMBEKE: On the Cleavage of the Egg in Batrachia.

FOR HINGER: On the Termination of Nerves in the Muscles of Insects.

FREDERIQUE AND VANDEVELDE: On the Physiology of the Muscles and Nerves of the Lobster.

MACLEOD: On the Harderian Gland of the Duck, &c., &c.

On the 1st of every Month, price One Shilling.

THE ZOOLOGIST:

A MONTHLY MAGAZINE OF NATURAL HISTORY.

Third Series. Edited by J. E. HARTING, F.L.S., F.Z.S., Member of the British Ornithologists' Union; contains—

Original articles by well-known naturalists in every branch of zoology: habits of animals; arrival and departure of migratory birds; occurrence of rare birds; distribution and migration of British fresh-water fish; new or rare marine fish; local aquaria; British reptiles; British land and fresh-water mollusca, with remarks on the haunts and habits of the species; and other matters of general interest to those who delight in natural history. Reports of the Linnean, Zoological, and Entomological Societies. Reviews of natural history books. Occasional translations from foreign zoological journals of important and interesting articles in various branches of zoology. There are occasional woodcuts.

JOHN VAN VOORST, 1, Paternoster Row.

"The leading Farmers' paper."—CLARE SEWELL READ, ESQ., M.P.

THE CHAMBER OF AGRICULTURE JOURNAL
AND FARMERS' CHRONICLE
(PRICE 3*d.* WEEKLY).

The representative organ of the Central and Provincial Chambers of Agriculture; *gives fuller reports of the discussions and proceedings* of this extensive organisation than any other agricultural paper It devotes *special attention to the treatment of Agricultural Questions by Parliament*, besides containing ample Reports of the LATEST LONDON and COUNTRY CORN, CATTLE, HOP, PROVISION, and other Markets, with Original Articles on Practical Farming, the Dairy, Herd and Flock News, Horticulture, &c., &c. It is despatched every Monday evening in time for the country post.

Terms of Subscription, payable in advance, post free:—3 months, 3*s.* 9½*d.*; 6 months, 7*s.* 7*d.*; 12 months, 15*s.* 2*d.*
Published by W. PICKERING, 21, Arundel Street, Strand, London, W.C.

NORTH BRITISH AGRICULTURIST

is the only Agricultural Journal in Scotland, and circulates extensively amongst Landed Proprietors, Factors, Farmers, Farm-bailiffs, and others interested in the management of landed property throughout Scotland and the Northern Counties of England.

The AGRICULTURIST has also a very considerable circulation on the Continent of Europe, America, Australia, and the Colonies.

The AGRICULTURIST is published every Wednesday afternoon in time for the evening mails, and contains Reports of all the principal British and Irish Markets of the week, besides Telegraphic Reports of those held on the day of publication.

The Veterinary Department is edited by one of the leading Veterinarians in the country, and is invaluable to the breeder and feeder as a guide to the rearing of animals, and their treatment when labouring under disease.

Full Reports are given of the Meetings of the Royal Agricultural Society of England, the Royal Agricultural Society of Ireland, the Highland and Agricultural Society of Scotland, the Scottish Chamber of Agriculture, and all the principal Agricultural Associations throughout Great Britain and Ireland.

For Advertisers addressing themselves to Farmers a better medium does not exist

Price 3*d.* By post 3½*d.* Annual Subscription, payable in advance, 14*s.*
Office—377, High Street, Edinburgh.
Post-Office Orders payable to Charles Anderson, Jun., Edinburgh.
ESTABLISHED 1843.

Now ready, Price 6*s.*, Part II., Vol. XV., January, 1881.

THE JOURNAL OF ANATOMY AND PHYSIOLOGY,
NORMAL AND PATHOLOGICAL.
CONDUCTED BY
Profs. HUMPHRY, TURNER, M'KENDRICK, & Dr. CREIGHTON.

Contents.

1. Bones, Articulations, and Muscles of Rudimentary Hind-limb of Greenland Right-Whale. By J. Struthers, M.D. (Plates XIV.–XVII.)
2. Infective Form of Tuberculosis in Man identical with Bovine Tuberculosis. By C. Creighton, M.D.
3. Medullary Neuroma of Brain. By W. Osler, M.D. (Plate XVIII)
4. Dissection of Genito-Urinary Organs in Case of Fissure of Abdominal Walls. By A. Doran, F.R.C.S. (Plate XIX.)
5. Description of a Polygraph (with Figure). By D. Newman, M.B.
6. Remarks on Mechanism of Secretion of Sweat. By C. Handfield Jones, M.B.
7. Anomalous Growth-Bearing Pilose Skin in Pharynx of a Young Woman. By P. S. Abraham, M.A. (With Figure.)
8. Histology of Granular Kidney (with Figure). By R. Saundby, M.D.
9. Two Cases of Cerebellar Disease. By T. Oliver, M.D.
10. Colouring Matter of Jelly Fishes. By Prof. M'Kendrick.
11. Nerves of the Hind-Limb of the Thylacine and Cuscus. By D. J. Cunningham, M.D.
12. Pulse Dicrotism. By Wm. Jas. Fleming, M.D.
13. Anatomical Notices.

MACMILLAN & CO., London and Cambridge.

LA SEMAINE FRANÇAISE: a Weekly Newspaper and Review in the French Language. Politics, Literature, Science, Art, Varieties, Notes. Price 3*d.*, through booksellers, and at the railway bookstalls. Office, 37, Southampton Street, Strand, W.C.

LA SEMAINE FRANÇAISE: Journal Français pour l'Angleterre: Politique, Littérature, Sciences, Arts, Variétés, Nouvelles, et Notes. Un exemplaire par la poste, 3½*d.*, en timbres poste Abonnement franco par la poste—un an, 15*s.* 2*d.*; six mois, 7*s.* 7*d.* Prix 3*d.*, chez tous les libraires et aux gares des chemins de fer. On s'abonne aux bureaux, 37, Southampton Street, Strand, Londres, W.C.

LA SEMAINE FRANÇAISE.—"'La Semaine Française' has been brought out in London for the benefit of those English readers who may wish to study contemporary French from all points of view, instead of confining their reading to one particular Gallic print. It certainly merits success."—*Graphic.*

LA SEMAINE FRANÇAISE.—"The numbers before us are full of good things. . . . . It will be far better for most than any one of the best papers published in Paris itself. We are much pleased with the character of it, and believe it will be highly valued in all those many households where French is cultivated. The printing is very well done."—*Queen.*

TERMS OF SUBSCRIPTION:—

	s.	d.
Three months	3	10
Six ,,	7	7
Twelve ,,	15	2

P.O.O. payable to T. SPANSWICK, at King Street, Covent Garden, W.C.
Publishing Office, 37, Southampton Street, Strand, W.C.

MANUALS FOR STUDENTS.

FLOWER (W. H.)—AN INTRODUCTION TO THE OSTEOLOGY OF THE MAMMALIA. Being the Substance of the Course of Lectures delivered at the Royal College of Surgeons of England in 1870. By W. H. FLOWER, F.R.S., F.R.C.S., Hunterian Professor of Comparative Anatomy and Physiology. With numerous Illustrations. Second Edition enlarged. Crown 8vo. 10*s.* 6*d.*

FOSTER and BALFOUR—THE ELEMENTS OF EMBRYOLOGY. By MICHAEL FOSTER, M.D., F.R.S., and F. M. BALFOUR, M.A. Part I. Crown 8vo. 7*s.* 6*d.*

FOSTER and LANGLEY—A COURSE OF ELEMENTARY PRACTICAL PHYSIOLOGY. By MICHAEL FOSTER, M.D., F.R.S., and J. N. LANGLEY, B.A. Fourth Edition. Crown 8vo. 6*s.*

HOOKER (Dr.)—THE STUDENT'S FLORA OF THE BRITISH ISLANDS. By Sir J. D. HOOKER, K.C.S.I., C.B., P.R.S., M.D., D.C.L. Second Edition, Revised. Globe 8vo. 10*s.* 6*d.*

"Cannot fail to perfectly fulfil the purpose for which it is intended."—*Land and Water.*

"Certainly the fullest and most accurate manual of the kind that has yet appeared."—*Pall Mall Gazette.*

HUXLEY and MARTIN—A COURSE OF PRACTICAL INSTRUCTION IN ELEMENTARY BIOLOGY. By Professor HUXLEY, F.R.S., assisted by H. N. MARTIN, M.B., D.Sc. New Edition, revised. Crown 8vo. 6*s.*

"It is impossible for an intelligent youth, with this book in his hand, placing himself before any one of the organisms described, and carefully following the directions given, to fail to verify each point to which his attention is directed."—*Athenæum.*

HUXLEY—PHYSIOGRAPHY. An Introduction to the Study of Nature. By Professor HUXLEY, F.R.S. With numerous Illustrations, and Coloured Plates. New and Cheaper Edition. Crown 8vo. 6*s.*

OLIVER (Professor)—FIRST BOOK OF INDIAN BOTANY. By DANIEL OLIVER, F.R.S., F.L.S., Keeper of the Herbarium and Library of the Royal Gardens, Kew, and Professor of Botany in University College, London. With numerous Illustrations. Extra fcap. 8vo. 6*s.* 6*d.*

"It contains a well-digested summary of all essential knowledge pertaining to Indian Botany, wrought out in accordance with the best principles of scientific arrangement."—*Allen's Indian Mail.*

PARKER and BETTANY—THE MORPHOLOGY OF THE SKULL. By Professor PARKER and G. T. BETTANY. Illustrated. Crown 8vo. 10*s.*

Other Volumes of these Manuals will follow.

MACMILLAN AND CO., LONDON.

Now publishing, in Crown 8vo. Price 2s. 6d. each.

ENGLISH MEN OF LETTERS.

Edited by JOHN MORLEY.

, Upwards of 150,000 Vols. of this series have been sold.

WORDSWORTH. By F. W. H. MYERS.
"Mr. Myers gives us a picture of the man and an estimate of his work which is certainly not inferior to anything that has preceded it."—*Academy.*

LOCKE. By Prof. FOWLER.
"In the case of Locke's biographer we venture to say that Mr. Morley has been exceptionally fortunate. A pen more competent than Prof. Fowler's for this particular work might have been sought, and sought in vain."—*Examiner.*

BYRON. By Prof. NICHOL.
"Decidedly one of the most careful and valuable of the whole series."—*Athenæum.*

POPE. By LESLIE STEPHEN.
"The writer's eminent qualities as a critic, his judgment, his wit, his abundant knowledge of eighteenth-century literature, and his keen enjoyment of literary form, have equipped him handsomely for the task he has undertaken."—*St. James's Gazette.*

COWPER. By GOLDWIN SMITH.
"Mr. Goldwin Smith has sketched, in a few decisive touches, the genius of the poet and weakness of the man."—*Daily News.*

CHAUCER. By Prof. A. W. WARD.
"Far away the best connected account of Chaucer and his works to be found in English."—*Academy.*

BUNYAN. By J. A. FROUDE.
"He has given us a real study of Bunyan's life and character, and at the same time a real study of his books."—*Athenæum.*

SOUTHEY. By Prof. DOWDEN.
"A truly scholarly and delightful monograph."—*Examiner.*

HAWTHORNE. By HENRY JAMES, JUN.
"He has made a careful, conscientious, and even vivid literary portrait, such as few of our own writers could have made."—*New York Nation.*

MILTON. By MARK PATTISON.
"Mr. Pattison's achievement is deserving of high praise. He has put life into old facts, he has taken an impartial estimate of a great man whose name is too often used for purposes of poetry."—*Spectator.*

JOHNSON. By LESLIE STEPHEN.
"The new series opens well with Mr. Leslie Stephen's sketch of Dr. Johnson. It could hardly have been done better, and it will convey to the readers for whom it is intended a juster estimate of Johnson than either of the two essays of Lord Macaulay."—*Pall Mall Gazette.*

SCOTT. By R. H. HUTTON.
"We could not wish for a more suggestive introduction to Scott and his poems and novels."—*Examiner.*

GIBBON. By J. C. MORISON.
"As a clear, thoughtful, and attractive record of the life and works of the greatest among the world's historians, it deserves the highest praise."—*Examiner.*

SHELLEY. By J. A. SYMONDS.
"The lovers of this great poet are to be congratulated at having at their command so fresh, clear, and intelligent a presentment of the subject, written by a man of adequate and wide culture."—*Athenæum.*

HUME. By Prof. HUXLEY, F.R.S.
"It may fairly be said that no one now living could have expounded Hume with more sympathy or with equal perspicuity."—*Athenæum.*

GOLDSMITH. By WILLIAM BLACK.
"Mr. Black brings a fine sympathy and taste to bear in his criticism of Goldsmith's writings"—*Athenæum.*

DEFOE. By W. MINTO.
"Mr. Minto's book is careful and accurate in all that is stated, and faithful in all that it suggests."—*Athenæum.*

BURNS. By Principal SHAIRP.
". . . None of the series has given a truer estimate either of character or of genius than this volume."—*Spectator.*

SPENSER. By the Very Rev. the DEAN OF ST. PAUL'S.
"Dr. Church is master of his subject, and writes always with good taste."—*Academy.*

THACKERAY. By ANTHONY TROLLOPE.
"Mr. Trollope's sketch is excellently adapted to fulfil the purpose of the series in which it appears."—*Athenæum.*

BURKE. By JOHN MORLEY.
"It is no disparagement to the literary studies already published in this admirable series to say that none of them have surpassed, while few have equalled, this volume on Burke."—*British Quarterly Review.*

, *Others in Preparation.*

MACMILLAN AND CO., LONDON.

Now ready, post quarto, cloth gilt, 272 pages. Price 15s.

LIGHTNING CONDUCTORS:

THEIR

HISTORY, NATURE, AND MODE OF APPLICATION.

By RICHARD ANDERSON, F.C.S., F.G.S.,
Member of the Society of Telegraph Engineers; Assoc. Inst. C.E.

With numerous Illustrations.

"The book is one to be commended to the builders of, or dwellers in, lofty houses, to the deans of our cathedrals, to the parsons of churches with lofty spires or towers, and to all owners, constructors, or occupiers of buildings which, from their height or situation, are exposed to danger from lightning."—*The Athenæum.*

"The book is clearly and sensibly written, and sufficiently illustrated, and is the work of a practical man who thoroughly understands what he is talking about."—*The Academy.*

London: E. & F. N. SPON, 46, Charing Cross.
New York: 446, Broome Street. 1880.

Recently Published,
Demy 4to, with 18 Plates (5 printed in Colours), 207 pages, cloth, £2 2s.

AURORÆ:

THEIR CHARACTERS AND SPECTRA.

By J. RAND CAPRON, F.R.A.S.

Part I.—THE AURORA AND ITS CHARACTERS.
Part II.—THE SPECTRUM OF THE AURORA.
Part III.—MAGNETO-ELECTRIC EXPERIMENTS IN CONNECTION WITH THE AURORA.

By the same Author.
Demy 8vo, with 37 Plates, cloth, 30s.

PHOTOGRAPHED SPECTRA.

One Hundred and Thirty-Six Photographs of Metallic, Gaseous, and other Spectra, printed by the Permanent Autotype Process, with Introduction, Description of Plates, and Index, and with an Extra Plate of the Solar Spectrum (showing bright lines) compared with the Air Spectrum.

London: E. & F. N. SPON, 16, Charing Cross.

EDITED BY HENRY WATTS, B.A., F.R.S.,
Editor of the *Journal* of the Chemical Society

FOWNES' PHYSICAL and INORGANIC CHEMISTRY.

Twelfth Edition, with Coloured Plate and 154 Engravings, crown 8vo. 8s. 6d.

Also,

FOWNES' CHEMISTRY OF CARBON COMPOUNDS; or, ORGANIC CHEMISTRY.

Twelfth Edition, with Engravings, crown 8vo. 10s.

London: J. & A. CHURCHILL.

PROF. HELMHOLTZ' SCIENTIFIC LECTURES.
In crown 8vo, with 17 Woodcuts, price 7s. 6d., cloth.

POPULAR LECTURES on SCIENTIFIC SUBJECTS,

SECOND SERIES, comprising the Origin and Signification of Geometrical Axioms, the Relation of Form, Shade, Colour, and Harmony of Colour to Painting, the Origin of the Planetary System, &c. By H. HELMHOLTZ, Prof. of Physics in the Univ. of Berlin. Translated by E. ATKINSON, Ph.D., F.C.S., Prof. of Experimental Science, Staff College.

PROF. HELMHOLTZ' FIRST SERIES

of LECTURES on SCIENTIFIC SUBJECTS, Translated by Prof. ATKINSON, with Introduction by Prof. TYNDALL. Second Edition, with 51 Woodcuts, uniform with the SECOND SERIES, now ready, price 7s. 6d.

London: LONGMANS & CO.

Second Edition, with Maps, price 10s. 6d., pp. 447.

EPIDEMIOLOGY; or, The Cause of Epidemic Disease, of Murrains, of Blight, of Hurricanes, and of Abnormal Atmospherical Vicissitudes.

With a History of Epidemic Diseases, and of the Phenomena that accompanied them. By JOHN PARKIN, M.D.

DAVID BOGUE, St. Martin's Place, London, W.C.

BRYCE-WRIGHT'S LATEST ARRIVALS.

GEMS.—Black Pearls, Moonstones, Cat's Eyes (Chrysoberyl, Crocidolite, and Quartz), and ONE OF THE FINEST OPALS KNOWN.

MINERALS.—Very fine Sphenes from Canada; Euclase, Siberia; Edingtonite, Leadlinlite, and Lanarkite, Scotland; Lumadrella Marble, and a beautiful series of Agates.

STONE IMPLEMENTS.—A very fine series of STONE and BRONZE IMPLEMENTS from the Lacustrine Habitations of Switzerland, also a large series of Scandinavian Implements.

BRYCE-WRIGHT, F.R.G.S., &c.,
Mineralogist and Expert in Gems and Precious Stones,
90, GREAT RUSSELL STREET, LONDON, W.C.

THURSDAY, JANUARY 27, 1881

UNCONSCIOUS MEMORY

Unconscious Memory, &c. By Samuel Butler. Op. 5. (London: David Bogue, 1880.)

MR. BUTLER is already known to the public as the author of two or three books which display a certain amount of literary ability. So long therefore as he aimed only at entertaining his readers by such works as "Erewhon," or "Life and Habit," he was acting in a suitable sphere. But of late his ambition seems to have prompted him to other labours; for in his "Evolution, Old and New," as well as in the work we are about to consider, he formally enters the arena of philosophical discussion. To this arena, however, he is in no way adapted, either by mental stature or mental equipment; and therefore makes so sorry an exhibition that Mr. Darwin may well be glad that his enemy has written a book. But while we may smile at the vanity which has induced so incapable and ill-informed a man gravely to pose before the world as a philosopher, we should not on this account have deemed "Unconscious Memory" worth reviewing. On the contrary, as a hasty glance would have been sufficient to show that the book is bad in philosophy, bad in judgment, bad in taste, and, in fact, that the only good thing in it is the writer's own opinion of himself—with all that was bad we should not have troubled ourselves, and that which was good we should not have inflicted on our readers. The case, however, is changed when we meet, as we do, with a vile and abusive attack upon the personal character of a man in the position of Mr. Darwin; for however preposterous, and indeed ridiculous, the charges may be, the petty malice which appears to underlie them deserves to be duly repudiated. We shall therefore do our duty in this respect, and at the same time take the opportunity of pointing out the nonsense that Mr. Butler has been writing, both about the philosophy of evolution and the history of biological thought.

The great theory which Mr. Butler has propounded, and which with characteristic modesty he says seems to himself "one, the importance of which is hardly inferior to that of the theory of evolution itself"—this epoch-making theory is as follows. The processes of embryonic development and instinctive actions are merely "repetitions of the same kind of action by the same individuals in successive generations." Therefore animals know, as it were, how to pass through their embryonic stages, and, after birth, are taught by instinctive knowledge, simply because [as parts of their ancestral organisms they have done the same things many times before; there is thus a race-memory as there is an individual memory, and the expression of the former constitutes the phenomena of heredity.

Now this view, in which Mr. Butler was anticipated by Prof. Hering, is interesting if advanced merely as an illustration; but to imagine that it reveals any truth of profound significance, or that it can possibly be fraught with any benefit to science, is simply absurd. The most cursory thought is enough to show that, whether we call heredity unconscious memory, or memory of past states of consciousness the hereditary offspring of those states, we have added nothing to our previous knowledge either of heredity or of memory. All that lends any sense to the analogy we perfectly well knew before—namely, that in the race, as in the individual, certain alterations of structure (whether in the brain or elsewhere) when once made, tend to remain. But the analogy throws no light at all upon the only point which requires illumination—namely, how is it that, in the case of heredity, alterations of structure can be carried over from one individual to another by means of the sexual elements. We can understand in some measure how an alteration of brain structure, when once made, should be permanent, and we believe that in this fact we have the physical basis of memory; but we cannot understand how this alteration is transmitted to progeny through structures so unlike the brain as are the products of the generative glands. And we merely stultify ourselves if we suppose that the problem is brought any nearer to a solution by asserting that a future individual while still in the germ has already participated, say in the cerebral alterations of its parent—and this in a manner analogous to that in which the brain of the parent is structurally altered by the effects of individual experience. But Mr. Butler goes even further than this, and extends his so-called theory even to inorganic matter. He "would recommend the reader to see every atom of the universe as living, and able to feel and remember, though in a humble way." Indeed he "can conceive of no matter which is not able to remember a little"; and he does "not see how action of any kind is conceivable without the supposition that every atom retains a memory of certain antecedents." It is hard to be patient with such hypertrophied absurdity; but if the bubble deserves pricking, it is enough to ask how it is "conceivable" that an "*atom*," even if forming part of a living brain, could possibly have "a memory of certain antecedents," when, as an atom, it cannot be conceived capable of undergoing any structural modification.

So much for Mr. Butler's main theory. But he has also a great deal to say on the philosophy of evolution. "Op. 4" was called "Evolution, Old and New," and now "Op. 5" continues the strain that was struck in the earlier composition. This consists for the most part in a strangely silly notion that "the public generally"—including, of course, the world of science—was as ignorant of the writings of Buffon, Dr. Erasmus Darwin, and Lamarck as was Mr. Butler when he first read the "Origin of Species." That is to say, "Buffon we knew by name, but he sounded too like 'buffoon' for any good to come from him. We had heard also of Lamarck, and held him to be a kind of French Lord Monboddo; but we knew nothing of his doctrine. . . . Dr. Erasmus Darwin we believed to be a forgotten minor poet," &c. No wonder, therefore, when such was our manner of regarding these men, that we required a Mr. Samuel Butler to show us our error. And no wonder that Mr. Charles Darwin, who doubtless may have peeped into the literature which Mr. Butler has discovered, should so well have succeeded in his life-long purpose of concealing from the eyes of all men how much he owes to his predecessors. No wonder, also, that Mr. Darwin, when he chanced to see an advertisement of a forthcoming work by Mr. Butler with the title "Evolution,

Old and New," should have inferred, as Mr. Butler observes, "what I was about," and forthwith began to tremble in dismay that at last the Buffoon, the French Lord Monboddo, and the forgotten minor poet had found a champion to vindicate their claims. For now the hideous corruption of the monster was about to be exposed who had fed as a parasite upon these "dead men," till he stands before our eyes bloated with honours undeserved, and extending "his power of fascination all over Europe," not only "among the illiterate masses . . . . but among experts and those most capable of judging." No wonder then that Mr. Darwin, knowing that at last a wise young judge had come to judgment and to open the eyes of the "experts," should at once have set about a book on his own grandfather to disarm by anticipation the justice of the avenger. But natural as all this unquestionably appears, it scarcely prepares us, as it did not prepare Mr. Butler, for the depths of deceit and depravity to which Mr. Darwin would "condescend" in order to thwart the arm of justice. Yet the fact is that Mr. Darwin entered into a foul conspiracy with Dr. Krause, the editor of *Kosmos*, to slay by infamous means the righteous but damning work of Mr. Butler. "The steps," as he points out, "are perfectly clear." A whole number of *Kosmos* was devoted to Mr. Darwin and his antecedents in literature, at about the time when "Evolution Old and New" was "announced" as in preparation. Soon afterwards arrangements were made for a translation of Dr. Krause's essay, and were completed by the end of April, 1879. Then "Evolution Old and New" came out, was read by Dr. Krause, who modified a passage or two in a manner that "he thought would best meet 'Evolution Old and New,' and then fell to condemning that book in a *finale* that was meant to be crushing." So far all was fair enough; but now comes the foul play. "Nothing was said about the revision which Dr. Krause's work had undergone, but it was expressly and particularly declared in the preface that the English translation was an accurate version of what appeared in the February number of *Kosmos*, and no less expressly and particularly stated that my book ["Evolution Old and New"] was published subsequently to this. Both these statements are untrue," &c. Having discovered this erroneous conspiracy, Mr. Butler wrote to Mr. Darwin for an explanation. With almost incredible complacency this arch-hypocrite had the hardihood to answer that it "is so common a practice" to modify articles in translation or republication, that "it never occurred to him to state that the article had been modified," but that now he would do so should there be a reprint. This, as Mr. Butler says, "was going far beyond what was permissible in honourable warfare, and it was time in the interests of literary and scientific morality . . . to appeal to public opinion." He therefore communicated the facts to the *Athenæum*, expecting as a consequence to raise a "raging controversy." Strange to say, however, the thing fell flat. "Not only did Mr. Darwin remain perfectly quiet, but all reviewers and *littérateurs* remained perfectly quiet also. It seemed . . . as if public opinion rather approved of what Mr. Darwin had done." Nevertheless Mr. Butler had a salve to his disappointment in that he saw "the 'Life of Erasmus Darwin' more frequently and more prominently advertised than hitherto," and "presently saw Prof. Huxley hastening to the rescue with his lecture 'On the Coming of Age of the Origin of Species.'" Truly, therefore, in some, if not quite in full measure, Mr. Butler's "vanity," as he himself observes, "was well fed by the whole transaction"; for he saw by it that Mr. Darwin "did not meet my work openly," and therefore that Prof. Huxley had to "hasten to the rescue" with a Royal Institution lecture. How sweet it doubtless was, if Mr. Butler attended that lecture, to think what a large proportion of the audience must have seen through the whole plot! Enough, surely, to "feed" any ordinary "vanity." But Mr. Butler's vanity is inordinate, and so requires a more than ordinary amount of nourishment. He therefore felt it desirable to give a detailed exposition of the whole affair, and this we have in some charmingly temperate and judicious chapters of "Op. 5."

But to be serious. If in charity we could deem Mr. Butler a lunatic, we should not be unprepared for any aberration of common-sense that he might display. His "Op. 5," however, affords ample evidence that he is not a lunatic, but a man who wants to make a mark somewhere, and whose common sense, if he ever had such a thing, has been completely blinded by self-conceit. To us, no less than to him, "the steps are perfectly clear." A certain nobody writes a book accusing the most illustrious man in his generation of burying the claims of certain illustrious predecessors out of the sight of all men. In the hope of gaining some notoriety by deserving and perhaps receiving a contemptuous refutation from the eminent man in question, he publishes this book, which, if it deserved serious consideration, would be not more of an insult to the particular man of science whom it accuses of conscious and wholesale plagiarism, than it would be to men of science in general for requiring such elementary instruction on some of the most famous literature in science from an upstart ignoramus who, until two or three years ago, "considered" himself "a painter by profession." The eminent man however did not administer the chastisement: hence these tears of rage and chagrin; hence too the morbid fancying of the great man's discomfort—of the rallying round of his friends, Krause's article, Huxley's lecture, &c., till such an explosive state of feeling was fermented that a mere omission to supply a reference to a book was magnified into a dark conspiracy—notwithstanding that a moment's thought might have shown how such a conspiracy, even if attempted, would not have been worthy of imbeciles.

But, in conclusion, let us ask what this work on "Evolution, Old and New" contained to produce, as its author imagines, such a scare among the leading "experts" in science. The work has already been reviewed in these columns (June 12, 1879) by Mr. Wallace, who, while fully exposing its weakness, treats the author with more consideration than he deserves—doubtless because Mr. Wallace is himself so personally associated with the theory of "natural selection." It is therefore sufficient for us here to say that "Evolution, Old and New," conveys a confession on the part of its author that until two or three years ago he was totally ignorant concerning the history of biological thought. His attention having at length been directed to the fact that some of

the best naturalists had speculated on the probability of evolution, he for the first time found, as he innocently enough observes, that evolution and natural selection are not quite the same thing. Having made this highly original discovery, he forthwith proceeds to display a feebleness of judgment even more lamentable than his previous ignorance. For he concludes that the older speculations on the causes of evolution are more satisfactory than those advanced by Mr. Darwin. In the columns of a scientific journal any comment on such a conclusion might well be deemed superfluous, although Mr. Wallace, in his review above mentioned, had the courtesy to expose its folly. The older evolutionists deserve indeed all honour for having perceived early in the day that some theory of descent must be true, even though they were not able to find the theory that could be seen to be in any measure satisfactory. But a man who in the full light of Darwin's theory can deliberately return to "the weak and beggarly elements" of Lamarck—such a man only shows that in judgment he is still a child. The extreme weakness of Mr. Butler's argumentation has, as we have said, already been shown by Mr. Wallace; but it is of more interest to ask what infatuation it can have been that led him to suppose "all Europe and those most capable of judging" required him as an author to make himself ridiculous as an expounder of this subject. The answer is not far to seek. As Mr. Butler himself has told us, he has vanity, and his vanity is not less childish than his judgment. Thus, to give only one illustration. Of so much importance does he deem his own cogitations, that in the book we are reviewing he devotes two chapters, or more than thirty pages, to "How I wrote 'Life and Habit,'" and "How I wrote 'Evolution, Old and New'"; entering into a minute history of the whole course of his speculative flounderings. This is the only part of the book that repays perusal; but that this part well repays perusal may be judged from the following, which we present as a sample:—

"The first passage in 'Life and Habit' which I can date with certainty is one on p. 52, which ran as follows: . . . '"Do this, this, this, which we too have done, and found our profit in it," cry the souls of his forefathers within him. Faint are the far ones, coming and going as the sound of bells wafted on to a high mountain; loud and clear are the near ones, urgent as an alarm of fire.' This was written a few days after my arrival in Canada, June 1874. I was on Montreal Mountain for the first time, and was struck with its extreme beauty. . . . Sitting down for a while, I began making notes for 'Life and Habit,' of which I was then continually thinking, and had written the first few lines of the above, when the bells of Nôtre Dame in Montreal began to ring, and their sound was carried to and fro in a remarkably beautiful manner. I took advantage of the incident to insert then and there the last lines of the piece just quoted. I kept the whole passage with hardly any alteration, and am thus able to date it accurately. . . . Early in 1876 I began putting these notes into more coherent form. I did this in thirty pages of closely-written matter, of which a pressed copy remains in my commonplace-book. I find two dates among them—the first 'Sunday, February 6, 1876"; and the second, at the end of the notes, 'February 12, 1876.'"

This historical sketch, which is without the smallest interest to any one but Mr. Butler himself, winds up with the following burst of eloquence:—

"Here, then, I take leave of this matter for the present. If it appears that I have used language such as is rarely seen in controversy, let the reader remember that the occasion is, so far as I know, unparalleled for the cynicism and audacity with which the wrong complained of was committed and persisted in. I trust, however, that, though not indifferent to this, my indignation has been mainly roused, as when I wrote 'Evolution, Old and New,' before Mr. Darwin had given me personal ground of complaint against him, by the wrongs he has inflicted on dead men, on whose behalf I now fight, as I trust that some one—whom I thank by anticipation—may one day fight on mine."

Mighty champion of the mighty dead! When our children's children shall read in Westminster Abbey the inscription on the tomb of Mr. Samuel Butler, how will it be with a sigh that in their day and generation the world knows nothing of its greatest men! But as it is our misfortune to live before the battle over Mr. Samuel Butler's memory has been fought, we respond to his abounding presumption by recommending him, whatever degree of failure he may have experienced in art, once more to "consider" himself "by profession a painter"—or, if the painters will not have him, to make some third attempt, say among the homœopathists, whose journal alone, so far as we are aware, has received with favour his latest work. GEORGE J. ROMANES

NEWTON'S BRITISH BIRDS

A History of British Birds. By the late William Yarrell, V.P.L.S., F.Z.S. Fourth Edition, revised by Alfred Newton, M.A., F.R.S. Part 10, November, 1876; 11, September, 1877; 12, October, 1878; 13, June, 1880. (London: Van Voorst.)

WE call this work advisedly "Newton's British Birds," although the title-page would seem to signify that it is only a fourth edition of Yarrell's well-known "History." It is however in fact a new book. The text has been completely rewritten, and the familiar woodcuts and vignettes alone remain to remind one of the former author.

The parts of Prof. Newton's work now before us conclude the account of the Passeres and contain the commencement of the history of the British Picariæ. We need hardly say that the article upon each species is worked out in the same careful and accurate way as in the former portion of this work. Prof. Newton, as every ornithologist knows, is our leading authority on this subject, which, during a course of many years of constan attention, he has made specially his own. We observe with great pleasure the elaborate manner in which the distribution of each species is described, not only within the area of the British Islands, but also wherever it is known to occur on other parts of the world's surface. We may likewise notice the entire absence of misprints and the excellence of the type and paper, which do credit alike to the author and publisher, and will no doubt greatly contribute to extend the circulation of the work. Having said thus much, it is with regret that we must add one word of discontent, for which we trust Mr. Van Voorst and Prof. Newton will alike forgive us. The rate of issue of the numbers is so slow that it is difficult to calculate when the new edition will be completed. As will be seen by the heading of the article, only four parts

have been published during the four past years. If, as we suppose, about twenty more parts are required to finish the work, it is manifest that unless the present rate of progress be expedited it will be twenty years before we are able to send our new "History of British Birds" to the binders. The edition was commenced, we believe, in 1871. Now thirty years seems rather long for the execution of a new edition of any work, even with all the improvements which, as we have shown above, the present editor has doubtless bestowed upon it. We would fain ask therefore whether the author and publisher cannot manage to move on a little faster. If this cannot be done it appears to us that the first portion of the work will be almost out of date before the last part is published, and that the subscribers will have good reason to complain.

OUR BOOK SHELF

Jahrbücher für wissenschaftliche Botanik. Herausgegeben von Dr. N. Pringsheim. Elfter Band, drittes und viertes Heft. With twenty-four plates. (Leipzig: W. Engelmann, 1877 and 1878.)

DR. JAKOB ERIKSSON describes in a lengthened paper the protomeristem of the roots of Dicotyledons, and directs attention to the four great types of structure observable in these roots. In the first type the apex consists of three separate zones of meristem: the plerome, periblem, and dermocalyptrogen. In the second type only two zones are present: the plerome and a common zone for primary cortex, epidermis, and root-cap. In the third type there is a common meristem zone from which all the others develop; while in the fourth there are two zones, the periblem and the plerome. Two additional types are met with in Monocotyledons: (1) in which there are four zones of meristem: calyptrogen, dermatogen, peroblem, and plerome; and (2) in which there are three zones: the calyptrogen, the plerome, and a common zone for cortex and epidermis.

The germination of Equisetum and Schizæaceæ forms the subject of two papers, one by Sadebeck and the other by Bauke, whose work was arrested by premature death. Woronin contributes a paper on the *Plasmodiophora Brassicæ*, the remarkable Myxomycete which seems to be the cause of the so-called Hernia of the cabbage plant, which has recently attracted so much attention.

The remaining papers are by Reinke, on *Monostroma bullosum* and *Tetraspora lubrica*. Wydler discusses at great length the morphology of certain forms of inflorescence, chiefly dichotomous; and lastly there is a paper by Pitra on the pressure in stems during the appearance of bleeding in plants. The contents of the parts are, as will be seen, very varied and deal with many different departments of botany, and will be found to sustain the reputation of the "Jahrbücher" so long associated with the name of Pringsheim.

LETTERS TO THE EDITOR

[*The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts. No notice is taken of anonymous communications.*

The Editor urgently requests correspondents to keep their letters as short as possible. The pressure on his space is so great that it is impossible otherwise to ensure the appearance even of communications containing interesting and novel facts.]

Unconscious Memory—Mr. Samuel Butler

WILL you kindly allow me a portion of your valuable space in order that I may demonstrate the completely groundless character of a series of insinuations which Mr. Samuel Butler has made not only against myself, but also against Mr. Charles Darwin, in the work which he has recently published, entitled "Unconscious Memory" (Op. 5).

1. Mr. Butler insinuates that Mr. Darwin caused my essay on Dr. Erasmus Darwin to be translated simply in order to throw discredit on his work, "Evolution, Old and New" (Op. 4), which was published in May, 1879. Upon this point I have to observe that Mr. Darwin informed me of his desire to have my essay published in English more than two months before the appearance of Mr. Butler's book; that the translation did not appear earlier is due to the fact that I asked for a delay in order that I might be able to revise it.

2. The assumption of Mr. Butler that Mr. Darwin had urged me to insert an underhand attack upon him (Mr. Butler) in my sketch, is not only absolutely unfounded, but, on the contrary, I have to state that Mr. Darwin specially solicited me *to take no notice whatever* of Mr. Butler's book, which had in the meantime appeared. Since however I thought it desirable to point out that Dr. Erasmus Darwin's views concerning the evolution of animated Nature still satisfy certain thinkers, even in our own day (a fact which must add greatly to Dr. Darwin's reputation), I have made some remarks upon the subject in a concluding paragraph, without however naming Mr. Butler. And I may here emphatically assert, that although Mr. Darwin recommended me to omit one or two passages from my work, he neither made nor suggested additions of any kind.

3. Mr. Butler's assertion that the revision of my translation was made "by the light" of his book is only in so far justifiable that I looked over the latter before sending off my work, and that my attention was thereby called to a remark of Buffon's. From Mr. Butler's book I have neither taken nor was I able to take the slightest information that was new to me concerning Dr. Erasmus Darwin's scientific work and views, since in it practically only one portion of the "Zoonomia" is discussed at any length, and this portion I had already quoted and analysed, while Mr. Butler only refers to one comparatively unimportant part of the "Botanic Garden," and absolutely ignores the "Phytologia" and the "Temple of Nature." So that no *single line* of Mr. Butler's far from profound work was of the slightest use to me.

Mr. Butler's contention that I have quoted from his book a remark from Coleridge is entirely without foundation. I have been acquainted with this remark for years, and from the source quoted. It is also quoted in Zoeckler's work (vol. ii. p. 256), mentioned by me on p. 151, which appeared *prior* to Mr. Butler's book (Op. 4). The whole of my indebtedness to Mr. Butler reduces itself therefore to a single quotation from Buffon.

4. Finally, as concerns the main accusation that no mention is made in the preface of the fact that my essay had been revised previously to publication, it is clear, as even a child could not fail to see, that this is not due to design, but is simply the result of an oversight. It would be simply absurd for a writer intentionally to attack a publication which appeared subsequently to the date indicated on his title-page; and the so-called falsification, so far from injuring Mr. Butler, could only be most agreeable to him, because it might induce the careless reader to fancy that no reference whatever was intended to Mr. Butler in the closing sentence. Should however such a reference be clearly intended—and to every reader posted up in the subject this could not be doubtful—every man of common sense would recognise this terrible falsehood to be a simple oversight.

Berlin, January 12 ERNST KRAUSE

Hot Ice

I VENTURE, in referring to Dr. Lodge's letter of this week, to put before your readers the meaning of the remarks made on Dr. Carnelley's experiment at the Chemical Society by Prof. Ayrton, who is now away from England. I understood him to say that as Dr. Carnelley's hot ice is obviously in a condition which cannot be represented within the as yet known fundamental water surfaces, it is necessary to produce these surfaces beyond the places at which, hitherto, abrupt changes have been supposed to take place in them. He took as an instance the *ice-water* surface which has hitherto been assumed to stop at Prof. James Thomson's "triple point," and showed that although Sir Wm. Thomson's experiments have proved that it is nearly plane for the stable state of water and ice, yet in the imaginary district beyond the triple point a change of latent heat might give such a change of curvature as to bring this surface into the hot-ice region.

With Prof. Ayrton I have done for water what Prof. James Thomson did for carbonic acid; we constructed in stiff paper a surface or surfaces which represent the relations of p, v and t for a given quantity of water-stuff. Three parts of the whole are cylindric surfaces and divide space into three regions; in one of them the substance is in the form of ice, in another in the form of water, in another in the form of vapour; and they meet in Thomson's triple point. Any one looking at this model must feel that Prof. Ayrton was right in looking for the hot-ice state in a region bounded by imaginary productions of the *all-ice*, the *all-water*, the *all-vapour*, and the above-mentioned three cylindric surfaces beyond their lines of intersection. This is what Prof. James Thomson did to indicate the state of water before boiling by bumping begins. He assumed that the *all-water* surface changed into the *all-vapour* surface gradually, and not through a purely cylindric *water-vapour* surface, and this is really what Dr. Lodge himself does for hot ice. That is, he imagines the *all-ice* surface to change into the *all-vapour* surface gradually, and not by sudden changes through a purely cylindric *ice-vapour* surface. According to Mr. Ayrton the imaginary production is even of a more complicated kind than Dr. Lodge supposes, as the ice probably changes into unstable water before it changes into steam. There can be no doubt that such imaginary productions find their place in the fundamental equation of water, but I cannot agree with Dr. Lodge in thinking that we have at present an explanation of such unstable conditions. If his explanation were satisfactory we ought to be able in the same way to explain the unstable position which precedes boiling by bumping, and this we cannot do. Where the explanation seems to me to fail is in the assumption that the hot vapour filling a cavity, being of lower temperature than the surface of the cavity, is always at a pressure less than that of saturation, in spite of the evaporation going on. Now when we consider how large the surface of a minute cavity is as compared with its volume, the very great increase in bulk when the solid is changed into vapour and the lowering of temperature which the surface must undergo on account of latent heat, we see that the condition which Dr. Lodge assumes to be maintained during the whole experiment would be instantaneously destroyed in a very minute cavity. In explaining hot ice I am afraid that neither Prof. Ayrton nor Dr. Lodge has given us more than Prof. James Thomson has given in explaining "boiling by bumping." The cause of the phenomenon is a molecular one probably, and must be left to the guesses of molecular physicists.

JOHN PERRY

14, Talgarth Road, West Kensington

Mr. Bottomley's Experiments with Vacuum Tubes and the Aurora

MR. BOTTOMLEY'S extremely interesting experiments briefly described in NATURE, vol. xxiii. pp. 218 and 243, appear to have a very important bearing on the question of atmospheric electricity; for if such high vacua are good conductors of electricity we have reason for thinking that the electrical conditions of our globe will be very different from what we have been accustomed to regard them. The layers of denser air surrounding the conducting matter of the globe will act like the glass of Mr. Bottomley's tubes in maintaining by a Leyden-jar-like action any difference of potential that there may be between their inner and their outer surface. Again, in the piercing of the glass tube by a minute spark, we have the analogue of the lightning flash between the clouds and the earth; the insulating layer in each case giving way, when, owing to an excessive increase in the surface density of the charge at any point, the dielectric stress exceeds the limits of the dielectric strength of the medium. The internal luminous effects observed by Mr. Bottomley as the result of change in the distribution of the external charge of electricity will be the physical analogues of the *aurora*, with this difference, that they take place in the ultra-gaseous interior, whereas in the case of our globe the luminous phenomena take place in the ultra-gaseous (*i.e.* highly rarefied) exterior regions of the atmosphere. It would be interesting to learn whether such discharges present any other analogies with auroral phenomena. I should be particularly interested in learning whether the conditions under which such luminous effects are obtained give any support to the theory which I think to be the only consistent one, that the aurora is due *not* to electrical discharges from regions of less atmospheric density to regions of a greater density (or *vice versâ*), but to electrical discharges in a region of pretty uniform (and small) density, and in which region differences of electric potential exist. According to this view the auroral streaks which appear to be radial should in reality lie approximately parallel to the earth's surface, and not stand (as most persons imagine) normal to it. A series of horizontal parallel lines drawn across the sky in a direction approximately north and south would necessarily appear to an observer on the earth's surface foreshortened into a set of lines diverging in fan-like forms at either the north point or the south point of the horizon. Their divergence would therefore be apparent only, like the "beams" diverging from the sun at sunset on a cloudy day, or like the beams of the *rayons du crépuscule*, or like the "radial streaks" which I have pointed out as frequently accompanying rainbows.

SILVANUS P. THOMPSON

University College, Bristol, January 22

P.S.—The behaviour of a hollow sealed glass tube containing a conducting substance in its interior was noticed just one hundred years ago by Cavallo, who sealed up a glass tube in which mercury was at its boiling-point, thus obtaining a fairly perfect vacuum.—S. P. T.

The Geological Age of the North Highlands of Scotland

FROM the abstract of *Proceedings* of the Geological Society (January 5) I learn with surprise that Sir R. Murchison's interpretation of the succession of the beds over the region north of the Caledonian Canal is disputed, and that the relations of the fossiliferous limestone of Durness to the quartzites "are" (according to Dr. Callaway) "by no means satisfactorily established, and that their conformity is rendered dubious by a marked discordance of strike"; in fact that the limestone lies in a synclinal basin amongst the quartzites, so that if the limestone be of Lower Silurian ("Arenig") age the quartzites and schists must be older; this I presume to be the inference Dr. Callaway intends to draw, as he says there "is no proof of the Lower Silurian age of the quartzite and newer series of flaggy gneiss and schist" constituting the interior mountainous district.

Having had an opportunity last spring of visiting the district lying between Lochs Broom and Inchard under the guidance of Prof. Geikie and in company with my colleague of the Irish Survey, Mr. Symes, I take the opportunity offered by Dr. Callaway's paper of expressing my entire concurrence in the interpretation of the structure of the country given by my late chief, whose elaborate and graphic descriptions in the pages of the *Quarterly Journal* of the Geological Society (vols. xv. and xvii.) will, I feel sure, never be invalidated.

After seeing the clear infra-position of the limestone to the upper quartzite and schists first in the section at the Bridge of Ault-Corry near Ullapool, then in the cliffs near Ullapool, next at Inchnadamff and the head of Loch Assynt, then again in the Forest of Arkle and the hills bordering Loch Stack, where the limestone band is clearly interbedded between the lower and upper quartzites, and this latter as clearly passes under the schists of the interior, it required no further evidence to prove that all these beds belong to one conformable formation; and that the geological age of the whole group is determined by the fossils discovered by Mr. Charles Peach in the limestone of Durness or Assynt, and named by the late Mr. Salter. The geological sequence is so clear throughout that region, and so entirely bears out the description given by Murchison and Geikie, that "he who runneth may read"; and I have no hesitation in saying that the evidence that the Millstone Grit overlies the Carboniferous Limestone, and that the New Red Marl overlies the New Red Sandstone is not more clear than that the upper quartzites and schists overlie the Assynt limestone.

I wish to point out in conclusion that the trough-shaped arrangement of the Durness limestone and its faulted position, described by Dr. Callaway, has already been described by Murchison in the *Quarterly Journal*, vol. xv. Any one visiting the grand tract of country lying between Durness and Loch Maree need have no better guide than the papers I have referred to, and a good geological map. He will find that there is little, if anything, to add to the details and conclusions there given, and were it not that Dr. Callaway's objections seem to find support with some geologists of more experience than himself, it would not have been necessary to enter a *caveat* against them.

As regards the question whether in any part of the Highlands of Scotland except along the western coast the Laurentian (or "pre-Cambrian") rocks reappear, as has been stated or suggested, I do not wish to offer an opinion. As regards the region

north of the Caledonian Canal, it seems to me that this is extremely improbable, as along the two traverses we made—one from Garve to Ullapool, the other from Laxford to Lairg—the prevalent dips are eastward, and the upper quartzites forming the elevations of Ben Dearig and Ben More are of great thickness. One may therefore assume that the Laurentian gneiss (even in the absence of the Cambrian sandstone) is deeply buried beneath these beds and their succeeding schists. The region of the Grampians of Aberdeenshire, on the other hand, is of great extent, and until it has been explored by the officers of the Geological Survey it would be injudicious (as it appears to me) to come to any opinion on the subject. EDWARD HULL

Geological Survey Office, Hume Street, Dublin, January 18

Geological Climates

HAVING considered the effects of Mr. Wallace's proposed redistribution of land and water, intended to raise the mean annual temperature of Bournemouth 15° or 20° F. above its present amount, I now, with your permission, shall say a few words on some minor questions, which have arisen during our discussion of the difficult problem of Geological Climates.

1. *The Clump of Bamboos at Cooper's Hill Engineering College.*—Prof. McLeod has kindly forwarded me a specimen of the foliage of the bamboo now growing in his garden, and has promised to send me the fruit when it ripens.

My botanical friends cannot decide its species, with certainty, from the foliage alone, without the seeds, but think that it, probably, is the bamboo called *Thamnocalamus Falconeri*, formerly called *Arundinaria falcata* (not *Arundinacea*) and also called *Bambusa gracilis*. If this opinion be correct my rejection of its evidence in favour of Cooper's Hill now having the climate of "torrid India" was also correct; for this bamboo is one of the hardiest of the "hardy bamboos" growing in the Himalayas, as high as the limit of perpetual snow, and being exposed, at night and in winter, to extremes of cold, which are never experienced in the British Islands. Whether our summers are hot enough to ripen its seeds, and fully acclimatise it amongst us, remains to be seen.

It is a suggestive fact that at Fota, in the Cove of Cork, where it grows in clumps 20 feet in circumference, from each of which spring over 400 canes reaching a height of 25 feet; the seeds ripen with difficulty and take a long time to germinate, some two months elapsing before they come through the soil, even in a temperature of 70° F.

2. *The Moreton Bay Pine at Bournemouth.*—Mr. William Ingram's letter, stating that an individual of this species, surrounded with "wooded heights" about it, has lived for forty years in Leicestershire, and attained a height of 35 feet, shows what the gardener's skill can accomplish in protecting a sub-tropical tree from the injurious effects of English winters, but throws no light whatever upon the possibility of the Moreton Bay pine living spontaneously in this country.

In order to do so it must ripen its fruit and produce seedlings, which (as I am informed) it cannot possibly do with the moderate heat of our cool summers.

3. *Tertiary Climates in England.*—Mr. Gardner states, that independently of the evidence afforded by the Moreton Bay pine, the Tertiary fossil plants of the Eocene require an increase of temperature of, at most, 20° F.

When we add to this that the London clay contains true *Crocodiles*, true *Palms*, many species of *Nautilus*, of *Volutes*, and large species of *Cypræa*, we may be certain that 20° F. increase of temperature is the very minimum required.

The question of importance is, whence did this required heat come from? This is a question of number and magnitude, and not of mere "naturalist talk." This question cannot be settled by redistributions of land and water, nor by repeating continually the assertion that all former causes of change of climate were the same as existing causes, not only in kind, but in degree.

SAMUEL HAUGHTON

Trinity College, Dublin, January 14

I AGREE with Prof. Haughton in his conclusion that no increase in the quantity of water sent into the Arctic Ocean by currents like the Gulf Stream would make much practical difference in the Arctic climate, though not altogether for his reasons. I think the question of total quantities of heat is irrelevant, and that the extent of glaciation and the distribution of plants and animals are almost exclusively determined by summer temperatures.

Respecting the distribution of plants and animals, I believe this is the general testimony of naturalists, and it is certainly confirmed by Nordenskjöld's observations on the Siberian flora. Respecting glaciation, I rely for proof on the well-known fact that the extent of perpetual snow on mountains—in other words, the height of the snow-line—depends, not on mean temperature, but on summer temperature.

If this is true it shows that no change in the ocean currents would make much difference; for a glance at Dové's isothermal lines for July and January shows that the effect of the Gulf Stream on the temperatures of Europe and Asia and the Arctic Ocean is chiefly confined to winter. The late Mr. Hopkins, in his well-known paper on changes of climate (Geological Society, December, 1851) estimated that the effect of the Gulf Stream on the July climate of London is null.

JOSEPH JOHN MURPHY

Old Forge, Dunmurry, Co. Antrim, January 17

Prof. Whitney on the Glaciation of British Columbia

IT must be gratifying to all geologists interested in the western part of America to find that a portion of the general results of the work of the Californian Survey is at length being published under the auspices of the Museum of Comparative Zoology at Harvard College, Prof. Whitney's "Auriferous Gravels of the Sierra Nevada" being now supplemented by the first part of a volume on the "Climatic Changes of Later Geological Times," dealing chiefly with the evidences of glaciation on the Pacific slope. No one will question Prof. Whitney's observations and deductions on this subject when he deals with that portion of the region with which he is personally familiar, especially as these are in substantial agreement with the already-published facts of Clarence King. The general result arrived at in the areas of Whitney's and King's surveys is that comparatively only a very small portion of the highest ranges of mountains has ever been covered with glaciers, and that there has never been in this region anything like a northern drift period or a transportation of material in any given direction independent of the present topographical features of the country.

This accords also with the statement published by Prof. Whitney in 1866 (*Proc.* Col. Acad. Sci. vol. iii. p. 271) as to the absence of glacial traces of a general character from California, but—as it appears to me unfortunately—a clause was added to this statement embracing in the generalisation the whole north-western extension of the Cordillera region. Now in 1866, as Prof. Whitney himself says, almost nothing was definitely known of the coast north of Oregon, and for that portion of it included in the province of British Columbia I have since maintained, as the results of observation, that there is conclusive proof of the occurrence of a period of general glaciation comparable in its effects with that of eastern North America (see *Quart. Journ.* Geol. Soc. vol. xxxiv. p. 89; *Canadian Naturalist*, vol. viii. No. 7; vol. ix. No. 1; also the following *Reports* of the Geological Survey of Canada, 1875-76, p. 261; 1877-78, p. 133 B.; 1878-79, p. 89 B.) In summarising and discussing the evidences of glaciation in British Columbia however Prof. Whitney still thinks it necessary to support the correctness of his paper of 1866. As Prof. Whitney's volume appears to be intended as a general, and, so far as the facts now known go, final review of the glaciation of the Pacific slope, and professes to contain "all that is necessary to set forth in regard to the former glaciation of the western side of the American continent," it may not be amiss to state that in my view the account given of the evidences of glaciation in British Columbia is in some cases insufficient, and that in the interpretation of other points misconceptions as to the nature of the facts have arisen. The tendency of the whole treatment of the subject is to minimise the glacial phenomena of the northern part of the coast and assimilate the conditions there found to those of California, which appear to me to be essentially different. (For a comparison of these see "Travelling Notes on the Surface Geology of the West Coast," *Canadian Naturalist*, vol. viii. No. 7.)

To criticise minutely the numerous features which seem open to such treatment in the account of this region, with which seven seasons' work in connection with the Boundary Commission and Geological Survey of Canada has rendered me familiar, would require a lengthened article, and would at best be an ungracious task. I will therefore touch on a few salient points only.

In dealing with the interior region of British Columbia lying between the Rocky and Coast Mountains no mention is made of the actual evidence obtained of a movement of ice from north to south in this plateau district, though it is afterwards incidentally alluded to in a quotation connected with a proposed explanation of the facts observed. The drift-covered and erratic-strewn character of the country is also ignored; and while the lower terraces bordering the rivers are mentioned, and attributed to fluviatile action—a view doubtless substantially correct—the fact that terraces are found beyond the river-valleys attaching themselves to the higher parts of the plateau and to the mountain-sides to an elevation of 5270 feet is passed over in silence. The conclusion is then easily arrived at that the "statement" of 1866 is "entirely borne out by an overwhelming weight of evidence."

Turning now to the coast of the province, Prof. Whitney of course admits the marked glaciation of the south-eastern extremity of Vancouver Island, which has been noticed by a number of observers, and which he has himself seen during a hurried visit. He states however that the markings he saw were everywhere parallel to the coast, and appeared to him more like iceberg than glacier work. Now as the coast is very sinuous in outline, while the main glaciation pursues *within a few degrees a uniform direction* (S. 11° W.), the two must in some places coincide, but an intimate acquaintance with the south-eastern part of Vancouver Island enables me to state that the glaciating agent has swept completely and steadily over it entirely, without reference to the present coast outlines. With regard to the second statement, I believe that a reference to the description of the character of the glaciation given in one of my papers already referred to (*Quart. Journ.* Geol. Soc. vol. xxxiv. p. 92) will be sufficient to convince any one who is familiar with ice action that a glacier has done the work. It is of course easier to be personally assured, where so much depends on judgment of local details, than to demonstrate the actual conditions to others; but the parallel grooving and furrowing out of hard rocks in the manner illustrated on pp. 93, 94, and 96, one has been accustomed to consider as characteristic of glaciers.

Further on Prof. Whitney assumes that the "manifestations" of the supposed Strait of Georgia glacier are "almost or quite exclusively limited to its termination." Some evidence to the contrary is however given in the publication to which special reference has just been made, while subsequent exploration—the published account of which Prof. Whitney appears to have overlooked—has brought to light similar and concordant glacier-work at Nanaimo, ninety miles to the north-west of Victoria, and has also demonstrated that a second branch of the great ice mass which choked the space between Vancouver Island and the mainland, comparable in size with that of the Strait of Georgia, discharged north-westward by Queen Charlotte's Sound (*Canadian Naturalist*, vol. ix. No. 1). In the lately-issued volume of the Geological Survey (1878-79) additional facts tending to show the importance of ice-action in the Queen Charlotte Islands and extreme north of the coast of British Columbia are given.

Not being in the position of having any favourite theory of glaciation to maintain, I wish merely to indicate by a few examples the inadequacy of the portion of Prof. Whitney's monograph which is intended to summarise the glacial conditions of British Columbia. Prof. Whitney appears to have been beset by observers "entirely inexperienced in the study of glacial phenomena" to such an extent as to render him unduly suspicious of the evidence obtained by other workers. He states, for example, that in passing to the region north of the boundary of the United States "we have to depend largely on the observations of others," and that "an attempt will be made to sift the evidence offered." Now while it is a little discouraging to find that one must belong to the class of "others," I feel confident that to any unprejudiced inquirer the facts already accumulated and published are sufficient to prove the general and pronounced character of the glaciation of British Columbia. It is perhaps not too much to ask that in this matter purely negative shall not be put on an equality with positive evidence. Prof. Whitney's profound distrust of the "others" again appears where he qualifies a reference to my statements by the clause "even if his observations be accepted as entirely trustworthy." It is, however, so far satisfactory to find oneself in good company, for Dr. Hector, who has also had the misfortune to have had something to say about this region which does not conform to Prof. Whitney's hypotheses, is referred to as "evidently quite inexperienced," and one whose "statements must be received with some caution," while Dr. R. Brown for a similar sin is characterised as "an entirely unpractised observer."

GEORGE M. DAWSON

Geological Survey of Canada, Montreal, December 22, 1880

Lophiomys Imhausi

IN NATURE of January 1, 1880, I published a note on the "habitat" of that strange and excessively rare rodent *Lophiomys Imhausi*; it may interest many of your readers to know that I have recently received from Count Lodovico Marazzani a splendid specimen of that species from a new locality, viz. Erkauid, on the mountains between Suakin and Singat, where it was captured quite accidentally on April 12 last by a shot from a small revolver. It was also secured and preserved by mere chance, for it was found by a small terrier and killed at the bottom of a deep fissure in the granitic rocks, and its value was quite ignored by those who first handled it; thus the skeleton and viscera were lost, but happily the skin was in excellent condition, and the skull had been left attached. It is an adult female and has four teats, two pectoral or rather axillary, and two inguinal; it is rather larger than the fine specimen at Genoa, but does not differ in colour or richness of fur. The luxuriant dorsal mane to which this creature owes its name is separated from the long hairs of the body by a narrow stripe of short stiff greyish green bristles. The iris was dark brown, and the animal emanated no special odour.

This is the *fourth* specimen of *Lophiomys Imhausi* that has been secured to science; the first was the type specimen accidentally brought alive by M. Imhaus at Aden and described by Prof. A. Milne-Edwards: it is in the Paris Museum, skin, skeleton, and viscera preserved. The second is the skull accidentally picked up by Dr. Schweinfurth at Maman, north of Kassala, and described in 1867 by Prof. Peters as *Phractomys æthiopicus*; it is I believe at Berlin. The third was accidentally killed by a blow on the head with a stick in the Seriba of Beccari and Antinori at Keren in the Bogos country in 1870; the mounted skin and skeleton are in the Civic Museum at Genoa. The fourth is the subject of this note; its skin has been splendidly mounted by my able taxidermist Signor R. Magnelli, and it and the cranium form an important item of the Florence Zoological Museum. The natives told Count Marazzani that *Lophiomys* is rare, that it lives in deep holes in the strangely fissured rocks of that country, and that it is a vegetable feeder; the stomach of the specimen I have was much distended with leaves and young shoots when Count Marazzani skinned it.

The "habitat" of this species is now pretty well defined by lines drawn from Suakin to Maman and Kassala, and thence southward towards the Somali coast.

HENRY HILLYER GIGLIOLI

Reale Istituto, Florence

Parhelion

YESTERDAY a parhelion or mock sun was seen here. At 3h. 20m. I was at the Observatory, and the true sun was sinking in the south-west upon a somewhat dense cloud-bank with light and long cirro strati about and above it. The air was comparatively calm, the anemometer cups moving only occasionally and slowly. The horizon was foggy and misty. The spectral sun appeared as a bright diffused circular spot of light tinged with prismatic colours about 30° to the left (E.) of the true sun, and in a horizontal line with it.

I could trace a segment of a circle having the sun for its centre, for a few degrees above and below the mock image.

To the west I could not trace any false image or continuation of the circle. The phantom image slowly faded away in about ten minutes from its being first observed. The weather has been severe here (something over 200 feet above sea), but hardly so sharp as in some other (probably lower-lying) places. With Negretti and Zambra's standard minimum in cage four feet from the ground, 11° is the lowest I have registered.

During, however, the past seven days the maximum has only twice risen above freezing-point, and then but 1°.

Guildown, Guildford, January 21 J. RAND CAPRON

Girton and Newnham Colleges

SOME of your readers may perhaps be glad to help the natural science students of Girton and Newnham Colleges to raise about 800*l.*, needed for a physical and biological laboratory. The

present provision for practical work is very inadequate, and the number of students has largely increased, while the required money is not forthcoming. I have already received the following donations, and shall gratefully acknowledge any further help:—Mr. Charles Darwin, 5*l.* 5*s.*; Mr. Edward Dormer, 5*l.*; Mr. T. Newland Allen, 3*l.* 3*s*; Mr. William Fasseridge, 2*l.* 2*s.*; Anonymous, 2*l.*; Mr. Frank Dethridge, 1*l.* 1*s.*; Anonymous, 1*l.*; Mr. G. Eves, 1*l.*; Mrs. Eves, 1*l.*; Mr. R. Wilkinson, 1*l.* 1*s.*; Rev. C. T. Mayo, 1*l.* 1*s.*; smaller subscriptions, 4*l.* 15*s.* Any further particulars will be most willingly given.

FLORENCE EVES,
Science Student of Newnham College

Mitton House, Uxbridge, January 22

Minerva Ornaments at Troy *v.* Net-Sinkers

NOT having seen the numbers of NATURE regularly during the autumn, I did not observe Mr. Sayce's reply to my letter on the above subject until lately. I may perhaps trespass on your space with a few lines in reference to it.

I certainly did not observe any markings upon the stones in question that could be construed into any likeness to a human face or to that of an owl. Not having the opportunity of re-examining them I must take this as granted according to Dr. Schliemann's judgment. Of course an expert can see, and see with certainty, what to one less experienced seems quite invisible. At the same time an enthusiast, as we all know, is rather apt to "oversee," and find in his relics more than actually exists. I say this, as it is a common occurrence, and not in any way to disparage Dr. Schliemann's valuable work.

But admitting the existence of such outlines upon the stones in question is it not far more probable that the half-savage natives of the Troad may have taken advantage of certain suggestive lines and roughly outlined an image upon a net-sinker, than that they made so large a number of rough and uncouth things as likenesses of Minerva? The use of stones similarly chipped in the middle as net-sinkers seems common to savages all over the world, and it would seem to me therefore wiser to name them net-sinkers (with outlines, &c.) than to ticket them "Minerva ornaments."

One point, if I understand him aright, which Dr. Schliemann endeavours to prove, is that Ancient Troy stood close to the river. Hence the occurrence of net-sinkers may be considered as probable.

E. W. CLAYPOLE

Antioch College, Yellow Springs, O., December 18, 1880

THE PROVOST OF TRINITY COLLEGE, DUBLIN

THE Rev. Humphrey Lloyd, D.D., was born in 1800. He was the eldest son of the Rev. Bartholomew Lloyd, who was Provost of Trinity College, Dublin, from 1831 to 1837. Humphrey Lloyd entered his father's college in 1815, graduated as a Gold Medallist in Science in 1820, and was elected a Fellow in 1824. In 1831 he was appointed Professor of Natural Philosophy. He was co-opted a Senior Fellow in 1843, was made Vice-Provost in 1862, and was appointed by warrant from the Crown to the Provostship in 1867. He died, after a few days' illness, in the Provost's house on the 16th inst.

Full of years and honours, a very distinguished life has been brought to a close. Part of it was spent in laborious scientific research, part as the head of a great teaching establishment. Both portions of his life were a success, as even a short sketch of that life will show.

Lloyd was an excellent, though by no means a profound, mathematician. On becoming the Professor of Natural Philosophy he devoted himself with some ardour to the study of physical optics, and his report on this subject, laid before the fourth meeting of the British Association, was quite a masterpiece of reporting, and may still be consulted with pleasure. He was not however by any means content with having a knowledge of the work done by others, but was determined to enter on the field of original work himself; an opportunity soon offered. About 1832 Sir William Hamilton had been investigating the relations between the surface of wave-slowness and that of the wave, and thereby had been led to the discovery of some new geometrical properties of the latter. These properties he demonstrated by means of certain transformations of the equations of the wave-surface, and he showed that this surface had four conoidal cusps at the extremities of the lines of single ray-velocity, at each of which the wave is touched not by *two* planes as Fresnel supposed, but by an *infinite* number forming a tangent cone of the second degree; while, at the extremities of the lines of single wave-velocity, there were four circles of plane contact, in every point of each of which the wave-surface is touched by a single plane. These singular properties led Hamilton to anticipate two new laws of refraction called by him external and internal "conical refraction." Hamilton was naturally desirous of having his theoretical conclusions proved by experiment; such experiments required a wonderful patience, delicacy of touch, and an almost instinctive sagacity. As possessing all these he selected Lloyd to solve his problem; and by his labours in a short time the reality of this interesting phenomenon was established.

The memoir by Hamilton and the experimental researches by Lloyd appear in the same volume (xvii.) of the *Transactions* of the Royal Irish Academy.

Lloyd published several treatises and memoirs relating to optical science, but he was persuaded by Sir Edward Sabine to turn his attention, about 1836, to the subject of terrestrial magnetism. At his request the Board of Trinity College, Dublin, built a magnetical observatory, and the Professor entered with zeal upon those studies of magnetism which will for ever remain connected with his name. It would be unnecessary here to enumerate his very numerous writings on this subject.

In 1838 the British Association resolved that having regard to the high interest of the simultaneous magnetic observations which have been for some time carried on in Germany and various parts of Europe, and the important results to which these have led, they regard it as highly desirable that similar series of observations should be instituted in various parts of the British Dominions, and they suggested, as localities particularly important, Canada, Ceylon, St. Helena, Van Diemen's Land, and the Cape of Good Hope, also in the Southern Hemisphere. They further appointed as a Committee to approach the Government on this question Sir J. Herschel and Mr. Whewell, Dr. Peacock and Prof. Lloyd. The Committee, appointed late in August, at once set about their arduous work, and their memorial was laid before Lord Melbourne in the November following. The President and Council of the Royal Society strongly supported the memorial, and these concurrent representations were attended with full effect. In the Report of the Committee to the British Association in 1839 it is stated, "probably at the very moment when this report will be read, two ships, the *Erebus* and the *Terror*, under the command of Sir James Clark Ross, will be already on their voyage to the Antarctic Seas, carrying with them every instrument requisite for the complete and effectual prosecution of important magnetical researches in the high southern latitudes, and also complete establishments, both personal and instrumental, of the fixed magnetical observations to be placed at St. Helena, the Cape of Good Hope, and Van Diemen's Land. It was no wonder that the Committee were proud of the result of their labours, and that they acknowledged in strong terms the ample and liberal manner in which every demand on the national resources had been without exception granted, expressing at the same time the hope that this splendid example might be followed up by other nations. The report is signed J. F. W. Herschel and H. Lloyd.

In 1843 Dr. Lloyd pointed out a mode of reducing the error attending the determination of the intensity of the earth's magnetic force to less than one-fifth of that by the ordinary method.

In 1858 he again pointed out a fatal imperfection

attending the ordinary mode of calculating the same force, and proposed instead a method requiring for its application only the use of the dip-circle, a vast advantage to the traveller, as it reduced to the smallest possible number the instruments which he would have to carry.

Along with his friend Sabine he visited the chief Continental cities in 1839, going as far as Berlin. This tour was altogether undertaken for the purposes of establishing still further a system of joint records of magnetical phenomena. His chief work in connection with magnetism was published under the title of "The Dublin Magnetical and Meteorological Observations" (2 vols. 4to, 1865-69). In 1857, when the British Association visited Dublin for a second time, Lloyd was their president, and many will still remember his dignified and courteous behaviour as such.

When, in 1867, Dr. Lloyd was appointed provost, there was scarcely one dissentient voice. He had distinguished himself in his college career; his researches had reflected lustre on his university, and the belief in him was never shaken. During his period of office as Senior Fellow the study of the experimental sciences was introduced into the curriculum; in 1851 it was even possible to graduate as a Gold Medallist in these. To the experimental sciences were at first joined the natural sciences. During his provostship, these two groups were separated, to the great encouragement of the students in both. It was something wonderful to find how the now aged provost kept pace with the time, encouraging in every way the more modern view of things. Among the Professors and Fellows of his college he was very popular; he was always affable, while he possessed a quiet dignity. Proudly conscious of the position he held as Provost of Trinity College, he was singularly unambitious of worldly honours, but the honorary degree of D.C.L. from the sister University of Oxford, conferred on him in 1856, was grateful to him, and he always spoke with pleasure of the recognition of his scientific merits by the Emperor of Germany, who conferred on him in 1874 the order "Pour le Mérite;" he was a F.R.SS. Lond. and Edin. He received the Cunningham gold medal of the Royal Irish Academy in 1862.

GEOLOGISING AT SHEPPEY

SO much has been said about the abundance of fossil fruits at Sheppey that most geologists picture them lying plentifully upon the shore waiting to be picked up, and their only concern might well be at the outset to provide baskets strong and ample enough to convey their collectings home. A day spent upon the beach would dispel these preconceived ideas.

The cliffs in a wet season are streams of liquid mud alternating with freshly-fallen landslips rendering them practically unapproachable. The wet and frost have this year proved exceptionally disastrous, and mere shreds of coast-paths remain. In places slabs of freshly-ploughed land are arrested half-way down the cliff, and at one point a cabbage garden with the produce still only partly cut is streaming down to the beach. It is a good time for the cement works, but when Roman cement falls into disuse, as it seems likely to, then perhaps steps will be taken to stay this perpetual removal of fine arable land into the channels of the Thames. The beach itself is gravelly, and at low water there are extensive mud-flats. Among the gravel are patches of rolled pyrites, and among these pyrites the fruits are found, though valuable specimens are rare. This Christmas five experienced collectors, including Mr. W. H. Shrubsole, F.G.S., Mr. O. A. Shrubsole, F.G.S., Dr. Häusler, F.G.S., myself and brother, searched for several hours without a single fairly perfect fruit being found, and no greater success attended us on subsequent days. The vast bulk of the pyrites is amorphous; the majority of that which retains any recognisable shape is made up of twigs; a considerable percentage is of nearly obliterated casts of shells; and here and there are broken up Nipadites and other water-worn fragments of fruits. The best way to collect is to lie down upon the pyrites and examine it closely, when seeds and twigs that are passed over by the copperas-gatherers may be picked out. In this way I found seeds and scales of Araucaria, twigs of Ephedra, and many other shapes that may some day be recognised as parts of still-existing plants. No rest, short of doing absolutely nothing, could be more perfect to an overworked geologist's brain than to sprawl and smoke upon this beach.

The fruits themselves are so rare in the London Clay that they are seldom if ever found *in situ*, no prolific patches are known, and to attempt to dig for them would be futile. Their abundance in collections is due to the facts that for several miles there are lofty cliffs perpetually wasting away, and that the whole of the clay that reaches the beach is slowly removed in suspension by the sea, every particle of pyrites remaining behind until picked up for copperas or dissolved away. For two hundred years they have been known and searched for daily by the septaria and copperas collectors, and any one may quickly purchase an extensive collection. I have within a few months received from my friend Mr. Shrubsole enough Nipadites to fill a twenty-gallon cask, besides other fruits innumerable. Bowerbank's collection numbers many thousands, 300 specimens of a rare cone alone from Herne Bay having been in his possession. There is in the British Museum a MS. catalogue by a Mr. Crowe of Faversham, with 831 very rough drawings representing, as he supposed, 700 varieties. Ettingshausen, when he examined the British Museum collection, made 200 species. How many there may really be is still unknown, but the number doubtless is very considerably beyond the latter. Among the Coniferæ alone I have to add, besides the Ephedra, a *Podocarpus* near to *P. elata*, a *Frenella* almost indistinguishable from *F. Endlicheri*, and an *Araucaria* near *A. Cunninghami*. I have grave doubts about the correctness of the determination of all the other Coniferæ except a few of Bowerbank's Cupressineæ, and am still at work upon them. The state in which they are preserved is not sufficiently taken into account. The woody matter is generally preserved as lignite, and easily removed when rolled upon the beach, and the pyrites which remains filled the cavities between the more solid parts, as well as replacing the fruit itself. The densest and most salient part now is the purest pyrites, and was therefore at the time of fossilisation probably the most open part of the fruit or the filling in of cavities. The casts that are found are thus, in the case of hard-shelled fruits, more often casts of the space between the outer ligneous shell and the kernel, than of either the kernel or the shell itself. In the case, for instance, of an almond, we should have most frequently a smooth cast of the inside of the shell, but in perfect fruits the pitted exterior would be preserved, and in fruits partially dissolved the wrinkled kernel would show. In fruits with septa the variety of aspect presented in different stages of preservation is very great, and has doubtless led to the same species being catalogued under several names. The so-called Sequoia or Petrophiloides of Herne Bay is another instance, for the filling-in between the open scales of the cone was thought by Bowerbank to represent confluent scales inclosing cells, the supposed cells being really the cavities left by the true scales which have decayed away, while the infiltrated pyrites has enveloped the seeds which lay under them.

On Monday we took the 8 a.m. train to Herne Bay and searched at Swalecliffe for cones. At Whitstable we set sail in an oyster-boat for Shellness, but some delay occurred in getting it off the ground; the wind dropped in the meantime, and we had to row. Shellness

was reached at dusk, and we experienced some difficulty in landing across the mud, which stretches a long way from shore at low water. We reached Warden Point at 6, and found that the fly we expected to meet us had driven home an hour before. The position of two mud-covered and complete strangers on a dark night on a most desolate spot, in drenching rain, eight miles from, and two hours late for dinner was not particularly enviable; yet a well-arranged excursion from Whitstable to Sheerness, *viâ* the singular shores of Shellness, would under pleasanter circumstances well repay any naturalist.

J. STARKIE GARDNER

THE CONSERVATOIRE DES ARTS ET MÉTIERS[1]

ONE of the most eminent English men of science said to us one day :—"You have at Paris collections, libraries, museums, observatories, faculties, schools; we have the equivalent of all that. There is only one thing we have not, which I always admire among you, and that is the Conservatoire des Arts et Métiers."

The National Conservatoire des Arts et Métiers[2] is, in fact, an establishment unique of its kind both in its scientific interest and practical utility. No institution is more



FIG. 1.—Plan of the Conservatoire des Arts et Métiers, and of projected additions.—1, Office for the verification of weights and measures; 2, Laboratory of the Course of Mechanics (Prof. Tresca); 3, Ground-floor: Laboratory of the Course of Dyeing and of Ceramics (Prof. Luyne); First floor: Laboratory of Agricultural Chemistry (Prof. Boussingault); 4, Ground-floor: Amphitheatre; First Floor: Physical Laboratory (Prof. Becquerel); 5, Provisional location of the Agronomic Institute; 6, Great Hall of Machinery in motion; 7, Great Amphitheatre; 8, Old Amphitheatre; 9, Library; 10, Laboratory of Industrial Chemistry (Prof. Girard); 11, Laboratory of General Chemistry (Prof. Peligot); 12, Great staircase; 13, The Echo Hall; 14, Galleries and Collections; 15, Ground-floor: Gallery in construction; First floor: Gallery of Ceramics and Optics; 16, Ground-floor: Weights and measures; First floor: Gallery of Spinning; 17, Exhibition Hall and Gallery of Spinning; 18, Administration and Gallery in construction; 19, Industrial drawings, patents, and trade-marks; 20, Projected construction, gallery of collections; 21, Projected construction; 22, Proposed location for the Central School of Arts and Manufactures.

worthy of the solicitude of the Government, since it has for its object the occupation of the workers and the instruction of the people. The Conservatoire is about to make a fresh start in consequence of the construction of a new block of buildings. There is even reason to hope that these works will only be the prelude of constructions still more important, and that very soon a law will insure the completion of our fine national establishment. The following are some of the improvements which have been recently introduced into the institution.

The service of patents and of the industrial department has been recently installed in the new buildings in the rue St. Martin. Early in November there was placed at the service of the public the old and remarkable collection of Vaucanson's drawings. These drawings, which form a considerable series, comprised between the years 1775 and 1829, have a great historical interest. We find in them the germ of a considerable number of apparatus or of systems realised in our time, and which the want of processes of execution condemned to remain in the condition of projects. We see there a great number of curious objects, and notably the original drawing of Fulton's first steamer.

Among recent additions we may mention the great gallery of machinery (No. 6 in the accompanying plan, Fig. 1), to which is added the entire apse of the old

[1] From an article in *La Nature*, by M. Gaston Tissandier.

[2] Descartes had the idea of its foundation; Vaucanson formed the first germ of it by his public collection of machines, instruments and utensils, intended for the working classes; and the Convention decided on its definitive creation by a decree of 8 vendémiaire of the year xii.



FIG. 2.—The Great Machinery Hall of the Conservatoire.

church of St. Martin's priory. We see here the curious steam-carriage of the mechanician Cugnot, and the fine statue of Denis Papin by M. Aimé Millot, the bronze duplicate of which was inaugurated at Blois some weeks ago. Besides the machinery which has long been at work in this gallery, the new administration of the Conservatoire is endeavouring to show visitors all the new and interesting apparatus used in the great Parisian industries. More than 3000 visitors witness every Sunday these experiments, very beautiful and very instructive for every one. Among the most notable apparatus are those connected with electrical phenomena. The beautiful experiments of M. Gaston Planté have obtained the greatest success, as also those relating to the transmission of power to a distance by electricity. The Conservatoire is thus becoming the museum of machinery in action.

While the machinery is thus at work in the great nave, other experiments are going on in the galleries. The great electrical machine throws off sparks in the physical hall, and projections by means of the oxyhydrogen light are made elsewhere by M. Molteni. Visitors show great interest in the Echo room, the Lavoisier room, in which is a great number of instruments used by the founder of modern chemistry, the Agricultural room, where are exhibited all the newest models of agricultural machinery. It is scarcely necessary to speak of the courses of lectures by eminent professors, many of whom are known beyond France; the gratuitous courses here and at the Sorbonne for 1880-81 comprise almost every branch of pure and applied science. The public library of more than 30,000 special works is freely placed at the disposal of workers.

Among the less known departments is the public service for testing the resistance of materials, very useful to architects, contractors, and builders. Any one may take advantage of it. It is sufficient to send to the Conservatoire specimens of stone, marble, pottery, metals, tubes, &c., which are crushed, broken, or bruised by special machinery, and the results accurately registered. The most powerful of these machines is a hydraulic press of 500,000 kilograms.

Such, in few words, is the Conservatoire des Arts et Métiers. By its collections, its public courses, its library, its eminently practical services, it may be regarded as one of the most valuable institutions of France.

NOTES

THE Faraday lecture will be delivered by Prof. Helmholtz in the theatre of the Royal Institution on Tuesday, April 5. The subject will be "The Modern Development of Faraday's Conception of Electricity." The lecture will be delivered in English.

PROF. HOLDEN, of the U.S. Naval Observatory, Washington, has published, through Scribner, a biography of Sir William Herschel. Prof. Holden is also publishing, through the Smithsonian Institute, a subject index and synopsis of the scientific writings of the great astronomer.

THE Kent's Cavern Committee, when presenting their *final* Report in August last to the British Association stated that, from the first day of the exploration in 1865 to its close in 1880, George Smerdon had been continually engaged on the work, and for nearly thirteen years had been the foreman; that during that period he had always discharged his duties in a most exemplary manner, and without the least misunderstanding with the superintendents; that he was nearly sixty years of age, and so crippled with chronic rheumatism—induced by working for so many years in the damp Cavern—as to be incapable of any ordinary labour, and that it was proposed to raise by subscription a fund sufficient to secure him a small annuity. The proposal was cordially received, and Mr. Pengelly was encouraged to carry it into effect. Several contributions have already been received from Mr. G. Busk, Prof. W. B. Dawkins, Dr. John Evans, Mr. J. E. Lee, Sir John Lubbock, Bart., M.P., F.R.S., Mr. W. Pengelly, Mr. E. Vivian, M.A., and others. Further contributions to the "Smerdon Testimonial Fund" may be paid directly to Mr. W. Pengelly, Lamorna, Torquay, or to Messrs. Vivian, Kitson, and Co., Bankers, Torquay.

A MARBLE statue of Nicephore Niépce, the inventor of photography, is now being executed by the celebrated sculptor, M. Guillaume of Paris, and will be erected and unveiled in May next at Châlons-sur-Saône.

PROF. MASKA of Neutitschein writes that the excavations now going on in the Schipka Cave, near Stramberg (Moravia), have yielded some interesting results. Among the numerous remains of Post-Tertiary animals (such as mammoth, rhinoceros, urochs, horse, lion, hyæna) the jaw-bone of a supposed diluvial human being has been found. It was imbedded in the immediate vicinity of a place where carbonised animal bones, stone implements, and bone utensils were found. The jaw-bone, described as having belonged to a child of some eight years of age (according to the development of the teeth), is of very large, indeed of colossal dimensions.

THE director of French Lighthouses has sent to the Minister of Public Works a communication recommending the lighting, by electricity, of all the great lighthouses on the French coasts. It will involve an expenditure of several millions of francs, which will end in a large economy and an extension of the range of illumination. A system of steam-trumpets is also to be established in connection with these improved lighthouses.

WITH the January number the *Quarterly Journal of Microscopical Science* enters on the twenty-first volume of its second series. First published in 1853, under the editorship of Dr. Edwin Lankester and Mr. George Busk, it now appears under the editorship of Prof. E. Ray Lankester, assisted by Mr. F. M. Balfour, Mr. W. T. Thiselton Dyer, and Dr. E. Klein. Mr. William Archer has withdrawn from the editorial staff.

THE minutes of the *Proceedings* of the Dublin Microscopical Club, which since 1865 have been published in the *Quarterly Magazine of Microscopical Science*, will for the future, we understand, be published in the *Annals and Magazine of Natural History*.

WE understand that Mr. Richard Anderson, the author of the well-known work on Lightning Conductors, has nearly ready for publication a treatise—based on the "Instruction sur les Paratonnerres adoptée par l'Académie des Sciences" of France—to be entitled "Information about Lightning Conductors."

AT its last session the French Parliament voted a grant of several millions of francs for the completion of an underground system of telegraphic wires connecting the principal cities with Paris.

SEVERAL electric railways are to be tried on the occasion of the forthcoming Electrical Exhibition at Paris. The most important will be built by Siemens Brothers, and will form consequently a prominent part of the British display. At the last sitting of the General Council of the Exhibition M. Georges Berger announced that a steam-engine of 800 horse-power will be arranged for the working of the electric light, and the number of lamps in operation is estimated at 600. A number of these will be in the large hall, but a large proportion in the gardens, in the *annexe*, and in a series of saloons fitted up magnificently with tapestry-work by the Government. The *annexe* is to be the Pavillon de la Ville de Paris, which was one of the wonders of the 1878 Exhibition, and will be transported to the vicinity of the Palais de Champs Elysées.

In connection with our recent note on the Young Men's Home Education Society, a lady in Cork sends us some information concerning the Minerva Club, whose head-quarters seem to be in that city, and which aims at enabling ladies to educate themselves at home. The regulations of the Club seem well adapted for this purpose, and the programme includes natural science. The books recommended are all standard ones, and the ex-examiners men of good standing in literature and science. The specimens of the examination papers sent us in geology and geography show that a high standard is aimed at. The honorary secretary of the Club is Mrs. W. S. Green, The Rectory, Carrigaline, Co. Cork.

In the course of dredging operations in the bed of the Limmat, at Zurich, some very interesting objects have been brought to light, among others ancient coins (including fifty gold pieces of Brabant), swords, and the skeleton of a stag of a species now extinct in Switzerland. The piers of a Roman bridge which once spanned the river have also been laid bare. All the finds are being placed in the Zurich Historical Museum.

A report has reached Vienna, January 24, which has not yet been confirmed, of a fresh earthquake at Agram, attended with disastrous consequences. At Landeck (Tyrol) three shocks were noticed on January 10, at 9 p.m. The first one was the most violent, and the other two followed at intervals of five minutes. The earthquake which was felt at 5.15 p.m. on December 25, in Southern Russia, extended as far as Odessa and Kishineff in south-west, Tiraspol, Byeltzy, in Bessarabia, and the Ouman district of the province of Kieff in north-east; it was strong enough in the villages Leghezino and Vishnepolie of this district. At Molokishi, district of Balta, and at Byetzy, it was very strong.

A meteoric stone fell at Wiener Neustadt a few days ago, near the telegraph office, and penetrated deeply into the gravel-covered road. The phenomenon was witnessed by several persons, who all declare that the meteor showed a brilliant light. Upon inspection a triangular hole was discovered of 5 centimetres width; the ground was frozen at the time. The meteoric stone was excavated in the presence of Dr. Schober, director of the Wiener Neustadt High School. It weighs 375 grammes, is triangular in shape, its exterior is crystalline, with curious blackish, greyish, and yellow-reddish patches. Here and there metallic parts give a brilliant lustre. Its specific weight is very high, its hardness about 9. An analysis is now being made.

The second series of Evening Lectures delivered at the Royal College of Science, Dublin, has commenced with satisfactory entries. The classes have been voluntarily undertaken by the professors in order to afford a systematic course of study available to beginners and to those who are earning their livelihood in various avocations during the day. Artisans and others receiving weekly wages are admitted at half fees. The courses consist of from fifteen to twenty lectures in each of the following subjects: Biology, Dr. McNab; Physical Geography, Prof. O'Reilly; Geology and Mineralogy, Profs. Hull and O'Reilly; Chemistry, Prof. Hartley; Physics, Prof. Barrett; and Mathematics, Mr. Stewart, the Demonstrator in Physics. During the session of 1879-80 the numbers in attendance at the various classes were 336. In order to give assistance needful for the continuance of this course of instruction the Worshipful Company of Drapers have generously voted the sum of 100*l.* per annum for a period of three years. The earnestness, intelligence, and regularity of those attending the evening classes is remarkable, giving evidence of a hearty desire for sound and solid scientific instruction in Ireland, as well for the love of knowledge itself as for the purposes of technical information.

News from Cairo states that to the north of Memphis, near Saggarah, two pyramids have been discovered which were constructed by kings of the sixth dynasty, and the rooms and passages of which are covered with thousands of inscriptions. The discovery is said to be of the greatest scientific importance.

The Prefect of the Seine has opened in Paris a public laboratory for the analysis of any substance used for food; the fees are very moderate, and vary from 5 francs to 20 francs, according to the difficulty in the determinations.

A medical gymnasium was opened on January 22 at Paris. It has been built in the Chausée d'Antin at an expense of 20,000*l.*, by a public company. About seventy mechanical contrivances of different descriptions have been arranged in a series of rooms. The greater number of these are worked by a steam-engine, and all of them can be graduated by screws, so that the extent, duration, and velocity of motion can be regulated according to the direction of the physicians.

The electric steamer *Pouyer-Quertier*, belonging to MM. Siemens Brothers, has arrived at Havre, after having successfully repaired the French cable, which had been discovered to be faulty.

In his last report to the Foreign Office H.M.'s Consul at Shanghai points out that the Chinese are much more disposed to allow the opening of coal-mines than the construction of railways. Without referring to the work being done in Formosa, he mentions that operations are in progress under English engineers for the opening of coal-pits at Kaiping, near Tientsin, and near Nganking, the capital of the Nganhwuy province. Both districts have plenty of coal, but unfortunately no navigable waterway, and for this reason the engineer of the Nganking coal-mines intends to remove to another locality near by, where there is an equal quantity of coal and better water-power. At Kaiping matters are worse, for the nearest navigable stream is at Lutai, forty miles away. To reach this it is expected that a railway may be constructed, but, as it can hardly be a commercial success, it would not much promote the cause of railway enterprise in general. The engineers find no difficulty at Kaiping in obtaining Chinese labour, but the English workmen sent there have not given satisfaction, and the Chinese are getting rid of them.

M. Magitot, a member of the Prehistoric Congress which met at Lisbon last autumn, reports on a Portuguese Pompeii, which he had occasion to inspect while on a tour to the territory of Tertiary Silex at Otta. The place is called Santarem and Citania. The latter is the general Portuguese name for ruins of ancient towns, which cover entire hills in the neighbourhood of Braga. The most important of these very old town-ruins is the Citania di Briteiros, which occupies nearly a kilometre square, and is supposed to be of Celtic origin. Circular walls, streets, squares, large architectural monuments, and even a number of houses have retained their typical forms. For twenty centuries this Citania was buried below *débris*, soil, and a rich vegetation; only a few years ago a zealous archæologist, Senhor Sarmento, succeeded, by costly and troublesome efforts, in clearing away the covering of centuries and to lay open to the world an ancient city in which quite a primitive state of civilisation is apparent. Its architecture and plastic ornamentation point to a somewhat advanced state of art and industry. Many stone monuments are covered with sculptures and inscriptions, which in their general character recall those of India and China, which the well-known Lyons archæologist, M. Guimet, declares to be of a symbolic and religious character, similar to those found upon the oriental monuments. It is possible that this fact might be adduced as a proof that the tribes who built these Citanias had originally emigrated from Turan.

News from Washington territory states that the volcano Mount Baker was in full eruption quite recently

We have received the first number of the *Revista* of the Society of Instruction of Oporto. There are various papers bearing on education, and one by Mr. E. J. Johnston on the Phanerogamous Flora of Oporto. The number of English names on the list of this Society is remarkable; the first name among the Foundation Members is that of Isaac Newton, followed by W. C. and A. W. Tait; there are several Allens, a Johnston, several Kendalls and Coverleys, F. C. Rawes, Henrique Rumsey, a Grant, a Hastings, and an Archer. This no doubt indicates the close commercial relations between Oporto and England.

It is known that Leverrier, urged by growing infirmities and apprehending that he would not live to accomplish his great work on the theory of Saturn, left a part of his calculations uncompleted, convinced that this would exert no real influence on the total result. But M. Gaillot, the director of the Calculation Service of the Paris Observatory, felt it a duty to fill up the gap left by the late director of the observatory and to revise the whole of his work. We are happy to state that, as far as the revision has gone, the accuracy of the conclusions published by the great astronomer is demonstrated, and none of the neglected terms will exert any appreciable influence.

We take the following from the *Albury Banner* (New South Wales):—It has long been a matter of popular belief that the great kingfisher was an enemy of the snake, perpetually warring upon the tribe in general, and never happier than when dining on serpent *au naturel*. It is not often, however, that even persons habitually residing in the bush have so good an opportunity as that afforded a few days since to Mr. Christian Westendorff of Jindera, for observing the laughing jackass when in the act of bagging the game referred to. Mr. Westendorff was engaged with another man in clearing some land, and in the course of the day's operations it became necessary to shift a large log. For this purpose levers were applied to each end, and after some straining the log was rolled from its resting-place. The very moment it commenced to move a laughing jackass, which had hitherto been taking a deep but unobtrusive interest in the proceedings, made a swoop down from the limb of an adjacent tree, and seized a large snake which had been lying under the log. The snake was gripped by the back of the neck (if snakes can be said to have necks) and borne away to the bird's previous perch, where the unfortunate reptile was banged against the bough until the body separated from the head and fell to the ground. The jackass then dropped the head, and seizing the body sailed away in triumph with his prize. Whether the bird had seen the snake go under the log and was watching for it to come forth again, or whether it knew by instinct that the reptile was there, is a question that may be left for naturalists to determine; but we are credibly informed that as soon as the log was shifted, and before Mr. Westendorff or his companion had any idea of a snake being in their neighbourhood, the jackass was down and had made good his seizure.

The Russian Technical Society has created a special branch which will devote its attention to aëronautics, especially to the popularisation of all branches of aëronautics, to recent researches on this field, to the meteorology of the higher regions of the atmosphere, and to the study of the applications of aërostatics to military purposes.

We note from the *Deutsche Industrie-Zeitung* that during 1879 some 140 tons of amber were obtained at the coast of the Baltic, of which the mine at Palmnicken yielded seventy-five tons, and the digging-engine at Schwarzort the remainder. About fifteen tons were gathered by nets and picked up on the shore. Some 3000 people (including women and children) gain their living by gathering amber.

At the end of 1880 the Berlin Electro-technical Union numbered no less than 1575 members, 1246 of whom are foreigners.

A number of Celtic tombs were recently discovered near Lichtenwald, on the frontier between Styria and Carniola, not far from Cilli. Several of them were opened, and numerous urns were found in them. A few objects of more interest have been sent to the local museum at Cilli.

The well-known Hungarian archæologist, Herr Wilhelm Lipp, continues the excavations of the ancient burial-ground discovered by him at Kessthely. The cost is borne by the Budapest Archæological Society. These tombs are rich in bronze and iron objects dating from the fourth and fifth centuries.

OUR ASTRONOMICAL COLUMN

Brorsen's Comet in 1842.—In September, 1846, it was pointed out by Mr. Hind (*Astron. Nach.* No. 582) that the comet of short-period discovered by Brorsen at Kiel on February 26 preceding must have approached very near to the planet Jupiter about May 20, 1842, possibly within 0·05 of the earth's mean distance, and it was surmised that an entire change of orbit might have been produced at that time. In 1857 D'Arrest examined this point more closely, applying the formulæ of the *Mécanique Céleste* to determine the elements prior to the encounter with the planet. His results were published in *Astron. Nach.* No. 1087. Adopting good elements for 1846, but without taking account of perturbations, since the comet left the sphere of activity of Jupiter after the near approach, he inferred that the closest proximity occurred May 20·6924 Berlin mean time, the distance between the two bodies being then 0·05112; that for April 19·5 the inclination of the comet's orbit was 40° 51′, or 10° greater than in 1846, and that the perihelion distance was greater than 1·5, instead of 0·65 at the time of Brorsen's discovery, and it was considered that the comet would not be visible when the radius-vector was much over unity; hence, perhaps, our ignorance of its existence before the year 1846. Thus the question has remained until within the last two years. Our object now is to record the results of a much more complete investigation of the effect of the comet's encounter with Jupiter, by Herr Harzer, forming the subject of an inaugural dissertation in the University of Leipsic in 1878. He adopts the definitive elements of Prof. Bruhns for 1846, with a small correction to the mean motion indicated by the observations at the comet's reappearance in 1868, and calculates backward with great care the perturbations of Mercury, Venus, the Earth, Mars, Jupiter, and Saturn to 1842, July 16·5, when the distance from Jupiter was 0·305; the total perturbations in the interval 1846, February 25·5—1842, July 16·5 are as follows:—Mean anomaly, − 1° 58′ 32″·6; mean sidereal motion, + 4″·391; longitude of perihelion, + 9′ 52″·8; ascending node, + 24′ 35″·4; inclination, + 1° 48′ 31″·4; angle of eccentricity, + 56′ 30″·0. From the ecliptical co-ordinates of the comet with respect to Jupiter at the latter date and the variations of these relative co-ordinates, the hyperbolic elements of the orbit about the planet are obtained and the perijove is found to have taken place May 27·28488 M.T. at Berlin, when the distance was 0·054714. The hyperbolic elements are assumed to 1842, April 7·5, when the distance between comet and planet was 0·30334, and the radius of the sphere of attraction 0·27149. The elements are then again referred to the sun, and thus the following figures defining the comet's orbit before this near approach to Jupiter, result:—

Epoch, 1842, April 7·5 Berlin M.T.

Mean anomaly	135° 0′ 58″·0	
Longitude of perihelion	111 50 20·6	1846·0
,, ,, ascending node ...	103 42 12·8	
Inclination...	46 18 57·4	
Angle of eccentricity	49 32 10·0	
Mean daily motion	686″·253	
Log. semi axis major	0·4756809	
Perihelion distance	0·7151810	

The only very striking difference from D'Arrest's figures, which were confessedly a rough approximation, is in the perihelion

distance, which, as will be seen, is found to be much smaller, indeed not one-half as great, by Herr Harzer.

The author of this very able dissertation remarks upon the similarity of the elements he has deduced for Brorsen's comet before the near approach to Jupiter, to those of the first comet of 1798, discovered by Messier on April 12 and observed by him till May 24; this comet was computed by Burckhardt and Olbers. Herr Harzer finds, however, that it is not probable Messier's observations will admit of an orbit widely different from a parabola. He considers there is reason to conclude that the orbit of 1842 was impressed upon the comet by a close approach to Jupiter in 1759-60, and that another change may be similarly produced in 1937, as hinted by D'Arrest.

HERSCHEL'S FIRST OBSERVATION OF URANUS.—We are now close upon the centenary of the discovery of Uranus on March 13, 1781. Perhaps some readers may be interested in the following examination of the first evening's measures of distance and angle of position from a small star, with which Herschel compared the planet till March 21. In his "Account of a Comet," for as such the planet was announced in a communication to the Royal Society read on April 26, he gives the distance from the small star "2′ 48″ by pretty exact estimation true to 20″," and the angle "0° 0′ by superficial estimation, liable to an error of 10° or 12°," this angle corresponding in our present system of double-star measures to 270°, or preceding on the parallel: this distance and angle are for 10h. 30m. at Bath.

By Prof. Newcomb's pretty accurate "provisional theory," we find the place of Uranus for 1781, March 13, at 10h. 30m. M.T. at Bath, or 10h. 39m. 20s. Greenwich M.T., to be as follows:—True R.A. 5h. 35m. 47·77s., true Decl. +23° 32′ 58″·3, and the corrections to apparent place are −0·32s. and −0″·2; the log. distance of the planet from the earth being 1·27742. It is clear from this that Herschel's star, which he calls *a*, is No. 1576 in Rümker's Catalogue (the first impression of 0h.−6h.), where it is estimated a tenth magnitude: Argelander in the *Durchmusterung* has 9·0. The mean place accurately carried back to 1781·0 was—

R.A. 5h. 36m. 0·85s. Decl. + 23° 32′ 3″·7.

For this date and hour we find, in the notation of the *Nautical Almanac*—

Log A. −1·2709. Log B. + 0·3473. Log C. +7·7110.
Log D. −0·8971.

Whence the apparent place of the star was—

R.A. 5h. 36m. 0·84s. Decl. + 23° 32′ 11″·6.

Consequently the calculated distance of planet from star is 3′ 10″·2, and the angle of position 284°·2, agreeing as nearly with Herschel's estimates as under the circumstances can be expected. At his next observation on March 17 the distance by observation was 42″; the computed distance 54″.

GEOGRAPHICAL NOTES

THE last meeting of the Russian Geographical Society was very animated, owing to the presence of Prof. Nordenskjöld. The great hall of the Society was crowded, and the explorer of the northern seas was greeted with loud cheers. The president of the Society, M. Semenoff, opened the meeting with a speech of welcome in which he sketched the long series of expeditions undertaken from Europe to Siberia since the year 1553, when Willoughby directed his three ships to the White Sea, and paid for his undertaking with his life. Prof. Nordenskjöld replied in a short speech, referring to the expeditions which will start next spring for the exploration of the Siberian shores; and Prof. Lentz made a communication on Polar meteorological stations and on their importance for science.

ORENBURG was the first town which enjoyed the pleasure of hearing the story of Col. Prjevalsky's journey told by himself. On his passage through this town, on January 2, the traveller gave a lecture on the adventures of his journey to Tibet, which we have already told. From Orenburg M. Prjevalsky started to visit his relations at Smolensk, whence he proceeded to St. Petersburg, reaching it at the same time as his companions and his collections, which were at the beginning of January on their way from Orsk to Orenburg.

DR. LENZ, the German traveller who lately accomplished the feat of reaching Timbuctoo from the north, has arrived at Bordeaux, and is expected at Berlin soon to give an account of his explorations.

THERE are at present sixty-five geographical Societies in the world. The oldest of these is that of Paris, founded 1821; there is also a Society of Commercial Geography at Paris, founded 1873. Besides these France has geographical societies at Lyons, Bordeaux, Marseilles, Montpellier, Rouen, Nancy, Bergerac, Périgueux, Rochefort, Mont-de-Marsan, Agen, Apinal, Rochelle, Douai, Dunkirk, St. Omer, Lille; and one is about to be founded at Bar-le-Duc. The Berlin Geographical Society was founded in 1828, besides which Germany has similar societies at Frankfort, Darmstadt, Leipsic, Dresden, Munich, Bremen, Halle, Hamburg, Friberg, Metz, Hanover; other societies are in formation at Halberstadt, Magdeburg, and Jena. The London Geographical Society, the only one in England, was founded in 1830. The next oldest society (after Frankfort) is that of Rio Janeiro, founded 1838; then Mexico, 1839; St. Petersburg, 1845; in Russia there are besides—societies at Tiflis, Irkutsk, Vilna, Orenburg, Omsk. The other societies are those of the Hague, 1851; New York, 1852; Vienna, 1856; Geneva, 1858; Rome, 1867; Buda-Pesth, 1872; Amsterdam, 1873; Bucharest, 1875; Lisbon, 1875; Madrid, Antwerp, Brussels, Copenhagen, Lima, all 1876; Stockholm and Quebec, 1877; St. Gall, Berne, Oran, 1878; Tokio, 1879; Buenos Ayres, Algiers, and Oporto, 1880.

THE Hamburg firm of C. Woermann has sent Mr. Hermann Soyaux to the French colony of Gaboon in order to try to cultivate the coffee-tree of Liberia at that place. Soyaux has now been at Gaboon for two years, and has there established the Scibomge farm, which is situated about a day's march inland from the Gaboon River, on the Awandu River, which flows in a north-easterly direction into the Bay of Corisco. He now employs some 100 negroes. Many thousand coffee-trees have been imported from Liberia, and have been planted, and experiments have also been made with sowing the beans, so that at the beginning of 1882 the first coffee-harvest is confidently expected. The Hamburg firm supports the undertaking in a most efficient manner by sending engines, implements, &c., and experiments are also pending to introduce and acclimatise horses and mules. Mr. Soyaux makes meteorological observations for the Leipsic Observatory and natural history collections for the Hamburg Museum.

IN the current number of *Les Missions Catholiques* we find appended to a letter from Mgr. Cluzel, the Apostolic Delegate in Persia, some notes on the Kurds, which are just now of considerable interest. These notes deal with the origin of the Kurds, their country, language, present condition, religion, manners and customs, &c.

THOUGH no doubt much geographical information respecting the Philippines may be obtained from Spanish works, there is but little readily accessible to the English reader. It may therefore be well to call attention to a useful *résumé* furnished by H.M.'s Consul at Manila in his commercial report for 1879. He gives some brief particulars respecting each of the twenty-one provinces into which the principal Island of Luzon is divided, and afterwards deals with some of the other chief islands. The interior of the Island of Mindoro, immediately south of Luzon, he tells us, is not explored, but is supposed to contain much mineral wealth. In the Visayan group much of the interior of Negros, Samar, and Paragua is likewise not explored. Capt. Pauli adds that the archipelago is believed to contain 1200 islands of all sizes. The report is accompanied by an outline map, on which the principal islands are shown, as well as the division of Luzon into provinces.

M. LUCERREAU, a member of the Paris Geographical Society, has been killed by natives on his exploring expedition in Eastern Africa. He had started from Aden in June last in order to reach the Upper Nile by crossing the territory inhabited by the Gallas Negroes.

THE *Bulletin* of the International Geographical Institute at Berne has with the new year begun a new series on a larger scale than the previous issue. In the first number the contents of previous issues are resumed, the chief novelty being a fine map of the South Polar regions, on linen, in connection with the proposed Italian expedition. We cannot yet see exactly what place this *Bulletin* fills in geographical journalism.

DEEP-SEA EXPLORATION[1]

THIS subject is one in which I have for many years taken much interest; and I will give you the result of my experience and studies. It is highly fascinating to all persons of ordinary intelligence, although they may not be naturalists. Our best poets have not disdained to sing its praises; one of them says,

> "There is a magnet-like attraction in
> These waters to the imaginative power
> That links the viewless with the visible,
> And pictures things unseen."

Speculations of this kind were not unknown to the ancients. In the "Halieutica" of Oppian, written nearly seventeen centuries ago, it is stated that no one had found the bottom of the sea, and that the greatest depth ascertained by man was 300 fathoms, where Amphitrite had been seen. But this grand discovery does not seem to have satisfied the poetical philosopher; and he enters into a long disquisition as to the many other wonderful things that may be concealed in the recesses of the boundless ocean, adding, nevertheless, what I will translate from the Greek:—

> "But men have little sense and strength."

However, man has not degenerated in this kind of knowledge since the days of Oppian; for he has now not only explored the greatest depths of the sea, but has mapped out its main features with nearly as much accuracy as he has done with respect to the land.

It will be more convenient to divide the subject into separate heads, viz.:—(1) Historical; (2) Apparatus; (3) Fauna; (4) Food; (5) Light; (6) Temperature; (7) Depth; (8) Inequalities of the Sea-bottom; (9) Deposits; (10) Geological; (11) Incidental; (12) Concluding Remarks.

I hope you will not be frightened at the number of these heads. Some of them you will find to be exceedingly short.

1. *Historical.*—Sir Wyville Thomson's "Depths of the Sea" gives an excellent account of the origin and progress of deep-sea exploration up to a very recent period. To this work I would refer my audience, contenting myself with some supplemental remarks.

In 1868 commenced the systematic examination of the sea-bed at considerable depths in that part of the North Atlantic which surrounds the British Isles. I then took my yacht, the *Osprey*, for another excursion to Shetland, and dredged off the most northern point of our isles. The greatest depth which I attained was 170 fathoms, or 1020 feet, each fathom being 6 feet. This depth, strictly speaking, is beyond the line of soundings, viz. 100 fathoms: and it may be a question whether the fauna of the sea-bed outside of that limit can be regarded as British, although adjacent to our coasts. If it be we ought to take the "medium filum aquæ" (as the lawyers in the time of Coke called it), and extend the geographical limit of the British marine fauna halfway across to North America! But such boundaries are neither national nor rational. We cannot lay claim to so extensive a dominion. International boundaries, for the purpose of naval warfare or as defined by fishery treaties, are limited to a distance of three miles, irrespective of depth. Later in the same year (1868) Dr. Carpenter and Prof. Wyville Thomson explored, in H.M. surveying-vessel *Lightning*, the sea-bed lying between the Butt of Lewis and the Faröe Isles, and reached the depth of 550 fathoms. These tentative excursions showed that the sea-bed everywhere was full of life, not merely of a microscopic and uniform kind, and of a low degree of organisation, but of a considerable size, great variety, and a high degree of organisation. In the following year (1869) our Government placed a better vessel at the disposal of the Royal Society; and I undertook the first scientific cruise in H.M. surveying-ship *Porcupine*. This cruise was off the western coast of Ireland, and the greatest depth dredged was 1476 fathoms. The second cruise was undertaken by Prof. Wyville Thomson, and extended from the south of Ireland to what is probably the deepest part of the North Atlantic in the European seas. The greatest depth dredged by him was 2435 fathoms, or nearly three miles. The third cruise, under the charge of Dr. Carpenter, was in the same direction as the *Lightning* expedition, but embraced a larger area, including the Shetland Isles; the greatest depth was 867 fathoms. In the following year (1870) the *Porcupine* was again placed at the disposal of the Royal Society for further exploration. This expedition was divided into two cruises, North Atlantic and Mediterranean. The former was assigned to me, and comprised the sea-bed lying between Falmouth and the Straits of Gibraltar, along the western coasts of Spain and Portugal. There were 38 dredging and sounding stations, at depths ranging from 81 to 1095 fathoms. The Mediterranean cruise was made by Dr. Carpenter, and extended round Sicily. There were 29 stations, at depths ranging from 51 to 1743 fathoms. Prof. Wyville Thomson was unfortunately prevented by illness from taking part in this year's expedition. In all these cruises an abundance as well as a great variety of marine life occurred at every depth.

The *Lightning* and *Porcupine* expeditions culminated in the celebrated voyage of H.M.S. *Challenger* round the world, which commenced on December 21, 1872, and ended on May 24, 1876, having thus occupied a period of three years and five months. During this expedition about 30,000 nautical miles were traversed, 504 soundings were taken, and 132 dredgings and 150 trawlings were made. The depths of soundings were from 25 to 4475, of dredgings from 4 to 3875, and of trawlings from 10 to 3050 fathoms. The greatest depth reached was five statute miles. The Americans have recorded a greater depth, viz. 5¼ miles, or 4620 fathoms. Even greater depths than this have been given; but they are not now considered reliable, by reason of the imperfect machinery which was formerly used for sounding.

The *Proceedings* of the Royal Society for 1873-1877 contain many "Preliminary Reports" by Sir Wyville Thomson and the other naturalists attached to the *Challenger* expedition; so that all the scientific world were from time to time kept informed of the progress and results of this great national undertaking.

During the last of our arctic voyages, in 1875, I had, through the influence and energy of the Royal Society, another opportunity of exploring a part of the North-Atlantic sea-bed which was not within the limits of the *Challenger* expedition; and I was intrusted with the scientific charge of the sounding and dredging conducted in H.M.S. *Valorous* between Bantry Bay and Hare Island in Davis Strait. This ship accompanied the *Alert* and *Discovery* on their way northwards. After a voyage of three months, which was rendered more eventful by a cyclonical storm and a partial shipwreck on the coast of Greenland, we succeeded in working sixteen stations, with depths of from 20 to 1785 fathoms. Here also, and even in the midst of icebergs, submarine life showed no diminution in number or extent.

To this short recital of our later expeditions I must not omit to add a notice of the valuable and suggestive researches which were accomplished under considerable difficulties by Dr. Wallich in H.M.S. *Bulldog* in 1860, while she was engaged in surveying the North-Atlantic sea-bed for the purpose of establishing telegraphic communication between this country and North America. The results of these researches were published in Dr. Wallich's important work, entitled "The North-Atlantic Sea-bed; comprising a Diary of the Voyage on board H.M.S. *Bulldog* in 1860, and observations on the presence of Animal Life, and the Formation and Nature of Organic Deposits at Great Depths in the Ocean." On the return voyage, about midway between Cape Farewell and Rockall, thirteen starfishes came up from a sounding of 1260 fathoms, "convulsively embracing a portion of the sounding-line which had been payed out in excess of the already ascertained depth, and rested for a sufficient period at the bottom to permit of their attaching themselves to it."

A short voyage in H.M.S. *Shearwater* through the Mediterranean in 1871 enabled Dr. Carpenter to have some dredging between Sicily and the northern coast of Africa, on the Adventure and Skerki Banks. This dredging was by no means unproductive; but the depths did not exceed 200 fathoms, which we are now inclined to call "shallow water"; Dr. Carpenter's word was "shallows." Fifty years ago such depths would have been regarded by naturalists as peculiarly "abyssal"!

The elaborate report of my lamented friend Prof. Edward Forbes, on the investigation of British Marine Zoology by means of the dredge, which he submitted to the British Association for the Advancement of Science in 1850, and to which I contributed as a humble fellow worker, was preceded by his equally valuable "Report on the Mollusca and Radiata of the Ægean Sea, and on their Distribution, considered as bearing on Geology." The last-mentioned Report was published by the Association in 1844. Forbes's conclusion that the sea-bottom at a depth of 300 fathoms is lifeless, because he found that life diminished gradually, and almost ceased when he dredged at 230 fathoms, has certainly been proved to be inaccurate as regards

[1] A Lecture by J. Gwyn Jeffreys, LL.D., F.R.S.

the ocean in general; but Dr. Carpenter, in his Report to the Royal Society on his biological researches in the Mediterranean during the *Shearwater* cruise, expresses his belief that "in the Mediterranean basin the existence of animal life in any abundance at a depth greater than 200 fathoms will be found quite exceptional"; and he infers "that Edward Forbes was quite justified in the conclusion he drew *as regards the particular locality he had investigated*, and that his only mistake lay in supposing that the same conditions would prevail in the open ocean." But this eminent naturalist and physiologist, Dr. Carpenter, to whose opinions on such subjects all respect is due, admits that "the history of science is full of instances in which erroneous doctrines have been more *productive*, because more suggestive, than well-determined facts that open no access to the unknown beyond." With the greatest deference to Dr. Carpenter's opinion that animal life is scanty in the depths of the Mediterranean, I venture to point out that very little had previously been done to investigate the fauna of that sea beyond the shores and shallow water to the extent which Forbes reached, viz. 230 fathoms.

Admiral Spratt in 1846 dredged, at a depth of 310 fathoms, 40 miles east of Malta, a number of living Mollusca, which I examined and found to be identical with species which I dredged at considerable depths in the North Atlantic during the *Porcupine* expeditions. Again, during the Mediterranean cruise of 1870 in the *Porcupine*, no fewer than 14 species of Mollusca (also Atlantic), besides a pelagic or surface-water species and a small freshwater shell, which must have been carried out to sea by some river or stream, occurred at a depth of 1415 fathoms, between the coasts of North Africa and Spain. All these species were recent, and some were living, although most of them were known to me as also belonging to the Pliocene formation in Sicily. However, we shall in all probability know a great deal more of this matter if our good neighbours the French are able to carry out their idea of extending their investigation of the deep sea near their own coasts by another dredging and sounding cruise off Marseilles or Toulon.

During the early part of the summer in the present year (1880) our Admiralty placed at the disposal of Sir Wyville Thomson H.M. surveying-vessel *Knight Errant* for a cruise off the Butt of Lewis, in prosecution of his researches in the *Lightning* Expedition as to the "warm" and "cold" areas which were noticed in the Report of that expedition. Mr. Murray took the scientific charge of the cruise; but the weather was boisterous, and unfavourable for dredging and trawling. There were, however, some zoological results of an interesting kind, especially as regards the Mollusca; and it is hoped that the application which has now been made by the Royal Society for another Government vessel will be successful, and will enable Sir Wyville to continue the work and make further discoveries.

Although we have of late years done a great deal to promote submarine researches, as shown by the expeditions of H.M.SS. *Bulldog*, *Lightning*, *Porcupine*, *Shearwater*, *Valorous*, and *Knight Errant*, our comparatively poor neighbours in Scandinavia have been earlier in the field and not less energetic. From the "Notices sur la Suède," published on the occasion of the International Congress of Geographical Sciences in 1875 at Paris, it appears that between the years 1837 and 1875 seventeen scientific expeditions were made from Sweden, fifteen of which explored the Arctic regions. Professors Lovén, Torell, and Nordenskjöld, with other distinguished naturalists, took an active part in these expeditions. The sister kingdom of Norway has since engaged in the same course of discovery; and a well-equipped Government vessel, the *Vöringen*, of the same size as the *Porcupine* (about 400 tons), left Bergen in the beginning of June, 1876. Dr. Danielssen, Professors Mohn and G. O. Sars, Herr Friele, and other scientific men accompanied the vessel, and were engaged in the zoological and physical work. Through the kindness of my friend Prof. Sars I am enabled to give the following particulars of these Norwegian expeditions:—They occupied nearly three months in each of the years 1876, 1877, and 1878. The first expedition was divided into three cruises, and extended along the western coast of Norway to the Faröe Isles and Iceland. There were 24 dredging-stations, at depths of from 90 to 1862 fathoms, besides 5 shore stations in Norway, Faröe, and Iceland. The second expedition was divided into four cruises, and extended from Bergen to outside the Loffoden Isles, and from Tromsö to Jan Mayen; there were 28 stations, with depths of from 70 to 1760 fathoms, besides 6 shore stations in Norway and Jan Mayen. The third expedition was divided into three cruises, and extended to Vardö, and thence westward to Beeren Island, and afterwards to Spitzbergen in 80° N. lat. The last expedition had 36 stations, with depths of from 21 to 1686 fathoms, besides 7 shore stations on the Arctic coasts of Norway, and in Beeren Island and Spitzbergen.

The United States have prosecuted this kind of research with their well-known activity and perseverance. From 1867 to the autumn of 1880 four Government steamers have been continuously employed in surveying the seas which border the coasts of Central and South America. Several hundred stations were investigated, at depths ranging from 6 to 2412 fathoms. Count Pourtales, Prof. Agassiz, and his no less eminent son, have been successively in charge of the scientific department. The results are both extensive and invaluable. In 1871 I was invited by the late Prof. Agassiz to pay him a visit and examine the Mollusca which had been procured during the previous years. The collection was in the custody of the late Prof. Stimpson at Chicago. It was extremely interesting to me, in connection with the expeditions of the *Lightning* and *Porcupine*. I examined the collection in the Museum at Chicago; and, at the request of Prof. Agassiz, I took home with me several of the shells for comparison with my own. On my return to England, after enjoying the kind hospitality of my scientific friends in the United States and Canada, I learnt that Chicago had been utterly burnt down; and I was fortunately enabled to restore the shells, which were the only specimens of natural history that had been saved from the fire. Through the kindness of Prof. Spencer Baird, I had, during this visit to America, an opportunity of joining in a dredging-excursion on the coast of New England, which was conducted under the auspices of the Fishery Commission.

Like a giant refreshed, France has awakened from a rather long sleep, and, with its accustomed spirit, has now rivalled all other nations in deep-sea work. Last summer a scientific commission was appointed, with the venerable Prof. Milne-Edwards as its president; and a large and well-equipped Government steamer, the *Travailleur*, explored the Bay of Biscay with most favourable results. I was obligingly asked to take part in this expedition; and I gave an account of it at the last meeting of the British Association at Swansea, which is published in the Report of that meeting.

Austria, Germany, and Holland have also not been last in the race of maritime voyages, although they have not contributed much to our knowledge of deep-sea life.

The harvest reaped in all the above-mentioned expeditions was most abundant and valuable.

But after all it must be borne in mind that if every civilised nation in the world were every year, during the next century, to send out similar expeditions, with improved appliances, for exploring the sea-bed, the field would be far from being exhausted. Every such expedition must be more or less tentative, and can only form the basis for a more complete investigation of "the deep bosom of the ocean." The area of investigation must be measured by many millions of square leagues; whereas all that has hitherto been effected has been to scrape in an imperfect manner the surface of a few scores of acres.

I here exhibit charts to show the tracks of the expeditions in which I have been personally engaged, as well as those of the *Challenger* and Norwegian expeditions.

2. *Apparatus.*—The sounding-line, ropes, dredge, trawl, tangles, towing-net, sieves, accumulators, steam-engines, and other contrivances for deep-sea exploration have been so fully described and illustrated in the "Depths of the Sea" and Capt. Sigsbee's "Deep-sea Sounding and Dredging," that it is unnecessary for me to do more than mention those books. The latest improvements consist in the substitution of steel-wire for line in sounding, and of galvanised wire-rope for hempen rope in dredging and trawling. Capt. Sigsbee's new towing-net for ascertaining whether floating or swimming animals are found in any zone or belt of water lying between the surface and the bottom will be hereafter noticed. It is still a desideratum to invent a dredge for deep-sea work which shall scrape the surface instead of sinking into the ooze or mud.

3. *Fauna.*—This word is used by naturalists to denote animal life in contradistinction to "Flora" or vegetable life. All the recent exploring expeditions have established the fact that animal life of various kinds abounds everywhere in the deepest parts of the ocean. Nor is such life microscopic or minute only. In the *Challenger* voyage was procured by the trawl, at the depth

of 1600 fathoms, in the South Atlantic (S. lat. 46° 16′, E. long. 48° 27′), a living specimen of a magnificent shell belonging to *Cymbium*, or an allied genus, which is 6¾ inches long and 4 inches broad! I dredged other Mollusca from an inch and a half to nearly double that length in the *Porcupine* and *Valorous* expeditions. Willemöes Suhm mentions among the *Challenger* discoveries a gigantic crustacean or sea-spider from 1375 fathoms, which measured nearly two feet across the legs.

Sir Wyville Thomson gives an eloquent description of life in the deep sea, when he says that the latter "is inhabited by a fauna more rich and varied on account of the enormous extent of the area, and with the organisms in many cases apparently even more elaborately and delicately formed, and more exquisitely beautiful in their soft shades of colouring, and in the rainbow tints of their wonderful phosphorescence, than the fauna of the well-known belt of shallow water teeming with innumerable invertebrate forms which fringes the land. And the forms of these hitherto unknown living beings, and their mode of life, and their relations to other organisms whether living or extinct, and the phenomena and laws of their geographical distribution, must be worked out."

It was formerly supposed that animals could not exist at great depths because of the great pressure to which they were subjected. Mr. Moseley says[1] "the pressure exerted by the water at great depths is enormous, and almost beyond comprehension. It amounts roughly to a ton weight on the square inch for every 1000 fathoms of depth; so that, at the depth of 2500 fathoms, there is a pressure of two tons and a half per square inch of surface, which may be contrasted with the fifteen pounds per square inch pressure to which we are accustomed at the level of the sea." But it must be recollected that water is nearly incompressible, and that marine animals which are surrounded by such a fluid, and are to a certain extent filled with it, would not necessarily be inconvenienced by the superincumbent weight.

Animals from great or even from what may be considered moderate depths are always brought up dead, the cause of death being unknown. This is another problem worthy of being worked out.

The migration or distribution of marine animals throughout the open sea is quite free, and is unobstructed only by great or abrupt changes of level in the bed of the ocean, which operate as barriers. Even animals of a fixed or sedentary nature in their earliest state of growth swim on the surface, and are therefore unchecked in their onward course by any submarine barrier.

The doubt whether any life exists in the intermediate space or zone which lies between that of the surface and that of the bottom of the deep sea has now, I believe, been set at rest. The naturalists in the *Josephine* expedition believed that this intermediate zone is lifeless; and Sir Wyville Thomson seems to have been of the same opinion. The towing-net adopted by Mr. Murray in the *Challenger* expedition for such researches was to some extent successful; but Capt. Sigsbee, of the U.S. Coast-Survey steamer *Blake*, invented a cylinder or machine, called the "gravitating trap," which completely answered the purpose of collecting at any particular depth the animals which occurred there. Prof. Alexander Agassiz, in his communication to the Superintendent of the Survey made last August, and now published, records the experiments thus made, and says that they "appear to prove conclusively that the surface-fauna of the sea is really limited to a comparatively narrow belt in depth, and that there is no intermediate belt, so to speak, of animal life between those living on the bottom, or close to it, and the surface pelagic fauna."

I am not aware that any deep-sea animals adopt or avail themselves of the same means that oceanic or land animals use for purposes of protection and concealment, chiefly by coloration or by what has been termed "mimicry." Many cases of this kind are known to occur in birds, fishes, mollusks, *Salpæ*, insects, crabs, shrimps, and worms.

None of the animals whose remains are found in geological formations older than the Pliocene or latest of the Tertiary strata have yet been detected in any exploring expedition. The late Prof. Agassiz and Sir Wyville Thomson were disappointed in their enthusiastic expectation of finding Ammonites, Belemnites, and other Old-World fossils in a living state. I have dredged Miocene fossils on the coasts of Guernsey and Portugal, the latter at considerable depths; but they were petrifactions, and must have come from some fossiliferous formation in the adjacent land, or perhaps in the sea-bed.

[1] "Notes of a Naturalist on the *Challenger*."

Sir Wyville Thomson, in his "Report of the Scientific Results of the Voyage of H.M.S. *Challenger*," has expressed his opinion as to the doctrine of evolution, that "in this, as in all cases in which it has been possible to bring the question, however remotely, to the test of observation, the character of the abyssal fauna refuses to give the least support to the theory which refers the evolution of species to extreme variation guided only by natural selection." I cannot understand how either "natural selection" or "sexual selection" can affect marine invertebrate animals, which have no occasion to struggle for their existence and have no distinction of sex.

(*To be continued.*)

THE RELATION BETWEEN ELECTRICITY AND LIGHT.[1]

EVER since the subject on which I have the honour to speak to you to-night was arranged, I have been astonished at my own audacity in proposing to deal in the course of sixty minutes with a subject so gigantic and so profound that a course of sixty lectures would be quite inadequate for its thorough and exhaustive treatment.

I must indeed confine myself carefully to some few of the typical and most salient points in the relation between electricity and light, and I must economise time by plunging at once into the middle of the matter without further preliminaries.

Now when a person is setting off to discuss the relation between electricity and light it is very natural and very proper to pull him up short with the two questions: What do you mean by electricity? and What do you mean by light? These two questions I intend to try briefly to answer. And here let me observe that in answering these fundamental questions I do not necessarily assume a fundamental ignorance on your part of these two agents, but rather the contrary; and must beg you to remember that if I repeat well-known and simple experiments before you, it is for the purpose of directing attention to their real meaning and significance, not to their obvious and superficial characteristics: in the same way that I might repeat the exceedingly familiar experiment of dropping a stone to the earth if we were going to define what we meant by gravitation.

Now then we will ask first, What is Electricity? and the simple answer must be, We don't know. Well, but this need not necessarily be depressing. If the same question were asked about Matter, or about Energy, we should have likewise to reply, No one knows.

But then the term Matter is a very general one, and so is the term Energy. They are heads, in fact, under which we classify more special phenomena.

Thus if we were asked what is sulphur, or what is selenium, we should at least be able to reply, A form of matter; and then proceed to describe its properties, *i.e.* how it affected our bodies and other bodies.

Again, to the question, What is heat? we can reply, A form of energy; and proceed to describe the peculiarities which distinguish it from other forms of energy.

But to the question, What is electricity? we have no answer pat like this. We cannot assert that it is a form of matter, neither can we deny it; on the other hand, we certainly cannot assert that it is a form of energy, and I should be disposed to deny it. It may be that electricity is an entity *per se*, just as matter is an entity *per se*.

Nevertheless I can tell you what I mean by electricity by appealing to its known behaviour.

Here is a battery, that is, an electricity pump: it will drive electricity along. Prof. Ayrton is going, I am afraid, to tell you, on the 20th of January next, that it *produces* electricity; but if he does, I hope you will remember that that is exactly what neither it nor anything else can do. It is as impossible to generate electricity in the sense I am trying to give the word, as it is to produce matter. Of course I need hardly say that Prof. Ayrton knows this perfectly well; it is merely a question of words, *i.e.* of what you understand by the word electricity.

I want you then to regard this battery and all electrical machines and batteries as kinds of electricity pumps, which drive the electricity along through the wire very much as a water-pump can drive water along pipes. While this is going on the wire manifests a whole series of properties, which are called the properties of the current.

[1] A lecture by Dr. O. J. Lodge, delivered at the London Institution on December 16, 1880.

[Here were shown an ignited platinum wire, the electric arc between two carbons, an electric machine spark, an induction-coil spark, and a vacuum tube glow. Also a large nail was magnetised by being wrapped in the current, and two helices were suspended and seen to direct and attract each other.]

To make a magnet, then, we only need a current of electricity flowing round and round in a whirl. A vortex or whirlpool of electricity is in fact a magnet; and *vice versâ*. And these whirls have the power of directing and attracting other previously existing whirls according to certain laws, called the laws of magnetism. And, moreover, they have the power of exciting fresh whirls in neighbouring conductors, and of repelling them according to the laws of diamagnetism. The theory of the actions is known; though the nature of the whirls, as of the simple stream of electricity, is at present unknown.

[Here was shown a large electro-magnet and an induction-coil vacuum discharge spinning round and round when placed in its field.]

So much for what happens when electricity is made to travel along conductors, *i.e.* when it travels along like a stream of water in a pipe, or spins round and round like a whirlpool.

But there is another set of phenomena, usually regarded as distinct, and of another order, but which are not so distinct as they appear, which manifest themselves when you join the pump to a piece of glass or any non-conductor and try to force the electricity through that. You succeed in driving some through, but the flow is no longer like that of water in an open pipe; it is as if the pipe were completely obstructed by a number of elastic partitions, or diaphragms. The water cannot move without straining and bending these diaphragms, and if you allow it, these strained partitions will recover themselves and drive the water back again. [Here was explained the process of charging a Leyden jar.] The essential thing to remember is that we may have electrical energy in two forms, the static and the kinetic; and it is therefore also possible to have the rapid alternation from one of these forms to the other, called vibration.

Now we will pass to the second question: What do you mean by light? And the first and obvious answer is, Everybody knows. And everybody that is not blind does know to a certain extent. We have a special sense-organ for appreciating light, whereas we have none for electricity. Nevertheless, we must admit that we really know very little about the intimate nature of light—very little more than about electricity. But we do know this, that light is a form of energy; and, moreover, that it is energy rapidly alternating between the static and the kinetic forms—that it is, in fact, a special kind of energy of vibration. We are absolutely certain that light is a periodic disturbance in some medium, periodic both in space and time: that is to say, the same appearances regularly recur at certain equal intervals of distance at the same time, and also present themselves at equal intervals of time at the same place; that in fact it belongs to the class of motions called by mathematicians undulatory or wave motions. The wave motion in this model (Powell's wave apparatus) results from the simple up-and-down motion popularly associated with the term *wave*. But when a mathematician calls a thing a wave he means that the disturbance is represented by a certain general type of formula, not that it is an up-and-down motion, or that it looks at all like those things on the top of the sea. The motion of the surface of the sea falls within that formula, and hence is a special variety of wave motion, and the term wave has acquired in popular use this signification and nothing else. So that when one speaks ordinarily of a wave or undulatory motion one immediately thinks of something heaving up and down, or even perhaps of something breaking on the shore. But when we assert that the form of energy called light is *undulatory*, we by no means intend to assert that anything whatever is moving up and down, or that the motion, if we could see it, would be anything at all like what we are accustomed to in the ocean. The kind of motion is unknown; we are not even sure that there is anything like motion in the ordinary sense of the word at all.

Now how much connection between electricity and light have we perceived in this glance into their natures? Not much truly. It amounts to about this: That on the one hand electrical energy may exist in either of two forms—the static form, when insulators are electrically strained by having had electricity driven partially through them (as in the Leyden jar), which strain is a form of energy because of the tendency to discharge and do work; and the kinetic form, where electricity is moving bodily along through conductors or whirling round and round inside them, which motion of electricity is a form of energy, because the conductors and whirls can attract or repel each other and thereby do work.

And, on the other hand, that light is the rapid alternation of energy from one of these forms to the other—the static form where the medium is strained, to the kinetic form when it moves. It is just conceivable then that the static form of the energy of light is *electro*-static, that is, that the medium is *electrically* strained, and that the kinetic form of the energy of light is *electro*-kinetic, that is, that the motion is not ordinary motion, but electrical motion—in fact that light is an electrical vibration, not a material one.

On November 5 last year there died at Cambridge a man in the full vigour of his faculties—such faculties as do not appear many times in a century—whose chief work has been the establishment of this very fact, the discovery of the link connecting light and electricity; and the proof—for I believe it amounts to a proof—that they are different manifestations of one and the same class of phenomena—that light is, in fact, an electro-magnetic disturbance. The premature death of James Clerk Maxwell is a loss to science which appears at present utterly irreparable, for he was engaged in researches that no other man can hope as yet adequately to grasp and follow out; but fortunately it did not occur till he had published his book on "Electricity and Magnetism," one of those immortal productions which exalt one's idea of the mind of man, and which has been mentioned by competent critics in the same breath as the "Principia" itself.

But it is not perfect like the "Principia"; much of it is rough-hewn, and requires to be thoroughly worked out. It contains numerous misprints and errata, and part of the second volume is so difficult as to be almost unintelligible. Some, in fact, consists of notes written for private use, and not intended for publication. It seems next to impossible now to mature a work silently for twenty or thirty years, as was done by Newton two and a half centuries ago. But a second edition was preparing, and much might have been improved in form if life had been spared to the illustrious author.

The main proof of the electro-magnetic theory of light is this. The rate at which light travels has been measured many times, and is pretty well known. The rate at which an electro-magnetic wave disturbance would travel if such could be generated (and Mr. Fitzgerald of Dublin thinks he has proved that it cannot be generated directly by any known electrical means) can be also determined by calculation from electrical measurements. The two velocities agree exactly. This is the great physical constant known as the ratio V, which so many physicists have been measuring, and are likely to be measuring for some time to come.

Many and brilliant as were Maxwell's discoveries, not only in electricity, but also in the theory of the nature of gases, and in molecular science generally, I cannot help thinking that if one of them is more striking and more full of future significance than the rest, it is the one I have just mentioned—the theory that light is an electrical phenomenon.

The first glimpse of this splendid generalisation was caught in 1845, five and thirty years ago, by that prince of pure experimentalists, Michael Faraday. His reasons for suspecting some connection between electricity and light are not clear to us—in fact they could not have been clear to him; but he seems to have felt a conviction that if he only tried long enough, and sent all kinds of rays of light in all possible directions across electric and magnetic fields in all sorts of media, he must ultimately hit upon something. Well, this is very nearly what he did. With a sublime patience and perseverance which remind one of the way Kepler hunted down guess after guess in a different field of research, Faraday combined electricity, or magnetism, and light in all manner of ways, and at last he was rewarded with a result. And a most out-of-the-way result it seemed. First you have to get a most powerful magnet and very strongly excite it; then you have to pierce its two poles with holes, in order that a beam of light may travel from one to the other along the lines of force; then, as ordinary light is no good, you must get a beam of plane polarised light and send it between the poles. But still no result is obtained until, finally, you interpose a piece of a rare and out-of-the-way material which Faraday had himself discovered and made, a kind of glass which contains borate of lead, and which is very heavy, or dense, and which must be perfectly annealed.

And now, when all these arrangements are completed, what is

seen is simply this, that if an analyser is arranged to stop the light and make the field quite dark before the magnet is excited, then directly the battery is connected and the magnet called into action a faint and barely perceptible brightening of the field occurs; which will disappear if the analyser be slightly rotated. [The experiment was then shown.] Now no wonder that no one understood this result. Faraday himself did not understand it at all: he seems to have thought that the magnetic lines of force were rendered luminous, or that the light was magnetised; in fact he was in a fog, and had no idea of its real significance. Nor had any one. Continental philosophers experienced some difficulty and several failures before they were able to repeat the experiment. It was in fact discovered too soon, and before the scientific world was ready to receive it, and it was reserved for Sir William Thomson briefly, but very clearly, to point out, and for Clerk Maxwell more fully to develop, its most important consequences. [The principle of the experiment was then illustrated by the aid of a mechanical model.]

This is the fundamental experiment on which Clerk Maxwell's theory of light is based; but of late years many fresh facts and relations between electricity and light have been discovered, and at the present time they are tumbling in in great numbers.

It was found by Faraday that many other transparent media besides heavy glass would show the phenomenon if placed between the poles, only in a less degree; and the very important observation that air itself exhibits the same phenomenon, though to an exceedingly small extent, has just been made by Kundt and Röntgen in Germany.

Dr. Kerr of Glasgow has extended the result to opaque bodies, and has shown that if light be passed through magnetised *iron* its plane is rotated. The film of iron must be exceedingly thin, because of its opacity, and hence, though the intrinsic rotating power of iron is undoubtedly very great, the observed rotation is exceedingly small and difficult to observe; and it is only by very remarkable patience and care and ingenuity that Dr. Kerr has obtained his result. Mr. Fitzgerald of Dublin has examined the question mathematically, and has shown that Maxwell's theory would have enabled Dr. Kerr's result to be predicted.

Another requirement of the theory is that bodies which are transparent to light must be insulators or non-conductors of electricity, and that conductors of electricity are necessarily opaque to light. Simple observation amply confirms this; metals are the best conductors, and are the most opaque bodies known. Insulators such as glass and crystals are transparent whenever they are sufficiently homogeneous, and the very remarkable researches of Prof. Graham Bell in the last few months have shown that even *ebonite*, one of the most opaque insulators to ordinary vision, is certainly transparent to some kinds of radiation, and transparent to no small degree.

[The reason why transparent bodies must insulate, and why conductors must be opaque, was here illustrated by mechanical models.]

A further consequence of the theory is that the velocity of light in a transparent medium will be affected by its electrical strain constant; in other words, that its refractive index will bear some close but not yet quite ascertained relation to its specific inductive capacity. Experiment has partially confirmed this, but the confirmation is as yet very incomplete. But there are a number of results not predicted by theory, and whose connection with the theory is not clearly made out. We have the fact that light falling on the platinum electrode of a voltameter generates a current, first observed, I think, by Sir W. R. Grove at any rate it is mentioned in his "Correlation of Forces"—extended by Becquerel and Robert Sabine to other substances, and now being extended to fluorescent and other bodies by Prof. Minchin. And finally—for I must be brief—we have the remarkable action of light on selenium. This fact was discovered accidentally by an assistant in the laboratory of Mr. Willoughby Smith, who noticed that a piece of selenium conducted electricity very much better when light was falling upon it than when it was in the dark. The light of a candle is sufficient, and instantaneously brings down the resistance to something like one-fifth of its original value.

I could show you these effects, but there is not much to see; it is an intensely interesting phenomenon, but its external manifestation is not striking—any more than Faraday's heavy glass experiment was.

This is the phenomenon which, as you know, has been utilised by Prof. Graham Bell in that most ingenious and striking invention, the photophone. By the kindness of Prof. Silvanus Thompson I have a few slides to show the principle of the invention, and Mr. Shelford Bidwell has been good enough to lend me his home-made photophone, which answers exceedingly well for short distances.

I have now trespassed long enough upon your patience, but I must just allude to what may very likely be the next striking popular discovery, and that is the transmission of light by electricity; I mean the transmission of such things as views and pictures by means of the electric wire. It has not yet been done, but it seems already theoretically possible, and it may very soon be practically accomplished.

ENDOWMENT OF RESEARCH IN BIRMINGHAM

THE President of the Birmingham Philosophical Society, Dr. Heslop, recently gave an address to the members, taking for his subject the "Scientific Situation in Birmingham." Having reviewed the various local agencies set up during the past year for the diffusion of knowledge, including the opening of Mason's Science College, he went on to say: I must now allude to the most important work undertaken by the Society, the establishment of the fund for the endowment of research. This action has received warm support in many quarters, and has in fact done more to place it in a favourable light before the country than any previous circumstances. Although the efforts made to raise this fund have been inconsiderable, yet nearly 100*l.* in annual subscriptions, of varying dates, and 900*l.* in donations have been obtained. The Council have invested 600*l.* in order to ensure the permanence of the fund. It is probable that some slight additions may be made to this sum, having the same object in view; but it is, I believe, their intention to recommend the Society to spend the whole income, howsoever derived, in annual grants to persons living in this town or neighbourhood who devote themselves wholly or in part to science research. It is an error to suppose that this fund is to be allotted either to any particular individual or specially to members of this Society. The Council are free to do what they deem best with the money intrusted to them, within the limits of the scheme agreed upon. There is another temporary limit to their powers. One eminent investigator (Dr. Gore) is allotted a certain sum for a certain period. The approval of this step evinced by those who have contributed to the fund, and by others, has been a source of satisfaction to the Council.

I wish now to remind you that the scheme in connection with this subject declares that "the Council are of opinion that this Society would be omitting a principal means of the advancement of science—the end for which all such associations exist—if it neglected the question of the endowment of research. To maintain a successful investigator in his labours, even though no results of immediate or obvious utility can be shown to spring out of them, is of interest to the community at large." It may be that you will pronounce these words to be truisms scarcely requiring formal enunciation. The fact is that though the sense of them has been repeatedly given to the public in late years, practical action has not ensued. Everybody is telling his neighbour what a good thing it would be if men endowed with an aptitude for research into the facts of nature were also endowed with the means of living during their work. The speaker and the listener go by on the other side, and no good Samaritan tenders help to the well-praised searcher after truth. Nay, Mr. Mark Pattison affirms in his late book on Milton that "the England of our day has decided against the endowment of science," and seems to think that the principle on which the decision is based may be wrong, but "is not unreasonable." But the endowment of ministers of science stands on quite another foundation from that of ministers of religion. "To assign a place with a salary," says Mr. Pattison, "is to offer a pecuniary inducement to simulate" the qualification, *i.e.* a state of grace. But in the case of science there is no question of place, and the endowment is offered, not to those who promise much, but to those who have already performed something; not to those who imagine themselves to be in the requisite spiritual state, but to those who, working for an audience, select though few, have demonstrated that they are touched by the divine fire which burns not for other men.

* In the opinion of others the only practicable mode of dealing with this question is by bestowing adequate funds on teachers, and by placing them in favourable conditions for research.

The necessity for making provision for the devotion of fit men to scientific work has occurred to many, and doubtless private generosity has often enabled such men to prosecute labours by which the world has greatly gained. One of the most striking instances is that of Priestley. His own remarks contained in his diary are full of interest. He says that Dr. Fothergill "having observed that many of my experiments had not been carried to their proper extent on account of the expense that would have attended them," proposed a subscription from himself and some of his friends, and named 100*l.* per annum. He consented to receive 40*l.*, which was regularly paid to him, three other gentlemen aiding. Afterwards for good reasons Fothergill proposed "an enlargement of the allowance for my experiments, and likewise for my maintenance, *without being under the necessity of giving my time to pupils*, which I must otherwise have done." This was accepted, as Priestley preferred it to any pension from the Court. He gives a minute list of the numerous donations, legacies (one of 2000*l.*) and subscriptions given to him, while he dilates on Mr. Wedgwood's gifts of pottery, retorts, tubes, &c., and presents in glass from another gentleman, among which figures "a capital burning-lens, sixteen inches in diameter." The Duke of Grafton remitted him annually 40*l.* When he went to America forty of his friends, without solicitation, raised the sum of 450*l.*, "which was meant to have been continued annually while he lived," as stated by his son.

You will hear these details with the interest naturally belonging to the subject, and doubtless ask the question, Have succeeding generations improved on this? I believe that there is no example of an equal generosity on the part of their fellow-countrymen to a man of science, although there are some agreeable exceptions to the rule of neglect. A few years ago the Fishmongers' Company presented the sum of 50*l.* to Prof. Parker, and an annual gift of 20*l.* for three years, to assist him in bearing the expenses of his researches on vertebrate animals. For three years the British Pharmaceutical Society voted 80*l.* in aid of pharmaceutical research. The principle of promoting research has also been recognised by the Government in their grant of 1000*l.*, and in the fund of 4000*l.* placed at the disposal of the Royal Society. Our Government has, however, as yet made no payment for the *labour* of pure research in experimental physics or chemistry. "A grant from the above sum," says Dr. Gore, "is often an unprofitable gift to accept, because it is in some cases only sufficient to pay expenses out of pocket for chemicals and apparatus, and allows nothing for skill or labour."

The mention of our able associate's name compels me to draw attention to the invaluable services he has rendered for ten years past to the cause of the endowment of research. His numerous articles and papers form a repository of facts and arguments of which I have largely availed myself. Any one who studies them will need no other evidence of the importance of the question, both in view of the progress of truth and of the maintenance of our national welfare. In one of them he mentions the difficulty experienced in the proper employment of the Government money, and proceeds as follows:—"By far the greater part of the expense of an investigation in physics or chemistry is the exceedingly large amount of time it occupies. Many necessary preliminary experiments have to be made, which yield either negative, unsuccessful, or incomplete results, and make the undertaking expensive." Further, "By order of the Council, all instruments, apparatus, and drawings, made or obtained by aid of the Government grants, shall, after serving the purpose for which they were procured, and in the absence of any undertaking to the contrary, be delivered into the custody of the Royal Society."

Research, then, in any fair sense of the word may be said to be unprovided for by public funds. The British Association annually bestows grants of varying amounts for specific researches. The Royal Institution helps. Yet we feel surprised when told that the average annual expenses relating to experimental research, including salaries to assistants in the laboratory, from the year 1867 to 1871, did not amount to two hundred and fifty pounds.

When it is remembered that not a single college, nor even a professorship, for pure scientific research exists in this country, we must feel humiliated when we cast a glance at what is going on in other countries. In France and Germany varied resources have been placed at the disposal of men of science, which I cannot now minutely specify. Nor will I delay to speak in detail of the importance of pure research in science, of the mighty material results as regards our comfort and national wealth which have sprung from the labours of men of science, for it may be assumed that all this is known. It is certain too that valuable inventions in various arts and manufactures will follow upon fresh discoveries regarding the principles involved in them. When we know more of the materials and forces of nature, new applications of them will soon follow. The progress of invention depends upon that of discovery; the various inventions wanted by manufacturers and others cannot be perfected until "suitable knowledge is found." The money of the capitalist, the hand of the inventor, await the products of the brains of the searcher after truth.

It is only too well known that other countries have for some years past distanced Britain in the field of research; that while Germany is sending her trained sons to all parts of the world, we scarcely even supply our own colonies. A writer in the *Monthly Journal of Science* said last year that "to a very great extent, both in the home kingdoms and the colonies, we find ourselves compelled to import that intellectual eminence which we refuse to cultivate in our midst. Foreigners occupy professorial chairs in our colleges; they fill the posts of botanists and geologists in our colonial governments; they hold high positions in the respective staffs of the British Museum, of the Geological Survey of India, and of our exploring expeditions."

Now as these results cannot be owing to any inbred deficiency in the countrymen of Newton, Faraday, and Darwin, it behoves us to ask if our educational system is at fault, and if fair provision is made for those able and willing to make original research. The latter question is already answered by the facts adduced. How far our great universities have provided for science-teaching can be learned by reading between the lines of certain resolutions passed a few years ago by an "Association for the organisation of academical study," the composition of which was an ample guarantee of competence. The resolutions were as follows:—

"That the chief end to be kept in view in any redistribution of the revenues of Oxford and Cambridge is the adequate maintenance of nature study and scientific research, as well for their own sakes as with the view of bringing the higher education within the reach of all who are desirous of profiting by it."

"That to have a class of men whose lives are devoted to research is a national object."

"That it is desirable in the interests of national progress and education that *professorships* and *special institutions* shall be founded in the universities for the promotion of scientific research."

"That the present mode of awarding Fellowships as prizes, has been unsuccessful as a means of promoting nature study and original research, and that it is therefore desirable that it should be discontinued."

The state of things here pointed at has improved and is improving, yet the verdict of a candid observer must still be summed up in the one word inadequacy.

Numerous suggestions have been made regarding the endowment of research, but most of them are unpractical. Those who imagine that the object will be gained by establishing adequate teacherships of science, seem to be too sanguine. The labour involved in the work of teaching, in the way of acquisition, preparation, and performance, is too great to permit the devotion of sufficient time and thought to the search after new truth. If it is desirable that new facts and principles be searched after, why should fit inquirers be put, either partly or wholly, to other work? I know that many of our teachers have hitherto been at a great disadvantage; that managers of institutions have had a sharper eye on their prospectus than on their internal arrangements; that they have thought of a college rather as a body of bricks than as productive of a body of learning; and that apparatus and assistants, though well enough in Berlin or Leipzig, are needless in prudent England. Yet the ideal Professor is rather the head of a department than a mere speaker by the yard of so many lectures; a man with numerous hands in the shape of demonstrators and assistants, themselves the possessors of well-trained brains; a director of work with all its apparatus freely supplied to him. Such a man adequately remunerated may be safely left to his own tendencies. Contact with nature breeds the desire to know her better. In favourable conditions the teacher becomes the investigator, and while seeking after new truth builds up his own fame.

After all, however, the question recurs, how can we best promote research, as the undivided life's work of fit persons? I believe that the solution lies, so far as this time is concerned, in

the establishment of special institutions having no other object than the search after new truth. Their administration would be difficult. The right men can be found for the work, but can the right electors be found? Ardent searchers after a more intimate knowledge of nature do still live, will ever live; but what of First Commissioners of Works like—but I need not name him? What of Lords of the Treasury who refused the request of a great physicist for 150*l.* for the investigation of the tides? Yet these gentlemen assist in governing a maritime state of some importance. Such electors as these are not within my view, and, if they were, how of the detailed management? Men given up to research are not to be tied by the common rules of official life; to be compelled to report in annual blue books the exact measure of work they have done; to show how many drachms of oil of vitriol they have used, and account for every ounce of platinum.

Special institutions will be founded, but they will owe their origin to private individuals like Sir Josiah Mason; who, having taken into their confidence the chiefs of the world of science in making the appointments, will speak to the masters of research in this wise:—

"I have built a house for you replete with every requirement for your work; I have provided you with such assistants as you have asked for; I have given you an income placing within your reach every reasonable comfort. Occupy your lives in the study of nature. If you succeed in your efforts to attain to new truth, the world will be the gainer. If you fail, your efforts will be enough reward for me."

Such language as this will be surely one day heard. In this fortunate town it is already heard. During the past year a member of this Society, Mr. Fulford, has taken a house, and, having admirably fitted it up, has handed it over to our two distinguished associates, Dr. Gore and Dr. Norris, in order that they may enjoy at least the requisite structural conveniences for the prosecution of research. This building is called the "Institute of Scientific Research."

I must, however, remind you that this noble enterprise must be supplemented by some such efforts in the way of endowment as those now made by this Society; and that those who work even in the highest sphere are bound by the same necessities as bind other men.

SCIENTIFIC SERIALS

Annalen der Physik und Chemie, No. 12 (December, first No.).—On the density and tension of saturated vapour, by A. Wüllner and O. Grotrian.—On the application of the electrodynamic potential to determination of the ponderomotive and electromotive forces, by R. Clausius.—On friction in free liquid surfaces, by A. Oberbeck.—Simple methods and instruments for resistance-measurements, especially in electrolytes, by F. Kohlrausch.—Influence of temperature on the phenomena of charge of a liquid cell acting as condenser, by H. Herwig.—On the modes of electric discharge in gases, by O. Lehmann.—On the electric discharge in liquid insulators, by W. Holtz.—On electric figures on the surface of liquids, by the same.—On the increase of danger from lightning and its probable causes, by the same.—On a microprismatic method for distinction of solid substances, by O. Maschke.—Note on Herr Weber's reply, by A. Winkelmann.

Reale Istituto Lombardo di Scienze e Lettere. Rendiconti. Vol. xii., fasc. xix.—The Leprosy of Upper Italy, especially of Comacchio (continued), by Prof. Sangalli.—Influence of traction and vibration of a metallic wire on its electric conductivity, by Dr. de Marchi.—On a case of twisted neck; a contribution to the doctrine of transport of spinal influence and to establishment of a hypothesis for its explanation, by Prof. de Giovanni.

Zeitschrift für wissenschaftliche Zoologie, November, 1880, contains: Dr. H. von Ihering, on the affinities and kinship of the Cephalopods.—Dr. J. Bellonci, on the origin of the optic nerve and on the minute structure of the "tectum opticum" in the Teleostei (Plates 1 and 2).—Dr. D. Sochaczewer, on the organ of smell in the terrestrial pulmonates (Plate 3).—Dr. Fritz Müller, on the case-making Trichoptera larvæ of the Province of Santa Catharina (Plates 4 and 5), translated by his brother, Dr. Hermann Müller, from the memoirs in Portuguese in the Archivos de Museu National, Rio de Janeiro.—Dr. William Marshall, researches in the sponge groups, Dysideidæ and Phoriospongiæ (Plates 6 to 8).—Prof. Dr. Krause, on two very early human embryos (Plate 9).—Dr. H. Simroth, on the nervous system in the foot of *Paludina vivipara*, with a woodcut of the nerves as dissected out.

Revue internationale des Sciences biologiques, December 1880 contains:—A. de la Calle, on the formation of language (continued).—M. Decatte, microcephalism, from the point of view of atavism.—M. Zaborowski, historical sketch of the relative knowledge possessed by the ancients and in mediæval times of the large monkeys.—Notices of learned societies.—French Association for the Advancement of Science (the Rheims Meeting).—The Academy of Sciences, Paris.

Schriften der physikalisch-ökonomischen Gesellschaft zu Königsberg (1877, ii.; 1878, i. and ii.).—These parts contain the following papers:—On Baron von Richthofen's loess theory and the alleged steppe character of Europe at the close of the Glacial period, by Dr. A. Jentzsch.—Observations of the station for measuring the temperature of the soil in various depths, at the Königsberg Botanical Gardens, by Prof. E. Dorn.—On the prehistoric-archæological work done by the Society, by Otto Tischler.—On the commercial routes of the ancients to the amber country, by Dr. Krosta.—On the physics of the soil, by Dr. von Liebenberg.—On the discoveries in prehistoric tombs at Fürstenwalde, by Otto Tischler.—On hair-covered human beings and the abnormal growth of hair, by Prof. Hildebrandt.—On the marine fauna near the Prussian coast, by Prof. Zaddach.—On the alleged steppe character of Central Europe, by Dr. Jentzsch.—On the state of civilisation in Denmark during the first centuries after Christ, by O. Tischler.—On Darwin's theory, by Herr Czwalina.—On East Prussian burial-grounds, by O. Tischler.—On the fauna of Madagascar, by Prof. Zaddach.—On the intra-Mercurial planet, by Dr. Franz.—On the geological maps at the Paris Exhibition, by Dr. Jentzsch.—On some special geological maps of Germany, by the same.—On the principles of the kinetic theory of gases, by Dr. Saalschütz.

SOCIETIES AND ACADEMIES

LONDON

Chemical Society, January 20.—Prof. H. E. Roscoe, president, in the chair.—The president announced that the Faraday lecture would be delivered by Prof. Helmholtz in the Royal Institution, On the Modern Development of Faraday's Conception of Electricity. The following papers were read:—On pentathionic acid, by Mr. V. Lewes. The author has succeeded in obtaining beautifully crystallised barium and potassium pentathionates by partially neutralising Wackenroder's solution and evaporation *in vacuo*.—A preliminary note on some hydrocarbons from rosin spirit, by Dr. Armstrong. Cymene, toluene, and metaxylene were found to be present. The hydrocarbons insoluble in sulphuric acid are probably hexhydrides of hydrocarbons of the benzene series. The author does not consider that rosin is directly derived from terpene.—On the determination of the relative weight of single molecules, by Dr. Vogel of San Francisco.—On the synthetical production of ammonia by the combination of hydrogen and nitrogen in presence of heated spongy platinum, by G. S. Johnson. About 0·0144 grm. of ammonia were obtained in two and a half hours.—On the oxidation of organic matter in water, by A. Downes.—Analyses of Queensland soils, by Prof. A. Liversidge. These analyses are interesting, as the soils include samples from districts which were exempt from the disease prevalent in the sugar plantations around.—On the volumes of some compounds of the benzene naphthalene, anthracene, and phenanthrene series, by Dr. Ramsay.—On the atomic volume of nitrogen, by Dr. Ramsay.—On a new theory of the conversion of bar iron into steel by the cementation process, by Dr. Marsden. The author thinks that carbon diffuses in an impalpable powder through the heated iron.—On the action of sulphydrate of potassium on chloral hydrate, by W. W. J. Nicol. Thioglyoxylic and thioformic acids are formed.

Zoological Society, January 18.—Prof. W. H. Flower, LL.D., F.R.S., president, in the chair.—The Secretary read a report on the additions that had been made to the Society's Menagerie during the month of December, 1880, amongst which special attention was called to a young female Red Wolf (*Canis jubatus*) from the Argentine Republic, presented by Mr. W. Petty of Monte Video, being the second example of this scarce animal received, and to a Pig from Brooker Island, Louisiade Archipelago, presented by Lieut. de Hoghton, of H.M.S.

Beagle.—A paper by Mr. P. L. Sclater and Dr. G. Hartlaub was read, on the birds collected in Socotra by Prof. I. B. Balfour in the early part of the year 1880. The collection contained 124 examples referable to thirty-four species. Of these seven of the Passeres appeared to be new, and were proposed to be called *Cisticola incana, Drymœca hæsitata, Lanius uncinatus, Cinnyris Balfouri, Passer insularis, Rhynchostruthus Socotranus*, and *Amydrus frater*.—Mr. A. G. Butler read a paper on the lepidoptera collected in Socotra by Prof. I. B. Balfour. The collection contained twenty-four specimens referable to thirteen species, seven of which were stated to be new to science.—Mr. W. A. Forbes read a paper on some points in the anatomy of the Koala (*Phascolarctos cinereus*), as observed in the specimen recently living in the Society's Gardens.—A communication was read from Mr. R. Bowdler Sharpe, in which was given the description of a new form of the family *Timeliidæ*, from Madagascar, proposed to be called *Neomixis*.—A communication was read from Dr. John Scully containing an account of the mammals of Gilgit, a district in the extreme north-western part of Kashmir. Thirty-three species were enumerated, and notes on their vertical ranges and habits were added. The mammals of Gilgit were shown to consist of an intermixture of Central Asiatic and Himalayan species, as might have been expected from the position of the country. Two species (a Bat and a Vole), apparently new to science, were named respectively *Harpiocephalus tubinaris* and *Arvicola Blanfordi*.

Meteorological Society, January 19.—Mr. G. J. Symons, F.R.S., president, in the chair.—The report of the Council for the year 1880, which was read by the Secretary, refers to subjects of considerable importance, and affords substantial evidence of the interest taken in meteorology by the scientific and general public. Amongst these may be mentioned the great success of the new climatological stations, as shown by their increased number and by the regularity and care with which the observations have been made and recorded, and the returns forwarded to the Society. The Council also advert to the number of new and improved instruments exhibited at the meeting held in March last, to the increase in the number of Fellows, fifty-two having been elected during the year, and finally the numerous papers which have been sent to the Society from various parts of the world, embracing records of the climate of several important localities, respecting which but little has hitherto been known in this country.—After a vote of thanks had been passed to the Council for their services during the year, and to the Institution of Civil Engineers for allowing free use of their rooms, the President delivered his address, in which he traced the history of English meteorological societies from 1823 to 1880. The earliest English effort at forming an English meteorological society, or at any rate at securing observations made with comparable instruments recorded upon a uniform system, was made in 1723 by Dr. James Jurin, who was then secretary to the Royal Society. In the *Philosophical Transactions* for that year will be found a Latin address by Dr. Jurin, in which he anticipates nearly all the conditions which are now considered essential for comparable observations. This appeal did not lead to much being done, and in 1744 another attempt was made by Mr. Roger Pickering, F.R.S., who read before the Royal Society a paper entitled "Scheme of a Diary of the Weather, together with Drafts and Descriptions of Machines subservient thereunto." The Meteorological Society of the Palatinate was established in 1780 under the auspices of the Elector Charles Theodore, who not only gave it the support of his public patronage, but entered with spirit and ability into its pursuits and furnished it with the means of defraying the expense of instruments of the best construction, which were gratuitously distributed to all parts of Europe and even to America. One of the first acts of the Association was to write to all the principal universities, scientific academies, and colleges, soliciting their co-operation and offering to present them with all the necessary instruments properly verified by standards and free of expense. The offer was accepted by thirty societies, and the list of distinguished men who undertook to make the observations shows the importance which was attached to the plan and the zeal with which it was promoted in every part of the Continent. In 1823 the first meeting of the Meteorological Society of London was held, and was attended by Luke Howard, Thomas Forster, Dr. Birkbeck, and others. After 1824 the Society languished, but it was never regularly dissolved. Owing to several letters and articles which appeared in *Loudon's Magazine of Natural History* a meeting was held on November 15, 1836, at which the Society was revived, Mr. W. H. White appointed secretary, and regular meetings resumed. Application was made to the Royal Society for permission to compare the instruments of the Society with the Royal Society's standards, and leave was granted on March 13, 1838. A volume of *Transactions* was published in 1839, and among other articles contains one entitled "Remarks on the Present State of Meteorological Science, by John Ruskin." The cost of the publication of this volume exhausted the funds of the Society, but in 1841 Mr. Gutch undertook personally the pecuniary risk of a new publication entitled the *Quarterly Journal of Meteorology*, but this does not appear to have been very successful, owing to the high rate of postage. Shortly after this the Society practically came to an end. On April 3, 1850, a meeting of some friends of the science was convened by Dr. Lee at Hartwell, when the British Meteorological Society was established, and Mr. S. C. Whitbread elected president. The first general meeting of the Members was not held till March 25, 1851; but in the meanwhile several important steps had been taken by the Council. Annual Reports were published from 1851 to 1861, and since then five volumes of the *Proceedings* and six volumes of the *Quarterly Journal* have been published. Up to 1858 absolutely nothing had been done towards forming a library, but in 1862 a catalogue was published containing about 200 titles. In 1876 a new catalogue was issued, which extends to eighty pages and contains over 1200 entries. On January 27, 1866, the Society obtained a Royal Charter of Incorporation, and has since been known as "the Meteorological Society." On April 4, 1872, the Council resolved upon taking a room for an office and for the protection of the library, and appointed Mr. W. Marriott as their Assistant Secretary. The work has now become so great that the Society has been obliged to take an additional room and to engage three computers. The subsequent eight years have been characterised by great progress. A series of second order stations has been organised which are systematically inspected, and at which strictly comparable observations are made. On January 1, 1880, another and larger series of stations—called climatological—was started, at which the observations are less onerous than those at the second order stations, but at which they are required to be equally accurate. Observations on natural periodical phenomena are also made at many places, and discussed yearly by the Rev. T. A. Preston. At the request of the Society a conference has been appointed consisting of delegates from several other societies to prepare accurate instructions respecting the erection of lightning conductors. At the conclusion of the President's address the following gentlemen were elected the officers and council for the ensuing year, viz.:—President—George James Symons, F.R.S. Vice-presidents: Edward Ernest Dymond, William Ellis, F.R.A.S., Joseph Henry Gilbert, F.R.S., Charles Greaves, M.Inst. C.E., F.G.S. Treasurer: Henry Perigal, F.R.A.S. Trustees: Sir Antonio Brady, F.G.S., Stephen William Silver, F.R.G.S. Secretaries: Robert Henry Scott, F.R.S., John William Tripe, M.D. Foreign Secretary: John Knox Laughton, M.A., F.R.A.S., F.R.G.S. Council: Edmund Douglas Archibald, M.A., Arthur Brewin, F.R.A.S., Henry Storks Eaton, M.A., Rogers Field, B.A., M.Inst. C.E., Frederic Gaster, Baldwin Latham, M.Inst.C.E., F.G.S., Robert John Lecky, F.R.A.S., Edward Mawley, Hon. Francis Albert Rollo Russell, M.A., Richard Strachan, George Mathews Whipple, B.Sc., F.R.A.S., Charles Theodore Williams, M.A., M.D.

Entomological Society, Annual Meeting, January 19.—Sir John Lubbock, Bart., F.R.S., &c., president, in the chair.—The President delivered his annual address, and the following gentlemen were elected as officers for the ensuing year:—President, H. T. Stainton, F.R.S.; Treasurer, E. Saunders, F.L.S.; Librarian, F. Grut, F.L.S.; Secretaries: E. A. Fitch, F.L.S., and W. F. Kirby, F.L.S.; Council: W. Cole; W. L. Distant, M.A.I.; F. du Cane Godman, F.L.S.; Sir John Lubbock, Bart., F.R.S., &c.; R. Meldola, F.R.A.S.; O. Salvin, M.A., F.R.S.; F. P. Pascoe, F.L.S.; R. Trimen, F.L.S.

Victoria (Philosophical) Institute, January 17.—A paper on Pliocene man in America, by Dr. Southall of Virginia, U.S., was read. In it he showed that the evidence brought forward as to the existence of such was wholly unreliable; the same ground was taken in special communications from the Duke of Argyll, K.G., Principal Dawson, F.R.S., of Montreal, Prof. Hughes (Woodwardian Professor of Geology at Cambridge), and Mr. Whitley, C.E.; also by Mr. S. R. Pattison, F.G.S.,

and Mr. Hall, F.R.G.S., who had examined the evidences on the spot, and by the Rev. J. M. Mello, F.G.S., Mr. T. K. Callard, F.G.S., and Mr. E. Charlesworth, F.G.S.—About twenty new Members were elected, bringing the total number to nearly 900.

Institution of Civil Engineers, January 18.—Mr. James Abernethy, F.R.S.E., president, in the chair.—The paper read was on deep winning of coal in South Wales, by Messrs. Thomas Forster Brown and George Frederick Adams, MM. Inst. C.E. The authors, who were professionally associated with Harris's Navigation Pits, the deepest winning in the district, described the operations as a fair example of the details connected with winning deep coals in South Wales. The depth of the lowest seam at present sunk to was 760 yards; the pits were each seventeen feet in diameter inside the walling. In addition to the depth a special feature was the thickness of hard and heavily-watered rock penetrated. Guide ropes, upon the Galloway principle, were used in sinking, and the value of this system was shown in the saving of over two minutes in steadying the bowk at the bottom of the pit at depths of 475 and 530 yards, the total time occupied in clearance at the latter depth being three minutes twenty-six seconds. The method of dealing with the various feeders of water during sinking was described: one of the pits was drained by a hole bored by the diamond machine, which was put down, at a depth of 175 yards from the surface, for a farther depth of 860 feet.

VIENNA

Imperial Academy of Sciences, January 13.—Dr. Fitzinger in the chair.—On the lacunar resorption in diseased bones, by Dr. Pommer.—On the physiological significance of the transpiration of plants, by Herr Reinitzer.—On the influence of prussic acid on breathing and circulation, by Dr. Lazarski.—On the relations of homogeneous deformations of solid bodies to surfaces of reaction, by Dr. Finger.—Contributions to the photochemistry of silver chloride, by Dr. Eder and Herr Pizzighelli.—On a new derivative of gallic acid, by Dr. Oser and Herr Kalmann.—Influence of form of cathode on the distribution of phosphorescence-light (sealed packet of November 17, 1880), by Herr Goldstein.—On a tetra-hydrocinchonin acid, by Dr. Weidel.—Determination of magnetic and diamagnetic constants of liquids and gases in absolute measure, by Herr Schuhmeister.

January 20.—Herr von Burg in the chair.—Studies on caffeïn and theobromin (first part), by Prof. Maly and Herr Hinteregger.—Researches on the anatomy, physiology, and development of Sternaspis, by Dr. Vejdovsky.—The flight of Libellula; contribution to the anatomy and physiology of organs of flight in insects, by Herr Lendenfeld.—Research on kynurenic acid (first part), by Dr. Kretschy.—Action of hydrate cupric oxide on some kinds of sugar, by Prof. Habermann and Herr Hönig.

PARIS

Academy of Sciences, January 17.—M. Wurtz in the chair.—The following papers were read:—Contemporaneous production of native sulphur in the subsoil of Paris, by M. Daubrée. This sulphur occurs abundantly in the ground of the Place de la République, from 0·2m. to 3m. from the surface, and in a space 50m. by 15 to 20m.; one finds a breccia with thin incrusted fragments of crystalline sulphur. The product is due to simultaneous presence of the sulphate of lime of plaster-rubbish, and organic *débris*, with which the ancient moat of the centre of the city was filled up two centuries ago.—Order of appearance of the first vessels in the ear of Lolium (second part), by M. Trécul.—On the treatment of phylloxerised vines, by M. Marés. He finds very successful an application of dilute sulpho-carbonate of potassium to the lower parts of the vines twice a year.—Discoveries in equatorial Africa; meeting of MM. de Brazza and Stanley; by MM. de Lesseps and de Quatrefages. M. de Brazza speaks of having descended the Congo and founded the station of Ntamo Ncouna, twelve marches from Ogôuué; it is the most advanced post in the heart of Africa, and will be an important centre for exploration, &c. He had met Stanley on November 7 near Vivi. Capt. Bloyet has established a station near Lake Touquerko.—Observations of the comet *f* 1880 (Pechulé) at Paris Observatory, by M. Bigourdan.—On the displacement of an invariable figure, by M. Darboux.—Integration in finite form of a new species of differential linear equations with variable coefficients, by M. André.—On the theory of vibrating plates, by M. Mathieu.—On complete combinations; number of complete combinations of *m* letters *n* to *n*, by M. Melon.—Remarks on an opinion attributed to me by a note of M. Cornu, by M. Gouy.—Minimum of the power of resolution of a prism, by M. Thollon.—On the production of intermittent luminous signals with the electric light, by M. Mercadier. One carbon is horizontal, and advances a little at each signal. The other is vertical, and is held in a peculiar clip at one end of a horizontal lever, to the other end of which is fixed a vertical rod with terminal friction roller working on a cam. The vertical carbon is connected with the battery by a wire spring, and it is dropped a little by the clip at certain positions of the cam. The cam may be turned by clockwork for regular signals, or with the hand, at a variable rate, for irregular.—Observations *à propos* of M. Dunand's recent paper on reproducing speech with electric condensers, by M. Herz. He patented the use of a condenser as telephonic receiver on M. Dunand's principle in June last year.—Some facts to serve in the history of nitrification, by MM. Hautefeuille and Chappuis. Electric effluves, intense enough to quickly give much ozone in a mixture of oxygen and nitrogen, but not to form hyponitric acid, produce the new unstable pernitric acid. Using lower tensions, the formation of this acid is found to go side by side with that of ozone. Pernitric acid is decomposed at all temperatures, but at 130° the decomposition is complete in a few seconds (into hyponitric acid and oxygen). Numerous experiments seem to prove that in simultaneous production of ozone and pernitric acid by the effluve the gases have not been raised to a temperature near that named; where hyponitric acid is formed, that temperature has been passed. A consequence of the facts is that effluves corresponding to weak tensions may furnish nitric acid, ultimate product of decomposition of pernitric acid.—On the conservation of grain in reservoirs (continued), by M. Müntz. Oats kept in a ventilated granary thirty months had lost 7·2 per cent. more of fixed matter (chiefly starch) than oats kept the same time in a metallic reservoir (of 220 cubic m. capacity), having its lower part in a subsoil. In the sereservoirs there is a distillation towards the upper part. To get all the advantage of closed reservoirs there should be a comparatively dry grain, a perfect closure, and a maintenance of the walls at pretty constant temperature.—Study of the peat of crystalline strata of Finisterre, by M. de Molon.—On the parts of the pancreas capable of acting as ferments, by M. Béchamp. All the known properties of the pancreas are concentrated in the microzymas.—Anatomical researches on the digestive, nervous, and reproductive apparatus of Onchidia, by M. Joyeux Laffine.—Hypertrophy and multiplication of nuclei in hypertrophied cells of plants, by M. Prillieux.—On the production of *verglas*, by M. Minary. He thinks the theory needs correction. Instead of regarding water in a state of surfusion as composed only of liquid, he supposes it formed of a mixture of liquid and of solid molecules (of ice) held apart by some unknown cause. For the congelation to be complete when surfusion ceases, the ice of the mixture merely requires (in order to rise to 0°) a quantity of heat equal to the latent heat still conserved by the quantity of water in surfusion.

CONTENTS

	PAGE
UNCONSCIOUS MEMORY. By GEORGE J. ROMANES, F.R.S.	285
NEWTON'S BRITISH BIRDS	287
OUR BOOK SHELF:—	
"Jahrbücher für wissenschaftliche Botanik"	288
LETTERS TO THE EDITOR:—	
Unconscious Memory.—Dr. ERNST KRAUSE	288
Hot Ice.—Prof. JOHN PERRY	288
Mr. Bottomley's Experiments with Vacuum Tubes and the Aurora.—Prof. SILVANUS P. THOMPSON	289
The Geological Age of the North Highlands of Scotland.—Prof. EDWARD HULL, F.R.S.	28
Geological Climates.—Prof. SAMUEL HAUGHTON, F.R.S.; JOSEPH JOHN MURPHY	290
Prof. Whitney on the Glaciation of British Columbia.—GEORGE M. DAWSON	290
Lophiomys Imhausi.—Prof. HENRY HILLYER GIGLIOLI	291
Parhelion.—J. KAND CAPRON	291
Girton and Newnham Colleges.—FLORENCE EVES	291
Minerva Ornaments at Troy *v.* Net-Sinkers.—Prof. E. W. CLAYPOLE	292
THE PROVOST OF TRINITY COLLEGE, DUBLIN	292
GEOLOGISING AT SHEPPEY. By J. STARKIE GARDNER	293
THE CONSERVATOIRE DES ARTS ET MÉTIERS (*With Illustrations*)	294
NOTES	296
OUR ASTRONOMICAL COLUMN:—	
Brorsen's Comet in 1848	298
Herschel's First Observation of Uranus	299
GEOGRAPHICAL NOTES	299
DEEP-SEA EXPLORATION. By J. GWYN JEFFREYS, LL.D., F.R.S.	300
THE RELATION BETWEEN ELECTRICITY AND LIGHT. By Dr. O. J. LODGE	302
ENDOWMENT OF RESEARCH IN BIRMINGHAM	304
SCIENTIFIC SERIALS	304
SOCIETIES AND ACADEMIES	304

SUBSCRIPTIONS TO NATURE

Yearly . . . . . 28s.
Half-yearly . . . . . 14s. 6d.
Quarterly . . . . . 7s. 6d.

To the Colonies, United States, the Continent, and all places within the Postal Union :—

Yearly . . . . . 30s. 6d.
Half-yearly . . . . . 15s. 6d.
Quarterly . . . . . 8s.

Office: 29, Bedford Street, Strand.

DIARY OF SOCIETIES.

LONDON

THURSDAY, JANUARY 27.

ROYAL SOCIETY, at 4.30.—The Refraction Equivalents of Carbon, Hydrogen, Oxygen, and Nitrogen in Organic Compounds: Dr. Gladstone, F.R.S.—On certain Definite Integrals, No. 8: W. H. L. Russell, F.R.S.—*Polacanthus Foxii*, a large undescribed Dinosaur from the Wealden Formation in the Isle of Wight: J. W. Hulke, F.R.S.—On Harmonic Ratios in the Spectra of Gases: Dr. Schuster, F.R.S.—Dielectric Capacity of Liquids: Dr. Hopkinson, F.R.S.—Note on the occurrence of Ganglion Cells in the Anterior Roots of the Cat's Spinal Nerves: E. A. Schäfer, F.R.S.—On the Iron Lines widened in Solar Spots: J. N. Lockyer, F.R.S.

LONDON INSTITUTION, at 7.—Manufacture of Indigo from Coal: Prof. Armstrong.

SOCIETY OF ARTS, at 8.—A New Mechanical Furnace, and a Continuous System of Manufacturing Sulphate of Soda: James Mactear.

ROYAL INSTITUTION, at 3.—The Troubadours: F. Hueffer.

FRIDAY, JANUARY 28.

QUEKETT MICROSCOPICAL CLUB, at 8.—On Sponges: B. W. Priest.—On *Filaria*: Dr. T. S. Cobbold.

ROYAL INSTITUTION, at 9.—Modern Spectroscopy: Dr. Schuster.

SATURDAY, JANUARY 29.

ROYAL INSTITUTION, at 3.—The Amazons: Prof. S. Colvin.

SUNDAY, JANUARY 30

SUNDAY LECTURE SOCIETY, at 4.—Physiological Unity of Plants and Animals: Prof. Boulger.

MONDAY, JANUARY 31.

ARISTOTELIAN SOCIETY, at 8.—Leibnitz: E. Clarkson.

INSTITUTE OF ACTUARIES, at 7.—On the Construction and Use of a Series of Select Mortality Tables to be used in connection with the Institute $H^m(5)$ Table, Parts 2 and 3: T. B. Sprague.

LONDON INSTITUTION, at 5.—The Thing that might be: Rev. Mark Pattison.

TUESDAY, FEBRUARY 1.

ZOOLOGICAL SOCIETY, at 8.30.—On the Evolution of the Placenta and its Application to the Classification of the Mammalia: F. M. Balfour.—Remarks upon the Habits of the Darter (*Plotus anhinga*): A. D. Bartlett.—On some Birds collected by Mr. E. F. im Thurn in British Guiana: P. L. Sclater.

ROYAL INSTITUTION, at 3.—The Blood: Prof. Schäfer.

SOCIETY OF ARTS, at 8.—Industrial Products of South Africa: Sir Bartle Frere.

WEDNESDAY, FEBRUARY 2.

GEOLOGICAL SOCIETY, at 8.—On the Coralliferous Series of Sind, and its connection with the last Upheaval of the Himalayas: Prof. P. M. Duncan, F.R.S.—On Two New Crinoids from the Upper Chalk of Southern Sweden: P. Herbert Carpenter, M.A. Communicated by Prof. P. M. Duncan, F.R.S.

SOCIETY OF ARTS, at 8.—Trade Prospects: Stephen Bourne.

THURSDAY, FEBRUARY 3.

ROYAL SOCIETY, at 4.30.

LINNEAN SOCIETY, at 8.—Notes on Cyperaceæ: George Bentham.—Observations on some British Fishes: Dr. Francis Day.—Remarks on the Coffee-Leaf Disease in India: William Biddie.

ROYAL INSTITUTION, at 3.—The Troubadours: F. Hueffer.

LONDON INSTITUTION, at 7.—Three Years of Daily Weather Forecasting: R. H. Scott.

R. W. NEEVES,
PHILOSOPHICAL INSTRUMENT
AND
INTENSITY COIL MAKER.

PRICE LIST, FOUR STAMPS.

55, SIDMOUTH STREET, LONDON, W.C.

DRAPER'S INK (DICHROIC).
THE NEW BLACK INK

DIFFERING FROM ANYTHING ELSE EVER PRODUCED.

Writing becomes a pleasure when this Ink is used. It has been adopted by the principal Banks, Public Offices, and Railway Companies throughout Ireland.

It writes almost instantly Full Black. Does not corrode Steel Pens. Is cleanly to use, and not liable to Blot. | Flows easily from the Pen. Blotting-paper may be applied at the moment of writing.

Can be obtained in London, through Messrs. BARCLAY & SONS, Farringdon Street; W. EDWARDS, Old Change; F. NEWBERY & SONS, Newgate Street; WM. MATHER, London and Manchester; J. AUSTIN & CO., Duke Street, Liverpool; and STACY & COOK, Paternoster Row; and to be had of all Stationers.

BEWLEY & DRAPER (Limited), Dublin.

Sale by Auction.

Natural History Specimens.

MR. J. C. STEVENS will Sell by Auction, at his Great Rooms, 38, King Street, Covent Garden, on FRIDAY, January 28, at half-past 12 precisely, Natural History Specimens, consisting of Animal Skins, Skulls, Horns, Rare Bird Skins, Eggs, Insects, Fossils, Shells, Minerals, British and Foreign Herbariums, Microscopic Objects, Cabinets and Glass Cases, South Sea Island Curiosities, &c., &c.

On view after 2 o'clock the day prior and morning of Sale, and Catalogues had.

NOTICE OF REMOVAL.
JAMES HOW & CO.,
SCIENTIFIC INSTRUMENT MAKERS,
73, FARRINGDON ST., LONDON
(LATE OF 5, ST. BRIDE ST., AND 2, FOSTER LANE)

HOW'S STUDENT'S MICROSCOPE. HOW'S MICROSCOPE LAMP.
Rock Sections and other Objects for the Microscope.

J. ORME & CO.,
(Late M. JACKSON & CO.)
MANUFACTURERS AND IMPORTERS OF
SCIENTIFIC APPARATUS
AND
CHEMICALS.

SOLE AGENTS FOR HICKLEY'S PATENT TELEPHONES,
Price 50s. per Pair, Cash with Order.
Price Lists sent on receipt of Three Stamps for Postage.
For Trade Terms inclose Business Card.

65, BARBICAN, LONDON, E.C.

EAGLE INSURANCE COMPANY,
79, PALL MALL.
FOR LIVES ONLY. ESTABLISHED 1807.

Accumulated Funds £3,043,542
Also a Subscribed Capital of more than £1,500,000

Reports, Prospectuses, and Forms may be had at the Office, or from any of the Company's Agents, post free.

GEORGE HUMPHREYS, Actuary and Secretary.

GIMINGHAM'S SPRENGEL AIR-PUMP,
with Multiple Fall Tubes and every recent improvement, including McLeod's Barometer Gauge, Radiometer, Terminals for testing non-conductivity of the Vacuum, &c., &c.

L. CASELLA having arranged with Mr. GIMINGHAM for the Sole Manufacture of these Pumps, as well as his Improved Forms of

CROOKES'S RADIANT MATTER TUBES,
Is prepared to supply them either in their simple form, or with any of their accessories.

Mr. GIMINGHAM has kindly engaged to examine each, in order that no Imperfect Instrument or Tubes may be sent away.

Also GIMINGHAM'S COMBINATION BLOWPIPE for Amateur and Professional Glass Work, the most simple and perfect in use.

L. CASELLA, 147, Holborn Bars, London, E.C.

NOW READY.
SECOND EDITION,
GRIFFIN'S
CHEMICAL HANDICRAFT.
PRICE 4s. 7d. POST FREE.
A CATALOGUE OF CHEMICAL APPARATUS:
ILLUSTRATED, CLASSIFIED, DESCRIPTIVE.

Demy 8vo, 480 pp., Illustrated with 1,600 Woodcuts.

Most Complete and Cheapest List of Apparatus.

JOHN J. GRIFFIN AND SONS, 22, GARRICK STREET, LONDON, W.C.

YORK'S
SERIES of SCIENTIFIC OPTICAL LANTERN SLIDES

Comprise over 2,000 of the following subjects:—Electricity, Magnetism, Sound, Telephone, Microphone, Electric Light, Light, Spectrum Analysis, Astronomy, Mines and Miners, Heat, Mechanics, Hydrostatics, Pneumatics, Human Physiology. Sample Slide and Catalogue sent on receipt of 2s.

F. YORK, OPTICAL LANTERN SLIDE MANUFACTURER,
87, Lancaster Road, Notting Hill, London, W.

THIN GLASS FOR MICROSCOPIC

MOUNTING, of best quality. Circles, 3s. 6d. per ounce; Squares, 2s. 0d.; post free 2d. extra; Ground edged Slips, 5s. per gross; also other Mounting Materials and Objects prepared for mounting.—CHAS. PETIT, 151, High Street, Stoke Newington, N.

W. LADD & CO.,

SCIENTIFIC INSTRUMENT MANUFACTURERS,

(*By Appointment to the Royal Institution of Great Britain*),

11 AND 12, BEAK STREET, REGENT STREET, W.

IMPROVED HOLTZ ELECTRICAL MACHINES. GRAMME'S MAGNETO-ELECTRIC MACHINE for Laboratory use.

PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3s. per oz.

Physical Apparatus of every Description.

ILLUSTRATED CATALOGUE, SIXPENCE.

PATERSON'S NEW CATALOGUE OF PHYSICAL APPARATUS.

LANTERN SLIDES for SCIENTIFIC LECTURES. Season 1880-1. Post free 6 Stamps.
Complete Sets of Physical Apparatus for Science Primers and all the Physical Text-books in use in Schools and Colleges.
Siemens and Gramme Dynamo Machines and Lamps for hire.
Schools supplied with Apparatus as per Science and Art Departments' Requirements in the Sections of Light, Heat, Sound, and Electricity.
Electric Signals for Houses, Hotels, &c., Colliery Signals, Lightning Conductors. The Gower-Bell Loud-speaking Telephone.

EDWARD PATERSON, Electrical Engineer.

SHOW ROOMS AND STEAM WORKS:—76, LITTLE BRITAIN, E.C. (late 3, Bedford Court, W.C.).

MOLISON'S HARMONOGRAPH; executes the Harmonic Curves in the most perfect manner. 15s. and 20s.

Illustrated Catalogue of Electrical Apparatus, Part 1, post free, 6 Stamps. Ditto, Electric Signals, Part 2, 6 Stamps.

CHEMICAL APPARATUS AND SCIENTIFIC INSTRUMENTS.

PURE CHEMICALS, &c.

IMPORTERS AND MANUFACTURERS.

AUG. BEL & CO.,

34, MAIDEN LANE, COVENT GARDEN, LONDON, W.C.

Laboratories fitted up. Sets of Apparatus as required by the Universities, Colleges, and Schools always ready and kept in stock. Professor Feser's Patent Lactoscope for Testing Milk, as recommended by Dr. Voelcker. Description on Application. A Liberal Discount allowed to the Trade.

Liberal Terms to Science Teachers and the Trade.

THOMAS CRAMPTON & Co. (formerly of 4, Little Britain, London, E.C.), ELECTRICIANS, OPTICIANS, and PHILOSOPHICAL INSTRUMENT MAKERS. Electric Bells, New Metallic Base Pattern, Constant Batteries, Indicators, Thief and Fire Alarms, and Automatic Switches, Induction and Medical Coils, or Specialities. Insulated Wires of every description. Microscopic and Optical Materials. Telescopes, Opera Glasses, Microscopes, Aneroid Barometers, and Lime-light Apparatus. Illustrated Catalogue Three Stamps.

THOMAS CRAMPTON & CO., 251, HIGH HOLBORN, LONDON, W.C.

For Trade Terms send Card.

£5 5s. ASTRONOMICAL TELESCOPE.

CRAMPTON & CO.'S IMPROVED TELESCOPE is of the highest workmanship and finish, combined with great power and clearness of definition; is entirely constructed of polished brass, with 3-inch Achromatic Object Lens, Altitude and Azimuth Movements, Rackwork, and Fine Adjustment, &c., &c.

THOMAS CRAMPTON & CO., 251, HIGH HOLBORN, LONDON, W.C.

ELECTRICAL AND SCIENTIFIC APPARATUS.

Wholesale Manufacturer of Metallic Base Electric Bells, Electric Reversing Indicators, and Constant Manganese Batteries, Telephone Switches and Transmitters, Induction Coils and Vacuum Tubes, Terminals, Carbons, Wire and all Materials. Instruments made, repaired, or altered on the premises.

Illustrated Bell List free. Complete Catalogue Two Stamps. Special Quotations to the Trade.

HENRY J. DALE, MANUFACTURING ELECTRICIAN and OPTICIAN, 4, Little Britain, London, E.C.

HOLLOWAYS OINTMENT A CERTAIN REMEDY

For BAD BREASTS, OLD WOUNDS, and SORES. If effectually rubbed on the Neck and Chest, it cures SORE THROATS, BRONCHITIS, COUGHS and COLDS; and for GOUT, RHEUMATISM, and all Skin Diseases it is unequalled.

SCIENTIFIC WORTHIES.

ENGRAVED BY THE LATE C. H. JEENS.

The following is a list of the Portraits that have appeared in the above Series.

MICHAEL FARADAY.
THOMAS HENRY HUXLEY.
CHARLES DARWIN.
JOHN TYNDALL.
GEORGE GABRIEL STOKES.
SIR CHARLES LYELL.
SIR CHARLES WHEATSTONE.
JEAN BAPTISTE ANDRÉ DUMAS.
SIR WYVILLE THOMSON.
SIR WILLIAM THOMSON.
HERMANN L. F. HELMHOLTZ.
SIR JOSEPH DALTON HOOKER.
WILLIAM HARVEY.
SIR GEORGE B. AIRY.
J. LOUIS R. AGASSIZ.
RICHARD OWEN.

Proof impressions of these, printed on India paper, may be had from the Publishers, price 5s. each, or the Set of 16 Portraits in a Handsome portfolio for £4 5s. carriage paid.

THE PORTFOLIO MAY BE HAD SEPARATELY, PRICE 6s.

NOTE.—ONLY A VERY FEW COMPLETE SETS CAN BE MADE UP.

Cheques and P.O.O.s payable to MACMILLAN & CO.,

OFFICE OF "NATURE," 29, BEDFORD STREET, STRAND.

CLASS-BOOKS OF SCIENCE.

ASTRONOMY, by the Astronomer-Royal.

POPULAR ASTRONOMY. With Illustrations. By Sir G. B. AIRY, K.C.B., Astronomer-Royal. New Edition. 18mo. 4*s*. 6*d*.

Six lectures, intended "to explain to intelligent persons the principles on which the instruments of an Observatory are constructed, and the principles on which the observations made with these instruments are treated for deduction of the distances and weights of the bodies of the Solar System."

ASTRONOMY.

ELEMENTARY LESSONS IN ASTRONOMY. With Coloured Diagram of the Spectra of the Sun, Stars, and Nebulæ, and numerous Illustrations. By J. NORMAN LOCKYER, F.R.S. New Edition. 18mo. 5*s*. 6*d*.

"Full, clear, sound, and worthy of attention, not only as a popular exposition, but as a scientific 'Index.'"—*Athenæum*.

QUESTIONS ON LOCKYER'S ELEMENTARY LESSONS IN ASTRONOMY. For the Use of Schools. By JOHN FORBES-ROBERTSON. 18mo, cloth limp. 1*s*. 6*d*.

PHYSIOLOGY.

LESSONS IN ELEMENTARY PHYSIOLOGY. With numerous Illustrations. By T. H. HUXLEY, F.R.S., Professor of Natural History in the Royal School of Mines. New Edition. 18mo. 4*s*. 6*d*.

"Pure gold throughout."—*Guardian*.

QUESTIONS ON HUXLEY'S PHYSIOLOGY FOR SCHOOLS. By T. ALCOCK, M.D. 18mo. 1*s*. 6*d*.

BOTANY.

LESSONS IN ELEMENTARY BOTANY. By D. OLIVER, F.R.S., F.L.S., Professor of Botany in University College, London. With nearly Two Hundred Illustrations. New Edition. 18mo. 4*s*. 6*d*.

CHEMISTRY.

LESSONS IN ELEMENTARY CHEMISTRY, INORGANIC AND ORGANIC. By HENRY E. ROSCOE, F.R.S., Professor of Chemistry in the Victoria University, the Owens College, Manchester. With numerous Illustrations and Chromo-Litho of the Solar Spectrum, and of the Alkalies and Alkaline Earths. New Edition. 18mo. 4*s*. 6*d*.

"We unhesitatingly pronounce it the best of all our elementary treatises on Chemistry."—*Medical Times*.

A SERIES OF CHEMICAL PROBLEMS, prepared with Special Reference to the above, by T. E. THORPE, Ph.D., Professor of Chemistry in the Yorkshire College of Science, Leeds. Adapted for the preparation of Students for the Government, Science, and Society of Arts Examinations. With a Preface by Professor ROSCOE, F.R.S. New Edition, with Key, 18mo. 2*s*.

QUESTIONS ON: A Series of Problems and Exercises in Inorganic and Organic Chemistry. By F. JONES, F.R.S.E., F.C.S. Fcap. 8vo. 3*s*.

GEOGRAPHY.

CLASS-BOOK OF GEOGRAPHY. By C. B. CLARKE, M.A., F.G.S. New Edition, with eighteen coloured Maps. Fcap. 8vo. 3*s*.

"Contains a large amount of information, systematically arranged."—*Examiner*.

A SHORT GEOGRAPHY OF THE BRITISH ISLANDS. By JOHN RICHARD GREEN, M.A., LL.D., and ALICE STOPFORD GREEN. With Maps. Fcap. 8vo 3*s*. 6*d*.

"The little work may be read with pleasure and profit by any one."—*Times*.

LOGIC.

ELEMENTARY LESSONS IN LOGIC; Deductive and Inductive, with copious Questions and Examples, and a Vocabulary of Logical Terms. By W. STANLEY JEVONS, M.A., LL.D., F.R.S. New Edition. 18mo. 3*s*. 6*d*.

"A manual alike simple, interesting, and scientific."—*Athenæum*.

PHYSICS.

LESSONS IN ELEMENTARY PHYSICS. By BALFOUR STEWART, F.R.S., Professor of Natural Philosophy in the Victoria University, the Owens College, Manchester. With numerous Illustrations and Chromo-litho of the Spectra of the Sun, Stars, and Nebulæ. New Edition. 18mo. 4*s*. 6*d*.

"The beau-ideal of a scientific text-book, clear, accurate, and thorough."—*Educational Times*.

PRACTICAL CHEMISTRY.

THE OWENS COLLEGE JUNIOR COURSE OF PRACTICAL CHEMISTRY. By FRANCIS JONES, F.R.S.E., F.C.S., Chemical Master in the Grammar School, Manchester. With Preface by Professor ROSCOE, F.R.S., and Illustrations. New Edition. 18mo. 2*s*. 6*d*.

ANATOMY.

LESSONS IN ELEMENTARY ANATOMY. By ST. GEORGE MIVART, F.R.S., Lecturer in Comparative Anatomy at St. Mary's Hospital. With upwards of 400 Illustrations. 18mo. 6*s*. 6*d*.

"The work is excellent, and should be in the hands of every student of human anatomy."—*Medical Times*.

STEAM.

AN ELEMENTARY TREATISE. By JOHN PERRY, B.E., Whitworth Scholar, &c., late Lecturer in Physics at Clifton College. With numerous Woodcuts and Numerical Examples and Exercises. 18mo. 4*s*. 6*d*.

"The young engineer and those seeking for a comprehensive knowledge of the use, power, and economy of steam, could not have a more useful work, as it is very intelligible, well arranged, and practical throughout."—*Ironmonger*.

SOUND.

ELEMENTARY LESSONS ON. By Dr. W. H. STONE. With Illustrations. Fcap. 8vo. 3*s*. 6*d*.

"This is an excellent little text-book. . . . The student of acoustics will find it a very acceptable help."—*English Mechanic*.

PHYSICAL GEOGRAPHY.

ELEMENTARY LESSONS IN PHYSICAL GEOGRAPHY. By A. GEIKIE, F.R.S., Murchison Professor of Geology, &c., Edinburgh. With numerous Illustrations. 18mo. 4*s*. 6*d*.

QUESTIONS ON THE SAME. 1*s*. 6*d*.

NATURAL PHILOSOPHY.

NATURAL PHILOSOPHY FOR BEGINNERS. By I. TODHUNTER, M.A., F.R.S. Part I. The Properties of Solid and Fluid Bodies. 18mo. 3*s*. 6*d*.

Part II. Sound, Light, and Heat. 18mo. 3*s*. 6*d*.

POLITICAL ECONOMY.

POLITICAL ECONOMY FOR BEGINNERS. By MILLICENT G. FAWCETT. New Edition. 18mo. 2*s*. 6*d*.

"The relations of capital and labour have never been more simply or more clearly expounded."—*Contemporary Review*.

ECONOMICS OF INDUSTRY. By A. MARSHALL and A. P. MARSHALL. Fcap. 8vo. 2*s*. 6*d*.

"The book is of sterling value, and will be of great use to teachers and students of Political Economy."—*Athenæum*.

MACMILLAN AND CO., LONDON.

Messrs. MACMILLAN & CO.'S PUBLICATIONS.

NEW BOOKS ON IRELAND.

Disturbed Ireland, being the Letters Written during the Winter of 1880-81. By BERNARD H. BECKER, Special Commissioner of the *Daily News*. With Route Maps. Crown 8vo. 6*s*.

"Will be found one of the most trustworthy pictures of the sister island as it is . . . It has, especially at this moment, high political value."—*Examiner*.

The Life's Work in Ireland of a Landlord who Tried to do his Duty. By W. BENCE JONES of Lisselan. Crown 8vo. 6*s*.

"Mr. Bence Jones has written an interesting and instructive little book; but not the least enlightening part of it is the Preface, dated December 12th, 1880. He had just been threatened with Boycotting, which he now undergoes."—*St. James's Gazette*.

Life of William Blake. With Selections from his Poems and other Writings. Illustrated from BLAKE'S own Works. By ALEXANDER GILCHRIST. A New and Enlarged Edition, with Additional Letters and a Memoir of the Author. 2 vols. Printed on hand-made paper, the Illustrations on India paper, and mounted in the text. Cloth elegant, gilt, with designs after BLAKE by FREDK. J. SHIELDS. Medium 8vo. 42*s*.

"One of the most beautiful and interesting books of the season."—*Daily News*.

"Without any reservation, it is undoubtedly one of the most tasteful and thorough editions of a fine art book which we ever remember to have seen."—*Notes and Queries*.

The Steam Engine and its Inventors. A Historical Sketch. By Robert L. GALLOWAY, Mining Engineer. With numerous Illustrations. Crown 8vo. 10*s*. 6*d*.

The Year's Art: A Concise Epitome of all matters relating to the Arts of PAINTING, SCULPTURE, and ARCHITECTURE, which have occurred during the Year, together with information respecting the events of the Year 1881. Compiled by MARCUS B. HUISH. Crown 8vo. 2*s*. 6*d*.

GOLDEN TREASURY SERIES.—NEW VOLUME.

Essays of Joseph Addison. Chosen and Edited by John Richard Green, M.A., LL.D. 18mo. 4*s*. 6*d*.

"This is a most welcome addition to a most excellent series."—*Examiner*.

Dictionary of Music and Musicians (A.D. 1450—1878). *By Eminent* Writers, English and Foreign. Edited by GEORGE GROVE, D.C.L. Three Vols. 8vo, with Illustrations and Woodcuts. Parts I. to XII. each 3*s*. 6*d*. Vols. I. and II., 8vo, cloth, each 21*s*.

Vol. I. A to Impromptu. Vol. II. Improperia to Plain Song.

"This work promises to be for music what the best encyclopædias are to general literature and science."—*Guardian*.

English Poets: Selections, with Critical Introductions by various Writers, and a General Introduction by MATTHEW ARNOLD. Edited by T. H. WARD, M.A. 4 vols., crown 8vo, each 7*s*. 6*d*.

Vol. I. CHAUCER to DONNE.
Vol. II. BEN JONSON to DRYDEN.
Vol. III. ADDISON to BLAKE.
Vol. IV. WORDSWORTH to SYDNEY DOBELL.

"An excellent design admirably executed."—*Pall Mall Gazette*.

English Men of Letters. Edited by John Morley. Crown 8vo. 2s. 6d.

(New Volume.)

WORDSWORTH. By F. W. H. MYERS.

"Mr. Myers gives us a picture of the man and an estimate of his work which is certainly not inferior to anything that has preceded it."—*Academy*.

The Abbott's Farm; or, Practice with Science. By Henry Tanner, M.R.A.C., F.C.S., Professor of the Principles of Agriculture in the Royal Agricultural College, Author of "First Principles of Agriculture." Extra fcap. 3*s*. 6*d*.

Kamilaroi and Kurnai. Group-Marriage and Relationship, and Marriage by Elopement. Drawn chiefly from the usage of the Australian Aborigines: also the Kurnai tribe—their Customs in Peace and War. By LORIMER FINSON, M.A., and A. W. HOWITT, F.G.S. With an Introduction by LEWIS H. MORGAN, LL.D., Author of "System of Consanguinity," "Ancient Society," &c. Demy 8vo. 15*s*.

Gilbert White's Natural History and Antiquities of Selborne. New Edition, with a Poem and Letters never before published. Edited, with Notes and Memoir by FRANK BUCKLAND; a Chapter on Antiquities by Lord SELBORNE; and the Garden Kalendar. With Illustrations by Prof. DELAMOTTE. Cheap Edition. Crown 8vo. 6*s*.

Physics of the Earth's Crust. By Rev. O. Fisher, M.A., F.G.S., Rector of Harlton, &c. 8vo. [*Shortly*.

MACMILLAN AND CO., LONDON.

Printed by R. CLAY, SONS, AND TAYLOR, at 7 and 8, Bread Street Hill, Queen Victoria Street, in the City of London, and published by MACMILLAN AND CO., at the Office, 29 and 30, Bedford Street, Covent Garden.—THURSDAY, January 27, 1881.

NATURE

A WEEKLY ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
Of Nature trusts the mind which builds for aye."—WORDSWORTH

No. 588, Vol. 23] THURSDAY, FEBRUARY 3, 1881 [Price Sixpence

Registered as a Newspaper at the General Post Office.]

[All Rights are Reserved.

UNIVERSITY OF LONDON MATRICULATION, JUNE, 1881.

Special Classes for this Examination will be formed at St. Thomas's Hospital Medical School, Albert Embankment, to commence on March 1st. The Special Classes for the Preliminary Scientific and 1st M.B. Examinations have now commenced. Full particulars can be obtained from the Secretary, Dr. GILLESPIE.

KING'S COLLEGE, LONDON.

The Office of the CURATOR of the ANATOMICAL MUSEUM is now VACANT.

Applications, accompanied by Testimonials of special aptitude for, and experience in, Museum work, to be sent to J. W. CUNNINGHAM, Esq., from whom also further information may be obtained.

ROYAL AGRICULTURAL SOCIETY OF ENGLAND.

AGRICULTURAL EDUCATION.

The Examination of Candidates for the Society's Prizes and Certificates, including the Life Membership of the Society, will take place in the week commencing TUESDAY, May 10th, 1881.

Copies of the Form of Entry, which is required to be sent in by April 1, 1881, may be had on application to

H. M. JENKINS, Secretary.

12, Hanover Square, London, W.

INSTRUCTION IN MATHEMATICS.—Youths or Adults attended at their Residence, on Reasonable Terms, by a M.A. of Cambridge. Unquestionable references if required.—Address, by letter, O. P., Post Office, Turnham Green.

Second-Hand Astronomical Telescopes, Microscopes, & other Scientific Instruments.

C. BAKER,

244 & 245, HIGH HOLBORN,

Begs to call the attention of the Scientific to his Large and Extensive Stock of

ASTRONOMICAL TELESCOPES,
MICROSCOPES,
TRANSIT INSTRUMENTS,
REGULATORS, SPECTROSCOPES,
METEOROLOGICAL AND ELECTRIC APPARATUS,

By ROSS, DALLMEYER, COOKE, SMITH & BECK, BROWNING, DENT, TROUGHTON,

And other Celebrated Makers. All at very Low Prices.

CATALOGUE FREE BY POST.

INSTRUMENTS TAKEN IN EXCHANGE.

ESTABLISHED 1765

BROWNING'S SPECTROSCOPES.

THE MINIATURE SPECTROSCOPE.

This Instrument will show many of Fraunhofer's lines, the bright lines of the metals and gases, and the absorption bands in coloured gases, crystals, or liquids.

Price, with Plain Slit, £1 2s.; ditto, with Adjustable Slit in Morocco Case, £1 15s.; ditto, with Achromatic Lenses, &c., &c., in Morocco Case, £2 6s.

An Illustrated Catalogue of Spectroscopes, Price Sixpence.

LIST OF SPECTROSCOPES SENT FREE.

JOHN BROWNING,
63, STRAND, LONDON, W.C.

STANDARD METEOROLOGICAL INSTRUMENTS



Now ready, a New Edition of Negretti & Zambra's Encyclopædic Catalogue of Mathematical, Philosophical, Optical, and Standard Meteorological Instruments, containing numerous Comparative Tables of Reference, and Illustrated by Twelve Hundred Engravings.

Royal 8vo, cloth, gilt lettered, price 5s. 6d.

NEGRETTI & ZAMBRA,

Opticians and Scientific Instrument Makers

To HER MAJESTY THE QUEEN,

HOLBORN VIADUCT,

45, CORNHILL, & 122, REGENT STREET, LONDON.

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 48N, Tollington Road, Holloway, London, N.

INSTITUTE OF CHEMISTRY.

PRIZES.

DR. FRANKLAND has offered a Prize of £50 for the best Original Investigation involving Gas Analysis, and DR. C. MEYMOTT TIDY has also offered a Prize of £25 for the best Original Investigation on Special Reactions of the Alkaloids and their Separation from Organic Mixtures. These prizes will be open to Associates, and to all persons (except Fellows of the Institute) who shall, before the 31st of December next, have qualified for the Associateship in all respects, short of passing the prescribed practical examination; and successful competition for these prizes will be accepted in lieu of such practical examination.

Further information may be obtained on application to the Secretary, Mr. C. E. GROVES, Somerset House Terrace, W.C.

FOR SALE, price £100.—A rapidly-growing ANALYTICAL PRACTICE in the West of England. To be sold because the owner is leaving England.—Apply by letter, G. W. R., 52, Drury Lane, London, E.C.

ROYAL POLYTECHNIC.—CLASSES for the Preparation of Students for University Examinations, under the direction of EDWARD B. AVELING, D.Sc., F.L.S. London University Matriculation, 1st and 2nd B.Sc., Preliminary Scientific M.B., Botany, Physiology, Chemistry. All the work practical.

MINERALOGY AND GEOLOGY.

Mr. HENSON having purchased an OLD COLLECTION formed in DERBYSHIRE, containing FINE SPECIMENS of ANGLESITE, CERUSSITE, FLUOR SPAR and CALC SPAR, DIOPTASE, EUCHROITE, and other RARE MINERALS, begs to offer the same singly or otherwise.

COLLECTIONS FOR STUDENTS, from £2 2s. COLLECTIONS FOR BEGINNERS, from 4s. BLOWPIPE CASES AND APPARATUS.

PRIVATE LESSONS AND EVENING CLASSES.

Catalogues free.

SAMUEL HENSON,

277 (*Late* 113*a*), STRAND, LONDON, W.C.

GEOLOGY AND MINERALOGY.

Special Collections for Teachers and Students, used with success by all Lecturers and Teachers of Geology in Great Britain. Obtained Gold and Bronze Medals at Sydney Exhibition, 1879, also in London, 1862, and Paris, 1867.

200 Specimens in Cabinet ...	...	...	...	£2 2 0
100 ditto	ditto	...	...	1 1 0
50 ditto	ditto	...	...	0 10 6

New Lists of Collections, Apparatus, &c., now ready, and free on application to

JAMES R. GREGORY'S

Geological Museum and Repository,

88, CHARLOTTE STREET, FITZROY SQUARE.

THOMAS D. RUSSELL'S

NATURAL HISTORY STORES,

48, ESSEX STREET, STRAND, W.C.

Students and others are invited to inspect the Collections of British and Foreign Shells, Corals, Zoophytes, Annelids, Crustacea, Echinoderms, Minerals, Fossils, Rock Specimens, Microscopic Objects, &c.

Cabinets, Geologist's Hammers, Glass Capped Boxes, Card Trays, Tablets, Glass Slips, Micro- Thin Glass, Canada Balsam, Marine Glue, and other requisites for the Geologist and Microscopist.

Catalogues Post Free.

DIAMONDS IN MATRIX.

R. C. NOCKOLD, Diamond and Oriental Stone Cutter and Dealer, has for sale Specimens of the above; also Cut Precious Stones in all Colours.

Precious Stones valued and bought.

18, FRITH STREET, SOHO, W.

GEOLOGY.—In the Preface to the STU- DENT'S ELEMENTS of GEOLOGY, by Lyell, 1874, he says: "As it is impossible to enable the reader to recognise rocks and minerals at sight by aid of verbal descriptions or figures, he will do well to obtain a well-arranged collection of specimens, such as may be procured from Mr. TENNANT (149, Strand), Teacher of Mineralogy at King's College, London." These Collections are supplied on the following terms, in plain Mahogany Cabinets:—

100 Specimens, in Cabinet, with 3 Trays ...	...	...	£2	2 0
200 Specimens, in Cabinet, with 5 Trays ...	...	...	5	5 0
300 Specimens, in Cabinet, with 9 Drawers	...	...	10	10 0
400 Specimens, in Cabinet, with 13 Drawers	...	...	21	0 0

More extensive Collections at 50 to 5,000 Guineas each.

"NATURE," Nov. 14, 1878, No. 472.—One Shilling each will be paid for Copies of this number.—Address Publishers of NATURE, 29, Bedford Street, Strand, W.C.

LIVING SPECIMENS FOR THE MICROSCOPE.

THOMAS BOLTON, NATURALISTS' and MICROSCOPISTS' STUDIO, 57, NEWHALL STREET, BIRMINGHAM.

T. B. has last week sent to his subscribers the Entomostracan, *Argulus foliaceus*, usually found parasitic on fish, and attached thereto as Commensals, a number of Infusoria, *Epistylis invaginata* of Claparède and Lachman. He has also sent out Hydra, Cordylophora, Rotifers, &c.,; also the large Edible Frog, *Rana esculenta*, suitable for dissection.

Weekly announcements will be made in this place of organisms T. B. is supplying.

Specimen Tube, One Shilling, post-free.

Twenty-six Tubes in course of Six Months for Subscription of £1 1s.

Price List of Specimens on application, with stamped addressed envelope.

Portfolio of Drawings, No. 4, One Shilling.

EVERY BOY A GEOLOGIST.

Now ready, and highly recommended, complete, price 7*s.* 6*d.*

This admirable little Work and most extraordinary Cabinet of wonderfully well-selected Natural Specimens, together with other Geological Preparations, and a powerful Lens, are calculated to start a boy thinking till he has mastered for himself no ordinary knowledge of the formation of the Earth's Crust.—THOMAS J. DOWNING, GEOLOGIST, &c., 38, Whiskin Street, London, E.C.—Catalogues free.

LA SEMAINE FRANÇAISE: a Weekly Newspaper and Review in the French Language. Politics, Literature, Science, Art, Varieties, Notes. Price 3*d.*, through booksellers, and at the railway bookstalls. Office, 37, Southampton Street, Strand, W.C.

LA SEMAINE FRANÇAISE: Journal Français pour l'Angleterre: Politique, Littérature, Sciences, Arts, Variétés, Nouvelles, et Notes. Un exemplaire par la poste, 3½*d.*, en timbres poste. Abonnement franco par la poste—un an, 15*s.* 2*d.*; six mois, 7*s.* 7*d.* Prix 3*d.*, chez tous les libraires et aux gares des chemins de fer. On s'abonne aux bureaux, 37, Southampton Street, Strand, Londres, W.C.

LA SEMAINE FRANÇAISE.—"'La Semaine Fran- çaise' has been brought out in London for the benefit of those English readers who may wish to study contemporary French from all points of view, instead of confining their reading to one particular Gallic print. It certainly merits success."—*Graphic.*

LA SEMAINE FRANÇAISE.—"The numbers before us are full of good things. . . . . It will be far better for most than any one of the best papers published in Paris itself. We are much pleased with the character of it, and believe it will be highly valued in all those many households where French is cultivated. The printing is very well done."—*Queen.*

TERMS OF SUBSCRIPTION:—							s.	d.
Three months	...	...	...	...	...	...	3	10
Six "	...	...	...	...	...	...	7	7
Twelve "	...	...	...	...	...	...	15	2

P.O.O. payable to T. SPANSWICK, at King Street, Covent Garden, W.C.

Publishing Office, 37, Southampton Street, Strand, W.C.

Chaque Samedi 16 pages grand in-8°. 2 colonnes

REVUE HEBDOMADAIRE

Scientifique, illustrée, spéciale, seul journal tenant les lecteurs au courant de tous les détails de l'Exposition universelle d'électricité. organe indépendant des exposants

RÉDACTEUR EN CHEF: **W. de FONVIELLE**

E. de CLISSON: DIRECTEUR

Un numéro, **40** *centimes. — L'année*, **18** *francs. Union postale* **20** *francs.*

PARIS, 16, rue du Croissant, PARIS

Envoi de numéros spécimens gratis sur demande

"The leading Farmers' paper."—CLARE SEWELL READ, ESQ., M.P.

THE CHAMBER OF AGRICULTURE JOURNAL

AND FARMERS' CHRONICLE

(PRICE 3*d.* WEEKLY).

The representative organ of the Central and Provincial Chambers of Agriculture; *gives fuller reports of the discussions and proceedings* of this extensive organisation than any other agricultural paper. It devotes *special attention to the treatment of Agricultural Questions by Parliament*, besides containing ample Reports of the LATEST LONDON and COUNTRY CORN, CATTLE, HOP, PROVISION, and other Markets, with Original Articles on Practical Farming, the Dairy, Herd and Flock News, Horticulture, &c., &c. It is despatched every Monday evening in time for the country post.

Terms of Subscription, payable in advance, post free:—3 months, 3*s.* 9½*d.*; 6 months, 7*s.* 7*d.*; 12 months, 15*s.* 2*d.*

Published by W. PICKERING, 21, Arundel Street, Strand, London, W.C.

Sales by Auction.

The Collection of Coleoptera formed by the late J. ASPINALL TURNER, Esq., of Manchester.

MR. J. C. STEVENS will Sell by Auction, at his Great Rooms, 38, King Street, Covent Garden, on FRIDAY, February 11, at half-past 12 precisely, the well-known and valuable Collection of Coleoptera formed by the late J. ASPINALL TURNER, Esq., of Manchester, including many fine Species, together with the Mahogany Cabinets; also the fine Collection of Lepidoptera formed by the late J. HUNTER, Esq.

On view after 2 o'clock the day prior and morning of Sale, and Catalogues had.

The Natural History, Ethnological, Geological, and other Collections of the late E. W. COOKE, Esq., R.A., F.R.S.

MR. J. C. STEVENS has been favoured with Instructions to Sell by Auction, at his Great Rooms, 38, King Street, Covent Garden, on FRIDAY, February 25th, at half past 12 precisely, by order of the Executor, the Collections of Objects of Natural History, Ethnology, Archæology, Geology, &c.; also Loddige's Botanical Cabinet, a rare and valuable work. Also a fine Collection of Casts from Antique Gems and other Curiosities collected by the late E. W. COOKE, Esq., R.A., F.R.S.

On view after 2 o'clock the day prior and morning of Sale, and Catalogues had.

THE ENTOMOLOGIST'S MONTHLY MAGAZINE.

Price Sixpence, Monthly, 24 pages 8vo, with occasional Illustrations.

Conducted by C. G. BARRETT, J. W. DOUGLAS, R. MCLACHLAN, F.R.S., E. C. RYE, F.Z.S., E. SAUNDERS, F.L.S., and H. T. STAINTON, F.R.S.

This Magazine, commenced in 1864, contains standard articles and notes on all subjects connected with Entomology, and especially on the Insects of the British Isles.

Subscription—Six Shillings per Volume, post free. The volumes commence with the June number in each year.

Vols. I. to VI. (strongly bound in cloth) may be obtained by purchasers of the entire set to date, at the increased price of 10*s.* each; the succeeding vols. may be had separately or together, at 7*s.* each.

London: JOHN VAN VOORST, 1, Paternoster Row.

N.B.—Communications, &c., should be sent to the Editors at the above address.

On the 1st of every Month, price Sixpence.

THE ENTOMOLOGIST:

AN ILLUSTRATED JOURNAL OF BRITISH ENTOMOLOGY.

Edited by JOHN T. CARRINGTON,

With the Assistance of

FREDERICK BOND, F.Z.S. | JOHN A. POWER, M.D.
EDWARD A. FITCH, F.L.S. | J. JENNER WEIR, F.L.S.
F. BUCHANAN WHITE, M.D.

Contains Articles by well-known Entomologists on all branches of the Science; on Insects injurious or beneficial to Farm or Garden; Notes on Habits, Life-Histories; occurrence of Rarities, &c.; there are monthly lists of Duplicates and Desiderata.

Numerous WOODCUT ILLUSTRATIONS, to the printing of which especial attention is given, and occasional LITHOGRAPHED and CHROMO-LITHOGRAPHED PLATES.

SIMPKIN, MARSHALL, & CO., Stationers' Hall Court.

NORTH BRITISH AGRICULTURIST

is the only Agricultural Journal in Scotland, and circulates extensively amongst Landed Proprietors, Factors, Farmers, Farm-bailiffs, and others interested in the management of landed property throughout Scotland and the Northern Counties of England.

The AGRICULTURIST has also a very considerable circulation on the Continent of Europe, America, Australia, and the Colonies.

The AGRICULTURIST is published every Wednesday afternoon in time for the evening mails, and contains Reports of all the principal British and Irish Markets of the week, besides Telegraphic Reports of those held on the day of publication.

The Veterinary Department is edited by one of the leading Veterinarians in the country, and is invaluable to the breeder and feeder as a guide to the rearing of animals, and their treatment when labouring under disease.

Full Reports are given of the Meetings of the Royal Agricultural Society of England, the Royal Agricultural Society of Ireland, the Highland and Agricultural Society of Scotland, the Scottish Chamber of Agriculture, and all the principal Agricultural Associations throughout Great Britain and Ireland.

For Advertisers addressing themselves to Farmers a better medium does not exist

Price 3*d.* By post 3½*d.* Annual Subscription, payable in advance, 14*s.*

Office—377, High Street, Edinburgh.

Post-Office Orders payable to Charles Anderson, Jun., Edinburgh.

ESTABLISHED 1843.

EAGLE INSURANCE COMPANY,

79, PALL MALL.

FOR LIVES ONLY. ESTABLISHED 1807.

Accumulated Funds £3,043,542
Also a Subscribed Capital of more than £1,500,000

Reports, Prospectuses, and Forms may be had at the Office, or from any of the Company's Agents, post free.

GEORGE HUMPHREYS, Actuary and Secretary.

THE QUARTERLY REVIEW, No. 301.

Contents.

I. LORD CAMPBELL'S MEMOIRS.
II. CALIFORNIAN SCENERY AND SOCIETY.
III. LORD BOLINGBROKE IN EXILE.
IV. PROTECTION OF BRITISH BIRDS.
V. LORD BEACONSFIELD'S "ENDYMION."
VI. BELIEF AND UNBELIEF.
VII. MCCARTHY'S HISTORY OF OUR OWN TIMES.
VIII. EMPLOYMENT OF WOMEN.
IX. THE RITUALISTS AND THE LAW.
X. THE TRUTH ABOUT IRELAND.

JOHN MURRAY, Albemarle Street.

In unserem Verlage erscheint:

DER NATURFORSCHER.

Wochenblatt zur Verbreitung der Fortschritte in den Naturwissenschaften.

Herausgegeben von Dr. WILHELM SKLAREK.

Wöchentlich 1—1½ Bgn. in 4°.

Preis vierteljährlich 4 Mk.

Die nunmehr ihren XIV. Jahrgang beginnende Zeitschrift hat bei Allen, welche sich mit Naturwissenschaften beschäftigen, grossen Beifall gefunden. Probenummern sind durch jede Buchhandlung zu erhalten.

Berlin, S.-W., 77, Charlottenstr.

FERD. DÜMMLER'S VERLAGSBUCHHANDLUNG (Harrwitz & Gossmann.)

Now ready, Price 6*s.*, Part II., Vol. XV., January, 1881.

THE JOURNAL OF ANATOMY AND PHYSIOLOGY, NORMAL AND PATHOLOGICAL.

CONDUCTED BY

Profs. HUMPHRY, TURNER, M'KENDRICK, & Dr. CREIGHTON.

Contents.

1. Bones, Articulations, and Muscles of Rudimentary Hind-limb of Greenland Right-Whale. By J. Struthers, M.D. (Plates XIV.–XVII.)
2. Infective Form of Tuberculosis in Man identical with Bovine Tuberculosis. By C. Creighton, M.D.
3. Medullary Neuroma of Brain. By W. Osler, M.D. (Plate XVIII.)
4. Dissection of Genito-Urinary Organs in Case of Fissure of Abdominal Walls. By A. Doran, F.R.C.S. (Plate XIX.)
5. Description of a Polygraph (with Figure). By D. Newman, M.B.
6. Remarks on Mechanism of Secretion of Sweat. By C. Handfield Jones, M.B.
7. Anomalous Growth-Bearing Pilose Skin in Pharynx of a Young Woman. By P. S. Abraham, M.A. (With Figure.)
8. Histology of Granular Kidney (with Figure). By R. Saundby, M.D.
9. Two Cases of Cerebellar Disease. By T. Oliver, M.D.
10. Colouring Matter of Jelly Fishes. By Prof. M'Kendrick.
11. Nerves of the Hind-Limb of the Thylacine and Cuscus. By D. J. Cunningham, M.D.
12. Pulse Dicrotism. By Wm. Jas. Fleming, M.D.
13. Anatomical Notices.

MACMILLAN & CO., London and Cambridge.

On the 1st of every Month, price One Shilling.

THE ZOOLOGIST:

A MONTHLY MAGAZINE OF NATURAL HISTORY.

Third Series. Edited by J. E. HARTING, F.L.S., F.Z.S., Member of the British Ornithologists' Union; contains—

Original articles by well-known naturalists in every branch of zoology: habits of animals; arrival and departure of migratory birds; occurrence of rare birds; distribution and migration of British fresh-water fish; new or rare marine fish; local aquaria; British reptiles; British land and fresh-water mollusca, with remarks on the haunts and habits of the species; and other matters of general interest to those who delight in natural history. Reports of the Linnean, Zoological, and Entomological Societies. Reviews of natural history books. Occasional translations from foreign zoological journals of important and interesting articles in various branches of zoology. There are occasional woodcuts.

JOHN VAN VOORST, 1, Paternoster Row.

THE "HANSA"

Published since 1864 in Hamburg, is the only independent professional paper in Germany, dedicated exclusively to Maritime Objects. Essays, Critiques, Reviews, Reports, Advertisements. Strict eye kept upon the development of Maritime Affairs in every respect. Every second Sunday one Number in 4to at least; frequent supplements and drawings. Subscription at any time; preceding numbers of the year furnished subsequently. Price 12*s.* for twelve months. Advertisements 4*d.* a line, widely spread by this paper; considerable abatement for 3, 6, 12 months' insertion. Business Office: Aug. Meyer and Dieckmann, Hamburg, Alterwall. 98. Edited by W. v. FREEDEN, M.R., Hamburg, Alexander Street, 8.

THE BREWERS' GUARDIAN:

A Fortnightly Paper devoted to the Protection of Brewers' Interests, Licensing, Legal, and Parliamentary Matters.

REVIEW OF THE MALT AND HOP TRADES; AND WINE AND SPIRIT TRADE RECORD.

The Organ of the Country Brewers.

"The Brewers' Guardian" is published on the evenings of every alternate Tuesday, and is the only journal officially connected with brewing interests. Subscription, 16*s.* 6*d.* per annum, post free, dating from any quarter-day. Single Copies 1*s.* each. Registered for transmission abroad.

Offices—5, Bond Court, Walbrook, London, E.C.

SOCIETY FOR PROMOTING CHRISTIAN KNOWLEDGE.

Just published.

MANUAL OF ELEMENTARY SCIENCE—ELECTRICITY.

By PROFESSOR FLEEMING JENKIN, F.R.S.

With numerous Illustrations. Fcap. 8vo, limp cloth, 1s.

NATURAL HISTORY OF BRITISH FISHES: their Structure, Economic Uses, and Capture by Net and Rod. Cultivation of Fish-Ponds, Fish suited for Acclimatisation, Artificial Breeding of Salmon. By the late FRANK BUCKLAND, H.M. Inspector of Fisheries, &c. With numerous Woodcuts. Crown 8vo, cloth boards, 5s.

NATURAL HISTORY RAMBLES:

A Series of Popular Handbooks of the Fauna and Flora of the British Isles.

Fcap. 8vo, cloth boards. 2s. 6d. each.

IN SEARCH OF MINERALS. By the late D. T. ANSTED, M.A., F.R.S., formerly Fellow of Jesus College, Cambridge, &c. With numerous Woodcuts.

"It is probable that his interesting chapters will induce many to go 'in search of minerals' for themselves."—*Athenæum.*

PONDS AND DITCHES. By M. C. COOKE, M.A., LL.D., Author of "The Woodlands." With numerous Woodcuts.

THE WOODLANDS. By M. C. COOKE, M.A., LL.D. With numerous Woodcuts.

LAKES AND RIVERS. By C. O. GROOM NAPIER, F.G.S. With numerous Woodcuts.

LANE AND FIELD. By the Rev. J. G. WOOD, M.A. With numerous Woodcuts.

MOUNTAIN AND MOOR. By J. E. TAYLOR, Esq., F.L.S., F.G.S. With numerous Woodcuts.

THE SEASHORE. By Prof. P. MARTIN DUNCAN, M.B. (London), F.R.S. With numerous Woodcuts.

UNDERGROUND. By J. E. TAYLOR, Esq. F.L.S., *F.G.S.* With numerous Woodcuts.

"With one or more of these little manuals in hand, a sojourn in the country may be made a time of unceasing delight and instruction."—*Saturday Review.*

"These handy little volumes are well put together, and seem to us decidedly superior to works of a similar kind with which we used to be familiar in our youth."—*Nature.*

LONDON: NORTHUMBERLAND AVENUE, CHARING CROSS, S.W.; 43, QUEEN VICTORIA STREET, E.C.; and 48, PICCADILLY, W.

With Illustrations and Maps, medium 8vo, 18s.

ISLAND LIFE:

OR, THE PHENOMENA AND CAUSES OF INSULAR FAUNAS AND FLORAS, INCLUDING A REVISION AND ATTEMPTED SOLUTION OF THE PROBLEM OF GEOLOGICAL CLIMATES. By ALFRED RUSSEL WALLACE, Author of "The Malay Archipelago," "The Geographical Distribution of Animals," &c.

"Mr. Wallace discusses in an admirably clear and able manner the questions of geological climate and time . . . such are only a few of the great problems discussed in this most instructive volume—a volume that ought to interest every thoughtful reader. While its theories are likely to meet with keen criticism from Mr. Wallace's fellow-scientists, his volume ought more than any other we know of to spread among the intelligent reading public a knowledge of and interest in some of the most momentous scientific problems of our time."—*Times.*

"His wonderful grasp of detail, depth of insight, and breadth of view remind one at every turn of Darwin, with whom he shares the honours of discovery in the theory of natural selection; but beyond this he has a lightness of touch, a beauty of style, and an ingenuity in unravelling intricate difficulties which are all his own. . . . 'Island Life' is a work to be accepted almost without reservation from beginning to end. . . . Whoever reads his book must be charmed with it."—*St. James's Gazette.*

"The work throughout abounds with interest. . . . It may be read with equal pleasure by those who are already acquainted with the general principles of distribution and by those who wish for the first time to learn something about modern biological geography."—*Athenæum.*

"We have said enough to show that Mr. Wallace is led to discuss subjects of great interest to speculative minds. With its numerous special maps 'Island Life' ought to prove as interesting as it is instructive."—*Pall Mall Gazette.*

MACMILLAN AND CO., LONDON.

This Day, 20 pp., 8vo, sewed, 1s.

DEEP-SEA EXPLORATION. A Lecture by J. GWYN JEFFREYS, LL.D., F.R.S.

By the same Author.

BRITISH CONCHOLOGY: An Account of the Mollusca which now Inhabit the British Isles and the Surrounding Seas. Five vols., with Plain Illustrations, £4; or Coloured, £5 5s.

JOHN VAN VOORST, 1, Paternoster Row.

EDITED BY HENRY WATTS, B.A., F.R.S., Editor of the *Journal* of the Chemical Society

FOWNES' PHYSICAL and INORGANIC CHEMISTRY. Twelfth Edition, with Coloured Plate and 154 Engravings, crown 8vo. 8s. 6d.

Also,

FOWNES' CHEMISTRY OF CARBON COMPOUNDS; or, ORGANIC CHEMISTRY. Twelfth Edition, with Engravings, crown 8vo. 10s.

London: J. & A. CHURCHILL.

BRYCE-WRIGHT'S LATEST ARRIVALS.

GEMS.—Black Pearls, Moonstones, Cat's Eyes (Chrysoberyl, Crocidolite, and Quartz), and ONE OF THE FINEST OPALS KNOWN.

MINERALS.—Very fine Sphenes from Canada; Euclase, Siberia; Edingtonite, Leadlinlite, and Lanarkite, Scotland; Lumadrella Marble, and a beautiful series of Agates.

STONE IMPLEMENTS.—A very fine series of STONE and BRONZE IMPLEMENTS from the Lacustrine Habitations of Switzerland, also a large series of Scandinavian Implements.

BRYCE-WRIGHT, F.R.G.S., &c.,

Mineralogist and Expert in Gems and Precious Stones,

90, GREAT RUSSELL STREET, LONDON, W.C.

THURSDAY, FEBRUARY 3, 1881

PREHISTORIC EUROPE

Prehistoric Europe. A Geological Sketch. By James Geikie, LL.D., F.R.S. 8vo. (London: Stanford, 1881.)

Les Premiers Hommes et les Temps Préhistoriques. Par le Marquis de Nadaillac. Two vols. 8vo. (Paris: Masson, 1881.)

THE condition of Europe outside the reach of history and the changes by which it has come to be what it is, the appearance of man and his progress in culture, combine to form a subject which cannot, in our opinion, be treated satisfactorily in the present state of knowledge. New facts are being daily brought to light, the speculations of yesterday are being tested by the discoveries of to-day, and the accumulation of materials necessary to form a sound judgment even in any one department, such, for instance, as archæology, is so great, that it may well daunt the courage of the boldest writer who knows the nature of the task before him. In the two books before us the subject is treated from totally different points of view. Dr. James Geikie takes his stand upon the glaciated mountains of Scotland, and attempts to throw the glacial net woven in his previous work, "The Ice Age," over the whole of Europe, and the Marquis de Nadaillac records the facts which he has collected from various quarters, America included, in what may be called a prehistoric gazetteer. The one avowedly takes up the position of an advocate, and pushes glacialism and interglacialism to an extreme, while the other takes the safer, though humbler, ground of a man who has no original views to put forward. The works of both will be useful exactly in proportion to the knowledge and judgment of the reader. There is wheat in both works, but it needs a careful winnowing, as we shall proceed to show.

In his previous work Dr. James Geikie proposed a classification of the Pleistocene deposits of Europe based mainly on observations which he has made in certain parts of Scotland, and attempted a more minute subdivision of the glacial strata than the threefold arrangement generally recognised by European geologists. He advocated a complicated series of arctic glacial and of warm interglacial periods, layers of clay with boulders representing the one, and strata of sand, gravel, loam, or peat the other. His views are by no means accepted, even for Scotland, and the small progress made in general classification during the last twenty years may be estimated from the fact, that scarcely any two geologists agree in correlating the clays and sands on the east and west side of the Pennine Chain with one another and with the glacial strata of Wales, Cumbria, or Scotland. There also is a considerable difference of opinion as to the clays themselves having been derived from glaciers or from icebergs. In his present work he treats these difficulties as solved, and devotes one large section to show "English geologists" (why English?) that all the fluviatile and cave-accumulations with Palæolithic man and the Pleistocene mammalia usually termed Post-glacial, are "of Interglacial, and not of Post-glacial date." The latter term is here used in the sense of being "later than the last great extension of glacier ice in Europe," while the former represents the interval of time between the retreat of one set of glaciers and the advance of another, or that between the deposits of one set of icebergs and those of another. Lyell, Prestwich, Evans, Hughes, and the great majority of those who have worked at the subject hold that the Pleistocene mammalia invaded Europe before the glacial cold had set in, and swung to and fro according to the fluctuations of temperature while the glaciers were advancing and retreating, and that there is proof that Palæolithic man and the extinct animals were in Britain "after the last great extension of the glaciers" (if they were glaciers and not icebergs). We will then appeal to the facts which have been repeatedly urged in the *Proceedings* of the Geological Society and of the Anthropological Institute, as well as in most of the separate works published in Britain since the year 1860.

The area over which Palæolithic implements and Pleistocene mammalia occur in direct relation to the glacial deposits is principally the valley of the Thames and of the Severn, and the Midland and Eastern counties. In the first of these they occur in fluviatile strata, such, for example, as the gravels on which London stands, which are composed of materials derived from the destruction of "the chalky boulder clay." In the valley of the Severn the Pleistocene mammalia are imbedded also in the *detritus* of the boulder clay of that region (Lucy). In the neighbourhood of Cambridge (Hughes, Fisher) the same is the case. In the neighbourhood of Bedford, Wyatt, Prestwich, and Lyell pointed out long ago, not only that the gravels containing the flint implements and fossil mammals were composed of materials that resulted from the wreck of the boulder clay, but that the deposit rested in a hollow which had been cut through "the great chalky boulder clay" of the district. At Hoxne the mammaliferous gravels with Palæolithic implements rest on that boulder clay. The clays in question are the only signs of the extension of glaciers (? icebergs) over those districts, and the fluviatile deposits are obviously of later date. This conclusion Dr. James Geikie does not venture to dispute, but he asks us to believe that formerly another sheet of boulder clay has covered up all these deposits, and that it has been removed so completely that no trace of it is now to be seen. He fixes his attention on the purple clay and the Hessle clay, which occupy an exceedingly limited area, in Yorkshire and Lincolnshire, and imagines that they represent glacial periods, one of which, not specified, extended over the fluviatile strata in question, and caused these strata to be inter- instead of post-glacial. These boulder clays are local and unimportant, and have not been met with over any deposit containing Palæolithic implements. In advancing this speculation he is drawing a cheque on our credulity which is not likely to be honoured. The strata in question are proved by their position to be later than the glacial deposits of the districts in which they occur; it is for him to prove that they are earlier than glacial deposits elsewhere. This he has not done. Still less can his conclusion be accepted that Palæolithic man and the Pleistocene beasts associated with him are solely "interglacial" in Britain and on the Continent in non-glaciated areas. The cases quoted above, and they might be greatly increased, prove that man and the Pleistocene beasts were

in Europe "since the last great extension of glaciers"—or in the Post-glacial times.

There is also reason to believe that man was living in Europe before and during the Glacial period, or, in other words, in Pre-glacial, Glacial, and Inter-glacial times, although the highest evidence of man in the Tertiary Epoch relied upon by Dr. J. Geikie has been shown to have been founded on a mistake, and the inter-glacial age of the implements in Britain and Thetford, which he claims is being of great importance, is not accepted by many geologists such as Dr. Evans and Prof. Hughes. These latter may be dismissed as throwing no light on the question as to the existence of man in Britain since the great extension of the glaciers.

Dr. J. Geikie's main point of attack is the climate of the "Inter-glacial periods" as against ours. He considers that they were warm and genial because of the presence of certain land shells, such as *Hyrnia fasciata*, the climatic value of which is at present unknown, of certain marine shells the distribution of which is dependent on the warm and hot currents, and of land-mammalia now "rare and local" in southern districts, such as the hippopotamus, the limit of whose endurance of cold is yet to be proved, since those in the Liverpool Gardens in London will take their full winter. But unfortunately for his argument the last animal is associated with arctic species, such as the reindeer, in all the caves (Kirkdale, Durnham Down, &c.) which yet, and in all the river deposits (Bedford, which has eight, some three or four of which have been found in the mammoth). The only reason we might infer that the climate was warmer from the presence of reindeer. The conclusion which he urges, that the two periods of animals could not live side by side because they do not live now, is met by the direct testimony of their bones, which, however, is the opinion not of the geologist. The presence of elephas primigenius (Kirkdale and Thetford) and reindeer (Bedford) unaccompanied and mingled them and their bones where they gravel implements (Thetford and the same district). We may remark that in dealing with the fauna of the "Glacial Epoch" Dr. J. Geikie omits all notice of the reindeer, the presence of which destroys his argument as to climate. This reindeer may be taken as a fair example of the whole of the land fauna of the "Inter-glacial" period in the British Isles mammalia. The land shells are few, but their value as witnesses will be found on the side. The two periods of reindeer are dated with the remains of Bos longifrons from the caves (Creswell, &c.) on the one, and from the Irish bogs and the valley of the Thames, above that of the present river, on the other. The latter are those found with "Neolithic implements," whose age is certainly with the Romans in Britain. Some of the graves of that age in Irish bogs.

The interglacial age of Thetford and the Thames valley. It includes not merely the bones with flint-implements, but also the implements themselves, which are found in the Thames valley and have been called "Palæolithic" implements. Their antiquity is such a climate as is implied by the surface-remains, which could not have existed in the glacial period. Hence the "Palæolithic" implements must have been made by men who lived in Britain after the glacial epoch, and before the Roman period, a period universally considered typical upper Pleistocene. It covers also the mammaliferous deposit of Ilford, near London, in the Italian Alps, in which the mammalia identical in French Meuse are considered Pleistocene. It is even searched so as to make it the so-called Pleistocene man of Lima, near Arezzo, the age of which, as Dr. Evans has pointed out, is proved to be Neolithic by the associated implements. Thus we have things of widely different and of well-ascertained age grouped together under the head of "inter-glacial," and we have in this fact proof that the classification is as far worthless, as must every system must be which is based on one and on man.

In further illustration of this we may quote the view of the author that in the period usually termed Pleistocene, or recent, or by him "Post-glacial," Europe was connected by land with the Faroes, Iceland, and Greenland, and that the climate was genial. It is assumed that the "last glacial period" killed off all the Pleistocene fauna in those regions, and that the present races of fauna are the result of subsequent growths, coming from the point of all the last many a continuous tract of land. If we allow this view in the far north, it by the east, the are "inter-glacial," seem that they are wedged in between "the last Glacial period" and the present glacial conditions. But we can allow neither its assumption nor can we accept its premises. The Post-glacial glaciers of Scotland, spoken of in p. 311, are seen to be proof that the ice-accumulation began down, and the submersion and the Irish Sea age is there "a stage or phase of the Pleistocene period," is a truly curious reading of that division.

It is also necessary to say a few words about the two large volumes of the Journal of Conchology. His attitude of reserve with regard to Pleistocene man is natural and important. But we would point out that here and there in the work serious errors are to be remarked. He considers, for example, the Scandinavian Neolithic age as associated the Glacial epoch with the "Danish Isles of Denmark and Norway Rivers," and he writes of the Scandinavians and Finlanders as if they belonged to the Bronze age.

In regard of these works can we find any addition to what has been already shown about Pleistocene Europe, and it will there are instances of well-known facts which it is impossible to refute within the limits of these columns.

W. Boyd Dawkins

[illegible]

[illegible] Herausgegeben von Dr. Ferdinand [illegible]. [illegible] Band, 3 Heft. [illegible] Heft. [illegible] Band, 1 Heft. [illegible] Heft. [illegible] Band, 1 Heft. [illegible] Heft. [illegible] Band, 1

tures up to 60° C., is described and figured at p. 348, and consists essentially of a closed vessel with triple walls, the space between the inner and middle plate filled with water, the outer containing air. For higher temperatures a simple tin plate thermostat was employed, the space being filled with water for temperatures up to 100° Cent. and with glycerine or oil for higher temperatures. The source of heat was always a gas-flame with the usual thermo-regulator. Numerous tabulated results are given of experiments upon moist and dry seeds at various temperatures, and it was found, as might be anticipated, that perfectly dry seeds can withstand a high temperature, even between 120° and 125° Cent., without injury.

Dr. Koch describes how bacteria can be observed, prepared, and photographed, this paper forming the sixth of the extremely important series of researches on bacteria which have from time to time appeared in the *Beiträge*. A thin layer of bacteria with the fluid containing them is to be dried on a thin cover of glass. By placing the glass cover with the dried material in absolute alcohol, or better, in a 0·5 per cent. solution of chromic acid, the bacteria are fixed to the cover, although the coagulated ground substance in which the bacteria are imbedded can be made to swell up and the bacteria themselves to resume their natural forms when the cover is placed in a solution of acetate of potash (1 part to 2 of distilled water). The bacteria can be coloured by means of aniline, the best of all being aniline brown; but methyl violet and fuchsin will also answer. The stained object can be preserved permanently on slides by mounting in Canada balsam, concentrated solution of acetate of potash, or in glycerine. Twenty-four photographs of bacteria, mostly from specimens stained with aniline brown, illustrate the paper; and in some, as 5 and 6 on Plate XIV., the cilia of bacillus are very beautifully shown, magnified 500 and 700 diameters. Koch finds that it is easier to photograph the cilia than to observe them directly with the microscope.

The other papers in this part are on certain Ustilaginæ, by Dr. Schroeter; and on two new species of Entomophthora (*E. conglomerata* and *E. rimosa*) discovered upon dead gnats, by Prof. N. Sorokin.

The first and second parts of vol. iii. contain eleven papers. Four of these are devoted to Bacteria, and form the seventh to the tenth of the series of Researches on Bacteria already alluded to. The titles of the papers are VII. Experiments on Infection with *Micrococcus prodigiosus*, by Dr. A. Wernich; VIII. Researches on the Bacteria in Air, by Dr. Miflet; IX. On the Action of the Electrical Current on the Multiplication of Bacteria, by Dr. F. Cohn and Dr. Mendelssohn; and X. Studies of Blue Milk, by Dr. F. Neelsen. Two of these papers may be briefly mentioned. By means of a specially contrived apparatus fitted with a new continuous aspirator, the invention of Paul Boehme in Brunn, atmospheric air from different localities was examined. These were (1) air in Botanical Laboratory; (2) in Fever Hospital; (3) in the Pathological Theatre; (4) in the Surgical Theatre; (5) air in Botanic Garden; (6) air for soil; and (7) air for drains. The results were briefly as follows:—1. Germs of bacteria capable of developing are abundant in the air, and could readily be collected and cultivated in a special mineral solution, malt extract, or solution of Liebig's extract of beef. 2. Many forms of bacteria can produce reproductive germs in air, while others, as *B. Termo*, seem only capable of producing germs in putrescent matter. 3. Air from the soil contained occasionally germs of bacteria. 4. Air from the Fever Hospital contained no germs, owing to the completeness of the ventilation and disinfection. 5. Air from a sewer contained abundance of germs of bacteria capable of reproducing.

Neelsen, in his paper on Blue Milk, finds that the special organism in it may assume three or four different forms, sometimes like Bacterium, then like Bacillus, then like a Chroococcus, and lastly like a Leptothrix. He discusses the Theory of Cohn and others that the Bacteria form many separate genera and species, and the Theory of Lankester and Warming, that they are forms of a protean species, and seems to conclude that the germs of a given form may under different conditions develop in one or other direction, as observed by him in blue milk.

Dr. Schroeter continues his observations on the Development of Rust, and Dr. Oscar Kirchner describes the Development of *Volvox minor*, Stein. Dr. Hielsher describes the Anatomy and Biology of the Genus Streptocarpus, and details many interesting facts regarding that curious and beautiful genus. When the seed of *Streptocarpus polyanthus* germinates, numerous adventitious roots form on the primary axis, one of the two cotyledons soon disappears, while the other develops greatly, and forms a perennial foliage leaf. On the petiole of this leaf numerous adventitious roots develop and the primary axis disappears. The leaf produces adventitious buds from which the flowers develop, while it also develops a series of adventitious leaf-buds. Dr. Beinling contributes a paper on the formation of adventitious roots and buds on the leaf-cuttings of Peperomia. Prof. Klein describes in detail the anatomy of *Pinguicula alpina* as an insectivorous plant, and points out that the plant occurs in two forms, one with green leaves, the other with the leaves more or less red-brown in colour, and that the tissues assume an intense yellow colour when acted on with caustic potash solution. The remaining papers are by Dr. Schwartz, Chemico-botanical Studies on the Acids in Lichens, and Dr. Eidam on the Gymnoasci. The various papers ably sustain the reputation of this work, and all of them will well repay careful study.

LETTERS TO THE EDITOR

[*The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts. No notice is taken of anonymous communications.*

The Editor urgently requests correspondents to keep their letters as short as possible. The pressure on his space is so great that it is impossible otherwise to ensure the appearance even of communications containing interesting and novel facts.]

Dust and Fogs

I MUCH regret the Hon. R. Russell, in his letter to NATURE, vol. xxiii. p. 267, takes such an extremely desponding view of the influence which my experiments on cloudy condensation are likely to exercise upon the present attempts to rid the atmosphere of our large towns of their ever-recurring fogs. The object of these experiments was to find out what caused fogs, in the hope that with the knowledge thus acquired we might be better able to find a remedy. The preferable course seemed to be to find the cause first, and then if possible devise some remedy, rather than try remedies at haphazard.

It is certainly very far from my desire to discourage the present attempts which are being made to clear the atmosphere of our large towns of smoke, and I have recognised the advantages which would result from the adoption of more perfect forms of combustion. In my paper I have simply distinguished between fogs and smoke, and separated them for distinct consideration and treatment, and have at the same time directed attention to some points which ought to be considered before deciding on their prevention.

With regard to Mr. Russell's difficulty in reconciling the result of the experiments with what is observed with regard to fogs in London, Paris, and other large towns, it appears to me to have arisen entirely from not putting sufficient weight on the all-important influence of the amount of vapour in the air of the different places. It is condensed vapour which forms the fog, and dust simply determines whether it will condense in fine- or coarse-grained particles. The atmosphere of Paris, compared with that of London, is an extremely dry one, and the air is seldom in a condition to produce fogs. The atmospheres of the other towns mentioned are also drier, some of them very much drier, than that of London. London however will probably be always more subject to fogs than other cities on account of its great size, some part of it being always in its own smoke.

Considered from a different point of view, might not the fog of January 31, 1880, referred to by your correspondent, be cited in evidence of a conclusion the opposite of that drawn by the writer, and in favour of the correctness of the experimental results? From this point of view the low white fog cleared away because it was formed in the comparatively pure air of the streets, while the higher fog did not clear away because it was formed in the products of combustion. The true explanation however would rather appear to be, that where the fog was white it was also of less depth than in those places where it "extended high" and mixed with the smoke; and the sun, which was only sufficient to dispel the lesser depth "more or less," would evidently be insufficient to clear away the greater depth. It is however impossible to form any definite idea as to how this particular fog conducted itself, without much fuller information as to air-current, &c.

I have communicated to the secretary of the Royal Society of Edinburgh a second experimental paper on fogs, with special reference to dry fogs. In this paper the full answer to the latter part of Mr. Russell's letter will be found. JOHN AITKEN

Darroch, Falkirk, January 24

Professors Exner and Young

MY statement in respect to Prof. Exner's having announced the thermo-electric neutrality of a bismuth-antimony pair immersed in pure nitrogen, rested upon a note in NATURE (vol. xxii. p. 156), and this it seems was based upon a statement in *L'Electricité*. I have seen those of Prof. Exner's papers which have appeared in the *Annalen der Physik*, and there is certainly nothing of the sort in *them;* but I supposed that it must be contained in some other paper in some one of the numerous other publications to which I have not access here. It never occurred to me, until within a very short time, that there could be any mistake as to his having made such an assertion. How or where the error originated I cannot quite understand; but I trust Prof. Exner will accept my apologies for my share in its propagation, and that he and all concerned will be satisfied that no misrepresentation was intended on my part. The incident is a good illustration of the extreme care necessary in commenting upon the views of another person. C. A. YOUNG

Princeton, U.S.A., January 12

The Flying-fish

IT is remarkable that there should still be any doubt as to the facts in connection with the flight of the flying-fish. Dr. Günther ("Study of Fishes," p. 622), summarising the observation of Möbius, says that "they frequently overtop each wave, being carried over it by the pressure of the disturbed air" (in the open sea!). Again, flying-fishes "never" fall on board vessels "during a calm or from the lee side." At night "when they are unable to see they frequently fly against the weather-board, when they are caught by the current of air and carried upwards to a height of twenty feet above the surface of the water." Surely the fish going at the rate of at least ten miles an hour would on striking the "weather-board" be dashed, bruised and helpless, back into the water instead of coming over the side fresh and vigorous, flapping about on the deck. Except when "by a stroke of its tail" it turns towards the right or left, Möbius concludes that "any deflection from a straight course is due to external circumstances, and not to voluntary action on the part of the fish."

I have watched flying-fish repeatedly, and have invariably seen them fly, or rather glide, over the surface of the sea, and from one to two feet above it, rising gently to the swell when there was no wind, and occasionally turning to the right or left without touching the water. I do not say that when there is a breeze the tail of the fish may not touch it, but I think that, with the foam and spray of the broken water, it would be very difficult to be sure of it, and, moreover, if the tail was used the motion would be a jerking one. Mr. Wallace speaks of their "rising and falling in the most graceful manner," which, although he is referring to another species, applies also to the North Atlantic form (*Exocœtus evolans*). Mr. Bennett ("Gatherings," &c., p. 14) says that they "spring from the sea to a great elevation." This is probably in reference to their coming on board ship at night, attracted, it is supposed, by the lights. I believe the pectoral fins are kept extended without any motion, except perhaps as Mr. Whitman,[1] a recent observer, says, just when they rise from the sea. He gives 800 to 1200 feet as the greatest distance he has seen them fly, and about forty seconds as the longest time out of the water. By what mechanical means they move when out of the water is still to me a mystery.

I have never known the flying-fish to be pursued by other fish, nor ever seen any bird near them; indeed few birds are ever seen far from the land north of the southern tropic, where flying-fish are most abundant. The dolphin (*Coryphæna*) is supposed to be their greatest enemy. I had once an opportunity of seeing one opened—in the West Indies—its stomach was quite full of *Orthagoriscus mola*, very young, being not quite an inch long.

FRANCIS P. PASCOE

1, Burlington Road, W., January 21

Mr. S. Butler's "Unconscious Memory"

I MUST reply to the review of my book, "Unconscious Memory," in your issue of the 27th inst., and to Dr. Krause's letter on the same subject in the same issue.

Mr. Romanes accuses me of having made "a vile and abusive attack upon the personal character of a man in the position of Mr. Darwin," which I suppose is Mr. Romanes' way of saying that I have made a vile and abusive personal attack on Mr. Darwin himself. It is true I have attacked Mr. Darwin, but Mr. Romanes has done nothing to show that I was not warranted in doing so. I said that Mr. Darwin's most important predecessors as writers upon evolution were Buffon, Dr. Erasmus Darwin, Lamarck, and the author of the "Vestiges of Creation." In the first edition of the "Origin of Species" Mr. Darwin did not allude to Buffon nor to Dr. Erasmus Darwin, he hardly mentioned Lamarck, and he ignored the author of the "Vestiges" except in one sentence. This sentence was so gross a misrepresentation that it was expunged—silently—in later editions. Mr. Romanes does not and cannot deny any part of this.

I said Mr. Darwin tacitly claimed to be the originator of the theory of evolution, which he so mixed up with the theory of "Natural Selection" as to mislead his readers. Mr. Romanes will not gainsay this. Here is the opening sentence of the "Origin of Species":—

"When on board H.M.S. *Beagle* as naturalist, I was much struck with certain facts in the distribution of the inhabitants of South America, and in the geological relations of the present to the past inhabitants of that continent. These facts, as will be seen in the latter chapters of this volume, seemed to throw some light on the origin of species; that mystery of mysteries, as it has been termed by one of our greatest philosophers. On my return home it occurred to me in 1837 that something might perhaps be made out on this question by patiently accumulating and reflecting upon all sorts of facts which could possibly have any bearing on it. After five years' work I allowed myself to speculate upon the subject, and drew up some short notes; these I enlarged in 1844 into a sketch of the conclusions which then seemed to me probable; from that period to the present day I have steadily pursued the same object. I hope that I may be

[1] See *Zoologist* for November, 1880.

excused for entering upon these personal details, as I give them to show that I have not been hasty in coming to a conclusion." —"Origin of Species," p. 1, ed. 1859.

What could more completely throw us off the scent of the earlier evolutionists, or more distinctly imply that the whole theory of evolution that follows was an original growth in Mr. Darwin's own mind?

Mr. Romanes implies that I imagine Mr. Darwin to have "entered into a foul conspiracy with Dr. Krause, the editor of *Kosmos*," as against my book "Evolution, Old and New," and later on he supposes me to believe that I have discovered what he calls, in a style of English peculiar to our leading scientists, an "erroneous conspiracy." The idea of any conspiracy at all never entered my mind, and there is not a word in "Unconscious Memory" which will warrant Mr. Romanes' imputation. A man may make a cat's paw of another without entering into a conspiracy with him.

Later on Mr. Romanes says that I published "Evolution, Old and New," "in the hope of gaining some notoriety by deserving, and perhaps receiving, a contemptuous refutation" from Mr. Darwin. I will not characterise this accusation in the terms which it merits.

I turn now to Dr. Krause's letter, and take its paragraphs in order.

1. Dr. Krause implies that the knowledge of what I was doing could have had nothing to do with Mr. Darwin's desire to bring out a translation of his (Dr. Krause's) essay, inasmuch as Mr. Darwin informed him of his desire to have the essay translated "more than two months prior to the publication of" my book, "Evolution, Old and New." This, I have no doubt, is true, but it does not make against the assumption which I made in "Unconscious Memory," for "Evolution, Old and New," was *announced* fully ten weeks before it was published. It was first announced on February 22, 1879, as about to contain "copious extracts" from the works of Dr. Erasmus Darwin and a comparison of his theory with that of his grandson, Mr. Charles Darwin. This announcement would show Mr. Darwin very plainly what my book was likely to contain; but Dr. Krause does not say that Mr. Darwin wrote to him before February 22, 1879—presumably because he cannot do so. I assumed that Mr. Darwin wrote somewhere about March 1, which would still be "more than two months before" the publication of "Evolution, Old and New."

2. Dr. Krause says I assume that "Mr. Darwin had urged him to insert an underhand attack upon him (Mr. Butler)." I did not assume this; I did not believe it; I have not said anything that can be construed to this effect. I said that Dr. Krause's concluding sentence was an attack upon me; Dr. Krause admits this. I said that under the circumstances of Mr. Darwin's preface (which distinctly precluded the reader from believing that it could be meant for me) the attack was not an open, but a covert one; that it was spurious—not what through Mr. Darwin's preface it professed to be; that it was antedated; that it was therefore a spurious and covert attack upon an opponent interpolated into a revised edition, the revision of which had been concealed. This was what I said, but it is what neither Mr. Romanes nor Dr. Krause venture to deny. I neither thought nor implied that Mr. Darwin asked Dr. Krause to write the attack. This would not be at all in Mr. Darwin's manner.

3. Dr. Krause does not deny that he had my book before him when he was amending his article. He admits having taken a passage from it without acknowledgment. He calls a page and a half "a remark," I call it "a passage." He says he did not take a second passage. I did not say he had; I only said the second passage was "presumably" taken from my book, whereas the first "certainly" was so. The presumption was strong, for the passage in question was not in Dr. Krause's original article; it was in my book, which Dr. Krause admits to have had before him when amending his article, and it came out in the amended article; but if Dr. Krause says it is merely a coincidence, of course there is an end of the matter.

4. Dr. Krause, taking up the cudgels for Mr. Darwin, does not indeed deny the allegations I have made as to the covertness, and spuriousness, and antedating of the attack upon myself, but contends that "this is not due to design, but is simply the result of an oversight"; he is good enough to add that this oversight "could only be most agreeable" to myself. When I am not in the wrong I prefer my friends to keep as closely as they can to the facts, and to leave it to me to judge whether a modification of them would be "most agreeable" to me or no. What, I wonder, does Dr. Krause mean by oversight? Does he mean that Mr. Darwin did not know the conclusion of Dr. Krause's essay to be an attack upon myself? Dr. Krause says, "To every reader posted up in the subject this could not be doubtful," meaning, I suppose, that no one could doubt that I was the person aimed at. Does he mean to say Mr. Darwin did not know he was giving a revised article as an unrevised one? Does he mean that Mr. Darwin did not know he was saying what was not true when he said that my book appeared subsequently to what he was then giving to the public? Does he pretend that Mr. Darwin's case was not made apparently better and mine worse by the supposed oversight? If the contention of oversight is possible, surely Mr. Darwin would make it himself, and surely also he would have made it earlier? Granting for a moment that an author of Mr. Darwin's experience could be guilty of such an oversight, why did he not when it was first pointed out, more than twelve months since, take one of the many and easy means at his disposal of repairing in public the injury he had publicly inflicted? If he had done this he would have heard no more about the matter from me. As it was, he evaded my *gravamen*, and the only step he even proposed to take was made contingent upon a reprint of his book being called for. As a matter of fact a reprint has not been called for. Mr. Darwin's only excuse for what he had done, in his letter to myself, was that it was "so common a practice" for an author to take an opportunity of revising his work that "it never occurred" to him to state that Dr. Krause's article had been modified. It is doubtless a common practice for authors to revise their work, but it is not common when an attack upon an opponent is known to have been interpolated into a revised edition the revision of which is concealed, to state with every circumstance of distinctness that the attack was published prior to the work which it attacked.

To conclude: I suppose Mr. Romanes will maintain me to be so unimportant a person that Mr. Darwin has no call to bear in mind the first principles of fair play where I am concerned, just as we need keep no faith with the lower animals. If Mr. Darwin chooses to take this ground, and does not mind going on selling a book which contains a grave inaccuracy, advantageous to himself and prejudicial to another writer, without taking any steps to correct it, he is welcome to do so as far as I am concerned—he hurts himself more than he hurts me. But there is another aspect of the matter to which I am less indifferent: I refer to its bearing upon the standard of good faith and gentlemanly conduct which should prevail among Englishmen—and perhaps among Germans too. I maintain that Mr. Darwin's recent action and that of those who, like Mr. Romanes, defend it, has a lowering effect upon this standard. S. BUTLER

Geological Climates

WHEN a reader of the intelligence of Mr. Wallace misunderstands my words it becomes plain to me they have failed to convey my meaning. I do not accept the interpretation he has put upon them, nor do I admit that even that interpretation would tell so much in favour of his theory as he supposes.

As however I agree with him that the question is far too large to be fully discussed in your columns, I shall allow the controversy, so far as I am concerned, to terminate, and shall publish my detailed views on geological climate in another way. SAMUEL HAUGHTON

Trinity College, Dublin, January 27

On the Spectrum of Carbon

IN the discussions on the spectrum of carbon which have recently appeared in your journal much stress is laid on the impossibility of volatilising that substance by any heat which man can produce. I think this assumption is not warranted by experience. Two or three facts in Despretz' account of a remarkable set of experiments which he made about thirty years ago, seem to me to show it to be unfounded. This is given in the *Comptes rendus*, vol. xxviii. He exposed rods of anthracite to the action of 125 Bunsens (zincs 5¼ in. high) and also to the solar focus of an annular lens 36 in. diameter. The rods bent under the combined action, and even appeared to fuse! In vol. xxix. he describes experiments with rods of sugar-charcoal under a battery of 500 similar cells. The electric egg was covered suddenly with a hard block crystalline powder.

He thinks attempts to fuse carbon should be made in condensed nitrogen and in metallic vessels. In the same volume he says that with 600 cells rods of sugar-charcoal bend—swell at the

ends—and when they touch, weld together, and their surfaces become metallic, like graphite.

Diamonds heated in charcoal tubes were suddenly changed and became conductors. Still more remarkable effects were produced when he used collaterally with the 600 Bunsens 135 Muncké with zincs 13¾ in. high and 19¾ in. wide. With these sugar-charcoal was volatilised immediately.

I think it may be inferred from these facts that even at the temperature of a powerful electric arc enough charcoal vapour may be present to form its spectrum, and there is little doubt that the temperature of discharge of a good inductorium combined with a sufficient condenser is still hotter than the arc.

It is to be noticed that Despretz in these experiments anticipated Dr. Siemens's electric furnace. He mentions that he fused 3750 grains of platinum in a few minutes, and could have done more had he had a larger crucible. R.

A Case of Fascination

SOME years ago it was my fortune to witness a case of "fascination" between a large striped snake and a medium-sized toad. When first seen they were about fifteen inches apart. The snake lay in a coil with its head thrust out towards its victim, and moving slowly, its eyes glittering and its tongue darting incessantly.

The toad was standing on the very tips of its claws, with its limbs rigidly drawn up to their full length, its eyes fixed upon its captor and fairly bursting from their sockets, its mouth covered with foam, and its whole body swaying to and fro, and seeming just ready to pitch forward upon its face.

The movement of the snake became more and more rapid, and the agitation of the toad more intense, until the space between them was reduced to some three or four inches, when the snake opened wide its mouth, and the laboured breathing of its victim stopped short in a low guttural moan.

At this point my own agitation became so great that, seizing a heavy stone, I finished the snake at one blow. The instant the snake was struck the toad fell backward as suddenly as though itself had been hit, and lay upon its back for some minutes with no signs of life. At length it gained its feet and began to creep languidly away. J. T. BROWNELL

Lyons, N.Y., January 18

Birds Laying in January

As a proof of the unusual mildness of the weather just previous to the intense frost and severe snowstorms most parts of the country have lately been suffering from, it may interest some of your readers to learn that not far from this place, on the 13th Jan., a wren's nest with seven eggs in it, quite fresh, was taken. The nest I have in my possession, and it bears every evidence of having been lately tenanted. The eggs, I am sorry to say, are broken; they were placed in a cup for safety, and were most unfortunately knocked down when the room was dusted, giving however unmistakable proof of their having been but lately laid.

I do not know whether there is any instance on record of a wren's nest having been found in January before.

JOHN H. WILLMORE

Queenwood College, near Stockbridge, Hants, January 28

Vibration of Telegraph Wires during Frost

WHILE walking with my son by the Liverpool, Crosby, and Southport Railway between Crosby and Hall Road stations he called my attention to the telegraph wires, which were in a state of rapid vibration. The day was frosty, the time 11.30 a.m., and the sun, which had been showing us a bright disk through the haze, was beginning to throw out rays and shine a little strongly. At first I thought the movement must be only apparent—a mere optical delusion—as the air was perfectly calm. A closer examination convinced me to the contrary, as the under part of the wires were covered with pendant ice needles, a sort of rime, which moved to and fro indicating a torsional or twisting vibration of the wires, and as the rapidity of the vibrations decreased this was more clearly seen. In about five minutes the movement ceased, and I have not noticed it since, though I have frequently passed under the wires on my way to skate. Can any of your correspondents account for the phenomenon? It appeared as if in some way connected with previous contraction by the frost and sudden expansion in jerks by the sun's rays. My son informs me that two years ago, during a frost, he noticed the strained wires of a garden-fence behaving in the same curious way.

Park Corner, Blundellsands T. MELLARD READE

"Mock Sun"

I SEND a sketch of a parhelion which I saw from the East Cliff, Hastings, on Thursday, January 20, at 3 p.m. The crescents above the sun were fairly bright and well developed, and there were faint traces of a *second* ring outside, and some distance from, the first.



There was a slight fog at the time, with a north-east wind and *hard frost*, which has continued up to this time. We have had no snow here since that "terrible Tuesday," the 18th.

I do not remember ever having seen this phenomenon before, except in pictures of the Arctic Regions.

St. Leonards, January 24 J. E. H. PEYTON

ON SOME RECENT CHARTS AND MAPS OF CURVES OF EQUAL MAGNETIC VARIATION OR DECLINATION

SINCE the year 1701, when Halley published his famous chart showing curves of equal magnetic variation for the Atlantic and Indian Oceans, the construction of similar charts, amended and enlarged as data increased, has been of great interest to magnetic science and of practical value to the navigator.

Halley's chart of 1701 was expanded to embrace the navigable parts of the whole world, and brought up to the epoch 1756 by Mountaine and Dodson, whose labours were followed by those of Churchman in 1794, Yeates in 1817, and Hansteen (for several distinct epochs between 1600 and 1787) in 1819. In 1833 Barlow's chart, together with curves for the North Polar regions, accompanied a descriptive paper in the *Phil. Trans.* for that year.

In 1840 Gauss and Weber's charts of theoretical curves of the three magnetic elements for the whole world, including special Polar charts, were published. These curves were culculated on the basis of a mathematical theory founded upon a large number of observations fairly distributed over the surface of the globe.

About this latter period the practice of ascertaining the errors of the compass on shipboard (as due to the effects of iron) for every ship in the Royal Navy, at certain periods and on change of magnetic latitude, was established by the Admiralty on the recommendation of a compass committee specially appointed to consider the question of compass efficiency and management. This, as bearing on the subject under review, was an important step towards obtaining reliable data for the construction of Variation charts now becoming so essential an element in navigation.

Following on this, Archibald Smith's mathematical investigations of the theory of the deviations of the compass on board ship enabled Sabine to correct observations made in the Atlantic and the Antarctic Oceans

with great precision. The charts accompanying Sabine's "Contributions to Terrestrial Magnetism," No. ix. (*Phil. Trans.* 1849), were among the earliest on which the data whence the curves were drawn are recorded, although it may be observed that even a portion of the observations made at sea and utilised in these charts had no corrections applied to them for the effects of the ship's iron.

Considering the local magnetic disturbance found to exist on land in many regions and the large area of water-covered portions of the globe, observations made at sea, when systematically carried out and corrected for local attraction in the ship, have become an important factor in ascertaining the magnetic variation for the use of navigators at any given epoch.

Evans's Variation chart for the epoch 1858, embracing the navigable parts of the world, and in which the whole of the observations made at sea were corrected for the effects of the ship's iron, was published by the Admiralty. A further advance on Variation charts of an earlier date was the addition to this of a map showing the amount of annual change of the variation as determined at several localities, enabling reductions for the succeeding ten years to be made with a reasonable approach to the truth.

The increase of iron-built and composite vessels in late years has rendered a reliable Variation chart a necessary adjunct to navigation. This object appears to have been kept steadily in view by the Hydrographic Department of the Admiralty, for, in 1871, a new edition of the "Variation Chart of the World," reduced to that epoch (with polar charts added) was published in continuation of the chart for 1858. This chart was the result of the joint labours of Capt. Evans and a member of the compass department, Navigating-Lieut. Creak, R.N.

We have now to notice the more recent publications of these contributions to terrestrial magnetism. A chart of the curves for 1880, in continuation of those for the epochs 1858 and 1871, by Staff-Commander Creak, has been published by the Admiralty. In its construction the observations made during the voyage of H.M.S. *Challenger* (1872-76) have been introduced, and amongst results from other sources, specially those taken from Mr. A. Schott's papers on the secular change of the variation published as Appendix No. 8 to the U.S. Coast Survey Report for 1874, and also as a preliminary publication to the Report for 1879; Dr. Thorpe's observations in the United States, made about the 40th parallel of latitude, and results from the maps of the excellent magnetic survey of a large portion of the Eastern Archipelago in 1874-77, made by Dr. Rijckevorsel, have also been included.

As confined to special portions of the world a map of the United States for the epoch 1875, constructed by Mr. J. E. Hilgard, Assistant U.S. coast and geodetic surveys, published in the *American Journal of Science* for March, 1880, and illustrating an article on the subject of magnetic variation or declination, is of a high order of excellence.

In this map the curves, which show several flexures strictly pourtraying results arising from local disturbance, have been drawn for every degree of [equal] variation. The results are from observations made during the progress of the U.S. Coast Survey up to 1877, also from about 200 observations made in the interior of the country under the direction of Mr. Hilgard, to which were added every available observation from the land and boundary surveys, as well as those of private observers. Many of these results having been obtained at different periods of time, have been reduced to the given epoch by means of Mr. A. Schott's paper on Secular Change before referred to.

Although in maps and charts covering large geographical areas the variation lines for the land portions are generally drawn in regular curves (and so far deviating from strict accuracy), whilst those for the larger sea areas are necessarily so done, still in delineating the magnetic features of a portion of a continent the system followed by Mr. Hilgard, as also by Lamont in his European surveys between 1850 and 1860, commends itself for accuracy.

The late Prof. A. D. Bache, who took a personal interest in the study of terrestrial magnetism, bequeathed a fund for scientific research. The expenses of obtaining the 200 observations in the interior of the United States before mentioned, were defrayed by a grant from this fund.

THE ZOOLOGICAL STATION AT NAPLES

"WHAT *is* a zoological station?" is a question we have often heard asked when Dr. Dohrn's institution at Naples is under discussion. A "zoological station" (according to Dr. Dohrn), we may reply, is a kind of zoological garden for marine animals, or what is commonly called an "aquarium," only that, contrary to the usual practice at Brighton, Westminster, and elsewhere, the scientific element of the establishment is mostly cultivated instead of the popular branch. Such at least is the case under Dr. Dohrn's system, and also, we believe, in other zoological stations that have been formed after his example.

It must be recollected that the lower forms of organic life, to the study of which zoological stations, as thus described, are mainly devoted, are much more numerous than the vertebrata, and much less understood. Even in our own seas a vast amount remains to be done before our knowledge of the thousands of marine organisms which populate our waters and shores can be deemed to be anything like complete. Still more is this the case in the Mediterranean, where under a bright sky and burning sun the clear waters teem with animal life in all its varieties. It was no doubt the well-known productiveness of the coast of Naples and the facilities offered for dredging in its land-locked Bay that induced Dr. Dohrn to fix his "Zoological Station" in this quarter instead of planting it on the shores of his Fatherland.

After several years of incessant labour Dr. Dohrn has got his establishment into excellent working order, and, as will be seen by our advertisement pages, promises us after so much cultivation a rich and abundant harvest. The proper subject to take up when the publication of results was determined upon was obviously the Biology of the Bay of Naples. Great difficulties however beset the advance of this project. As regards the Fishes, the more highly-organised Crustaceans, the Mollusca, and some of the Cœlenterata and Echinodermata, it appeared possible for the students at the Zoological Station to avail themselves largely of the results arrived at by former workers. But when they proceeded to examine into the scattered literature in which the innumerable armies of Lower Crustaceans, Annelids, Nemertians, Planarians, Nematodes, and such-like creatures are described, the case was very different. The ancient naturalists have mostly characterised their species in these groups in such vague diagnoses that it is impossible to identify them. Under such circumstances the students of the higher animals are accustomed to resort to the type-specimens whence the descriptions were taken in order to see what the authors really intended. But the impossibility of preserving many of the lower animals cuts this resource away from the marine zoologists, who have consequently contented themselves in some instances with referring their specimens to species never sufficiently described, in other cases with describing them as new. Hence has arisen a mass of confusion which can be only regarded as parallel to what existed among the more highly-organised animals in the ante-Linnean period. The transformations undergone by many of the lower marine animals and the extraordinary sexual differences add

greatly to the difficulties already spoken of. Even when an animal of one form is gravely suspected to be merely the immature stage or corresponding sex of another form it is most difficult to prove it, and it frequently requires a whole series of researches conducted by practised biologists with logical exactitude to show that such is really the case.

Under these circumstances, even with the now rich collections and well-stored library of the Zoological Station, it was a serious question how the proposed "History of the Life of the Bay of Naples" could be best accomplished. Dr. Dohrn has wisely adopted the project of attacking the fortress by a number of small approaches. By dividing the labour into a large series of restricted monographs he hopes finally to accomplish a complete account of the fauna and flora of the Bay of Naples. In the first place, under this system each of his assistants can thus take up the group he is most familiar with, and work it out. Then in this way he is likewise able to secure the contributions of various naturalists who pay temporary visits to the Zoological Station, but who would not bind themselves to join in an extensive general work on the whole subject.

It will be seen by reference to our advertising columns that Dr. Dohrn's scheme thus elaborated is now on the eve of execution. Two of the proposed monographic memoirs on the Ctenophoræ by Dr. Cheen of Leipsic, and on the Fishes of the genus *Fierasfer*, by Prof. Emery of Cagliari, are already issued, and three other memoirs are announced as being in preparation for the present year. Dr. Dohrn is quite cosmopolitan in his arrangements. Though, as might have been expected, the greater number of his fellow-workers are natives of the Fatherland, he has many Italian co-operators, and the monographs may be written in German, Italian, English, or French. It is with some regret we observe that no English naturalist is yet on the list of contributors, although, as is well known, many of our countrymen have done good work on Dr. Dohrn's "tables." We trust that English recruits may still be enlisted in so good a cause, and that the "Fauna and Flora of the Bay of Naples" may attain to a goodly list of subscribers, and be brought to a satisfactory conclusion.

CHARLES FREDERIC KUHLMANN

WE regret to record the death, at Lille, during the past week, of Charles F. Kuhlmann, the distinguished French chemist and economist. Born at Colmar, May 22, 1803, he pursued his scientific studies under Vauguelin at Strassburg, and later at Paris. In 1832 he was appointed Professor of Applied Chemistry at Lille. Soon after he devoted himself almost exclusively to the practical solution of the problems of manufacturing chemistry, and established at Lille extensive works, which rank to-day among the important chemical manufactories of the world. During the past forty years he has been a prominent figure in the industrial, scientific, and even political circles of France, attracting general admiration by a remarkable combination of inventive power and executive ability. The Government named him Commander of the Légion d'Honneur, and the French Academy of Sciences elected him a corresponding member, in recognition of his important services, while he was frequently called upon to occupy prominent posts of responsibility in public life and commercial undertakings. His failing health during the past year forced him to decline one of the leading honours in the scientific world of France, the presidency of the Société Française pour l'Avancement des Sciences.

As an investigator Kuhlmann was a prominent member of that group of Alsatian chemists which includes Wurtz, Friedel, and Schützenberger, and forms the chief school of modern French chemistry. His researches, extending over nearly every department of inorganic chemistry, and touching on the tinctorial branches of organic chemistry, are characterised by a broad range of knowledge, a happy application of fact and theory, and a marked reverence for the demands of pure chemistry, while contributing so notably to the advancement of applied science.

First among his great researches mention should be made of that on baryta compounds, made over twenty years since, and by means of which he created the entire industry of this important group of salts. Another investigation, scarcely less valuable, was that made a few years previously, which led to the introduction of the process of saturation in the manufacture of sugar. Equally prolific of practical results were his extensive studies on the crystallisation of insoluble bodies, on the chemistry of mortars and cements, of manures, of bleaching, of dyeing and printing, and of numerous other branches. Especially interesting were his researches (1847) on the formation of nitric acid from ammonia, and on the relation of this reaction to the fertility of the soil. Among his more purely scientific investigations mention should be made of those on the formation of ethers, on the formation of cyanides and of prussic acid, on nitrous oxide, on the use of oxide of iron as an oxidising agent for organic compounds, on the action of gases on minerals, on the use of gaseous hydrofluoric acid for the analysis of silicates, and on a variety of minerals. The subject of crystallisation was throughout his career of investigation one of Kuhlmann's favourites, and we are indebted to him for the artificial reproduction of a variety of natural minerals, the most novel of which are the pseudomorphic forms of protoxide of manganese, of the sulphides of copper and lead, and of these metals themselves.

In 1879 Kuhlmann gathered together his numerous researches, extending over a period of forty years, into a volume of 750 pages, in which we have a remarkable picture of his many-sided and untiring activity.

The deceased leaves behind him a son who has already obtained a name as a chemist, and who made an able report to the French Government on the Chemical Section of the Philadelphia Exhibition. T. H. N.

THE SCIENTIFIC SOCIETIES OF DUBLIN

OF the scientific societies of Dublin two take special rank as publishing societies; but from inquiries made of us we conclude that their publications are not everywhere known.

The Royal Irish Academy issues both *Transactions* of a quarto size and *Proceedings* in octavo. Of its series of *Transactions* 26 volumes have been published. Of these vols. 1 to 23 contained memoirs chiefly on Science, but occasionally on Polite Literature and Antiquities. Vol. 24 was divided into two sections—the first, Science; the second, Polite Literature and Antiquities. Vols. 25 and 26 were exclusively Science. Vol. 27, in course of publication, is devoted to Polite Literature and Antiquities; and vol. 28, which also is in course of publication, is devoted to Science. These quarto volumes contain from 600 to 700 pages each, with numerous plates and other illustrations. To give some idea of their contents we add the following analysis of vol. 26. It contains papers on Astronomical Subjects by Dr. Doberck (2), J. Birmingham, J. L. E. Dreyer, and C. E. Burton; on Meteorological Subjects, by Dr. H. Lloyd; on Geological Subjects, by Rev. Dr. S. Haughton, Dr. E. Hull, Dr. A. Leith Adams, and Prof. O'Reilly (2); on Mathematical Subjects, by J. C. Malet (3), Dr. A. S. Hart, Dr. J. Casey; on Biological Subjects, by Dr. R. J. Harvey, Dr. E. P. Wright (4), and W. H. Mackintosh; on Chemical Subjects, by H. N. Draper and R. J. Moss. The memoirs which form the volumes of *Transactions* are published shortly after they are read, and without waiting to form a part of a volume. The *Proceedings*, like the *Transac-*

tions, now also form two series: the Science Parts being published twice a year, in December and April, and the Polite Literature and Antiquary Part once a year, in December. Quite recently the Academy have determined to publish another series of quarto *Transactions* under the title of "The Cunningham Memoirs," part 1 of the first volume of which, containing a memoir by Dr. John Casey, F.R.S., on Cubic Transformations, has just appeared.

The publications of the Royal Dublin Society are of the same type as those of the Irish Academy, except that they are exclusively confined to science. Of their new series of *Transactions*, parts 1 to 13 of volume 1 have been published, and for convenience of publication the first two parts of volume 2, containing "Observations of Nebulæ and Star Clusters, 1848–1878," by the Earl of Rosse, have also appeared. The first two volumes of these *Proceedings* have been published, and a part makes its appearance pretty regularly every third month. Following the example of the Academy, the memoirs forming the *Transactions* are published separately.

It would thus appear that not only is there evidence of scientific life among the societies of Dublin, but that there is also an abundant opportunity for the publication of any really valuable scientific information, and so far at least as the publications of the Irish Academy are concerned they fall in no respect as regards type, paper, or illustrations, behind the best of our London societies.

JOHN DUNCAN

ALONG with a cheque for 5*l.* to John Duncan, whose story was told by Mr. W. Jolly in NATURE of January 20, we have received the following note from Mr. W. Westgarth:—

January 27, 1881

DEAR SIR,—On reading the account of John Duncan in your last week's issue, it occurred to me that surely your readers would respond to your invitation to get up a small fund, say of 100*l.* to 200*l.*, for the brave old man who has so long and perseveringly fought, and against all "odds," for the cause of science and mind. I enclose 5*l.* towards the object. Should you see objections to opening a list in NATURE, please send on my small dole to Mr. Jolly as he directs. W. WESTGARTH

We have the greatest pleasure in acting upon Mr. Westgarth's hint, and we trust that many of our readers will be prompt to follow his good example. Subscriptions addressed to the Editor of NATURE, 30, Bedford Street, Covent Garden, W.C., will be duly forwarded. We have already received the following:—

	£	s.	d.
W. Westgarth	5	0	0
Publishers of NATURE	5	5	0
F.R.S.	0	10	0
Mrs. Forster	1	0	0

CASSELL'S NATURAL HISTORY[1]

THE third volume of this useful cyclopædia of zoology consists of the concluding portion of the Birds by R. Bowdler Sharpe, and of the Reptiles and Amphibia by the Editor. On glancing over the well-printed and beautifully-illustrated pages, a few facts have struck us, to which, for the benefit of the series, we would call the editor's attention. In the opening sentence of Chapter I. of this volume we are referred to "the preceding chapters" for an account of the Picarian birds. The context proves it should be to the preceding volume. This, which might mislead the reader, is evidently the result of the publication of the work in parts, and could be easily avoided.

All through Mr. Sharpe's portion of the work, when the scientific names of birds are referred to they are quoted generally within brackets in the same line as the popular name; while in the editor's special portion no such useful uniformity is attended to. Sometimes, as on p. 245, the eye has to wander from the text to foot-notes at the bottom of the page; sometimes, as at p. 248, the name is quoted after Mr. Sharpe's fashion (for a mixture of both styles see p. 362). The use of the word "kind," when the editor refers to "species," is in our judgment, though perhaps sanctioned by its use in the English translation of the Bible, not happy. Thus we read that, while genera among the reptiles are abundant, "kinds" are numerous. The "kinds" of some families swim freely; some "kinds" have a skin; by the way, what kind of a reptile be it that has *no* skin? In other cases the word "member" instead of species is used. Is it not a mistake to say that in many Chelonians "the well-known 'tortoise-shell' covers over all the hind parts." Surely in *Caretta squamosa* the tortoise-shell plates cover over most of the carapace. While the families of the Chelonian order are given, we find, when we come to the Lacertine order, no intelligible mention of the families of the split-tongued lizards. In referring to the important paper on Archæopteryx by the Professor of Geneva, the editor ought to have seen that the name of Carl Vogt was correctly spelled. The divisions of the Snakes is such as must necessarily confuse any student. The sub-order Thanatophidia is made to include two sub-orders in the text, when in the table of classification one of these sub-orders, Solenoglypha, is called a family. The groove-fanged Opisthoglypha are included with the Aglyphodontia with solid teeth. In a work of this nature nothing is, we take it, of more importance than that there should be some well-defined system of classification, not necessarily to be treated of in full detail, but as far as is possible to be rigidly adhered to. That this is possible, a glance over the sections of this and the previous volume treating of Birds will abundantly demonstrate; and that this is practicable, even with an extreme compression of space, is also to be proved by an appeal to the way in which the eighth order of Birds is managed, where, though only three pages were allowed to this most interesting and important of orders, yet we are even in these few lines enabled to get an idea of the orderly sequence of its families. This work is in many ways so excellent, that we venture on these criticisms with the object of trying to keep it up to a fairly good standard, and of making it useful in some measure as a work of reference.

As specimens of the excellent illustrations in this volume we have, through the courtesy of the publishers, the opportunity of presenting to our readers the two following. The Common Quail (*Coturnix dactylisonans*) visits Europe in the summer, when prodigious numbers are trapped and sold for purposes of food. Waterton mentions that 17,000 specimens were brought to Rome in one day. They are to be found in large quantities on the coasts of the Mediterranean, and so abundant are they in the beautiful Island of Capri, that it is said that it was from this source that the bishops in the olden times derived a large part of their wealth. The Quail is most rapid in its flight, and performs long and fatiguing journeys. Sunset is its time for active exertion; during the day it remains quite quiet, reserving its energies for the evening, when it goes off in quest of food.

Their favourite nourishment is insects, but at times they feed on grain and seeds; small stones are also swallowed to facilitate digestion. The habits of the quail are most unamiable and unsocial, and generally, when they meet with one of their own species, they display a very pugnacious disposition. The female has a much better nature; she is a most excellent mother, even protecting young birds who have been deprived of their parents' care. She builds her nest of small portions of plants, and lays eight to fourteen eggs; these are pear-

[1] "Cassell's Natural History." Edited by Prof. P. Martin Duncan, M.B., F.R.S. Vol. III. (London, Paris, and New York: Cassell, Petter, Galpin, and Co., 1880.)

shaped in form, of a light-brown colour, marked with a darker shade; the young seem full-grown when only six months old, and are ready to join their parents in their long autumn journey, which may extend as far as the Cape of Good Hope, where they are known to arrive in large numbers. The quail, unlike the partridge, also figured in our illustration, has several wives, and displays great spirit in keeping rivals at a distance; while the mother is attending to the care of her young ones, the cock bird, too, often amuses himself in the vicinity with his companions.

Our second illustration is taken from the higher of the two classes of the Ichthyopsida, known as the Amphibia; these skull-bearing animals have no amnion and but a rudimentary allantois, and they breathe by gills at some period of their life. In this volume they are placed as an independent class alongside of the Sauropsidian reptiles. Among the permanently tailed Amphibians (Urodela) the sub-order containing those species with gills that fall off (*Cryptobranchiata*) contains the interesting species known as Salamanders. It is of one of these of which we give the accompanying figure, not only as a fair specimen of those in the volume we are reviewing, but also in the hope of awakening some interest in a rather uncommon

FIG. 1.—The Partridge and the common Quail.

Amphibian. "The next genus [to Salamandra], Pleurodeles, has *short* ribs, which give the appearance as if they penetrated the flanks, but their ends come against the tissue under the skin and produce horny projections thereon. The tail is long and compressed, and the small *tongue is adherent only in front*, and there are two series of palatine teeth in longitudinal series. The Spanish kind (*P. Waltlii*) has an ashy grey body, very prettily marked with long transverse stripes and dots. It is like a heavy lizard." Lord Cernuti, in his useful work on the Reptiles of Europe, describes the tongue as small, warty, free behind and on the sides, adhering in front; he also describes the ribs as piercing the skin, and they are also said by some to be capped by horny tubercles; but this is denied by Leydig. Prof. St. George Mivart tells us that this species differs from all the other Urodela in the length and strength of its ribs, the longer ones considerably exceeding the length of two of the longest vertebræ of the body. M. Wiegmann first discovered it at Chiclana in Spain; Schinz states that it is very common in Andalusia in tanks and cisterns of water; Wallace gives its distribution as Spain, Portugal, and Morocco. Lord Cernuti hints that the Pleurodeles inhabitants of Tschud is probably the young of this species.

Now when Lord Cernuti wrote his book there was not much more known about this interesting animal,

but some sixteen months ago Dr. F. Leydig of Bonn published an excellent account of it in *Wiegmann's Archiv*, in which he gives a short account of Dr. Joseph Waltl, who first discovered Pleurodeles, and of the gallant Dr. Michahelles, who called it after his friend, its discoverer (1830). Among the specimens sent to Bonn, one was living, and in it could be easily seen the tips of some of the ribs sticking through the skin; and that "this penetration" of the skin of the sides was not in the first instance caused by or through the transport, the accompanying note from the kind sender proved. "You will remark that in the Pleurodeles the ribs pierce the integuments, and that if this be an accident, it is in some sort a physiological one." The habits of the Pleurodeles seem to be more or less like that of our native Tritons. During the procreative season they remain upright in the water; later they leave it and hide themselves in damp places under stones. Like the Water Newts, they possess a sort of cry; when frightened, as on being suddenly seized, they emit a low, short, almost squeaking sound, generally repeated several times. This seemed to come not so much from the throat as to be caused by a rapid expulsion of air through the openings of the nose—in fact, to be a sort of snort.



FIG. 2.—*Pleurodeles Waltlii*

It had a tendency to crawl vigorously backward when uneasy, by prising the ends of the ribs against the skin: this snake-like progression no doubt causing the skin openings. Prof. Leydig's specimen lived on slugs of small size, which it took eagerly as well as worms, indeed preferring these latter. The skin surface was rather dry than clammy. The colour changes through the chromatophores were clearly to be noticed; during cold weather it was of a tolerably uniform dark, when warmer the colour became lighter, numerous dark spots standing out from a light gray ground colour. On very warm days it would lie for hours motionless on the surface of the water.

It would almost seem worth one's while to pay a visit to those Andalusian tanks, and by their semi-limpid sides and under the shelter of their surrounding fig and olive-trees work out the complete history of this interesting little form.

These woodcuts will show that in point of illustration this volume keeps up with both its predecessors in effect; while we have gently hinted at a few blemishes, the work deserves a very considerable mead of praise, and we heartily recommend it as an excellent volume to be placed in the hands of all interested in the animal kingdom.

NOTES

THE *Akhbar* published a programme of the excursions which have been arranged for the next session of the French Association at Algiers on April 14. The excursions are very numerous, and are classified according to the length of time required for their completion. One of the most attractive in the vicinity of Algiers is the tomb of the Kings of Mauritania; Laghouat and the desert is one of the most protracted, and requires eight days for its completion. The travellers will enjoy unexampled facilities for visiting the country. The seat of the French Association is 76, rue de Rennes, Paris. Applications are to be made to M. Gariel, Professor of Physics to the École de Medicine, permanent secretary. A reduction of 50 per cent. has been granted by the railway companies; the arrangements made for the sea passage will be published in proper time. An influential local committee has been established in Algiers. M. Chauveau, Professor to the Veterinary School of Lyons, has been appointed president of the session; the vice-president is M. Janssen.

MINERALOGICAL science has suffered a great loss by the early death, on January 27, of Prof. Dr. Emanuel Boricky, who was well known by his microscopical researches in petrography. Boricky was born at Milín, near Príbram (Bohemia) in the year 1840, and he had therefore just completed his fortieth year. In 1865 he became an assistant of the mineralogical section of the Bohemian Museum, and in 1866 he was named Assistant Professor of Mineralogy at the University of Prague. Having attained the degree of a Doctor of Philosophy, he became a teacher of mineralogy at one of the colleges of Prague in 1868, and in 1869 he was promoted to the post of a custos of the mineralogical collections at the museum. Since 1871 he ha

lectured in the Bohemian language on petrography at the University of Prague. He was a diligent and successful worker in science, and his microscopical researches have made his name familiar to mineralogists far beyond the boundaries of his native country. He has left a monograph on the porphyries ready for printing. Science has lost in him a devoted student, and the Bohemian nation regrets the death of one of its best sons.

THE *Times* announces the death of Mr. William White, a well-known chemist and mining authority. Mr. White was the author of numerous works, including the "History of Chemistry," "Economy of Health," "Chemistry of Vegetation," "Chemistry for Students," "Hints from a Chemist," "Mineral Resources of Newfoundland," &c, and was for over half a century a constant contributor to scientific literature. He had held at different periods lectureships on metallurgy and chemistry at various educational establishments, and had earned for himself a reputation as a lecturer and writer on agricultural chemistry. He died in London on Sunday last, at the age of seventy-one, from a painful disease contracted while conducting experiments in his laboratory.

THE Prussian Government, according to Berlin papers, intends to purchase the Godeffroy Museum at Hamburg for the Berlin Anthropological Museum. The former is one of the most interesting zoological and anthropological collections, particularly with regard to Eastern Asia and the islands of the Pacific; it was formed by the Hamburg firm of that name by means of special scientific expeditions during the last decades.

THE Senatus of Glasgow University has just been presented with a portrait of the Very Rev. Principal Caird, the esteemed head of the University, and Mrs. Caird with a replica. The portraits are the gift of subscribers belonging to all religious and political parties, and are the works of Mr. Millais, R.A. The Principal is represented in academic dress, and the likeness is very striking. The portrait presented to the Senatus will be placed in the University library, the walls of which are already adorned with likenesses of former principals and professors.

M. MARIETTE, better known as Mariette Bey, the celebrated Egyptologist, has died in Alexandria. M. Maspero, his pupil, Professor of Egyptology to the Collège de France in Paris, has been appointed by the Egyptian Government to fill the place vacated by the death of M. Mariette.

A PROPOSITION has been made by the *Operator* and other electrical papers of the United States to open at New York an international exhibition of electricity in 1882. It is stated that the United States Congress will vote a sum of money to subsidise the American exhibitors at the exhibition of this year in Paris.

THE Royal Commission appointed in 1879 to inquire into the cause of accidents in mines have concluded the taking of evidence. The attention of the Commission is now directed to a series of experiments as to the explosive nature of coal dust, as to the best kind of safety lamp, and as to other matters designed to elucidate the causes of explosions. It is proposed that some experiments shall take place to test the efficacy of the electric light as an illuminating power in mines.

THE Committee formed for the exploration of the remarkable holes, which have recently appeared on the surface of Blackheath, have been negotiating with an experienced well-sinker, and intend to commence active operations in the course of a few days in the hope of finding a clue to their origin. Contributions in aid of the work, from persons interested in the investigation, will be gladly received by the honorary treasurers of the Committee—Dr. Prior Purvis, Landstown Place, Blackheath, or Mr. E. W. Brabrook, F.S.A., director of the Anthropological Institute, 28, Abingdon Street, Westminster.

ORDINARY MEETINGS of the Sanitary Institute of Great Britain, 9, Conduit Street, W., for the reading of papers and discussion upon sanitary matters, will be held during 1881 on the second Wednesday in the months of February, April, and June, chair to be taken at eight o'clock precisely. At the first meeting, February 9, a paper will be read by W. H. Michael, Q.C., upon "The Law in Relation to Sanitary Progress," to be followed by a discussion.

AN earthquake was felt over a considerable area of Switzerland on January 27. It was felt with varying degrees of intensity at Berne, Muensingen, Thun, Basle, Solothurn, Zurich, Bienne, Oberhofen, and Aarberg. The principal shock occurred at 2.20 in the afternoon, Berne mean time. A slight shock was observed at three o'clock the same day, and another equally slight at six the following Friday morning. According to a report of the Berne Observatory the first and principal shock was in the direction from east to west, with a slight northerly deviation. The oscillation was both vertical and lateral, and according to some accounts, was preceded by a rumbling subterranean sound. Its intensity may be judged from the facts that the chimes in the church clocks were made to strike and the bells to toll, books were thrown from their shelves, and pictures detached from the walls, while in Berne alone more than 100 chimneys were thrown down. This is the twenty-fourth earthquake that has been recorded in Switzerland since November, 1879, and is probably the most severe.

A SHOCK of an earthquake was felt at 5 p.m. on January 24 at Bologna, Florence, Venice, Padua, Ferrara, &c. At Bologna there were also slighter shocks at midnight, and at 8 and 9.15 a.m. next day; while Florence likewise had a second shock at 7.53 a.m. on the 25th.

IN a recent number of the *Journal de Physique*, of which the late M. d'Almeida was so long the editor, the following interesting episode is narrated:—During the investment and siege of Paris by the German armies in the winter of 1870-71 M. d'Almeida took a prominent part in certain attempts to re-establish telegraphic communication between Paris and the provinces, using the River Seine as a conductor. This suggestion originated with M. Bourbouze (of galvanometer fame), who was, after the war, created a chevalier for his suggestion. It was proposed to send powerful currents into the River Seine from batteries at the nearest available point outside the German lines, and to receive in Paris, by delicate galvanometers, from the river such a portion of these currents as might not have leaked into the earth. After some preliminary experiments had been made between the Hôtel de Ville and the manufactory of M. Claparède at St. Denis, by Professors Desains, Jamin, and Berthelot, it was decided to make the attempt, and accordingly on December 17, 1870, M. d'Almeida was despatched by balloon to the provinces in order to try to establish this novel mode of telegraphy without wires. The balloon descended after sundry perils in the Arcadian solitudes of Champagne outside the Prussian lines. Thence he proceeded *viâ* Lyons and Bordeaux to Havre. Not finding suitable appliances and apparatus, there was again a delay in sending to England for the necessaries, which on arrival were conveyed to Poissy, where M. d'Almeida regained the banks of the Seine on January 14, 1871. Here however the frost proved inimical, the river having been frozen hard since the beginning of December. The attempts at communication were however to have been made on January 24, when the armistice was proclaimed. It was too late; and the world missed a famous scientific exploit from amongst those which made the siege of Paris notable beyond all other sieges of history.

M. JULES FERRY, French Minister of Public Instruction, and M. Tirard, Minister of Agriculture and Commerce, paid an

official visit the other day to the schools of apprenticeship established at the expense of the City of Paris in the rue Herold and the boulevard of La Villette. The time required for the scientific education of the young workmen is three years. During the first year the pupils are trained in working wood as well as iron. The choice of the speciality is only made at the beginning of the second year. No work is executed without a drawing having been made, so that the workman is enabled to understand the use of the object he is manufacturing. Regular courses of lectures are given in the establishment on scientific subjects. Meanwhile experiments are conducted in three different primary schools, to determine whether it is possible to join manual to mental training in all the city schools.

PROF. HULL has published a fourth edition of his "Coal-Fields of Great Britain" (Stanford). This edition has been largely rewritten, and contains an entirely new chapter on Carboniferous Plants, by Prof. Williamson, F.R.S. The Classification of the Carboniferous Series of Beds has been modified in accordance with the views enunciated in Prof. Hull's paper on this subject read before the Geological Society in 1877. Various other modifications have been made in accordance with the results of recent geological research, and the statistical portions have been brought down to 1878.

MESSRS. LONGMANS AND CO. send us the fourth edition of Prof. Atkinson's "Natural Philosophy for General Readers and Young Persons," translated and edited from Ganot's French work. To this edition have been added twenty-five pages of new matter and sixteen additional illustrations.

MR. E. S. BAKER, photographer of Bristol, sends us a photograph of a jar, which is a fine illustration of the fact that water expands on freezing. During the recent frost the water in the jar froze, and the ice is seen protruding from its mouth to a considerable distance like a well-shaped cork.

MR. C. V. RILEY of 1700, Thirteenth Street, Washington, writes to us that, having been obliged to cease the publication of the *American Entomologist*, he has a few full sets of vol. iii., just closed, to dispose of, and has concluded to send the full volume to all former subscribers who may want it, or to any Library, Natural History Association, or editor of journal, postage prepaid, at the reduced price of $1.50. The information in the magazine, Mr. Riley states, is of permanent interest, and the volume will be of value to any one interested in entomology in any of its bearings.

M. CH. JOLY has republished as a pamphlet a paper which he lately contributed to the *Journal* of the National Horticultural Society of France, under the title of "Note sur une Exposition de Géographie botanique et horticole, organisée par la Société Centrale d'Horticulture de Nancy."

NEW SOUTH WALES, Victoria, and South Australia have agreed to jointly bear the expense of exterminating the *Phylloxera vastatrix*, the alarming extension of which in Victoria has threatened the destruction of the wine industry.

WE have received the three first numbers for this year of the *Chicago Field*, which seems modelled on a small scale after its well-known English contemporary.

THE *Revue Scientifique* of January 29 contains a lecture recently given at the Sorbonne by M. Faye, on the Volcanoes of the Moon.

AT Cracow a new Polish review for literature, science, and art is now being published fortnightly. Its title is *Museum*, and its editor Dr. Thaddaeus Rutowski.

THE works in the Arlberg tunnel are progressing. On the Tyrolese side the lower shaft has been pushed to a distance of 340 metres, by help of the boring machines, and in spite of the hardness of the rock the daily progress is two metres. The upper shaft is some 100 metres behind.

A NUMBER of Roman antiquities were found last year during some military earthwork operations near Metz, close to the Lunette d'Arçon. It appears that the place was one of the most important burial-places of Roman Metz. The Metz Geological and Archæological Society gave the details at its last December meeting. Some thirty-five vases, four metal objects, three coins, and two tombstones with inscriptions are mentioned. Of human remains four skulls were found, one of which was lying upon a square stone plate, besides carbonised (cremated?) bone remains in a round stone urn. The inscriptions were epitaphs; of the three coins, one dated from the year 41 (when Claudius commenced to reign), another from the year 160 (reign of Antoninus Pius). Prof. Schaaffhausen of Bonn states that three of the skulls found belong to three different tribes. One belonged to a German, another to a Frisian, the owner of the third came from so far a country as Lapland.

A REMARKABLE discovery of Russo-byzantine antiquities was made near Kiew some weeks ago, when a canal for the water-works of the city was being excavated. They consist principally of twenty gold and enamelled lockets, three buttons of the same materials with heads of saints upon them, gold rings, agraffes and studs, all dating from the fifteenth or sixteenth century; they doubtless served as ornaments upon the costumes of the grand princes. Besides these some thirty-four silver coins were found, also a highly original bronze vessel in the shape of a fabulous quadruped. The metal value of all the antiquities is estimated at 1000 roubles (150*l.*). The Archæological Commission has taken possession of them.

OUR ASTRONOMICAL COLUMN

THE OBSERVATORY OF HARVARD COLLEGE, U.S.—We have received the Annual Report presented to the Visiting Committee of this Observatory by Prof. Pickering on December 6. The year has been one of unusual activity in the establishment, funds which had been liberally forthcoming from its friends having enabled both the equatorial and meridian circle to be regularly employed, and further having allowed of many researches of importance being conducted with the smaller instruments. With the large equatorial Prof. Pickering claims that he has succeeded in making a more extensive series of observations for position of the satellites of Mars at the last opposition than was obtained elsewhere, and states that Deimos was last seen at Harvard Observatory; the number of observed angles of position of Deimos was 825, and of Phobos 278, and that of observed distances 245. In addition to measures for position photometric observations were made, which appear to show that if the satellites possess a capacity for reflecting sunlight equal to that of the planet, Deimos may have a diameter of about six and Phobos of seven miles. It was noted at various observatories that Deimos appeared somewhat brighter in 1879 than at the preceding opposition in 1877, and in both years Prof. Pickering states it seems to have been brighter measured photometrically, and to have been seen more easily when it followed than when it preceded Mars.

Photometrical determinations of the times of eclipses of Jupiter's satellites, commenced in the summer of 1878, have been continued during the year, and it is considered with reasonable hope that these phenomena may be more accurately observed than hitherto by this method. Observations of planetary nebulæ described in the previous Report have been nearly completed.

With regard to spectroscopic observations, Prof. Pickering says the most remarkable discovery is that the spectrum of No. 17681 of Oeltzen's Catalogue, the place of which for 1880 is in R.A. 18h. 1m. 17s., N.P.D. 111° 1′, possesses a peculiar character. "The light of this star is principally concentrated in two points of the spectrum, one in the blue, the other in the yellow, a little more refrangible than the D line. A faint continuous spectrum is also seen."

The variable star of Ceraski, the true period of which was determined at Harvard College, is referred to; systematic observations have been made upon it. The Report describes the progress made in observations with the "meridian photometer," whereby it is intended to determine the light of all stars visible to the naked eye between the North Pole and N.P.D. 120°. The principal want of the Observatory at the present time is stated to be the means of publication of these and other classes of observations, the large number of volumes issued during the last five years having exhausted the funds specially appropriated for defraying expenses of publication.

CERASKI'S VARIABLE STAR T CEPHEI.—Prof. Julius Schmidt, from his own observations of minima of this variable in the last five months of the past year, finds reason to conclude that in that interval each successive period was longer by 0·08753m. or 5·25s. than the preceding one, and has calculated the times of minima upon this assumption between June 11, 1880, and February 15, 1881. For elements with this correction to the period to be applied, he adopts for his starting-point—

Minimum ... 1880, December 7, 10h. 6·7m.
Athens M.T. + 2d. 11h. 50·812m. E.

E being the number of periods from December 7. Thus the next minimum is found to occur on February 5, at 6h. 50·3m. Athens time, or at 5h. 15·4m. M.T. at Greenwich. Prof. Schmidt has remarked what we believe was soon detected by Mr. Knott from his observations in October last, that for more than two hours about the minimum there is no perceptible variation of brightness; decrease and increase are very rapid, particularly the latter.

SWIFT'S COMET, 1880 *c*.—The Superintendent of the Observatory at Washington, Admiral Rodgers, communicates to *Science* of January 10, an orbit of this comet which has been calculated by Prof. Frisby from three meridian observations made there on October 25 and November 7 and 25, and without any assumption as to the periodic time. The revolution resulting from this application of the general method is about 2178 days, or a little less than six years, and thus the conclusion arrived at by MM. Schulhof and Bossert of Paris, and Mr. S. C. Chandler of Boston, U.S., receives confirmation. From the position of the orbit it happens at present that only every second return to perihelion can be made available for observations.

BARON DEMBOWSKI.—Practical astronomy has sustained a severe loss in the death of Baron Ercole Dembowski, which took place on the evening of the 19th ult. at Monte, Frazione di Solbiate, Arno. Few have attained as great skill or exhibited greater industry and patience in that somewhat difficult and tedious branch, the measurement of the double stars, to which the Baron specially devoted himself, and we hope some means may be found of publishing in a collective form the results of his long-continued labours in this direction.

METEOROLOGICAL NOTES

OUR readers will learn with much satisfaction that Sweden has resolved to take part in the international meteorological and magnetical observations in the Polar regions, and arrangements have been made for carrying on the observations from June 1, 1882, till June 1, 1883. The house erected at Masselbay in Spitzbergen by Nordenskjöld's expedition, is still in good condition, and will be fitted up for the observatory. In connection with the Spitzbergen Observatory, Haparanda, at the head of the Gulf of Boothnia, is to be created into a first-class observatory, and furnished with Theorell's self-registering and printing meteorological apparatus; and all other observations will be made which are expected of a first-class observatory. M. Hjeltström is appointed director of the Haparanda Observatory. The funds to meet the expenses of the expedition and the two observatories have been most generously supplied by M. L. O. Smith, Stockholm. Prof. Hildebrandsson, the eminent Swedish meteorologist, has been entrusted with the discussion of the observations made by Prof. Nordenskjöld on the celebrated *Vega* Expedition, to the publication of which meteorologists will look forward with the liveliest interest.

IN his fourteenth contribution to meteorology Prof. Loomis returns to the discussion of the interesting question of the course and velocity of storm centres in tropical regions. In a previous communication he had shown that in middle latitudes the average progress of storm centres corresponds pretty closely with the average direction of the prevailing wind of these latitudes. In marked contradistinction to this result is that now obtained regarding the course of the intertropical cyclones which occur within the region of the North-east Trade Winds. These cyclones, instead of following the ordinary course of the Trades towards the south-west, advance westward, but in a direction somewhat north of west.

DURING the winter months, storms while crossing the United States frequently advance during a part of their course from north-west to south-east. This course is followed most frequently in the region between the Rocky Mountains and the Mississippi, is seldom continued as far south as lat. 30°, and the storm centre, after reaching its most southerly point, often changes its course towards the north-east. Storms which cross the United States north of lat. 38° generally pursue a course a little to the north of east; while those which come from south of that latitude pursue a course nearly north-east. During the summer months however few storms travel south of lat. 38°, and during this part of the year the average course of storms is almost exactly towards the east.

PROF. LOOMIS next institutes a comparison between the West India hurricanes and those of the Bay of Bengal, China Sea, &c. The average course of the latter is towards the west, ranging from 13° south of west to 86° north of west, which agrees closely in this respect with the general course pursued by West India hurricanes. The velocity of their onward course is however markedly different, being only about eight miles per hour, which is less than half the average velocity of the West India cyclones. The average latitude when the course becomes north is nearly lat. 20°, being 10° more to southward than in the West Indies, and the velocity during this part of the course is only about nine miles an hour. Ultimately the cyclones curve round and pursue a course nearly east-north-east, with a velocity of onward movement scarcely reaching ten miles an hour, or less than half of the velocity found for West India hurricanes. Lastly, while in the West Indies cyclones or hurricanes have been found no farther south than lat. 10° N., in Southern Asia they have occurred as far south as lat. 6° N.

THE concluding part of the Contribution is taken up with an examination of those storms of middle latitudes which advance in a westerly direction. In these cases, which may be regarded as abnormal directions, it is found that the wind is generally greatest on the east side of the low centre of the storm. While there are thus on the east side of the low pressure areas, causes tending to increase pressure on that side, there are different conditions on the west side tending to divert the winds westward, and this, Prof. Loomis thinks, is the most important reason why in such cases the storm centres advance to westward. In the United States, over the Atlantic, and in Europe, the influence of one area of low pressure upon another is a very common cause of abnormal movements of storm centres—such, for instance, as the coalescence of two low areas into one, resulting occasionally in an apparent westerly movement of the centre of lowest pressure.

THE "Results of Meteorological Observations made at Mauritius during 1877" fully sustains the high reputation of Dr. Meldrum's previous reports for fulness of detail, accuracy, and special observations not usually given in meteorological reports. The hourly monthly values have been calculated from the readings of the barograph for the year, and a valuable table is appended to this part of the report (p. 5), showing the mean monthly diurnal variation of atmospheric pressure for the three years 1875-77. The value of these results will be greatly enhanced when the thermograph which has been received has been got into working order. A comparison, a very satisfactory one, is made of the barograph readings with those of the standard barometer. As in 1876 the wind during 1877 attained its annual maximum velocity in the colder months from June to August, and its minimum in the warmer months, from November to March; and its diurnal maximum velocity from 11 a.m to 2 p.m., and its minimum from about 2 to 5 a.m. The departures, however, from these times are such as to point to a considerable number of years' observations as required before the true average can be ascertained. Thirty-one stations for recording the rainfall are now in working order, and in each case the annual amounts available from 1862 are printed, and the averages of the years given for each station. Mean temperatures for seven stations appear in the report, the three highest

stations, with the mean temperatures for 1877, being, Curepipe (1800 feet) 68°·3, Bonne Veine (1500 feet) 69°·5, and Midlands (1400 feet) 73°·2. The difference in height (400 feet) of the first and last of these, and the difference of their mean annual temperatures, 4°·9, call for inquiry, and in connection therewith it may be suggested that a small map showing the physical features of Mauritius and the positions of the various stations would usefully illustrate these reports. As regards thunderstorms, which are carefully recorded, none occurred from May to October during 1876 and 1877, and the daily maximum is from 1 to 4 p.m., with a tendency to a secondary maximum about sunset, and the daily minimum from 10 p.m. to a little after sunrise.

IN a supplement to No. 366 of the *Bulletin International* of the Paris Observatory M. Mascart gives an interesting and rapid sketch of the meteorology of Europe for December last, illustrated with two maps showing the storm-tracks over the Continent during the month. During the first half of the month the storm-tracks were all to northward of the British Isles and Denmark, and fine weather prevailed particularly in Scotland, Denmark, and Germany. In France high barometers ruled with light winds, and temperatures high for the season. The contrast afforded with the weather in France during December, 1879, is is most striking; thus on December 10 of both years barometers were unusually high in France, but in 1880 the mean temperature was 50°·5, whereas on December 10, 1879, the mean temperature was −14°·1. The bearings of the geographical positions of anticyclones, with their high pressures, on the temperature of the regions covered by them is a point well worthy of examination. The influence of a high-pressure area resting over the Atlantic and extending on its eastern side over Western Europe, has doubtless a very different influence on the temperature of that part of the Continent than an area of high pressure covering the Continent and terminated on its west side by France and Spain, even though the barometer be equally high over the west of Europe. During the second half of December the storm-tracks took a much more southerly course, several being as far south as the Channel and the north shores of Germany. The result was an extension south of the cold, so that in Orkney and the Hebrides temperatures were nearly 3°·0 below the normal, on the Tweed about the normal, rising farther south to 1°·1 above the normal in North Wales, 5°·0 in the Channel Isles, and 6°·7 in Paris. During December, 1879, temperature in Paris was 21°·2 below the normal, the mean for that month being 17°·6, or 27°·9 colder than that of last December.

GEOGRAPHICAL NOTES

ON Tuesday night, at the Royal Institution, Mr. Edward Wymper described his ascents of Chimborazo and Cotopaxi to a distinguished audience. While purely athletic mountaineers had his sympathy in the practice of mountaineering as a sport, Mr. Whymper confessed that his sympathies were much more with those who en ployed their brains as well as their muscles. His journey to the Andes was to be one of work, and all its arrangements were devised so as to economise time to the uttermost. In observations for altitudes and position, in studying the manners and customs of the country, in photography and sketching, in the collection of objects of interest, from beetles on the summits of mountains to antiquities buried in the ground, he found quite sufficient to occupy his time. From Bodegas the party was composed of two Swiss mountaineers, the cousins Carrel of Val Tournanche, Mr. Perring, some muleteers, and their teams. When they reached the summit of Chimborazo, on the 3rd of January, after a most arduous climb, they found the wind blowing at the rate of 50 miles an hour, from the north-east, and driving the snow before it. With extreme difficulty, a reading of the mercurial barometer was effected. The mercury fell to 14·1 inches with a temperature of 21 deg. Fahr. This being worked out, in comparison with a nearly simultaneous observation at Guayaquil, gave 20,545 feet for the height of Chimborazo. They began the descent at 20 minutes past 5, with scarcely an hour and a quarter of daylight, and reached their camp (about 17,400 feet above the sea-level) about 9 p.m., having been out nearly sixteen hours, and on foot the whole time. Passing from an extinct to an active volcano, Mr. Wymper next gave an account of his journey to the crater of Cotopaxi. Observing with the telescope, during an enforced stay at Machachi, that much less smoke or vapour was given off at night than by day, he resolved, if possible, to pass a night on the summit. On the 18th of February the party got to the edge of the crater, having passed almost the whole way from their camp at a height of 15,000 feet to the foot of the final cone over snow, and then over ash mixed with ice. The final cone was the steepest part of the ascent, and on their side presented an angle of 36 deg. When they reached the crater vast quantities of smoke and vapour were boiling up, and they could only see portions of the opposite side at intervals, and the bottom not at all. Their tent was pitched 250 feet from the edge of the crater, and during a violent squall the india-rubber floor of the tent was found to be on the point of melting, a *maximum* thermometer showing a temperature of 110 deg. on one side of the tent and of but 50 deg. on the other; in the middle it was 72·5 deg. Outside it was intensely cold, and a thermometer on the tent cord showed a *minimum* of 13 deg. At night they had a fine view of the crater, which has a diameter from north to south of 2000 feet, and from east to west of about 1500 feet. In the interior the walls descend to the bottom in a series of steps of precipice, and slope a good thousand feet, and at the bottom there was a nearly circular spot of glowing fire, 200 feet in diameter. On the sides of the interior higher up, fissures, from which flickering flames were leaping, showed that the lava was red hot a very short distance below the surface. The height he found to be 19,600 feet. The party remained at the top for twenty-six consecutive hours, sleeping about 130 feet below the loftiest point. At first they had felt the effects of the low pressure of the atmosphere, and again, as at Chimborazo, took chlorate of potash with good effect. All signs of mountain sickness had passed away before they commenced the descent, and did not recur during the journey. Nearly five months later Mr. Whymper returned to Chimborazo, and from a second reading of the barometer at 14·028 inches, with a temperature of 15 deg. Fahrenheit, he made the height 20,489 feet, the mean of the two readings giving 20,517 feet. While on the side of Chimborazo he witnessed a magnificent eruption of Cotopaxi, ashes rising in a column 20,000 feet above the rim of the crater and then spreading over an area of many miles. Prof. Bonney had submitted the ash to microscopic examination, and found that the fineness varied from 4000 to 25,000 particles to the grain in weight, and from observation of the area over which the ash fell Mr. Whymper calculated that at least two million tons must have been ejected in this one eruption.

A TELEGRAM was read at a recent meeting of the French Academy of Sciences from M. de Brazza, who has been conducting an exploration in the region of the Ogowé and Congo, West Africa. Quite recently a French station has been founded in the upper course of the former river in connection with the International African Association. In July last, M. de Brazza informs the Academy, he reached the Congo from this station on the Ogowé, between the river Inpaka Mpania and the river "Lawson Afrisi." Gaining the favour of King Makoko he pacified the tribes on the right bank of the Congo, and peacefully descended the river in a canoe. On October 3 he founded the station of Ntamo Ncoma on land ceded by King Makoko on the right bank of the Congo. M. de Brazza surveyed the route between the Ogowé and Congo; it is twelve marches in length, over a plateau of an average height of 800 metres. The country is healthy, and the population dense and peaceful. In November last M. de Brazza arrived at Mdambi Mbongo, the advanced post of Mr. Stanley, whom he met, and with whom he reached the latter's headquarters at Vivi on November 12. If the new station can be maintained and victualled, it is no doubt well chosen as a starting-point for further discovery, for both north and south of it there are large regions of which he knew nothing.

AT the meeting of the Geographical Society on Monday last, Mr. E. Delmar Morgan gave some account of his journey last year to Semiretchia and the town of Kulja. Being unable to make use of the more southern line of communications, Mr. Morgan travelled by the northern post-road from Orenburg to Troitsk and Petropaulofsk, and thence to Omsk and Semipalatinsk. He then struck southwards to Sergiopol, where he was detained three weeks owing to the southern road being blocked by snow. He afterwards went to Kulja for a short time, and he also made some excursions to Issyk-kul and other places of interest. In the course of the discussion which followed the paper, Mr. Ashton Dilke, the only other Englishman

who has visited Kulja, gave an interesting account of his experiences in that region a few years back.

FEARS had been entertained by many that the expedition sent out by the Russian merchant M. Alexander Sibiriakoff to discover the North Passage by means of the steamer *Oscar Dickson*, on board of which M. Sibiriakoff was himself, had been lost, and M. Konstantin Sibiriakoff, his brother, had already equipped another expedition to find and assist the *Oscar Dickson*. In the meantime the welcome news has arrived that Alexander Sibiriakoff reached Tobolsk at the end of December. The *Oscar Dickson* and another ship, the *Nordland*, had met fresh ice near Mate-Ssale, and had retired into the Gydan Bay on the coast of Siberia, in order to winter there.

M. TARRY, a member of the French Commission for Trans-Saharan Communications, is stated to have discovered in the south of Wargla the ruins of a large city called Cedrada, which had been entombed by sands of the desert. This city is placed in the Valley of Wed Mya, and in the vicinity of a number of sources which in former centuries watered thousands of palm-trees. Orders have been sent to procure a set of sounding apparatus, and it is expected a large quaniity of pure water will be extracted from the earth. M. Tarry published an appeal to the local papers in order to obtain from the Government the foundation of a colony in this remote region.

DEEP-SEA EXPLORATION[1]

II.

4. *FOOD.*—The late Prof. Sars, in his remarks on the distribution of animals in the depths of the sea, asks "Whence do animals that live at depths far below the limits of vegetation obtain their food?" Bronn, Wallich, Wyville Thomson, and others have endeavoured to answer this question; but I do not think the problem has yet been satisfactorily solved. A considerable quantity of vegetable food is undoubtedly supplied from the Sargasso Sea and a similar area in the Pacific Ocean, as well as by the sea-weeds which fringe every coast. But this supply is not sufficient for the indirect support of the countless host of animals that inhabit the depths of the ocean, all of which are necessarily zoophagous or subsist on other animals. Plant life, except perhaps one of a peculiar kind, which will be presently noticed, appears to be absent in depths exceeding 150 fathoms.

In all probability the chief supply of vegetable food is derived from the countless diatoms, coccoliths, rhabdoliths, and oscillatoriæ, which are plants of a low degree of organisation, and swarm on the surface of the sea; these are swallowed by pelagic animals (such as *Salpæ* and Pteropods, or "sea-butterflies"), and the latter fall to the bottom after death, and form that flocculent or glairy mass which I have described in the Report of the *Porcupine* Expedition of 1869 as covering the bed of the North Atlantic at great depths.[2] The preservative effect of sea-water on animal tissues would stay decomposition for a long while; and Mr. Moseley ascertained by a curious experiment that it would take only about four days for a *Salpa* to reach the bottom at a depth of 2000 fathoms, and that the *Salpa* was not greatly decomposed after having remained in sea-water for a month in the tropics.

When we say that vegetable life does not exist at any considerable depth, we must not forget that some kind is said to occur in great abundance even in the benthal or deepest zone. The word "benthal" is applied to depths exceeding 1000 fathoms (see my Address, which is referred to hereafter in this lecture). Shells, corals, and other organisms, are everywhere permeated by what are considered to be minute plants allied to fungi or confervæ, which form branching canals, like those of the *Cliona* or perforating sponge; and such canals have been also detected in all fossiliferous strata of a marine nature, from the Silurian to the present epoch. These plants, or Thallophytes, have been called "parasitic"; but they do not live on any other living thing. They can hardly serve as food for deep-sea animals, because they are never exposed. Whether they may not be a link to connect the animal and vegetable kingdoms may be a matter for further investigation.

Food is of course a very important factor as regards the size of all animals. I have noticed, in my work on "British Conchology," that Mollusca from moderate depths are generally larger than those of the same species from shallow water; but this does not seem to be the case with a species of coral obtained in the *Challenger* Expedition, which ranged from a depth of 30 to one of 2900 fathoms, and was very variable in size.

5. *Light.*—Milton tells us of the

> "world of waters dark and deep."

One of the most interesting problems relating to the subject of this lecture is whether the above is a poetical idea or based on fact, as regards the absence of light in the abysses of the ocean.

We do not know to what extent the sun's rays penetrate the sea, nor whether the bottom at all depths is absolutely devoid of light. An ingenious apparatus, which was contrived by Dr. Siemens for ascertaining the presence of light at different depths by means of highly sensitive photographic paper, has never yet been properly tried. An experiment of this kind made by Prof. Forel proved that in the Lake of Geneva, even at a depth of only thirty fathoms, the paper was entirely unaffected after protracted exposure. But the water of that lake is peculiar; it is said to be rendered less transparent by suspended and floating particles of mica brought from glacier streams, and to have thus acquired its deep blue colour. I cannot believe that the only abyssal light, if there be any, is phosphorescent.

At all events we are certain that, as regards the sea, many animals at very great depths have eyes, and that there is no absence of colour.

Cuttlefishes, which have eyes not less highly organised than our own, have frequently been obtained from depths of many hundred fathoms; they do not eat phosphorescent polypes and such small deer. Nor are the deep-sea Mollusca blind. During the *Porcupine* Expedition of 1869 an undescribed species of *Pleurotroma* from 2090 fathoms had a pair of well-developed eyes on short footstalks; and a *Fusus* from 1207 fathoms had its eyes at the base of the tentacles. The last-named mollusks chiefly prey on bivalves. I have taken at moderate depths, living on the same ground, closely-allied species of univalve mollusks, some of which were eyeless or blind, and others were provided with the usual organs of vision. Numerous instances have been given by the *Challenger* naturalists of apparently seeing as well as of apparently sightless animals taken at great depths. Prof. Semper, of Würzburg, says, in "The Natural Conditions of Existence as they Affect Animal Life" (1881), "Many creatures furnished with well-constructed eyes live associated with the actually blind species, and which have been partly enumerated above." He mentions among the former five species of fish (one of a new genus) discovered in the *Challenger* Expedition at depths of from 675 to 2040 fathoms, besides several Mollusca and Crustacea.

Some land-slugs and mollusks (e.g. *Geomalacus maculosus* and *Achatina acicula*) are also blind. On the sea-shore and in shallow water most bivalves, as well as all the species of *Chiton*, are eyeless.

Some deep-sea animals are brightly and deeply-coloured. In the *Challenger* Expedition shrimps "of an intense bright scarlet colour" were obtained in very great abundance; and many Holothurians or Sea-cucumbers were of a "deep purple" hue. The same observation occurred to me in the *Porcupine* and *Travailleur* Expeditions.

6. *Temperature.*—The highest temperature of the sea-bottom observed in the *Challenger* voyage at depths over 1000 fathoms was 50°·5 Fahr., in 2550 fathoms; the lowest was 32°·1 only, in 1950 fathoms. The average bottom-temperature at great depths does not much exceed the freezing-point; but life does not appear to be affected by that circumstance. In the Arctic Expedition of 1875 I found an abundance and variety of animals in icy cold water.

7. *Depth.*—The average depth of the ocean between latitudes 60° N. and 60° S. is nearly three miles, or 2500 fathoms. The greatest depth which has been ascertained by sounding is five miles and a quarter, or 4620 fathoms, and occurs in the North-west Pacific Ocean; it is nearly equal to the height of Mount Everest, the highest known mountain, in the proportion of 27,720 to 29,000 feet.

8. *Inequalities of the Sea-bottom.*—The operations of the Telegraph Construction and Maintenance Company have materially added to our knowledge of the shape and contour of the floor of the ocean. They have shown us that the bed of the sea is quite as uneven as the surface of the land, and that it represents the same mountains, hills, gorges, and valleys, equally

[1] A Lecture by J. Gwyn Jeffreys, LL.D., F.R.S. Given at Swansea, Llanelly, and Barrow-in-Furness, in December 1880 and January 1881. Continued from p. 302.

[2] See *Proc.* Roy. Soc. 1870, p. 490.

diversified in the one case by oceanic currents on the surface as well as on the bottom, and in the other by foaming rivers and gentle streams. I will give a few instances of such inequalities in the North Atlantic. While repairing in 1878 the Anglo-American Cable, a tract of rocky ground was discovered, about 100 miles in length, in the middle of the North Atlantic, between 33° 50′ and 36° 30′ West longitude, and about 51° 20′ North latitude. Within a distance of eight miles the shallowest sounding was 1370, and the deepest 2230 fathoms, a difference of 860 fathoms, or 5160 feet; within four miles the difference was 3180 feet, and within half a mile 1380 feet. There are also the Laura Ethel Bank, with a depth of only 36 fathoms, and the Milne Bank, with 81 fathoms, both about 550 miles from Newfoundland, which is the nearest continental land. Other instances are the Josephine Bank, with 82 fathoms, and Gettysburg Bank, with 30 fathoms, the distance of the former from Cape St. Vincent being 250, and the latter 130 miles, with intermediate depths of from 1700 to 2500 fathoms. The soundings in the *Bulldog* Expedition also gave 748 between 1168 and 1260 fathoms, and the *Valorous* soundings gave 690 between 1450 and 1230 fathoms in another part of the North Atlantic and very far from any land.

A glance at the large series of diagrams of the *Challenger* soundings will at once serve to convince one of the extreme unevenness of the sea-bottom everywhere in the Atlantic and Pacific oceans. It would be difficult to find a greater degree of unevenness in any diagrams of the earth's surface, the total extent of which scarcely exceeds one fourth of that of the sea.

Diagrams to illustrate the inequalities of the sea-bottom in the case of the telegraph cable, and the irregularities of level in a similar extent of land in the Perthshire Highlands, are placed before you.

9. *Deposits.*—The floor of the ocean is covered by a more or less thick layer of ooze or mud, and of clays of different sorts and colours, which is inhabited by various animals. One of these deposits is called "*Globigerina*"-ooze, and is widely distributed over the bed of both the Atlantic and the Pacific. Another deposit is called "Red Clay," and is found at depths exceeding 2000 fathoms. Mr. Murray, one of the *Challenger* naturalists, has carefully worked out the deep-sea deposits which were observed and collected during the expedition. According to him the *Globigerina*-ooze occurred in the North Atlantic at forty-nine stations, from depths between 780 and 2675 fathoms; in the South Atlantic at six stations, from depths of between 1375 and 2150 fathoms; and in the Pacific Ocean at twenty-two stations, from depths of between 275 and 2925 fathoms. He also mentions other deposits, viz. Coral-mud, Radiolarian ooze, and Diatomaceous ooze. Mr. Murray also says that volcanic products, such as pumice, lava, and scoriæ, as well as the peroxide of manganese, are universally spread over the bottom of the deep sea; and, in consequence of copper, cobalt, and nickel having been detected in the clays, he was tempted to suggest the presence of meteoric or cosmic dust in those deposits.

An animated, but quite amicable, controversy has of late years taken place as to whether *Globigerina* (from which the first-mentioned ooze has taken its name) lives only on the bottom or on the surface of the sea, or on both of them. You will doubtless ask, What is a *Globigerina?* It is a microscopic shell, consisting of a few globular cells, which are added together in the course of growth, the smallest cell being the original one or nucleus, and the largest being the last formed. All the cells are full of a protoplasmic substance called sarcode, which is amorphous or has no definite structure—no head, no limbs, no heart, viscera, muscles, or nerves. Its entire body is a stomach, and nothing but a stomach. The same kind of sarcode forms the living pulp of sponges, which have a horny or glass-like skeleton instead of a shell. The *Globigerina* is a member of an extensive and extremely variable class of invertebrate animals called Foraminifera; and this class, as well as sponges, belong to a kingdom called Protozoa, the name of which imports not that it was the earliest form of life, but that its organisation is of the very primary or simplest kind. The cells of the *Globigerina* are in their living state covered with the most delicate spines of comparatively great length, which are set outwards, and probably serve to keep at a respectful distance all predatory animals of an equally minute size. Between these spines some of the sarcode is occasionally, if not habitually, protruded at the will of the animal through very fine pores of the shell, which gave rise to the name Foraminifera. Such prolongations or expansions of the sarcode are called pseudopodia, and are used for capturing and taking into the body or stomach animal or vegetable particles which serve for food, and are engulfed in the internal sarcode. Having premised thus much, and in the hope that my description may be tolerably intelligible to those who have not, like myself, studied the Foraminifera, I will proceed with my account of the controversy. I have frequently taken with a towing-net on the surface of the sea a multitude of floating *Globigerinæ*, which were certainly alive and showed their pseudopodia as well as their long and thick-set spines. Major Owen and Lieut. Palmer, who especially studied the surface-fauna of the Atlantic, observed and have published the same facts.[1] Therefore when, in the joint report of my colleagues and myself to the Royal Society, on the results of the first *Porcupine* Expedition in 1869, it was stated or strongly inferred that the *Globigerinæ* really "inhabit the bottom on which they are found in such extraordinary abundance," and that the hypothesis accounting for such accumulation by their having fallen to the bottom after death, their lives having been passed at or near the surface, was conclusively disproved, I ventured to record my dissent from that conclusion. The observations of Mr. Murray, one of the naturalists in the *Challenger* Expedition, have fully confirmed the hypothesis that *Globigerina* lives on the surface; and Sir Wyville Thomson now admits[2] it as an established fact. But Dr. Carpenter is not satisfied. He is of opinion that "whilst the *Globigerinæ* are pelagic in an earlier stage of their lives, frequenting the upper stratum of the ocean, they sink to the bottom *whilst still living*, in consequence of the increasing thickness of their calcareous shells, and not only continue to *live* on the sea-bed, but probably *multiply* there—perhaps there exclusively."[3] I must say that I am not convinced by the instances and arguments which he adduced in support of his opinion. There is no question that a great many species of Foraminifera live always on the sea-bottom; but I do not know that any species of pelagic or surface-dwelling animal inhabits also the sea-bottom. Dr. Wallich found that the stomachs of star-fishes which came up with the sounding-line from 1260 fathoms contained fresh-looking *Globigerinæ*, and that the latter were full of sarcode. This does not prove much, because sea-water is to some extent antiseptic or retards putrefaction. Many star-fishes feed like earthworms, and swallow quantities of organic and inorganic matter for the purpose of extracting nutriment from it. Sir Wyville Thomson says, in his paper "On Dredgings and Deep-Sea Soundings in the South Atlantic" (*Proc.* R. S. vol. xxii. p. 427), that the appearance of *Globigerina* and certain other Foraminifera, "when living on the surface, is so totally different from that of the shells at the bottom that it is impossible to doubt that the latter, even although they frequently contain organic matter, are all dead." Mr. Murray adds (*Proc.* R. S. vol. xxvi. p. 535):—"No living specimen of a *Globigerina*, an *Orbulina*, a *Pulvinulina*, or of the new genera found on the surface, which undoubtedly came from the bottom, has yet been met with. The foregoing observations appear to justify the opinion that these organisms live only in the surface and subsurface waters of the ocean."

I will not however presume to assert that Dr. Carpenter may not be right; but is he justified in taking for granted "that the *onus probandi* rests on those who maintain that the *Globigerinæ* do *not* live on the bottom"? It is rather difficult to prove such a negative.

The colour of the "Red Clay" was attributed by Mr. Murray to the presence of oxide of iron.

Mr. Etheridge obligingly examined some of the pebbles and minerals which I had dredged in the *Valorous* Expedition at depths of from 690 to 1750 fathoms. He reported that many of them were "most likely derived from Iceland." If this were the case, the pebbles and minerals might have been transported by a deep submarine current.

The deposits in very deep water, and beyond the range of fluviatile and tidal action, are so slight as to be almost filmy, and are chiefly composed of the skeletons or hard parts of *Globigerinæ*, Diatoms, and *Radiolariæ*. The subjacent layer of mud or ooze, where it is beyond the scope of river action, may have been formed from the ruins of a sunken continent.

The proportion of carbonate of lime contained in the deep-sea mud or ooze of the North Atlantic, which was procured in the first two cruises of the *Porcupine* Expedition of 1869, slightly differed. In a sample from 1443 fathoms, dredged off the west

[1] *Journal* of the Linnean Society, vol. ix. p. 147.
[2] *Proc.* Roy. Soc. vol. xxiii. p 34.
[3] *Ibid.* p. 235.

coast of Ireland in the first cruise, the proportion given by the late Mr. David Forbes was only about one-half, while in another sample from 2435 fathoms, dredged off the south coast of Ireland in the second cruise, Mr. Hunter found a little over 60 per cent.

As to a mysterious deposit called *Bathybius*, Mr. Buchanan, who had charge of the chemical work on board the *Challenger*, proved by careful and repeated analysis that this substance was not organic; and he "determined it to be sulphate of lime, which had been eliminated from the sea-water, always present in the mud, as an amorphous precipitate on the addition of spirit of wine." Mr. Murray came to the same conclusion; and the lifeless and inorganic nature of *Bathybius* may now be considered settled. This gelatinous slime was once imagined to be primordial, and to constitute the basis of life. But the sea-bed is the tomb of past generations, not the womb of creation.

10. *Geological.*—The late Sir Charles Lyell says, in the sixth edition of his "Elements of Geology" (1865), "that white chalk is now forming in the depths of the ocean, may now be regarded as an ascertained fact, because the *Globigerina bulloides* is specifically undistinguishable from a fossil which constitutes a large part of the chalk of Europe." He assumed that the *Globigerina* inhabited the ooze on the sea-bed. Edward Forbes and other geologists had initiated and adopted the same view that Chalk was a deep-sea deposit. In my Presidential Address to the Biological Section of the British Association at the Plymouth Meeting in 1877, I ventured to question the validity of this theory, and especially that which my colleague and friend Sir Wyville Thomson started as to the "continuity of the Chalk" from the Cretaceous to the present period. I there endeavoured to show that the Chalk differed in composition from the Atlantic mud, and that the fauna of the Chalk formation represented shallow and not deep water. My view has, I am glad to say, been to some extent admitted by Sir Wyville Thomson in his "Report on the Scientific Results of the Voyage of H.M.S. *Challenger*," when he speaks (pp. 49 and 50) of the belt of "shallower water" during the Cretaceous period. At all events, Mr. Wallace has lately accepted and confirmed my opinion.[1] It is highly probable that the Gault, which underlies the Chalk and is the lowest member of the Upper Cretaceous formation, was a deep-water deposit, because it abounds in small shells of the *Arca* and *Corbula* families, which are wanting in the Chalk; as well as in Ammonites and other free-swimming Cephalopods.

Mr. Sollas, indeed, in his paper "On the Flint Nodules of the Trimmingham Chalk" (*Annals and Magazine of Natural History* for December, 1880) believes that some deep-sea mud is analogous with the Chalk. He is aware that the former contains siliceous organisms and the latter none; and he supposes that the flints had been in some way derived from these organisms. But how flints originated and were formed is still a vexed question. Mr. Sollas is perhaps our best authority on Sponges; but he states (p. 444) that "the bottom-water of the sea is remarkably free from organic matter." This statement does not agree with the analyses of the bottom-water of the sea which were made by Mr. Lant Carpenter, Dr. Frankland, and Mr. Buchanan, the chemist of the *Challenger*, nor with the observations of Sir Wyville Thomson in his "Depths of the Sea," in which he says (p. 46) "the bottom of the sea is a mass of animal life."

Several species of Mollusca which were previously known as fossil only, and were supposed to be extinct, have lately been dredged by myself and others from the bottom of the Atlantic. Some of these same species had been described and figured by Prof. Seguenza of Messina from Pliocene beds in Sicily. I have no doubt that many more, perhaps all, of such fossil species will be hereafter discovered in a living state by means of deep-sea explorations.

Some geologists, and especially of late years, have advocated the theory that oceans have continued for an enormously long period to occupy the same areas that they still occupy. Mr. Darwin was, I believe, the first to broach this idea. He says, in the chapter "On the Imperfection of the Geological Record," "We may infer that where our oceans now extend oceans have extended from the remotest period of which we have any record; and, on the other hand, that where continents now exist large tracts of land have existed, subjected, no doubt, to great oscillations of level, since the earliest Silurian period." There does not seem to be any fact adduced or reason given for either of the above inferences.

[1] "Island Life."

If the present oceans and continents have remained unchanged since the Silurian period, how can we account for the widespread distribution of fossiliferous formations, Palæozoic, Mesozoic, Cainozoic or Tertiary, and Quaternary or Recent, miles in thickness, all over Europe, Asia, Africa, Australasia, and New Zealand? All oceanic islands are of volcanic origin; but some of them contain Miocene fossils. These formations are chiefly marine, both deep water and shallow; and they necessarily imply the presence of oceans in those parts of the globe which are now continents and dry land. All the "secrets of the deep" will probably never be revealed to man, nor is he likely to know what terrestrial formations underlie the floor of the mid ocean.

In my paper "On the Occurrence of Marine Shells of Existing Species at different Heights above the Present Level of the Sea," which was published in the *Quarterly Journal of the Geological Society* for August 1880, I stated that many existing species of Mollusca which inhabit great depths only are found in a fossil state at considerable heights above the present level of the sea, so as to show an elevation equal to nearly 12,000 feet, and that such elevation must have taken place at a very late and comparatively recent stage of the Tertiary or Post-Tertiary epoch. In the face of facts like this, can we rightly assign to the present oceans that geologically remote antiquity which is claimed for them?

11. *Incidental.*—Clarence's dream of wrecks, corpses, wonderful treasures, and

> "reflected gems
> That woo'd the slimy bottom of the deep,
> And mock'd the dead bones that lay scatter'd by,"

has not yet, I believe, been realised by any dredger. I have in this way explored for between forty and fifty years all our own seas, besides a considerable part of those on the coasts of North America, Greenland, Norway, France, Spain, Portugal, Morocco, and Italy; but I have never found anything of value except to a naturalist, nor any human bone, although many thousand human beings must have perished in those seas.

12 *Concluding Remarks.*—To give a better idea of the ocean and of its life in the depths as well as on the surface, let me strongly recommend my hearers to read Mr. Moseley's admirable volume entitled "Notes of a Naturalist on the *Challenger*." His graphic account of this marvellous voyage far surpasses in interest (to say nothing of accuracy) every work of fiction or imagination, and it has not the melancholy dulness of most books on history and travels.

The subject of this lecture is inexhaustible; and, as our knowledge of it becomes more extended, we must continually say with Seneca, "Our predecessors have done much, but have not finished. Much work yet remains, and much will remain; nor to any one, born after a thousand ages, will be wanting the opportunity of still adding something." Such increase of knowledge must tend to confirm our acknowledgment, with a reverential awe, of that Great Creator whose wondrous works are dimly seen in every form of life, marine and terrestrial, and especially in

> "all that glides
> Beneath the wave, yea, in the wave itself,
> And mighty waste of waters."

GAS AND ELECTRICITY AS HEATING AGENTS[1]

I.

ON March 14, 1878, I had the honour of addressing you "On the Utilisation of Heat and other Natural Forces." I then showed that the different forms of energy which Nature has provided for our uses had their origin, with the single exception of the tidal wave, in solar radiation; that the forces of wind and water, of heat and electricity, were attributable to this source, and that coal formed only a seeming and not a real exception to the rule,—being the embodiment of a fractional portion of the solar energy of former geological ages.

On the present occasion I wish to confine myself to one branch only of the general subject, namely, the production of heat energy. I shall endeavour to prove that for all ordinary purposes of heating and melting, gaseous fuel should be resorted to for the double reason of producing the utmost economy and of doing away with the bugbear of the present day, the smoke nuisance; but that for the attainment of extreme degrees of heat

[1] A lecture by C. William Siemens, D.C.L., LL.D., F.R.S., on January 27, in St. Andrew's Hall, Glasgow, under the auspices of the Glasgow Science Lecture Association.

the electric arc possesses advantages unrivalled by any other known source of heat.

Carbonaceous material such as as coal or wood is practically inert to oxygen at ordinary temperatures; but if wood is heated to 295° C. (593° F.), or coal to 326° C. (617° F.), according to experiments by M. Marbach, combination takes place between the fuel and the oxygen of the atmosphere, giving rise to the phenomenon of combustion. It is not necessary to raise the whole of the combustible materials to this temperature in order to continue the action; the very act of combustion when once commenced gives rise to a great development of heat, more than sufficient to prepare additional carbonaceous matter, and additional air for entering into combination; thus a match suffices to ignite a shaving, and that in its turn to set fire to a building.

The first effect of combustion is therefore to heat the combustible and the air necessary to sustain combustion to the temperature of ignition, but in dealing with the combustible called coal other preparatory work has to be accomplished besides mere heating in order to sustain combustion. The following is an analysis from Dr. Percy's work on "Fuel" of a coal from the Newcastle district :—

Carbon	81·41	Nitrogen	2·05
Hydrogen ...	5·83	Sulphur	0·74
Oxygen	7·90	Ash	2·07

which shows at a glance that nearly 16 per cent. of the total weight consists of such permanent gases as hydrogen, oxygen, and nitrogen. These gases are partly occluded or absorbed within the coal, but are also combined with carbon-forming volatile compounds, such as the hydrocarbons and ammonia, so that when coal is subjected to heat in a closed retort, as much as 35 per cent. passes away from the retort in a gaseous condition and as vapour of water, partly to condense again in the form of tar, and of ammoniacal liquor, and partly to pass into the gas mains as illuminating gas, a mixture mainly of marsh gas (Ch_4), olefiant gas (C_2H_4), and acetylene (C_2H_2), its value as an illuminant depending upon the percentage of the last two constituents rich in carbon. The result of the distillation of a ton of coal will be as follows, from data with which Mr. A. Upward has kindly supplied me :—

	cwt.
Coke	13·60
Tar	1·20
Ammoniacal Liquor	1·45
Gas	3·15
Carbonic acid	0·18
Sulphur removed by purifying	0·30
Loss	0·12

So great is the loss of heat sustained in an ordinary coal fire, in consequence of the internal work of volatilisation, that such a fire is scarcely applicable for the production of intense degrees of heat, and it has been found necessary to deprive the coal in the first place of its volatile constituents (to convert it into coke) in order to make it suitable for the blast furnace, for steel melting, and for many other purposes where a clear intense heat is required.

In the ordinary coke oven the whole of the volatile constituents are lost, and each 100 lbs. of coal yield only 66 lbs. of coke, including the whole of the earthy constituents which on a large average may be taken at 6 lbs., leaving a balance of 60 lbs. of solid carbon. In burning these 60 lbs. of pure carbon, 220 lbs. of carbonic anhydride (CO_2) are produced, and in this combination $60 \times 14,500 = 870,000$ heat units (according to accurate determinations by Favre and Silbermann, Dulong, and Andrews) are produced.

The 34 per cent. of volatile matter driven off yield, when the condensible vapours of water, ammonia, and tar are separated, about 16 lbs. of pure combustible gas (being equal to about 10,000 cubic feet per ton of coal), which in combustion produce $16 \times 22,000 = 352,000$ heat units. The escape of these gases from the coke oven constitutes a very serious loss, which may be saved, to a great extent at least, if the decarburisation is effected in retorts. The total heat producible from each 100 lbs. of coal is in that case $870,000 + 352,000 = 1,222,000$ or 12,220 units per lb. of coal. Deduction must, however, be made from this for the heat required to volatilise 34 lbs. of volatile matter for every 100 lbs. of coal used, and also for heating the coke to redness, or say to 1000° F. Considering the multiplicity of gases and vapours produced it would be tedious to give the details of this calculation, the result of which would approximate to 60,000 heat units, or 600 units per lb. of coal treated.

We thus arrive at $12,200 - 600 = 11,600$ heat units as the maximum result to be obtained from 1 lb. of best coal. Considering, however, that the coal commonly used for industrial purposes contains more ashes and more water than has been here assumed, a reduction of say 10 per cent. is necessary, and the calorific power of ordinary coal may fairly be taken at 10,500 units per. lb.

In applying this standard of efficiency to actual practice it will be found that the margin for improvement is large indeed. Thus in our best steam-engine practice we obtain one actual HP. with an expenditure of 2 lbs. of coal per hour (the best results on record being 1·5 lb. of coal per Indicated HP.) A HP. represents $33,000 \times 60 = 1,980,000$ foot-lbs. per hour, which is $\frac{1,980,000}{2} = 990,000$ foot-lbs., or units of force, per lb. of fuel. Dr. Joule has shown us that 772 foot-lbs. represent one unit of heat, and 1 lb. of coal therefore produces $\frac{990,000}{772} = 1282$ units of heat instead of 10,500, or only one-eighth part of the utmost possible result.

In melting steel in pots in the old-fashioned way, as still practised largely at Sheffield, 2½ tons of best Durham coke are consumed per ton of cast steel produced. The latent and sensible heat really absorbed in a pound of steel in the operation, does not exceed 1800 units, whereas 2½ lbs. of coke are capable of producing $13,050 \times 2·5 = 32,625$ units, or 18 times the amount actually utilised.

In domestic economy the waste of fuel is also exceedingly great, but it is not easy to give precise figures representing the loss of effect, owing to the manifold purposes to be accomplished, including cooking and the heating and ventilation of apartments. If ventilation could be neglected, close stoves such as are used in Russia would unquestionably furnish the most economical mode of heating our apartments; but health and comfort are after all of greater importance than economy, and these are best secured by means of an open chimney. Not only does the open chimney give rise to an active circulation of air through the room, which is a necessity for our well-being, but heat is supplied to the room by radiation from the incandescent material instead of by conduction from stove surfaces; in the one case the walls and furniture of the room absorb the luminous heat rays, and yield them back to the transparent air, whereas, in the latter case, the air is the first recipient of the stove heat, and the walls of the room remain comparatively cold and damp, giving rise to an unpleasant musty atmosphere, and to dry rot or other mouldy growth. The adversaries of the open fireplace say that it warms you on only one side, but this one-sided radiant heat produces upon the denizens of this somewhat humid country, and indeed upon all unprejudiced people, a particularly agreeable sensation; which is proof I think of its healthful influence. The hot radiant fire imitates indeed the sun in its effect on man and matter, and before discarding it on the score of wastefulness and smokiness, we should try hard, I think, to cure it of its admitted imperfections.

If incandescent coke is the main source of radiant heat, why, it may be asked, do we not resort at once to coke for our domestic fuel? The reasons are twofold: the coke would be most difficult to light, and when lighted would look cheerless without the lively flickering flame.

The true solution consists, I venture to submit, in the combination of solid and gaseous fuel when brought thoroughly under control, by first separating these two constituents of coal. I am bold enough to go so far as to say that raw coal should not be used as fuel for any purpose whatsoever, and that the first step toward the judicious and economic production of heat is the gas retort or gas producer, in which coal is converted either entirely into gas, or into gas and coke, as is the case at our ordinary gas works.

When in the early part of the present winter London was visited by one of its densest fogs, many minds were directed towards finding a remedy for such a state of things. In my own case it has resulted in an arrangement which has met with a considerable amount of favour and practical success, and I do not hesitate to recommend it to you also for adoption. Its general application would, as regards dwelling-houses, make our town atmosphere as clear as that of the surrounding country. If it can be shown that the arrangement may be easily and

cheaply applied, that it will relieve our housemaids of the most irksome portion of their daily work in laying fires and cleaning grates, and that a warm and cheerful fire can be made at a considerably cheaper rate than when using coal, you will admit, I hope, that the proposal is worthy of a trial.

In outward appearance my fire-grate, which I have not made the subject of a patent, and which may therefore be put up by any grate or gas-fitter without restraint, is very similar to the ordinary coal-grate; the latter may indeed be converted into the smokeless grate at a very trifling cost. The essential features of this grate are that solid carbonaceous fuel, such as coke or anthracite, are used in combination with as much gas as is found necessary to raise the former to the point of incandescence, that the combustion is entirely confined to the front of the grate, whence radiation into the room takes place, and that any heat reaching the back of the grate is conducted away and utilised in heating the incoming air, by which combustion in front of grate is supported; in this way greater brilliancy and considerable economy are realised.

One arrangement by which this is effected is represented in diagram 1 (see NATURE, vol. xxiii. p. 26). The iron dead plate *c* is riveted to a stout copper plate *a* facing the back of the fire-grate, and extending five inches both upwards and downwards from the point of junction. The dead plate *c* stops short about an inch behind the bottom bar of the grate to make room for a half-inch gas-pipe *f*, which is perforated with holes of about one-sixteenth of an inch placed at distances of one and a half inch along the inner side of its upper surface. This pipe rests upon a lower plate *d*, which is bent downwards towards the back so as to provide a vertical and horizontal channel of about one inch in breadth between the two plates. A trap-door *e*, held up by a spring, is provided for the discharge of ashes falling into this channel. The vertical portion of this channel is occupied by a strip of sheet copper about four inches deep, bent in and out like a lady's frill and riveted to the copper back piece. Copper being an excellent conductor of heat, and this piece presenting (if not less than a quarter of an inch thick) a considerable sectional conductive area, transfers the heat from the back of the grate to the frill-work in the vertical channel. An air current is set up by this heat, which, in passing along the horizontal channel, impinges on the line of gas flames and greatly increases their brilliancy. So great is the heat imparted to the air by this simple arrangement that a piece of lead of about half a pound in weight introduced through the trap-door into this channel melted in five minutes, proving a temperature exceeding 619° F. or 326° C. The abstraction of heat from the back has moreover the advantage of retarding the combustion of the coke there while promoting it at the front of the grate.

The sketch represents a fire-place at my office, in a room of 7200 cubic feet capacity facing the north. I always found it difficult during cold weather to keep this room at 60° F. with a coal fire, but it has been easily maintained at that temperature since the grate has been altered to the gas-coke grate just described.

In order to test the question of economy, I have passed the gas consumed in the grate through a Parkinson's 10-light dry gas-meter; the coke used is also carefully weighed.

The result of one day's campaign of nine hours is a consumption of 62 cubic feet of gas and 22 lbs. of coke (the coke remaining in the grate being in each case put to the debit of the following day). Taking the gas at the average London price of 3*s.* 6*d.* per 1000 cubic feet, and the coke at 18*s.* a ton, the account stands thus for nine hours:—

	d.
62 cubic feet of gas at 3*s.* 6*d.* per thousand	2·604
22 lbs. coke at 18*s.* a ton	2·121
Total	4·725

or at the rate of 0·525*d.* per hour. In its former condition as a coal-grate the consumption exceeded generally two and a half large scuttles a day, weighing 19 lbs. each, or 47 lbs. of coal, which at 23*s.* a ton equals 5·7*d.* for nine hours, being 0·633*d.* per hour. This result shows that the coke-gas fire, as here described, is not only a warmer but a cheaper fire than its predecessor; with the advantages in its favour that it is lit without the trouble of laying the fire, as it is called, and keeps alight without requiring to be stirred, that it is thoroughly smokeless, and that the gas can be put off or on at any moment, which in most cases means considerable economy.

A second and more economical arrangement as regards first cost is shown in diagram 2 (NATURE, vol. xxiii., pp. 92, 93), and consists of two parts, which are simply added to the existing grate, viz.: (1) the gaspipe *d* with a single row of holes of about $\frac{1}{16}$ inch diameter, 1·5 inch apart along the upper side inclining inward, and (2) an angular plate *a*, of cast iron, with projecting ribs *b*, extending from front to back on its under side, presenting a considerable surface, and serving the purpose of providing the heating surface produced by the copper plate and frill-work in my first arrangement. In using iron instead of copper it is necessary however to increase the thickness of these plates and ribs in the inverse ratio of the conductivity of the two metals, or as regards the back plate, from $\frac{1}{4}$ inch to $\frac{3}{4}$ inch according to the best determinations recently published by Sir W. Thomson. This thickness would be practically inconvenient, and in order to avoid it the construction of the grate had to be modified for cast iron.

An inclined plate fastened to the lower grate bar directs the incoming air upon the heating surfaces and provides at the same time a support for the angular and ribbed plate, which is simply dropped into its firm position between it and the back of the grate.

The front edge of the horizontal plate has vandyked openings *c*, forming a narrow grating, through which the small quantity of ashes that will be produced by combustion of the coke or anthracite in the front part of the grate discharge themselves down the incline towards the back of the hearth, where an open ash-pan may be placed for their reception.

In adapting the arrangement to existing grates, the ordinary grating may be retained to support the angular plate, which has in that case its lower ribs cut short, to the level of the horizontal grate.

But it may be asked, Are you sure that the coke and gas grate you advocate will do away with fogs and smoke? My answer is, that it would certainly do away with smoke, because the products of combustion passing away into the chimney are perfectly transparent. Mr. Aitken has, however, lately proved in an interesting paper read before the Royal Society of Edinburgh, that even with perfect combustion a microscopic dust is sent up into the atmosphere, each particle of which may form a molecule of fog. We have evidence, indeed, that the whole universe is filled with dust, and this is, according to Prof. Tyndall, a fortunate circumstance, for without dust we should not have a blue, but a pitch-black sky, and on our earth we should be, according to Mr. Aitken, without rain, and should have to live in a perpetual vapour bath. The gas fires would contribute, it appears, to this invisible dust, and we should, no doubt, continue to have fogs, but these would be white fogs, which would not choke and blacken us. It is not clearly shown what this fine dust, resulting from the combustion of gas, consists of, and it seems reasonable to suppose that in perfect combustion it will be avoided.

Granted the cure of smoke, it might still be questioned whether such a plan as here proposed could be carried out on so large a scale as to affect our atmosphere with the existing mains and other plant of the gasworks. If gas were to be depended upon entirely for the production of the necessary heat, as is the case with an ordinary gas and asbestos grate, it could easily be proved that the existing gas mains would not go far to supply the demand; each grate would consume from 50 to 100 cubic feet an hour, representing in each house a consumption exceeding many times the supply to the gaslights. My experiments prove, however, that an average consumption of from 6 to 8 cubic feet of gas per hour suffices to work a coke gas grate on the plan here proposed. This is about the consumption of a large Argand burner, and therefore within the limits of ordinary supply.

But independently of the practical question of supply, it is desirable on the score of economy to rely upon the solid carbon chiefly for the production of radiant heat for the following reason:—

1000 cubic feet of ordinary illuminating gas weigh 34 lbs., and the heat developed in their combustion amounts to $34 \times 22{,}000 = 748{,}000$ heat units.

One pound of solid coke develops in combustion, say, 13,400 heat units (assuming 8 per cent. of incombustible admixture), and it requires $\frac{748{,}000}{13{,}400} = 56$ lbs., or just half a hundredweight, of this coke to produce the same heating effect as 1000 cubic feet of gas. But 1000 cubic feet of gas cost on an average

3*s.* 6*d.* and half a hundredweight of coke not more than 6*d.* (at 20*s.* a ton), or only one-seventh part of the price of gas.

If heating gas was supplied at a much cheaper rate, it would in many cases be advantageous to substitute incombustible matter, such as balls of asbestos, for the coke or anthracite. The consumption of gas would in that case have to be increased very considerably, but the economical principle involved (that of heating the air of combustion by conduction from the back of the grate) would still apply, and produce economical results as compared with those obtained by the gas-asbestos arrangements hitherto used.

To illustrate the efficiency of this mode of heating the in-coming air by what is called waste heat, I will show you another application of the same principle which I have made very recently to the combustion of gas for illuminating purposes.

(*To be continued.*)

THE RECENT SEVERE WEATHER

IN a recent contribution to the literature of meteorology Mr. E. J. Lowe, F.R.S., endeavours to prove that droughts and great frosts are periodical, occurring at intervals of between eleven and twelve years. In support of this theory he remarks: "There can be no reasonable doubt that the cycles are more than eleven years and less than twelve (more nearly eleven than twelve)," and a table of "great frosts" is given, from which we take the dates for the present century in the same order as printed.

1801—2	1819—20	1860—61
1813—14	1837—38	1856—57
1810—11	1840—41	1870—71

The present year may now be added to the above list.

It will be noticed that there are some variations in the lengths of the intervening periods, but there is at the same time a distinct recurrence of eleven-year epochs.

The great frost of the month just ended will doubtless form one of the main features in the meteorology of the nineteenth century. In the table below are given the average temperatures of the United Kingdom for the three weeks ended January 10, 17, and 24 of the present year, together with the temperatures for the same weeks ended January 12, 19, and 26 of the year 1880. Each year the average for these periods was below the mean seasonal value. The deficiency is given in the fifth and tenth columns.

Districts.	1881. 1st week.	2nd week.	3rd week.	Average.	Below the mean.	1880. 1st week.	2nd week.	3rd week.	Average.	Below the mean.
	°	°	°	°	°	°	°	°	°	°
Scotland, East	30	24	25	26·3	11·7	38	34	34	35·3	2·3
England, N.E.	35	23	25	27·7	9·7	37	32	32	33·7	4·3
England, East	36	23	24	27·7	10·7	34	32	31	32·3	6·0
Midland Counties...	34	21	22	25·7	13·3	35	33	29	32·0	6·7
England, South.....	37	26	26	29·7	10·3	35	32	30	32·3	7·0
Scotland, West	33	23	26	27·3	12·0	40	34	33	35·7	4·0
England, N.W.....	35	25	27	29·0	11·0	38	34	33	35·0	5·0
England, S.W.	38	31	28	32·3	10·3	39	38	35	37·1	6·3
Ireland, North	35	24	26	28·3	12·0	42	37	31	36·7	4·3
Ireland, South	38	27	27	30·7	10·7	43	37	35	38·3	3·3
London	37·4	24·2	24·8	28·8	10·3	34·2	32·4	29·1	31·9	7·1

The weather during the above periods was cold in both years, and the deficiency of solar heat is more noticeable, if the figures of the second and third weeks in each year are compared. On several days bright sunshine occurred for several hours, yet at some stations the sunshine was so weak as to fail to mark the recording cards of Prof. Stokes's sunshine recorders.

The weather over the whole of north-western Europe has been generally intensely cold, and on January 28 the temperature at Haparanda (extreme north of Gulf of Bothnia) was reported as being 60° F. below freezing point. H. W. C.

THE AURORA OF JANUARY 31

WE have received the following communications on the recent brilliant display of aurora:—

HAVING noticed an auroral light through the mist on the evening of January 30, I looked out last evening, the 31st, and saw what to me at least was a new appearance. There was a strong yellowish-white auroral light in the north, with an uneven boundary—not a well-defined arch. From it there arose, at intervals of a minute or two, what looked like wisps of luminous mist of an elliptical form, with their longer axes east and west. These chased one another towards the zenith, appearing and disappearing with great rapidity, so that one could hardly say "look!" before they had vanished. Sometimes three or four were flashing out at once. They were of large size, and being unaccustomed to the description of such objects, I know not how to describe their size. They must however have subtended horizontally angles of 45° and more at the eye. This appearance lasted, from the time I first looked out at about 6h. 45m., for about ten minutes or less, and then the appearance gave place to ordinary streamers, yellowish-white at their base and rosy towards their summits.

The flashing lights which I have mentioned suggested to me this idea: One has seen two men shaking a carpet held at two adjoining corners. Their strokes not exactly coinciding, an irregular, undulatory movement is produced, something like the waves of a chopping sea. If a stratum of *something* was in such a state of undulation above the atmosphere, and became visibly luminous where the crests of the undulations dipped down into the atmosphere, it would produce the kind of appearance that I saw. OSMOND FISHER

Harlton Rectory, Cambridge, February 1

LEST the magnificent auroral display of last evening has not been generally visible, the following short account of it, as witnessed here, may not be unacceptable to the readers of NATURE.

At about 6.15 p.m. indications of the disturbance were noticed in an unusually bright appearance of the sky from the north-east to north-west by west, the light being white, and similar in character to that reflected from the upper part of a bank of fog. By 6.25 the upper limit of this phenomenon had gradually changed into a number of bands, alternately bright and dark, but not well defined, which after another short interval disappeared in a change of the light to a very ruddy tint, accompanied by a kind of throbbing in the north, exactly like rapid repetitions of faint lightning. At this period a great number of parallel bands of light of a beautifully clear salmon tint were extended from the ruddy bank in a southerly direction, those from the north passing beyond the zenith, and losing their definition in a diffused patch of light of the same colour. These bands slowly faded away, but were succeeded by a similar and equally beautiful display at from ten to fifteen minutes later.

About seven o'clock I walked two and a half to three miles in a northerly direction, and found in ascending a slight hill that the fog was sufficiently thick to obscure the stars. This I imagine explains the peculiar bank and thick appearance of the light near the horizon.

The whitish illumination in the same quarter of the sky was still visible at 12 p.m. JOHN HARMER

Wick near Arundel, February 1

A BRILLIANT aurora borealis has been visible here this evening. It commenced at twenty minutes to seven, extending from west-north-west to a little east of north. The western part was of a deep ruddy colour, extending (at a rough estimate) some 35 or 40 degrees from the horizon, and varied by long white streamers, one of which—nearly due north—reached to within 15 or 20 degrees of the zenith. I was unable to watch it for more than a few minutes, but at half-past ten the sky in the same direction was still remarkably bright. R. W. TAYLOR

Kelly College, Tavistock, January 31

A VERY brilliant auroral display was visible here last night. There was a short heavy shower of hail and rain at six o'clock, and the sky was entirely overclouded. Thirty minutes later the sky was again clear, and the northern horizon was beautifully illuminated, and broad quivering bands of light stretched from thence upward beyond the zenith, some in unbroken continuity, while others were broken up. Not connected with these rays, and on the south side of the zenith, were frequent flashes of light, usually crescentic in form. The light near the horizon was silvery and moonlight like, but higher up it became much ruddier. I watched the aurora from 6.30 till 7, when I was obliged to go in-doors till 10.30, and then able to observe it again. At that time the light near the northern horizon had greatly increased in brightness, but fewer bands extended

upwards and to a less distance. As I walked home along elevated country roads, the effect produced by a dark sky on one side with a bright sky on the other, as if lighted up by an invisible full moon, was very beautiful. E. H.

Sheffield, February 1

THE aurora borealis which occurred last night was first visible here at 6 p.m. As is usual, the glow extended in an arc about 15° above the horizon, and was of a faint greenish colour.

From it arose frequent streamers of the same colour, having a slow westerly motion: these streamers attained to various heights, one at 6.55 reaching almost to the zenith; their colour, of various intensities, was as a rule greenish, but at times the streamers were of a reddish tint, more remarkably that one which occurred at 5.55, above referred to. At 6.50 the low arc changed its character, becoming irregular, finally assumed the form of a double arc, of which the centres of curvature were north-east and north-west of the place of observation.

At irregular intervals, during the whole of the first half hour, after the first appearance of the aurora, a flickering arc of light would ascend from the lower arc, up to an elevation, in many cases, of about 80° At 7 p.m. the aurora decreased in intensity, and at about nine o'clock had disappeared.

Cirencester, February 1 G. W. PREVOST

UNIVERSITY AND EDUCATIONAL INTELLIGENCE

OXFORD.—The term's work has been delayed a little by the severity of the weather. Many of the colleges were but half filled on the regular day of meeting.

At the University Museum the following courses will be given during the term:—Prof. Henry Smith lectures on Pure Geometry, and Prof. Barth. Price on Geometrical and Physical Optics. Prof. Clifton will lecture on Terrestrial Magnetism at the Clarendon Laboratory. In this department Messrs. Stocker and V. Jones will lecture on Mechanics, and will give practical instruction in Physics. In the Chemical Department Dr. Odling will continue his course on Organic Chemistry. Mr. Fisher will lecture on Elementary Inorganic, and Dr. Watts on Elememtary Organic, Chemistry. The laboratories will be open under the direction of Messrs. Fisher, Watts, and M. Robb. Dr. F. D. Brown will lecture (for the Professor) on Chemical Affinity. In the Physiological Department, in the absence of Dr. Rolleston through illness, there will be practical instruction given by Messrs. Robertson, Hatchett Jackson, and Thomas. Mr. Jackson will lecture on Circulation and Respiration; Mr. Thomas on Comparative Embryology; Mr. Robertson will form a class for Practical Microscopy; and Mr. Lewis Morgan will form a class for Human Anatomy.

The following afternoon lectures will be given in the Museum: Prof. Prestwich will lecture on the Palæozoic Strata, and Prof. Westwood will give an informal lecture on the Arthropoda. In the University Observatory Prof. Pritchard gives two courses, one on the Lunar and Planetary Theories, the other on General Elementary Astronomy, once a week in the evening.

At the Botanical Garden Prof. Lawson gives a course of elementary botany.

At the Colleges which possess laboratories the following courses will be given:—At Christchurch Mr. Baynes will lecture on Thermodynamics; Mr. Dixon, owing to the illness of Mr. Vernon Harcourt, will continue his course on Inorganic Chemistry. At Balliol Mr. Dixon will lecture on Elementary Electricity and Magnetism; at Exeter Mr. Lewis Morgan will lecture on Histology; at Magdalen Mr. Yale will give a series of practical demonstrations on the Physiology of Circulation and Respiration.

In the School of Natural Science Prof. W. A. Tilden has been nominated as Examiner in Chemistry; Dr. S. J. Sharkey, of Jesus College, has been nominated Examiner in Biology; and Mr. J. W. Russel, of Merton College, has been nominated Examiner in Physics.

An examination for a Fellowship in biological subjects will be held in March at University College. The examination will comprise papers of questions, and practical work in zoology, physiology, and botany, and will begin on Thursday, March 3, at 9 a.m. Intending candidates are desired to send in their names to the Master (if possible) before February 11, with a list of the subjects they offer for examination. They are also invited to mention any original work on which they have been engaged, and to send copies of any original articles or books on biological subjects of which they are the authors. Candidates are desired to call on the Dean with the usual testimonials and certificates on Wednesday, March 2, between 5 and 6 p.m.

CAMBRIDGE.—The senior wrangler in this year's Mathematical Tripos is Mr. Andrew Russell Forsyth, of Trinity College, born in Glasgow in 1858, and educated at Liverpool College. The next two are Mr. Robert Samuel Heath and Mr. Ernest Steinthal, both also of Trinity.

In connection with the list published in these columns in December, of those who had obtained first class honours in the Natural Sciences Tripos, the following statistics may be of interest:—In the year in which the Tripos was instituted (1851), 6 names appeared in the list; the same number in 1861; in 1871, 14; in 1878, 22; and in 1880, 31 passed the examination, obtaining honours. In 1869, 7 men passed the Special Examination in Natural Science for the ordinary B.A. degree; the number increased to 25 in the Easter examination of 1870; in 1878 it slightly diminished to 22; and in 1880, 16 passed the examination in December. So far as these results go, it would appear that an increasing number of those students who declare for natural science at Cambridge aim at thoroughness in their work, and are not content with that superficial smattering of book knowledge which is considered sufficient in the examination for the Pass degree.

M. FERRY, the French Minister of Public Instruction, has given an important character to the next meeting of the schoolmasters of France. Each of the 40,000 teachers of the 40,000 parishes (communes) is to meet with his fellow-teachers at the proper district towns. There are about 2000 of each of these little assemblies, each of which is to elect a delegate who will go to the chief town of the Department, and all these cantonal delegates are to appoint a department of delegates, who will go to Paris with a memoir written for communication and discussion before the pedagogical congress. All these memoirs are to deal with questions proposed by the Government.

SOCIETIES AND ACADEMIES

LONDON

Royal Society, January 27.—"*Polacanthus Foxii*, a large undescribed Dinosaur from the Wealden Formation in the Isle of Wight." By J. W. Hulke, F.R.S. (Abstract.)

A description of the remains of a large dinosaur, discovered in 1865 by the Rev. W. Fox, in a bed of shaly clay between Barnes and Cowleaze Chines, in the Isle of Wight. Head, neck, shoulder-girdle, and fore ribs were missing, but the rest of the skeleton was almost entire. Some of the præsacral vertebræ recovered show a double costal articulation. In the trunk and loins the centrum is cylindroid, relatively long and slender, with plano-concave, or gently biconcave ends. Several lumbar centra are anchylosed together, and the hindmost to the sacrum. The sacrum comprises five relatively stout and short anchylosed centra of a depressed cordiform cross-sectional figure. The post-sacral vertebræ have a stout short centrum.

The limb bones are short, their shafts slender, and their articular ends very expanded. The femur has a third trochanter, and the distal end of the tibia has the characteristic dinosaurian figure.

The back and flanks were stoutly mailed with simple, keeled, and spined scutes, and the tail was also sheathed in armour.

The animal indicated by these remains was of low stature, great strength, and probably slow habits. It is manifestly a dinosaur, and is considered to be very nearly related to Hylæosaurus.

Linnean Society, January 20.—The Rev. J. M. Crombie, F.L.S., in the chair.—The proposed alterations in the bye-laws were again successively read, voted for, and confirmed, excepting sect. 2, chap. viii. which was not confirmed.—Portfolios of British sea-weeds and zoophytes, prepared by Mr. W. Smith of Falmouth, were exhibited by the Rev. J. Gould.—A squirrel's nest was also shown and commented on by Mr. Chas. Berjeau.—A new form of microscopical cabinet designed by Mr. W. Hillhouse of Cambridge was explained by him, its compactness and portability rendering it advantageous to teachers.—Mr. Thos. Christy exhibited some horn-shaped galls growing on a branch of *Pistacia atlantica*, and somewhat similar in appearance to those known in India under the name of "Kalera-singhi" galls. From the galls a substance exuded not unlike Chian turpentine; Mr. Christy also drew attention to the fruit of the

White Quibracho.—Notes on the Orchideæ formed the subject of an important contribution from Mr. G. Bentham. Orchids early attracted the attention of botanists, though their popularity as objects of cultivation is comparatively a recent phase due in a great measure to Loddige's celebrated collections and to the fashion set up by the Duke of Devonshire in his famous Chatsworth collection, a still further incentive being given by Chas. Darwin in his studies of their singular modifications of fertilising apparatus and its protecting perianth. In their classification Swartz's labours (1800), thereafter the Richards', Dupetit-Thouars, and others, have been superseded by the influx of strange forms then unknown. Rb. Brown first established the principles of their natural arrangement on a solid basis, and Lindley's grouping remains true till the present day. Blume's observations must always take a high rank, and good analytic generic characters and illustrations obtain in the works of Sir W. Hooker, Wight, Griffith, Fitzgerald, and others. The younger Reichenbach has devoted great attention to the group, but we still lack from him a synopsis of contrasted characters adaptive to limitation of tribes and genera. Dr. Pfester has of late studied their vegetative characters advantageously; while J. G. Beer proposes divisions founded on modifications of the labellum, unfortunately neglecting other structural peculiarities. In reviewing the Lindleyan system Mr. Bentham observes that the primary division based on the consistence of the pollen has not been replaced by any other equally good, although it is by no means absolute. He admits that the distinctions dependent upon the so-called *caudicles* and gland can scarcely be maintained, independent of the confusion occasioned by the term having been applied to three different parts of the pollinary system. The result of Mr. Bentham's extended examination of all growing and dried specimens procurable, and of the literature extant, is that he divides the order into five tribes and some twenty-seven subtribes, as indicated below, and he further gives lengthened explanations of these and of the more remarkable genera, &c. :—ORCHIDEÆ: *Tribe I. Epidendreæ*—Subtribes (1) Pleurothalleæ, (2) Microstyleæ, (3) Liparieæ, (4) Dendrobieæ, (5) Erieæ, (6) Bletieæ, (7) Coelogyneæ, (8) Stenoglosseæ, (9) Loelieæ; *Tribe II. Vandeæ*—Sub-tribes (1) Eulophieæ, (2) Cymbidieæ, (3) Cyrtopodieæ, (4) Stanhopieæ, (5) Maxillarieæ, (6) Oncidieæ, (7) Sarcantheæ, (8) Notyleæ; *Tribe III. Neottieæ*—Sub-tribes (1) Vanilleæ, (2) Corymbieæ, (3) Spiranthеæ, (4) Diurideæ, (5) Arethuseæ, (6) Limodoreæ; *Tribe IV. Ophrydeæ*—Sub-tribes (1) Serapiadeæ, (2) Habenarieæ, (3) Diseæ, (4) Corycieæ; *Tribe V. Cypripedieæ*.—In a paper by Mr. Edw. J. Lowe on some hybrid British ferns, the author's experiments lead him to believe that *Polystichum aculeatum* and *P. angulare* are forms of one species, and *P. lonchitis*, *Lastrea recurva*, and *L. Alpina* are merely mountain forms of *P. angulare* and *L. dilatata* respectively. Spores of *Athyrium Filix fœmina* were mixed, viz., vars. *Victoriæ*, with *frisellie* and *proteum* and var. *Fieldiæ*, with *Pullerii* and var. *Howardiæ*, with *Du Boulæ*, whence sprung varieties of singular beauty and vigour.—A revision of the genus *Vibrissea* was a communication by Mr. W. Phillips, which was taken as read.

Geological Society, January 19.—Robert Etheridge, F.R.S., president, in the chair.—Jabez Church, M.Inst.C.E., George Augustus Freeman, B.Sc. Lond., Charles Horsley, C.E., Edwin Simpson-Baikie, F.L.S., and Charles John Wood, M.Inst.C.E., were elected Fellows of the Society. William Henry Goss was proposed as a Fellow of the Society.—The following communications were read:—Further notes on the family Diastoporidæ, Busk, by G. R. Vine, communicated by Prof. P. Martin Duncan, M.B. Lond., F.R.S. In continuing his review of the family of the Diastoporidæ, the author stated that upon the question of the classification of the Polyzoa he is inclined to accept the views recently published by the Rev. T. Hincks in preference to the earlier ones enunciated by Prof. Busk. He now described the forms found in the Lias and Oolite, including *Diastopora stromatoporides*, Vine (= *liassica*, Quenst.), *D. ventricosa*, Vine, *D. oolitica*, Vine, *D. cricopora*, Vine. The author then proceeded to argue against the inclusion of the foliaceous forms in the genus *Diastopora*, and concluded by giving a definition of the genus, as now limited by himself.—Further notes on the Carboniferous Fenestellidæ, by G. W. Shrubsole, F.G.S. The author pointed out the discrepancies in the descriptions given by Lonsdale, Phillips, McCoy, and King of the genus *Fenestella*, as represented in the Silurian, Devonian, Carboniferous, and Permian formations respectively. He then proposed a new definition of his own, and described the following species:—*F. plebeia*, McCoy, *F. membranacea*, Phil. *F. nodulosa*, Phil., *F. polyporata*, Phil., *F. crassa*, McCoy, *F. halkinensis*, sp. nov.; and in conclusion he pointed out that the few species to which he has reduced the Carboniferous Fenestellæ find their representatives in the North American continent, only one really new form, *F. Norwoodiana*, having been described there.

Physical Society, January 22.—Prof. W. G. Adams in the chair.—New Member, Mr. G. Palgrave Simpson, B.Sc.—Notes on the construction of the photophone, by Prof. Sylvanus Thompson, were read by Prof. Rheinold. Prof. Thompson was led by experiment to question whether Prof. Bell's form of photophone receiver was adapted to give the best results. Theoretically he finds with a given maximum of incident light distributed uniformly over the surface, the change of resistance in a selenium receiver will vary proportionally with its linear dimensions, provided its parts be arranged so that on whatever scale constructed the normal resistance shall remain the same. A cell n times greater linearly each way will produce n times the variation in resistance for the same total amount of light. This follows from Prof. W. G. Adams' law that the change in the resistance of selenium is directly as the square root of the illuminating power. The author also finds that if the thickness of the conducting disks in the enlarged cell be kept the same as before and their number increased n times, the change of resistance will be n^3 times as great as before. Selenium cells should therefore be as large as possible, and the light should be distributed over them uniformly, not focussed to a point. A conical mirror would therefore be better than a parabolic one to receive the beam. Such a reflector would be cheaper to construct, and there would be a minimum loss by reflection, as the light would fall perpendicularly on a cylindrical cell parallel to its axis. To give the best effect, its angular semi-aperture should be 45°, and this will bring the front end of the cell in the same plane as the mouth of the reflector. Prof. Thompson has also constructed an improved cell by winding parallel wires on a cylinder of slate grooved with a double-threaded screw, and filling the interval between them with selenium. This form gives superior effects to Prof. Bell's disk device. Mr. Shelford Bidwell said that long annealing improved the sensitiveness of selenium for photophone purposes. He got the best speech from cells of high total resistance, made with fine wire. The selenium should however have a low specific resistance. With the apparatus he showed at a recent meeting of the Society he could now transmit articles from NATURE and the *Nineteenth Century* so as to be heard, every word, by the listener. Prof. Guthrie suggested that amorphous phosphorus should be tried in place of selenium as a more permanent substance.—Mr. Glazebrook, of the Cavendish Laboratory, Cambridge, read a paper on the measurement of small resistances and the comparison of the capacities of two condensers. In measuring small resistances by the Wheatstone balance the results differed on varying the resistance in the battery wires. According to Prof. Chrystal this was due to a thermo-electric effect produced by the hand at the middle point of the divided platinum iridium wire when the contact is made with it. It could be avoided by making this contact first and then making the battery contact. Mr. Glazebrook investigated the effect mathematically and experimentally. He suggested that the resistance in the battery wire should be kept small in comparison with the other resistances, and then the effect was inappreciable. It could best be eliminated by taking two measurements with reversed currents and calculating out. The author next considered the effect of a small leakage in comparing condensers by the Wheatstone balance method. The sensibility of this method is increased by increasing the two resistances and the resistance of the galvanometer. Dr. Hopkinson stated that he had found a modification of this plan to be very promising. For the battery he uses an induction coil, and for the galvanometer a telephone. Thus a high electromotive force and sensibility was obtained.

Anthropological Institute, January 11.—Edward B. Tylor, F.R.S., president, in the chair.—Mr. G. M. Atkinson exhibited some stone celts from British Guiana.—Mr. John Evans, F.R.S., gave a short account of the proceedings of the International Congress of Prehistoric Archæology and Anthropology held at Lisbon in September last, at which he had been present in the capacity of delegate from the Institute. One of the excursions was to Otta, to inspect the beds in which it was thought that traces of man living in Miocene times had been discovered. This discovery had been accepted by many members of the Congress, but Mr. Evans had not been satisfied as to the un-

doubtedly human origin of the single bulbs of percussion on the flints, nor as to their actually forming integral parts of the beds in or on which they were found, nor as to the geological antiquity of the beds themselves.—The President read a communication from Mr. F. F. Tuckett, on the subject of a supposed diminution in the size of heads during the last half century.—A paper by Mr. W. D. Gooch was read, on the Stone age in South Africa. The paper was illustrated by a large number of specimens collected by the author.

Royal Asiatic Society, January 24.—Sir H. C. Rawlinson, K.C.B., president, in the chair.—The following gentlemen were elected as Resident Members:—Colonel S. C. Law, E. H. Man, J. W. McCrindle; and Thomas T. Fergusson, Rev. Mr. Cain, Atinaram S. G. Jayakar of Maskat as Non-Resident.—A paper was read by Mr. Simpson, F.R.G.S., on the identification of Nagara-hara with reference to the travels of Hiouen-Tsang. Nagara-hara, he stated, was the name of the chief city of the Jelalabad Valley, as also of the Province, the extent of which, according to Hiouen-Tsang, was probably from Gundamack to the Khyber Pass. It was visited by Hiouen-Tsang and Fah-Hian, who describe some of the buildings in it, at the same time referring to its distance from Hidda (now Hada), and thus confirming the suggested identification. Mr. Simpson stated that when in the Jelalabad Valley with General Sir Samuel Browne's column in 1879, he made many explorations into the Buddhist remains there, discovering, *inter alia*, an isolated rock covered with ruins of Buddhist masonry, bearing the local name of Bala-Hissar (*i.e.* "the Citadel"), the whole ground about it being strewed with stones and fragments of topes. Around it may also be seen a series of ridges, most likely the remains of the ancient defences of the town. Hiouen-Tsang states that it was four miles in circumference, and that it was six miles from Hidda, both of which measures agree exactly with those made by Mr. Simpson. M. Vivien de St. Martin, who very nearly worked out a correct map of this district in his "Mémoire sur la carte de l'Asie Centrale," was, Mr. Simpson states, misled by the map published in the "Ariana Antiqua."

Statistical Society, January 18.—Mr. James Heywood, F.R.S., in the chair.—The following papers were read:—On the method of statistical analysis, by Wynnard Hooper.—On the growth of the human body, by J. Towne Danson.

PARIS

Academy of Sciences, January 24.—M. Wurtz in the chair.—M. Berthelot presented a supplement to his recent work, containing various new measurements by himself and others.—The following papers were read:—On the periodic development of any function of the radii vectores of two planets, by M. Tisserand.—On the theory of heat, by M. Resal.—On a new disease caused by the saliva of a child that had died of hydrophobia, by MM. Pasteur, Chamberland, and Roux. Rabbits inoculated with the dilute saliva died within thirty-six hours; symptoms, loss of appetite, paralysis, asphyxia, congestion of trachea, with hæmorrhage, swellings in groin, axillæ, &c. Other rabbits inoculated with saliva or blood from the first soon died also. The disease is attributed to a small organism (found in the blood); it is of rod shape, constricted at the middle and surrounded by mucous matter. It is like the microbe of chicken cholera, but has no effect on fowls. By artificial cultivation it is changed in form somewhat. Guinea-pigs, though so like rabbits, seem hardly affected by inoculation. Dogs that were inoculated died in a few days, but without symptoms of rabies. The disease seems distinct from rabies, but the authors do not at this stage affirm its absolute independence.—Experiments proving that thiotetrapyridine and isodipyridine have not the poisonous power of nicotine, whence they are derived, by M. Vulpian.—The mechanical contact of gneiss and limestone in the Bernese Oberland, observed by M. Baltzer, by M. Studer. M. Baltzer was requested by the Swiss Geological Commission to study the superposition of gneiss on the Jurassic system in the region named. This he did in 1874-76, and his observations are given in the work now presented.—M. Heer was elected Correspondent in Botany in place of the late M. Schimper.—Elements and ephemerides of comet *f* 1880 (Pechüle), by M. Bigourdan.—Presentation of a photograph of the nebula of Orion, by Prof. Draper. The exposure was for fifty-one minutes.—On the divisions of certain homogeneous functions of the third order with two variables, by M. Pepin.—On the distinction of integrals of linear differential equations in sub-groups, by M. Casorati.—On the separation of the roots of equations, the first member of which is decomposable into real factors and satisfies a linear equation of the second order, by M. Laguerre.—On the development of elliptic integrals of the first and second species in entire recurrent series, by M. Farkas.—On the choice of unit of force in absolute electric measurements, by M. Lippmann. The electric standards and chief theoretical formulæ being independent of choice of the unit of force, the choice is not of very great importance, and a change of it is always easy. The dyne presents no essential advantage in some cases. For unification of measurement in electricity and the rest of physics electricians might take for fundamental units the second, metre, and gramme.—Laws of liberation of electricity by pressure in tourmaline, by MM. Jacques and Curie. The two ends of a tourmaline liberate equal quantities of contrary electricity. The quantity liberated by a certain increase of pressure is of contrary sign and equal to that produced by equal diminution of pressure. It is proportional to variation of pressure, and independent of the length of the tourmaline. For a given variation of pressure per unit of surface it is proportional to the surface.—On baryta used to obtain arsenic, with arsenious acid and sulphides of arsenic, by M. Brame.—Action of dry carbonic acid on quick lime, by M. Raoult. When CO_2 is sent into (say) 100 gr. quick lime in a glass vessel which has been heated to the point at which the glass begins to soften, the lime absorbs the gas very powerfully, and becomes incandescent, remaining so about fifteen minutes. A bibasic carbonate is produced. It is practically impossible to produce neutral carbonate of lime by direct synthesis. Lime that has once been heated over 1100° acts on dry carbonic acid at a much slower rate than before.—On the losses of nitrous compounds in manufacture of sulphuric acid, and a means of attenuating them, by MM. Lasne and Benker. The means referred to are a direct injection of sulphurous acid.—On the resistance to flexure of tempered glass, by M. de la Bastie. This is proved from experiments to be considerably superior to that of ordinary glass.—On cholestene (cholestérilène), by M. Walitzky.—On the preparation of crotonic aldehyde, by Mr. Newbury.—On the *Mus pilorides*, or musk-rat of the Antilles, considered as a type of a new sub-genus in the genus *Hesperomys*, by M. Trouessart.—Formation of the blastoderm in Araneides, by M. Sabatier.—Resection of two metres of the small intestine, followed by cure, by M. Koeberlé.—The wild vines of California, by M. de Savignon. There are five varieties of these, though all have hitherto been usually comprised under the name *Vitis Californica*.—On *Theligonum cynocrambe*, L., by M. Guilland.

CONTENTS

	PAGE
PREHISTORIC EUROPE. By Prof. W. BOYD DAWKINS, F.R.S.	309
THE BIOLOGY OF PLANTS	310
LETTERS TO THE EDITOR:—	
Dust and Fogs.—JOHN AITKEN	311
Professors Exner and Young.—Prof. C. A. YOUNG	312
The Flying-Fish.—FRANCIS P. PASCOE	312
Mr. S. Butler's "Unconscious Memory."—S. BUTLER	312
Geological Climates.—Prof. SAMUEL HAUGHTON, F.R.S.	313
On the Spectrum of Carbon.—R.	313
A Case of Fascination.—J. T. BROWNELL	314
Birds Laying in January.—JOHN H. WILLMORE	314
Vibration of Telegraph Wires during Frost.—T. MELLARD READE	314
"Mock Sun."—J. E. H. PEYTON (*With Illustration*)	314
ON SOME RECENT CHARTS AND MAPS OF CURVES OF EQUAL MAGNETIC VARIATION OR DECLINATION	314
THE ZOOLOGICAL STATION AT NAPLES	315
CHARLES FREDERIC KUHLMANN	316
THE SCIENTIFIC SOCIETIES OF DUBLIN	316
JOHN DUNCAN	317
CASSELL'S NATURAL HISTORY (*With Illustrations*)	317
NOTES	319
OUR ASTRONOMICAL COLUMN:—	
The Observatory of Harvard College, U.S.	321
Ceraski's Variable Star T Cephei	322
Swift's Comet 1880 *e*	322
Baron Dembowski	322
METEOROLOGICAL NOTES	322
GEOGRAPHICAL NOTES	323
DEEP-SEA EXPLORATION, II. By J. GWYNN JEFFREYS, LL.D., F.R.S.	324
GAS AND ELECTRICITY AS HEATING AGENTS, I. By C. WILLIAM SIEMENS, D.C.L., LL.D., F.R.S.	326
THE RECENT SEVERE WEATHER	329
THE AURORA OF JANUARY 31. By Rev. OSMOND FISHER; JOHN HARMER; R. W. TAYLOR; E. H.; G. W. PREVOST	330
UNIVERSITY AND EDUCATIONAL INTELLIGENCE	330
SOCIETIES AND ACADEMIES	330

SUBSCRIPTIONS TO NATURE

Yearly . . . . . 28*s.*
Half-yearly . . . . . 14*s.* 6*d.*
Quarterly . . . . . 7*s.* 6*d.*

To the Colonies, United States, the Continent, and all places within the Postal Union :—

Yearly . . . . . 30*s.* 6*d.*
Half-yearly . . . . . 15*s.* 6*d.*
Quarterly . . . . . 8*s.*

Office: 29, Bedford Street, Strand.

DIARY OF SOCIETIES.

LONDON

THURSDAY, FEBRUARY 3.

ROYAL SOCIETY, at 4.30.—On the Cause of the Striation of Voluntary Muscular Fibre: J. B. Haycraft.—Description of some Remains of the Gigantic Land Lizard (*Megalonia prisca*, Owen) from Australia, Part 3: Prof. Owen, F.R.S.—On a Method of Destroying the Effects of slight Errors of Adjustment which may vitiate the Results of Experiments of changes of Refrangibility due to Relative Motions in the Line of Sight: E. J. Stone, F.R.S.—On an Improved Bimodular Method of Computing Natural and Tabular Logarithms and Anti-Logarithms to 12 or 16 Places, with very brief Tables: A. J. Ellis, F.R.S.—On the Potential Radix as a means of Calculating Logarithms to any required Number of Decimal Places, with a Summary of all preceding Methods Chronologically arranged: A. J. Ellis, F.R.S.—On the Influence of Temperature on the Musical Pitch of Harmonium Reeds: A. J. Ellis, F.R.S.

LINNEAN SOCIETY, at 8.—Notes on Cyperaceæ: George Bentham.—Observations on some British Fishes: Dr. Francis Day.—Remarks on the Coffee-Leaf Disease in India: William Biddie.—Coffee Disease in South America: Dr. M. C. Cooke.

CHEMICAL SOCIETY, at 8.—On the Estimation of Organic Carbon in Air: Drs. Dupré and Hake.—On the Action of the Copper Zinc Couple upon Nitrates: M. W. Williams.

ROYAL INSTITUTION, at 3.—The Troubadours: F. Hueffer.

LONDON INSTITUTION, at 7.—Three Years of Daily Weather Forecasting: R. H. Scott.

FRIDAY, FEBRUARY 4.

GEOLOGISTS' ASSOCIATION, at 7.30.—Annual Meeting.

ROYAL INSTITUTION, at 9.—Colonial Organisms: Dr. A. Wilson.

SATURDAY, FEBRUARY 5.

ROYAL INSTITUTION, at 3.—The Amazons: Prof. S. Colvin.

SUNDAY, FEBRUARY 6.

SUNDAY LECTURE SOCIETY, at 4.—The Guardianship of Children: Miss Orme.

MONDAY, FEBRUARY 7.

LONDON INSTITUTION, at 5.—Succession to Thrones: Sir H. S. Maine.

SOCIETY OF ARTS, at 8.—Watchmaking: Edward Rigg.

VICTORIA INSTITUTE, at 8.—Revelation and Science: Dr. S. Kinns.—Biblical Proper Names: Rev. H. G. Tomkins.

TUESDAY, FEBRUARY 8.

ANTHROPOLOGICAL INSTITUTE, at 8.—Notes on Two Stone Circles in Shropshire: A. L. Lewis.—Surgery and Superstition in Neolithic Times: Miss A. W. Buckland.

ROYAL INSTITUTION, at 3.—The Blood: Prof. Schäfer.

PHOTOGRAPHIC SOCIETY, at 8.—Anniversary.

WEST LONDON SCIENTIFIC ASSOCIATION, at 8.

WEDNESDAY, FEBRUARY 9.

ROYAL MICROSCOPICAL SOCIETY, at 8.—Annual Meeting.

SOCIETY OF ARTS, at 8.—Wood Carving in England: J. H. Pollen.

THURSDAY, FEBRUARY 10.

ROYAL SOCIETY, at 4.30.

MATHEMATICAL SOCIETY, at 8.—Some Theorems of Kinematics on a Sphere: E. B. Elliott.—On some Integrals expressible in Terms of the First Complete Elliptic Integral and of Gamma Functions: J. W. L. Glaisher, F.R.S.—On Mr. McColl's Calculus of Equivalent Statements: Herr Schlöttel (Strasburg).—An Application of Conjugate Functions: E. J. Routh, F.R.S.

ROYAL INSTITUTION, at 3.—The Troubadours: F. Hueffer.

LONDON INSTITUTION, at 7.—The Castes and Trades of India: Prof. Monier Williams.

SOCIETY OF TELEGRAPH ENGINEERS, at 8.—Earth Currents—Electric Tides: A. J. S. Adams.

FRIDAY, FEBRUARY 11.

ROYAL ASTRONOMICAL SOCIETY, at 3.—Anniversary.

ROYAL INSTITUTION, at 9.—Distances of the Stars: Prof. R. S. Ball.

QUEKETT MICROSCOPICAL CLUB, at 8.

SOCIETY OF ARTS, at 8.—The Gold-Fields of India: Hyde Clarke.

SATURDAY, FEBRUARY 12.

ROYAL INSTITUTION, at 3.—The Amazons: Prof. Colvin.

PHYSICAL SOCIETY, at 3.—Annual General Meeting.—Special General Meeting.—On a Hydrostatic Illustration of Electrical Phenomena, and other Lecture Experiments: Dr. O. J. Lodge.

£5 5*s.* ASTRONOMICAL TELESCOPE.

CRAMPTON & CO.'S IMPROVED TELESCOPE is of the highest workmanship and finish, combined with great power and clearness of definition; is entirely constructed of polished brass, with 3-inch Achromatic Object Lens, Altitude and Azimuth Movements, Rackwork, and Fine Adjustment, &c., &c.

THOMAS CRAMPTON & CO., 251, HIGH HOLBORN, LONDON, W.C.

Liberal Terms to Science Teachers and the Trade.

THOMAS CRAMPTON (formerly of 4, Little Britain, London, E.C.), ELECTRICIANS, OPTICIANS, and PHILOSOPHICAL INSTRUMENT MAKERS. Electric Bells, New Metallic Base Pattern, Constant Batteries, Indicators, Thief and Fire Alarms, and Automatic Switches, Induction and Medical Coils, or Specialities. Insulated Wires of every description. Microscopic and Optical Materials. Telescopes, Opera Glasses, Microscopes, Aneroid Barometers, and Lime-light Apparatus. Illustrated Catalogue Three Stamps.

THOMAS CRAMPTON & CO., 251, HIGH HOLBORN, LONDON, W.C.
For Trade Terms send Card.

GIMINGHAM'S SPRENGEL AIR-PUMP,

with Multiple Fall Tubes and every recent improvement, including McLeod's Low Tension Gauge, Barometer Gauge, Radiometer, Terminals for testing non-conductivity of the Vacuum. &c., &c.

L. CASELLA having arranged with Mr. GIMINGHAM for the Sole Manufacture of these Pumps, as well as his Improved Forms of

CROOKES'S RADIANT MATTER TUBES,

Is prepared to supply them either in their simple form, or with any of their accessories.

Mr. GIMINGHAM has kindly engaged to examine each, in order that no Imperfect Instrument or Tubes may be sent away.

Also **GIMINGHAM'S COMBINATION BLOWPIPE** for Amateur and Professional Glass Work, the most simple and perfect in use.

L. CASELLA, 147, Holborn Bars, London, E.C.

LIGHTNING CONDUCTORS.

Experience, accumulated since the time of Benjamin Franklin, proves conclusively that a Conductor made of Copper of adequate size is the best of all appliances for the protection of every description of building from the destructive effects of lightning.

NEWALL & CO.'S

PATENT COPPER LIGHTNING CONDUCTOR,

As applied to all kinds of Buildings and Shipping in all parts of the world with unvarying success; is the most Trustworthy, most Effective, and also the Cheapest Conductor ever offered to the public.

It is simple in its application, no insulators being required, and it costs only one shilling per foot for the standard size, which ensures safety in any storm.

R. S. NEWALL & CO., 130, STRAND, W.C.
36, WATERLOO ROAD, LIVERPOOL.
68, ANDERSTON QUAY, GLASGOW.
MANUFACTORY—GATESHEAD-ON-TYNE.

YORK'S

SERIES of SCIENTIFIC OPTICAL LANTERN SLIDES

Comprise over 2,000 of the following subjects:—Electricity, Magnetism, Sound, Telephone, Microphone, Electric Light, Light, Spectrum Analysis, Astronomy, Mines and Miners, Heat, Mechanics, Hydrostatics, Pneumatics, Human Physiology. Sample Slide and Catalogue sent on receipt of 2*s.*

F. YORK, OPTICAL LANTERN SLIDE MANUFACTURER,
87, Lancaster Road, Notting Hill, London, W.

R. W. NEEVES,

PHILOSOPHICAL INSTRUMENT

AND

INTENSITY COIL MAKER.

PRICE LIST, FOUR STAMPS.

55, SIDMOUTH STREET, LONDON, W.C.

MUSEUMS AND COLLECTORS.

MR. DAMON, of WEYMOUTH, will forward an abridged Catalogue of his Collections in Natural History Objects, including RECENT SHELLS (Foreign and British), FOSSIL REMAINS, MINERALS, ROCKS, MARINE ZOOLOGY, &c., &c., &c.

NOW READY.
SECOND EDITION,

GRIFFIN'S

CHEMICAL HANDICRAFT.

PRICE 4*s.* 7*d.* POST FREE.

A CATALOGUE OF CHEMICAL APPARATUS:

ILLUSTRATED, CLASSIFIED, DESCRIPTIVE.

Demy 8vo, 480 pp., Illustrated with 1,600 Woodcuts.

Most Complete and Cheapest List of Apparatus.

JOHN J. GRIFFIN AND SONS, 22, GARRICK STREET, LONDON, W.C.

W. LADD & CO.,

SCIENTIFIC INSTRUMENT MANUFACTURERS,

(By Appointment to the Royal Institution of Great Britain),

11 AND 12, BEAK STREET, REGENT STREET, W.

IMPROVED HOLTZ ELECTRICAL MACHINES. GRAMME'S MAGNETO-ELECTRIC MACHINE for Laboratory use.

PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3s. per oz.

Physical Apparatus of every Description.

ILLUSTRATED CATALOGUE, SIXPENCE.

PATERSON'S NEW CATALOGUE OF PHYSICAL APPARATUS.

LANTERN SLIDES for SCIENTIFIC LECTURES. Season 1880–1. Post free 6 Stamps.
Complete Sets of Physical Apparatus for Science Primers and all the Physical Text-books in use in Schools and Colleges.
Siemens and Gramme Dynamo Machines and Lamps for hire.
Schools supplied with Apparatus as per Science and Art Departments' Requirements in the Sections of Light, Heat, Sound, and Electricity.
Electric Signals for Houses, Hotels, &c., Colliery Signals, Lightning Conductors. The Gower-Bell Loud-speaking Telephone.

EDWARD PATERSON, Electrical Engineer.

SHOW ROOMS AND STEAM WORKS:—76, LITTLE BRITAIN, E.C. (late 3, Bedford Court, W.C.).

MOLISON'S HARMONOGRAPH; executes the Harmonic Curves in the most perfect manner. 15s. and 20s.

Illustrated Catalogue of Electrical Apparatus, Part 1, post free, 6 Stamps. Ditto, Electric Signals, Part 2, 6 Stamps.

FLETCHER'S
PATENT VENTILATED
HOT-AIR OVEN.

At a cost of less than one halfpenny per hour for gas this oven will grill, roast, toast, bake, warm dishes and plates; and with the assistance of Fletcher's Patent Solid Flame Boiling Burners will do everything possible with a first-rate open fire (except drying clothes on washing days).



It is unapproached by any oven for pastry, and is fully hot in one minute after the gas is lighted.

Fish, joint, and pastry can be cooked all at once, in the most perfect manner, without the slightest taint from one to the other. The cooking is always good and always alike.

It will roast joint and fowls both at once, at least as well as an open fire.

Complete illustrated list of gas cooking and labour-saving appliances free by post. List of Gas and Petroleum Laboratory Furnaces and Apparatus, price 2*d*

THOS. FLETCHER,
4 & 6, *MUSEUM STREET, WARRINGTON.*

FRY'S COCOA

GOLD MEDAL, PARIS EXHIBITION.

In Packets and Tins. Pure Cocoa only, with the superfluous oil extracted.

"If properly prepared, there is no nicer or more wholesome preparation of cocoa."—*Food, Water, and Air, edited by Dr. Hassall.*

EXTRACT

J. S. FRY & SONS, Bristol and London.

S. C. TISLEY & Co.,
OPTICIANS,
172, BROMPTON ROAD, S.W.
(Close to South Kensington Museum.)

THE PHONEIDOSCOPE

An Instrument for Observing the Colour-Figures of Liquid Films under the action of Sonorous Vibrations,

Being a visible demonstration of the Vibratory and Molecular Motion of a Telephone Plate.

The PHONEIDOSCOPE, with 3 Discs, Bottle of Solution, Descriptive Pamphlet, &c., in Cardboard Box, 10s. 6*d*.

MANUFACTURED AND SOLD WHOLESALE AND RETAIL BY
S. C. TISLEY & CO., 172, BROMPTON ROAD, LONDON, S.W.

TELEPHONIC ELECTRICITY. All Materials supplied for Experimental Purposes.

Price Lists of Electrical and Acoustic Apparatus, with Drawings and Description of the Harmonograph. Post Free, 2d.

BROKEN!!
DAVY'S DIAMOND CEMENT

SECURELY AND NEATLY MENDS
CHINA, GLASS,
CABINET WORK,
AND
FANCY ARTICLES.

Of all Chemists in 1s. Bottles.

See the name "E. DAVY," the Original Inventor, is on the Label, and also that of

BARCLAY & SONS, 95, Farringdon Street, London.

MICROSCOPIC SPECIALITIES.

SECTION LAVA SURFACE-FLOW, MOUNT VESUVIUS POLAR. 1s. 9*d*. post free.

SECTION PALATE of the EAGLE RAY. Opaque and Transparent, 2s. 3*d*. post free.

Catalogue of 32 Pages free on application to

JOHN T. NORMAN,
178, CITY ROAD, E.C.

HOLLOWAY'S OINTMENT

A CERTAIN REMEDY

For BAD BREASTS, OLD WOUNDS, and SORES. If effectually rubbed on the Neck and Chest, it cures SORE THROATS, BRONCHITIS, COUGHS and COLDS; and for GOUT, RHEUMATISM, and all Skin Diseases it is unequalled.

Messrs. MACMILLAN & CO.'S PUBLICATIONS.

THE STEAM ENGINE AND ITS INVENTORS.

A HISTORICAL SKETCH.

By ROBERT L. GALLOWAY,

Mining Engineer.

With numerous Illustrations. Crown 8vo, 10*s.* 6*d.*

Eighteenth Annual Publication, Revised after Official Returns.

THE STATESMAN'S YEAR-BOOK FOR 1881.

A Statistical and Historical Annual of the States of the Civilised World.

By FREDK. MARTIN.

Crown 8vo, 10*s.* 6*d.*

"The 'Statesman's Year Book' is a handbook for the politician as well as the merchant, and as a statistical and historical annual of the States of the civilised and mercantile world, stands without a rival."—*Times.*

Kamilaroi and Kurnai. Group-Marriage and Relationship, and Marriage by Elopement. Drawn chiefly from the usage of the Australian Aborigines: also the Kurnai tribe—their Customs in Peace and War. By LORIMER FISON, M.A., and A. W. HOWITT, F.G.S. With an Introduction by LEWIS H. MORGAN, LL.D., Author of "System of Consanguinity," "Ancient Society," &c. Demy 8vo. 15*s.*

NEW BOOKS ON IRELAND.

Disturbed Ireland, being the Letters Written during the Winter of 1880-81. By BERNARD H. BECKER, Special Commissioner of the *Daily News.* With Route Maps. Crown 8vo. 6*s.*

"Will be found one of the most trustworthy pictures of the sister island as it is . . . It has, especially at this moment, high political value."—*Examiner.*

The Life's Work in Ireland of a Landlord who Tried to do his Duty. By W. BENCE JONES of Lisselan. Crown 8vo. 6*s.*

"Mr. Bence Jones has written an interesting and instructive little book; but not the least enlightening part of it is the Preface, dated December 12th, 1880. He had just been threatened with Boycotting, which he now undergoes."—*St. James's Gazette.*

The Year's Art: A Concise Epitome of all matters relating to the Arts of PAINTING, SCULPTURE, and ARCHITECTURE, which have occurred during the Year, together with information respecting the events of the Year 1881. Compiled by MARCUS B. HUISH. Crown 8vo. 2*s.* 6*d.*

GOLDEN TREASURY SERIES.—NEW VOLUME.

Essays of Joseph Addison. Chosen and Edited by John Richard Green, M.A., LL.D. 18mo. 4*s.* 6*d.*

"This is a most welcome addition to a most excellent series."—*Examiner.*

English Poets: Selections, with Critical Introductions by various Writers, and a General Introduction by MATTHEW ARNOLD. Edited by T. H. WARD, M.A. 4 vols., crown 8vo, each 7*s.* 6*d.*

Vol. I. CHAUCER to DONNE.
Vol. II. BEN JONSON to DRYDEN.
Vol. III. ADDISON to BLAKE.
Vol. IV. WORDSWORTH to SYDNEY DOBELL.

"An excellent design admirably executed."—*Pall Mall Gazette.*

The Abbott's Farm; or, Practice with Science. By Henry Tanner, M.R.A.C., F.C.S., Professor of the Principles of Agriculture in the Royal Agricultural College, Author of "First Principles of Agriculture." Extra fcap. 3*s.* 6*d.*

Gilbert White's Natural History and Antiquities of Selborne. New Edition, with a Poem and Letters never before published. Edited, with Notes and Memoir by FRANK BUCKLAND; a Chapter on Antiquities by Lord SELBORNE; and the Garden Kalendar. With Illustrations by Prof. DELAMOTTE. Cheap Edition. Crown 8vo. 6*s.*

Physics of the Earth's Crust. By Rev. O. Fisher, M.A., F.G.S., Rector of Harlton, &c. 8vo. [*Shortly.*

MACMILLAN AND CO., LONDON.

FAUNA AND FLORA OF THE BAY OF NAPLES.

FAUNA UND FLORA DES GOLFS VON NEAPEL UND DER ANGRENZENDEN MEERES-ABSCHNITTE,

HERAUSGEGEBEN VON DER

ZOOLOGISCHEN STATION ZU NEAPEL.

I. Vol.—MONOGRAPHIE DER CTENOPHOREN. By Dr. C. Chun of Leipzig. 312 Pages, 18 Plates. (Already issued.)

II. Vol.—DIE ARTEN DER GATTUNG FIERASFER. By Prof. Emery of Cagliari. 80 Pages, 9 Plates.

These two Volumes will be given to Subscribers for the year 1880.

In the year 1881 will be published :—

III. Vol.—PANTOPODA (PYCNOGONIDÆ). By Prof. Dohrn of Naples, with ca. 250 Pages, 17 Plates.

IV. Vol.—ALGAE CORALLINEÆ. By Prof. Count Solms of Göttingen, with ca. 64 Pages, 3 Plates.

V. Vol.—BALANOGLOSSUS. By Dr. Spengel of Göttingen, with 10 Plates.

In preparation for the following years :—

ZOOLOGICAL.

PLANARIÆ. By Dr. Lang of Naples.
CAPRELLIDÆ. By Dr. Mayer of Naples.
CAPITELLIDÆ. By Dr. Eisig of Naples.
ÆOLIDIÆ. By Prof. Trinchese of Naples.
ACTINIÆ. By Dr. Andres of Bormio.
NEMERTINÆ. By Dr. Hubrecht of Leiden.
SIPUNCULOIDÆ. By Dr. Spengel of Göttingen.
ASTERIDÆ. By Dr. Ludwig of Bremen.
AMPHIPODA. By Dr. Della Valle of Naples.

BOTANICAL.

BANGIACEÆ. By Dr. Berthold of Naples.
HILDEBRANDTIA. By Prof. Schmitz of Bonn.
CRYPTONEMIACEÆ. By Dr. Berthold.
RHODOMELEÆ. By Dr. Falkenberg of Göttingen.

The Annual Subscription to this Series is £2 10s. The subscription must be made for at least three years. Subscribers for three or more years receive all the volumes published during the term of their subscription.

The volumes will be sold separately, Vol. I. for £3 15s., Vol. II. for £1 5s.

Subscriptions are received by the Zoological Station at Naples; at the Publishers' Office (Messrs. Engelmann, Leipzig): Or in this country at

Messrs. MACMILLAN & CO., Bedford Street, and Messrs. WILLIAMS & NORGATE, Henrietta Street, where copies may be obtained.

Printed by R. Clay, Sons, and Taylor, at 7 and 8, Bread Street Hill, Queen Victoria Street, in the City of London, and published by Macmillan and Co., at the Office, 29 and 30, Bedford Street, Covent Garden.—Thursday, February 3, 1881.

NATURE

A WEEKLY ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
Of Nature trusts the mind which builds for aye."—WORDSWORTH

No. 589, VOL. 23] THURSDAY, FEBRUARY 10, 1881 [PRICE SIXPENCE

Registered as a Newspaper at the General Post Office.]

[All Rights are Reserved.

UNIVERSITY OF LONDON MATRICULATION, JUNE, 1881.

Special Classes for this Examination will be formed at St. Thomas's Hospital Medical School, Albert Embankment, to commence on March 1st. The Special Classes for the Preliminary Scientific and 1st M.B. Examinations have now commenced. Full particulars can be obtained from the Secretary, Dr. GILLESPIE.

KING'S COLLEGE, LONDON.

The Office of the CURATOR of the ANATOMICAL MUSEUM is now VACANT.

Applications, accompanied by Testimonials of special aptitude for, and experience in, Museum work, to be sent to J. W. CUNNINGHAM, Esq., from whom also further information may be obtained.

GEOLOGICAL SOCIETY OF LONDON.

The ANNIVERSARY MEETING of this Society will be held at the Society's Apartments, Burlington House, on FRIDAY, February 18th, at One o'clock; and the ANNUAL DINNER will take place the same Evening, at the St. James's Hall Restaurant, Regent Street Entrance, at Six o'clock.

Fellows and Visitors intending to dine are requested to leave their Names at the Society's Apartments.

LIVERPOOL COLLEGE of CHEMISTRY, LIVERPOOL.

Founder ... ... Dr. SHERIDAN MUSPRATT.
Principals ... ... Drs. JABE AND GRANVILLE H. SHARPE.

Special advantages offered to Students.
Assays, Analyses, and Chemical Investigations conducted.
For Prospectuses, apply to the Principals.

Second-Hand Astronomical Telescopes,
Microscopes, & other Scientific Instruments.

C. BAKER,

244 & 245, HIGH HOLBORN,

Begs to call the attention of the Scientific to his Large and Extensive Stock of

ASTRONOMICAL TELESCOPES,
MICROSCOPES,
TRANSIT INSTRUMENTS,
REGULATORS, SPECTROSCOPES,
METEOROLOGICAL AND ELECTRIC APPARATUS,

By ROSS, DALLMEYER, COOKE, SMITH & BECK, BROWNING, DENT, TROUGHTON,

And other Celebrated Makers. All at very Low Prices.

CATALOGUE FREE BY POST.
INSTRUMENTS TAKEN IN EXCHANGE.

ESTABLISHED 1765.

McCLEAN'S STAR SPECTROSCOPE.
(PATENT.)

MR. BROWNING begs to call the attention of scientific gentlemen to McClean's Star Spectroscope, which is by far the most efficient Star Spectroscope yet contrived. It is simply an eye-piece which can be used with *any* telescope. Being without a slit, there is no difficulty in keeping the spectrum of a star under observation constantly in the field of view, and the spectra are of great brilliancy. Price of the Star Spectroscope in case, £2 10s.

LIST OF PRICES OF SPECTROSCOPES FREE.

Illustrated Catalogue, Sixpence.

JOHN BROWNING, 63, STRAND, LONDON, W.C.

STANDARD METEOROLOGICAL INSTRUMENTS



Now ready, a New Edition of Negretti & Zambra's Encyclopædic Catalogue of Mathematical, Philosophical, Optical, and Standard Meteorological Instruments, containing numerous Comparative Tables of Reference, and Illustrated by Twelve Hundred Engravings.

Royal 8vo, cloth, gilt lettered, price 5s. 6d.

NEGRETTI & ZAMBRA,
Opticians and Scientific Instrument Makers
TO HER MAJESTY THE QUEEN,
HOLBORN VIADUCT,
45, CORNHILL, & 122 REGENT STREET, LONDON.

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 48N, Tollington Road, Holloway, London, N.

ASSOCIATION for the IMPROVEMENT OF GEOMETRICAL TEACHING.

SEVENTH GENERAL REPORT, containing the Address of the President, H. B. HAYWARD, Esq., F.R.S., on "The Future of the Association." Price Sixpence. Complete Sets of the Reports of the Association, price 3*s.* 6*d.*

Apply by letter, inclosing Stamps or P.O.O., to Mr. JOSIAH ALLEN, Printer, 74, Suffolk Street, Birmingham.

INSTRUCTION IN MATHEMATICS.—

Youths or Adults attended at their Residence, on Reasonable Terms, by a M.A. of Cambridge. Unquestionable references if required.—Address, by letter, O. P., Post Office, Turnham Green.

ROYAL POLYTECHNIC.—CLASSES for

the Preparation of Students for University Examinations, under the direction of EDWARD B. AVELING, D.Sc., F.L.S. London University Matriculation, 1st and 2nd B.Sc., Preliminary Scientific M.B., Botany, Physiology, Chemistry. All the work practical.

ROYAL SCHOOL OF MINES.

Prof. J. W. JUDD, F.R.S., will commence a Course of Fifty Lectures on Geology at the Science Schools, South Kensington, on MONDAY next, the 14th inst., at 10 o clock a.m., to be continued on every week-day except Saturday at the same hour. Fee for Lectures, £4; for Practice in Laboratory and Field, £6.

Mr. WARINGTON W. SMYTH, M.A., F.R.S., will commence a Course of Forty Lectures on Mineralogy at the Museum of Practical Geology, Jermyn Street, on MONDAY, the 21st inst., at 12 o'clock at noon, to be continued on every succeeding Tuesday, Thursday, Friday, and Monday at the same hour. Fee for the Course, £4.

F. W. RUDLER, Registrar.

MINERALOGY AND GEOLOGY.

Mr. HENSON having purchased an OLD COLLECTION formed in DERBYSHIRE, containing FINE SPECIMENS of ANGLESITE, CERUSSITE, FLUOR SPAR and CALC SPAR, DIOPTASE, EUCHROITE, and other RARE MINERALS, begs to offer the same singly or otherwise.

COLLECTIONS FOR STUDENTS, from £2 2*s.* COLLECTIONS FOR BEGINNERS, from 4*s.* BLOWPIPE CASES AND APPARATUS.

PRIVATE LESSONS AND EVENING CLASSES.

Catalogues free.

SAMUEL HENSON,

277 (*Late* 113*a*), STRAND, LONDON, W.C.

GEOLOGY.—In the Preface to the STU-

DENT'S ELEMENTS of GEOLOGY, by Lyell, 1874, he says: "As it is impossible to enable the reader to recognise rocks and minerals at sight by aid of verbal descriptions or figures, he will do well to obtain a well-arranged collection of specimens, such as may be procured from Mr. TENNANT (149, Strand), Teacher of Mineralogy at King's College, London." These Collections are supplied on the following terms, in plain Mahogany Cabinets:—

100 Specimens, in Cabinet, with 3 Trays	£2	2	0
200 Specimens, in Cabinet, with 5 Trays	5	5	0
300 Specimens, in Cabinet, with 9 Drawers	10	10	0
400 Specimens, in Cabinet, with 13 Drawers	21	0	0

More extensive Collections at 50 to 5,000 Guineas each.

GEOLOGY AND MINERALOGY.

Special Collections for Teachers and Students, used with success by all Lecturers and Teachers of Geology in Great Britain. Obtained Gold and Bronze Medals at Sydney Exhibition, 1879, also in London, 1862, and Paris, 1867.

200 Specimens in Cabinet ...	...	...	...	£2	2	0
100	ditto	ditto ...	...	...	...	1	1	0
50	ditto	ditto ...	...	...	...	0	10	6

New Lists of Collections, Apparatus, &c., now ready, and free on application to

JAMES R. GREGORY'S

Geological Museum and Repository,

88, CHARLOTTE STREET, FITZROY SQUARE.

EVERY BOY A GEOLOGIST.

Now ready, and highly recommended, complete, price 7*s.* 6*d.*

This admirable little Work and most extraordinary Cabinet of wonderfully well-selected Natural Specimens, together with other Geological Preparations, and a powerful Lens, are calculated to start a boy thinking till he has mastered for himself no ordinary knowledge of the formation of the Earth's Crust.—THOMAS J. DOWNING, GEOLOGIST, &c., 38, Whiskin Street, London, E.C.—Catalogues free.

DIAMONDS IN MATRIX.

R. C. NOCKOLD, Diamond and Oriental Stone Cutter and Dealer, has for sale Specimens of the above; also Cut Precious Stones in all Colours.

Precious Stones valued and bought.

12*a*, FRITH STREET, SOHO, W.

LIVING SPECIMENS FOR THE MICROSCOPE.

THOMAS BOLTON, NATURALISTS' and MICROSCOPISTS' STUDIO, 57, NEWHALL STREET, BIRMINGHAM.

T. B. has last week sent to his subscribers the Entomostracan, *Argulus foliaceus*, usually found parasitic on fish, and attached thereto as Commensals, a number of Infusoria, *Epistylis invaginata* of Claparède and Lachman. He has also sent out Hydra, Cordylophora, Rotifers, &c.,: also the large Edible Frog, *Rana esculenta*, suitable for dissection.

Weekly announcements will be made in this place of organisms T B is supplying.

Specimen Tube, One Shilling, post-free.

Twenty-six Tubes in course of Six Months for Subscription of £1 1s.

Price List of Specimens on application, with stamped addressed envelope.

Portfolio of Drawings, No. 4, One Shilling.

THE "HANSA"

Published since 1864 in Hamburg, is the only independent professional paper in Germany, dedicated exclusively to Maritime Objects. Essays, Critiques, Reviews, Reports, Advertisements. Strict eye kept upon the development of Maritime Affairs in every respect. Every second Sunday one Number in 4to at least; frequent supplements and drawings. Subscription at any time; preceding numbers of the year furnished subsequently. Price 12*s.* for twelve months. Advertisements 4*d.* a line, widely spread by this paper; considerable abatement for 3, 6, 12 months' insertion. Business Office: Aug. Meyer and Dieckmann, Hamburg, Alterwall. 28. Edited by W. v. FREEDEN, M.R., Hamburg, Alexander Street, 8.

On the 1st of every Month, price One Shilling.

THE ZOOLOGIST:

A MONTHLY MAGAZINE OF NATURAL HISTORY.

Third Series. Edited by J. E. HARTING, F.L.S., F.Z.S., Member of the British Ornithologists' Union; contains—

Original articles by well-known naturalists in every branch of zoology: habits of animals; arrival and departure of migratory birds; occurrence of rare birds; distribution and migration of British fresh-water fish; new or rare marine fish; local aquaria; British reptiles; British land and fresh-water mollusca, with remarks on the haunts and habits of the species; and other matters of general interest to those who delight in natural history. Reports of the Linnean, Zoological, and Entomological Societies. Reviews of natural history books. Occasional translations from foreign zoological journals of important and interesting articles in various branches of zoology. There are occasional woodcuts.

JOHN VAN VOORST, 1, Paternoster Row.

THE ENTOMOLOGIST'S MONTHLY MAGAZINE.

Price Sixpence, Monthly, 24 pages 8vo, with occasional Illustrations.

Conducted by C. G. BARRETT, J. W. DOUGLAS, R. MCLACHLAN, F.R.S., E. C. RYE, F.Z.S., E. SAUNDERS, F.L.S., and H. T. STAINTON, F.R.S.

This Magazine, commenced in 1864, contains standard articles and notes on all subjects connected with Entomology, and especially on the Insects of the British Isles.

Subscription—Six Shillings per Volume, post free. The volumes commence with the June number in each year.

Vols. I. to VI. (strongly bound in cloth) may be obtained by purchasers of the entire set to date, at the increased price of 10*s.* each; the succeeding vols. may be had separately or together, at 7*s.* each.

London: JOHN VAN VOORST, 1, Paternoster Row.

N.B.—Communications, &c., should be sent to the Editors at the above address.

NORTH BRITISH AGRICULTURIST

is the only Agricultural Journal in Scotland, and circulates extensively amongst Landed Proprietors, Factors, Farmers, Farm-bailiffs, and others interested in the management of landed property throughout Scotland and the Northern Counties of England.

The AGRICULTURIST has also a very considerable circulation on the Continent of Europe, America, Australia, and the Colonies.

The AGRICULTURIST is published every Wednesday afternoon in time for the evening mails, and contains Reports of all the principal British and Irish Markets of the week, besides Telegraphic Reports of those held on the day of publication.

The Veterinary Department is edited by one of the leading Veterinarians in the country, and is invaluable to the breeder and feeder as a guide to the rearing of animals, and their treatment when labouring under disease.

Full Reports are given of the Meetings of the Royal Agricultural Society of England, the Royal Agricultural Society of Ireland, the Highland and Agricultural Society of Scotland, the Scottish Chamber of Agriculture, and all the principal Agricultural Associations throughout Great Britain and Ireland.

For Advertisers addressing themselves to Farmers a better medium does not exist

Price 3*d.* By post 3½*d.* Annual Subscription, payable in advance, 14*s.*

Office—377, High Street, Edinburgh.

Post-Office Orders payable to Charles Anderson, Jun., Edinburgh.

ESTABLISHED 1843.

On the 1st of every Month.

TRIMEN'S JOURNAL OF BOTANY,

BRITISH AND FOREIGN.

New Series. Edited by JAMES BRITTEN, F.L.S., British Museum.

CONTENTS.—Original Articles by leading Botanists.—Extracts, and Notices of Books and Memoirs.—Articles in Journals.—Botanical News.—Proceedings of Societies.

Price 1*s.* 3*d.* Subscription for One Year, payable in advance, 12*s.*

London: WEST, NEWMAN, & CO., 54, Hatton Garden, E.C.

Sale by Auction.

The Natural History, Ethnological, Geological, and other Collections of the late E. W. COOKE, Esq., R.A., F.R.S.

MR. J. C. STEVENS has been favoured with Instructions to Sell by Auction, at his Great Rooms, 38, King Street, Covent Garden, on FRIDAY, February 25th, at half-past 12 precisely, by order of the Executor, the Collections of Objects of Natural History, Ethnology, Archæology, Geology, &c.; also Loddige's Botanical Cabinet, a rare and valuable work. Also a fine Collection of Casts from Antique Gems and other Curiosities collected by the late E. W. COOKE, Esq., R.A., F.R.S.

On view after 2 o'clock the day prior and morning of Sale, and Catalogues had.

Now ready, Price 6*s.*, Part II., Vol. XV., January, 1881.

THE JOURNAL OF ANATOMY AND PHYSIOLOGY, NORMAL AND PATHOLOGICAL.

CONDUCTED BY

Profs. HUMPHRY, TURNER, M'KENDRICK, & Dr. CREIGHTON.

Contents.

1. Bones, Articulations, and Muscles of Rudimentary Hind-limb of Greenland Right-Whale. By J. Struthers, M.D. (Plates XIV.–XVII.)
2. Infective Form of Tuberculosis in Man identical with Bovine Tuberculosis. By C. Creighton, M.D.
3. Medullary Neuroma of Brain. By W. Osler, M.D. (Plate XVIII)
4. Dissection of Genito-Urinary Organs in Case of Fissure of Abdominal Walls. By A. Doran, F.R.C.S. (Plate XIX.)
5. Description of a Polygraph (with Figure). By D. Newman, M.B.
6. Remarks on Mechanism of Secretion of Sweat. By C. Handfield Jones, M.B.
7. Anomalous Growth-Bearing Pilose Skin in Pharynx of a Young Woman. By P. S. Abraham, M.A. (With Figure.)
8. Histology of Granular Kidney (with Figure). By R. Saundby, M.D.
9. Two Cases of Cerebellar Disease. By T. Oliver, M.D.
10. Colouring Matter of Jelly Fishes. By Prof. M'Kendrick.
11. Nerves of the Hind-Limb of the Thylacine and Cuscus. By D. J. Cunningham, M.D.
12. Pulse Dicrotism. By Wm. Jas. Fleming, M.D.
13. Anatomical Notices.

MACMILLAN & CO., London and Cambridge.

"The leading Farmers' paper."—CLARE SEWELL READ, Esq., M.P.

THE CHAMBER OF AGRICULTURE JOURNAL AND FARMERS' CHRONICLE

(PRICE 3*d.* WEEKLY).

The representative organ of the Central and Provincial Chambers of Agriculture; *gives fuller reports of the discussions and proceedings* of this extensive organisation than any other agricultural paper. It devotes *special attention to the treatment of Agricultural Questions by Parliament*, besides containing ample Reports of the LATEST LONDON and COUNTRY CORN, CATTLE, HOP, PROVISION, and other Markets, with Original Articles on Practical Farming, the Dairy, Herd and Flock News, Horticulture, &c., &c. It is despatched every Monday evening in time for the country post.

Terms of Subscription, payable in advance, post free:—3 months, 3*s.* 9½*d.*; 6 months, 7*s.* 7*d.*; 12 months, 15*s.* 2*d.*

Published by W. PICKERING, 21, Arundel Street, Strand, London, W.C.

Chaque Samedi 16 pages grand in-8°, 2 colonnes

REVUE HEBDOMADAIRE

Scientifique, illustrée, spéciale, seul journal tenant les lecteurs au courant de tous les détails de l'Exposition universelle d'électricité, organe indépendant des exposants

RÉDACTEUR EN CHEF : **W. de FONVIELLE**

E. de CLISSON : DIRECTEUR

Un numéro, **40** *centimes. — L'année*, **48** *francs. Union postale* **20** *francs.*

PARIS, 16, rue du Croissant, PARIS

Envoi de numéros spécimens gratis sur demande

THE BREWERS' GUARDIAN:

A Fortnightly Paper devoted to the Protection of Brewers' Interests, Licensing, Legal, and Parliamentary Matters.

REVIEW OF THE MALT AND HOP TRADES; AND WINE AND SPIRIT TRADE RECORD.

The Organ of the Country Brewers.

"The Brewers' Guardian" is published on the evenings of every alternate Tuesday, and is the only journal officially connected with brewing interests. Subscription, 16*s.* 6*d.* per annum, post free, dating from any quarter-day. Single Copies 1*s.* each. Registered for transmission abroad.

Offices—5, Bond Court, Walbrook, London, E.C.

THE ART JOURNAL.

NEW SERIES.

With the JANUARY NUMBER a NEW SERIES of the ART JOURNAL was COMMENCED, with several important Alterations and Additions.

THE ART JOURNAL.—ETCHINGS.—An Etching will be included with Every Number of the Journal during the year 1881. The Etching for February is "An Old German Mill," by A. H. Haig.

THE ART JOURNAL.—OLD BATTERSEA BRIDGE, with Facsimiles from Etchings of the Old Bridge and Whistler's House at Chelsea, by Mr. S. A. McN. Whistler, appears in the February Number.

THE ART JOURNAL.—INDUSTRIAL ART.—A Series of Illustrated Papers will be continued Monthly on "Our Home Surroundings." The first, on "Chimney-pieces and Over-shelves," is continued in the February Number. The principal Art Furniture Manufacturers have promised their assistance.

THE ART JOURNAL.—Hints to Collectors of ETCHINGS, Water-colour Drawings, Lacquer, Ivories, Marqueterie, China, Turner's Liber Studiorum, &c.—A series of practical Papers on these subjects from the pens of Mr. Seymour Haden, Mr. Roget, Mr. Rawlinson, Mr. Cutler, Mr. A. Nesbitt, and others will appear in the course of the year. IVORIES, Part I., by A. Nesbitt, is in the February Number.

THE ART JOURNAL.—ARTISTS will find every information respecting forthcoming Exhibitions and other matters of importance to them. A portion of the Journal will be devoted each month to Queries on Art Matters.

THE ART JOURNAL.—PROOFS of the ETCHINGS.—One Hundred Proofs of each of the Etchings will be printed from the original plates. Price 21*s.* each, or £10 10*s.* for the series of 12.

THE ART JOURNAL.—Published Monthly, price 2*s.* 6*d.*

London: ART JOURNAL OFFICE, Ivy Lane, Paternoster Row.

THE NEW BIOLOGICAL JOURNAL.

ARCHIVES DE BIOLOGIE.

Edited by Professors EDOUARD VAN BENEDEN of Liège, and VAN BAMBEKE of Ghent.

This Journal is devoted to the publication of original Memoirs on the Embryology, Histology, Physiology, and Comparative Anatomy of Plants and Animals. Each number is illustrated with numerous Coloured Plates, and appears at the commencement of the Quarter.

Price:—A Single Number, Six Shillings and Sixpence. Annual Subscription: Twenty-five Shillings, or Twenty-seven Shillings post free.

Orders received by Messrs. WILLIAMS & NORGATE, 14, Henrietta Street, Covent Garden, London.

In the first two numbers have appeared:—

VAN BENEDEN: On the Embryology of the Mammalia.

VAN BAMBEKE: On the Cleavage of the Egg in Batrachia.

FOR HINGER: On the Termination of Nerves in the Muscles of Insects.

FREDERIQUE AND VANDEVELDE: On the Physiology of the Muscles and Nerves of the Lobster.

MACLEOD: On the Harderian Gland of the Duck, &c., &c.

LA SEMAINE FRANÇAISE: a Weekly

Newspaper and Review in the French Language. Politics, Literature, Science, Art, Varieties, Notes. Price 3*d.*, through booksellers, and at the railway bookstalls. Office, 37, Southampton Street, Strand, W.C.

LA SEMAINE FRANÇAISE: Journal Français pour l'Angleterre: Politique, Littérature, Sciences, Arts, Variétés, Nouvelles, et Notes. Un exemplaire par la poste, 3½*d.*, en timbres poste. Abonnement franco par la poste—un an, 15*s.* 2*d.*; six mois, 7*s.* 7*d.* Prix 3*d.*, chez tous les libraires et aux gares des chemins de fer. On s'abonne aux bureaux, 37, Southampton Street, Strand, Londres, W.C.

LA SEMAINE FRANÇAISE.—"'La Semaine Française' has been brought out in London for the benefit of those English readers who may wish to study contemporary French from all points of view, instead of confining their reading to one particular Gallic print. It certainly merits success."—*Graphic.*

LA SEMAINE FRANÇAISE.—"The numbers before us are full of good things. . . . . It will be far better for most than any one of the best papers published in Paris itself. We are much pleased with the character of it, and believe it will be highly valued in all those many households where French is cultivated. The printing is very well done."—*Queen.*

TERMS OF SUBSCRIPTION:—

	s.	*d.*
Three months	3	10
Six ,,	7	7
Twelve ,,	15	2

P.O.O. payable to T. SPANSWICK, at King Street, Covent Garden, W.C.

Publishing Office, 37, Southampton Street, Strand, W.C.

"NATURE," Nov. 14, 1878, No. 472.—One Shilling each will be paid for Copies of this number.—Address Publishers of NATURE, 29, Bedford Street, Strand, W.C.

JUST PUBLISHED, Crown 8vo, cloth. 5s.

CONSCIOUS MATTER:

OR,

THE PHYSICAL and the PSYCHICAL UNIVERSALLY IN CAUSAL CONNECTION.

By W. STEWART DUNCAN.

London: DAVID BOGUE, 3, St. Martin's Place, Trafalgar Square, W.C.

With Illustrations and Maps, medium 8vo, 18s.

ISLAND LIFE:

OR, THE PHENOMENA AND CAUSES OF INSULAR FAUNAS AND FLORAS, INCLUDING A REVISION AND ATTEMPTED SOLUTION OF THE PROBLEM OF GEOLOGICAL CLIMATES. By ALFRED RUSSEL WALLACE, Author of "The Malay Archipelago," 'The Geographical Distribution of Animals," &c.

"Mr. Wallace discusses in an admirably clear and able manner the questions of geological climate and time . . . such are only a few of the great problems discussed in this most instructive volume—a volume that ought to interest every thoughtful reader. While its theories are likely to meet with keen criticism from Mr. Wallace's fellow-scientists, his volume ought more than any other we know of to spread among the intelligent reading public a knowledge of and interest in some of the most momentous scientific problems of our time."—*Times.*

"His wonderful grasp of detail, depth of insight, and breadth of view remind one at every turn of Darwin, with whom he shares the honours of discovery in the theory of natural selection; but beyond this he has a lightness of touch, a beauty of style, and an ingenuity in unravelling intricate difficulties which are all his own. . . . 'Island Life' is a work to be accepted almost without reservation from beginning to end. . . . Whoever reads his book must be charmed with it."—*St. James's Gazette.*

"The work throughout abounds with interest. . . . It may be read with equal pleasure by those who are already acquainted with the general principles of distribution and by those who wish for the first time to learn something about modern biological geography."—*Athenæum.*

"We have said enough to show that Mr. Wallace is led to discuss subjects of great interest to speculative minds. With its numerous special maps 'Island Life' ought to prove as interesting as it is instructive."—*Pall Mall Gazette.*

MACMILLAN AND CO., LONDON.

In Medium 8vo, price 18s. Vol. I.

A TREATISE ON

COMPARATIVE EMBRYOLOGY.

By F. M. BALFOUR, M.A., F.R.S., Fellow and Lecturer of Trinity College, Cambridge. In Two Vols. Illustrated.

"It is scarcely possible to exaggerate the expressions of gratitude which are due from zoologists to Mr. Balfour for the execution of the great task which some three or four years ago he set himself. . . . Zoologists have to be thankful to him for the admirable style in which he has carried out his work."—*Nature.*

MACMILLAN AND CO., LONDON.

Just Published, demy 8vo, cloth, with Chart, price 15s.

ON SOME PROPERTIES OF THE EARTH.

By O. REICHENBACH.

London: WERTHEIMER, LEA, & CO., Circus Place, London Wall.

EDITED BY HENRY WATTS, B.A., F.R.S.,
Editor of the *Journal* of the Chemical Society.

FOWNES' PHYSICAL and INORGANIC CHEMISTRY. Twelfth Edition, with Coloured Plate and 154 Engravings, crown 8vo. 8s. 6d.

Also,

FOWNES' CHEMISTRY OF CARBON COMPOUNDS; or, ORGANIC CHEMISTRY. Twelfth Edition, with Engravings, crown 8vo. 10s.

London: J. & A. CHURCHILL.

Recently Published,
Demy 4to, with 18 Plates (5 printed in Colours), 207 pages, cloth, £2 2s.

AURORÆ:

THEIR CHARACTERS AND SPECTRA.

By J. RAND CAPRON, F.R.A.S.

Part I.—THE AURORA AND ITS CHARACTERS.
Part II.—THE SPECTRUM OF THE AURORA.
Part III.—MAGNETO-ELECTRIC EXPERIMENTS IN CONNECTION WITH THE AURORA.

By the same Author.
Demy 8vo, with 37 Plates, cloth, 30s.

PHOTOGRAPHED SPECTRA.

One Hundred and Thirty-Six Photographs of Metallic, Gaseous, and other Spectra, printed by the Permanent Autotype Process, with Introduction, Description of Plates, and Index, and with an Extra Plate of the Solar Spectrum (showing bright lines) compared with the Air Spectrum.

London: E. & F. N. SPON, 16, Charing Cross.

In unserem Verlage erscheint:

DER NATURFORSCHER.

Wochenblatt zur Verbreitung der Fortschritte in den Naturwissenschaften.

Herausgegeben von Dr. WILHELM SKLAREK.

Wöchentlich 1—1½ Bgn. in 4°.

Preis vierteljährlich 4 Mk.

Die nunmehr ihren XIV. Jahrgang beginnende Zeitschrift hat bei Allen, welche sich mit Naturwissenschaften beschäftigen, grossen Beifall gefunden. Probenummern sind durch jede Buchhandlung zu erhalten.

Berlin, S.-W., 77, Charlottenstr.

FERD. DÜMMLER'S VERLAGSBUCHHANDLUNG
(Harrwitz & Gossmann.)

POTTERY.

A SERIES OF URNS, &c.,

INCLUDING

BRITISH, ROMAN, SCANDINAVIAN, PERUVIAN.

To be Sold at Extremely Low Prices, the Owner being desirous of immediately parting with them.

BRYCE-WRIGHT,

90, GREAT RUSSELL STREET, LONDON, W.C

METALS and their CHIEF INDUSTRIAL APPLICATIONS. By C. ALDER WRIGHT, D.Sc., Lecturer on Chemistry in St. Mary's Hospital Medical School. With Illustrations.

MACMILLAN & CO., LONDON.

THURSDAY, FEBRUARY 10, 1881

ALPINE FLOWERS

Alpenblumen ihre Befruchtung durch Insekten und ihre Anpassungen au dieselben. Von Dr. Herman Müller, Oberlehrer an der Realschule I. Ordnung zu Lippstadt. 8vo, 611 pp. (Leipzig: W. Engelmann, 1881.)

THE naturalist who studies animals or plants in a state of nature must often wish that he could test his conclusions experimentally by varying the conditions under which a given set of facts are observed. He wishes that he could change the food of a group of organisms, or the climate to which they were exposed, or that he could diminish the numbers of one sub-group while those of another were increased. As he cannot do this he is obliged to be content with treating the facts within his grasp in the spirit of an experimentalist, by comparing large classes of facts as they occur under different conditions.

The present volume of Dr. Müller's is something more than a descriptive study of the means of fertilisation found among alpine plants, for it is an admirable example of the kind of comparative investigation to which we have alluded, and as such is an extremely valuable contribution to the general science of plant-fertilisation.

It is a difficulty inherent in such inquiries that the observer, not having had a hand in varying the conditions, has to discover exactly in what way the environments differ in his two stations of observation. The most important feature in the environment of a plant considered in relation to fertilisation is the manner in which it is visited by insects. Thus an extensive knowledge of the alpine and lowland insect fauna is a necessary part of Dr. Hermann Müller's inquiry. Nor is it enough to study as an entomologist the relative frequency of bees, flies, butterflies, &c., in the mountains and in the plains; but the observer must discover by long and patient observation the different manner in which these insects visit the flowers in the two regions. The amount of this kind of labour condensed into the volume may be guessed at by looking at the long lists of insect-visits appended to each plant described, or arranged in the statistical tables in the latter part of the book.

The collection of this mass of detail must have tried Dr. Müller's almost unbounded energy and patience to the utmost. Several weeks in each of the last six summers have been devoted to the research; and the record of a single day's work (which we are glad to find was a somewhat exceptional one) will show how well the time at his command has been utilised. On this day, which was spent in the Heuthal on the Bernina, he was surrounded by flowers and insects from 8 a.m. to 4 p.m., during which interval he made notes on the visits of 237 insects, 225 of which were numbered and brought home. Dr. Müller adds that he was continuously spurred to the utmost of his powers by the consciousness that numbers of insects were making unobserved visits behind his back.

Nor has his energy and ingenuity in classifying and tabulating his results been less remarkable, as will be seen by an examination of the twelve tables which are interspersed in the latter part of the book; in these tables the visits of the various orders of insects to various kinds of flowers in different localities are numerically compared.

It is not a little remarkable that the visits of insects, which to the ordinary observer appear so casual and lawless, should be capable of such strict and statistical treatment. But it should be remembered that treatment of this kind is only possible with the large mass of facts which Dr. Müller has collected.

The most striking facts in the book are those connected with the predominance of butterflies in the alpine regions. The changes which occur in the insect fauna as we ascend are briefly that the relative number of Lepidoptera and Diptera (especially the short-trunked flies) increase, while the Hymenoptera and Coleoptera, as well as the other unimportant kinds, diminish in relative number. Thus if we compare the number of different visits made to flowers in the lowlands and the alps,[1] we find the following proportions:—

	Lowlands.	Alps.
Lepidoptera	100	614
Diptera	100	109
Hymenoptera	100	35·5

the number of visits made by each order of insects in the lowlands being taken as 100.

One marked result is that classes of flowers chiefly visited by bees in the lower regions are in the alps much frequented by Lepidoptera. Thus, of a hundred different visits made to Papilionaceæ in the lowlands 73 per cent. are those of Apidæ, 17 per cent. are made by Lepidoptera, so that in the plains they are markedly "bee-flowers." But in the alps only 40 per cent. of the visits made to Papilionaceæ are those of bees, and 56 per cent. are those of Lepidoptera. The same fact was observed in the Labiates and in a number of Composite flowers. The adaptations which alpine flowers exhibit in relation to this preponderance of Lepidoptera form some of the most interesting parts of the book; with some of the facts the readers of NATURE are already familiar, through Dr. Müller's admirable articles on the subject which have appeared in these pages. The principle which underlies these alpine modifications may be illustrated by two sections of the genus Gentian. In the first of these (Cœlanthe) fertilisation is effected by humble-bees creeping inside the corolla. This necessitates so wide a tube that Lepidoptera can steal the nectar without effecting fertilisation. The second section, Cyclostigma, is characteristic of the alpine regions, and the flower has been adapted for fertilisation by Lepidoptera. The passage by which the nectar is reached is so narrow that the proboscis of the butterfly is obliged to touch the anthers, and to effect cross-fertilisation. At the same time the tube in many of the Cyclostigmata is so much lengthened that only such a long proboscis as that of Macroglossus or of Deilephila can reach the nectar. It is probable that the first steps towards the development of closed nectaries were originally serviceable to the plant in protecting the nectar from rain; the flowers being thus rendered more attractive, because the visiting insects had a chance of finding undiluted nectar even after a shower. The lengthening of the corolla tube in the above-mentioned section of Gentians which protects the nectar from all but a few long-trunked insects, confers the same kind of advantage on the flower, for it is thus rendered highly attractive to those insects which can alone obtain

[1] Alpine as used by Dr. Müller means above the tree-limits.

the honey; and they will fly from flower to flower, passing over the less attractive kinds.

The genus Rhinanthus has been made especially interesting by Dr. Müller. Rhinanthus is essentially a "bee-flower," but *R. alpinus* has been modified so as to be fertilised by Lepidoptera. The ordinary entrance by which bees visit the flowers of *Rhinanthus cristagalli* is here closed, and a special "butterfly-door," a minute aperture at the tip of the upper lip, has been developed; it is moreover advertised to Lepidoptera by a pair of violet flaps on each side of the entrance. The interesting point about this genus is the existence in it of a species which shows in what manner the flower of *R. alpinus* (fitted for Lepidoptera) may have been developed out of a "bee-flower" such as *R. cristagalli*. This intermediate form (*R. alectorolophus*) possesses a "Lepidoptera-door" like that of *R. alpinus*, but has not closed the bee-door; it is therefore visited by both bees and Lepidoptera and cross-fertilised by both. In spite of our knowledge of this interesting intermediate form, the evolution of *R. alpinus* remains a difficulty. For although it is adapted for the legitimate visits of Lepidoptera only, it is plundered by bees, who break in by the closed bee-door; and these useless or injurious visits are actually more frequent than the advantageous ones of Lepidoptera. It seems impossible to believe that a butterfly-flower could be developed under such circumstances, and the only explanation which Dr. Müller offers requires the assumption of two changes of condition. First, the spread of the bee-fertilised ancestors into regions (such as the Heuthal in the Bernina) where they would be visited exclusively by Lepidoptera, and where the present form of the corolla might be developed. Secondly, we must suppose that the plant has spread into regions where it is visited by bees; or else the plant has remained stationary while bees have invaded its habitat. A similar kind of argument is applied to those flowers, *Polygala alpestris*, various Papilionaceæ, &c., which, though structurally adapted for fertilisation by bees, are, in the alps, chiefly visited by Lepidoptera. They cannot therefore have been developed in their present habitat, but must have spread to the alps from the lowland regions.[1] Dr. Müller compares flowers like *Rhinanthus alpinus*, Gentiana, (Cyclostigma), *Erica carnea*, &c., to air-breathing vertebrates which have been derived from water-breathing ancestors, whose gills have been replaced by special air-breathing structures—the lungs; while *Rhinanthus alectorolophus* corresponds to those intermediate forms which still possess both gills and lungs. We may perhaps, by an inversion of the simile, compare such plants as *Polygala alpestris*, a nearly unmodified bee-flower visited almost exclusively by Lepidoptera, to the Cetacea, which, though actually breathing air, lead almost the life of a fish.

Dr. Müller's treatment of the genera Rhinanthus and Gentiana are instances of the manner in which many other groups are treated. Thus the interesting series of forms exhibited by the Caryophylleæ suggest the possible steps through which bright-coloured flowers adapted for Lepidoptera, such as those of the pinks, have been developed from the pale-coloured scentless flowers with unprotected nectar which are chiefly visited by Diptera.

[1] This view is, for reasons given in the text, put forward merely as a speculation (p. 559).

The present volume gives continual evidence of Dr. Müller's knowledge of the structure and habits of insects. But it does not (and this could not have been expected) contain anything like the valuable study of insects contained in the author's "Befruchtung"—a research of which we take this opportunity of expressing our high admiration, in which we shall be joined by those of our readers who remember the excellent articles by Dr. Müller on insects which appeared in these pages.

In considering the modifications of flowers produced by their relations to insects, we are prepared to find that, for instance, flowers fertilised by bees differ in shape from those visited exclusively by Lepidoptera, but it does not seem *primâ facie* probable that the colours should be characteristic of the two classes. Yet Dr. Müller believes that this is the case, and shows how it may probably be connected with fundamental differences between the lives of bees and butterflies. A bee having to work not only for its own livelihood but also for its nest, is driven to a greater degree of activity than the self-indulgent butterfly. It is therefore important that a bee should work with more method, and thus it happens that bees usually visit one species of flower at a time, instead of passing from species to species and wasting time in the constant change of action. On this account it is obviously an advantage for a bee to be able to distinguish easily a large number of species, thus their unconscious selection has acted in the direction of producing great variety of colouring. It is indeed a remarkable fact that flowers which are visited by short-trunked insects are often characterised by a single colour (usually yellow or white) running through a whole group, whereas closely-related "bee-flowers" are generally varied in colour.

Here then we have a curious chain of cause and effect, beginning with the fact that bees have to provide food for their young, and ending with the varied colours of species of Labiates, Pedicularis, and Trifolium, &c.! If any proof is needed of the correctness of the first link in the argument, it may be found in the curious fact that parasitic or cuckoo bees differ markedly from other bees in their habits,[1] visiting merely those flowers whence they can obtain enough honey for themselves with least trouble and doing it in a dawdling manner which meets with no approval from Dr. Müller.

In the flowers adapted for or chiefly visited by Lepidoptera, red and in a less degree blue are the prevailing tints. There seem to be some grounds for believing that butterflies prefer flowers resembling themselves in tint, Thus in sunshiny weather the orange-yellow flower-heads of Arnica, *Senecio Doronicum*, &c., and the orange-red ones of *Crepis aurea* and *Hieracium aurantiacum* are veritable "Tummelplätze" for yellow-red species of Argynnis and Melitæa. On the other hand the blue Phyteumas which decorate the alpine turf in thousands are especially visited by blue Lepidoptera ("Blues"). It is hard to say whether the butterflies have preferred flowers coloured like themselves, because these tints have been already rendered attractive through sexual selection. Or whether *vice versâ* we may suppose that the colours of their favourite flowers have reappeared as sexual decoration; or lastly, that

[1] P. 522; Dr. Müller adds a caution that the number of observations on this point are perhaps hardly sufficient to warrant a well-grounded conclusion.

some physical quality in their organisation makes certain colours attractive wherever they appear.

To Dr. Hermann Müller belongs the credit of studying not only the means by which cross-fertilisation is effected, but also the means for ensuring cross-fertilisation. He has indeed made this subject peculiarly his own, and has worked it out with valuable and striking results. He has pointed out that flowers which are incapable of self-fertilisation may run great risks of not being fertilised at all. Whereas the flowers in which self-fertilisation is possible are in no danger of becoming sterile, though they may lose the advantage of cross-fertilisation. He has shown that in many plants two forms of flowers exist, one adapted for cross- the other for self-fertilisation. This is the case with *Lysimachia vulgaris* ("Befruchtung," p. 348); when it grows in sunny places where it is freely visited by insects, it has large dark-yellow petals coloured red at the base, conspicuously coloured filaments, and sexual organs arranged so that self-fertilisation can hardly occur; the other form grows in shady ditches, and has a pale yellow corolla and inconspicuous filaments, and the style is so short that self-fertilisation will be sure to take place if no insects visit the flower.

The present volume, though it does not, as far as we are aware, add anything new in principle to the subject of self-fertilisation, contains many illustrations of the correctness of Dr. Müller's views.

We cannot pretend to give, in the short compass of a review article, any fair idea of the richness of Dr. Müller's latest work in new facts and generalisations; we conclude by expressing a hope that it may before long find a translator, or what is a much greater difficulty—a publisher in England.

FRANCIS DARWIN

OUR BOOK SHELF

Lehrbuch der organischen Qualitativen Analyse. Von Dr. Chr. Th. Barfoed. Zweite Lieferung. (Kopenhagen: Andr. Fried. Höst und Sohn, 1881.)

THE first part of this excellent book has already been noticed in these columns. The book is to consist of three parts: the second, which is now published, is characterised by the same completeness and exactness which rendered the earlier part so valuable as a reference book for the laboratory. The present part treats fully of the methods for detecting, in mixtures of varying degrees of complexity, alcohol, ether, chloral, neutral fats, volatile oils, sugar, gum, albumin, &c.

LETTERS TO THE EDITOR

[*The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts. No notice is taken of anonymous communications.*

The Editor urgently requests correspondents to keep their letters as short as possible. The pressure on his space is so great that it is impossible otherwise to ensure the appearance even of communications containing interesting and novel facts.]

Mr. Butler's "Unconscious Memory"

MR. BUTLER appears to have somewhat misunderstood the aim and scope of my review. He says, "It is true I have attacked Mr. Darwin, but Mr. Romanes has done nothing to show that I was not warranted in doing so." Why should Mr. Butler have expected any such consideration of his case from me? If I were to assault a man in the street I should not expect the policeman to show that I was not warranted in doing so; it would be for me to show that I was so warranted. Therefore, while acting the part of policeman in this matter, my only object was that which I stated, viz. the punishment of an offender, not the refutation of charges which I advisedly characterised as "preposterous, and indeed ridiculous." Truly it would have been a senseless thing had I for a moment imagined that such charges called for anything like a defence of Mr. Darwin. If ever in the world's history there was a book which appealed to all classes of intelligent readers, that book is the "Origin of Species"; and never in the world's history has a book been more studiously criticised or produced a more tremendous change of thought. Can Mr. Butler therefore seriously believe, that after this book has thundered through the world for more than twenty years, it required him to show in what degree it had been anticipated by some of the most celebrated writers within the last two or three generations? Surely common modesty and common sense, were either present, might alike have dictated caution in attributing to all the world an ignorance such as his own, which could be "thrown off the scent of the earlier evolutionists" by anything that Mr. Darwin could say. The publication of the "Origin of Species" could only have had the effect, whether or not its author desired it, of directing renewed attention to the works of "the earlier evolutionists"; and therefore, to put it on no other grounds, it is difficult to imagine a case in which any intentional concealment of the claims of predecessors could well be more impolitic. But the simple fact is that these predecessors had no claims to be concealed, further than those mentioned in my previous communication; that is to say, while they unquestionably and *notoriously* believed in the fact of evolution, they had nothing which deserves to be called a theory of evolution. Therefore, when Mr. Butler asks of the opening passage in the "Origin of Species," "What could . . . . . more distinctly imply that the whole theory of evolution that follows was a growth in Mr. Darwin's own mind?" the answer simply is that this whole theory *was* a growth in Mr. Darwin's own mind. And if Mr. Butler has not judgment enough to distinguish between the scientific value of Mr. Darwin's work and that of "the earlier evolutionists," at least he might pay sufficient deference to the judgment "of all Europe and those most capable of judging" to explain why it is that the work of all the earlier evolutionists proved barren, while the work of Mr. Darwin has produced results unparalleled in the history of thought.

But I am being drawn into a mere waste of time in thus discussing what every one must feel does not admit of discussion. My object in now writing is not to justify Mr. Butler's view that Mr. Darwin requires to be defended from any such nonsensical "attack"; I write in order to withdraw two passages from my review. Mr. Butler says I was wrong in implying that he supposed Mr. Darwin to have entered into a conspiracy with Dr. Krause; he merely supposes Dr. Krause to have acted the part of a "cat's-paw." In this therefore I stand corrected; for while reading "Unconscious Memory" it never occurred to me that Mr. Butler's view was other than I stated. The second passage which I desire to cancel is that which attributes a motive to Mr. Butler in publishing "Evolution, Old and New." He scornfully repudiates the motive which I attributed, and I therefore willingly withdraw the attribution—observing merely that I was induced to advance it because it seemed to present the only rational motive that could have led to the publication of such a book.

Two other allusions to myself may be noticed before I end. Mr. Butler says, "I suppose Mr. Romanes will maintain me to be so unimportant a person that Mr. Darwin has no call to bear in mind the first principles of fair play where I am concerned." To this I answer emphatically, No; but I do maintain that had Mr. Butler been a more important person than he is, he would not have regarded the mere omission of a foot-note of reference to his book, either as an intentional wrong to himself, or as a matter of such grave concern to the public.

Lastly, Mr. Butler says, "I maintain that Mr. Darwin's recent action and that of those who, like Mr. Romanes, defend it, has a lowering effect upon this standard [*i.e.* of good faith and gentlemanly conduct]." I am sure the world of science ought to feel very grateful to Mr. Butler for his kind solicitude on the subject of its morals and gentlemanly feeling. But he has already said in "Unconscious Memory" that he does not look to "ladies and gentlemen of science" for much sympathy, seeing that his case rests on "facts," and that among these "ladies and gentlemen" "familiarity breeds contempt of facts"; and I fear that in this his conclusion will prove better than his argument. For unless some facts and feelings are displayed other than those already exhibited, I cannot think

that either the morality or the courtesy of the scientific world is likely to be improved by the renewed exertions on their behalf which are about to be made by Mr. Samuel Butler.

GEORGE J. ROMANES.

[This correspondence is now closed.—ED.]

WILL it go any way towards calming Mr. Butler's zeal in the cause of literary honesty to remark that at any rate fifteen years ago, and it may have been further back, Mr. Darwin prefixed to "The Origin of Species" a historical sketch of the progress of opinion on that subject? In view of this it is at least very *misleading* on the part of Mr. Butler to quote the first sentence from the edition of 1859, and then to ask: "What could more completely throw us off the scent of the earliest evolutionists?" as if in those days it would have made a pin's difference to him, or any one else whom he includes in the *us*, whether the scent of the earlier evolutionists lay strong or weak in the track. In these days he should know, if he knows anything of the history of opinion, that these predecessors of Mr. Darwin, with their great though varied merits, had been laughed down, and, for all popular estimation, might be said to have disappeared. To have relied in any way on their authority when Mr. Darwin's book was first published might well have increased the mountain of prejudice against his views without in any way relieving the weight of ridicule that lay upon theirs. When the whole scientific world had been stirred to its foundations and when the whole world almost had been roused into paying attention to science by the awakening genius displayed in the new exposition *de rerum naturâ*, then, when it could best be done, Mr. Darwin turned ridicule into renown, and made all who could even remotely claim to have anticipated or shared his views participators of his fame. Not those who scatter seed at random, but those who cultivate it in chosen ground with indefatigable industry and prevailing skill should, I imagine, be considered the chief benefactors of mankind; and in like manner the fancy that may have fluttered uselessly through many brains becomes at last a fruitful hypothesis or a wide-stretching theory when it falls beneath the cultivation of undaunted genius.

T. R. R. STEBBING

Tunbridge Wells, February 7

"Prehistoric Europe"

WILL you kindly allow me a few words in reply to certain statements made by Prof. Dawkins in his notice of my "Prehistoric Europe." I shall not remark on the perplexing confusion which he gravely puts forward as an outline of my general argument further than to say, in all sincerity, that I fail to recognise in it any trace of what that argument really is. The few observations I have to make shall be confined chiefly to questions of fact.

1. Mr. Dawkins states that I ask geologists to believe that the mammaliferous gravels with Palæolithic implements, which overlie the chalky boulder-clay of East Anglia, were covered by an upper and younger boulder-clay, which latter "has been removed so completely that no trace of it is now to be seen." Now I do not believe that the gravels in question ever were covered by boulder-clay, nor have I written anything which could justify Mr. Dawkins in attributing to me an opinion so absurd.

2. The account I have given of Victoria Cave was written after a careful perusal of all that has been said about it, and my proofs were submitted to Mr. Tiddeman, who reported on the explorations; and therefore I have every reason to believe that my description is correct.

3. The so-called Upper Pliocene deposits at Mont Perrier are described in detail by Dr. Julien, who shows that they are truly interglacial, being younger than the great "pumiceous conglomerate" with its striated stones and blocks, and older than the more recent moraines of the same neighbourhood. Dr. Julien remarks: "La période pliocène supérieure doit disparaître de la science." He correlates the interglacial beds of Mont Perrier with those of Dürnten.

4. The lignites of Leffe and Borlezza, according to Prof. Stopanni, who has carefully studied those closely-adjoining districts, belongs without any doubt whatever to the glacial series; and his observations I have confirmed by a personal examination of the ground. They are generally admitted by Italian and Swiss geologists to be on the same horizon as the lignites of Dürnten.

5. I have not asserted the interglacial age of the so-called Pliocene of Olmo. The newer deposits in the Upper Val d'Arno, which have usually been assigned by palæontologists to the Upper Pliocene, have been shown by Prof. Mayer, after an exhaustive analysis of the evidence (as well stratigraphical as palæontological) to belong to the Pleistocene; and as their mammalian fauna corresponds with the fauna of the lignites of Leffe and Borlezza, I have said that this fact is "significant," meaning thereby that the beds in question may very likely be of the same age as those near Gandino.

6. Mr. Dawkins says that I deal with my subject not with the impartiality of a judge, but as an advocate, and that I have only called those witnesses which count on my side. I am probably as well acquainted with the literature of the subject as my critic, and after many years' careful reading and study must confess that I have not encountered any evidence that contradicts my views. Had it been my fortune to come upon such evidence I feel sure that I should not have been so weak and foolish, or so untruthful as to have ignored it. Doubtless I have met with many forcible statements of opinion by Mr. Dawkins that he does not agree with me; but I may remind him (and not for the first time) that mere expressions of opinion, however emphatic, prove nothing save, as a rule, the sincerity of him who utters them.

7. My critic further ventures the statement that my classification "is based on ice, and ice only." How very far this is from being the case any candid person may see who shall take the trouble merely to run his eye over the "contents" of my book. Geologists rightly refuse to accept classifications which are based upon so narrow a foundation as a single series of phenomena, such, for example, as Mr. Dawkins's attempt to classify the Pleistocene by reference to the mammalia alone—a classification which, while it draws the line that separates Pliocene from Pleistocene at the base of the glacial deposits in England, would carry the same line, in France and Central Europe, through the middle of the glacial series. Or, to put it another way, if we accepted Mr. Dawkins's classification, we should be forced to admit that the Glacial Period attained its climax in France and Central Europe during Pliocene times, but that it did not begin in England until after the Pleistocene had commenced. And this is the classification which, as may be inferred from the tenor of my critic's remarks, I ought to have adopted.

Mr. Dawkins's remarks upon my views in regard to the evidence of climatic changes I am sorry to say I do not understand. All that I am sure of is that he has quite failed to grasp my meaning—that he has attributed to me opinions which I have done my best to refute—in a word, that he has strangely misrepresented me. But I need not attempt to set him right, as those who are sufficiently interested in the matter are not likely, after this repudiation, to accept his travesty for a reliable presentment of my views.

JAMES GEIKIE

Perth, January 7

On Dust, Fogs, and Clouds

A CURIOUS confirmation of Mr. Aitken's theory of fog was brought to my notice a short time ago. A friend of mine residing in Streatham, struck with the perfection of the heating arrangements in American residences, fitted up his house with a similar contrivance. In the basement was a furnace and boiler which warmed pure air that entered from without, and circulated at a regulated temperature throughout the house. A water-pipe that was connected with the boiler became stopped by frost; an explosion ensued, and the house was filled with so-called steam (hot fog, in fact) from top to bottom. Wherever a cold surface (clock faces, metal fixtures, &c.) was found, even in the topmost bed-rooms, the vapour condensed and left behind it black carbon dust. Nowhere else was this dust found.

Again, few persons who have read Mr. Aitken's paper can have noticed the dejected appearance of the late beautiful snow on the first morning of the welcome thaw without thinking of his theory. What on the previous evening was a clean dazzling mass of exquisite white became a sooty speckled heap of dirty snow. As the sparkling crystals liquefied into water which drained away, they left behind the dust and carbon, around which, according to Mr. Aitken, they originally formed, becoming by multiplication molar and visible. In the streets of London the masses of white snow rapidly became, as somebody remarked, like streams of cold *café au lait*. The whiteness rapidly disappeared and left behind mere dirt.

It may interest some of your readers to know that in 1537

Benvenuto Cellini was attracted to Paris from Florence in consequence of the much clearer and more beautiful atmosphere in the capital of France than in Italy! This fact is derived from the artist's autobiography. What a change now! Paris is rapidly becoming as bad as London. W. H. PREECE

February 5

IN NATURE, vol. xxiii. p. 195, I found an interesting abstract of a paper read to the Royal Society of Edinburgh, December 20, by Mr. John Aitken, showing "that dust is the germ of which fogs and clouds are the developed phenomena." It is not in the least the intention of this letter to diminish the value of the above-mentioned paper and experiments, but I wished to say that already, several years past, the same results were obtained by Messrs. Coulier and Mascart (1875) in France (*Naturforscher*, 1875, p. 400; *Journal de Pharmacie et de Chimie*, série 4, xxii. p. 165).

In my "Théorie cosmique de l'Aurore Polaire," p. 36, I have already pointed out the great importance of these results on the relation between auroræ and clouds and the danger of measuring the height of auroral displays by means of superior cloudy apparitions (p. 35). In fact, if the invisible aqueous vapour is able to reach much higher regions than terrestrial dust, and if auroræ are in close connection with cosmical matter in a state of extreme division, like our theory attempts to prove, this cosmical matter is without any doubt enabled to form aqueous clouds in a much higher than the usual level. Moreover we have already, in 1873, in the German journal *Gaea* (Köln und Leipzig, E. H. Mayer), asked: "Welches wohl die weitere Rolle der Eisen- und anderen Dämpfe sei, welche nach der Verbrennung in den oberen Regionen der Atmosphäre schwebend bleiben und offenbar nach vollständiger Abkühlung einen Niederschlag von fein vertheiltem Eisenoxyd und anderen Stoffen bilden. Sollten diese Theilchen . . . keine Veranlassung geben können zu den von deutschen Beobachtern so oft wahrgenommenen 'Polarbändern,'[1] deren Zusammenhang mit dem Nordlicht schon öfters dargethan ward, aber bisher unerklärt blieb. Noch würden wir hinzufügen können, mit Hinweis auf die Beobachtung Secchi's eines angeblichen Nordlichts bei Tage (NATURE, October 17, 1872), dass auch die bis jetzt ganz unerklärte, eigenthümliche Gestalt der Cirri, mit ihren ganz regelmässigen, auf ein gewisses Gesetz hindeutenden transversalen Verzweigungen, von der Anwesenheit feiner Eisenstaubkerne in den Eisnadeln möglicherweise bedingt ist. Bekanntlich schweben diese Cirri in den höchsten Wolkenregionen."

It will further be generally known that microscopic meteorites have been found in the centre of hailstones (*Comptes rendus*, 1872, p. 683). H. J. H. GRONEMAN

Groningen (Netherlands), January, 1881

New Cases of Dimorphism of Flowers—Errors Corrected

REVIEWING my notes and drawings of some years ago, I find the following new cases of dimorphism of flowers:—

1. *Syringa persica*, L., cultivated in the garden of the Lippstädter Realschule, is gynomonœcious. In the same inflorescence there are found a majority of hermaphrodite flowers of larger size and a minority of female flowers of smaller size. The hermaphrodite flowers are homogamous and short-styled, like *Syringa vulgaris*, L. (H. Müller, "Die Befruchtung der Blumen," p. 340, Fig. 125). The anthers of the female flowers, which are much reduced in size and never contain any pollen, are inserted sometimes above, sometimes beneath, but commonly in the same height with the stigma. In some few of the small-sized flowers the number of the petals is reduced to three.

2. *Stellaria glauca*, L., near Lippstadt, is gynodioecious, like *St. graminea*, L., as described by F. Ludwig (*Bot. Centralblatt*, No. vi. p. 28), some stems bearing small-sized flowers with very reduced anthers of white colour and greatly-developed stigmas, a vast majority of other stems bearing larger-sized proterandrous flowers with anthers of red colour.

3. *Sherardia arvensis*, L., near Lippstadt, is likewise gynodioecious, its hermaphrodite flowers being proterandrous and larger-sized, with a corolla of 3½-4 mm. diameter, its female flowers possessing a corolla of only 2½-3 mm. diameter, with extremely reduced anthers.

4. *Asperula tinctoria*, L., produces in Thuringia so frequently flowers with only three petals that in those stems examined by myself by far the greatest part of the flowers were three-petaled.

In my book "Alpenblumen" Dr. Focke of Bremen has detected two errors of naming, which immediately ought to be corrected: the flower described and illustrated on p. 171 is not *Empetrum nigrum*, but *Azalea procumbens*, like that of p. 377; *Cerinthe*, in pp. 264, 265, is not *major*, L., but *glabra*, Mill = *alpina*, Kit. HERMANN MÜLLER

Lippstadt

Geological Climates

I HAVE read with much interest and attention the letters that have appeared in recent numbers of NATURE on the subject of "geological climates," and although it must appear presumptuous on my part to do so, I shall endeavour to show that each of the distinguished writers of these letters may be somewhat in error on at least one point, which—if I am right—must materially affect the correctness of the conclusions they have come to.

I think that Mr. Wallace, whilst very justly giving the Gulf Stream and other currents which *might* exist were certain lands submerged, credit for great influence in ameliorating the rigour of climate, does not take into sufficient consideration the fact that the waters of the Gulf Stream, although warmer, are, in consequence of holding much more salt in solution, heavier than the colder and less saline Arctic current.

Some experiments show, as clearly as anything done on a very small scale can, that two waters brought as nearly as possible to the conditions of the Gulf Stream and the Arctic current do not mingle when simultaneously poured into a long narrow glass trough; the Arctic water invariably taking its place on the surface.

Supposing then that these two currents meet somewhere about latitude 80° or 81° N., the Arctic water flowing south—if my experiments are of any value—will retain its position on the surface and the warm current pass underneath, and thus lose all its heating influence on the air over a Polar area about 1000 geographical miles or more in diameter.

We can have no stronger example of this effect of difference of density of ocean water than is shown by the two currents *in* and *out* of the Mediterranean Sea.

In NATURE, vol. xxiii. p. 242, Prof. Haughton says, "The thickness of this ideal ice-cap at the Pole is unknown, but from what we know of the Palæocrystic ice of Banks Land and Grinnel Land *must be measured by hundreds of feet, and its mean temperature must be at least* 20° F. *below the freezing-point of water.*"

With regard to both the above assumptions—which are in italics—I must beg to disagree entirely with the learned Professor. He appears to consider the so-called Palæocrystic ice as the normal state of the ice at and near the Pole, and as a natural growth by the gradual freezings or increase of a single floe during a series of years; whereas I am of opinion that this mis-called Palæocrystic ice is the result of a number of floes being forced over and under each other by immense pressure caused by gales of wind and currents.

The western and northern shores of Banks and Grinnel Lands are peculiarly well suited for the formation of such ice-heaps, as they are exposed to the full force of the prevailing north and north-west storms, which pile up the ice in a wonderful manner on these shores and others similarly placed, for a distance of miles seaward. The whole of the west shore of Melville Peninsula is so lined with rough ice of this kind that sledging is impossible.

It will wholly depend upon the form of land—if any—at or near the Pole, whether or not any floebergs are there. If there is no land it is probable there will be few or none, as the ice will meet with no great obstruction, as it is driven by winds and currents.

I have no authorities by me that give the thickness of ice formed in one season at or near the winter quarters of any of the Arctic expeditions, except my own in 1853-4 at Repulse Bay, latitude 66° 32′ north.

The measurements of the ice—taken at some distance out in the bay where there was very little snow—and the mean temperature of the air are given on next page.

[1] Or "Polarbanden." My daily observations of these phenomena, beginning with the year 1875, are to be found in the German journal *Wochenschrift*, editor, Dr. Hermann J. Klein in Köln.

1853	Ice thickness	Increase	Monthly Mean Temp. F.
December 20	... 4 feet 7 inches ...	—	... −24°·5 below zero
1854			
January 24	... 5 feet 9 inches	... 14 in 35 days	... −30°·6 ,, ,,
February 25	... 7 feet 0¾ inch	... 16 in 32 days	... −34°·9 ,, ,,
April 25[1]	... 8 feet 1½ inch	... 12¾ in 59 days	... − 8°·5 ,, ,,
May 25	... 8 feet 1¾ inch	... none 30 days	... +24° above zero

The above table shows that the ice ceased to increase in thickness some time between April 25 and May 25, after which it decreased rapidly; but I was unable to decide what proportion of this decrease was due to thaw and evaporation from the surface, and what amount from the lower part of the floe that was under water: no doubt by far the greater effect was produced by the two first causes.

Eight feet may perhaps be considered a fair or rather a high average of one winter's formation of new ice (not increase of an old floe) over the whole of the Arctic Sea, because Repulse Bay, although in a comparatively low latitude, was particularly favourable for ice-formation, there being no currents of any consequence. Where there are currents, one year's ice does not exceed three or four feet.

The winter's ice of 1875-6 at Discovery Bay, in latitude 81° 40′ N., did not exceed, if I remember correctly, six feet in thickness.

Even were these great compound floes, called Palæocrystic ice, found at or near the Pole, and of only the same thickness as those seen at Grinnel Land—instead of "hundreds of feet"—they would not probably have nearly so low an average temperature all the year round as 20° F. below the freezing-point of water, because only one-sixth of their mass would be exposed to very low temperatures for about six months of the year, the surface being during that time protected by a more or less thick covering of snow, whilst at least five-sixths of their bulk was under water, having a temperature for the whole twelve months at or above the freezing-point of the sea. The question is, how far the very low temperatures of an Arctic winter do penetrate a mass of, say sixty feet of ice, the surface of which is covered with a foot of snow, and fifty feet or five-sixths under water of a temperature at or above the freezing-point of the sea?

From my experience on a much smaller scale, I do not believe that the atmospheric cold would, under the circumstances mentioned, penetrate to the lower surface of ice sixty feet thick; and if it does not do so there would be no increase to its thickness during winter.[2]

An excellent example of formation of Palæocrystic ice, or floe-berg is afforded by the experience of the Austro-Hungarian Expedition under Weyprecht and Payer in the Barentz Sea in 1873-4. Their ship was lifted high out of the water by the pressure of the floes, which were forced over and under each other to a great thickness and extent in a very few days.

The ship and her crew were helplessly drifted about for many months, during which the floes were frozen together into one solid mass, and the inequalities of the surface in a great measure filled up with snow-drift. JOHN RAE

4, Addison Gardens, January 29

[1] The mean temperature opposite to April is that of March and April combined, and it will be seen that the average increase of ice for each of these months is only 6¼ inches.

[2] That the sea raises the temperature of the ice on its surface even in very cold weather, is evinced by the fact that a snow hut built on the ice is warmer than if built on the land.

On the Spectrum of Carbon

IN addressing to you my former letter regarding Dr. Watts's experiments on the spectrum of carbon, it was not my intention to enter on any discussion concerning matters of opinion. The reference made in that letter to the difficulty of perfectly drying a gas so as to eliminate the ultra-violet spectrum of water had reference to gases at ordinary atmospheric pressure; and the expectation a gas will be dried "to all intents and purposes" by the use of a U-tube of phosphoric anhydride goes far to explain the origin of different experimental results. The cogent experimental evidence which Dr. Watts justly demands may, so far as the relations of carbon and nitrogen are concerned, be found in our complete papers on the spectrum of carbon compounds in the *Proceedings* of the Royal Society.

The supposition, which appears to be a difficulty to Dr. Watts's mind, that traces of nitrogen in hydrocarbons give with the spark the spectrum of nitrocarbons, and that traces of hydrogen in cyanogen give the hydrocarbon spectrum, is not only "reasonable," but appears to me most consistent with the spectrum observations on the whole, and with the chemical regarding the formation and relations of acetylene and hydrocyanic acid.

Cambridge, January 22 G. D. LIVEING

Vibration of Telegraph Wires During Frost

MR. T. M. READE asks for an explanation of this phenomenon. In *Science Gossip* for 1874, p. 254, there is a short article of mine on "Frost Phenomena," and one of those referred to is this curious vibration of telegraph wires.

The explanation there suggested, which was only a guess, is probably incorrect; but I think I can give the true one now, and it is, as usual in such cases, extremely simple.

Hoar frost is only deposited in air which is nearly at rest; a strong wind shakes it down as it forms. But there is nearly always a slight air-current in one definite direction, and the ice spicules are built up "in the teeth" of this current, that is on the windward side of the wire or twig.

They always point *towards* the wind. When they have attained a length of, say, half an inch, if the direction of the air-current slightly changes, it may strike the comb-like fringe no longer on the points, but on the side, and, obtaining thus a leverage upon the wire, will twist it round till the pressure is balanced by the torsion. If the pressure were absolutely constant the wire would perhaps remain in this position, but the very slightest variation of pressure would set up a vibratory motion, and this, I think, must be the true cause of the phenomenon.

Birstal Hill, Leicester, February 5 F. T. MOTT

The Star Oeltzen, 17681

THE star Oeltzen, 17681, whose spectrum was announced by me to consist mainly of a yellow and blue band (NATURE, vol. xxii. p. 483), proves to belong to the same class as the three stars in Cygnus discovered by Wolf and Rayet in 1867 (*Comptes rendus*, vol. lxv. p. 292). A curious feature of these spectra is that they resemble each other without being identical, the relative brightness of the lines being very different. A further study of them is much to be desired.

Cambridge, U.S., January 24 EDWARD C. PICKERING

Zeuglodontia

IN consequence of my letter in NATURE, vol. xxiii. p. 54, the sub-editor of the *Graphic* was kind enough to send me the number of that paper containing the engraving of the animal seen from the *City of Baltimore* (not *City of Washington*, as I had misunderstood), and which is that of April 19, 1879. The sketch from which this was taken was sent by Major H. W. J. Senior of the Bengal Staff Corps, with the following description, viz. :—

"On January 28, 1879, at about 10 a.m., I was on the poop deck of the steamship *City of Baltimore*, in lat. 12° 28′ N. long. 43° 52′ E. I observed a long *black* object abeam of the ship's stern on the starboard side, at a distance of about three-quarters of a mile, darting rapidly out of the water and splashing in again with a sound distinctly audible, and advancing nearer and nearer at a rapid pace. In a minute it had advanced to within half a mile, and was distinctly recognisable as the veritable 'sea-serpent.' I shouted out 'Sea-serpent! sea-serpent! call the captain!' Dr. C. Hall, the ship's surgeon, who was reading on deck, jumped up in time to see the monster, as did also Miss Greenfield, one of the passengers on board. By this time it was only about 500 yards off, and a little in the rear, owing to the vessel then steaming at the rate of about ten knots an hour in a westerly direction. On approaching the wake of the ship the serpent turned its course a little away, and was soon lost to view in the blaze of sunlight reflected on the waves of the sea. So rapid were its movements that when it approached the ship's wake I seized a telescope, but could not catch a view, as it darted rapidly out of the field of the glass before I could see it. I was thus prevented from ascertaining whether it had scales or not, but the best view of the monster obtainable when it was about three cables' length, that is about 500 yards distant, *seemed to show that it was without scales*. I cannot, however, speak with certainty. The head and neck, about two feet in diameter, rose out of the water to the height of about twenty or thirty feet, and the monster opened its jaws wide as it rose, and closed them again as it lowered its head and darted forward for a dive,

reappearing almost immediately some hundred yards ahead. The body was not visible at all, and must have been some depth under water, as the disturbance on the surface was too slight to attract notice, *although occasionally a splash was seen at some distance behind the head.* The shape of the head was not unlike pictures of the dragon I have often seen, *with a bulldog appearance of the forehead and eyebrow.* When the monster had drawn its head sufficiently out of the water it let itself drop, as it were, like a huge log of wood, prior to darting forward under the water. This motion caused a splash of about fifteen feet in height on either side of the neck, much in the shape of a pair of wings."

The italics in the foregoing and in the account of Capt. Cox are my own.



FIG. 1.—The Animal as seen from the *City of Washington.*

The engraving being a large one, of which the foreground is formed by the deck of the steamer, I have copied and send with this that portion of it which shows the animal; and in this it should be observed that besides the splash rising round the neck "like wings," the separate splash at some distance behind the head is also shown, the position of which corresponds to that where the cetacean tail occurs in the figure sent by the captain of the *Kiushiu-maru*, which accompanied my first letter. The foam around the neck, I think, may be due to the splash of the humeroid paddles which a cetacean should possess.

FIG. 2.—The Animal as first seen from H.M.S. *Dædalus.*

The sub-editor of the *Graphic* has also been kind enough to obtain for me tracings from the three figures given in the *Illustrated News* of October 28, 1848, of the animal seen from the *Dædalus*. From two of these I have made the accompanying reductions to one-fourth (linear) of the originals; and the head portrayed in one of these (as seen when the animal passed close under the stern of the *Dædalus*) is evidently not reptilian, but mammalian; and it seems to bear out the "bulldog appearance of the forehead and eyebrow" which Major Senior describes in his case.

FIG. 3.—Head of the Animal as seen when passing passing under the stern of the *Dædalus.*

From the *Times* of September 24, 1879, I cut the following notice:—

"Capt. J. F. Cox, master of the British ship *Privateer*, which arrived at Delaware breakwater on the 9th inst. from London, says:—'On the 5th ult., 100 miles west of Brest (France), weather fine and clear, at 5 p.m., as I was walking the quarter-deck, looking to windward, I saw something *black* rise out of the water about twenty feet, in shape like an immense snake about three feet in diameter. It was about 300 yards from the ship, coming towards us. It turned its head partly from us, *and went down with a great splash*, after staying up about five seconds, but rose again three times at intervals of ten seconds, until it had turned completely from us and was going from us with great speed, *and making the water boil all round it.* I could see its eyes and shape perfectly. Itwas like a great eel or snake, *but as black as coal tar*, and appeared to be making great exertions to get away from the ship. I have seen many kinds of fish in five different oceans, but was never favoured with a sight of the great sea-snake before.'"

In this account we have almost a duplicate of that of Major Senior in the dropping of the animal with a great splash into the water prior to its darting forward under it; while the boiling of the water around, which is so inconsistent with the motion of a snake in water (which I have more than once seen) evidently resulted from the strokes of the cetacean tail, and possibly also from those of the paddles, as in the case witnessed by Major Senior. The black colour also is described in both cases.

Capt. Drevar, the statutary declaration of whom and of several of his crew I quoted in my former letter, has written to me, and sent me a printed account (which he says he has circulated) of the conflict which he witnessed, and of the subsequent appearance of the animal rearing its long neck out of the water. This is satisfactory as showing that the declaration I quoted was no hoax, as I feared it might have been; but Capt. Drevar rejects with disdain my suggestion that the animal he saw was not a serpent, though I pointed out to him that nothing having the form of a snake would possess in its submerged portion the buoyancy necessary to enable it to elevate so great a proportion of its length out of water.

Judging from the figures which accompany this and my previous letter, it appears to me that the external form of the animal must resemble the well-known *Pleisosaurus*, if we imagine the hinder (femuroid) paddles of that *Enaliosaurian* to be absent, and a cetacean tail (which is their homologue), to be present in their stead. Since in the direction of the *Porpesse* the cetacean in external form so closely simulates the fish, so it may in another direction simulate this Mesozoic marine saurian, or the gigantic *Elasmosaurus* of the American Cretaceous formations, of which a nearly perfect skeleton is described by Prof. Cope as forty-five feet in length, the neck constituting twenty-two of this length.

Whether, through your circulation, any light on this subject, so far as the character of the skeleton of *Zeuglodon cetoides* is concerned, may be forthcoming from American palæontologists remains to be seen; but there ought, I submit, to remain no longer with naturalists any doubt that a hitherto unknown group of carnivorous cetaceans, with necks of extraordinary length, inhabit the ocean.

It seems to me also most probable that the conflicts which have been so often witnessed (and which Mr. Pascoe in his letter in NATURE, vol. xxiii. p. 35, says he himself twice witnessed), and referred to the Thresher, have been attacks by the animals in question upon whales.

SEARLES V. WOOD

Martlesham near Woodbridge

Ice Intrusive in Peat

I HAVE just returned from a walk on the shore at Crosby, where I have been much interested in observing one of the effects of the late severe frost combined with the present thaw.

At the Alt Mouth is a submarine peat-and-forest-bed, and, lying over it, I was much surprised to see innumerable slabs of peat, which an examination showed in most cases contained interlaminations of ice. One slab measured 5 yards by 2¾ yards by about 8 inches thick, and right through its mass in a parallel plane with the surface, separating the peat into an upper and lower layer, was a slab of transparent ice, wedge-shaped, being 4 inches thick at one side, diminishing to 1 inch at the other. How the ice got there was the surprising thing, as the peat is very hard and compact, and about 18 inches thick. The holes or places from which the sea had quarried these frozen slabs were plainly to be seen, and I noticed round one of them that the edges or lips of the peat had been forced up by ice inserting itself between the laminæ.

A good deal of water ordinarily oozing through the sandhills flows or trickles over the surface of the peat, and as nearly six inches of rain fell in December last, and the two previous months were wet, the quantity of water would be abnormally increased. In some way or other it must have percolated along the peaty laminæ, and by gradual accretion the frozen water has forced up the layer of peat above it. This has occurred at neaps, and the late high tides, assisted by the thaw and the decreased specific gravity of the mass, has lifted the frozen slabs of peat and

inclosed slabs of ice, and torn them from the unfrozen and softer peat below. The slabs may be compared to sandwiches, the ice representing the meat. The ice is evidently fresh-water ice, and possesses a striated prismatic structure at right angles to its surface. In places it protrudes like a tongue from the peat, and is then occasionally perforated with round holes evidently melted through it.

Is it not possible that some of the beds mentioned by geologists in Russia and North America, consisting of alternate layers of ice and earth or gravel, may have been formed similarly by percolation of water, and not be truly bedded, but intrusive?

T. MELLARD READE

Park Corner, Blundellsands, January 30

P.S.—Since writing the above I have again visited the shore to-day, but all the slabs have been rafted out to sea by the high tide. With my geological hammer I broke off some of the frozen peat *in situ*, and find the explanation given to be substantially correct; but I also found that the upper layer of peat was minutely and beautifully interlaminated with ice. It is quite evident that the ice is the frozen water which has percolated from the sand-hills.

January 31

The Squirrel Crossing Water

NEVER having heard of the squirrel taking to the water, I send the following authentic communication. I had heard the story told by another person, and thinking it of sufficient interest I requested her to get it in detail from the lady under whose personal observation it had come. This the latter has most kindly complied with, and I forward it, trusting it may prove of interest to some of the readers of NATURE interested in the habits of animals. Loch Voil, in Perthshire, near Balquhidder, is about four miles in length, with a mean breadth of about one-third of a mile—a considerable extent of water for so small a rodent to face and cross, in search, I suppose, of new nutting grounds.

H. H. GODWIN-AUSTEN

Thalford House, near Guildford, February 5

"*Mountquhanie, Cupar Fife*

"When rowing two ladies down Loch Voil, one afternoon last August, I observed what looked like a little stripe of red brown fur in the middle of the loch. On coming nearer we saw that it was a squirrel swimming across, its tail lying flat on the water. We then heard its claws scratching on the side of the boat, and to our surprise the little bedraggled sprite appeared on the bow of the boat. It was evidently tired, for it sat quite still, staring at us and panting. I rowed on towards the shore, hoping to be able to ferry it across, but after a few minutes it scrambled down to the water again and resumed its journey, probably frightened at the sight of the collie dog who was in the boat. We watched it swimming till it looked like a small speck close to the shore, but lost sight of it before it landed."

SEA-WAVES.—E. B. P., 18, Cromwell Place, S.W., asks: Can any reader of NATURE inform me as to in what books or pamphlets I can obtain the best information relating to the height and length of sea-waves, especially when considered in relation to the navigation of vessels?

BARON NORDENSKJÖLD IN FINLAND[1]

AS is known, Baron Nordenskjöld was born in Finland, and completed his studies at the University of Helsingfors. After his recent visit to St. Petersburg, where the celebrated explorer was made much of, he promised to stop at Helsingfors a few days, for the first time after his successful discovery of the North-East Passage and his circumnavigation of the Eurasian Continent. Having previously paid a short visit to his paternal hall (Frugärd), Nordenskjöld, accompanied by the Baroness his wife, arrived at Helsingfors on the evening of January 13. He was received at the railway station by a deputation consisting of the Rector of the University, Mr. H. Lagus; the President of the Finnish Society of Science, Mr. G. Mittag-Leffler; the Secretary, Mr. L. L. Lindelöf, and others, as well as a select chorus of students, who sang a few patriotic songs. Before the station-house a crowd numbering thousands of people stood cheering and greeting him.

On January 14 the Society of Science had arranged a special meeting, to which friends and followers of science had been invited, and at which were present members of Government, professors of the University, a few of the higher military dignitaries, and a great many fashionables of the town, ladies as well as gentlemen. After an interesting lecture "On the Religions of the Populations of Siberia" by the linguist, Prof. A. Ahlquist, the President of the Society of Science, Mr. Mittag-Leffler, presented to Baron Nordenskjöld a gold medal struck by order of the Society of Science, in memory of their renowned countryman and honorary member, and of the remarkable historical event. The presentation of the medal was accompanied by an address, in which it was stated that the Society of Science, being neither wealthy nor numerous, and well remembering to what a little nation it belonged, could not and would not try to compete with the many eminent scientific societies which had already honoured him with their grants and gifts. Yet the Society of Science hoped Baron Nordenskjöld would kindly accept this tribute of admiration, as having issued from his native country. Nordenskjöld expressed his gratitude in a hearty manner, and then gave a lecture on his "Observations of the Northern Lights at Behring Strait," which greatly excited the interest of his audience. Nordenskjöld was then entertained at dinner by the Scientific Society and the University, at which entertainment toasts were given in honour of Baron Nordenskjöld, the Baroness, and the members of the *Vega* Expedition. At the close of the dinner a torchlight procession, arranged by students, appeared, paying homage to their celebrated countryman by singing and cheering.

The Helsingfors Skating Club having meanwhile adorned its skating-rink on the ice with electric lights and innumerable lamps and torches, then had a visit from the Baron. He was received with singing by a student chorus, followed by the appearance of two polar bears with a chair on skates, who, giving him kind regards from Spitzbergen and Siberia, took him at a tremendous rate up to a pretty little ice temple, where he was greeted by twelve young ladies and gentlemen, all dressed in the picturesque costumes of the Chukchis. These gave him a hearty welcome, and then, with the bears, performed a characteristic dance on skates. Surrounded by thousands of cheering spectators, he was taken back to his carriage again by the bears. In expressing his gratitude Nordenskjöld said that if the Chukchis, and especially the ladies, had been so civilised he would most certainly not have left them so soon.

The following day he was invited to dinner by the Governor-General of Finland, Count Adlerberg, and in the evening the inhabitants of Helsingfors gave a splendid banquet, at which toasts were given in honour of the Emperor Alexander II. and King Oscar II., followed by a speech by Prof. L. L. Lindelöf, relating Baron Nordenskjöld's great deed, and inviting the audience to drink to his health. Other toasts were also given in honour of the Baroness Nordenskjöld, the promoters and members of the *Vega* Expedition, the Fatherland, &c. Nordenskjöld's appearance in Finland excited great rejoicing everywhere, but amid that rejoicing the melancholy thought occurred to one's mind that he had been denied the opportunity of living, and acting, and working in his own country.

On January 16, early in the morning, he left Helsingfors; once more the singing of the students sounded on the platform amid loud cries of "Hurrah" from friends and admirers.

[1] From a Helsingfors Correspondent.

THE JOHN DUNCAN FUND

MR. JOLLY informs us that the subscriptions sent to form a fund to raise this old botanist above the need of parochial relief and provide for his comfort during his remaining years, has already reached a considerable sum, all which has been sent spontaneously from all parts of the country, without the formation of any committee or pressure whatever. More is coming in daily, and the old man's future independence would seem in the end to be pretty well assured. The sympathy shown in the case has been widespread and of the warmest kind. Her Majesty the Queen has graciously sent 10*l.*, and the Duke of Argyll, who sent 10*l.* at first, writes that it is a subscription which ought to be zealously supported by all who are interested in the pursuit of science, and who honour the high moral and intellectual qualities by which John Duncan is distinguished. All this speaks well for the generosity of the country, but more is required. The case is without doubt unusually deserving.

The following is a list of the subscriptions which have been received at this office during the past week:—

	£	s.	d.
Amount previously announced	11	15	0
Matthew Gray ...	2	0	0
F. A. Hamilton ...	2	0	0
Received in Registered Letter ...	2	0	0
Jas. Greig	0	10	0
George Russell ...	0	10	0
Thomas Clarke ...	1	1	0
A Friend	0	10	0
L. M.	3	3	0
E. V.	0	2	6
Miss Wilson	0	5	0
Isaholt Fraser ...	0	3	0
Mrs. Tuckwell ...	0	10	0
Alfred Shipley ...	1	1	0
E. H. Millar	1	0	0
John Noble	5	0	0
W.	0	10	0
Clay, Sons, & Taylor	1	1	0
Dr. Sim	1	0	0
Henry Stretch	0	2	0
A. A. Rathbone ...	3	0	0
A. G.	0	10	0
Sidney Billing	0	10	0
A. W. Agnew	1	0	0
Orry's Dale	0	5	0
John Renton Dunlop.	1	0	0
Prof. Prestwich, F.R.S.	2	2	0
George Knott	1	1	0
H. F. R.	0	10	0
Mrs. Henry	1	0	0
Miss Weir	0	10	0
An Old Woman ...	0	2	6
A. E.	0	10	0
J. B. B.	2	2	0
	48	6	0

EXPERIMENTS ON ICE, UNDER LOW PRESSURES

CERTAIN theoretical considerations on the relations of the solid, liquid, and gaseous states of matter led me three or four years ago to the speculation that in a perfect vacuum the liquid state would be impossible, and that under this condition it might be possible to raise bodies to temperatures above their ordinary melting-points. These ideas were mentioned to one or two friends at the time, but they naturally considered them as speculations which would not be verified by experiment. From the pressure of other work the subject was for the time dropped, and it was not till the autumn of 1879 that an experimental investigation was commenced. The first substance tried was sulphur, but this was ultimately found to be unsuitable, as under low pressures, though it apparently boiled as low as 130° C., yet at that or a little above that temperature it began to froth. Naphthalene was then tried, but as the pressure at which the boiling-point fell below the melting-point was less than about 7 mm., it was not easy to *maintain* the pressure at a sufficiently low point. Mercuric chloride however, which was the next body tried, yielded better results.

Mercuric chloride melts at 288°, resolidifies at 270°-275°, and boils at 303°. About 40 grammes of the pure compound were placed in the tube A (Fig. 1), and a thermometer arranged with its bulb imbedded in the salt. The drawn-out end of the tube was connected by stout india-rubber tubing with one branch of the three-wayed tube B, whilst the other was attached to the manometer C. B was connected with a Sprengel pump fitted with an arrangement for regulating the pressure. When the pressure had been reduced by means of the pump to below 420 mm., the mercuric chloride was strongly heated by the flame of a Bunsen's burner, with the following results:—Not the slightest fusion occurred, but the salt rapidly sublimed into the cooler parts of the tube, whilst the unvolatilised portion of the salt shrank away from the side of the tube, and clung tenaciously in the form of a solid mass to the bulb of the thermometer, which rose considerably above 300° C., the mercury shooting up to the top of the stem. After slight cooling, the air was let in, and under the increased pressure thus produced the salt attached to the bulb of the thermometer at once melted and began to boil, cracking the tube at the same time.

The experiment was next varied as follows:—About the same quantity of chloride was placed in the tube as before and heated by the full flame of a Bunsen's burner. The lamp was applied during the whole of this experiment, and the size of the flame kept constant throughout. The



Fig. 1.

mercuric chloride first liquefied and then boiled at 303° under ordinary pressure, and whilst the salt was still boiling the pressure was gradually reduced to 420 mm., when the boiling-point slowly fell to 275°, at which point the mercuric chloride suddenly began to solidify, and at 270° was completely solid, the pressure then being 376 mm. When solidification was complete the pump was stopped working, but the heat still continued to the same extent as before. The salt then rose rapidly to temperatures above that at which a thermometer could be used, but not the least sign of fusion was observed. From the completion of the solidification to the end of the experiment the pressure remained at about 350 mm.

The above experiment, which was repeated three times, shows therefore that when the pressure is gradually reduced from the ordinary pressure of the atmosphere to 420 mm., and the boiling-point simultaneously from 303° to 275°, the salt solidifies while it is still boiling, notwithstanding that it is being strongly heated at the same time, and that, after solidification is complete at 270°, the temperature then rises far above the ordinary boiling-point (303°) of the substance without producing any signs of fusion. Under ordinary circumstances mercuric chloride melts at

288° and re-solidifies at 270°-275°, *i.e.* at a temperature identical with that at which it solidifies under diminished pressure as above described.

After the above experiments had been made the investigation had to be unavoidably deferred, and was not resumed till last autumn, when a large number of determinations were made of the boiling-points of several different substances under various pressures, and from these was drawn the general conclusion described in a letter to NATURE (vol. xxii. p. 434), in September last, viz.: "In order that any solid substance may become liquid it is necessary that the pressure be *above* a certain point, called the critical pressure, otherwise it cannot be melted, no matter how great the heat applied." Assuming the truth of this conclusion, I set to work to apply it in the case of ice, as it would undoubtedly have the greatest interest in connection with that substance. On this account my experiments since the end of August have related almost solely to ice.



Fig. 2.

The problem to be solved was whether ice could be prevented from melting by maintaining the pressure below its critical pressure, *i.e.* the tension of its vapour at the melting-point, and that whatever the intensity of the heat applied. Now the theory of critical pressure gives us no information as to whether the ice, on non-fusion, would or would not rise above its ordinary melting-point when strongly heated, but as this result had been previously attained in the case of mercuric chloride it appeared not impossible that the ice *might* become hot.

The question as to the rise of temperature of the ice above 0°, though at first but a side issue of the investigation, became from its more especial interest the chief object of inquiry, and the experiments which have been made and those which are at present in hand relate almost solely to this point.

The great difficulty to be overcome was to maintain the pressure in the containing vessel below 4·6 mm., *i.e.* the tension of aqueous vapour at the freezing-point; for it will be easily understood that if the ice be but slightly heated the quantity of vapour given off would soon be sufficient to raise the pressure above that point. After several fruitless attempts, the following plan, involving the principle of the cryophorus, was adopted:—A strong glass bottle, such as is used for freezing water by means of Carre's pump, was fitted with a cork and glass tube C (Fig. 2) and the cork well fastened down by copper wire. A and C were then filled with wet mercury (the water facilitating the removal of the air-bubbles) and C connected with the end of the tube D E by means of the stout india-rubber tubing B, a thermometer having been previously attached by the wire *x* to the lip of the tube at B. The tube D E was about one inch diameter, and about four feet long from the bend to the end E; after connection with C it was completely filled with mercury and the whole inverted over the mercurial trough F, as shown in the figure, when the mercury fell to O, the ordinary height of the barometer. The mercury was run out of A by tilting up the bottle and inclining the tube D E. By this means a Torricellian vacuum was obtained from A to O. D was next brought to the vertical, and the bottle A placed in the trough P. A tin bottle G without a bottom was



Fig. 3.

fitted with a cork, so that it might slide somewhat stiffly along D E.

To begin with, the tin bottle was placed in the position G and filled with a freezing mixture of salt and ice. Some boiled water was then passed up into the tube D E, sufficient to form a column at M about two inches deep. The thermometer H had been previously arranged so that its bulb might be one or two inches above the surface of the water M. The bottle A was next surrounded by a good quantity of freezing mixture, in order that any vapour given off from the water at M might be condensed in A as fast as it was formed, and thus the internal pressure might never be more than about 1·0 to 1·5 mm. When A had been sufficiently cooled, which required about fifteen minutes, the tin vessel G was slid down the tube D E, and its freezing mixture removed. The water at M had then solidified to a mass of ice, which on heating with the flame of a Bunsen's burner, melted either wholly or partially, and the liquid formed began at once to boil. The fusion commenced first at the bottom of the column of ice, whereas the upper part fused only with difficulty, and required rather a strong heat. The fusion in this case was probably due

to the steam evolved from the lower portions of the ice column being imprisoned and unable to escape, and hence producing pressure sufficient to cause fusion.

When the greater part of the ice had been melted, the tube was tightly clasped by the hand, the heat of which was sufficient to produce a somewhat violent ebullition. The liquid in boiling splashed up the side of the tube and on to the bulb of the thermometer, where it froze into a solid mass, as represented in Fig. 3. By this means the ice was obtained in moderately thin layers. The tube at the points indicated by the arrows was then strongly heated by the flame of a Bunsen's burner with the following results:—The ice attached to the sides of the tube at first slightly fused, because the steam evolved from the surface of the ice next the glass, being imprisoned between the latter and the overlying strata of ice, could not escape, and hence produced pressure sufficient to cause fusion, but as soon as a vent-hole had been made fusion ceased, and the whole remained in the solid state, and neither the ice on the sides of the tube nor that on the bulb of the thermometer could be melted, no matter how great the heat applied, the ice merely volatilising without previous melting; thus proving that if the pressure be maintained below the critical pressure the ice cannot be melted. In different experiments the thermometer rose to temperatures considerably above the melting- and even the boiling-point of water, the highest temperature reached being 180° C., when the ice had either wholly volatilised or had become detached from the bulb of the thermometer, but in no case did the ice attached to the thermometer melt when these temperatures had been reached, as erroneously stated in some reports of my experiments. The ice attached to the thermometer did not partially fuse at the commencement of the heating, because, the heat reaching the outer surface of the ice first, evaporation could take place from a free surface and the vapour not become imprisoned, as was the case with the ice attached to the sides of the tube. These experiments were repeated many times with the same result, except in one case in which the heat applied had been very strong indeed, and the ice attached to the sides of the tube fused completely. On removing the lamp however for a few seconds the water froze again, notwithstanding that the portion of the glass in contact with it was so hot that it could not be touched without burning the hand.

The chief conditions necessary for success appear to be (1) that the condenser A (Fig. 2) is sufficiently large to *maintain* a good vacuum. For the size of apparatus given above it ought to be about 1 litre; (2) that the ice is not in too great mass, but arranged in thin layers. Nor must it expose too great a surface for evaporation, otherwise the steam is liable to be evolved more quickly than it can be condensed, and the pressure would therefore rise above the critical pressure. Further, in the case where the heat is applied to the under surface of the layers of ice, the latter must be sufficiently thin to allow of a vent-hole being formed for the escape of the steam comlng from below, if not, fusion occurs. When the heat is applied to the free surface of the ice the layers may be much thicker. In order to get the temperature to rise above the ordinary melting-point of ice, it is necessary that a very strong heat be applied, otherwise all the heat is used to convert the ice into steam without raising its temperature; it must in fact be applied more quickly than it can be absorbed for changing the state of aggregation. Prof. McLeod, who has written to me to the effect that he has been unable to obtain any symptoms of hot ice, has failed I believe on account of not having complied with this condition. Dr. Lodge, in an admirable and very clear letter to NATURE (vol. xxiii. p. 264), has endeavoured to explain why "hot ice" is possible, and also points out the absolute necessity for supplying the heat more rapidly than it can be absorbed by the vapour.

Now the question arises, Does the thermometer in the above experiments indicate the real temperature of the ice? It has been said by Prof. Stokes that the ice, though attached to the thermometer, is not at the same temperature as the latter, and that the action is really as follows: The pressure is reduced till the boiling-point falls below the melting-point, and when heat is applied to the ice in contact with the glass tube a film passes into vapour, and thus prevents the ice from touching the glass except at a few isolated points. The great latent heat of evaporation prevents the ice from rising to its ordinary melting-point, and hence no fusion occurs. The ice is only heated —except at the few isolated points of contact—by radiation, and therefore comparatively slowly. A portion of the heat passes through the ice and falls on the thermometer inside, and the latter rises in temperature; this causes the formation of a film of vapour between the ice and the bulb of the thermometer, so that the latter is in contact with the ice at a few points only, and therefore hardly any heat passes by conduction to the ice.

As under the circumstances of the case this appeared the most probable explanation of the phenomena, it was of great importance to show by other and more conclusive experiments whether the ice really was hot or not. For this purpose Prof. Roscoe suggested the most decisive test which could be applied, viz., dropping the supposed hot ice into water and observing the amount of heating or cooling of the latter. Up to the present I have only had the opportunity of completing two of these calorimetrical determinations, and the second of these was merely a qualitative experiment, as the weight of ice dropped in could not be found, owing to a small quantity of the water having been jerked out of the calorimeter the moment the ice entered it. In both experiments, however, the water distinctly increased in temperature, and therefore showed that the ice must have been above 80° C. In the complete experiment the weight of ice dropped into 185 grammes of water was 1·3 grammes, and the rise in temperature 0·2°C., showing that the temperature of the ice was 122° C. From the nature of the experiment the weight of ice which could be dropped into the calorimeter was only small, and though the rise in temperature was but slight, yet if the ice had been at 0° a relatively large cooling ought to have been observed. Great care was taken to avoid any error in the determinations. The thermometer employed was graduated so as to allow of a difference of 0·05° C. being easily detected, two observers read off the temperatures independently of one another, the calorimeter was inclosed in several casings and filled with the water to be used some hours before the experiment, so that it might have the temperature of the room, whilst the time which elapsed between the readings of the thermometer would not be more than about fifteen seconds, and finally the calorimeter was not brought into position to receive the ice till the source of heat had been removed. To place the point beyond doubt, however, several additional and perfectly satisfactory calorimetrical determinations are necessary, and if possible on a larger scale. Such experiments are at present in hand. In the meantime I would make the following remarks in favour of the high temperature of the ice. If the ice is not really hot, notwithstanding that the thermometer indicates say a temperature of 120° C., how is it possible for the ice to hang on to the thermometer? For if it be separated from the bulb by a layer of steam, it cannot hang by steam, it would at once become detached from the thermometer. The thermometer was chosen so that the bulb was of the same, and in most cases of a less, diameter than the stem, so that there was nothing to prevent the ice falling away if so inclined.

In some cases I have had thin plates of ice attached by their edge at right angles to the stem of a paper scale thermometer for a considerable time without being

detected in mercury, notwithstanding the temperature was so high that the paper close at that portion of the stem to which the ice clung was charred; this was the case in one of the experiments shown at the Chemical Society. In another instance I have had a thin circular piece of ice attached to the otherwise bare bulb of the thermometer, and though this piece was very thin and no more than about 2 mm. diam., it took fully one minute or more to vaporize, notwithstanding the thermometer indicated a mean temperature of about 70° C., and the surrounding tube was very hot. If the ice were not capable of being heated above its melting-point, a piece so small as that referred to would, I think, under these circumstances have fused or volatilised almost instantaneously. If the ice be really above 80° C., it ought to melt suddenly and at once on disseminating the heat and increasing the pressure, and this I have in one or two instances found to be the case. Thus in one experiment a beautiful rod of ice nearly six inches long and about half an inch diameter was attached to a glass rod suspended in the apparatus described above and heated very strongly with a large Bunsen's burner for several minutes; the pressure was then let in, when the ice at once fell off the rod into the mercury trough below, melting completely, and as far as could be seen even before it reached the mercury. Careful observations have also been made to see whether any cavity could be detected between the ice and the hot thermometer when the latter was only partially covered with ice, and indicated a high temperature, but such could not be seen either with ice or mercuric chloride. In both cases the substance appeared to rest in actual contact with the bulb of the thermometer, in this respect differing from camphor, which does exhibit such a space. I have however never been able to get camphor above its ordinary melting-point, though by reducing the pressure below 400 mm., it solidifies while boiling, and cannot be re-melted unless the pressure be increased.

One curious point about the ice experiments is the comparative slowness with which the ice appears to evaporate, though the surrounding tube is very strongly heated.

In conclusion, I need hardly say that it is highly desirable that my results should be confirmed by other observers.

THOS. CARNELLEY

TELE-PHOTOGRAPHY

WHILE experimenting with the photophone it occurred to me that the fact that the resistance of crystalline selenium varies with the intensity of the light falling upon it might be applied in the construction of an instrument for the electrical transmission of pictures of natural objects in the manner to be described in this paper.

In order to ascertain whether my ideas could be carried out in practice, I undertook a series of experiments, and these were attended with so much success that although the pictures hitherto actually transmitted are of a very rudimentary character, I think there can be little doubt that if it were worth while to go to further expense and trouble in elaborating the apparatus excellent results might be obtained.

The nature of the process may be gathered from the following account of my first experiment. To the negative (zinc) pole of a battery was connected a flat sheet of brass, and to the positive pole a piece of stout platinum wire; a galvanometer was interposed between the battery and the brass, and a set of resistance-coils between the battery and the platinum-wire (see Fig. 1, where B is the battery, R the resistance, P the wire, M the brass plate, and G the galvanometer). A sheet of paper which had been soaked in a solution of potassium iodide was laid upon the brass, and one end of the platinum wire previously ground to a blunt point was drawn over its surface. The path of the point across the paper was marked by a brown line, due, of course, to the liberation of iodine. When the resistance was made small this line was dark and heavy; when the resistance was great the line was light and fine; and when the circuit was broken the point made no mark at all. If we drew a series of these brown lines parallel to one another, and very close together, it is evident that by regulating their intensity and introducing gaps in the proper places any design or picture might be



Fig. 1.

represented. This is the system adopted in Bakewell's well-known copying telegraph. To ascertain if the *intensity* of the lines could be varied by the action of light, I used a second battery and one of my selenium cells, made as *described* in NATURE, vol. xxiii. p. 58. These were arranged as shown in Fig. 1, the *negative* pole of the second battery, B', being connected through the selenium cell S with the platinum wire P, and the positive pole with the galvanometer G. The platinum point being pressed firmly upon



Fig. 2.

the sensitised paper and the selenium exposed to a strong light, the resistance was varied until the galvanometer needle came to zero. If the two batteries were similar this was found when the resistance of R was made about equal to that of the selenium cell in the light. The point was then drawn over the paper. The selenium was then darkened, and the point immediately passed a strong brown line; a feeble light was next thrown upon the selenium, and the intensity of

the line became at once diminished. Lastly, a screen of black paper, having a large pin-hole in the middle, was placed at a short distance before the selenium, and the image of a gas-flame was focussed upon the outer surface of the screen, a small portion of the light passing through the pin-hole and forming a luminous disk upon the selenium. The galvanometer was again brought to zero, and, as before, the platinum point made no mark. When however the gas-flame was shaded a firm and steady line could be drawn; and when the light was interrupted by moving the fingers before the pin-hole a broken line was produced. For this last operation a very sensitive paper was required, and it was found necessary to move the platinum point slowly.

In consequence of the very satisfactory results of these preliminary experiments I made a pair of "tele-photographic" instruments, of which the receiver was slightly modified from Bakewell's form. They are of rude construction, and I shall say nothing more about them except that on January 5 they produced a "tele-photograph" of a gas-flame, which was good enough to induce me to make the more perfect apparatus now to be described.

The transmitting instrument consists of a cylindrical brass box four inches in diameter and two inches deep, mounted axially upon a brass spindle seven inches long, and insulated from it by boxwood rings. The spindle is divided in the middle, its two halves being rigidly connected together by an insulating joint of boxwood. One of the projecting ends of the spindle has a screw cut upon it of sixty-four threads to the inch; the other end is left plain. The spindle revolves, like that of a phonograph, in two brass bearings, the distance between which is equal to twice the length of the cylinder; and one of the bearings has an inside screw corresponding to that upon the spindle. At a point midway between the two ends of the cylinder a hole a quarter of an inch in diameter is drilled, and behind this hole is fixed a selenium cell, the two terminals of which are connected respectively with the two halves of the spindle. The bearings in which the spindle turns are joined by copper wires to two binding screws on the stand of the instrument. The transmitter thus described is represented in diagrammatic section at Y (Fig. 2), where H is the hole in the cylinder and S the selenium cell.

The receiving instrument, shown at X (Fig. 2) contains another cylinder similar to that of the transmitter, and mounted upon a similar spindle, which however is not divided, nor insulated from the cylinder. An upright pillar D, fixed midway between the two bearings, and slightly higher than the cylinder, carries an elastic brass arm fitted with a platinum point P, which presses normally upon the surface of the cylinder. To the brass arm a binding screw is attached, and a second binding screw in the stand is joined by a wire to one of the brass bearings.

To prepare the instruments for work they are joined up as shown in Fig. 2, two batteries, a set of resistance coils, and a galvanometer being used, in exactly the same manner as in the preliminary experiments. The cylinder of the transmitting instrument Y is brought to its middle position, and a picture not more than two inches square is focussed upon its surface by the lens L. The pictures upon which I have operated have been mostly simple geometrical designs cut out of tinfoil and projected by a magic lantern. It is convenient to cover a portion of the cylinder with white paper to receive the image. The comparatively large opening H is covered with a piece of tin-foil, in which is pricked a hole which should be only just large enough to allow the instrument to work. [I have not been able to reduce it below one-twentieth of an inch, but with a more sensitive selenium cell it might with advantage be smaller.] The hole is then brought, by turning round the cylinder, to the brightest point of the picture, and a scrap of sensitised paper, in the same condition as that to be used, being placed under the point P of the receiver, the resistance R is adjusted so as to bring the galvanometer to zero. When this is accomplished the two cylinders are screwed back as far as they will go, the cylinder of the receiver is covered with sensitised paper, and all is ready to commence operations.

The two cylinders are caused to rotate slowly and synchronously. The pin-hole at H in the course of its spiral path will cover successively every point of the picture focussed upon the cylinder, and the amount of light falling at any moment upon the selenium cell will be proportional to the illumination of that particular spot of the projected picture which for the time being is occu-



FIG. 3.—Image focussed upon Transmitter.

pied by the pin-hole. During the greater part of each revolution the point P will trace a uniform brown line; but when H happens to be passing over a bright part of the picture this line is enfeebled or broken. The spiral traced by the point is so close as to produce at a little distance the appearance of a uniformly-coloured surface, and the breaks in the continuity of the line constitute a picture which, if the instrument were perfect, would be a monochromatic counterpart of that projected upon the transmitter.

An example of the performance of my instrument is shown in Fig. 4, which is a very accurate representation of the manner in which a stencil of the form of Fig. 3 is reproduced when projected by a lantern upon the transmitter. I have not been able to send one of its actual productions to the engraver, for the reason that they are exceedingly evanescent. In order to render the paper sufficiently sensitive, it must be prepared with a very strong solution (equal parts of iodide and water), and when this is used the brown marks disappear completely



FIG. 4.—Image as reproduced by Receiver.

in less than two hours after their formation. There is little doubt that a solution might be discovered which would give permanent results with equal or even greater sensitiveness, and it seems reasonable to suppose that some of the unstable compounds used in photography might be found suitable; but my efforts in this direction have not yet been successful.

In case any one should wish to repeat the experiments here described a few practical hints may be useful. In order that as large a portion as possible of the current from the battery B' (which is varied by the selenium cell)

may pass through the sensitised paper, the resistance R must be high; the EMF of the battery B must therefore be great, and several cells should be used.

An electromotive force is produced by the action of the platinum point, and the metal cylinder upon the sensitised paper, and the resulting current is for many reasons very annoying. I have got rid of this by coating the surface of the cylinder with platinum foil.

Stains are apt to appear upon the under-surface of the paper, which sometimes penetrate through and spoil the picture. They may be prevented by washing the surface of the cylinder occasionally with a solution of ammonia.

Slow rotation is essential in order both that the decomposition may be properly effected and that the selenium may have time to change its resistance. The photophone shows that *some* alteration takes place almost instantaneously with a variation of the light, but for the greater part of the change a very appreciable period of time is required.

The distance between the two instruments might be a hundred miles or more, one of the wires, M, N, being replaced by the earth, and for practical use the two cylinders would be driven by clockwork, synchronised by an electromagnetic arrangement. For experimental purposes it is sufficient to connect the two spindles by a kind of Hooke's joint (some part of which must be an insulator), and drive one of them with a winch-handle.

The instrument might be greatly improved by the use of two, four, or six similar selenium cells and a corresponding number of points. If two such cells were used the transmitting cylinder would have two holes, diametrically opposite to each other, with a selenium cell behind each. A second point would press upon the under surface of the receiving cylinder, and be so adjusted that the lines traced by it would come midway between those traced by the upper point. Four or six selenium cells could be similarly used. The adjacent lines of the picture might thus be made absolutely to touch each other, and moreover the screw upon the spindles might be coarser, which for obvious reasons would be advantageous. A self-acting switch or commutator in each instrument would render additional line-wires unnecessary.

SHELFORD BIDWELL

NOTES

THE Murchison medal of the Geological Society has this year been awarded to Prof. Geikie.

THE Associateship of the Institute of Chemistry, along with the prize of 50*l.*, offered by Prof. Frankland for the "best research involving gas analysis," has been awarded to Mr. Frank Hatton, of 14, Titchfield Terrace, Regent's Park, student in the Royal School of Mines, South Kensington.

WE regret to record the death, at the age of seventy-seven years, of Mr. John Gould, F.R.S., the eminent ornithologist. We hope to give some account of his life and work in our next number.

A REMARKABLE discovery has been made by Mr. Alex. Adams, one of the technical officers of the Post Office Telegraph Department. It is the existence of electric tides in telegraph circuits. By long-continued and careful observations he has determined distinct variations of strength in those earth currents, which are invariably present on all telegraphic wires, following the different diurnal positions of the moon with respect to the earth. He will read a paper on the subject at the meeting of the Society of Telegraph Engineers to-night.

MR. JOSEPH THOMSON has, we understand, received the offer of an advantageous post under the Sultan of Zanzibar, which no doubt he is likely to accept. Mr. Thomson's work will be mainly that of geological surveying in the region of the Rovuma River, and the Sultan has offered him every facility for carrying on the work. The Sultan deserves every credit for showing such enterprise, and we have no doubt that Mr. Thomson will be able to do work of great scientific value.

AT the Royal College of Surgeons Prof. W. K. Parker, F.R.S., will give nine lectures on the Structure of the Skeleton in the Sauropsida, on Mondays, Wednesdays, and Fridays, February 11, 16, 18, 21, and 23, at 4 p.m. Prof. W. H. Flower, LL.D., F.R.S., will give nine lectures on the Anatomy, Physiology, and Zoology of the Cetacea, on Mondays, Wednesdays, and Fridays, February 28, March 2, 4, 7, 9, 11, 14, 16, and 18, at the same hour.

WE are glad to learn that the new 23-inch object-glass of Prof. C. A. Young of Princeton, N.J., is completed. Prof. Young has tested it at Cambridge, Mass., and finds it very fine; he hopes by and by to do some good stellar spectroscopic work with it. The mounting is well under way, and it is expected that the instrument will be in place next autumn.

MR. LAMONT YOUNG, the Government geologist of New South Wales, has suddenly and mysteriously disappeared, and foul play is suspected. Mr. Young arrived safely at Bermagui, 180 miles south of Sydney, and at once set out to cross the bay in a boat. No news of him came in, and two days later his boat was found jammed among the rocks of the coast, ten miles north of the point from which he had started. It was at first, and naturally, supposed that Mr. Young and his company had been drowned, and that his boat had drifted on shore. A closer examination proved that the boat had been drawn carefully up on the coast, and that the party had dined after landing. Next some bullet holes were found in the boat, and this suggested the idea that the explorers had been attacked and murdered. But not a single mark of blood or additional trace of any violent assault could be discovered. The party were five in number, and the coast has been examined for traces or tidings of them in vain. An official of the Mines Department has been assisted by detectives and by the boasted "black trackers," natives whose acuteness is seldom at fault in a case of this sort.

PROF. MCK. HUGHES writes on January 27, suggesting the following scientific uses of the late severe weather:—When this frost breaks up and the frozen snow and ice begin to travel along our rivers to the sea there will be an opportunity of making observations upon several points upon which accurate information will be of use in seeking an explanation of some of the glacial and post-glacial phenomena of the British Isles, *e.g.* (1) Dimensions of the ice floes; (2) whether they consist chiefly of frozen snow or solid ice, *i.e.* an approximate estimate of their specific gravity; (3) amount of material carried by them and dimensions of larger boulders; (4) whether any of these were dropped on to the floe from cliffs of glacial drift so as to give scratched stones and *remanie* drift in modern mud; (5) how far out to sea such floes have been traced with or without earth and stones; (6) salinity of the water where the observations were made; (7) transport of shore shells, &c., by ice; (8) crumpling of mud by impinging ice; (9) grinding of ice along bridge piers, and many similar observations which it will be useful to record.

THE great annual *soirée* at the Observatory of Paris has been a great success. Almost all the Cabinet ministers and M. Gambetta were present. A plan was exhibited in the Astronomical Museum showing the present state of the Observatory, and what it will be when all the works for which credits have been voted shall be completed. A ball took place after a series of lectures and projections given in the *grande galerie*. One of the lecturers, M. Bertus, exhibited magic mirrors, and reminded those present that in 1844 M. Moucher, then a junior officer in the French naval service, brought home with him one of these mirrors from Japan, which was presented to the Academy

of Sciences by Arago. The *Comptes rendus* states that Arago was asked to inquire into the properties of this curious phenomenon, but it does not appear that he made any effort to comply with the request of the Academy.

AFTER a series of experiments which have proved successful, the Administration of French lighthouses has given an order to M. de Meritens to build six magneto-electric machines for the three first lighthouses which are to be illuminated by electricity.

THE Chemical Section of the Russian Physico-Chemical Society has, on the proposal and at the expense of Mr. V. J. Ragosine, established a competition for a prize of 750 metallic roubles (3000 francs) for the invention of a lamp intended to burn the heavy oils of petroleum (naphtha), *i.e.* the parts of the raw petroleum which distil after the kerosene or ordinary petroleum (density from 0·79 to 0·83 at 20° C.); as also astral oil (density 0·83 to 0·85 at 20° C.), but before the oils intended for greasing purposes (density about 0·88), *i.e.* oils whose density is from 0·85 to 0·88 at 20° C. The lamps ought (1) to be as simple as possible in construction, so that they may be easily manufactured and manipulated; (2) only glasses existing already in the retail trade to be used, if they are used at all; (3) to burn, without giving either soot or smell, the heavy oils whose density is at least between 0·865 and 0·875. The lamps must be sent in by January 12, 1882, and three specimens of each should be sent, accompanied by a detailed description in Russian, French, German, or English. There is no restriction as to nationality. Further information may be obtained from the Secretary of the Society, St. Petersburg.

WE would call the attention of our readers to a very valuable and ingenious instrument which has been recently introduced by Messrs. Francis and Co., the Telegraph Engineers, Hatton Garden, London, for the purpose of receiving the "Greenwich Time Signal" at the various telegraph stations and offices of private firms who may be in communication with the Postal Telegraph Service. Hitherto the passage of the time-signal current at 10 a.m. along the wires gives no other indication of its presence than a deflection of the needle of ordinary instruments, and a corresponding movement of the armature of the Morse Ink-Writer and Sounder, so that unless a sharp look-out be kept with the eye constantly directed to the instrument, the actual time of signal may be lost, perhaps also again to be lost on the following day through similar accident. By the new instrument, however, the instant the current is sent the needle on its dial is deflected, and simultaneously a bell rings and continues to ring so long as the current is passing. The index-needle, or in other words the needle of the galvanometer, which is the principal feature of the invention, when deflected, presses against a small spiral spring surrounding the stops or ivory pins on the dial plate, and by this contact the galvanometer forms itself into a "relay" and brings a local battery in circuit with the bell, which is contained in the same instrument, so that when the first part of the time-signal is sent the needle is deflected, and at the same moment the bell rings; thus attention to the time is at once arrested. It should be mentioned that the resistance to the line, although low, is intended to be inserted only during the transmission of the time-signal, as by means of what is generally termed a "switch" the instrument is put on and off the circuit at will, and employed only during the time set apart for the transmission of the "Greenwich Time Signal." However feeble the current may be, the galvanometer is so sensitive that a deflection of its needle is absolutely certain, whilst the bell cannot fail to answer to the power of its local battery. We are informed that not only is Messrs. Francis and Co.'s new instrument capable of doing what we have already stated, but it may be made available for communication from different parts of the building, an advantage which is certain to be recognised and approved by many conducting large business establishments, where the saving of time in conveying messages and giving orders is a matter which is not unfrequently of great importance.

A. P. S. WRITES:—During the late severe frost we had a number of bottles broken in our laboratory by the freezing of their contents, and it is curious to observe what salts tend to prevent such an occurrence. Out of thirty sets of reagents the following were destroyed:—27 ammonium oscalate, 7 calcium sulphate, 8 potassium ferrocyanide, 1 lead acetate. It is remarkable that not one bottle of lime-water was frozen. That calcium sulphate, which only contains $\frac{1}{500}$th of solid, should freeze, is not astonishing; but the ammonium oscalate bore away the palm with ease, although the amount dissolved was considerable. A single bottle of saturated solution of alum was broken, also one of mercuric chloride. A curious thing happened to one bottle, which shows, I think, that ice does not expand suddenly when it freezes. I unstoppered a bottle of Am_2O that was still liquid, when the contents immediately solidified in my hand, without bursting the bottle. The next day I found the ice had protruded 3½ inches from the neck of the bottle, carrying the stopper at its extremity.

THOSE who wish to see women have every fair play in the struggle for existence may be interested to know that at 399, Edgeware Road, Mme. Lina from Geneva is prepared to do good work as a practical watchmaker and jeweller.

A NUMBER of holes of the same description as those which have been observed at Blackheath have been opened in several parts of Paris. These enigmatical holes are several yards wide, long, and deep. Men of science are trying to solve the mystery of their formation.

A VERY satisfactory report was given at the recent annual meeting of the Birmingham Natural History Society, which now has apartments in Mason's College. The number of members is 382.

MR. J. B. JORDAN has issued a little pamphlet giving an account of his glycerine barometer, with plate and tables of correction for temperature. Stanford is the publisher.

UNDER the title of "All about Cardamoms, Botanical Descriptions, Commercial Uses, and Modes of Cultivation," a pamphlet of forty closely-printed pages has recently been issued in Colombo from the office of the *Ceylon Observer*. In this useful little pamphlet nothing new or original is professed to be given, it is simply a compilation of all matter bearing on the subject collected from all available sources, each article being printed in its entirety and its source acknowledged. Thus we find the article on Cardamoms from the latest edition of the *Encyclopædia Britannica*, Flückiger and Hanbury's *Pharmacographia*, Bentley and Trimen's *Medicinal Plants*, and many others. In this arrangement there is of course much repetition of the same matter, but the idea is good as bringing together all that has been published on a given subject which is frequently scattered through many, and often inaccessible publications.

THE works for the Paris Exhibition of Electricity will soon begin. A viaduct will be built for the English electrical railway by Siemens, which will convey visitors from the Place de la Concorde to the Palais de l'Industrie. The internal arrangements will only be made at the end of the Art Exhibition, which will take place from May to July. The French exhibitors of the electric light have come to an agreement in order to combine for the illumination of the nave and other parts. They are trying to obtain from the High Commission an indemnity for their working expenses. It is desirable that the English Government appoint without delay an agent on behalf of the intended English exhibitors, who may be numerous, even in the light department.

ANOTHER slight shock of earthquake was felt at Berne on the night of the 1st inst. Fresh earthquake shocks are reported from Agram, where shocks were observed on January 25 at 1h. 15m. (in the morning) 11h. a.m.; on the night of January 26 at 11h. 28m.; in the morning of January 31 at 3h.; on January 3 at 3h. (in the morning), 1h. 15m., and 4h. 13m. p.m. In the night of January 27-28 shocks were felt at St. Ivan, Zelina (Hungary) at 12h. 52m., 3h. 9m., 4h. 32m. On January 28 two shocks were felt at Gurkfeld (Carinthia) and neighbourhood at 8h. 50m. p.m., direction north-west to south-east. Earthquakes were also noticed on January 25 at Venice, Bologna, and Padua. In the night of January 3-4 shocks were observed in the regions of the Carinthian Alps, in Klagenfurt, at 2h. 22m. 25s., direction east to west, duration 5-6s.; in Trieste at 2h. 24m., direction north-east to south-west, duration about 4s.; at the same time shocks were felt in Laibach, in Gurkfeld, and in Czegled (Hungary).

AN examination has taken place at Brussels of the railway *employés*, in order to test their eyes. More than one-twentieth of them have been found defective, and consequently will be discharged as being unable to fulfil their functions with a sufficient security for travellers.

THE AURORA AND ELECTRIC STORM OF JANUARY 31

WE have received the following further communications on the recent brilliant display of aurora:—

THE beautiful display of aurora on the evening of Thursday was accompanied by the usual earth-current disturbances. They were evident over the whole of the United Kingdom. Telegraphic lines were stopped, railway block-signals were disturbed, and all the usual accompaniments of these curious storms were observed.

The electric storm commenced about 3 p.m., it reached a maximum at 6.40 p.m., and disappeared about 9 p.m. It was renewed about 11 p.m., and disappeared again about 1 a.m. on the next morning. The currents attained an intensity that I have never before observed. At Llanfair in Anglesey they measured 41·4 millivebers. At Haverfordwest 30 millivebers; at Bristol 17·32 millivebers; in the Central Station, London, 11 millivebers; at Edinburgh 8 millivebers. Now as working-currents vary from 5 to 10 millivebers, it is clear that these uninvited wanderers must play sad havoc with the working telegraphs. In some instances they were strong enough to ring the bells used on railways. They are eliminated, where this can be done, by joining two wires in *metallic circuit*, and so excluding the earth. They were characterised by the usual reversals, the direction of the current changing slowly. The changes in direction and variation in strength were always observed on the southern lines first. The line of maximum force commenced south-east to north-west, then passed south to north, and ended south-west to north-east.

It is unfortunate that on such occasions the whole energies of the technical staff are taken up in maintaining communication, and that no time or means can be found to obtain accurate measurements. The results however, such as they were, fully confirm my view that these storms are due to a violent disturbance of the distribution of electric potential on the earth's surface arising from violent changes in the electrification of the sun. There was a violent disturbance in the sun's envelope on that day, as I learn from Mr. Norman Lockyer, and I am looking with interest to some particulars of it.

February 5 W. H. PREECE

ON yesterday evening, January 31, a most brilliant display of the aurora was seen here. It was by far the finest I have seen, and others have expressed the same opinion. At 6.25 p.m. I saw a considerable illumination on the northern horizon, and an outlying bright patch on the north-west having somewhat the appearance of the zodiacal light, as shown in the sketch, Fig. 1. This outlying patch was distinctly in motion along the horizon towards the west; streamers from the horizon then shot up, and there appeared several arches of light apparently about the width of an ordinary rainbow, passing from the north-west to north-east points on the horizon; these arches gradually approached the zenith, and the southernmost from the east and west points of the horizon at last passed through it. Some of these arches are shown in Fig. 2, but there were more visible. In a few minutes, about 6.40, the arches faded, and there appeared, rather west of north, a mass of bright green light; then the



streamers from the north lengthened out, as shown in Fig. 3, converging on the Pleiades, as near as I could judge; waves of red light commenced to pass upwards along them, and large sheets of light appeared to pass rapidly over the sky. The streamers gradually died away, leaving flashing lights near the horizon, which in their turn left a slight light over the northern horizon, which gradually faded away. Mr. Percy Smith made the sketches, but owing to the rapid changes their accuracy is only general. Both he and I saw only one line in the spectrum in the usual place. GEORGE M. SEABROKE

Temple Observatory, Rugby, February 1

THE aurora observed during the evening of January 31 was accompanied by a magnetic perturbation, and although it was on a much smaller scale than that registered on August 12 to 14 last, a brief account of it may possess some slight interest to your readers.

The magnets of all three instruments at Kew, the declination, bifilar, and balance magnetometers, began to be disturbed to a somewhat larger extent than usual about noon on the 31st, the

general tendency of the movement being an increase of westerly declination and of vertical force, whilst the horizontal force slightly diminished. Quicker movements of the needles commenced at 3.40 p.m. Greenwich mean time, and from that hour until 8.33 p.m. oscillations followed each other at short intervals, although the magnets at no time appeared to be in the state of rapid vibration they were in during the afternoon of August 12.

The principal deviations registered were as follows:—A large westerly deflection of the needle was recorded at 6.2 p.m., but the greatest excursion in that direction took place at 6.47 p.m.; at 7.12 p.m. there was also another considerable westerly movement, followed by an easterly, which reached its maximum at 7.48 p.m. At 8.18 p.m. it deviated again to the west, after which it returned to its approximately normal position at 8.33 p.m. An isolated deflection to the west at about 0.25 a.m. of February 1 wound up the storm.

As regards force, the greatest changes of horizontal force occurred at about 6 p.m., but they were not large in extent. The vertical force curve moved in the extent of an augmented force beyond the limits of registration of the instrument between 4.20 and 5.32 p.m., and again between 6.2 and 6.45 p.m. The greatest movement in the direction of diminished force was at 8.12 p.m.

The self-registering Thomson electrometer was not apparently affected by the aurora; the tension of atmospheric electricity being somewhat high positive at 9 a.m., fell to a low positive tension at 2 p.m., from which it rose gradually, although somewhat irregularly, until 8 p.m.; from that hour until 9 p.m. it was more disturbed; it then became more strongly positive, and remained so until the next day.

This want of accordance between the electrograph and magnetographs was also well marked during the August aurora, and would appear to prove that the electrical disturbances in the upper aërial strata during aurora do not cause changes of tension in the lower at all commensurable with those ordinarily produced by wind, snow, or rain. G. M. WHIPPLE

Kew Observatory, February 2

THE commencement of the aurora consisted in the sudden lighting up of various portions of the sky by patches of white cloud, the northern horizon remaining constantly bright, and sending forth vertical streamers. The general appearance of the heavens was that of a smooth lake ruffled here and there every other second by fitful gusts of wind.

At 6.45 p.m. no ordinary clouds could be seen, but the flashes of white light were incessant, and varied continually in position. The light was strongest towards the north-east horizon, but the whole of the north was well lit up from north-east to west.

At 6.50 the streamers from the horizon increased in length and enveloped Polaris.

At 6.55 the number of the streamers increased, and springing from the whole northern horizon, traversed an imperfect arch of white light which passed between ϵ and ζ Ursæ, and just below β and γ Ursæ Minoris.

At 6.57 streamers 10° west of north passed from the horizon through the zenith, and the display was becoming very brilliant when I was obliged to enter the observatory for a few minutes to observe an eclipse of Jupiter's second satellite.

On returning to the garden at 7h. 5m. nothing remained of the aurora except patches of white light in different parts of the heavens, and a strong glow in the north. Using a hand spectroscope I could see the green auroral line very strongly marked in every part of the sky, but no other line was visible.

There was no change in the phenomenon until 7h. 45m., when a most brilliant cone of light of a reddish hue darted from between α and γ Aquarii, and developed almost immediately into a number of streamers which stretched out towards the Pleiades, this cluster being then some 30° from the zenith towards the west of south. Other streamers also appeared near the horizon from the west point to east of north.

A lull succeeded this display, followed at 6h. 15m. by a grand outburst of red streamers from Aquarius and also from near Orion, both converging towards the Pleiades, these from Aquarius being the brightest. These were visible for at least six seconds along with other rays in the north-west.

Cloud and haze were then collecting fast, and seven-tenths of the sky was already obscured. During this aurora the three self-recording magnets were very much disturbed, their movements being all rapid and extended. During the whole of the morning of the 31st the declination was very irregular, but it was only about noon that the storm began in earnest. From 3.30 until 9 p.m. the declination magnet was oscillating incessantly in long vibrations, several of fully a degree in extent; and between 7h. 53m. and 8 p.m. the western bearing increased by 1° 37′ 24″. Many other movements were nearly equally rapid, but not so extensive. The movements of the horizontal force magnet were irregular from noon till after midnight, and they were very much exaggerated between 3h. 45m. p.m. and 8.15; the most rapid change was the remarkable diminution of 2·1m. in the ordinate between 6.14 and 6.20 p.m.; this was preceded by a very quick rise, and followed by another nearly equally sharp.

The vertical force magnet was most irregular between 2 p.m. on the 31st and 1 a.m. on the morning of the 1st. The extreme maximum was attained at 4h. 20m., and the two principal minima at 8h. 12m. p.m., and at 12m. after midnight. The movement was most rapid at 8 p.m., and this principal disturbance on all the curves coincided with the grand outbursts of red streamers which converged towards a point some 30° south of the zenith.

Stonyhurst Observatory, February S. J. PERRY

MR. E. DOWLEN has been again good enough to furnish me with notes on the aurora (of Monday last), as seen from Medway, Poynton, Cheshire.

He first saw it at 6.30, it having been previously seen at 6 as a single shaft of white light. At 6.30 it consisted of quickly-darting rays and waving curtains of light, filling almost the whole sky. The horizon from extreme east to west was glowing, and from all this region streamers and waves of light shot upwards, meeting at or near the Pleiades, the rays often passing into Orion. About 7.0 the light in the north-west extending from Venus to some distance north of the moon was rose-coloured; the other parts were white. Now for a few minutes the display almost ceased and clouds began to come up in the north-east; but the glow increased in brilliancy in the north and north-west, forming a concave mass of light, almost an inverted arch; and from this sprang a broad band of streamers filling up all the northern region, and reaching almost to the zenith. This died down, and was succeeded by a similar display having a drifting movement westward, and a rose tint in the upper portion, which extended throughout it as it went westward. This display also died out, and was followed by another similar band more to the west, white in colour.

At 7.30 this was gone, and the whole aurora gradually grew smaller, the glow still remaining and giving feeble spurts until 8.30. About 9.30 the clouds were all gone, and Mr. Dowlen saw that a long low arch of inconsiderable width but tolerable brightness had been formed; the crown of the arch being just above Arided in Cygnus. No streamers came from this arch, but there seemed to be a fringe of glow to it. At midnight it faded away. During the whole time there was no wind; and although there was a ground-frost, the temperature up to 9 o'clock, by thermometer without frame suspended at the end of a bough four feet from the ground, was 34°. At 5 p.m. there had been a sharp shower of rain. Mr. Dowlen had no access to a spectroscope at the beginning. Later on he saw only the citron line.

At Guildown the display was not seen, and some fog prevailed. On the Monday morning at 8 a.m. a thermometer read 35° in a Stevenson cage four feet from the ground, while ice one-eighth of an inch thick lay on the garden paths.

The shower of rain is interesting in connection with the suspicion that the aurora is generally formed in a mist or vapour region. I have seen several eye-descriptions of this aurora, but no spectroscopic ones up to the present date.

Guildown, February 4 J. RAND CAPRON

THIS was a display of aurora borealis having appearances quite new to me. There was a faint auroral glare at 6 p.m.; at 6h. 15m. a confused but brilliant mass of light was situated west of Ursa Major, which moved quickly horizontally towards the west, there was also another mass of pink light in west, streamers shot up to the altitude of Cassiopeia. 6h. 24m. the first-mentioned mass of light was now mostly to the west of Cassiopeia. There was also another mass of light low down in north by east. Stars shone brightly through the aurora, but without scintillation, and somewhat orange-coloured. 6h. 25m. brilliant streamers in north-east, a wavy arch stretched from west-north-west to east, its east end terminating in a black, almost perpendicular mass. There were also smaller black patches but quite distinct in character to the first-mentioned one. The low dark segment had also a wavy edge, and there was a patch of strong light above

the north-east horizon. One very long streamer nearly due north rose from the dark segment and extended beyond the upper arch. At 6h. 27m. there were six well-formed arches, the upper one being that visible at 6h. 25m. They were all bent more or less, pointed towards east and west, and moved in a north current, *i.e.* rising perpendicularly; and increasing rapidly in speed as they neared the zenith, and fading away on reaching a point some 20° S. (of the zenith). Their brilliancy was great, and a strong orange and red glare coloured the walls of the Observatory. A large intense patch of light was situated in north-east, from which streamers rose to the zenith; at 6h. 28m. the whole of the



Seen at 6h. 25m. p.m.

arches (except that of the dark segment) had disappeared, occasional streamers and a strong glare continued, which at 7h. 9m. was unusually brilliant, and red and orange in colour. There were confused patchy lights, but no streamers. At 7h. 10m. these patches, together with their veil-like flames, passed to the south of the zenith, and formed a cupola which did not last a second; 7h. 16m. the phenomenon was now all confusion, and so thin that there appeared to be no brilliancy, yet the time by a watch was readily seen; 7h. 26m. very similar; 7h. 39m. still very bright, but settling down to the horizon; 8h. 34m. the whole northern heavens up to the zenith was a glare of thin sheets of aurora; 9h. 0m. a glare alone remained.



Seen at 6h. 27m. p.m.

The streamers west of north all moved westerly, but not those in north-east, and this also applies to the patches of light, whilst the arches moved in a north current.

The appearance was that of a luminous mist, and from the great speed when near the zenith was evidently much lower than usual. Flashes of thin light were very constant, appearing and disappearing incessantly.

The patches of light were a close copy of the aurora of October 1848, *i.e.* thirty-two years three and a half months ago, and if this be the third return of that appearance the period would be eleven years and thirty-five days. E. J. LOWE

Highfield House, Nottingham

AURORIC lights have been faint and scarce of late. There were some good ones a little before midnight on January 16, while on the 31st there was a most brilliant display, and of the observations made the following is an epitome:—

At 6 o'clock the sky was cloud-masked, with faint traces of orange-red columns between the north-west and north-east; coming up to 6.30 the clouds cleared away, and about 7 there were brilliant white lights to the north-west, making the night as light as day. At 7.40 an oblique band of silver light extended from the west to the upper star of the Plough, and from it shot up horns towards the zenith, while the southern portion of the sky was a fiery red, with columns rising in places. At 7.48 there were remarkable silver lights in two oblique systems, one set rising between the south and west and going northward, and the other between the west and north-east and going southward. The first were steady and fairly constant, the second a series of rapid successive flashes, streaks, and glows. The systems of lights formed beautiful crosses at the zenith. The flush lights passed round to the east, and all disappeared.

At 7.53 fans of pencils of silver lights came up between the north-north west and north-north-east, with at times disks at the north. Red, orange, and purple lights were rising at the same time in the southern portion of the heavens. Subsequently the northward heavens usually were light and bright, with flushes of light at intervals, while the southern portion was dark, with columns of orange and reddish lights; some displays to the northward being very bright, of green, silver, and pink colours.

At 9.30 there appeared an elliptic arch of silver light from the west-north-west by north to the north-east, which continued to 10.50, sometimes being much more distinct than at other times, its length being considerably contracted before it finally disappeared; the arch in general was white, but sometimes a silvery green. The under-sky was different shades of violet, the over-sky pale bright yellowish green. At times this arch was very similar to the pictures of auroræ given in books on Arctic travels.

At 10.45, a little before the arch finally disappeared, a brilliant display of silver pencils instantaneously sprang up between west-north-west and north-north-east; those at the north-north-west by north being perpendicular, while those on either side sloped slightly; this lasted for nearly ten minutes; glow and pencils of pink lights were also coming up during the time, especially at the north-west. Afterwards white lights appeared at times in the north heavens, and orange and purple in the south, up to 11.45, when there was another brilliant display of silver lights. It began by pencils shooting up perpendicularly between the west to the north-east, which changed into a fan, the perpendicular lights only rising at the north-north-west; this lasted five minutes, the largest, most constant, and brilliant lights coming up at the north-west. At 12 there was the best display I had seen during the night. It consisted of pencils between the north-west and north north-east, some perpendicular, others fan-shaped; some steady, others in flashes; while at the same time there was a continuous upward stream of waves or lines of vivid white bright lights. The latter were so peculiar that I am at a loss to describe them sufficiently; while this display was in progress at the north, to the south-east, bounded by hard lines at the east and south, there were red lights rising. The white lights in about five minutes disappeared as suddenly as they came, but at 12.10 horizontal wavy white lights shot up in rapid succession between the north-west and north-north-east by north, followed by radiating pencils of white lights, all disappearing at 12.15. No very remarkable lights appeared afterwards up to 1 o'clock, when the last observations were made.

There were severe frosts on the nights of the 30 and 31st, while during the daytime on the 31st and February 1 there were remarkably hot suns. G. HENRY KINAHAN

Ovoca, co. Wicklow

CLEAR starry night; slight frost. Shortly before 12 midnight beautiful auroras, when first observed, consisted of cloud-like white masses extending from about midway between Orion's belt and the Pleiades northward and eastward at about 30° above horizon, a little west of north, where the crown of the arc it formed lay below this arch of cloud-like masses (which at intervals shot up individually to the zenith); there were a number of pencils or rays of white light of varying length and intensity, some bright and sharply defined, and as a rule narrow and extending up to or beyond the cloud-like masses; others short, and some indistinct, all continually altering their position, boundaries, and intensities. While they were being watched, the cloud-like masses kept shooting upwards or horizontally like brush discharges.

Narrow sharply-defined rays were remarked to shoot up on several occasions from the horizon; these gradually widened out, losing their sharp boundaries and becoming less distinct, some times behaving like the cloud-like masses or becoming intensified by a "brush discharge" occurring across them; at others they faded gradually away.

At about 12.30 they had all disappeared, but a bright glow to the north horizon and faint glows at intervals over the sky between north and west.

It was not observed how far the discharges extended eastward.

24, Waterloo Road, Dublin GERARD A. KINAHAN

THE following details of this evening's remarkable aurora may be of interest to your readers. At 6.45 p.m., while the new moon was setting, there was an appearance of a belt of luminous white cloud reaching along the northern and north-western horizon, giving indications of a tendency to divide into two separate parts, of which the western one had its upper surface parallel with the horizon, but that to the north was arched. From both parts rays and vertical bands of white light began to shoot upwards, reaching nearly to the zenith, and becoming more and more distinct, especially in the north (as opposed to the north-west), and one long feathery streamer was very conspicuous, and reached in a slanting direction from a point on the horizon immediately under the Pole Star up to Capella.

In the meantime the cloud-like appearance to the north-west had spread upwards over the heavens and assumed a dark ruddy colour, which gradually became brighter and more rosy, until it exactly resembled the light of dawn or sunset, which is sometimes reflected on the opposite side of the sky to the rising or setting sun. At this time the northern heavens became suffused with white light extending over the space where the bands and rays had been appearing, which throbbed repeatedly and vividly like the electric discharge in a vacuum tube, continuing some minutes. This gradually faded away, and the pink light to the north-west also disappeared by degrees, so that within twenty or twenty-five minutes from the commencement (say at about five or ten minutes past seven) there was little to be seen but a hardly noticeable light along the north horizon. F. HORNER

Mells Park, Somerset, January 31

IT may interest your readers to know that the aurora of January 31 was distinctly seen by me here at about seven o'clock on that evening. Such a sight is so uncommon in this part of London that I had some difficulty in convincing my friends that it was the *aurora*. As I walked down the Wickham Road, Brockley, towards Greenwich, broad bands of light shot up from the northern regions and reached nearly to the zenith. Descending amongst the fog and smoke that overhung the lower parts of New Cross, the light gradually faded, and I saw no more of it.

W. J. SPRATLING

Aske's Hatcham Schools, Hatcham, February 4

THE aurora of January 31 was well seen here. It was at its brightest at 6.40 p.m. It extended from about north-west to nearly east. In the north-west and to the north of the crescent moon there was a large irregularly shaped patch of *greenish* phosphorescent light. Then round from it towards the north rose *crimson* streamers towards the zenith. The streamers continued round to the east nearly, still ascending zenithward, but white rather than crimson, between north-east and east. The streamers changed every instant, but the large greenish patch of light in the north-west was steady for some minutes.

It would be interesting to know whether observers in America noticed any unusual solar activity at the same absolute time as the aurora was occurring here, and also whether the magnetic elements in both hemispheres (north and south) showed disturbances in sympathy. D. TRAILL

Raleigh Lodge, Exmouth, February 4

GAS AND ELECTRICITY AS HEATING AGENTS[1]

II.

GAS engineers have been under the impression until now that a supply of cold air was favourable to the production of a brilliant flame. This is a misconception, which was very general also as regards the combustion of solid fuel in furnaces, until it was disproved by Stirling, by Neilson, and by the introduction of the Regenerative Gas Furnace. The "duplex burner" owes its brilliancy to the heating effect of the one burner upon the other; and my brother, Mr. Frederick Siemens, has more recently constructed a burner in which the flame of the gas is reversed in its action in order to heat in its descent the ascending current of flame-supporting air.

By the application of the principle of conduction before described, I obtain the hot-air current in a most simple manner without interfering with the free action of the flame. The construction of my burner will be seen from the diagram. A is an ordinary Argand burner, taking its supply of gas through the enlarged vertical copper tube B. This copper pipe terminates in a rod C of highly conductive copper, which passes upward through the burner, and carries at its top a ball of porcelain or other refractory material. The rod is coated with platinum or nickel to prevent oxidation when heated (almost to redness) by the heat of the flame. The tube B is armed with radial plates of copper presenting a considerable aggregate surface, and abutting externally against a covering of asbestos or other non-conductive material.

The waste heat of the flame, or that portion of the heat produced in combustion which is not utilised in luminous rays, serves to heat the ball of refractory material D and the conductive rod C. The heat is thus transferred by conduction to the tube B, with its laminar radii, between the extensive surfaces of which currents of air are free to ascend toward the Argand burner. The air is thus heated to from 700° to 800° F. before meeting the gas, and the ultimate temperature of the flame is increased to at least the same amount, causing a larger proportion of the heat developed in combustion to reach the point of luminous radiation.

But not only the quantity of light but its quality is improved by the higher temperature obtained.

It may appear surprising, but it is a fact susceptible of accurate proof, that the light obtained in consumption of a given amount of gas may thus be increased by some 40 per cent., and that in this large proportion the deleterious influences connected with gas lighting may be diminished. Gas will thus be better able to hold its position against its more brilliant rival the electric light, except for such large applications as the lighting of public halls and places, of harbours, railway stations, warehouses, &c, for which it is pre-eminently suited. Add to these improved applications of gas the ever-increasing ones for heating purposes, and I have only to express regret that I am not a gas shareholder.

If gas is to be largely employed, however, for heating purposes, it will have to come down in price; and considering that heating gas need not be highly purified, or possessed of high illuminating power, the time will come, I believe, when we shall have two services, one for illuminating, and the other for heating gas.

In many towns two systems of gas mains already exist; and it would only be necessary to appropriate the one for illuminating and the other for heating gas. The ordinary retorts could be used for the production of both descriptions of gas, it being well known that even ordinary coal will give up gases of high illuminating power during a certain portion of the time occupied in their entire distillation. The gases emitted from the retort when first charged are to a great extent occluded gases of low illuminating power such as fire-damp or marsh-gas, and these should be turned into the heating mains. In the course of half-an-hour these occluded gases, together with the aqueous and other vapours, will have left the coal, which is then in the best condition to evolve olefiant gas and other gases rich in carbon, and therefore of high illuminating power. The period during which such illuminating gases are emitted extends over probably two hours, after which the retorts should again be connected with the heating gas mains, until the end of the process. The result of this *modus operandi* would be that the illuminating gas supplied, say in London, from Newcastle coal would probably exceed 20 candle power, instead of 16 as at present, whereby the objectionable results of gas lighting would be greatly diminished, and there would be, say, an equal volume of heating gas available, consisting for the most part of marsh-gas, which, although greatly inferior to olefiant gas in illuminating effect, would be actually more suitable for heating purposes, because less liable to produce soot in its combustion.

The total cost of production would not be increased by this separation of the gases, and the price might with advantage

[1] A lecture by C. William Siemens, D.C.L., LL.D., F.R.S., on January 27, in St. Andrew's Hall, Glasgow, under the auspices of the Glasgow Science Lecture Association. Continued from p. 329.

both to the supplier and to the consumer be so adjusted that the latter, while paying for his illuminating gas an increased price proportionate to the increase of illuminating power, would be furnished with a heating gas at greatly reduced cost; for the heating gas could be reduced in price in a much larger proportion than the illuminating gas would have to be raised, because it would not require the same purification from sulphur which renders illuminating gas comparatively costly. The enormous increase of consumption would moreover enable the gas companies to reduce prices all round very considerably without interfering with their comfortable revenues.

For large applications of heating gas to the working of furnaces and boilers, simpler means than the retort can be found for its production. I constructed a gas producer many years ago in connection with my Regenerative Gas Furnace; this I need not now describe in detail. In it all the carbonaceous matter of the coal is converted into combustible gas, the solid carbon yielding a supply of carbonic oxide; the resultant mixture of combustible gas contains a very large proportion averaging 61·5 per cent. of nitrogen, which swells its volume without in any way contributing to its heating power.

It has been my endeavour for some time to construct a gas producer which, without losing the simplicity of the first, should be capable of yielding a heating gas of superior calorific power. This producer consists of a wrought-iron cylindrical chamber, truncated downwards, and lined with brickwork. The fuel to be converted into gas is introduced through a hopper, and the cinder and ashes work out through the open orifice at the bottom.

Instead of a grating for the introduction of atmospheric air a current of heated air is brought in, either through the hopper or through the orifice at the bottom, and is discharged into the centre of the mass of fuel; the effect is the generation of a very intense heat at that point. The fuel, after its descent through the hopper, arrives gradually at this region of intense heat, and when subjected to it, parts with its gaseous constituents. At the point of maximum heat coke is consumed, producing carbonic anhydride, which, in passing through the considerable thickness of fuel surrounding this portion, takes up a second equivalent of carbon, and becomes changed into carbonic oxide. Here also the earthy constituents are for the most part separated in a fused or semi-fused condition, and in descending gradually reach the orifice at the bottom, whence they are removed from time to time. Air enters through the bottom orifice to some extent, causing the entire consumption of the carbonaceous matter, which may have got past the zone of greatest heat; water is also here introduced in a hollow tray, and after evaporation by the heat of the hot clinkers, passes upwards through the incandescent mass, and is converted by decomposition into carbonic oxide and hydrogen gas. The exit orifices for the gases are placed all round, near the circumference of the chamber, ascending upwards into an annular space, whence they are taken through pipes to the furnace or other destination.

The advantages connected with this *modus operandi* consist in the intensity of the heat produced within the centre of the mass, whereby the whole of the fuel is converted into combustible gases, with the least amount of nitrogen. The hydrocarbons formed in the upper portion of the apparatus have to descend through the hotter fuel below, and in so doing the tar and other vapours mixed up with them are decomposed, and furnish combustible gases of a permanent character.

The orifice at the bottom of the apparatus may be enlarged, and so arranged that, instead of ashes only being produced, coke may be withdrawn, and in this way a continuous coke oven may be constructed, which is at the same time a gas producer, or in other words an apparatus in which both the solid and gaseous constituents of the coal are fully utilised.

The intense heat in the very centre of a large mass of fuel has for its result a very rapid distillation, and thus one gas producer does the work of two or three gas producers of the type hitherto employed; this more concentrated action will moreover allow of the introduction of gaseous fuel, where want of space and considerations of economy have militated hitherto against it, and in favour of the ordinary coal furnace.

It has been already proved that steam boilers can be worked economically on land with gaseous fuel, and there is no reason that I know of why the same mode of working should not also be applied to marine boilers. The marine engine has, within the last fifteen years, been improved to an extent which is truly surprising: the consumption of coal, which at the commencement of that period was never less than 8 lbs. per HP., has been reduced by expansive working in compound cylinders to 2 lbs., or even less, per actual HP. The mode of firing marine boilers has, however, remained the same as it was in the days of Watt and Fulton. In crossing the Atlantic one may see a considerable number of men incessantly employed in the close stoke-hole of the vessel opening the fire-doors and throwing in fuel. Each charge gives rise to the development of great clouds of black smoke issuing from the chimney, to the great annoyance and discomfort of the passengers on deck. If, instead of this, the fuel could be discharged mechanically into one or more gas producers, the gaseous fuel produced would maintain the boilers at a very uniform heat, without necessitating the almost superhuman toil of the fireman; no smoke or dust would be emited from the chimney, and a large saving of fuel would be effected.

This change would be specially appreciated by the numerous tourists visiting the Western Highlands. Speaking from my own experience on one occasion, I may say that the pleasure of a trip on the beautiful Loch Lomond was very seriously marred in consequence of the fumigation which my fellow passengers and myself had to endure.

The change from the use of solid to gaseous fuel would be the prelude probably to another, and still more important change, namely the entire suppression of the steam boiler. We are already in possession of gas-engines working at moderate expense as compared with small steam-engines, even when supplied with the comparatively expensive gas from our town gas-mains, and all that will be required is an extension of the principle of operation already established. The realisation of such a plan would of course involve many important considerations, and may be looked upon as one of those subjects the accomplishment of which may be left for the energy and inventive power of the rising generation of engineers.

Before leaving this branch of the subject I wish to call attention to a favourite suggestion which I had occasion to make some years ago. It consists in placing gas-producers at the bottom of the coal mines themselves, so that instead of having to raise the coal by mechanical power, the combustible gases ascending from the depth of the mine to the surface would acquire by virtue of their low specific gravity such an onward pressure that they could be conducted in tubes to distances of many miles, thus saving the cost of raising and transporting the solid fuel.

Glasgow with its adjoining coal-fields appears to me a particularly favourable locality for putting such a plan to a practical trial, and the well-known enterprise of its inhabitants makes me sanguine of its accomplishment. When thus applied with gaseous fuel, the town would not only be able to boast of a clear atmosphere, but the streets would be relieved of the most objectionable portion of the daily traffic.

I now approach another and the last portion of my address, the attainment of very intense degrees of heat either for effecting fusion or chemical decomposition. Although by means of the combustion of either solid or gaseous fuel heats are produced which suffice for all ordinary purposes, there is a limit imposed upon the degree of temperature attainable by any furnace depending upon combustion. It has been shown by Bunsen and by St. Claire-Deville, that at certain temperatures the chemical affinity between oxygen on the one hand and carbon and hydrogen on the other absolutely ceases, and that if the products of combustion CO_2 and H_2O be exposed to such a degree of temperature they would fall to pieces into their constituent elements. This point of dissociation, as it is called, is influenced by pressure, but has been found for CO_2 under atmospheric pressure to be 2600° C. (or 4700° Fahr.). But long before this extreme point has been arrived at, combustion is greatly retarded, and the limit is reached when the losses of heat by radiation from the furnace balance its production by combustion.

To electricity we must look for the attainment of a temperature above that of dissociation, and we have evidence of the early application of the electric arc to such a purpose. In 1807 Sir Humphry Davy succeeded in decomposing potash by means of an electric current from a Wollaston battery of 400 elements, and in 1810 he surprised the members of the Royal Institution by the brilliant electric arc produced between carbon points through the same agency.

Magneto-electric and dynamo-electric currents allow of the production of the electric arc much more readily and econo-

mically than by the use of Sir Humphry Davy's gigantic battery, and Messrs. Huggins, Lockyer, Liveing, and other physicists have taken advantage of the comparatively new method to advance astronomical and chemical research with the aid of spectrum analysis.

My object is now to show that the heat of the electric arc is not only available within a focus or extremely contracted space, but that it is capable of producing such larger effects as will render it useful in the arts for fusing platinum, iridium, steel, or iron, or for effecting such reactions or decompositions as require for their accomplishment an intense degree of heat, coupled with freedom from such disturbing influences as are inseparable from a furnace worked by the combustion of carbonaceous material.

The apparatus which I employ to effect the electro-fusion of such material as iron or platinum is represented in the drawing. It consists of an ordinary crucible of plumbago or other highly refractory material, placed in a metallic jacket or outer casing, the intervening space being filled up with pounded charcoal or other bad conductor of heat. A hole is pierced through the bottom of the crucible for the admission of a rod of iron, platinum, or dense carbon, such as is used in electric illumination. The cover of the crucible is also pierced for the reception of the negative electrode, by preference a cylinder of compressed carbon of comparatively large dimensions. At one end of a beam, supported at its centre, is suspended the negative electrode by means of a strip of copper, or other good conductor of electricity, the other end of the beam being attached to a hollow cylinder of soft iron free to move vertically within a solenoid coil of wire, presenting a total resistance of about 50 units or ohms. By means of a sliding weight the preponderance of the beam in the direction of the solenoid can be varied so as to balance the magnetic force with which the hollow iron cylinder is drawn into the coil. One end of the solenoid coil is connected with the positive and the other with the negative pole of the electric arc, and, being a coil of high resistance, its attractive force on the iron cylinder is proportional to the electromotive force between the two electrodes, or, in other words, to the electrical resistance of the arc itself.

The resistance of the arc was determined and fixed, at well within the limits of the source of power, by sliding the weight upon the beam. If the resistance of the arc should increase from any cause the current passing through the solenoid would gain in strength, and the magnetic force overcoming the counteracting weight would cause the negative electrode to descend deeper into the crucible; whereas, if the resistance of the arc should fall below the desired limit, the weight would drive back the iron cylinder within the coils, and the length of the arc would increase, until the balance between the forces engaged had been re-established.

Experiments with long solenoid coils have shown that the attractive force exerted upon the iron cylinder is subject only to slight variation within a range of several inches, which circumstance allows of a working range to that extent of nearly uniform action on the electric arc.

This automatic adjustment of the arc is of great importance to the attainment of advantageous results in the process of electric fusion; without it the resistance of the arc would rapidly diminish with increase of temperature of the heated atmosphere within the crucible, and heat would be developed in the dynamo-electric machine to the prejudice of the electric furnace. The sudden sinking or change in electrical resistance of the material undergoing fusion would, on the other hand, cause sudden increase in the resistance of the arc, with a likelihood of its extinction, if such self-adjusting action did not take place.

Another important element of success in electric fusion consists in constituting the material to be fused the positive pole of the electric arc. It is well known that it is at the positive pole that the heat is principally developed, and fusion of the material constituting the positive pole takes place even before the crucible itself is heated up to the same degree. This principle of action is of course applicable only to the melting of metals and other electrical conductors, such as metallic oxides, which constitute the materials generally operated upon in metallurgical processes. In operating upon non-conductive earth or upon streams of gases it becomes necessary to provide a non-destructible positive pole, such as is supplied by the use of a pole of fused platinum, or iridium, or by a plumbago crucible. In working the electric furnace some time is taken up in the first instance in raising the temperature of the crucible to a considerable degree, but it is surprising how rapidly an accumulation of heat takes place. In using a pair of dynamo-machines capable of producing 70 webers of current with an expenditure of 7-horse power, and which, when used for purposes of illumination, produce a light of 12,000 candles, a crucible of about 8 inches in depth, immersed in a non-conductive material, has its temperature raised to a white heat in fifteen minutes, and 4 lbs. of steel are fused within another fifteen minutes, successive fusions being effected in somewhat diminishing intervals of time. The process can be carried on on a still larger scale by increasing the power of the dynamo-machines and the size of the crucibles.

The purely chemical reaction intended to be carried into effect within the crucible might be interfered with through the detachment of particles from the dense carbon used for the negative pole, although its consumption within a neutral atmosphere is exceedingly slow. To prevent this I have used, both in this connection and also in the construction of electric lamps, a water pole, or tube of copper, through which a current of water circulates, so that it yields no substance to the arc. It consists simply of a stout copper cylinder closed at the lower end, having an inner tube penetrating to near the bottom for the passage of a current of water into the cylinder, which water enters and is discharged by means of flexible india-rubber tubing. This tubing being of non-conductive material, and its sectional area small, the escape of current from the pole to the reservoir is so slight that it may be neglected. On the other hand some loss of heat is incurred, through conduction, with the use of the water pole, but this loss diminishes with the increasing heat of the furnace, inasmuch as the arc becomes longer, and the pole is retired more and more into the crucible cover.

In the experiments which I shall now place before you the current which has supplied the one electric lamp in the centre of the hall will be diverted by means of a commutator through the electric furnace. After it has been active for five minutes to warm the crucible, I shall charge it with 8 lbs. of broken steel files, which I shall endeavour to melt and pour out into an ingot mould before your eyes.

By some obvious modifications of this electric furnace it can be made available for a variety of other purposes where intense heat is required combined with immunity from disturbing chemical actions. By piercing a number of radial holes through the sides of the chamber, and introducing the ends of wires through the same, an excellent means is provided of heating those wire ends very rapidly, without burning them, for the purpose of welding them together. The electrical furnace will also be found useful, I believe, in the hands of the chemist to effect those high temperature reactions between gaseous bodies which require the employment of temperatures far exceeding the hitherto available limits, and will thus increase the area of available reactions at his disposal for the attainment of either scientific or practical ends.

I have endeavoured to compress within the limited space of a single lecture, subject matter that might occupy the close attention of the student for weeks or months, and I may therefore be pardoned if I have failed to convey to you more than a very rough outline of what may be accomplished by the judicious use of gaseous fuel, and of the electric current, as heating agents. The one purpose that has been foremost in my mind in preparing this lecture, has been to make war upon the smoky chimney, which, so far from being a necessity under any circumstances whatever, should be regarded only as a remnant of that stage of our industrial and social progress which satisfied with the attainment of certain ends, could afford to neglect the economical and sanitary conditions under which those ends were accomplished.

The Exhibition which has lately been held in this city of appliances for heating and illuminating by means of gas and electricity, in which your President, my esteemed friend, Sir William Thomson, took so prominent a part, as he does in everything tending towards the advancement of human knowledge and well-being—proves how deep is the interest felt amongst you in those very questions with which I have had to deal this evening.

And so I thought you might not be disinclined to give attention once more to a particular view of the question, which happens to be the result of the independent labour of one who may claim at any rate to have given a life-long attention to the subject.

PHOTOPHONE EXPERIMENTS

MR. ANDREW JAMIESON, C.E., Principal of the Glasgow Mechanics Institution, sends us an account of the following experiments on the photophone, shown by him at a lecture delivered by him on January 19, before the Glasgow Philosophical Society, on the history of selenium.

The effects of light and heat on the conductivity of selenium were shown by means of a simple and inexpensive form of "cell" joined up in a Wheatstone's Bridge with a reflecting galvanometer. The cell is constructed in the following way:—A piece of plate-glass or of a glass tube of about an inch diameter and about three inches long is chosen, and upon its exterior are tightly wound two separate parallel wires of No. 25 B.W.G., the wires themselves being of copper covered with silk or cotton. A red-hot iron or poker is then applied to the middle region of the coil of wire so as to burn off the insulating covering of silk

Fig. 1.



or cotton. The bare wires are cleaned, and the blank cell being raised to the proper temperature, vitreous selenium is rubbed on the wires so as to fill the narrow interspaces left by the removal of the silk covering. The selenium is afterwards annealed in the the usual fashion to render it more highly conductive. One of the cells thus used had resistances of 5740 and 3440 ohms respectively in the dark and in the light; but others have less resistances, one being as small as 500 ohms in the dark. The first-named cell (a flat one) was twenty-one days old, and had increased several thousand ohms in that time.

The musical note of a "singing flame" was reproduced in the telephone by means of one of the annular cells thus formed upon a glass tube in the following manner, suggested by Prof. Blyth (Fig. 1):—The cell, C, joined in circuit with a battery, B, and telephone, T, was placed outside entirely surrounding the glass tube in which a small gas-jet was "singing." Speech was afterwards reproduced by the arrangement shown in Fig. 2. At the



Fig 2.

back conical mouthpiece which receives the voice is fixed a membrane of goldbeater's skin which forms the front of a chamber, A, into which gas is led, and from which a short tube leads to a small gas-jet, in the manner devised by König. Opposite the gas-flame was placed the selenium cell in circuit with a battery of twenty cells and a distant telephone. There were thus eleven changes going on simultaneously:—

1. Muscular movement of speaker's vocal organs.
2. Vibration of air opposite speaker's mouth.
3. Corresponding vibrations of the thin membrane.
4. Variations of pressure controlling the supply of gas to jet.
5. Hence increase and decrease of gas-flame.
6. Increase and decrease of resistance of the selenium cell.
7. Rise and fall of battery current.
8. Increase and decrease of magnetism in magnet of telephone.
9. To-and-fro movement of telephone disk.
10. Vibration of air opposite the same.
11. Vibration of drum of ear of listener at the telephone and a sound heard.

Not only the pitch but the tone of the voice was distinctly heard.

THE COFFEE-LEAF DISEASE

TWO interesting papers on this subject were read at the last meeting (3rd inst.) of the Linnean Society, the one treating of its ravages in India, the other its nature and spread in South America.

In the first Mr. Wm. Bidie, in a letter to Mr. J. Cameron of Bangalore, refers to the Coorg country, situated in the Western Ghats, where European enterprise in coffee has been wholly developed within the last twenty-five years, and no disease was observed till four or five years ago. The author mentions that the disease appears to have been imported from Ceylon by way of Chickmoorloor, a district of Mysore, sixty miles distant from Coorg. It seems worst in impoverished, exposed fields, and least where there is shade and rich soil. A small red insect has been noticed feeding over leaves covered with the pest, but what the insect's relation is to the disease as yet remains undetermined. Plants grown from Ceylon seed suffer most, while those trees of Coorg origin and growth are least affected. A system of "renovation-pitting" has been successfully tried, a pit being dug at short intervals wherein, after judicious pruning, all the affected leaves are buried, and this precaution seems to check the spread of the disease, particularly among the Coorg coffee-trees.

In the second communication Dr. M. C. Cooke describes and summarises all the data extant up to the present time of the progress of coffee disease in South America. Plantations in Venezuela, Costa Rica, Bogota, Carácas, and Jamaica have been affected. He discourses on the nature of the blight, and is of opinion that the disease is a complicated one, being himself as yet unprepared to affirm that either the *Septoria*, the *Sphærella*, or the *Stilbum*, three so-called different kinds of fungi, or altogether, is the true cause of the disease. At the same time he thinks it possible that none of these forms of fungus are autonomous, and that all may be related to each other as forms or conditions of the same fungus, of which *Sphærella* is the highest and most perfect manifestation. He observes that the discoloured spots may be without any visible fungus upon them, and exhibit no trace of mycelium in the tissues, or they may nourish a *Septoria*, as seen by the Rev. M. J. Berkeley, or a *Sphærella* as found by himself, or finally a species of *Stilbum* as seen by Prof. Saenx and himself. Further, the *Stilbum* may occur on the same spot as the perithecia of the *Sphærella*, or both perithecia and *Stilbum*; the one without the other may be found occupying different spots. Mr. Cooke admits that altogether it is difficult satisfactorily to answer the question, What is the cause of this form of coffee disease?

UNIVERSITY AND EDUCATIONAL INTELLIGENCE

OXFORD.—Sir William Harcourt announced on Monday that the evidence taken before the Oxford University Commissioners would be laid before Parliament without delay.

CAMBRIDGE.—The first Smith prize has been adjudged to A. R. Forsyth, of Trinity College, Senior Wrangler. R. S. Heath, of Trinity College, Second Wrangler, and A. E. Steinthal, also of Trinity College, Third Wrangler, were equal in the competition for the second prize.

Mr. W. J. Lewis, M.A., of Trinity College, Cambridge, and Fellow of Oriel College, Oxford, has been elected to the Chair of Mineralogy, in the place of the late Prof. Miller, F.R.S. The University is to be congratulated on having secured as Professor of Mineralogy one so competent to take Prof. Miller's place.

Mr. A. Scott is giving demonstrations in Elementary Organic Chemistry at the University Laboratory. Mr. J. F. Walker is lecturing on the same subject at Sidney Sussex College.

Lord Rayleigh is giving a short course on the Unit of Electrical Resistance, and on February 21 will commence an advanced course of lectures on Sound. Mr. Glazebrook is giving demonstrations on Advanced Electricity and Magnetism, and

Mr. Shaw on Heat. All these courses are given in the Cavendish Laboratory.

Prof. Stuart is lecturing on the Differential Calculus and its Application to Mechanics; the Demonstrator has a course on Elementary Applied Mechanics.

Dr. Michael Foster continues his course of Elementary Physiology. The advanced lectures announced this term are by Mr. Lea (who has been appointed Lecturer in Physiology at Gonville and Caius College), on Physiological Chemistry; Mr. Langley, on the Histology and Physiology of the Digestive System, and Mr. Hill (Downing College), on the Central Nervous System.

The Report of the Syndicate on the Higher Education of Women is to be discussed to-morrow (February 11).

The Board of Natural Science Studies recommends that the agreement between the University and Dr. Dohrn, of the Zoological Station at Naples, by which 75*l.* per annum is paid from the Worts Travelling Bachelors' Fund towards the expenses of the station, be renewed for five years. The Board calls attention to the services which those members of the University who have studied at Naples have rendered to science and the University, and to the fact that three of them have obtained professorships elsewhere, namely Professors A. M. Marshall (Owens), T. W. Bridge (Mason's College, Birmingham), and A. C. Haddon (Dublin).

At Newnham College Miss Harland is lecturing on Euclid and Algebra, and Miss Scott on Analytical Conics, Mr. Garnett lectures on Statics and on Experimental Physics, Mr. Hudson on Arithmetic and on the Differential Calculus, Mr. Hillhouse on Botany, while Miss Cross superintends practical and paper work in Chemistry and Geology.

SOCIETIES AND ACADEMIES

LONDON

Royal Society, December 9, 1880.—"The Electrostatic Capacity of Glass," by J. Hopkinson, M.A., D.Sc., F.R.S.

In 1877 I had the honour of presenting to the Royal Society (*Phil. Trans.*, 1878, Part i.) the results of some determinations of specific inductive capacity of glasses, the results being obtained with comparatively low electromotive forces, and with periods of charge and discharge of sensible duration. In 1878 Mr. Gordon (*Phil. Trans.*, 1879, Part i.) presented to the Royal Society results of experiments, some of them upon precisely similar glasses, by a quite different method with much greater electromotive forces, and with very short times of charge and discharge. Mr. Gordon's results and mine differ to an extent which mere errors of observation cannot account for. Thus for double extra dense flint glass I gave 10·1, Mr. Gordon 3·1, and subsequently 3·89 (Report of British Association for 1879). These results indicate one of three things, either my method is radically bad, Mr. Gordon's method is bad, or there are some physical facts not yet investigated which would account for the difference. Two suggestions occur:—1. Possibly for glass K is not a constant, but is a function of the electromotive force. 2. When a glass condenser is discharged for any finite time, a part of the residual discharge will be included with the instantaneous discharge, and the greater the time the greater the error so caused. To test the first I measured the capacity of thick glass plates with differences of potential ranging from 10 to 500 volts, and also of thin glass flasks between similar limits; the result is that I cannot say that the capacity is either greater or less where the electromotive force is 5000 volts per millimetre than where it is $\frac{1}{4}$ volt per millimetre. The easiest way to test the second hypothesis is to ascertain how nearly a glass flask can be discharged in an exceedingly short time. A flask of light flint glass was tested; it was charged for some seconds, discharged for a time not greater than $\frac{1}{1700}$ second, and the residual charge observed so soon as the electrometer needle came to rest; the result was that the residual charge under these circumstances did not exceed 3 per cent. of the original charge, also that it mattered not whether the discharge lasted $\frac{1}{1700}$ second or $\frac{1}{10}$ second. These experiments suffice to show that neither of the above suppositions accounts for the facts.

I have repeated my own experiments with the guard-ring condenser, but with a more powerful battery, and with a new key which differs from the old one, inasmuch as immediately after the condensers are connected to the electrometer they are separated from it. In no case do I obtain results differing much from those I had previously published.

Lastly, a rough model of the five plate induction balance used by Mr. Gordon was constructed, but arranged so that the distances of the plates could be varied within wide limits. So far as instrumental means at hand admitted Mr. Gordon's method was used. A plate of double extra dense flint and a plate of brass were tried. In the first, by varying the distances of the five plates, values of K were obtained ranging from $1\frac{1}{2}$ to $8\frac{1}{4}$, with the latter results from $\frac{1}{10}$ to 3. It is clear that the five plate induction balance thus arranged cannot give reliable results.

The explanation of the anomaly, then, is that the deviation from uniformity of field in Mr. Gordon's apparatus causes errors greater than any one would suspect without actual trial. It is probable that the supposed change of electrostatic capacity with time may be accounted for in the same way.

January 27.—"Dielectric Capacity of Liquids." By J. Hopkinson, F.R.S.

These experiments have for object the determination of the refractive indices and the specific inductive capacity of certain liquids, and a comparison of the square of the refractive index for long waves and the specific inductive capacity.

In the following table are given the results obtained for refractive index for long waves deduced by the formula $\mu = \mu_\infty + \frac{b}{\lambda^2}$, the square of μ_∞, and the observed values (K) of the specific inductive capacity.

	μ^2_∞	K
Petroleum spirit (Field's)	1·922	1·92
Petroleum oil (Field's)	2·075	2·07
,, (Common)...	2·078	2·10
Ozokerit lubricating oil (Field's) ...	2·086	2·13
Turpentine (Commercial)	2·128	2·23
Castor oil	2·153	4·78
Sperm oil	2·135	3·02
Olive oil	2·131	3·16
Neatsfoot oil	2·125	3·07

It will be seen that whilst for hydrocarbons $\mu^2_\infty = K$, for animal and vegetable oils it is not so.

Zoological Society, February 1.—Prof. W. H. Flower, LL.D., F.R.S., president, in the chair.—Mr. F. M. Balfour, F.R.S., read a paper on the evolution of the placenta and made some observations on the possibility of employing the characters of this organ in the classification of the mammals.—Mr. Sclater read notes on some birds collected by Mr. E. F. im Thurn in British Guiana, amongst which was an example of a new species of *Agelæus*, proposed to be called *A. im-Thurni*, after its discoverer.—Mr. W. T. Blanford, F.R.S., read an account of a collection of reptiles and frogs made at Singapore by Dr. W. B. Dennys. In this collection were two new species of Ophidians, which were named respectively *Cylindrophis lineatus* and *Simotes Dennysi*, and two new frogs, which the author proposed to call *Rana laticeps* and *Rhacophorus Dennysi*.—Mr. A. D. Bartlett read an account of a peculiar habit of the Darter (*Plotus anhinga*) in casting up parts of the epithelial lining of its stomach, as observed by him in the specimen now living in the Society's collection.—A communication was read from Mr. A. Heneage Cocks, F.Z.S., containing notes on the breeding of otters, as observed by him in specimens living in his possession.—The Secretary read a paper by the late Mr. Arthur O'Shaughnessy, containing an account of a large collection of lizards made by Mr. C. Buckley in Ecuador. The collection was stated to be of great interest, both on account of the number of new species it contained and the fresh material it afforded for the study of species already known. Mr. O'Shaughnessy had given last year a partial notice of this collection, confined however to a preliminary list of the species of *Anolis* identified. The present paper gave the results of a study of the whole collection, and was not restricted to a description of the new forms, but enumerated all the species, for the purpose of recording additional remarks and revisions which appeared necessary. In it twenty-seven species were mentioned, ten of which were new.—Mr. G. A. Boulenger read an account of a new species of *Enyalius* in the Brussels Museum, from Ecuador, which he proposed to name *Enyalius O'Shaughnessyi*.—Lieut.-Col. H. H. Godwin-Austen, F.R.S., read the first part of a memoir on the land-shells collected on the island of Socotra by Prof. I. B. Balfour. The present communication comprised an account of the species of *Cyclostomaceæ* found on the island.

Photographic Society, January 11.—J. Glaisher, F.R.S., president, in the chair.—Papers were read by E. Viles on the

lime-light. The principal matter insisted upon was that the oxygen and hydrogen gases should unite in one stream, just before issuing from the nozzle of the burner, and the tubes kept entirely free from wire gauze or any impediment whatever; also that the lime cylinder should be in two pieces, when if the upper part splits the lower part (already heated) could be screwed into position at once.—Also by T. Bolas, F.C.S., on the detective camera. This apparatus consists of two cameras working simultaneously together: in one the image can be seen, whilst in the other a sensitive dry plate is ready for instant exposure by pneumatic power. The whole is inclosed in an unsuspicious wooden box, which can even be placed upon the ground, and scenes and persons photographed unawares.

Victoria (Philosophical) Institute, February 7.—The Earl of Shaftesbury, K.G., in the chair.—A paper was read by Dr. Samuel Kinns, F.R.A.S., on "The Truths of Revelation confirmed by the Advances of Science."

Institution of Civil Engineers, February 1.—Mr. Abernethy, F.R.S.E., president, in the chair.—The paper read was on the Portsmouth Dockyard Extension Works, by Mr. Charles Colson, Assoc. M. Inst. C.E.

PARIS

Academy of Sciences, January 31.—M. Wurtz in the chair.—The following papers were read:—On the long duration of the life of germs of *charbon*, and on their preservation in cultivated earth, by M. Pasteur, with MM. Chamberland and Roux. This relates to an inquiry made by a committee elected by the Paris Society of Veterinary Medicine. Sheep caught the disease from being a few hours daily on ground where animals that died of *charbon* had been buried twelve years before. There was no grass to eat; the germs must have entered the sheep by reason of their habit of smelling about the ground. The farmer had a scar of malignant pustula.—Observations on the birds of the Antarctic Region, by M. Alph. Milne-Edwards. This relates to the first part of a work on the fauna of Austral regions. Birds serve more than any other animals to mark the profound differences between faunas of the southern and those of the northern hemisphere. The geographical distribution of penguins and spheniscans present interesting features in this respect.—On a mode of representation of functions, by M. Gyldén.—On a fall of sleet at Geneva, on January 19, by M. Colladon. The grains were compact and pretty round, and they showed curious dancing movements (sometimes after being motionless two or three seconds), like those of pith balls under electricity.—M. Clos was elected Correspondent in Botany, in room of the late M. Godron.—On the circulatory apparatus of edriophthalmate crustaceans (continued), by M. Delage. This relates to Amphipoda and Læmodipoda.—Action of sulphocarbonate of potassium on phylloxerised vines, by M. Mouillefert. The effects of three to six, two, and one year's treatment are severally considered.—On the figure of planets, by M. Hennessy. For the earth and near planets supposed like it the compression deduced from the theory of fluidity agrees better with observation than that deduced from the theory of superficial erosion.—On the series of Fourier, by M. Jordan.—On an extension of the rule of signs of Descartes, by M. Laguerre.—On a particular cyclic system, by M. Ribaucour.—On the quadrature on which depends the solution of an extensive class of linear differential equations with rational coefficients, by M. Dillner.—On the distinction of integrals of linear differential equations into sub-groups, by M. Casorati.—On the invariant of the eighteenth order of binary forms of the fifth degree, by M. Le Paige.—Action of hydrochloric acid on metallic chlorides (continued), by M. Ditte. In the case of chlorides very soluble in water (less so in acid liquor), and deposited in it as crystallised hydrates, hydrochloric acid diminishes the weight of chloride dissolved, and in the acid liquors one still finds hydrated salts, though much less rich than the crystals that form in this liquid. Another (and last) group contains chlorides that crystallise anhydrous in water or hydrochloric acid, but the solubility of which in concentrated acid is reduced almost to zero.—Determination of the colours which correspond to fundamental sensations, by means of rotatory disks, by M. Rosenstiehl. The line which represents the proportion of extreme sensations in the intermediate colours is a straight one (they are thus, to sight, rigorously equidistant). The line which represents the sensation of yellow reaches its culminating point in the ordinate corresponding to yellow. The sensation of red rises in a straight line to the red, and beyond that to the orange, where it culminates; then it falls to the yellow, where it is zero.—On the determination of carbonic acid in air, by MM. Muntz and Aubin. They have studied the variations of which the proportion of CO_2 in special parts of the atmosphere is susceptible, and here first describe their method (absorption by pumice-stone impregnated with potash solution, then liberation, and measurement of volume), and verify its value.—Observations on a note by M. Eisenberg, on separation of trimethylamine from substances accompanying it in commercial chlorhydrate of trimethylamine, by MM. Duvillier and Buisine.—On a process of total destruction of organic matters, for investigation of poisonous mineral substances, by M. Pouchet. The principle is that it is possible to heat between 300° and 400°, in presence of carbon or organic compounds, mineral elements contained in a mixture of sulphuric acid and acid sulphate of potash. The sulphate of potash retains substances the most volatile and decomposable (*e.g.* salts of mercury), while the organic matters are quickly destroyed.—On the invasion of pulmonary tissue by a champignon, in peripneumonia, by M. Poincaré.—The third edition of M. Domeyko's Treatise on Mineralogy (in Spanish) was presented. It contains original researches on various South American minerals.

VIENNA

Imperial Academy of Sciences, February 4.—V. Burg in the chair.—F. Osnaghi and V. Lorenz, fifth report of the Adria Commission on the Physical Exploration of Adria.—Prof. L. Pelz, on scientific treatment of axionometry.—Prof. A. Wassmuth, on the possibility of magnetising iron at high temperatures.—Prof. T. Tlann, on the daily course of some meteorological elements in Vienna (city).—G. Bruder, on the knowledge of the tura-formation of Sternberg near Zeidler (Bohemia).—Prof. Sigmund Exner, on the knowledge of the minute structure of the cortex of the brain.

GÖTTINGEN

Royal Society of Sciences, August 7, 1880.—On fluospar in granite of Drammen, by O. Lang.—Some experiments on induction in conducting bodies, by F. Himstedt.

November 5.—On an increase of the meteorite-collection of the University, by C. Klein.—Communication regarding the publication of a text-book of analysis, by R. Lipschitz.—Electrical shadows, by W. Holtz.

December 6.—Electrical shadows (continued), by W. Holtz.—On the connection between the general and the particular integrals of differential equations, by L. Königsberger.—Observations in the magnetic observatory, by K. Schering.—On congenital growth in the thallus of Pollexfeniæ, by P. Falkenberg.—Communications on the University Library from 1876-79, by W. Willmanns.

CONTENTS

	Page
Alpine Flowers. By Francis Darwin	333
Our Book Shelf:—	
Barfoed's "Lehrbuch der organischen Qualitativen Analyse"	335
Letters to the Editor:—	
Mr. Butler's "Unconscious Memory."—George J. Romanes, F.R.S.; T. R. R. Stebbing	335
"Prehistoric Europe."—Dr. James Geikie, F.R.S.	336
On Dust, Fogs, and Clouds.—W. H. Preece; Dr. H. J. H. Gronemann	336
New Cases of Dimorphism of Flowers.—Errors Corrected.—Dr. Hermann Müller	337
Geological Climates.—Dr. John Rae, F.R.S.	337
On the Spectrum of Carbon.—Prof. G. D. Liveing, F.R.S.	338
Vibration of Telegraph Wires during Frost.—F. T. Mott	338
The Star Oeltzen, 17681.—Prof. Edward C. Pickering	338
Zeuglodontia.—Searles V. Wood (*With Illustrations*)	338
Ice Intrusive in Peat.—T. Mellard Reade	339
The Squirrel Crossing Water.—H. H. Godwin-Austen	340
Baron Nordenskjöld in Finland	340
The John Duncan Fund	342
Experiments on Ice, under Low Pressures. By Dr. Thos. Carnelley (*With Diagrams*)	342
Tele-Photography. By Shelford Bidwell (*With Diagrams*)	344
Notes	346
The Aurora and Electric Storm of January 31. By W. H. Preece; George M. Seabroke; G. M. Whipple; Rev. S. J. Perry, F.R.S.; J. Rand Capron; E. J. Lowe; G. Henry Kinahan; Gerard A. Kinahan; F. Horner; W. J. Spratling; D. Traill (*With Diagrams*)	348
Gas and Electricity as Heating Agents, II. By C. William Siemens, D.C.L., LL.D., F.R.S.	352
Photophone Experiments (*With Illustrations*)	354
The Coffee-Leaf Disease	354
University and Educational Intelligence	354
Societies and Academies	355

DIARY OF SOCIETIES.

LONDON

THURSDAY, FEBRUARY 10.

ROYAL SOCIETY, at 4.30.—On the Influence of Molecular Grouping in Bodies on their Absorption in the Infra-red Region of the Spectrum: Capt. Abney, F.R.S.—Experiments undertaken during the Summer 1880, at Yvoire (1230 feet), at Courmayeur (3495 feet), and on the Col du Géant (11,030 feet), on the Influence of Altitude on Respiration: Dr. Marcet, F.R.S.—On a New Seismograph: Prof. A. J. Ewing.

MATHEMATICAL SOCIETY, at 8.—Some Theorems of Kinematics on a Sphere: E. B Elliott.—On some Integrals expressible in Terms of the First Complete Elliptic Integral and of Gamma Functions: J. W. L. Glaisher, F.R.S.—On Mr. McColl's Calculus of Equivalent Statements: Herr Schlötel (Strasburg).—An Application of Conjugate Functions: E. J. Routh, F.R.S.—Supplement on Binomial Bi-ordinates: Sir J. Cockle, F.R.S.—Note on Abel's Theorem: T. Craig.

ROYAL INSTITUTION, at 3.—The Troubadours: F. Hueffer.

LONDON INSTITUTION, at 7.—The Castes and Trades of India: Prof. Monier Williams.

SOCIETY OF TELEGRAPH ENGINEERS, at 8.—Earth Currents—Electric Tides: A. J. S. Adams.

FRIDAY, FEBRUARY 11.

ROYAL COLLEGE OF SURGEONS, at 4.—The Skeleton in the Sauropsida: Prof. Parker.

ROYAL ASTRONOMICAL SOCIETY, at 3.—Anniversary.

ROYAL INSTITUTION, at 9.—Distances of the Stars: Prof. R. S. Ball.

QUEKETT MICROSCOPICAL CLUB, at 8.

SOCIETY OF ARTS, at 8.—The Gold-Fields of India: Hyde Clarke.

SATURDAY, FEBRUARY 12.

ROYAL INSTITUTION, at 3.—The Amazons: Prof. Colvin.

PHYSICAL SOCIETY, at 3.—Annual General Meeting.—Special General Meeting.—On a Hydrostatic Illustration of Electrical Phenomena, and other Lecture Experiments: Dr. O. J. Lodge.

SUNDAY, FEBRUARY 13.

SUNDAY LECTURE SOCIETY, at 4.—Use and Abuse of Charity Property: C. S. Kenny.

MONDAY, FEBRUARY 14.

ROYAL COLLEGE OF SURGEONS, at 4.—The Skeleton in the Sauropsida: Prof Parker.

ROYAL GEOGRAPHICAL SOCIETY, at 8.30.—Geographical and Physical Aspects of Sarawak and North Borneo: William M. Crocker.

LONDON INSTITUTION, at 5.—Fruits and Seeds: Sir John Lubbock.

ROYAL INSTITUTION, at 3.—The Troubadours: F. Hueffer.

SOCIETY OF ARTS, at 8.—Watchmaking: Edward Rigg.

ARISTOTELIAN SOCIETY, at 8.—Berkeley: W. C. Barlow.

TUESDAY, FEBRUARY 15.

ZOOLOGICAL SOCIETY, at 8.30.—On Additions to the Society's Menagerie during the Month of January, 1881: The Secretary.—On the Coleopterous Insects belonging to the Family *Hispidæ*, collected by Mr. Buckley in Ecuador: C. O. Waterhouse.—Additions to the Rhyncotal Fauna of the Ethiopian Region: W. L. Distant.—On a Collection of Shells from Lakes Tanganyika and Nyassa and other Localities in East Africa: Edgar A. Smith.

ROYAL INSTITUTION, at 3.—The Blood: Prof. Schäfer.

WEDNESDAY, FEBRUARY 16.

ROYAL COLLEGE OF SURGEONS, at 4.—The Skeleton in the Sauropsida: Prof. Parker.

SOCIETY OF ARTS, at 8.—Participation of Labour in the Profits of Enterprise: Sedley Taylor.

METEOROLOGICAL SOCIETY, at 7.—Relative Humidity: Charles Greaves, F.G.S.—The Frost of January 1881 over the British Isles: William Marriott.

THURSDAY, FEBRUARY 17.

ROYAL SOCIETY, at 4.30.

LINNEAN SOCIETY, at 8.—British Fishes: Dr. Francis Day.—On Right and Left-Hand Contortion of the Corolla: C. B. Clarke.—On a New Form of Sponge: Prof. P. M. Duncan.—On the Reparative Processes which occur in Vegetable Tissues: Samuel J. Shattock.

CHEMICAL SOCIETY, at 8.—On a New Apparatus for showing the Dissociation of Ammonium Salts: D. Tommasi.—On the Estimation of Organic Carbon and Nitrogen in Water Analysis simultaneously with the Estimation of Nitric Acid: M. W. Williams.

LONDON INSTITUTION, at 7.—Violins: Rev. H. R. Haweis.

ROYAL INSTITUTION, at 3.—Drawing-Room Music: Prof. Pauer.

NUMISMATIC SOCIETY, at 7.

FRIDAY, FEBRUARY 18.

ROYAL COLLEGE OF SURGEONS, at 4.—The Skeleton in the Sauropsida: Prof. Parker.

GEOLOGICAL SOCIETY, at 1.—Anniversary.

ROYAL INSTITUTION, at 9. Fruits and Seeds: Sir John Lubbock.

SATURDAY, FEBRUARY 19.

ROYAL INSTITUTION, at 3.—Ancient Egypt: R. S. Poole.

LIGHTNING CONDUCTORS.

Experience, accumulated since the time of Benjamin Franklin, proves conclusively that a Conductor made of Copper of adequate size is the best of all appliances for the protection of every description of building from the destructive effects of lightning.

NEWALL & CO.'S

PATENT COPPER LIGHTNING CONDUCTOR,

As applied to all kinds of Buildings and Shipping in all parts of the world with unvarying success; is the most Trustworthy, most Effective, and also the Cheapest Conductor ever offered to the public.

It is simple in its application, no insulators being required, and it costs only one shilling per foot for the standard size, which ensures safety in any storm.

R. S. NEWALL & CO., 130, STRAND, W.C.
36, WATERLOO ROAD, LIVERPOOL.
68, ANDERSTON QUAY, GLASGOW.
MANUFACTORY—GATESHEAD-ON-TYNE.

Liberal Terms to Science Teachers and the Trade.

THOMAS CRAMPTON (formerly of 4, Little Britain, London, E.C.), ELECTRICIANS, OPTICIANS, and PHILOSOPHICAL INSTRUMENT MAKERS. Electric Bells, New Metallic Base Pattern, Constant Batteries, Indicators, Thief and Fire Alarms, and Automatic Switches, Induction and Medical Coils, or Specialities. Insulated Wires of every description. Microscopic and Optical Materials. Telescopes, Opera Glasses, Microscopes, Aneroid Barometers, and Lime-light Apparatus. Illustrated Catalogue Three Stamps.

THOMAS CRAMPTON & CO., 951, HIGH HOLBORN, LONDON, W.C
For Trade Terms send Card.

NOW READY.
SECOND EDITION,
GRIFFIN'S
CHEMICAL HANDICRAFT.
PRICE 4*s.* 7*d.* POST FREE.
A CATALOGUE OF CHEMICAL APPARATUS:
ILLUSTRATED, CLASSIFIED, DESCRIPTIVE.
Demy 8vo, 480 pp., Illustrated with 1,600 Woodcuts.
Most Complete and Cheapest List of Apparatus.
JOHN J. GRIFFIN AND SONS, 22, GARRICK STREET, LONDON, W.C.

ELECTRICAL AND SCIENTIFIC APPARATUS.

Wholesale Manufacturer of Metallic Base Electric Bells, Electric Reversing Indicators, and Constant Manganese Batteries, Telephone Switches and Transmitters, Induction Coils and Vacuum Tubes, Terminals, Carbons, Wire and all Materials. Instruments made, repaired, or altered on the premises.

Illustrated Bell List free. Complete Catalogue Two Stamps. Special Quotations to the Trade.

HENRY J. DALE, MANUFACTURING ELECTRICIAN and OPTICIAN,
4, Little Britain, London, E.C.

YORK'S
SERIES of SCIENTIFIC OPTICAL LANTERN SLIDES

Comprise over 2,000 of the following subjects:—Electricity, Magnetism, Sound, Telephone, Microphone, Electric Light, Light, Spectrum Analysis, Astronomy, Mines and Miners, Heat, Mechanics, Hydrostatics, Pneumatics, Human Physiology. Sample Slide and Catalogue sent on receipt of 2*s.*

F. YORK, OPTICAL LANTERN SLIDE MANUFACTURER,
87, Lancaster Road, Notting Hill, London, W.

GIMINGHAM'S SPRENGEL AIR-PUMP,

with Mul ple Fall Tubes and every recent improvement, including McLeod's Low Tension Gauge, Barometer Gauge, Radiometer, Terminals for testing non-conductivity of the Vacuum, &c., &c.

L. CASELLA having arranged with Mr. GIMINGHAM for the Sole Manufacture of these Pumps, as well as his Improved Forms of

CROOKES'S RADIANT MATTER TUBES,

Is prepared to supply them either in their simple form, or with any of their accessories.

Mr. GIMINGHAM has kindly engaged to examine each, in order that no Imperfect Instrument or Tubes may be sent away.

Also GIMINGHAM'S COMBINATION BLOWPIPE for Amateur and Professional Glass Work, the most simple and perfect in use.

L. CASELLA, 147, Holborn Bars, London, E.C.

CHEMICAL APPARATUS AND SCIENTIFIC INSTRUMENTS.
PURE CHEMICALS, &c.
IMPORTERS AND MANUFACTURERS:
AUG. BEL & CO.,
34, MAIDEN LANE, COVENT GARDEN, LONDON, W.C.

Laboratories fitted up. Sets of Apparatus as required by the Universities, Colleges, and Schools always ready and kept in stock. Professor Fesar's Patent Lactoscope for Testing Milk, as recommended by Dr. Voelcker. Description on Application. A Liberal Discount allowed to the Trade.

W. LADD & CO.,

SCIENTIFIC INSTRUMENT MANUFACTURERS,

(By Appointment to the Royal Institution of Great Britain),

11 AND 12, BEAK STREET, REGENT STREET, W.

IMPROVED HOLTZ ELECTRICAL MACHINES. GRAMME'S MAGNETO-ELECTRIC MACHINE for Laboratory use.

PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3*s.* per oz.

Physical Apparatus of every Description.

ILLUSTRATED CATALOGUE, SIXPENCE.

PATERSON'S NEW CATALOGUE OF PHYSICAL APPARATUS.

LANTERN SLIDES for SCIENTIFIC LECTURES. Season 1880-1. Post free 6 Stamps.
Complete Sets of Physical Apparatus for Science Primers and all the Physical Text-books in use in Schools and Colleges.
Siemens and Gramme Dynamo Machines and Lamps for hire.
Schools supplied with Apparatus as per Science and Art Departments' Requirements in the Sections of Light, Heat, Sound, and Electricity.
Electric Signals for Houses, Hotels, &c., Colliery Signals, Lightning Conductors. The Gower-Bell Loud-speaking Telephone.

EDWARD PATERSON, Electrical Engineer.

SHOW ROOMS AND STEAM WORKS:—76, LITTLE BRITAIN, E.C. (late 3, Bedford Court, W.C.).

MOLISON'S HARMONOGRAPH; executes the Harmonic Curves in the most perfect manner. 15*s.* and 20*s.*

Illustrated Catalogue of Electrical Apparatus, Part 1, *post free,* 6 *Stamps. Ditto, Electric Signals, Part* 2, 6 *Stamps.*

SUBSCRIPTIONS TO NATURE

Yearly . . . . . 28*s.*
Half-yearly . . . . . 14*s.* 6*d.*
Quarterly . . . . . 7*s.* 6*d.*

To the Colonies, United States, the Continent, and all places within the Postal Union :—

Yearly . . . . . 30*s.* 6*d.*
Half-yearly . . . . . 15*s.* 6*d.*
Quarterly . . . . . 8*s.*

Office: 29, Bedford Street, Strand.

EAGLE INSURANCE COMPANY,

79, PALL MALL.

FOR LIVES ONLY. ESTABLISHED 1807.

Accumulated Funds £3,043,542
Also a Subscribed Capital of more than £1,500,000

Reports, Prospectuses, and Forms may be had at the Office, or from any of the Company's Agents, post free.

GEORGE HUMPHREYS, Actuary and Secretary.

R. W. NEEVES,
PHILOSOPHICAL INSTRUMENT
AND
INTENSITY COIL MAKER.

PRICE LIST, FOUR STAMPS.

55, SIDMOUTH STREET, LONDON, W.C.

S. C. TISLEY & Co.,

OPTICIANS,

172, BROMPTON ROAD, S.W.

(Close to South Kensington Museum.)

THE PHONEIDOSCOPE

An Instrument for Observing the Colour-Figures of Liquid Films under the action of Sonorous Vibrations,

Being a visible demonstration of the Vibratory and Molecular Motion of a Telephone Plate.

The PHONEIDOSCOPE, with 3 Discs, Bottle of Solution, Descriptive Pamphlet, &c., in Cardboard Box, 10*s.* 6*d.*

MANUFACTURED AND SOLD WHOLESALE AND RETAIL BY

S. C. TISLEY & CO., 172, BROMPTON ROAD, LONDON, S.W.

TELEPHONIC ELECTRICITY. All Materials supplied for Experimental Purposes.

Price Lists of Electrical and Acoustic Apparatus, with Drawings and Description of the Harmonograph. Post Free, 2*d.*

HOLLOWAY'S PILLS

THIS MEDICINE

Is a Certain Cure for all Disorders of the LIVER, STOMACH AND BOWELS. A Great PURIFIER of the BLOOD; a Powerful Invigorator of the System, in cases of WEAKNESS AND DEBILITY, and is unequalled in Female Complaints

On the 1st of every Month, price Sixpence.

THE ENTOMOLOGIST:

AN ILLUSTRATED JOURNAL OF BRITISH ENTOMOLOGY.

Edited by JOHN T. CARRINGTON,
With the Assistance of
FREDERICK BOND, F.Z.S. | JOHN A. POWER, M.D.
EDWARD A. FITCH, F.L.S. | J. JENNER WEIR, F.L.S.
F. BUCHANAN WHITE, M.D.

Contains Articles by well-known Entomologists on all branches of the Science; on Insects injurious or beneficial to Farm or Garden; Notes on Habits, Life-Histories; occurrence of Rarities, &c.; there are monthly lists of Duplicates and Desiderata.

Numerous WOODCUT ILLUSTRATIONS, to the printing of which especial attention is given, and occasional LITHOGRAPHED and CHROMO-LITHOGRAPHED PLATES.

SIMPKIN, MARSHALL, & CO., Stationers' Hall Court.

DRAPER'S INK (DICHROIC).
THE NEW BLACK INK

DIFFERING FROM ANYTHING ELSE EVER PRODUCED.

Writing becomes a pleasure when this Ink is used. It has been adopted by the principal Banks, Public Offices, and Railway Companies throughout Ireland.

It writes almost instantly Full Black. | Flows easily from the Pen.
Does not corrode Steel Pens. | Blotting-paper may be applied at the
Is cleanly to use, and not liable to Blot. | moment of writing.

Can be obtained in London, through Messrs. BARCLAY & SONS, Farringdon Street; W. EDWARDS, Old Change; F. NEWBERY & SONS, Newgate Street; WM. MATHER, London and Manchester; J. AUSTIN & Co., Duke Street, Liverpool; and STACY & COOK, Paternoster Row; and to be had of all Stationers.

BEWLEY & DRAPER (Limited), Dublin.

NOTICE OF REMOVAL.

JAMES HOW & CO.,

SCIENTIFIC INSTRUMENT MAKERS,

73, FARRINGDON ST., LONDON

(LATE OF 5, ST. BRIDE ST., AND 2, FOSTER LANE)

HOW'S STUDENT'S MICROSCOPE. HOW'S MICROSCOPE LAMP.

Rock Sections and other Objects for the Microscope.

£5 5*s.* ASTRONOMICAL TELESCOPE.

CRAMPTON & CO.'S IMPROVED TELE-

SCOPE is of the highest workmanship and finish, combined with great power and clearness of definition; is entirely constructed of polished brass, with 3-inch Achromatic Object Lens, Altitude and Azimuth Movements, Rackwork, and Fine Adjustment, &c., &c.

THOMAS CRAMPTON & CO., 251, HIGH HOLBORN, LONDON, W.C.

J. ORME & CO.

(Late M. JACKSON & CO.)

MANUFACTURERS AND IMPORTERS OF

SCIENTIFIC APPARATUS
AND
CHEMICALS.

SOLE AGENTS FOR HICKLEY'S PATENT TELEPHONES,

Price 50*s.* per Pair, Cash with Order.

Price Lists sent on receipt of Three Stamps for Postage.

For Trade Terms inclose Business Card.

65, BARBICAN, LONDON, E.C.

SCIENTIFIC WORKS

PUBLISHED BY

Messrs. LONGMANS & CO.

DICTIONARIES AND ENCYCLOPÆDIAS.

DICTIONARY OF CHEMISTRY AND THE ALLIED BRANCHES OF OTHER SCIENCES. By HENRY WATTS, F.R.S., Editor of the Journal of the Chemical Society, assisted by eminent Scientific and Practical Chemists. 7 vols. 8vo. £10 16*s.* 6*d.*

THIRD SUPPLEMENTARY VOLUME, completing the Record of Chemical Discovery to the year 1877. In Two Parts. PART I. 8vo. Price 36*s.* PART II. Completion in the Press.

GWILT'S ENCYCLOPÆDIA OF ARCHITECTURE, Latest Edition, with Alterations and considerable Additions. By WYATT PAPWORTH. Additionally illustrated with nearly 400 Wood Engravings by O. JEWITT, and upwards of 100 other New Woodcuts. 8vo. 52*s.* 6*d.*

URE'S DICTIONARY OF ARTS, MANUFACTURES, AND MINES; Containing a clear Exposition of their Principles and Practice. The Seventh Edition, completely revised and greatly enlarged by ROBERT HUNT, F.R.S., Keeper of Mining Records, assisted by F. W. RUDLER, F.G.S., and by numerous Contributors. With above 2604 Woodcuts. Four vols. Medium 8vo. Price £7 7*s.*

TEXT-BOOKS OF SCIENCE, MECHANICAL AND PHYSICAL,

FOR THE USE OF ARTISANS AND OF STUDENTS IN PUBLIC AND SCIENCE SCHOOLS.

Edited by C. W. MERRIFIELD, F.R.S.

ABNEY'S PHOTOGRAPHY. 3*s.* 6*d.*

ANDERSON'S (Sir J.) STRENGTH of MATERIALS. 3*s.* 6*d.*

ARMSTRONG'S ORGANIC CHEMISTRY. 3*s.* 6*d.*

BALL'S ASTRONOMY. 6*s.*

BARRY'S RAILWAY APPLIANCES. 3*s.* 6*d.*

BLOXAM'S METALS. 3*s.* 6*d.*

GOODEVE'S MECHANICS. 3*s.* 6*d.*

GORE'S ELECTRO-METALLURGY. 6*s.*

GRIFFIN'S ALGEBRA and TRIGONOMETRY. 3*s.* 6*d.* NOTES. 3*s.* 6*d.*

JENKIN'S ELECTRICITY and MAGNETISM. 3*s.* 6*d.*

MAXWELL'S THEORY of HEAT. 3*s.* 6*d.*

MERRIFIELD'S TECHNICAL ARITHMETIC. 3*s.* 6*d.* KEY. 3*s.* 6*d.*

MILLER'S INORGANIC CHEMISTRY. 3*s.* 6*d.*

PREECE and SIVEWRIGHT'S TELEGRAPHY. 3*s.* 6*d.*

RUTLEY'S STUDY of ROCKS, or TEXT-BOOK OF PETROLOGY. 4*s.* 6*d.*

SHELLEY'S WORKSHOP APPLIANCES. 3*s.* 6*d.*

THOMÉ'S STRUCTURAL and PHYSIOLOGICAL BOTANY Price 6*s.*

THORPE'S QUANTITATIVE ANALYSIS. 4*s.* 6*d.*.

THORPE and MUIR'S QUALITATIVE ANALYSIS. 3*s.* 6*d.*

TILDEN'S CHEMICAL PHILOSOPHY. 3*s.* 6*d.*

UNWIN'S MACHINE DESIGN. 3*s.* 6*d.*

WATSON'S PLANE and SOLID GEOMETRY. 3*s.* 6*d.*

MILLER'S ELEMENTS of CHEMISTRY, Theoretical and Practical. PART I. *Chemical Physics.* Sixth Edition, revised, with Additions, by H. MACLEOD, F.C.S. With 274 Woodcuts. 8vo. 16*s.*

MILLER'S ELEMENTS of CHEMISTRY. PART II. *Inorganic Chemistry.* Sixth Edition, revised throughout, with Additions by C. E. GROVES. With 376 Woodcuts. 8vo. 24*s.*

MILLER'S ELEMENTS of CHEMISTRY. PART III. Fifth Edition, revised, and for the most part rewritten, by H. E. ARMSTRONG, F.R.S., and C. E. GROVES, F.C.S. The Chemistry of Carbon Compounds, or Organic Chemistry, in Two Sections. SECTION I. *Hydrocarbons, Alcohols, Ethers, Aldehides,* and *Paraffinoid Acids;* with 20 Woodcuts. 8vo. 31*s.* 6*d.* SECTION II. completion, is in the press.

The ELEMENTS of MECHANISM. By T. M. GOODEVE, M.A., Barrister-at-Law, Lecturer on Applied Mechanics at the Royal School of Mines. New Edition, rewritten and enlarged: with 342 Woodcuts. Crown 8vo. 6*s.*

EXPERIMENTAL CHEMISTRY for Junior Students. By J. EMERSON REYNOLDS, M.D., F.R.S., Professor of Chemistry, University of Dublin. PART I. *Introductory.* Fcap. 8vo. 1*s.* 6*d.*

DESCRIPTIVE and ANALYTICAL BOTANY. Translated from the French Work of DE CAISNE and LE MAOUT by Mrs. HOOKER; edited and arranged by J. D. HOOKER, M.D. With 5500 Woodcuts. Imperial 8vo. Price 31*s.* 6*d.*

GANOT'S NATURAL PHILOSOPHY, for GENERAL READERS and YOUNG PERSONS: a Course of Physics divested of Mathematical Formulæ and expressed in the language of daily life. Translated by E. ATKINSON, F.C.S. Fourth Edition. Plates and Woodcuts. Crown 8vo, 7*s.* 6*d.*

GANOT'S ELEMENTARY TREATISE on PHYSICS, Experimental and Applied. For the use of Colleges and Schools. Translated by E. ATKINSON, F.C.S. Ninth Edition. Plates and Woodcuts. Large crown, 8vo, 15*s.*

HEAT a MODE OF MOTION. By JOHN TYNDALL, LL.D. D.C.L. F.R.S. Sixth Edition (Thirteenth Thousand), thoroughly revised and enlarged; with Frontispiece and 123 Woodcuts. Crown 8vo. 12*s.*

FRAGMENTS of SCIENCE: a Series of detached Essays, Addresses, and Reviews. By JOHN TYNDALL, LL.D., D.C.L., F.R.S. Sixth Edition, revised and augmented. 2 vols., crown 8vo, 16*s.*

A HANDBOOK of PRACTICAL TELEGRAPHY. By R. S. CULLEY, Member Inst. C.E., Engineer-in-chief of Telegraphs to the Post Office. Seventh Edition, revised and enlarged; with 132 Woodcuts, and 18 Lithographic Plates of Apparatus. 8vo, 16*s.*

On ARTIFICIAL MANURES, their Chemical Selection and Scientific Applications to Agriculture; a Series of Lectures given at the Experimental Farm, Vincennes. By GEORGES VILLE. Translated and edited by W. CROOKES, F.R.S., V.P.C.S. With 31 Illustrations. 8vo, 21*s.*

LONDON: LONGMANS, GREEN, & CO.

NEW HIGH-CLASS JOURNAL.

LAND

A Weekly Journal for all interested in LANDED and HOUSE PROPERTY.

WITH "INDEX TO THE ESTATE EXCHANGE REGISTERS."

EVERY SATURDAY, PRICE SIXPENCE.

NUMBER I., READY FEBRUARY 12.

Extract from Prospectus.

The Journal, in short, will do for the Land Market what financial organs do for the Money Market—scanning, discussing, and forecasting every circumstance or contingency likely to affect the great network of interests connected with Real Estate, so that persons of all classes desiring to realise or invest may have full information as to the state of the Market, and timely notice of every circumstance, social, financial, or political, which may influence their decisions.

Owners, Occupiers, Buyers and Sellers of land and houses, Solicitors, Surveyors, Land Agents, and Auctioneers, will each and all find in LAND not only indispensable and accurate records of past, but also suggestive and trustworthy guidance for future transactions.

TERMS OF SUBSCRIPTION: One Year, 26s. (*or by post*, **28s.**); **Half-Year, 13s.** (*or by post*, **14s.**); **Quarter, 6s. 6d.** (*or by post* **7s.**).

PRINTED AND PUBLISHED FOR THE PROPRIETORS BY

Cassell, Petter, Galpin & Co., La Belle Sauvage Yard, Ludgate Hill, E.C.

*** *All communications respecting Advertisements in LAND should be addressed to the Manager, Advertisement Department, La Belle Sauvage Yard.*

On MARCH 25th will be published,

UNIFORM WITH "PICTURESQUE EUROPE."

PART 1, price **2s. 6d.,** of

PICTURESQUE AMERICA.

A PICTORIAL DELINEATION OF

THE MOUNTAINS, RIVERS, LAKES, FORESTS, WATERFALLS, SHORES, CAÑONS, VALLEYS, CITIES, AND OTHER PICTURESQUE FEATURES OF THE NORTH AMERICAN CONTINENT.

WITH 48 EXQUISITELY ENGRAVED STEEL PLATES,

AND

SEVERAL HUNDRED ENGRAVINGS ON WOOD,

From ORIGINAL DRAWINGS specially made for the Work.

Prospectuses can be obtained at all Booksellers', or will be forwarded post free on application to the Publishers, CASSELL, PETTER, GALPIN & CO., Ludgate Hill, London.

Price **12s. 6d.** each.

FAMILIAR WILD FLOWERS.

FIRST AND SECOND SERIES. By F. E. HULME, F.L.S., F.S.A. Each Series is complete in One Volume, and contains **Forty full-page Coloured Plates,** with Descriptive Text.

Cassell, Petter, Galpin & Co., London.

Price **12s. 6d.**

FAMILIAR GARDEN FLOWERS.

FIRST SERIES. Complete in One Volume. By SHIRLEY HIBBERD. With **Forty full-page Coloured Plates** from Original Paintings by F. E. HULME, F.L.S., F.S.A.

Cassell, Petter, Galpin & Co., London.

384 pages, extra crown 4to, price **9s.**

SCIENCE FOR ALL. Yearly Volume for 1880. Edited by Dr. ROBERT BROWN, M.A., F.L.S. With about **350 Illustrations and Diagrams.**

The *Athenæum* says—"Whatever branch of science a man may happen to be studying, he is sure to find something to his taste in turning over the pages of this work."

Cassell, Petter, Galpin & Co., London.

EVERY FRIDAY, PRICE **4d.**

The Live Stock Journal & Fancier's Gazette

A CHRONICLE FOR COUNTRY GENTLEMEN, BREEDERS, AND EXHIBITORS.

The Journal, which is the official organ of the ROYAL AGRICULTURAL, SHORTHORN, SMITHFIELD CLUB, BRITISH DAIRY FARMERS', ENGLISH CART HORSE, CLYDESDALE, and other ASSOCIATIONS, now stands without a rival as a Chronicle for Country Gentlemen, Breeders, and Exhibitors.

Terms of Subscription by Post—Three Months, **4s. 11d.**; *Six Months,* **9s. 9d.**; *Twelve Months,* **19s. 6d.**

Publishing Office and Office for Advertisements: LA BELLE SAUVAGE YARD, LUDGATE HILL, E.C.

Printed by R. CLAY, SONS, AND TAYLOR, at 7 and 8, Bread Street Hill, Queen Victoria Street, in the City of London, and published by MACMILLAN AND CO., at the Office, 29 and 30, Bedford Street, Covent Garden.—THURSDAY, February 10, 1881.

NATURE

A WEEKLY ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
Of Nature trusts the mind which builds for aye."—WORDSWORTH

No. 590, VOL. 23] THURSDAY, FEBRUARY 17, 1881 [PRICE SIXPENCE

Registered as a Newspaper at the General Post Office.]

[All Rights are Reserved.

UNIVERSITY OF LONDON MATRICULATION, JUNE, 1881.

Special Classes for this Examination will be formed at St. Thomas's Hospital Medical School, Albert Embankment, to commence on March 1st. The Special Classes for the Preliminary Scientific and 1st M.B. Examinations have now commenced. Full particulars can be obtained from the Secretary, Dr. GILLESPIE.

ASSOCIATION for the IMPROVEMENT OF GEOMETRICAL TEACHING.

SEVENTH GENERAL REPORT, containing the Address of the President, H. B. HAYWARD, Esq., F.R.S., on "The Future of the Association." Price Sixpence. Complete Sets of the Reports of the Association, price 3*s.* 6*d.*

Apply by letter, inclosing Stamps or P.O.O., to Mr. JOSIAH ALLEN, Printer, 74, Suffolk Street, Birmingham.

LIVERPOOL COLLEGE of CHEMISTRY, LIVERPOOL.

Founder ... ... Dr. SHERIDAN MUSPRATT.
Principals ... ... Drs. TATE AND GRANVILLE H. SHARPE.

Special advantages offered to Students.
Assays, Analyses, and Chemical Investigations conducted.
For Prospectuses, apply to the Principals.

INSTRUCTION IN MATHEMATICS.—Youths or Adults attended at their Residence, on Reasonable Terms, by a M.A. of Cambridge. Unquestionable references if required.—Address, by letter, O. P., Post Office. Turnham Green.

TRAVELLERS' SCIENTIFIC REQUISITES.

ANEROID BAROMETER with ALTITUDE SCALE, THERMOMETER and COMPASS in Flat Pocket Case, various Forms,
£7 7s. and **£8 8s.**
Price Lists of Instruments free by post.
NEGRETTI & ZAMBRA,
Opticians and Scientific Instrument Makers
To HER MAJESTY THE QUEEN,
HOLBORN VIADUCT,
45, CORNHILL, & 122 REGENT STREET, LONDON.

BROWNING'S SPECTROSCOPES.

The New Spectroscope, with Micrometer, may be used for showing any of the leading experiments in Spectrum Analysis; the Fraunhofer lines; the Lines in the Spectra of the Metals, and the Alkaline Earths and Alkalies; the Spectra of Gases; and the Rain-bands. On a Telescope it will show the lines of the Solar Prominences. It can also be used as a Micro-Spectroscope, and the position of the Bands in any Spectrum can be seen with the Micrometer. Price, complete in Case, £3 10*s.*

Illustrated Catalogue of Spectroscopes, Six Stamps.

HOW TO WORK WITH THE SPECTROSCOPE. By JOHN BROWNING. Bound in cloth, 1*s.* 6*d.* post free.

JOHN BROWNING,
63, STRAND, LONDON, W.C.

Second-Hand Astronomical Telescopes,
Microscopes, & other Scientific Instruments.

C. BAKER,
244 & 245, HIGH HOLBORN,
Begs to call the attention of the Scientific to his Large and Extensive Stock of
ASTRONOMICAL TELESCOPES,
MICROSCOPES,
TRANSIT INSTRUMENTS,
REGULATORS, SPECTROSCOPES,
METEOROLOGICAL AND ELECTRIC APPARATUS,
By ROSS, DALLMEYER, COOKE, SMITH & BECK, BROWNING, DENT, TROUGHTON,
And other Celebrated Makers. All at very Low Prices.
CATALOGUE FREE BY POST.
INSTRUMENTS TAKEN IN EXCHANGE
ESTABLISHED 1765.

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 48N, Tollington Road, Holloway, London, N.

FOR SALE.—AN ASTRONOMICAL

TELESCOPE by Negretti and Zambra, on Brass Folding Stand, with 3½-inch Object-Glass, 1 Terrestrial and 2 Astronomical Eyepieces of Powers 50, 80, and 100. Mahogany Case. QUITE NEW; has never been used.—Address "ASTRA," 56, Chelsham Road, Clapham, S.W.

TO BE SOLD.—A Large First-Class

MICROSCOPE, with Apparatus, in Case complete, at Half its Cost Price.—Apply, Mr. E. WERDEN, 22, St. James's Walk, Clerkenwell, E.C.

WANTED (Second-Hand), a 4½ or 5-inch

ASTRONOMICAL TELESCOPE by Cooke, Wray, Grubb, Merz, Steinheil, or A. Clark.—Apply to J. N. H., Saling Grove, Braintree.

ROYAL POLYTECHNIC.—CLASSES for

the Preparation of Students for University Examinations, under the direction of EDWARD B. AVELING, D.Sc., F.L.S. London University Matriculation, 1st and 2nd B.Sc., Preliminary Scientific M.B., Botany, Physiology, Chemistry. All the work practical.

GEOLOGY.—In the Preface to the STU-

DENT'S ELEMENTS of GEOLOGY, by Lyell, 1874, he says: "As it is impossible to enable the reader to recognise rocks and minerals at sight by aid of verbal descriptions or figures, he will do well to obtain a well-arranged collection of specimens, such as may be procured from Mr. TENNANT (149, Strand), Teacher of Mineralogy at King's College, London." These Collections are supplied on the following terms, in plain Mahogany Cabinets:—

100 Specimens, in Cabinet, with 3 Trays	£2	2	0
200 Specimens, in Cabinet, with 5 Trays	5	5	0
300 Specimens, in Cabinet, with 9 Drawers	10	10	0
400 Specimens, in Cabinet, with 13 Drawers	21	0	0

More extensive Collections at 50 to 5,000 Guineas each.

GEOLOGY AND MINERALOGY.

Special Collections for Teachers and Students, used with success by all Lecturers and Teachers of Geology in Great Britain. Obtained Gold and Bronze Medals at Sydney Exhibition, 1879, also in London, 1862, and Paris, 1867.

200 Specimens in Cabinet	£2	2	0
100 ditto ditto	1	1	0
50 ditto ditto	0	10	6

New Lists of Collections, Apparatus, &c., now ready, and free on application to

JAMES R. GREGORY'S
Geological Museum and Repository,
88, CHARLOTTE STREET, FITZROY SQUARE.

Chaque Samedi 16 pages grand in-8°, 2 colonnes

REVUE HEBDOMADAIRE

Scientifique, illustrée, spéciale, seul journal tenant les lecteurs au courant de tous les détails de l'Exposition universelle d'électricité, organe indépendant des exposants

RÉDACTEUR EN CHEF : W. de FONVIELLE
E. de CLISSON : DIRECTEUR

***Un numéro*, 40 *centimes*. — *L'année*, 18 *francs*.**
***Union postale* 20 *francs*.**

PARIS, 16, rue du Croissant, PARIS
Envoi de numéros spécimens gratis sur demande.

In unserem Verlage erscheint:

DER NATURFORSCHER.

Wochenblatt zur Verbreitung der Fortschritte in den Naturwissenschaften.
Herausgegeben von Dr. WILHELM SKLAREK.
Wochentlich 1—1½ Bgn. in 4°.
Preis vierteljährlich 4 Mk.

Die nunmehr ihren XIV. Jahrgang beginnende Zeitschrift hat bei Allen, welche sich mit Naturwissenschaften beschäftigen, grossen Beifall gefunden.
Probenummern sind durch jede Buchhandlung zu erhalten.
Berlin, S.-W., 77, Charlottenstr.

FERD. DÜMMLER'S VERLAGSBUCHHANDLUN
(Harrwitz & Gossmann.)

LIVING SPECIMENS FOR THE MICROSCOPE.

THOMAS BOLTON, NATURALISTS' and MICROSCOPISTS'
STUDIO, 57, NEWHALL STREET, BIRMINGHAM.

T. B. has last week sent to his subscribers specimens of the Infusorian, *Opercularia nutans*, together with several species of Rotifers, Vorticella, and Diatoms. He has also sent out Stephanoceros, Melicerta, Limnias, Floscularia, Hydra, Argulus, Asellus, Gammarus, &c.
Weekly announcements will be made in this place of organisms T. B. is supplying.

Specimen Tube, One Shilling, post-free.
Twenty-six Tubes in course of Six Months for Subscription of £1 1s.
Price List of Specimens on application, with stamped addressed envelope.
Portfolio of Drawings, No. 4, One Shilling.

MINERALOGY AND GEOLOGY.

Mr. HENSON having purchased an OLD COLLECTION formed in DERBYSHIRE, containing FINE SPECIMENS of ANGLESITE, CERUSSITE, FLUOR SPAR and CALC SPAR, DIOPTASE, EUCHROITE, and other RARE MINERALS, begs to offer the same singly or otherwise.
COLLECTIONS FOR STUDENTS, from £2 2s. COLLECTIONS FOR BEGINNERS, from 4s. BLOWPIPE CASES AND APPARATUS.
PRIVATE LESSONS AND EVENING CLASSES.
Catalogues free.

SAMUEL HENSON,
277 (*Late* 113*a*), STRAND, LONDON, W.C.

EVERY BOY A GEOLOGIST.

Now ready, and highly recommended, complete, price 7s. 6d.
This admirable little Work and most extraordinary Cabinet of wonderfully well-selected Natural Specimens, together with other Geological Preparations, and a powerful Lens, are calculated to start a boy thinking till he has mastered for himself no ordinary knowledge of the formation of the Earth's Crust.—THOMAS J. DOWNING, GEOLOGIST, &c., 38, Whiskin Street, London, E.C.—Catalogues free.

DIAMONDS IN MATRIX.

R. C. NOCKOLD, Diamond and Oriental Stone Cutter and Dealer, has for sale Specimens of the above; also Cut Precious Stones in all Colours.
Precious Stones valued and bought.
12, FRITH STREET, SOHO, W.

LA SEMAINE FRANÇAISE: a Weekly

Newspaper and Review in the French Language. Politics, Literature, Science, Art, Varieties, Notes. Price 3d., through booksellers, and at the railway bookstalls. Office, 37, Southampton Street, Strand, W.C.

LA SEMAINE FRANÇAISE: Journal Français pour l'Angleterre: Politique, Littérature, Sciences, Arts, Variétés, Nouvelles, et Notes. Un exemplaire par la poste, 3½d., en timbres poste Abonnement franco par la poste—un an, 15s. 2d.; six mois, 7s. 7d. Prix 3d., chez tous les libraires et aux gares des chemins de fer. On s'abonne aux bureaux, 37, Southampton Street, Strand, Londres, W.C.

LA SEMAINE FRANÇAISE.—"'La Semaine Française' has been brought out in London for the benefit of those English readers who may wish to study contemporary French from all points of view, instead of confining their reading to one particular Gallic print. It certainly merits success."—*Graphic*.

LA SEMAINE FRANÇAISE.—"The numbers before us are full of good things. . . . . It will be far better for most than any one of the best papers published in Paris itself. We are much pleased with the character of it, and believe it will be highly valued in all these many households where French is cultivated. The printing is very well done."—*Queen*.

TERMS OF SUBSCRIPTION:—	s.	d.
Three months	3	10
Six ,, ...	7	7
Twelve ,, ...	15	2

P.O.O. payable to T. SPANSWICK, at King Street, Covent Garden, W.C.
Publishing Office, 37, Southampton Street, Strand, W.C.

On the 1st of every Month, price One Shilling.

THE ZOOLOGIST:

A MONTHLY MAGAZINE OF NATURAL HISTORY.

Third Series. Edited by J. E. HARTING, F.L.S., F.Z.S., Member of the British Ornithologists' Union; contains—

Original articles by well-known naturalists in every branch of zoology: habits of animals; arrival and departure of migratory birds; occurrence of rare birds; distribution and migration of British fresh-water fish; new or rare marine fish; local aquaria; British reptiles; British land and fresh-water mollusca, with remarks on the haunts and habits of the species; and other matters of general interest to those who delight in natural history. Reports of the Linnean, Zoological, and Entomological Societies. Reviews of natural history books. Occasional translations from foreign zoological journals of important and interesting articles in various branches of zoology. There are occasional woodcuts.

JOHN VAN VOORST, 1, Paternoster Row.

Messrs. MACMILLAN & CO.'S PUBLICATIONS.

THE STEAM ENGINE AND ITS INVENTORS.

A HISTORICAL SKETCH.

By ROBERT L. GALLOWAY,

Mining Engineer.

With numerous Illustrations. Crown 8vo, 10*s.* 6*d.*

Eighteenth Annual Publication, Revised after Official Returns.

THE STATESMAN'S YEAR-BOOK FOR 1881.

A Statistical and Historical Annual of the States of the Civilised World.

By FREDK. MARTIN.

Crown 8vo, 10*s.* 6*d.*

"The 'Statesman's Year Book' is a handbook for the politician as well as the merchant, and as a statistical and historical annual of the States of the civilised and mercantile world, stands without a rival."—*Times.*

Kamilaroi and Kurnai. Group-Marriage and Relationship, and Marriage by Elopement. Drawn chiefly from the usage of the Australian Aborigines: also the Kurnai tribe—their Customs in Peace and War. By LORIMER FISON, M.A., and A. W. HOWITT, F.G.S. With an Introduction by LEWIS H. MORGAN, LL.D., Author of "System of Consanguinity," "Ancient Society," &c. Demy 8vo. 15*s.*

NEW NOVEL BY HENRY JAMES, JUN.

Washington Square: the Pension Beaurepas: a Bundle of Letters. 2 vols. Crown 8vo. 21*s.*

"The very clever sketches . . . . are, on the whole, even more marvellously clever. . . . . There is no doubt that it is genius of the most marked order—genius for painting character."—*Spectator.*

"Mr. James has contrived, as he usually does, to throw a new charm over the old story. . . . Mr. James's style is as pleasant as ever."—*Athenæum.*

Disturbed Ireland, being the Letters Written during the Winter of 1880-81. By BERNARD H. BECKER, Special Commissioner of the *Daily News.* With Route Maps. Crown 8vo. 6*s.*

"Will be found one of the most trustworthy pictures of the sister island as it is . . . It has, especially at this moment, high political value."—*Examiner.*

Loukis Laras. Reminiscences of a Chiote Merchant during the Greek War of Independence. Translated from the Greek of D. BIKÉLAS by J. GENNADIUS, late Chargé d'Affaires at the Greek Legation in London. With Introduction on the Rise and Development of Greek Literature. Crown 8vo. 7*s.* 6*d.*

The Year's Art: A Concise Epitome of all matters relating to the Arts of PAINTING, SCULPTURE, and ARCHITECTURE, which have occurred during the Year, together with information respecting the events of the Year 1881. Compiled by MARCUS B. HUISH. Crown 8vo. 2*s.* 6*d.*

GOLDEN TREASURY SERIES.—NEW VOLUME.

Essays of Joseph Addison. Chosen and Edited by John Richard Green, M.A., LL.D. 18mo. 4*s.* 6*d.*

"This is a most welcome addition to a most excellent series."—*Examiner.*

English Poets: Selections, with Critical Introductions by various Writers, and a General Introduction by MATTHEW ARNOLD. Edited by T. H. WARD, M.A. 4 vols., crown 8vo, each 7*s.* 6*d.*

Vol. I. CHAUCER to DONNE.
Vol II. BEN JONSON to DRYDEN.
Vol. III. ADDISON to BLAKE.
Vol. IV. WORDSWORTH to SYDNEY DOBELL.

"An excellent design admirably executed."—*Pall Mall Gazette.*

The Abbott's Farm; or, Practice with Science. By Henry Tanner, M.R.A.C., F.C.S., Professor of the Principles of Agriculture in the Royal Agricultural College, Author of "First Principles of Agriculture." Extra fcap. 3*s.* 6*d.*

"Prof. Tanner's little book may be read with considerable profit."—*Saturday Review.*

A Short Manual of the History of India, with an Account of India as it Is: the Soil, Climate, and Productions—the People: their Races, Religions, Public Works, and Industries—the Civil Services and System of Administration. By ROPER LETHBRIDGE, M.A., C.I.E., Press Commissioner with the Government of India, late Scholar of Exeter College, &c. Crown 8vo, with Maps. 5*s.*

Physics of the Earth's Crust. By Rev. O. Fisher, M.A., F.G.S., Rector of Harlton, &c. 8vo. [*Shortly.*

MACMILLAN AND CO., LONDON.

In Medium 8vo, price 18s. Vol. I.

A TREATISE ON

COMPARATIVE EMBRYOLOGY.

By F. M. BALFOUR, M.A., F.R.S., Fellow and Lecturer of Trinity College, Cambridge. In Two Vols. Illustrated.

"It is scarcely possible to exaggerate the expressions of gratitude which are due from zoologists to Mr. Balfour for the execution of the great task which some three or four years ago he set himself. . . . Zoologists have to be thankful to him for the admirable style in which he has carried out his work."—*Nature*.

MACMILLAN AND CO., LONDON.

Just Published, demy 8vo, cloth, with Chart, price 15s.

ON SOME PROPERTIES OF THE EARTH.

By O. REICHENBACH.

London: WERTHEIMER, LEA, & CO., Circus Place, London Wall.

Sale by Auction

The Natural History, Ethnological, Geological, and other Collections of the late E. W. COOKE, Esq., R.A, F.R.S.

MR. J. C. STEVENS has been favoured with Instructions to Sell by Auction, at his Great Rooms, 38, King Street, Covent Garden, on FRIDAY, February 25th, at half-past 12 precisely, by order of the Executor, the Collections of Objects of Natural History, Ethnology, Archæology, Geology, &c.; also Loddige's Botanical Cabinet, a rare and valuable work. Also a fine Collection of Casts from Antique Gems and other Curiosities collected by the late E. W. COOKE, Esq., R.A., F.R.S.

On view after 2 o'clock the day prior and morning of Sale, and Catalogues had.

"The leading Farmers' paper."—CLARE SEWELL READ, ESQ., M.P.

THE CHAMBER OF AGRICULTURE JOURNAL AND FARMERS' CHRONICLE

(PRICE 3*d*. WEEKLY).

The representative organ of the Central and Provincial Chambers of Agriculture; *gives fuller reports of the discussions and proceedings* of this extensive organisation than any other agricultural paper. It devotes *special attention to the treatment of Agricultural Questions by Parliament*, besides containing ample Reports of the LATEST LONDON and COUNTRY CORN, CATTLE, HOP, PROVISION, and other Markets, with Original Articles on Practical Farming, the Dairy, Herd and Flock News, Horticulture, &c., &c. It is despatched every Monday evening in time for the country post.

Terms of Subscription, payable in advance, post free:—3 months, 3s. 9½*d*.; 6 months, 7s. 7*d*; 12 months, 15s. 2*d*.

Published by W. PICKERING, 21, Arundel Street, Strand, London, W.

NORTH BRITISH AGRICULTURIST

is the only Agricultural Journal in Scotland, and circulates extensively amongst Landed Proprietors, Factors, Farmers, Farm-bailiffs, and others interested in the management of landed property throughout Scotland and the Northern Counties of England.

The AGRICULTURIST has also a very considerable circulation on the Continent of Europe, America, Australia, and the Colonies.

The AGRICULTURIST is published every Wednesday afternoon in time for the evening mails, and contains Reports of all the principal British and Irish Markets of the week, besides Telegraphic Reports of those held on the day of publication.

The Veterinary Department is edited by one of the leading Veterinarians in the country, and is invaluable to the breeder and feeder as a guide to the rearing of animals, and their treatment when labouring under disease.

Full Reports are given of the Meetings of the Royal Agricultural Society of England, the Royal Agricultural Society of Ireland, the Highland and Agricultural Society of Scotland, the Scottish Chamber of Agriculture, and all the principal Agricultural Associations throughout Great Britain and Ireland.

For Advertisers addressing themselves to Farmers a better medium does not exist

Price 3*d*. By post 3½*d*. Annual Subscription, payable in advance, 14s.

Office—377, High Street, Edinburgh.

Post-Office Orders payable to Charles Anderson, Jun., Edinburgh.

ESTABLISHED 1843.

On the 1st of every Month, price Sixpence.

THE ENTOMOLOGIST:

AN ILLUSTRATED JOURNAL OF BRITISH ENTOMOLOGY.

Edited by JOHN T. CARRINGTON,

With the Assistance of

FREDERICK BOND, F.Z.S. | JOHN A. POWER, M.D.
EDWARD A. FITCH, F.L.S. | J. JENNER WEIR, F.L.S.
F. BUCHANAN WHITE, M.D.

Contains Articles by well-known Entomologists on all branches of the Science; on Insects injurious or beneficial to Farm or Garden; Notes on Habits, Life-Histories; occurrence of Rarities, &c.; there are monthly lists of Duplicates and Desiderata.

Numerous WOODCUT ILLUSTRATIONS, to the printing of which especial attention is given, and occasional LITHOGRAPHED and CHROMO-LITHOGRAPHED PLATES.

SIMPKIN, MARSHALL, & CO., Stationers' Hall Court.

Just Published, price 2s. 6*d*.

An ELEMENTARY COURSE of PRACTICAL PHYSICS.

By A. M. WORTHINGTON, M.A., F.R.A.S., Assistant Master at Clifton College.

RIVINGTONS, Waterloo Place, Pall Mall, London.

THE ENTOMOLOGIST'S MONTHLY MAGAZINE.

Price Sixpence, Monthly, 24 pages 8vo, with occasional Illustrations.

Conducted by C. G. BARRETT, J. W. DOUGLAS, R. MCLACHLAN, F.R.S., E. C. RYE, F.Z.S., E. SAUNDERS, F.L.S., and H. T. STAINTON, F.R.S.

This Magazine, commenced in 1864, contains standard articles and notes on all subjects connected with Entomology, and especially on the Insects of the British Isles.

Subscription—Six Shillings per Volume, post free. The volumes commence with the June number in each year.

Vols. I. to VI. (strongly bound in cloth) may be obtained by purchasers of the entire set to date, at the increased price of 10s. each; the succeeding vols. may be had separately or together, at 7s. each.

London: JOHN VAN VOORST, 1, Paternoster Row.

N.B.—Communications, &c., should be sent to the Editors at the above address.

THE BREWERS' GUARDIAN:

A Fortnightly Paper devoted to the Protection of Brewers' Interests, Licensing, Legal, and Parliamentary Matters.

REVIEW OF THE MALT AND HOP TRADES; AND WINE AND SPIRIT TRADE RECORD.

The Organ of the Country Brewers.

"The Brewers' Guardian" is published on the evenings of every alternate Tuesday, and is the only journal officially connected with brewing interests.

Subscription, 16s. 6*d*. per annum, post free, dating from any quarter-day. Single Copies 1s. each. Registered for transmission abroad.

Offices—5, Bond Court, Walbrook, London, E.C.

Price 6s., Part II., Vol. XV., January, 1881.

THE JOURNAL OF ANATOMY AND PHYSIOLOGY, NORMAL AND PATHOLOGICAL,

CONDUCTED BY

Profs. HUMPHRY, TURNER, M'KENDRICK, & Dr. CREIGHTON.

Contents.

1. Bones, Articulations, and Muscles of Rudimentary Hind-limb of Greenland Right-Whale. By J. Struthers, M.D. (Plates XIV.-XVII.)
2. Infective Form of Tuberculosis in Man identical with Bovine Tuberculosis. By C. Creighton, M.D.
3. Medullary Neuroma of Brain. By W. Osler, M.D. (Plate XVIII.)
4. Dissection of Genito-Urinary Organs in Case of Fissure of Abdominal Walls. By A. Doran, F.R.C.S. (Plate XIX.)
5. Description of a Polygraph (with Figure). By D. Newman, M.B.
6. Remarks on Mechanism of Secretion of Sweat. By C. Handfield Jones, M.B.
7. Anomalous Growth-Bearing Pilose Skin in Pharynx of a Young Woman. By P. S. Abraham, M.A. (With Figure.)
8. Histology of Granular Kidney (with Figure). By R. Saundby, M.D.
9. Two Cases of Cerebellar Disease. By T. Oliver, M.D.
10. Colouring Matter of Jelly Fishes. By Prof. M'Kendrick.
11. Nerves of the Hind-Limb of the Thylacine and Cuscus. By D. J. Cunningham, M.D.
12. Pulse Dicrotism. By Wm. Jas. Fleming, M.D.
13. Anatomical Notices.

MACMILLAN & CO., London and Cambridge.

POTTERY.

A SERIES OF URNS, &c.,

INCLUDING

BRITISH, ROMAN, SCANDINAVIAN, PERUVIAN.

To be Sold at Extremely Low Prices, the Owner being desirous of immediately parting with them.

BRYCE-WRIGHT,

90, GREAT RUSSELL STREET, LONDON, W.C.

THURSDAY, FEBRUARY 17, 1881

ISLAND LIFE

Island Life; or, The Phenomena and Causes of Insular Faunas and Floras, including a Revision and Attempted Solution of the Problem of Geological Climates. By Alfred Russel Wallace. (London: Macmillan and Co., 1880.)

I.

MR. WALLACE is to be congratulated on his success in that most difficult part of book-writing—the choice of a good descriptive, yet short and euphonious, title. "Island Life!" What do not the words suggest! How many old associations do they not recall! A vacant and unsuspicious reader may indeed be lured by them to open what he may expect will prove a good novel, perhaps a story of the "Robinson-Crusoe" type. His hopes will be quenched by the first chapter; but if he possesses any capacity for an interest in the flowers, insects, birds, and beasts of his home, it will almost certainly be quickened by a perusal of that chapter. Like a skilful composer Mr. Wallace strikes at once with a firm touch the key-note of his volume. In a few pages he puts before us the problem he seeks to solve, and does this in so graphic and masterly a way that most readers will not only comprehend what he aims at, but will be persuaded into the belief that as they are familiar with some parts of the subject they have a personal interest in seeing what the author can make of it.

Hardly any problem in modern science is at once so complex and so fascinating as the geographical distribution of plants and animals. Strange to say, this complexity and fascination have steadily increased with the growth of knowledge. A generation ago, the grouping of floras and faunas found a ready explanation in differences of climate and special creations. But no such easy solution of the difficulties now avails. Ever since the classic essay of Edward Forbes on the history of the British flora there has been a growing conviction that the present arrangement of the life of the globe is the outcome of previous geological and biological changes. The doctrine of evolution has given to this conviction the strength of demonstrated truth. But while the theoretical aspect of the question may be clear enough, we are beset on all sides by what seem utterly insuperable obstacles when we try to work out the application of this theory to the history of any given flora or fauna. This is true even in those areas of Europe and North America where the living plants and animals are most fully known, and where some approach to a complete unravelling of the geological record has been made. But over most of the rest of the globe our knowledge of botanical and zoological distribution, and still more of geological history, is of the scantiest and most fragmentary kind. A few broad facts in the history of the mammalian life of the northern hemisphere are well established. The pedigree of some modern forms, such as the horse, can be traced back into early Tertiary times; the former wide spread of other forms, the lion for instance, and their gradual restriction in area, have been satisfactorily made out. But the kind of evidence available in these cases fails us in dealing with others. It seems as if all that we may hope to achieve is to establish by a few examples, capable of clear proof, the general laws by which variation in form and in geographical distribution appears to have been effected among the animal and vegetable populations of the globe.

By no living naturalist could these problems be more fittingly and exhaustively discussed than by the author of "The Malay Archipelago." Years of research in the East, followed by years of research and reflection at home, have enabled him to explore every highway and a vast number of byways in the wide realm of inquiry in which he has been so active and untiring a worker. Thoroughly conversant with all that has been done by others, he brings to his task a wealth of information and a breadth of view that stamp his works with the authority of a master.

The present volume may be regarded as an expansion of a part of the author's "Geographical Distribution of Animals." Further study of the problem of distribution has enabled him to treat it with greater fulness. He has devoted especial attention to geological operations that have affected the successive races of plants and animals, and has connected these operations with biological changes more closely and clearly than has hitherto been done. Of his new volume the first half is mainly occupied with a discussion of this subject. He there seeks to establish a number of fundamental propositions or laws, the confirmation of which leads in his opinion to a simpler and fuller solution of the problem than has before been possible. Two of these doctrines deserve the careful consideration of geologists and naturalists. They are (1) the permanence of continental and oceanic areas; and (2) the frequency of changes of climate during geological time and the combined influence of cosmical and geographical causes in the production of these changes.

The abundance of marine organisms in the rock-masses which constitute the bulk of the continents naturally led to a belief in the mutability of the land. Not once only but many times in succession the sites of some of our loftiest mountains were under the sea. And if it was discovered that the position of the land had been so variable, and that the sea-floor had been so continually upraised, the inference was easily drawn that land and sea must have been continually changing places. Tacitly or explicitly it was assumed that just as there appeared to be no area, even in the heart of the continents, which had not been submerged beneath the waves, so there was probably no tract even of mid-ocean where a continent might not have bloomed. It is probably a safe assertion to say that this is still the belief of most geologists. It finds formal expression in their most authoritative text-books, and can be traced everywhere in its influence upon the discussion of questions of geological history. From geological treatises it has passed out into the current literature of the time, as one of the accepted conclusions of science. Our Poet Laureate, who has embodied in musical language not a little of the scientific speculation of his day, has given terse expression to this universal belief in the often-quoted lines:—

> "There rolls the deep where grew the tree.
> O earth, what changes hast thou seen!
> There, where the long street roars, hath been
> The stillness of the central sea."

R

Inevitable as was this belief in the early days of geology, and firmly as it still maintains its hold, it is unquestionably based upon a partial view and erroneous interpretation of the facts. This has for some years been recognised by a few writers, and will before long be generally acknowledged. Instead of shifting their places on the earth's surface, continents, so far as the evidence of their history can be gleaned, have been wonderfully persistent.

This conclusion is reached by many different paths of inquiry. Of these it may suffice to notice here only two. (1) The rocks of which the greater part of the dry land consists, are upraised marine sediments. But their materials were derived from the waste of neighbouring dry land. They everywhere contain indications of the proximity of that land, and even reveal terrestrial surfaces, such as rippled-marked and rain-pitted shores, in the very midst of marine formations. Nowhere do they present indications of really deep water. (2) An examination of the floor of the present ocean proves that the sediment now removed from the surface of the continent is deposited in the shallower waters within 150 or 200 miles from land. Beyond this limit terrestrial sediment ceases to be transported and deposited, its place being taken by organic accumulations and by peculiar red and grey "clays" in which the inorganic material is mainly of volcanic origin, and must gather on the bottom with almost inconceivable slowness. This grouping of the detritus, derived from the degradation of the land, is evidently the only one possible, and it has now been abundantly demonstrated by recent deep-sea researches. We may be sure also that it must always have obtained in every geological period. The coarser and more lenticular sheets of sediment have accumulated nearest to the sources of supply, that is to the shores of the land; while the finer and more wide-spread silts have been spread over the farther and deeper tracts of that still comparatively narrow belt of sea to which sedimentation has always been mainly confined. To hasty readers it will seem an obvious and ridiculous paradox to maintain that the continents have been permanent throughout geological time, and yet to admit that probably no part of their surface has not been many times submerged beneath the ocean. Further reflection, however, and better acquaintance with the facts will convince every candid inquirer that the paradox is only in appearance. The continental ridges have been the great lines of terrestrial movement from the dawn of geological history. They have continually been undergoing disturbance; one portion has been equably upraised, another has been convulsed and corrugated, a third has been depressed. Every part of their surface has been subject to these changes. Moreover every portion of the crust which has risen above the sea-level has been exposed to the unremitting attacks of the subaërial agents of destruction. Again and again the solid bulk of the continents has been reduced to mere detritus and has been spread over the sea-bottom. And yet the continental ridges have never ceased to exist. Their disappearance would necessarily have been followed by the cessation of sedimentary accumulation. The character of their component rocks however teaches that, whether by the operation of underground movements or by the action of superficial causes, the land has been continually wandering, as it were, to and fro across the continental areas, disappearing beneath the sea in one region, reappearing from the sea in another. In one sense of course it may be said that land and sea have been continually changing places. But the submerged land has not become truly a part of the oceanic realm. The waters covering it have been mere prolongations of the upper layers of the ocean, like the Mediterranean, Black, and Caspian Seas of the present day. An elevation or depression of a few hundred feet, sufficed to turn wide tracts into land or into water. But such oscillations made no real change in the essential position of the grand aboriginal oceanic basins and continental ridges.

Mr. Wallace has thoroughly grasped the truth and significance of these averments, and has not been slow to perceive their fundamental importance in the history of terrestrial floras and faunas. He finds that they furnish new and unexpected assistance to the student of biological evolution, and indeed form a necessary part of the doctrine. "It is impossible," he says, "to exaggerate or even adequately to conceive the effect of these endless [terrestrial] mutations on the animal world. Slowly but surely the whole population of living things must have been driven backward and forward from east to west or from north to south, from one side of a continent or a hemisphere to the other. Owing to the remarkable continuity of all the land masses, animals and plants must have often been compelled to migrate into other continents, where in the struggle for existence under new conditions many would succumb; while such as were able to survive would constitute those widespread groups whose distribution often puzzles us. Owing to the repeated isolation of portions of continents for long periods, special forms of life would have time to be developed, which when again brought into competition with the fauna from which they had been separated, would cause fresh struggles of ever-increasing complexity, and thus lead to the development and preservation of every weapon, every habit, and every instinct which could in any way conduce to the safety and preservation of the several species."

Besides interchanges of sea and land Mr. Wallace lays great stress upon former vicissitudes of climate as agents in the modification of plant and animal life. He has discussed this subject with great detail and offers an original explanation of the causes of secular changes of climate. Adopting generally Dr. Croll's views as to the relation between the Glacial period and the excentricity of the earth's orbit, he introduces into them certain modifications and limitations. If, he argues, the effects of a high excentricity have always been shown in great Polar refrigeration and a general lowering of the temperature in the hemisphere whose winter occurred in *aphelion*, there ought to be geological evidence of the change. He confesses however that although indications of local ice-action have been noticed in different geological formations, even as far back as old Palæozoic deposits, there is certainly no trace of such general glaciations as the theory would lead us to expect. Not only so, but the testimony of organic remains is everywhere and unmistakably against the theory. He concludes, therefore, that while the astronomical influences must unquestion-

ably be a *vera causa* in the production of terrestrial climate, and must always *tend* to produce alternate mild and severe conditions, there must be some counteracting cause whereby these influences are weakened or neutralised. This modifying effect he assigns to changes in the distribution of land and sea, especially in high latitudes. He contends that without lofty land there can be no permanent snow and ice. Consequently by the due elevation of Arctic land an area would be provided on which, when winter occurred in *aphelion* during a period of high excentricity, there would be so copious an accumulation of snow and ice, that even during *perihelion* the wintry conditions would continue, and perhaps even in an intensified form. Subsidence of this land, however, would admit the warm oceanic currents from lower latitudes, and so great would be the amount of heat thereby transferred that even winter occurring when the North Pole was turned from the sun and the earth's orbit was at a maximum of excentricity would be insufficient to cover the Polar regions with an ice-cap. The alternate phases of precession, which tend to bring warmer and colder conditions of climate every 10,500 years, would introduce a complete climatal change only where the land was partially snow-clad. The general conclusion is thus reached that, the climates of the globe being mainly dependent on geographical conditions, their mutations in former periods have been chiefly brought about by changes in physical geography. Mr. Wallace supports these views by much ingenious reasoning. He argues that during by far the greater part of geological time the distribution of land has been such that warm oceanic currents have been able to pass freely to the North Pole, giving a mild climate to the whole northern hemisphere. He would thus account for the palæontological evidence of long-continued glacial conditions within the Arctic circle from Palæozoic to late Tertiary times. It was only in very recent times, he thinks, that the great northern continents became so completely consolidated as to shut out the tropical currents and to render possible the wide-spread and intense glaciation which was actually brought about by the high excentricity that occurred about 200,000 years ago. According to this view geographical revolutions "have been the chief, if not the exclusive, causes of the long-continued mild climates of the Arctic regions, while the concurrence of astronomical influences has been essential to the production of glacial epochs in the temperate zones, as well as of local glaciations in low latitudes."

In a remarkable chapter, remarkable as the deliberate judgment of an accomplished naturalist, the author decides that the vast periods of time which used to be demanded for the changes of geological history are not required even for the evolution of the floras and faunas of the earth. He admits, with some geologists who have advanced the same view from physical data, that geological changes probably occurred more vigorously and rapidly in former times than they do at present, and as these changes have always been accompanied by relative alterations in the forms of the organic world, he believes that organic evolution has taken place far more rapidly than has been hitherto thought possible.

ARCH. GEIKIE

ALGÆ

Species, Genera, et Ordines Algarum, seu descriptiones succinctæ specierum, generum, et ordinum, quibus Algarum regnum constituitur, auctore Jacobo Georgio Agardh, Bot. in Acad. Lund. Prof. Emer. Vol. iii. pars ii. 8vo. pp. 301. (Lipsiæ: apud T. O. Weigel, 1880.)

THE appearance of Dr. J. G. Agardh's excellent work, "Florideernes Morphologi," published in the *Acta* of the Royal Scientific Academy of Stockholm, was duly noticed in the pages of NATURE (vol. xxi. p. 282), but, as the work was written in Swedish, a knowledge of its contents was accessible to a limited number of students only; the indefatigable author has therefore, with a view to render it more useful to those who take an interest in his subject, now issued an edition in Latin of the Morphology.

This new volume, which is in 8vo, forms the second part of the third volume of Dr. Agardh's "Species, Genera, et Ordines Algarum," and may be considered rather as a revised edition of the Swedish work than as an exact translation of it. The author has made some alterations both in the text and in the notes. These alterations include important remarks on the most recent algological publications, including M. Bornet's "Notes Algologiques," M. Sirodot's observations on the fecundation of the Batrachospermeæ, and those of M. Dodel-Port on the fertilisation of the spores of Algæ by Vorticellæ.

For a summary of the contents of the new work the reader is referred to the before-mentioned notice in NATURE; it may however be remarked that the present volume forms a valuable addition to the "Species, Genera, et Ordines Algarum," to which it is now appended, and its appearance will undoubtedly be welcomed by all who take an interest in the morphology of Algæ.

In addition to a table of contents and an *index rerum*, there is also an index of the species referred to. The latter is the more useful, because, in addition to the name of the species, there are special references to the descriptions of the structure, ramification, reproductive organs, and other particulars relating to the plants. This arrangement is especially convenient, inasmuch as these matters are treated separately in different parts of the work.

It is to be regretted that the beautiful illustrations appended to the Swedish edition do not accompany the present. The figures are referred to in the latter, and may be consulted by those who are fortunate enough to possess a copy of the former, or who have access to libraries which contain copies of the *Acta* of the before-mentioned Swedish Academy. It may be added that Dr. Agardh's descriptions of the parts of the plants are expressed with his usual precision and clearness, and can, therefore, be understood without the plates—though, undoubtedly, better with them.

It may be observed that the present volume treats solely of the morphology of the Florideæ, and the author does not allude to the classification of Algæ, except to express his opinion that certain Algæ of red or purple colours, such as Bangiæ and Porphyræ, included by many algologists among the Florideæ, do not really belong to that class (p. 9, *note*). MM. Thuret and Le Jolis excluded these plants from the old class of chlorosperms, to which they were formerly considered to belong,

Dr. Agardh does not admit them among the Florideæ; and in Dr. A. W. Bennett's new scheme for the classification of the lower cryptogams,[1] they seem to be literally nowhere. Neither has Dr. Bennett assigned any place in his scheme to the rather extensive family Valonieæ. It is to be hoped that algologists will agree before long on the position which these forms are finally to occupy in the classification of Algæ.

His work on the Florideæ having been thus brought to a successful termination, it is to be hoped that Dr. Agardh will now turn his attention to the Melanosperms, and that he will, before long, give us a new edition of the first volume of his "Species Algarum"; a work rendered necessary by an increased knowledge of the structure and fructification of these plants, and by the discovery and accurate examination of many new species. The ex-professor has already revised and reconstructed the extensive genera *Laminaria*, *Zonaria*, *Fucus*, *Cystophora*, and *Sargassum*—the latter as far as relates to the Australian species of the sections *Pterocaulon* and *Arthrophycus* only. To these must be added descriptions of many new species of Melanosperms, all of which have been published in the *Proceedings* of the Swedish Academies, and are, therefore, not within reach of many who would gladly consult them. A new edition, in which these scattered papers shall be collected and classified, would be a boon to algologists, and, we trust, would not entail very great labour upon the learned and industrious author. M. P. M.

LETTERS TO THE EDITOR

[*The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts. No notice is taken of anonymous communications.*

The Editor urgently requests correspondents to keep their letters as short as possible. The pressure on his space is so great that it is impossible otherwise to ensure the appearance even of communications containing interesting and novel facts.]

"The New Cure for Smoke"

NATURE, vol. xxiii. p. 25, contains a letter from Dr. Siemens on a "new cure for smoke," and in that letter it is stated that, instead of using inert matter such as pumice-stone, he (Dr. Siemens) considers it far more economical and efficacious, in a gas-grate to transfer the heat of the gas-flames to gas-coke or anthracite, and that the result obtained shows that the "coke-gas fire" is not only warmer, but cheaper than its predecessor, the coal-fire, with the advantage in its favour that it is thoroughly smokeless.

Now having had considerable experience with gas-heating fires of various kinds, and being much interested in the success thereof, I determined to give the "gas-coke grate" a practical trial; and as the result of the trials which I have just completed, and which extended over a period of two months, may interest many of your readers, possibly you may be able to find space in your columns to record the following particulars:—

In the first set of trials a good modern fire-grate was arranged (as described by Dr. Siemens) with a solid iron dead-plate, and ½-inch gas-pipe, pierced with holes $\frac{1}{10}$th of an inch in diameter, placed in the front part of the grate, but behind the lowest bar, and all air excluded from below except that which was allowed to pass in between the hollow bottom and enter on the line of gas flames. The grate was then filled with coke broken into pieces about the size of a large walnut, the gas turned on and lighted. In a short time a good bright fire with a rich flame was obtained; the external temperature at starting was 32° F., and that of the room 45° F. This latter rose within two hours to 62° F., and was maintained as long as the fuel lasted, viz. fifteen hours, the gas and coke burning brightly the whole time.

[1] See the Report in NATURE (vol. xxii. p. 451) of a paper read before the British Association at Swansea last year.

The result of a number of these trials, with an expenditure of 28 lbs. of coke, was an average consumption of 325 cubic feet of gas, the expenditure of the latter being very accurately ascertained by passing the gas through a standard test meter.

A second set of trials was then made under conditions precisely similar to the above, with the exception that the gas was used only for lighting the coke at the commencement, and when a good fire was obtained, and the temperature had risen to 62° F., it was turned off, and only used again for a short time to reinvigorate the fire and maintain the temperature. This second series of trials—with an expenditure of 28 lbs. of coke—resulted in an average consumption of fifty cubic feet of gas; the fire, when the gas was turned off, was not so bright or rich as in the first series, and the fuel only lasted thirteen hours.

Upon the completion of the coke and gas trials as above, the grate was restored to its original condition for burning coal. The fire was lighted in the usual manner, and within two hours the temperature rose to 62° F. as in the previous trials, the external temperature at starting being 32° F., and that of the room 45° F., and with a consumption of 28 lbs. of coal 62° F. was maintained for fourteen hours.

The room in which the experiments were made was the same in each case, having a capacity of about 3000 cubic feet, a due north aspect, and situated about 150 yards from the river, to which it is entirely open.

The above facts having been ascertained after an extended and repeated series of trials, in which the fuel was most carefully weighed and the gas measured, it now becomes a simple matter to reduce the results to £ *s. d.*, and in doing so I have taken the present prices of gas, coke, and coal in this neighbourhood, which are as follows:—Coal, 26*s.* per ton; coke, 12*s.* per chaldron; and gas, 3*s.* 3*d.* per thousand cubic feet. From these we obtain the undermentioned results, viz.:—

First Trials. Coke and Gas continuously for fifteen hours

	d.
28 lbs. of coke at 12*s.* per chaldron	2·571
325 cubic feet of gas at 3*s.* 3*d.* per 1000 cubic feet	12·675
	15·246

Or 1·0164 pence per hour.

Second Trials. Coke, with Gas for lighting and use occasionally for assisting the Coke, for thirteen hours

	d.
28 lbs. of coke at 12*s.* per chaldron	2·571
50 cubic feet of gas at 3*s.* 3*d.* per 1000 cubic feet	1·950
	4·521

Or ·3477 of a penny per hour.

Third Trial. Coal only, for fourteen hours

	d.
28 lbs. of coal at 26*s.* per ton	3·9

Or ·2785 of a penny per hour.

It will, I think, be at once seen from the foregoing results that although by the use of gas and coke we get rid of the smoke nuisance, that desirable end is not obtained entirely without cost, and that, judging from these experiments, the "coke gas fire," while possessing many of the advantages claimed for it, has not proved in this instance to be warmer and cheaper than its predecessor the "coal fire."

Possibly some of your professional readers may find time to pursue the subject further and favour us with the result of their investigations. I have given a good deal of attention for years past to the employment of gaseous fuels, and have made many experiments, but I do not at the present time know of any fire-grate or stove (for ordinary household purposes) wherein gas is employed as the heating agent, either wholly or in part, which gives such good results as the raw material coal. At the same time there can be little doubt but that we shall yet discover the way to effect great economy in the use of fuel both for domestic and manufacturing purposes, and ultimately to solve the smoke nuisance question; but whether it will be by separating the raw material into its several constituents and bringing some of them together again under different conditions and proportions when being consumed in a gas furnace or grate, or by better and more perfect appliances for effectually burning the fuel in its raw state, has, I think, yet to be settled. The question however is one which concerns all alike, being a matter of both personal and national interest. J. A. C. HAY

Royal Arsenal, Woolwich, January 29

I HAVE been much interested in reading the above, and I hope that Mr. Hay's example will be followed by other observers, in order to establish a fair average result of the relative cost of the coke-gas grate and the ordinary coal grate. Mr. Hay's results are not as favourable as those obtained by myself, owing probably to some imperfection in his arrangements, which are not described sufficiently to form any judgment upon them. I should like to know, for instance, whether the copper-back plate, which I presume he used, although it is not referred to, was backed by fire-clay, or whether it touched the ironwork of the fireplace, whereby its heat would be conducted away. This alone might account for the difference in result obtained by Mr. Hay and myself, and I think this opportunity is a favourable one to send you the figures resulting from my own observation of the original grate described in my article in NATURE, vol. xxiii. p. 25. This grate has now been in use from November 8 to January 31, during which period it has been alight sixty-six days, and the average time during which a bright fire has been kept up has been eight hours daily. During this period of 528 hours there has been consumed—

	£	*s.*	*d.*
1112 lbs. coke at 18*s.* a ton	0	9	0
581 lbs. smokeless coal at 20*s.* a ton	0	5	2
4100 cubic feet of grs at 3*s.* 6*d.* per 1000 ...	0	14	4
	1	8	6

Or an average of 0·518*d.* per hour, instead of 0·525*d.*, as resulting from my first observation. The average consumption of solid fuel per hour has been 3·2 lbs., and of gas 7·7 cubic feet. The full supply of gas has generally been allowed during the first hour of lighting, after which it is turned down to about a third; this I find to be a convenient mode of working.

In comparing my results with Mr. Hay's, it must be borne in mind that my room has a capacity of 7200 cubic feet, with northern aspect, and his a capacity of 3000 cubic feet, also with northern aspect; his consumption should therefore be only $\frac{3000}{7200} \times 0{\cdot}518 = 0{\cdot}216d.$ (instead of 0·347*d.*), which figure would prove an economy in the employment of the coke-gas grate over the coal grate, which is 0·2785*d.* by his own showing, and would agree with the comparative results contained in my original communication.

C. W. SIEMENS

February 2

On the Spectrum of Carbon

IT is very desirable that, if possible, some definite conclusion should be arrived at concerning the chemical origin of the bands, which Prof. Liveing calls "hydrocarbon bands," and the importance of the point at issue must be my excuse for again addressing you on this subject.

In my previous communications I pointed out that if it can be shown experimentally that the electric spark, in an atmosphere of cyanogen *free from hydrogen*, gives the groups in question (the groups δ and γ, wave-lengths 5165 to 5082 and 5635 to 5478 respectively, are here the only ones considered), they must be due to carbon, and remarked that the hypothesis that they were due to traces of hydrogen present as impurity is "to adopt an extreme hypothesis which must be supported by cogent experimental evidence before it can be accepted." Prof. Liveing admits the justice of this demand, and then goes on to say that such "cogent experimental evidence, so far as the relations of carbon and *nitrogen* are concerned, will be found in our complete papers on the spectrum of carbon compounds in the *Proceedings* of the Royal Society." This appears to me to be equivalent to an admission that—as concerns carbon and *hydrogen*—no such experimental evidence has yet been given; which is also the conclusion to which I came after perusal of the papers of Profs. Liveing and Dewar referred to.

It would seem then that the burden of proof that cyanogen exists in which the spark will not give rise to the bands δ and γ rests with Prof. Liveing. Nevertheless I have repeated the experiment with cyanogen, described in this journal (vol. xxiii. p. 197), so as to set aside the objections raised by Prof. Liveing to the former experiment. The apparatus was in this case constructed of one piece of glass—a long piece of hard glass tubing. This was carefully cleaned, the tube was then contracted at two points, so as to separate a short portion of the tube, into which platinum wires were fused, so as to form a discharge tube. The whole tube was next heated to redness in a furnace, while a current of oxygen passed through it for some considerable time. The greater portion of the tube on each side of the part containing the wires was then filled with phosphoric anhydride, and a short length of the tube, separated from the discharge tube by as great a length of phosphoric anhydride as the length of the tube permitted, was employed as a retort, and filled with mercuric cyanide; the other end of the tube was drawn out and dipped beneath sulphuric acid. The mercuric cyanide employed, after being finely powdered, was dried for a long time in an air-bath, then transferred to a clean hard-glass tube, in which it was repeatedly heated, while a current of air dried by passing over calcium-chloride and phosphoric anhydride was drawn over it. From this tube it was transferred immediately to the retort-tube. In making the experiment the mercuric cyanide was heated so as to give as slow a current of cyanogen as possible, which was continued long enough to expel all the air from the tube. The tube was then sealed up, leaving the discharge-tube, with a phosphoric anhydride tube on each side of it, and put aside for a week. The spectrum was then examined, with the same result as before. The tube gave a brilliant carbon spectrum, of which γ and δ (the positions of which were measured) were the brightest groups. No trace of the hydrogen C-line was obtained. Prof. Liveing objects that this is not a sufficient proof that hydrogen is absent (in which I cannot agree with him), and suggests that "a real test would be to see whether, when the spark gives the line-spectrum of carbon, the hydrogen-lines do not also appear." This test is however not applicable, since (according to my experience) cyanogen cannot be made to give the line-spectrum of carbon. Further, in this particular case the spark could not be got through the tube when the condenser was put on.

Giggleswick, February 11 W. M. WATTS

"Prehistoric Europe"

As there was no space to allow of all the authorities being cited in my criticism of the above work I now give those which relate to the facts called in question by Dr. James Geikie in NATURE, vol. xxiii. p. 336.

1. Dr. James Geikie repudiates as absurd the view attributed to him, that the palæolithic gravels "which overlie the chalky boulder clay of East Anglia were covered by an upper and younger boulder clay," and denies that he ever wrote anything which would justify that opinion. In "The Great Ice Age," 2nd edition, p. 531, he writes: "The palæolithic beds dovetail into the glacial drifts, and are overlapped (as in Yorkshire) by the deposits thrown down during the final cold period. To the last interglacial period then we must refer the great bulk of the palæolithic river gravels of the south-east of England." If this be true, where are the glacial deposits in question to be seen? If they ever were above, or "overlapped," the palæolithic gravels, they have, so far as our present knowledge goes, been utterly destroyed. Of course this view *is* absurd.

2. The reindeer associated with the hippopotamus and hyæna in the same stratum in the Victoria Cave was discovered while the exploration was under my management, and was published in Brit. Assoc. Rep. 1872, *Trans.* p. 179, and again in Mr. Tiddeman's Report, *op. cit.* 1876, *Reports*, p. 118. The animal is omitted by the author where its presence would destroy his argument as to climate, but he does not forget to record its subsequent discovery at a higher level, where it falls in with his argument. It may be remarked that the association of reindeer with hippopotamus in this cave has no special theoretical value, because the two animals have been found together in several other hyæna dens.

3. The fossil mammalia of Mont Perrier are typical Upper Pleiocene, as may be seen from the works of Croizet and Jobert, Gaudry and Gervais, and as I can testify from their examination. The glacial origin of the overlying tuffs, which I have examined under the guidance of M. Julien, seems to me to be open to considerable doubt.

4. The mammalia of Leffé, and those of the Val d'Arno with which they are classified by Dr. James Geikie, characterise the Upper Pleiocenes of Italy, as may be seen from the careful essays published by Dr. Forsyth Major, and from an examination of the magnificent collection in the museum of the University of Florence.

5. If pages 309-318 of "Prehistoric Europe," dealing with "interglacial epochs," do not imply a belief that the Neolithic skull of Olmo is interglacial, I am unable to ascertain their meaning.

The questions whether a geological period is to be classified as hitherto it always has been classified, by an appeal to zoology or by an appeal to ice, and whether the naturalists who have devoted themselves to the study of mammalia have only "opinions," while Dr. James Geikie enjoys "the facts," may be left in silence to the judgment of geologists. In the review under discussion all reference to my own opinion and works has been carefully omitted. Here, so far as I am concerned, the discussion ends.

W. BOYD DAWKINS

Owens College, February 11

Geological Climates

IN NATURE, vol. xxiii. p. 241, Dr. Haughton repeats his former statement that "it is impossible to suggest any rearrangement of land and water which shall sensibly depress the temperature of the east of North America." Now we must only look about us to see that the east of Asia is colder than the east of North America, parallel for parallel, and this especially in winter. The *mean temperature of January* is as follows in places situated as far as possible under the same latitude and at the same distance from the sea :—

Lat. N.	Eastern Asia.		Eastern North America.		Difference.
°					
56½	Ajan	− 4·2	Nain, Labrador	− 3·8 ...	0·4
53	Nikolayewsk, Amoor	− 12·1	Rigolet, Labrador	− 1·1 ...	11·0
43½	St. Olga Bay ...	12·9	Portland, Maine	21·2 ...	9·3
43½	Wladivostok ...	6·1	Portsmouth. N.H.	25·0 ...	18·9
40½	Newchwang ...	10·4	Paterson, N J. ...	26·6 ...	16·2
40	Pekin	23·7	Philadelphia ...	31·3 ...	7·6
			Mean of Savannah		
31½	Shanghai	38·3	and Ft. Marion	53·6 ...	15·3
22½	Victoria, Hong Kong	59·5	Habana, Cuba[1]	71·4 ...	11·9

This shows that (1) from lat. 20° to 55°, Eastern Asia is everywhere from 7½° to 19° F. colder in January than Eastern North America ; and that (2) those parts of the coast of Eastern Asia which are not separated by mountains from the interior lowlands are much colder than those which are sheltered, but even the latter parts, though relatively warmer, are yet much colder than the same latitudes in Eastern North America. These differences are explained by geographical position. Asia is the larger continent ; its eastern interior is more secluded from the influences of warmer seas, and its eastern coast more subject to Continental influences, and thus colder in winter than North America. We thus see by the example of Asia that a colder temperature than in Eastern North America does really exist now in the same latitudes. The example of Eastern Asia shows us geographical conditions which tend to produce an exceedingly cold winter. We have but to look at the middle and higher latitudes of the southern hemisphere to see so cold summers that nothing of the kind is met with in the northern. I do not know on what authority Dr. Haughton states that the annual temperature of 32° F. is met in the southern hemisphere but on 62° 41′ S. We do not have observations during the winter in these latitudes, but the mean temperature of January (the warmest month) is found to be 35·2 on 60° S. and 32·4 on 63½° S. Or (by the observations of Sir J. Ross) the mean annual temperature can certainly not be less than 4½° below that of January, so that it would be not higher than 30·7 on the 60° S., and 27·9 on the 63½° S.

St. Petersburg, February 5

A. WOEIKOFF

Variable Stars

WITH reference to your remarks on variable stars in the Astronomical Column of NATURE, vol. xxiii. p. 206, I beg to send a few observations made by me (on some of the stars referred to) during the past few years :—

5. 35 Camelopardi. October 1875. I found this star about 6½ m. and fainter than *o* (27 Fl.).—October 6, 1879. 7 mag. ; about 1 mag. less than *o*.

6. Rümker's star. I have the following observations : March 27, 1875. About 7 m. ; fainter than 25 Monocerotis.—January 19, 1876. 6½ m. ; less than 25, but brighter than two 7 m. stars *s.f.* it.—March 18, 1877. Distinctly visible to the naked eye ; about 6 m., but less than 25 (5.6 m. Heis). The above observations were made in the Punjab.

7. 65 b^2 Geminorum. December 1, 1880. 65 so exactly equal to 64 Geminorum with opera glass that I could see no difference between them in magnitude.

[1] Nearly one degree to the North of Victoria.

8. 16 Leonis Minoris. March 27, 1875. About 7½ m.—January 19, 1876. 7·3 or 7·5 m.

10. Lalande 38405. August 31, 1877, I found this star fainter than Lalande 38388, which lies about 20′ north of it ; also less than a 6 m. Harding (Lalande 38214) *s.p.* it. Brighter than Lalande 38342 (7½, 8), which lies *n.p.* it.

11. 33 Capricorni. August 1875 I estimated this star as 6½ m. ; August 1876, 6 m., and slightly brighter than 35 Capricorni.

12. ι (17) Andromedæ. From numerous observations, beginning in May 1875, I have detected a variation in the light of this star to the extent of about half a magnitude. It is sometimes distinctly brighter than κ Andromedæ, and sometimes decidedly fainter.

With reference to β and δ Scorpii I find the following observation in my note-book :—

"Punjab, August 10, 1876. β Scorpii (2 m. Heis) and δ Scorpii (2·3 m. Heis) almost exactly equal. Perhaps δ, if anything, *very* slightly the brighter of the two.

J. E. GORE

Ballisodare, Co. Sligo, Ireland, February 5

The Mode of Flight of the Albatross

THERE seems to be a prevailing idea that the albatross in his flight is in some way "assisted by the wind." I think this is a mistake ; the manner is well known. The method I believe admits of a very simple explanation. His secret consists in his power of acquiring great momentum together with the large superficial area of his extended wings ; with scarcely a motion of his wings he will fly straight against a strong wind with a velocity greater than that of any racehorse ; this is inconsistent with the idea of his being "assisted by the wind."

In attempting to rise from the water (I believe he is unable to rise from the land or from a ship's deck) he flaps his wings violently to get his body out of the water ; at the same time, paddling rapidly with his webbed feet, he acquires a moderate degree of momentum, sufficient, with outstretched wings, to carry him forward and upward upon an easy incline. The case is similar to that of a boy taking a run with his kite string in his hand to give his kite a start. During this first rise he will generally give a few heavy, lazy flaps, and then stretch his wings steadily to their full extent ; now as he gradually rises he must of course as gradually lose his acquired momentum till it suits him to acquire more, when he may be twenty, thirty, or fifty feet above the surface, but a much greater distance from the place where he left the water, measured on the surface ; by slightly altering his position, by a movement of his tail, he takes a shoot downwards at any angle that suits his convenience, still without his wings outstretched. This is precisely the case of a boy shooting down a coast on his sled ; the propelling force is the same. The bird directs his course mainly with his tail, the action of which upon the air is identical with the action of a ship's rudder upon the water. By this downward motion, his velocity rapidly increasing, he acquires a degree of momentum sufficient to carry him up again to a height equal to or greater than that from which he started. In this up and down long wave-like motion, with all its variations on either side, consists the whole of his flight day after day for hundreds of miles ; at long irregular intervals he may give a few lazy flaps with his immense wings. Other birds use the mode of flight of the albatross, but to a smaller extent, for the reason, in the case of smaller birds that, the ratio of feathers to bulk being greater, their specific gravity is less, consequently they are unable to acquire the degree of momentum necessary to carry them upward ; but on the other hand they have the power of sustained effort in moving their wings rapidly, which the albatross has not. Gravitation then, which prevents him from rising directly on the wing, is the motive power of the albatross when aloft. He must always take a run or paddle over the surface of the water in order to get a start, and on the land or the deck he is a prisoner, because he has no water in which to paddle himself along with his webbed feet, and he is unable to run. Instead of being assisted by the wind, his speed is lessened by just so much as the wind's velocity, when it happens that the direction of the wind and his intended course are opposed to each other, but with the wind his speed is just so much greater than it would be in a calm.

I do not advance this explanation as an imaginative theory. I claim more for it. I have had many opportunities of studying the movements of the albatross for consecutive days, and I feel confident that the above will be found to answer all required conditions.

HOWARD SARGENT

Cambridge, U.S.

Auroral Phenomena

IT is perhaps worth a note that my daughter saw at Folkestone a very unusual phenomenon on the evening of January 25, a little before 6.30. Some distance to the left of Orion (for the night was clear and starry) she observed a small cloud of a bright golden hue, from which streamers of great brilliancy darted in various directions, the cloud alternately paling and brightening. She describes the streamers as like small meteors, leaving trails of light behind them. C. M. INGLEBY

Athenæum Club, February 12

Ozone

IN reply to Mr. Capron (NATURE, vol. xxiii. p. 219) the following explanation may perhaps serve :—

On a flat piece of brass two strips of paper are laid, one plain white, the other prepared. With a clean camel-hair brush they are moistened liberally with pure alcohol. This is then burnt off, firing it with a spirit flame; the plain paper remains *clear* and *white*, the prepared paper (beginning at the edges) gradually changes to a *purple brown*. On immersing both strips in clean water the plain paper still remains white, prepared paper changes to a deep purple (No. 8, Negretti's scale).

In about an hour this deep purple colour fades away *precisely in the same way as if the slip had been ozonized by exposure for a day or two to the air*. It may be added that if the prepared slip is not plunged into water the purple brown tint remains for several days.

The experiment suggested by Mr. Capron has been made, using a very delicate gold-leaf electrometer. When this is uncharged there is no apparent effect; when charged either directly or inductively with either positive or negative electricity the gold leaves collapse, the charge appearing to be dissipated with the flame.

I may add, when the leaves are *charged* the alcohol is lighted on the plate of the electrometer with a glass rod dipped in alcohol, care being taken to prevent the discharge by conduction. The above experiments have been performed in an ordinary study, but I cannot say they are very conclusive.

Mr. Capron states "ozone is very strong just now," and he obtains No. 10 (Negretti's scale) at an inland town. This is a very high number. I have repeatedly obtained this number at Hunstanton on the Wash (Norfolk), where I made experiments daily for a month. The ozone cage was kept in the shade, a fine cloudless day with cold north east wind blowing, and one day's exposure. I have been engaged for some years in testing for ozone on the coast to see if its abundance, or deficiency, is in any way dependent on the physical and geological conditions of the shore. My experiments are not sufficiently advanced to be published, but the three following conditions have always been found to be present where ozone is abundant.

1. A long sandy shore exposed for some hours to the sun's rays.

2. Cloudless sky, with cold north or east wind.

3. An abundance of phosphorescent light from the presence of *Noctiluca miliaris* with the evening flow of tide.

This town is singularly deficient in ozone. After numerous experiments I have as yet only obtained No. 1 (Negretti's scale). Whether this deficiency may not have some connection with our notoriously great infantile mortality of the autumn is a question for further consideration. J. P.

Leicester, January 27

Citania

I HAVE not had an opportunity of reading NATURE for some time, but I am told that in a late number there is some mention of a so-called "Pompeii" near Braga in Portugal.

I do not presume to write as a learned antiquarian; but having lived for some years within thirty miles of Citania, and having often visited the place and examined the ruins with a wish to gain some explanation of their mystery, I venture to write as an ordinary witness.

In no sense can Citania be described as a Celtic Pompeii; it is merely a collection of circular buildings erected so close to each other as almost to touch, and grouped on the top of a hill which runs out as a spur from the higher ground behind it, and overlooks the rich valley beneath it. The walls have fallen, and the stones which composed them remain *in situ*, generally visible, though more or less overgrown with grass. From the foundations it seems that these round houses must have been some ten feet in diameter internally, with walls eighteen inches thick. The original height of the walls may be inferred, from the quantity of stones fallen, to have been some twelve or fifteen feet.

My utmost examination discovered scarcely anything beyond some shattered bits of coarse pottery. But over the surface of the hill there are still lying about many well-shaped round stones about twenty inches in diameter, which I always thought to be hand millstones. These seemed to me to afford the most likely solution of any mystery connected with the place, and I inferred it was a place of security, to which the corn of the district round was carried. The apparent absence of water forbade the supposition that it was a place of permanent abode. I never could see any necessity for referring its origin to Celtic time. The buildings were probably used, and possibly only date from much later days. Remembering the condition of that district as being the debatable ground lying between the Asturian kingdom in the north and the moors in the south, and open to sudden and transient incursions from either side, the utility of such a place to the farmers of that district seems evident. A Portuguese gentleman, whose name I forget, has so far interested himself in the place as to rebuild one of the circular buildings in what he conceives its original condition, and inside he has collected any remains of antiquarian interest that he could scrape together. Unfortunately his enthusiasm for forming a kind of local museum has led him to carry to it what never belonged to the place. For outside his museum there is a large granite slab, which in character is utterly foreign to the place, and long mystified me. This "Pedra Formosa," as it is called by the neighbouring villagers, is about nine or ten feet long, six feet high, with an average thickness of one foot, and must weigh six or seven tons. It looks like a pretentious *façade* stone, which has survived the building to which it was once attached. It has some carving about it, and signs which may or may not have any meaning in them. But whatever the stone was, it has no right to be where it is; for one day, in a conversation with a local farmer at the inn in the valley, I learnt the fact that some years ago all the farmers of the neighbourhood combined, and yoking thirty-nine pair of bullocks together, dragged the said stone from the valley below, where from time immemorial it had been lying, and added it in triumph to the other objects of the museum.

I may add that during my stay in Portugal I corresponded with the late Senhor Herculano, the Portuguese historian, on the subject, and I believe I have stated his conclusions.

R. BURTON LEACH

Sutton Montis Rectory, Castle Cary, February 8

The Recent Severe Weather

YOUR correspondent H. W. C. in his communication on the above in NATURE, vol. xxiii. p. 329, quotes Mr. Lowe's theory of an eleven-year cycle of "great frosts," and after giving the dates upon which that theory is apparently based, says: "There are some variations in the lengths of the intervening periods, *but there is a distinct recurrence of eleven-year epochs*."

With the first part of this sentence I quite agree, but I fail to see the very least ground for the latter part of it, the intervals taken in order being as follows:—9, 3, 6, 18, 3, 16, 4, and 10 years. Three intervals approximating to eleven years can be "screwed" in by manipulating the years between which you reckon, disregarding inconvenient ones and using others which suit better; but surely this cannot be held sufficient to justify the statement, such a method of dealing with the figures being, it is scarcely necessary to point out, quite unallowable.

I have noticed before that when the discovery of similar epochs for abnormal heat, cold, rain, &c., have been announced, a similar method of dealing with dates has been followed to that which seems to have been adopted in this case. F. M. S.

February 3

THE epochs which show recurrence are obtained by "manipulating" the figures in the following manner:—

December 1801 to January 1814, interval 12 years 2 months.
" 1810 " 1820, " 9 " 2 "
" 1840 " 1861, " 20 " 2 "

(It should here be remarked that a *long* but not "great" frost was experienced in the winter of 1849-50; as it was not severe enough to entitle it to the designation of great frost it was

omitted from the table; if it had been inserted the 20 years and 2 months period would have counted as two 10 year periods.)

December 1860 to January 1841, interval 10 years 2 months.
„ 1870 „ 1881, „ 10 „ 2 „

Thus at least four periods (out of a possible seven) do not require much "screwing" to make them approximate to 11-year epochs; while if we were to add in the *long* frost of 1850 we should have no less than six periods, showing a distinct recurrence.

It may not be quite clear why the remaining dates are inserted; but if they are analysed in the following manner they are not uninstructive.

December 1813 to January 1838, interval 22 years 2 months.
„ 1837 „ 1857, „ 19 „ 2 „

These periods, like the one 1840 to 1861, tend to show that the intervals approximate nearer to 22 years. How does F. M. S. obtain the intervals he quotes? As regards the last paragraph of the letter of F. M. S. respecting the "abnormal heat, cold, rain, &c.," it is only necessary to say that he would have considerable difficulty to prove to Norman Lockyer, Meldrum, and others, that 11-year cycles do not exist, even if F. M. S. "screwed" his figures, as he seems to have done in his letter above. H. W. C.

Butterflies in Winter

A COUNTRYMAN has shown me to-day two fine specimens of *Vanessa urtica* in a lively condition caught on the 4th inst. in an empty room on the border of the New Forest, exposed to the severity of the late frost. THOMAS W. SHORE

Southampton, February 8

JOHN GOULD, F.R.S.

THE grave has recently closed over the remains of a very remarkable man, and although the annals of science, we are proud to think, afford many instances of indomitable energy and unceasing perseverance rewarded, they have no greater record of success than is to be found in the life of John Gould. No one can regard the series of works written and illustrated by him without acknowledging that they are a monument of human energy, and the story of his life makes the fulfilment of these large enterprises the more interesting. In the character of the man we must look for the secret of his success, because it is well known that he possessed neither the advantages of wealth nor education at the commencement of his career, and yet he has left behind him a series of works the like of which will probably never be seen again; and this because it is rare to find the qualities of a naturalist, an artist, and a man of business combined in one and the same person. John Gould was all these in an eminent degree; he knew the characters of birds as well as any man living, and although it has often been said that he made too many species—and latterly it has been the fashion with certain writers to sink a good many of them—yet the monographer, travelling over the ground again, generally finds that the critic, and not Gould himself, was at fault. As an artist he possessed talent combined with the greatest taste, and this, added to the knowledge of botany, acquired in his early days, enabled him to give to the world the most beautiful series of pictures of animal life which have yet been produced. Certain special works, where the pencils of Wolf or Keulemans have been employed, many vie with those of Gould, but taken in a collective sense, his splendid folios, full of coloured plates, are as yet without a rival. That he was a good man of business the fact that his writings were not only self-supporting, but further realised him a considerable fortune, is the best proof. Though in outward seeming he was stern and even somewhat brusque in manner, those who knew him well can vouch for the goodness of his heart, and can tell of many an act of kindness and charity, concealed from the world under a bluff exterior, and no one ever heard him speak unkindly of any of his contemporaries. Straightforwardness was one of his especial characteristics, as well as an exact manner of doing business, paying for everything the moment the work was done; and this probably accounts for the way in which his artists, lithographers and colourers, worked for him for long periods of years.

Mr. Gould at his death was in his seventy-seventh year, having been born in September, 1804. He was a native of Lyme in Dorsetshire, but when quite an infant his parents moved to the neighbourhood of Guildford When he was fourteen years of age his father was appointed a foreman in the Royal Gardens at Windsor, under Mr. J. T. Aiton, and here the lad had a grand opportunity of studying British birds in a state of nature; in his collection are still to be seen two magpies shot by himself and stuffed at the age of fourteen, which are even now most creditable specimens of taxidermy, and foreshadowed the excellence which he afterwards attained to in that art. Till the year 1827, when he came to London, he was still employed in active gardening, having left Windsor for a post at Sir William Ingleby's at Ripley Castle in Yorkshire. Immediately after coming to town he was appointed curator to the Zoological Society's Museum, at that time in its infancy, and he enjoyed the intimate friendship of Mr. N. A. Vigors, then one of the leading English naturalists, and through him John Gould received his first opportunity of appearing as an author. So rare were Himalayan birds in those days that a small collection was thought worthy of description by Mr. Vigors in the *Proceedings* of the Zoological Society, and the figuring of these specimens was commenced by Mr. Gould under the title of "A Century of Birds from the Himalayan Mountains." By this time however an event had taken place which had an influence on the whole of his later life, viz., his marriage with Miss Coxen, the daughter of Mr. Nicholas Coxen of Kent. Besides her other accomplishments Mrs. Gould was an admirable draughtswoman, and, from her husband's sketches, she transferred to stone the figures of the above-named work. Its success was so great that in 1832 the "Birds of Europe" was commenced, and finished in five large folio volumes in 1837, while simultaneously, in 1834, he issued a Monograph of the Rhamphastidæ or family of Toucans, and in 1838 a Monograph of the Trogonidæ or family of Trogons. To the last he maintained his love for these birds, and one of his most recently finished works was a second edition of the last-mentioned Monograph.. It is a curious fact that when John Gould proposed to publish his first work, he applied to several of the leading firms in London, and not one of them would undertake to bring it out, so that it was only with reluctance that he began to issue the work on his own account. Besides these larger publications he had described the birds collected during the voyage of the *Beagle* by his friend Mr. Darwin, and had contributed papers on other subjects to the Zoological Society's publications.

We now come to what we consider the most striking incident in Mr. Gould's life, one unsurpassed in its effects in the annals of ornithology. Beyond a few scattered descriptions by some of the older authors and an account of the Australian birds in the museum of the Linnean Society, by Messrs. Vigors and Horsfield, the birds of Australasia were very little known at the date we speak of. Accompanied therefore by his devoted wife, Mr. Gould proceeded in 1838 to study Australian birds in their own home, and he personally explored Tasmania, the islands in Bass's Straits, South Australia, and New South Wales, travelling 400 miles into the interior of the latter country. This voyage, specially undertaken for the purpose of obtaining an exact knowledge of Australian birds, must ever be reckoned as a distinct scientific achievement, and the accounts of the habits of some of the more remarkable species, such as the mound-building Megapodes and the Bower birds were quite triumphs in the way of field ornithology. Nests and eggs were collected as well as an excellent series of skins, both of mammals and birds, and here Mr. Gould's beautiful method of

preparation was especially noticeable; some of his specimens, skinned more than thirty years ago, are as neat in appearance and as fresh as the day they were prepared. Returning in 1840, after two years' absence, he commenced the great work on the "Birds of Australia," which makes seven folio volumes and occupied seven years in its production, being completed in 1848. One of the features of this work is the great increase in our knowledge of the range and habits of petrels and other sea-birds, to which the author paid great attention during his travels.

Within a year of Mr. Gould's return from his adventurous voyage he had the misfortune to lose his wife, and for some time he was completely overwhelmed by his bereavement. His collectors in Australia too, about the same period, lost their lives; one of them, Mr. Gilbert, was killed during Dr. Leichhardt's expedition overland from Moreton Bay to Port Essington, and Mr. Drummond, while collecting in Western Australia, was also murdered by natives, and a third collector was killed by the explosion of a gun on one of the islands of Bass's Straits. It speaks volumes however for the zeal and energy with which Mr. Gould had prosecuted his researches in the Australian continent that very few birds, sufficient only to form a supplement in a single folio volume, have been discovered since he left the field of his labours in that quarter of the globe.

Another landmark in the career of this great ornithologist was the publication of his Monograph of the Trochilidæ, or Family of Humming Birds. These lovely little birds had been for a long time favourites with Mr. Gould, who gradually began to amass that fine collection which has been the admiration of naturalists for so many years. Taking advantage of the Great Exhibition of 1851, he obtained permission from the Zoological Society to erect at his own cost a large building in their gardens in the Regent's Park, where the collection was open to the public at a charge of sixpence per head. A considerable sum was realised by this exhibition, and a large number of subscribers to his monograph was obtained, including nearly all the royal families of Europe. Though sketched by Mr. Gould himself (for even to the last days of his life he executed the designs for all his plates), the majority of the humming-birds were placed on stone by Mr. Richter, who also did the same for Mr. Gould's next work, "The Birds of Asia." We cannot but regard this as one of the most valuable of all the works done by the author, for, notwithstanding the fact that it is left unfinished at his death, it contains a large number of plates of species not elsewhere figured. The "Mammals of Australia," produced simultaneously with the last-mentioned work, deserved, in Mr. Gould's own opinion, more credit for its issue than perhaps any work he had done, because it touched upon a branch of zoology of which he never pretended to have a very exact knowledge. So large however had been his collections of mammalia during his sojourn in Australia that some account of them seemed to be demanded, and he therefore published his large folio work; but the pecuniary results were less satisfactory than with any of his ornithological productions. His typical specimens of the Australian mammalia are in the national collection. No sooner were the humming-birds finished than his active brain conceived a new idea, to illustrate becomingly the birds of his native land, and he commenced the publication of the "Birds of Great Britain." Opinions may differ as to the merit of Mr. Gould's other works; volumes less ponderous than the folios which he adopted for the better figuring of the objects of the natural size, may take their place with the student; but no work of greater beauty will be produced than that on which John Gould, returning in his later life to his first love, bestowed the fulness of his energy and the acme of his artistic talent. The care bestowed on the plates of this work was remarkable, the aim of the author being to produce a picture of the birds as they appeared in their natural haunts, and especial pains were bestowed on the young, particularly those of the wading-birds and natatores. In this fine work most of the drawings were developed and placed on stone by Mr. W. Hart, who also executed all the plates of the later works.

In 1865 Mr. Gould republished his letterpress of the big work in an octavo form, under the title of "A Handbook to the Birds of Australia," but with all the additional species inserted in their proper families; these two volumes are therefore of great use to the student. After the completion of his work on "British Birds," Mr. Gould devoted himself to the continuation of the "Birds of Asia" and the Supplement to the "Birds of Australia," until in 1875 he commenced a work on the "Birds of New Guinea," which was to contain also descriptions of any new species to be discovered in Australia or any part of the Australian region. Of the last-named work eleven parts have appeared, and it was left unfinished at his death, as well as the following works:—a "Monograph of the Pittidæ or Ant-Thrushes of the Old World" (one part published), the Supplement to the "Monograph of the Humming Birds" (two parts published), and the "Birds of Asia."

The above list enumerates, we believe, nearly all the works published by Mr. Gould with the exception of the "Icones Avium," issued about 1838, and containing supplementary plates to his previous volumes, with descriptions of new species, and the "Monograph of the Odontophorhinæ or Partridges of America." In addition to the folio volumes he was also in the habit of publishing the introductions to his larger works in an octavo form.

Many of the above details of Mr. Gould's life are taken from "Men of Eminence," aided by the personal recollections of the writer, who was for many years an intimate friend of the deceased, and knew him first as a successful trout-catcher on the Thames, for his prowess in throwing the fly was scarcely second to his skill as an artist. Were he to write an epitaph of John Gould he would do so in the words which Mr. Gould himself was fond of quoting:—"Here lies John Gould, the Bird-Man." The latter words were used by an old and intimate friend in introducing Mr. Gould to another relative. We may hope that the Government, according to the well-known wishes of the deceased naturalist, will allow no false motives of economy to interfere with the purchase of Mr. Gould's collection of birds for the British Museum, and that the disgraceful spectacle of his Australian collection (unrivalled to this day, and offered to the nation for the small sum of 1000*l.*) being allowed to leave the country, may not be repeated.

THE BLACKHEATH HOLES

THE chalk forming the base of the escarpment between Woolwich and the entrance to the valley of the Ravensbourne, dips at a low angle to the south-south-east under Greenwich Park and Blackheath, where it is overlaid by the Thanet Sands, estimated by Mr. Whitaker of the Geological Survey at 40 to 50 feet, the Reading and Woolwich Beds, consisting of shelly clays, sometimes 40 feet thick, associated near Lewisham with fine laminated sands. These beds are overlain by the Oldhaven or Blackheath gravels, reaching a thickness of about 50 feet, which have been largely dug for gravel in various parts of the district.

In the centre of this tract at Blackheath, on the west side of the angle of the roads from Greenwich Park to Blackheath Station, and from the Park to the Paragon, appeared in the early morning of Thursday, April 12, 1878, a subsidence near the row known as Rotten Row, referred to in these columns at the time, the hole being 8 or 9 yards in circumference. In November, 1880, appeared another hole near the gravel pit below Eliot Place

and Heath House, and about 550 yards south-west of the first hole; and still later in that month, on the 19th, a third subsidence made its appearance, this time about 100 yards to the south-east of the first subsidence, and nearer to All Saints' Church.

The Astronomer-Royal and other inhabitants of the district being anxious to know how far other subsidences were probable, asked the Metropolitan Board of Works, who have jurisdiction over the Heath, and who had fenced in the sinkings, to investigate their cause. This however they declined to do, though giving to the Astronomer-Royal permission to do so; this authority he handed over to a newly-formed society, called the Lewisham and Blackheath Scientific Association, who formed a committee of investigation, including members of the West Kent Natural History Society, for which end subscriptions are now being sought, and operations will shortly be commenced, as announced in our columns.

The surface of the chalk is estimated by one member of the committee, Mr. T. V. Holmes, as probably occurring at about 100 feet from the surface at or about the Ordnance datum line. The investigations so far made show the third sinking to consist of an oval vertical shaft 7 feet 8 inches diameter by 6 feet 9 inches, with a depth of 18 feet, opening into a cavity extending in both directions, and partly choked with fallen earth, giving a total diameter, as far as examined, of 14 feet. The upper part of the shaft is described by Mr. Holmes as consisting of sand and clay resting on sand, overlying pebbles, in which the cavity below is formed. The material carefully removed from the bottom of the pit is found by Mr. H. W. Jackson to be of the same material as the upper beds of the shaft, proving the sinking due to removal of material from below. The first sinking is filled up and cannot be investigated; the second is not fully examined for want of funds, but is wholly in gravel, and also extends underground in two directions.

Various theories have been suggested by different observers to account for their origin, some considering them artificial, Admiral Hamilton that they are caused by the abstraction of water caused by the main-drainage works, which tapped powerful springs in the Lower Woolwich Road; others connect their appearance with removal of chalk, and water in the chalk, by the Kent Waterworks, who lift daily about nine million gallons a day from their wells in the neighbourhood, whilst others connect them with excessive rainfalls, the first subsidence having taken place after the great floods in the Ravensbourne, caused by the rain of the night of the 11th and morning of the 12th of April, 1878.

The height of the chalk water-line (*Journal*, Society of Arts, 1877) at Woolwich Dockyard well is about 15 feet below the Ordnance datum line before pumping, at the Kent Waterworks, Plumpstead, 1 foot 4 inches below, but at the Kent Waterworks wells at Deptford it is pumped down to nearly 70 feet below, rising 50 feet after pumping, or about 20 feet below Ordnance datum. The surface of the chalk at Bromley, at the Shortlands pumping-station, has risen to 70 feet above the datum, the water rising after pumping to 122 feet above it. This district is on the south side of a synclinal axis ranging east-north-east through Eltham, described by Mr. Whitaker, which throws in a trough of London clay, that cuts off this supply, from the chalk water entering at the Greenwich Park escarpment.

The water-level under Blackheath is at, or about, Ordnance datum, trending south towards the London clay synclinal, corresponding, under the site of the subsidences, to the surface of the chalk beneath the Thanet sands, and if there is no great quantity of chalk above the water-level it appears improbable that the subsidences are due to pipes descending vertically into the chalk, but it is quite possible that the drainage works, removing the waters held by the pebble beds above, disturbed their stability, and caused their subsidence. On the other hand it is not impossible that drift levels may have been driven into the chalk from the ancient chalk-pits a mile distant, ceasing when they reached the outcrop of the chalk against the Thanet sand, and which is immediately under the site of the subsidences.

C. E. De Rance

MERCADIER'S RESEARCHES ON THE PHOTOPHONE

An elegant series of researches in photophony have lately been published by M. E. Mercadier of Paris, who has very carefully examined the phenomenon discovered by Graham Bell and Sumner Tainter, that an intermittent beam of light may generate a musical tone when it falls upon a thin disk. By way of distinguishing this phenomenon and its applications from the phenomenon of sensibility to light exhibited by annealed selenium, which constitutes the essential principle of the articulating photophone, M. Mercadier adopts the name of *radiophony* for the subject of his research: a name which appears moreover to have the advantage of not assuming *à priori* what kind of radiations, luminous, calorific, or actinic, are concerned in the production of the phenomenon. It is agreed by all who have experimented in this direction that the pitch of the note emitted by the disk corresponds precisely with the frequency of the intermittent flashes of light: but it has been disputed whether the effect is due to light or to heat. Prof. Bell found that the beam filtered through alum water to absorb the calorific ultra-red rays produced tones; and that even when a disk of thin ebonite rubber was interposed, the beam robbed of both heat-rays and light-rays could still generate tones. On the other hand, from the list of substances given by the original discoverers, it was evident that since dark and opaque substances with dull surfaces, and those which, like zinc and antimony, have high coefficients of thermal expansion, produce, *cæteris paribus*, the best results, the effects must probably arise from heating effects due to absorption of radiations of *some* kind and their degradation into heat of low temperature.

M. Mercadier has summarised his results in an article in the *Comptes rendus*, from which the substance of this article is translated freely. The chief conclusions are as follows:—

I. *Radiophony does not appear to be an effect due to the vibration of the receiving disk vibrating transversely in one mass as in an ordinary vibrating elastic plate.*—This conclusion appears to be justified by the following observations: that, given a thin plate of any kind, under the conditions necessary for the production of the phenomenon, it produces equally well tones of all different degrees of pitch from the lowest audible up to the highest that can be generated experimentally by optical intermissions, and which in M. Mercadier's apparatus attained to a frequency of 700 vibrations per second. Moreover it was found that these changes of pitch were accomplished without any defect in the continuity of the phenomenon; which would seem to indicate that it was not necessary for the plate to vibrate in any particular nodal or partial mode. Also the receiving disk will produce *chords* equally well in all possible tones from the highest to the lowest, the chord being complete no matter whether the fundamental pitch be raised or lowered by altering the speed of the rotating apparatus by which the intermittences are produced. M. Mercadier's apparatus consisted of a glass wheel carrying on its surface a paper disk pierced with four series of holes, numbering respectively 40, 50, 60, and 80. Through any one of these series of holes a small pencil of rays could be passed, and, by raising or depressing the axis of rotation of the wheel, could be sent successively through each of the four, thus

producing, at any given rate of rotation, the separate tones of a common chord in succession: or by interposing a cylindrical lens to distribute the rays in a linear beam to the four series at once, the united tones of the chord could be produced simultaneously.

Further it was found that the thickness and the breadth of the receiving-disk makes no difference within certain limits in the loudness or quality of the resulting tone. And in the case of transparent substances such as mica and glass these limits may be wide: in the case of glass the loudness was the same with a disk of half a millimetre as with one of three centimetres thickness. In consequence rare substances may be used in disks as small as one square centimetre in area. Cracked or split disks of glass, copper, and aluminium produce sensibly the same effects as if they were whole.

II. *The molecular structure and state of aggregation of the receiving disk appear to exercise no important influence upon the nature of the tones emitted.*—Disks of similar thickness and surface emit sounds of the same pitch no matter of what material they be. Although there may be slight specific differences between the actual modes of production of the phenomenon from *very* thin disks of different materials, these differences are reduced to a vanishing quantity by rendering the receptive surface alike, as for example by covering them all alike with a film of lampblack. Moreover the effect produced by ordinary radiations is, *cæteris paribus*, the same practically for transparent substances as widely differing from one another as glass, mica, selenite, Iceland-spar, and quartz, whether cut parallel or perpendicular to the optic axis, and is the same in polarised light as in ordinary light.

III. *The radiophonic sounds result from a direct action of radiations upon the receiving substances.*—This proposition appears to be established by the following facts:—1. That the loudness of the sounds is directly proportional to the quantity of rays that fall upon the disk. 2. That by using a polarised beam and taking as a receiving-disk a thin slice of some substance which can itself polarise or analyse light, such as a slice of tourmaline, the resulting sounds exhibit variations of loudness corresponding to those of the rays themselves, when either polariser or analyser is turned; and the sound is loudest when the light transmitted by the analysing disk is a minimum.

IV. *The phenomenon appears to be chiefly due to an action on the surface of the receiver.*—The loudness of the emitted sound depends very greatly upon the nature of the surface. Everything that tends to diminish the reflecting power, and increase the absorbing power of the surface, assists the production of the phenomenon. Surfaces that are rough-ground or tarnished with a film of oxidation are therefore preferable. It is also advantageous to cover the receiving surface with black pulverulent deposits, bitumen black, platinum black, or best of all with lampblack; but the increase of sensitiveness under this treatment is only considerable in the case of very thin disks, as for instance from ·1 to ·2 of a millimetre. Very sensitive radiophonic receivers may be thus made with extremely thin disks of zinc, glass, or mica smoked at the surface. It may here be noted amongst M. Mercadier's results that for *opaque* disks, the thinner they are the louder is the sound, and that excellent results are given by metallic foil—copper, aluminium, platinum, and especially zinc—of but ·05 millim thickness. The employment of such sensitive receivers has enabled M. Mercadier to arrive at several other important conclusions

V. *Radiophonic effects are relatively very intense.*—They can be produced not merely with sunlight or electric light, but with the lime-light, and also with gas-light, and even with petroleum flames, and with a spiral of platinum wire heated in the Bunsen-flame.

VI. *Radiophonic effects appear to be produced principally by radiations of great wave-length, or those commonly regarded as calorific.*—In order to satisfy himself on this point M. Mercadier had recourse to the spectrum direct, without attempting to employ cells of absorbant material such as alum solution or iodine in dissolved bisulphide of carbon as ray-filters. A brilliant beam of light was produced by means of a battery of fifty Bunsen cells, and with this, by means of ordinary lenses and a prism of glass a spectrum was produced, the various regions of which could be explored with one of the sensitive receiving-disks mentioned above. The maximum effect was found to be produced by the red rays and by the invisible ultra-red rays. From yellow up to violet, and beyond, no perceptible results were obtained. The experiment was tried several times with receivers of smoked glass, platinised platinum, and plain bare zinc. The greatest effect appeared to be yielded at the limit of the visible red rays. The rays which affect the electric conductivity of selenium in the photophone are, as Prof. W. G. Adams has shown, not the red rays, but rays from the yellow and green-yellow regions of the spectrum. This fact alone would justify the distinction drawn between the phenomena of radiophony and those of the selenium photophone, though probably these are only two of several ways of arriving at a solution of the problem of the transmission of sonorous vibrations by radiation. Theoretically a telephone with a blackened disk inclosed in a high vacuum and connected with an external telephone should serve as a receiver; and the writer of these lines has already attempted to devise a thermo-electric receiver for reproducing sounds from invisible calorific rays.

S. P. T.

THE JOHN DUNCAN FUND

THE following subscriptions to this fund have been received during the past week:—

	£	s.	d.
Amount previously announced	48	6	0
Charles F. Tomes, F.R.S.	1	0	0
J. S.	2	0	0
Dr. Vacher	1	1	0
R. R. Glover	1	1	0
Thomas Walker ...	5	0	0
M. M. Pattison Muir	1	1	0
Major Deedes ...	0	10	0
Anon.	0	1	3
Sir J. Fayrer	1	1	0
T. C. Kent	1	0	0
Lawson Tait	1	1	0
Heinrich Simon ...	2	0	0
	65	2	3

THE TIME OF DAY IN PARIS

THE importance of precise and uniform time throughout Paris becoming ever and continually more appreciated, the Municipality have taken the matter in hand, and have established a system of what they call "horary centres." These horary centres really consist of standard clocks, erected in different places, and controlled by electricity from the Paris Observatory. Moreover each standard clock is furnished with additional electrical work of its own, which enables it to send out an hourly current and control other clocks in its neighbourhood, placed in circuit with it. The advantage of this arrangement over any system of electrical dials is apparent, for with the latter any mischance or practical joke with the wires would cause the whole city to be misled or completely deprived of time. The problem, as put by Leverrier, and as it has been practically solved by M. Breguet, was this:—To keep correct the hour given by various regulators distributed in the city by means of an electric current sent from the Observatory. If the current, in consequence of any accident, fails, the regulators continue to work, with a very slight advance, without the electric correction. The wires have their centre at the Observatory, where there is an astronomical regulator on the first floor. This instrument is maintained at the exact time indicated by the astronomical observations,

by means of an arrangement which obviates the stopping of the pendulum and changing its length. At the bottom of Fig. 1 is a box C, in which may be placed small weights. The weights are of such a shape that it is easy with suitable pincers to put them in or take them out without touching the clock or disturbing anything. The addition of a weight makes the regulator go faster; its withdrawal retards it. At the upper part of the pendulum is seen the apparatus by which the currents are transmitted; it is in duplicate, because the pendulum beats seconds, and it is desired to send the current every second. Each apparatus is composed of three identical pieces; three small levers are placed side by side, pivoted at their farthest ends. Their end *i* is raised by the arm v carried by the pendulum at each of its oscillations. During all the time which this contact lasts, the current of a battery passes by the suspension of the pendulum to the arm which carries the three screws and the three levers which conduct it to the line. With a single lever there would be danger of interruptions by a grain of dust; with three, contact and transmission of the current are absolutely assured. From the Observatory two wires set out; no use is made of the return earth current. The wires are entirely in the drains, like those of the Telephone Company. Fig. 3 shows these two circuits, each of



FIG. 1.—Regulator of Paris Observatory.

which is attached to the Observatory by its two extremities. These lines pass by a series of points and traverse the regulators, of which we shall now speak, and which are called horary centres. The pendulum of each regulator (Fig. 2) presents at its lower part a piece of soft iron, which in the oscillations of the pendulum is brought in front of the poles of two electro-magnets in succession. The transmission of the current into these electro-magnets tends to retard a little the movements of the pendulum, and causes each to be perfectly synchronous with that of the Observatory. The regulators of the horary centres show the second; they are placed in the street, and consequently in view of the passers-by, who may thus compare their watches. Watchmakers may also thus obtain the exact time without making a journey to the Observatory. They are placed in several prominent buildings in various convenient centres.

Why these regulators are called horary centres is explained thus: upon the circuit of horary centres spoken of above, and which the accompanying plan (Fig. 3) indicates by a black line, is grafted another accessory, called the transmission of the hour. Each regulator of the main circuit is itself the centre of a less extensive network of wires, which transmit the hour to the public clocks. For this second service no unique system has been adopted, and uniformity has not been aimed at. Several of the principal watchmakers of Paris, inventors each of a special method of transmitting the hour, are authorised to apply it to the clocks of which they have the care, by borrowing the hour and the current from the nearest horary centre. The most interesting horary centre is that installed at the Hôtel de Ville (at present the Tuileries), and which radiates to the twenty *mairies* of Paris. The city has a telegraphic communication which places the Prefecture of the Seine in connection with the twenty *mairies*. The wires of this system are interrupted about two minutes every hour to place the clock of each *mairie* into agreement with the regulator (horary centre) of the Hôtel de Ville as follows. Beside the regulator are placed twenty relays, into which it sends every hour a current, which cuts off the line from the telegraph; this commutation is made 100 seconds before the hour. The same regulator, about twelve seconds before the hour, sends the current from a second battery along



FIG. 2.—Regulator of the Horary Centre.

the lines; it interrupts it at the hour precisely. Ten seconds after the hour the relays are restored to their normal position by the suppression of the first current; that is to say, the lines are restored to the telegraph.

On the other hand sixty-five seconds before the hour each *mairie* clock makes its commutation, *i.e.* cuts off the line from the telegraph and connects it with the electro-magnet of the clock. And five seconds after the hour it makes the inverse commutation and restores the line to the telegraph five seconds before the resumption of the line by the telegraph at the horary centre of the Tuileries. As the clocks are thus regulated every hour their errors are extremely small. If however a clock gets suddenly out of order or stops, what happens? The current of the horary centre is sent into the telegraph of the *mairie* for thirty seconds cc[illegible] this abnormal fact announces at once to t[illegible] that the clock is out of order, and he may [illegible]ave it set right.

In the other hora[illegible]anisation is less

complicated; it is provided for only six lines, but on each of these may be placed several clocks. The lines are shorter, and radiate only in the quarter which surrounds the horary centre; but they are special to the service of



FIG. 3.—Telegraph for the Unification of Time in Paris.

clocks, and are not subject to the complicated operation which is necessary on the circuit of the *mairies*. This service has been organised under the direction of the City Engineers, and does them the highest credit; no doubt it will be gradually developed, so as to include the whole of the *mairies* of Paris.[1]

NOTES

THE honour of knighthood is to be conferred on Dr. James Risdon Bennett, F.R.S., President of the Royal College of Physicians.

M. MARCEL DESPREZ, the well-known electrician, has been created a Knight of the Order of the Legion of Honour.

THE first volume of the U.S. Geological Survey, issued under the headship of Mr. Clarence King, is a magnificent quarto by Prof. O. C. Marsh:—"Odontornithes: a Monograph on the Extinct Toothed Birds of North America"; with thirty-four beautifully executed plates and forty woodcuts. We hope to refer in detail to Prof. Marsh's work very soon.

IN the House of Commons on Tuesday Mr. Shaw-Lefevre said that both the botanical and mineralogical collections have been already removed from the British Museum to the new Museum of Natural History at South Kensington, and are now being arranged there. It is expected that these collections will be open to the public on the next bank holiday—namely, Easter Monday, April 18.

THE Paris Exhibition of Electricity will contain a number of curiosities. M. Salignac will present to the Director-General a plan for cooking by electricity in the grill-room of the restaurant. This plan should provide useful work during the day for the magneto-electric machinery, and test its warming power. M. Michels, an American residing in Paris, has patented a revolving carbon which can be rolled like an ordinary conductor.

WE have now more detailed information about the earthquake which was felt in the Swiss Jura on January 27 at 2h. 18m. p.m. There were two shocks at an interval of five seconds. They were felt especially at Berne, where several chimneys were thrown down, the bell of a church sounded, and the ceiling of a school fell down. At St. Imier the shocks were also rather strong. They were felt also at Neufchâtel, Corcelles, Fontaines, Colombier, Auvernier, and Chaux-de-Fonds to west; at Morges (but not at Lausanne) to south-west; at Solothurn, Basel, and Zürich to north and north-east; and at Signau, Hüttwyl, Berthoud, and Thoune to south and south-east. Two smaller shocks were felt: one on the same day at six o'clock in

[1] From an article in *La Nature*, by M. A. Niaudet.

the evening, and the other at three o'clock on the morning of the following day.

SHOCKS of earthquake were noticed at Baraccone, Italy, on January 31, at 8.30 p.m.; at Fiume, Hungary, on the night of January 3-4, at 2.26, direction, north-east to south-west, duration, two to three seconds; in Upper Italy, *e.g.* at Ancona, on the night of January 3-4.

THE incredulity with which the news about an earthquake at St. Petersburg was met in some quarters, when M. Wagner described it some years ago in consequence of quite unusual oscillations of the level of his transit-instrument at Pulkova, seems to be unfounded. We learn from Russian papers that on January 26, at 2.15 p.m., an earthquake was felt at Narva and at the Korff railway station, as well as on the estates of Lagen and Repnik, seven and eight miles distant from Narva. At all these places it was accompanied with a subterranean noise.

AT the Observatory of Pawlowsk, Russia, extraordinary magnetic perturbations (variations 2°) were noticed on the evening of January 31. On the same evening an auroral display was visible in different parts of the Russian Empire, *e.g.* in Western Siberia, at Ekaterineburg and Irbit (Ural), at Baltishport, and at Hasenpoth.

ON Saturday evening last the President of the French Republic, accompanied by all the members of the Government, visited the Paris Bourse in order to witness some experiments with Mr. Graham Bell's photophone. M. Antoine Breguet began by explaining the principles of the wonderful invention, after which experiments were made over a distance of fifty metres, by means of an electric light produced by a Gramme machine and a Serrin lamp.

M. BOGDANOFF, who took part in the Russian North Sea Expedition sent out during last summer, communicated, at the general meeting of the St. Petersburg Society of Naturalists, his observations on the influence of whaling on the fishing on the Normannic coast, which illustrates very well the complicated chain which exists in the animal world. The whale used to be very important to the fisheries, as during the spring it drove to the coast immense shoals of small fishes. Now, whaling being pursued by means of steamers which use a bullet instead of the old harpoon, and the annual number of whales killed being, during the last seventeen years, from 50 to 143, the amount of small fishes coming to the coast has much diminished. Besides, the great quantities of fat which are thrown into the sea at Varanger attract sharks, and these last destroy cod-fish, so that now the cod-fishing is nearly extinct in the western parts of the Varanger fjörd region.

MR. WALLACE in his "Island Life," pp. 495, 496, has discussed the apparent inability of Australian plants to become naturalised in the northern hemisphere. The gist of his explanation is the want of elasticity in their constitution, owing to their long-continued insular and uniform conditions of existence. The accompanying extract from the Report of the Government Gardens at Rangoon for 1880 points to the incapacity of even the vegetation of Tropical Australia to stand really humid climatic conditions:—"The Australian Eucalypti grew well during the dry weather, and some of them were four feet in height when the monsoon commenced; they then damped off one after another, as did also the Australian Acacias and the Queensland Ficus. The Moreton Bay Chestnut is not flourishing. From the above it will, I think, be evident that plants of Tropical Australia will not readily accommodate themselves to this very moist climate." It may be added that the result of attempting to grow species of *Eucalyptus* from all parts of Australia in the West African Settlements has uniformly failed, and apparently from the same cause.

SOME experiments have been made at the Cawnpore Experimental Farm during 1879-80 on the cultivation of imported English and American wheats and barleys. The result seems to point to the conclusion that the time available for the growth of cereals in India is too short to allow of English and American varieties being grown with success unless possibly the seed is sown in September and runs a risk of being damaged by excessive heat. Experimental sowings were made of three kinds of English and three kinds of American wheat, as well as of three kinds of barley. All nine sowings were complete failures. The seeds in most cases germinated freely, and the plants spread out into stools in a manner very different to the habit of country wheat. But all crops grew extremely slowly, and were still green when native wheat had finished ripening. In consequence the hot winds of March completely shrivelled up whatever grain had been formed, and no crop worth the name was gathered.

THE Manchester Field Naturalists' Society has recently attained its majority, and the event has been marked by a social meeting of past and present members in honour of the founder, Mr. Leo Grindon, author of "Manchester Walks and Wild Flowers," &c. In 1860 Mr. Grindon gathered around him a company of friends wishful to make some acquaintance with nature, and fortnightly summer excursions were established under his pleasant guidance. A prominent feature of the Society's proceedings has been the winter *soirées*. Now that the possibility of establishing a successful society, whose aspirations may be thought by some incompatible with commercial pursuits, has been demonstrated, the executive will do wisely to thoughtfully extend their operations in the direction of the Society's aims. Some attention has been paid to such practical matters as tree-planting in towns and window-gardening, and the discussion of such questions will tend to give a firmer hold upon public favour. Lancashire contains an unusual number of field-clubs, some of which have been inspired by this Society, whilst others were earlier in existence. In one of his letters the late Mr Carlyle laments that "for many years it has been one of my constant regrets that no schoolmaster of mine had a knowledge of *natural history*, so far at least as to have taught me the grasses that grow by the wayside, and the little winged and wingless neighbours that are continually meeting me with a salutation which I cannot answer." Had he been a native of Lancashire he would have found many instructors willing to read him the lessons of the wayside.

ON the 9th inst. the Dundee Naturalists' Society held their sixth annual *conversasione*, which seems to have been quite successful. All sorts of scientific *matériel* were exhibited, and among other lectures given was one by Dr. McIntosh of Murthly on Sponges. This society is evidently in a flourishing condition, and is no doubt doing something to create an interest in science in the important seaport in which it is located.

MR. QUARITCH has just issued the second part of his new Catalogue of Works on Natural History. It seems to contain a large number of very scarce and valuable works.

A FEW months ago three large blocks of petrified wood were found in the Devonian bed at Döppersberg, Germany. They were recognised by Prof. Göppert of Breslau as belonging to a fossil Araucaria, named by him *Araucarites Elberfeldensis* (Döppers).

THE Baltic Centralverein für Thierzucht und Thierschutz will hold its third exhibition of domestic birds on March 11-13 at Greifswald. In addition the exhibition will include living and dead freshwater and marine fish, fish embryos, &c., and all apparatus pertaining to pisciculture and fishing.

AN important step has been attained in telephony by Dr. Cornelius Herz, by which the principle of magnetism has been entirely discarded and the magnetic receiver abolished. A long series of experiments have been successfully conducted under the patronage of the French Government on the telegraphic lines of the State; concluding trials were witnessed, among others, by M. Cochéry, Minister of Postal Telegraphy, M. Jules Ferry, Prime Minister, M. Leon Say, President of the Senate, M. Becquerel, and other Members of the Academy of Sciences, and other Members, Senators, Deputies, and a great number of engineers. One of the most extraordinary experiments was the transmission of speech on a single wire from Tours to Brest, on a wire passing through Paris, the length of which exceeded eight hundred miles. One single Leclanche's element was the sole battery in use.

SOME dredging work which is going on at Zürich in the bed of the Limmat has brought to light the shore pillars of a Roman bridge, as well as the skeleton of a prehistoric stag.

INTERESTING new discoveries have been made at Pompeii. In block 7 of the 9th district a house has been excavated which was in course of construction when the terrible catastrophe occurred, and which differs materially from all other Pompeiian houses in its plan. In another house a large square piece of black glass was found fixed into the wall, which when slightly moistened forms the most perfect mirror. In a third house various wall-paintings were discovered, which however are rather of artistic than scientific interest.

THE newly-elected Municipal Council of Paris has been summoned by the Prefect of the Seine for a session which will begin on the 11th inst. It is stated that one of the proposals made will be to establish in Paris a system of police telephonic stations, as practised in Chicago.

M. JULES FERRY has created a library for patients in every hospital in Paris. The system will be extended to the whole of France.

AT the meeting of the Royal Academy of Sciences at Berlin on January 27 last, the year's report (for 1880) for the Humboldt Institution for Natural Research and Travels was read. Prof. du Bois Reymond, in conjunction with Prof. G. Fritsch, is about to publish the observations and experiments made by the late Dr. Karl Sachs on *Gymnotus electricus* in South America during 1876 and 1877, by order of the Institution. The present traveller of the Institution, Dr. Otto Finsch, after staying for nearly a year upon Talint Island (one of the Marshall group) proceeded to Matupi (on the north coast of New Britain) at the end of last year. His last letter is dated October 27, 1880, and he announces that he has made rich zoological collections. He intended to visit New Ireland and New Guinea if possible, and then to return to Europe by way of Dutch East India. Four of Dr. Finsch's collections have arrived at Berlin; a fifth is announced by his first letter from Matupi. The funds of the Institution have been increased by small legacies. The sum which will be at the disposal of the Institution for 1881 is 12,750 marks (635*l.*)

THE Sydney correspondent of the *Colonies* writes:—"We have long had in Sydney splendid botanical gardens, containing the choicest plants in the world, but we have only recently started a 'Zoological Gardens,' though Melbourne has had one many years, which has been brought to a high degree of perfection. Last week a deputation waited on our Colonial Secretary, asking for funds to stock the Gardens. Sir Henry Parkes replied that if the members of the Zoological Society would undertake next year to put as many animals in the grounds of the Sydney Zoological Gardens as they have in Melbourne, he would guarantee them 10,000*l.* from the Government. The offer was not accepted."

THE *Chrysanthemum* is the title of a monthly magazine "for Japan and the Far East," the first number of which has been sent us. The contents are mostly of a literary character, the main object of the magazine being "to aid in bringing the pales of Eastern and Western thought into such contact as may result in the diffusion of a general warmth and light around us." The publishers are Kelly and Co. of Yokohama, the English agents being Trübner and Co.

A SKELETON of a mammoth has been discovered at Bendery, Government of Bessarabia, in the upper clay drift.

THE St. Petersburg Society of Naturalists has already 276 Fellows; the Mineralogical Society has 398 members.

THE Commission of Fisheries of the United States have sent a quarter of a million ova of the American whitefish to Bremen, *en route* for the Lake of Constance, where the attempt to acclimatise this fish is to be made.

THE centenary of the birth of the philosopher Karl Christian Friedrich Krause will be celebrated on May 6 next at his birthplace, Eisenberg (Saxe-Altenburg). At the same time a simple monument with a bronze bust of Krause will be unveiled. The design is by Herr Enger of Altenburg, the bust by Robert Henze of Dresden. A Krause Scholarship has also been established at the Gymnasium.

WE have on our table the following books:—"Practical Plane Geometry," John W. Pallister (Simpkin); "Introduction to Study of Indian Languages," J. W. Powell; "Journal of Iron and Steel Institute, 1880" (Spon); "Practical Botany," D. Houston (W. Stewart); "Popular Scientific Lectures," 2nd series, Helmholtz (Longmans); "The Evolutionist at Large," Grant Allen (Chatto and Windus); "Journal of Royal Society of New South Wales;" "Extinct British Animals," J. E. Harting (Trübner); "Calendar of University of Wales, 1880-81;" "The Silk Goods of America," 2nd edition, W. C. Wyckoff; "London Catalogue of British Mosses" (Bogue); "The Statistical Atlas," part 1, G. P. Bevan (W. and A. K. Johnston); "Kamelaroi and Kurnai," Fison and Howitt (Macmillan and Co.); "Meeresfauna," K. Möbius (Otto Enstin); "Annuaire pour l'an 1880" (Villars, Paris); "A Polar Reconnaissance," A. H. Markham (Kegan Paul); "Natural History of British Fishes," Frank Buckland (S.P.C.K.); "Ventilation and Heat," Frederick Edwards (Longmans); "Practical Physics," A. H. Worthington (Rivington); "Muscles and Nerves," Dr. T. Rosenthal (Kegan Paul); "Natural Philosophy Examination Papers," Rev. G. Molloy (Browne and Nolan); "On some Properties of the Earth," O. Reichenbach; "Evolution, Expression, and Sensation," John Cleland (Maclehose, Glasgow); "The Wild Coast of Nipon," Capt. H. C. St. John (Douglas).

OUR ASTRONOMICAL COLUMN

THE SO-CALLED NOVA OF 1600.—Referring to a note which recently appeared in this column on "Janson's Star of 1600," Prof. van de Sande Bakhuysen, Director of the Observatory of Leyden, writes us that "Janson or Gulielmus Jansonius is Willem Jansz Blaeu, who is well known as the maker of globes, which are now very rare, and as editor of a treatise on the use of globes, of different treatises on navigation, and of a great number of charts and different atlases. From 1598 till his death in 1638 he lived in Amsterdam. Janson signifies that he was the son of Jan (John), but his family name was Blaeu." This explanation will be acceptable to those who may have been perhaps somewhat in doubt as to the correct form of identifying the discoverer of the variable star of 1600; Kepler styled him Jansonius, without reference to what Prof. Bakhuysen states to have been his surname: and he is frequently called Jansen. Lalande refers to the globes constructed by Blaeu as the best of the period, and the fact of his remarking the star in question, of which there is no previous mention, proves that he was a careful

observer of the heavens. In the *Bibliographie Astronomique* we find an astronomical work printed in 1625, attributed to him as Willem Jansz Blauw.

It will be seen from the works of Kepler and Cassini that Blaeu's star (34 Cygni of our present catalogues) at no time rose higher than the third magnitude, though even Mädler (*Populäre Astronomie*) has so far overlooked its history as to tell us "it reached the first magnitude"; and he attributes its discovery to Kepler.

THE "ASTRONOMISCHE NACHRICHTEN."—Contrary to what has been lately stated, it appears that this periodical will still be edited by Dr. C. F. W. Peters, who has for some time conducted it, and we are informed there is a probability that Prof. Krüger may set afloat a new astronomical journal under his own management. Whether the multiplication of high-class astronomical journals to the extent we are likely to witness is a practical advantage may perhaps be doubtful. For many years the *Astronomische Nachrichten* contained almost all that bore upon the progress of exact astronomy; *sed tempora mutantur, et nos mutamur in illis.*

THE COMET 1880 *e* (SWIFT, OCTOBER 10).—The completion of the mounting of the large Merz-Repsold refractor at the Imperial Observatory, Strassburg, enabled Prof. Winnecke to observe this interesting comet as late as January 26, when unfavourable weather interfered, and he was not without the hope that it would be within reach after the next period of absence of moonlight. Even if this should not prove to have been the case, there will be more than fifteen weeks' observations available for the determination of the actual orbit of the comet, affording every reason to expect that its track in the heavens nearly eleven years hence, or at its next visible return, may be pretty closely predicted. The following positions are deduced from MM. Schulhof and Bossert's last elements:—

At Greenwich midnight

1881.	R.A. h. m. s.	Decl. ° ′	Log. distance from Earth.	Sun.
Feb. 14	6 42 20	+21 21·4	9·9007	0·2147
16	6 44 54	21 10·4	9·9158	0·2192
18	6 47 29	20 59·8	9·9307	0·2236
20	6 50 5	20 49·7	9·9454	0·2280
22	6 52 41	20 39·9	9·9600	0·2323
24	6 55 18	+20 30·4	9·9745	0·2366

Prof. Winnecke reports that the Merz-Repsold refractor is a great success; *Mimas* is an easy object, and it may be hoped that the observation of the nebulæ, to which it is understood the instrument is to be chiefly directed, may not preveat attention being given to the closest of Saturn's satellites.

THE PERSEIDS IN AUGUST, 1880.—M. Baillaud, Director of the Observatory of Toulouse, has published the results of the watch for meteors, maintained by three observers on the nights of August 9, 10, and 11 in the past year: 1172 shooting-stars were observed, and 83 of the longest tracks were traced upon a chart; generally the tracks were very short, and their extremities pretty distant from the radiant. The meteors appeared to diverge from two points—the more numerous group from R.A. 42° 37′, Decl. 56° 39′; and a group of about one third the former, from R.A. 60° 39′, Decl. 62° 4′. The maximum occurred on August 10, between 14h. and 15h., in which interval 200 meteors were noted.

PHYSICAL NOTES

M. WIESNEGG has lately constructed for M. d'Arsonval a new steam-pressure regulator which deserves notice. It fulfils, according to the inventor, the following conditions:—(1) It maintains a perfectly constant pressure of steam in a boiler, whatever the actual output; (2) it maintains the consumption of fuel at a rate proportional to the output of steam; and (3) it is absolutely automatic, and therefore prevents all risks of explosion. This regulator is of very simple construction. A lead pipe from the boiler leads to a little apparatus somewhat resembling an ordinary lever safety-valve, but in which the valve-plug, instead of fitting into the usual conical seat, rests upon a thin disk of india-rubber. This disk rises when the pressure from below exceeds the downward pressure of the plug and the superincumbent lever, and of the weight which it carries. It cannot get hot, as it is far from the boiler, and the space below the disk is filled with water condensed from the steam. The upper surface of the valve-plug regulates by its movement the flow of gas, which comes in and goes out by two pipes leading to the upper part of the regulator. One of these comes from the gas mains, the other goes out to the burners under the boiler. By this arrangement, whenever the pressure in the boiler reaches any desired maximum, the apparatus itself reduces the supply and turns down the flame, thus maintaining the pressure constant and the consumption proportional to the output of vapour. It will be seen that the invention is only applicable to the case where the fuel employed is gas. The apparatus is also in itself an automatic safety-valve, putting out the fire when the pressure exceeds the limit. M. Wiesnegg has had practical experience during three years of the working of the new regulator, which appears to leave nothing to be desired in its performance. The same gentleman has constructed a constant-pressure air-blast on the same principle.

PROF. CASSANI invites attention in the *Rivista Sci. Ind.* (November 30) to some singular phenomena of geometrical optics, thus indicated:—The real images, presented by a concave mirror or by a convergent lens, of a plane or spherical mirror, a lens or a prism, may by a suitable arrangement be made to appear like a real mirror, lens, or prism respectively. An observer stands opposite a concave mirror supported (with slight slant) at a distance greater than the radius of curvature, and receiving no other light than that reflected from his face (illuminated by a dark lantern). A small plane mirror placed in a position nearer the concave mirror than the observer, and sloping in opposite direction (it is concealed from his eye). The effect is that, on looking obliquely upwards, the observer seems to see a plane mirror (which is of larger size than the other) with his direct image in it. The illusion is the more complete if the actual plane mirror have an ornamental frame, and this be illuminated by a special lamp. As the image in the ideal mirror is always rather small and too near the mirror, this may arouse suspicion, the more so when the image is seen to diminish on receding and increase on advancing; but a person not familiar with the phenomena of concave mirrors may easily be deceived, thinking he sees a real mirror.

IN the *Proc. R.S.E.* Sir W. Thomson describes a thermo-magnetic thermoscope of an ingenious nature. It is well known that the "permanent" magnetism of steel magnets is not constant, but changes slightly with changes of temperature, the magnet becoming weaker when warmed, and recovering its strength as it is cooled. The magnetic thermoscope is intended to indicate differences of temperature by showing differences between the magnetic moments of steel magnets. Two thin wires of hard steel, each one centimetre long, are arranged so as to form a *nearly* astatic couple, being magnetised to equal strength and set in opposite directions, but not quite parallel, so that they set at right angles to the magnetic meridian. Two other magnets, about twice the size of the former pair, are placed one on each side of this astatic couple as "deflectors," being laid in one line nearly along the magnetic meridian, with their similar poles facing one another at about two centimetres apart. When properly adjusted the little astatic pair suspended between them will be found to be excessively sensitive to the least change in the strength of either of the deflectors, and if they are at different temperatures will turn through an angle which if small may be regarded as a measure of the temperature-difference. A small mirror suspended from the lower needle of the pair serves to reflect a spot of light on to a scale in the usual way.

IN 1870 and 1871 MM. Leverrier and Crova experimented with an optical telegraph between Nîmes and Redessan. Their system of signals were made by means of oil lamps or petroleum lamps fed by oxygen from a supply that could be turned on or off at will by an operator, who thus produced intermittent brilliant outbursts of flame according to a pre-arranged code. During December, 1880, a similar device was conceived by M. Mercadier, against whom M. Crova now reclaims the essential principles of his invention. He adds that two of the requisites of success lay in the use of oxygen under *very low pressure*, feeding the flame by an orifice in the midst of the flame, and in the employment of keys opening and shutting the gas-passages very suddenly by means of strong springs, without which the changes in the intensity of the flame go on too slowly to be comfortably observed. In the experiments of 1870-71 the lights at Nîmes were visible at Redessan and *vice versâ*, even in broad daylight. The oxygen supply was contained in ordinary gas bags of caoutchouc and prepared in the usual manner.

ONE of M. Mercadier's recent experiments in radiophony deserves a note. A disk of thin copper about 4 centims. in diameter, heated at its back by an oxyhydrogen blowpipe, was placed behind a rotating wheel with apertures, and the intermittent heat-rays were received upon one of his sensitive disks of thin metal blackened at the surface. With a bright red heat the customary note was well heard from the intermittent beams. On putting out the flame the sound gradually fell off in intensity, but was still audible after the copper disk had ceased to emit visible rays. All that this experiment proves, however, is that the dark rays, when they fall intermittently upon an absorbent surface, can cause it to undergo rapid expansions and contractions; while Graham Bell's earlier experiment showed that visible rays could produce this result.

M. CORNU discusses in the *Comptes rendus* the propositions of M. Gouy concerning the velocity of propagation of light proceeding from a source of variable amplitude, on which we lately published a note. He denies the truth of M. Gouy's fundamental assumptions, and concludes that since all our appliances can only change the amplitude of the waves by quantities which may be regarded as constant during a great many successive waves, the formula of waves of persistent type will still hold good, and the velocity of propagation of the amplitudes will be identical with that of the waves themselves.

M. CHAPPUIS thinks that the blue of the sky may be due to ozone present in the upper regions of the air. He argues that the electrical discharges constantly taking place will produce ozone; and the recent researches of himself and M. Hautefeuille have shown that ozone, at any rate when near its condensation point, is of a blue tint. He has examined the absorption-spectrum of ozone and finds nine dark bands in it, three at least of which correspond with known bands in the telluric spectrum.

TO obtain enlarged impressions from the phonograph, MM. Roig and Torres (*Cronica científica*, No. 4) substitute for the metallic membrane which bears the indenting style a plate of mica, quite free at the border, and supported at the centre by an axis of caoutchouc fixed to a small spring. This axis carries, besides the short style for acting on the tin sheet, a small metallic piece in a plane perpendicular to the axis of the style, and this supports a second style, long and thin, the vibrations of which are inscribed on a cylinder blackened with smoke. The same angular velocity is imparted (by means of clockwork) to the cylinder of the phonograph and the blackened cylinder, and while the short style makes its usual marks on the tin, the long one produces a larger tracing on the cylinder, which the authors have tried to decipher. They have succeeded easily in recognising the different vowels, some consonants, and even some syllables, but they have not been able to read entire phrases. The curves are more characteristic if the voice be used with ordinary intensity; on forcing it they are deteriorated.

PROF. AVENARIUS, of Kiew, has taken out an Austrian patent for a new method of division of the electric light. The method is that of insertion of a polariser in a secondary circuit, connected with each electric lamp. The polariser, consists of several voltameters connected together. The current, supplied by an electrodynamic machine, divides before entering each lamp: one part goes through the lamp, while the second goes through the secondary circuit and the polariser and then back to the primary circuit. By insertion of a considerable resistance, *e.g.* increase of the voltameters, the light-intensity of the lamps may be varied. The individual lamps are independent of each other, and lamps of different systems may be simultaneously used.

WE notice in the minutes of meetings of the Russian Physical and Chemical Society (vol. xii. fasc. 9) the researches, by M. Glasenap, on refraction. The want of concentricity of sheets of air of equal density produces a certain variation in the normal refraction given in the tables; the surfaces of equal density being as a rule inclined to some degree instead of being horizontal, and the degree of inclination being submitted to a certain periodicity during a whole year, there necessarily arises from this cause a certain correction to be applied to the observed position of a star, much like to that of the annual parallax and aberration, and which might be described as "parallax of refraction." As this correction must obviously affect the values of the annual parallax and of aberration, it is easy to understand the necessity to determine its true value with much accuracy. The values deduced by M. Glasenap for the stars ι of the Ursæ Majoris, ι and O Draconis, are $-0''{\cdot}04$, $-0''{\cdot}11$, and $-0''{\cdot}11$, which figures would explain to a certain extent the negative parallaxes received by M. Nyrén ("Nutation der Erdaxe"), and which respectively are $-''{\cdot}03$, $-0''{\cdot}05$, and $-0''{\cdot}16$. The whole work of M. Glasenap on this subject will soon be published.

CHEMICAL NOTES

THE influence of time on processes of chemical change has not yet been thoroughly investigated. In a recent number of *Comptes rendus* Berthelot makes a contribution to this subject which is scarcely likely to be accepted by chemists without further investigation. From the results of many thermo-chemical measurements Berthelot states that the chemical change, which occurs when an acid soluble in water acts on a soluble base or salt, or *vice versâ*, or when two soluble salts mutually react, is completed in a space of time not appreciably greater than that required for completely mixing the two solutions.

FROM experiments on the evolution of carbon dioxide from the roots of plants, detailed in the *Bull. de la Soc. botanique de France*, M. Cauvet concludes that carbon dioxide is certainly evolved from plant-roots; that the quantity evolved is less during night than during day; and that the quantity evolved increases at sunrise, decreases towards midday, and again increases in the evening.

HERR SALLERON describes in *Naturforscher* an instance of the modifying influence of moderately heated liquids on glass. An aræometer used in a sugar-work lost about 0·5 grm. in weight after immersion for eight days in a sugar syrup at 95°. The syrup contained 115 grm. sugar and 91 grm. ash per litre. After a few more days the glass split off in splinters.

MR. A. A. NESBIT has recently patented a very ingenious process for preventing fraudulent alterations of bankers' cheques. Mr. Nesbit prints his cheques with a dye or dyes, the colour of which is differently changed by acids and by alkalies; the inscriptions on the cheques are apparent by virtue of the alkalinity or acidity of the dye. Immersion in dilute acid—for the purpose of dissolving out the written part of the cheque—causes the whole inscription to become acid tint; as subsequent treatment with alkali changes the whole inscription to alkaline tint, the original inscription cannot be restored. If the acid part of the inscription be printed with a dye which is more strongly acid than the alkaline part is alkaline, treatment of the cheque with a neutral solvent of writing ink suffices to blur the inscription, and this blurring cannot be removed. Various modifications of the invention, and details of the processes of printing, colours used, &c., are given in the specification.

M. ÉTARD thinks that boron shows certain analogies with vanadium; in endeavouring further to illustrate such analogies he has obtained indications, although not yet positive proof, of the existence of an acid containing more oxygen than boric acid. He has also obtained, by the action of a saturated solution of boric acid on hydrated barium dioxide, a salt to which he gives the formula $B_2O_4 . BaO . 3H_2O$, and the name *barium perborate*. This salt dissolves in acids with evolution of oxygen; it is very deliquescent (*Compt. rend.*).

IN continuation of his investigation into the compounds of sulphur and nitrogen M. Demarcay describes (*Compt. rend.*) various bodies which he regards as compounds of the radicle—$(S_4N_3)'$—called by him *thiotriazyl*. The more important of the new compounds are formulated as $(S_4N_3)Cl$, $(S_4N_3)NO_3$, and $(S_4N_3)HSO_4$.

LIEBEN describes (in *Wien. Akad. Ber.*) several compounds of calcium chloride with fatty acids, more especially the three compounds with butyric acid, viz.:—

$$CaCl_2 . C_4H_8O_2;\ CaCl_2 . 2C_4H_8O_2 . 2H_2O;\ \text{and}$$
$$CaCl_2 . Ca(C_4H_7O_2)_2 . 4C_4H_8O_2.$$

M. BYASSON states (*Compt. rend.*) that if every trace of sulphurous acid be removed from chloral, the latter retains its liquid condition for an indefinite time, and that the change into solid metachloral, which soon takes place in chloral purified only by distillation, may be thus prevented. To remove the last traces of sulphurous acid M. Byasson agitates the chloral with $\frac{1}{10}$ of its weight of finely-powdered caustic baryta, decants the liquid, and distils.

BERTHELOT has recently succeeded in isolating several compounds of metallic chlorides with hydrochloric acid; in *Compt. rend.* he describes three such chlorhydrates of metallic chlorides, viz. :—

$CdCl_2 . 2HCl . 7H_2O$; $PbI_2 . HI . 5H_2O$; and $3AgI . HI . 7H_2O$;

and in another number of the same journal M. Ditté describes, among others, the salts $BiCl_3 . 3HCl$; $SbCl_3 . 3HCl$, &c. These hydrated salts are formed from their constituent compounds with a considerable evolution of heat, the amount varying from 11,000 to 15,000 units. The anhydrous salts readily undergo dissociation into their constituent compounds, and cannot therefore be readily obtained. Berthelot regards the formation and dissociation of these chlorhydrates as playing an important part in the mechanism of many chemical changes. Thus calomel is changed into corrosine sublimate and mercury by the action of hydrochloric acid: Berthelot would formulate this change as $Hg_2Cl_2 + x HCl = HgCl_2 . x HCl + Hg$ (attended with evolution of 9500 heat-units), with subsequent dissociation of the chlorhydrate of $HgCl_2$. Again in the reduction of metallic chlorides by hydrogen Berthelot supposes that chlorhydrates are produced, and that the heat thus developed aids in dissociating fresh quantities of the original metallic chloride; thus he would indicate the initial stage of the reduction of cadmium chloride by hydrogen, as :—

$$2CdCl_2 + H_2 = Cd + CdCl_2 . 2HCl.$$

M. WURTZ has recently been studying (*Compt. rend.*) the action of the ferment *Papaïn* on fibrin, whereby the fibrin is rendered soluble in water. The process appears to be analogous with many ordinary chemical changes in which the formation and decomposition of a compound are continually proceeding. Papaïn forms an insoluble compound with fibrin, which compound is then decomposed by the water present with formation of a soluble hydrated fibrin, and setting free of the ferment, which again acts on fresh quantities of fibrin.

IN the *American Chem. Journ.* Clarke and Stallo describe a series of experiments on the tartrates of antimony, wherein they are led to regard tartar emetic as the potassium salt of a new acid, to which they give the name *tartrantimonious*, viz. $Sb . C_4H_4O_6 . OH$. This acid they regard as derived from orthantimonious acid, $Sb(OH)_3$, which they have prepared in definite form. The behaviour of an aqueous solution of tartrantimonious acid towards heat is peculiar. Below 30° the solution remains nearly clear; at a few degrees above 30° a white curdy precipitate deposits; on evaporating in a water bath the curdy precipitate disappears and a transparent gummy mass remains, which is completely soluble in cold water, re-forming the original acid. These changes are shown to be expressible by the equations—

1. $C_4H_5SbO_7 + 2H_2O = SbH_3O_3 + C_4H_6O_6$; the curdy precipitate consisting of orthantimonious acid.

2. $C_4H_6O_6 + SbH_3O_3 = 2H_2O + C_4H_5SbO_7$; *i.e.* on heating, water is eliminated, and the original acid is reproduced.

IN a series of papers in the *Berliner Berichte* Th. Thomsen endeavours to show that the "molecular rotation" of many classes of compounds is, for each class, a simple multiple of a constant number. "Molecular rotation" he defines as rotatory power $\times \frac{\text{molecular weight}}{100} \left(\frac{M.(a)_D}{100}\right)$. The constant for one group appears generally to bear a simple relation to that for other groups; in fact a constant may be found which belongs to many groups. Adopting a classification analogous to that of natural history, Thomsen shows that the constant 0·95 belongs to a large "class" of compounds; that this multiplied by 4 gives the constant (3·8) for the "family" of alcohols, and by 9 gives the constant (8·65) for the "family" of amides, &c. From a determination of the molecular rotation of compounds, aided by the use of these constants, he attempts also to deduce conclusions as to the chemical structure of the molecules of these compounds.

IN various papers noticed in this journal, Brühl attempted to show that the "molecular refraction" $\left[M.\left(\frac{\mu - 1}{d}\right)\right]$ of isomeric carbon compounds is constant when only "singly-linked" carbon atoms are present; and that variations in this quantity are to be traced to variations in the "linking" of carbon atoms. Janowsky (*Berliner Berichte*) maintains that slight differences are always noticeable between the molecular refractions of isomeric compound where isomerism is due not to "linking," but to "grouping" of carbon atoms: but he thinks that if the values of the refractive indices of such compounds are considered, better results are obtained than by calculating the molecular refractions. Brühl however had himself shown that the refraction indices of such isomers are not the same.

LANDOLT has gathered together in *Berliner Berichte* the more important data concerning the inversion of specific rotatory power of carbon compounds by the influence of heat or of inactive solvents: those data he supplements by further experiments of his own, and develops shortly the outlines of a mechanical theory analogous to that of Rammelsberg.

THE atomic weight of beryllium is still the subject of experiment. Emerson Reynolds has redetermined the specific heat of the pure metal (*Chem. News*) and obtained a number which points to 9·1 as the true atomic weight. The same value is assigned by Brauner, who (*Berliner Berichte*) criticises the arguments of Nilson and Pettersson, and attempts to show that the specific heat, specific volume, and general physical properties of beryllium oxide are more in keeping with the formula BeO (Be = 9·1) than with the formula Be_2O_3 (Be = 13·6) assigned to it by the Swedish observers.

IN a paper on bismuth compounds in *Chem. Soc. Journal*, by Muir, Hoffmeister, and Robbs, the new salts bismuth fluoride (BiF_3) and bismuth oxyfluoride (BiOF) are described. The former is the more stable of the halogen compounds of bismuth: it is not decomposed by water, and is scarcely changed at a red heat in air.

PROF. BEILSTEIN, who has recently studied the various substances used for disinfection, arrives, in a communication made to the St. Petersburg Technical Society, at the following conclusions:—Sulphuric acid would be the best disinfectant if it did not destroy the sides of the tanks; the use of lime and of salts of lime ought to be completely renounced, as they but temporarily destroy bacteria, and under some circumstances may contribute to their development; nor does sulphate of iron, even in a solution of 15 per cent., ultimately destroy bacteria, as they revive when put into a convenient medium. Therefore Prof. Beilstein recommends sulphate of aluminium, which is used in paper and printed-cotton manufactures. The best means for providing it is to make a mixture of red clay with 4 per cent. of sulphuric acid, and to add to this mixture some carbolic acid for destroying the smell of the matter which is to be disinfected.

ACTION OF AN INTERMITTENT BEAM OF RADIANT HEAT UPON GASEOUS MATTER[1]

THE Royal Society has already done me the honour of publishing a long series of memoirs on the interaction of radiant heat and gaseous matter. These memoirs did not escape criticism. Distinguished men, among whom the late Prof. Magnus and the late Prof. Buff may be more specially mentioned, examined my experiments, and arrived at results different from mine. Living workers of merit have also taken up the question, the latest of whom,[2] while justly recognising the extreme difficulty of the subject, and while verifying, so far as their experiments reach, what I had published regarding dry gases, find me to have fallen into what they consider grave errors in my treatment of vapours.

None of these investigators appear to me to have realised the true strength of my position in its relation to the objects I had in view. Occupied for the most part with details, they have failed to recognise the stringency of my work as a whole, and have not taken into account the independent support rendered by the various parts of the investigation to each other. They thus ignore verifications, both general and special, which are to me of conclusive force. Nevertheless, thinking it due to them and me to submit the questions at issue to a fresh examination, I resumed some time ago the threads of the inquiry. The results shall in due time be communicated to the Royal Society; but meanwhile I would ask permission to bring to the notice of the Fellows a novel mode of testing the relations of radiant heat to gaseous matter, whereby singularly instructive effects have been obtained.

After working for some time with the thermopile and galvano-

[1] Paper read at the Royal Society, January 13, by Prof. Tyndall, F.R.S

[2] Lecher and Pernter, *Philosophical Magazine*, January, 1881; *Sitzb. der k. Akad. der Wissensch. in Wien*, July, 1880.

meter, it occurred to me several weeks ago that the results thus obtained might be checked by a more direct and simple form of experiment. Placing the gases and vapours in diathermanous bulbs, and exposing the bulbs to the action of radiant heat, the heat absorbed by different gases and vapours ought, I considered, to be rendered evident by ordinary expansion. I devised an apparatus with a view of testing this idea. But at this point, and before my proposed gas-thermometer was constructed, I became acquainted with the ingenious and original experiments of Mr. Graham Bell, wherein musical sounds are obtained through the action of an intermittent beam of light upon solid bodies.

From the first I entertained the opinion that these singular sounds were caused by rapid changes of temperature, producing corresponding changes of shape and volume in the bodies impinged upon by the beam. But if this be the case, and if gases and vapours really absorb radiant heat, they ought to produce sounds more intense than those obtainable from solids. I pictured every stroke of the beam responded to by a sudden expansion of the absorbent gas, and concluded that when the pulses thus excited followed each other with sufficient rapidity, a musical note must be the result. It seemed plain, moreover, that by this new method many of my previous results might be brought to an independent test. Highly diathermanous bodies, I reasoned, would produce faint sounds, while highly athermanous bodies would produce loud sounds; the strength of the sound being, in a sense, a measure of the absorption. The first experiment made with a view of testing this idea, was executed in the presence of Mr. Graham Bell [1]; and the result was in exact accordance with what I had foreseen.

The inquiry has been recently extended so as to embrace most of the gases and vapours employed in my former researches. My first source of rays was a Siemens' lamp connected with a dynamo-machine, worked by a gas-engine. A glass lens was used to concentrate the rays, and afterwards two lenses. By the first the rays were rendered parallel, while the second caused them to converge to a point about seven inches distant from the lens. A circle of sheet zinc provided first with radial slits and afterwards with teeth and interspaces cut through it, was mounted vertically on a whirling table, and caused to rotate rapidly across the beam near the focus. The passage of the slits produced the desired intermittence,[2] while a flask containing the gas or vapour to be examined received the shocks of the beam immediately behind the rotating disk. From the flask a tube of india-rubber, ending in a tapering one of ivory or boxwood, led to the ear, which was thus rendered keenly sensitive to any sound generated within the flask. Compared with the beautiful apparatus of Mr. Graham Bell, the arrangement here described is rude; it is, however, very effective.

With this arrangement the number of sounding gases and vapours was rapidly increased. But I was soon made aware that the glass lenses withdrew from the beam its most effectual rays. The silvered mirrors employed in my previous researches were therefore invoked; and with them, acting sometimes singly and sometimes as conjugate mirrors, the curious and striking results which I have now the honour to submit to the Society were obtained.

Sulphuric ether, formic ether, and acetic ether being placed in bulbous flasks, their vapours were soon diffused in the air above the liquid. On placing these flasks, whose bottoms only were covered by the liquid, behind the rotating disk, so that the intermittent beam passed through the vapour, loud musical tones were in each case obtained. These are known to be the most highly absorbent vapours which my experiments revealed. Chloroform and bisulphide of carbon, on the other hand, are known to be the least absorbent, the latter standing near the head of diathermanous vapours. The sounds extracted from these two substances were usually weak and sometimes barely audible, being more feeble with the bisulphide than with the chloroform. With regard to the vapours of amylene, iodide of ethyl, iodide of methyl and benzol, other things being equal, their power to produce musical tones appeared to be accurately expressed by their ability to absorb radiant heat.

It is the vapour, and not the liquid, that is effective in producing the sounds. Taking, for example, the bottles in which my volatile substances are habitually kept, I permitted the intermittent beam to impinge upon the liquid in each of them. No sound was in any case produced, while the moment the vapour-laden space above an active liquid was traversed by the beam, musical tones made themselves audible.

A rock-salt cell filled entirely with a volatile liquid and subjected to the intermittent beam produced no sound. This cell was circular and closed at the top. Once, while operating with a highly athermanous substance, a distinct musical note was heard. On examining the cell however a small bubble was found at its top. The bubble was less than a quarter of an inch in diameter, but still sufficient to produce audible sounds. When the cell was completely filled the sounds disappeared.

It is hardly necessary to state that the pitch of the note obtained in each case is determined by the velocity of rotation. It is the same as that produced by blowing against the rotating disk and allowing its slits to act like the perforations of a syren.

Thus, as regards vapours, prevision has been justified by experiment. I now turn to gases. A small flask, after having been heated in the spirit-lamp so as to detach all moisture from its sides, was carefully filled with dried air. Placed in the intermittent beam it yielded a musical note, but so feeble as to be heard only with attention. Dry oxygen and hydrogen behaved like dry air. This agrees with my former experiments, which assigned a hardly sensible absorption to these gases. When the dry air was displaced by carbonic acid, the sound was far louder than that obtained from any of the elementary gases. When the carbonic acid was displaced by nitrous oxide the sound was much more forcible still, and when the nitrous oxide was displaced by olefiant gas it gave birth to a musical note which, when the beam was in good condition and the bulb well chosen, seemed as loud as that of an ordinary organ-pipe. We have here the exact order in which my former experiments proved these gases to stand as absorbers of radiant heat. The amount of the absorption and the intensity of the sound go hand in hand.

In 1859 I proved gaseous ammonia to be extremely impervious to radiant heat. My interest in its deportment when subjected to this novel test was therefore great. Placing a small quantity of liquid ammonia in one of the flasks, and warming the liquid slightly, the intermittent beam was sent through the space above the liquid. A loud musical note was immediately produced. By the proper application of heat to a liquid the sounds may be always intensified. The ordinary temperature however suffices in all the cases thus far referred to.

In this relation the vapour of water was that which interested me most, and as I could not hope that at ordinary temperatures it existed in sufficient amount to produce audible tones, I heated a small quantity of water in a flask almost up to its boiling-point. Placed in the intermittent beam, I heard—I avow with delight—a powerful musical sound produced by the aqueous vapour.

Small wreaths of haze, produced by the partial condensation of the vapour in the upper and cooler air of the flask, were however visible in this experiment; and it was necessary to prove that this haze was not the cause of the sound. The flask was therefore heated by a spirit-flame beyond the temperature of boiling water. The closest scrutiny by a condensed beam of light then revealed no trace of cloudiness above the liquid. From the perfectly invisible vapour however the musical sound issued, if anything, more forcible than before. I placed the flask in cold water until its temperature was reduced from about 90° to 10° C., fully expecting that the sound would vanish at this temperature; but notwithstanding the tenuity of the vapour, the sound extracted from it was not only distinct but loud.

Three empty flasks filled with ordinary air were placed in a freezing mixture for a quarter of an hour. On being rapidly transferred to the intermittent beam, sounds much louder than those obtainable from dry air were produced.

Warming these flasks in the flame of a spirit-lamp until all visible humidity had been removed, and afterwards urging dried air through them, on being placed in the intermittent beam the sound in each case was found to have fallen almost to silence.

Sending, by means of a glass tube, a puff of breath from the lungs into a dried flask, the power of emitting sound was immediately restored.

[1] On November 29: see *Journal* of the Society of Telegraph Engineers, December 8, 1880.

[2] When the disk rotates the individual slits disappear, forming a hazy zone through which objects are visible. Throwing by the clean hand, or better still by white paper, the beam back upon the disk, it appears to stand still, the slits forming so many dark rectangles. The reason is obvious, but the experiment is a very beautiful one.

I may add that when I stand with open eyes in the flashing beam, at a definite velocity of recurrence, subjective colours of extraordinary gorgeousness are produced. With slower or quicker rates of rotation the colours disappear. The flashes also produce a giddiness sometimes intense enough to cause me to grasp the table to keep myself erect.

When, instead of breathing into a dry flask, the common air of the laboratory was urged through it, the sounds became immediately intensified. I was by no means prepared for the extraordinary delicacy of this new method of testing the athermancy and diathermancy of gases and vapours, and it cannot be otherwise than satisfactory to me to find that particular vapour, whose alleged deportment towards radiant heat has been most strenuously denied, affirming thus audibly its true character.

After what has been stated regarding aqueous vapour we are prepared for the fact that an exceedingly small percentage of any highly athermanous gas diffused in air suffices to exalt the sounds. An accidental observation will illustrate this point. A flask was filled with coal-gas and held bottom upwards in the intermittent beam. The sounds produced were of a force corresponding to the known absorptive energy of coal-gas. The flask was then placed upright, with its mouth open upon a table, and permitted to remain there for nearly an hour. On being restored to the beam, the sounds produced were far louder than those which could be obtained from common air.[1]

Transferring a small flask or a test-tube from a cold place to the intermittent beam it is sometimes found to be practically silent for a moment, after which the sounds become distinctly audible. This I take to be due to the vaporisation by the calorific beam of the thin film of moisture adherent to the glass.

My previous experiments having satisfied me of the generality of the rule that volatile liquids and their vapours absorb the same rays, I thought it probable that the introduction of a thin layer of its liquid, even in the case of a most energetic vapour, would detach the effective rays, and thus quench the sounds. The experiment was made and the conclusion verified. A layer of water, formic ether, sulphuric ether, or acetic ether one-eighth of an inch in thickness rendered the transmitted beam powerless to produce any musical sound. These liquids being transparent to light, the efficient rays which they intercepted must have been those of obscure heat.

A layer of bisulphide of carbon about ten times the thickness of the transparent layers just referred to, and rendered opaque to light by dissolved iodine, was interposed in the path of the intermittent beam. It produced hardly any diminution of the sounds of the more active vapours—a further proof that it is the invisible heat rays, to which the solution of iodine is so eminently transparent, that are here effectual.

Converting one of the small flasks used in the foregoing experiments into a thermometer bulb, and filling it with various gases in succession, it was found that with those gases which yielded a feeble sound, the displacement of a thermometric column associated with the bulb was slow and feeble, while with those gases which yielded loud sounds the displacement was prompt and forcible.

Further Experiments.—Since the handing in of the foregoing note, on January 3, the experiments have been pushed forward; augmented acquaintance with the subject serving only to confirm my estimate of its interest and importance.

All the results described in my first note have been obtained in a very energetic form with a battery of sixty Grove's cells.

On January 4 I chose for my source of rays a powerful lime-light, which, when sufficient care is taken to prevent the pitting of the cylinder, works with admirable steadiness and without any noise. I also changed my mirror for one of shorter focus, which permitted a nearer approach to the source of rays. Tested with this new reflector the stronger vapours rose remarkably in sounding power.

Improved manipulation was, I considered, sure to extract sounds from rays of much more moderate intensity than those of the lime-light. For this light, therefore, a common candle flame was substituted. Received and thrown back by the mirror, the radiant heat of the candle produced audible tones in all the stronger vapours.

Abandoning the mirror and bringing the candle close to the rotating disk, its direct rays produced audible sounds.

A red-hot coal, taken from the fire and held close to the rotating disk, produced forcible sounds in a flask at the other side.

A red-hot poker, placed in the position previously occupied by the coal, produced strong sounds. Maintaining the flask in position behind the rotating disk, amusing alternations of sound and silence accompanied the alternate introduction and removal of the poker.

[1] The method here described is, I doubt not, applicable to the detection of extremely small quantities of fire-damp in mines.

The temperature of the iron was then lowered till its heat just ceased to be visible. The intermittent invisible rays produced audible sounds.

The temperature was gradually lowered, being accompanied by a gradual and continuous diminution of the sound. When it ceased to be audible the temperature of the poker was found to be below that of boiling water.

As might be expected from the foregoing experiments an incandescent platinum spiral, with or without the mirror, produced musical sounds. When the battery power was reduced from ten cells to three the sounds, though enfeebled, were still distinct.

My neglect of aqueous vapour had led me for a time astray in 1859, but before publishing my results I had discovered my error. On the present occasion this omnipresent substance had also to be reckoned with. Fourteen flasks of various sizes, with their bottoms covered with a little sulphuric acid, were closed with ordinary corks and permitted to remain in the laboratory from December 23 to January 4. Tested on the latter day with the intermittent beam, half of them emitted feeble sounds, but half were silent. The sounds were undoubtedly due, not to dry air, but to traces of aqueous vapour.

An ordinary bottle containing sulphuric acid for laboratory purposes, being connected with the ear and placed in the intermittent beam, emitted a faint, but distinct, musical sound. This bottle had been opened two or three times during the day, its dryness being thus vitiated by the mixture of a small quantity of common air. A second similar bottle, in which sulphuric acid had stood undisturbed for some days, was placed in the beam: the dry air above the liquid proved absolutely silent.

On the evening of January 7 Prof. Dewar handed me four flasks treated in the following manner:—Into one was poured a small quantity of strong sulphuric acid; into another a small quantity of Nordhausen sulphuric acid; in a third were placed some fragments of fused chloride of calcium; while the fourth contained a small quantity of phosphoric anhydride. They were closed with well-fitting india-rubber stoppers, and permitted to remain undisturbed throughout the night. Tested after twelve hours, each of them emitted a feeble sound, the flask last-mentioned being the strongest. Tested again six hours later, the sound had disappeared from three of the flasks, that containing the phosphoric anhydride alone remaining musical.

Breathing into a flask partially filled with sulphuric acid instantly restores the sounding power, which continues for a considerable time. The wetting of the interior surface of the flask with the sulphuric acid always enfeebles, and sometimes destroys, the sound.

A bulb less than a cubic inch in volume, and containing a little water lowered to the temperature of melting ice, produces very distinct sounds. Warming the water in the flame of a spirit-lamp, the sound becomes greatly augmented in strength. At the boiling temperature the sound emitted by this small bulb[1] is of extraordinary intensity.

These results are in accord with those obtained by me nearly nineteen years ago, both in reference to air and to aqueous vapour. They are in utter disaccord with those obtained by other experimenters, who have ascribed a high absorption to air and none to aqueous vapour.

The action of aqueous vapour being thus revealed, the necessity of thoroughly drying the flasks when testing other substances becomes obvious. The following plan has been found effective:—Each flask is first heated in the flame of a spirit-lamp till every visible trace of internal moisture has disappeared, and it is afterwards raised to a temperature of about 400° C. While the glass is still hot a glass tube is introduced into it, and air freed from carbonic acid by caustic potash, and from aqueous vapour by sulphuric acid, is urged through the flask until it is cool. Connected with the ear-tube, and exposed immediately to the intermittent beam, the attention of the ear, if I may use the term, is converged upon the flask. When the experiment is carefully made, dry air proves as incompetent to produce sound as to absorb radiant heat.

In 1868 I determined the absorptions of a great number of liquids whose vapours I did not examine. My experiments having amply proved the parallelism of liquid and vaporous absorption, I held undoubtingly twelve years ago that the vapour of cyanide of ethyl and of acetic acid would prove powerfully absorbent. This conclusion is now easily tested. A small

[1] In such bulbs even bisulphide of carbon vapour may be so nursed as to produce sounds of considerable strength.

quantity of either of these substances, placed in a bulb a cubic inch in volume, warmed, and exposed to the intermittent beam, emits a sound of extraordinary power.

I also tried to extract sounds from perfumes, which I had proved in 1861 to be absorbers of radiant heat. I limit myself here to the vapours of pachouli and cassia, the former exercising a measured absorption of 30, and the latter an absorption of 109. Placed in dried flasks, and slightly warmed, sounds were obtained from both these substances, but the sound of cassia was much louder than that of pachouli.

Many years ago I had proved tetrachloride of carbon to be highly diathermanous. Its sounding power is as feeble as its absorbent power.

In relation to colliery explosions, the deportment of marsh-gas was of special interest. Prof. Dewar was good enough to furnish me with a pure sample of this gas. The sounds produced by it, when exposed to the intermittent beam, were very powerful.

Chloride of methyl, a liquid which boils at the ordinary temperature of the air, was poured into a small flask, and permitted to displace the air within it. Exposed to the intermittent beam, its sound was similar in power to that of marsh-gas.

The specific gravity of marsh-gas being about half that of air, it might be expected that the flask containing it, when left open and erect, would soon get rid of its contents. This however is not the case. After a considerable interval the film of this gas clinging to the interior surface of the flask was able to produce sounds of great power.

A small quantity of liquid bromine being poured into a well-dried flask, the brown vapour rapidly diffused itself in the air above the liquid. Placed in the intermittent beam, a somewhat forcible sound was produced. This might seem to militate against my former experiments, which assigned a very low absorptive power to bromine vapour. But my former experiments on this vapour were conducted with obscure heat; whereas in the present instance I had to deal with the radiation from incandescent lime, whose heat is in part luminous. Now the colour of the bromine vapour proves it to be an energetic absorber of the luminous rays; and to them, when suddenly converted into thermometric heat in the body of the vapour, I thought the sounds might be due.

Between the flask containing the bromine and the rotating disk I therefore placed an empty glass cell: the sounds continued. I then filled the cell with transparent bisulphide of carbon: the sounds still continued. For the transparent bisulphide I then substituted the same liquid saturated with dissolved iodine. This solution cut off the light, while allowing the rays of heat free transmission: the sounds were immediately stilled.

Iodine vaporised by heat in a small flask yielded a forcible sound, which was not sensibly affected by the interposition of transparent bisulphide of carbon, but which was completely quelled by the iodine solution. It might indeed have been foreseen that the rays transmitted by the iodine as a liquid would also be transmitted by its vapour, and thus fail to be converted into sound.[1]

To complete the argument:—While the flask containing the bromine vapour was sounding in the intermittent beam, a strong solution of alum was interposed between it and the rotating disk. There was no sensible abatement of the sounds with either bromine or iodine vapour.

In these experiments the rays from the lime-light were converged to a point a little beyond the rotating disk. In the next experiment they were rendered parallel by the mirror, and afterwards rendered convergent by a lens of ice. At the focus of the ice-lens the sounds were extracted from both bromine and iodine vapour. Sounds were also produced after the beam had been sent through the alum solution and the ice-lens conjointly.

With a very rude arrangement I have been able to hear the sounds of the more active vapours at a distance of 100 feet from the source of rays.

Several vapours other than those mentioned in this abstract have been examined, and sounds obtained from all of them. The vapours of all compound liquids will, I doubt not, be found sonorous in the intermittent beam. And, as I question whether there is an absolutely diathermanous substance in nature, I think it probable that even the vapours of elementary bodies, including the elementary gases, when more strictly examined, will be found capable of producing sounds.

[1] I intentionally use this phraseology.

INTERESTING NEW CRINOIDS

IN the *Memoirs* of the Swiss Palæontological Society for 1880 Prof. P. de Loriol has recently described a remarkable new Crinoid which he refers to the little known genus *Thiollericrinus*, Étallon, under the name of *T. ribeiroi*. It occurs in the Upper Jurassic beds of Engenheiro, in Portugal. The calyx, like that of most Jurassic *Comatulæ*, has five small prismatic basals attached to the under surface of the radials. But the centrodorsal piece on which the calyx rests is not entirely separated from the lower part of the stem, as is the case in the *Comatulæ*, though it resembles that of a *Comatula* in bearing cirrhi.

Thiollericrinus was a stalked Crinoid that never developed beyond the stage at which cirrhi appear on the enlarged uppermost stem-joint of the stalked larva of *Comatula*. The underface of the centrodorsal and the terminal faces of the other stem-joints resemble those of the *Comatula* larva and also of *Bourgueticrinus* and *Rhizocrinus* in their oval shape and in the presence of transverse ridges which are in different planes at the two ends of each joint. *Thiollericrinus* therefore is a permanent larval form, and furnishes an intermediate stage between the stalked *Bourgueticrinus* and the free *Comatula*. The top stem-joint of the former bears no cirrhi, as it does in *Thiollericrinus* and in *Comatula*; while in the latter it develops cirrhi, and unites closely with the calyx, separating from the rest of the larval stem on which it was previously fixed.

Another form of considerable morphological interest, from its occupying an intermediate position between two well-defined genera, has been lately described by Mr. P. H. Carpenter under the name of *Mesocrinus*. The stem-joints are of the type already mentioned as characteristic of *Bourgueticrinus*, having oval faces marked by transverse ridges in different planes. But the upper stem-joint is not enlarged as it is in *Bourgueticrinus* and in the *Apiocrinidæ* generally, while the form of the calyx recalls that of the *Pentacrinidæ*. It consists of five radials with well-developed articular faces, resting on five basals which form a complete ring as in the recent *Pentacrinus Wyville-Thomsoni*, from 800 fathoms in the Atlantic off the coast of Portugal.

Broadly speaking, therefore, *Mesocrinus* combines the stem of *Bourgueticrinus* with the calyx of *Pentacrinus*, or rather of *Cainocrinus*, as Prof. de Loriol prefers to call that section of the *Pentacrinus* type in which the basal ring is closed. *Mesocrinus* is an Upper Cretaceous genus, one species occurring in the "Plänerkalk" of Streben in Saxony, while another and larger one was found in the "Mucronaten Kreide" of Southern Sweden.

UNIVERSITY AND EDUCATIONAL INTELLIGENCE

OXFORD.—In consequence of the unsatisfactory state of many of the lodging-houses in Oxford, in respect of their sanitary arrangements, a proposal will be brought before Congregation on March 1 "to make better provision for the supervision of lodging-houses." One of the delegates for licensing lodgings will be stipendiary, and it will be his duty to inspect every dwelling-house proposed for this use and to satisfy himself of its sanitary fitness. He shall have the assistance of a sanitary inspector, and shall have proctorial authority over members of the University in his character of inspector.

A special statute will also be proposed authorising the present delegates of lodging-houses to spend whatever sum they may think necessary on a general inspection of lodging-houses during the present year.

There will be holden at Christ Church on Saturday, March 12, an election to at least one Mathematical Junior Studentship, and at least one in Natural Science, tenable for five years from the day of election. They will be of the annual value either (1) of 100*l.* (including an allowance for room rent) if the Governing Body shall so determine; or (2) of 85*l.* (also including an allowance for room rent), which may be raised to the larger sum above named after the completion of one year's residence, if the Governing Body shall so determine. Candidates for the Mathematical Studentships and candidates for the Natural Science Studentships who offer mathematics will call upon the Dean on Monday, February 28, between 12.30 and 1.30 p.m.; candidates for the Natural Science Studentships who do not offer mathematics, on March 2, between 12.30 and 1.30 p.m. All must produce certificates both of the day of their birth and of good character. The examinations will follow in each case at

2 p.m. Candidates for either the Classical or the Mathematical Studentships must not have exceeded the age of nineteen on January 1, 1881; candidates for the Natural Science Studentships must not have exceeded the age of twenty on the same day.

CAMBRIDGE.—There was a meeting of the members of the Senate on February 11, for the purpose of discussing the report of the Syndicate appointed last June to consider certain memorials as to the higher education of women. The Syndicate recommend that, subject to certain conditions of residence at Girton and Newnham Colleges, female students may be admitted to the Tripos Examinations, and certificates issued to them as to the result of the examination.—The Master of Emmanuel, in opening the discussion, remarked that he had never sat on any Syndicate before where so little difficulty had been experienced in agreeing to a report. Personally he wished the Syndicate had arrived at a different conclusion, and had recommended the admission of women to all the University examinations. He claimed for the recommendations of the Syndicate, however, that they closely followed the views of an influential number of residents who had signed a memorial on the subject, and wished for an official sanction to that which had been done for ten years without authority. He contended that it was the imperative duty of the University to give all possible access to its educational advantages, and that the proposed scheme was only a step in that direction.—Dr. Campion contended that the public opinion of the University had been carefully excluded in the constitution of the Syndicate. He charged the report with being both illiberal and harsh. It was illiberal, because the Syndicate had restricted the examinations to inmates of particular colleges, and was not for the encouragement of the higher education of women all over the country. Why was the advantage given only to Newnham and Girton Colleges? The report was harsh, for when they admitted women to test their scientific powers, it was unfair to do so after the conclusion of a time race with the men. Why not let the women study as long as they liked? He did not object to their being compelled to pass the previous examination, but to compel them to go step by step with undergraduates was placing them, by reason of their defect of physical power, in a false position.—Prof. Kennedy said, it was proposed to limit the competition to those within their reach; if the experiment succeeded, it would be a matter for future consideration what extensions should be made. As to the harshness, that surely might be left to the better judgment of the friends, relations, and guardians of these women who asked for these concessions. Women were mentally men's equals, but physically not. To urge their want of physical power as an objection to their admission to the same intellectual pursuits and pleasures as men was more for the Brahmin than the believer in the Bible; it was a fitter argument for the Turk than the Saxon.—Prof. Liveing defended the Syndicate from the attack of Dr. Campion, and asserted that the matter was discussed fully and fairly, without any bias of previously formed opinions.—Prof. Westcott, who did not concur in the whole of the report, expressed his great regret that the Syndicate before reporting had not collected further information on a problem so difficult and obscure.—Mr. Prothero, King's, was of opinion that the same course of training which was good for male students was equally good for women.—Mr. Sidgwick, Trinity, draw attention to the remarkable fact that no objection had been raised to the main proposal of the Syndicate.—The discussion lasted upwards of two hours.

KIEFF.—The number of students at the University of Kieff was, on January 1, 1881, as much as 1041, with fifty-eight professors.

SCIENTIFIC SERIALS

THE *Quarterly Journal of Microscopical Science* for January contains notes on a peculiar form of Polyzoa closely allied to Bugula (Kinetoskias, Kor. and Dan.), by George Busk, F.R.S., with plates 1 and 2.—On the germination and histology of the seedling of *Welwitschia mirabilis*, by F. Orpen Bower, B.A., with plates 3 and 4.—Notes on some of the Reticularian Rhizopoda of the *Challenger*, by Henry B. Brady, F.R.S.—On the head-cavities and associated nerves of Elasmobranchs, by Prof. A. M. Marshall, M.A., with plates 5 and 6.—Contributions to the minute anatomy of the nasal mucous membrane, by Dr. E. Klein, F.R.S., with plate 7.—Histological notes, by Dr. E. Klein, F.R.S.—On the intra-cellular digestion and endoderm of Limnocodium, by E. R. Lankester, M.A., F.R.S., with plates 8 to 10.—On the micrometric numeration of the blood-corpuscles, and the estimation of their hæmoglobin, by Mrs. Ernest Hart.—Preliminary account of the development of the lampreys, by W. B. Scott, M.A.—On some appearances of the red blood-corpuscles of men and other vertebrata, by G. F. Dowdeswell, B.A.

THE *Journal of Anatomy and Physiology, Normal and Pathological*, vol. xv., part 2, January, 1881, contains—Dr. John Struthers, the bones, articulations, and muscles of the rudimentary hind-limb of the Greenland right-whale (*Balæna mysticetus*), (with four plates).—Dr. Creighton, on an infective form of tuberculosis in man identical with bovine tuberculosis.—Dr. W. Osler, medullary neuroma of the brain (plate 18).—A. Doran, case of fissure of the abdominal walls (plate 19).—Dr. D. Newman, description of a polygraph (with woodcut).—Dr. O. H. Jones, on the mechanism of the secretion of sweat.—Dr. P. S. Abraham, anomalous pilose growth in the pharynx of a woman (woodcut).—Dr. R. Saundby, histology of granular kidney (woodcut).—Dr. J. Oliver, two cases of cerebellar disease.—Prof. M'Kendrick, on the colouring-matter of jelly-fishes.—Dr. Cunningham, nerves of hind-limb of the Thylacine and Cuscus.—Dr. W. J. Fleming, pulse dicrotism.

THE *American Naturalist* for January, 1881, contains: Prof. A. Geikie, the ancient glaciers of the Rocky Mountains.—Fred. W. Simonds, the discovery of iron implements in an ancient mine in North Carolina.—William Trelease, on the fertilisation of *Calamintha nepeta* (woodcuts).—S. V. Clevenger, comparative neurology.—E. L. Greene, botanising on the Colorado desert.—W. J. Beal, on a method of distinguishing species of poplars and walnuts by their young leafless branches (woodcuts).—James L. Lippincott, an address to the fossil bones in a private museum.—The Editor's table: Recent Literature.—General Notes [this portion of the journal has been very considerably enlarged with this number. The Botanical, Zoological, Entomological, Anthropological, Geological, Geographical, and Microscopical Sections are each under the charge of a special editor as formerly].—Scientific News.—Proceedings of Scientific Societies.

SOCIETIES AND ACADEMIES

LONDON

Royal Society, January 27.—"The Refraction Equivalents of Carbon, Hydrogen, Oxygen, and Nitrogen in Organic Compounds." By J. H. Gladstone, Ph.D., F.R.S.

Since the communication which I had the honour to read before this Society in 1869, "On the Refraction Equivalents of the Elements," very little has been done on the subject.

Of late however its importance in regard to theories of chemical structure has been recognised by Dr. Thorpe and other chemists in this country, and attention has been recalled to it in Germany by the papers of Brühl, who, following closely in the footsteps of Landolt, has endeavoured to explain the results in the language of modern organic chemistry.

At this juncture it may be of service to put on record my present views in regard to the refraction equivalents of the four principal constituents of organic bodies—carbon, hydrogen, oxygen, and nitrogen.

Carbon.—Carbon in its compounds has at least three equivalents of refraction, 5·0, 6·0, or 6·1, and about 8·8.

Whether its refraction should be one or other of these appears to depend on the way in which the atoms are combined.

When a single carbon atom has each of its four units of atomicity satisfied by some other element, it has a value not exceeding 5·0.

When a carbon atom has one of its units of atomicity satisfied by another carbon atom and the remainder by some other element, it has the value of 5·0. This is also the case if two of its units of atomicity are satisfied by carbon atoms.

When a carbon atom has three of its units of atomicity satisfied by other carbon atoms, its value is 6·0. The most striking instance is that of benzol, C_6H_6 (refraction equivalent 43·7).

There are other organic compounds in which only some of the atoms of carbon have the higher value. It has been especially the work of Brühl to point this out, and to show that where they occur (as in amylene or the allyl compounds) the carbon atom is in a condition similar to those in the phenyl nucleus, that condition in fact which is generally represented in our

graphic formulæ by two carbon atoms linked by double bonds. The value assigned by Brühl in such cases is however 6·1. This somewhat higher figure is deduced from the aggregate value of the six carbon atoms in the nucleus of the aromatic series, which (except in benzol and its simpler substitution products) would appear to be nearer 37 than 36. The fact however is susceptible of another interpretation. The replacement of hydrogen by some nomad radicle is an important change; and if that radicle be CH_2 it is evident that according to present views the carbon atom must have all four of its units of atomicity satisfied with carbon, and by analogy we should expect it to have its refraction increased.

When a carbon atom has all four of its units of atomicity satisfied by other carbon atoms, each of which has the higher value of 6·0 or 6·1, its equivalent of refraction is greatly raised. There are compounds in which the atoms of carbon actually out-number the atoms of hydrogen or its substitute, such as naphthalene, $C_{10}H_8$ (ref. eq. 75·1), naphthol, $C_{10}H_8O$ (79·5), phenanthrene, $C_{14}H_{10}$ (108·3), and pyrene, $C_{16}H_{10}$ (126·1). That the refraction is greatly raised is evident from the fact that, if we were to reckon all the carbon atoms at 6·1, the refraction equivalent of the body would not be fully accounted for. It is evident that in pyrene only ten of the atoms of carbon can be in the same condition as they are in benzol or styrol, the other six must have all their units of atomicity satisfied by carbon alone. Provisionally I venture to assign 8·8 as the refraction equivalent of this highest carbon.

There are several other bodies, such as anthracene, anethol, furfurol, and hydride of cinnamyl, which from their abnormally high refraction appear to contain carbon in this last condition.

Hydrogen.—The general evidence with regard to hydrogen in organic compounds tends to show that it has only one refraction equivalent, that originally assigned to it by Landolt, 1·3.

Oxygen.—Brühl has been the first to point out that oxygen in organic compounds has two values, and he comes to the conclusion that it has the value 3·4 where the oxygen is attached to a carbon atom by a double linking, but 2·8 in hydroxyl and where the oxygen is united to two other atoms. This is deduced from experimental data. But there are other results which present difficulties, such as the various alcohols.

Nitrogen.—Nitrogen has two values, 4·1 and 5·1, or thereabouts.

The lower value, 4·1, is that originally deduced from cyanogen and metallic cyanides, and it seems to be generally confirmed by the observations on organic cyanides and nitriles. The higher value, 5·1, is deduced from observations on organic bases and amides.

I hope shortly to submit to the public the whole of the data for these conclusions.

February 3.—"On the Influence of Temperature on the Musical Pitch of Harmonium Reeds." By Alex. J. Ellis, F.R.S.

The writer gave a tabular account of the experiments on the harmonium reeds of Appunn's treble tonometer at South Kensington Museum, at temperatures differing by from 20° to 26° F., which rendered it probable that the pitch of such reeds was affected by temperature to twice the extent of tuning-forks and in the same direction, that is, that they flattened by heat and sharpened by cold about 1 in 10,000 vibrations in a second for each degree Fahrenheit.

"On an Improved Bimodular Method of computing Natural and Tabular Logarithms and Anti-Logarithms to Twelve or Sixteen Places, with very brief Tables." By Alex. J. Ellis, F.R.S.

A bimodular method is one founded on the familiar proposition, that if the bimodulus (that is, twice the modulus of any system of logarithms) be multiplied by the difference and divided by the sum of two numbers, the result would be approximatively the difference of their logarithms. The improvement consisted in a simple preparation of a given number to make it lie between two numbers in a given table of interpolation, consisting of 100 entries, and in then determining how many places might be trusted without correction, and in correcting the result by a short table so as to give twelve places at sight and sixteen places by means of ordinary table of seven figure logarithms. The antilogarithms were found by first depriving a logarithm of its correction, and then dividing the result added to the bimodulus by the result subtracted from the bimodulus—an entirely new rule. Complete tables and worked-out examples fully explained were added.

"On the Potential Radix as a Means of Calculating Logarithms to any Required Number of Decimal Places, with a Summary of all Preceding Methods Chronologically Arranged," by Alexander J. Ellis, F.R.S.

A positive numerical radix consists of the numbers r, $1 + {}^{\cdot}0_m r$, and their logarithms, where r varies from 1 to 9; 0_m means a series of m successive zeros, and m varies from 1 to any required number. The term "radix" is due to Robert Flower (1771) and is preserved *in memoriam*. It was shown that such a table would enable any logarithm to be calculated by the improved bimodular method and other methods. A negative numerical radix consists of the numbers $1 - {}^{\cdot}0_m r$, and their negative logarithms, and it was shown that such a table would serve the same purpose somewhat more easily. Hence the whole process is reduced to the construction of such radixes. A chronological summary was then given of all preceding methods, showing that most of them depended on having such radixes. The construction of a numerical radix is however a very long and troublesome process by the methods ordinarily used. For this purpose the potential radix for natural logarithms was first constructed, consisting of 10^r, 2^r, $(1{\cdot}1)^r$, and $(1{\cdot}0_m 1)^r$, negative $(1 - {}^{\cdot}0_m 1)^r$, from $r = 1$ to $r = 10$ (the latter terms being calculated by simple addition), and their natural logarithms, first to any number of places from the very simple series for nat. log. $(1 \pm {}^{\cdot}0_m r)$, and secondly, by simple addition. This gives a radix from which natural logarithms of all numbers can be calculated to any number of places by the improved bimodular method. But the main use of the potential radix is to calculate the nat. logs. of the numbers of the numerical radix. The radix for tabular logarithms is then found by multiplying by the modulus, already calculated from the potential radius. All this was fully explained by tables and examples.

Mathematical Society, February 10.—Mr. S. Roberts, F.R.S., president, in the chair.—Mr. W. Woodruff Benson, University of Michigan, was elected a member, and Prof. Rowe and Mr. J. Parker Smith were admitted into the Society.—The following communications were made:—On some integrals expressible in terms of the first complete elliptic integral and of gamma functions, by Mr. J. W. L. Glaisher, F.R.S.—Some theorems of kinematics on a sphere, by Mr. E. B. Elliott, M.A.—Supplement on binomial biordinates, by Sir J. Cockle, F.R.S.—An application of conjugate functions (to the case of membranes), by Mr. E. J. Routh, F.R.S.—Note on Abel's theorem, by Mr. T. Craig.

Linnean Society, February 3.—Robt. McLachlan, F.R.S., in the chair.—Lieut.-Col. A. A. Davidson was elected a Fellow.—Examples of Prof. C. Semper's method of preserving the soft tissues of animals as teaching-specimens were exhibited on behalf of Herr L. Würth of Würzburg.—Mr. G. Murray exhibited and made remarks on a Japanese book containing wood sections.—Mr. C. Craig-Christie exhibited, and a note was read on, the presence of what appeared to be deciduous stipules in *Ilex aquifolium*, thus contrary to the usually-accepted assertion that the order Ilicineæ is exstipulate.—The following paper by Mr. G. Bentham was read: "Notes on Cyperaceæ; with special reference to Lestiboudois' Essay on Beauvois' Genera." The essay in question was founded on Palisot and Beauvois' MS., which was originally intended to follow his "Agrostographia," and has been almost entirely lost sight of, and random guesses have been made at the species intended by the short characters given in Roemer and Schultze's "Systema."—Nees von Esenbeck, in the 7th, 8th, and 10th vols. of the "Linnæa," and Supplement 123, or Kunth in vol. ii. of his excellent "Enumeratio," appear to have correctly identified many of these. Eighteen so-called genera are now referred to various established genera. Steudel's Synopsis is marred by the author's hazy ideas of species. Boekeler has a thorough knowledge of species, but his diagnoses are often excessively long. Mr. Bentham proposes few changes in the order of genera as set forth by Kunth, and he considers that Boekeler's primary division of the order as to whether the fertile flower is hermaphrodite or female only, bears the test of detailed examination.—Hermaphrodite flowers:—(1) Scirpeæ, (2) Hypolyteæ, (3) Rhyncasporeæ. Unisexual flowers:—(1) Cryptangeæ, (2) Scheriæ, (3) Cariceæ.—A paper was read by Mr. A. D. Michael, observations on the life history of Gamasinæ. In this the author endeavours to decide some of the disputed and knotty points in reference to these humble parasites; M.

Megnin of Versailles and Dr. Kramer of Schleusingen, both good authorities on the subject, being at variance thereon. Mr. Michael, believing that detached observations on captured specimens may have produced unreliable results, has himself bred Gamasids, closely followed their changes and growth, and watched their manners, and thus has arrived at what he on good grounds assumes to be important results respecting their life-history. He states that the remarkable power of darting each mandible separately with speed and accuracy of aim far in advance of the body, the powerful retractile muscles attached to these mandibles, the organisation of the remainder of the mouth, the extreme swiftness of the creatures, the use of the front legs as tactile organs only, and not for the purpose of locomotion, and the ample supply of tactile hairs in front only, seem to fit the animals for a predatory life, and point to habits similar to those of *Cheyletus* and *Trombidium*, rather than to those of the true vegetable-feeders, such as the Orbatidæ and Tetramachi. He further concludes (1) that Megnin is correct in saying *Gamasus coleoptratorum* and other allied creatures, with the conspicuously-divided dorsal plates, are not species at all, but are immature stages of other species; (2) that the division of the dorsal plate is, in most cases at all events, a question of degree, and does not form a sound basis for classification, as applied by Koch, Kramer, and others; (3) that the dorsal plates do not grow gradually, but alter in size, shape, or development at the ecdysis; (4) that Megnin is right in saying that the characteristic of the so-called *G. marginatus* is simply a provision possessed by the females of a large number of species; (5) that the extent of the white margin depends upon the extent to which the abdomen is distended by eggs; (6) that Megnin is in error in saying that *Coleoptratorum* is the nymph of *Crassipes*. The nymph of *Crassipes* does not show any divided dorsal plates which can be seen on the living creature; (7) that in the species bred there has not been observed any inert stage before the transformations or ecdysis; (8) that in the same species copulation takes place with the adult female, and not with the immature one, as Megnin contends, and that it is by the vulva, not the anus.—Two papers were read on the coffee-leaf disease (see Science Notes, p. 354).

Institution of Civil Engineers, February 8.—Mr. Abernethy, F.R.S.E., president, in the chair.—A paper on the temporary works and plant at the Portsmouth Dockyard Extension, by Mr. C. H. Meyer, Assoc. M. Inst. C.E., was read.

PARIS

Academy of Sciences, February 7.—M. Wurtz in the chair.—The following papers were read:—On photographs of nebulæ, by M. Janssen. It is comparatively easy to get a photographic image of the brightest parts of nebulæ, but very difficult to get complete images which may serve for future comparison. The optical and photographic conditions should be exactly defined. M. Janssen suggests taking for criteria images of stars, with plates a little out of focus, so as to give an opaque circle. Five or six of these stellar circles accompanying the photograph of a nebula would indicate what the conditions had been.—On the thermic formation of pyrogenic carburets, by M. Berthelot.—Some remarks on the characters of chloro-organic gases and vapours, by M. Berthelot. The formation of a white precipitate in neutral or slightly acid nitrate of silver, traversed by a gaseous current, is not a sufficient character of chlorine or hydrochloric acid.—Examination of materials from some vitrified forts of France; conclusions, by M. Daubrée. The methods of producing these forts seem to have been various. To soften a rock like granite (sometimes used), to fuse its mica, and even, at times, its felspar, in thicknesses of several metres, implies large use of fuel and prolonged skilful effort. The fire was probably applied *within* the walls, and a current of forced air may have been used, besides draught. The makers unconsciously produced some minerals that have only of late been reproduced in the laboratory.—On the Great Canal de l'Est and the machines set up to ensure its alimentation, by M. Lalanne. This canal (made in consequence of the change of frontier in 1871) runs from near Givet, on the Meuse, by Mezières, Sedan, Commercy, Toul, &c., to Port-sur Saône (it includes, in a total length of 468 km., 20 km. of the canal from the Marne to the Rhine). There are two large pumps in the Moselle valley, worked by the water of that river, also steam-pumps at Vacon. Two large reservoirs are projected, one near Paroy, the other at Aouze.—Study of actions of the sun and the moon in some terrestrial phenomena, by M. Bouquet de la Grye.—Observations of Perseids at Toulouse Observatory in 1880, by M. Baillaud. 1172 falling stars were counted on August 9, 10, and 11; the maximum was on the 10th, between 14h. and 15h. The trajectories were generally very short, and their extremities pretty far from the radiant point. The meteors were divisible into two groups.—On modes of transformation which preserve lines of curvature, by M. Darboux.—On simultaneous linear differential equations, with rational coefficients, whose solution depends on the quadrature of a given irrational algebraic product, by M. Dillner.—On a property of the product of k integrals of k linear differential equations, with rational coefficients, the solution of which depends on the quadrature, respectively, of k rational functions of the independent variable, and of a given algebraic irrationality, by the same.—The problem of remainders in two Chinese works, by M. Matthiessen.—On a peculiar phenomenon of resonance, by M. Gripon. A tuning-fork, giving a simple sound, will set in resonance masses of air which produce a sound comprised in the harmonic series of the fork's sound. The form of the mass of air is unimportant. One grave fork set in vibration forks which gave harmonic sounds, but not others, the two forks being connected by very fine copper wire (stretched).—On elliptic double refraction, and the three systems of fringes, by M. Croullebois.—On a new apparatus for showing the dissociation of ammoniacal salts, by M. Tommasi. In a glass tube is hung with platinum wire a strip of blue litmus paper that has imbibed a concentrated solution of chlorhydrate of ammonia. On putting this dissocioscope in boiling water, the sal-ammoniac is dissociated and the paper turns red; if then put in cold water the dissociated ammonia combines again with the acid, and the paper turns violet again.—On derivatives of acroleine, by MM. Grimaux and Adam.—Action of hydrochloric acid on aldehyde, by M. Hauriot.—Inoculation of the dog for glanders, by M. Galtier. The dog may contract the disease (through inoculation) and recover many times; but its receptivity (comparatively small at first) gradually diminishes, and, there is reason to believe, may be quite effaced. The power of the virus is attenuated by successive cultivations in the dog; this appears in an ass, *e.g.* inoculated with the later virus of a dog inoculated several times.—Physiology of dyspepsia, by M. Sée. In grave dyspepsia the stomach pump may advantageously be used to clear the stomach of liquids unfavourable to digestion.—On the histology of the pedicellaria and muscles of the sea urchin (*Echinus sphæra*, Forbes), by MM. Geddes and Beddard.—Researches on the development of sterile sporangia, in *Isoetes lacustris*, by M. Mer.

VIENNA

Imperial Academy of Sciences, February 10.—V. Burg in the chair.—C. Heller, on the distribution of the fauna of the high mountains of Tyrol.—R. Maly and F. Hinseregger, studies on caffeine and theobromine (second paper).—V. Hochstetter, on the Kreutzberg Cave, near Laas, in Carniola, and *Ursus spelæus*.—R. Puluj (1) on radiant electrode-matter; (2) remarks relating to the priority claimed by Dr. Eugen Goldstein.

CONTENTS

	Page
Island Life, I. By Prof. Arch. Geikie, F.R.S.	357
Algæ	359
Letters to the Editor:—	
"The New Cure for Smoke."—J. A. C. Hay; Dr. C. W. Siemens, F.R.S.	361
On the Spectrum of Carbon.—W. M. Watts	361
"Prehistoric Europe."—Prof. W Boyd Dawkins, F.R.S.	362
Geological Climates.—Dr. A. Woeikoff	362
Variable Stars.—J. E. Gore	362
The Mode of Flight of the Albatross.—Howard Sargent	363
Auroral Phenomena.—Dr. C. M. Ingleby	363
Ozone.—J. P.	363
Citania.—Rev. R. Burton Leach	363
The Recent Severe Weather.—F. M. S.; H. W. C.	364
Butterflies in Winter.—Thomas W. Shore	364
John Gould, F.R.S.	365
The Blackheath Holes. By C. E. De Rance	365
Mercadier's Researches on the Photophone	367
The John Duncan Fund	368
The Time of Day in Paris (*With Illustration*)	369
Notes	369
Our Astronomical Column:—	
The So-called Nova of 1600	371
The "Astronomische Nachrichten"	371
The Comet 1880 *c* (Swift, October 10)	372
The Perseids in August, 1880	372
Physical Notes	373
Chemical Notes	373
Action of an Intermittent Beam of Radiant Heat upon Gaseous Matter. By Prof. Tyndall, F.R.S.	374
Interesting New Crinoids	377
University and Educational Intelligence	377
Scientific Serials	378
Societies and Academies	378

SUBSCRIPTIONS TO NATURE

Yearly . . . . . 28*s.*
Half-yearly . . . . . 14*s.* 6*d.*
Quarterly . . . . . 7*s.* 6*d.*

To the Colonies, United States, the Continent, and all places within the Postal Union :—

Yearly . . . . . 30*s.* 6*d.*
Half-yearly . . . . . 15*s.* 6*d.*
Quarterly . . . . . 8*s.*

Office: 29, Bedford Street, Strand.

DIARY OF SOCIETIES.

LONDON

THURSDAY, FEBRUARY 17.

ROYAL SOCIETY, at 4.30.—On the Viscosity of Gases at High Exhaustions: W. Crookes.—Notes on the Earthquakes of July, 1880, at Manila: Consul W. B. Pauli.

LINNEAN SOCIETY, at 8.—British Fishes: Dr. Francis Day.—On Right and Left-Hand Contortion of the Corolla: C. B. Clarke.—On a New Form of Sponge: Prof. P. M. Duncan.—On the Reparative Processes which occur in Vegetable Tissues: Samuel G. Shattock.

CHEMICAL SOCIETY, at 8.—On a New Apparatus for showing the Dissociation of Ammonium Salts: D. Tommasi.—On the Estimation of Organic Carbon and Nitrogen in Water Analysis simultaneously with the Estimation of Nitric Acid: M. W. Williams.

LONDON INSTITUTION, at 7.—Violins: Rev. H. R. Haweis.

ROYAL INSTITUTION, at 3.—Drawing-Room Music: Prof. Pauer.

NUMISMATIC SOCIETY, at 7.

FRIDAY, FEBRUARY 18.

ROYAL COLLEGE OF SURGEONS, at 4.—The Skeleton of the Sauropsida: Prof. W. K. Parker.

GEOLOGICAL SOCIETY, at 1.—Anniversary.

ROYAL INSTITUTION, at 9.—Fruits and Seeds: Sir John Lubbock.

SATURDAY, FEBRUARY 19.

ROYAL INSTITUTION, at 3.—Ancient Egypt: R. S. Poole.

SUNDAY, FEBRUARY 20.

SUNDAY LECTURE SOCIETY, at 4.—Science and Superstition: A. Elley Finch.

MONDAY, FEBRUARY 21.

ROYAL COLLEGE OF SURGEONS, at 4.—The Skeleton of the Sauropsida: Prof. W. K. Parker.

LONDON INSTITUTION, at 5.—Art among the Ancient Greeks: J. E. Hodgson.

SOCIETY OF ARTS, at 8.—Watchmaking: Edward Rigg.

VICTORIA INSTITUTE, at 8.—Implements of the Stone Age: Dr. J. P. Thompson.—The Caves of South Devon: J. E. Howard.

TUESDAY, FEBRUARY 22.

ANTHROPOLOGICAL INSTITUTE, at 8.—Remarks on Arrow-Poisons prepared by some Tribes of North American Indians: W. J. Hoffman, M.D.—The Gauchos of San Jorge, Central Uruguay: David Christison, M.D.

WEST LONDON SCIENTIFIC ASSOCIATION, at 8.

SOCIETY OF ARTS, at 8.—The Languages of South Africa: R. N. Cust.

ROYAL INSTITUTION, at 3.—The Blood: Prof. Schäfer.

WEDNESDAY, FEBRUARY 23.

GEOLOGICAL SOCIETY, at 8.—The Permian, Triassic, and Liassic Rocks of the Carlisle Basin: T. V. Holmes.—On *Astroconia Granti*, a New Cyssakine Hexactinelled from the Silurian Formation of Canada: Prof. W. J. Sollas, M.A.

ROYAL COLLEGE OF SURGEONS, at 4.—The Skeleton of the Sauropsida: Prof. W. K. Parker.

ROYAL SOCIETY OF LITERATURE, at 8.—The Fathers of the English Church Music: W. A. Barrett.

SOCIETY OF ARTS, at 8.—River Conservancy: C. N. Cresswell.

THURSDAY, FEBRUARY 24.

ROYAL SOCIETY, at 4.30.

LONDON INSTITUTION, at 7.—One Aspect of Colour: Capt. Abney.

SOCIETY OF TELEGRAPH ENGINEERS, at 8.—Adjourned Discussion on Mr. Alex. J. S. Adams's Paper (Earth Currents—Electric Tides).—On the Application of Dynamo-Electric Machines to Railway Rolling Stock: Lieut. P. Carden.—On the Interference with the Processes of Manufacture of Wool and Hair arising from the Development of Electricity during Spinning; with a Description of Apparatus applied to obviate it: Edward B. Bright.

SOCIETY OF ARTS, at 8.—Deep-Sea Investigation: J. G. Buchanan.

ROYAL INSTITUTION, at 3.—Drawing-Room Music: Prof. Pauer.

FRIDAY, FEBRUARY 25.

QUEKETT MICROSCOPICAL CLUB, at 8.

ROYAL INSTITUTION, at 9.—Excitability in Plants and Animals: Dr. J. Burdon-Sanderson.

SATURDAY, FEBRUARY 26.

PHYSICAL SOCIETY, at 3.—On an Integrating Machine: C. V. Boys.—On the Telegraphic Transmission of Pictures of Natural Objects: Shelford Bidwell.

ROYAL INSTITUTION, at 3.—Ancient Egypt: R. S. Poole.

METALS and their CHIEF INDUSTRIAL APPLICATIONS. By C. ALDER WRIGHT, D.Sc., Lecturer on Chemistry in St. Mary's Hospital Medical School. With Illustrations.

MACMILLAN & CO. LONDON.

LIGHTNING CONDUCTORS.

Experience, accumulated since the time of Benjamin Franklin, proves conclusively that a Conductor made of Copper of adequate size is the best of all appliances for the protection of every description of building from the destructive effects of lightning.

NEWALL & CO.'S

PATENT COPPER LIGHTNING CONDUCTOR,

As applied to all kinds of Buildings and Shipping in all parts of the world with unvarying success; is the most Trustworthy, most Effective, and also the Cheapest Conductor ever offered to the public.

It is simple in its application, no insulators being required, and it costs only one shilling per foot for the standard size, which ensures safety in any storm.

R. S. NEWALL & CO., 130, STRAND, W.C.
36, WATERLOO ROAD, LIVERPOOL.
68, ANDERSTON QUAY, GLASGOW.
MANUFACTORY—GATESHEAD-ON-TYNE.

GIMINGHAM'S SPRENGEL AIR-PUMP,

with Multiple Fall Tubes and every recent improvement, including McLeod's Low Tension Gauge, Barometer Gauge, Radiometer, Terminals for testing non-conductivity of the Vacuum. &c., &c.

L. CASELLA having arranged with Mr. GIMINGHAM for the Sole Manufacture of these Pumps, as well as his Improved Forms of

CROOKES'S RADIANT MATTER TUBES,

Is prepared to supply them either in their simple form, or with any of their accessories.

Mr. GIMINGHAM has kindly engaged to examine each, in order that no Imperfect Instrument or Tubes may be sent away.

Also **GIMINGHAM'S COMBINATION BLOWPIPE** for Amateur and Professional Glass Work, the most simple and perfect in use.

L. CASELLA, 147, Holborn Bars, London, E.C.

Liberal Terms to Science Teachers and the Trade.

THOMAS CRAMPTON (formerly of 4, Little Britain, London, E.C.), ELECTRICIANS, OPTICIANS, and PHILOSOPHICAL INSTRUMENT MAKERS. Electric Bells, New Metallic Base Pattern, Constant Batteries, Indicators, Thief and Fire Alarms, and Automatic Switches, Induction and Medical Coils, or Specialities. Insulated Wires of every description. Microscopic and Optical Materials. Telescopes, Opera Glasses, Microscopes, Aneroid Barometers, and Lime-light Apparatus. Illustrated Catalogue Three Stamps.

THOMAS CRAMPTON & CO., 251, HIGH HOLBORN, LONDON, W.C.
For Trade Terms send Card.

NOTICE OF REMOVAL.

JAMES HOW & CO.,

SCIENTIFIC INSTRUMENT MAKERS,

73, FARRINGDON ST., LONDON

(LATE OF 5, ST. BRIDE ST., AND 2, FOSTER LANE)

HOW'S STUDENT'S MICROSCOPE. HOW'S MICROSCOPE LAMP.
Rock Sections and other Objects for the Microscope.

NOW READY.
SECOND EDITION,

GRIFFIN'S

CHEMICAL HANDICRAFT.

PRICE 4*s.* 7*d.* POST FREE.

A CATALOGUE OF CHEMICAL APPARATUS:

ILLUSTRATED, CLASSIFIED, DESCRIPTIVE.

Demy 8vo, 480 pp., Illustrated with 1,600 Woodcuts.

Most Complete and Cheapest List of Apparatus.

JOHN J. GRIFFIN AND SONS, 22, GARRICK STREET, LONDON, W.C.

£5 5*s.* ASTRONOMICAL TELESCOPE.

CRAMPTON & CO.'S IMPROVED TELESCOPE is of the highest workmanship and finish, combined with great power and clearness of definition; is entirely constructed of polished brass, with 3-inch Achromatic Object Lens, Altitude and Azimuth Movements, Rackwork, and Fine Adjustment, &c., &c.

THOMAS CRAMPTON & CO., 251, HIGH HOLBORN, LONDON, W.C.

EAGLE INSURANCE COMPANY,

79, PALL MALL.

FOR LIVES ONLY. ESTABLISHED 1807.

Accumulated Funds £3,043,542
Also a Subscribed Capital of more than £1,500,000

Reports, Prospectuses, and Forms may be had at the Office, or from any of the Company's Agents, post free.

GEORGE HUMPHREYS, Actuary and Secretary.

"NATURE," Nov. 14, 1878, No. 472.—One Shilling each will be paid for Copies of this number.—Address Publishers of NATURE, 29, Bedford Street, Strand W.C.

W. LADD & CO.,

SCIENTIFIC INSTRUMENT MANUFACTURERS,

(By Appointment to the Royal Institution of Great Britain),

11 AND 12, BEAK STREET, REGENT STREET, W.

IMPROVED HOLTZ ELECTRICAL MACHINES. GRAMME'S MAGNETO-ELECTRIC MACHINE for Laboratory use.

PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3s. per oz.

Physical Apparatus of every Description.

ILLUSTRATED CATALOGUE, SIXPENCE.

PATERSON'S NEW CATALOGUE OF PHYSICAL APPARATUS.

LANTERN SLIDES for SCIENTIFIC LECTURES. Season 1880-1. Post free 6 Stamps.
Complete Sets of Physical Apparatus for Science Primers and all the Physical Text-books in use in Schools and Colleges.
Siemens and Gramme Dynamo Machines and Lamps for hire.
Schools supplied with Apparatus as per Science and Art Departments' Requirements in the Sections of Light, Heat, Sound, and Electricity.
Electric Signals for Houses, Hotels, &c., Colliery Signals, Lightning Conductors. The Gower-Bell Loud-speaking Telephone.

EDWARD PATERSON, Electrical Engineer.

SHOW ROOMS AND STEAM WORKS:—76, LITTLE BRITAIN, E.C. (late 3, Bedford Court, W.C.).

MOLISON'S HARMONOGRAPH; executes the Harmonic Curves in the most perfect manner. 15s. and 20s.

Illustrated Catalogue of Electrical Apparatus, Part 1, post free, 6 Stamps. Ditto, Electric Signals, Part 2, 6 Stamps.

FLETCHER'S
PATENT VENTILATED
HOT-AIR OVEN.

At a cost of less than one halfpenny per hour for gas this oven will grill, roast, toast, bake, warm dishes and plates; and with the assistance of Fletcher's Patent Solid Flame Boiling Burners will do everything possible with a first-rate open fire (except drying clothes on washing days).



It is unapproached by any oven for pastry, and is fully hot in one minute after the gas is lighted.

Fish, joint, and pastry can be cooked all at once, in the most perfect manner, without the slightest taint from one to the other. The cooking is always good and always alike.

It will roast joint and fowls both at once, at least as well as an open fire.

Complete illustrated list of gas cooking and labour-saving appliances free by post. List of Gas and Petroleum Laboratory Furnaces and Apparatus, price 2*d*.

THOS. FLETCHER,
4 & 6, *MUSEUM STREET, WARRINGTON.*

HOLLOWAY'S OINTMENT

A CERTAIN REMEDY

For BAD BREASTS, OLD WOUNDS, and SORES. If effectually rubbed on the Neck and Chest, it cures SORE THROATS, BRONCHITIS, COUGHS and COLDS; and for GOUT, RHEUMATISM, and all Skin Diseases it is unequalled.

BROKEN!!

DAVY'S DIAMOND CEMENT

SECURELY AND NEATLY MENDS
CHINA, GLASS,
CABINET WORK,
AND
FANCY ARTICLES.

Of all Chemists in 1s. Bottles.

See the name "E. DAVY," the Original Inventor, is on the Label, and also that of

BARCLAY & SONS, 95, Farringdon Street, London.

S. C. TISLEY & Co.,

OPTICIANS,

172, BROMPTON ROAD, S.W.

(Close to South Kensington Museum.)

THE PHONEIDOSCOPE

An Instrument for Observing the Colour-Figures of Liquid Films under the action of Sonorous Vibrations,

Being a visible demonstration of the Vibratory and Molecular Motion of a Telephone Plate.

The PHONEIDOSCOPE, with 3 Discs, Bottle of Solution, Descriptive Pamphlet, &c., in Cardboard Box, 10s. 6*d*.

MANUFACTURED AND SOLD WHOLESALE AND RETAIL BY
S. C. TISLEY & CO., 172, BROMPTON ROAD, LONDON, S.W

TELEPHONIC ELECTRICITY. All Materials supplied for Experimental Purposes.

Price Lists of Electrical and Acoustic Apparatus, with Drawings and Description of the Harmonograph. Post Free, 2d.

R. W. NEEVES,

PHILOSOPHICAL INSTRUMENT

AND

INTENSITY COIL MAKER.

PRICE LIST, FOUR STAMPS.

55, SIDMOUTH STREET, LONDON, W.C.

FRY'S COCOA

GOLD MEDAL,
PARIS EXHIBITION.

In Packets and Tins. Pure Cocoa only, with the superfluous oil extracted.

"If properly prepared, there is no nicer or more wholesome preparation of cocoa."—*Food, Water, and Air, edited by Dr. Hassall.*

EXTRACT

J. S. FRY & SONS, Bristol and London.

T. COOKE & SONS,

OPTICIANS

TO

H.R.H. the late Prince Consort, the Royal Family, Her Majesty's Home, Indian, and Colonial Governments, and most of the Foreign Governments.



Messrs. T. COOKE & SONS are now in a position to construct with punctuality and on the most reasonable terms every size and form of Equatorial Telescope; also Observatories, Transit Instruments, Spectroscopes, Chronographs, Theodolites, Levels, Astronomical Turret Clocks, &c.

Catalogues of Scientific Instruments on Application; also Catalogues of Amateurs' Lathes and Lathe Apparatus.

15-INCH EQUATORIAL MOUNTING, CONSTRUCTED FOR THE ROYAL OBSERVATORY, BRUSSELS, 1880.

T. COOKE AND SONS, Buckingham Works, York.

WORKS ON SCIENCE AND THE USEFUL ART

PUBLISHED BY MESSRS. LONGMANS & CO.

GANOT'S ELEMENTARY TREATISE ON PHYSICS, Experimental and Applied, f the use of Colleges and Schools. Translated and Edited, with the Author's sanction, by E. ATKINSON, Ph.D F.C.S., Professor of Experimental Science, Staff College. The Ninth Edition; with 4 Coloured Plates and 8 Woodcuts. Large crown 8vo. Price 15s.

"This well-known work has been before the public for sixteen years, and has now reached a ninth edition. Each new editi has contained both additions and revisions in accordance with the progress of science. The present edition differs from the la by an increase of subject-matter of twenty-five pages, while twenty-four new illustrations have been added. The illustrations a extremely good, and the various subjects are discussed with a sufficient infusion of mathematics to make the book serviceable f the use of the highest forms in schools, and for scholarships and other examinations."—*Academy.*

GANOT'S NATURAL PHILOSOPHY, FOR GENERAL READERS AND YOUN PERSONS: a Course of Physics divested of Mathematical Formulæ and expressed in the language of daily life Translated and Edited, with the Author's sanction, by E. ATKINSON, F.C.S. The Fourth Edition, complete revised; with 25 pages of New Matter, 2 Coloured Plates, and 471 Woodcuts, of which 16 are New in thi Edition. Crown 8vo. Price 7s. 6d.

"We are glad to notice this volume, which will prove useful to a wide circle of readers and teachers, since it represents th amount of knowledge required for the matriculation examination of the London University. It is divided into eight books, treating respectively of the General Properties of Matter, Hydrostatics, Gases, Acoustics, Heat, Light, Magnetism, and Electricity. I is admirably illustrated, and throughout most clearly written. It ought to be in the hands of the higher classes of all our public schools; and if the principal facts it contains were early demonstrated by experiment to those about to become members of the profession, we should have a far larger number of accurate observers, and much fewer loose theories than at present."—*Lancet.*

POPULAR LECTURES ON SCIENTIFIC SUBJECTS, Second Series, comprising the Origin and Signification of Geometrical Axioms, the relation of Form, Shade, Colour and Harmony of Colour to Painting, the Origin of the Planetary System, &c. By H. HELMHOLTZ, Professor of Physics in the University of Berlin. Translated by E. ATKINSON, Ph.D., F.C.S., Professor of Experimental Science, Staff College. With 17 Woodcuts. Crown 8vo. Price 7s. 6d.

PROF. HELMHOLTZ' FIRST SERIES OF LECTURES ON SCIENTIFIC SUBJECTS. Translated by Prof. ATKINSON, with Introduction by Prof. TYNDALL, F.R.S. Second Edition, revised; with 51 Woodcuts, uniform with the Second Series. Crown 8vo. Price 7s. 6d.

FRAGMENTS OF SCIENCE: a Series of detached Essays, Addresses, and Reviews. By JOHN TYNDALL, LL.D., D.C.L., F.R.S. Sixth Edition, revised and augmented. 2 vols. Crown 8vo. 16s.

HEAT A MODE OF MOTION. By JOHN TYNDALL, LL.D, D.C.L., F.R.S. Sixth Edition (Thirteenth Thousand), thoroughly revised and enlarged; with Frontispiece and 123 Woodcuts. Crown 8vo. 12s.

THE ELEMENTS OF MECHANISM. By T. M. GOODEVE, M.A., Barrister-at-Law, Lecturer on Applied Mechanics at the Royal School of Mines. New Edition, rewritten and enlarged; with 342 Woodcuts. Crown 8vo. 6s.

MILLER'S ELEMENTS OF CHEMISTRY, Theoretical and Practical. Part I. *Chemical Physics.* Sixth Edition, revised, with Additions, by H. MACLEOD, F.C.S. With 274 Woodcuts. 8vo. 16s.

MILLER'S ELEMENTS OF CHEMISTRY. Part II. *Inorganic Chemistry.* Sixth Edition, revised throughout, with Additions by C. E. GROVES. With 376 Woodcuts. 8vo. 24s.

MILLER'S ELEMENTS OF CHEMISTRY. Part III. Fifth Edition, revised, and for the most part rewritten, by H. E. ARMSTRONG, F.R.S. and C. E. GROVES, F.C.S. The Chemistry of Carbon Compounds, or Organic Chemistry, in Two Sections. SECTION I. *Hydrocarbons, Alcohols, Ethers, Aldehyds,* and *Paraffinoid Acids;* with 20 Woodcuts. 8vo. 31s. 6d. SECTION II., completion, is in the press.

DICTIONARY OF CHEMISTRY AND THE ALLIED BRANCHES OF OTHER SCIENCES. By HENRY WATTS, F.R.S., Editor of the *Journal* of the Chemical Society, assisted by eminent Scientific and Practical Chemists. 7 vols. 8vo. £10 16s. 6d.

THIRD SUPPLEMENTARY VOLUME, completing the Record of Chemical Discovery to the Year 1877. In Two Parts. PART I. 8vo. price 36s. PART II., completion, in the Press.

URE'S DICTIONARY OF ARTS, MANUFACTURES, AND MINES; Containing a clear Exposition of their Principles and Practice. The Seventh Edition, completely revised and greatly enlarged by ROBERT HUNT, F.R.S., Keeper of Mining Records, assisted by F. W. RUDLER, F.G.S., and by numerous Contributors. With above 2604 Woodcuts. 4 vols. medium 8vo. Price £7 7s.

ON ARTIFICIAL MANURES, their Chemical Selection and Scientific Applications to Agriculture; a Series of Lectures given at the Experimental Farm, Vincennes. By GEORGES VILLE. Translated and Edited by W. CROOKES, F.R.S., V.P.C.S. With 31 Illustrations, 8vo. 21s.

A TREATISE ON MILLS AND MILL-WORK. By the late Sir W. FAIRBAIRN, Bart., C.E. Fourth Edition, with 18 Plates and 333 Woodcuts. 1 vol, 8vo. 25s.

A HANDBOOK OF PRACTICAL TELEGRAPHY. By R. S. CULLEY, Member Inst. C.E., Engineer-in-Chief of Telegraphs to the Post Office. Seventh Edition, revised and enlarged; with 132 Woodcuts, and 18 Lithographic Plates of Apparatus. 8vo. 16s.

LONDON: LONGMANS, GREEN, & CO.

Printed by R. CLAY, SONS, AND TAYLOR, at 7 and 8, Bread Street Hill, Queen Victoria Street, in the City of London, and published by MACMILLAN AND CO., at the Office, 29 and 30, Bedford Street, Covent Garden.—THURSDAY, February 17, 1881.

NATURE

A WEEKLY ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
Of Nature trusts the mind which builds for aye."—WORDSWORTH

NO. 591, VOL. 23] THURSDAY, FEBRUARY 24, 1881 [PRICE SIXPENCE

Registered as a Newspaper at the General Post Office.]

[All Rights are Reserved.

SOLAR PHYSICS.

The following COURSE of LECTURES will be given by Members of the Committee on SOLAR PHYSICS, appointed by the Lords of the Committee of Council on Education:—

An Introductory Lecture. By Prof. STOKES, Sec. R.S. 6th April, 1881.

A Lecture on the Practical Importance of Studying the Influence of the Sun on Terrestrial Phenomena. By Lieut.-General STRACHEY, R.E., C.S.I., F.R.S. 8th April.

Two Lectures on the Connection between Solar and Terrestrial Phenomena By Prof. BALFOUR STEWART, F.R.S. 27th and 29th April.

Six Lectures on Spectroscopy in Relation to Solar Chemistry. By Mr. J. NORMAN LOCKYER, F.R.S. 4th, 6th, 11th, 13th, 18th, and 20th May.

Three Lectures on the Photography of the Infra-red of the Spectrum in its Application to Solar Physics. By Capt. ABNEY, R.E., F.R.S. 25th and 27th May, and 1st June.

The LECTURES will be delivered in the Lecture Theatre of the South Kensington Museum at 4 p.m on the days stated above.

Admission will be by Tickets, which may be obtained, as far as there is room, on application by Letter to the SECRETARY, Science and Art Department, South Kensington, S.W.

ASSOCIATION for the IMPROVEMENT OF GEOMETRICAL TEACHING.

SEVENTH GENERAL REPORT, containing the Address of the President, H. B. HAYWARD, Esq., F.R.S., on "The Future of the Association." Price Sixpence. Complete Sets of the Reports of the Association, price 3*s.* 6*d.*

Apply by letter, inclosing Stamps or P.O.O., to Mr. JOSIAH ALLEN, Printer, 74, Suffolk Street, Birmingham.

MICROSCOPES.

C. BAKER, of 244, High Holborn, begs to call the attention of the Scientific to his large stock of ACHROMATIC MICROSCOPES, BINOCULAR AND MONOCULAR, at extremely low prices, commencing from £3 10*s.* OBJECT-GLASSES, APPARATUS, OBJECTS, and MATERIALS of all kinds kept in stock. Catalogues free by post.

C. BAKER being the appointed Agent for ZEISS, SEIBERT, and other first-class GERMAN MAKERS, is now supplying their beautiful productions at very Low Prices. ZEISS's new HOMOGENEOUS and other IMMERSION OBJECTIVES now in stock. Catalogue free by post.

A Large Assortment of SECOND-HAND MICROSCOPES and other Scientific Instruments in stock at the Lowest Prices. Lists of same forwarded on application.

Instruments taken in Exchange.

ESTABLISHED 1765.

BROWNING'S MICROSCOPES.

The "COMPLETE" MICROSCOPE, with rack and fine adjustment to body, mechanical motions to stage, removable fittings for apparatus, revolving diaphragm with 3 apertures, A or B eyepiece, 1 in. 16° and ¼ in. 75° objectives, of which the performance will be guaranteed.

PRICE £7 10s. 0d.

Price List of Microscopes Free.

A New Edition of the Illustrated Catalogue of Microscopes, with 41 Illustrations, 10 whole page engravings, post free, 7 stamps.

BROWNING'S new Cheap Series of high-power Objectives, ½-in. 80°, £2 7*s.* 6*d.*; ⅛-in. 90°, £2 12*s.* 6*d*; ¼-in. 95°, £3 5*s.* 0*d.*

JOHN BROWNING,

Optical and Physical Instrument Maker to H.M. Government, the Royal Society, the Royal Observatories of Greenwich, Edinburgh, &c., &c.

63, STRAND, LONDON, W.C.

Factory—Southampton Street and Exeter Street, London.

PRIZE MEDAL, 1862. ESTABLISHED 100 YEARS.

Telescopes, Spectroscopes, Opera Glasses, &c., &c.

TRAVELLERS' SCIENTIFIC REQUISITES.



ANEROID BAROMETER with ALTITUDE SCALE, THERMOMETER and COMPASS in Flat Pocket Case, various Forms,

£7 7s. and £8 8s.

Price Lists of Instruments free by post.

NEGRETTI & ZAMBRA,

Opticians and Scientific Instrument Makers

TO HER MAJESTY THE QUEEN,

HOLBORN VIADUCT,

45, CORNHILL, & 122 REGENT STREET, LONDON.

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 48N, Tollington Road, Holloway, London, N.

LIVERPOOL COLLEGE of CHEMISTRY, LIVERPOOL.

Founder ... ... Dr. SHERIDAN MUSPRATT.
Principals ... ... Drs. TATE AND GRANVILLE H. SHARPE.

Special advantages offered to Students.
Assays, Analyses, and Chemical Investigations conducted.
For Prospectuses, apply to the Principals.

UNIVERSITY OF LONDON MATRICULATION, JUNE, 1881.

Special Classes for this Examination will be formed at St. Thomas's Hospital Medical School, Albert Embankment, to commence on March 1st. The Special Classes for the Preliminary Scientific and 1st M.B. Examinations have now commenced. Full particulars can be obtained from the Secretary, Dr. GILLESPIE.

SEDBERGH SCHOOL, YORKSHIRE.

SIX SCHOLARSHIPS of £40, £30, and £20. Examination in April. Apply to Head-Master, HENRY HART, Esq., School House, Sedbergh, Yorkshire.

INSTRUCTION IN MATHEMATICS.—

Youths or Adults attended at their Residence, on Reasonable Terms, by a M.A. of Cambridge. Unquestionable references if required.—Address, by letter, O. P., Post Office, Turnham Green.

PREHISTORIC AND ANTIQUARIAN

COLLECTION for Sale; containing many interesting and choice Specimens from all parts of the World, formed with much trouble and at considerable expense. Apply for Particulars by Post to R. P. GREG, Esq., F.G.S., &c., Coles, Buntingford, Herts.

EVERY BOY A GEOLOGIST.

Now ready, and highly recommended, complete, price 7s. 6d.

This admirable little Work and most extraordinary Cabinet of wonderfully well-selected Natural Specimens, together with other Geological Preparations, and a powerful Lens, are calculated to start a boy thinking till he has mastered for himself no ordinary knowledge of the formation of the Earth's Crust.—THOMAS J. DOWNING, GEOLOGIST, &c., 38, Whiskin Street, London, E.C.—Catalogues free.

GEOLOGY.—In the Preface to the STUDENT'S ELEMENTS of GEOLOGY, by Lyell, 1874, he says: "As it is impossible to enable the reader to recognise rocks and minerals at sight by aid of verbal descriptions or figures, he will do well to obtain a well-arranged collection of specimens, such as may be procured from Mr. TENNANT (149, Strand), Teacher of Mineralogy at King's College, London." These Collections are supplied on the following terms, in plain Mahogany Cabinets:—

100 Specimens, in Cabinet, with 3 Trays	£2	2	0
200 Specimens, in Cabinet, with 5 Trays	5	5	0
300 Specimens, in Cabinet, with 9 Drawers	10	10	0
400 Specimens, in Cabinet, with 13 Drawers	21	0	0

More extensive Collections at 50 to 5,000 Guineas each.

GEOLOGY AND MINERALOGY.

Special Collections for Teachers and Students, used with success by all Lecturers and Teachers of Geology in Great Britain. Obtained Gold and Bronze Medals at Sydney Exhibition, 1879, also in London, 1862, and Paris, 1867.

200 Specimens in Cabinet	£2	2	0
100 ditto ditto	1	1	0
50 ditto ditto	0	10	6

New Lists of Collections, Apparatus, &c., now ready, and free on application to

JAMES R. GREGORY'S
Geological Museum and Repository,
88, CHARLOTTE STREET, FITZROY SQUARE.

MINERALOGY AND GEOLOGY.

MAGNIFICENT DERBYSHIRE FLUOR SPAR VASE. Height, with Pedestal, 2ft. 8in.; Diameter 13½in. This is, with one exception, the finest vase of the kind known, the vein having been worked out some forty years ago.

FINE PINK APOPHYLITE, EISENROSE, CONNELLITE, CALC SPAR, BARYTA, FAHLERZ, LIBETHENITES.

COLLECTIONS FOR STUDENTS, from £2 2s. COLLECTIONS FOR BEGINNERS, from 4s. BLOWPIPE CASES AND APPARATUS.

PRIVATE LESSONS AND EVENING CLASSES.

Catalogues free.

SAMUEL HENSON,
277 (*Late* 113*a*), STRAND, LONDON, W.C.

LIVING SPECIMENS FOR THE MICROSCOPE.

THOMAS BOLTON, NATURALISTS' and MICROSCOPISTS'
STUDIO, 57, NEWHALL STREET, BIRMINGHAM.

T. B. has last week sent to his subscribers a young American Trout *Salmo fontinalis*, in the Alevin Stage, with Drawing and Description. In this Stage it is admirably adapted for showing the Circulation of the Blood and the Action of the Heart.

Weekly announcements will be made in this place of organisms T. B. is supplying.

Specimen Tube, One Shilling, post-free.

Twenty-six Tubes in course of Six Months for Subscription of £1 1s.

Price List of Specimens on application, with stamped addressed envelope.

Portfolio of Drawings, No. 4, One Shilling.

On the 1st of every Month, price Sixpence.

THE ENTOMOLOGIST:

AN ILLUSTRATED JOURNAL OF BRITISH ENTOMOLOGY.
Edited by JOHN T. CARRINGTON,
With the Assistance of
FREDERICK BOND, F.Z.S. | JOHN A. POWER, M.D.
EDWARD A. FITCH, F.L.S. | J. JENNER WEIR, F.L.S.
F. BUCHANAN WHITE, M.D.

Contains Articles by well-known Entomologists on all branches of the Science; on Insects injurious or beneficial to Farm or Garden; Notes on Habits, Life-Histories; occurrence of Rarities, &c.; there are monthly lists of Duplicates and Desiderata.

Numerous WOODCUT ILLUSTRATIONS, to the printing of which especial attention is given, and occasional LITHOGRAPHED and CHROMO-LITHOGRAPHED PLATES.

SIMPKIN, MARSHALL, & CO., Stationers' Hall Court.

"The leading Farmers' paper."—CLARE SEWELL READ, ESQ., M.P.

THE CHAMBER OF AGRICULTURE JOURNAL AND FARMERS' CHRONICLE

(PRICE 3*d.* WEEKLY).

The representative organ of the Central and Provincial Chambers of Agriculture; *gives fuller reports of the discussions and proceedings* of this extensive organisation than any other agricultural paper. It devotes *special attention to the treatment of Agricultural Questions by Parliament*, besides containing ample Reports of the LATEST LONDON and COUNTRY CORN, CATTLE, HOP, PROVISION, and other Markets, with Original Articles on Practical Farming, the Dairy, Herd and Flock News, Horticulture, &c., &c. It is despatched every Monday evening in time for the country post.

Terms of Subscription, payable in advance, post free:—3 months, 3s. 9½d.; 6 months, 7s. 7d.; 12 months, 15s. 2d.

Published by W. PICKERING, 21, Arundel Street, Strand, London, W.

NORTH BRITISH AGRICULTURIST

is the only Agricultural Journal in Scotland, and circulates extensively amongst Landed Proprietors, Factors, Farmers, Farm-bailiffs, and others interested in the management of landed property throughout Scotland and the Northern Counties of England.

The AGRICULTURIST has also a very considerable circulation on the Continent of Europe, America, Australia, and the Colonies.

The AGRICULTURIST is published every Wednesday afternoon in time for the evening mails, and contains Reports of all the principal British and Irish Markets of the week, besides Telegraphic Reports of those held on the day of publication.

The Veterinary Department is edited by one of the leading Veterinarians in the country, and is invaluable to the breeder and feeder as a guide to the rearing of animals, and their treatment when labouring under disease.

Full Reports are given of the Meetings of the Royal Agricultural Society of England, the Royal Agricultural Society of Ireland, the Highland and Agricultural Society of Scotland, the Scottish Chamber of Agriculture, and all the principal Agricultural Associations throughout Great Britain and Ireland.

For Advertisers addressing themselves to Farmers a better medium does not exist

Price 3*d.* By post 3½*d.* Annual Subscription, payable in advance, 14s.

Office—377, High Street, Edinburgh.

Post-Office Orders payable to Charles Anderson, Jun., Edinburgh.

ESTABLISHED 1843.

THE BREWERS' GUARDIAN:

A Fortnightly Paper devoted to the Protection of Brewers' Interests, Licensing, Legal, and Parliamentary Matters.

REVIEW OF THE MALT AND HOP TRADES; AND WINE AND SPIRIT TRAD RECORD.

The Organ of the Country Brewers.

"The Brewers' Guardian" is published on the evenings of every alternate Tuesday, and is the only journal officially connected with brewing interests. Subscription, 16s. 6d. per annum, post free, dating from any quarter-day. Single Copies 1s. each. Registered for transmission abroad.

Offices—5, Bond Court, Walbrook, London, E.C.

On the 1st of every Month.

TRIMEN'S JOURNAL OF BOTANY,

BRITISH AND FOREIGN.

New Series. Edited by JAMES BRITTEN, F.L.S., British Museum.

CONTENTS.—Original Articles by leading Botanists.—Extracts, and Notices of Books and Memoirs.—Articles in Journals.—Botanical News.—Proceedings of Societies.

Price 1s. 3d. Subscription for One Year, payable in advance, 12s.

London: WEST, NEWMAN, & CO., 54, Hatton Garden, E.C.

THE CHEMICAL NEWS AND JOURNAL OF PHYSICAL SCIENCE.

EDITED BY W. CROOKES, F.R.S., &c.

Published every Friday. Price *4d.*

No. 1109 (Friday, February 25) contains:—Viscosity of Gases at High Exhaustions, by W. Crookes, F.R.S.—Reduction of Mr Crookes's Experiments on the Decrement of the Arc of Vibration of a Mica Plate in Bulb, containing Rarefied Gas, by Prof. G. G. Stokes, Sec.R.S.—Determination of Sulphur in Sulphides and in Coal and Coke, by Dr. T. M. Drown.—Chemistry of Sewage Precipitation, by Dr. W. Wallace.—Proceedings of Societies.—Notices of Books.—Correspondence.—Chemical Notices from Foreign Sources.—Notes and Queries, &c. &c.

London: Boy Court, Ludgate Hill, E.C.

PRICE 1*s.* MONTHLY.

MACMILLAN'S MAGAZINE

FOR MARCH, 1881.

CONTENTS.

1.—"The Portrait of a Lady." By Henry James, Jun. Chapters XXI.—XXIV.
2.—"Christmas and Ancestor Worship in the Black Mountain." By Arthur J. Evans. Part III.
3.—"Byron." By Matthew Arnold.
4.—"Connemara." By Robert J. Martin.
5.—"The Penny Press." By Francis Hitchman.
6.—"On a Recent Criticism of Mr. Swinburne's." By Alfred Austin.

MACMILLAN & CO., LONDON.

DIAMONDS IN MATRIX.

R. C. NOCKOLD, Diamond and Oriental Stone Cutter and Dealer, has for sale Specimens of the above; also Cut Precious Stones in all Colours.

Precious Stones valued and bought.

18. FRITH STREET. SOHO, W.

Chaque Samedi 16 pages grand in-8°, 2 colonnes

REVUE HEBDOMADAIRE

Scientifique, illustrée, spéciale, seul journal tenant les lecteurs au courant de tous les détails de l'Exposition universelle d'électricité, organe indépendant des exposants

RÉDACTEUR EN CHEF : W. de FONVIELLE

E. de CLISSON : DIRECTEUR

Un numéro, **40** *centimes. — L'année*, **18** *francs. Union postale* **20** *francs.*

PARIS. 16. rue du Croissant. PARIS

Envoi de numéros spécimens gratis sur demande.

THE ENTOMOLOGIST'S MONTHLY MAGAZINE.

Price Sixpence, Monthly, 24 pages 8vo, with occasional Illustrations.

Conducted by C. G. BARRETT, J. W. DOUGLAS, R. MCLACHLAN, F.R.S., E. C. RYE, F.Z.S., E. SAUNDERS, F.L.S., and H. T. STAINTON, F.R.S.

This Magazine, commenced in 1864, contains standard articles and notes on all subjects connected with Entomology, and especially on the Insects of the British Isles.

Subscription—Six Shillings per Volume, post free. The volumes commence with the June number in each year.

Vols. I. to VI. (strongly bound in cloth) may be obtained by purchasers of the entire set to date, at the increased price of 10*s.* each; the succeeding vols. may be had separately or together, at 7*s.* each.

London: JOHN VAN VOORST, 1, Paternoster Row.

N.B.—Communications, &c., should be sent to the Editors at the above address.

In unserem Verlage erscheint:

DER NATURFORSCHER.

Wochenblatt zur Verbreitung der Fortschritte in den Naturwissenschaften.

Herausgegeben von Dr. WILHELM SKLAREK.

Wochentlich 1—1½ Bgn. in 4°.

Preis vierteljährlich 4 Mk.

Die nunmehr ihren XIV. Jahrgang beginnende Zeitschrift hat bei Allen, welche sich mit Naturwissenschaften beschäftigen, grossen Beifall gefunden.

Probenummern sind durch jede Buchhandlung zu erhalten.

Berlin, S.-W., 77, Charlottenstr.

FERD. DÜMMLER'S VERLAGSBUCHHANDLUN

(Harrwitz & Gossmann.)

Now publishing, in Crown 8vo. Price 2*s.* 6*d.* each.

ENGLISH MEN OF LETTERS.

Edited by JOHN MORLEY.

*** Upwards of 150,000 Vols. of this series have been sold.

WORDSWORTH. By F. W. H. MYERS.

"Mr. Myers gives us a picture of the man and an estimate of his work which is certainly not inferior to anything that has preceded it."—*Academy.*

LOCKE. By Prof. FOWLER.

"In the case of Locke's biographer we venture to say that Mr. Morley has been exceptionally fortunate. A pen more competent than Prof. Fowler's for this particular work might have been sought, and sought in vain."—*Examiner.*

BYRON. By Prof NICHOL.

"Decidedly one of the most careful and valuable of the whole series."—*Athenæum.*

POPE. By LESLIE STEPHEN.

"The writer's eminent qualities as a critic, his judgment, his wit, his abundant knowledge of eighteenth-century literature, and his keen enjoyment of literary form, have equipped him handsomely for the task he has undertaken."—*St. James's Gazette.*

COWPER. By GOLDWIN SMITH.

"Mr. Goldwin Smith has sketched, in a few decisive touches, the genius of the poet and weakness of the man."—*Daily News.*

CHAUCER. By Prof. A. W. WARD.

"Far away the best connected account of Chaucer and his works to be found in English."—*Academy.*

BUNYAN. By J. A. FROUDE.

"He has given us a real study of Bunyan's life and character, and at the same time a real study of his books."—*Athenæum.*

SOUTHEY. By Prof. DOWDEN.

"A truly scholarly and delightful monograph."—*Examiner.*

HAWTHORNE. By HENRY JAMES, JUN.

"He has made a careful, conscientious, and even vivid literary portrait, such as few of our own writers could have made."—*New York Nation.*

MILTON. By MARK PATTISON.

"Mr. Pattison's achievement is deserving of high praise. He has put life into old facts, he has taken an impartial estimate of a great man whose name is too often used for purposes of poetry."—*Spectator.*

JOHNSON. By LESLIE STEPHEN.

"The new series opens well with Mr. Leslie Stephen's sketch of Dr. Johnson. It could hardly have been done better, and it will convey to the readers for whom it is intended a juster estimate of Johnson than either of the two essays of Lord Macaulay."—*Pall Mall Gazette.*

SCOTT. By R. H. HUTTON.

"We could not wish for a more suggestive introduction to Scott and his poems and novels."—*Examiner.*

GIBBON. By J. C. MORISON.

"As a clear, thoughtful, and attractive record of the life and works of the greatest among the world's historians, it deserves the highest praise."—*Examiner.*

SHELLEY. By J. A. SYMONDS.

"The lovers of this great poet are to be congratulated at having at their command so fresh, clear, and intelligent a presentment of the subject, written by a man of adequate and wide culture."—*Athenæum.*

HUME. By Prof. HUXLEY, F.R.S.

"It may fairly be said that no one now living could have expounded Hume with more sympathy or with equal perspicuity."—*Athenæum.*

GOLDSMITH. By WILLIAM BLACK.

"Mr. Black brings a fine sympathy and taste to bear in his criticism of Goldsmith's writings"—*Athenæum.*

DEFOE. By W. MINTO.

"Mr. Minto's book is careful and accurate in all that is stated, and faithful in all that it suggests."—*Athenæum.*

BURNS. By Principal SHAIRP.

". . . None of the series has given a truer estimate either of character or of genius than this volume."—*Spectator.*

SPENSER. By the Very Rev. the DEAN OF ST. PAUL'S.

"Dr. Church is master of his subject, and writes always with good taste."—*Academy.*

THACKERAY. By ANTHONY TROLLOPE.

"Mr. Trollope's sketch is excellently adapted to fulfil the purpose of the series in which it appears."—*Athenæum.*

BURKE. By JOHN MORLEY.

"It is no disparagement to the literary studies already published in this admirable series to say that none of them have surpassed, while few have equalled, this volume on Burke."—*British Quarterly Review.*

*** *Others in Preparation.*

MACMILLAN AND CO., LONDON.

FOR SALE.

A MAGNIFICENT DERBYSHIRE

FLUOR SPAR VASE.

THE OLD BULL BEEF VARIETY,

HEIGHT WITH WHITE FLUOR AND BLACK MARBLE PEDESTAL 2 FEET 8 INCHES, DIAMETER 13½ INCHES.

SAMUEL HENSON, *Mineralogist, &c.*, 277 (Late 113A), Strand, London, W.C.

SOCIETY FOR PROMOTING CHRISTIAN KNOWLEDGE.

MANUALS OF ELEMENTARY SCIENCE.

Fcap. 8vo, limp cloth, 1*s.*

Just published

ELECTRICITY. By Professor Fleeming Jenkin, F.R.S. With numerous illustrations.

NATURAL HISTORY OF BRITISH FISHES: Their Structure, Economic Uses, and Capture by Net and Rod. Cultivation of Fish-Ponds, Fish suited for Acclimatisation, Artificial Breeding of Salmon. By the late FRANK BUCKLAND, H.M. Inspector of Fisheries. With numerous Woodcuts. Crown 8vo, cloth boards, 5*s.*

"The Christian Knowledge Society has done well in republishing such a delightful, and at the same time valuable book."—*Graphic.*

CHIEF ANCIENT PHILOSOPHIES.

[This Series of Books will deal with the Chief Systems of Ancient Thought, not merely as dry matters of History, but as having a bearing on Modern Speculation.]

EPICUREANISM. By William Wallace, M.A., Fellow and Tutor of Merton College, Oxford. Fcap. 8vo, satteen cloth boards, 2*s.* 6*d.*

"This little volume appears to us an almost model handbook."—*Pall Mall Gazette.*

STOICISM. By the Rev. W. W. Capes, M.A., Fellow of Hertford College. Fcap. 8vo, satteen cloth boards, 2*s.* 6*d.*

"To sum up, we think the style and tone of the book worthy of high praise; its moral and philosophic criticism singularly just and searching."—*Pall Mall Gazette.*

"We may permit ourselves to point to the clearness and style of arrangement which distinguish both these little treatises."—*Times.*

MANUALS OF HEALTH.

Fcap. 8vo, 128 pages, limp cloth, 1*s.* each.

The Habitation in Relation to HEALTH. By F. S. B. FRANÇOIS CHAUMONT, M.D., F.R.S., Professor of Military Hygiene in the Army Medical School, Netley.

"The book, small as it is, should be in every house."—*Land and Water.*

On Health and Occupation. By BENJAMIN WARD RICHARDSON, Esq. F.R.S., M.D., M.A.

"The Manuals of Health, published by the Society for Promoting Christian Knowledge, should be in the possession of every family that is not utterly careless of its own safety and welfare."—*Illustrated London News.*

On Personal Care of Health. By the late E. A. PARKES, M.D., F.R.S.

"The Society for Promoting Christian Knowledge has conferred a very great benefit, principally on the poor and on those who have much intercourse with the poor, but incidentally on persons in all ranks, by the publication of this little manual on personal care of health."—*Pall Mall Gazette.*

Food. By Albert J. Bernays, Professor of Chemistry at St. Thomas's Hospital.

"Nothing could be better than Dr. Bernays' little work, and we cordially recommend it to every one that finds it necessary to consider either his stomach or his purse."—*Church Times.*

Water, Air, and Disinfectants. By W. NOEL HARTLEY, Esq., King's College.

"The present volume, from the pen of Mr. Hartley, is well fitted to become a recognised authority, friend, and companion in every home in England."—*Echo.*

LONDON: NORTHUMBERLAND AVENUE, CHARING CROSS, S.W.; 43, QUEEN VICTORIA STREET, E.C.; and 48, PICCADILLY, W.

Just Published, price 2*s.* 6*d.*

An ELEMENTARY COURSE of PRACTICAL PHYSICS. By A. M. WORTHINGTON, M.A., F.R.A.S., Assistant Master at Clifton College.

RIVINGTONS, Waterloo Place, Pall Mall, London.

Recently Published,
Demy 4to, with 18 Plates (5 printed in Colours), 207 pages, cloth, £2 2*s.*

AURORÆ:
THEIR CHARACTERS AND SPECTRA.
By J. RAND CAPRON, F.R.A.S.

Part I.—THE AURORA AND ITS CHARACTERS.
Part II.—THE SPECTRUM OF THE AURORA.
Part III.—MAGNETO-ELECTRIC EXPERIMENTS IN CONNECTION WITH THE AURORA.

By the same Author.
Demy 8vo, with 37 Plates, cloth, 30*s.*

PHOTOGRAPHED SPECTRA.

One Hundred and Thirty-Six Photographs of Metallic, Gaseous, and other Spectra, printed by the Permanent Autotype Process, with Introduction, Description of Plates, and Index, and with an Extra Plate of the Solar Spectrum (showing bright lines) compared with the Air Spectrum.

London: E. & F. N. SPON, 16, Charing Cross.

DIAGRAMS

TO ILLUSTRATE LECTURES. Prepared by ROBERT FORSYTH, Chryston, near Glasgow.

Just Published, demy 8vo, cloth, with Chart, price 15*s.*

ON SOME PROPERTIES OF THE EARTH.

By O. REICHENBACH.

London: WERTHEIMER, LEA, & CO., Circus Place, London Wall.

ROYAL POLYTECHNIC.—CLASSES for the Preparation of Students for University Examinations, under the direction of EDWARD B. AVELING, D.Sc., F.L.S. London University Matriculation, 1st and 2nd B.Sc., Preliminary Scientific M.B., Botany, Physiology, Chemistry. All the work practical.

POTTERY.

A SERIES OF URNS, &c.,

INCLUDING

BRITISH, ROMAN, SCANDINAVIAN, PERUVIAN.

To be Sold at Extremely Low Prices, the Owner being desirous of immediately parting with them.

BRYCE-WRIGHT,
90, GREAT RUSSELL STREET, LONDON, W.C

THURSDAY, FEBRUARY 24, 1881

PROFESSOR MAX MUELLER AT UNIVERSITY COLLEGE

UNIVERSITY COLLEGE, London, is to be congratulated on the fresh step which was celebrated on Wednesday last week. The new wing which was then formally opened, and which will be largely devoted to scientific teaching, and let us hope research as well, will give the College more elbow-room in its career. Of course the "toasting" and speechifying at the dinner were largely collegiate, the speakers generally expressing their approval of the principles upon which University College and similar institutions have been founded. We have repeatedly called attention not only to the admirable educational work which University College has done since its foundation, but to the influence it has had on the higher teaching all over the country. Not only has it been in a sense the parent of not a few similar institutions, the number of which is almost every year on the increase, but it has undoubtedly had much to do with rousing from the lethargy of generations the two oldest and wealthiest universities of the country. Much as has been done recently in the way of reforming these two great educational centres, the work has been little more than begun. The advocates of university reform may therefore congratulate themselves that Prof. Max Müller was called upon to reply to the toast of "British Universities." His reply was not likely to be, and certainly was not, compounded of the common-places usually uttered on such occasions. Prof. Max Müller has reason to be grateful to Oxford, and his gratitude he expressed in terms of genuine tenderness. "At the same time," he went on to say, "Oxford, or at all events my friends at Oxford, have no feelings but those of sincere rejoicing at the springing up, and growing, and spreading of what may be called the young universities, the universities of the future. We watch them rising in every part of England as we watch the rising of new planets. We greet them as on a stormy night we greet new lighthouses coming into sight and shooting their rays of electric light through the darkness—yes, the darkness of this so-called enlightened century, the darkness visible, and best visible to those who have spent their lives in the study of even the smallest subject, and know how every one of them still bristles with problems that cannot be solved without a large collection of new facts, and without bringing to bear on them more powerful batteries of thought than are yet at our command."

Prof. Müller was so far loyal to his *Alma Mater* as to admit that the Oxford of the past has done good work; but the Oxford of the present is doing better work, and we trust with him that the Oxford of the future will do infinitely better work still. How the desirable end is to be accomplished is a problem that all true friends of learning in the country are anxious to have solved, and to attempt to solve which the recent Universities Commissioners were appointed. We do not mean at present to criticise the work which these Commissioners have been attempting to do; how far short that work is of anything like a high standard of reform may best be seen by comparing what is known of their recommendations with the aspirations expressed in Prof. Max Müller's admirable speech.

"To compare the work that Oxford or Cambridge could do, and ought to do, with that of any other university, whether British or Continental, is simply absurd. Oxford, with its excellent material, the well-fed and well-bred youth of these islands; Oxford, with its many students who have not to work for their bread; Oxford, with its rich colleges and libraries and fellowships, can do for the advancement of learning fifty times over what Giessen or even Leipsic can do. Oxford and Cambridge could beggar the whole world and make the old universities the home of all English genius, all English learning, all English art, all English virtue."

Alas, how far are we from realising what Prof. Müller modestly called his "German dreams"! But that these "dreams" are perfectly realisable Prof. Müller went on to show by facts and figures based on the report of the Commissioners themselves. Why, in accordance with his suggestion, should a certain number of prize fellowships at Oxford not be thrown open to the whole of England? Prof. Müller's suggested scheme is as wide and liberal as the most advanced friends of education could wish, including the practical endowment of research in all departments of literature, science, and art.

"Prize Fellowships," he went on to say, "are in future to be tenable for five or seven years only. This is quite right. But if after five or seven years a young man has developed a taste for scientific work and wishes to continue it, then let him have a second Fellowship, again with duties attached to it, and let that man, with the proceeds of two Fellowships, do the work and fill the place which the Extraordinary Professors fill in Continental universities. Lastly, if after another five years the few who remain true to a scientific life can show that they have done good work and are able and willing to do still better work, let them have a third Fellowship and become permanent Professors in the University on an income of about 1000*l.* a year for life. I must not enter into fuller detail," Prof. Müller went on, "I only wanted to sketch out to you how the national funds of national universities could be made to subserve truly national interests: how Prize Fellowships could be made a blessing both to the giver and the receiver, and how England could stamp out of the ground an army of, call them soldiers, or missionaries, or colonists, or men—true men of science, such as the past has never dreamt of. All this could be done to-morrow, and no one would suffer from it. I know I shall be told—in fact I have been told—that such changes are far too great; that the fathers who send their boys to Oxford and Cambridge would not approve them, and—this is always the last trump—that public opinion is against them. With regard to public opinion, if public opinion—if Parliament—is against us we must bow and wait. As to the fathers of boys—*ces pères de famille*—I am one of them myself, and I do not think we are always the most disinterested judges. As to changes, great or small, Nature teaches us that nothing can live which cannot grow and change, and history confirms her lesson that nothing is so fatal to institutions as a faith in their finality."

The scheme is one which, in its essential points,

has received the approval of the *Times*. "In fact," that journal concludes, in a leading article on the speech, "if the objects proposed by Prof. Müller for attainment are desirable in themselves, there ought to be no difficulty in obtaining funds for the purpose In view of what the Commissioners have sanctioned in principle for one College at least in Oxford, it can hardly be said that the objects aimed at are either very visionary or very far in advance of public opinion. If Prize Fellowships may legitimately be used for the purpose of giving some men a start in ordinary life, it is difficult to see why they should not also be used, within reasonable limits, for giving others a modest provision for the pursuit of a learned career."

Why not? every one is likely to repeat except those who imagine they have a vested interest in being supported in idleness on what is really the property of the nation. By so doing, the university would once more make an approach to what it was intended to be, a really national institution. The change would incommode none but idlers, and those who have at heart the real advancement of science and learning must be convinced that the present isolation of both universities can lead to nothing but stagnation. Oxford especially, with its silent and all but deserted laboratories, could only gain by an accession of activity from the outside. Only thus indeed, only by having regular additions of fresh energy, can the place be kept sweet and wholesome; and if once this principle be accepted, as indeed it must be, and the sooner the better, there need be little difficulty in regulating its application. At present it would be difficult to calculate how much of the best intellectual energy of the country is wasted or misapplied, simply because there is no channel open by which it may be guided into the course in which it could do the best work.

There were several other subjects touched upon by the speakers at the University College dinner, to which we have not space to refer. Prof. Morley's tribute to the memory and the work of Mr. Carlyle was well-timed and appropriate, coming as it did just when the country was awed by its recent loss. Mr. Carlyle often said hard things of science, as he did of everything else under the sun. All the same, his methods and his philosophy were as scientific as they could well be, being simply his peculiar applications of the doctrine of the reign of inevitable law everywhere. Apart from this, and while we might disagree with everything he said and positively taught, it must be admitted that the inspiration of his teaching gave fresh energy and earnestness to scientific research, as it did to every other sphere of intellectual activity.

ATLAS OF HISTOLOGY

Atlas of Histology. By E. Klein, M.D., F.R.S., and E. Noble Smith, L.R.C.P., M.R.C.S. (London: Smith, Elder, and Co., 1880.)

MODERN histology is not yet fifty years old, but fifty years old in the nineteenth century means a great deal, and it is rather a matter of surprise that no English work entirely devoted to histology should have yet appeared than that we should be welcoming the largest and in some respects the most important illustrated work on that subject in this or any language.

That modern histology is most faithfully represented in the book before us becomes abundantly evident on looking at the figures and their description. We find the tissues and organs of the body delineated under every aspect and after every possible method of treatment; hardened with chromic acid, osmic acid, picric acid; stained with hæmatoxylin, carmine, aniline blue; submitted to the action of gold and silver salts and otherwise prepared *lege artis*. Of the value of these in elucidating structure there can be no question whatever, but at the same time we think it would have been well in a comprehensive work of this description had more space been given to the representation of the tissues in their living condition and unaltered by the action of reagents: the almost complete absence of allusion to and representation of the fresh tissues being a defect in the book.

Dr. Klein, in selecting the subjects for illustration, and Mr. Noble Smith in executing them, alike deserve high praise. Many of the figures are evidently as near an approach to facsimile of the preparations as can well be attained, and it need hardly be said that the preparations themselves, made as they are by so skilful a histologist, are as good in all probability of their kind as it is possible to make them.

In looking through the plates one is especially struck with the excellent manner in which the minute anatomy of the various organs is detailed, indeed the part of the work which relates to the structure of the viscera is in all respects better than that in which the simple tissues are dealt with. The illustrations of the latter are comparatively meagre, and in many cases too small, considering the size and aim of the work. This is very marked in the figures of the blood and in those of cartilage and osseous tissue, as well as in the illustrations of the structure of voluntary muscle. On the other hand, the development of bone is well and carefully represented, especially so far as the more intimate processes are concerned; but we miss the general features of bone-formation, such as the first calcification of the primitive cartilage bone, the periosteal irruption, and so on. The nervous tissue is also abundantly and beautifully illustrated, and here we are glad to observe that Dr. Klein has availed himself of the magnificent representations given by Key and Retzius in their monograph on the nervous system: representations that could scarcely have been improved upon, and to compete with which would have involved needless labour.

That the lymphatic system should occupy an important part of the work was to be expected from the fact that we already owe to Dr. Klein two monographs wholly devoted to that system, and from them, as well as from the plates in the "Handbook for the Physiological Laboratory," some delineations are here republished. With the exception of these and one or two other less important instances the figures throughout the book are new, and will no doubt for many years furnish a stock to which both teachers and authors may come for diagrams and illustrations.

As before remarked, the representations of the minute structure of the viscera are particularly good, and will prove useful in replacing many of the coarse and semi-diagrammatic figures which at present occupy a prominent place in the text-books of histology and physiology. We

may signalise those of the stomach and those of the kidney—the structure of the last-named organ being illustrated with particular minuteness. One is glad to think that one's examinations are over on finding that there are now no less than sixteen several named parts to be remembered in describing the course of a uriniferous tubule!

We have hitherto been writing as if the book before us were an Atlas of Plates and their description, and nothing more. This is emphatically not the case however, for the plates are accompanied by a text written by Dr. Klein, which forms a complete and independent compendium of the present state of histology, giving in plain terms and as briefly as is consistent with clearness, an account of the minute structure of each tissue and organ. In this account credit is given wherever possible to those to whom the discovery of new facts is due, but it is, we think, to be regretted that the references to the works in which the facts were published has not been added; such a notice of the literature of each subject would have been of much value.

At the end of the book a description of the appearances which are presented by nuclei in process of division will be found, embodying the results of the recent researches of Strasburger, Flemming, Mayzel, Klein, and others; results which have not unnaturally created a feeling of wonderment that in objects which have long engaged the special attention of histologists, changes of so marked a character should occur, and until now have wholly escaped observation.

We see that endothelium is still described as a tissue distinct from and indeed in contradistinction to epithelium, but it seems to be upon its last legs, for it now has to depend for existence upon a negative definition, and no longer presumes to base its claims to the place upon its developmental history.

There is a general tendency throughout the text to teach the subject somewhat dogmatically, and this, with the absence of detailed reference to literature, detracts from its value as a work of reference, while perhaps increasing its value as a text-book for students. Taking the work however as a whole it is not too much to say that it is in every way worthy of the high reputation of its principal author, and that its appearance, supplying as it does a want that has been long felt, will be welcomed by histologists both at home and abroad.

OUR BOOK SHELF

Urania: an International Journal of Astronomy. Edited by Ralph Copeland, Ph.D., and J. L. E. Dreyer, M.A.

THE first number of what is intended to be a high-class astronomical periodical, with the above title, has just appeared, and forms twenty-four pages demy quarto. It is proposed to issue it in numbers of from sixteen to twenty-four pages, whenever sufficient material offers, with shorter numbers when subjects of immediate interest require it. Papers will be accepted and printed in French, German, and Italian. This first number is well supported. It contains an article on the solution of Lambert's equation by Prof. Klinkerfues, and auxiliary tables for the calculation of occultations of stars by the moon, by Dr. C. Borgen. The Earl of Crawford and Balcarres contributes observations of comets 1880 *b*, *c*, and *d* made at Dunecht; the Earl of Rosse has a paper on determinations of lunar radiant heat during an eclipse; and Dr. R. S. Ball communicates an investigation of the parallax of the star Groombridge 1618, which is No. 89 in Argelander's list of stars with large proper motions, the observations having been made at Dunsink in 1878-79: a parallax to the amount of a third of a second is indicated by the measures both of distance and position, so that, as Dr. Ball remarks, there is reason to consider Groombridge 1618 entitled to a place amongst the sun's nearest neighbours. Dr. Copeland has a note upon a nebula detected at Dunecht on the method of sweeping suggested by Prof. Pickering of Harvard College, U.S., which is termed "a new planetary nebula." The nebula however is not new; it was discovered several years since by Mr. S. C. Burnham with a refractor of 6-inches aperture, and was notified at the end of his third catalogue of new double-stars: it is referred to also in the notes to his observations of double-stars in 1877-78, in the *Memoirs* of the Royal Astronomical Society, vol. xliv.: he found it to be double, the distance between the centres of the two parts and a star of 9m. (which appears to be *Durch.* + 47°, No. 3289), being 27″·3 at the epoch 1878·47. The double nucleus has also been remarked at Dunecht, and the measures of position and distance made there have a particular interest when compared with Mr. Burnham's in 1878; thus we have—

Burnham,	1878·476	...	Position, 88°·5	...	Distance, 2″·57
Dunecht,	1880·913	...	,, 71°·9	...	,, 8″·00

Such differences surely indicate rapid motion. Dr. Copeland does not allude to the star of about ninth magnitude distant less than half a minute of arc in 1878. This journal may be obtained by applying to Mr. J. L. E. Dreyer, Observatory, Dunsink, Co. Dublin.

LETTERS TO THE EDITOR

[*The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts. No notice is taken of anonymous communications.*

The Editor urgently requests correspondents to keep their letters as short as possible. The pressure on his space is so great that it is impossible otherwise to ensure the appearance even of communications containing interesting and novel facts.]

Infusible Ice

PROF. CARNELLEY'S directions in NATURE, vol. xxiii. p. 341, just received, for producing the hitherto fabulous commodity, "hot ice," have succeeded so much beyond our expectations for a first experiment in our College laboratory to-day, that the ease and simple means with which the experiment was performed, and the unaccountable and unaccustomed appearances which it presented, recommend it very strongly, as Prof. Carnelley remarks in his paper, and as I hope that the following description may also serve to prove, to other observers' trials and repetitions.

A 30 oz. flask of stout glass (made nearly as strong as the Carré decanters, for vacuum experiments) was tightly fitted, by forcing a two inch plug of large solid india-rubber tube placed round a tube into its mouth and firmly fixing it there with wire, with a delivery-tube of three-eighths of an inch large glass barometer-tube about two feet long. This tube was bent into an S-shape, and at the extreme end of the small U-part, which turned up, it was drawn out to a nearly capillary neck and bent over to communicate by india-rubber tubing through another similar flask surrounded by cold water to act as a condenser, with a Swan's aspirator giving a vacuum of twenty-eight inches by the action of the town water-supply. About 15 oz. of distilled water previously introduced was now boiled in the flask *in vacuo*, and distilled over, at a very gentle heat, into the second flask. After two or three hours' boiling the quantity of water in the flask was reduced to about 3 oz., and the capillary end of the tube was then sealed with a blowpipe. The flask thus exhausted makes an excellent water hammer and cryophorus, ringing with sharp raps when the water is shaken to and fro in it or in its tube. The least warmth of the flask, or cold applied to the U-part of the tube, suffices to collect there, by distillation, a quantity of beautifully clear water completely freed from air.

To obtain the rapid evaporation and superheated state of ice, the U part of the tube was placed in a freezing-mixture of ice and salt till the condensed water coated the tube internally with a hollow sleeve of ice extending in the long and short parts of the U to a total length of about eight inches, and the flask itself was thereupon placed in a sawdust-bedded tin pail containing a large freezing-mixture of 5 lbs. of salt and 10 lbs. of pounded ice. Hydrochloric acid was at the same time added to the frigorific mixture round the U-tube, lowering the temperature of that part of the cryophorus to − 29° C. (− 20° F.), which had the effect of cracking the ice-sleeve (apparently by contraction) in all directions, giving rise at first, from its appearance, to the apprehension that the glass tube was completely splintered! Now came the critical operation. Would the hard frozen ice-coat bear the application of the heat ordeal without melting?

The freezing mixture round the U-tube was replaced by cold water in a water-bath, which was heated rapidly with a Bunsen-flame. About two inches of the ice-sleeve in the long part of the tube stood above the surface of the water; the rest soon melted, while the temperature of the water in the bath rose to 70° C., and a thick rime of white frost from the condensed vapours of this water formed round the tube containing the projecting part of the ice-tongue, which must have been intensely cold, since the rime almost touched the surface of the warm water. Below the surface of the water the tube appeared always to contain some snowy-looking solid, along with what resembled water proceeding from its liquefaction. When the temperature of the bath reached 70° C. the projecting ice-tongue was still unmelted; it had replenished itself by condensing and freezing the vapours rising up to it from below, and formed a snowy plug in the tube an inch or more long.

The water-bath was then removed in order to heat this snow-plug with a Bunsen-flame, and to our extreme surprise a similar snow-lining was found still to remain coating, quite dry, the whole long part and much of the short part of the U-bend. The flame was applied, and the whole tube was heated violently without for some time appearing to have the least effect upon the white crust within, notwithstanding the tube was too hot to be touched! A small flake weighing at most a few tenths of a grain, at the bottom of the U, withstood the strongest heat there for several minutes, wasting insensibly away, and unchanged in shape, until it vanished with perhaps a moment's collection to a drop as it disappeared. As it slowly grew thinner the white coating in the tube seemed in general to be no more affected by the heat than white feathers would have been; but in particular parts there often occurred partial liquefaction or pasty fusion allowing pieces of the film to turn over by their weight and roll or slip down the glass while still adhering to it, quite in the manner of drops. That the liquid itself, completely freed from air, refuses to boil, and may be described in that respect as practically oily, was evident enough in the preparation of the flask, when except by sudden bumps the distillation of vapour, however much it was urged by heat, and seen to be passing copiously through the bent worm-tube, proceeded almost entirely from the surface of the water in the flask.

In these drops at least, adhering to the heated glass, it seems difficult to believe that the solid ice which makes them angular, jagged in form, and pasty, can be anything but superheated; and it seems also scarcely credible that the latent heat of sublimation of the insignificant weight of a few grains of ice-crust in the tube resisting its strong heat for many minutes can reach the large amount of its gain of heat in that time by conduction and radiation from the surrounding tube, if the ice-film is at no higher temperature than its natural melting-point. These are questions however which the calorimetric methods devised and pursued by Prof. Carnelley are best designed to answer, and to which replies without such positive determinations can only be urged at present as probable conjectures, or as clear preceptions and presentiments, on the other hand, of the action and operation of some hitherto undiscovered thermal laws.

Whether by direct sublimation, or by evaporation accompanied by liquefaction, the slender snowdrift with its enlargement at the top was gradually reduced in thickness, and subdivided into remaining parts along its length, which all adhered to the tube until they wasted away, and the largest top piece never fell by withdrawal of support below, but, like the rest, it clung like a thin scale to the last to its original place on one side of the tube. This power of adhesion of hermetically volatilised ice to hot bodies with which it is in contact forms, as Prof. Carnelley observes, one of its most marked, although not at all one of its most prognosticable, properties, and it certainly prompts, if it does not unequivocally substantiate, the supposition that the ice in such close contact with extremely hot bodies must be superheated, or at a temperature sensibly higher than its natural melting-point.

The perfect success of the experiment and the beautiful appearance of the ineffaceable white snow-lining of the tube afforded us unqualified pleasure and surprise, and the simple preparation and preservation of the cryophoric apparatus needed for its exhibition will, I have no doubt, cause the experiment to be often reproduced and shown wherever freezing-mixtures and the cryophorus, and Boutigny's and Leidenfrost's phenomena, and Prof. Carnelley's theory and researches, are subjects of lecture-demonstrations.

A. S. HERSCHEL

College of Physical Science, Newcastle-on-Tyne, February 15

Dust, Fogs, and Clouds

I NEED not say that the information contained in M. H. J. H. Groneman's letter in NATURE, vol. xxiii. p. 337, was a most unexpected surprise. Nothing whatever seems to have been known in England about the results obtained by Messrs. Coulier and Mascart; and my astonishment was not diminished when I considered that their important investigation had borne no fruit, never having been practically applied by meteorologists or others.

I have just seen the article by M. Coulier in the *Journal de Pharmacie et de Chimie*, and will (with your permission) make a few remarks on his paper and on my own. M. Coulier was led to the discovery of the important part played by dust in the condensation of vapour, by making experiments on the well-known cloudy condensation produced by expanding saturated air. Instead of the ordinary air-pump arrangement M. Coulier's apparatus consisted of a glass flask, in which was placed some water. This flask was connected by a tube to a hollow india-rubber ball. He first compressed the india-rubber ball, thus compressing the air in the flask. The pressure was then removed from the ball, when the air in the flask expanded, and the condensation became visible.

In making repeated experiments with this apparatus M. Coulier noticed that the action of the air was capricious. After the air had remained in the flask some days he found it quite inactive. He also found it inactive after shaking it up with the water in the flask, and that on expelling some of the inactive air and replacing it with the air of the room the cloudiness again appeared. He then found that if he filtered the air before admitting it to the flask it did not give any cloudiness when expanded, and he explains with perfect clearness that the dust in the air formed the nuclei on which the vapour condensed.

Having explained the manner in which M. Coulier approached the subject I shall now give the history of the corresponding part in my work and show the direction from which I approached it. I had been studying the action of "free surfaces" in water and other forms of matter, when changing from one state to another. I knew that water could be cooled below the freezing-point; I was almost certain ice could be heated above the melting-point, and I had shown that water could be heated far above the boiling point; that the material of which the vessel holding the water was composed had no influence on the result—and all that was necessary to prevent the change of state taking place, at the freezing and boiling points, was an absence of "free surfaces" at which the change could begin. Arrived at this point, the presumption was very strong that vapour could be cooled below the "condensing point" without changing to water, if no "free surfaces" were present. I first intended to experiment with steam at the pressure of the atmosphere, but found difficulties in operating at so high a temperature. I then made arrangements to conduct the experiments at a lower temperature, and for convenience experimented on steam mixed with air. I then saw that dust in the air would form "free surfaces" on which the vapour would condense. I therefore attached a cotton-wool filter to the apparatus, and filtered the air before it entered the receiver. When this was done I found that the steam on entering the receiver was perfectly invisible, and gave rise to no cloudy condensation, the air remaining supersaturated. The experiment was immediately afterwards repeated somewhat in the same way as was done by M. Coulier, the air being supersaturated by expanding it by means of an air-pump.

Though the two investigations approached the subject from very different points, they seem afterwards to have flowed in almost parallel directions. Starting from his first experiments,

M. Coulier made experiments with the products of combustion from flames in which the combustion was as perfect as possible. He found these gases much more active than the air of the room. This he attributed to particles of unconsumed carbon. He also found the air after rain and storms to be less active, and the air in summer less active than in winter. After extending the experiments to alcohol and benzine, the paper concludes with some remarks on the peculiar action of ozone.

Up to this point the two investigations run perfectly parallel, and the strange likeness between the two sets of experiments is not the least interesting point connected with them. After going over this first paper by M. Coulier, I found he had communicated a second paper, which will also be found in the same volume of the *Journal de Pharmacie et de Chimie*, at page 254. This second paper is almost entirely occupied with a description of some experiments in which inactive air was heated and rendered active.

In the first experiment described in M. Coulier's second paper a platinum wire was heated in the purified air of the flask, after which the air was active. In the second experiment pure air in which hydrogen was burned became active. In the third experiment pure air which was passed through a glass tube surrounded with tinsel ("clinquant"), and moderately heated, was made active. Fourth experiment, oxygen, nitrogen, and hydrogen became active after they had been heated in a tube. After describing some effects in ventilation when *highly* heated air is used, he says, "In the preceding note (the first paper) I believed I could attribute the activity of the air to the presence of solid bodies, and it seemed to me that the only solid body that could escape from a carbon flame could be nothing but carbon itself. It was the remarkable experiment, so easily made, of filtering air through cotton-wool, that led me to form this hypothesis, which the experiments above related invalidate (à faire cette hypothèse, que les expériences relatées plus haut infirment)." He concludes by saying, "The explanation of these phenomena remains still to be found."

Experiments exactly corresponding to some of those described in M. Coulier's second paper will be found in mine. Wishing to test the effect of combustion on air, I first made experiments to test the effect of heat on the apparatus to be used in collecting the hot gases. For this purpose I passed filtered air through a heated glass tube, after which I found it was remarkably active. It was found however that this activity is not due, as M. Coulier seemed to suppose, to the heating of the air, but to impurities driven off the surface of the tube by the heat. This was proved by showing that the air remained inactive when the hot tube through which it was passed was thoroughly cleansed.

In making experiments on the effect of burning gas I arranged a platinum wire, connected with a battery, to enable me to light the gas in the pure air of the receiver. On testing the action of the heated wire alone, it was found that simply heating the wire gave rise to cloudiness. It was however found that by highly heating the wire its activity was destroyed, all impurities being driven off.

These experiments explain M. Coulier's first and third experiments. The fourth experiment is also to be explained by the nuclei driven off the tube by the heat. These nuclei may be driven off in the solid state, or as gases which condense without nuclei when *highly* supersaturated on being cooled to the temperature of the flask. The nuclei are in some cases formed by chemical union of the gases driven off by the heat, and in other ways unnecessary to enter upon here. As to the second experiment, more information is required as to arrangement of apparatus, &c., before any opinion can be formed as to the origin of the nuclei.

It now appears to me that this second paper explains why the first results of M. Coulier, though repeated and confirmed by M. Mascart, have not received that general acceptance we should have expected. In his second paper he describes a number of results which he did not succeed in fitting into his hypothesis. They even seemed to him to shake his first conclusions, and the uncertain sound given by his second paper seems to have blighted any fruit his first paper was likely to have produced. There can however be no doubt that M. Coulier was the first to show the important part played by dust in the cloudy condensation of the vapour in air, and his first paper clearly explains its action. It seems highly probable that if it had not been followed by his second paper, or if he had succeeded in getting the key to the explanation of his experiments, and his conclusions had confirmed instead of weakening the teaching of his first paper, his result would long ere now have been applied to explain the different causes and the different forms of cloudy condensation in our atmosphere, as well as other physical phenomena.

Darroch, Falkirk, February 15 JOHN AITKEN

Geological Climates

I DESIRE to express my thanks to Dr. John Rae for the valuable contribution of "facts" which he has added to this interesting question, of which I hope to make use in due time.

I wish also to answer the question asked by Prof. Woeikoff in his letter of February 17. My authority for January, July, and mean temperatures in the northern hemisphere and in the southern is the most recent and accurate available, viz., United States Coast Survey, "Meteorological Researches for the use of the Coast Pilot," Part I, by William Ferrel (Washington, 1877). Mr. Ferrel gives the January and July temperatures for every ten degrees of longitude and latitude, up to 80° N. and 60° S. as follows, so far as regards the annual means :—

Lat. N.	Annual.	Lat. S.	Annual.
°	°	°	°
0 ...	80·1 F. ...	0 ...	80·1 F.
10 ...	81·0 ,, ...	10 ...	78·7 ,,
20 ...	77·6 ,, ...	20 ...	74·7 ,,
30 ...	67·6 ,, ...	30 ...	66·7 ,,
40 ...	56·5 ,, ...	40 ...	57·9 ,,
50 ...	43·4 ,, ...	50 ...	47·8 ,,
60 ...	29·3 ,, ...	60 ...	35·3 ,,
70 ...	14·4 ,, ...	70 ...	—
80 ...	4·5 ,, ...	80 ...	—

This table fully justifies what I said of the southern hemisphere as compared with the northern, and is, of course, explained by the existence of three great gulf streams in the south, which raise the mean temperature, producing insular climates with a small range from July to January.

Mr. Ferrel adds, at the close of his discussion (p. 22) :—

"From Dove's Charts of Isothermal Lines, which do not extend beyond the middle latitudes in the southern hemisphere, it has been inferred that the southern hemisphere is colder than the northern, and this has been the accepted view ever since his charts were first published, in the year 1852; but from the results obtained above it is seen that the mean temperature of the southern hemisphere is the greater of the two."

I was well aware that the east coast of Asia is colder, latitude for latitude, than the east coast of North America, but this has nothing to do with reducing the temperatures of the east coast of America, by means of alterations in the ocean currents of the North Atlantic, which I deny to be possible.

SAMUEL HAUGHTON

Trinity College, Dublin, February 19

Climate of Vancouver Island

As questions connected with the climate of Vancouver Island and the influence on it of ocean currents have lately been the subject of several communications in the pages of NATURE, it may be worth while to draw attention to the fact that Esquimalt, at the southern extremity of the island, together with several places on the mainland of British Columbia, have now been for a number of years occupied as regular stations of the Canadian Meteorological Service, and that trustworthy meteorological results are to be found in the annual reports to Government.

When writing a report on British Columbia for the Canadian Pacific Railway Survey in 1877, I applied to Prof. Kingston, then in charge of the Meteorological Department, for some information on climate, and received from him an abstract, which was published at the time ("Can. Pacific Ry. Report, 1877," p. 246), by which it appears that the mean summer temperature of Esquimalt is 57°·82 F., mean winter temperature 34°·45, mean annual temperature 47°·97. This does not include however the additional results of the last few years.

Much information on the climate of the northern part of the north-west coast may also be found in the *Alaska Coast Pilot*, 1869, and the *U.S. Pacific Coast Pilot*, Appendix I, 1879. In the latter, series of monthly and mean annual isothermal lines are given for the air and sea surface, which—though the observations at command are by no means complete—are doubtless nearly correct. A partial abstract of these, with some discussion

of the climatic features of British Columbia, may be found in an appendix written by me for the Canadian Pacific Railway Report of 1880, p. 107.

The mean temperature of Tongass at the southern extremity of Alaska, from two years' observations, is stated as 46°·5.

Observations have been maintained at Sitka with little interruption for a period of forty-five years. The latitude of this place is 57° 3′, or about one degree north of Glasgow. The mean temperatures are as follows:—spring 41°·2, summer 54°·6, autumn 44°·9, winter 32°·5, and for the year 43°·3.

According to the *Pacific Pilot* above quoted, that portion of the Kuro-siwo, having a temperature of 55° F. or more, approaches the coast in the vicinity of Vancouver Island. Temperatures not much lower than this however prevail much further north. The average temperature of the surface of the sea during the summer months in the vicinity of the Queen Charlotte Islands as determined by me in 1878 ("Report of Progress, Geological Survey of Canada, 1878-79") is 53°·8. Observations by the U.S. Coast Survey in 1867, in the latter part of July and early in August between Victoria and Sitka, gave a mean surface-temperature of 52°·1.

GEORGE M. DAWSON

Geological Survey of Canada, February 1

"The New Cure for Smoke"

IT was not my intention to trouble you further on this subject at present, but as Dr. Siemens has been good enough to notice the result of my trials with the coke-gas grate, and has asked a question with reference to the grate used by me, it is due to that gentleman that I should at once explain that the grate in which the trials were made is of modern construction and permanently fitted with side-cheeks and back of fire-clay lumps, and that when in use with the coke and gas the back was fitted with a copper plate, and in all other respects the grate was arranged in the manner described and illustrated in NATURE, vol. xxiii. p. 26.

J. A. C. HAY

On the Space Protected by Lightning-Conductors

THE very interesting article by Mr. W. H. Preece on the "Space Protected by a Lightning-Conductor" (*Phil. Mag.* 5th series, vol. x. p. 427 *et seq.*, December, 1880) revives this important practical question. The old rule, first enunciated by M. Charles, which makes the radius of the protected circular area around the base of the rod equal to twice its vertical height, has never been satisfactorily verified either on theoretical or experimental grounds. This rule was adopted in the Report of the Commission of the French Academy of Sciences drawn up by M. Gay-Lussac in 1823 (*Ann. de Chim. et de Phys.* 2nd series, t. 26, p. 258), and also in two other reports drawn up by M. Pouillet, one in 1854 (*Comptes rendus*, t. 39, p. 1142), and the other in 1867 (*Comptes rendus*, t. 64, p. 102). But still more recently the Committee appointed by the Préfet de la Seine to superintend the construction of lightning-conductors in the City of Paris, in their Report in February, 1876, *reduced* the radius of the protected area to 1·45 times the height of the rod. I am ignorant on what grounds the Commission adopted this precise number.

In this state of the problem Mr. Preece's paper was both apposite and welcome. The rule which he deduces certainly has the merit of *definiteness*; but it seems to me that it fails to be *practically satisfactory*. For it is very evident that his investigation is exclusively applicable to "*Blunt-Conductors*," since the "*Power of Points*" is entirely left out of consideration. His deductions might apply to the *blunt*-conductors which crowned the Royal Palace of George III., but are scarcely applicable to the *pointed* rods now employed! His investigation assumes that the *distance* of the earth-connected objects from the electrified cloud is the *only element* which determines the *direction* of the discharge. It seems to me that the well established "power of points" to discharge, or rather to *neutralise* the electricity of charged conductors, is an essential element in the problem of the protected space.

It is a well-known fact that when an electrified cloud approaches a *pointed* lightning-conductor which is in good conducting connection with the earth, the sharp point becomes charged by induction with opposite electricity of *high tension* long before the distance between them approximates that required for a *disruptive* discharge; so that electricity of the opposite kind from that of the cloud *escapes* from the point in the form of a *connective discharge* or electrical *glow*, and *neutralises* that of the cloud, and thus silently *disarming* it, *averts* the disruptive stroke of lightning. This *neutralisation*, due to the power of points, constituting the *preventive action* of lightning-conductors, is justly regarded as the *most important* function of such rods; although, under certain extraordinary circumstances, they may be forced to carry disruptive discharges. Under any circumstances, however, it is obvious that *pointed* conductors must *enlarge* the protected area as compared with *blunt* conductors.

It is very difficult, if not impossible, to estimate in a precise manner how this *power of points* would *modify* and *distort* the *equipotential surfaces* in the intervening electric field. The problem is evidently one of great complexity. The following circumstances must obviously influence, to a greater or less extent, the *magnitude* and *direction* of the resultant electromotive force, which determines the path of discharge, *convective* or *disruptive*, viz.: (1) *Distance* of thunder-cloud from the point of the conductor; (2) variable *dielectric properties* of the intervening air; (3) *size* of the cloud; (4) the variable *tension* of its electric charge, especially under the neutralising action of the pointed rod; and (5) the *velocity* with which the thunder-cloud approaches the point of the conductor. The *last* consideration is very important, and at the same time most difficult to formulate; for the *convective neutralisation* is a *gradual* process requiring *time*. It is evident that a heavily-charged thunder-cloud *rapidly* driven towards the point of the conductor might give rise to a *disruptive* spark, while, if *slowly* approaching the same, it would have been *silently neutralised*, and the stroke averted. In fact the strength and direction of the resultant force is influenced by so many variable conditions that it would tax the resources of a powerful calculus to indicate a formula which would satisfy, even approximately, the demands of practice in the construction of lightning-conductors.

Nevertheless, it is quite certain that Mr. Preece's rule, which makes the radius of the protected circular area equal to the *height* of the rod for *blunt* conductors, is perfectly *safe* for *pointed* rods; for there can be no question as to the fact that the "power of points" *enlarges* the protected area.

The late Prof. Henry frequently witnessed the efficacy of convective discharges from the point of the lightning conductor attached to the high tower of the Smithsonian Institution. During violent thunder-storms at night, at every flash of lightning he observed that "a jet of light, at least five or six feet in length, issued from the point of the rod with a hissing noise."

It is proper to add that while the circumstances influencing *disruptive* discharges of electricity have been experimentally investigated by a number of physicists, the laws of *convective* discharges from points do not seem to have received attention from any experimenter. Thus I have not been able to find a satisfactory answer to the following elementary inquiry, viz.—Under given conditions, at what *distance* will a pointed conductor connected with the earth *begin* to neutralise the electricity of an insulated conductor by the convective discharge of the opposite kind of electricity from the point?

In short, the whole subject of the "power of points," although one of the best-established and most conspicuous phenomena in electricity, is sadly in need of experimental investigation. This class of electrical phenomena is pretty much in the same condition in which Franklin left it more than a century ago.

Berkeley, California, January 1 JOHN LE CONTE

[Mr. Preece has shown by considering the area between the conductor and the charged cloud as an electric field mapped out in equipotential surfaces and lines of force, that "a lightning-rod protects a conic space whose height is the length of the rod, whose base is a circle having its radius equal to the height of the rod, and whose side is the quadrant of a circle whose radius is equal to the height of the rod."—*Phil. Mag.*, December, 1880.—ED.]

Localisation of Sound

MY friend the Rev. H. J. Marston, Second Master of the School for Blind Sons of Gentlemen at Worcester, has communicated to me some very singular instances of the power of localising sound possessed by blind boys.

One of the games in which his pupils most delight is that of *bowls*. A bell is rung over the nine-pins just as the player is ready to throw the bowl, when, totally blind as he is, he delivers it with considerable accuracy of aim. Mr. Marston vouches for the fact that it is no uncommon feat for a boy to strike down a single pin at a distance of forty feet three times in succession.

It is significant that this game cannot be played by the blind boys in windy weather. And yet the allowance for windage on a heavy bowl can be no very large quantity.

The boys also play football with great zeal and considerable skill. Bells are rung at the goals throughout the game, and the ball contains two little bells. With these guides the boys manage both to follow the ball and to direct it to the goals.

Clifton College, February 15 H. B. JUPP

Migration of the Wagtail

THE inclosed extract from the New York *Evening Post*, a newspaper of high standing for accuracy and intelligence, contains statements which are not, I think, generally known in regard to the migration of the water-wagtail, and your insertion of the same may be the means of drawing from other correspondents some evidence in confirmation or disproof. Though riding is not quite unknown among animals other than men, yet such purposeful riding as is here described is, to say the least, very extraordinary. E. W. CLAYPOLE

Antioch College, Yellow Springs, Ohio, Dec. 12, 1880

The Singular Methods of Travel the Wagtail adopts to Cross the Mediterranean Sea.—In the autumn of 1878 I spent several weeks on the Island of Crete. On several occasions the papas—village priest—a friendly Greek with whom I spent the greater part of my time—frequently directed my attention to the twittering and singing of small birds which he distinctly heard when a flock of sand-cranes passed by on their southward journey. I told my friend that I could not see any small birds, and suggested that the noise came from the wings of the large ones. This he denied, saying, "No, no! I know it is the chirping of small birds. They are on the backs of the cranes. I have seen them frequently fly up and alight again, and are always with them when they stop to rest and feed." I was still sceptical, for with the aid of a field-glass I failed to discover the "small birds" spoken of. I inquired of several others, and found the existence of these little feathered companions to be a matter of general belief among both old and young. I suggested that possibly the small birds might go out from the shore a short distance and come in with the cranes. "No, no," was the general answer, "they come over from Europe with them." I certainly heard the chirping and twittering of birds upon several different occasions, both inland and out upon the sea. But in spite of the positive statements of the natives I could not believe their theory until convinced one day while fishing about fifteen miles from the shore, when a flock of cranes passed quite near the yacht. The fishermen, hearing the "small birds," drew my attention to their chirping. Presently one cried out "There's one," but I failed to catch sight of it. Whereupon one of them discharged his flint-lock. Three small birds rose up from the flock and soon disappeared among the cranes.

I subsequently inquired of several scientific men, among whom were two ornithologists, as to the probability of such a state of affairs. They all agreed that it could not be, and I, too, was forced to cling to my original judgment, and let the matter go. Recently however while reading the *Gartenlaube* my attention was attracted to an article bearing directly upon the subject. The writer, Adolf Ebeling, tells the same story, and adds the statements of some ornithologists of distinction, which makes the whole matter so striking and interesting that I quote the paragraph from his book :—

"Shortly after my arrival in Cairo I greeted various old German friends among the birds that I observed in the palm-garden of our hotel. First, naturally, was the sparrow, the impudent proletariat—I had almost said social democrat, because the whole world to-day has that bad word in the mouth. He appeared to me to be more shameless than ever in the land of the Pharaohs, for he flew without embarrassment on the breakfast table, and picked off the crumbs and bits from every unwatched place. But the mark of honour we paid to the wagtails, and in truth chiefly because we did not then know that the wagtails were birds of passage. We had thought that they passed the winter in Southern Europe, or at farthest as many of them do, in Sicily and the Grecian Islands. That they came to Africa, and especially to Nubia and Abyssinia, was then unknown to us. This appeared to us singularly strange, nay, almost incredible, particularly on account of the peculiar flight of the wagtail, which it is well known always darts intermittingly through the air in longer or shorter curves, and apparently, every few moments, interrupts its flight to sit again and 'wag its tail.' But there was the fact, and could not be denied. Everywhere in the gardens of Cairo you could see them under the palms that border the banks of the Nile; on the great avenues that lead to the pyramids; nay, even on the pyramids themselves in the middle of the desert. And there it was that I first heard of this singular phenomenon.

"One evening we were sitting at the foot of the pyramid of Cheops, sipping our cup of fragrant Mocha and in jolly conversation, rolling up clouds of blue smoke from our Korani cigarettes. We were waiting for the sinking of the sun to make our return to Cairo. The deep silence of the surrounding desert possessed something uncommonly solemn, only now and then disturbed by the cry of the hoarse fishhawks far above us. Still higher the pelicans were grandly circling. Their flight, though heavy when seen from anear, possesses a majesty in the distance attained by no other bird. Right before us several wagtails were hopping around and 'tilting.' They were quite tame, and flew restlessly hither and thither. On this occasion I remarked, 'I could not quite understand how these birds could make the long passage of the Mediterranean.' Sheik Ibrahim heard this from our interpreter. The old Bedouin turned to me with a mixture of French and Arabic as follows, which the interpreter aided us to fully comprehend :—

"'Do you not know, Hadretch (noble sir), that these small birds are borne over the sea by the larger ones?'

"I laughed, as did our friends; for at first we thought we had misunderstood him; but no: the old man continued quite naturally :—

"'Every child among us knows that. These little birds are much too weak to make the long sea journey with their own strength. This they know very well, and therefore wait for the storks and cranes and other large birds, and settle themselves upon their backs. In this way they allow themselves to be borne over the sea. The large birds submit to it willingly; for they like their little guests, who by their merry twitterings help to kill the time on the long voyage.'

"It appeared incredible to us. We called to a pair of brown Bedouin boys, pointed out the wagtails to them, and inquired :—

"'Do you know whence come these small birds?'

"'Certainly,' they answered. 'The Abu Saad (the stork) carried them over the sea.'

"At supper, in the Hôtel du Nil, I related the curious story to all present, but naturally enough found only unbelieving ears.

"The only one who did not laugh was the Privy Councillor Heuglin, the famous African traveller, and, excepting Brehm, the most celebrated ornithologist of our time for the birds of Africa. I turned to him after the meal, and inquired of his faith. The good royal councillor smiled in his caustic way, and with a merry twinkle remarked: 'Let the others laugh: they know nothing about it. I do not laugh, for the thing is known to me. I should have recently made mention of it in my work if I had had any strong personal proof to justify it. We must be much more careful in such things than a mere story-teller or novel-writer; we must have a proof for everything. I consider the case probable, but as yet cannot give any warrant for it.'

"My discovery, if I may so call it, I had kept to myself, even after Heuglin had thus expressed himself, and would even now maintain silence on the subject had I not recently discovered a new authority for it."

I read lately in the second edition of Petermann's great book of travels the following :—

"Prof. Roth of Munich related to me in Jerusalem that the well-known Swedish traveller, Hedenborg, made the following interesting observation on the Island of Rhodes, where he stopped. In the autumn tide, when the storks come in flocks over the sea to Rhodes, he often heard the songs of birds without being able to discover them. Once he followed a flock of storks, and as they lighted he saw small birds fly up from their backs, which in this manner had been borne over the sea. The distance prevented him from observing to which species of singing birds they belonged."

Thus wrote the famous geographer Petermann. Prof. Roth and Hedenborg and Heuglin are entirely reliable authors. This was a matter of great curiosity to me, and after I found others had made similar observations and expressed them in print, I thought they would be of no less curiosity and interest on this side of the Atlantic, and equally deserving of public notice. I hope that connoisseurs, amateurs, and experts may be excited by this to extend their observation in this line also. The instinct of animals is still, in spite of all our observations and experience,

almost a sealed book to us. By a little attention we might hear of still more curious things in this field. PHONE

New York, November 20, 1880

Subsidence of Land caused by Natural Brine-Springs

A THEORY has been put forward to account for the subsidence of land in the salt districts of Cheshire. It is said that, supposing the manufacturers of salt ceased to pump up the brine, it would run away to the sea, and subsidence would go on at as rapid a rate as now. Can any of the readers of NATURE tell me of any *facts* to substantiate such a theory, or refer me to any district where such rapid subsidence is going on, owing to the escape of natural brine-springs to the sea? Any reference to works giving information on this point will be thankfully received. THOS. WARD

Northwich, February 15

Chlorophyll

THE following experiment may be interesting in its bearing on the relation between chlorophyll-development and light.

If cress seed are grown for a few days in the dark on damp cotton-wool, and then, beneath the surface of water, introduced into an inverted glass jar filled with water, they may be exposed to daylight for an indefinite time without chlorophyll being developed. But the plants are not dead; for if, after a few days' exposure, the cotton-wool on which they have been grown is cut in two beneath the surface of the water, and one half, with its plants, is restored to the inverted jar of water, while the other is placed under an inverted glass jar containing air only, and then these two jars be exposed to full daylight, the plants beneath the jar containing air rapidly become green, while the others never do so.

Light therefore cannot always cause the development of chlorophyll in the etiolated leaves of living plants.

Liverpool, January 24 WILLIAM CARTER

[This is an interesting observation, but seems to need some further investigation. As shown by Sachs ("Text-book," pp. 665, 666) the formation of chlorophyll has a complicated dependence upon light. If the temperature be sufficiently high it is formed in the cotyledons of conifers and the leaves of ferns even in complete darkness. The seedlings of angiosperms require exposure to light for the production of chlorophyll, but it does not take place at low temperatures. All the visible parts of the spectrum possess the power of turning etiolated grains of chlorophyll green, although the yellow and adjoining rays are most effective. The failure of the seedlings immersed in water to become green can hardly therefore be attributed to the absorption of the heat rays. Is it possible that their water-bath keeps their temperature too low?]

Squirrels Crossing Water

IN NATURE, vol. xxiii. p. 340, I read that Mr. Godwin-Austen never had heard of a squirrel taking to the water. As here are perhaps more readers of NATURE in Mr. Godwin-Austen's case, I take this opportunity to transcribe what Bachman related to us about that matter in the year 1839.

The northern grey and black squirrel *Sciurus leucotis*, has occasionally excited the wonder of the populace by its wandering habits and its singular and long migrations. Like the lemming, *Lemmus norvegicus*, of the Eastern Continent, it is stimulated, either from a scarcity of food or from some other inexplicable instinct, to leave its native haunts and seek for adventures or for food in some distant and, to him, unexplored portion of our land. The newspapers from the West contain frequent details of these migrations; they appear to have been more frequent in former years than at the present time. The farmers in the Western wilds regard them with sensations which may be compared to the anxious apprehensions of the Eastern nations of the flight of the devouring locust. At such periods, which usually occur in autumn, the squirrels congregate in different districts of the far North-West, and in irregular troops bend their way instinctively in an eastern direction. Mountains and cleared fields, the head-waters of lakes and broad rivers, present no unconquerable impediments. Onward they come, devouring on their way everything that is suited to a squirrel's taste, laying waste the corn and wheat-fields of the farmer; and as their numbers are thinned by the gun, the dog, and the club, others are ready to fall in the rear and fill up the ranks, till they occasion infinite mischief and call forth no empty threats of revenge.

It is often inquired how these little creatures, that on common occasions have such an instinctive dread of water, are enabled to cross broad and rapid rivers, like the Ohio and Hudson, for instance. It is usually asserted, and believed by many, that they carry to the shore a suitable piece of bark, and seizing the opportunity of a favourable breeze, seat themselves upon this substitute for a boat, hoist their broad tails as a sail, and float safely to the opposite shore. This, together with many other traits of intelligence ascribed to this species, I suspect to be apocryphal. That they do migrate at irregular and occasionally at distant periods is a fact sufficiently established; but in the only instance in which I had an opportunity of witnessing the migrations of the squirrel, it appeared to me that he was not only an unskilful sailor, but a clumsy swimmer. It was (as far as my recollection serves me of the period of early life) in the autumn of 1808 or 1809, troops of squirrels suddenly and unexpectedly made their appearance in the neighbourhood, but among the grey ones were varieties not previously seen in those parts; some were broadly striped, with yellow on the sides, and a few with a black stripe on each side, bordered with yellow or brown, resembling the stripes of the little chipping squirrel (*Tamias lysteri*). They swam the Hudson in various places between Waterford and Saratoga; those which I observed crossing the river were swimming deep and awkwardly, their bodies and tails wholly submerged; several that had been drowned were carried downward by the stream, and those which were so fortunate as to reach the opposite bank were so wet and fatigued that the boys stationed there with clubs found no difficulty in securing them alive or in killing them. Their migrations on that occasion did not, as far as I could learn, extend farther eastwardly than the mountains of Vermont; many remained in the county of Rensellaer, and it was remarked that for several years afterwards the squirrels were far more numerous than before. It is doubtful whether any ever return westwardly; but finding forests and food suited to their tastes and habits, they take up their permanent residence in their newly-explored country; there they remain and propagate their species until they are gradually thinned off by the effects of improvement and the dexterity of the sportsmen around them. (*The Magazine of Natural History*, vol. iii., new series, 1839.)

Leyden, February 16 F. A. JENTINK

Flying-Fish

WITH reference to the letter of Mr. Pascoe in NATURE, vol. xxiii. p. 312, allow me to offer a suggestion as to the mechanical means by which the flying-fish moves when out of the water. During a voyage to India and back I took a great interest in observing the movements of these beautiful creatures by means of a powerful opera-glass; and soon came to the conclusion that a slight but rapid tremor of the pectoral fins could be seen for a few moments after the fish left the water. In very calm weather I noticed a series of little ripples on each side of the fish as it skimmed along the surface before rising for its flight, evidently caused by the wing-points tipping the water. My idea is that the flying-fish springs from the sea, and by beating the surface rapidly with its pectoral fins obtains an impetus which carries it along for some distance in the air. It then descends to the surface, and in the same manner acquires a fresh accession of speed. This process however is never repeated more than twice, though the fish does sometimes resume its flight after a moment of immersion. R. E. TAYLOR

THE TRANSIT OF VENUS

THE President of the Royal Society presents his compliments to the Editor of NATURE, and will be much obliged to him if he will, at as early a date as may be convenient, be so good as to give publicity to the enclosed minute of the Transit of Venus Committee.

The Royal Society, Burlington House,
London, W., February 21

"THE Committee appointed by the Royal Society, at the request of the Government, to make arrangements for observing the Transit of Venus in 1882, would be glad to be informed whether astronomers have at their disposal, and are willing to lend, for use in the observations, 4-inch, 5-inch, or 6-inch refracting telescopes, and 10-inch or 12-inch reflectors, with equatorial mountings; also portable transits or altazimuths.

"The instruments would be returned, in perfect order, as soon as possible after the transit, and, in any case, before the end of 1883.

"All communications should be addressed to the Secretary, Transit Committee, Royal Society, Burlington House."

The Committee, we are informed, is constituted as follows :—The President of the Royal Society is the chairman, the other members being Prof. J. C. Adams, the Astronomer-Royal, the Earl of Crawford and Balcarres, Mr. De la Rue, Mr. Hind, Dr. Huggins, Vice-Admiral Sir G. H. Richards, Prof. H. J. S. Smith, Prof. Stokes, and Mr. E. J. Stone.

DR. J. J. BIGSBY

YET another of the links that have bound the geologists of the present time in association with the early leaders of their science has been severed by the removal of the kindly and venerable form of Dr. Bigsby. Upwards of sixty years ago he began his geological career in North America, devoting himself mainly to the investigation of the structure of the older Palæozoic rocks of Canada and of the adjoining tracts of the States. As secretary to the Boundary Commission under the Treaty of Ghent he had opportunities of investigating the region from Quebec to Lake Superior, and published numerous descriptions, of which the exactness has been amply verified by the subsequent researches of the Geological Survey of Canada. It is chiefly as an admirable pioneer in Canadian geology that his name will be inscribed in the records of scientific progress. But he has other claims to grateful remembrance. Since he returned to spend his later years in this country he has devoted himself with the most untiring patience to the compilation of his "Thesaurus Siluricus" and "Thesaurus Devonicus"—works in which the geological and geographical range of the organisms of the earlier half of Palæozoic time is clearly shown in a series of valuable tables.

Still more recently, in 1877, he presented to the Geological Society a bronze medal which, with a sum of money derived from the interest of a fund also given by him, is to be awarded every two years as an incentive to geological study. The terms according to which he directed that the prize should be given are that the medal and interest from the fund should be awarded "as an acknowledgment of eminent services in any department of geology, irrespective of the receiver's country; but he must not be older than forty-five years at his last birthday, thus probably not too old for further work, and not too young to have done much." The founder lived to see two fitting awards of his prize go to the eminent palæontologists of the United States, Professors O. C. Marsh and E. D. Cope. He died just before the third presentation was made, last week, to Dr. Charles Barrois of Lille.

ON TIDAL FRICTION IN CONNECTION WITH THE HISTORY OF THE SOLAR SYSTEM[1]

THIS paper forms one of a series on the subject of tidal friction which have been read from time to time before the Royal Society and reported in NATURE.

The first part of the paper contains the investigation of the changes produced by tidal friction in the system formed by a planet with any number of satellites revolving about it in circular orbits. As the results cannot be conveniently stated without the aid of mathematical notation, they are here passed over.

The previous papers treated of the effects which tidal friction must have had on the motions of the earth and moon, on the supposition that time enough has elapsed for this cause to have its full effect. It then appeared that we are thus able to co-ordinate together the various elements of the motions of these two bodies in a manner too remarkable to be the product of chance.

The second part of the present paper contains a discussion of the part which the same agency may have played in the evolution of the solar system as a whole and of its several parts.

It is first proved that the rate of expansion of the planetary orbits, due to the reaction of the frictional tides raised by the planets in the sun must be very slow compared with that due to the reaction of the tides raised by the sun in the planets. Thus it would be much more nearly correct to treat the sun as a rigid body, and to suppose the planets alone to be subject to frictional tides, than the converse. It did not, however, seem expedient to attempt to give any numerical solution of the problem thus suggested which should apply to the solar system as a whole.

The effect of tidal friction is to convert the rotational momentum of the tidally disturbed body into orbital momentum of the tide-raising body. Hence a numerical evaluation of the angular momentum of the various parts of the solar system will afford the means of forming some idea of the amount of change in the orbits of the several planets and satellites, which may have been produced by tidal friction. Such an evaluation is accordingly made in this paper, with as much accuracy as the data permit.

From the numerical values so found it is concluded that the orbits of the planets round the sun can hardly have undergone a sensible enlargement from the effects of tidal friction since those bodies first attained a separate existence.

Turning to the several sub-systems, it appears that, although it is possible that the orbits of the satellites of Mars, Jupiter, and Saturn about their planets may have been considerably enlarged, yet it is certainly not possible to trace the satellites back to an origin almost in contact with the present surfaces of their planets, in the same manner as was done for the case of the moon in the previous papers.

The numerical values above referred to exhibit so marked a contrast between the case of the earth with the moon, and that of the other planets with their satellites, that it might *à priori* be concluded as probable that the modes of evolution have differed considerably. The conclusion above stated concerning the satellites of the other planets cannot therefore be regarded as unfavourable to the acceptance of the views maintained in the previous papers. It must, however, be supposed that some important cause of change other than tidal friction has been concerned in the evolution of the solar system and the planetary sub-systems. According to the nubular hypothesis of Laplace, that cause has been the condensation of the heavenly bodies. Accepting that hypothesis, the author then proceeds to consider the manner in which contraction and tidal friction are likely to have worked together.

A numerical comparison shows that, notwithstanding the greater age which the nebular theory assigns to the exterior planets, yet the effects of solar tidal friction in reducing planetary rotation must in all probability be considerably less for the remote than for the nearer planets. It is, however, remarkable that the number expressive of the rate of retardation of the Martian rotation by solar tidal friction is nearly the same as the similar number for the earth, notwithstanding the greater distance of Mars from the sun. This result is worthy of notice in connection with the fact that the inner satellite of Mars revolves with a periodic time much shorter than that of the planet's rotation; for (as suggested in a previous paper) solar tidal friction will have been com-

[1] An account of a paper entitled "On the Tidal Friction of a Planet attended by several Satellites, and on the Evolution of the Solar System," by G. H. Darwin, F.R.S., read before the Royal Society on January 20, 1881.

petent to reduce the planetary rotation without directly affecting the satellite's orbital motion.

It is then shown to be probable that solar tidal friction was a more important cause of change when the planets were less condensed than it is at present. Thus we are not to accept the present rate of action of solar tidal friction as indicating that which has held true in all past time.

It is also shown that if a planetary mass generates a large satellite, the planetary rotation is reduced after the change more rapidly than before; nevertheless the genesis of such a satellite is preservative of the moment of momentum which is internal to the planetary subsystem. This conclusion is illustrated by the comparatively slow rotation of the earth, and by the large amount of angular momentum residing in the system of moon and earth.

An examination of the manner in which the difference of distances of the various planets from the sun will have affected the action of tidal friction leads to a cause for the observed distribution of satellites in the solar system.

According to the nebular hypothesis a planetary mass contracts, and rotates quicker as it contracts. The rapidity of the revolution causes its form to become unstable, or perhaps, as seems more probable, an equatorial belt gradually detaches itself; it is immaterial which of these really takes place. In either case the separation of that part of the mass which before the change had the greatest angular momentum permits the central portion to resume a planetary shape. The contraction and increase of rotation proceed continually until another portion is detached, and so on. There thus recur at intervals a series of epochs of instability or of abnormal change.

Now tidal friction must diminish the rate of increase of rotation due to contraction, and therefore if tidal friction and contraction are at work together the epochs of instability must recur more rarely than if contraction acted alone.

If the tidal retardation is sufficiently great, the increase of rotation due to contraction will be so far counteracted as never to permit an epoch of instability to occur.

Now the rate of solar tidal friction decreases rapidly as we recede from the sun, and therefore these considerations accord with what we observe in the solar system. For Mercury and Venus have no satellites, and there is a progressive increase in the number of satellites as we recede from the sun.

Whether this be the true cause of the observed distribution of satellites amongst the planets or not, it is remarkable that the same cause also affords an explanation of that difference between the earth with the moon and the other planets with their satellites, which has permitted tidal friction to be the principal agent of change with the former, but not with the latter.

In the case of the contracting terrestrial mass we may suppose that there was for a long time nearly a balance between the retardation due to solar tidal friction and the acceleration due to contraction, and that it was not until the planetary mass had contracted to nearly its present dimensions that an epoch of instability could occur.

If the contraction of the planetary mass be almost completed before the genesis of the satellite, tidal friction, due jointly to the satellite and the sun, will thereafter be the great cause of change in the system, and thus the hypothesis that it is the sole cause of change will give an approximately accurate explanation of the motion of the planet and satellite at any subsequent time. It is shown in the previous papers of this series that this condition is fulfilled with the earth and moon.

The paper ends with a short recapitulation of those facts in the solar system which are susceptible of explanation by the theory of the activity of tidal friction. This series of investigations affords no grounds for the rejection of the nebular hypothesis, but while it presents evidence in favour of the main outlines of that theory, it introduces modifications of considerable importance.

Tidal friction is a cause of change of which Laplace's theory took no account, and although the activity of this cause is to be regarded as mainly belonging to a later period than the events described in the nebular hypothesis, yet its influence has been of great, and in one instance of even paramount, importance in determining the present condition of the planets and their satellites.

G. H. D.

INDIGO

IN July, 1878, an account was given in this journal of the synthesis of indigo-blue from phenylacetic acid, accomplished by Prof. Baeyer of Munich (NATURE, xviii. 251). The process there described did not permit of the successful production of indigo-blue on a manufacturing scale at reasonable cost. Since that time Prof. Baeyer has continued to work at the problem, and he has so far succeeded that he has now taken out a patent for the artificial manufacture and application of indigo-blue.

In a paper in the last number of the *Berliner Berichte* Baeyer gives an interesting *résumé* of the steps whereby progress has been slowly made, since 1865, in solving the problem of the synthesis of indigo.

Following up the work sketched in the article already referred to, Baeyer attempted to prepare *orthonitrophenyl acetic aldehyde*, expecting that this substance would yield indol, which may be regarded as the parent substance of the indigo group of compounds. But as the work proceeded Baeyer became more and more convinced that the hypothesis which had guided his earlier work was that which should still regulate his experiments. In 1869 he had written, "In order to prepare indol synthetically it is necessary—in accordance with the formula already given—to introduce a pair of carbon atoms and one nitrogen atom into benzene, and to link these together. The necessary conditions are found in *nitro-cinnamic acid*, if one supposes carbon dioxide and the oxygen of the nitro-group to be removed. And indeed it has been shown that nitro-cinnamic acid yields indol by fusion with potash." The steps in the preparation of indigo-blue, according to Baeyer's patent, are these:—

1. *Cinnamic acid* (or *phenyl acrylic acid*)—

$$C_6H_5 . C_2H_2 . CO_2H.$$

2. *Orthonitrocinnamic acid*—

$$C_6H_4\begin{cases}NO_2\\C_2H_2 . CO_2H.\end{cases}$$

3. *Orthonitrocinnamic acid dibromide*—

$$C_6H_4\begin{cases}NO_2\\C_2H_2Br_2 . CO_2H\end{cases};$$

prepared by acting on No. 2 with gaseous bromine and crystallising from benzene.

The dibromide in alcoholic solution is then treated with alcoholic potash, in the proportion of 1 : 2 molecules; and after dilution with water

4. *Orthonitromonobromcinnamic acid*—

$$C_6H_4\begin{cases}NO_2\\C_2HBr . CO_2H,\end{cases}$$

is precipitated. By again treating this acid with three molecules of alcoholic potash

5. *Orthonitrophenylpropiolic acid*—

$$C_6H_4\begin{cases}NO_2\\C_2 . CO_2H\end{cases}$$

is produced. When an aqueous solution of this acid is warmed with such feeble reducing agents as grape- or milk-sugar, in presence of caustic or carbonated alkali, indigo-blue separates in crystals. It is not however

necessary to prepare pure orthonitrophenylpropiolic acid; if orthonitrocinnamic acid (No. 2 above) be treated with bromine, then with alcoholic potash, and lastly with grape-sugar, without separating the various products indigo-blue is produced. Orthonitrocinnamic acid may be prepared, without difficulty, from oil of bitter almonds.

Artificial indigo may be directly printed on cloth by mixing orthonitrophenylpropiolic acid—or *orthonitrophenyloxyacrylic acid* described below—with soda and grape- or milk-sugar, and after proper thickening, soaking the cloth in the mixture, and heating: or the material may be simply soaked in orthonitrophenyloxyacrylic acid and heated.

Orthonitrophenyloxyacrylic acid is prepared by the action of alcoholic potash on an alcoholic solution of orthonitrophenylchlorolactic acid (itself prepared by the action of chlorine on orthonitrocinnamic acid), in accordance with the equation—

$$C_6H_4\begin{cases}NO_2\\ C_2H_2OCl\end{cases}.CO_2H + 2KOH = C_6H_4\begin{cases}NO_2\\ C_2H_2O\end{cases}.CO_2K + KCl + H_2O.$$

By boiling an aqueous solution of orthonitrocinnamic acid dibromide (No. 3 above) with sodium carbonate, indigo blue separates out. M. M. P. M.

MICROSCOPIC STRUCTURE OF MALLEABLE METALS

THE following observations on the minute structure of metals, which have been hammered into thin leaves, are instructive. Notwithstanding the great opacity of metals, it is quite possible to procure, by chemical means, metallic leaves sufficiently thin to examine beneath the microscope by transmitted light. Silver leaf, for instance, when mounted upon a glass slip and immersed for a short time in a solution of potassium cyanide, perchloride of iron, or iron-alum, becomes reduced in thickness to any required extent. The structure of silver leaf may also be conveniently examined by converting it into a transparent salt by the action upon it of chlorine, iodine, or bromine. Similar suitable means may also be found for rendering more or less transparent most of the other metals which can be obtained in leaf.

An examination of such metallic sections will show two principal types of structure, one being essentially granular, and the other fibrous.

The granular metals, of which tin may be taken as an example, present the appearance of exceedingly minute grains, each one being perfectly isolated from its neighbours by still smaller interspaces. The cohesion of such leaves is very small.

The fibrous metals, on the other hand, such as silver and gold, have a very marked structure. Silver, especially, has the appearance of a mass of fine, elongated fibres, which are matted and interlaced in a manner which very much resembles hair. In gold this fibrous structure, although present, is far less marked. The influence of extreme pressure upon gold and silver seems to be, therefore, to develop a definite internal structure. Gold and silver in fact appear to behave in some respects like plastic bodies. When forced to spread out in the direction of least resistance their molecules do not move uniformly, but neighbouring molecules, having different velocities, glide over one another, causing a pronounced arrangement of particles in straight lines.

This development of a fibrous structure, by means of pressure, in a homogeneous substance like silver, is an interesting lesson in experimental geology, which may serve to illustrate the probable origin of the fibrous structure of the comparatively homogeneous limestones of the Pyrenees, Scotland, and the Tyrol.

J. VINCENT ELSDEN

ISLAND LIFE[1]

II.

IN the second half of his volume Mr. Wallace proceeds to apply to the elucidation of the history of the characteristic assemblages of plants and animals in islands, the principles laid down with so much explicitness in the first half. He points out that for the purposes of the naturalist a fundamental difference exists between islands that have once formed part of continents and those which have not. Continental islands are those which, by geological revolutions at more or less remote periods, have been severed from the continental masses in their neighbourhood. They are recognisably portions of the continental ridges of the earth's surface. This relation is usually made strikingly apparent by the chart of soundings between them and the nearest mainland (Fig. 2). Further, in geological structure they resemble parts of the continents, like which they contain both old and new formations, with or without volcanic accumulations. In some cases the evidence of recent severance from the adjacent continent is abundant. In others it is less distinct; for example, where the islands are separated from the nearest land by a depression of a thousand fathoms or more, and where their fauna, though abundant, is of a fragmentary nature, almost all the species being distinct, many of them forming distinct and peculiar genera or families, while many of the characteristic continental orders or families are entirely absent, and in their place come animals to which the nearest allies are to be found only in remote parts of the world. Oceanic islands, on the other hand, exhibit no geological connection with any continental area, but owe their birth either to upheaval of the ocean floor or to the piling up of lavas and tuffs round submarine vents of eruption. Their geological structure is of the simplest kind. As Mr. Darwin long ago showed, they consist of volcanic rocks or of coral reefs, or of volcanic and coralline formations combined. Ancient formations, so characteristic of continental islands, are wholly wanting. These islands lie far removed from a continent, and rise from water of profound depth. Their fauna is in curious keeping with this isolation, for it contains no indigenous land-mammals or amphibians, but abounds in birds and insects, and usually possesses some reptiles. These animals or their ancestors must have reached the islands by crossing the ocean.

Mr. Wallace first attacks the problems presented by the Oceanic Islands (Fig. 1). He describes the characters of the flora and fauna of the Azores, Bermuda, the Galapagos, St. Helena, and the Sandwich Islands, and endeavours in each case to show how the resemblances and differences between them and the plants and animals of the continents may be accounted for. The contrast offered by two groups of islands on either side of the American continent—the Bermudas and Galapagos—brings vividly before the mind the nature of the difficulties with which the author grapples, and the methods by which he seeks to solve them. In the case of the Bermuda group a series of coral islets having a total area of no more than fifty square miles rises from the very deepest depression in the Atlantic basin in 32° N. lat. at a distance of 700 miles from North Carolina. The chief elements in the fauna of these islands are birds and land-shells. Upwards of 180 species of birds have been observed, more than half of which belong to wading and swimming orders, while eighty-five are land-birds, of which twenty species are frequent visitors. Only ten species live as permanent residents on the island, and these are all common North American birds. No bird, and indeed no vertebrate animal, save a species of lizard, is peculiar to Bermuda. The feathered population of the islands is de-

[1] "Island Life; or, the Phenomena and Causes of Insular Faunas and Floras," &c. By Alfred Russel Wallace. (London: Macmillan and Co., 1880.) Continued from p. 359

rived from the North American continent, whence every year, especially during the autumnal storms, numbers of birds are blown out to sea. Most of these no doubt perish, but some succeed in reaching Bermuda. Hence from this constant introduction of fresh individuals there has been no development even of any distinct variety in the avian fauna. The land-shells include twenty species, of which at least four, or about a fourth of the whole, are peculiar. The proportion of peculiar land-shells among the Azores is about a half of the whole number of resident species. It is obvious that these organisms have comparatively feeble and uncertain means of transport as compared with birds. They may be carried only at widely separated and irregular intervals, enclosed in drift-wood from some other island or continent. Hence the conditions for their gradual change under the new circumstances of their insular home are exceptionally favourable. The flora of Bermuda contains a majority of tropical and West Indian plants, and includes a number of species identical with



FIG. 1.—Map of Bermuda and the American Coast. The darker tint indicates sea more than 1000 fathoms deep, the lighter shows sea less than 1000 fathoms. The figures mark the depth in fathoms.

those in the Southern States of the American Union. The origin of this vegetation is thus easily traced, first, to the operation of marine currents, whereby plants of the West Indian Islands have been actually observed to be washed ashore on Bermuda and to germinate there; next, of cyclones by which fine seeds transported in the higher parts of the atmosphere may doubtless be easily carried from the American continent; and thirdly, of birds, which among their feathers and in the mud adhering to their feet are known to transport living seeds to enormous distances.

The Galapagos, though less distant from the west side of the American continent than the Bermudas are from the east side, rise nevertheless out of a profoundly deep ocean. The whole group of seventeen islands ranges over an area of 300 miles in length by 200 in breadth, being of volcanic origin, and still containing in the western islands numerous active volcanoes. Between the fauna of the Galapagos however and that of the nearest part of South America a remarkable difference obtains. As usual, no indigenous mammalia or amphibia occur on these islands; but a few species of reptiles abound—land-tortoises, lizards, and snakes, that find their nearest allies on the American continent, whence doubtless their ancestors at some remote period were derived. Out of a total of fifty-seven species of birds no fewer than thirty-eight are peculiar. In particular the land-birds number thirty-one species, which are all, with but one exception, confined to the Galapagos, and more than half of them are so peculiar as to be ranked in distinct genera, though all are undoubtedly allied to birds inhabiting Tropical America. Mr. Wallace points out that every gradation can be traced, from perfect identity with continental species to marked generic divergence, and that "this diversity bears a distinct relation to the probabilities of and facilities for migration to the islands." A species which is widely diffused and essentially migratory will by frequent arrival of fresh individuals from the parent stock and intercrossing, continue unchanged, while others, in proportion to the rarity of their re-introduction, will be subject to all the variation which change of habitat and prolonged isolation may induce. The flora of these islands includes 174 peculiar flowering-plants, and 158 common to other regions. Among the latter occur forms found both in North and South America, with some that range into the West Indies. Sir Joseph Hooker has observed that the peculiar plants of the Galapagos are allied to forms now found in temperate America, or in the high Andes, while the non-peculiar species are such as live in tropical latitudes near the sea-level. These facts in zoological and botanical distribution the author seeks to explain by the meteorological conditions and geological history of the region. The Galapagos Islands lie in a tract of almost perpetual calms. The storms that annually transport a fresh immigration of birds and seeds to the Bermudas are there unknown; consequently the fauna and flora present a far greater contrast to those of the continent than is the case of Bermuda. The presence of West Indian species is regarded as pointing to the former submergence of the Isthmus of Panama and the consequent drifting of those forms from the north-east, perhaps by a deflected branch of the Gulf Stream. Again, the affinity of a portion of the Galapagos flora to plants of northern or sub-alpine types is looked upon as an indication of that ancient southward migration of northern forms consequent upon the extension of the snow and ice of the Glacial Period.

As examples of Continental Islands the author describes the British Isles, Borneo, Java, Japan, Formosa, and the Madagascar group. The difference between the plants and animals of continental islands and those of the neighbouring continents varies extensively, one main effective element in the case being the length of time during which insular relations have been established. Taking Britain as perhaps the most typical illustration of a large and recently separated continental island (Fig. 2), Mr. Wallace points out how many are the proofs of comparatively recent subsidence, which he regards as the cause of the severance of Britain from the continent. Undoubtedly subsidence was one, probably the principal.

operation whereby the British Islands were isolated. We must not forget however that denudation also played its part. The excavation of the Strait of Dover, for example, may have been in large measure effected by streams diverging from the watershed and partly by the littoral erosion of the waves as they advanced upon the slowly foundering land. The recent date of the separation of Britain is shown by the identity of the fauna as a whole with that of France and Germany. But as compared with the continent, the British Isles are remarkably poor in species. In Germany, for example, there are nearly ninety species of land mammals; even Scandinavia possesses about sixty; but Britain can boast only forty—a number which in Ireland is reduced to twenty-two. Still more remarkable is the contrast presented by the reptiles and amphibia; for while Belgium possesses twenty-two species, Britain can show no more than thirteen, and Ireland has only four. This progressive diminution of the fauna westward is even illustrated by animals possessing the power of flight, though, as might be supposed, it is in these cases less strongly marked. The twelve bats of Britain are reduced to seven in Ireland, the 130 land-birds to about 110. In Britain 1425 species of flowering plants and ferns are known, but in Ireland only 970, or two-thirds of the British flora. The reason assigned by Mr. Wallace for this poverty of species is the extensive submergence of the British Islands during the later stages of the Glacial Period. He believes that the interval between the subsequent elevation and the final separation of Britain from the continent cannot have been of long duration. It was indeed sufficiently prolonged to allow of the migration westwards of a considerable part of the Post-glacial fauna and flora, but the insular condition was established before more than a part had succeeded in reaching Britain, where both the soil and climate would have been eminently favourable for the reception of the rest. The time that has elapsed since our area ceased to be continental has been long enough for the production of a few peculiar varieties. No distinct species or variety of mammal, reptile, or amphibian has arisen. But we possess three peculiar birds—the coal-tit, long-tailed tit, and grouse—fifteen peculiar species of fresh-water fishes, sixty-nine lepidopterous insects, seventy-two beetles, four caddis-flies, and four terrestrial and fluviatile shells believed to be peculiar. In the flora the chief contrasts are exhibited by the mosses and hepaticæ, of which respectively seventeen and nine forms appear to be peculiar. This mode of considering the British fauna and flora brings out in clear relief the relations between them and those of the continent, and their bearings upon the question of the origin of peculiar forms. Not only do the British Islands as a whole contain species or varieties that do not appear on the mainland of Europe, but some of our outlying islands, such as the Shetland Isles, the Isle of Man, and Lundy Island, possess each its local forms that are not met with on the main island.

As "anomalous islands" the author classes together Celebes and New Zealand, the former because it belongs to no one of the six zoological regions of the globe, and cannot be certainly affirmed to have been united to a continent, the latter because in some respects it may be regarded as an oceanic, in others as a continental island. Celebes is supposed by Mr. Wallace to be probably a fragment of Miocene Asia, preserving down to the present time a few remnants of its Tertiary fauna, together with an intermixture of more modern types that have been introduced by ordinary means of dispersal. Three interesting chapters are devoted to New Zealand, and in these is discussed the important question of the origin of the European element in the floras of the temperate southern latitudes.

Enough has been said here to show the nature and value of this new contribution to scientific literature. Even where Mr. Wallace's conclusions may be disputed, they are always of the most suggestive kind. His volume, as he acknowledges, is the development and application of a theory; but it is not written in the spirit of a mere partisan. Its facts are of course marshalled in such form as most effectively to sustain the theory; yet with a transparent directness and honesty of purpose that runs through the whole book, and gives it one of its great charms. The writer does not consciously shut his eyes to any of the difficulties of his case. Candidly admitting them, he presents such explanation as seems to him to offer the most likely pathway to their ultimate solution.



FIG. 2.—Map of the shallow bank connecting the British Isles with the Continent. The dark tint marks sea of more than, the paler tint shows sea of less than, 1000 fathoms in depth. The figures show the depth in fathoms. The narrow channel between Norway and Denmark is 2580 feet deep.

He deserves the thanks alike of geologists and of biologists for a treatise, the appearance of which marks another epoch in the history of the doctrine of Evolution.

ARCH. GEIKIE

HONOUR TO MR. DARWIN

THE following address to Mr. Darwin, from New Zealand, speaks for itself:—

To Charles Darwin, Esq.

SIR,—We, the members of the Council of the Otago Institute, beg to offer you our congratulations on this, the

twenty-first anniversary of the publication of your great work, the "Origin of Species."

However limited the field of our own labours may be, we cannot but be sensible of the influence which that work has had throughout the whole domain of Natural Science, and especially upon Biology, which, as one great comprehensive Science, may be said to owe its very existence to the fact that you made belief in Evolution possible by your theory of Natural Selection.

We are glad to think that you have lived to see the almost universal acceptance of the great doctrine which it has been the work of your life to establish; it is hardly an exaggeration to say that every important Botanical or Zoological discovery of the last twenty-one years, particularly in the departments of Embryology and Palæontology, has tended to fill up some gap in the evidence you had originally collected, and to make Evolution no longer a theory, but an established doctrine of Science.

We hope that you may long live to continue your labours and to see the further spread of their influence upon all scientific thought and upon all higher scientific work.

We are, sir, your obedient servants,

THOS. MORGAN HOCKER	*President*
F. W. HUTTON	*Vice-Presidents*
GEORGE H. F. ULRICH	*Vice-Presidents*
GEORGE M. THOMSON	*Hon. Sec.*
HENRY SKEY	*Hon. Treasurer*
ROBERT GILLIES	*Members of Council*
C. W. BLAIR	*Members of Council*
ALEXANDER MONTGOMERY	*Members of Council*
T. JEFFERY PARKER	*Members of Council*
W. MACDONALD	*Members of Council*
DONALD PETRIE	*Members of Council*

Dunedin, New Zealand, October 1, 1880.

DEGREES TO WOMEN

WE trust the Grace which is to-day to be submitted to the Cambridge Senate, advocating the admission of women to receive University degrees, will meet with the approval of that body. In fact, as the *Times* put it yesterday, the point was ruled ten years ago. "Cambridge, in conniving at its public examiners examining Girton and Newnham students precisely as if they were Trinity or Johnian scholars, gave in spirit what is now demanded. It seems ungenerous, and not very rational, for a university to let its authorities proclaim a man in the Senate House eighth wrangler, and inform Girton College that the real eighth wrangler was a woman. Even a country clerical passman would not venture to withdraw the existing licence; all that remains is for the Senate to ratify with a good grace the principle upon which its officials have long and openly been acting."

The following paper, which has been issued from Cambridge in view of to-day's discussion, puts the case as fairly as it can be put:—

Reasons why the university should be one of the leading centres of female education.

1. Because no line can be drawn separating main subjects of study or whole branches of learning into those suitable for men and unsuitable for women, or *vice versâ*. No true classification of human knowledge will admit of the distinction, "Propria quæ maribus tribuntur, mascula dicas." 2. Because the University as a chief inheritor and transmitter of learning from generation to generation has no right to dissociate itself from any great movement connected with the advancement of learning. The participation of women in the general and particularly in the higher studies of their time must be a great fact and factor in the future of education. 3. Because whatever educational resources may be found elsewhere, those of Cambridge and Oxford are peculiar; and though as long as there was no public demand for these resources except from male students they were properly applied only to male education, now that a demand has sprung up and persistently declared itself on the part of the other sex, the university will incur the reproach of inhospitable partiality if it bars its doors, like a monastery, to female applicants for admission. 4. Because one of the legitimate wants and aspirations of the University—leisure for continued study and research—is likely to be promoted by increasing the amount of remunerative educational work done in the university. The more work, the more workers, and the more remuneration; and out of work, workers, and earnings, the legitimate and sure outcome will be leisure for the worthiest work and workers. 5. Because the education of women in England must, from irresistible national feelings and convictions, be religious and Christian; and if female education is centred in the university a stimulus will be given to the best religious influences in study and life; and from these the English universities have never for any long period been dissociated. 6. Because any mischievous consequences that might be feared, whether to the university or to the students, by the admission of women can be guarded against by suitable regulations, and still more by responsible authorities; whereas the diversion of the interests and influences that are gathering round the question of women's education from the university to other centres would be an irretrievable step, isolating the university for the future from a movement of great force and promise. J. L. BRERETON

February 16

NOTES

AT the anniversary meeting of the Royal Astronomical Society on the 11th inst., Mr. Hind, president, in the chair, the gold medal was presented to Prof. Axel Möller, Director of the Observatory at Lund, in Sweden, for his investigations on the motion of Faye's comet. Prof. Möller's researches commenced in 1860, soon after attention had been directed to this comet by the offer of a prize for the accurate determination of its orbit by the Society of Natural Sciences of Dantzic, and they have been continued to the present time, the comet's track at each of the three subsequent returns in 1865-66, 1873, and 1880-81, having been predicted with a precision which has excited in no small degree the admiration of astronomers; indeed, at the re-appearance in 1873, M. Stephan's first observation at the Observatory of Marseilles, showed that the error of predicted place was less than *six seconds of arc*, and after the last revolution, when the perturbations from the action of the planets were greater than in any previous revolution since the comet was first detected by M. Faye in 1843, the agreement between observation and calculation was still very close. One important result of these investigations has been a striking confirmation, from the motion of Faye's comet, of the value for the mass of Jupiter deduced by Bessel from the elongations of the satellites, the two values according within the limits of their probable errors. Prof. Möller also carried back the accurate computation of the perturbations to December, 1838, so as to ascertain the effect of a pretty near approach to Jupiter in March, 1841, upon the previous orbit, and having done this he examined the probable circumstances of a very near approach of the two bodies near the passage of the node in 1816, to which attention had been drawn by Valz soon after the comet's orbit was fairly determined. Thus Möller's laborious investigations extend over a period of forty-three years, during which he has followed the motion of the comet with all the refinements of which the actual state of the science admits. It will be generally accorded that the medal has been well earned in Prof. Möller's case. The last occasion on which it was awarded for investigations of a similar kind was as far back as 1837, when the Astronomer-Royal presented the medal to Rosenberger for his researches on the motion of Halley's comet.

AT the anniversary of the Geological Society on Friday the medals were awarded as follows:—The Wollaston medal to Prof. P. Martin Duncan, M.B., F.R.S., F.G.S.; the Murchison medal to Prof. Archibald Geikie, F.R.S., F.G.S.; the Lyell medal to Principal Dawson, LL.D., F.R.S., F.G.S., of McGill College, Montreal; and the Bigsby medal to Dr. Charles Barrois of Lille. The Wollaston Fund was awarded to Dr. R. H.

Traquair, F.G.S., of Edinburgh; the Murchison fund to Frank Rutley, F.G.S.; the Lyell Fund in equal parts to G. R. Vines of Sheffield, and to Dr. Anton Fritsch of Prague.

In addition to the amount reported last week, we have received two guineas from Mr. William Black for the John Duncan Fund, making the total received through NATURE £67 4*s.* 3*d.*

The first of Prof. Flower's nine lectures on the Anatomy, Physiology, and Zoology of the Cetacea, in the theatre of the College of Surgeons, will be given on Monday next. The Comparative Anatomy of Man, which formed the subject of the last four courses of lectures, is far from being exhausted, especially as the acquisition of the Barnard Davis collection has more than doubled the materials at the disposal of the lecturer for its illustration. But the work of removing, cleaning, arranging, and cataloguing the numerous specimens of this collection has absorbed so much time, that little has been left as yet for their scientific examination. As any attempt at exposition of the variations of the osteological structure of man, from which the evidence afforded by the newly-acquired specimens is omitted, would be very incomplete, it has been thought advisable to postpone the continuation of the subject to a future time. The anatomy of the group selected for consideration this year is of great interest, and particularly well illustrated in the Museum, (as it is a subject to which John Hunter devoted much attention, and upon which he published a valuable memoir in the *Philosophical Transactions* for 1787, entitled "Observations on the Structure and Œconomy of Whales"):—General characters of the Cetacea; Division into two distinct groups—*Mystacoceti* or whalebone-whales, and *Odontoceti* or tooth whales; Anatomy of the lesser rorqual (*Balænoptera rostrata*) as a type of the *Mystacoceti*; Other whalebone-whales—rorquals (*Balænoptera*), humpbacks (*Megaptera*), and right whales (*Balæna*); Anatomy of the porpoise (*Phocæna communis*) as a type of the *Odontoceti*; Other toothed whales—*Delphinidæ*, dolphins, beluga, narwhal, platanista, &c.; *Physeteridæ*—sperm-whale and its allies; Extinct Cetacea—position of the order in the animal kingdom, and relation to other groups.

We regret that the Lords should have thrown out the Bill on Tuesday for the Opening of Museums and similar places on Sundays. The smallness of the majority leads us to hope that this forward and really beneficial step will be taken ere very long. As the *Times* very well puts it:—"The gravity of the question is that London has in its midst people to whom anything of the nature of intellectual toil—and prolonged sight-seeing is of that character—is essentially irksome. But they are human beings, and not lost to all salutary influences. It would be folly to despair of making the Sunday more tolerable than it is to them. Our climate does not often admit of men and women sitting out of doors talking or listening to elevating music. Some substitute must be found to put us on equality with the people of more sunny lands. It is the task of true friends of the working classes to suggest means by which, without any revolution in national ideas as to the sacredness of Sunday, they may be enabled to taste those simple and primitive pleasures—for example, the pleasure of pure repose of mind and body, or that of hearing music—which all, even the untutored, can enjoy. The movement is directed towards the cure of a real social evil, and those who oppose it are bound to suggest a more effectual remedy."

By an oversight, for which the American authorities must be held partly responsible, we did not observe that the volume on "Odontornithes," by Prof. Marsh, briefly alluded to in NATURE of last week, was the same work which had already been reviewed in our columns as far back as September 16 of last year (vol. xxii. p. 457). The monograph now sent to us bears no reference to the previous issue of the same work. It is announced as a portion of the Survey of the Fortieth Parallel under Mr. Clarence King; but no number is assigned to it as a volume of that splendid series of quartos. We hope that this new issue of the work will secure for it a still wider circle of readers, as it certainly adds additional lustre to the Survey of the Fortieth Parallel.

The Hunterian Oration this year was so far original that the orator, Mr. Luther Holden, gave the results of some original research he has been making into the early life of John Hunter. It is usually said that Hunter, up to the time of his coming to London, led a completely idle life, giving no promise whatever of future eminence. Dr. Holden however thinks he has proved that Hunter, instead of being apprenticed to a cabinet-maker, entered Glasgow University when he was seventeen years old, and had the advantage of a regular training under the eye of Cullen. Whatever may be thought of the evidence Mr. Holden adduced, he has certainly opened fresh ground, quite deserving to be worked out by future orators.

The freedom of the Cutlers' Company was conferred upon Sir Henry Bessemer last week. At the dinner which followed he stated that a young and rising American "city" had been named after him.

Can any reader send us information concerning the fate of the instruments which belonged to the late Dr. Dick of Broughty Ferry, Scotland, the author of a number of theologico-scientific works ("Philosophy of a Future State," &c.), rather remarkable for their advanced views, considering the time at which they were published—about forty years ago? He is said to have left, among other things, a large telescope, the subsequent history and present possessor of which we are anxious to trace.

The Commissariat-General of the Paris International Exhibition of Electricity are anxious that all requests for space be sent in as soon as possible, and not later than March 31.

The following are prize-subjects lately proposed by the Society of Arts and Sciences at Utrecht:—Researches on the development of one or several invertebrate species of animals whose history is not yet known; exact anatomical description of the larva and nymph of the common cockchafer (*Melolontha vulgaris*); means of purifying the rivers of Holland so as to render them potable, and expense of application on a large scale; results of experiments in recent times as to the movement of liquids and the resistance they offer to moving bodies; study of the theories of electric phenomena in muscles and nerves; critical *aperçu* of the methods for determining the place occupied in bodies of the aromatic series by substituted atoms and groups of atoms (according to Kekulé and Ladenburg's theory regarding benzol); quantities of heat liberated or absorbed in the allotropic change of two or several simple substances; heat given by the moon in different phases. Papers may be written in French, Dutch, German, English, or Latin, and must be sent to the Secretary, Baron R. Melvil, of Lynden, before December 1, 1881. The prize is a diploma of honour and 300 Dutch florins.

A classified list of the books published in Germany during 1880, just issued by Hinrichs of Leipzig, shows the number of publications to be steadily increasing. We find a total of 14,941 new works against 14,179 in 1879. The largest number belongs to the class of school-books and other works for the young, viz., 2446 (against 2175 in 1879). We give the further classes in a descending scale, adding the numbers for 1879:—Law, politics, statistics, conveyancing, 1557 (1683); theology, 1390 (1304); Belles Lettres, 1209 (1170); medicine, 790 (732); natural history, chemistry, pharmacy, 787 (841); historical works, 752

(680); popular works, almanacs, 657 (642); fine arts, stenography, 627 (584); commerce, 583 (577); classical and oriental languages, archæology, mythology, 533 (481); modern languages, old German literature, 506 (485); agriculture, 433 (421); miscellaneous writings, 423 (378); architecture, railways, engineering, mines, and navigation, 403 (384); bibliography, encyclopædias, 377 (278); geography, travels, 356 (306); war, 353 (337); maps, 301 (300); mathematics, astronomy, 201 (158); philosophy, 125 (139); forests and game, 112 (103); freemasonry, 20 (21).

MESSRS. MACMILLAN AND CO. have in preparation, and will publish this year, "A Course of Instruction in Zootomy (Vertebrata)," by T. Jeffery Parker, B.Sc. Lond., Professor of Biology in the University of Otago. The work will consist of full directions for the dissection of the Lamprey, Skate, Cod, Lizard, Pigeon, and Rabbit, and will be illustrated by numerous woodcuts from the author's original drawings.

THE death is announced of Count Alexander Erdödy, a Member of the Pesth Academy of Sciences, vice-president of the Society for Plastic Art, and a liberal patron of science and art. His death occurred on January 24 at Vep (Hungary); he was eighty years of age. We regret also to announce the death of Herr Gabriel Koch, a Frankfort tradesman and an eminent lepidopterist, whose "Schmetterlingsbuch" has a wide reputation in Germany. He died at Frankfort-on-Main on January 22, aged eighty. On February 2 died Prof. Gorini at Lodi, well known by his works on volcanic phenomena. He was a teacher at the Lodi High School, and one of the warmest advocates of cremation in Italy.

EARTHQUAKES continue at Berne. A new shock, directed from east to west, was felt in the north of the town on February 8, at 5.25 p.m. Shocks of earthquake are reported from Braila on February 11 at 7h. 15m. a.m., and from Galatz at the same time.

IT was not difficult to foresee that the warm weather which prevails now in the Alpine region, together with immense quantities of snow fallen during the previous days, would occasion several avalanches. On February 13 a terrible one descended from the slopes of Mont Pourri, and covered with a mass of snow, thirty feet deep, the village of Brévières, in the Tignes commune. Thirty-two persons were buried under the snow, and no less than three hundred peasants from the neighbourhood were engaged in sinking pits to reach the buried houses. Of the buried, twenty-five were found alive, four were dead, and three are not yet discovered. Two days later, another avalanche descended from the same mountain, and covered a space 10,000 metres wide, with a mass of snow fifteen to twenty metres deep. The pressure of air displaced by the avalanche was so great that all the windows of the village were broken within a few seconds. The quantity of snow fallen during the previous days was so great that all communication was broken up between Brévières village and the bottom of the valley; a peasant from Tignes took thirteen hours to reach the next town, Bourg-Saint-Maurice, travelling in the snow more than one metre deep.

THE provincial governments of Navarre and Logroño (Spain) have received the royal sanction to the necessary outlay for constructing and maintaining meteorological stations in these provinces.

OUR ASTRONOMICAL COLUMN

ENCKE'S COMET IN 1881.—So far as can be judged without the calculation of the perturbations since 1878 this comet will again arrive at perihelion about November 8 in the present year. In 1848, when the comet passed this point of its orbit on November 26, it was detected with the 15-inch refractor at Cambridge, U.S., on August 27, as "a misty patch of light faint and without concentration: its light coarsely granulated, as that were it not for its motion it might be mistaken for a group of stars of the 21st magnitude" (Bond). The theoretical intensity of light at this time was 0·21, and we find that, assuming the perihelion passage to occur on November 8, the comet should have this degree of brightness soon after the middle of August next, so that it may be anticipated observations will be practicable with the waning moon about the 20th of that month. The last perihelion passage took place on July 26, 1878, the period of revolution at that time being 1200·58 days according to the late Dr von Asten. The aphelion distance is 4·0879, the perihelion distance 0·3335, and the minor semi-axis 1·1675 (the earth's mean distance from the sun = 1). The approach to the orbit of the planet Mercury is still very close (0·031) in about 126° heliocentric longitude. The nearest approximation of the two bodies that has occurred since the discovery of the comet's periodicity took place on November 22, 1848, when their distance was only 0·038. It is known that from his investigations on the motion of Encke's comet, von Asten inferred a much smaller value for the mass of Mercury than had been previously assigned, viz. $\frac{1}{7636440}$.

CINCINNATI MEASURES OF DOUBLE STARS.—Mr. Ormond Stone has issued an important series of measures of double stars made at the Observatory of Cincinnati, which is under his superintendence, between January 1, 1878, and September 1, 1879. The number of stars measured is 1054, of which 622 are south, and 432 north of the celestial equator: 560 belong to Struve's catalogue, 171 were discovered by the Herschels, 161 by Mr. Burnham, and 85 were found with the Cincinnati refractor, which has an aperture of eleven inches. The measures of the southern stars have a special interest, as there are comparatively few previous ones upon record. In his introduction Mr. Stone points out the most notable differences between the Cincinnati measures of angle and distance, and those of Struve, Sir John Herschel, and others; we shall refer to several of these cases in a future column. The volume is published by the Board of Directors of the University of Cincinnati, and will be a necessary addition to the libraries of those who are making the double stars their special study. Mr. Stone acknowledges his obligation to the Manual of Double Stars lately published by Messrs. Crossley, Gledhill, and Wilson, and M. Flammarion's "Catalogue des Étoiles Doubles et Multiples en Mouvement relatif certain."

THE MINOR PLANETS IN 1881.—The usual supplement to the *Berliner astronomisches Jahrbuch* (1883), containing its specialty, elements and ephemerides of the small planets for the present year, has been issued. We have in it approximate ephemerides for every twentieth day throughout the year of 210 planets, the latest being No. 217, and accurate opposition ephemerides of 58. Three planets are omitted for want of proper data for computation, viz. No. 99 *Dike*, No. 155 *Scylla*, and No. 206 *Hersilia*. A glance at this long series of ephemerides shows how wide a range over the heavens the apparent tracks of these small bodies present: thus we find *Euphrosyne* in opposition in 52½° south declination, in the constellation Indus, and *Vesta* in the vicinity of ζ Persei, with 43° north declination. A favourable opportunity for repeating observations for determination of the solar parallax would have been afforded if, in the first place, the actual position of No. 132 *Æthra* were pretty accurately known, and if Mr. Gill were able to utilise his heliometer at the Cape of Good Hope: this planet on February 28 being distant from the earth less than 0·84 of the earth's mean distance from the sun, with 47° south declination and rather greater brightness than a star of the ninth magnitude.

CHEMICAL NOTES

HAUTEFEUILLE AND CHAPPUIS state (*Comptes rendus*) that when a high tension spark is passed through a mixture of nitrogen and oxygen, ozone and "pernitric acid" are produced, but the latter compound is readily decomposed with production of a less oxygenated body and oxygen. When the electric discharge is passed through air in presence of water vapour very noticeable quantities of nitric acid are formed. The same observers have examined the absorption-spectrum of ozone and have recognised certain bands which they state are also found in the solar

spectrum. They think that the blue colour of the sky may probably be partly due to the presence of ozone.

BRAME (in *Comptes rendus*) recommends the use of baryta in place of sodium carbonate and charcoal, in the ordinary dry test for arsenic. If arsenious oxide is heated with baryta a mirror is obtained consisting partly of metallic arsenic, and partly of barium arsenate: the test does not succeed so well with arsenious sulphide.

A CONSIDERABLE deposit of crystallised (octahedral) sulphur has been found under the soil of Paris, where organic refuse matter has long accumulated. The sulphur appears to be a product of the deoxidising action of the carbon compounds present in the refuse on the calcium sulphate of the soil.

M. LOUGHININ continues, in the *Journal* of the Russian Chemical Society, his interesting researches on the quantities of heat produced by burning alcohols of the allyl series; he publishes in the *Journal* the figures corresponding to two new bodies of this series ($C_8H_{12}O$ and $C_{10}H_{20}O$), which figures, together with those he has already published in the *Comptes rendus* (vol. xci.), allow him to draw a complete table of the calories disengaged by the whole of the alcohols of this series.

THE first number of the *Gazetta Chimica Italiana* for the present year is devoted, with the exception of a paper by M. Fileti on gas analysis, to papers on organic chemistry: these include work on Camphor Derivatives by Schiff; on Picrotoxin by Paterno and Oglialoro; and on Synthesis of Aromatic Aldehydes by the use of Chromyl Dichloride, by Paterno and Scichiloni.

IN the course of a paper on the Photo-chemistry of Silver Chloride, Eder states (in *Wien. Akad. Ber.*) that this substance is more sensitive to light when substances which absorb chlorine are present, than when in the pure state. To develop the latent image he recommends especially ammonium ferrocitrate, and hydroquinone along with ammonium carbonate.

BY the action of potassium dichromate and sulphuric acid on caffeine, Hinteregger has obtained as much as 40 per cent. of dimethyl parabanic acid, and 39 per cent. of the monomethyl acid from theobromine.

IN continuation of his investigations into the action of hydrochloric acid on metallic chlorides, Ditte describes (*Compt. rend.*) several new hydrated salts which crystallise from aqueous solutions when these are saturated with hydrochloric acid. In the absence of hydrochloric acid hydrated salts with more water of crystallisation are always produced. The following table contains the principal results obtained by Ditte:—

Aqueous solution.			Solution saturated with HCl at 15°.		
Grams of salt dissolved per litre.		Crystals which form	Grams of salt dissolved per litre.		Crystals which form
700	...	$CaCl_2.6H_2O$	270	...	$CaCl_2.2H_2O$
500	...	$SrCl_2.6H_2O$	20	...	$SrCl_2.2H_2O$
720	...	$MgCl_2.6H_2O$	65	...	$MgCl_2.2H_2O$
415	...	$CoCl_2.6H_2O$	205	...	$2CoCl_2.3H_2O$ and $CoCl_2.H_2O$
600	...	$NiCl_2.6H_2O$			
870	...	$MnCl_2.4H_2O$	40	...	$NiCl_2.H_2O$
630	...	$CuCl_2.2H_2O$	190	...	$MnCl_2.H_2O$
			290	...	$CuCl_2.H_2O$

M. POUCHET describes in *Compt. rend.* a method for destroying organic matter before testing for mineral poisons in contents of a stomach, &c.; the method is based on the oxidising action of potassium-hydrogen sulphate followed by addition of sulphuric acid.

PHYSICAL NOTES

IN a little mathematical note in the *Comptes rendus* M. Thollon investigates the general equation for the passage of light through a prism, and thence deduces the proposition that for every prism there is an angle of minimum resolving power. Differentiating the general equation with respect to the index of refraction, he obtains, first, a differential equation expressing the dependence of the angular distance between two rays upon the dispersive index. A separate differentiation with respect to the angle of incidence yields a second differential equation expressing the dependence of the apparent width of the slit as seen through the prism upon the angular aperture of the slit, as viewed from the prism through the collimator. Hence a relation can be obtained between the angular distance between two rays and their apparent breadth. Further examination of the equations shows that for a certain incidence there will be a minimum of resolution (*i.e.* an incidence at which the rays are least well defined), and that for another incidence there will be a minimum of dispersion; these two incidences being symmetrically related to the angle of incidence corresponding to minimum deviation. M. Thollon states that these deductions may be readily verified by the following experiment:—A dense flint glass prism is adjusted in the position of minimum deviation for the rays D upon its supporting table in the spectroscope, lit by a sodium flame. The slit is then narrowed or widened until the two yellow rays are just in mutual contact. On then turning the prism around its axis so as to increase the angle of incidence the two rays are seen to separate and to become perfectly distinct, *the angular distance between them diminishing all the while.* But if the prism be turned in the opposite direction, so as to decrease the angle of incidence, the yellow band is seen to become wider, but without being resolved into two rays. Perhaps this research may explain why the so-called "half prism" spectroscope failed to realise all the hopes of its inventor.

RECENT observations by Hrn. Wüllner and Grotrian (*Wied. Ann.* No. 12) seem to prove that the specific volume of vapours is independent of the size of the space in which it is determined. They also confirm Herr Herwig's result, that vapours always undergo precipitation before reaching the so-called maximum tension. Further, the tension at which condensation begins is found to have a relation to the maximum tension, which depends on the nature of the liquid, but is nearly independent of the temperature. Experiments made in order to find in what measure vapour must be compressed so as to present maximum tension, gave the unexpected result, that there is in general no maximum tension in the sense hitherto accepted; but that the tension of saturated vapours, even when they are in contact with a large and excessive quantity of liquid, is perceptibly increased by compression.

THE varieties of the electric discharge in gases are fully investigated by Herr Lehmann in a recent paper (*Wied. Ann* No. 12). The chief conclusion is that there are four well-characterised modes of discharge to be distinguished, viz. glow, brush, band, and spark discharge; and these may all be obtained in air of ordinary (as well as of less) density, and also in other gases, with inserted resistances and breaks, and with sharp and rounded form of electrodes, at great or small distances. The principal characteristics are these:—1. Glow-discharge; positive glow, negative light pencil, consisting of two parts separated by a dark space. 2. Brush-discharge; positive brush, consisting of stem and branches; negative light-pencil. 3. Band-discharge; positive light with two places of intermittence, sometimes stratified, and separated from the negative glow by a dark space. 4. Spark-discharge: band of light connecting both electrodes; with two places of intermittence, brushes of metallic vapour at both ends, the positive longer, the negative thicker; sometimes oblique dark spaces.

THE influence of traction and vibrations of a metallic wire on its electric conductivity is the subject of a paper by Dr. De Marchi in the *Reale Ist. Lomb. Rend.* (vol. xiii. fasc. xix.). The results he arrives at are summed up thus: 1. Any traction of a metallic wire increases in general its resistance; when the traction is very slight however there is diminution instead of increase; with increase of traction the case comes under the general law. 2. In general the increments are proportional to the increments of traction, up to a certain limit, beyond which the variations of resistance are manifested in sudden bounds, indicating an instantaneous and profound perturbation of the molecular state of the wire. 3. The law of increments of resistance is apparently independent of that of the elongations. 4. Any vibration of a wire is accompanied by a variation of resistance generally very perceptible. In most cases there is decrease of resistance if the vibration be sonorous, and more so if harmonic; increase, if the vibration be silent. This last law however requires confirmation.

IT is known that M. Plateau distinguishes between an internal and a surface viscosity of liquids, a distinction which Signor Marangoni does not consider warranted. Herr Oberbeck (*Wied. Ann.* No. 12) has approached the question experimentally thus: A brass cross is hung bifilarly with two platinum wires by one arm; its horizontal arms carry weights whose positions can be varied by screwing, so as to vary the swing; it carries a mirro reflecting a scale, and to the lower arm is attached a thin plat

or cylinder of brass to swing in the liquid at various depths. The whole can be raised or lowered with a micrometer screw, and it is thrown into slight oscillation by means of a magnet. A rectangular glass vessel is used for the liquid. The author finds that with distilled water the resistance increases suddenly and to a quite considerable extent whenever the upper edge of the plate comes into the free surface, and he does not doubt this is due to increased friction in the surface layer. The increase of resistance from the last previous position of the plate was 60·9 per cent., and with four aqueous salt solutions there was also an increase, varying between 75·1 to 54·1 per cent. Precautions adopted to prevent the presence of foreign particles on the surface (filtration, covering with moist filter-paper, &c.) had hardly any influence on the values. Long-standing of the liquid increased the surface-resistance, and stirring then diminished it; still it was always considerable at first. With M. Plateau, Herr Oberbeck found a decrease of resistance at the surface in some liquids; this was comparatively small (alcohol 11·9 per cent., oil of turpentine 12·6, sulphide of carbon 26·3, &c.). A small addition of alcohol to water lessens its surface-resistance property in a marked degree, and with further addition the mixture behaves like pure alcohol.

IN a paper on dew and fog (*Zeits. für Meteor.* Bd. xv. p. 381) Herr Dines, from observations of the former with watch-glasses exposed on different substances at night, estimates the annual dew formation to be about 35·5 mm. (on grass, 26 mm.); at the best 38 mm. The average nightly dew (in 198 observations) was hardly 0·1 mm.; in a few cases 0·3 mm.; average on grass 0·07 mm. Morning fog along a river course arises when the water is warmer than the air over it. The evaporation goes on more quickly than the vapour can be carried away; hence the latter is condensed and spreads as fog (similarly with fogs over the Gulf Stream). The evening fog on moist low-lying meadows is due to the fact that the grass surface cooled by radiation cools the lowest air-layers, so causing condensation of the aqueous vapour. The fine drops of dew, Herr Dines estimates, are about 0·001 mm. in diameter; while the finest rain-drops have a diameter of 0·3 to 0·33 mm. The particles of fog vary in diameter from 0·016 to 0·127 mm.

THE colour-changes presented in the microscope by various substances (chiefly mineral) of uneven surface, when immersed successively in liquids of different refracting power, have been made by Herr Maschke (*Wied. Ann.* No. 12) the basis of a method of distinguishing substances. Such changes may be had, *e.g.* with small glass particles, observed in water, in oil of almonds, and in mixtures of the latter with oil of cassia. The dark and the bright parts of the image show different series of colours. That the effects are simply due to prismatic action of the object appears from the fact that they may be got without the microscope, by looking *e.g.* through a tube at a piece of rock-crystal in water, &c. For mineral objects Herr Maschke used five liquids; amylic alcohol and glycerine, besides the three just named. By various mixtures of these a series of liquids is obtained, giving any desired index of refraction from 1·333 to 1·606. (Coloration begins when the refraction of the liquid is near that of the object; when the former greatly exceeds the latter a certain stability of colour appears.) The method is not applicable to bodies opaque in the microscope, or having too strong colours of their own; nor yet to bodies having a greater index of refraction than oil of cassia. It may, too, prove difficult sometimes to find a liquid sufficiently indifferent to the object. Herr Maschke indicates how the refractive indices of substances may be compared by his method, and (a more difficult task) numerically determined. He also gives a number of his own determinations.

AN interesting study, by Herr Holtz, of the electric discharge in insulating liquids appears in *Wiedemann's Annalen*, No. 12. Among other results the length of spark is found hardly at all dependent on quantity or on retardation of the discharge. Naturally it differs in different liquids, but only in one liquid (sulphuric ether) did it increase with velocity of rotation of the disk (this appears to be due rather to the mode of preparation than to the nature of the liquid). As in air, with dissimilar electrodes, the spark-length is conditioned by the polarity of the electrodes. The thickness, sound, and luminous force of the spark depend chiefly on the electric quantity and the retardation. The spark is thinner than in air, but brighter (brightest in sulphide of carbon, least bright in olive-oil and ether). It is more crooked than in air. Throughout its length it shows innumerable very small dark spaces. With large striking distance: appears within a largely-branching brush. (The appearances of the brush discharge, got best in petroleum, are also described.)

FROM data obtained in various parts of Germany, Austria, and Switzerland (*Wied. Ann.* No. 12), Herr Holtz finds a well-marked increase in risk from lightning in these parts since 185-, while no such increase appears in the number of thunderstorms. Hence he infers the causes to be telluric, and he suggests as probable causes the clearing of forests and increase of railways (attracting storms more to towns and villages); further, the increased use of metal in buildings.

PROF. BOMBINI has lately communicated to the Bologna Academy an interesting paper on spherohedry in crystallisation (*Riv. Sci. Ind.* No. 21), by which he means any known manner of production of a fibrous-radiate structure. From a survey of facts he concludes that the great phenomenon of crystallisation comprises two different orders of attractive energy. In the first there is simple centralised attraction, with concurrence of the elements attracted to a common centre. In the second there is attraction with directive polarity according to certain axes of symmetry, and concurrence of the attracted elements towards nodal points in a certain reticular system. Between these two kinds of crystallogenic action there are many gradations, or rather syntheses, superpositions. Further, the correlations between the sphericity characteristic of the liquid state; the spherohedry of globosity with radiated structure; the isometry of radiate pseudocubical groups; leading from the amorphous state of liquids to the absolutely reticular state of the true crystals (isotropic, orthoprismatic, and clinohedric) confirm the cubicity of the first system, and at the same time point to some further significant terms in the progressive series of the physical states of inorganic matter. Prof. Bombini indicates three conditions: I. Spherohedric crystallisation; II. Polyhedric crystallisation; and III. Pseudocubic, &c., crystallisation. The third may be considered intermediate between the first and the second; the first appearing as a term of transition between the sphericity of the liquid state and the polyhedry of physical solidity.

GEOGRAPHICAL NOTES

THE February *Proceedings* of the Geographical Society opens with Capt. Holdich's paper on the "Geographical Results of the Afghan Expedition"; but of more importance from a geographical point of view are Mr. Wilfred Powell's "Observations on New Britain and Neighbouring Islands." The latter is accompanied by a sketch-survey of the north-east portion of New Britain by the author, which of itself is of considerable value. A correspondence between Admiral Ryder, Naval Commander in-Chief at Portsmouth, and the Council of the Society follows, by which we learn that the latter, in declining his offer to establish certain medals, are of opinion that "the plan of granting medals to officers and seamen for independent surveys is impracticable," and further that they do not consider it their business to take any action in regard to an international congress of hydrographers.

UNDER the title of "Union Géographique du Nord de la France," a geographical association was formed some time ago, with its head-quarters at Douai, and branches at Amiens, Arras, Boulogne, Cambrai, Charleville, Dunkerque, Laon, Lille, St. Omer, St. Quentin, and Valenciennes. In the first part of the *Bulletin* of the Union, which has been sent to us, the list of members covers about fifty pages. The object of the association is by every means to promote the development and spread of geographical knowledge, investigating specially questions relating to the industry, commerce, and agriculture of the region of the Nord. The *Bulletin*, a volume of some size, contains papers on the Exploration of the Sahara, Nordenskjöld's last voyage, a Project for Exploring the Wellé, the Proposed Canal between the Atlantic and the Mediterranean, and the Maritime and Commercial Statistics of Dunkerque. In the *Comptes rendus* of the meetings of the various societies are abstracts of papers on a great variety of subjects, and there are besides a geographical chronicle and a pretty full bibliography. We have no doubt the Association will do much good in the North of France.

PROF. UJFALVY has left St. Petersburg on his return from Central Asia. The journey he made during last summer was not so successful as his preceding travels, because of a serious

illness which kept the traveller in his bed for more than two months. Nevertheless the ethnographical collections brought in are very interesting.

THE *Smolensky Vestnik* gives the following information as to Colonel Prjevalsky. He was born on April 12, 1839, at the village of Otradnoye, in the Smolensk district. His mother and his old nurse, both still alive, were the first who inspired him with a warm love of nature, and his life, on the estate of his mother, contributed to the development of this love. He studied at the Smolensk College (gymnasium), and notwithstanding the desire of his mother, who wished him to enter a university, he entered as a sub-officer in the Polotzk infantry regiment. Promoted to the grade of officer, he went to the military academy, and soon we find him as an officer during the Polish campaign, and afterwards as a teacher of geography and history in the cadet school at Warsaw. A keen hunter, he could not stay long in a city, and he soon undertook a journey to the Oussouri. This determined his ultimate career; the richness of the fauna and the pleasure of hunting in uncivilised countries determined him to undertake further journeys, first to Southern Mongolia, then to Lob-nor, and finally to Tibet, which he reached last year.

UNDER the title of "The Expiring Continent," Mr. A. W. Mitchinson gives an account of his travels in Senegambia, mainly of journeys he made up the rivers Senegal and Gambia. The work contains no dates, thus detracting somewhat from its scientific value, and abounds with speculations and reflections on all sorts of subjects connected with Africa. His notes on what he saw during his journeys are of value as showing the recent condition of the country visited, and, as may be inferred from the title, the author's views are rather despanding. His inference from his observations on the small district visited by him, that the African continent as a whole is "expiring," is far too sweeping. While like the other continents it contains "desert places," the bulk of it, so far as we know it, is capable of the greatest industrial development. That its waters are drying up as a whole there is no reason for believing; but evidently in this and in other respects there is ample room for trustworthy scientific examination. The publishers are Allen and Co.

THE February number of *Petermann's Mittheilungen* begins with a paper on the Chukchis on the shores of the Arctic Ocean, their number and present position, based on two articles by O. Nordqvist and Lieut. Hovgaard. Dr. Gustav Radde contributes the first part of a narrative of his journey to Talgsch, Aderbeijan, and Sawalan in 1879-80. From the papers in the *North American Review* a long account is given of M. Désiré Charnay's explorations of the ruins in Central America. There is an elaborate and detailed map, with accompanying text, illustrating Dr. Junker's journey through the valley of the Chor Baraka, in the Egyptian province Taka in 1876.

MESSRS. W. AND A. K. JOHNSTON have sent us the first two parts of a "Statistical Atlas of England, Scotland, and Ireland," by Mr. G. Phillips Bevan. These two parts include Religious and Educational Statistics, and subsequent parts will be devoted to Industry, Crime, Marine, Agricultural, Railways, Geology, and Mining, &c.; there will be fifteen parts in all. In the first two parts a vast amount of useful statistics are graphically exhibited on the maps, and systematically arranged in separate tables. Much of the information thus exhibited could not be obtained from any other single source.

NO. 90, the concluding part of the fifteenth volume of the *Zeitschrift* of the Berlin Geographical Society, contains the conclusion of the late Dr. Erwin von Bay's interesting journal of his journey from Tripoli to Ghât and Air, and a paper on the region which caused the recent contest between Chili and Bolivia, by Dr. C. Marten. The rest of the number, 130 pages, is occupied with the bibliography of the past year, one of the most valuable features of this most important of geographical journals. The bibliography is practically exhaustive, is arranged in a thoroughly systematic manner, and includes works relating to all departments of geography.

M. SIBIRIAKOFF has safely returned to St. Petersburg, where he had a brilliant reception. At a meeting of the Society for the Furtherance of Russian Commercial Navigation, M. Sibiriakoff pointed out the grave errors contained in Russian marine charts, which caused two of his captains to mistake the Gydan Bay for the Yenisei Estuary. They entered it on September 12, and soon met with thick-packed ice. The *Nordland* had stopped at once, the *Oskar Dickson* proceeding some 100 versts further to the south. Thence the travellers had journeyed to Obdorsk, with Samogedes as guides.

THE Rüppell fund at Frankfort-on-the-Main, which was founded in honour of the Nestor of African travellers, Dr. Eduard Rüppell, and for the exclusive object of supporting scientific exploration, consisted of the sum of 35,570 marks (1770*l.*) at the end of last year. From this the Senkenberg Naturforschende Gesellschaft, at their last meeting, granted the sum of 3000 marks (150*l.*) to Dr. Wilhelm Kobelt of Schwanheim, an eminent conchologist. Dr. Kobelt is now engaged upon the investigation of the existing and fossil molluskan fauna of the Mediterranean, and had during the last few years repeatedly visited Italy and Sicily for this purpose. His next tour, which is to extend from March to September, will comprise Spain, Algeria, and, if possible, Morocco. We may remind our readers that the journeys of Drs. Noll and Grenacher to Spain and the Canary Islands in 1871, as well as those of Verkrüzen to Newfoundland in 1874 and 1875, were also largely supported by grants from the Rüppell fund.

GEODETICAL measurements will be begun next spring on the stretch between Great St. Bernard and the St. Gothard for connecting together the Italian and the Swiss geodetical network.

A NEW expedition will start, next spring, for the exploration of the Obi, under the direction of M. Moïséeff. Six pupils of the Marine School of Arkhangelsk will accompany him.

THERE is some talk of uniting the three geographical societies of Switzerland, those of Berne, Geneva, and St. Gall, as well as those which may be created afterwards, into one great Swiss geographical association, which will have a central committee and an annual general assembly devoted to the study of geographical questions, and especially of those which have a commercial interest.

UNDER the title of "Das Frauenleben der Erde," illustrated by A. von Schweiger-Lerchenfeld, A. Hartleben of Vienna has published a highly interesting description of the social life of the women of all nations. The work contains much that is of ethnographical value, and the numerous well-executed illustrations, as well as the attractive style of the text, are likely to render it of popular interest.

THE Austrian Section of the German and Austrian Alpine Society held its annual meeting at Vienna, on January 26 last. The Section now numbers 1302 members.

ON January 29 a branch of the Berlin "Centralverein" for commercial geography was formed at Düsseldorf. The new branch is directing its main attention to South Africa.

IN the place of the late Dr. Mook, Dr. Manthey has joined the Riebeck expedition, which will leave Cairo in the course of a few days, and will, first of all, proceed to Socotra by way of Aden.

ABNORMAL VARIATIONS OF BAROMETRIC PRESSURE IN THE TROPICS AND THEIR RELATIONS TO SUN-SPOTS, RAINFALL, AND FAMINES

MR. F. CHAMBERS, in his valuable and highly interesting article (vol. xxiii. p. 88) under the above title, has made an important step towards placing the relation between secular weather changes and sun-spots on a more substantial basis than it has hitherto occupied. This has been mainly effected by his employing the most reliable data we at present possess of the latter phenomena, thereby bringing the salient features of their *minor* variations for the first time into direct comparison with a definite meteorological element, which, it may be remarked, possesses the distinct advantage of representing the integrated effect of changes occurring throughout the entire atmospheric envelope.

He has also shown how the remarkable lag which takes place in the occurrence of the critical barometric epochs at the more easterly stations may be utilised to previse famines from a knowledge of what is going on at more westerly ones.

This however would only be practicable if we knew for certain that famines in all the districts mentioned invariably took their rise from one set of conditions, such as failure of the usual summer rains, preceded and accompanied by high barometric pressure. In attributing the majority of the famines occurring within the tropics to such a proximate cause, Mr. Chambers

would no doubt be correct; but this relation between pressure and rainfall, strange though the fact may appear, does not apparently hold in the winter in the sub-tropical region of Northern India, nor is famine always caused in *this* region by a failure of summer rain alone.

For as Mr. S. A. Hill has shown in a paper on "Variations of Rainfall in Northern India" ("Indian Meteorological Memoirs," No. vii. p. 204), a *heavy* winter rainfall generally coincides with a *high* barometric pressure over Northern India, and *vice versâ*, while two of the most severe famines in Mr. Chambers' list, viz., those of 1837-38 and 1860-61, in Northern India were caused by "a partial failure of the summer rains, followed by an almost complete absence of the usual winter fall."

It is straining the evidence therefore to attempt to relate these famines, as Mr. Chambers has done, to the *previous* occurrence of high barometric pressures, since if the law just quoted held good, the famine of 1860-61 was mainly due to the absence of winter rain, caused by the *low* pressure which observations show actually existed at that time, and the same was very probably the case in 1837-38, a strongly-marked epoch of sun-spot maximum.

It has moreover been shown by Mr. Hill in the paper just referred to that "the summer rains of the North-West Provinces and Rajpootana have failed quite as often when sun-spots were numerous as when they were few, but whereas in the *former* case a comparatively slight scarcity has generally been developed into a severe famine through the failure of the winter rains, this has seldom happened in the latter case, the distress at such times being alleviated by the in-gathering of the rabi harvest, rendered more abundant than usual by a copious winter fall." This saving clause with respect to the winter rainfall of Northern India does not unfortunately apply to Southern India, where failure of the usual monsoon supply means drought and probably famine until the next monsoon, *i. e.* for an entire year.

On the whole it is plain that high and low atmospheric pressures differ specifically in their effects in different parts of the Indian peninsula, since while the former is generally associated with drought in the southern provinces, the latter in the winter is almost equally fatal in the northern provinces. If therefore the future prevision of famines is to be based on the empirical law connecting high barometric pressure with the occurrence of drought and famine, propounded by Mr. Chambers, it must be remembered that this law strictly applies only to regions where the annual water-supply is dependent upon the monsoons alone, and therefore lying for the most part between the two tropics.

It may be remarked that at least half of the Indian peninsula lies north of the tropic of Cancer.

Though I am sceptical as to the idea of motion from west to east, conveyed by the existence of a lag at the more easterly stations, this in no way affects the possibility of prevision as long as the lag remains fairly constant. I am therefore of opinion that in regard to this question the evidence furnished by Mr. Chambers is exceedingly valuable, and that so long as districts are only taken into account that lie within the tropics, such as Southern India, the possibility of prevising famines by noting the occurrence of barometric maxima at more westerly stations may in time be accomplished. For Northern India, and probably other similar sub-tropical regions, the matter is at present more complicated. E. DOUGLAS ARCHIBALD

P.S.—In the preceding letter I have only dwelt upon the limitation to be applied to Mr. Chambers's conclusions in the case of Northern India. It is obvious however that there are at least two distinct difficulties to be explained, before they can be finally accepted, even for countries within the Tropics, viz. (1) Why the barometric waves should commence on one meridian rather than on another, and (2) if, as Mr. Chambers thinks, the waves of pressure travel slowly round the earth, why they do not reappear at the place where they started after an interval of about one year and eight months (calculated from the lags given in Mr. Chambers's paper). At present there does not appear to be the slightest evidence to show that they reappear at all, and if they do not, when and where do they disappear?—E. D. A.

MR. E. D. ARCHIBALD states in his friendly criticism of my paper on "Abnormal Variations of Barometric Pressure in the Tropics, and their Relations to Sunspots, Rainfall, and Famines," that the occurrence of a decided lag in the barometric movements at easterly, as compared with westerly stations, could only be utilised to previse famines if we knew for certain that famines in those districts to which the method applied invariably took their rise from *one* set of conditions, such as failure of the usual summer rains, preceded and accompanied by high barometric pressure. It appears to me, however, that if the variations of the rainfall can be *definitely* related in *any* manner to the corresponding variations of the barometric pressure, there is no necessity for such a limitation. If, for instance, in Northern India, "a heavy winter rainfall generally coincides with a high barometric pressure, and *vice versâ*," as Mr. Archibald seems prepared to admit, then the occurrence of the *winter* of a *high* pressure would portend a *heavy* winter rainfall, and *vice versâ*, and in this case the failure of the winter rains might be foreseen by observing the progress eastward of the barometric *minima*.

But I am not aware that the relation above mentioned between the barometric pressure and the winter rainfall of Northern India has yet been worked out with sufficient definiteness for the purpose in view, for although there does appear to be some evidence in favour of that relation when the *average* pressure and the *total* rainfall of the whole winter are taken into account, yet on the other hand it is now known that the short rainy periods of the winter are periods of relatively *low* pressure. It is not improbable that these periods of low pressure, and the rainfall which accompanies them, are connected with the feeble cyclonic disturbances which (as appears from the charts of storm-tracks published by the American Government) occasionally enter the north-west of India in the winter months and travel down the Ganges Valley sometimes as far as Bengal. The facts concerning these winter rains seem to accord far better with the view of their origin than with the old notion of their connection with the upper anti-monsoon current, an idea which I observe has now been abandoned by Mr. Blanford, the Meteorological Reporter to the Government of India, although up to a recent date it was still retained by some other Indian meteorologists. The question is as yet involved in much obscurity, and I must, with the above suggestion, leave it to be dealt with by those more immediately concerned.

But whatever the relation between the winter rainfall and the barometric pressure may be, I cannot help thinking that Mr. Archibald attaches an exaggerated relative importance to these winter rains, for, from the register of Allahabad, the capital of the province, it appears that the winter rain amounts on the average to only 1·54", whereas the average summer rain amounts to 36·84". And similarly at Delhi, the average total winter rain is only 3·01", while that of the summer is no less than 24·60". Such being the case, I think it would be difficult to prove that "the famine of 1860–61 in the North-West Provinces was *mainly* due to the absence of the winter rain," more especially as the summer rain of 1860 in that province was deficient to the extent of nearly one-half, the fall having amounted to only 54 per cent. of the average.

Neither does it seem clear why the methods of forecasting the general character of a coming season, which are suggested in my paper, should of necessity be applicable only to intertropical regions. It is true that I have dealt only with barometric data furnished by stations lying within the tropics, but my only reason for doing so was that there seemed a better prospect of obtaining definite results from the records of tropical stations, where the weather is generally of a comparatively settled character, than from those of stations situated in extra-tropical regions, where the weather is generally more disturbed. Indeed I am not without hope that the results I have obtained will induce European meteorologists to take up the subject with a view to the possibility of prevising the general character of coming seasons in Europe from observations recorded in America.

FRED. CHAMBERS

STANDARD THERMOMETERS

DEAR SIR,—The Kew Committee have instructed me to forward you the enclosed Memorandum on Standard Thermometers, and to request on their behalf that you would be so good as to publish it in NATURE if you consider it suitable for insertion. G. M. WHIPPLE

Kew Observatory, Richmond, Surrey, February 9

DR. LEONARD WALDO has recently communicated to the *American Journal of Science* an article entitled "Papers on Thermometry from the Winchester Observatory of Yale College."

In it he treats of the errors of three standard thermometers constructed for him at the Kew Observatory, and after describing minutely the instruments, the manner in which he verified the accuracy of the positions of the fixed points, and the appliances he used in the work, proceeds to state that he then rigorously examined the thermometers for errors depending on calibration. Of these he says: "The results of our calibration are given in the following table. The observations were made with Apparatus II., and special care was taken to guard against any changes of temperature. The reduced results are as follows, where each line is the mean of three observations:—

Thermometer.	Date.	Extreme readings.	Computed length of col.	Correction for calibration error.
	1880.	° °	°	°
Kew, 578	Oct. 15	− 1·1 + 33·6	32·487	At 32 C. = +0·007
		+ 31·0 + 65·1	32·507	65 C. = −0·014
		+ 63·7 + 98·6	32·487	99 C. = +0·007
Kew, 584	Oct. 15	+ 32·2 + 82·3	49·040	79 F. = +0·021
		+ 76·1 + 127·3	49·068	123 F. = −0·006
		+ 119·1 + 170·1	49·078	166 F. = −0·016
		+ 162·2 + 213·2	49·060	212 F. = +0·001
Kew, 585	Oct. 15	− 1·0 + 50·9	49·813	50 C. = +0·015
		+ 49·0 + 100·9	49·843	100 C. = 0·000
		+ 99·1 + 151·7	49·820	150 C. = +0·008
		+ 148·9 + 201·0	49·807	200 C. = +0·029
		+ 199·2 + 250·8	49·747	250 C. = +0·110

REMARKS.—The observations were all made by daylight, and at one sitting for each thermometer. The extreme variations of the temperature of the room during the observations as measured by two thermometers, one at each end of the tube being measured, were as follows:—

Kew, 578 = 0°·0 F.
584 = 0·1 F.
585 = 0·1 F.

The length of the column used for the Kew calibration, and by which the thermometers were graduated, was 5°·026 C. for Kew 578, 10°·405 F. for 584, and 10°·673 F. for Kew 585. We may therefore conclude that between 0° and 100° C. the errors of the three Kew standards depending on the calibration are practically insensible; for the errors shown above are too small to be certainly detected, owing to the width of the lines which make up the graduation of the thermometer scales.

Accidental errors of graduation could not be guarded against except by the direct examination of every degree, and that accordingly has been done.

The tedious examination of each degree was accomplished with the aid of Prof. J. E. Kershner. We used the apparatus I., and each degree was measured twice. The resulting means were expressed in terms of hundredths of one division of the eye-piece micrometer, and gave a subdivision of about $\frac{1}{1100}$, $\frac{1}{1300}$, and $\frac{1}{1100}$ of 1° in the cases of Kew 578, 584, and 585 respectively. There were about 2300 separate micrometer readings made, and the result of the reductions shows that no sensible accidental errors have been introduced into the graduations of these standards.

UNIVERSITY AND EDUCATIONAL INTELLIGENCE

CAMBRIDGE.—The latest edition of the schedule of subjects for the Moral Sciences Tripos fully recognises physiology. In the advanced part of the examination special knowledge is required (1) of the physiology of the senses and of the central nervous system; (2) of experimental investigations into the intensity and duration of psychical states; and (3) of such facts of mental pathology as are of psychological interest. Questions will also be set relating to the philosophic treatment of the relation of body and mind as regards both the method and the general theory of psychology. Mr. Lewes's "Problems of Life and Mind," vols. iii.-v., Dr. Michael Foster's "Text-book of Physiology," Book iii., Wundt's "Physiologische Psychologie," Fechner's "In Sachen der Psychophysik," Maudsley's "Physiology of Mind" and "Pathology of Mind" are among the books recommended.

MR. J. M. H. MUNRO, D.Sc. Lond., F.C.S., has been elected resident Professor of Chemistry in the Wilts and Hants Agricultural College, Downton, Salisbury, and he will act in co-operation with Prof. A. H. Church, M.A. Oxon. Dr. Munro headed the list in first-class honours in chemistry at both of the examinations for the B.Sc. degree, and obtained the chemical exhibition of the University in 1874. He was also classed in botany and vegetable physiology, and in logic and moral philosophy, and took the Doctor's degree in 1877. He recently received a grant from the Chemical Society in aid of a research on which he is at present engaged.

SCIENTIFIC SERIALS

THE *Proceedings of the Royal Irish Academy* ("Science"), part 5, vol. iii., series 11, December, 1880, contains—W. R. Roberts, on the satellite of a line meeting a cubic.—A. H. Anglin, mathematical notes.—Prof. J. P. O'Reilly, on the directions of main lines of jointing observable in the rocks about the Bay of Dublin, and their relations with adjacent coast-lines;—also on the correlation of the lines of faulting of the Palamow coal-field district, Northern India, with the neighbouring coast-lines.—Prof. E. Davy, preliminary report on some new organic nitroprussides.—Prof. W. King, preliminary notice of a memoir on rock-jointing in its relation to phenomena in physical geography and physical geology.—J. F. Knott, on some anomalies in human anatomy (woodcuts).—Prof. Mackintosh, note on the occurrence of a premaxillo-frontal suture in the skull of the koala (*Phascolarctos cinereus* (with plates 10 to 13).—G. H. and G. A. Kinahan, eurites or basic felstones of Silurian age.—G. H. Kinahan, supposed Upper Cambrian rocks in the counties of Tyrone and Mayo.

THE *Proceedings of the Royal Irish Academy*.—"Polite Literature and Antiquities," part 2, vol. ii. series 11, December, 1880, contains the following papers of interest to the student of nature:—W. Frazer, description of a great sepulchral mound near Donnybrook (in Co. Dublin), containing human and animal remains, as well as some objects of antiquarian interest referable to the tenth or twelfth centuries (woodcuts).—G. Allmann Armstrong, particulars relative to the finding of human remains in the neighbourhood of Dundalk (woodcut).—R. J. Ussher and G. H. Kinahan, on a submarine crannog at Ardmore, Co. Waterford (plate 1 and woodcut).—Thos. Plunkett, on an ancient settlement found about twenty-one feet beneath the surface of the peat in the coal-bog at Boho, Co. Fermanagh (plate 2).

THE *Scientific Proceedings of the Royal Dublin Society*, vol. ii. new series, part vii., November, 1880, contains:—V. Ball, on the mode of occurrence and distribution of diamonds in India.—A. B. Wynne, on some points in the physical geology of the Dingle and Iveragh Promontories.—Dr. C. A. Cameron, on the action of water upon mercuric sulphate.—J. H. Luby, voluntary act of self-destruction by the worker bee.—G. F. Fitzgerald, F.I.C.D., notes on fluorescence.—Thos. Plunkett, on chert in the limestone of Knockbeg, county of Fermanagh (woodcut).—R. M. Barrington, M.A., on the introduction of the squirrel into Ireland (with a map).

Vol. iii., new series, part i., January 1881, contains:—C. E. Burton and Howard Grubb, on a new form of ghost micrometer for use with astronomical telescopes (plates 1 to 4).—E. T. Hardman, on a travertine from Ballisodare near Sligo, containing a considerable amount of strontium.—W. Swith, preliminary note on the manufacture of paper from melic grass (*Molinia cærulea*).—D. M'Ardle.—On some new or rare Irish Hepaticæ (with plates 5 and 6).—Percy Evans Freke, on North American birds crossing the Atlantic (with tables).

Journal and Proceedings of the Royal Society of New South Wales, vol. xiii., 1879 (Agents in London Messrs. Trübner and Co.), contains—On the "gem" cluster in Argo, by H. C. Russell.—On the water of Sydney Harbour, by the Rev. W. H. Sharp.—On the anatomy of Distichopora, with a monograph of the genus, by Rev. J. E. Tenison-Woods (two plates).—On the geological formations of New Zealand compared with those of Australia, by Dr. Jas. Hector.—On the languages of Australia in connection with those of the Mozambique and of the south of Africa, by Hyde Clarke.—On *Ottelia præterita*, F. v. M., by Baron von Müller, with a plate (an alisma-like leaf-impression from the green-bush quarry near to Parramatta, apparently allied

to *Ottelia ovalifolia*).—On a compiled catalogue of latitude stars, epoch 1880, by H. S. Hawkins.—On the occurrence of remarkable boulders in the Hawkesburg rocks, by C. S. Wilkinson.—On the Wentworth hurricane, by H. C. Russell.—Abstract of the meteorological observations taken at the Sydney Observatory, by H. C. Russell. (January to December, 1879).

American Journal of Science, December, 1880.—Note on the zodiacal light, by H. C. Lewis.—The early stages of renilla, E. B. Wilson.—Geological relations of the limestone belts of Westchester, co. New York, by S. D. Dana.—Abstract of some palæontogical studies of the life-history of *Spirifer brevis*, H, by H. S. Williams.—Index to vols. xi.-xx.

Journal of the Franklin Institute, January.—Experiments with the Parkins machinery of the steam yacht *Anthracite*, by Chief-Engineer Isherwood.—The determination of silicon and titanium in pig-iron and steel, by Dr. Drown and Mr. Shimer.—An adaptation of Bessemer plant to the basic process, by Mr. Holley.—The value of the study of the mechanical theory of heat, by Mr. Wolff.—Blasting, by Mr. Kirk.—On the wholesomeness of drinking-water, by Mr. Haines.—An inquiry into the laws of the beautiful in music, by Prof. Clarke.

THE last number of the *Journal* of the Physical and Chemica Society (Russian) contains, besides minutes of meetings, papers on the electrolyse of formic and mellite acids, by M. N. Bunge.—On the variations of the quantity and pressure of oxygen in the lungs, by Prof. Ivan Setchenoff.—On products of the decomposition of albuminous matters, by Dr. Danilevsky.—On hops, by M. Tchekh; and several smaller notes on organic chemistry.—In the physical part, M. Shvedoff continues his researches on hail, trying to establish by various very interesting arguments the cosmic origin of hail, which he considers as a variety of meteorites.—M. Reinboth describes a new naphtha barometer which has a great sensibility.—M. Van der Flith gives several new mathematical formulæ concerning electrodynamics.

THE *Schriften der physikalisch-ökonomischen Gesellschaft zu Königsberg* (1879, i. and ii.; 1880, i.).—These parts contain the following papers:—On the *Uredo* fungus, by Dr. Caspary.—On the Gastræa theory, by Prof. Kupffer.—On pisciculture, by Dr. Seidlitz.—On some acoustical and optical experiments with the telephone, by Prof. Berthold.—On the phonograph, by Dr. Zenker.—On the ancestors of carnivora, by Dr. Albrecht.—What is species, and what variety? by Dr. Caspary.—On bacteria, by Dr. Baumgarten.—On the observations made at the station for measuring the temperature of the soil in various depths at the Botanical Gardens at Königsberg, by Prof. E. Dorn.—On some periodical phenomena in inorganic nature, by Dr. Jentsch.—On the ancestors of hoofed animals and Edentata, by Dr. Albrecht.—On the rhythmical motions in the animal and in the human body, by Prof. Grünhagen.—On the fauna of New Zealand, by Prof. Zaddach.—On the archæopteryx, by Prof. Zaddach.—On the ancestors of rodentia, by Dr. Albrecht.

Bulletin de l'Academie Royale des Sciences (de Belgique), No. 12, 1880.—Application of the tuning-fork to study of the propagation of sound and vibratory movements in liquids, by M. Montigny.—On the falling stars of November 27, 1880, observed at Brussels Observatory, by M. Houzeau.—On two plesiosaurs of the lower lias of Luxembourg, by M. van Beneden.—Science and the imagination (lecture at public *séance*), by M. Stas.—Voyages and metamorphoses of a drop of water, by M. Van der Mensbrugghe.—Announcement of the results of prize competitions.—Reports on memoirs, &c.

Rivista Scientifico-Industriale, No. 1, January 15.—Singular verticillate configuration (in the form of a rose) of the laminæ of crystallised water, by Prof. Bombicci.—On storms, by Prof. Cantoni.—A modification of the Ruhmkorff coil, by Dr. Scarpa and S. Baldo.—Two new species in the Mediterranean fauna, by Prof. Richiardi.—Some ammonites of the middle lias, by S. Canavari.—Paramagnetism and diamagnetism of liquids, by Prof. Marangoni.—Experiments proving that air saturated with moisture is an insulator as well as dry air, by the same.

Journal de Physique, January.—Atmospheric absorption of ultra-violet radiations, by M. Cornu.—Experimental researches on the psychrometer, by M. Macé de Lépinay.—On the division of instantaneous currents, by M. Brillouin.—Electric *explorateur* of M. Trouvé, by M. Guriel.—M. Trouvé's apparatus for examination of deep natural or artificial cavities, by the same.—On resultant sounds, by M. Nicotra.

SOCIETIES AND ACADEMIES

LONDON

Royal Society, February 3.—Prof. Owen read a third part of his description of the great extinct horned lizard of Australia (*Megalania prisca*). The materials had been transmitted from the same formation and locality-petrified drift-bed of King's Creek, Queensland, as the subjects of Part 2, and were discovered by Mr. Geo. Fred. Bennett, about thirty feet from the fore skull. They proved to be, when recomposed, the opposite extremity of the animal, and consisted of an ossified sheath of the tail, in annular segments supporting conical cores of horn-like weapons. Of these segments the three terminal ones had coalesced; a fourth detached segment fitted the antepenultimate ring. Each ring, save the last, supported two pairs of horn-cores, of which dimensions were given and drawings exhibited of the natural size. From tip to tip of the dorsal pair of the antepenultimate segment measured ten inches. In this segment was included the corresponding vertebra, exemplifying the caudal modifications of the type of the dorsal, sacral, and other vertebræ of *Megalania* described in the parts communicated to the Royal Society in 1858 and 1880. The author then entered into an exhaustive review of analogous caudal armatures in other animals. The nearest approach, in the class *Reptilia*, was made by the small existing Australian lizard (*Moloch horridus*) and by the *Uromastix princeps*, recently described by the late Arthur W. E. O'Shaughnessy, of whom Prof. Owen spoke in terms of deep regret and respect.

The supports of the caudal horns or spines in the above small lizards retained the immature condition of fibro-cartilage. Examples where histological development had proceeded to ossification were cited from recent and fossil *Reptilia*. In the latter the nearest approach to the caudal armature of *Megalania* was presented by the *Scelidosaurus*, of the Dorsetshire lias. A still nearer resemblance to the singular structures described in the present paper was made by certain extinct species of gigantic armadillos, e.g. *Glyptodon asper*, from South American tertiaries.

The author associated this repetition or lingering of a reptilian osteodermal character in the mammalian class with the previously-known repetition of the horny scutation of lizards in the mammalian pangolins (*Manis*); he referred to the low dental condition in the numerous similar simple teeth of armadillos and the still lower characters which had suggested the ordinal term "Edentata." He cited the tenacity of life and long continuance of the muscular irritability after death in the sloths; the winter sleep of bats and certain rodents, with their faculty of circulating blood in the venous state; the quills in hedgehogs and porcupines as indicative of a repetition of a dermal character of an oviparous class; the anatomical modifications giving a faculty of flight, as in Pterosaurians.

The sole common organic character of, and peculiar to, such members of a large and otherwise much varied group of mammals was a cerebrum, small, not extending upon the cerebellum, smooth or with few and simple convolutions, but with the hippocampal commissure ascending to connect the hemispheres above the lateral ventricles, and so constituting the anthropotomical "corpus callosum." A still lower group of mammals had no such commissural development, but this common cerebral character was associated with as many and great variations of inferior structures as in the *Lissencephala*. The *Lyencephala* included the marsupials and monotremes.

In the discussion which followed the reading of the paper the chief objection was an averment that the author had no evidence of its subjects having belonged to *Megalania prisca*, and that they were more probably parts of some Chelonian reptile.

To this the author replied that he had evidence both negative and positive. From the year 1857 he had received parts of the skeleton of a great terrestrial reptile from localities hundreds of miles apart in the provinces of New South Wales, Victoria, Queensland, but not a single fragment of a carapace, plastron, or other characteristic part of a Chelonian; every large reptilian fossil was not only "Lacertian," but of the very genus and species *Megalania prisca*. Perhaps no part of the axial skeleton was more differentiated than the occipital vertebra in a lizard and a tortoise. In the latter the elements remained as distinct as in a fish; in the former as confluent as in the mammal; this at least was the case in *Moloch* as it is in *Megalania*. Finally Prof. Owen pointed to the vertebra in organic connection with the tail-sheath in the fossils last received; it was Lacertian, not Chelonian.

"On a Method of Destroying the Effects of Slight Errors of Adjustment in Experiments of Changes of Refrangibility due to Relative Motions in the Line of Sight," by E. J. Stone, F.R.S., Director of the Radcliffe Observatory, Oxford.

Let arrangements be made for the reversion of the prisms without any disturbance of the other optical arrangements, including, of course, the position of the cylindrical lens, if one be used. Any slight errors of adjustment which prevent the light from the star and the comparison light from falling upon the train of prisms under the same optical circumstances, so far as mere direction is concerned, will have opposite effects in the reversed positions of the prisms; but the separation of the emergent lights due to relative motion will remain unchanged by the reversal of the positions of the prisms.

If, therefore, the apparent change of refrangibility due to relative motion remains unchanged by the reversion of the prisms, all doubts about the effects of errors of adjustment will be removed. But if the results in the reversed positions of the prisms sensibly differ, then the existing errors of adjustment must be removed, or their effects allowed for by taking a mean of the results in reversed positions, before any reliance can be fairly placed upon the determination of relative motions in the line of sight.

A reversible spectroscope was arranged by me, and made by Mr. Simms, some years ago, but I have never since had an equatorial, with a good driving clock, under my control, with which the experiment indicated could be properly tried.

With the direct prisms now in use the required reversion can be easily arranged. I am not likely for some time to have the use of a good equatorial, and I therefore publish the plan with the hope that some one more fortunately situated may give it a fair trial.

The experiment is a crucial one, and in my opinion should be tried.

Chemical Society, February 3.—Dr. Gladstone, vice-president, in the chair.—It was announced that a ballot for the election of Fellows would take place at the next meeting of the Society.—The following papers were read:—On the estimation of organic carbon in air, by Drs. Dupré and Hake. The carbon is converted into carbonic acid by passing the air over heated oxide of copper; the carbonic acid thus produced is absorbed by baryta water, and the carbonate is converted into sulphate which is weighed. The carbonic acid present in the air, as such, is estimated in a similar way and deducted. The mean quantity of organic carbon in ten litres of ordinary London air was 0·000154; Boussingault and Verser found ten times as much. The authors also refer to the results obtained by Pettenkofer in his well-known experiments on the elimination by animals of H and CH_4. Pettenkofer seems to have entirely neglected the organic carbon in the atmosphere, and thus his results require very important corrections.—On the action of the copper-zinc couple upon nitrates and the estimation of nitric acid in water analysis, by M. W. Williams. Some strips of clean zinc foil are placed in a wide mouth stoppered bottle and covered with a 3 per cent. solution of copper sulphate: when the zinc has acquired a sufficient coating of copper the solution is poured off and the copper zinc couple washed. The water to be analysed is then poured on the couple and allowed to remain for some hours at 24° C., after the addition of a little pure sodium chloride. The nitrates are thus completely converted into ammonia, which is estimated by nesslerising.—On the position taken by the nitro-group on nitrating the dibromo-toluenes, by R. Nevile and A. Winther.—On some of the various derivatives of toluene and the toluidines, by R. Nevile and A. Winther.

Anthropological Institute, January 25.—Anniversary Meeting.—Edward B. Tylor, F.R.S., president, in the chair.—Dr. Tylor, the retiring president, gave the annual address on the year's progress of the science of man and civilisation. He described the excellent arrangements in the United States for supplying Indian agents, missionaries, and others in contact with native tribes, with manuals to guide them in collecting information as to laws, customs, languages, religion, &c., the very memory of which will die out with the present generation of Indians. He contrasted the active intelligence of the United States in this with the fact that the Dominion of Canada, though kindly and wise in their practical management of the Indians, do not seem alive to the value of the scientific knowledge which is being lost among them for want of a little cost and trouble in collecting it. Dr. Tylor also spoke of Prof. Flower's study of the mountaineers of Fiji, the Kai Colo, a race who have the narrowest skulls of all mankind. The public have not yet become aware of the value of minute measurement of skull-dimensions, but Prof. Flower has clearly shown in it a means of bringing the study of races under arithmetical calculation, a step which will do much to bring anthropology among the exact sciences.—The new president is Major-General A. Pitt-Rivers, F.R.S.

Physical Society, February 12.—Prof. W. G. Adams in the chair.—This being the annual general meeting, the yearly report was read by the Chairman. The report showed that the Society now numbered 321 members as against 298 of last year. Two eminent members, Sir T. H. Elliot and the Rev. Arthur Rigg, had been lost by death. The Society had decided to republish the scientific papers of Dr. Joule in a collected form.—Dr. Atkinson, treasurer, read the balance-sheet for the past year, which showed the Society to be flourishing.—The new Council and Officers were then elected, Sir W. Thomson retaining the presidency.—Mr. Bakewell and Herr G. Wiedemann were created Honorary Members.—Votes of thanks were passed to the Lords Commissioners of the Council of Education for granting the use of the meeting-room to the Society, to Prof. Adams and to Dr. Guthrie, the demonstrator, the auditors, and the secretaries, Professors Rheinhold and Roberts.—The meeting was then resolved into a special general meeting, and a resolution put and carried giving the Council power to invest money of the Society in the name of the Society, or of persons appointed by them, in certain stock, home and foreign.—The meeting was then constituted an ordinary one, and Mr. T. Wrightson, C.E., read a paper by Prof. Chandler Roberts and himself on the density of fluid bismuth. By means of the oncosimeter, an instrument which records on a band of paper the sinking or floating effect of a ball of the solid metal immersed in the molten metal, they had determined the density of fluid bismuth from six experiments to be 10·055. A former value by a different method was 10·039. In the discussion which ensued, Mr. Wrightson stated that his experiments proved solid cast iron to be heavier than fluid, and to sink in the latter when first immersed, but it rapidly became lighter as its temperature rose, till it floated when in its plastic state, and was consequently lighter than when in the molten state. The oncosimeter could be utilised for determining the change of volume in melting rocks, and Prof. Chandler Roberts suggested that it might throw light on the difference of state between the carbon of grey pig and white iron.—Dr. O. J. Lodge exhibited working models showing the hydrostatic analogies between water and electricity. A battery was represented by a pump, conductors by open pipes, dielectrics by a pipe closed by an elastic membrane, electrometers by pressure gauges. With these analogues he showed the action of a Leyden jar, and the passage of telegraphic signals along a cable.

Geological Society, February 2.—Robert Etheridge, F.R.S., president, in the chair.—Joseph Groves, George Lewis, Rev. Edouard Méchin, S.J., James Osborne, and the Rev. William Sharman were elected Fellows of the Society.—The following communications were read:—On the coralliferous series of Sind and its connection with the last upheaval of the Himalayas, by Prof. P. Martin Duncan, F.R.S.—This communication is the result of the author's study and description of the fossil corals of Sind, undertaken at the request of the Geological Survey of India. The history of the researches in the geology of the Tertiary deposits of Western Sind was noticed in relation to a statement made some years since by the author and Mr. H. M. Jenkins, F.G.S., that there was more than one Tertiary series there, in opposition to both D'Archiac and Haime. After a brief description of the geology of the Khirthar and Laki ranges of hills, which were called Hala Mountain by the French geologists, the succession of the stratigraphical series demonstrated by the survey under Blanford and Fedden was given, and the author proceeded to discuss the peculiarities of the six coral faunas of the area, and to argue upon the conditions which prevailed during their existence. A transitional fauna, neither Cretaceous nor Eocene, underlies a trap; to the trap succeeds a great development of Nummulitic beds containing corals, the Ranikot series, some of which are gigantic representatives of European Nummulitic forms. A third fauna, the Khirthar, succeeds, and a fourth, Khirthar-Nari, which was a reef-building one; and a fifth, the Nari, is included in the Oligocene age. An important Miocene coralliferous series (the Gaj) is on the top of all. These faunas above the trap are Nummulitic, Oligocene, and Miocene in age, and in the first two European forms

which are confined to definite horizons, are scattered indefinitely in a vertical range of many thousands of feet. The corals grew in shallow seas, but most of them were not massive limestone builders, but there were occasional fringing reefs, or rather banks of compound forms, which assisted in the development of limestones. Many genera of corals which elsewhere are massive are pedunculate in Sind, and the number of species of the family Fungidæ is considerable. There are also alliances with the Eocene coral fauna of the West Indies. The depth of the coralliferous series and the intercalated unfossiliferous sandstones, &c., is, according to the Survey, 14,000 feet, without counting an estimated 6000 feet of unfossiliferous strata in one particular group. The subsidence has therefore been vast, but not always continuous. After noticing the numbers of genera and species in this grand series of coral faunas and the remarkable distinctness of each, the author proceeded to discuss the second part of his subject. When president of the Society he had stated in his anniversary address for 1878 that he was not convinced of the truth of the theory of the Geological Survey of India regarding the Pliocene age of the last Himalayan upheaval. The considerations arising from the position of a vast thickness of sedimentary deposits overlying the Gaj or marine Miocene, and containing *Amphicyon*, *Mastodon*, *Dinotherium*, and many Artiodactyles of the supposed pig-like ruminant group, lead to the belief that the author was not justified in opposing the theory enunciated by Lyddeker and the directors of the Survey. The position of these Manchhar strata on the flanks of the mountain system of Sind was compared with that of the sub-Himalayan deposits. The faunas were compared, and the Sewalik deposits, the equivalents of the Upper Manchhar series of Sind, were pronounced to be of Pliocene age. They were formed before and during the great upheaval of the Himalayas, and in some places are covered with glacial deposits. A comparison was instituted between these ossiferous strata and the beds of Eppelsheim and Pikermi, and the auihor discussed the question relating to the age of terrestrial accumulations overlying marine deposits.—On two new crinoids from the Upper Chalk of Southern Sweden, by P. H. Carpenter, M.A. Communicated by Prof. P. Martin Duncan, F.R.S. Stem-joints of a crinoid resembling those of *Bourgueticrinus* have long been known in the Plänerkalk of Streben (Elbe); but on the discovery of the calyx it was found to differ considerably from that genus. It was then referred to the genus *Antedon* by Prof. Geinitz. Stems also resembling *Bourgueticrinus* have been found in the upper chalk of Köpinge (S. Sweden), and a calyx resembling that described by Prof. Geinitz has also been found. Prof. Lundgren kindly entrusted this to the author for description. For these two fossils he considers not only a new genus but also a new family required. He proposes for the former the name *Mesocrinus*, as the characters of its calyx ally it to the Pentacrinidæ. The author describes the characteristics of the genus *Mesocrinus* and of the species *M. suecica* (the Swedish) species, and its differences from *M. fischeri* (from Streben), and discusses the relationships of the genus, which combines the characters of a *Pentacrinus*-calyx with a *Bourgueticrinus*-stem.—A new species of Comatula (*Antedon impressa*) from the Ignaherga limestone of Scania was also described, and its systematic position discussed.

Entomological Society, February 2.—Mr. H. T. Stainton, president, in the chair.—The president thanked the Society for electing him to that office, and nominated Sir John Lubbock, Bart., and Messrs. Meldola and Distant as vice-presidents for the ensuing year. Two new members were then elected.—Exhibitions and communications:—Mr. O. Salvin exhibited two boxes of insects collected by Mr. Champion in Guatemala.—Mr. W. A. Forbes exhibited a leaf from New Britain, having a curious filamentous growth upon it, caused by a *Coccus*; and also the larva of one of the *Blattidæ*, from Pernambuco, which presented a remarkable resemblance to an Isopod crustacean.—Mr. R. McLachlan exhibited a coleopterous larva from South America attacked by a fungoid parasite (*Sphæria*), and a *Noctua* from South Wales similarly attacked by an *Icasia*. He also exhibited *Thore concinna*, a beautiful new dragon-fly from Ecuador.—Mr. T. R. Billups exhibited *Pæomachus distincta*, a hymenopterous insect new to Britain; and a new species of *Stibentes*.—Mr. F. P. Pascoe exhibited a specimen of *Peripatus Novæ-Zealandiæ*, and made some observations on the structure and affinities of this anomalous genus.—Mr. W. L. Distant exhibited a new species of *Platypleura* from Madagascar.—Mr. W. F. Kirby announced the death of Dr. Gabriel Koch, of Frankfort-on-the-Main, the author of several works on the geographical distribution of *Lepidoptera*.—Mr. R. Meldola read a letter from M. André in reply to some criticisms made at a former meeting of the Society respecting the publication of new species on the wrapper of a periodical work.—The Secretary read a cutting from an Australian newspaper, communicated by Mr. G. Giles, relative to the death of a child, in consequence, as was supposed, of the bite of a small spider.—Papers read:—Mr. A. G. Butler communicated a paper entitled "Descriptions of new genera and species of Heterocerous *Lepidoptera* from Japan."—Mr. R. McLachlan read some notes on *Odonata* of the sub-families *Corduliinæ*, *Calopteryginæ*, and *Agrioninæ* (Legion *Pseudostigma*) collected by Mr. Buckley in the district of the Rio Bobonaza in Ecuador.—Mr. W. F. Kirby read a list of the Hymenoptera of New Zealand, in which eighty-two species were enumerated, five being described as new.—Mr. Joseph S. Baly communicated a paper entitled descriptions of new species of *Galerucidæ*.

Victoria (Philosophical) Institute, February 21.—A paper on the implements of the Stone age as a primitive demarcation between man and other animals, by Dr. Thompson, LL.D., of Harvard University, was read; after which a second brief paper on the caves of Devonshire was read by Mr. Howard, F.R.S., in which the author, as a chemist, pointed out the important bearing that the new investigations into the mode of formation of the cave floor had upon the whole question at issue.

VIENNA

Imperial Academy of Sciences, February 17.—V. Burg in the chair.—Prof. Schmarda presented a paper by Henry B. Brady, F.R.S., on Arctic foraminifera from soundings obtained on the Austro-Hungarian North Pole Expedition of 1872-74. It will be published in the *Denkschriften der Academie*.—F. Steindachner, ichthyological materials (part 10).—F. Wild studies on chemical processes producing energy.—E. Brücke, supplement to his communication of January 7 on an uncrystallisable acid obtained by oxidation of egg albumen. It is not a pure substance, but a mixture.—E. Weiss, on the computation of the differential quotients of the radius vector and the apparent anomaly in orbits of great excentricity.—T. V. Robra on *Amphioxus lanceolatus*.—Dr. Td. H. Skraup, on synthetical experiments in the Chinolin series.

CONTENTS

Page

PROFESSOR MAX MUELLER AT UNIVERSITY COLLEGE 405
ATLAS OF HISTOLOGY 405
OUR BOOK SHELF:—
"Urania" 406
LETTERS TO THE EDITOR:—
Infusible Ice.—Prof. A. S. HERSCHEL 406
Dust, Fogs, and Clouds.—JOHN AITKEN. 406
Geological Climates.—Prof. SAMUEL HAUGHTON, F.R.S. 406
Climate of Vancouver Island.—Dr. GEORGE M. DAWSON 407
"The New Cure for Smoke."—J. A. C. HAY 407
On the Space Protected by Lightning-Conductors.—Prof. JOSEPH LE CONTE 407
Localisation of Sound.—H. B. JUPP 408
Migration of the Wagtail.—Prof. E. W. CLAYPOLE 408
Subsidence of Land caused by Natural Brine-Springs.—THOS. WARD 408
Chlorophyll.—WILLIAM CARTER 408
Squirrels Crossing Water.—F. A. JENTINK 408
Flying-Fish.—R. E. TAYLOR 408
THE TRANSIT OF VENUS 408
DR. J. J. BIGSBY 409
ON TIDAL FRICTION IN CONNECTION WITH THE HISTORY OF THE SOLAR SYSTEM. By G H. DARWIN, F.R.S. 409
INDIGO. 411
MICROSCOPIC STRUCTURE OF MALLEABLE METALS. By J VINCENT ELSDEN 412
ISLAND LIFE, II. By Prof. ARCH. GEIKIE, F.R.S. (*With Map*) 413
HONOUR TO MR. DARWIN. 416
DEGREES TO WOMEN 416
NOTES 417
OUR ASTRONOMICAL COLUMN:—
Encke's Comet in 1881 419
Cincinnati Measures of Double Stars 419
The Minor Planets in 1881 419
CHEMICAL NOTES 419
PHYSICAL NOTES 420
GEOGRAPHICAL NOTES 420
ABNORMAL VARIATIONS OF BAROMETRIC PRESSURE IN THE TROPICS AND THEIR RELATIONS TO SUN-SPOTS, RAINFALL, AND FAMINES. By E. DOUGLAS ARCHIBALD and FRED. CHAMBERS 421
STANDARD THERMOMETERS 422
UNIVERSITY AND EDUCATIONAL INTELLIGENCE 422
SCIENTIFIC SERIALS 422
SOCIETIES AND ACADEMIES 422

DIARY OF SOCIETIES.

LONDON

THURSDAY, FEBRUARY 24.

ROYAL SOCIETY, at 4.30.—On a Simple Mode of Eliminating Errors of Adjustment in Delicate Observations of Compared Spectra: Prof. Stokes. Sec.R.S.—Notes on Physical Geology, No. VII. On the Secular Inequalities in Terrestrial Climates depending on the Perihelion, Longitude, and Excentricity of the Earth's Orbit: Rev. Dr. Haughton, F.R.S.

LONDON INSTITUTION, at 7.—One Aspect of Colour: Capt. Abney.

SOCIETY OF TELEGRAPH ENGINEERS, at 8.—Adjourned Discussion on Mr. Alex. J. S. Adams's Paper (Earth Currents—Electric Tides).—On the Application of Dynamo-Electric Machines to Railway Rolling Stock: Lieut. P. Carden.—On the Interference with the Processes of Manufacture of Wool and Hair arising from the Development of Electricity during Spinning; with a Description of Apparatus applied to obviate it: Edward B. Bright.

SOCIETY OF ARTS, at 8.—Deep-Sea Investigation: J. G. Buchanan.

ROYAL INSTITUTION, at 3.—Drawing-Room Music: Prof. Pauer.

FRIDAY, FEBRUARY 25.

QUEKETT MICROSCOPICAL CLUB, at 8.

ROYAL INSTITUTION, at 9.—Excitability in Plants and Animals: Dr. J. Burdon-Sanderson.

SATURDAY, FEBRUARY 26.

PHYSICAL SOCIETY, at 3.—On an Integrating Machine: C. V. Boys.—On the Telegraphic Transmission of Pictures of Natural Objects: Shelford Bidwell.

ROYAL INSTITUTION, at 3.—Ancient Egypt: R. S. Poole.

SUNDAY, FEBRUARY 27.

SUNDAY LECTURE SOCIETY, at 4.—A Common Source of Error in Seeing and Believing: Dr. H. Maudsley.

MONDAY, FEBRUARY 28.

ROYAL COLLEGE OF SURGEONS, at 4.—The Cetacea: Prof. Flower.

ROYAL GEOGRAPHICAL SOCIETY, at 8.30.

INSTITUTE OF ACTUARIES, at 7.—On the Mortality observed amongst the various Classes of Bonus Policies in the British Empire Mutual Assurance Company: G. R. Hardy.

ARISTOTELIAN SOCIETY, at 8.—Hume: W. A. Casson.

TUESDAY, MARCH 1.

ZOOLOGICAL SOCIETY, at 8.30.—Descriptions of New Genera and Species of Asiatic Nocturnal Lepidoptera: F. Moore.—Observations on Two Species of Indian Butterflies (*Papilio castor* and *P. pollux*): Prof. J. O. Westwood.—On *Halichærus gryphus* and its Breeding on the Fro Islands, off Trondhjem's Fiord, in Norway: R. Collett.

SOCIETY OF ARTS, at 8.—The Languages of South Africa: R. N. Cust.

ROYAL INSTITUTION, at 3.—The Blood: Prof. Schäfer.

WEDNESDAY, MARCH 2.

ROYAL COLLEGE OF SURGEONS, at 4.—The Cetacea: Prof. Flower.

SOCIETY OF ARTS, at 8.—Lighthouse Characteristics: Sir Wm. Thomson.

ENTOMOLOGICAL SOCIETY, at 7.

THURSDAY, MARCH 3.

ROYAL SOCIETY, at 4.30.

LINNEAN SOCIETY, at 8.—Reparative Processes in Plants: S. G. Shattock.—On the Apparent Retention of a Sur-anal Plate by a young *Echinometra*: Prof. F. Jeffrey Bell.—On *Arnebia* and *Macrostomia*: C. B. Clarke.—Pleurotomidæ of *Challenger* Expedition: Rev. R. Boog Watson.

CHEMICAL SOCIETY, at 8.—On the Action of Bacteria on various Gases: F. Hatton.—On the Oxidation of Organic Matter in Running Water: Dr. C. M. Tidy.—On the Action of Aldehydes on Phenanthrenequinone in presence of Ammonia (Second Notice): Dr. F. R. Japp and Edgar Wilcock.—On the Action of Benzoic Acid on Naphthaquinone (Preliminary Notice): Dr. Japp and R. H. J. Miller.

LONDON INSTITUTION, at 7.—The Production of Electricity: Prof. W. E Ayrton.

ROYAL INSTITUTION, at 3.—Cuneiform Characters: Rev. W. Houghton.

FRIDAY, MARCH 4.

ROYAL COLLEGE OF SURGEONS, at 4.—The Cetacea: Prof. Flower.

GEOLOGISTS' ASSOCIATION, at 8.

SOCIETY OF ARTS, at 8.—British Rule in India: J. M. Maclean.

ROYAL INSTITUTION, at 9.—Elasticity: Sir W. Thomson.

SATURDAY, MARCH 5.

ROYAL INSTITUTION, at 3.—Ancient Egypt: R. S. Poole.

THE "HANSA"

Published since 1864 in Hamburg, is the only independent professional paper in Germany, dedicated exclusively to Maritime Objects. Essays, Critiques, Reviews, Reports, Advertisements. Strict eye kept upon the development of Maritime Affairs in every respect. Every second Sunday one Number in 4to at least; frequent supplements and drawings. Subscription at any time; preceding numbers of the year furnished subsequently. Price 12s. for twelve months. Advertisements 4d. a line, widely spread by this paper; considerable abatement for 3, 6, 12 months' insertion. Business Office: Aug. Meyer and Dieckmann, Hamburg, Alterwall. 98. Edited by W. v. FREEDEN, M.R., Hamburg, Alexander Street, 8.

SUBSCRIPTIONS TO NATURE

Yearly . . . . . 28s.
Half-yearly . . . . . 14s. 6d.
Quarterly . . . . . 7s. 6d.

To the Colonies, United States, the Continent, and all places within the Postal Union :—

Yearly . . . . . 30s. 6d.
Half-yearly . . . . . 15s. 6d.
Quarterly . . . . . 8s.

Office: 29, Bedford Street, Strand.

LIGHTNING CONDUCTORS.

Experience, accumulated since the time of Benjamin Franklin, proves conclusively that a Conductor made of Copper of adequate size is the best of all appliances for the protection of every description of building from the destructive effects of lightning.

NEWALL & CO.'S

PATENT COPPER LIGHTNING CONDUCTOR,

As applied to all kinds of Buildings and Shipping in all parts of the world with unvarying success; is the most Trustworthy, most Effective, and also the Cheapest Conductor ever offered to the public.

It is simple in its application, no insulators being required, and it costs only one shilling per foot for the standard size, which ensures safety in any storm.

R. S. NEWALL & CO., 130, STRAND, W.C.
36, WATERLOO ROAD, LIVERPOOL.
68, ANDERSTON QUAY, GLASGOW.
MANUFACTORY—GATESHEAD-ON-TYNE.

Liberal Terms to Science Teachers and the Trade.

THOMAS CRAMPTON (formerly of 4, Little Britain, London, E.C.), ELECTRICIANS, OPTICIANS, and PHILOSOPHICAL INSTRUMENT MAKERS. Electric Bells, New Metallic Base Pattern, Constant Batteries, Indicators, Thief and Fire Alarms, and Automatic Switches, Induction and Medical Coils, or Specialities. Insulated Wires of every description. Microscopic and Optical Materials. Telescopes, Opera Glasses, Microscopes, Aneroid Barometers, and Lime-light Apparatus. Illustrated Catalogue Three Stamps.

THOMAS CRAMPTON & CO., 251, HIGH HOLBORN, LONDON, W.C.
For Trade Terms send Card.

NOTICE OF REMOVAL.

JAMES HOW & CO.,

SCIENTIFIC INSTRUMENT MAKERS,

73, FARRINGDON ST., LONDON

(LATE OF 5, ST. BRIDE ST., AND 9, FOSTER LANE)

HOW'S STUDENT'S MICROSCOPE. HOW'S MICROSCOPE LAMP.

Rock Sections and other Objects for the Microscope.

NOW READY.
SECOND EDITION,

GRIFFIN'S

CHEMICAL HANDICRAFT.

PRICE 4s. 7d. POST FREE.

A CATALOGUE OF CHEMICAL APPARATUS:
ILLUSTRATED, CLASSIFIED, DESCRIPTIVE.

Demy 8vo, 480 pp., Illustrated with 1,600 Woodcuts.

Most Complete and Cheapest List of Apparatus.

JOHN J. GRIFFIN AND SONS, 22, GARRICK STREET, LONDON, W.C.

EAGLE INSURANCE COMPANY,

79, PALL MALL.

FOR LIVES ONLY. ESTABLISHED 1807.

Accumulated Funds £3,043,542
Also a Subscribed Capital of more than £1,500,000

Reports, Prospectuses, and Forms may be had at the Office, or from any of the Company's Agents, post free.

GEORGE HUMPHREYS, Actuary and Secretary.

CHEMICAL APPARATUS AND SCIENTIFIC INSTRUMENTS.

PURE CHEMICALS, &c.

IMPORTERS AND MANUFACTURERS:

AUG. BEL & CO.,

34, MAIDEN LANE, COVENT GARDEN, LONDON, W.C.

Laboratories fitted up. Sets of Apparatus as required by the Universities, Colleges, and Schools always ready and kept in stock. Professor Feser's Patent Lactoscope for Testing Milk, as recommended by Dr. Voelcker. Description on Application. A Liberal Discount allowed to the Trade.

ELECTRICAL AND SCIENTIFIC APPARATUS.

Wholesale Manufacturer of Metallic Base Electric Bells, Electric Reversing Indicators, and Constant Manganese Batteries, Telephone Switches and Transmitters, Induction Coils and Vacuum Tubes, Terminals, Carbons, Wire and all Materials. Instruments made, repaired, or altered on the premises.
Illustrated Bell List free. Complete Catalogue Two Stamps. Special Quotations to the Trade.
HENRY J. DALE, MANUFACTURING ELECTRICIAN and OPTICIAN, 4, Little Britain, London, E.C.

DRAPER'S INK (DICHROIC).
THE NEW BLACK INK

DIFFERING FROM ANYTHING ELSE EVER PRODUCED.
Writing becomes a pleasure when this Ink is used. It has been adopted by the principal Banks, Public Offices, and Railway Companies throughout Ireland.

It writes almost instantly Full Black. | Flows easily from the Pen.
Does not corrode Steel Pens. | Blotting-paper may be applied at the
Is cleanly to use, and not liable to Blot. | moment of writing.

Can be obtained in London, through Messrs. BARCLAY & SONS, Farringdon Street; W. EDWARDS, Old Change; F. NEWBERY & SONS, Newgate Street; WM. MATHER, London and Manchester; J. AUSTIN & Co., Duke Street, Liverpool; and STACY & COOK, Paternoster Row; and to be had of all Stationers.
BEWLEY & DRAPER (Limited), Dublin.

J. ORME & CO.
(Late M. JACKSON & CO.)
MANUFACTURERS AND IMPORTERS OF
SCIENTIFIC APPARATUS
AND
CHEMICALS.
SOLE AGENTS FOR HICKLEY'S PATENT TELEPHONES,
Price 50*s.* per Pair, Cash with Order.
Price Lists sent on receipt of Three Stamps for Postage.
For Trade Terms inclose Business Card.
65, BARBICAN, LONDON, E.C.

S. C. TISLEY & Co.,
OPTICIANS,
172, BROMPTON ROAD, S.W.
(Close to South Kensington Museum.)
THE PHONEIDOSCOPE
An Instrument for Observing the Colour-Figures of Liquid Films under the action of Sonorous Vibrations,
Being a visible demonstration of the Vibratory and Molecular Motion of a Telephone Plate.
The PHONEIDOSCOPE, with 3 Discs, Bottle of Solution, Descriptive Pamphlet, &c., in Cardboard Box, 10*s.* 6*d.*
MANUFACTURED AND SOLD WHOLESALE AND RETAIL BY
S. C. TISLEY & CO., 172, BROMPTON ROAD, LONDON, S.W.
TELEPHONIC ELECTRICITY. All Materials supplied for Experimental Purposes.
Price Lists of Electrical and Acoustic Apparatus, with Drawings and Description of the Harmonograph. Post Free, 2d.

R. W. NEEVES,
PHILOSOPHICAL INSTRUMENT
AND
INTENSITY COIL MAKER.
PRICE LIST, FOUR STAMPS.
55, SIDMOUTH STREET, LONDON, W.C.

HOLLOWAY'S OINTMENT **A CERTAIN REMEDY**
For BAD BREASTS, OLD WOUNDS, and SORES. If effectually rubbed on the Neck and Chest, it cures SORE THROATS, BRONCHITIS, COUGHS and COLDS; and for GOUT, RHEUMATISM, and all Skin Diseases it is unequalled.

On the 1st of every Month, price One Shilling.
THE ZOOLOGIST:
A MONTHLY MAGAZINE OF NATURAL HISTORY.
Third Series. Edited by J. E. HARTING, F.L.S., F.Z.S., Member of the British Ornithologists' Union; contains—
Original articles by well-known naturalists in every branch of zoology; habits of animals; arrival and departure of migratory birds; occurrence of rare birds; distribution and migration of British fresh-water fish; new or rare marine fish; local aquaria; British reptiles; British land and fresh-water mollusca, with remarks on the haunts and habits of the species; and other matters of general interest to those who delight in natural history. Reports of the Linnean, Zoological, and Entomological Societies. Reviews of natural history books. Occasional translations from foreign zoological journals of important and interesting articles in various branches of zoology. There are occasional woodcuts.
JOHN VAN VOORST, 1, Paternoster Row

LA SEMAINE FRANÇAISE: a Weekly Newspaper and Review in the French Language. Politics, Literature, Science, Art, Varieties, Notes. Price 3*d.*, through booksellers, and at the railway bookstalls. Office, 37, Southampton Street, Strand, W.C.

LA SEMAINE FRANÇAISE: Journal Français pour l'Angleterre: Politique, Littérature, Sciences, Arts, Variétés, Nouvelles et Notes. Un exemplaire par la poste, 3½*d.*, en timbres poste. Abonnement franco par la poste—un an, 15*s.* 2*d.*; six mois, 7*s.* 7*d.* Prix 3*d.*, chez tous les libraires et aux gares des chemins de fer. On s'abonne aux bureaux, 37, Southampton Street, Strand, Londres, W.C.

LA SEMAINE FRANÇAISE.—"'La Semaine Française' has been brought out in London for the benefit of those English readers who may wish to study contemporary French from all points of view, instead of confining their reading to one particular Gallic print. It certainly merits success."—*Graphic.*

LA SEMAINE FRANÇAISE.—"The numbers before us are full of good things. . . . . It will be far better for most than any one of the best papers published in Paris itself. We are much pleased with the character of it, and believe it will be highly valued in all those many households where French is cultivated. The printing is very well done."—*Queen.*

TERMS OF SUBSCRIPTION:—

	s.	*d.*
Three months	3	10
Six "	7	7
Twelve "	15	2

P.O.O. payable to T. SPANSWICK, at King Street, Covent Garden, W.C.
Publishing Office, 37, Southampton Street, Strand, W.C.

Price 6*s.*, Part II., Vol. XV., January, 1881.
THE JOURNAL OF ANATOMY AND PHYSIOLOGY.
NORMAL AND PATHOLOGICAL.
CONDUCTED BY
Profs. HUMPHRY, TURNER, M'KENDRICK, & Dr. CREIGHTON.
Contents.
1. Bones, Articulations, and Muscles of Rudimentary Hind-limb of Greenland Right-Whale. By J. Struthers, M.D. (Plates XIV.–XVII.)
2. Infective Form of Tuberculosis in Man identical with Bovine Tuberculosis. By C. Creighton, M.D.
3. Medullary Neuroma of Brain. By W. Osler, M.D. (Plate XVIII.)
4. Dissection of Genito-Urinary Organs in Case of Fissure of Abdominal Walls. By A. Doran, F.R.C.S. (Plate XIX.)
5. Description of a Polygraph (with Figure). By D. Newman, M.B.
6. Remarks on Mechanism of Secretion of Sweat. By C. Handfield Jones, M.B.
7. Anomalous Growth-Bearing Pilose Skin in Pharynx of a Young Woman. By P. S. Abraham, M.A. (With Figure.)
8. Histology of Granular Kidney (with Figure). By R. Saundby, M.D.
9. Two Cases of Cerebellar Disease. By T. Oliver, M.D.
10. Colouring Matter of Jelly Fishes. By Prof. M'Kendrick.
11. Nerves of the Hind-Limb of the Thylacine and Cuscus. By D. J. Cunningham, M.D.
12. Pulse Dicrotism. By Wm. Jas. Fleming, M.D.
13. Anatomical Notices.

MACMILLAN & CO., London and Cambridge.

"NATURE," Nov. 14, 1878, No. 472.—One Shilling each will be paid for Copies of this number.—Address Publisher of NATURE, 29, Bedford Street, Strand, W.C.

METALS and their CHIEF INDUSTRIAL APPLICATIONS. By C. ALDER WRIGHT, D.Sc., Lecturer on Chemistry in St. Mary's Hospital Medical School. With Illustrations.
MACMILLAN & CO. LONDON

In fcap. 8vo, price 3*s.* 6*d.*
SOUND: ELEMENTARY LESSONS ON.
By Dr. W. H. STONE, Lecturer on Physics at St. Thomas's Hospital. With numerous Illustrations.
"This is an excellent little text-book, well adapted for students of the Science and Art Classes, but also of considerable value to those who desire to do something more than cram. The student of acoustics will find it a very acceptable help, and a stepping-stone to the more elaborate works on the subject, while the musician will find in its pages information which may be of great assistance to him in the acquisition of his art."—*English Mechanic.*
MACMILLAN & CO., LONDON.

W. LADD & CO.,

SCIENTIFIC INSTRUMENT MANUFACTURERS,

(By Appointment to the Royal Institution of Great Britain),

11 AND 12, BEAK STREET, REGENT STREET, W.

IMPROVED HOLTZ ELECTRICAL MACHINES. GRAMME'S MAGNETO-ELECTRIC MACHINE for Laboratory use.

PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3s. per oz.

Physical Apparatus of every Description.

ILLUSTRATED CATALOGUE, SIXPENCE.

PATERSON'S NEW CATALOGUE OF PHYSICAL APPARATUS.

LANTERN SLIDES for SCIENTIFIC LECTURES. Season 1880-1. Post free 6 Stamps.
Complete Sets of Physical Apparatus for Science Primers and all the Physical Text-books in use in Schools and Colleges.
Siemens and Gramme Dynamo Machines and Lamps for hire.
Schools supplied with Apparatus as per Science and Art Departments' Requirements in the Sections of Light, Heat, Sound, and Electricity.
Electric Signals for Houses, Hotels, &c., Colliery Signals, Lightning Conductors. The Gower-Bell Loud-speaking Telephone.

EDWARD PATERSON, Electrical Engineer.

SHOW ROOMS AND STEAM WORKS:—76, LITTLE BRITAIN, E.C. (late 3, Bedford Court, W.C.).

MOLISON'S HARMONOGRAPH; executes the Harmonic Curves in the most perfect manner. 15s. and 20s.

Illustrated Catalogue of Electrical Apparatus, Part 1, post free, 6 Stamps. Ditto, Electric Signals, Part 2, 6 Stamps.

A HANDBOOK OF DOUBLE STARS.

With a Catalogue of Twelve Hundred Double Stars, and extensive Lists of Measures. With additional Notes bringing the Measures up to 1879. For the use of Amateurs. By EDWARD CROSSLEY, F.R.A.S., JOSEPH GLEDHILL, F.R.A.S., and JAMES M. WILSON, M.A., F.R.A.S. With Illustrations. 8vo. 21s.

Just ready. 44 pages 8vo. 1s.

CORRECTIONS, TOGETHER WITH NOTES, CRITICISMS, RECENT MEASURES AND DISCOVERIES, &c., &c., TO THE HANDBOOK OF DOUBLE STARS.

THE BIBLIOGRAPHY HAS ALSO BEEN BROUGHT UP TO DATE.

"The volume is one which may be expected to find its way to the shelves of most amateurs and students of astronomy."—*Nature.*

"This is a truly delightful work, and one which will admirably supply a want. Into the hands of abler, more impartial and painstaking observers and compilers than the authors' its preparation could not have fallen."—*The Astronomical Register.*

"Will be welcomed by all who take an interest in the subject of double stars."—*Academy.*

"The names of the authors, noted authorities on the subject treated of, will lead the reader to open this volume with the feeling that in it he has a treasure of lore on the knowledge brought to light in the last hundred years respecting the relative motions of physically connected stars, nor will he be disappointed."—*Athenæum.*

"One of the most valuable additions to the library of the amateur astronomer that has been made for many years. It is full of information of perennial interest to the student and the practical observer, and assuredly ought to be upon the table of every single observatory in the United Kingdom, and of all those in other parts of the world where the language in which it is written is intelligible."—*The English Mechanic.*

"The book is well and clearly printed, and we heartily recommend it to our readers as a most valuable contribution to the literature of double-star astronomy."—*The Observatory.*

MACMILLAN AND CO., LONDON.

SCIENTIFIC WORTHIES.

ENGRAVED BY THE LATE C. H. JEENS.

The following is a list of the Portraits that have appeared in the above Series.

MICHAEL FARADAY.
THOMAS HENRY HUXLEY.
CHARLES DARWIN.
JOHN TYNDALL.
GEORGE GABRIEL STOKES.
SIR CHARLES LYELL.
SIR CHARLES WHEATSTONE.
JEAN BAPTISTE ANDRÉ DUMAS.
SIR WYVILLE THOMSON.
SIR WILLIAM THOMSON.
HERMANN L. F. HELMHOLTZ.
SIR JOSEPH DALTON HOOKER.
WILLIAM HARVEY.
SIR GEORGE B. AIRY.
J. LOUIS R. AGASSIZ.
RICHARD OWEN.

Proof impressions of these, printed on India paper, may be had from the Publishers, price 5s. each, or the Set of 16 Portraits in a Handsome portfolio for £4 5s. carriage paid.

THE PORTFOLIO MAY BE HAD SEPARATELY, PRICE 6s.

NOTE.—ONLY A VERY FEW COMPLETE SETS CAN BE MADE UP.

Cheques and P.O.O.s payable to MACMILLAN & CO.,

OFFICE OF "NATURE," 29, BEDFORD STREET, STRAND.

Messrs. MACMILLAN & CO.'S PUBLICATIONS.

THE STEAM ENGINE AND ITS INVENTORS

A HISTORICAL SKETCH.

By ROBERT L. GALLOWAY,

Mining Engineer.

With numerous Illustrations. Crown 8vo, 10s. 6d.

Eighteenth Annual Publication, Revised after Official Returns.

THE STATESMAN'S YEAR-BOOK FOR 1881.

A Statistical and Historical Annual of the States of the Civilised World.

By FREDK. MARTIN.

Crown 8vo, 10s. 6d.

"The 'Statesman's Year Book' is a handbook for the politician as well as the merchant, and as a statistical and histor annual of the States of the civilised and mercantile world, stands without a rival."—*Times.*

Kamilaroi and Kurnai. Group-Marriage and Relationship, and Marriage by Elopement. Drawn chiefly from the usage of the Australian Aborigines: also the Kurnai tribe—their Cus in Peace and War. By LORIMER FISON, M.A., and A. W. HOWITT, F.G.S. With an Introduction by LEW H. MORGAN, LL.D., Author of "System of Consanguinity," "Ancient Society," &c. Demy 8vo. 15s.

NEW NOVEL BY HENRY JAMES, JUN.

Washington Square: the Pension Beaurepas: a Bundle of Letter 2 vols. Crown 8vo. 21s.

"The very clever sketches . . . . are, on the whole, even more marvellously clever. . . . . There is no doubt that it is gen of the most marked order—genius for painting character."—*Spectator.*

"Mr. James has contrived, as he usually does, to throw a new charm over the old story. . . . Mr. James's style is as plea as ever."—*Athenæum.*

Disturbed Ireland, being the Letters Written during the Winter o 1880-81. By BERNARD H. BECKER, Special Commissioner of the *Daily News*. With Route Maps. Crown 8vo. 6.

"Will be found one of the most trustworthy pictures of the sister island as it is . . . It has, especially at this moment, hig political value."—*Examiner.*

Loukis Laras. Reminiscences of a Chiote Merchant during the Greek War of Independence. Translated from the Greek of D. BIKÉLAS by J. GENNADIUS, late Chargé d'Affaires at the Gre Legation in London. With Introduction on the Rise and Development of Greek Literature. Crown 8vo. 7s. 6d.

The Year's Art: A Concise Epitome of all matters relating to th Arts of PAINTING, SCULPTURE, and ARCHITECTURE, which have occurred during the Year, together with informa respecting the events of the Year 1881. Compiled by MARCUS B. HUISH. Crown 8vo. 2s. 6d.

GOLDEN TREASURY SERIES.—NEW VOLUME.

Essays of Joseph Addison. Chosen and Edited by John Richard Gree M.A., LL.D. 18mo. 4s. 6d.

"This is a most welcome addition to a most excellent series."—*Examiner.*

English Poets: Selections, with Critical Introductions by various Writers and a General Introduction by MATTHEW ARNOLD. Edited by T. H. WARD, M.A. 4 vols., crown 8vo, each 7s.

Vol. I. CHAUCER to DONNE.
Vol II. BEN JONSON to DRYDEN.
Vol. III. ADDISON to BLAKE.
Vol. IV. WORDSWORTH to SYDNEY DOBELL

"An excellent design admirably executed."—*Pall Mall Gazette.*

The Abbott's Farm; or, Practice with Science. By Henry Tanner M.R.A.C., F.C.S., Professor of the Principles of Agriculture in the Royal Agricultural College, Author of "First Princi of Agriculture." Extra fcap. 3s. 6d.

"Prof. Tanner's little book may be read with considerable profit."—*Saturday Review.*

A Short Manual of the History of India, with an Account of India as it Is: the Soil, Climate, and Productions—the People: their Races, Religions, Public Works, and Industries—the C Services and System of Administration. By ROPER LETHBRIDGE, M.A., C.I.E., Press Commissioner with th Government of India, late Scholar of Exeter College, &c. Crown 8vo, with Maps. 5s.

Physics of the Earth's Crust. By Rev. O. Fisher, M.A., F.G.S. Rector of Harlton, &c. 8vo. [Shor

MACMILLAN AND CO., LONDON.

Printed by R. CLAY, SONS, AND TAYLOR, at 7 and 8, Bread Street Hill, Queen Victoria Street, in the City of London, and published by MACMILLAN AND CO., at the Office, 29 and 30, Bedford Street, Covent Garden.—THURSDAY, February 24, 1881.

NATURE

A WEEKLY ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
Of Nature trusts the mind which builds for aye."—WORDSWORTH

NO 592, VOL. 23] THURSDAY, MARCH 3, 1881 [PRICE SIXPENCE

Registered as a Newspaper at the General Post Office.]

[All Rights are Reserved.

THE MASON SCIENCE COLLEGE, BIRMINGHAM.

APPOINTMENT OF ADDITIONAL PROFESSORS.

The Trustees intend from the commencement of the Second Session of the College, on the 1st of October next, to enlarge the Course of Instruction.

The present Chairs are Mathematics (Prof. M. J. M. HILL, M.A. Cantab.), Chemistry (Prof. W. A. TILDEN, D.Sc. Lond., F.R.S.), Physics (Prof. J. H. POYNTING, M.A. Cantab., B.Sc. Lond.), and Biology (Prof. T. W. BRIDGE, M.A. Cantab., F.L.S.). In the ensuing Session Prof. Tilden will add Metallurgy to his Course.

The Trustees invite applications (to be sent to "Mr. G. H. Morley, Secretary, The Mason Science College, Birmingham," on or before the 30th of April next) for the following additional Professorships and Lectureships, viz.:—

1.—A Professor of Physiology, with special reference to the Laws of Health.
2.—A Professor of Geology and Mineralogy.
3.—A Professor of Civil and Mechanical Engineering.
4.—A Professor of Latin and Greek.
5.—A Professor of English Language and Literature.
6.—A Lecturer on the French Language.
7.—A Lecturer on the German Language.

Particulars of the Salaries and Conditions will be sent by the Secretary on application.

By a resolution of the Trustees, Candidates are especially requested to abstain from canvassing.

JOSIAH MASON, Bailiff.
J. GIBBS BLAKE, M.D., Chairman of Trustees.
G. J. JOHNSON, Hon. Sec.

Edmund Street, Birmingham, February 23rd, 1881.

MICROSCOPES.

C. BAKER, of 244, High Holborn, begs to call the attention of the Scientific to his large stock of ACHROMATIC MICROSCOPES, BINOCULAR AND MONOCULAR, at extremely low prices, commencing from £3 10s. OBJECT-GLASSES, APPARATUS, OBJECTS, and MATERIALS of all kinds kept in stock. Catalogues free by post.

C. BAKER being the appointed Agent for ZEISS, SEIBERT, and other first-class GERMAN MAKERS, is now supplying their beautiful productions at very Low Prices. ZEISS's new HOMOGENEOUS and other IMMERSION OBJECTIVES now in stock. Catalogue free by post.

A Large Assortment of SECOND-HAND MICROSCOPES and other Scientific Instruments in stock at the Lowest Prices. Lists of same forwarded on application.

Instruments taken in Exchange.

ESTABLISHED 1765.

BROWNING'S MICROSCOPES.

The MODEL MICROSCOPE, made expressly for class demonstration, has rack and fine adjustments to the body, large stage fitted with universal stage motions, removable stage fittings for apparatus, revolving diaphragm, A or B eye-pieces, and 1-in. and ¼-in. combined objectives of my own manufacture.

PRICE £5 10s. 0d.

Price List of Microscopes Free.

Illustrated Catalogue of Microscopes with 41 Illustrations, 10 whole page engravings, post free, 7 stamps.

JOHN BROWNING,

Optical and Physical Instrument Maker to H.M. Government, the Royal Society, the Royal Observatory,

63, STRAND, LONDON, W.C.

Factory—Southampton Street and Exeter Street, London.

PRIZE MEDAL, 1862. ESTABLISHED 100 YEARS.

Telescopes, Spectroscopes, Opera Glasses, &c., &c.

TRAVELLERS' SCIENTIFIC REQUISITES.



ANEROID BAROMETER with ALTITUDE SCALE, THERMOMETER and COMPASS in Flat Pocket Case, various Forms,

£7 7s. and £8 8s.

Price Lists of Instruments free by post.

NEGRETTI & ZAMBRA,

Opticians and Scientific Instrument Makers

TO HER MAJESTY THE QUEEN,

HOLBORN VIADUCT,

45, CORNHILL, & 122 REGENT STREET, LONDON.

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 48N, Tollington Road, Holloway, London, N.

UNIVERSITY OF LONDON.

NOTICE is Hereby Given, that on WEDNESDAY, 27th of April next, the Senate will proceed to elect Examiners in the following Departments:—

	Examinerships.	*Salaries.* (*Each.*)	*Present Examiners.*
Arts and Science.			
Two in Classics		200*l.*	James S. Reid, Esq., LL.M., M.A. Vacant.
Two in the English Language, Literature, and History		120*l.*	Prof. Henry Morley, LL.D. Prof. A. W. Ward, LL.D., M.A.
Two in the French Language and Literature		100*l.*	B. P. Buisson, Esq., M.A. Prof. Cassal, LL.D.
Two in the German Language and Literature		50*l.*	Prof. Althaus, Ph.D. Prof. Schaible, Ph.D., M.D.
Two in the Hebrew Text of the Old Testament, the Greek Text of the New Testament, the Evidences of the Christian Religion, and Scripture History		50*l.*	R. Lubbock Bensly, Esq., M.A. Rev. W. F. Moulton, D.D., M.A.
Two in Mental and Moral Science		80*l.*	James Sully, Esq., M.A. Vacant.
Two in Political Economy		30*l.*	Herbert S. Foxwell, Esq., M.A. Prof. J. E. Thorold Rogers, M.A., M.P.
Two in Mathematics and Natural Philosophy		200*l.*	J. Hopkinson, Esq., D.Sc., M.A., F.R.S. B. Williamson, Esq., M.A., F.R.S.
Two in Experimental Philosophy		120*l.*	Prof. W. G. Adams, M.A., F.R.S. William Garnett, Esq., M.A.
Two in Chemistry		200*l.*	Prof. Debus, Ph.D., F.R.S. Prof. Dewar, M.A., F.R.S.
Two in Botany and Vegetable Physiology		75*l.*	W. T. Thiselton Dyer, Esq., M.A., F.R.S. Sydney H. Vines, Esq., D.Sc., M.A.
Two in Comparative Anatomy and Zoology		100*l.*	Prof. E. Ray Lankester, M.A., F.R.S. Prof. A. Milnes Marshall, D.Sc., M.A.
Two in Geology and Palæontology		75*l.*	Prof. P. M. Duncan, M.B., F.R.S. R. Davies Roberts, Esq., D.Sc., M.A.
Laws.			
Two in Jurisprudence, Roman Law, Principles of Legislation, and International Law		100*l.*	Prof. W. A. Hunter, M.A. T. Waraker, Esq., LL.D.
Two in Equity and Real Property Law		50*l.*	W. H. G. Bagshawe, Esq., B.A., Q.C. J. M. Solomon, Esq., M.A.
Two in Common Law and Law and Principles of Evidence		50*l.*	Arthur Charles, Esq., B.A., Q.C. Vacant.
Two in Constitutional History of England		25*l.*	Rev. Hereford B. George, M.A. Prof. Edmund Robertson, M.A.
Medicine.			
Two in Medicine		150*l.*	W. H. Dickinson, Esq., M.D. C. Hilton Fagge, Esq., M.D.
Two in Surgery		150*l.*	Prof. John Wood, F.R.S. Vacant.
Two in Anatomy		100*l.*	Prof. Redfern, M.D. Vacant.
Two in Physiology		100*l.*	P. H. Pye-Smith, Esq., M.D., B.A. Vacant.
Two in Obstetric Medicine		75*l.*	J. M. Duncan, Esq., M.D., LL.D. Henry Gervis, Esq., M.D.
Two in Materia Medica and Pharmaceutical Chemistry		75*l.*	Prof. E. B. Baxter, M.D. Prof. F. T. Roberts, M.D., B.Sc.
Two in Forensic Medicine		50*l.*	Thomas Stevenson, Esq., M.D. Vacant.

The Examiners above named are re-eligible, and intend to offer themselves for re-election.

Candidates must send in their names to the Registrar, with any attestation of their qualifications they may think desirable, on or before Tuesday, March 29th. It is particularly desired by the Senate that no personal application of any kind be made to its individual Members.

By order of the Senate,

University of London, Burlington Gardens, W., March 1st, 1881.

ARTHUR MILMAN, M.A., *Registrar.*

INSTRUCTION IN MATHEMATICS.—

Youths or Adults attended at their Residence, on Reasonable Terms, by a M.A. of Cambridge. Unquestionable references if required.—Address, by letter, O. P., Post Office, Turnham Green.

UNIVERSITY OF LONDON MATRICULATION, JUNE, 1881.

Special Classes for this Examination will be formed at St. Thomas's Hospital Medical School, Albert Embankment, to commence on March 1st. The Special Classes for the Preliminary Scientific and 1st M[illegible] tions have now commenced. Full particulars can be o[btained] Secretary, Dr. GILLESPIE.

LIVING SPECIMENS FOR THE MICROSCOPE.

THOMAS BOLTON, NATURALISTS' and MICROSCOPISTS' STUDIO, 57, NEWHALL STREET, BIRMINGHAM.

T. B. has last week sent to his subscribers Embryo Mussels, *Anodon cygneus*, with Drawing and Description. (Specimens Mounted for Polarised Light, 1*s.* 2*d.*) He has also sent out Young American Trout and the Ova of Great Lake Trout, and of Salmon; also Lophopus, Marine Polyzoa, and Hydrozoa, Argulus, Asellus, Gammarus, Volvox, Batrachospermum, &c.

Weekly announcements will be made in this place of organisms T. B. is supplying.

Specimen Tube, One Shilling, post-free.

Twenty-six Tubes in course of Six Months for Subscription of £1 1s.

Price List of Specimens on application, with stamped addressed envelope.

Portfolio of Drawings, No. 4, One Shilling.

MATRICULATION EXAMINATION.

UNIVERSITY OF LONDON.

Instruction in all the Subjects of the above Examination is given at Guy's Hospital.

The Classes for the June Examination will commence on MONDAY, March 21st. The Classes are not confined to Students of the Hospital.

For further particulars address the DEAN, Guy's Hospital, S.E.

MATRICULATION of the UNIVERSITY OF LONDON.

ST. BARTHOLOMEW'S HOSPITAL AND COLLEGE.

A CLASS in all the Subjects of this Examination will begin on MONDAY, March 7, and continue till the Examination in July. The Class is not confined to Students of the Hospital.

For particulars apply to the WARDEN of the College, St. Bartholomew's Hospital, London, E.C.

A Handbook is forwarded on application.

SOLAR PHYSICS.

The following COURSE of LECTURES will be given by Members of the Committee on SOLAR PHYSICS, appointed by the Lords of the Committee of Council on Education:—

An Introductory Lecture. By Prof. STOKES, Sec. R.S. 6th April, 1881.

A Lecture on the Practical Importance of Studying the Influence of the Sun on Terrestrial Phenomena. By Lieut.-General STRACHEY, R.E., C.S.I., F.R.S. 8th April.

Two Lectures on the Connection between Solar and Terrestrial Phenomena. By Prof. BALFOUR STEWART, F.R.S. 27th and 29th April.

Six Lectures on Spectroscopy in Relation to Solar Chemistry. By Mr. J. NORMAN LOCKYER, F.R.S. 4th, 6th, 11th, 13th, 18th, and 20th May.

Three Lectures on the Photography of the Infra-red of the Spectrum in its Application to Solar Physics. By Capt. ABNEY, R.E., F.R.S. 25th and 27th May, and 1st June.

The LECTURES will be delivered in the Lecture Theatre of the South Kensington Museum at 4 p.m. on the days stated above.

Admission will be by Tickets, which may be obtained, as far as there is room, on application by Letter to the SECRETARY, Science and Art Department, South Kensington, S.W.

ROYAL AGRICULTURAL SOCIETY OF ENGLAND.

AGRICULTURAL EDUCATION.

The Examination of Candidates for the Society's Prizes and Certificates, including the Life Membership of the Society, will take place in the week commencing TUESDAY, May 10th, 1881.

Copies of the Form of Entry, which is required to be sent in by April 1, 1881, may be had on application to

H. M. JENKINS, Secretary.

12, Hanover Square, London, W.

SCIENCE CLUB, 4, SAVILE ROW, W.

—This Club is OPEN for the use of Members. Annual Subscription—Town Members, £4 4*s.*; Country Members, £3 3*s.*—For further information apply to the HONORARY SECRETARY, at the Club House.

FOLLOWING BOOKS WANTED:—

Hewitson's "Butterflies," 5 vols., complete.
Stainton, "Tineæ."
Donovan, "Insectes de la nouvelle Hollande."
Hernch Schäffer, "Europäische Schmetterl.nge."
Hebner's We[illegible] [illegible]nge.

Address E. E., NATURE [illegible] Street, Strand.

WANTED.—B[illegible] ES & MOTHS

from India and Africa [illegible]TURE Office, 29 Bedford Street, Strand.

FOR SALE.—[illegible] TION OF

North-American BEETL[illegible] Unique Specimens —Address A. Z., NATURE

MINERALOGY AND GEOLOGY.

MAGNIFICENT DERBYSHIRE FLUOR SPAR VASE. Height, with Pedestal, 5ft. 8in.; Diameter 13½in. This is, with one exception, the finest vase of the kind known, the vein having been worked out some forty years ago.

FINE PINK APOPHYLITE, EISENROSE, CONNELLITE, CALC SPAR, BARYTA, FAHLERZ, LIBETHENITES.

COLLECTIONS FOR STUDENTS, from £2 2s. COLLECTIONS FOR BEGINNERS, from 4s. BLOWPIPE CASES AND APPARATUS.

PRIVATE LESSONS AND EVENING CLASSES.

Catalogues free.

SAMUEL HENSON,

277 (*Late* 113*a*), STRAND, LONDON, W.C.

EVERY BOY A GEOLOGIST.

Now ready, and highly recommended, complete, price 7s. 6*d*.

This admirable little Work and most extraordinary Cabinet of wonderfully well-selected Natural Specimens, together with other Geological Preparations, and a powerful Lens, are calculated to start a boy thinking till he has mastered for himself no ordinary knowledge of the formation of the Earth's Crust.—THOMAS J. DOWNING, GEOLOGIST, &c., 38, Whiskin Street, London, E.C.—Catalogues free.

GEOLOGY AND MINERALOGY.

Special Collections for Teachers and Students, used with success by all Lecturers and Teachers of Geology in Great Britain. Obtained Gold and Bronze Medals at Sydney Exhibition, 1879, also in London, 1862, and Paris, 1867.

200 Specimens in Cabinet ...	...	...	...	£2 2 0
100 ditto	ditto ...	...	...	1 1 0
50 ditto	ditto ...	...	...	0 10 6

New Lists of Collections, Apparatus, &c., now ready, and free on application to

JAMES R. GREGORY'S
Geological Museum and Repository,
88, CHARLOTTE STREET, FITZROY SQUARE.

GEOLOGY.—In the Preface to the STUDENT'S ELEMENTS of GEOLOGY, by Lyell, 1874, he says: "As it is impossible to enable the reader to recognise rocks and minerals at sight by aid of verbal descriptions or figures, he will do well to obtain a well-arranged collection of specimens, such as may be procured from Mr. TENNANT (149, Strand), Teacher of Mineralogy at King's College, London." These Collections are supplied on the following terms, in plain Mahogany Cabinets:—

100 Specimens, in Cabinet, with 3 Trays ...	...	...	£2	2 0
200 Specimens, in Cabinet, with 5 Trays ...	...	...	5	5 0
300 Specimens, in Cabinet, with 9 Drawers	...	...	10	10 0
400 Specimens, in Cabinet, with 13 Drawers	...	...	21	0 0

More extensive Collections at 50 to 5,000 Guineas each.

MUSEUMS AND COLLECTORS.

MR. DAMON, of WEYMOUTH, will forward an abridged Catalogue of his Collections in Natural History Objects, including RECENT SHELLS (Foreign and British), FOSSIL REMAINS, MINERALS, ROCKS, MARINE ZOOLOGY, &c., &c., &c.

MICROSCOPIC SPECIALITIES.

SECTION LAVA SURFACE-FLOW, MOUNT VESUVIUS POLAR, 1s. 9*d*. post free.

SECTION PALATE of the EAGLE RAY, Opaque and Transparent, 2s. 3*d*. post free.

Catalogue of 32 *Pages free on application to*

JOHN T. NORMAN,

178, CITY ROAD, E.C.

DIAMONDS IN MATRIX.

R. C. NOCKOLD, Diamond and Oriental Stone Cutter and Dealer, has for sale Specimens of the above; also Cut Precious Stones in all Colours.

Precious Stones valued and bought.

18, FRITH STREET, SOHO, W.

ROYAL POLYTECHNIC.—CLASSES for the Preparation of Students for University Examinations, under the direction of EDWARD B. AVELING, D.Sc., F.L.S. London University Matriculation, 1st and 2nd B.Sc., Preliminary Scientific M.B., Botany, Physiology, Chemistry. All the work practical.

THE "HANSA"

Published since 1864 in Hamburg, is the only independent professional paper in Germany, dedicated exclusively to Maritime Objects. Essays, Critiques, Reviews, Reports, Advertisements. Strict eye kept upon the development of Maritime Affairs in every respect. Every second Sunday one Number in 4to at least; frequent supplements and drawings. Subscription at any time; preceding numbers of the year furnished subsequently. Price 12s. for twelve months. Advertisements 4*d*. a line, widely spread by this paper; considerable abatement for 3, 6, 12 months' insertion. Business Office: Aug. Meyer and Dieckmann, Hamburg, Alterwall 28. Edited by W. v. FREEDEN, M.R., Hamburg, Alexander Street, 8.

THE CHEMICAL NEWS AND JOURNAL OF PHYSICAL SCIENCE.

EDITED BY W. CROOKES, F.R.S., &c.

Published every Friday. Price 4*d*.

No. 1110 (March 4) contains:—Upon the Invariable Production, not only of Ozone and Hydrogen Peroxide, but also of Ammonium Nitrate, in the Ozonation of Purified Air by Moist Phosphorus, by Prof. A. R. Leeds.—Aräometric Method for the Estimation of Fat in Milk, by Dr. F. Soxhlet.—Determination of Basic Cinder and Oxides in Manufactured Iron, by W. Bettel.—Report on the London Water Supply.—Proceedings of Societies.—Notices of Books.—Correspondence.—Chemical Notices from Foreign Sources.—Notes and Queries, &c., &c.

London: Boy Court, Ludgate Hill, E.C.

Chaque Samedi 16 pages grand in-8°, 2 colonnes

REVUE HEBDOMADAIRE

Scientifique, illustrée, spéciale, seul journal tenant les lecteurs au courant de tous les détails de l'Exposition universelle d'électricité, organe indépendant des exposants

RÉDACTEUR EN CHEF : W. de FONVIELLE

E. de CLISSON : DIRECTEUR

Un numéro, **40** *centimes. — L'année*, **18** *francs. Union postale* **20** *francs.*

PARIS, 16, rue du Croissant, PARIS

Envoi de numéros spécimens gratis sur demande.

In unserem Verlage erscheint:

DER NATURFORSCHER.

Wochenblatt zur Verbreitung der Fortschritte in den Naturwissenschaften.

Herausgegeben von Dr. WILHELM SKLAREK.

Wochentlich 1—1½ Bgn. in 4°.

Preis vierteljährlich 4 Mk.

Die nunmehr ihren XIV. Jahrgang beginnende Zeitschrift hat bei Allen, welche sich mit Naturwissenschaften beschäftigen, grossen Beifall gefunden.

Probenummern sind durch jede Buchhandlung zu erhalten.

Berlin, S.-W., 77, Charlottenstr.

FERD. DÜMMLER'S VERLAGSBUCHHANDLUN
(Harrwitz & Gossmann.)

On the 1st of every Month, price Sixpence.

THE ENTOMOLOGIST:

AN ILLUSTRATED JOURNAL OF BRITISH ENTOMOLOGY.

Edited by JOHN T. CARRINGTON,
With the Assistance of

FREDERICK BOND, F.Z.S. | JOHN A. POWER, M.D.
EDWARD A. FITCH, F.L.S. | J. JENNER WEIR, F.L.S.
F. BUCHANAN WHITE, M.D.

Contains Articles by well-known Entomologists on all branches of the Science; on Insects injurious or beneficial to Farm or Garden; Notes on Habits, Life-Histories; occurrence of Rarities, &c.; there are monthly lists of Duplicates and Desiderata.

Numerous WOODCUT ILLUSTRATIONS, to the printing of which especial attention is given, and occasional LITHOGRAPHED and CHROMO-LITHOGRAPHED PLATES.

SIMPKIN, MARSHALL, & CO., Stationers' Hall Court.

NORTH BRITISH AGRICULTURIST

is the only Agricultural Journal in Scotland, and circulates extensively amongst Landed Proprietors, Factors, Farmers, Farm-bailiffs, and others interested in the management of landed property throughout Scotland and the Northern Counties of England.

The AGRICULTURIST has also a very considerable circulation on the Continent of Europe, America, Australia, and the Colonies.

The AGRICULTURIST is published every Wednesday afternoon in time for the evening mails, and contains Reports of all the principal British and Irish Markets of the week, besides Telegraphic Reports of those held on the day of publication.

The Veterinary Department is edited by one of the leading Veterinarians in the country, and is invaluable to the breeder and feeder as a guide to the rearing of animals, and their treatment when labouring under disease.

Full Reports are given of the Meetings of the Royal Agricultural Society of England, the Royal Agricultural Society of Ireland, the Highland and Agricultural Society of Scotland, the Scottish Chamber of Agriculture, and all the principal Agricultural Associations throughout Great Britain and Ireland.

For Advertisers addressing themselves to Farmers a better medium does not exist

Price 3*d*. By post 3½*d*. Annual Subscription, payable in advance, 14s.

Office—377, High Street, Edinburgh.

Post-Office Orders payable to Charles Anderson, Jun., Edinburgh.

ESTABLISHED 1843.

FOR SALE.

A MAGNIFICENT DERBYSHIRE

FLUOR SPAR VASE.

THE OLD BULL BEEF VARIETY,

HEIGHT WITH WHITE FLUOR AND BLACK MARBLE PEDESTAL 2 FEET 8 INCHES. DIAMETER 13½ INCHES.

SAMUEL HENSON, *Mineralogist, &c.*, 277 (Late 113A), Strand, London, W.C.

One of the mountain-tops of Time
Is left in Africa to climb!

Now ready, in 2 vols., imperial 8vo, cloth, price 36s.

A BOOK OF THE BEGINNINGS. By GERALD MASSEY. Beautifully printed, on special paper, by Clay, Sons, and Taylor.

Containing an attempt to recover and reconstitute the lost Origines of the Myths and Mysteries, Types and Symbols, Religion and Language, with Egypt for the Mouthpiece and Africa as the Birthplace.

CONTENTS OF VOL. I.—Egypt—Comparative Vocabulary of English and Egyptian—Hieroglyphics in Britain—Egyptian Origines in Words—Egyptian Water-Names—Egyptian Names of Personages—British Symbolical Customs identified as Egyptian—Egyptian Deities in the British Isles—Place-Names and the Record of the Stones—Egyptian Type-Names of the People.

CONTENTS OF VOL. II.—Comparative Vocabulary of Hebrew and Egyptian—Hebrew Cruxes, with Egyptian Illustrations—Egyptian Origines in the Hebrew Scriptures, Religion, Language, and Letters—Phenomenal Origin of Jehovah-Elohim and Shadai—Egyptian Origin of the Exodus—Moses and Joshua, or the Two Lion-Gods of Egypt—An Egyptian Dynasty of Hebrew Deities, identified from the Monuments—Egyptian Origin of the Jews, traced from the Monuments—Comparative Vocabulary of Akkado-Assyrian and Egyptian—Egyptian Origines in the Akkadian Mythology—Comparative Vocabulary of Maori and Egyptian—African Origines of the Maori—The Roots in Africa beyond Egypt.

WILLIAMS & NORGATE, 14, Henrietta Street, Covent Garden, London; and 20, South Frederick Street, Edinburgh.

Just Published, demy 8vo, price 1s.

The WEATHER of 1880 as OBSERVED in the NEIGHBOURHOOD of LONDON, and compared in all respects with that of an Average Year. By EDWARD MAWLEY, F.M.S., Hon. Sec. National Rose Society. With Tables of Daily Observations and a Diagram.

London: BEMROSE & SONS, 23, Old Bailey.

NEW WORK BY MR. MIVART, F.R.S.

Next Week, with 200 Illustrations, medium 8vo.

The CAT. An Introduction to the Study of Back-boned Animals, especially Mammals. By ST. GEORGE MIVART, F.R.S., Author of "Lessons from Nature," &c., &c., Vice-President of the Linnean Society and of the Zoological Society.

JOHN MURRAY, Albemarle Street.

Just Published, demy 8vo, cloth, with Chart, price 15s.

ON SOME PROPERTIES OF THE EARTH.

By O. REICHENBACH.

London: WERTHEIMER, LEA, & CO., Circus Place, London Wall.

Just Published, price 2s. 6d.

An ELEMENTARY COURSE of PRACTICAL PHYSICS. By A. M. WORTHINGTON, M.A., F.R.A.S., Assistant Master at Clifton College.

RIVINGTONS, Waterloo Place, Pall Mall, London.

THE BREWERS' GUARDIAN:

A Fortnightly Paper devoted to the Protection of Brewers' Interests, Licensing, Legal, and Parliamentary Matters.

REVIEW OF THE MALT AND HOP TRADES; AND WINE AND SPIRIT TRADE RECORD.

The Organ of the Country Brewers.

"The Brewers' Guardian" is published on the evenings of every alternate Tuesday, and is the only journal officially connected with brewing interests. Subscription, 16s. 6d. per annum, post free, dating from any quarter-day. Single Copies 1s. each. Registered for transmission abroad.

Offices—5, Bond Court, Walbrook, London, E.C.

On the 1st of every Month.

TRIMEN'S JOURNAL OF BOTANY,

BRITISH AND FOREIGN.

New Series. Edited by JAMES BRITTEN, F.L.S., British Museum.

CONTENTS.—Original Articles by leading Botanists.—Extracts, and Notices of Books and Memoirs.—Articles in Journals.—Botanical News.—Proceedings of Societies.

Price 1s. 3d. Subscription for One Year, payable in advance, 12s.

London: WEST, NEWMAN, & CO., 54, Hatton Garden, E.C.

PRICE 1s. MONTHLY.

MACMILLAN'S MAGAZINE

FOR MARCH, 1881.

CONTENTS.

The Portrait of a Lady. By Henry James, Jun. Chapters XXI.—XXIV.
Christmas and Ancestor Worship in the Black Mountain. By Arthur J. Evans. Part III.
Byron. By Matthew Arnold.
Connemara. By Robert J. Martin.
The Penny Press. By Francis Hitchman.
On a Recent Criticism of Mr. Swinburne's. By Alfred Austin.

MACMILLAN & CO., LONDON.

PRICE 1s.

ST. JAMES'S MAGAZINE.

MARCH, 1881.

Contents.

KATHARINE JOHNSTON. By Mrs. FORBES-ROBERTSON. Chapters IX., X.
WILL THE DRAMA REVIVE? By a DRAMATIC CRITIC.
"SOCIETY SMALL-TALK." By JENNETT HUMPHREYS.
A MORNING PERFORMANCE AT THE LYCEUM, MR. TENNYSON'S "CUP."
GUILTY AND NOT GUILTY. A Novel from the German. By MARIE SOPHIE SCHWARTZ. Chapters XXI., XXII., XXIII.
LOST IN LONDON. By WM. A. GIBBS.
AUSTRALIAN CULTURE. II. By A. H. KEANE.
NOTICES OF BOOKS.

London: GRATTAN, MARSHALL, & CO., Paternoster Row, E.C.

LA SEMAINE FRANÇAISE: a Weekly Newspaper and Review in the French Language. Politics, Literature, Science, Art, Varieties, Notes. Price 3d., through booksellers, and at the railway bookstalls Office, 37, Southampton Street, Strand, W.C.

LA SEMAINE FRANÇAISE: Journal Français pour l'Angleterre: Politique, Littérature, Sciences, Arts, Variétés, Nouvelles, et Notes. Un exemplaire par la poste, 3½d., en timbres poste Abonnement franco par la poste—un an, 15s. 2d.; six mois, 7s. 7d. Prix 3d., chez tous les libraires et aux gares des chemins de fer. On s'abonne aux bureaux, 37, Southampton Street, Strand, Londres, W.C.

LA SEMAINE FRANÇAISE.—"'La Semaine Française' has been brought out in London for the benefit of those English readers who may wish to study contemporary French from all points of view, instead of confining their reading to one particular Gallic print. It certainly merits success."—*Graphic.*

LA SEMAINE FRANÇAISE.—"The numbers before us are full of good things. . . . . It will be far better for most than any one of the best papers published in Paris itself. We are much pleased with the character of it, and believe it will be highly valued in all those many households where French is cultivated. The printing is very well done."—*Queen.*

TERMS OF SUBSCRIPTION:—							s.	d.
Three months	...	...	...	...	...	...	3	10
Six "	...	...	...	...	...	...	7	7
Twelve "	...	...	...	...	...	...	15	2

P.O.O. payable to T. SPANSWICK, at King Street, Covent Garden, W.C. Publishing Office, 37, Southampton Street, Strand, W.C.

WANTED.—NATURE, No. 513.—Address A. B. M., care of NATURE, 29, Bedford Street, Strand.

POTTERY.

A SERIES OF URNS, &c.,

INCLUDING

BRITISH, ROMAN, SCANDINAVIAN, PERUVIAN.

To be Sold at Extremely Low Prices, the Owner being desirous of immediately parting with them.

BRYCE-WRIGHT,

90, GREAT RUSSELL STREET, LONDON, W.C.

THURSDAY, MARCH 3, 1881

NATURAL CONDITIONS AND ANIMAL LIFE

The Natural Conditions of Existence as they Affect Animal Life. By Karl Semper, Professor in the University of Würzburg. International Scientific Series. (London: Kegan Paul and Co., 1881.)

THIS is in many respects one of the most interesting contributions to zoological literature which has appeared for some time. The author is well known as an accomplished anatomist and microscopist who, after spending some years in exploring the fauna of the Philippine and neighbouring islands, returned to Europe, and having been appointed to the Chair of Zoology in Würzburg, set himself to work at the morphological problems which so largely occupy at present the attention of anatomists. His most remarkable productions in this department have been his speculations and observations on the segmentation of animals and on the origin of the vertebrate kidney. But Prof. Semper has the advantage of being something more than an anatomist; as a traveller and one who has seen and studied life under most varied conditions, he has thought much and collected many facts bearing upon the problem of the influence of changed conditions of life in modifying the structure of animals submitted to those conditions.

With the leading theoretical consideration advanced by Prof. Semper no naturalist who knows the history of evolutional theory will agree, but the large collection of well-described and well-illustrated facts for which he claims attention in consequence of his theoretical preconceptions, are none the less interesting. The book has the great merit of being one which will be found equally readable by the professed zoologist and by the general reader.

Prof. Semper, whilst accepting the doctrine of the origin of new forms of life by the natural selection of fittest varieties of pre-existing forms, is unable to conceive of the "fittest varieties" in question, being such slightly divergent forms as are normally to be found in the offspring of all parents. Though he does not explicitly deny the physiological importance of even such minute variations as are not readily perceived by the human eye, and consequently does not openly controvert Mr. Darwin's theory to the effect that such of these minute variations as are fitted to given conditions of existence, are perpetuated and intensified by the survival of those animals in which they occur, and the failure and death of those in which they do not occur, yet Prof. Semper is among those who look for a more rapid and conspicuous method of the production of new species than that taught by pure Darwinism. He thinks that Mr. Darwin has overlooked or underrated the importance of "*directly-transforming* agents." He is no doubt aware that it is equally possible to over-estimate the importance of such action, and that this was done by Mr. Darwin's predecessors. Accordingly he examines in the volume before us such cases as may tend to give evidence on the subject.

Such cases are to be found when an animal living upon special food, or in given temperature, or light, or in water (still or running, fresh or saline), or air (dry or moist, still or breezy), or in isolation, or as parasite, is subjected to a change in those conditions either by natural processes or by experiment. A large series of natural instances are afforded by pairs of representative species of one genus, the one living under one set of conditions, the other under conditions in which the factor, the influence of which is sought, is removed or altered. Very few experiments, as Prof. Semper remarks, have been made upon this subject, but some of remarkable interest are cited.

The result of the examination of the instances which have been gathered together in this volume is *not* such as to lead to the conclusion that directly transforming agents play an important part in the production of new species. "Changed conditions," Mr. Darwin has said, "induce an almost indefinite amount of fluctuating variability, by which the whole organism is rendered in some degree plastic," and it is to the non-significant variations so produced which are selected by survival and fixed by heredity that new forms are due, and not to those *direct* adaptations effected in the individual by changed conditions, which are remarkably rare, and moreover, as Prof. Semper recognises (p. 38), are not transmitted, as a rule, to offspring. In order to establish his point Prof. Semper should have been able to give us, firstly, numerous instances of change of structure in the individual brought about in adaptation to a change in that individual's conditions of life. He produces very few, whilst the most striking and numerous facts which he records are instances of physiological adaptation to or toleration of new conditions *without any corresponding change of structure.* Secondly, he should have been able to give instances of the transmission to offspring of peculiarities acquired by the parent by undoubted action of the environment on the individual parent. Such instances are excessively rare, though a few are on record; but none are cited by Prof. Semper, and indeed the evidence as at present before us is such as to warrant the conclusion that such transmission cannot be in any way an important factor in the production of new races.

In his concluding paragraph (p. 405) Prof. Semper states that "there is a universal difficulty of deciding whether a modification which has taken place is to be ascribed to some direct determining and modifying cause, or to the enhancing of a previously modified character which is frequently connected with selection," and then deprecates the habit of theoretical explanations from general propositions. He holds apparently that we are not to seek an explanation of such modifications in those truths of heredity and adaptation, of variation and selection, which have been actually demonstrated and established by Mr. Darwin, but must, if we would behave as right-minded philosophers, keep before us the possibility of these modifications being due to—what? Not to a cause which has been shown to be necessarily or even usually at work, as have those to which Mr. Darwin points, but to a cause which has always proved illusory, namely, the "directly-transforming" action of the environment. It was because they appealed to this cause and could not show that it had a real existence that the "transformists" of the beginning of this century failed, where Mr. Darwin, appealing to another cause which he showed was an existing cause, has succeeded. Prof.

Semper's contribution to the subject does not tend to alter the low estimate which has been formed of the efficiency of directly-transforming agents, nor to justify the "final warning" which closes his book. It is then as a repertory of physiological facts of a kind usually neglected both by the professed physiologist and by the professed zoologist that this book will be found of value, not as the expository of new or of old theory.

After an introduction in which, amongst others, some interesting observations on the casting of the skin of reptiles and of crayfish are given with illustrative cuts, we find a chapter on "Food and its Influence." The variety of mineral and organic substances which constitute the food of animals is noted, and monophagous and polyphagous animals distinguished; curious adaptations to a special food such as that of egg-eating snakes, with their gastric teeth formed by processes of the vertebræ, are cited, and some remarkable examples of change of diet naturally occurring in a species *without any modification of structure*, *e.g.* the New Zealand parrot, which used to feed on the juices of plants and flowers, but now sucks the blood of sheep. Again, horses eating pigeons, vegetivorous snails (Lymnæus) eating young newts, crocodiles, some eating men, and others of the same species not prone to the habit. The only well-established instances of modification of structure caused by change of food are due to John Hunter, who fed a gull for a year on grain, and so hardened the inner coat of the bird's stomach as to make it resemble the gizzard of a pigeon; whilst Dr. Holmgren is cited as having obtained the converse result by feeding a pigeon on meat. The change brought about here is, however, not strictly speaking a change of structure, but rather a modification of the chemical activity of the gastric epithelium.

Many instances of wide difference of diet in closely allied species of animals not accompanied by any corresponding difference of structure are given in the text and in the valuable notes at the end of the book.

The influence of light is next discussed, and we have some statements as to the difference in their relation to light, of plants and animals. Prof. Semper does not admit the presence of chlorophyll in any animal, and goes so far as to say that the similarity of the spectrum of the solution of the green pigment of an animal with that of chlorophyll would not prove the pigment to be chlorophyll. If by "similarity" exact correspondence is meant, we should differ from him; but it is no doubt true that further exact observation is needed of those cases among invertebrate animals in which chlorophyll has been supposed to be present.

Semper holds that there is a high degree of probability in the view that the green-coloured bodies present in some lower animals in such abundance are really parasitic Algæ like the gonidia of lichens. As an argument in favour of this view he adduces Max Schultze's observation that the "chlorophyll-bodies" of the worm *Vortex viridis* divide and multiply spontaneously, which he states (in opposition to the generally received observations of Nägeli and the statements of his colleague Sachs) the chlorophyll bodies of plants do not. It would be interesting if this should prove to be the case, and if Prof. Semper should be destined to reform our notions of Vegetable histology among other things.

In a note Semper attacks Paul Bert for saying that "Infusoria containing green matter decompose carbonic acid in the same way as vegetable cells." The French physiologist is well within the facts, for Priestley's green matter was the Flagellate *Euglena viridis*.

It is necessary to point out that it is by no means proved by Cienkowski's observations that the yellow cells of Radiolaria are parasitic one-celled Algæ, as Semper assumes, though it is possible that such is their nature.

Light affects animals mostly through the eye only, and its intensity undoubtedly has a modifying influence upon that organ; but whether the degeneration of the eye in cave animals and deep-sea Fishes and Crustacea is due *directly* to disuse in any instance or to altered selection and heredity, is not clear. Many important facts and some good drawings bearing on this matter are given. Dr. Hagen informed the author that in all the species of cave-beetles of the genus Machærites the females *only* are blind, while the males have well-developed eyes, although both live together in total darkness, whilst it is well known that many blind animals, *e.g.* certain Mollusks, Crustacea, and Worms, live in bright daylight.

Facts are cited showing that the colours of animals are not developed by or dependent on light, whilst the change of colour effected by cuttle-fish, fishes, and Amphibia when light acts on the eye are discussed at length, and the researches of Lister and of Pouchet cited. Prof. Semper, in common with other naturalists, explains the difficulty presented by the colouration of some animals such as those which live in the dark (many marine polyps and worms), by the assumption that the pigment is the inevitable secondary product of some indispensable physiological process. The same explanation is applied to the phosphorescent material of many marine organisms, which is apparently useless or even injurious to the animals which produce it.

Temperature affords subject-matter for a chapter, abounding in important records of fact, which are, it must be admitted, quite antagonistic to the notion that variations in the environment in this respect can directly produce *adaptative* change of structure. The most remarkable instance of temperature effecting a change of structure is that quoted from Weissman, who, by artificially lowering the temperature, succeeded in rearing *Vanessa levana* from the eggs of *Vanessa prorsa-levana*, the two supposed "species," being only winter and summer varieties of one. But here, though the colouring is different in the two varieties, there is no adaptational character about it, nor a transmission of the changed colouring to offspring.

A number of facts are cited as to the supposed change of colour of Arctic animals in winter, but the conclusion seems to be that no such change occurs. Facts establishing the possibility of freezing whole fish and other animals are given, and other facts showing that 5° below 0° C. kills the tissues of such animals as frogs, and may thus cause death to the whole animal. Important researches of Horvath are cited, showing that the Ground-squirrel (Spermophilus), the temperature of whose body is in summer like that of man, about 38° C., can, during its winter sleep, sink to as low a temperature as 2° C. without injury; its body, in fact has, at this period, the same temperature as that of the surrounding air. The

rabbit, on the other hand, is infallibly killed when the temperature of its body is reduced to 15° C. The glacier flea (*Desoria glacialis*, one of the Thysanura) is cited as an example of an animal taking up by preference, as it were, a permanently cold life-arena; whilst as examples of endurance of high temperatures we have Crustaceans found in hot springs of 60° C., and fish (Sparus) in hot springs of 75° C. The acclimatisation of Mr. Buxton's parrots in Norfolk is described at length, and amongst many other details of the kind concerning the influence of temperature on the spawning and hatching of eggs of various animals, the fact is recorded that at 10°·5 C. the common frog requires 235 days to pass from the egg through complete metamorphosis, whilst at 15°·5 C. only 73 days are required. "Nothing in the Philippine Islands struck me so much," Prof. Semper writes, "as to observe that there all true periodicity had disappeared even from insects, land mollusks, and other land animals; I could at all times find eggs, larvæ, and propagating individuals, in winter as well as in summer." An important reflection in this connection is the following:—"It is generally assumed that we are justified in attributing to extinct animals a mode of life analogous to that of the nearest related surviving forms; . . . as soon as we reach the deeper strata, and the identity of the species with those now living ceases, our right to construct a theory of the climate of past epochs by a comparison of fossil and living species, absolutely disappears." How far, it may well be asked, is this true when plants are substituted for animals?

In a chapter on "The Influence of Stagnant Water" we have a large series of interesting facts and records of experiment under the headings "Freshwater Animals that Live in the Sea" and "Marine Animals in Fresh Water." In both these categories we find a number of animals, whilst as a matter of experiment it is found that, though very few animals will endure *sudden* transference from fresh to saline water, or *vice versâ*, yet a large number will tolerate the change if it be accomplished by slow degrees, whilst others will not endure it, however brought about. The same effect of gradation is noted with regard to change of temperature. But in neither the one case nor the other is Prof. Semper able to cite an instance which tends to favour the view that direct modification of structure is produced by such changes of life conditions.

The instances cited, though not so distinguished by Prof. Semper, may be divided into those afforded by certain species living in one kind of water (fresh or salt), whilst the other species of the genus live in the other kind of water; and secondly, those afforded by exceptional individuals naturally found in one kind of water, whilst normally the individuals of the *same* species occur in the other kind of water. Results derived from the experiment of gradual transference from one kind of water to the other would form a subdivision under this second head. The rare instances of animals living in brine may also be classified in the same manner. Many species allied to river-worms and earth-worms (Oligochæta) are now known to occur in the sea; also Crustacea allied to fresh-water forms. Sea-insects and sea-spiders (like the common fresh-water diving spider) are cited in the valuable list of references given at the end of Prof. Semper's book, and such characteristically fresh-water mollusks as Cyclas, Unio, and Anodonta (found living in the Livonian Gulf with Telluria and Venus). Paludina and Neritina are found living in the Caspian with Mytilus and Cardium: *Planorbis glaber*, in 1415 fathoms in the Mediterranean. Many freshwater species of fishes are recorded from marine waters, and the whole group of sea-snakes form an example in point.

Of marine animals living in fresh-water we have, besides the polyp, *Cordylophora lacustris* (of which some interesting facts, showing its historical advance into fresh-waters, are given by Prof. Semper), and the new jelly-fish Limnocodium, and other jelly-fish and polyps living in estuarine conditions (see *Quart. Journ. of Microsc. Science*, October 1880, for observations by Agassiz and Moseley), some Bryozoa of marine affinities, *e.g.* Membranipora, some Nemertines, and one cephalobranchiate Annelid, numerous Crustacea, such as Balanus, Mysis, Palæmon. Among Mollusks Pholades and Teredines are recorded from fresh-water, their congeners being marine, whilst actual marine species of fish (the grey-mullet and the basse) have been bred successfully for the market in the fresh-water Lake of Acqua, near Padua. The common stickleback, as is well known, can be kept in a marine aquarium. Migratory fish such as the salmon are further examples.

The experiments of Beudant and Plateau on the influence on animals of the change of saline to fresh-water or *vice versâ* are given in detail, and both are of great interest. Beudant's experiments were made with two series of molluscs—a fresh-water series transferred to salt-water, and a salt-water series transferred to fresh-water. The Pulmonata and species of Paludina were found to be very tolerant of sea-water, whilst Unio, Anodonta, and Cyclas were all eventually killed by it. *Patella vulgata*, *Purpura lapillus*, *Arca barbata*, *Venus maculata*, and *Ostrea edulis* survived in large proportion the gradual transference to absolutely fresh-water, whilst of *Mytilus edulis* not a single specimen died in the course of the experiments; species of Fissurella, Haliotis, Buccinum, Tellina, Pecten, and Chama were, on the other hand, killed by the same process.

For full reference to sources of information on this and all the many interesting observations recorded we must refer the reader to Prof. Semper's book.

In successive chapters we have similar details as to the influence of dry air, of currents of water, and of change of life from aquatic to terrestrial conditions; the land leeches, land planarians, land crabs, and land fishes being described and sometimes figured.

Some very remarkable observations on pulmonate snails living in the Lake of Geneva made by M. Forel and by Dr. Pauly are given at length on pp. 197, 198. Certain Lymnæi live at great depths in the lake with their lung-sac filled with water; they never come to the surface, and actually breathe water all their lives; but if brought to the surface they take air into the lung-sac and will not again return to the submerged existence. If forced to do so they retain air in their lung-sac and breathe water by the general surface of the body. "In no single case," Prof. Semper frankly observes, "have we as yet succeeded in proving that such a change of function as is involved in the transformation of a gill-

cavity into a lung must necessarily be accompanied by definite changes in the structure of that organ."

After chapters expounding Prof. Semper's original observations and special theory as to the formation of coral islands, in which he characteristically seeks to improve upon Mr. Darwin, and a chapter upon the influence of parasitism, we come to a final chapter entitled "The selective influence of living organisms upon animals." Here new facts bearing upon the competition for similar conditions, the relations of the pursuer and the pursued, and mimicry, are set forth in abundance. The curious dorsal eyes of the marine slug Onchidium are described and figured, and an ingenious attempt is made to account for their evolution in relation to the pursuit of the Onchidium by the leaping-fish Periophthalmus. Prof. Semper is not blundering when he states that these eyes are constructed on what he calls "a type identical with those of the vertebrata." At the same time such a statement is very misleading, for these eyes differ essentially in their origin and structure from those of vertebrates, although having one superficial resemblance to the vertebrate eye in the fact that the retinal nerve is distributed to the anterior instead of to the deep surface of the retinal cells. This arrangement exists also in Pecten, contrary to Prof. Semper's statement that Onchidium is a solitary example of its occurrence in invertebrata.

As to mimicry Prof. Semper brings forward a new instance among land-snails where a Philippine Helicarion which sheds its tail (metapodium) and so escapes when seized by a bird or lizard, is imitated closely in appearance by a Xesta which has not the power of shedding its tail, but benefits by the reputation for elusiveness of the Helicarion. On the general subject of mimicry Semper does not consider the doctrine of selection adequate, but thinks it necessary to improve the current theory relating to it by some original touches. He has made the not very new discovery that "under some circumstances the most perfect and complete resemblance between two creatures not living associated may originate without its being referable to the selective power of mimicry, *i.e.* a protective resemblance." The resemblance referred to is of course a superficial one of colour or appearance of one part of the body, and not really "perfect" or "complete." From this he goes on to suggest that subsequently to this stage a necessity for protection may arise, and the previously-established resemblance *may* become protective to one or other of the reciprocally counterfeit organisms. On the strength of this suggestion he proceeds further to question whether natural selection has ever produced mimicry, and declares that some causes "*must* have availed to produce by their direct action an advantageous and protective change of colouring" in the first instance. Similar to this, he states, is the conclusion which is arrived at in each chapter of his book in reference to other adaptations besides those coming under the head of mimicry, viz. that natural selection cannot operate until directly transforming agencies have produced advantageous characters of a definite and obvious kind upon which it may operate.

With the whole of this reasoning, and especially with the statement that any such conclusion can be derived from the facts stated in earlier chapters, we disagree. On the contrary, we maintain tha operates upon advantageous variatio ingly small, and do not, by an imme to such coarse advantages as thos Semper. Such small variations are i the action of external forces on the c units of the parents and by the acti parent upon those of another. Thes are not transforming causes, but pr multifarious variations of small amou that natural selection acts. The exis tions, the power of selection to inten transform species and further the na necessary selection, have been establi by an enormous mass of evidence. from having brought his reader in ea clusion favourable to his views, ha evidence to show that natural selec not act as taught by Mr. Darwin, completely failed to adduce any evide probable that large changes of struct by "directly transforming agents," o of which he can offer no evidence. succeeded in showing that natural sel that it could make use of such large c which it is difficult to reason, since not them excepting that Prof. Semper beli

The supposed cases of minute r mimicry which are given by Semp explained as due to a protective rese object, or as due to like advantages se in each case by natural selection in become apparent when we have more of the particular cases, or lastly, as du superficial identity in two things ha relations in common. To argue that the matter is the true one, and that the of insects is to be explained with the frequent occurrence of such coincidem the doctrine of natural selection, is, it

[1] It is necessary to plainly and emphatically state few other writers of similar views (*e.g.* the R *Modern Thought*, vol. ii. No. 5. 1881), are not a Mr. Darwin's theory, but are actually opposing distinctive in that theory by the revival of the explo transforming agents" advocated by Lamarck an seem to be aware of this, for they make n examine Mr. Darwin's accumulated facts and ar of organic evolution has become an accepted sequence of Mr. Darwin having demonstrated th the evolution is possible; it was almost unan such undemonstrable agencies as those arbitrarily a Semper and Mr. George Henslow were the only advocates. Mr. Darwin's argument rests on the *pe* many-sided, irrelative variations *not* produced b agents, but showing themselves at each new act of the phenomenon of heredity. Such minute "sports due to constitutional disturbance, and appear not in new conditions, but in the offspring of all, though spring of those subjected to special causes of constitu Darwin has further *proved* that these slight variati and intensified by selective breeding. They have a remarkably tenacious or persistent character, as their origin in connection with the reproductive proc mutilations and other effects of directly transforming ever, transmitted.

It is little short of an absurdity for persons to cons when evolution is at length accepted solely because of and coolly to propose to replace that doctrine by the and rejected.

That such an attempt should be made is an illustra ness of humanity. Not unfrequently, after a lon triumphed and all have yielded allegiance thereto few generations have passed that men have clean fo was that made that cause triumphant, and ignorantly the name of a traitor or of an impostor, or attribute to deeds and thoughts which he spent a long life in oppo

original and startling; but it involves a deliberate renunciation of the exercise of reason.

The translation of Prof. Semper's highly entertaining and really valuable and suggestive book has been remarkably well executed. Throughout great care has been taken to give the correct English equivalents for the German names of many obscure animals, and to preserve the sense of the original. At the same time there is not from beginning to end any trace of that awkward diction which sometimes infects a translation from the German. It is not too much to say that it is the best executed translation of a foreign work on science which has appeared for twenty years. E. RAY LANKESTER

LETTERS TO THE EDITOR

[*The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts. No notice is taken of anonymous communications.*

The Editor urgently requests correspondents to keep their letters as short as possible. The pressure on his space is so great that it is impossible otherwise to ensure the appearance even of communications containing interesting and novel facts.]

Movements of Plants

FRITZ MÜLLER, in a letter from St. Catharina, Brazil, dated January 9, has given me some remarkable facts about the movements of plants. He has observed striking instances of allied plants, which place their leaves vertically at night, by widely different movements; and this is of interest as supporting the conclusion at which my son Francis and I arrived, namely, that leaves go to sleep in order to escape the full effect of radiation. In the great family of the Gramineæ the species in one genus alone, namely Strephium, are known to sleep, and this they do by the leaves moving vertically upwards; but Fritz Müller finds in a species of Olyra, a genus which in Enlicher's "Genera Plantarum" immediately precedes Strephium, that the leaves bend vertically down at night.

Two species of Phyllanthus (Euphorbiaceæ) grow as weeds near Fritz Müller's house; in one of them with erect branches the leaves bend so as to stand vertically up at night. In the other species with horizontal branches, the leaves move vertically down at night, rotating on their axes, in the same manner as do those of the Leguminous genus Cassia. Owing to this rotation, combined with the sinking movement, the upper surfaces of the opposite leaflets are brought into contact in a dependent position beneath the main petiole; and they are thus excellently protected from radiation, in the manner described by us. On the following morning the leaflets rotate in an opposite direction, whilst rising so as to resume the diurnal horizontal position with their upper surface exposed to the light. Now in some rare cases Fritz Müller has observed the extraordinary fact that three or four, or even almost all the leaflets on one side of a leaf of this Phyllanthus rise in the morning from their nocturnal vertically dependent position into a horizontal one, without rotating, and on the wrong side of the main petiole. These leaflets thus project horizontally with their upper surfaces directed towards the sky, but partly shaded by the leaflets proper to this side. I have never before heard of a plant appearing to make a mistake in its movements; and the mistake in this instance is a great one, for the leaflets move 90° in a direction opposite to the proper one. Fritz Müller adds that the tips of the horizontal branches of this Phyllanthus curl downwards at night, and thus the youngest leaves are still better protected from radiation.

The leaves of some plants, when brightly illuminated, direct their edges towards the light; and this remarkable movement I have called paraheliotropism. Fritz Müller informs me that the leaflets of the Phyllanthus just referred to, as well as those of some Brazilian Cassiæ, "take an almost perfectly vertical position, when at noon, on a summer day, the sun is nearly in the zenith. To-day the leaflets, though continuing to be fully exposed to the sun, now at 3 p.m. have already returned to a nearly horizontal position." F. Müller doubts whether so strongly marked a case of paraheliotropism would ever be observed under the duller skies of England; and this doubt is probably correct, for the leaflets of *Cassia neglecta*, on plants raised from seed formerly sent me by him, moved in this manner, but so slightly that I thought it prudent not to give the case. With several species of Hedychium, a widely-different paraheliotropic movement occurs, which may be compared with that of the leaflets of Oxalis and Averrhoa; for "the lateral halves of the leaves, when exposed to bright sunshine, bend downwards, so that they meet beneath the leaf." CHARLES DARWIN

Down, Beckenham, February 22

Barometric and Solar Cycles

REGARDING one of the conclusions drawn by Mr. F. Chambers in his paper on "Abnormal Variations of the Barometer in the Tropics," and Dr. Balfour Stewart's remarks concerning the same in the first article of NATURE (vol. xxiii. p. 237), I and other meteorologists would like very much to know which side of the earth is to be considered the east, and which the west.

In other words, if waves of high barometer travel slowly from west to east, on what meridian do they commence, and is there any reason why they should commence on one meridian more than on another? The only reason that I can think of is that some meridians embrace more land than others; but in this respect the meridians passing through the centres of America, Europe-Africa, and East Asia-Australia are very much alike. Again, if barometric changes originate, say at St. Helena, and travel slowly eastwards, as Mr. Chambers supposes, they ought after several months to reappear on the meridian from which they started, but Mr. Chambers's paper gives no evidence of this whatever.

Dr. Balfour Stewart says it is unmistakably indicated by all the elements that the connection between the state of the sun's surface and terrestrial meteorology is of such a nature as to imply that the sun is most powerful when there are most spots on his surface. The barometric evidence, however, is all the other way.

Mr. Blanford, following up a suggestion originally made by the present writer, has shown clearly enough that the decennial variation of the height of the barometer has nearly opposite phases in the Indo-Malayan region and in Western Siberia, especially if the winter season, when the pressure is higher over Siberia than in South-Eastern Asia, be considered alone (NATURE, vol. xxi. p. 480). From Mr. Blanford's paper it is clear that the barometrical differences, on which the strength of the winds depends, are greater when the sun-spot area is small than when it is large.

The true relation between the variations of sun-spot area, solar radiation, and barometric pressure will, I feel confident, be soon discovered through the agency of the United States Weather Maps in the manner pointed out by you at page 567, vol. xxi., in discussing the United States Weather Map for July, 1878. It is there shown that in the middle of summer in the last year of minimum sun-spot, the pressure of the air was below the average over all the great continents, and above it over the neighbouring oceans. In India, it is true, the pressure was above the average; but then India is not Asia, but merely a narrow triangular peninsula surrounded on two sides by the ocean, and on the third by a broad zone of snow-covered mountains which may be likened to an oceanic area as far as constancy of temperature is concerned.

Meteorologists will all agree with Dr. Balfour Stewart that "unexceptionable observations of the sun's intrinsic heat-giving power, if these could be obtained, would furnish a more trustworthy instrument of prevision than the sun-spot record." We may soon hope for a nearly continuous series of such observations, for, according to the last published Administration Report of the Indian Meteorological Department, a trustworthy form of actinometer is being sent to Leh, 11,500 feet above the sea, in the dry region of Tibet, where observations will be taken with it under the superintendence of Mr. Ney Elias.

Meantime we may perhaps adopt what is considered by Mr. Blanford the best criterion of the sun's heating power which can be obtained from ordinary meteorological observations, viz. the highest excess of the vacuum black-bulb thermometer above the maximum in shade for each month. At ten stations in India where comparable thermometers have been used since 1875, the mean maximum solar excess has been:—

1875		1876		1877		1878
67°·0	...	67°·2	...	68°·8	...	68°·1

The means of thirty-eight stations since 1876 give similar results, viz. :—

1876		1877		1878
68°·2	...	68°·8	...	68°·3

For 1879 and 1880 the figures have not yet been all worked up, but as far as they have been reduced they indicate that the intensity of solar radiation was a good deal less than in 1878.

Allahabad, February 3 S. A. HILL

The Continents always Continents

MR. WALLACE, in his recent excellent work on "Island Life," places me in a wrong relation to the question as to the continents having always been continents. After sustaining the view at length in Chapter VI. of his work, without any reference to my arguments on the subject, he later, in Chapter IX., says that "it appears to be the general opinion of geologists [*sic*] that the great continents have undergone a process of development from earlier to later times," and then quotes a paragraph of mine by way of proof.

My first discussion of the subject was published in the *American Journal of Science* for 1846 (vol. ii. of second ser. p. 352), where the "opinion" is partly speculative, the origin of the continents being made one of the initial results of the earth's refrigeration; but it is not left without the mention of facts sustaining it derived from the actual geological progress of the American continent. In the following volume, in an article entitled "On the Origin of Continents," the view is presented at more length, with some additional confirmatory facts connected with the structure of the continent; and facts from the earth at large bearing the same way are brought out in a second paper, "On the Origin of the Grand Outline Features of the Earth." In my "Geological Report" (published in 1849) of the Wilkes Exploring Expedition around the World, in which the same views are briefly presented (p. 431), I argue against "the existence of a continent in the Pacific Ocean within any of the more recent geological epochs" [referring here to those of the Tertiary and Quaternary], on the ground of "the absence of all native quadrupeds from its islands, and even from New Zealand."

A few years later (in 1856) I published, in vol. xxii. of the *American Journal*, two papers under the titles "On American Geological History" and "On the Plan of Development in the Geological History of North America," and in them I gave what I have regarded as a geological demonstration of the view by stating with some detail the facts with respect to the successively-developed features and geological formations of the American continent. Again, in my "Manual of Geology," the first edition (that of 1863), the progress of the rocks and mountains of the continent is traced out, from the V-shaped Archæan (Azoic) nucleus, in British America, onward; and in the account of the Archæan the statement is made (p. 136) that the structure lines apparent over the continent at the close of Archæan time were "features that were never afterwards effaced; instead of this, they were manifested in every new step in the progress of the continent"; and in the edition of the Manual of 1874, after a fuller account of the positions of Archæan mountains, it is then added (p. 160): "Hence, in the very inception of the continent, not only was its general topography foreshadowed, but its main mountain chains appear to have been begun, and its great intermediate basins to have been defined—the basin of New England and New Brunswick on the east; that between the Appalachians and the Rocky Mountains over the great continental interior; that of Hudson's Bay, between the arms of the northern V. The evolution of the grand structure-lines of the continent was hence early commenced, and the system thus initiated was the system to the end. Here is one strong reason for concluding that the continents have always been continents; that, while portions may have at times been submerged some thousands of feet, the continents have never changed places with the oceans. Tracing out the development of the American continent from these Archæan beginnings is one of the main purposes of geological history." In the course of the following pages (nearly 400) on Historical Geology in both editions, the evidence on this point is variously set forth—evidence afforded by the limits of the successive geological formations, by the occurrence of beds of shallow-water deposition at many levels in the long series, and by the progressive origin of the mountain-ranges. Then, in the edition of 1874 (and also that of 1880) I bring in (p. 525) the paragraph which Mr. Wallace cites in his Chapter IX. (p. 196)—not as the expression of an "opinion," but as the summing up after a demonstration.

The view that the continents have always been continents, which I have held for forty years, is written so plainly in the geology of North America that I am sure it would never have been set down among speculations, even by the most exacting of British geologists, had attention been fairly given to American facts. If the truth is not taught by British rocks, it is because these represent only a narrow margin of a continent, and hence could not be expected to illustrate general continental development, hardly more than an animal's leg, however profoundly studied, the embryological laws of the species.

JAMES D. DANA

New Haven, Connecticut, February 8

The Aurora of January 31; Position of Auroral Rays

THE bright loop shown in G. F. Seabroke's drawings of the aurora on January 31 at 6.30 and 6.35 p.m., as seen at Rugby, remind me of a striking feature seen here. If it was the same, a comparison of the observations will give some idea of the height of the phenomenon. As seen here at about 6.24½ the feature was the most conspicuous part of the aurora; it was a somewhat pear-shaped bright patch, with a region along the middle of it not quite so bright. Its edge was 10° above the moon, at Venus, Jupiter, β and η Pegasi; its pointed end being low down, and a good deal further to the right. At 6.26½ Venus was in the midst of its left end, and Jupiter quite outside. The moon was 5° below the lower edge. The dusky region gradually darkened, and finally opened through the right end of the patch, which became united by a rather serpentine bright band to a somewhat similar, but partly red, bright patch rising up in the east-north-east. This bright band formed the southern border of the aurora. At 6.31½ the position of the central line of this band, including the western bright patch which now formed a loop in it open to the north, was about as follows:—At or near the moon, one-third of the way from ι Ceti to Venus, ζ Cygni (the junction of the patch with the new band), α Pegasi I think, β Trianguli, α Tauri, and below Procyon.

The motion of these features, as well as of all the large masses of the aurora throughout the evening, was approximately from east to west (magnetic), so far as I could observe. The four or more arches seen at Rugby by G. M. Seabroke at 6.35 were not seen by me.

The spectrum of this aurora was very similar to those of February 4, 1874, and October 4, 1874, as given in Capron's "Auroræ," Plate V.; the band marked 4 of the former being sometimes present and sometimes absent. I also saw traces of the red line at times.

I am surprised that Prof. S. P. Thompson (NATURE, vol. xxiii. p. 289) is not aware that it is a thoroughly ascertained fact that the rays of auroras lie in the direction of the magnetic dip. I may add that the flashes or pulsations also generally appear to move away from the earth in the direction of the magnetic dip.

Sunderland, February 24 T. W. BACKHOUSE

Auroric Light

As Mr. W. H. Preece records the magnetic storms, if not too much trouble would he record what took place on the night of January 16?—as at midnight there was all the appearance of a grand display; but as the windows were all frost-masked, and my only place of observation was exposed to a cutting wind that would have "shaved a cast-iron policeman," to quote *Punch*, I could not observe what took place. I should also like to know why the grand displays this winter are of white lights. Those I saw in previous years—the best being while stationed in West Galway between 1867 to 1872—were principally red lights, some of them being most brilliant between midnight and morning, while all of them this year have been best early in the night, all lights usually disappearing before or a little after eleven. I am used to white lights in the summer months, but I never before saw them so prominent in the winter months—main lights, cross lights, and glows being white; while usually, each respectively have different colours. I have not seen an aurora that changed so much in character as the last, except that of September, 1866 or 1868 (I think, but I have not my notes to give the exact year). That of 1867 or 1868 was a grand display, rising in a red mass to the zenith, and then shooting out pencils of red, green, white, purple, and orange lights.

G. H. KINAHAN

Ovoca, February 20

The Recent Severe Weather

GRANTING (1) that solar periodicity produces a corresponding periodicity in any of the elements which make the climate of the earth as a whole what it is, and (2) that the expression for that periodical change contains only the two first terms of the general expression, *i.e.* that there are no secondary . . . periods, both large admissions in the present state of our knowledge, it does not appear how a simple fluctuation of solar temperature, recurring, we will say, every eleven years, could produce several periodic fluctuations of terrestrial temperature, identical in duration but not simultaneous, some one or more being therefore partially or completely opposed in phase to some one or more of the remainder, and to the causal fluctuation.

Further, we know that solar conditions are not as simple as those above assumed, and that the sun-spot period is subject to large and seemingly capricious variation amounting to something like ± 3 years at least. If then, as some able physicists believe, solar atmospheric changes are reflected in marked variations in terrestrial climate, we shall find these latter to be common to the whole earth, and to be represented by a function of the same form. The mere citation of local (for in this view even the climate of Europe is merely local) phenomena which have occurred at intervals approximately equal *individually* to the *average* length of a sun-spot period, proves nothing in favour of the view supported by your correspondent "H. W. C.," in NATURE, vol. xxiii. pp. 329, 363; and an analysis of the dates given in his first communication, which would make the occurrence of great frosts simultaneous, sometimes with sun-spot maxima, at other times with sun-spot minima, seems calculated to weaken his case in a material degree, on the supposition of an *uniform* eleven-year cycle.

Arranging the dates given by him in parallel column with the eleventh years of the present century, we get

Dates of severe frost.	1800 +
1. 1801—2	0
2. 1810—11	11
3. 1813—14	—
4. 1819—20	22
5. 1837—38	33
6. 1840—41	44
7. 1856—57	55
8. 1860—61	66
9. 1870—71	77
10. 1880—81	88

2 and 7 are placed as above, as those positions seem to favour the cyclic theory more than their original ones did. A *complete* list of great frosts collated with *actual* sun-spot variations is however most desirable, and would be specially valuable if representative of terrestrial climate in the cosmical sense. I trust that H. W. C. will favour us with such a table.

London, February 19 M. R. I. A.

Migration of the Wagtail

I FEAR I may be attempting to trespass too frequently on the columns of NATURE recently, but the paper in vol. xxiii. p. 387 on the subject of wagtails taking a passage on the backs of cranes in a long flight, resembles so much a somewhat similar story told and believed in by the Indians in several parts of North America, that I venture to send you an account of it.

All the Indians (Maskegon Crees) round the south-western part of Hudson's Bay, assert that a small bird of the Fringillidæ tribe takes a passage northward in the spring on the back of the Canada goose (*A. Canadensis*), which reaches the shores of Hudson's Bay about the last week of April.

They say that they have often seen little birds fly away from geese when the latter have been shot or shot at.

An intelligent, truthful, and educated Indian named George Rivers, who was very frequently my shooting companion for some years, assured me that he had witnessed this, and I believe I once saw it occur.

It is only the Canada goose that these little migrants use as an aërial conveyance, and certainly they both arrive at the same date, which is a week or two earlier than the other kinds of geese (*A. hyperboreus* and *albifrons*) make their appearance.

I knew the little bird well and have preserved specimens of it, but it is so long ago that I have forgotten the name.

The Indians on the shores of Athabasca and Great Slave Lakes—both great resorts of wild geese—tell a similar story. If a fabrication, I do not see why it should be invented about the Canada goose only, and not about other species which are equally numerous.

It may perhaps be necessary to explain that all the Coast Indians of Hudson's Bay devote a month or more every spring to wild fowl (chiefly geese) shooting, the game killed forming their entire food for the time.

As soon as the geese begin to arrive, the Indian constructs a concealment of willows and grass, usually near a pool of open water, at the edge of which he sets up decoys. When geese are seen approaching (usually flying at a great height) the Indian imitates their call, and the geese on seeing the decoys circle round, gradually coming lower down until within shot, when they are fired at. It is from these high-flying geese that the small birds are seen to come.

If the geese are flying low it is a pretty sure indication that they have already rested on the ground somewhere near, after their long flight, when of course their tiny passengers would have alighted. JOHN RAE

Royal Institution, February 26

Phosphorescence of the Sea

YOU will perhaps permit me to record the occurrence of a phenomenon very rarely witnessed on this coast—I mean the general and quasi-spontaneous luminosity of the sea.

It is of course common enough to observe sparkles of light more or less abundant when sea-water is briskly disturbed by contact with an oar or the bow of an advancing vessel; but it has only once before been my fortune, and that was twenty years ago, to witness the crest of each wavelet illuminated by the pale silvery light proceeding from countless phosphorescent organisms present in the water.

The night, being cloudy, favoured observation, but there was considerable haze. The wind was south-east or thereabouts, the temperature of the air being 52° F., that of the sea close by the shore 47°·5 F.

The phenomenon was visible on the night of Thursday, February 17 only. The following night was equally favourable for observation, and the temperatures were the same within a degree, but the cause or causes no longer operated. On casting into the sea a shower of pebbles, which the night before produced brilliant flashes of light, or larger stones, which then developed concentric luminous wavelets, only a doubtful effect was observed. The organisms had, it seemed, already expended their force—probably had actually died—and I thought I perceived an unusual frothiness in the water.

Is it not uncommon for this to occur so early in the year? It is in summer, when the temperature of the sea is high, that we expect to see the water "fiery." Was the phenomenon observed on other parts of the coast? THOS. B. GROVES

Weymouth, February 21

Minerva Ornaments

I HAVE twice had an opportunity of being in London during the time Dr. Schliemann's Trojan antiquities were exhibited at South Kensington, and the examination of them gave me very much pleasure. My last visit took place at the time Mr. Claypole's first letter and Prof. Sayce's reply appeared in NATURE, and I gave the "Minerva ornaments" particular attention. My interest in the subject has been revived by seeing another letter from Mr. Claypole in a recent number, and having refreshed my memory from notes taken during my visits, perhaps you would kindly afford me space for a few remarks.

Some of the "Minerva ornaments" appeared to me somewhat similar to Irish objects in my possession, but mine are more symmetrical, less flattish, and on the whole more suitable, I should say, for net-sinkers than the others, yet I never thought of ticketing them as such. I think that both sets of objects have had too much labour expended on them to favour the idea that they were used for such a common object as net-sinking. The Irish objects, which I should say are of stone, are identical in form with a class of glass ornaments known as double glass beads, found in most collections of Irish antiquities, which are certainly not net-sinkers. "Net-sinker" is a very common name in Ireland for almost any stone with a hole in it, and, without intending the slightest disrespect to Mr. Claypole, I believe the term is one of a set, of which "sling-stone" is another, applied in doubtful cases to cover our ignorance. As regards the use of the objects discovered by Dr. Schliemann, there may

be good grounds for believing that they were idols; but had I been left without help to interpret for myself I should not have guessed them to be net-sinkers, but rather children's playthings—the ancient representatives of modern dolls. To show how little pains are sometimes taken in the preparation of net-sinkers, I may mention that a few months ago, while walking along the banks of the River Bann, I saw a fisherman cutting the tough sward into pieces about two inches by three or four, which, in answer to my inquiry, he informed me were intended for net-sinkers. I asked him why he did not use stone or lead, and he replied that turf sinkers were much superior, as in using them the nets never became entangled in the bottom of the river. I wonder if this custom is a recent invention or a survival from earlier times.

I was struck by the close resemblance which several other objects in the Schliemann collection bore to Irish antiquities. I have noted several tool-stones with the usual hollowed marks on the sides, especially those bearing the double numbers 26 and 1578, 26 and 1478, 26 and 1522, 45 and 1499, and also a stone celt or hatchet with marks on the sides like those on the tool-stones, and hammered at the edge, numbered 13 and 1505, all of which I could match from my own collection. Several whorls are marked in my notes as being similar to others found in Ireland, and an object bearing the numbers 6 and 1636 as being almost identical with double stone beads in my collection. I have also a large series of rubbing or polishing stones similar to others in Dr. Schliemann's collection. Hammer-stones numbered 6 and 7268, 26 and 1529, 26 and 1566, 13 and 1570 are perfect duplicates of some of those found by myself, with flint and bone implements, &c., at Portstewart and Ballintoy. The ornamentation on a few of the stone and glass whorls and beads in my collection have a sort of resemblance to that on some of the terra-cotta whorls exhibited by Dr. Schliemann.

Cullybackey, Belfast, February 10 W. J. KNOWLES

Selenium

THE use of selenium for the automatic registry of star transits, proposed by me in a letter which you were good enough to publish in NATURE, vol. xxiii. p. 218, leads to the idea of applying it in a somewhat similar way for photometric purposes, in order to improve the existing scale of star magnitudes, and to watch any variations therein. W. M. C.

Bombay, February 5

A CHAPTER IN THE HISTORY OF THE CONIFERÆ

THE Sequoias form the third genus of the Taxodieæ in the "Genera Plantarum." The only existing species are the Wellingtonia and the Red-wood of California, both of which are confined to the south-west coast regions of the United States. Their nearest living allies are Taxodium and Glyptostrobus; but these were as completely differentiated in the Eocene as at present, and they all appear, like the Ginkgo, to be survivals from more ancient floras; Sequoia especially had formerly a far wider range than it has at the present day.

The Sequoias are monœcious, and have obtusely ovate ligneous solitary and terminal cones one to two inches in length, which are persistent and gaping after shedding the seed. The scales are spirally disposed, sixteen to twenty in number, wedge-shaped, with an orbicular or transversely oblong nail-like head, depressed, wrinkled, and mucronate in the centre, sharing thus to some extent the ornamentation which seems a characteristic of the Taxodieæ. The foliage is distichous and yew-like in *Sequoia sempervirens*, and spiral and imbricated in *S. gigantea*, but both occasionally foliate in the opposite way. The former, or red-wood, occupies the Coast Range, a sandy rock rising to 2000 feet, of supposed Cretaceous age, and forms dense forests twenty to thirty miles in width, from a little south of Santa Cruz to the southern borders of Oregon, following the coast line for some 350 to 500 miles, its distribution depending, according to Prof. Bolander, upon the sandstone and oceanic fogs. The *S. gigantea* extends at intervals along the western slope of the Sierra Nevada for nearly 200 miles, and at elevations of 5000 to 8000 feet. "Towards the north the trees occur as very small, isolated, remote groves of a few hundreds each, most of them old and interspersed amongst gigantic pines, spruces, and firs, which appear as if encroaching upon them; such are the groves visited by tourists (Calaveras, Mariposa, &c.). To the south, on the contrary, the Big-trees form a colossal forest forty miles long and three to ten broad, whose continuity is broken only by the deep sheer-walled cañons that intersect the mountains; here they displace all other trees, and are described as rearing to the sky their massive crowns; whilst seen from a distance the forest presents the appearance of green waves of vegetation, gracefully following the complicated topography of the ridges and river-basins which it clothes."[1] The leaves are scale-formed, rounded dorsally, concave on the inner face and closely inlaid, regularly imbricated on the branchlets, longer and looser on the branches. In young trees they are much larger and freer, with long and awl-shaped leaves at an acute angle to the stem. No trees under cultivation in this country seem yet to have completely assumed the small imbricated foliage characteristic of the giant trees of California.

Although the types of foliage in the two existing species appear to be perfectly distinct, they are not really entirely so; for *S. sempervirens* preserves the spiral scale-like leaves for a short distance at the base of each branchlet, and *S. gigantea* sometimes assumes the distichous arrangement. Besides, the foliage of the former is not in two rows as it is in Taxodium, being spirally arranged round the stem; but the leaflets, where they are flat and comparatively expanded, have a strong tendency to grow into two marginal rows, so that every surface becomes exposed to light and moisture. The leaflets take a half twist near their base, and then diverge upward or downwards towards the sides of the branchlet, an additional row frequently lying centrally along the branch.

The earliest-known Sequoias are Cretaceous, and were described by Carruthers, one as *S. Woodwardii* from Blackdown, and others as *S. Gardneri* and *S. ovalis* from the Folkestone Gault. The foliage from the latter has falcate leaves like Araucaria, and it is only inferred that it and the cones belonged to the same trees. It is not impossible that the cones may have been brought down from some high ground, and the foliage been shed by trees near the sea-level. Although Sequoia itself cannot be traced farther back than the Cretaceous, Schimper speculates on its probable derivation from some much older Araucarian form, and believes its position to be between the Cupressineæ and the Abietineæ.

Saporta regards the Chalk period as the age of Sequoias, and our principal knowledge of them is derived from Heer's "Flora fossilis arctica," where a large number are figured. Saporta speaks of Pattorfik as a Sequoia wood carpeted with ferns, and Ekkorfat as a forest composed of cycads, sequoias, and firs. *S. Reichenbachii* is the chief form, and occurs in the Cretaceous of Kome, Spitzberg, and doubtfully at Atane. The foliage resembles the larger foliage of *S. gigantea*, being spiral, awl-shaped, set at an acute angle to the stem, and with the points overlapping. It differs in being less regularly spiral, and often combines an approach to the more distichous *S. sempervirens* type, being called in such cases, *S. Smittiana*. In several of the figured specimens from the Komeschichten the branchlets of the two forms are almost united, and a very slight degree more care in collecting would, it seems, have placed the reality of the union beyond the possibility of doubt. One instance is reproduced from plate xx., and a fragment from the same plate determined as *S. Reichenbachii*, to show that even apart from the frequent association of the two species on the same slabs, their distinctness cannot be maintained if the

[1] Lecture before Royal Institution, April 19, 1878, by Sir J. Hooker.

plates are faithfully drawn. The separation of another species, *S. rigida* from *S. Smittiana*, seems even less warranted; but *S. ambigua* has somewhat smaller foliage and cones, and *S. gracilis* still smaller foliage, approaching *S. Couttsiæ*, yet compared, for no obvious reason, with *S. Gardneri*.

Spitzbergen has no Cretaceous species peculiar to it, but the Upper Cretaceous of Atanekerdluk possesses, besides two of the Komeschichten species, *S. fastigiata*, Sternb., and *S. subulata*, Heer. These two bear the

a, *b*, *S. Reichenbachii*; *c*, *S. Smittiana*, Fig. 7, pl. xx. vol. iii. "Flora foss. Arctica."

same relationship to each other that we have seen between *S. Reichenbachii* and *S. Smittiana*, only they are both considerably smaller, and were, as in the other case, doubtless the same tree.

S. Reichenbachii is said to be met with in other Cretaceous deposits in Bohemia, Saxony, Moravia, Belgium, &c., and *S. fastigiata* over the same, but a more restricted area; their wide distribution being held by Saporta to evidence a former universal equality in temperature.

It is of course useless, without further material, to seek



S. rigida, Fig. 11*a*, pl. xxii. *S. Reichenbachii*, Fig. 8, pl. xx.

to unite the whole of the above species, since they have been described as distinct by Heer; but it seems perfectly certain that had collecting been systematically carried on, a small proportion only of the specific distinctions could have been maintained. The excessive subdivision is to be regretted, since it has given undue prominence to the Arctic Sequoias of this age as a group, and will otherwise lead to inconvenience. Their chief and most interesting characteristics have been overlooked by Heer. These are first the union in one plant of the now almost completely differentiated *S. sempervirens* and *S. gigantea* types; and second, that the foliage, which then approached to the distichous *S. sempervirens* form, was produced, if the plates are correctly drawn, by the shortening almost to abortion of the upper and under leaves, and not to their being narrowed at the base and twisted, as at present, towards the sides of the branchlets.

The Arctic Tertiaries have yielded no foliage of the spiral, needle-leaved *S. gigantea* type, except that which has been referred to *S. Couttsiæ*. The large Araucaria-like foliage of *S. Sternbergi* does not seem at that time to have existed much farther north than Iceland, while the *S. sempervirens* type seems to have been abundant. *Sequoia Lagnsdorfii* is in fact the prevailing fossil in Greenland, scarcely any stone with leaf impressions being without some remains of it. The branchlets are generally simple and single, rarely forking, and seem thus to have had a short season of growth and been quickly shed, an adaptation probably to the long Arctic winter. Flowers, fruits, and seeds have been collected. It is hardly less abundant at Spitzbergen, Mackenzie River, and other localities near the Arctic circle and in Iceland. The cones are said to be somewhat larger, and with more scales, and the leaves less pointed than in the existing species. The more decidedly imbricated character of the fruit-bearing branchlets implies a closer affinity with the Cretaceous forms. Heer makes six duly-named varieties out of the Spitzbergen species, being probably unaware of the extent to which foliage on the same tree may vary at the present day. *S. brevifolia*, again, is at best a variety, and *S. disticha* has leaves in opposite pairs, and while unlike in this respect, has nothing besides to support its reference to Sequoia. *S. Langsdorfii* next appears in the Miocene Baltic and in the Aquitanian and Mayencian stages in Switzerland, Germany, Austria, and France, but does not seem to appear in any Upper Miocene beds except as far south as Italy, where it occurs in several localities. This distribution is important, as well as the fact that branchlets from beds of Central Europe are more compound than those from the far north. Another Spitzbergen species, extremely abundant where first found, is *S. Nordenskiöldi*, said to be distinguishable by smaller and softer foliage, narrower leaflets scarcely tapering at the base and at more acute angles to the stem, the last being the chief distinctive character. None seem to have been met with in the 1872 expedition, only *S. Langsdorfii* being illustrated in the fourth volume of the "Flora fossilis arctica."

Another species belonging to the same group, described by Saporta as *S. Tournalii*, is found in the Miocenes of Manosque, Armissan, and Kumi. It is principally characterised by the clustered, rarely solitary cones, and while the foliage resembles generally that of the existing species, the branchlets bearing fruit were much more imbricated, and in this respect resembled those of *S. Langsdorfii* of the Arctic floras.

Most of these types have also been met with in America —where Lesquereux, following Heer, has over-subdivided the fragments into species.

The *S. gigantea* type had by far the more restricted distribution of the two in the Tertiaries. Much of this form of foliage from the Lower and Middle Eocenes of England and France has been referred to Araucaria; but elsewhere, in the Oligocenes especially, almost the whole of it is referred to a single species of Sequoia, *S. Sternbergi*. It agrees with that of young plants of *S. gigantea*, the leaflets being less falcate, longer, and at a more acute angle to the stem than in the nearest existing Araucaria. On the other hand, however, no nearer approach to the ordinary adult foliage of *S. gigantea* is ever associated with them. The characteristic cones of Sequoia, which are small and numerous, and very persistent on the branches after the seed is shed, remain attached in several fossil species, as *S. Couttsiæ*, wherever

they are met with: but are rarely associated with the foliage figured as *S. Sternbergi*, none having been found at such important localities as Sotzka, Häring, Monte Promina, and Bilin, where foliage abounds. This absence of cones is very strong negative evidence against their foliage in the above localities at least being Sequoia, and in favour of their being Araucaria. The cones of Araucaria are few and large, shaken to pieces by the wind almost as soon as ripe, and when carried by water the flotation of the winged seeds and of the foliage would differ enough to lead to their being separately imbedded. The foliage was described for years as *Araucarites*, and a well-defined immature cone of Araucaria was found in the deposit at Häring and figured by Sternberg[1] and by Goeppert[2] as *Araucarites Goepperti*, and afterwards considered by Unger and Ettingshausen[3] to belong to *A. Sternbergi*. Another small Araucaria-like cone is figured by Massalongo from Chiavon,[4] which was found associated with foliage identical with that from Bournemouth. Similar foliage, but still nearer to Araucaria, is found at many places in France, and in England at Sheppey, Bournemouth, Bracklesham, the Isle of Wight, &c., but also always without any Sequoia cones, although I have found an Araucaria cone at Sheppey.

Against all this evidence we have to set the fact that a branch with compressed cones attached has been found in the Upper Miocene near Turin, and that Sequoia cones are found in the same strata with somewhat similar foliage in Iceland. In both these instances however the foliage differs materially from the typical *S. Sternbergi* of Sotzka. If we consider that foliage of existing species of Araucaria, Sequoia, Cryptomeria, and Arthrotaxis can with difficulty be distinguished, and that species which have died out may have approached each other still more closely, the evidence upon which Heer has changed the determination of all the Austrian and German specimens must appear insufficient. The possibly accidental similarity, not identity, of foliage occurring in deposits far apart and of widely different age, does not, I hold, outweigh the other facts I have advanced.

This type of foliage, whether it belong to one or many genera, has not been found of Tertiary age north of Iceland, nor in the newer Miocenes of Central Europe, if we set aside two more than doubtful fragments from Oeningen. It abounds however in England, France, Germany, and Austria in Eocenes and Oligocenes, and recurs, as an Upper Miocene form, in Italy only.

The British Eocenes have been credited with several Sequoias, as *S. Sternbergi* and *S. Bowerbankii* from Sheppey, *S. Langsdorfii* from Alum Bay and Bournemouth, *S. du Noyeri* from Antrim, &c., &c. There is, I believe, no good evidence yet of the presence of any Sequoia except *S. Couttsiæ*, confined to Bovey, Hempstead, and perhaps Bournemouth, in any Tertiary rock of Great Britain. This question however cannot here be profitably discussed. *S. Couttsiæ* was originally described by Heer from Bovey Tracey, where it literally abounded. The foliage resembles that of *S. gigantea*, though smaller and more delicate, and must have been very graceful; but Heer's restoration of it, since copied into other works, is very stiff and unnatural. The foliage in the "Flora fossilis arctica" is much coarser, and should not have been referred to the same species. Saporta describes a beautiful variety "*Polymorpha*" from Armissan, in which the ultimate branchlets take on the *sempervirens* character. *S. Couttsiæ* seems to have been capable of supporting considerably greater heat than any of the other species, if we may judge from the associated plants.

The leading facts known to us respecting the past history of the Sequoias may be summed up thus. They are not known to be older than the Cretaceous, when they were principally a northern fo
the existing types has progress
present, being slight in the C
bachii); more pronounced in t
v. polymorpha); yet more s
Miocene (*S. Langsdorfii*), and
though even now there is a t
other. The number of fossil s
ably reduced, and much of the
transferred to other genera.
have ranged as far south as C
Cretaceous, seems to have re
Lower and Lower Middle Eoce
habitats in the Upper Middle E
through *S. Couttsiæ*, and then
and ranged into Italy during th
well-nigh exterminated during t
been strangely preserved in tw
beyond its original range, wh
fluence of the Pacific enabled i
at a remote period lofty mounta
of ancient glaciers. Fixed on
stations with congenial soil, the
slowly adapted themselves to
genial than that supported by
in adapting themselves to an alt
have acquired that stupendous
makes them the giants of vegeta

The moral to be drawn from t
is that we should not place
minimum temperature of the s
land, Spitzbergen, Vancouver's
America and Asia, as settled
argument, as for instance tha
requires such and such a temp
but different species must hav
entitled to but little deference
opinions are quoted as axiom
workers. When examined they
whether taken as physiologica
logical, or any other data. Pr
use, but the questions dependin
data are so important and the e
they should not be deemed se
amount of care has been bestow

1 "Versuch," v. i. ii. p. 204, Pl. 39, Fig. 4.
2 "Monogr. foss. Conif.," 1850, Haarlem *Trans.*, p. 237, Pl. 44, Fig. 2.
3 "Flora von Häring," p. 36. 4 "Specim. Photogr.," pl. xxi.

GEOMETRICAL

WE are glad to see that
Improvement of Geome
by no means idle, though no
since January, 1878, but that the
of silent work going on in the w
cussions upon the several syllabu
higher plane geometry, and of
who know the president will hea
in his bereavement, and will un
must have been for any other w
position at Harrow imperativel
has now thrown himself with mu
and proof of his interest in the l
is manifest throughout the inte
printed on pp. 12-17 of this R
that he has long advocated an e
the Association, and in this addr
tunity of putting his views well f
"It was doubtless well at th
concentrate our attention and
definite field, in which perhaps t

1 If we can really trace back the history
becomes curious to notice that it is only
type which there is reason to believe former
ture of any Tertiary Sequoia.
* Association for the Improvement of
General Report, January, 1881.

was most pressing, that of the teaching of geometry. But it can hardly be denied, I think, that there are other branches of mathematics whose teaching might also be greatly improved by an association of teachers, conferring together as to the defects of existing books or methods, and intrusting to sub-committees the task of suggesting means of remedying such acknowledged defects. If this be granted it appears to me that it is our next duty to bring the strength of our existing organisation to bear on other branches of mathematics besides pure geometry. To do this would, I believe, assist rather than injure the work which we have still to do for geometry.

"I cannot doubt but that we have to some extent suffered from the restriction of the field within which we have hitherto worked. Elementary geometry is essentially a *school* subject, that is, one in which a student of mathematics ought to be fairly proficient before he enters on his university course, and which therefore is not a subject of *real teaching* in our universities or higher colleges at all. To this, and not to any ingrained spirit of opposition to improvement, which in the face of the changes going on in our universities it seems to me it would be absurd to charge upon any body of active workers therein, I am inclined to attribute the small amount of interest and attention which we have hitherto been able to obtain for our work, and our failure as yet to procure any recognition of our syllabus in any university of the United Kingdom. Where a subject is not taught, but is only a subject, and rather a subordinate subject, of examination, there can hardly be any very lively and active interest in the improvement of its teaching. It is reasonable to expect, therefore, that, by extending the scope of our work to other subjects, of which only the elements can in general be taught in schools, and which will afterwards be more fully studied at the universities, we shall enlist the sympathies of a wider circle of mathematical teachers, extend the list of our members, and connect ourselves more intimately with the living mathematical teaching of our universities, and then we shall, I believe, greatly promote the recognition of the work which we have already done. . . . . Algebra and trigonometry are perhaps less in need of our attention than other subjects, though even as regards these I believe valuable suggestions as to improved methods and range of teaching would arise in the discussion of a committee specially interested in them. But it is only necessary to mention the subjects of analytical geometry, higher geometry, higher algebra, elementary kinematics and dynamics (or mechanics), to bring before the minds of those whom I am addressing a number of questions as to their teaching, from the discussion of which great advantages might arise. Further, I think no one can have followed the more recent expositions of mathematical physics, more especially in the 'Matter and Motion' of Maxwell, and the 'Elements of Dynamic' (alas, only a fragment) of Clifford—to mention only the names of two of the most penetrative geniuses and profound thinkers of our age, whom we have loved and admired while living, and whose premature deaths we, in common with the whole world of mathematical and physical science, deplore as an irreparable loss—without feeling convinced that the time is not far distant when the notion of a *vector* or *step*, as Clifford happily names it, and the simpler consequences of that notion forming a *vector* or *step*-geometry (the basis of the calculus of quaternions), must be made a part of the elementary studies of every student of mathematics, more especially for the purposes of mathematical physics, but perhaps not less for its application to pure geometry. And if this be so I cannot help thinking that our Association, extended as I have suggested, might be the means of bringing together the right men to organise the method and bring it into a suitable stage for elementary instruction . . . I refer to the improvement of the teaching of arithmetic. I suppose there are none of us here who have had any experience in the teaching of arithmetic, who have not often wished that they could make a *tabula rasa* of their pupils' minds, as regards this subject, so fatally destructive of all appeals to reason have early unintelligent teaching and bad traditional methods shown themselves to be. In an effort to reform in many points the teaching of arithmetic, we might naturally expect to associate with us the best teachers in preparatory and even in primary schools; and perhaps also members of that very important body of men, the Government Inspectors of Schools; and thus our organisation might become the means of linking together all grades of mathematical teachers, from the humblest to the highest, in an association which could not fail, if heartily supported, to become a powerful influence for good on the whole education of the country."

As the President's proposal took many of the members present by surprise, it was ultimately resolved, as we read, that a special meeting of the Association should be held about Easter next, to consider the desirability or the contrary of thus extending the scope of the Association.

In connection with this matter we have also received a letter addressed to non-members to ascertain, if such an extension of the aims of the Association were adopted, whether they would allow themselves to be proposed as members of the new Association. A draft of rules accompanies the Report, from which we extract the following proposed rules:—"That the Association be called 'The Association for the Improvement of Mathematical Teaching'; that its object shall be to effect improvements in the teaching of the various branches of elementary mathematics and mathematical physics by such means as may appear most suitable in each particular case. This object to be carried out by the reading of papers or raising discussions at meetings of the Association, by the appointment of committees to report on existing defects in the usual methods, order, range, &c., in teaching special subjects, and the expediency of drawing up syllabuses or text-books of such subjects; by the employment of suitable means for bringing the work done by the Association before the universities and other educational or examining bodies, and using its influence to obtain recognition of such work from those bodies."

Another action on the part of the meeting was the passing a resolution "that a sub-committee be appointed to draw up proofs of the propositions of the syllabus of plane geometry." It was shown that many teachers had adopted the syllabus, and that it was meeting with a growing acceptance was evidenced by the steadily improving annual sale, 2033 copies having been already sold.

ILLUSTRATIONS OF NEW OR RARE ANIMALS IN THE ZOOLOGICAL SOCIETY'S LIVING COLLECTION[1]

II.

NORTH-EASTERN ASIA has of late years disclosed to its explorers a number of very curious novelties in the class of Mammals. Amongst them are several species of great interest, examples of which have reached the Gardens of the Zoological Society alive.

4. The Tcheli Monkey (*Macacus Tcheliensis*) was so named by the distinguished zoologist, M. Alphonse Milne-Edwards of Paris, from the Chinese province of Tcheli (or Petcheli), in which it is found. The existence of a monkey in a latitude so far north—on nearly the same isothermal line as the city of Paris—is a very remarkable fact, and quite new to zoological distribution.

The occurrence of this monkey in the mountains of the north-eastern district of the province of Petcheli seems to have been first ascertained by M. Fontanier, who was for some years French Consul at Pekin, and who transmitted

[1] Continued from p. 38.

many valuable specimens to the Museum of the Jardin des Plantes at Paris. Amongst these was an example of the present animal—a female, not quite adult—which was described and figured by M. Alphonse Milne-Edwards in his "Études pour servir a l'Histoire Naturelle des Mammifères" (Paris, 1868-1874). The celebrated naturalist, Père David, also seems to have met with this monkey in the same district, as he includes it in several lists of the Mammals of Northern China which he has recently published.

For their pair of this scarce monkey now living in the Regent's Park, the Zoological Society are indebted to the kind exertions of one of their Corresponding Members, Dr. S. W. Bushell of H.B.M. Legation at Pekin. Dr. Bushell obtained these animals in 1880 from the Yung-ling, or Eastern Mausoleum, of the reigning Manchu dynasty, situated about 70 le from Pekin to the north of 40° N.L.

The Tcheli monkey belongs to the same section of the group as the well-known Rhesus monkey (*Macacus rhesus*), but has a shorter ta
rufous colour. It is also
dense coat of short thick
bitter winter climate of its
meter often descends 10°
congeners it is rock-loving
5. The Water-deer (*Hy*
Chinese animal which has
Europe.

Until of late years it w
production of deciduous b
the frontal bones was an inv
males of the deer-tribe (Ce
antlers might attain enorm
Wapiti (*Cervus Canadensis*)
in others they might consist
in the Pudu-deer of Chili
were always present to a grea
covery of this little animal

FIG. 4.—The Tcheli Monkey.

the truth of the axiom, that in Nature at least there is no law without an exception. Here we have a deer complete in everything except its antlers, usually the *most* characteristic feature in the males of these animals. In place of antlers the buck Water-deer is provided with other organs of defence in the shape of two long exserted canine teeth, which grow to a considerable size in the adult, and give him ample means of exercising his pugnacious powers.

For our first knowledge of the existence of this singular deer we are indebted to the exertions of the late Robert Swinhoe, who, during his residence in various parts of the Chinese Empire, added so largely to our knowledge of every part of its fauna. Mr. Swinhoe obtained his first specimens of the *Hydropotes* in the market of Shanghai in the winter of 1879, and described it at one of the meetings of the Zoological Society in the following year.

"In the large riverine is
Chinkiang," Mr. Swinhoe te
in large numbers, living am
there grown for thatching
rushes are cut down in the
swim away to the main sho
the hills.

"In autumn, after the
again grown, they return wi
winter through. They are
sprouts and coarse grasse
finish off with a dessert from
&c., which the villagers cu
winter.

"They cannot however d
or they would not be suffere
they do; for the islands ha
numerous agricultural popu

xtraordinary dislike for their
only killed for the European
rice. The venison is coarse
t is considered tolerable for
only venison procurable in
lf gives sport to the gunner;
every winter by the European
me of *sport*. Their numbers
much thinned."
characteristic of these antler-

less deer is their extraordinary fecundity. Mr. Swinhoe states that according to the testimony of the natives the mothers have four or five young at a birth, and that this is corroborated by Europeans who have killed gravid females and found the like number of embryos in the uterus. This account is to some extent confirmed by observations on the Water-deer in captivity in Europe. Although the Zoological Society have not succeeded in inducing this animal to breed in the Regent's Park, this feat has been accomplished by M. Josephe Cornély of the

FIG. 5.—The Water-deer.

rs, in France—one of the
rs" in Europe. In M.
these deer produced three
1879, two of which, it is
urity. There can be no
deer is much more fruitful
rs, which certainly never
th, and for this reason at
al for domestication.
ng reached at its shoulder

a height of about twenty inches, and is generally of a pale fawn-colour, paler below.

According to Mr. Swinhoe the "Chinese at Shanghai call this animal the *Ke*; but at Chinkiang it is named *Chang*—the classical term for the Muntjac (*Cervulus Reevesi*). The Chinese dictionary, compiled under authority of the Emperor *Kanghe*, describes the *Ke* as 'stag-like, with feet resembling those of a dog, has a long tusk on each side of the mouth, and is fond of fighting.'"

TY OF THE COREAN LAGO'

consists of a number of
ds separated by a depth
fifty fathoms, lies off the
a of Corea. Whilst many
two to six miles in their
considerable height: their
vation generally ranging
above the sea—Ross or
rest corner of the archi-
of as much as 1935 feet.
of rock which crown their
a somewhat rugged and

uninviting aspect: and their quaint inhabitants view with ill-concealed dislike the presence of foreign ships within their waters.

I was enabled to land on two occasions on the Island of Mackau—the largest of a group of islands bearing that name. About six miles in length, it possesses some half-dozen lofty peaks, which range in height from 800 or 900 feet to 1400 feet above the sea. Naked masses of quartzite or quartz-rock crown the summits and often compose the upper third of the hills, whilst a thick and dense growth of creepers, shrubs, and mimosas clothes the hill-slopes for their lower two-thirds. The quartzite passes insensibly into a compact quartzitic sandstone underlying it; and lower down this rock assumes a coarse-grained texture, occasionally containing pebbles of quartz embedded in it. From the nature of the ground it was difficult to find

forest to these islands in October.

trustworthy signs of bedding in these rocks. Cropping out in the lower third of the hills—from the cliffs and the slopes immediately above them—are beds of a highly micaceous rock—greisen—and a gneissose rock sometimes approaching in its characters the typical gneiss; these beds are inclined at an angle of 15° to the east-north-east. Veins of quartz are observed to traverse both these rocks, whilst occasionally a layer of quartz—an inch in thickness—separates contiguous beds.

I had no opportunity of landing on any other islands of the archipelago, many of which in their general appearance resemble that of the Island of Mackau.

H. B. GUPPY

NOTES

THE International Medical Congress which it is proposed to hold in London in the beginning of August will be the seventh of its kind. The previous meetings have been held biennially in the principal university towns of the Continent. At the last meeting in Amsterdam in 1879, a general wish was expressed that the next should be in England, and the wish having been informally communicated to the Presidents of the College of Physicians and the College of Surgeons, they called a meeting of presidents or other delegates of all the Univerities, Medical Corporations, Public Medical Services, and the Medical Societies. The proposal to hold the Congress in London was heartily agreed to, and an Executive Committee was appointed under who-e direction, and, especially, by the energy of the General Secretary, Mr. MacCormack, a very large scheme has been arranged for the discussion of the most interesting questions in all the divisions of the Medical Sciences. The Meetings will be held in fifteen sections, in rooms of most of which the use has been granted by the University of London, the Royal Academy, and all the learned Societies at Burlington House. Others have been engaged at Willis's Rooms. The officers and councils of the several sections include, with very few exceptions, all the chief and most active teachers and workers in the several subjects of medical science and practice, not in London alone, but in all the universities and great towns in the United Kingdom. In so far as general consent to the design of the Congress may be regarded as a promise of success, all looks well, and the agreement of our own countrymen is well matched by the assurances of co-operation already received from a large number of the most distinguished medical investigators and practitioners in both the Old World and the New. About 4000 invitations were issued, and it is expected that the roll of members will include at least 2000 names. Of course there are large arrangements for receptions and various hospitalities, and for making London as agreeable and instructive as may be in August; but if the design in the programme of the Congress be fairly fulfilled, a great quantity of hard and useful scientific work will be well done.

AT a meeting of the American Academy of Arts and Sciences held in Boston, Massachusetts, on January 12, the Rumford medal was conferred on Prof. Josiah Millard Gibbs, of Yale College, for his researches on Thermodynamics.

WE regret to hear of the death of Prof. James Tennant, F.G.S., the well-known mineralogist. Mr. Tennant was the assistant and afterwards the successor of Mr. Mawe, author of "Travels in Brazil," and of a "Treatise on Diamonds," and by adding to the series obtained by Mr. Mawe many fine specimens from every part of the globe, succeeded in thus forming a very large and valuable collection of minerals. Mr. Tennant was an excellent authority on gems, and his advice was taken by the Government with respect to the cutting of the Koh-i-Noor and other crown jewels. Besides holding the office of "Mineralogist to the Queen," Mr. Tennant was for many years Professor of Geology and Mineralogy in Kin
resigned the professorship of
the post of Professor of Minera
of his death. Mr. Tennant, in
Ansted and the Rev. W. O.
Geology, Mineralogy, and Cryst
the Sciences," and he was al
educational works. Mr. Ten
preparing collections of mineral
tional purposes; and by popula
aided in disseminating a knowl
he was so greatly interested. M
of seventy-three at the time of h

PROF. MARTIN DUNCAN, F.
of the Royal Microscopical Soci

THE *Daily News* Naples cor
to the Zoological Station at Na
naturalists working in the labora
five, but this year it will be al
permanent staff of the station,
naturalists bent upon promotin
zoology and botany, while enjo
and elaborate technical arrang
contrived. The use of the di
naturalists to find marine plants
and on the undersides of overhang
never have been brought to light
them. By this means many inte
been brought nearer to a solutio

COLONEL PREJEWALSKI has
with a fine botanical collection
Maximowicz states that upon a c
impression is strengthened that
flora of China, but with an altog
the border of the great Central
Chinese forms of trees or shru
The general character is entire
Maximowicz thinks that this Ce
with a distinct individuality of i
the Tangut flora, from the nam
explorer, Marco Polo, to the p
and inaccessible region.

THE arrangements for the int
exhibition of the Parkes Muse
held at South Kensington from
complete. The exhibition is t
service for the prevention, det
disease.

THE Clarendon Press is abou
late Admiral W. H. Smythe's
book which by universal conse
popular astronomy in England
The new edition has been edi
F.R.A.S., whose "Handbook
don Press book, is well known,
only a new edition, may be reg
Whereas the original edition
new one comprises no fewer tha
the number of the objects dealt w
edition will consist. It will be
down here, expanded there, a
Smythe's printed matter, so as
science down to the year 1880.
hundreds of double-stars annu
and many of them annually u

been called upon to perform is not all. Admiral Smythe's in England, his labours only ube which were visible in Eng- ans of materials gathered from the book to the whole of the ns made it an observer's hand- king populations of India and ntinents. The New "Cycle" umber of double-star measures them as recent as 1880. The uniformly set out for the epoch he book will be up to date for thograph of twenty four typical our intended for the methodical ppropriate frontispiece.

actory report from the Sunday interesting experiment in Edin- ol, in which ninety-two pupils attendance from November to mostly of the artisan class and s hours, could not avail them-

gets" who have lately been to ugh House are being taken by a, under the direction of the essful casts of the mouths, dentition, have been obtained xhibited in the library of the ing.

ity Exhibition Commission in ounced that arrangements had ustry being lighted up during d foreign systems concurrently. and more than 50 kilometres e classes, viz.—1. Production l'electricité; 3. electro-métrie; mécanique générale dans ses ques; 6. Bibliographie et his- to the Municipal Council of ns the concession of an elec- e, in the Bois de Boulogne, incurred by the construction Consuls to the Exhibition nstructed on a viaduct, the rances, and it is impossible to the 107 days of the exhibition, listance by electricity will be ring the Electrical Exhibition. floor will be utilised to work will do various kinds of work. direction of MM. Hachette, electrical publications, and a e admitted all the scientific f their language.

sking the census of our vast e have been sometimes very erations in the interior created Karens, who were doing all The native officials employed hown their zeal in a curious a census enumerator in the book a certain old tomb as a he phrase "to be numbered ear a new and vital meaning; majority. Another anecdote states that when the census commissioner entered a certain compound with the forces of enumeration in his train, an ayah who had been taken account of by enumerator and supervisor both, ran excitedly to her mistress and warned her that there would be certainly some mistake in the hisab, for that the sirkar had counted her twice already and was going to count her again!

In a note on the Russian and Siberian varieties of the *Gammarus pulex* (*Memoires* of the St. Petersburg Society of Naturalists, vol. xi. fasc. 1) M. Semenovsky shows that the representatives of this species in Lake Baikal and in Lake Goktcha of High Armenia, 6400 feet above the sea-level, are quite identical, and most akin to the Norwegian typical representative of this species, described by Prof. Sars. On the contrary, the *G. pulex*, which inhabits the lakes of the Taimyr *tundras* of Northern Siberia, that of the Baraba Steppe in Western Siberia and of the Ural region, belongs to another variety. A second variety, very different from the two preceding, was discovered in two salt lakes of the Government of Orenburg, notwithstanding the close proximity of one of these lakes to those of the Ural region. A third variety inhabits the northern lakes of European Russia and those of the Valdai Hills, whilst a fourth variety, being most like to that which is known from the lakes of Savoy, was discovered in the lakes near St. Petersburg.

It is known that the young horns of the *Cervus maral* (Severtzoff), when they are filled with blood and not yet ossified, are very much prized by the Chinese, who purchase them at the Siberian frontier, paying as much as six to twenty pounds the pair. A very active chase of the maral has therefore always been carried on in Siberia, and since it became rather rare, the Cossacks in the neighbourhood of Kiakhta have domesticated this stag. Now we learn from a communication by M. Polakoff that its domestication has greatly extended in Western Siberia, so that there are herds of seventy head; but the horns of the domesticated deer, as might be expected, have lost a good many of their original qualities.

In a recently-discovered stalactite cave at Kirchberg, near Kremsmünster (Austria), a jaw-bone of a man with well-preserved teeth was found among numerous remains of *Ursus spelæus*.

It is reported from Stuttgart (Wirtemberg) that bones of mammoth and rhinoceros have been brought to light by digging in a cellar on loamy ground. Dr. Fraas has recognised, besides ribs (60 cm. and 200 cm. long), two pieces of a jaw-bone belonging to a mammoth, and parts of mandibles, scapula, and maxilla of a rhinoceros.

The Mineralogical Museum at Breslau University has received a large number of bones belonging to the woolly-haired Rhinoceros (*Rhinoceros tichorhinus*). They were found near Skarsine in Silesia. The complete skeleton was found in a marl-pit at a depth of sixteen feet. Unfortunately the skull and several bones were broken through inattention on the part of the workmen. This is the fifth skeleton of the kind found in Silesia.

On February 20 a slight shock of earthquake occurred at Agram at 2h. 15m. a.m., and a more severe one at 6h. 15m. a.m., accompanied by a subterranean noise. During the last week wave-like motions were also felt.

The *Daily News* Lisbon correspondent, telegraphing on February 23, states that thirty-six successive shocks of earthquake have been experienced at St. Michael's in the Azores. "The church and 200 houses fell in. Several people were killed. A religious and penitential procession had taken place, the Civil Governor at the head. A volcanic island has been formed. At latest advices slight shocks continued. Many people were in tents outside the town."

THE Khedive of Egypt has nominated M. Gaston Maspero to the directorship of the museums in the place of the late archæologist, M. Mariette. To the latter a monument is to be erected at Cairo. A committee has already been formed, of which the Foreign Minister is president.

A NEW Italian serial will shortly be published at Naples. Its title will be *Rassegna critica di opere scientifiche e letterarie*, and its editor Prof. Andrea Angiulli. It will appear six times a year.

LAST Thursday the Hackney Microscopical and Natural History Society held their annual *soirée*, always a very successful event. Many other similar London societies were represented at the meeting.

AN elaborate report upon the opening up of two of the pyramids at the boundary of the Libyan Desert near Sakkara is now published by Prof. Brugsch. The learned professor estimates the matter to be of the most important and valuable kind. At the close of 1880 the entrances to the sepulchral chambers of the three pyramids were laid bare. The ceilings were taken off, and only the two sides, all covered with hieroglyphics, rose from the *débris*. The hieroglyphics point to the reign of Pharaoh Apappus.

THE additions to the Zoological Society's Gardens during the past week include a Bactrian Camel (*Camelus bactrianus*) from Afghanistan, presented by Col. O. B. C. St. John, R.E., F.Z.S.; a Punjaub Wild Sheep (*Ovis cycloceros*) from Afghanistan, presented by Capt. W. Cotton; a Mona Monkey (*Cercopithecus mona*) from West Africa, presented by Mr. W. Macmillan Scott; two Common Peafowls (*Pavo cristatus*) from India, presented by Mrs. Edward Brown; a Roseate Cockatoo (*Cacatua rosicapilla*) from Australia, presented by Miss Mary J. Richardson; a Stump-tailed Lizard (*Trachydosaurus rugosus*) from Australia, presented by Mr. F. O. Maitland; a Horsfield's Tortoise (*Testudo horsfieldi*) from Cabul, deposited; two Globose Curassows (*Crax globicera*) from Central America, a White-browed Amazon (*Chrysotis albifrons*) from Honduras, purchased.

GEOGRAPHICAL NOTES

WE take the following from the March number of the *Proc.* of the Royal Geographical Society:—The eminent Russian traveller and *savant*, Col. Prejevalsky, intends, we are informed, to devote himself for some time to the preparation in retirement of a great work on the results of his travels, including, besides his recent expedition to Tibet, his previous journey to Lob-nor, of which he was prevented, by want of time, from giving more than a bare outline. The work is to consist of eight volumes, and to be entitled "Travels in the Deserts of Central Asia." Volumes i. and ii. will contain the narrative and an account of the physical geography and ethnography of the countries he has visited, and will include also his surveys, the pictorial illustrations being from original sketches by his companion, Lieut. Robarofsky. Vol. iii. will be devoted to the mammalia of Central Asia; vol. iv. to the birds; vol. v. to the reptiles, amphibia, and fishes; vol. vi. to the flora of Mongolia; and vol. vii. to that of Tibet. Vol. viii. and last will contain the geology and mineralogy as far as materials will permit. The first two volumes, each containing 500 pages, and perhaps more, will be written by the traveller himself, and will appear towards the close of 1882. The ornithology will also proceed from his pen, as well as that portion of the zoology which treats of the antelope, buffalo, and a few other of the more important animals. The remainder will be written by the Academicians Strauch and Maximovitch, Professors Kepler, Inostrantsef, and Bogdanof, and will be issued in parts. The whole will not be completed for several years. The work will be brought out under the auspices of the Geographical Society, and a special grant for the purpose will be asked for from H.M. the Emperor.

AT the Geographical Society on Monday evening Sir Richard Temple delivered a lecture on the lake-region of Sikkim on the frontier of Tibet, which, in point of fact, was a description of the impressions acquired during a tour which he made as Lieu... Governor of Bengal. Sir R. Temple told his audience that t... fact of any part of Sikkim being British territory was due to t... imprisonment of Sir Joseph Hooker and Dr. Campbell by t... Rajah; and he then gave a geographical sketch of the whol... region. Possibly the most important matter dealt with was t... construction of the politico-commercial road from Darjiling ... the Jyalap Pass into the Chumbi Valley, which Sir R. Temp... considers the frontier-line between British and Chinese territ... Sir R. Temple is apparently sanguine that the Tibetans w... continue the road on to Lhasa, but he did not say when th... were likely to do so. Mr. W. T. Blanford, who had a... visited Sikkim, afterwards explained to the meeting that ... believed these lakes to be due to glacial action, and that t... Bidan Tso was a beautiful specimen of this kind of lake. M... Blanford also called attention to the opening afforded ... exploration in Northern Sikkim, which has not as yet be... visited by Europeans.

WE understand that Mr. Joseph Thomson has been elec... a life-member of the Royal Geographical Society, in furth... recognition of his eminent services to geography during ... recent East African expedition. The Council of the Soci... have presented to the British Museum the collection of sk... which he made during his journey.

THE *Oesterreichische Monatschrift für den Orient* of t... month contains a highly interesting paper by Prof. H. Vambé... on the proposed Hyrkanian railway, a valuable description ... the roads and land communications of Persia by Baron Göl... Lannoy in Tcheran, a paper on the coffee districts of Yem... by Baron Schweiger-Lerchenfeld, besides two well-writt... historical papers.

AT the last meeting of the Berlin Geographical Society Pr... W. Förster, the director of the Berlin Observatory, made ... interesting communication regarding one of the most import... tasks of travellers in unknown regions, &c., the exact determi... tion of latitude, longitude, and elevation above sea-level. W... several of the results of recent German expeditions scie... errors in this regard were detected. Prof. Förster stated t... the Berlin Observatory staff would shortly be in a position ... undertake the practical and theoretical instruction of travell... and to superintend the selection, testing, and packing of t... necessary scientific instruments for the various expeditions bef... starting.

THE last number of the *Tour du Monde* contains an inte... ment of Dr. Crevaux's account of his journey from Cayenne ... the Andes, the present part dealing more particularly with t... exploration of the River Parou. The illustrations are fro... original sketches, and are admirably drawn.

IN a recent issue *Les Missions Catholiques* publishes a lett... from a missionary among the Kakhyens, which contains so... interesting notes concerning that comparatively unknown peopl...

A SYDNEY telegram states that a bushman named Skulthor... has telegraphed from Blackall asserting that he has found t... explorer Leichhardt's grave, and has recovered the diary of t... whole of his last expedition, together with other relics. Sku... thorpe refuses to show any of the articles until his arrival i... Sydney.

THE last number of *Le Globe* contains part of a paper entitle... "Tartarie," by M. F. de Morsier, in which the writer propose... to deal with the Tartar, Turcoman, and Kirghiz steppes.

BY a telegram from Brisbane we learn that the Queensland... Government expedition for the survey of the projected Trans... continental railway started on January 14, presumably from ... Blackall. A previous survey, it will be remembered, was ... made by a party under Mr. Favenc, despatched by the proprietor... of the *Queenslander*, but so far as we are aware no detailed ... account of his explorations has ever been made public, and ... possibly the new expedition has been sent to endeavour to find ... a better line of route.

THE Wellington correspondent of the *Colonies and India* ... states that the Southern Alps and other of the principal mount... tains of New Zealand are to be explored next year by members ... of the Alpine Club, who will find ample scope for their energies. ... The top of Mount Cook, the loftiest peak in New Zealand, ... between 13,000 and 14,000 feet in height, has not yet been ... reached.

THE International Alpine Congress will meet at Salzburg in ... 1882. The committee is now being formed.

ON THE VISCOSITY OF GASES AT HIGH EXHAUSTIONS[1]

BY the viscosity or internal friction of a gas is meant the resistance it offers to the gliding of one portion over another. In a paper read before the British Association in 1859 Maxwell[2] presented the remarkable result that on theoretical grounds the coefficient of friction, or the viscosity, should be independent of the density of the gas, although at the same time he stated that the only experiments he had met with on the subject did not seem to confirm his views.

An elaborate series of experiments were undertaken by Maxwell to test so remarkable a consequence of a mathematical theory; and in 1866, in the Bakerian lecture for that year,[3] he published the results under the title of "The Viscosity or Internal Friction of Air and other Gases." He found the coefficient of friction in air to be practically constant for pressures between 30 inches and 0·5 inch; in fact numbers calculated on the hypothesis that the viscosity was independent of the density agreed very well with the observed values.

The apparatus used by Maxwell was not of a character to admit of experiments with much lower pressures than 0·5 inch.

Maxwell's theory that the viscosity of a gas is independent of the density presupposes that the mean length of path of the molecules between their collisions is very small compared with the dimensions of the apparatus; but inasmuch as the mean length of path increases directly with the expansion, whilst the distance between the molecules only increases with the cube root of the expansion, it is not difficult with the Sprengel pump to produce an exhaustion in which the mean free path is measured by inches, and even feet,[4] and at exhaustions of this degree it is probable that Maxwell's law would not hold.

The experiments recorded in this paper were commenced early in 1876, and have been continued to the present time. In November, 1876, the author gave a note to the Royal Society on some preliminary results. Several different forms of apparatus have since been used one after the other, with improvements and complexities suggested by experience or rendered possible by the extra skill acquired in manipulation. The earlier observations are now of little value, but the time spent in their prosecution was not thrown away, as out of those experiments has grown the very complicated apparatus now finally adopted.

The Viscosity Torsion Apparatus, with which all the experiments here given have been performed, is a very complicated instrument. It consists essentially of a glass bulb, blown with a point at the lower end, and sealed on to a long narrow glass tube. In the bulb is suspended a plate of mica, by means of a fine fibre of glass 26 inches long, which is sealed to the top of the glass tube, and hangs vertically along its axis. The plate of mica is ignited and lamp-blacked over one-half. The tube is pointed at the upper end, the upper and lower points are 46 inches apart, and are accurately in the prolongation of the axis of the tube. Sockets are firmly fixed to a solid support, so that when the tube and bulb are clamped between them they are only able to move around the vertical axis. The glass fibre being only connected with the tube at the top, rotating the tube on its axis communicates torsion to the fibre, and sets the mica plate swinging on the same axis without giving it any pendulous movement. The diameter of the fibre is about 0·001 inch. The viscosity apparatus is connected to the pump by a flexible glass spiral, so as to allow the apparatus to rotate on the pivots and at the same time to be connected to the pump altogether with sealed glass joints. An arm working between metal stops limits the rotation to the small angle only which is necessary.

The torsional movement given to the mica plate by the light of the candle shining on it or by the rotation of the bulb and tube on its axis by the movement of the arm between the stops, is measured by a beam of light from a lamp, reflected from a mirror to a graduated scale.

The pump employed has already been described. The measuring apparatus is similar to that described by Prof. McLeod[1] before the Physical Society, June 13, 1874. As it contains several improvements shown by experience to be necessary when working at very high vacua, a detailed description is given in the paper.

When taking an observation the arm is moved over to the stop, and in a few seconds allowed to return to its original position by the action of a spring. This movement rotates the viscosity apparatus through a small angle, and sets the mica plate vibrating, the reflected line of light traversing from one side of the scale to the other in arcs of diminishing amplitude till it finally settles down once more at *zero*.

The observer watching the moving index of light records the scale number reached at the extremity of each arc. The numbers being alternately on one and the other side of zero are added two by two together, to get the value of each oscillation. The logarithms of these values are then found, and their differences taken; the mean of these differences is the logarithmic decrement per swing of the arc of oscillation. For the state of brevity this is called the log dec.

A very large number of experiments have been made on the viscosity of air and other gases. Observations have been taken at as high an exhaustion as 0·02 M, but at these high points they are not sufficiently concordant to be trustworthy. The pump will exhaust to this point without difficulty if a few precautions are taken, but at this low pressure the means of measuring fail in accuracy.

The precautions which experience shows to be necessary when exhausting to the highest points are fully described in the paper.

Viscosity of Air.—The mean of a very large number of closely concordant results gives as the log decrement for air for the special apparatus employed, at a pressure of 760 millims. of mercury and a temperature of 15° C., the number 0·1124. According to Maxwell the viscosity should remain constant until the rarefaction becomes so great that we are no longer at liberty to consider the mean free path of the molecules as practically insignificant in comparison with the dimensions of the vessels.

The author's observations show that this theoretical result of Maxwell's is at least approximately and may be accurately true in air up to comparatively high exhaustions; and that at higher exhaustions the viscosity falls off, as it might be expected to do according to theory.

The results are embodied in a table and diagrams.

The first half of the table gives the viscosity of air, in so far as it is represented by the log dec., at pressures intermediate between 760 millims. and 0·76 millim. (1000 millionths of an atmosphere). In order to avoid the inconvenience of frequent reference to small fractions of a millimetre, the millionth of an atmosphere[2] (= M) is now taken as the unit instead of the millimetre. The second half of the table is therefore given in millionths, going up to an exhaustion of 0·02 millionth of an atmosphere.[3]

Starting from the log dec. 0·1124 at 760 millims., the viscosity diminishes very regularly, but at a somewhat decreasing rate. Between 50 millims. and 3 millims. the direction is almost vertical, and a great change in the uniformity of the viscosity curve commences at a pressure of about 3 millims. At this point the previous approximation to, or coincidence with, Maxwell's law begins to fail, and further pumping considerably reduces the log decrement.

From 1000 M the diminution of viscosity is very slight until the exhaustion reaches about 250 M; after that it gets less with increasing rapidity, and falls away quickly after 35 M is reached.

The curves of increasing mean free path and diminishing viscosity closely agree. This agreement is more than a mere coincidence, and is likely to throw much light on the cause of viscosity of gases.

[1] Abstract of a paper read before the Royal Society, February 17, 1881, by William Crookes, F.R.S.

[2] *Phil. Mag.*, 4th ser. vol xix. p. 31.

[3] *Phil. Trans.* 1866, part 1, p. 249.

[4] Thus, supposing the mean free path of the molecules of air at the ordinary pressure is the 1-10,000th of a millimetre, at an exhaustion of the ten-thousandth of an atmosphere, the mean free path will be 1 millim. At one-millionth of an atmosphere the mean free path will be 10 centimetres, and at an exhaustion of one hundred millionth—by no means a difficult point to attain with present appliances—the mean free path will be over 30 feet. This rarefaction corresponds to that of the atmosphere at a height above the earth of a little more than ninety miles, assuming that its density decreases in geometrical progression as its height increases in arithmetical progression, and neglecting the small corrections for diminished gravity and temperature. As the height above the earth increases, the length of the mean free path of the molecules of air rapidly approaches to planetary distances; at about 200 miles height the mean free path is 10 million miles, whilst between eighty and ninety miles higher the rarity is such that the mean free path would extend from here to Sirius.

[1] *Philosophical Magazine*, vol. xlvii. p. 110, August, 1874.

[2] M = 0·00076 millim.; 1315·789 M = 1 millim.

[3] To give some idea of the high exhaustions at which its measurements can be taken it may be mentioned that the highest exhaustion on the table—0·02 M—bears about the same proportion to the ordinary atmospheric pressure that 1 millimetre does to thirty miles, or, converting it into time, that one second bears to twenty months.

In the table is also given the measurements of the repulsion exerted on the blackened end of the mica plate by a candle-flame placed 500 millims. off. The repulsion due to radiation commences just at about the same degree of exhaustion where the viscosity begins to decline rapidly, and it principally comes in at the exhaustions above 1000 M.

The close agreement between the loss of viscosity and the increased action of radiation is very striking up to the 35 millionth, when the repulsion curve turns round and falls away as rapidly as the viscosity.

Experiments are next described on the resistance of air to the passage of an induction spark.

Since the publication of the author's researches on the phenomena presented by the passage of the induction discharge through high vacua, the present results—which, although never published, precede by a year or two those just mentioned—have lost much of their interest.

The phenomena at the very high exhaustion of 0·02 M may be of interest. With a coil giving a spark 85 millims. long, no discharge whatever passes. On increasing the battery power till the striking distance in air was 100 millims. the spark occasionally passed through as an intermittent flash, bringing out faint green phosphorescence on the glass round the end of the — pole.

On one occasion the author obtained a much higher exhaustion than 0·02 M. It could not be measured, but from the repulsion by radiation and the low log dec. it was probably about 0·01 M. The terminals of the vacuum tube and wires leading to them were well insulated, and the full power of a coil giving a 20-inch spark was put on to it. At first nothing was to be seen. Then a brilliant green light flashed through the tube, getting more and more frequent. Suddenly a spark passed from a wire to the glass tube, and pierced it, terminating the experiment.

Since these experiments vacua have frequently been got as high, and even higher, but the author has never seen one that would long resist a 20-inch spark from his large coil.

Viscosity of Oxygen.—The series of experiments with air show a complete history of its behaviour between very wide limits of pressure. It became interesting to see how the two components of air, oxygen and nitrogen, would behave under similar circumstances. Experiments were therefore instituted exactly as in the case of dry air, but with the apparatus filled with pure oxygen.

The results are given in the form of tables and plotted as curves on diagrams.

The figures show a great similarity to the air curve. Like it the log dec. sinks somewhat rapidly between pressures from 760 millims. to about 75 millims. It then remains almost steady, not varying much till a pressure of 16 millims. is reached. Here however it turns in the opposite direction, and increases up to 1·5 millim. It then diminishes again, and at higher exhaustions it rapidly sinks. This increase of viscosity at pressures of a few millimetres has been observed in other gases, but only to so small an extent as to be scarcely beyond the limits of experimental error. In the case of oxygen however the increase is too great to be entirely attributable to this cause.

Oxygen has more viscosity than any gas yet examined. The viscosity of air at 760 millims, being 0·1124, the proportion between that of air and oxygen, according to these results, is 1·1185.

This proportion of 1·1185 holds good (allowing for experimental errors) up to a pressure of about 20 millims. Between that point and 1 millim. variations occur, which have not been traced to any assignable cause; they seem large to be put down to "experimental errors." The discrepancies disappear again at an exhaustion of about 1 millim., and from that point to the highest hitherto reached the proportion of 1·1185 is fairly well maintained.

Viscosity of Nitrogen.—The proportion between the viscosities of nitrogen and air at a pressure of 760 millims is, according to these experiments, 0·9715.

A comparison of the air curves with those given by oxygen and nitrogen gives some interesting results. The composition of the atmosphere is, by bulk,

Oxygen	20·8
Nitrogen	79·2
	100·0

The viscosity of the two gases is almost exactly in the same proportion: thus at 760 millims—

$$\frac{20{\cdot}8 \textit{ vis. } O + 79{\cdot}2 \textit{ vis. } N}{100}$$

$$\frac{20{\cdot}8\,(0{\cdot}1257) + 79{\cdot}2\,(0{\cdot}1092)}{100}$$

$$\frac{2{\cdot}61456 + 8{\cdot}64072}{100}$$

a result closely coinciding with 0·1124, th
for air. Up to an exhaustion of about 30
between the viscosities of air, oxygen, and
with but little variation. From that po
between the individual curves of the thr

Observations on the Spectrum of Nitroge
tions during exhaustion give the following

At 55 millims. pressure the band spect
mences to be visible. The red and yellow
and the green and blue are exceedingly fa
grows less the bands become more distinct,
the band spectrum is at its brightest.

At a little higher exhaustion a change co
and traces of the line spectrum are observe

At 812 M both the band and the line s
very brilliantly.

At 450 M the line spectrum is seen in g
exhaustion becomes higher the lines comm
the two ends of the spectrum.

At 188 M the lines below λ 610 ms. of
and above λ 400, cease to be visible.

At 94 M a bright greenish yellow lin
λ 567.

At 55 M this greenish yellow line is still
red lines have disappeared altogether, and
visible is one at λ 419. The line 567 varie
sometimes it cannot be seen, whilst at oth
Thus—

At 40 M the line 567 has quite disappear

At 17 M line 567 is visible again, being
line left.

At 12 M line 567 is not seen, although se
blue lines are left.

At 3 M only three lines are visible in the
very faint.

At 2·8 M line 567 is detected again.

At 2 M only traces of one or two lines ca
light of the lines being overpowered by th
cence of the glass.

Line 567 has been seen on several occasio
tions when the gas under examination has be
air. It is probably a nitrogen line, for one
nitrogen lines has a wave-length of 567
(Huggins), or 568·1 (Plücker), and the a
curve is not sufficiently accurate to enable
line entered in as being at 567 may not
higher. The reason of its being only so
be accounted for by a difference in the sens
at different times, or by a difference in ba
however cannot be the whole explanation, f
found to vary in the same manner.

The curve of Repulsion exerted by Radi
than in oxygen or air, and sinks rapidly af
passed.

Viscosity of Carbonic Anhydride.—The c
given in diagrams plotted from the observ
curve seems to follow the same direction as
at a pressure of about 620 millims. it slopes
pressure is reduced to about 50 millims., w
takes the direction of the air curve. T
between 760 millims. and 1 millim. is nearly

Observations have also been taken wi
during the exhaustion of carbonic anhydri
brilliancy of the spectrum occurs at an
300 M. After that it gets fainter; at about
(λ 409 to 408 ms. of mm.) disappears; as
higher the other bands vanish until, at a vac
nothing is visible but the two lines λ 519 an
exhaustions these lines disappear, and
"Radiant Matter" commence.

The proportion between the viscosity of
and air at 760 millims. is 0·9208.

Viscosity of Carbonic Oxide.—The results with this gas are remarkable as showing an almost complete identity with those of nitrogen both in position and shape. The viscosity at 760 millims. is in each case 0·1092.

Like that of nitrogen the curve of carbonic oxide is seen to be vertical—*i.e.*, assuming the curve to represent the viscosity, the gas obeys Maxwell's law, at pressures between 90 millims. and 3 millims. The straight portion in nitrogen is at a little higher pressure—between 100 millims. and 6 millims.

The curve of repulsion resulting from radiation is lower in carbonic oxide than in any other gas examined, and, unlike the other gases, there is no sudden rise to a maximum at about 40 M. At lower exhaustions the curve is, however, higher than it is in nitrogen.

During exhaustion observations were continued on the variations in the spectrum. The ordinary band spectrum is first seen with a few sharp lines terminating the bands.

At 12 millims. pressure a sharp green line is first seen, λ 515 ms of mm. This line rapidly grows brighter as exhaustion continues, and then fades out; it is last seen at a pressure of about 0·9 millim. This line is probably the bright oxygen-line, the wave-length of which is given by Plücker at 514·4.

At a pressure of 2·8 millims. the spectrum agrees in appearance with the "Carbon No. 2" in Watts's "Index of Spectra."

At 553 M the bands between the sharp lines appear to be breaking up into masses of fine lines.

At 211 M these fine lines are distinctly visible. The brightness of this spectrum is now near its maximum.

At 100 M the general spectrum is growing faint, but a sharp green line at λ 534 makes its appearance by fits and starts. This is coincident with Plücker's bright oxygen line λ 534.

After this degree of exhaustion the spectrum rapidly gets fainter. The line λ 534 soon disappears, and the carbon lines also go one after the other, until at an exhaustion of 4 M only two lines are visible, λ 560 and λ 519.

Viscosity of Hydrogen.—It has been found that hydrogen has much less viscosity than any other gas; the fact of the log dec. not decreasing by additional attempts at purification is the test of its being free from admixture. This method of ascertaining the purity of the gas, by the uniformity of its viscosity coefficient at 760 millims., is more accurate than collecting samples and analysing them eudiometrically.

Several series of observations in hydrogen have been taken. For a long time it was considered that hydrogen, like other gases, showed the same slight departure from Maxwell's law of viscosity being independent of density that appeared to be indicated with other gases; for the log dec. persistently diminished as the exhaustion increased, even at such moderate pressures as could be measured by the barometer gauge. Had it not been that the rate of decrease was not uniform in the different series of observations, it might have been considered that this variation from Maxwell's law was due to some inherent property of all gases. After working at the subject for more than a year it was discovered that the discrepancy arose from a trace of water obstinately held by the hydrogen. Since discovering this property extra precautions (already described at the commencement of the paper) have been taken to dry all gases before entering the apparatus.

The remarkable character of hydrogen is the uniformity of resistance which it presents. It obeys Maxwell's law almost absolutely up to an exhaustion of about 700 m., and then it commences to break down. Up to this point the line of viscosity is almost perfectly vertical. It then commences to curve over, and when the mean free path assumes proportions comparable with the dimensions of the bulb and approaches infinity, the viscosity curve in like manner draws near the zero line.

The repulsive force of radiation is higher in hydrogen than in any other gas. It commences at as low an exhaustion as 14 millims., but does not increase to any great extent till an exhaustion of 200 M is attained; it then rises rapidly to a maximum at between 40 and 60 M, after which it falls away to zero. The maximum repulsion exerted by radiation in hydrogen is to that in air as 70 to 42·6. This fact is now utilised in the construction of radiometers and similar instruments when great sensitiveness is required.

Taking the viscosity of air at 760 millims. as 0·1124, and hydrogen as 0·0499, the proportion between them is 0·4439.

The Spectrum of Hydrogen.—The red line (λ = 656), the green line (λ = 486), and the blue line (λ = 434) are seen at their brightest at a pressure of about 3 millims., and after that exhaustion they begin to diminish in intensity. As exhaustion proceeds a variation in visibility of the three lines is observed. Thus at 36 millims. the red line is seen brightly, the green faintly, whilst the blue line cannot be detected. At 15 millims. the blue line is seen, and the three keep visible till an exhaustion of 4·18 M is reached, when the blue line becomes difficult to see. At 3·8 M only the red and green lines are visible, the red being very faint. It is seen with increasing difficulty up to an exhaustion of 2 M, when it can be seen no longer. The green line now remains visible up to an exhaustion of 0·37 M, beyond which it has not been seen.

It is worthy of remark that although when working with pure hydrogen the green line is always the last to go, it is not the first to appear when hydrogen is present as an impurity in other gases. Thus, when working with carbonic anhydride insufficiently purified, the red hydrogen line is often seen, but never the green or the blue line.

(*To be continued.*)

SEEING BY ELECTRICITY[1]

ON being called upon by the chairman to show his experiments, Prof. Ayrton stated that he and Mr. Perry thought that the occasion of the reading of Mr. Bidwell's paper was a suitable one for their showing to the Society that they were constructing the apparatus described by them in a letter in NATURE, vol. xxii. p. 31. The feasibility of their plan had been combated, and at the last meeting of the British Association at Swansea it was confidently asserted that the action of selenium was not quick enough to register rapid changes of light intensity—an idea, however, which they stated in the discussion at the time there was experimental evidence to disprove. After that came the publication and exhibition of the photophone, proving that selenium changed its electrical properties synchronously with rapid changes in light intensity. For a light telegraph however not only was this property necessary, but in addition that the electric changes in the selenium should be considerable for a comparatively small change in the light. They had, therefore, tried to make sensitive selenium cells of low resistance. The method they had employed consisted in winding two wires parallel on strips of box-wood, ivory, and other non-conductors in section, somewhat like that of a paper-knife in the manner subsequently described by Mr. Bidwell in NATURE, but they had not found it necessary to cut a screw on the wood or mica in a lathe. Of the twenty-five cells that they had constructed they had invariably found, like Mr. Bidwell, that only those were sensitive that had a high resistance. They were aware that Prof. Adams had made sensitive cells of low resistance, and had he been present they would have liked to ask whether it was not only for very small electromotive forces that the cells were sensitive. They had also found that when sensitive cells of 100,000 ohms resistance diminished in resistance to only a few hundred ohms by natural annealing extending over some months, the cells lost entirely their sensibility. Further that certain sensitive cells of high resistance were sensitive as long as an electromotive force of not more than about seven volts was employed to send a current through them, but for electromotive forces much above this the cells were comparatively unsensitive to light, but the sensibility was not destroyed for electromotive forces smaller than seven volts used subsequently. These phenomena, which they believed had not been previously noticed, pointed, they suggested, to the sensibility of selenium being due almost entirely to a polarisation and not merely to a change of resistance, as was commonly supposed and stated. Might it not be possible, they asked, that there was an electromotive force developed in selenium by light, which, for different cells, increased more rapidly than the resistance of the cell, and which was the greater, the greater the electromotive force of the auxiliary battery employed; that in fact selenium became rapidly polarised by the auxiliary current flowing through it, and that this polarisation, the amount of which depended on this current, was removed in proportion to the intensity of the light. That a small electromotive force was developed in selenium by light when no auxiliary current was sent through it, had been conclusively shown by Prof. Adams and Mr. Day in 1876, a result that they had also experienced; and they would mention that a careful examination which they had recently made of the paper published by Prof. Adams and

[1] Paper communicated to the Physical Society, February 26.

Mr. Day in the *Phil. Transactions* for 1876, showed that if we assumed *all* the instances therein mentioned of sensibility of selenium to light were due to an electromotive force set up, and not to change of resistance at all, then on the whole all the results would have been arrived at if this electromotive force set up in different cells, for the same intensity of light, increased more rapidly than the resistance of the cell, and was the greater, the greater the electromotive force of the auxiliary battery employed. They disagreed therefore from Mr. Bidwell in his idea that the name "cell" was at all inappropriate.

Professors Ayrton and Perry referred the Members to their original letter in NATURE for the account of their plan for seeing by electricity. Shortly, it consisted in projecting at the sending-station an image on a screen consisting of a number of selenium cells, the current flowing in each of which from an auxiliary battery was controlled by the intensity of the light falling on it. At the receiving-end of the line a light was thrown on a screen intercepted more or less by little shutters, the opening or closing of each of which was controlled by the current allowed to pass through the corresponding selenium cell at the sending end. Hence on the receiving screen a picture in mosaics was cast corresponding with the image projected on the screen at the sending-end, and varying with every change in the image cast on the sending-screen.

The experiment they desired to show the Society was the successful reproduction on the receiving-screen of every change of illumination of one square of the sending-screen. The shutter was an elliptical blackened aluminium disk suspended in a blackened tube of a kind of galvanometer, and making an angle of 45° with the tube when all the light tending to pass through the tube was cut off. When this disk was deflected through 45° all the light passed through the tube and an image of a square hole was formed by a small lens attached to the tube. For every intermediate position of the shutter an image of the square hole was formed on the screen, but varying in intensity of illumination. Attached to the shutter was a small magnet making an angle of 67½° with it, and the two were suspended by a silk fibre about one-twentieth of an inch in length. These particular angles were selected so that first all variation in intensity of the illumination could be produced with a small motion of the shutter, and secondly, so that the magnet should always be in its most sensitive position in the coil through which passed the electric current which traversed and was controlled by the corresponding selenium square at the receiving-end of the line. [The apparatus was then shown in action.]

They explained how their method of putting, say, thirty or forty selenium cells on a revolving arm would enable them, while dispensing with a large number of cells, to transmit electrically a complete picture of even moving objects, and would in addition obviate the difficulty arising from abnormal variations of selenium.

Instead of the apparatus exhibited to the meeting to show the perfect feasibility of the scheme, Professors Ayrton and Perry mentioned that they were also experimenting with a large thin mirror with many thick ribs at the back crossing one another. Electro-magnets firmly fixed behind the thin parts of the mirror produced by their expansion and contraction very small convexities and concavities on the mirror's face. From their experiments, published in the *Proc.* Roy. Soc., on the so-called Japanese magic mirrors, it was known that excessively small convexities and concavities of this kind might be made to show themselves in a very decided way on a screen by a divergent beam of reflected light. They proposed to have a circular mirror in rotation, but with only a certain sectional space at the back fitted with electro-magnets as described, and they anticipated that this in conjunction with the rotating section of selenium cells at the other end of the line would produce on a screen a picture over the whole area of the mirror corresponding with the distant image projected on the area traced out by the revolving sector of selenium cells.

EARTH CURRENTS—ELECTRIC TIDES

AT a meeting of the Society of Telegraph Engineers and of Electricians on Thursday evening, February 10, Prof. G. C. Foster in the chair, a communication was read by Mr. Alex. J. S. Adams upon "Earth Currents—Electric Tides," in which the author related that, from investigations he had carried on in connection with earth currents since the year 1866, he considered the globe we inhabit as an electrified sphere whose normal electrical condition was liable to disturbance both from within and from without. Starting upon this theory as a basis, and finding from the result of his observations no evidence that the sun exerted sufficient influence to materially disturb the earth's electricity, he undertook a series of systematic observations upon the daily earth-current variations in strength, to elucidate the question, and obtained consecutive observations every quarter of an hour during the interval from April 1 to 21, 1879, with a result that the curves of those observations coincided throughout with the curve of moon-phases for the same period, and clearly indicated that the chief disturbing power was the moon, and that the earth current variations were strictly *lunar-diurnal*.

"But," said he, "there is a yet deeper meaning to the lunar-diurnal current curve than at first sight appears, for an examination shows that the curve for each day represents *four electric maxima, two of a kind*, and that each maximum is divided from the other by a zero or point of no current." He further explained that whilst two of these maxima always exist upon the opposite sides of the globe, which are in a line *perpendicular* to the moon, two other maxima were also found upon the sides of the globe lying at right angles to the former maxima, and that from a long and careful consideration of these features of the phenomenon he had arrived at the conclusion that whilst the earth's disturbing electricity was, as it were, heaped up by the moon upon the sides of the earth nearest to and farthest from her, much as are the waters of the globe in forming the oceanic tides, the two *lateral* maxima, upon the other hand, must be considered as parts of a belt or band of electrical maximum that encircles the earth in a position at right angles to a line drawn between the earth and moon. Thus it appeared that there were zones of maximum at the sides of the globe nearest to and farthest from the moon, and a *circle* of maximum at right angles between them, the divided from them by zones of no current. This arrangement of the earth's electricity by the moon the author termed the earth's *lunar electric distribution*; the electric maximum facing the moon he designated the *major electric pole*, that farthest from the moon the *minor electric pole*, and the belt of maximum that encircles the earth the *electric circle*. Likewise the zone of no current that divides the electric circle from the major pole he terms the *major zero circle*, and that zero which separates the electric circle from the minor pole, the *minor zero circle*.

The earth's electricity, as thus arranged by the moon, follows that orb in her course through the heavens, and this motion of the earth's disturbed electricity round the earth, yet irrespective of the globe itself, was termed the *lunar diurnal electric circulation*, and the axis upon which it turned the *lunar-diurnal axis*.

A due apprehension however that *the moon's influence is in proportion felt by the earth's electricity at every part of the earth's surface* he considered necessary for the proper appreciation of the reasonings which led to the foregoing deductions.

It was then pointed out that there existed a regular retardation or lagging of the earth-current variations behind the corresponding phases of the moon to the extent of nearly three hours, this curious phenomenon being in no way, so far as he could trace, attributable to solar influence.

The magnetic variations were then considered, and a striking coincidence between the electric and the magnetic lunar-diurnal variation-curves was shown to obtain. The author reasoned that the earth's electric forces as constituted in the *electric distribution* revolved also about an axis parallel to a line passing through the centres of the earth and moon, *i.e.* a line drawn between the major and minor electric poles—a motion of the electric forces that agreed with the *observed direction* of the earth current, and which appeared fully sufficient to account for the effect of lunar-diurnal magnetic variation.

In conclusion he said that a comprehensive consideration of earth-current phenomena opens out a much wider sphere of investigation than that simply embracing variations of strength; it has to recognise *directive influence* which, applied to electricity, means the production of magnetism, and that the electric circulating systems that appear to obtain by reason of these three motions, the *earth's diurnal rotation*, the *lunar current circulation*, and the *terrestrial current circulation*—causes which result in the apparently disconnected variations observable in the movements of the magnetic-needle.

UNIVERSITY AND EDUCATIONAL INTELLIGENCE

CAMBRIDGE.—The examiners for the Natural Science Tripos during this year are Dr. W. H. Gaskell, Prof. Bonney, Mr. T. [illegible], Prof. Watson (Owens College), Prof. Lewis [illegible]

appointed Professor of Mineralogy), Messrs. W. Garnett, F. M. Balfour, and S. H. Vines.

The Rev. W. Cunningham, M.A., of Trinity College, has been appointed Deputy for the Knightbridge Professor, Prof. Birks, and has resigned the Assistant-Secretaryship of the Local Examinations and Lectures Syndicate.

Mr. W. Hillhouse, B.A., of Trinity College, Assistant-Curator of the Botanical Museum, has been approved as a teacher of botany, and Mr. J. J. Lister, B.A., of St. John's College, Demonstrator of Comparative Anatomy, as a teacher of that subject for the purposes of medical certificates.

It was resolved last Thursday to admit women students at Cambridge to the Previous Examination and to the various Tripos Examinations, to publish separate class-lists for women, and in cases where order of merit is indicated in the men's class-lists, to indicate the position which any female student would have taken in the corresponding list of men. The examiners may also state that any candidate who does not attain an honour standard is adjudged to have deserved an ordinary degree. It will be necessary to present a further report on minor details of fees and regulations, but it can hardly be doubted that students duly qualified may be admitted formally to the examinations coming on in June next.

The University accounts just published show that examiners cost the University last year 2200*l.*, professors, demonstrators, lecturers, &c., 8400*l.*, in addition to those specially endowed. The ordinary expenses of the museums and lecture-rooms have been 2500*l.*, while the grant from the University is 2000*l.* The botanic garden has cost nearly 1000*l.*, and 660*l.* has been so far spent on a curator's house. The Local Examinations and Lectures Board have received 8400*l.*, and have invested a further sum of 500*l.*, which at a future time may help to provide a building for this extensive work. The University Library has overdrawn its balance nearly 900*l.*, and the Museums and Lecture Rooms Building Fund is in debt 2725*l.* On the whole it appears that the University has been very careful not to sanction new expenditure in this time of transition, and has succeeded in laying by 3000*l.*, now possessing a capital of 27,000*l.* in stocks. 3000*l.* was the University's income last year from common rents and dividends, while 27,000*l.* was paid by members of the University in fees for examinations, degrees, &c.

In the Special Examinations for the ordinary B.A. degree last year thirty-six candidates entered in Chemistry, nine of whom failed; two in Geology, nine in Botany; only one failed, viz. in Botany. The examiners report that in Chemistry the requirement of practical work has exerted a useful influence. This requirement however entails much additional work on the examiners in Natural Science, and the appointment of a third examiner is recommended.

Next Monday at three o'clock, Dr. W. H. Gaskell will make a communication to the Philosophical Society on the action of the vagus nerve upon the frog's heart; and Mr. F. M. Balfour will discuss the ancestral form of the chordata.

THE Calendar of St. David's College, Lampeter, for 1881, is of interest in connection with the forthcoming report of the Commission on Higher Education in Wales. It contains a full account of the foundation and history of the University, the means at its disposal, and the nature of the education it offers to students. The examination for the B.A. degree of this college includes either physics or chemistry.

SCIENTIFIC SERIALS

Archives des Sciences Physiques et Naturelles, No. 1, January 15.—Contributions to knowledge of the family of the Pintinnodea, by H. Fol.—On the use of the microphone in the service of the astronomical hour, by M. W. Meyer.—Exercises of analytical geometry, by L. de la Rive.—On the use of some azoic colours in physiological chemistry, by A. Danilewsky.—*Comptes rendus* of the Geneva Chemical Society, by S. Walter.—On the botanical geography of Southern Tessin, by S. Calloni.—Annals of Berne Observatory, by A. Forster.

Rivista Scientifico Industriale, No. 24, December 31, 1880.—Description of three new species of the aphides of Sardinia, by L. Marchiati.

Reale Istituto Lombardo di Scienze e Lettere. Rendiconti, vol. xiii. fasc. xx.—On the rotatory movement of the heart, by E. Oehl.—On a new nuclearia; description and considerations as to its position in the geological system and its importance in animal ontogeny, by L. Maggi.—Registering instruments in meteorology, by C. Chistoni.—Synthesis of two new acids isomeric with vanillic acid, by G. Körner and G. Bertoni.

SOCIETIES AND ACADEMIES

LONDON

Royal Society, January 27.—"On the Iron Lines widened in Solar Spots." By J. Norman Lockyer, F.R.S.

The observations put forward with reserve in my last communication to the Society have now been confirmed.

In the fine spots visible on December 24, January 1 and 6, many lines in the spectrum of iron were seen contorted, while others were steady.

The facts are given in the following table:—

	The iron lines indicating motion.	Iron lines, visible in the same field of view, steady.
Dec. 24, 1880 ...	5403·2	
	5404·8	5410·0
	b 5409·0	5414·5
	5408·8	
	5396·0	
	5370·5	
	5369·0	5366·5
	4919·8	
	4918·0	4923·0
	5142·2	5269·8
	5138·5	5268·5
In another part of the same spot—		
	5269·8	5323·5
	5268·5	5327·0 (double).
Jan. 1, 1881 ...	5323·5	5269·8
	5327·0 (double)	5268·5
Jan. 6,[1] 1881 ...	4919·8	
	4918·0	4923·5
	All lines between λ 5323·5 and 5410·0 except ...	5382·1

It is to be noted that these observations furnish us with an instance of inversion similar to those frequently obtained in our observations of the most widened lines in spots.

The inferences to be drawn from these observations, and those on which we are now continuously engaged, must be matter for future communication. But I cannot resist calling attention to the crucial nature of the evidence, at least as regards iron, in favour of the view first put forward by Sir B. Brodie, whom we have so recently lost, that the constituents of our terrestrial elements exist in independent forms in the sun.[2]

I have thought it right to send in a record of this work at once, with a view to induce other observers to follow the continually varying phases of the spots during the approaching maximum.

The observations have been made by Mr. H. A. Lawrance, and confirmed by myself in the majority of cases.

Chemical Society, February 17.—Prof. Roscoe, president, in the chair.—The following papers were read:—On the estimation of organic carbon and nitrogen in water analysis simultaneously with the estimation of nitric acid, by M. W. Williams. The author has modified the well-known process of Frankland and Armstrong. Instead of reducing the nitrates with sulphurous acid, he uses the copper-zinc couple of Gladstone and Tribe, which converts nitrates into ammonia. The ammonia produced is distilled off and the distillate nesslerised; the water left in the retort, after distilling off the ammonia, is evaporated to dryness and the residue burnt in the ordinary way. The errors which accompany the use of sulphurous acid are thus avoided, and the time required for the analysis is much shortened.—Capt. Abney and Col. Festing then gave an account of their recent researches on the influence of the molecular grouping in organic bodies on their absorption in the ultra-red region of the spectrum. The authors have photographed the absorption-spectra of numerous inorganic and organic liquids in the region beyond the red. In many cases the presence of an organic radical seems to

[1] In this spot the D lines indicated motion, and *did not retain their parallelism.*

[2] Lecture delivered before the Chemical Society, June 6, 1867.

be characterised throughout its compounds by particular bands. Further research will probably throw much light on the internal structure of chemical substances.—On absorption-bands in the visible spectrum produced by certain colourless liquids, by Dr. Russell and Mr. Lapraik. The authors have carefully drawn the absorption-spectra of various liquids—water, ammonia, &c.—as seen through an ordinary spectroscope.—On the action of hydrochloric acid on ethylene alcohol, by C. Schorlemmer. By heating glycol with an excess of fuming hydrochloric acid in a sealed tube to 100° the author has converted this substance into ethylene dichloride, and has thus disproved the conclusion that the two hydroxyl groups had different functions.—On an attempt to accelerate the process of determining the soluble salts in a soil, by E. W. Prevost. The author added calcium sulphate and barium carbonate to the soil, but in neither case were satisfactory results obtained.

Linnean Society, February 17.—Frank Crisp, LL.B., F.L.S., in the chair.—Mr. Wickham exhibited two collections of Arctic plants. Of fifty-seven species collected by Capt. Markham in Novaya Zemlya (1879) thirty-seven of the most interesting Phanerogams were shown. The absence of species of Gentian is noteworthy, for Arctic Russia, in proximity, possesses six species. Leguminosæ are unrepresented in Spitzbergen and Arctic Greenland, but three species of the order obtain in Novaya Zemlya. Other features of the latter island's flora are equally remarkable. The second collection of typically Polar plants exhibited were those obtained by Mr. Grant in Mr. Leigh Smith's successful voyage to Franz-Josef Land, 1880, and where sixty-one flowering plants were obtained; though the facies of the flora indicates the probability of more yet to be got in this high latitude.—Mr. A. Hammond drew attention to a microscopic specimen and drawing of portion of the wall of the so-called glandular sac of the larva of the Puss moth, from which that insect ejects an acid liquid when alarmed or irritated. Although doubtless the organ is the source of the excretion, it yet is questionable to regard it as a true glandular structure, inasmuch as its tissue is largely composed of chitinous matter.—Dr. Francis Day read a paper, observations on some British fishes. In this he pointed out:—that *Fimelepterus Cornubiensis* is identical with the American *Pamnelas percisformis*, Mitchell; that great confusion exists in the works of Yarrel and Couch respecting the Tunnies and their allies, most, if not all, the examples of the short-finned Tunnies being in reality specimens of *Pelamys sarda*; that the Comber Wrasse (*Labrus Donovani*, Cuv. and Val.), is a peculiarly-coloured variety of *L. maculatus*, Bloch; that *Crenilabrus Bailloni*, Couch, is the *C. melops*, Cuv. and Val. Adult examples of Brill and Sole, coloured on both sides, but in which the eyes were normal, were exhibited. Some Sprats obtained off St. Ives were adverted to, which had fully-developed ova in January this year. It was also proved that the specimen of *Ostracion quadricornis* figured by Couch as a British fish had been brought in salt from abroad by a sailor. Observations also were made by Dr. Day concerning the habits of the Thresher Shark towards the Whale.—Mr. C. B. Clarke gave a communication on right-hand and left-hand contortion of the corolla. In this he maintains that Linnæus's definition of right-hand contortion is correct, and that the criticisms published by M. Alph. de Candolle in "Phytographie" are founded on a misconception. Mr. Clarke holds:—that everybody understands the same direction (viz. the watch-hand direction) by the term right-hand contortion; that the apparent direction of the heavenly bodies is reversed if the spectator looks north instead of south; that the direction of rotation is the same whether the observer supposes himself within or without the helix, but that the apparent direction of a helix is altered if the spectator reverses the direction in which he looks along the axis.—Prof. P. M. Duncan read a paper on some sponges obtained among a mass of fistulose coral from deep water off the coast of Spain during the expedition of the *Porcupine*. One kind, apparently new, is described as a species of *Leodermatium*, *L. affine*, Dunc., and another belongs to the genus *Aphrocalliste*.

Geological Society, February 18.—Annual General Meeting. Robert Etheridge, F.R.S., President, in the chair.—The Secretaries read the Reports of the Council and of the Library and Museum Committee for the year 1880, the Council announcing with much satisfaction that the financial depression under which the Society had been suffering during 1878 and 1879 had proved, as was anticipated, only temporary, and that the Society is now in a very prosperous condition. The Council's Report also announced the publication of the n
Library, which, although considerably lar
expected, will be issued to the Fellows
fixed for it. The Report further announc
various medals and of the proceeds of the
gift of the Society. In presenting the W
to Prof. P. Martin Duncan, M.B., F.R.S
dent addressed him as follows:—Professor
no ordinary pleasure that the Council hav
Wollaston Medal, the highest honour that
bestow, in recognition of the valuable ser
rendered during so many years to the adva
and especially of palæontology; and I may
productive of gratification to me that this
mally conferred upon you by my hands.
palæontologists have been indebted to y
twenty-six memoirs relating to the history,
bution of the fossil Actinozoa, a group w
peculiarly your own by long-continued
searches. Further, you have enriched th
Palæontographical Society with several mo
on the British fossil corals, supplementar
complementary, to the classical monogra
Edwards and Haime. These labours alo
their results, might have justified the Cou
the Wollaston Medal; but besides your
Actinozoa, we have to point to several in
the fossil Echinodermata, to others relating
cal geology (also freely touched upon i
memoirs), and particularly to your exceedi
in connection with the Geological Survey o
the fossil corals of that peninsula, and dis
of both zoological and geological interest
out of the study of those organisms. Pa
sively for nearly twenty years you have foll
research necessary for the fulfilment of you
you have sacrificed the advantages of profe
your energies to the advancement of scienc
it is with much pleasure that I hand to
Medal. The President then presented th
to Prof. Archibald Geikie, F.R.S., F.G
him as follows:—Prof. Geikie,—If a
our Society more than another coul
receive the Murchison Medal for his valu
to geology, it would be yourself; since
contributed more to the advancement of th
the special object of our Society to cultivate
labours in the field connected with your duti
Geological Survey of Scotland, your learned
butions to the *Journal* of our Society, the
Royal Society of Edinburgh and the Glasgow
and other publications too numerous to
qualify you to be the recipient of the medal
chief and friend Sir Roderick Murchison.
contributions to the literature of the geology
many important writings connected with our
me too far—some thirty papers, besides edu
resulted from your industry and knowledge
alone, on the "Old Red Sandstone of Sco
the *Transactions* of the Royal Society of
entitle you to the highest consideration of
indeed are other contributions, especially thos
logy of the Trap Rocks of Scotland," "On
Elevation of Central Scotland" (in vol. xvi
"On the Phenomena of Succession amongst
of Scotland" (*Trans.* Glasgow Geol. Soc.
Earth Sculpture." The President next hand
to Mr. Warington W. Smyth, F.R.S., for
J. W. Dawson, F.R.S., of Montreal, and
follows:—Mr. Warington Smyth, I need
Council, in awarding the Lyell Medal to Pri
done so with a sincere appreciation of the hi
great labours in the cause of palæontology a
I refer to his published papers I find that
120, and that they give the results of most e
researches in various departments of geology,
upon the palæontology of the Devonian
formations of Northern America. Consid
these numerous contributions, the Council w
justified in awarding to Dr. Dawson one of

ole ground of the value of their contents; but these are far from epresenting the whole of the results of his incessant activity in he pursuit of science. His "Acadian Geology," "Post-pliocene Geology of Canada," and "Fossil Plants of the Devonian and Upper Silurian of Canada," are most valuable contributions to our knowledge of North American geology; whilst in his 'Archaia," "The Dawn of Life," and other more or less popular writings he has appealed, and worthily, to a wider public. We are indebted to his researches for nearly all our knowledge of he fossil flora of the Devonian and other Precarboniferous rocks of America, and of the structure and flora of the Nova-Scotian coal-field; and finally I must refer especially to his original investigation of the history, nature, and affinities of *Eozoon*. These researches are so well known that they have gained for Dr. Dawson a world-wide reputation. The President then handed the Bigsby Medal to Prof. Morris, F.G.S., for transmission to Dr. Charles Barrois, and addressed him as follows:—Professor Morris, Dr. Barrois's chief or most important work written in the year 1876, and published at Lille) is "Recherches sur le terrain crétacé supérieur de l'Angleterre et de l'Irlande," a production almost exhaustive in its description of the cretaceous rocks of England and Ireland, and of the utmost value to English students of geology. Dr. Barrois in this work has been the first to attempt to arrange the English Cretaceous rocks in palæontological zones, and eminently has he succeeded in defining and correlating the horizons of France and Britain. In handing to Prof. J. W. Judd, F.R.S., Sec.G.S., the balance of the Wollaston Donation Fund for transmission to Dr. Ramsay H. Traquair, F.G.S., the President said:—Professor Judd, in handing to you, to be forwarded to Dr. Traquair, the balance of the proceeds of the Wollaston Donation Fund, I have to request that you will inform him of the feeling of the Council, that it is rarely that they can have the opportunity of awarding this fund to a more able and accomplished naturalist than himself. His long-continued researches upon the ganoid fishes of the Carboniferous formation have rendered his name eminent in this department of palæontology. The President next presented the balance of the proceeds of the Murchison Donation Fund to Mr. Frank Rutley, F.G.S.; one moiety of the balance of the proceeds of the Lyell Donation Fund to Mr. G. R. Vine; the second moiety of the Lyell Donation Fund to Prof. H. G. Seeley, F.R.S., F.G.S., for transmission to Dr. Anton Fritsch, of Prague. The ballot for the council and officers was taken, and the following were duly elected for the ensuing year: President, R. Etheridge, F.R.S.; Vice-Presidents: John Evans, F.R.S., J. W. Hulke, F.R.S., Prof. J. Morris, M.A., and H. C. Sorby, F.R.S.; Secretaries: Prof. T. G. Bonney, F.R.S., Prof. J. W. Judd, F.R.S. Foreign Secretary, Warington W. Smyth, F.R.S.; Treasurer, J. Gwyn Jeffreys, F.R.S. Council: H. Bauerman, Rev. J. F. Blake, M.A., Prof. T. G. Bonney, F.R.S., W. Carruthers, F.R.S., Prof. P. M. Duncan, F.R.S., Sir P. de M. Grey-Egerton, Bart., M.P., F.R.S., R. Etheridge, F.R.S., John Evans, F.R.S., Lieut.-Col. H. H. Godwin-Austen, F.R.S., J. Clarke Hawkshaw, M.A., Rev. Edwin Hill, M.A., W. H. Hudlestone, M.A., J. W. Hulke, F.R.S., J. Gwyn Jeffreys, F.R.S., Prof. J. W. Judd, F.R.S., Prof. N. S. Maskelyne, M.P., F.R.S., J. Morris, M.A., J. A. Phillips, F. W. Rudler, Prof. H. G. Seeley, F.R.S., Warington W. Smyth, F.R.S., H. C. Sorby, F.R.S., H. Woodward, F.R.S.

Zoological Society, February 15.—Prof. W. H. Flower, F.R.S., president, in the chair.—The Secretary read a report on the additions that had been made to the Society's Menagerie during the month of January, and called special attention to a White-nosed Saki (*Pithecia albinasa*), purchased January 11; an American Monkey of the genus *Callithrix*—probably referable to *C. brunnea*, purchased along with the preceding; and an example of an Insectivore of the genus *Tupaia* (probably *T. tana*), obtained by purchase on the same day.—Mr. Sclater exhibited and made remarks on some eggs of *Opisthocomus cristatus*, obtained at Obydos on the Amazons.—Mr. Howard Saunders exhibited on behalf of Capt. E. A. Butler, and made remarks on specimens of the eggs of *Dromas ardeola*.—The Rev. O. P. Cambridge, C.M.Z.S., exhibited and made remarks on a Hymenopterous parasite, hatched from larvæ found on two spiders—*Linyphia obscura*, Blackw. ♀ and *L. zebrina*, Menge ♂. The larvæ were stated to be apodous, and to adhere to the abdomen of the spider, which, when full-grown, they fully equalled in size.—Mr. E. W. H. Holdsworth exhibited a specimen of White's Thrush (*Turdus varius*), killed in South Devonshire in January last.—Mr. C. O. Waterhouse read a paper on the Coleopterous Insects belonging to the family *Hispidæ*, collected by Mr. Buckley in Ecuador. Seventeen species of *Hispidæ* had hitherto been recorded as inhabiting that country; of these Mr. Buckley had met with fifteen, which, together with nineteen new species, made a total of thirty-six species in the series now described.—Mr. W. L. Distant read a paper on some additions which had been lately made to the Rhynchotal Fauna of the Ethiopian Region, nine new species belonging to the families *Pentatomidæ*, *Coreidæ*, and *Pyrrhocoridæ* were pointed out, and in the *Coreidæ* two new genera, allied to *Petillia* and *Petascelis*, were described. The specimens had been obtained from Western, Southern, and Eastern Africa.—A communication was read from Mr. Edgar A. Smith on some shells from Lakes Tanganyika and Nyassa and from other localities in East Africa, lately received by the British Museum. Great interest attached to some of the shells from Lake Tanganyika, from the fact that they had all the appearance of being modified marine types.—Lord Walsingham read a paper on some new and little known species of North American Tineidæ, amongst which were three new generic forms.

Meteorological Society, February 16.—Mr. G. J. Symons, F.R.S., president, in the chair.—I. L. Bell, F.R.S., J. Bernays, A. W. Blyth, J. Church, F. W. Cory, S. Cutler, T. L. K. Edge, C. Horsley, W. D. Howard, C. Kelly, M.D., G. Lingwood, W. Macgeorge, Capt. J. P. Maclear, R.N., A. Rigg, and H. C. Stephens were elected Fellows of this Society.—The following papers were read:—Relative humidity, by Charles Greaves, M. Inst. C.E., F.G.S. The object of this paper was to show that the term "relative humidity" was frequently the cause of misunderstanding, and that it was desirable that some other tables with a more correct denomination should be used in order that reliable values of this factor in our climate should be recorded.—On the frost of January, 1881, over the British Isles, by William Marriott, F.M.S. The author pointed out that the severe frost of the 7th to the 26th was remarkable for its unexpected appearance, its long continuance, and its sudden breaking up. The weather during the first week of January was comparatively mild, but frost set in over the north of Scotland on the 5th. The author then gave the lowest thermometrical readings from about 300 stations in the United Kingdom for each day of the frost, which were plotted upon diagrams, clearly showing the relative severity of the weather experienced in each district. The lowest readings were − 15° at Garstang on the 16th, and − 22° at Blackadder, − 16° at Kelso, − 15° at Stobo, − 11° at Thirlestane Castle, and − 10° at Melrose, on the 17th. Reference was also made in detail to the rivers and lakes which had been frozen over, and to other incidents proving the remarkably low temperatures which had occurred. Some idea of the intensity of the frost may be gathered by the fact that in the south of Scotland the temperature fell below 10° on more than eleven occasions, below 20° on nineteen occasions, and was below 32° on twenty-five to twenty-nine occasions. In the London district readings below 10° occurred on two or three days, below 20° on ten days, and below 32° on twenty days. In Ireland temperatures below 10° were registered on six or seven occasions, below 20° on twelve or fourteen occasions, and below 32° on twenty-two to twenty-four occasions. No place in the British Isles was exempt from the frost, even at Scilly the temperature was below 32° on three days, the lowest being 29° on two occasions. The winter sea-side health resorts afforded no protection from the frost; at Penzance the temperature fell below 32° on ten occasions, at Torquay on eleven occasions, and was below 20° on six occasions. At Ventnor it was below 32° on nineteen occasions, and below 20° on three occasions, and at Bournemouth it was below 32° on twenty-three, and below 20° on ten occasions. The heavy falls of snow prevented the frost from penetrating far into the ground, but where the snow was cleared away the temperature of the soil fell considerably. A diagram was exhibited showing the mean temperature of January, in the neighbourhood of London, for each year, from 1774 to 1881, from which it appeared that the low mean temperature of 31°·6 for last month had only been surpassed on five occasions, and that the three years, 1879-81, have been very cold, the mean for this period being only 32°·2; there is no instance during the past 100 years of any three consecutive Januarys having so low a mean temperature.

Royal Microscopical Society, February 9 (Anniversary Meeting).—Dr. Beale, F.R.S., president, in the chair.—The Report of the Council showed an addition of [illegible] Fellows

during the year (making 611 in all), with a considerable increase in the revenue and capital accounts of the Society. The attendance at the meetings was also shown to have increased by nearly 50 per cent. The President read his annual address, in which he dealt with the theory of evolution. A vote of thanks was passed by the meeting on the occasion of his retirement from the presidency, as also to the retiring treasurer, Mr. J. W. Stephenson.—The following Council was elected for the ensuing year:—President, Prof. P. Martin Duncan, F.R.S.; Vice-presidents: Prof. F. M. Balfour, F.R.S., W. B. Carpenter, C.B., F.R.S., John Millar, L.R.C.P. Edin., John Ware Stephenson; Treasurer, Lionel S. Beale, F.R.S.; Secretaries: Charles Stewart, M.R.C.S., Frank Crisp, LL.B., B.A.; Members of Council: Robert Braithwaite, M.D., Charles James Fox, William H. Gilburt, James Glaisher, F.R.S., A. de Souza Guimaraens, William J. Gray, M.D., John E. Ingpen, John Matthews, M.D., John Mayall, jun., Albert D. Michael, Frederic H. Ward, M.R.C.S., C. Tharters White, M.R.C.S.

Photographic Society, February 8.—J. Glaisher, F.R.S., president, in the chair.—A paper on sensitometers, was read by Leon Warnerke. After alluding to those already existing, he exhibited and explained one of his own, the "standard sensitometer." This consisted of a frame constructed to hold a thin block made of phosphorescent calcium sulphide mixed with paraffin, and made luminous by burning one inch of magnesium ribbon in close proximity; next is a glass, having upon it a series of squares (with consecutive figures on them) increasing in opacity; then a photographic plate, or any other material sensitive to light, is placed in front, and the phosphorescent light is then permitted to pass through the glass containing the squares; and the highest number visible represents the sensitiveness of the matter experimented upon; the numbers enabling relative values to be determined.

Statistical Society, February 15.—Mr. Jas. Caird, C.B., F.R.S., president, in the chair.—A paper was read on the number of deaths from accident, negligence, violence, and misadventure in the United Kingdom and some other countries, by Mr. Cornelius Walford, Barrister-at-Law, wherein he reviewed the numbers and causes of deaths of this class from the earliest periods at which records existed in the United Kingdom, bringing them down also to the latest date, and noting the circumstances which had helped to increase them, as also those which had a retarding influence. He was of opinion, supported by the statistics adduced, that violent deaths of various kinds had advanced with the progress of civilisation. New forces, as also increasing mechanical productiveness, rendered the risk to life and limb continually greater.

PARIS

Academy of Sciences, February 14.—M. Wurtz in the chair.—The following papers were read:—Progress of the zoological station of Roscoff, by M. de Lacaze-Duthiers. Since 1872 there have been 114 workers of various nationalities at the station, the numbers rising from three in 1872 to twenty-seven last year. Last August seventeen were accommodated at once. A keeper now stays at the station constantly, and despatches live animals to various laboratories in France. Zoologists can be lodged in winter. The station has a good sea-going vessel, and is about to acquire a diving-dress. (Particulars of the aquarium, laboratory, &c., are given.) A new station is being formed at Port Vendres, on the Mediterranean.—Existence of large spiral cells distributed in the parenchyma of certain *Crinum*, by M. Trécul.—Theorems relative to the equation of Lamé, by M. Brioschi.—On periodic movements of the ground, by M. Plantamour. In the year ending September 30, 1880, a great lowering took place on the east side, from October 4 to January 28, viz. 95"·80 (as against 28"·08 the previous year). The mean temperature of December was unusually low, but the author thinks some other cause must have operated also. The level placed in the meridian showed nearly the same oscillation as the previous year (4"·56). In winter the south side rises with rise of temperature; in summer it falls.—On the earthquake in Switzerland on Jan. 27, 1881, by M. Colladon.—Lithological and geological examination of the meteorite that fell on Oct. 13, 1872, in the neighbourhood of Soko Banja, in Servia, by M. M. Sunier.—On Fuchsian functions, by M. Poincaré.—On the laws which rule periods and coefficients of intensity in one of the principal groups of elementary electromotive forces due to solar induction, and on the possibility of using the magnetic needle to measure the velocity of rotation of the sun about its axis, by M. Quet.—On the relations which exist between the temperature, pressure and circulation of the air on the Iberian peninsula, by M. Teisserenc de Bort. In winter the peninsula is colder than the seas around; it shows a barometric maximum, the air flowing outwards to the coasts. In summer the isotherms group round a maximum in the middle of Spain, where, on the other hand, the pressure shows a minimum, and the winds tend inwards. In intermediate seasons the isotherms are nearly perpendicular to the meridians; the isobars are grouped uniformly round great centres of atmospheric action, the most important being the oceanic barometric maximum. Spain is somewhat like monsoon countries. (The author also studies the action of the peninsula as revealed in daily phenomena).—On m'boundou (test-poison of the Gaboonese), new physiological, chemical, histochemical, and toxicological researches, by MM. Heckel and Schlagdenhauffen. It contains only one alkaloid, strychnine. The division of *Strychnos* into *tetanising* and *paralysing* is not warranted. The effect depends on the dose employed.—On the treatment of phylloxerised vines by insufflation of vapours of sulphide of carbon, by M. Bourdon. He sends the vapours through a permanent drainage-system.—The Secretary made reference to the death of M. Kuhlmann.—Research on the specific magnetism of ozone, by M. Becquerel. Ozone is found to be more magnetic than oxygen, and the ratio of the one specific magnetism to the other is considerably greater than the supposed ratio of the densities. Thus the specific magnetism of ozone is greater than that corresponding to the quantity of oxygen contained in it.—On the electric phenomena of tourmaline and of hemihedral crystals with inclined faces, by MM. Jacques and Curie.—On the combination of hydrochloric acid with bichloride of mercury, by M. Ditte. These substances may unite in several proportions.—Violet illumination of the retina under the influence of luminous oscillations, by M. Charpentier. If the sky, uniformly illuminated by diffused white light, be looked at steadily, and two fingers (separate about 0·02 m.) passed to and fro rapidly before the eye for about half a minute, one perceives a mosaic system of hexagons of violet purple colour separated by white lines. The author supposes the hexagons to represent the cones in the fovea and yellow spot, and the white lines filaments from the choroidian cells.—Determination of fundamental colour-sensations by study of the distribution of complementary colours in the chromatic circle (continued), by M. Rosenstiehl.—On a glucoside extracted from common ivy, by M. Vernet.—On cultivation of the microbe of rot, by M. Toussaint. This succeeds best in rabbit or mutton bouillon. The microbe appears in two states, that of bacteria and that of spores.—Structure and texture of the ink-bag of Sepia, by M. Girod.—Artificial reproduction of basalts, by MM. Fouqué and Lévy. They followed the igneous method. The peridote was crystallised at a higher temperature than the other minerals. The black earth used consisted of one of olivine, two of augite, and six of labrador.—Map of the central part of the Spanish Pyrenees, by M. Schroder.

CONTENTS

P. 7

NATURAL CONDITIONS AND ANIMAL LIFE. By Prof. E. RAY LANKESTER, F.R.S. 1
LETTERS TO THE EDITOR:—
Movements of Plants.—CHARLES DARWIN, F.R.S. 2
Barometric and Solar Cycles.—S. A. HILL 3
The Continents always Continents.—Prof. JAMES D. DANA . . . 3
The Aurora of January 31; Position of Auroral Rays.—T. W. BACKHOUSE 4
Auroric Light.—G. H. KINAHAN 4
The Recent Severe Weather.—M. R. I. A. 4
Migration of the Wagtail.—Dr. JOHN RAE, F.R.S. 4
Phosphorescence of the Sea.—THOS. B. GROVES 4
Minerva Ornaments.—W. J. KNOWLES 4
Selenium.—W. M. C. 4
A CHAPTER IN THE HISTORY OF THE CONIFERÆ. By J. STARKIE GARDNER (*With Illustrations*) 4
GEOMETRICAL TEACHING 6
ILLUSTRATIONS OF NEW OR RARE ANIMALS IN THE ZOOLOGICAL SOCIETY'S LIVING COLLECTION, II. (*With Illustrations*) 7
NOTES ON THE GEOLOGY OF THE COREAN ARCHIPELAGO. By Surgeon H. B. GUPPY 8
NOTES 9
GEOGRAPHICAL NOTES 11
ON THE VISCOSITY OF GASES AT HIGH EXHAUSTIONS. By WILLIAM CROOKES, F.R.S. 11
SEEING BY ELECTRICITY 11
EARTH CURRENTS—ELECTRIC TIDES 11
UNIVERSITY AND EDUCATIONAL INTELLIGENCE 11
SCIENTIFIC SERIALS 11
SOCIETIES AND ACADEMIES 11

SOCIETIES.

1878

7. MARCH 7.
...ermeneum Metallic Reflection: Sir ...Anniversary Dinner: The King-...Oxidation, an Organic Ferment ...Hydrogen Peroxide, its Function ...the Dr. Hope-Vere Lecture: Dr. Oswald Flamel ...ombes on High Power Instrument ...of Leptospermeæ Indigenous to ...mon Pigott, F.R.S. ...Specimens in Plastic: C. G. Sharrock ...and Plate for 3 years: Z. Simmonds ...and Bacteroids": A. B. Griffiths ...ent: Rev. R. Boog Watson ...tion of Bacteria in Natural Waters: ...ous Matter in Running Waters: Dr. ...Inquiry on Phosphorescence of ...ters": Dr. F. B. Jevons: and Edgar ...Ad on Naphthalamine Diabenzoyl ...

...ductor of Electricity": Prof. W. E. ...

Chemistry: Rev. W. Haughton.

MARCH 4.
The Croonian: Prof. Flower.
...narks on Proposed Classification of ...thing Nests: Theory of the Formation ...—Notes on the Microscopic Anato... Elphidium: L. Wade, Exon. ...in Insects": J. M. Maclaren. ...Sir W. Thomson.

MARCH 5.
...per: R. S. Poole.

MARCH 6
...mission of English Workmen": Prof. ...

MARCH 7.
...he Croonian: Prof. Flower. ...s. E. P. Wright. ...r. F. Brown. ...ng.: Prof. W. G. Adams. ...arterly Meeting.

MARCH 8.
...Exhibition of Bulldogs: Notes from ...Zealand: with a Note from Prof. ...ngs": S. E. Peal.—A Search Apparatus ...ential Scale Units on our Notion ...s: Woodthorpe, R. E. ...—Scientific Committee ...y at 8.

...: Prof. Schäfer.

MARCH 10.
The Croonian: Prof. Flower. ...n of parts of the Skeleton of an ...ordinaria, Daw.): Prof. Duncan. ...the Color Determination, with a ...ion of Experiments on Animals, Cox. ...and Instruction on the Superficial ...on Regions": G. M. Dawson, B.Sc. ...On a Species of Acoela Infesting ...

...d Patterns": Edward Wyndham ...in Relation to Sanitary Progress": ...

MARCH 11.
...—Parelic-Currents—Electric Telegraphy ...ations on Iron Pipes—On the Applic... Railway Rolling Stock: Jones, F. ...Processes of Manufacture of Wool ...se of Electricity during Sparking: ...Leyden Jar: Edward B. Bright. ...ry Question of Elliptic Function to ...

...f Architecture in Modern Civilisation ...

...SOCIETY: Rev. W. Houghton.

...ORD at ... ...s Cathedral: Prof. Flower.

...and Literature of the Semitic ...

MARCH 13.
...ay: R. S. Poole.

...achers and the Trade.

ON (formerly of 4, ...TRICIANS, OPTICIANS, and ...NT MAKERS. Electric Bells, ...it Batteries, Indicators, Dial and ...Induction and Medical Coils, of ...ery description. Microscopic and ...ral Glasses. Microscopes, Assorted ...ons. Illustrated Catalogue Three ...

HIGH HOLBORN, LONDON, W.C. ...ecial Card.

SUBSCRIPTIONS TO NATURE

Yearly . . . . . 28s.
Half-yearly . . . . . 14s. 6d.
Quarterly . . . . . 7s. 6d.

To the Colonies, United States, the Continent, and all places within the Postal Union :—

Yearly . . . . . 30s. 6d.
Half-yearly . . . . . 15s. 6d.
Quarterly . . . . . 8s.

Office : 29, Bedford Street, Strand.

NOTICE OF REMOVAL.
JAMES HOW & CO.,
SCIENTIFIC INSTRUMENT MAKERS,
73, FARRINGDON ST., LONDON
(LATE OF 5, ST. BRIDE ST., AND 2, FOSTER LANE)
HOWS STUDENT'S MICROSCOPE. HOWS MICROSCOPE LAMP.
Rock Sections and other Objects for the Microscope.

NOW READY.
SECOND EDITION,
GRIFFIN'S
CHEMICAL HANDICRAFT.
PRICE 4s. 9d. POST FREE.
A CATALOGUE OF CHEMICAL APPARATUS:
ILLUSTRATED, CLASSIFIED, DESCRIPTIVE.
Demy 8vo, 480 pp., Illustrated with 1,600 Woodcuts.
Most Complete and Cheapest List of Apparatus.
JOHN J. GRIFFIN AND SONS, 22, GARRICK STREET, LONDON, W.C.

LIGHTNING CONDUCTORS.
Experience, accumulated since the time of Benjamin Franklin, proves conclusively that a Conductor made of Copper of adequate size is the best of all appliances for the protection of every description of building from the destructive effects of lightning.

NEWALL & CO.'S
PATENT COPPER LIGHTNING CONDUCTOR,
As applied to all kinds of Buildings and Shipping in all parts of the world with unvarying success, is the most Trustworthy, most Effective, and also the Cheapest Conductor ever offered to the public.
It is simple in its application, no insulators being required, and it costs only one shilling per foot for the standard size, which ensures safety in any storm.
R. S. NEWALL & CO., 110, STRAND, W.C.
38, WATERLOO ROAD, LIVERPOOL.
62, ANDERSTON QUAY, GLASGOW.
MANUFACTORY—GATESHEAD-ON-TYNE.

S. C. TISLEY & Co.,
OPTICIANS,
172, BROMPTON ROAD, S.W.
(Close to South Kensington Museum.)
THE PHONEIDOSCOPE
An Instrument for Observing the Colour-Figures of Liquid Films under the action of Sonorous Vibrations,
Being a visible demonstration of the Vibratory and Molecular Motion of a Telephone Plate.
The PHONEIDOSCOPE, with 3 Discs, Bottle of Solution, Descriptive Pamphlet, &c., in Cardboard Box, 10s. 6d.
MANUFACTURED AND SOLD WHOLESALE AND RETAIL BY
S. C. TISLEY & CO., 172, BROMPTON ROAD, LONDON, S.W.
TELEPHONIC ELECTRICITY. All Materials supplied for Experimental Purposes.
Price Lists of Electrical and Acoustic Apparatus, with Drawings and Description of the Harmonograph, Post Free, 2d.

EAGLE INSURANCE COMPANY,
79, PALL MALL.
FIRE LIFE ONLY. ESTABLISHED 1807.
Accumulated Funds £1,043,540
Also a Subscribed Capital of more than £1,500,000
Reports, Prospectuses, and Forms may be had at the Office, or from any of the Company's Agents, post free.
GEORGE HUMPHREYS, Actuary and Secretary.

W. LADD & CO.,

SCIENTIFIC INSTRUMENT MANUFACTURERS,

(By Appointment to the Royal Institution of Great Britain),

11 AND 12, BEAK STREET, REGENT STREET, W.

IMPROVED HOLTZ ELECTRICAL MACHINES. GRAMME'S MAGNETO-ELECTRIC MACHINE for Laboratory use.

PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3s. per oz.

Physical Apparatus of every Description.

ILLUSTRATED CATALOGUE, SIXPENCE.

PATERSON'S NEW CATALOGUE OF PHYSICAL APPARATUS.

LANTERN SLIDES for SCIENTIFIC LECTURES. Season 1880–1. Post free 6 Stamps.
Complete Sets of Physical Apparatus for Science Primers and all the Physical Text-books in use in Schools and Colleges.
Siemens and Gramme Dynamo Machines and Lamps for hire.
Schools supplied with Apparatus as per Science and Art Departments' Requirements in the Sections of Light, Heat, Sound, and Electricity.
Electric Signals for Houses, Hotels, &c., Colliery Signals, Lightning Conductors. The Gower-Bell Loud-speaking Telephone.

EDWARD PATERSON, Electrical Engineer.

SHOW ROOMS AND STEAM WORKS:—76, LITTLE BRITAIN, E.C. (late 3, Bedford Court, W C.).

MOLISON'S HARMONOGRAPH; executes the Harmonic Curves in the most perfect manner. 15s. and 20s.

Illustrated Catalogue of Electrical Apparatus, Part 1, post free, 6 Stamps. Ditto, Electric Signals, Part 2, 6 Stamps.

FLETCHER'S
PATENT VENTILATED
HOT-AIR OVEN.

At a cost of less than one halfpenny per hour for gas this oven will grill, roast, toast, bake, warm dishes and plates; and with the assistance of Fletcher's Patent Solid Flame Boiling Burners will do everything possible with a first-rate open fire (except drying clothes on washing days).



It is unapproached by any oven for pastry, and is fully hot in one minute after the gas is lighted.

Fish, joint, and pastry can be cooked all at once, in the most perfect manner, without the slightest taint from one to the other. The cooking is always good and always alike.

It will roast joint and fowls both at once, at least as well as an open fire.

Complete illustrated list of gas cooking and labour-saving appliances free by post. List of Gas and Petroleum Laboratory Furnaces and Apparatus, price 2d

THOS. FLETCHER,
4 & 6, *MUSEUM STREET, WARRINGTON.*

FRY'S COCOA EXTRACT

GOLD MEDAL, PARIS EXHIBITION.

In Packets and Tins. Pure Cocoa only, with the superfluous oil extracted.

"If properly prepared, there is no nicer or more wholesome preparation of cocoa."—*Food, Water, and Air, edited by Dr. Hassall.*

J. S. FRY & SONS, Bristol and London.

BROKEN!!
DAVY'S DIAMOND CEMENT

SECURELY AND NEATLY MENDS
CHINA, GLASS
CABINET WORK,
AND
FANCY ARTICLES.

Of all Chemists in 1s. Bottles.

See the name "E. DAVY," the Original Inventor, is on the Label, and also that a

BARCLAY & SONS, 95, Farringdon Street, Londo

R. W. NEEVES,
PHILOSOPHICAL INSTRUMENT
AND
INTENSITY COIL MAKER

PRICE LIST, FOUR STAMPS.

55, SIDMOUTH STREET, LONDON, W.C.

"The leading Farmers' paper."—CLARE SEWELL READ, Esq., M.P.

THE CHAMBER OF AGRICULTURE JOURNAL
AND FARMERS' CHRONICLE
(PRICE 3d. WEEKLY).

The representative organ of the Central and Provincial Chamber of Agriculture; *gives fuller reports of the discussions and proceedings* of this extensive organisation than any other agricultural paper. It devotes *special attention to the treatment of Agricultural Questions by Experiment*, besides containing ample Reports of the LATEST LONDON and COUNTRY CORN, CATTLE, HOP, PROVISION, and other Markets, with Original Articles on Practical Farming, the Dairy, Herd and Flock, News, Horticulture, &c., &c. It is despatched every Monday evening in time for the country post.

Terms of Subscription, payable in advance, post free:—3 months, 3s. 3d.; 6 months, 7s. 7d.; 12 months, 15s. 2d.

Published by W. PICKERING, 21, Arundel Street, Strand, London.

METALS and their CHIEF INDUSTRIAL APPLICATIONS.

By C. ALDER WRIGHT, D.Sc., Lecturer on Chemistry in St. Mary's Hospital Medical School. With Illustrations.

MACMILLAN & CO. LONDON.

HOLLOWAY'S PILLS

THIS MEDICINE

Is a Certain Cure for all Disorders of the LIVER, STOMACH AND BOWELS. A Great PURIFIER of the BLOOD; Powerful Invigorator of the System, in cases of WEAKNESS AND DEBILITY, and is unequalled in Female Complaints

CMILLAN & CO.'S PUBLICATIONS.

; an Introduction to the Study of Man and Civilisation. By
S. With Illustrations. Crown 8vo. 7*s. 6d.* *[Immediately.*

CIENT GEOGRAPHY. From the German of Dr. H.
[Immediately

RANKS TO A COMMISSION. Crown 8vo. 6*s.*
ime, the Publishers feel bound to state that they have seen documents and letters from well-known
ch to guarantee the genuineness of the narrative.

VOLUME, "MACMILLAN'S BIOGRAPHICAL SERIES."

CRAUFURD TAIT, WIFE AND SON OF ARCHI-
BISHOP OF CANTERBURY: a Memoir. Edited, at the request of the Archbishop, by the
ıear of Marden, and one of the Six Preachers of Canterbury Cathedral. With Two Portraits
Cheaper Edition. Crown 8vo. 6*s.*

FLORENCE: Dante, Giotto, Savonarola, and their City.
Illustrations from Drawings by Prof. DELAMOTTE, and a Steel Portrait of Savonarola.
hird and Cheaper Edition. Crown 8vo. 10*s.* 6*d.*

VOLUME OF MACMILLAN'S POPULAR 6*s.* NOVELS.

CITY: being a Narrative of Certain Recent Events in the
ent of the Haute Bourgogne. A Story of the Seen and Unseen. By Mrs. OLIPHANT.
d very original to boot."—*Times.*

F LETTERS. Edited by JOHN MORLEY. New Volume.

AINTSBURY.

NEW NOVEL BY HENRY JAMES, Jun.

UARE: THE PENSION BEAUREPAS: A BUNDLE
own 8vo. 21*s.*
are, on the whole, even more marvellously clever . . . There is no doubt that it is genius of the
ling character."—*Spectator.*
a finished piece of workmanship . . . We do not know of anything more complete than the
e."—*St. James's Gazette.*

NEW NOVEL.

', the Reminiscences of a Chiote Merchant during the Greek
the Greek of D. BIKÉLAS. Translated, with Introduction on the Rise and Development of
GENNADIUS, late Chargé-d'Affaires at the Greek Legation in London. Crown 8vo. 7*s. 6d.*
glish, and one can be sure that he has faithfully interpreted the original. . . . The tale here
lready be said to have achieved a European reputation."—*St. James's Gazette.*

hteenth Annual Publication, Revised after Official Returns.

'S YEAR BOOK: Statistical and Historical Annual of the
for the Year 1881. By FREDERICK MARTIN. Crown 8vo. 10*s. 6d.*
possibly be desired by politicians, merchants, and public speakers and writers relative to the
hurch and education, the revenue and expenditure, the army and navy, the area and population,
y civilised country in the world is to be found readily accessible within the small limits of this

TICS. (Issued by the National Liberal Federation.) 1. The
ND AND TENANT. By JAMES HOWARD, M.P. 8vo. 1*s.*—2. FOREIGN POLICY.
-DUFF, M.P. 8vo. 1*s.*—3. FREEDOM OF LAND. By the Right Hon. G. SHAW-
6*d.*

TIAL POLICY. By SIR DAVID WEDDERBURN, M.P. 8vo. 1*s.*

MACMILLAN AND CO., LONDON, W.C.

NEW HIGH-CLASS JOURNAL.

LAND

A JOURNAL FOR ALL INTERESTED IN LANDED AND HOUSE PROPE

WITH

INDEX TO THE ESTATE EXCHANGE REGISTERS.

TERMS OF SUBSCRIPTION BY POST :—**One Year, 28s.; Half-year, 14s.; Quarter, 7s.**

Printed and Published for the Proprietors by

Cassell, Petter, Galpin & Co., La Belle Sauvage Yard, Ludgate Hill, E.C.

*** *All Communications respecting Advertisements in* LAND *should be addressed to the Manager, Advertisement De La Belle Sauvage Yard.*

Messrs. CASSELL, PETTER, GALPIN & CO. will publish,

UNIFORM WITH "PICTURESQUE EUROPE,"

In Monthly Part, price 2s. 6d.,

Picturesque Americ

A PICTORIAL DELINEATION OF

The Mountains, Rivers, Lakes, Forests, Waterfalls, Shores, Canons, Valleys, Cities, and other Pictu Features of the North American Continent.

WITH 48 EXQUISITELY ENGRAVED STEEL PLATES,

And Several Hundred Engravings on Wood,

From ORIGINAL DRAWINGS specially made for the Work.

PART I. ready MARCH 25th, 1881, price 2s. 6d.

TO BE COMPLETED IN 48 PARTS.

*** *Prospectuses are now ready at all Booksellers, or will be sent post free on application to CASSELL, PETTER, GALPIN & CO., LUDGATE HILL, LONDON.*

Just published, cloth. Price 10*s.* 6*d.*

INSECT VARIETY: its Propagation and Distribution. By A. H. Sw
Member of the Entomological Society of London.

"This is a delightful book, brightly, naturally, and picturesquely written, containing an immense amount of informatio and yet not dry for a single page from beginning to end."—*Standard.*

"We congratulate the author on his work. It is a successful and valuable addition to entomological literature."—*Li Water.*

CASSELL, PETTER, GALPIN & CO., LUDGATE HILL, LONDON.

Every FRIDAY, price 4d.

The Live Stock Journal & Fancier's Gazet

A CHRONICLE FOR COUNTRY GENTLEMEN, BREEDERS, AND EXHIBITOR

The Journal, which is the official organ of the ROYAL AGRICULTURAL, SHORTH SMITHFIELD CLUB, BRITISH DAIRY FARMERS', ENGLISH CART HORSE, CLYDESDALE, other ASSOCIATIONS, now stands without a rival as a Chronicle for Country Gentlemen, Breed and Exhibitors.

TERMS OF SUBSCRIPTION BY POST :—**Three Months, 4s. 11d.; Six Months, 9s. 9d.; Twelve Months, 1**

Publishing Office and Office for Advertisements: LA BELLE SAUVAGE YARD, LUDGATE HILL, E.C.

Printed by R. CLAY, SONS, AND TAYLOR, at 7 and 8, Bread Street Hill, Queen Victoria Street, in the City of London, and published by MACMILLAN AND CO., at the Office, 29 and 30, Bedford Street, Covent Garden.—THURSDAY, March 3, 1881.

NATURE

A WEEKLY ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
Of Nature trusts the mind which builds for aye."—WORDSWORTH

NO. 593, VOL. 23] THURSDAY, MARCH 10, 1881 [PRICE SIXPENCE

Registered as a Newspaper at the General Post Office.]

[All Rights are Reserved.

THE MASON SCIENCE COLLEGE, BIRMINGHAM.

APPOINTMENT OF ADDITIONAL PROFESSORS.

The Trustees intend from the commencement of the Second Session of College, on the 1st of October next, to enlarge the Course of Instruction. The present Chairs are Mathematics (Prof. M. J. M. HILL, M.A. Cantab.), emistry (Prof. W. A. TILDEN, D.Sc. Lond., F.R.S.), Physics (Prof. J. POYNTING, M.A. Cantab., B.Sc. Lond.), and Biology (Prof. T. W. IDGE, M.A. Cantab., F L.S.). In the ensuing Session Prof. Tilden will l Metallurgy to his Course.

The Trustees invite applications (to be sent to "Mr. G. H. Morley, Secrey, The Mason Science College, Birmingham," on or before the 30th of ril next) for the following additional Professorships and Lectureships, :—

1.—A Professor of Physiology, with special reference to the Laws of Health.
2.—A Professor of Geology and Mineralogy.
3.—A Professor of Civil and Mechanical Engineering.
4.—A Professor of Latin and Greek.
5.—A Professor of English Language and Literature.
6.—A Lecturer on the French Language.
7.—A Lecturer on the German Language.

Particulars of the Salaries and Conditions will be sent by the Secretary on plication.

By a resolution of the Trustees, Candidates are especially requested to stain from canvassing.

JOSIAH MASON, Bailiff.
J. GIBBS BLAKE, M.D., Chairman of Trustees.
G. J. JOHNSON, Hon. Sec.

Edmund Street, Birmingham, February 23rd, 1881.

MICROSCOPES.

. **BAKER, of 244, High Holborn, begs to** call the attention of the Scientific to his large stock of ACHROMATIC MICROSCOPES, BINOCULAR AND MONOCULAR, at extremely low prices, commencing from £3 10s. OBJECT-GLASSES, APPARATUS, OBJECTS, and MATERIALS of all kinds kept in stock. Catalogues free by post.

C. BAKER being the appointed Agent for ZEISS, SEIBERT, id other first-class GERMAN MAKERS, is now supplying their autiful productions at very Low Prices. ZEISS's new HOMOGNEOUS and other IMMERSION OBJECTIVES now in stock. talogue free by post.

A Large Assortment of first-class *Second-hand Microscopes Ross, Powell,* and *Beck;* also other Scientific Instruments in ck, by the most esteemed makers, at the Lowest Prices. sts of same forwarded on application.

Instruments taken in Exchange.

ESTABLISHED 1765.

BROWNING'S POCKET MICROSCOPE.

The New Pocket or Field Microscope, on Firm Folding Brass Tripod Stand, with fine Adjustment, 1-inch Objective, Large Field Eye-piece, Hand-pliers, &c.; height when set up, 10 inches; dimensions, packed in Morocco Case, 5½ inches long. Price £1 11s. 6d.

Or with 1-inch and 2-inch Objectives, Stage, Forceps, Stage Plate, and Dipping Tube, £2 2s.

List of Microscopes sent free.

Illustrated Catalogue of Microscopes, with 41 Illustrations, 10 whole page Illustrations, sent for Six Stamps.

JOHN BROWNING,

Optical and Physical Instrument Maker to Her Majesty's Government, the Royal Society, the Royal Observatories of Greenwich, Edinburgh, &c., &c.,

63, STRAND, LONDON, W.C.

TRAVELLERS' SCIENTIFIC REQUISITES.



ANEROID BAROMETER with ALTITUDE SCALE, THERMOMETER and COMPASS in Flat Pocket Case, various Forms,

£7 7s. and £8 8s.

Price Lists of Instruments free by post.

NEGRETTI & ZAMBRA,

Opticians and Scientific Instrument Makers

To HER MAJESTY THE QUEEN,

HOLBORN VIADUCT,

45, CORNHILL, & 122 REGENT STREET, LONDON.

cxlvi NATURE [March 10, 1

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 48N, Tollington Road, Holloway, London, N.

SOLAR PHYSICS.

The following COURSE of LECTURES will be given by Members of the Committee on SOLAR PHYSICS, appointed by the Lords of the Committee of Council on Education:—

An Introductory Lecture. By Prof. STOKES, Sec. R.S. 6th April, 1881.

A Lecture on the Practical Importance of Studying the Influence of the Sun on Terrestrial Phenomena. By Lieut.-General STRACHEY, R.E., C.S.I., F.R.S. 8th April.

Two Lectures on the Connection between Solar and Terrestrial Phenomena. By Prof. BALFOUR STEWART, F.R.S. 27th and 29th April.

Six Lectures on Spectroscopy in Relation to Solar Chemistry. By Mr. J. NORMAN LOCKYER, F.R.S. 4th, 6th, 11th, 13th, 18th, and 20th May.

Three Lectures on the Photography of the Infra-red of the Spectrum in its Application to Solar Physics. By Capt. ABNEY, R.E., F.R.S. 25th and 27th May, and 1st June.

The LECTURES will be delivered in the Lecture Theatre of the South Kensington Museum at 4 p.m on the days stated above.

Admission will be by Tickets, which may be obtained, as far as there is room, on application by Letter to the SECRETARY, Science and Art Department, South Kensington, S.W.

MATRICULATION of the UNIVERSITY OF LONDON.

ST. BARTHOLOMEW'S HOSPITAL AND COLLEGE.

A CLASS in all the Subjects of this Examination will begin on MONDAY, March 7, and continue till the Examination in July. The Class is not confined to Students of the Hospital.

For particulars apply to the WARDEN of the College, St. Bartholomew's Hospital, London, E.C.

A Handbook is forwarded on application.

LONDON UNIVERSITY, ARMY, CIVIL SERVICE.

Dr. R. H. JUDF, D.Sc. (Lond.), M.A. (Cantab.), High Wrangler, First Class Natural Science Tripos, late Scholar of Christ's and sometime Demonstrator of Chemistry at Caius College, Cambridge, with qualified Assistants, prepares Gentlemen in all the subjects for the above Exams.

Natural Science treated both experimentally and theoretically.

Highest Testimonials and References to present and former Pupils. A few Pupils taught by Correspondence. Special Classes now forming for Matriculation, B.A., B.Sc., and Prel. Sci.

119, Cambridge Gardens, Notting Hill, W.

CONCHOLOGY.

The Survivor of Rigacci Brothers, Rome, wishes to DISPOSE of their well-known CONCHOLOGICAL COLLECTION, which contains more than 10,000 Species of Recent Shells, and a great number of Fossil Shells from the Paris Basin, Belgium, Vienna, England, Russia, Tuscany, Sicily, and other countries, besides a peculiarly valuable Collection from Monte Mario near Rome, together with the Library relating to the subject. Signor Rigacci therefore begs to inform the Directors of Public Museums and Naturalists that he is prepared to treat for the Sale of the above-mentioned Collection and Library, and to supply a printed Catalogue.—Address VINCENZO RIGACCI, No. 5, Piazza Campo Marzio, Rome.

FOR SALE, at Half Original Cost, RUHMKORFF COIL, by Owen, City Road, producing 3-inch Sparks, £6. Rotating Spark Magnet in Vacuum-jar, Gesler Fountain and Uranium Cap, 30-inch Uranium Vacuum-tube mounted on Stand. Three large Vacuum-tubes, Phosphorus, Hydrogen, and Quinine. Also an Analytical Balance by Oertling, nearly new. No. 3 in Glass Case; 12-inch Beam; cost £8 8s.; will be sold for £6.—A. DECK, 9, King's Parade, Cambridge.

PREHISTORIC AND ANTIQUARIAN

COLLECTION for Sale; containing many interesting and choice Specimens from all parts of the World, formed with much trouble and at considerable expense. Apply for Particulars by Post to R. P. GREG, Esq, F.G.S., &c., Coles, Buntingford, Herts.

ROYAL POLYTECHNIC.—CLASSES for the Preparation of Students for University Examinations, under the direction of EDWARD B. AVELING, D.Sc., F.L.S. London University Matriculation, 1st and 2nd B.Sc., Preliminary Scientific M.B., Botany, Physiology, Chemistry. All the work practical.

INSTRUCTION IN MATHEMATICS.—

Youths or Adults attended at their Residence, on Reasonable Terms.

LIVING SPECIMENS FOR THE MICROSCO

THOMAS BOLTON, NATURALISTS' and MICROSCOPIS

STUDIO, 57, NEWHALL STREET, BIRMINGHAM.

T. B. has last week sent to his subscribers *Batrachosperma* forme, with Drawing and Description. He has also sent out Young Trout and Salmon; also Ova of Great Lake Trout and Salmo Lophopus, Marine Polyzoa, Hydrozoa, and Crustacea, Argulus, Volv

Weekly announcements will be made in this place of organisms is supplying.

Specimen Tube, One Shilling, post-free.

Twenty-six Tubes in course of Six Months for Subscription

Price List of Specimens on application, with stamped addressed

Portfolio of Drawings, No. 4, One Shilling.

TELESCOPE by Browning; 6½-inch Sp

lum, on Alt-azimuth Stand, with fine Screw-motions and 3 Eye 100 to 450: to be disposed of. Cost £30. Offers to be made C. H. JOBERNS, Lancaster.

DIAMONDS IN MATRIX.

R. C. NOCKOLD, Diamond and Oriental Stone Cutter and Dea for sale Specimens of the above; also Cut Precious Stones in all Cas

Precious Stones valued and bought.

12, FRITH STREET, SOHO, W.

MINERALOGY AND GEOLOG

MAGNIFICENT DERBYSHIRE FLUOR SPAR VASE. Hei Pedestal, 2ft. 8in.; Diameter 13½in. This is, with one exception vase of the kind known, the vein having been worked out years ago.

FINE PINK APOPHYLITE, EISENROSE, CONNELLITE SPAR, BARYTA, FAHLERZ, LIBETHENITES.

COLLECTIONS FOR STUDENTS, from £2 2s. COLLECTIONS BEGINNERS, from 4s. BLOWPIPE CASES AND APPARA

PRIVATE LESSONS AND EVENING CLASSES

Catalogues free.

SAMUEL HENSON,

277 (*Late* 113*a*), STRAND, LONDON, W.

EVERY BOY A GEOLOGIST.

Now ready, and highly recommended, complete, price 7s. 6

This admirable little Work and most extraordinary Cabinet of well-selected Natural Specimens, together with other Geological tions, and a powerful Lens, are calculated to start a boy thinker, has mastered for himself no ordinary knowledge of the formation Earth's Crust.—THOMAS J. DOWNING, GEOLOGIST, &c., Street, London, E.C.—Catalogues free.

GEOLOGY AND MINERALOGY

Special Collections for Teachers and Students, used with s Lecturers and Teachers of Geology in Great Britain. Obtained Bronze Medals at Sydney Exhibition, 1879, also in London, 18 1867.

200 Specimens in Cabinet	...	...	...	£2 2
100 ditto	ditto	...	...	1 1
50 ditto	ditto	...	...	0 10

New Lists of Collections, Apparatus, &c., now ready, and free cation to

JAMES R. GREGORY'S

Geological Museum and Repository,

88, CHARLOTTE STREET, FITZROY SQUARE

LA SEMAINE FRANÇAISE: a Weekl

Newspaper and Review in the French Language. Politics, Liter Science, Art, Varieties, Notes. Price 3d., through booksellers the railway bookstalls. Office, 37, Southampton Street, Strand, W.

LA SEMAINE FRANÇAISE: Journal Français pu l'Angleterre: Politique, Littérature, Sciences, Arts, Variétés, Nouv et Notes. Un exemplaire par la poste, 3½d., en timbres poste Abo ment franco par la poste—un an, 15s. 2d.; six mois, 7s. 3d. Prix à tous les libraires et aux gares des chemins de fer. On s'abonne bureaux, 37, Southampton Street, Strand, Londres, W.C.

LA SEMAINE FRANÇAISE.—"'La Semaine Fra çaise' has been brought out in London for the benefit of those Engl readers who may wish to study contemporary French from all point view, instead of confining their reading to one particular Gallic jou It certainly merits success."—*Graphic.*

LA SEMAINE FRANÇAISE.—"The numbers before us are full of good things. . . . . It will be far better for most than one of the best papers published in Paris itself. We are much pleased with the character of it, and believe it will be highly valued in all many households where French is cultivated. The printing is very well done."—*Queen.*

TERMS OF SUBSCRIPTION:—

	£ s.
Three months	3 10
Six ,, ...	7 7
Twelve ,, ...	15 0

Gardens, W.C.

THE CHEMICAL NEWS AND JOURNAL OF PHYSICAL SCIENCE.

EDITED BY W. CROOKES, F.R.S., &c.

Published every Friday. Price 4d.

No. 1111 (March 11) contains:—Detection of Iodine in Urine, by F. Field, F.R.S.—Simple and Expeditious Method of Preparing Pyrogallol for Dry-Plate Development, by T. E. Thorpe, F.R.S.—Preparation of Potassic Hydric Saccharate, by T. Bayley.—Reaction of Tartaric Acid, by H. J. K. Fenton, B.A., F.C.S.—Aräometric Method for the Estimation of Fat in Milk, by Dr. F. Soxhlet.—Proceedings of Societies.—Notices of Books.—Correspondence.—Chemical Notices from Foreign Sources.—Notes and Queries, &c., &c.

London: Boy Court, Ludgate Hill, E.C.

THE "HANSA"

Published since 1864 in Hamburg, is the only independent professional paper in Germany, dedicated exclusively to Maritime Objects. Essays, Critiques, Reviews, Reports, Advertisements. Strict eye kept upon the development of Maritime Affairs in every respect. Every second Sunday one Number in 4to at least; frequent supplements and drawings. Subscription at any time; preceding numbers of the year furnished subsequently. Price 12s. for twelve months. Advertisements 4d. a line, widely spread by this paper; considerable abatement for 3, 6, 12 months' insertion. Business Office: Aug. Meyer and Dieckmann, Hamburg, Alterwall. 28. Edited by W. v. FREEDEN, M.R., Hamburg, Alexander Street, 8.

THE BREWERS' GUARDIAN:

A Fortnightly Paper devoted to the Protection of Brewers' Interests, Licensing, Legal, and Parliamentary Matters.

REVIEW OF THE MALT AND HOP TRADES; AND WINE AND SPIRIT TRADE RECORD.

The Organ of the Country Brewers.

"The Brewers' Guardian" is published on the evenings of every alternate Tuesday, and is the only journal officially connected with brewing interests, Subscription, 16s. 6d. per annum, post free, dating from any quarter-day. Single Copies 1s. each. Registered for transmission abroad.

Offices—5, Bond Court, Walbrook, London, E.C.

NORTH BRITISH AGRICULTURIST

is the only Agricultural Journal in Scotland, and circulates extensively amongst Landed Proprietors, Factors, Farmers, Farm-bailiffs, and others interested in the management of landed property throughout Scotland and the Northern Counties of England.

The AGRICULTURIST has also a very considerable circulation on the Continent of Europe, America, Australia, and the Colonies.

The AGRICULTURIST is published every Wednesday afternoon in time for the evening mails, and contains Reports of all the principal British and Irish Markets of the week, besides Telegraphic Reports of those held on the day of publication.

The Veterinary Department is edited by one of the leading Veterinarians in the country, and is invaluable to the breeder and feeder as a guide to the rearing of animals, and their treatment when labouring under disease.

Full Reports are given of the Meetings of the Royal Agricultural Society of England, the Royal Agricultural Society of Ireland, the Highland and Agricultural Society of Scotland, the Scottish Chamber of Agriculture, and all the principal Agricultural Associations throughout Great Britain and Ireland.

For Advertisers addressing themselves to Farmers a better medium does not exist

Price 3d. By post 3½d. Annual Subscription, payable in advance, 14s.

Office—377, High Street, Edinburgh.

Post-Office Orders payable to Charles Anderson, Jun., Edinburgh.

ESTABLISHED 1843.

"The leading Farmers' paper."—CLARE SEWELL READ, ESQ., M.P.

THE CHAMBER OF AGRICULTURE JOURNAL AND FARMERS' CHRONICLE

(PRICE 3d. WEEKLY).

The representative organ of the Central and Provincial Chambers of Agriculture; *gives fuller reports of the discussions and proceedings* of this extensive organisation than any other agricultural paper. It devotes *special attention to the treatment of Agricultural Questions by Parliament*, besides containing ample Reports of the LATEST LONDON and COUNTRY CORN, CATTLE, HOP, PROVISION, and other Markets, with Original Articles on Practical Farming, the Dairy, Herd and Flock News, Horticulture, &c., &c. It is despatched every Monday evening in time for the country post.

Terms of Subscription, payable in advance, post free:—3 months, 3s. 9½d.; 6 months, 7s. 7d.; 12 months, 15s. 2d.

Published by W. PICKERING, 21, Arundel Street, Strand, London, W.

On the 1st of every Month.

TRIMEN'S JOURNAL OF BOTANY,

BRITISH AND FOREIGN.

New Series. Edited by JAMES BRITTEN, F.L.S., British Museum.

CONTENTS.—Original Articles by leading Botanists.—Extracts, and Notices of Books and Memoirs.—Articles in Journals.—Botanical News.—Proceedings of Societies

Price 1s. 3d. Subscription for One Year, payable in advance, 12s.

London: WEST, NEWMAN, & CO., 54, Hatton Garden, E.C.

In unserem Verlage erscheint:

DER NATURFORSCHER.

Wochenblatt zur Verbreitung der Fortschritte in den Naturwissenschaften.

Herausgegeben von Dr. WILHELM SKLAREK.

Wochentlich 1—1½ Bgn. in 4°.

Preis vierteljährlich 4 Mk.

Die nunmehr ihren XIV. Jahrgang beginnende Zeitschrift hat bei Allen, welche sich mit Naturwissenschaften beschäftigen, grossen Beifall gefunden.

Probenummern sind durch jede Buchhandlung zu erhalten.

Berlin, S.-W., 77, Charlottenstr.

FERD. DÜMMLER'S VERLAGSBUCHHANDLUNG.

(Harrwitz & Gossmann.)

On the 1st of every Month, price Sixpence.

THE ENTOMOLOGIST:

AN ILLUSTRATED JOURNAL OF BRITISH ENTOMOLOGY.

Edited by JOHN T. CARRINGTON,

With the Assistance of

FREDERICK BOND, F.Z.S. | JOHN A. POWER, M.D.
EDWARD A. FITCH, F.L.S. | J. JENNER WEIR, F.L.S.
F. BUCHANAN WHITE, M.D.

Contains Articles by well-known Entomologists on all branches of the Science; on Insects injurious or beneficial to Farm or Garden; Notes on Habits, Life-Histories; occurrence of Rarities, &c.; there are monthly lists of Duplicates and Desiderata.

Numerous WOODCUT ILLUSTRATIONS, to the printing of which especial attention is given, and occasional LITHOGRAPHED and CHROMO-LITHOGRAPHED PLATES.

SIMPKIN, MARSHALL, & CO., Stationers' Hall Court.

Chaque Samedi 16 pages grand in-8°, 2 colonnes

REVUE HEBDOMADAIRE

Scientifique, illustrée, spéciale, seul journal tenant les lecteurs au courant de tous les détails de l'Exposition universelle d'électricité, organe indépendant des exposants

RÉDACTEUR EN CHEF : W. de FONVIELLE

E. de CLISSON : DIRECTEUR

Un numéro, 40 *centimes.* — *L'année*, 18 *francs.*
Union postale 20 *francs.*

PARIS, 16, rue du Croissant, PARIS

Envoi de numéros spécimens gratis sur demande.

PRICE 1s. MONTHLY.

MACMILLAN'S MAGAZINE

FOR MARCH, 1881.

CONTENTS.

The Portrait of a Lady. By Henry James, Jun. Chapters XXI.—XXIV.
Christmas and Ancestor Worship in the Black Mountain. By Arthur J. Evans. Part III.
Byron. By Matthew Arnold.
Connemara. By Robert J. Martin.
The Penny Press. By Francis Hitchman.
On a Recent Criticism of Mr. Swinburne's. By Alfred Austin.

MACMILLAN & CO., LONDON.

FOR SALE.—A Collection of MINERALS,

the Property of the late Sir W. C. TREVELYAN, Bart.—Apply to S. G. PERCEVAL, Henbury, Bristol.

DRAPER'S INK (DICHROIC).

THE NEW BLACK INK

DIFFERING FROM ANYTHING ELSE EVER PRODUCED.

Writing becomes a pleasure when this Ink is used. It has been adopted by the principal Banks, Public Offices, and Railway Companies throughout Ireland.

It writes almost instantly Full Black. | Flows easily from the Pen.
Does not corrode Steel Pens. | Blotting-paper may be applied at the moment of writing.
Is cleanly to use, and not liable to Blot.

Can be obtained in London, through Messrs. BARCLAY & SONS, Farring-

In course of Publication.

PHILOSOPHICAL CLASSICS for ENGLISH READERS. Edited by Prof. KNIGHT, St. Andrews. In crown 8vo Volumes, with Portraits, price 3s. 6d. each.

This Day is Published, Vol. III.

BERKELEY. By A. Campbell Fraser, Professor of Logic and Metaphysics in the University of Edinburgh.

Vols. I. and II. contain—

DESCARTES. By Prof. Mahaffy, Dublin.

BUTLER. By the Rev. W. Lucas Collins, M.A.

Other Volumes in Preparation.

WILLIAM BLACKWOOD & SONS, Edinburgh and London.

This Day is Published.

A MONOGRAPH of the SILURIAN FOSSILS of the GIRVAN DISTRICT in AYRSHIRE. With Special Reference to those contained in the "Gray Collection." By Prof. H. ALLEYNE NICHOLSON, St. Andrews; and ROBERT ETHERIDGE, Jun., Pres. R.P.S., Ed. Vol. I.—The Protozoa, Actinozoa, Crustacea, Annelida, and Echinodermata. Royal 8vo, with 24 Lithographed Plates and other Illustrations on Wood. Price 21s.

Also sold in separate Fasciculi, viz.—

Fasciculus I. (Rhizopoda, Actinoza, Trilobita.) With 9 Lithographed Plates. 7s. 6d.

Fasciculus II. (Trilobita, Phyllopoda, Cirripedia, and Ostracoda.) With 6 Lithographed Plates. 5s.

Fasciculus III. (The Annelida and Echinodermata.) With 9 Lithographed Plates. 7s. 6d.

"A piece of palæontographical work of the very highest character, and we trust that the authors may be encouraged, by the reception it meets with from their *confrères* and the public, to complete it in the same style."—*Popular Science Review.*

WILLIAM BLACKWOOD & SONS, Edinburgh and London.

The CURRENTS of the AIR: Being Weather Forecast for 1881. Price 6d. By D. DEWAR.

JAMES BROWN & SON, 13, Drury Street, Glasgow.

In fcap. 8vo, with 50 Woodcuts, price 1s. 6d., cloth.

EXPERIMENTAL CHEMISTRY FOR JUNIOR STUDENTS. By J. EMERSON REYNOLDS, M.D., F.R.S., Professor of Chemistry, University of Dublin. PART I.—INTRODUCTORY.

"Dr. Reynolds' little manual is an excellent example of the experimental method applied to teaching, and is admirably adapted as a text-book for the use of the lower science classes in schools."—*Chemists' Journal.*

London: LONGMANS & CO.

LATEST EDITION OF GANOT'S PHYSICS.

In large crown 8vo, illustrated by 4 Coloured Plates and 844 Woodcuts, price 15s., cloth.

ELEMENTARY TREATISE on PHYSICS, Experimental and Applied, for the use of Colleges and Schools. Translated and Edited, with the Author's sanction, from GANOT'S "Éléments de Physique" by E. ATKINSON, Ph.D., F.C.S., Professor of Experimental Science, Staff College, Sandhurst. Ninth Edition, Revised and Enlarged.

"This well-known work has been before the public for sixteen years, and has now reached a ninth edition. Each new edition has contained both additions and revisions in accordance with the progress of science. The present edition differs from the last by an increase of subject-matter of twenty-five pages, while twenty-four new illustrations have been added. The illustrations are extremely good, and the various subjects are discussed with a sufficient infusion of mathematics to make the book serviceable for the use of the highest forms in schools and for scholarship and other examinations."—*Academy.*

By the same Translator, in crown 8vo, price 7s. 6d.

GANOT'S NATURAL PHILOSOPHY for GENERAL READERS and YOUNG PERSONS. Third Edition, Revised, with a Coloured Plate and 454 Woodcuts.

London: LONGMANS & CO.

Just Published, royal 8vo, cloth, 25s.

LIGHTHOUSE CONSTRUCTION AND ILLUMINATION. By THOMAS STEVENSON, F.R.S.E., F.G.S., Mem. Inst. C.E., Author of "Lighthouse Illumination," "The Design and Construction of Harbours," &c.

London: E. & F. N. SPON, 16, Charing Cross; New York: 446, Broome Street.

Now ready,

TRANSACTIONS of the ZOOLOGICAL SOCIETY of LONDON, Vol. xi. Part 3, price 30s., containing following papers:—On the Genera and Species of the Lepidop Sub-family Ophiderinæ inhabiting the Indian Region, by F. M F.Z.S., with three Coloured Plates.—On the Structure of the Sk the Chameleons, by W. K. Parker, F.R.S., with five Plates.

To be obtained at the Society's Office (11, Hanover Square, W.), at M Longmans', the Society's Publishers (Paternoster Row, E.C.), or th any Bookseller.

Just Published, price 2s. 6d.

An ELEMENTARY COURSE of PRACTICAL PHYSICS. By A. M. WORTHINGTON, M.A., F.R. Assistant Master at Clifton College.

RIVINGTONS, Waterloo Place, Pall Mall, London.

CHEMISTRY: a TREATISE ON. Prof. ROSCOE, F.R.S., and Prof. SCHORLEMM F.R.S., of Victoria University, Owens College, Manche With Illustrations, &c. Vols. I. and II. Inorg Chemistry.

Vol. I. The NON-METALLIC ELEMENTS.
Vol. II. Part 1.—METALS. 18s.
Vol. II. Part 2.—METALS. 18s.
Vol. III. ORGANIC CHEMISTRY. [In the p

"It would be difficult to praise this most valuable Tre too highly. . . . . The arrangement is clear and scientific facts gained by modern research are fairly represented judiciously selected, and the style throughout is singularly le —*Lancet.*

"A most valuable contribution to the literature of chem . . . . . The work when finished will afford the most co plete systematic exposition of the existing state of chem science that has yet appeared in the English langua *Nature.*

By Prof. ROSCOE, F.R.S.

LESSONS IN ELEMENTARY CHEMISTRY; Inorganic and Organic. With numerous Illus tions. New Edition. Fcap. 8vo. 4s. 6d.

PRIMER OF CHEMISTRY. With Illus trations. 18mo. 1s.

By Prof. SCHORLEMMER, F.R.S.

THE CHEMISTRY OF THE CARBON COMPOUNDS; or, Organic Chemistry. With Illus tions. 8vo. 14s.

"A better book than this, on organic chemistry, has not been written in any language."—*Pharmaceutical Journal.*

"Must prove eminently useful to the chemical student. *Athenæum.*

MACMILLAN AND CO., London.

THE ENTOMOLOGIST'S MONTHLY MAGAZINE.

Price Sixpence, Monthly, 24 pages 8vo, with occasional Illustrations Conducted by C. G. BARRETT, J. W. DOUGLAS, R. MCLACHLAN, F.L.S., E. C. RYE, F.Z.S., E. SAUNDERS, F.L.S., and H. T. STAINTON, F.L.S.

This Magazine, commenced in 1864, contains standard articles and notes on all subjects connected with Entomology, and especially on the Insects of the British Isles.

Subscription—Six Shillings per Volume, post free. The volumes commence with the June number in each year.

Vols. I. to VI. (strongly bound in cloth) may be obtained by purchasers of the entire set to date, at the increased price of 10s. each; the numbers of vols. may be had separately or together, at 7s. each.

London: JOHN VAN VOORST, 1, Paternoster Row.

N.B.—Communications, &c., should be sent to the Editors at the above address.

GEOLOGY AND MINERALOGY.

IN the Preface to the "Student's Elements of Geology" Lyell he says, "As it is impossible to enable the reader recognise rocks and minerals at sight by aid of verbal descr tions or figures, he will do well to obtain a well-arranged lection of specimens." These can be had from BAT WRIGHT, MINERALOGIST, 90, Great Russell Street, WC

50 Specimens in Cabinet	...	...	...	...	...	£1
100 ,, ,,	...	...	...	...	...	3
200 ,, ,,	...	...	...	...	...	5

&c., &c.

More extensive Collections from 50 to 2000 Guineas

THURSDAY, MARCH 10, 1881

SIR WILLIAM HERSCHEL

I.

ON March 13, 1781, the planet *Uranus* was discovered by William Herschel, and very opportunely at this ntenary of that memorable addition to the planetary stem, Prof. Holden has presented us with a popu- biography of the great astronomer and an outline of works, which he has been careful to make intelligible the general reader.[1]

Of the great modern philosophers, writes Prof. Holden, t one of whom least is known, is William Herschel, l we may appropriate the words which escaped him as of the starless spaces in the constellation Scorpio ssed through the field of his telescope, when his sister roline Herschel, his constant attendant during his ht-watches, tells us he exclaimed, "*Hier ist wahr- tig ein Loch im Himmel.*" A life of Herschel which all be satisfactory in every particular, Prof. Holden iarks, can only be written after a full examination of materials which may have been preserved by the ily; but as two generations have passed since his th, he thinks no apology will be needed for a con- entious attempt to make the best use of material eady in hand, scanty as it may be.

Herschel did prepare, about the year 1818, a biographi- note or memorandum, which was then placed amongst papers, and which has not been made public, and his er, writing in June, 1842, mentions having commenced work which she almost despaired of finishing, "The story of the Herschels," in which presumably her ther's life and work would have formed the main ture, but we do not hear that in her then infirm state health any considerable progress was made with it.

The only authentic sources of biographical information ore the world are in the "Memoir and Correspondence Caroline Herschel," published in 1876, and in a much known sketch of his life furnished by Herschel him- f in a communication to Lichtenberg, dated November 1783, and printed in the *Göttingen Magazine of ience and Literature*, iii. 4; this sketch was forwarded the request of Lichtenberg, when acknowledging the eipt of memoirs on double stars, &c., which Herschel d sent him.

William Herschel was born in Hanover on November , 1738, and was the second son of Isaac and Anna erschel. The musical taste which he exhibited early in appears to have been inherited from his father, who med one of the band of the Hanoverian Guards in 31. The eldest son Jacob was a clever musician, and st violin in the Court orchestra in 1759; he afterwards ned his brother William in this country, and on return- g to Hanover carried on a correspondence with him on usical subjects till his death in 1792. The youngest other Dietrich also shared in the musical abilities of e family, and at fifteen years of age was so far advanced to England, Herschel accompanied them as one of the band, and remained in this country about a year, when he returned to Hanover. During part of the disastrous campaign of 1757 he was on active service with the regiment, but after the defeat at Hastenbeck in July, it became evident that he had not the physical strength for the service, and his parents resolved to remove him. In connection with this circumstance Prof. Holden recalls a statement made by Sir George Airy, that the "removal" was a desertion, as he was told by the Duke of Sussex that on Herschel's first visit to the king after the discovery of the *Georgium Sidus*, "his pardon was handed to him by the king himself, written out in due form."

Herschel returned to England, though at what time does not appear. In fact from 1757 to 1760 we know nothing of his life. It is related in the Memoirs of Caroline Herschel that several pages referring to this period had been torn out in both her original Recollections and in the unfinished Memoir commenced in 1840. In 1760, however, he is again heard of, at Pontefract, as a young German in the band of the Durham militia, who spoke English almost as well as a native, and who was an excellent performer on the violin. It is conjectured that till his appointment as organist at Halifax in 1765, pupils and public concerts must have filled up his time; during a portion of this interval of five years he resided at Leeds, and in April, 1764, we are told he returned to Hanover on a very brief visit. In 1766 he obtained an engagement at Bath, and soon after was appointed organist at the Octagon Chapel. In this year, says Prof. Holden, he began a life of unceasing activity. His engaging manners made him friends, while "his talents brought him admirers and pupils, and pupils brought him money"; at this time he was giving thirty-five or more musical lessons in a week. In August, 1772, he proceeded to Hanover to take back to England his sister Caroline, afterwards his untiring assistant and companion in his surveys of the heavens. At this time his residence was in New King Street, Bath, and here in 1774 he had made himself a Gregorian telescope, probably on the model of Short's. In the preceding year, it is related of him, that he used to retire to bed with Smith's Harmonics and Optics, Ferguson's Astronomy, &c., and his first thoughts on rising were how to obtain instruments for viewing the objects of which he had been reading. We are told no optician had settled in Bath at that time.

Prof. Holden mentions that in *Journal* No. 1, preserved at the Royal Society, is a copy of Herschel's first observation of the nebula of Orion, made with his 5½-feet Gregorian reflector on March 4, 1774. In 1775, with a Newtonian telescope of 4½ inches aperture, and power of 222, also made by himself, he made his first review of the heavens, consisting in the examination of every star of first to fourth magnitudes and the planets; no records of these observations are now known to be in existence. In the same year the first 7-feet reflector was finished, and in 1777 one of 10 feet and one of 20 feet had been projected, and a grass-plot behind a house near Walcot turnpike, to which Herschel had removed at midsummer,

course of time, I took up astronomy, I determined to accept nothing on faith, but to see with my own eyes everything which others had seen before me. Having already some knowledge of the science of optics, I resolved to manufacture my own telescopes, and after many continuous, determined trials, I finally succeeded in completing a so-called Newtonian instrument, seven feet in length. From this I advanced to one of ten feet, and at last to one of twenty, for I had fully made up my mind to carry on the improvement of my telescopes as far as it could possibly be done." A very good twenty-feet reflector was finished in 1783, but the celebrated forty-feet instrument was not commenced until 1785. Herschel tells us in his description of the latter telescope that in all he made "not less than 200 7-feet, 150 10-feet, and about 80 20-feet mirrors, not to mention those of the Gregorian form, or of the construction of Dr. Smith's reflecting microscope," of which he also made a great number.

In or about 1779 Herschel removed to 19, New King Street, which was his last change of residence at Bath, and it was at this house that the planet Uranus was discovered. His first astronomical paper, on the variable star Mira Ceti, was written from thence, and appeared in the *Philosophical Transactions* for 1780: he had previously contributed a paper (his first publication) to the *Ladies' Diary* in 1779, in answer to a prize question proposed by Landen, viz. "the length, tension, and weight of a musical string being given, it is required to find how many vibrations it will make in a given time, when a small given weight is fastened to its middle, and vibrates with it." In the same volume of the *Phil. Trans.* he published observations relating to the mountains in the moon; at this time and subsequently he measured the heights of about 100, on three different methods. Most of these measures were never printed, and as Prof. Holden remarks at this date they would probably be of no material service to science.

His next paper presented to the Royal Society on January 11, 1781, is entitled "Astronomical Observations on the rotation of the Planets round their Axes, made with a view to determine whether the Earth's Diurnal Motion is perfectly equable," a paper which Prof. Holden views as affording the first obvious proof of the truth of the statement made by Herschel thirty years later, when he said, "A knowledge of the construction of the heavens has always been the ultimate object of my observations." It marks too an advance in practical astronomy: not only are the results given, but careful estimates of the errors to which they may be liable is made, with a discussion of the source of such errors.

On March 13 following Herschel made his great discovery of the planet *Uranus*, that *Georgium-Sidus*, as it was his wish it should be called, which made his name at once familiar throughout Europe. The discovery was announced in a paper communicated to the Royal Society on April 26 by Dr. Watson of Bath, an intimate friend of Herschel's, and strange as it may now appear to us, it is entitled "Account of a Comet." His own words referring to the circumstances of the discovery are as follows:—"On Tuesday, the 13th of March, between ten and one that appeared visibly larger than the rest: be struck with its uncommon magnitude, I compared : H Geminorum and the small star in the quartile betw Auriga and Gemini, and finding it so much larger t either of them, suspected it to be a comet. I was t engaged in a series of observations on the parallax of fixed stars, ... and those observations requiring r high powers, I had ready at hand several magnifiers 227, 460, 932, 1536, 2010, &c., all of which I have cessfully used upon that occasion. The power I had when I first saw the comet was 227. From experienc knew that the diameters of the fixed stars are not portionally magnified with higher powers as the pl are; therefore I now put on the powers of 460 and and found the diameter of the comet increased in pro tion to the power, as it ought to be, on a supposition its not being a fixed star, while the diameters of the s to which I compared it were not increased in the s ratio. Moreover, the comet being magnified much bey what its light would admit of, appeared hazy and defined with these great powers, while the stars preser that lustre and distinctness which from many thou observations I knew they would retain." The obser tions given in this paper extend to April 19, and Hers adds he was "happy to surrender it to the care Astronomer-Royal" (Dr. Maskelyne) and others as soo he found they had begun their observations upon little idea had he six weeks after he first glimpsed object of the great discovery he had made.

It is certain that at the date of this discovery the n of Herschel was unknown to the principal astrono on the Continent, and it is almost ludicrous to re the various guesses that were made respecting it. Holden transcribes the amusing passage from account of the discovery of *Uranus*: "In the *Littéraire* of June, 1781, this worthy man is MERSTHEL; in Julius' *Journal Encyclopédique*, SCHEL; in a letter from Mr. Maskelyne to M. Mes HERTHEL; in another letter of Maskelyne's to Herr at Manheim, HERRSCHELL [doubtless mis-reading Darquier calls him HERMSTEL. What may his name He must have been born a *German*." In the first no of the discovery in the *Connaissance des Temps* he is ca HOROCHELLE.

The telescope which Herschel was using on the even of March 13, 1781, was that with which his second re of the heavens was made, a reflector[1] of 85·2 inches f 6·2 inches aperture, and power, 227. This survey writes in 1783, "extended to all the stars of Harris's ca and the telescopic ones near them, as far as the eighth ma nitude. The catalogue of double-stars and the discov of the *Georgium Sidus* were the results of that review

Arago says if Herschel had directed his telescope towa the constellation Gemini eleven days earlier (March instead of March 13) the proper motion of the pla would have escaped him, for the planet was on the near one of its stationary points, and adds, "On par cette remarque à quoi peuvent tener les plus gran découvertes astronomiques." This implies a total conception of the case: as Prof. Holden remarks:—"

[1] When Sir John Herschel contemplated presenting one of his fa

new planet was detected by its appearance and not by its motion." Herschel, referring to his discovery in his communication to Lichtenberg, says: "This was by no means the result of chance, but a simple consequence of the position of the planet on that particular evening, since it occupied precisely that spot in the heavens which came in the order of the minute observations that I had previously mapped out for myself. Had I not seen it just when I did I must inevitably have come upon it soon after, since my telescope was so perfect that I was able to distinguish it from a fixed star in the first minute of observation." It is not to be supposed that so striking an object would have been viewed once and forgotten, even if no motion were immediately detected.

As is well known, Herschel feeling deeply his indebtedness to the liberality of George the Third, desired to testify his gratitude by giving his planet a name which would mark the epoch of its discovery, and in his letter on the subject addressed to Sir Joseph Banks, then President of the Royal Society, writes, "I cannot but wish to take this opportunity of expressing my sense of gratitude by giving the name Georgium Sidus,

Georgium Sidus
——jam nunc assuesce vocari,

to a star, which (with respect to us) first began to shine under his auspicious reign."

Prof. Holden dwells upon the changes which may be considered to have been effected in the state of astronomy not only in England but in the whole world, simply by the discovery of Uranus. "Herschel's researches would have gone into the *Philosophical Transactions* as the work of an amateur astronomer, Mr. Herschel, of Bath. They would have been praised and they would have been doubted. It would have taken a whole generation to have appreciated them. They would have been severely tried, entirely on their merits, and finally they would have stood where they stand to-day—unrivalled. But through what increased labours these successes would have been gained! . . . Certainly, if Herschel's mind had been other than it was, the discovery of Uranus, which brought him honours from every scientific society in the world, and which gave him authority, might have had a hurtful effect. But as he was, there was nothing which could have aided his career more than this startling discovery. It was needed for him. It completed the solar system far more by affording a free play to a profoundly philosophical mind, than by occupying the vacant spaces beyond Saturn. His opportunities would have been profoundly modified, though his personal worth would have been the same." We think there are few astronomers who will not be able to follow Prof. Holden in the views he has thus forcibly expressed.

At the hands of Sir Joseph Banks, Herschel received the Copley Medal of the Royal Society in 1781, for his "discovery of a new and singular star," and was formally admitted a Fellow of the Society on May 30, 1782. It was during this visit to London that Herschel was received by the king, and as he wrote to his sister the same day, met with a very gracious reception. Prof. Holden reproduces from the Memoirs of Caroline Herschel his letter of July 2, in which he describes his general satisfaction; the king in particular, he states, "enjoys observations with telescopes exceedingly." Herschel returned to Bath in the last week of July, and immediately prepared for removing to Datchet.

Here, at the end of his second chapter, we close our present notice of Prof. Holden's welcome volume, reserving for another week his third chapter on "Life at Datchet, Clay Hall, and Slough," and the concluding one on the general scientific labours of Herschel. It should be stated that while taking Prof. Holden's work as our text, particulars have been included in this notice which are not specially referred to in it, in view of the interest attaching to them at the present time, when, as stated above, a hundred years have elapsed since Herschel's discovery of *Uranus* doubled the known extent of the planetary system.

J. R. HIND

EXTINCT BRITISH ANIMALS

British Animals Extinct within Historic Times; with some Account of British Wild White Cattle. By J. E. Harting, F.L.S. (London: Trübner, 1880.)

THE wild animals formerly inhabiting Britain, which disappeared before the advance of the hunter and farmer in historic times, have hitherto only been treated in a disconnected fashion, in essays scattered through various periodicals, or in portions of books relating to other subjects. Mr. Harting has collected together in the present volume his own essays in the *Field* and in the *Popular Science Review*, and has brought to bear upon his subject a knowledge of records, and an acquaintance with sport, which render his work extremely valuable. His references are accurate, and he has availed himself of nearly every source of information. Consequently we have before us a work dealing with the bear, wolf, beaver, reindeer, and "wild cattle," worthy to be classed between Bell's "British Quadrupeds" on the one hand, and White's "History of Selborne" on the other, relating not merely to the animals, but to the forests in which they lived and to the mode in which they were hunted.

The common brown bear made its appearance on the Continent in the Pleistocene age, and crossed over to Britain while the areas of the North Sea and of the English Channel were fertile valleys abounding in animal life. Its remains occur both in the river-deposits and in the caves, and have been met with in the turbaries and alluvia of England and of Scotland, which belong to the prehistoric period. It was hunted by the Neolithic inhabitants of Britain, and used for food by the inhabitants of Colchester and Richmond in Roman times. From the "Penitentiale" of Archbishop Egbert (A.D. 750), in which the flesh of any animal torn by dog, wolf, fox, or bear, or any other wild animal is forbidden to be used for human food, it is clear that it was alive in this country at that time. In the days of Edward the Confessor Norwich furnished annually one bear to the king and six dogs for the baiting of it. This however does not prove the existence of wild bears in Britain at that date, because bear-baiting was almost a national sport among the English until bears became too costly and the public taste too refined for such brutal exhibitions. Fitz-Stephen tells us, in the

season with boar-fights, or bull- and bear-baiting. A grand exhibition of bear-baiting took place at Hatfield House when Queen Mary visited her sister, the Princess Elizabeth, during her confinement there, "with which their Highnesses were right well content." Soon after the ascension of the latter to the throne she entertained the Spanish ambassadors with bulls and bears, and some years afterwards she received the Danish ambassador at Greenwich, and entertained him with bear-baiting, "tempered with other merry disports." On one occasion at Kenilworth no less than thirteen bears were baited before the queen with large ban-dogs. From these notices it is evident that Queen Elizabeth was very fond of this sport. Some of the great nobles and ecclesiastics also kept bears and bear-wards. Latterly there were travelling bear-wards dependent upon their patrons. The bear was probably extinct in Britain about the time of the Norman Conquest, and is not known to have existed in Ireland within the historic period.

The wolf abounded in Britain in the Pleistocene and prehistoric periods, and varied in numbers in the historic age in proportion to the waste lands. It was a subject of many legal enactments, and grants of land were held for its capture. To the numerous references which Mr. Harting gives we may add an extract from the Litany of Dunkeld current in Scotland in the eleventh or twelfth century: "A cateranis et latronibus, a lupis et omni mala bestia, Domine, libera nos."

The animal had a price set upon its head by statute in 1621; the price paid for one wolf in Sutherlandshire was six pounds, thirteen shillings, and fourpence. In Ireland, in 1683, "for every bitch wolfe the price was six pounds, for every dog wolfe five pounds, for every cubb which preyeth for himself forty shillings, and for every suckling cubb ten shillings." It is obvious from these large prices that the wolf was becoming rare in Scotland and Ireland in the middle of the seventeenth century. The last of the British wolves was killed in Scotland in 1743 by MacQueen, a man remarkable for his stature and courage, who died in the year 1797. The memory of the exploit is still preserved by tradition. In Ireland the animal lingered until 1770. Mr. Harting deserves great credit for having collected together the evidence by which these dates can be fixed. The wolf became extinct in England in the reign of Henry VII.

The wild boar still lingered in Lancashire in 1617, and the last notice of the animal in the south of England is of the hunting of the wild boar at Windsor by James I. and his court. Mr. Harting considers that an entry in an account book of the steward of the manor of Chartley "1683.—February. Pd. the cooper for a paile for ye wild swine, 0 . 2 . 0.," proves that it was not extinct in England at that date. It seems however to us very unlikely that wild boars would have such attention paid to their wants, and more probable that they were domestic swine turned out into the woodlands to get the greater part of their own living.

The reindeer, so abundant in the late Pleistocene age, and so generally found along with Palæolithic implements, and so strangely associated with the remains of hippopotamus in the bone-dens of this country (a fact which ... gether from its last foothold in Caithness about the ... half of the thirteenth century. We may remark th... recent attempts to introduce the animal into Swit... have failed, apparently from the great heat of sum...

The beaver was living in the River Teivi, accord... Girald du Barry, in 1159; and, according to Boeth... taken in Lochness for the sake of its fur towards t... of the fifteenth century. We would call the atten... our readers to the remarkably interesting accoun... reintroduction by the Marquis into the Island o... where they are now increasing rapidly and build... dams. There is evidently no difficulty in natur... them in this country.

We close this review regretting that it is impos... do justice to the careful account of the different br... the "wild white cattle," which we believe to b... descendants of the domestic cattle introduced ... English, and which have always lived in unm... lands. W. BOYD DAWK...

OUR BOOK SHELF

Notes of Observations of Injurious Insects. N... 1880. By Eleanor A. Ormerod. 8vo. pp. ... (London: W. Swan Sonnenschein and Allen. ... burgh: J. Menzies, 1881.)

MISS ORMEROD and her assistants are to be con... lated on this very excellent Report, which is fa... bulky than its predecessors, and correspondingly ... and interesting, and well illustrated. At the ... a very significant fact is mentioned. The s... of 1880 was remarkably suitable for vegetation, an... attacks of insects consequently less severe; a high ... tion of vitality enabled the plants to more succes... cope with their insect enemies. The most ... species for the year was the well-known larva of ... (daddy-long-legs), which not only attacked its ... usual food, the roots of grasses, but proved ex... tremely injurious to peas, so that in one field of ... acres the prospective value in March was reduce... realised value of only about one half in June. ... crops were also attacked. Stimulating remedies ... as guano, salt, ammoniacal liquor, &c., had a good e... but the grubs appeared to be remarkably inse... to ordinary poisonous solutions. An experiment m... Kew Observatory as to the amount of cold they can en... showed that some survived 42° of frost. Another ... injurious species was *Tephritis onopordinis* (the celery ... a dressing of gas-lime, unslaked lime, and soot had a ... effect. The singularly misnamed *Psila rosæ* (the c... fly) was also obnoxious; sowing the seeds in a mi... of leaf-mould, ashes, &c., proved of excellent servi... this case. *Sitones lineatus* was very injurious to ... We think Miss Ormerod acts injudiciously in calling ... insect the "pea-weevil." Its larva is certainly very ... given to attacking peas and many other plants, by ea... the young shoots, but the true pea-weevil is *Bruchus* ... which destroys the peas themselves by feeding inside ... For the gooseberry saw-fly nothing proved so effectu... digging out the earth round the bushes when the l... and pupæ are underground, the removed portion ... taken away and burnt; a suggestion that if pre... woollen cloth be placed on the bushes the parent fly ... deposit her eggs thereon seems far-fetched. Miss ... merod has great faith in the efficacy of paraffine. ... future it is proposed to extend the Report to insects ... hitherto specially mentioned as desirable for observa... We ...

Mémoires de la Société des Sciences Physiques et Naturelles de Bordeaux. 2e série, tome iv., 1me cahier. (Paris: Gauthier-Villars, 1880.)

THIS number contains Conférences de Géométrie supérieure by M. Saltel, in which is given an exposition of the method of analytical correspondence with two applications, the object of the one being to find the number of common solutions in k equations between k unknowns, and of the other to find the degree of a geometrical locus defined by certain algebraic conditions. The methods employed are based on that of M. Chasles's "Principe de Correspondance." The next paper, by M. Imchenetsky, "Détermination en fonction des coordonnées de la force qui fait mouvoir un point matériel sur une section conique," is an interesting one, and is founded upon a remark of M. Bertrand's ("Sur la possibilité de déduire d'une seule des lois de Kepler, le principe de l'attraction, *Comptes rendus*, April 2, 1877), "il serait intéressant de résoudre la question suivante. En sachant que les planètes décrivent des sections coniques, et sans rien supposer de plus, trouver l'expression des composantes de la force qui les sollicite en fonction des coordonnées de son point d'application." The author arrives at his result by taking his equation in the form—

$$px^2 + qy^2 + 2rxy = (ax + by + c)^2.$$

Prof. Teixeira of Coimbra has a short note "Sur les principes du calcul infinitésimal," which calls for no special comment. Dr. G. Sous follows with what appears to us a good article entitled "Phakomètre et Optomètre." For the uninitiated "Les phakomètres sont des instruments destinés à mésurer la distance focale d'une lentelle quelconque." The principle of construction of Silbermann's and of Snellen's is, when an object is placed at twice the focal distance from a converging lens, the real image of the same size as the object is situated also at double the focal distance from the lens. The objection to Silbermann's appears to be its length, which renders it awkward to carry, and to Snellen's that it is not applicable to diverging lenses.

Dr. Sous gives a form which is not liable to either of these defects, and the construction of which is based upon a physical theory, not hitherto, he states, applied to these instruments; but we must refer those interested in optics to the paper itself (fourteen pages in length). The rest of the book is devoted to "Morphologie de la membrane de Schrapnell," Dr. Coyne; "Études d'Optique Physiologique; Influence du Diamètre de la Pupille et des Cercles de Diffusion sur l'acuité visuelle," Dr. Badal; "Les Températures de la Mer dans l'estuaire Girondin et à Arcachon en décembre, 1879, et janvier, 1880," M. Hautreux; "Des Os et de leur Emploi dans la Fabrication du noir Animal, du Suif, du Sulfate d'ammonique, des Boutons," &c., M. Huyard.

LETTERS TO THE EDITOR

[The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts. No notice is taken of anonymous communications.

The Editor urgently requests correspondents to keep their letters as short as possible. The pressure on his space is so great that it is impossible otherwise to ensure the appearance even of communications containing interesting and novel facts.]

Aberration of Instinct

CASES of individual variations of instinct are of importance in relation to Mr. Darwin's theory of the development of instincts by natural selection. Under the belief that aberration of instinct may be regarded as a case, more or less extreme, of variation, I originally from Sussex, and had lived, respected and admired, to see their children of the third generation, when he suddenly became the victim of the infatuation I am about to describe. . . .

"No eccentricity whatever was remarked in his conduct until one day I chanced to pick up somewhere in the garden a ginger-beer bottle of the ordinary brown stone description. I flung it into the yard, where it fell immediately below the pigeon house. That instant down flew paterfamilias, and to my no small astonishment commenced a series of genuflexions, evidently doing homage to the bottle. He strutted round and round it, bowing and scraping and cooing and performing the most ludicrous antics I ever beheld on the part of an enamoured pigeon. . . . Nor did he cease these performances until we removed the bottle; what proved that this singular aberration of instinct had become a fixed delusion was this, whenever the bottle was thrown or placed in the yard—no matter whether it lay horizontally or was placed upright—the same ridiculous scene was enacted; at that moment the pigeon came flying down with quite as great alacrity as when his peas were thrown out for his dinner, to continue his antics as long as the bottle remained there. Sometimes this would go on for hours, the other members of his family treating his movements with the most contemptuous indifference, and taking no notice whatever of the bottle. At last it became the regular amusement with which we entertained our visitors, to see this erratic pigeon making love to the interesting object of his affections, and it was an entertainment which never failed, throughout that summer at least. Before next summer came round he was no more."

GEORGE J. ROMANES

Prehistoric Europe

A FEW last words with Prof. Dawkins, and I have done:—

1. Having discovered that a certain absurd opinion which he attributed to me is nowhere to be met with in the volume he was supposed to be criticising, Mr. Dawkins now imagines that he has found grounds for his assertion in my "Great Ice Age," written and published some years ago. Here again he is quite mistaken. The passage cited by him, even if it be considered apart from its context, will not bear the interpretation he puts upon it. Had he read the page he quotes from with intelligent attention he would have seen that I was referring to the well-known fact that the ossiferous and Palæolithic gravels of East Anglia are represented in the North by the equivalent ossiferous *Cyrena*-beds near Hull, which dovetail with and are overlapped by glacial deposits. In other words, they rest upon a *lower*, and are covered by an *upper* boulder-clay. But I have nowhere said, nor would any candid reader infer from what I have written, that this upper boulder-clay (that of Hessle) ever extended south so as to cover the Palæolithic gravels throughout East Anglia. I am surprised that a professor of geology does not apparently understand the meaning of the term "overlap." Were I to state that in certain districts in Scotland the Carboniferous strata are overlapped by a conformable series of Red Sandstones, should I be understood to imply that these Red Sandstones formerly covered the entire area now occupied by the Carboniferous rocks of Great Britain?

2. Mr. Dawkins has accused me of having suppressed evidence which told against my views, and he now repeats this offensive accusation, citing in justification my description of the Victoria Cave, from which, he says, I have omitted all reference to the discovery of reindeer in the lower cave-earth. Now it is not true that I have ignored this alleged discovery, for I remark that "it seems doubtful whether the remains of that animal, said to have been obtained from the lower earth, really belonged to that deposit." My reasons for this doubt (which I share with other geologists) I did not consider it necessary to give, but they are simply these:—

(1) The explorations in the cave were carried on at first, under Mr. Dawkins's superintendence, by means of shaft-digging, a very unsatisfactory system of "cave-hunting," and one which, even with the most conscientious care, is liable to give false results.

(2) During the subsequent prolonged and scientifically-conducted explorations no recognisable reindeer remains were ever obtained in the lower stratum. These facts alone are sufficient to justify my scepticism. I quite agree with Mr. Dawkins

enough commingled in one and the same accumulation. It is to account for this remarkable commingling that a large portion of my book was written.

3. Mr. Dawkins seems to be ignorant of the fact that the ossiferous deposits of Mont Perrier occur on two separate and distinct horizons. The *lower* bed, characterised by the presence of *Mastodon arvernensis* and other extinct forms, is unquestionably true Pliocene. It is overlaid by the "puniceous conglomerate," with its far-transported and glacially-striated erratics. Upon the denuded surface of this well-marked morainic accumulation rests the *upper* bed, which contains a very different mammalian fauna—*Elephas meridionalis, Rhinoceros leptorhinus* (Cuv.), hippopotamus, tapir, horse, cave-bear, hyæna, hedgehog, &c. The flora associated with this fauna is not Pliocene but Pleistocene. The upper bed is overlaid in turn by a newer set of glacial moraines and erratics. The list of Upper Pliocene Mammalia from Mont Perrier and Issoire, given by Mr. Dawkins in his "Early Man in Britain," consists of a "hash-up" of the species derived from those two separate and distinct horizons.

4. The most recent list of mammalia from the lignite-beds of Leffe and Borlezza is quoted by me from Prof. Stopanni, on the authority of Dr. Forsyth Major. All the species in that list, without exception, have frequently occurred in Pleistocene beds, the age of which is generally admitted. The plants and shells associated with these species are all likewise Pleistocene forms. Moreover, as Stopanni has demonstrated, and as I can testify, the stratigraphical evidence proves that the beds pertain to the Glacial series. Prof. Mayer, no mean authority, has shown that the upper beds of the so-called Pliocene of the Val d' Arno (containing *Elephas meridionalis* and hippopotamus) are not the equivalents of the marine Pliocene, as has hitherto been the belief of palæontologists, but must be classified as Quaternary or Pleistocene.

5. All that I say with regard to the age of the skull of Olmo occurs on p. 318 of my book, and what I say is simply this, "It pertains to Pleistocene times—to the period during which *Elephas meridionalis* belonged to the European fauna." I do not assert its Interglacial age. It may be either Preglacial (*i.e.* early Pleistocene) or Interglacial as the Leffe beds are.

I was not aware that geological classification is always based on zoology alone. I am under the impression that botanical evidence, when it can be obtained, is not despised, and that stratigraphical and other physical evidence is not usually ignored. In trying to work out the historical geology of the Pleistocene, I have considered the palæontological as fully as the physical evidence. Mr. Dawkins would have me rest contented with that of the mammalia alone, as interpreted by himself.

Perth, February 19. JAMES GEIKIE

As my name has been imported into the controversy between Prof. Dawkins and Dr. James Geikie, will you kindly permit me to state that I am quite prepared, after re-reading the account given by Dr. Geikie of the Victoria Cave, to accept all responsibility for its correctness.

Without entering into the general question, in the particular case of the Victoria Cave the evidence for the contemporaneity in the same area of the reindeer and hippopotamus is not very cogent; a review of all the evidence from that source indeed points the other way. The specimen mentioned by Prof. Dawkins was, according to his Report,[1] found in digging a shaft, a method of exploration unfortunately at that time (1872) employed by the Committee. The subsequent explorations, which were not conducted in this manner, but by carefully removing the deposits, layer by layer, to prevent any possibility of accidental mixture of the remains, gave abundant evidence of reindeer in the upper beds, but not any satisfactory evidence of its presence in the lower beds, containing *Hippopotamus, Elephas antiquus, Rhinoceros leptorhinus*, &c. This is a point, amongst others, to which, as Reporter to the Committee, I paid careful attention, and the details were impartially given in the Reports.[2] The absence of reindeer from a lower bed, the only one containing the same fauna in the Creswell caves explored by the Rev. M. Mello and Prof. Dawkins, is worthy of note as bearing on the same subject.

As regards the evidence for the antiquity of man from the he "has only called those witnesses which count on his Prof. Dawkins, in dismissing the whole of this evide "founded on a mistake," must be aware that he is using venient formula which can only apply fairly to a part of doubtfulness of which has already been fully conceded entirely shelves other evidences which are the result of and careful exploration.[1]

To state that he doubts their cogency would be to course of which no one would complain; but to say as a matter of general agreement that they are "founded mistake," looks like an attempt to stifle discussion.

But his remarks are so obviously polemical that t geologists they will probably carry more amusement conviction than the writer contemplated.

Hastings, February 19 R. H. TIDDEM

Les lettres d'Outre-mer

IN the Notes, published in NATURE of January 13, the last paragraph gives, as a fact, an announcement simplest post-office in the world" in Magellan Straits, existence.

At least fourteen years ago there was published account of this unique establishment by the most emine living French writers, M. Victor Hugo, who introduces cumstance into his famous work of fiction, "Les Trav de la Mer"; and ever since reading the account I have wa where the great author obtained his circumstantial relati refers to the year 1823. Nor can I believe that such of oceanic exchange ever really was in existence, at least spot indicated, for a very good reason; that at the poi cated, viz. the neighbourhood of Port Famine, when the was there in 1834 (see Darwin's "Naturalist's Voyage," xi.), "the Fuegians twice came and plagued" the crew; an open barrel would hardly be safe. Darwin, also, who Mount Tarn, the most elevated point in this district, wou have mentioned this famous barrel post-office, had it exis

I am therefore curious to know whence the note in N was compiled, but I fancy the account is apocryphal. Th were however other oceanic post-offices somewhat s principle is a fact in reality.

In 1673 Ascension was visited by the Dominican F Navarette, who speaks of it then as the "*Sailor's Pos* "Mariners of all nations being accustomed at that time letters here, sealed up in a bottle, in a certain known some rock, to be taken away by the first ship which pass opposite direction" (Mrs. Gill's "Six Months in Asce p. 61). And again in 1769 we find the following extract

"1769, *Feby.*

"Ascension island.

Bougainville.

Louis de Bougainville, Colonel of Foot and Commodore Expedition in the Frigate *La Boudeuse*.

Arrd. and anchored in the North-west creek or '*Cro Mountain of the Cross.*'

Anchorage according to Abbé la Caille.

7° 54′ s.—16° 19′ west, of Paris.

Variation 9° 45′ NW.

Three creeks caught turtle.

N.E. creek. N.W. creek. English creek, S.W.

"In the afternoon the bottle was brought to me which tains the paper whereon the ships of every nation generally their name, when they touch at Ascension Island.

"This bottle is deposited in a cavity of the rocks of th where it is equally sheltered from rain and the spray of the In it I found written the *Swallow*, that English ship Captain Carteret commanded, and which I was desirous of ing.[2] He arrived here the 31st of January, and set sail on the 1st of February; thus we had already gained six upon him, after leaving the Cape of Good Hope. I inver the *Boudeuse* and sent back the bottle."

At page 4 of Melliss' "Account of St. Helena (187 wood-cut of the South Atlantic Post Office of 1645. Spea of the island of St. Helena. Mr. Melliss says:—

nglish; and Portuguese authority seems to have been lessened, rough that Power being interested in acquiring possessions lsewhere, and the island was for a while deserted, though still sed by the captains and crews of ships as a South Atlantic ost-office. It was customary to place letters under huge oulders of stone, marked in a conspicuous manner, so that ie crews of ships returning from India might obtain news om home. An interesting record of this period is still to be en on a rude block of lava measuring nearly five feet high and vo feet six inches wide, which has been preserved by being ubsequently built into a large mass of masonry in the James-own burial-ground."

In the Galapagos Islands there is a bay named Post-Office ay, which seems to indicate an analogous nautical exchange ation.

I subjoin Victor Hugo's description, and shall be much bliged to any of your readers who can refer me to any ac-ount of the earlier voyagers whence this scene was derived.

S. P. OLIVER

2, Eastern Villas, Anglesey, Gosport, February 28

P.S.—If any one can give me a reference, also, where I can nd an account of the wreck of the *Grosvenor* on the south-east ast of Africa in 1782, I shall be extremely obliged.

"*Les Travailleurs de la Mer*, édition illustrée (1866). Livre nquième, ix.

—Renseignement utile aux personnes qui attendent, ou raignent, des lettres d'outre-mer" (p. 91).

"Ne disiez-vous pas, Capitaine Gertrais que la *Tamaulipas* ne élâchera point?

—Non. Il va droit au Chili.

—En ce cas il ne pourra pas donner de ses nouvelles en route.

—Pardon, Capitaine Clubin. D'abord il peut remettre des épêches à tous les bâtiments qu'il rencontre faisant voile pour urope.

—C'est juste.

—Ensuite il a *la boite aux lettres de la mer.*

—Qu'appelez-vous la boite aux lettres de la mer?

—Vous ne connaissez pas ça, Capitaine Clubin?

—Non.

—Quand on passe le detroit de Magellan.

—Eh bien?

—Partout de la neige, toujours gros temps, de vilains mauvais ents, une mer de quatre sous.

—Après?

—Quand vous avez doublé le cap Monmouth.

—Bien. Ensuite?

—Ensuite vous doublez le cap Valentin.

—Et ensuite?

—Ensuite vous doublez le cap Isidore.[1]

—Et puis?

—Vous doublez la pointe Anna.[1]

—Bon. Mais qu'est ce que vouz appelez la boite aux lettres le la mer?

—Nous y sommes. Montagnes à droite, montagnes à gauche. Des pingouins partout, des pétrels-tempêtes. Un endroit terrible. Ah! mille saintes mille singes! Quel bataclan, et comme ça tape! La bourrasque n'a pas besoin qu'on aille á son secours. C'est là qu'on surveille la lisse de hourdi! C'est là qu'on diminue la toile! C'est là qu'on te vous remplace la grande voile par le foc, et le foc par le tourmentin! Coups de vent sur coups de vent. Et puis quelque-fois quatre, cinq, six jours de cape sèche. Souvent d'un jeu de voiles tout neuf il vous reste de la charpie. Quelle danse! des rafales à vous faire sauter un trois-mâts comme une puce. J'ai vu sur un brick anglais, le '*True Blue*,' un petit mousse occupé à la '*gibboom*' emporté à tous les cinq cent mille millions de tonnerres de Dieu et la '*gibboom*' avec. On va en l'air comme des papillons, quoi! J'ai eu le contre-maître de la *Revenue*, une jolie goëlette, arraché de dessus le *fore-crosstree*, et tué roide. J'ai eu ma lisse cassée, et mon serre-gouttière en capilotade. On sort de là avec toutes ses voiles mangées. Des frégates de cinquante font eau comme des paniers. Et la mauvaise diablesse de côte! Rien de plus bourru. Des rochers déchiquetés comme par enfantillage. On qu'on a doublé la pointe Anna on voit sur un caillou de cent pieds de haut un grand bâton. C'est un poteau qui a une barrique au cou. Cette barrique, c'est la boîte au lettres. Il a fallu que les anglais écrivent dessus: POST OFFICE. De quoi se mêlent ils? C'est la poste de l'océan; elle n'appartient pas à cet honorable gentleman, le roi d'Angleterre. Cette bôite aux lettres est commune. Elle appartient à tous les pavillons. POST OFFICE, est-ce assez chinois? Ça vous fait l'effet d'une tasse de thé que le diable vous offrirait tout à coup. Voici maintenant comment se fait le service. Tout bâtiment qui passe expédie au poteau un canot avec ses dépêches. Le navire qui vient de l'Atlantique envoie ses lettres pour l'Europe, et le navire qui vient du Pacifique envoie ses lettres pour l'Amérique. L'officier commandant votre canot met dans le baril votre paquet et y prend le paquet qu'il y trouve. Vous vous chargez de ces lettres-la; le navire qui viendra après vous se chargera des vôtres. Comme on navigue en sens contraire, le continent d'ou vous venez, c'est celui ou je vais. Je porte vos lettres, vous portez les miennes. Le baril est bitté au poteau avec une chaîne. Et il pleut! Et il neige! Et il grêle! Une fichue mer! Les satanicles volent de tous côtés. Le *Tamaulipas* ira par là. Le baril a un bon couvercle à charnière, mais pas de serrure ni de cadenas. Vous voyez qu'on peut écrire à ses amis. Les lettres parviennent.

—C'est très-drôle, murmura Clubin rêveur."

Explosive Gas in a Lake

A FRIEND, on whom I can rely, informs me that during the late frost, Loch Ken in Kirkcudbrightshire was frozen over, affording pastime to curlers and skaters. Here and there, however, small spots of the surface, near to the shore, resisted the frost longer, and when they did freeze the ice was very thin. These pot-holes were dangerous to skaters, the largest being about size enough to admit an ordinary curling stone. Gas was emitted from them, and when the ice for the first time was formed over them one person got his face severely burned by boring a small hole in the thin ice and setting fire to the gas thus liberated, with a match. After a while the gas seemed to lose its power of combustion and the experiment could be repeated with impunity, a feeble flame only being evoked, when the hole was first drilled.

J. SHAW

Dumfriesshire, March 4

Colours of British Butterflies

THE sober colouring of the under-wings of many of our butterflies is universally accepted as being "protective." Let the gorgeous "peacock," for instance, but close his wings, and it takes a sharp eye to see him. Why then should he and so many other kinds flaunt their most brilliant hues in the brightest sunshine, and often be rendered even more conspicuous by perching on a yellow flower? One would think that this was the exact way to attract birds, especially as the colours are not likely to be "warning" ones, for if so, why the sober hues of the under sides of the wings? The colours can hardly be "warnings" to particular kinds of birds and "protective" against the attacks of others. The explanation may be that the facilities for recognition, and thus for the continuation of the species, are so much greater in bright light, as to render it advantageous on the whole to run the chance of easier capture in the brighter parts of the day: or it may be that relatively few birds feed at the times that butterflies choose to display their beauties.

In watching butterflies it appears clear that they are, so to speak, shortsighted, for it is the commonest thing possible to see two entirely different sorts circle round each other for some time as if they had to decide whether they are of the same kind or not. In doing this it will be observed that they fly, as it were, over and over each other, so that for quite half the time the gambols are going on, the dark side of the "protected" kinds is shown to the insect below. There steps in a provision which seems admirably adapted for enabling recognition to take place. It will be found that though the wings of protectively coloured butterflies appear very dark at a casual glance, yet that

coloured under-wings. Of these fifteen all have some more or less transparent spaces or colourings. In some cases portions of the under-wings are brightly coloured, though not transparent, but both in this case and when there are transparent places they appear chiefly on parts that are apparently invisible when the wings are closed. If these observations are correct, the insects are carefully protected when at rest or when they are laying their eggs. Whether they pair on the ground or with shut wings I do not actually know, for after carefully watching every butterfly I have come across for two summers, I have not succeeded in seeing any of the protectively coloured sorts pairing. It seems likely enough therefore that their protective colours come into play then. My opportunities for observation are however extremely limited, and it is to draw the attention of those more favourably situated to the subject of the colours of our common butterflies that I write this. In the fifteen protectively-coloured butterflies mentioned above I did not include the "fritillaries," because of the strange metallic lustre on their under-wings. Still they seem suddenly to disappear when they settle, and the metallic spots may take the place of the transparent or coloured ones in other sorts by throwing off the light, and thus enable the insects to recognise each other. Eight kinds more or less transparent but not seemingly protectively coloured, and two common "Blues," make up the thirty kinds I have been able to handle. The under-wings of the "Blues" are certainly protectively coloured, but there seems to be no transparency or bright markings in them.

J. INNES ROGERS

Putney, February 24

Dust, Fogs, and Smoke

THE present endeavours to alleviate the smoke nuisance in London give some interest to the description of the effects of coal smoke on London life in former ages.

I do not mean to speak of the well-known petition presented to Edward the First by the nobility and gentry against the use of sea-coal in London and the consequent proclamation of that monarch interdicting its use. But I allude to the following lines written and published by Evelyn in 1661 in his "Fumifugium," but which I borrow from the "History of London," by Noorthouck, London, 1773.

"The immoderate use of, and indulgence to sea-coale alone in the city of London, exposes it to one of the fowlest inconveniences and reproaches, that can possibly befall so noble, and otherwise incomparable city: and that, not from the culinary fires, which for being weak and lesse often fed below, is with such ease dispelled and scattered above, as it is hardly at all discernible, but from some few particular tunnells and issues, belonging only to brewers, diers, lime-burners, salt, and sope-boylers, and some other private trades one of whose spiracles alone, does manifestly infect the aer, more than all the chimnies of London put together besides. And that this is not the least hyperbolie, let the best of judges decide it, which I take to be our senses: whilst these are belching it forth their sooty jaws, the city of London resembles the face rather of Mount Ætna, the court of Vulcan, Stromboli, or the suburbs of hell, than an assembly of rational creatures, and the imperial seat of our incomparable monarch. For when in all other places the aer is most sereue and pure, it is here ecclipsed with such a cloud of sulphure, as the sun itself, which gives day to all the world besides, is hardly able to penetrate and impart it here; and the weary traveller, at many miles distance, sooner smells, than sees the city to which he repairs. This is that pernicious smoake which sullyes all her glory, superinducing a sooty crust, or furr upon all that it lights, spoyling the moveables, tarnishing the plate, gildings, and furniture, and corrodding the very iron bars and hardest stones with those piercing and acrimonious spirits which accompany its sulphure; and executing more in one year than exposed to the pure aer of the country it could effect in some hundreds. It is this horrid smoake which obscures our churches and makes our palaces look old, which fouls our clothes, and corrupts the waters, so as the very rain and refreshing dews which fall in the several seasons precipitate this impure vapour, which with its black and tenacious quality, spots and contaminates whatever is exposed to it. It is this which scatters and strews about those black and smutty atomes upon all things fowl, and kills our bees and flowers abroad, suffering not our gardens to bud, display themselves or ripen; so a anemonies and many other choycest flowers will by no be made to blow [*sic*] in London, or the precincts of it, they be raised on a hot-bed and governed with extraor artifice to accellerate their springing; imparting a bitter ungrateful tast to those few wretched fruits, which never ing to their desired maturity seem, like the apples of Sod to fall even to dust when they are but touched. Not there to be forgotten is that which was by many observed, that year 1644 when Newcastle was besieged and blocked up late wars, so as through the great dearth and scarcity of co those fumous works many of them were either left off, or but few coales in comparison to what they now use; gardens and orchards, planted even in the very heart of L (as in particular my lord Marquesse of Hertford's in the Str my lord Bridgewater's and some others about Barbican), observed to bear such plentiful and infinite quantities of as they never produced the like either before or since to great astonishment: but it was by the owners rightly to the penury of coales and the little smoake, which they notice to infest them that year; for there is a virtue in the to penetrate, alter, nourish, yea and to multiply plants and without which no vegetable could possibly thrive."

The improvement mentioned by Evelyn, when the use of was for a time less extensive in London, is particularly w of notice, and ought, I think, to be considered as an encou ment to persist in the attempt of rendering London as sm as possible.

CHAR

Jersey, February 25

THE GERMAN CHEMICAL SOCIETY

ON November 11, 1867, a meeting of about e chemists was held in Berlin to take step inaugurating a new Chemical Society. On Januar the succeeding year (1868) the first meeting of the S was held, when Prof. A. W. Hofmann was el president, and the roll-call of the Society contained names. During the first year of its existence 97 pa were read before the Society; at the close of the ye membership had increased to 275, and the Society or that a volume of 282 pages was needed to contain papers communicated to it.

Since 1868 the German Chemical Society has be increased in size and in usefulness; the *Berichte* fo consists of two large volumes numbering, between th 2473 pages, and containing the 563 papers communic to the Society during the year, besides numerous abs of papers published elsewhere. The income of Society for 1880 amounted in round numbers to the s of 2000*l.*, and of this about 1400*l.* was set against the of publishing the *Berichte*.

During the thirteen years of its existence the Ger Chemical Society has published in its *Berichte* mo the important discoveries in pure chemistry made in period. It has been the aim of the Society to pub papers communicated to it with as little delay as poss Meetings are held twice monthly during the session. the papers read at one meeting are published in *Berichte*, which appears on the day on which the meeting takes place. Papers appearing within so shor time after they are communicated are necessarily bre and concise; but this rapid publication confers a gre benefit on all chemists, as they are thus put in possess of at least the leading facts concerning all recent wo almost as soon as these facts have been established the workers. If papers in the *Berichte* are sometime wanting in completeness and symmetry, many of them are full of life and stir, telling as they do of work actual proceeding in the laboratory; appearing sometimes short abrupt snatches, they convey something of the

y the Society; formerly a correspondent in London or aris, &c., sent a general account of chemical work published in the country from which he wrote. The abstracts f the German Society are on the whole shorter than ıose which have for many years made the *Journal* of our wn Chemical Society of such great value to the student; ıey are, however, published at a shorter interval after ıe appearance of the original paper.

Brief accounts are given of recent chemical patents, ıut little space is devoted to purely technical chemistry. s not the *Journal* of the Chemical Society sometimes verburdened by abstracts which might better find a lace in a book professing to collect receipts for the urely "practical man"?

The German Chemical Society in 1877 appointed Dr. . Bischof of Berlin to prepare a general index for the rst ten volumes of the *Berichte*. The arduous task has een admirably fulfilled. Fellows of the Society have now ı their hands not only an index to the *Berichte*, but a olume which is really a general guide to the chemical ork published during the period 1868–1877.

The "Generalregister" extends to 1020 pp.; of these, 62 pp. are devoted to an index of authors, 732 pp. to an ndex of subjects, 42 pp. to an index of patents, and 84 p. to a systematic classification of the carbon compounds eferred to in the index.

Under an author's name are given, not the exact title f his paper, but a very succinct statement of the leading oints in the paper. The same method is pursued in the ubjects-index. Taking, for instance, such a general ubject as "Dissociation," one finds, first, references to ork on the general Theory of Dissociation, *e.g.* connecion between dissociation and temperature, tension, &c.; hen follow special instances of dissociation, inorganic ompounds preceding organic. In the case of individual lements or compounds, the references begin with those apers on the existence of the substance in question, hen follow its preparation and formation, its properties, ts action on other substances, the action of other bodies n it, its estimation, &c., &c.

A systematic nomenclature is adopted, more especially or the carbon compounds: the principles which guided he compiler are stated in a few introductory pages.

The "Generalregister" cannot but be of the greatest value to chemists generally. Almost every chemist is a Fellow of the German Society; many possess the *Berichte* complete up to date; with the *Berichte* and this admirable guide which Dr. Bischof has supplied, they can find almost everything that has been done in experimental chemistry within the period 1868–1877. M. M. P. M.

IRISH ESPARTO GRASS

IT is now over two years ago since attention was called in our pages to the importance of the purple Molinia (*Molinia cærulea*) as a material for making paper. Mr. Christie of Edinburgh sent a small quantity of it to be operated on by Mr. T. Routledge of Sunderland, and the report on this was most favourable. In January, 1879, a notice appeared in the *Times* also calling attention to the subject, and referring to the above favourable report; it expressed the hope that some effort would be used to have this grass collected on an extensive scale. It would seem to be ripe for gathering in the early autumn, when some hands could be spared for such work, and as the ground on which it flourishes—wet or partially drained bogs—pays, at least in Ireland, little if any rent, the crop would cost little over the expense of reaping it. Since the first notice appeared in our columns, the Spanish and African Esparto grass has been getting more difficult to obtain, and the demand for it has been steadily on the increase. It is said that the greater part of what is gathered in Morocco finds its way to the *Times* paper-mills, and its value for paper-making is now known in America. Several analyses of specimens of the dried hay made from this grass are given in a paper by Dr. Cameron, "On the Composition of a Crop of Hay" (*Proc.* Roy. Dub. Soc., n.s., vol. ii. p. 101); we select one of these, which yielded as follows:—

100 parts contained—

Water	27·95
Albuminoids	7·49
Fats	2·70
Non-nitrogenous substances	30·00
Woody fibre	31·26
Mineral water	0·60
	100·00

And of this the ash contained—

Lime	28·86
Magnesia	4·76
Potash and soda	42·17
Phosphoric acid	12·36
Sulphuric acid	5·98
Oxide of iron and alumina	1·00
Chlorine	4·32
Silica	0·55
	100·00

This freedom from silica of the purple Melic grass is very remarkable.

From a paper by Mr. W. Smith in the recent number of the *Proceedings* of the Royal Dublin Society, we learn that a very successful trial has been made in the county of Galway to grow this grass in some quantity. As a native plant it is found in every county in Ireland, both on wet heaths and boggy pastures. It flowers in July and August, and its seeds are ripe early in September; it would seem to grow well on partially drained bogs, and if the surface of these has been burnt, the purple Melic grass grows thereon most luxuriantly. It seems fond of growing in tufts, of somewhat large size, and it does not form a sod like so many other grasses. It would appear that in Ireland alone there are over 1,000,000 acres at the present moment not worth sixpence a year each for any agricultural purpose; each acre would easily grow half a ton weight of dried Melic grass, which at its lowest value would be worth 2*l*. Would not this crop, in time, more than compensate for the loss of the potatoe? It seems a pity that the manufacturer should have to go to the Port of Mogador for what he might get with so much greater ease at the Port of Dublin.

SIBERIAN METEOROLOGY

UP to the present time Yakutsk, in North-east Siberia, has often been cited as the place of our earth where the winter is coldest, while the minima observed during Arctic expeditions are believed to be the lowest known. Neither the one nor the other is true. In Maak's book, "Olekminski Okrug," I find many data which prove that the coldest winter as well as the lowest well-authenticated minima were observed at Werkhojansk, to the north-east of Yakutsk. The name of the author gives us some guarantee that the observations are trustworthy. I give below the minima at some places cited by Maak, and compare them with those observed in Central and Western Siberia, and the Arctic Archipelago of America:—

North-East Siberia

Serdze-Kamen.	67° N.	173° E.	(Nordenskjöld)	– 50·3 F.
Yakutsk	62° N.	130° E.	(Maak)	– 77·3 F.
Wiljuisk	64° N.	122° E.	(Maak)	– 76·3 F.
Werkhojansk	67½° N.	134° E.	(Maak)	– 81·0 F.

Central and West Siberia

Yenisseisk	58½° N.	92° E.		– 73·5 F.
Barnaul	53½° N.	84° E.		– 61·4 F

Arctic Archipelago

British Expeditions, 1875-76.	83½° N. Floeberg Reach (Nares)	− 73·7 F.
	81½° N. Discovery Bay (Nares)	− 70·7 F.

The temperature at Werkhojansk is the lowest of all given here, and it must be borne in mind that the observations lasted but one year, while we have more than thirty-five years at Yakutsk, and eight and a half at Yenisseisk.

The mean temperatures are as follows :—

	Year	July	Nov.	Dec.	Jan.	Feb.	March
Serdæ Kamen 1 yr.	—	—	2·1	− 9·0	−13·1	−13·2	− 6·9
Ustjansk 2 years	2·8	52·7	− 2·2	−33·0	−38·9	−36·9	−17·5
Werkhojansk 1 year	4·3	60·1	−29·2	−46·8	−55·5	−54·5	−29·0
Yakutsk 10 years [1]	12·2	66·5	−20·5	−41·9	−46·8	−37·7	− 0·0
Yakutsk 24 years [2]	12·4	63·3	−19·1	−37·8	−41·4	−30·8	− 8·7
Floeberg Beach 1 yr.	− 3·5	38·3	−16·8	−22·2	−33·0	−38·0	−39·8
Discovery Bay 1 yr.	− 4·2	37·2	−18·4	−24·5	−40·7	−35·0	−37·4

Though the observations were made only during one year at Werkhojansk, it is probable that it would have the coldest winter of all observed till now, as even at Yakutsk, which is the next coldest, January and February were in no single year colder than at Werkhojansk in 1869. From a comparison with the other stations of North-east Siberia it is probable that here in 1869 February was too cold and December too warm.

Now as to the reason why the winter should be colder in North-east Siberia than on the North American Archipelago farther to the north, it is to be found in the extent of the continent, the distance from any sea open in winter, and the prevailing calms. How important is the last reason is best seen by the comparison of the December and January temperatures of the last British expedition. The more northerly Floeberg Beach is warmer, because more exposed to winds. Now in Eastern Siberia calms prevail to a large extent in winter, except near the coast.

There is a phenomenon to be considered, which is noticed everywhere in winter in high latitudes: during calms with clear sky the valleys are colder than the surrounding hills and slopes, because the cold air sinks downwards and stagnates there. This is confined to the night where the mid-day sun rises high enough, but in high latitudes during some months the mid-day heat of the sun is too small and the day too short to interfere much with the equilibrium of the strata of air established during the night. Even in middle latitudes (45°-50°), when calms and clear weather prevail very largely in December, the valleys are regularly colder than the hills. So it was felt in December, 1879, in Central Europe. What is an exception here is the rule in North-East Siberia, because calms and clear sky are the rule in winter; the valleys are much colder than the hills. On this account the exceedingly low temperature of Werkhojansk in winter is probably not common to the whole surrounding country, and especially in the mountains rising to a short distance south we may expect a much higher temperature. The more we consider the conditions of the winter temperature of North-East Siberia, the more difficult it seems to draw isotherms. We know that plains and valleys there are colder than hills and mountain-slopes, but how much, and what conditions are most favourable to that so-called interversion of temperature? I consider it as highly probable that both at Yakutsk and at Werkhojansk the local topographical conditions are very favourable to winter cold. This being the case, it is quite natural that the latter place is colder in winter than the former, being situated 5° farther to the north, and yet far enough from the west to have a continental climate.

A. WOEIKOF

[1] According to Maak.
[2] Older series of Neverof (1829-54).

SPHYGMOGRAPHY

THE pulse has in all ages been held by physicians to be a valuable aid to the diagnosis of disease, but until the invention of the sphygmograph, or pulse-writer, the determination of the character of the pulse was left to the tutored tact of the doctor's finger, which varies much in delicacy of perception in different operators, and in the same practitioner at different times. At most the finger, even of the most experienced, can only determine regarding the pulse, that it is soft or hard, quick or slow, jerky or languid, regular or irregular; but the finger is incapable of analysing the beats, and detecting any departure from the normal standard of each of the component elements. The sphygmograph, which is quite a modern invention, causes the pulse to write its own autograph, enables us to see at a glance the peculiar characters of the pulse, and to ascertain how and when it differs from the healthy or normal pulse.

Hitherto, however, the sphygmograph has been very little used, for those that have been introduced are large and expensive instruments, requiring a great amount of skill and trouble to fix them on the arm and bring them into action; and for these reasons they are not available for general or private practice. Hence their use has almost been confined to hospital practice; but even here



they are not always available, for Dr. B. Bramwell, who is a strong advocate for employing the sphygmograph, relates that a patient of his was so terrified by the proposal to employ the instrument that he preferred leaving the hospital to allowing it to be fixed on his arm.

The objections to the general use of the sphygmograph do not apply to the instrument recently introduced into medical practice by Dr. Dudgeon, and from its portability called "the pocket sphygmograph." Though this instrument is so small as to deserve the name of "pocket," it is not inferior in sensitiveness to the most elaborate and complicated of the cumbrous instruments hitherto in use, indeed in some respects it is greatly superior in accuracy to any that have yet appeared. Its size is 2½ by 2 inches, its weight only four ounces. It magnifies the movements of the artery exactly fifty times. The spring that presses on the artery can be regulated to press with a weight from one to five ounces, and the pressure can be altered at will while the instrument is *in situ*. It requires no wrist-rest; all the other sphygmographs have to be used with wrist-rests of more or less complexity. It can be used with equal facility whether the patient is standing, sitting, or lying. With it an accurate and extremely distinct tracing of the pulse can be made almost as quickly as the pulse can be felt with the finger.

construction is so simple that if accidentally broken any watchmaker can repair it. The smoked paper on which the pulse is recorded runs through the instrument in ten seconds, so that the number of the beats per minute can be reckoned by multiplying the pulse-tracings on the paper by six. The patient's name, the date, the disease, the pressure of the spring, and some conventional sign to indicate his position when the tracing was made, may be written on the marked paper with any sharp-pointed instrument, such as a pin or a toothpick, and the whole permanently fixed by dipping the paper in some quickly-drying varnish, such as is used by photographers. In this way a series of pulse-tracings taken during the course of the disease may be preserved for future study and comparison.

Dr. Dudgeon's pocket sphygmograph is manufactured by Mr. John Ganter, 19, Crawford Street, W. The wood-cut represents its actual size.

NOTES

WE understand that the fifth volume of the Catalogue of Birds in the British Museum will shortly be published. According to the classification followed in this work the families to be described will be the Thrushes and Warblers, and the volume will be written by Mr. Henry Seebohm, whose co-operation Dr. Günther has been fortunate in obtaining. Mr. Seebohm has devoted a close study of several years to these families of birds, and may now be considered the best living authority on the subject.

M. FLAMMARION, the author of several works in popular astronomy, has been made a Knight of the Légion d'Honneur. Admiral Mouchez, director of the Paris Observatory, has consented to act as his *parrain*, and to hand over to him the star and ribbon. This liberal determination has created some sensation in the French astronomical world. The work of transformation of the Observatory will begin very shortly, all the legal difficulties having been solved. The area of the establishment is now 30,000 square metres. The magnetical instruments will be placed in the deep trenches separating the old ground from the newly annexed buildings.

WE regret to have to announce the death of M. Eugène Cortambert, author of a number of geographical works, honorary president of the Geographical Society of Paris, and head of the geographical department in the National Library.

ABOUT a year ago Admiral Mouchez asked for a credit of 4000 francs per year in order to publish a monthly astronomical review. M. Jules Ferry refused the grant, but a similar review is now being published at Brussels under the name *Ciel et Terre*. It appears twice a month, and is devoted to meteorology and astronomy.

ALTHOUGH our Government has declared the interest which it takes in the forthcoming International Exhibition of Electricity at Paris, still it sees no necessity for appointing a Special Commissioner to take measures with regard to the participation of British subjects in the Exhibition which is to open in Paris on August 1 next in the Champs Elysées Palace. The French Government is nevertheless disposed to welcome all British subjects wishing to participate in the Exhibition. M. Berger, the Commissaire-Général, has placed himself unreservedly at the disposal of intending exhibitors to afford every information and assistance. He would be thankful if they would fill up and return to his address the printed form of demand of admission which accompanies the copy of the general regulations. English exhibitors will be placed in every respect on the same footing as French exhibitors. M. Berger will form a special section for the group of English exhibitors, and requests that all demands be forwarded within the briefest delay possible. The Exhibition rooms and dependencies will be considered as real Custom-house stores, so that all the articles sent there shall be exempt from the duties to which they would otherwise have been liable. The French railway companies have consented to an abatement of 50 per cent. on the ordinary rates of transport, whether by fast or by slow trains, for all packages or boxes forwarded to the Exhibition Hall, and bearing the official labels. The Postmaster-General has been authorised by the British Government to exhibit in the name of the latter.

A COMMITTEE has been formed at Dijon for erecting a statue to Carnot, the celebrated French geometer and politician, who was born in Nolay, a small country town of Burgundy, in 1753. The youngest son of Carnot is now living, one of the members of Senate, and his grandson is M. Sadi Carnot, the present Minister of Public Works. The other son of Carnot died fifty years ago, after having written a small essay, "Sur la Puissance motive du feu." M. Carnot's brother has just published a new edition of this work, with a number of essays, mostly unpublished, by the same author, and a history of his life.

AT the conclusion of the proceedings of the Quekett Microscopical Club on February 25 occasion was taken to present to Mr. J. E. Ingpen a memorial of the esteem in which he is held and the appreciation of his services as honorary secretary for the last eight years. After an able address by Dr. Matthews, setting forth the reasons which had led to this movement on the part of the members, and short speeches by Dr. Cobbold, Mr. Crisp, and Mr. Michael, Mr. T. C. White handed to Mr. Ingpen a beautifully illuminated and framed memorial, together with a valuable microscope by Zeiss and a handsome silver tea-service, which were accepted and acknowledged amidst hearty demonstrations of good feeling on the part of the meeting. The attendance of members was unusually large, and in the course of the evening telegrams were received from Dr. M. C. Cooke and Mr. Henry Lee, expressing their regret at unavoidable absence.

AT the ordinary meeting of the Meteorological Society, to be held at 25 Great George Street, Westminster, on Wednesday, the 16th inst., at 7 p.m., there will be an exhibition of instruments, consisting of various kinds of hygrometers and of such new instruments as have been brought out since January 1, 1880. During the evening the President will give a historical sketch of the different classes of hygrometers, and will also describe such forms as are exhibited.

THE town of Casamicciola, in the Island of Ischia, has been almost entirely destroyed by an earthquake. More than 200 houses have been thrown down, and many others are so much damaged as to be uninhabitable. The number of persons thus far ascertained to have been killed is 104, and very many more have been injured. The total number of victims is estimated at 300. This dreadful catastrophe was the result of two shocks—the first at half-past one in the afternoon of the 4th inst., lasting seven seconds; the second after an interval of an hour and a half. The whole upper part of the town has been destroyed. The handsome Albergo della Grande Sentinella is a mass of ruins. Clefts and fissures opened in the streets 50 centimetres in width. It was at first supposed that this disaster was connected with the partial eruption of Vesuvius on the 3rd inst., but Prof. Palmieri has stated that the seismographic instruments having given no indications, he is inclined to think the catastrophe is due to some local phenomenon, possibly to a sudden sinking of the ground through subterranean corrosion caused by the continual working of the mineral waters. Shortly before the first shock of earthquake the mineral springs were observed to be in a state of ebullition. Another shock was felt at midnight.

SHOCKS of earthquake occurred at St. Ivan-Zelina (Hungary) on February 26 at 3h. 54m., in the night of February 26-27 at

12h. 30m., and on February 27 at 5h. 28m. a.m. At Agram a rather severe shock was felt on February 25 at 3h. 45m., duration two seconds, direction west-south-west; and another at noon of March 4. Earthquakes are also reported from Kirchberg (Austria), on February 28, at 2h. 20m. a.m., duration two seconds, and from different parts of Switzerland on March 3, *e.g.* Zürich and its environs, at 3h. 35m. a.m.; Aussersiehl, at 3h. 42m., direction west to east, duration two seconds; Riesbach, Selnau, Knonau, Aaran, Zofingen, Hunzenschwyl, Rapperschwyl, Glarus, Zug, Berne. The earthquake shock felt at Berne on Thursday morning last shortly after three o'clock was a very smart one. The area of disturbance was wide, extending as far as the Lakes of Geneva and Bienne.

MR. H. J. JOHNSON-LAVIS writes to us from Naples, under date March 2:—Vesuvius has to-day been covered with snow, and this evening, during a short interval between the mantling of clouds, a splendid stream of lava is pouring down the northern side and has reached the Atrio del Cavallo. The stream is very liquid and very abundant, and from this it may be concluded that its course will be progressive.

M. JULES FERRY has established a number of colleges for females in several parts of France; some of them have been already opened.

THE authorities of the British Museum will very soon issue their scheme for publishing the great catalogue of printed books. The projected issue, at the rate of five volumes a year, is not expected to be completed in less than forty years. The work, however, can of course proceed no faster than the Government grant of 1600*l.* a year for this special purpose will permit. Altogether the catalogue is likely to comprise about 3,000,000 titles, which to put in type will cost from 4*d.* to 6*d.* each. It has already been announced that the publication will commence with volumes specially devoted to certain subjects, or rather sub-headings, which have now become too voluminous for convenient handling in their present form. Meanwhile the Trustees have adopted the plan of printing and publishing the titles of all additions to the library. It may be interesting to know that in this case all titles are stereotyped on separate "plaques," and are therefore susceptible of any amount of re-arrangement.

AN important experiment in electric lighting is about to be made in the City. Hitherto the electric light has been used, as on the Thames Embankment and Waterloo Bridge, in conjunction with gas; but in the City the thoroughfares selected are to be lighted by electricity alone, which will be continued all night. The first district begins with Blackfriars Bridge, and extends along Bridge Street, Ludgate Hill, the north side of St. Paul's Churchyard, and down Cheapside as far as King Street. The distance is 1648 yards, and is to be lighted by the Brush system. At King Street the Siemens system will begin, and will extend along the rest of Cheapside, the Poultry, Mansion House Street, King William Street, and Adelaide Place, and across London Bridge. The same system will be extended down King Street, Queen Street, and Mansion House Street. The whole length of street covered by the Siemens light will be 1521 yards. Another district to the south of these will be lighted by the Jablochkoff lamps, like the Embankment. It will include Southwark Bridge, Queen Victoria Street, Queen Street Place, and part of Queen Street, a distance of 1703 yards. The experiment is to be continued for a year, at an outlay of about 8000*l.*

PROF. BLACKIE being unable to lecture through illness, Mr. Shelford Bidwell, M.A., LL.B., will give a discourse on Selenium and its Applications to the Photophone and Telephotography, at the Royal Institution, on Friday evening next March 11), at 9 p.m.

THE Calendar of the Mason Science College, Birmingham, is a volume of respectable size, but then it contains a full report of proceedings and addresses at the opening meeting. We are glad to see that a large number of new chairs are about to be added, including Greek, Latin, and modern languages; so that the College will shortly be as well equipped as that at Manchester. As the curriculum is being extended to include only literature, science, and art, might it not be well to drop the "science" from its designation? it looks so one-sided.

THE *Proceedings* of the last Congress of Russian Naturalists, which was held at St. Petersburg, have just appeared as a separate bulky volume.

A PAPER has been published by Gustav Hauser of Erlangen on the organs of smell in insects, in which he describes several experiments. Numerous species of insects, on approaching vessels containing turpentine or acetic acid, showed—by raising and moving their antennæ—a distinct perception of the smell. After the ends of the antennæ had been cut off, the same insects placed close to the vessels appeared quite insensible to it. A number of flies, which had been attracted by a piece of putrid meat, showed no inclination to approach it after the third segment of the antennæ had been cut off.

WE have received a pleasant report of the Queenwood College Mutual Improvement Society for the year ending Christmas 1880. The Society seems to have a comprehensive programme.

UNDER the title of the *Northern Microscopist*, and under the editorship of George E. Davis, a monthly periodical has been started, beginning with January of this year, the chief aim of which is to keep a record of the proceedings of the chief microscopical societies in the North of England, and thereby to furnish each individual member of these societies with as much permanent information as such members would obtain if the society to which they belonged published its own Transactions. There ought to be abundant support for a little journal like this, and numerous subscribers ought to be obtained from large centres like Liverpool, Leeds, Chester, Bolton, Manchester, Nottingham, Newcastle-on-Tyne, and the like. If the various Northern societies were to do nothing more than prepare local lists of all the varied species of animal and vegetable life, which come under the well-known denomination of "microscopical forms," and if this journal were to be the medium of publishing these, it would become a journal of importance, one that would be constantly referred to; and it would in the meantime be doing a good work in advancing the study of the biological sciences. We wish it every success, and trust that it will steadily pursue the path that it has marked out for itself.

A STENOGRAPHIC piano has been experimented on by the daughter of the inventor, in the French Chamber of Deputies, the Senate, and to the Municipal Council of Paris, with great success. The system consists of a combination of signs through which every sound is represented. The reproduction is as rapid as speaking, and the same operator can continue the work for hours. The signs used in this system being printed by machinery, the reading is immediate, and can be made by other people than the operator. The State stenographers propose to be trained in the use of the instrument. It is an affair of a few months' practice.

A SCIENTIFIC society has been formed at Scarborough, called "Scarborough Scientific Society and Field Naturalists' Club." President-elect, Mr. J. Woodall, M.A.; Secretary, Mr. G. Massee.

THE excavations in the 9th region of Pompeii are being prosecuted with alacrity, and yield unexpected results. Besides a second mosaic fountain and valuable frescoes recently found,

there were excavated the other day some vases of Egyptian manufacture, which will greatly interest archæologists. They are made of a particular kind of paste, composed of white clay and glass, and are extremely brittle. All round they have high relief representations of the animals worshipped by the ancient Egyptians.

A PHONOGRAPH of a new construction will be tried in the New Polyglot Institute of Paris, for the purpose of teaching pupils the art of pronouncing correctly the difficult words of foreign languages.

A SCHOOL for clockmakers has been organised in Paris, and was inaugurated yesterday by a meeting at the Conservatoire des Arts et Métiers.

THE new part of the *Transactions* of the Asiatic Society of Japan contains a paper by Dr. Edkins on the influence of Chinese dialects on the Japanese pronunciation of the Chinese part of the Japanese language.

WE have received part 3 of the *Transactions* of the Epping Forest Club, containing the address of the president, Mr. Meldola, proceedings, and list of members.

WE have to acknowledge the receipt of a postal order for 2*s*. 6*d*. from "Bullphumpus" for the John Duncan Fund.

THE additions to the Zoological Society's Gardens during the past week include an Indian Leopard (*Felis pardus*) from India, presented by the Duke of Buckingham and Chandos; an Entellus Monkey (*Semnopithecus entellus*) from India, a Greater Sulphur-crested Cockatoo (*Cacatua galerita*) from Australia, a Blue-fronted Amazon (*Chrysotis festiva*) from Brazil, deposited; four Indian Rat Snakes (*Ptyas mucosa*) from India, a Matamata Terrapin (*Chelys matamata*) from Upper Amazons, purchased; two Calandra Larks (*Melanocorypha calandra*), European, a Chinese Quail (*Coturnix chinensis*) from China, two Fire-tailed Finches (*Erythrura prasina*) from Java, received from Paris.

OUR ASTRONOMICAL COLUMN

THE SOLAR PARALLAX.—M. Faye has just communicated to the Academy of Sciences a paper on the actual state of our knowledge of the sun's parallax, of which we subjoin some particulars, without professing to regard his mean result as necessarily so definitive as he appears to view it himself.

M. Faye considers that there is no other scientific constant, the determination of which depends on an equal number of results completely independent of one another, and obtained by methods so totally different, and subdivides the various values assigned for the sun's mean parallax as follows:—

Geometrical methods, 8″·82	8″·85 by Mars (Cassini's method)	Newcomb.
	8·79 by Venus, 1769 (Halley's method)	Powalky.
	8·81 by Venus, 1874 ,, ,,	Tupman.
	8·87 by Flora (Galle's method)	Galle.
	8·79 by Juno ,, ,,	Lindsay.
Mechanical methods, 8″·83	8·81 by the lunar inequality (Laplace's method)	—
	8·85 by the monthly equation of the earth	Leverrier.
	8·83 by the perturbations of Venus and Mars	Leverrier.
Physical methods, 8″·81	8·799 Velocity of light (Fizeau's method)	Cornu.
	8·813 Velocity of light (Foucault's method)	Michelson.

With regard to the first value by "mechanical methods," M. Faye mentions that he has obtained it by adopting for the coefficient of the inequality 125″·2, the mean between the results of Sir George Airy from the Greenwich observations, and that of Prof. Newcomb, from the observations made at Washington, taking for the moon's mean parallax, 57′ 2″·7, and for her mass $\frac{1}{80{\cdot}8}$. Leverrier found the value 8″·95 from the said equation, which was reduced after correction by Mr. Stone for two small errors to 8″·85. The value from the perturbations of Venus and Mars assigned by Leverrier was 8″·86, but one of the numbers requiring a small correction, it is reduced to 8″·83. Michelson, after bringing to bear upon Foucault's method improvements which M. Faye says completely surmounted all difficulties, found for the velocity of light 299940 km., while Helmert altered Cornu's result to 299990 km. With Struve's constant of aberration the corresponding values for the solar parallax are 8″·799 and 8″·813, as above.

The general mean in which it may be considered that the errors of the individual results, obtained by so many methods, are to a great extent compensated is 8″·82, and to this value M. Faye, for reasons given, attributes a probable error of ± 0″·016. The mean value by the physical methods is 8″·806, and by astronomical methods 8″·825. He then considers which of these values is the more reliable, and states that he does not hesitate in giving the preference to the physical result, and arrives at the conclusions:—

1. That the method of the physicists is superior to all others, and ought to be substituted.

2. That the value of solar parallax, 8″·813 (by physical methods), is now determined to about $\frac{1}{10}$ of a second.

3. That the seven astronomical methods of procedure converge more and more towards that value, and tend to confirm it without equalling it in precision.

M. Faye adds that he has no idea of attempting to diminish the importance of the observation of the approaching transit of Venus: but as Leverrier pointed out, "il faut que les efforts des astronomes aient pour but d'obtenir une précision toute nouvelle dans leur prochaines expéditions." Without neglecting the contacts, he considers it will be desirable to employ to a greater extent than was done in 1874 "les procédés si puissants de la photographie," to which, be it observed, M. Faye from his own experiences drew attention a quarter of a century back. He thinks it will be very surprising if that admirable method of procedure, which has already succeeded so well in measuring delicate stellar groups, should fail for the transit of Venus, or under circumstances more favourable for its application. The value 8″·813 for the sun's parallax, which appears to him definitive, is in accordance with that adopted by Laplace in the *Mécanique céleste*, 27·2 centesimal seconds or 8″·812.

SWIFT'S COMET, 1880 *e*.—Mr. Winslow Upton of the Naval Observatory at Washington, sends us elements of this comet, which, as he remarks, afford a further confirmation of the 5½-years' period already assumed. He employed two observations made with the meridian circle of the Washington Observatory on October 25 and November 23, and one with the 26-inch equatorial on December 22. The elements are as follow:—

Epoch 1880, October 25·5 M.T. at Washington.

Mean anomaly	357	48	49″·3		
Perihelion from node	106	18	13·8	M. Eq. 1880·0	
Ascending node	296	41	55·4		
Inclination	5	31	3·5		
Angle of eccentricity	42	31	39·7		
Log. semi-axis major	0·518438				

The corresponding period is 2189 days, or a little less than six years. The middle place is represented within the small errors of − 1″·2 in longitude and − 0″·6 in latitude.

PHYSICAL NOTES

MR. T. C. MENDENHALL of Japan has measured with a so-called "invariable pendulum" the acceleration of gravity at the top of the extinct volcano Fujiyama, which plays so prominent a part in the mythology and in the art of Japan. The value found for the summit of the mountain was g = 9·7886, whereas at Tôkio the value was found to be 9·7984. The average barometric pressure at the summit was 19·5 inches, the mountain itself being an almost perfectly symmetrical cone of vertical angle 138°, and of a height of 2·35 miles. It rises alone out of a plain of considerable extent, and appears to be composed of a uniform rock of porous nature. Tradition states that the mountain was thrown up in a single night in the year B.C. 286. The density of the rock in the lump was 1·75, but when reduced to powder the density was 2·5; competent geologists conclude the mean density of the mountain mass to be 2·12. Assuming the mountain to be a cone of semi-vertical angle of 69°, and density 2·12, Mr. Mendenhall calculated its attraction upon a particle

placed at the vertex, and comparing it with his result, deduced for the mean density of the earth the value $D = 5{\cdot}77$. If however the accepted density of the earth as determined by Bailly at 5·67 be adopted, it follows that the mean density of Fujiyama is only 2·08.

A CAPITAL summary of the recent thermochemical investigations of Julius Thomsen appears in the current number of the *Am. Journ. Sci.* from the pen of Prof. Josiah P. Cooke (of Cambridge, Mass.). The peculiar significance of these researches in their bearing upon the problems of molecular structure in general and upon the supposed ring-structure of the benzene molecule in particular, is pointed out in a clear and emphatic manner.

M. ROSENSTIEHL has freshly determined the tints corresponding to the three primary colour-sensations, on the principle of rotating disks originally devised by Clerk-Maxwell. Constructing a disk with seventy-two sectors of gradating tints of as nearly equal saturation as could be judged of by the eye, he found that a sensation of red more powerful than any single red tint could be compounded from blue, violet, red, orange, and orange-yellow, with a maximum intensity in the orange. Similarly a sensation of green more powerful than the brightest green tint, could be compounded out of a set of tints having a greenish-yellow for their maximum point, and the sensation of blue culminated in a tint named "third blue" by M. Rosenstiehl. Hence M. Rosenstiehl proposes to accept as the primary-sensation tints of the Young-Helmholtz theory the orange, the yellow green, and the ("third") blue tints, in which the three sensations of red, green, and blue find their respective maxima; further arguments on this point are promised shortly by M. Rosenstiehl.

ACCORDING to Wiedemann Swedish filter-paper, pyroxylised by steeping in mixed strong nitric and sulphuric acids, forms an excellent source for electricity by friction. Prof. Guthrie's films of collodion and gutta-percha, in five or six alternate layers, realise the same end, namely that of utilising for the generation of electricity the most powerfully *negative* electric known pyroxylin.

DURING a hailstorm in Geneva on January 19 Prof. Colladon observed the hailstones as they fell to repel each other mutually and to bound about after lying quiet for a moment or two on the ground exactly after the fashion of the pith balls in Newton's well-known experiment of the *electric hail*. The observation would appear to have a bearing on Volta's somewhat neglected theory of the formation of hail.

COMMANDER O. J. SHERMAN has taken some observations of deep-sea temperatures during the summer of 1880 on the Arctic steamer *Gulnare*, when becalmed at about lat. 61° N., long. 56° W., at a point where a branch of the warm Gulf Stream current is represented on the maps as being overlapped by an Arctic current whose direction is to the eastward coast of Greenland. The temperatures at the surface being in two observations respectively 41°·9 (F.) and 45°·0, those at the depth of sixty fathoms were found to be 39°·0 and 40°·0 respectively. At 150 fathoms a temperature of 38°·2 was observed, but at lower depths the temperature was again higher, reaching 40°·8 at 300 fathoms.

M. PAUL SÉGUY, whose experience as a constructor of vacuum-tubes is very great, gives the following results of observation upon the effect of cold upon the discharge through exhausted tubes. A tube cooled (naturally by being placed in a cold room) exhibits increased resistance, sometimes double its usual resistance, and may even require to be warmed at the fire or over a spirit-lamp to bring it to its usual working condition. But then the tube does not at once recover itself, but only gradually as the passage of the spark liberates heat and warms the glass and the electrodes. This experiment is best shown with a long thin tube and with a feeble induction-coil. With Crookes's high-vacua tubes the effects of heat are more pronounced, and can be readily observed by arranging a discharger in a branch circuit, the spark leaping between the poles of the discharger when the air-resistance is less than that of the tube. A cooled Crookes's tube does not transmit a spark equivalent to a 3-centimetre spark in air; but when warmed, the "radiant" effects appear to give place in turn to ordinary stratified discharges as the temperature rises. The inverse order of phenomena should take place on cooling, but does not if care has not been taken in the construction of the tube to expel residual occluded gases from the aluminium electrodes by heating them during the exhaustion. The effects of extreme artificial cold upon vacuum-tubes was not tried by M. Séguy. In conclusion M. Séguy asserts the existence of a curious phenomenon, namely, that in a tube used frequently and for a long time, the vacuum may grow more perfect, so as at last to be almost absolute. M. Séguy attributes this effect to the gradual occlusion by the electrodes of the residual gases.

IT has been proved by Herren Stroubal and Barus (*Wied. Ann.*, No. 13, 1880), from experiments in which steel wire was treated so as to show all degrees of hardness between the glass-hard and annealed states, that the thermo-electric and galvanic properties of steel vary with the degree of hardness in a very sensitive manner. Their researches throw some useful light on the nature of the annealing process and on the magnetic behaviour of steel in relation to its hardness and other properties.

HERR HOLTZ has been able (*Wied. Ann.*, i. 1881) to measure the modulus of elasticity of rods of carbon used for the electric light (Carré's, of Paris) by the acoustical method: the rod being held in the middle with two fingers, and stroked lengthwise with two other fingers on which colophonium has been rubbed. The modulus increases with the density, which is, as a rule, greater in the thinner rods. The tone of thin rods alters a good deal, on repeated rubbing, through heat being generated. On an average the modulus is equal to that of lead. As to the improved increase of electric conductivity of carbon rods with rise of temperature, Siemens has tried to account for it by supposing allotropic modification (as is probably the case with selenium). Herr Holtz, however, shows that pyrolusite, a metallic oxide, behaves similarly, but such an explanation would not here apply. Nor does pyrolusite conduct as an electrolyte; there is no polarisation. For carbon Herr Holtz adheres to his hypothesis (of closer pressure of molecules caused by heat, improving the conduction), in default of a better.

A CENTIGRADE photometer devised by S. Coglievina is described in the *Rivista Sci. Ind.* for January 31. He seeks to remedy the imperfections of ordinary methods by substituting for a single source of light, defined by the substance of the candle, bustible or its hourly consumption, a flame of variable size, which can be reduced to a particular degree of illuminating force. He means to apply the same principle to the electric and other light sources.

AN interesting phenomenon of polarisation of light was observed by Herr Sörrensen in the recent cold weather (*Nature*, No. 9). Some of the ice on a window-pane had melted, the water forming a small pool at the bottom. In this pool various bright and beautiful colours appeared; on looking closer they were seen to be only in the grotesque images of frost flowers as the lower part of the window, reflected in the water. The reflecting water surface was here the analyser, while the thin ice crystals, varying according to position and thickness in the ice flowers, played the part of polychromatic gypsum and mica plates. To find the polariser Herr Sörrensen took a Nicol prism, and observed that the daylight itself was strongly polarised; and this he accounts for by the presence of a light mist of ice particles reflecting the sunlight. The temperature outside was about − 12°.

WITH reference to the physical conditions of heavenly bodies Herr Lohse (*Wied. Ann.* 1) has experimentally studied the phenomena of glow on various metallic electrodes (magnesium, zinc, iron, cadmium, copper, &c.) in a hydrogen atmosphere of varying pressure. Quantitative data as to the relation of vapour formation to the density of the gas are furnished; and it is proved, *inter alia*, that with progressive rarefaction of hydrogen the luminous power of metallic vapours in the more refrangible parts of the spectrum increases (a sign of exalted temperature).

M. PELLAT gives, in the *Journal de Physique* (February), results of an inquiry into the apparent difference of potential of two metals in contact. This difference he finds to depend essentially on the nature of their superficial layer, and to vary (sometimes considerably) with chemical or simply physical changes of the surface. When an inert gas surrounding the metals is rarefied, the apparent difference of potential increases, and it recovers its former value on the pressure being restored. Further, the said difference has the same value as the electromotive force of a battery element formed by alcohol and the same metals (not yet altered).

DR. PULUJ has made the following experiment to prove his suggestion that radiant matter consists of electrode particles

pulled off by the action of electricity. The cathode of a vacuum-tube was covered with chalk. It exhibits phosphorescence of orange-yellow colour, while in a short time the tube-wall becomes covered by a very delicate layer of chalk, without losing its clearness and transparency, and phosphoresces like chalk. Puluj believes that the yellow-coloured phosphorescence observed on metallic cathodes is caused by the phosphorescence of the oxides covering the metal.

GEOGRAPHICAL NOTES

AT its annual meeting the Russian Geographical Society elected as vice-president M. Semenoff, and Baron Osten-Secken as his "aid." The great Constantine medals were awarded to M. Moushketoff, for his geological researches in Central Asia, and to M. Yanson, for his remarkable work on "Comparative Statistics of Russia," the two first volumes of which have already appeared; the Lütke gold medal was awarded to Baron Kaulbars for his papers on the Lowlands of the Amu-daria; the two great gold medals instituted last year for ethnographical and statistical researches were awarded to Dr. Pyasetzky for his work, "Travels to China during the Years 1875-77," and to M. Roussoff for his statistical description of the Nyejin district. Small gold medals were awarded to M. Nordkvist, who took part in Nordenskjöld's expedition; to M. Potanin for his travels in Mongolia; to M. Tyaghin, for meteorological observations on Novaya Zemlya, and to M. Mainoff for anthropological explorations among the Mordovians. Silver medals were awarded to Mme. Treskina and to MM. Andrianoff, Unterberger, Polonsky, Orloff, Skassi, Karatin, Zinovieff, Krasovsky, and Mikhalenko.

WE learn from the last number of the *Isvestia* of the Russian Geographical Society that the Society sends this spring M. Polyakoff with an assistant for the exploration of Sakhalin Island. M. Polyakoff will start from Odessa, on board of a Russian ship, and proceed to Sakhalin, where he will stay during a year; thence he will go to the Mantchurian shore of the Pacific for further explorations.

THE explorer Begaert has arrived at Lisbon. He was sent by the King of the Belgians to make scientific researches on the route of Mr. Stanley at Vivi and other parts of Zaire.

WE are glad to learn that the U.S. Congress have decided to appropriate 175,000 dollars to send out an expedition in a whaling vessel in search of the missing steamer *Jeannette*, which was sent out in 1879 by Mr. Gordon-Bennett to carry on Arctic exploration by way of Behring Strait. The initiative in this matter is due to Chief-Justice Daly, President of the American Geographical Society.

IN addition to two papers descriptive of the visits of Mr. Leigh Smith to Franz-Josef Land and Mr. Delmar Morgan to Kuldja, the new number of the Geographical Society's *Proceedings* gives Mr. F. C. Selous' notes on some of his many journeys in South Central Africa, those dealt with here being to the north of the Zambesi between the 27th and 29th meridians, and in the neighbourhood of the River Chobe which empties into the great river above the Victoria Falls. We gave last week the text of the interesting note on Col. Prejevalsky, in addition to which we may refer to the record of some altitudes recently determined in Matabele Land, and a note of Dr. Otto Finsch's explorations in Polynesia. The maps this month are of the South Coast of Franz-Josef Land and the Central Zambesi region.

WE observe that M. Henri Duveyrier's interesting observations on the question of the sources of the Niger appear in the last (December) number of the French Geographical Society's *Bulletin*, but we regret to find that they are published without a map.

IN last week's issue of *Les Missions Catholiques* Mgr. Lavigerie, Archbishop of Algiers, commences an account of the missions of Equatorial Africa, with the direction of which he has been charged. There is also a letter from Père Antonin de Reschio in Brazil, in which will be found some notes on curious traditions among the Indians.

MARQUIS ANTINORI and the other members of the Italian expedition to Shoa are expected shortly at Zeila. It is also stated that Signor Libman, an Italian traveller, has gone to Assab in order to make an attempt to open commercial relations with the interior and to survey some of the little-known regions in the neighbourhood. Signor Giuletti, who accompanied the Italian official representative to Assab in January, is charged by the Italian Geographical Society to undertake a journey through the country of the Danakil and Adel tribes, and to study the best means for opening a trade-route between Assab and Abyssinia. His mission has considerable geographical importance, as the region to be traversed is unknown, and he will have an opportunity of solving the problem of the River Gualima, which probably he found to empty into some lake in the interior, as the Hanash does, if indeed it be not part of the latter river-system.

CAPT. NEVES FERREIRA, Governor of Benguela, and other Portuguese officers, have placed their services at the disposal of the Lisbon Geographical Society for a scientific expedition across Africa, to start from the West Coast.

THE *Sydney Morning Herald* of January 17 publishes a telegram from their Queensland correspondent as follows, dated January 14:—"Skuthorpe arrived two days ago from his exploring trip out west. He reports having travelled 200 miles inside the South Australian boundary, and in the Herbert River discovered relics of Leichhardt, consisting of his diary and Classen's diary; also a telescope with presentation engraving, compasses, and other things. These, he alleges, are in two packs which he has brought with him. The diary of Classen is to the effect that he left Leichhardt at the Saltwater Creek while he searched for water, and that on his returning he found the party dead, and then joined the blacks, with whom he lived until three years ago. Skuthorpe will not allow any one to inspect the alleged relics, and here it is considered doubtful whether they are genuine."

INTELLIGENCE has been received at the Foreign Office from Her Majesty's Consul at Mozambique, which confirms the report of the deaths of Capt. Phipson-Wybrants and Messrs. Carr and Mears, of the Wybrants' expedition. Mr. Mayes is stated to be at Umzeilas, and Mr. Owen to have left with the remainder for Inhambane, whither Her Majesty's ship *Ruby* will proceed forthwith.

ON THE VISCOSITY OF GASES AT HIGH EXHAUSTIONS[1]

II.

INFLUENCE of Aqueous Vapour on the Viscosity of Air.—In the foregoing experiments many discrepancies were traced to the presence of moisture in the gas. The influence of aqueous vapour does not appear to be great when present in moderate amount in gas of normal density, but at high exhaustions it introduces errors which interfere with the uniformity of the results. A series of experiments were accordingly undertaken to trace the special action of aqueous vapour when mixed with air.

Up to a pressure of about 350 millims. the presence of aqueous vapour has little or no influence on the viscosity of air. The two curves are in fact superimposed. At this point, however, divergence commences, and the curve rapidly bends over, the viscosity falling from 0·0903 to 0·0500 between 50 and 7 millims. pressure. Here it joins the hydrogen curve, and between 7 millims. and 1 millim. they appear to be identical.

These results are partly to be explained by the peculiar action of water vapour in the apparatus. At the normal pressure the amount of aqueous vapour present in the air, supposing it to be saturated, is only about thirteen parts in a million, and the identity of the log dec. with that of dry air shows that this small quantity of water has no appreciable action on the viscosity. When the pump is set to work the air is gradually removed, whilst the aqueous vapour is kept supplied from the reservoir of liquid. As the exhaustion approaches the tension of aqueous vapour, evaporation goes on at a greater rate, and the vapour displaces the air with increasing rapidity; until, after the pressure of 12·7 millims. is passed, the aqueous vapour acts as a gas, and, being constantly supplied from the reservoir of water (as long as it lasts), washes out all the air from the apparatus, the log dec. rapidly sinking to that of pure water gas.

This explanation requires that the viscosity of pure aqueous vapour should be the same as that of hydrogen, at all events between 7 millims. and 1 millim. pressure. The facts can, however, be explained in another way. During the action of the Sprengel pump sufficient electricity is sometimes generated to render the fall tubes luminous in the dark. It is conceivable

[1] Abstract of a paper read before the Royal Society, February 17, 1881. by William Crookes, F.R.S. Continued from p. 423.

that under such electrical influence the falling mercury may be able to decompose aqueous vapour at these high exhaustions, with formation of oxide of mercury and liberation of hydrogen. Of these two theories the latter appears to be the more probable.

The presence of water vapour shows itself likewise in the very slight amount of repulsion produced by radiation. Repulsion commences in air at a pressure of 12 millims., whilst at a higher exhaustion the maximum effect rises to over 40 divisions. Here, however, repulsion does not begin till the exhaustion is higher than the barometer gauge will indicate, whilst the maximum action after long-continued pumping is only 9 divisions.

Viscosity of Kerosoline Vapour.—The rapid diminution of viscosity in the last experiment after reaching the pressure of 400 millims., is probably due to the aqueous vapour in the air being near its liquefying point. It was thought advisable to test this hypothesis by employing a somewhat less easily condensible vapour, which could be introduced into the apparatus without any admixture of air. An experiment was accordingly tried with a very volatile hydrocarbon, commercially known as Kerosoline, boiling at a little above the ordinary temperature. The vapour of this body was introduced into the well-exhausted apparatus, when the gauge at once sank 82·5 millims. After the usual precautions to eliminate air a series of observations were taken.

The loss of viscosity is more rapid than with any other gas examined except aqueous vapour. Conversely a very great increase of viscosity occurs on increasing the pressure from 8 to 82·5 millims. The explanation of this is that the vapour of kerosoline is very near its liquefying point, and therefore very far from the state of a "perfect" gas.

The negative bend in the curve at about 10 millims. pressure, already noticed with other gases, is strongly marked with this hydrocarbon vapour.

Discussion of Results.—When discussing the viscosity results obtained with the different gases experimented with, the author gives the following approximate comparison of viscosities, such as is afforded by a comparison of the log decs. of each gas and that of air, comparing the ratio with that obtained by Graham, Kundt and Warburg, and Maxwell.

	Graham	Kundt & Warburg.	Maxwell.	Crookes.
Air	1·0000	1·0000	1·0000	1·0000
Oxygen	1·1099	—	—	1·1185
Nitrogen	0·971	—	—	0·9715
Carbonic oxide... ...	0·971	—	—	0·9715
Carbonic anhydride ..	0·807	0·806	0·859	0·9201
Hydrogen	0·4855	0·488	0·5156	0·4439

Graham's numbers are the theoretical results deduced from his experiments on transpiration of gases. They are, he says,[1] the numbers to which the transpiration times of the gases approximate, and in which they have their limit. Graham concludes that the "times of oxygen, nitrogen, carbonic oxide, and air are directly as their densities, or equal *weights* of these gases pass in equal times. Hydrogen passes in half the time of nitrogen, or twice as rapidly for equal volumes. The result for carbonic acid appears at first anomalous. It is that the transpiration time of this gas is inversely proportional to its density when compared with oxygen."

The proportion between air and oxygen, nitrogen, or carbonic oxide is not very different at any degree of exhaustion to that which it is at 760 millims. Carbonic anhydride, however, is different; the proportion between it and air holds good between 760 and 650 millims. Then it gets lower and lower as the pressure sinks, until 50 or 55 millims is reached, when the proportion between it and air again becomes constant.

Hydrogen, however, is entirely different to the other gases; its log dec. remains the same to a very high exhaustion, and, that of other gases sinking, it is evident that the proportion between this gas and any other is different for each pressure.

It must not be forgotten that the pressure of 760 millims. is not one of the constants of Nature, but is a purely arbitrary one, selected for our own convenience when working near the level of the sea. In the diagrams accompanying his R.S. paper the author has started from this pressure of 760 millims., and has given the log dec. curves which approximately represent the viscosities through a wide range of exhaustion. But the curves might also be continued, working downwards instead of upwards. From

[1] *Loc. cit.* pp. 178, 179.

the shape and direction in which they
reasonable to infer their further progre
may assume that an easily liquefiable gas
increase in viscosity than one which is diff
sure. For instance, hydrogen, the least c
shows scarcely any tendency to increase i
Oxygen and nitrogen, which are only a lit
dense than hydrogen, show a slight increas
anhydride, which liquefies at a pressure
15° C., increases so rapidly in log dec. t
would have a log dec. of about 1·3, repr
resistance to motion that it is difficult to
the nature of gas being capable of exerti
Kerosoline vapour is rendered liquid b
readily than carbonic anhydride. Its
increase in density for a very slight acc
Again, aqueous vapour is condensible to
the greatest readiness; and the almost hor
curve representing aqueous vapour mixed
hypothesis.

It follows, then, that Maxwell's law h
gases. The disturbing influence spoken of
of this paper as occasioning a variation fr
the tendency to liquefaction, which prevent
any gas as "perfect," and which hinders i
and Mariotte's law. The nearer a gas obe
closely does it conform to Maxwell's law.

Maxwell's law was discovered as the con
matical theory. It presupposes the existen
fect" state—a state practically unknown to
hydrogen gas very nearly approaches that
gas may be said to be bounded, as regards
the one side by the sub-gaseous or liquid c
other side by the ultra-gaseous condition.
former state when condensed by pressure or
to the latter state when highly rarefied. Is
ing either of these states there is a kind
change, with partial loss of gaseity. Wh
pressure or cold, are made to approach each
they begin to enter the sphere of each oth
therefore the amount of pressure or cold ne
certain density is less than the theoretical am
attraction exerted on each other by the mole
the gas approaches the point of liquefactio
attraction of one molecule to another, a
pressure required to produce any given d
portionally less than that theoretically requir
gas.

A noteworthy point in connection with th
is observed on the curves of viscosity. They
beyond the 0·02 M exhaustion, but the genera
indicates that, if they were produced beyon
observations, they would cut the line repres
vacuum. The curve representing the repuls
radiation evidently goes up to the zero poin
an absolute vacuum there would be no repulsi
viscosity cannot, however, be supposed to end
without a sudden change in direction. They
top line of zero pressure long before the l
reached. This means that in an absolute va
still be a measurable amount of viscosity. T
to the viscosity of the glass torsion fibre, for i
tained that glass is not perfectly elastic, but will
set if kept under constraint for a considerable
notice. In 1862 he purchased a piece of gla
spun glass from which the lace was made. Th
long straight threads, about 0·001 inch diamet
sionally been used for torsion fibres. The fib
lace was made were originally straight, but the
in which they have been kept for eighteen years
altered their direction, and on dissecting a porti
component fibres remain distorted and bent, e
resume their original shape.

Were glass perfectly elastic the log dec in a
would probably be equal to *zero*: there would th
nution in the arc of vibration, and the torsio
swinging would go on for ever.

The Ultra-Gaseous State of Matter.—A com
curves of viscosity of the gases, especially hydr

given in the foregoing pages, confirms the supposition that a gas, as the exhaustions become extreme, gradually loses its gaseous characteristics, and passes to what the author has ventured to call an ultra-gaseous state. Certainly it ceases to possess many of the properties usually held to be the essential attributes of gaseity.

For instance, Maxwell's law that the viscosity of a gas is independent of pressure holds good to a certain point, and then it rapidly breaks down. All gases appear to obey Maxwell's law between some limits of exhaustion, and diverge from it at others. Thus the nearly perfect gas hydrogen shows signs of increasing in viscosity as the pressure approaches 760 millims., and it is very improbable that its viscosity would remain the same if the pressure were to be considerably increased. Between 5 and 35 millims. the respective viscosities of carbonic anhydride, carbonic oxide, nitrogen, oxygen, and air scarcely vary at all, showing that between these limits they are practically as "perfect" gases as hydrogen is throughout the whole barometric range from 760 millims. to 1 millim., and here therefore they obey Maxwell's law as perfectly as hydrogen does. The change to the ultra-gaseous state commences to be assumed at about an exhaustion of half a millim. In hydrogen the change then proceeds slowly, but in the less perfect gases experimented with, the change to ultra-gas takes place with greater rapidity.

In gases, variation of pressure in different parts of a closed vessel equalises itself with great rapidity, but in the ultra-gaseous state differences of pressure may exist for twenty minutes or more in different parts of the apparatus.

In gases, electrically charged bodies do not permanently retain their charge, but gradually discharge themselves. In ultra-gas, however, a pair of electrified gold leaves have remained repelled at absolutely the same angle for thirteen months.[1]

Another property of gases is that of facilitating the cooling of bodies immersed in them, by communicating an increase of motion to the molecules of the gas which carry it to the walls of the containing vessel,—*i.e.* by *carriage* instead of *convection*. There is little difference in the rate of cooling with increased exhaustion, so long as we work with such ordinary good vacua as can be obtained by air-pumps. For if, on the one hand, there are fewer molecules impinging on the warm body (which is averse to the carriage of heat), yet, on the other hand, the mean length of path between collisions is increased so that the augmented motion is carried farther; the number of steps by which the temperature passes from the warmer to the cooler body is diminished, but the value of each step is correspondingly increased. Hence the difference of velocity before and after impact may make up for the diminution in the number of molecules impinging.

In gases, therefore, the rate of cooling is little affected by rarefaction, the law in this case being analogous to that governing the viscosity.

In a paper which the author has recently read before the Royal Society,[2] he shows that when the exhaustion is carried to so high a point that the mean free path is comparable with the diameter of the containing vessel, the rate at which heat is conveyed across is much diminished. The molecules are now in the ultra-gaseous state, and further exhaustion produces a notable fall in the rate of cooling, an increase of exhaustion from 20 M to 2 M retarding the carriage of heat more than all the previous exhaustion from 760 millims. to 20 M.

The author has shown elsewhere[3] that the property of gaseity is pre-eminently a property dependent on collisions. A given space full of air at the ordinary pressure contains millions of millions of molecules rapidly moving in all directions, each molecule momentarily encountering millions of other molecules in a second. In such a case the length of the mean free path of the molecules is exceedingly small compared with the dimensions of the containing vessel, and those properties are observed which constitute the ordinary gaseous state of matter—properties which depend upon constant collisions.

The gaseous state continues so long as the collisions are almost infinite in number, and of inconceivable irregularity. But in such high vacua as are now described the free path of the molecules is made so long that the hits in a given time may be disregarded in comparison to the misses, and the average molecule is allowed to obey its own motions or laws without interference; and when the mean free path is comparable to the dimensions of the containing vessel, the properties which constitute gaseity are reduced to a minimum, and the matter then becomes exalted to an ultra-gaseous state.

In the ultra-gaseous state properties of matter which exist even in the gaseous state are shown *directly*, whereas in the state of gas they are only shown *indirectly*, by viscosity and so forth.

The ordinary laws of gases are a simplification of the effects arising from the properties of matter in the ultra-gaseous state; such a simplification is only permissible when the mean length of path is small compared with the dimensions of the vessel. For the sake of simplicity we make abstraction of the individual molecules, and feign to our imagination *continuous* matter of which the fundamental properties—such as pressure varying as the density, and so forth—are ascertained by experiment. A gas is nothing more than an assemblage of molecules contemplated from a simplified point of view. When we deal with phenomena in which we are obliged to individually contemplate molecules, we must not speak of the assemblage as *gas*.

An objection has been raised touching the existence of ultra-gaseous matter in highly-exhausted electrical tubes, that the special phenomena of radiation and phosphorescence which the author has considered characteristic of this form of matter can be made to occur at much lower pressures than that which exhibits the maximum effects. For the sake of argument let us assume that the state of ultra-gas with its associated phenomena is at the maximum at a millionth of an atmosphere. Here the mean free path is about 4 inches long, sufficient to strike across the exhausted tube. But it has been shown by many experimentalists that at exhaustions so low that the contents of the tube are certainly not in the ultra-gaseous state, the phenomena of phosphorescence can be observed. This circumstance had not escaped the author's notice. In his first paper on the "Illumination of Lines of Molecular Pressure and the Trajectory of Molecules"[1] the author drew attention to the fact that a molecular ray producing green phosphorescence can be projected 102 millimetres from the negative pole when the pressure is as high as 0·324 millim. or 427 M. In this case the mean free path of the molecules is 0·23 millim.; and it is not surprising that with more powerful induction discharges, and with special appliances for exalting the faint action to be detected, the above-named phenomena can be produced at still higher pressures.

It must be remembered that we know nothing of the *absolute* length of the free path or the *absolute* velocity of a molecule; these may vary almost from zero to infinity. We must limit ourselves to the *mean* free path and the *mean* velocity, and all that these experiments show is that a few molecules can travel more than a hundred times the *mean* free path, and with perhaps a corresponding increase over the *mean* velocity, before they are stopped by collisions. With weak electrical power the special phosphorogenic action of these few molecules is too faint to be noticed; but by intensifying the discharge the action of the molecules can be so increased as to render their presence visible. It is also probable that the absolute velocity of the molecules is increased so as to make the mean velocity with which they leave the negative pole greater than that of ordinary gaseous molecules. This being the case, they will not easily be stopped or deflected by collisions, but will drive through obstacles and so travel to a greater distance.

If this view is correct, it does not follow that gas and ultra gas can co-exist in the same vessel. All that can be legitimately inferred is, that the two states insensibly merge one into the other, so that at an intermediate point we can by appropriate means exalt either the phenomena due to gas or to ultra gas. The same thing occurs between the states of solid and liquid and liquid and gas. Tresca's experiments on the flow of solids prove that lead and even iron, at the common temperature, possess properties which strictly appertain to liquids, whilst Andrews has shown that liquid and gas may be made to merge gradually one into the other, so that at an intermediate point the substance partakes of the properties of both states.

Note on the Reduction of Mr. Crookes's Experiments on the Decrement of the Arc of Vibration of a Mica Plate oscillating within a Bulb containing more or less Rarefied Gas[2]

THE determination of the motion of the gas within the bulb, which would theoretically lead to a determination of the coefficient of viscosity of the gas, forms a mathematical problem

[1] *Proceedings* of the R. S., No. 193, 1879, p. 347.
[2] *Proc.* R. S., No. 208, 1880, p. 239.
[3] *Proc.* R. S., No. 205, 1880, p 469.

[1] *Phil. Trans.* part 1, 1879, the Bakerian Lecture.
[2] Abstract of a paper read before the Royal Society, February 17, by Prof. G. G. Stokes, Sec.R.S.

of hopeless difficulty. Nevertheless we are able, by attending to the condition of similarity of the motion in different cases, to compare the viscosities of the different gases for as many groups of corresponding pressures as we please. Setting aside certain minute corrections which would have vanished altogether had the moment of inertia of the vibrating body been sufficient to make the time of vibration sensibly independent of the gas, as was approximately the case, the condition of similarity is that the densities shall be as the log decrements of the arc of vibration, and the conclusion from theory is that when that condition is satisfied, then the viscosities are in the same ratio. Pressures which satisfy the condition of similarity are said to "correspond."

It was found that on omitting the high exhaustions, the experiments led to the following law :—

The ratios of the viscosities of the different gases are the same for any two groups of corresponding pressures. In other words, if the ratios of the viscosities of a set of gases are found (they are given by the ratios of the log decrements) for one set of corresponding pressures, these pressures may be changed in any given ratio without disturbing the ratios of the viscosities.

This law follows of course at once from Maxwell's law, according to which the viscosity of a gas is independent of the pressure. It does not however by itself alone prove Maxwell's law, and might be satisfied even were Maxwell's law not true. The constancy however of the log decrement, when the circumstances are such that the molar inertia of the gas may presumably be neglected, proves that at any rate when the density is not too great that law is true; and the variability of the log decrement at the higher pressures in all but the very light gas hydrogen is in no way opposed to it, though Mr. Crookes's experiments do not enable us to test it directly, but merely establish a more general law, which embraces Maxwell's as a particular case.

The viscosities referred to air as unity which came out from Mr. Crookes's experiments were as follows :—

Oxygen	1·117
Nitrogen and carbonic oxide	0·970
Carbonic anhydride	0·823
Hydrogen	0·500

The viscosity of kerosoline vapour could not be accurately deduced from the experiments, as the substance is a mixture, and the vapour-density therefore unknown. Assuming the relative viscosity to be 0·0380, the vapour-density required to make the experiments fit came out 3·408 referred to air, or 49·16 referred to hydrogen.

When once the density is sufficiently small, the log decrement may be taken as a measure of the viscosity. Mr. Crookes's tables show how completely Maxwell's law breaks down at the high exhaustions, as Maxwell himself foresaw must be the case. Not only so, but if we take pressures at those high exhaustions which are in the same ratios as "corresponding" pressures, the log decrements in the different gases are by no means in the ratios of the densities.

It would appear as if the mechanical properties of a gas at ordinary pressures and up to extreme exhaustions (setting aside the minute deviations from Boyle's law, &c.) were completely defined by two constants, suppose the density at a given pressure and the coefficient of viscosity; but that specific differences come in at the high exhaustions at which the phenomena of "ultra-gas" begin to appear; and that to include these, an additional constant, or perhaps more than one, requires to be known.

ANIMAL REMAINS IN THE SCHIPKA CAVERN

ON December 6, 1880, Prof. Schaaffhausen gave a lecture to the Lower Rhine Society in Bonn, on the discoveries made by Prof. Maschke in the Schipka Cavern, near Stramberg, in Moravia. In this cavern were found remains of Bos, Ursus, Elephas, Rhinoceros, Leo, and Hyæna, besides roughly-hewn implements of quartzite, basalt, and flint, and some incisor teeth of Ursus, which were cut into on both sides at the beginning of the crown, perhaps because people did not yet know how to bore a hole into the root. Carbonised animal bones in numerous small fragments were met with. A solitary human relic was found in a protected place at the wall of a side passage of the cavern, and near a fireplace. It was the fragment of a lower jaw, amid ashes and inter-breccia of lime. The same layer contained mammoth remains and ston
only the front part with incisors, o
molars, of the right side remained.
still in the jaw undeveloped, but w
wall of the jaw was wanting. T
of the jaw, first of all, were remarka
corresponds to the first year of life,
as large as those of an adult. As is
pre-molar seemed nearest being cut ;
then the second pre-molar.

The height of the jaw in the lin
the alveolar border, 30 mm., to the
(In the jaw of a child seven years old
ments were 23 mm. and 30 mm. ; in
and 33 mm. ; in a boy of 12, 22 mm
eight adults measured in height, to
average, 31 mm.) The jaw fragmen
line of symphysis, is 14 mm. thick ;
thickness is 15 mm. (In an ordinar
the line of symphysis is about 11 mm
surface of the incisors is placed ho
the prognathous jaw bends so much
chin as a prominence. A vertical fr
falls 4 to 5 mm. in front of the lowe
hinder surface of the symphysis is pl
a high degree in the anthropoids, and
races, but has also before been obser
as in the jaw of La Naulette, to whic
Cavern has much similarity. The
adapted to the thick prognathous jaw
root measures from front to back 84
measurement here is 6 mm. Further
in front. The curvature correspon
The *spina mentalis interna* is abs
as in the anthropoids, a cavity, at
some unevenness can easily be fe
attachment of the *Musculi digastrici*
a correspondingly strong develop
muscles, the masticatory. All these
on the jaw of La Naulette, but more
that the jaw of the Schipka Cavern a
liarity, that its tooth-line was not ho
premolars to the incisors, and its boc
at the sides, because the cutting-su
sinks obliquely outwards. The size
markable, its enamel crown being 13
lower jaw of Uelde the canine tooth
3·5 mm. According to measureme
skulls with the teeth hardly, or not at
of the canine tooth was 11·5 mm, lon
than fifty skulls, was it found 14 mm
posed that this jaw, caught in dentitio
of giant growth, since in such individ
according to Langer, first begins abou
The assumption that some pathologic
development of the three teeth that
seems quite groundless. As little ca
prehistoric time the teeth developm
the change of teeth occurred at a late
lopment corresponds to a lower org
come into the world with teeth, and t
sooner than man.)

The size of the front part of the
be regarded as pithecoid ; and there
that other pithecoid characters are pr
grey-yellow bone with small dark h
with often in cavern bones. The en
like that of the Quaternary cave anim
fissures with dark infiltration ; while
and in some places yellow, spots.

SOME REMARKS ON
EDWARDSII, B

SINCE I learnt from Mr. Moseley
Peripatus (Ann. and Mag. of N
that one of them, referred by Grube
obtained from this country, in the
Tovar[1]), I tried to get specimens

[1] Not Colony *Tovar*, as the name is print

animal. But all my efforts being unsuccessful for a long time, I finally lost all hopes, and the pressure of other business, scientific and not scientific, caused me to lay the matter on the shelf, little thinking that I had my *desideratum* close at my elbows.

There is within our University building a large square yard, where stones, old bricks, and other such refuse had been accumulating in the course of years. About a month ago it was fortunately resolved to transform this very ugly place into a garden, and I engaged the workmen to bring me any kind of animal they might turn up under the heaps of rubbish. How great was my satisfaction to find in the very first gatherings half a dozen of *Peripatus* among some common beetles, centipedes, and earthworms! I offered immediately a prize for every other specimen of the former, and so good proved the locality that in a few days I was in possession of more than fifty of these unexpected *cives academici* of ours, the supply being apparently far from exhausted.[1]

As there are still some points in the natural history of *Peripatus* which are not well settled, I beg leave to offer the following remarks based on the careful examination of living or dissected specimens.

The number of females appears to be much larger than that of males; for among fifty-three specimens I found only five males, which are about half the size of the females. These are



FIG. 1. FIG. 2.

FIG. 1.—Horny claws of one of the foot-jaws in the young animal when born. FIG. 2.—The same, from an adult female. *a*, first claw; *b*, second claw; *c*, horny saw; *d*, pigment-line.

sometimes nearly 1 decimetre long, 5 to 6 millimetres broad, and somewhat tapering on both extremities. The colour is brownish black, with a diffused black line on the middle of the back; the ventral side is dark flesh-coloured. Full-grown animals have thirty-one pairs of ambulatory feet, the new-born animals have but twenty-nine; the length of the latter is about 25 millimetres, their breadth two, the tentacles measure 3 mm.; their colour is reddish, with a line of somewhat lozenge-shaped figures of a paler tint running down the middle of the back.

I twice observed the birth of a young *Peripatus*. The mother raised slightly the hind part of the body, moving it slowly from one side to the other. After some minutes the head of the embryo protruded from the sexual porus, and in half an hour half the body came out, twisting around all the while in every direction. The old animal remained rather quiet, moving occasionally its head, but not crawling about. As soon as the process was advanced thus far, the young *Peripatus* clung with its feet to the nearest surface in its reach; and the mother walking off, the hind part of the embryo came forth in a few seconds.

In one case a young *Peripatus* was born in a tumbler of water, in which I had placed the mother, in order to kill it in an extended condition, as recommended by Moseley in his well-known paper in the *Phil. Transactions*. I did not see the birth, but found the young animal already crawling on the back of the mother, and there floated in the water close by a very thin skin of the size of the young animal, exhibiting its whole form, even the tentacles. I suppose it must have been shed soon after birth, but have failed hitherto to see anything alike in the other cases of birth, which I watched very carefully.

I could not well make out the number of articulations in the tentacles; there are, however, more than thirty in those of the young animal, having each a ring of short spiny bristles at the base. The slime-glands of the young *Peripatus* are already well developed. It has twenty-nine pairs of feet; and as the adult animal has never more than thirty-one, there must be specimens with the intermediate number of thirty, which would settle Mr. Moseley's question (*Ann. and Mag. of Nat. Hist.*, l. c.) It is probable that *Peripatus* goes through several moultings, and that the new feet then make their appearance.

This may be further surmised from the development at the horny claws of the foot-jaws, which are simple, and not indented in the young animal, but of a much more complicate structure



FIG. 3.—Schematic sketch of ovary (*a*), beginning of oviducts (*b*), cæca (*c*), receptacula seminis (*d*), covered by tracheal tubes (*e*), zone of ovary without tracheal tubes (*f*).

in the old one. The annexed figures represent these claws in both conditions.

In the adult animal there is first a large pointed tooth, then follows a shorter one, which is obtuse; both are formed apparently of three to four superposed lamellæ, the outlines of which are distinctly visible by changing the focus of the microscope. The second maxillary claw has likewise two teeth of the same shape and structure, but bears behind them a kind of saw, composed of ten small teeth of the same amber-yellow colour as the inner parts of the larger teeth. This saw is followed by an oblique line of a yellowish pigment, perhaps the rudiment of another developing saw, or a reservoir of horny matter.

The structure of the sexual organs may deserve a few remarks. There can be no doubt that the sexes are separate. The male organs are very much like those described by Moseley in his paper; only the *vesiculæ seminales* are not nearly so spirally twisted as in his figure on plate lxxii. The testes contain spermatozoa of the same shape as those of *P. Capensis*. I noticed

[1] Those desirous of obtaining specimens from me in exchange for books or papers on zoological topics, will be good enough to write to me.

that the slime-glands were much less developed in the males than in the females.

The structure of the female organs in our Caracas species agrees pretty well with Prof. Hutton's drawings (*Ann. and Mag. of Nat. Hist.*, iv. ser., vol. 18, pl. xvii., fig. 8); but I am not prepared to accept his interpretation. The following sketch will give an idea of what I saw.

Moseley's Fig. 1 on pl. lxxiv. is very different from the shape of the ovary in our species; nor can I well understand the existence of ova on the *outside* of the ovary as they appear in his drawing. The ovary in *P. Edwardsii* is rather long, and abundantly covered by fine tracheal tubes, with the exception of a narrow zone close to the branching out of the oviducts. I could not satisfy myself as to its being divided by a septum, nor could I find any ova in it; most likely it is not now the right time. At a very short distance from the beginning of the oviducts there is a kind of obtuse *cæcum* on each of them, which is followed by a spherical body covered by tracheal tubes. These bodies are the organs described by Prof. Hutton as testes.

There is however in our species no trace of what he takes for *vasa deferentia*, the spherical body adhering directly to the oviduct. Its wall is of considerable resistance, and bursts only under great pressure, giving issue to an immense number of thin rod-like corpuscula, which soon after begin to move slowly in the surrounding water. They are of course spermatozoa which have lost their nuclei, and the spherical body can therefore be nothing else but a *receptaculum seminis*.

The oviducts of three specimens which I dissected contained very few embryos; in one there was only one in each oviduct, in the others there were two. They were fully developed, and occupied the part of the oviducts close to the vulva. It would appear from this that the time of reproduction is now almost over; further observations will show whether there is really such a periodicity in our species.

It is probable that the oviducts of *P. Edwardsii* never present the shape of strings of sausages, as seen by Mr. Moseley in *P. Capensis*, the embryos being so considerably larger.

Animals thrown alive into alcohol pour forth from their slime-glands first the viscid substance contained in these; then there comes out a slightly reddish matter, which dissolves in the alcohol, giving it the same colour.

With respect to all other points I can only confirm Mr. Moseley's statements. I keep alive a colony of *Peripatus* of both sexes in the hope to have once a chance to observe the copula.

I cannot conclude these remarks without confessing that I am not at all quite sure whether our *Peripatus* is really *P. Edwardsii*, as the figure of this species in Nicholson's "Manual of Zoology" (5th edit. p. 315), which is said to be after Grube, does not agree well with my living specimens. Grube's original paper I cannot consult here. It may be however that he made his drawing from a contracted alcoholic specimen. A. ERNST

The University, Carácas, January 16

ACOUSTICS IN CHINA

THE following letter to Prof. Tyndall has been sent to us for publication by the writer, Mr. Fryer. It will be seen that a really scientific modern correction of an old law has singularly turned up from China, and has been substantiated with the most primitive apparatus. Dr. W. H. Stone, to whom the letter has been submitted, has kindly appended a note.

TO PROF. TYNDALL, LL.D., F.R.S., &c.

DEAR SIR,—My friend Mr. Hsü has brought some interesting facts relating to acoustics before my notice. As he is the father of the native official who translated with me your work "On Sound," and as he refers particularly to that work, I venture to forward you a translation of his remarks, in the hope that you will satisfy his mind on a subject in which he takes such deep interest. He says:—

"In ancient Chinese works on music it is stated that strings or pipes produce an octave or twelve semitones higher or lower by halving or doubling their length.

"In a work written during the Ming dynasty by Chen-toai-yoh it is stated that this rule will only hold good with strings, but not with open pipes such as the flute or flageolet.

"Some years ago I tried to investigate the cause of this difference and its exact amount. A round open brass tube, say nine inches long, gave a certain note by pressing the end of it against the upper lip and blowing through an *embouchure* made there. Cutting off half the tube, the remaining four and inches would not sound the octave; but by cutting off inch more, thus leaving four inches in length, the oct sounded accurately. This experiment was tried on various lengths and diameters with a similar result, four-ninths of the length always sounded the octave mo exactly. Looking at a foreign keyed flute I noticed t principle carried out in the arrangements for producing I could not however see the reason why open pipes sh follow the same rule as strings and closed pipes.

"When I read the translation of Prof. Tyndall's 'On Sound,' I was surprised to find the old Chin strictly maintained. It says (p. 214): 'In both st open pipes the number of vibrations executed in a giv inversely proportional to the length of the pipe,' &c. A to this, as the octave of any note has to execute exactly d number of vibrations in a given time, an open pipe oc exactly halved to make it sound an octave higher. Th shown to be erroneous by my experiments.

"Fearing that I have misunderstood the English meaning, I beg that he may be written to on this su that my doubts may be thereby cleared up. What know is the exact proportion in length that exists be open pipe and a pipe of similar diameter sounding higher. Also the exact proportions in length for e open pipes sounding the twelve semitones which form one octave. If the length forming the octave in c does not agree with the length for strings or closed the lengths of all the pipes giving intermediate notes differ. How are these lengths to be calculated? C expressed by any mathematical curve or formula? not the same rule hold good for open pipes as fo stopped pipes? I have a theory of my own, but I sufficient confidence in myself to make it public u bestowed more thought and attention upon it. In th I shall be glad if any foreign scientists can enable m stand this interesting and important subject. The practice of music in China has gradually become vitia errors in the construction of musical instruments, therefore desirous of having a scientific basis up reformation may be effected."

There is no treatise on music or acoustics that I ca throws any light on these interesting questions, therefore deem it a great favour if you will direc work that will enable me to satisfy the eager inq native friend.

I send by book-post a pamphlet for your kind containing an account of the Department for the T Scientific Books at the Kinagnan Arsenal. You your "Notes on Light" are now published in Chin will be forwarded to you shortly. Your "Heat Motion" I hope to begin to translate at no very Your "Notes on Electricity" in Chinese will shortly.

I remain, dear Sir, yours faithfully,

Shanghai, June 1, 1880 Jo

November

P.S.—I have sent a copy of this letter to t NATURE, and shall feel greatly obliged if you will reply, if any, to him for publication.—J. F.

MR. FRYER is perfectly correct in his observatio find the explanation and formula needed at p. 16 book on Sound, under the heading "Correction o Law." "It has long been known," I there say, open pipe be stopped at one end its note is not exa below that given by it when open, but somewhat le being about a major seventh instead of an octave."

Then follows the mathematical statement, fr corrections needed by Mr. Fryer could easily be Bosanquet's excellent experimental investigation of briefly described. His results give the correctio end of the pipe as ·635 of radius of pipe, and mouth. Mr. Bosanquet remarks that in Bernouill hypothesis is made that the change from the the pipe to a condition in which no remains of to be perceived takes place *suddenly* at the point w system leaves the pipe. It is however evident th ence which takes place may be conceived of as e the pipe *a series* of reflected impulses, instead

from the open end of the pipe
y, and that these elementary im-
distances, may be altogether
impulse from a point at a little
ipe. It is not a little interesting
le-known fact should have come
n obtained by such simple experi-

W. H. STONE.

uary 8

IC SERIALS

emie, No. 13, 1880.—On currents
by H. Helmholtz.—On the course
. Witkowski.—On the changes of
bodies wrought by electricity, by
berg figures and electric valves,
ectromotive forces of some zinc-
—On the measurement of electric
.—Some experiments on induction
—On the discharge of electricity
cin.—On the production of har-
ns of a fundamental tone, by K.
w of dispersion, by O. Heaviside.—
sky.—On the law of heat-radia-
power of glass, by L. Graetz.—
asurement of its hardness, by V.
the height of the atmosphere
searches on the volume-constitu-
H. Schroder.—On variations of
dogical change, by K. Zöppritz.
fundamental experiment, by F.
alvanic element, by the same.—
t carried away by currents of an
A. Oberbeck.—Note on Herr
ctric conductivity of carbon and

dies on Newton's rings, by L.
n vapour-tension of homologous
s the elasticity and the electric
. Beetz.—Thermal theory of the
urweg.—On electric light pheno-
.—On the phenomena of glow at
ydrogen atmosphere of varying
on Riecke's paper on the electric
g.—Clausius' law and the motion
hich.—On the application of the
kinetic theory of gases, by H. A.
f expansion of molecules on the
tewez.—On the velocity of light
y W. Hallock.—Reply to Herr
nes arising through intermittent
C. Röntgen.—On phenomena of
a screen, by O. Tumlirz.

vol. iii, No. 2, January, contains:
ebt substances contained in the
rtant paper is appended a classifi-
classified list of the plants whose
Sydney Ringer, the influence of
the action and on the antagonisms
elastic properties of the arterial
). Ott, on crossed hyperæsthesia,

ographical Society, ser. ii, vol. i,
Dr. C. T. Hudson, on *Rotifer*
w, two new species of Rotifers
summary of current researches
y, meteorology, &c.—The minutes
ciety are given at the end of the

ciatti, February.—On the revolu-
ree unequal axes, by T. Craig.—
of the ellipse, and its application
. Leavitt.—A simple transmission-
n.—Methods for judging of the
ater, by R. Haines.—The basic
J. Reece.—Riehle Brothers' im-
s, 50,000 pounds capacity.

THE *American Naturalist*, February, 1881.—L. F. Ward, incomplete adaptation as illustrated by the history of sex in plants.—Sarah P. Monks, a partial biography of the green lizard.—G. K. Morris, a new leaf-cutting ant.—S. V. Clevenger, comparative neurology (continued).—Justin Spaulding, the bee's tongue, and glands connected with it.—Wm. E. Doyle, history of the buffalo.

Revue Internationale des Sciences biologiques, January 15, 1881.—Prof. Hanstein, protoplasm considered as the basis of animal and vegetable life.—D. Delsierre, an introduction to the earth's history.—Ch. Letourneau, the ethics of egoism (Schopenhauer's "Aphorisms on Moderation in Life").—J. L. de Lanessan, digestion in vegetables.

The Proceedings of the Linnean Society of New South Wales, vol. iv. part 4, Sydney, 1880.—John Brazier, synonymy of, and remarks upon, Port Jackson, New Caledonian, and other shells, with their distribution; list of landshells found on Thursday Island, with description of new species; Port Jackson and New South Wales brachiopods; mollusca recently dredged at Port Jackson Heads; on the locality of *Ornithoptera pandorana*.—E. P. Ramsay, on an undetermined species of Lalage; contribution to the zoology of New Guinea, part 6.—W. A. Haswell, supplementary note on Australian Leucosiidæ; on Australian *Brachyura Oxyrhyncha*, plates 25, 27.—C. Jenkins, on the geology of Yass Plains (3).—W. Macleay, on the Muglidæ of Australia.—C. S. Wilkinson, on the Abercrombie caves.

Journal of the Asiatic Society of Bengal, vol. xlix. part 2, No. 2, August 30, 1880, contains:—Alexander Fedler, on the past and present water supplies of Calcutta.—R. Lydekker, on the zoological affinities of the bharal or blue sheep of Tibet. "While forming a very closely connecting link between the sheep and the goat; the author thinks it cannot be referred to either of the genera Ovis or Capra, and that Hodgson's genus Pseudovis should be retained for its reception.—J. Wood-Mason, on a new butterfly (*Hebomoia Kheiherfii*) from South Andaman, near *H. sulphurea*, Wallace.

Journal de Physique, February.—On radiophony, by E. Mercadier.—Researches on the differences of potential of two metals in contact; results, by H. Pellat.—Dr. Cusco's lens with variable focus, by C. M. Gariel.—On the correction of cooling in calorimetry, by M. Berthelot.—Edelmann's universal support for physical experiments, by A. Terquem.

SOCIETIES AND ACADEMIES

LONDON

Zoological Society, March 1.—Prof. W. H. Flower, F.R.S., president, in the chair.—The Secretary exhibited the cast integument of a large spider (*Mygale histrioia?*) which had been shed in the Society's Gardens.—Mr. G. E. Dobson, C.M.Z.S., read a paper on the anatomy of the family *Erinaceidæ*, commencing with that of the curious and rare form *Gymnura Rafflesii*, with which the species of *Erinaceus* were compared. *Gymnura* was shown to be a peculiarly central form, the survivor probably of a once widely-spread group. Altogether the anatomy of thirteen species of Erinaceidæ was treated of in this paper.—A communication was read from Mr. F. Moore, F.Z.S., containing the descriptions of some new genera and species of Asiatic nocturnal lepidoptera. The characters of 150 new species were given, representing eighty-two genera, of which twenty-nine were new to science.—A communication was read from Mr. R. Collett, C.M.Z.S., containing an account of the breeding habits of the grey seal (*Halichœrus gryphus*), as observed on the Fro Islands, off Trondhjem's Fiord, in Norway.—Mr. R. Bowdler Sharpe, F.Z.S., read a note on the fantail flycatcher of Western Australia (*Rhipidura preissi*), of which he had lately had for the first time an opportunity of examining a specimen.

Geological Society, February 23.—Robert Etheridge, F.R.S., president, in the chair.—William Henry Goss was elected a Fellow of the Society.—The following communications were read:—A letter from Dr. John Kirk, communicated to the Society by the Right Hon. Earl Granville, dated H.M. Agency and Consulate General, Zanzibar, December 20, 1880. "It may be of interest to record the occurrence here of an earthquake shock felt in the island of Zanzibar at 6.58 a.m., mean time, on the morning of the 15th inst. Although the shock was very distinct no damage appears to have been done to any buildings in town. It is now twenty-four years since a similar shock has been here noticed; but on the mainland, espe-

cially in the vicinity of Ujiji, they are both more common and more severe than at the coast. Shortly after the cable was laid between Mozambique and Delagoa Bay, the communication was suddenly interrupted after one of these earthquake shocks, which seems to have caused the falling in of rocks by which the cable was crushed."—The Permian, Triassic, and Liassic rocks of the Carlisle Basin, by T. V. Holmes, F.G.S. The district discussed in the author's paper was worked over by him when engaged on the geological survey, and consists of those parts of Cumberland and Dumfriesshire which adjoin the Solway. Its southern boundary is, approximately, a line ranging from Maryport to Rose Castle on the River Caldew, and touching the Eden about two miles above Wetheral. On the east and north-east its limits are the immediate neighbourhoods of the junction of the rivers Eden and Irthing, Hethersgill on the Hether Burn, Brackenhill Tower on the Line, and the border boundary on the Rivers Esk and Sark; and in Dumfriesshire the small tract south of a line ranging from the junction of Scots Dyke with the Sark on the north-east, to Cummertrees on the south-west. The lowest bed in this area is the great Upper Permian or St. Bees Sandstone, which occupies a belt of country in the neighbourhood of the outer boundary. Directly above St. Bees Sandstone, in the west of the district, lies a formation consisting of shales with gypsum, which, though 700 feet thick in the neighbourhood of Abbey Town, is nowhere visible, but is known solely from borings, the country west of the Caldew, and of the Eden below the junction of the two streams, being thickly drift-covered and almost sectionless. In the east of the district the St. Bees Sandstone is overlain directly by a soft, red, false-bedded sandstone, called by the author Kirklinton Sandstone, from the locality in which the rock is best seen, as well as its relations to the under- and overlying beds. But while there is no evidence of any unconformity between the St. Bees Sandstone and the overlying Gypseous Shales in the west, there is evidence of a decided unconformity between the St. Bees and Kirklinton Sandstones in the east. In Carwinley Burn (for example), which runs into the Esk at Netherby, only from 200 to 300 feet of St. Bees Stone was seen below the outcrop of the Kirklinton, instead of the 1000 to 1500 feet which probably exist about Brampton on the one hand, and in Dumfriesshire on the other. Yet Carwinley Burn affords an almost continuous series of sections, from the (non-faulted) Permian-Carboniferous junction to some distance above the outcrop of the Kirklinton Sandstone. As, in addition, the shales underlying the St. Bees Sandstone are gypseous, both near Carlisle and at Barrowmouth, close to St. Bees Head, the author classed the (Upper) Gypseous Shales as Permian, and the Kirklinton Sandstone as Bunter. Resting unconformably on the Kirklinton Sandstone, in the district between Carlisle and Kirklinton, are the Marls seen on the Eden, between Stanwix and Beaumont, and on the line between Westlinton and Cliff Bridge, Kirklinton. Their unconformity is shown by the fact that on the line they rest on the lower, or red, beds, and between Stanwix and Beaumont on the upper, or white, beds of the Kirklinton Sandstone. The Marls have therefore been classed as Keuper. So far as the evidence goes they appear to be very thin, and to extend but a very small distance south of the Eden. Lastly, the Lias appeared to the author to be unconformable to all the beds below, and to rest partly on the Gypseous Shales, partly on the Kirklinton Sandstone, and partly on the Keuper Marls. Of the existence of Rhætic beds there was no evidence, all fossils hitherto found having been determined by Mr. Etheridge (the president) to be Lower-Lias forms. But the Lias-sections are so small and few in number, and the ground so persistently drift-covered, that only a boring could settle the question.—On *Astroconia Granti*, a new Lyssakine Hexactinellid from the Silurian formation of Canada, by Prof. W. J. Sollas, M.A., F.G.S. This paper contained a description of a new fossil Hexactinellid sponge from the Niagara chert beds of Hamilton, Ontario. It is the second oldest known example of the Lyssakina.

Anthropological Institute, February 8.—Major-General A. Pitt-Rivers, F.R.S., president, in the chair.—The election of the following new members was announced: A. G. Geoghegan, E. H. Man, Owen Roberts, and Bruno Müller.—Mr. W. L. Distant exhibited some Carib chisels from Barbadoes, which had been sent to him by Mr. W. J. Sollas, of Bristol. They were taken with about 100 more from a cave, and were found six or eight inches below the surface. The cave is about 350 feet above the sea level, and is situated at a distance of two miles from the coast.—Mr. A. L. Lewis read a paper on two stone circles in Shropshire. Between five and six miles west Minsterly is a circle of small stones known as the "Hoarstone." The largest stone is in the centre and is surrounded by the three stones and fragments arranged in a circle about 74 feet diameter. About a mile and a half in a south-westerly direction from the Hoarstone is another circle called in Gough's "Camden Britannia" "Madge's Pinfold." Here thirteen stones and the fragments stand and lie in an oval ring, the diameters of which are about 86 feet and 92 feet, the longest diameter running north-west and south-east.—Miss A. W. Buckland read a paper on surgery and superstition in neolithic times; the object which was to bring before the Institute the frequent practice trepanning in Neolithic times, as proved by the late Dr. Broca to call attention to the proofs he has given of the facts, and his explanation of the reason of the practice, and of the superstitions associated with it, as also its connection with the use of cranial amulets.

Physical Society, February 26.—Prof. Fuller in the chair. The former resolution regarding the moneys of the Society for investment was adopted.—Dr. O. J. Lodge exhibited a mechanical apparatus illustrating the fact that conductors of electricity are opaque to light, and showed by means of Wheatstone's photometer, which combines two circular motions into a harmonic one, how the plane of polarisation of a beam of light passing through a magnetic medium is rotated.—Mr. C. V. Boys exhibited his new integrating machine, which is the first one illustrative of the mathematical process of integration, and is therefore specially valuable for teaching purposes.—Mr. Shelford Bidwell read a paper on the telegraphic transmission of pictures of natural objects. The process is explained as follows:—The positive pole of a battery is connected through a set of resistance-coils to a piece of platinum wire, and the negative pole to a plate of zinc, upon which is placed a sheet of paper moistened with a solution of potassium iodide. The negative pole of a second battery is connected through a selenium cell with the same platinum wire, and the positive pole to the zinc plate. The point of the platinum wire is pressed on to the paper, and the selenium being exposed to a strong light, the variable resistance is so adjusted that the currents from the two batteries which pass through the paper in opposite directions exactly neutralise each other. The platinum point will now make no mark when drawn over the paper; but if the selenium is shaded, its resistance is immediately increased: the current from the first battery then predominates, and the path of the platinum point across the paper is marked by a brown line due to the liberation of iodine. The line is fainter the feebler the light is. This arrangement has been applied by Mr. Bidwell in his "telephotograph," exhibited to the meeting. The transmitter consists of a brass cylinder mounted on a screw spindle which carries the cylinder laterally $\frac{1}{100}$ inch at each revolution. A pin-hole in the middle of the cylinder allows light to fall upon a selenium cell placed behind it within the hollow cylinder. The cell is connected in circuit with a battery and the line. The receiver consists of a similar metal cylinder mounted so as to rotate synchronously with the first, and having a platinum point pressing upon a sheet of chemical paper wrapped round the cylinder. This receiver and transmitter are connected up as described above with two batteries and a set of resistance-coils. The image to be transmitted is focussed upon the cylinder of the transmitter and the resistance adjusted, and the receiving cylinder covered with sensitised paper. The two cylinders are caused to rotate synchronously, the pin-hole in the course of its spiral path covering successively every point of the focussed picture. The amount of light falling upon the selenium will be proportional to the illumination of that particular spot of the projected image which is for the time being occupied by the pin-hole, and the intensity of the line traced by the platinum point in the receiver will vary in the same proportion. These variations will produce a picture which, if the instrument were perfect, would be a counterpart of that projected upon the transmitter. Simple designs cut out of tin-foil and projected by a lantern have been successfully transmitted. With selenium and paper of greater sensitiveness more perfect results might undoubtedly be obtained.—Professors Ayrton and Perry showed an experiment illustrating their plan for sending light and shade images by electricity. A selenium cell was connected in circuit with a battery and a coil of wire surrounding a tube along which a beam of light passed. A shutter having a small magnet attached was suspended in the tube like a galvanometer mirror, so that when a current traversed

e coils the shutter was deflected so as to close or partially close e tube and shut off the beam of light. It will be understood that hen a ray of light fell on the cell and diminished its resistance, ie current in the coils would increase to a degree proportional to ie intensity of the ray, and thus the shutter would proportionally ut off the light in the receiver. If now a number of these lementary circuits were combined so as to provide a mosaic of ells to transmit the reflected image of an object, and a screen o receive the corresponding beams of light controlled by the hutters at the other end of the line, there would be a means of ending light and shade images by wire. A rapidly rotating rm carrying a row of cells upon it might answer for a stationary nosaic transmitter, and need fewer cells, while a Japanese mirror aving its curvature altered by electromagnets behind might be made to act as a receiver; the "magic" images of that mirror being due to inequalities of curvature. Prof. Ayrton agreed with Mr. Bidwell in his conclusion that selenium cells of high resistance were more sensitive to light than cells of low resistance. Dr. Coffin suggested that Mr. Bidwell should adopt other than the cylindrical form of receiver, and move an image of the object across the pin-hole. Prof. G. C. Foster advised bringing the light always on one and the same part of the selenium cell.

Quekett Microscopical Club, February 25.—T. C. White, president, in the chair.—Ten new Members were elected, and numerous donations received.—A communication was made by Mr. A. D. Michael, announcing the discovery by Mr. Beaulah of *Myobia musculi* upon a mole, this parasite having been previously regarded as one confined to mice. A discussion ensued as to the frequent errors in classification and nomenclature arising from insufficient observation.—The Rev. J. E. Fase exhibited and described a convenient form of grooving slide, which could be used either with high- or low-power objectives.

Institution of Civil Engineers, February 22.—Mr. Abernethy, F.R.S.E., president, in the chair.—The paper read was on the weight and limiting dimensions of girder bridges, by Mr. M. am Ende, Assoc. M. Inst. C.E.

Edinburgh

Royal Society, February 7.—Prof. Maclagan, vice-president, in the chair.—After reading the obituary notices of Lord Ormidale, Dr. Sharpey, Mr. Lassell, and other deceased Fellows, the chairman called on Prof. George Forbes to communicate his paper on a simple and accurate method of determining the longitude of a place by a single observer without the aid of any instrument for measuring time. The method consisted in taking advantage of the daily change in the moon's declination, which for four or five days during each lunation was sufficiently rapid to be measured with considerable accuracy by means of a sextant and artificial horizon. The calculations and reductions were too intricate to be effected save by a method of approximation and interpolation such as that which the author had given in his paper.—Mr. J. Y. Buchanan read a short paper from Prof. Liversidge descriptive of a specimen of Stilbite that had been brought by the *Challenger* from Kerguelen's Island.—Prof. J. Blyth gave an interesting account of certain experiments which he had made with a simple form of selenium cell. Two ordinary metal combs with every alternate tooth broken away were set close together, so that each remaining tooth in either fitted without touching into the interstice between two remaining teeth in the other. The two combs were then brought into electrical contact by the selenium, which was poured in between the teeth; and thus a selenium cell was formed with a large surface and small resistance. In one special form of cell the combs were bent round a glass tube, inside which a singing flame was set. The accompanying rhythmic fluctuations in the luminosity of the flame were reproduced as sound in the telephone receiver. The difficulty of getting good selenium at the time induced the author to try if amorphous phosphorus would serve as a substitute. A "radial cell," in which the interstices between the dove-tailing electrodes were filled with phosphorus, was found to be not sensitive to light; but such an arrangement was discovered to be a battery in itself, giving rise to currents which varied with the pressure that was brought to bear upon the phosphorus. This property at once suggested a phosphorus cell as a possibly useful transmitter in a telephonic circuit. Another curious effect was noted, viz. that phosphorus under the action of a variable current glowed with a beautifully varying phosphorescence.—Mr. Aitken communicated further experiments on the formation of fogs. His former experiments he had repeated at as low temperatures as 8° F., invariably finding that in filtered air no fog formed. Discussing the production of dry fogs, *i.e.* fogs that are formed in *non-saturated* air, the author pointed out that certain kinds of fog-forming dust were much more efficient in their action than others. Some, in virtue probably of their deliquescent properties, formed clouds in non-saturated air; others only acted in saturated air; while a third class required the air to be super-saturated. In connection with the change of state of moisture in the atmosphere, Mr. Aitken explained the formation of the various forms of ice-crystals by application of the principle that the slower the crystallisation the more regular and simple it is. Hence complex types of crystals betoken a rapid crystallisation. The paper ended with a few instructive remarks upon liquid surface-tension as an important factor in the growth and coalescence of raindrops as they descend towards the earth.—Prof. Tait, in a short note on thermal conductivity, intimated that he had solved the equation for conduction, taking into account the temperature-variations of the conductivity and specific heat. He further pointed out that, at least in the case of iron, most of the decrease with temperature that apparently takes place in the value of the conductivity is in all likelihood referable at once to the change in specific heat; so that perhaps after all conductivity varies very slightly indeed with temperature, and is practically constant through ordinary ranges. Prof. Tait also gave a simple experimental illustration of the diminution in the surface-tension of water produced by heating. A red-hot poker was held close over a level water surface on which Lycopodium dust was sprinkled, when at once the dust was drawn away to cooler regions as if violently repelled by the strongly-heated metal.—Dr. Haycraft communicated a paper in which he showed that the hepatic cells of man and other domestic animals, several of which he had examined, are possessed of true cell-walls. These may be demonstrated by placing a few scrapings from a fresh organ on a slide, and pressing the cover-glass down so as to crush them. The membranes are then to be seen projecting from the half-broken cells, or scattered about the preparation.

Boston, Mass., U.S.A.

American Academy of Arts and Sciences, February 9.—The president, Prof. J. Lovering, in the chair.—Prof. H. P. Bowditch presented some observations on the senses of sight and touch. An observer having noticed the position of a point at the centre of a target, shut his eyes, and after a measured interval of time attempted to touch this point again. It was found that the attempts were more successful when two seconds had elapsed than in the cases when more or less time had intervened.—Mr. N. D. C. Hodges read a paper upon the thermodynamic basis for the kinetic theory of gases. By means of the fundamental equations of thermodynamics the mathematical analysis of the kinetic theory results at once; and an expression is obtained for the absolute mass of a molecule.—Prof. Pickering, in a paper on variable stars, discussed their changes in brilliancy and grouped them according to a new law.—Mr. Arthur Searle gave some of the results of his observations on the zodiacal light.—Mr. Harold Whiting, in an abstract of a forthcoming paper, stated that he had found the rate of propagation of what may be called the magnetic wave to vary from 30 feet to 300 feet per second.—Prof. Goss presented some observations on the strength of fir beams.

Paris

Academy of Sciences, February 21.—M. Wurtz in the chair.—The following papers were read:—Meridian observations of small planets at Greenwich and Paris Observatories during the fourth quarter of 1880, communicated by M. Mouchez.—On the parallax of the sun, by M. Faye. He indicates in a table nine methods of determining the earth's distance from the sun. He holds that the method of physicists is best; that the sun's parallax, 8″·813, is now determined by them to within $\frac{1}{100}$ of a second; and that the seven astronomical methods converge more and more towards this result, and tend to confirm it, without having equal certainty.—Male eels, compared with the females, by M. Robin.—General considerations on the Crustacean fauna of great depths in the Carribbean Sea and the Gulf of Mexico, by M. Alph. Milne-Edwards. This deals with some results of the cruises in the *Blake*. Many new Crustacean species were obtained, and certain groups previously thought foreign to American waters were found abundantly at great depths. Anomouran and macrouran Crustacea there abound. Numerous forms intermediate between groups that have been thought very distinct are discovered (and the author cites several examples).—New clinical researches tending to prove that the cerebellum

is the co-ordinating nerve-centre for movements necessary to standing and walking, considered in all their forms, by M. Bouillaud.—On the systems of faults or diaclases which traverse the series of stratified formations; new examples furnished by Cretaceous strata in the environs of Etretat and Dieppe, by M. Daubrée.—On Fuchsian functions, by M. Poincaré.—A letter of Ampère was presented.—On a class of Abelian integrals and on certain differential equations, by M. Picard.—On an integrator, or instrument for graphic integration, by M. Abdank-Abakanowicz.—On the cooling power of gases and vapours, by M. Witz. He infers equality of the cooling powers of dry air and air saturated with moisture. The cooling power of coal-gas compared with that of air is equal to 3·48, that of sulphurous acid does not exceed 0·61 (the pressure being 760 mm.). The velocities of cooling increase more quickly than the 1·233 power of the excesses. For steam they increase proportionally to the 0·83 power.—On the surfaces of revolution limiting liquids deprived of weight, by M. Terquem.—On radiophony: third note by M. Mercadier. He proves that the radiophonic effects are due to vibratory motion caused by alternate heating and cooling through intermittent radiations, principally in the gaseous layer adherent to the solid wall struck by these radiations; the anterior wall in opaque receivers, the posterior in transparent receivers.—Magic mirrors of silvered glass, by M. Laurent. He uses either pressed glass (polishing the surface opposite to the projections), or thin glass of commerce (engraving a hollow design on it).—On pyridic bases, by M. de Coninck.—On the hystolysis of the muscles of larva during the post-embryonic development of Diptera, by M. Viallanes. This relates to the phenomena of disappearance of muscles as the insect passes into the state of *pupa*.—On a new larva of Cestoïdes belonging to the type of the Cysticercus of Arion, by M. Villot.—On a new form of segmentary organ in Trematodes, by M. Macé.—Researches on the circulation and respiration of Ophiures, by M. Apostolidès. The circulatory system is formed of the general cavity and the spaces connected with it; and the respiratory sacs, by their alternate contraction and expansion, draw the blood into the peristomachal cavity, then drive it to the periphery. This explains how the sanguineous liquid, bathing all the organs, respires, and is set in motion.—On a method of coloration of Infusoria and anatomical elements during life, by M. Certes. Placed in a weak solution of chinoline blue, or cyanine, Infusoria take a pale blue colour, and may continue to live twenty-four to thirty-six hours. After twenty-four hours in a moist chamber, the white corpuscles of a frog's blood, coloured with cyanine (in serous solution) show amœboid movements. Chinoline blue is, *par excellence*, the reagent of fatty matter (which is quite absent in nuclei and nucleoli).—On the permanence of prussic acid during a month in the bodies of animals poisoned with this substance pure, by M. Brame. A rabbit and a cat were poisoned with 1 gramme of the substance each. In such dose it seems to preserve the animals perfectly at least a month, remaining in the tissues (especially those of the stomach), with which it seems to become intimately united.

February 28.—M. Wurtz in the chair.—The following papers were read:—On the attenuation of virus and its return to virulence, by MM. Pasteur, Chamberland, and Roux. The bacterium of *charbon* in artificial cultivation produces true germs (unlike the microbe of chicken cholera, which multiplies by division), whose virulence is not affected by air. This spore-production can be hindered by cultivation at 16° or at 42° to 43°. The mycelian product, in the latter case, becomes sterile after about a month; up to that point reproduction is easy, but the virulence is gone after the first eight days, in which time it passes through various stages of attenuation. The secret of causing a return of virulence consists in successive cultivation in the bodies of certain animals. The facts throw light on the etiology of epidemics.—Action of hydracids on halogen salts containing the same element, by M. Berthelot. Compounds so formed exist both in the case of alkaline salts, where they are denoted by absorption of gas, liberation of heat, and special reactions, and in the case of metallic salts properly so called, where they are obtained crystallised.—M. de Lesseps presented a fifth series of documents relating to the history of the Suez Canal.—On the disinfectant and anti-putrid action of vapours of nitrous ether, by M. Peyrusson. Its action is shown both from laboratory and hospital observations. It has the advantage of an agreeable and harmless smell.—On a new definition of the surface of waves, by M. Darboux.—On the development of the infinite product $(1-x)$, $(1-x^2)$ $(1-x^3)$ $(1-x^4)$ . . . by Mr. Franklin.—On radiophony, by M. Mercadier. He makes *thermophon*[illegible] or *phonic thermomultipliers* (after the analogy of electric [illegible] multipliers), for study of radiant heat, a single element consisting of a short glass tube containing a thin plate of smoked [illegible] mica, and several such being connected by caoutchouc or [illegible] tubes. The air in these tubes vibrates longitudinally, and lengthening them he gets *thermosonorous* pipes, having the same properties as ordinary sounding-pipes.—Application of Talbot fringes to determination of the refractive indices of liquids, by M. Hurion.—On the displacement of the soda of chlorate of sodium by hydrate of copper, by M. Tommasi. This takes place even at a low temperature (4° to 5°). With pure sodium chlorate the reaction is almost instantaneous. Potassium chlorate gives like results.—On the heats of combustion of some alcohols of the allylic series and of aldehydes which are isomeric with them, by M. Louguinine.—On the products of decomposition of proteic matters, by M. Blennard.—On a synthetic homologue of [illegible] letierine, by M. Étard.—On a cause of alteration of canvas, by M. Balland. This relates to an observation by Dr. Tripier on some rusty-coloured hammock canvas used by the Algerian army in 1847. This showed dark spots after washing, and were [illegible] pieces in use. The spots were probably due to iron salts produced by alkaline sulphides in the artificial soda and by the oxide fixed by the stuff in manufacture. The sulphide passes to the state of sulphate in air by a combustion involving [illegible] tissue.—Contribution to the study of trichinosis, by M. Chatin.—Contribution to the physiological action of [illegible] of ammoniacal salts, by MM. Richet and Moutard-Martin. *Inter alia*, it is singular that injection of a concentrated solution of urea increases the elimination of water more than of urea. The uremia death cannot be attributed to non-elimination of the ammoniacal salts of urine.—On the inflammatory nature of the lesions produced by the poison of the Bothrops serpent, by M. Couty and De Lacerda.—On the pulmonary alterations produced by long stay in the purifying chambers of gas-works, by M. Poincaré. Animals kept eight months in those chambers exhibit in the lungs an accumulation of epithelial cells in some alveoli, but especially a prodigious nuclear proliferation in the connective tissue. This shows that it is not without danger to send children with whooping-cough to similar treatment.—Retina of the cylinder axis and the peripheral nerve-cells with rods of sense in insects, by MM. Künckel and Gazagnaire. In man every nervous enlargement consists essentially of a bipolar cell (true nerve-termination), connected on one hand with the cylinder axis of the nerve-fibre, and on the other with a nerve-rod which is its prolongation; this rod is surmounted by a cone, properly so called, or a transformed hair.—On the genus [illegible] of Pyrosoma, by M. Joliet.—Antiquity of *Elephas primigenius* (Blum) in the sub-Pyrenean Valley, by M. Caraven-Cachin. It seems to have appeared first after the diluvium of the plain, on the old Pleistocene spread in a nearly horizontal sheet of Tertiary and other strata.

CONTENTS

Sir William Herschel, I. By J. R. Hind, F.R.S . . . .
Extinct British Animals. By Prof. W. Boyd Dawkins, F.R.S
Our Book Shelf:—
Ormerod's "Notes of Observations of Injurious Insects"
"Mémoires de la Société des Sciences Physiques et Naturelles de Bordeaux" . . . .
Letters to the Editor:—
Aberration of Instinct.—George J. Romanes, F.R.S.
Prehistoric Europe.—Dr. James Geikie, F.R.S.; R. H. Tiddeman . . . .
Les Lettres d'Outre-Mer.—Capt. S. P. Oliver . . . .
Explosive Gas in a Lake.—J. Shaw . . . .
Colours of British Butterflies.—J. Innes Rogers . . . .
Dust, Fogs, and Smoke.—M. Chatel . . . .
The German Chemical Society . . . .
Irish Esparto Grass . . . .
Siberian Meteorology. By Dr. A. Woeikof . . . .
Sphygmography (*With Illustration*) . . . .
Notes . . . .
Our Astronomical Column:—
The Solar Parallax . . . .
Swift's Comet, 1880 *e* . . . .
Physical Notes . . . .
Geographical Notes . . . .
On the Viscosity of Gases at High Exhaustions, II. By William Crookes, F.R.S. . . . .
Animal Remains in the Schipka Cavern . . . .
Some Remarks on Peripatus Edwardsii, Blanch. By Dr. A. Ernst (*With Illustrations*) . . . .
Acoustics in China. By John Fryer and Dr. W. H. Stone . . . .
Scientific Serials . . . .
Societies and Academies . . . .

OCIETIES.

18

March 10.
nversion of Radiant Energy into
to the Limit of the Liquid State:
ir.: Prof. E. W. Atkinson.
—Earth-Currents—Electric Tides.
ations on his Paper—On the Appli-
Railway Rolling Stock: Lieut.-F.
Processes of Manufacture of Wood
n of Electricity during Spinning:
l to obviate it: Edward B. Bright.
application of Infinite Functions to
the Flexure and Equilibrium of a
—A Note on Prof. C. S. Peirce's
ld.
f Architecture in Modern Civiliza-

lassrooms: Rev. W. Houghton.

RCH 17.
e Cetacea: Prof. Flower.

and Literature of the Scottish

TARCH 17.
ation Species of Organic Bodies:
at: R. S. Poole.

RCH 13.
dies": Miss Fenwick Miller.

RCH 14.
Cetacea: Prof. Flower.

Prof. W. G. Adams.
Silver Mines of the World: G.
S. Obers.

RCH 15.
tions to the Society's Collection
the Secretary.—Micrographic in-
IV. "The Echinocystidæ," their
E. Jeffrey Bell, F.Z.S.—Contri-
Part IV. On some Points in
and its Spectroscopic Positions: W.

Prof. Schäfer.
South Africa: R. W. Murray.
at S.—Movements of Plants:

ses of the English Stations in the

ARCH 16.
Cetacea: Prof. Flower.
Engine: Col. F. Bramwell.
ion of Instruments.

ARCH 17.

ories of Paleozoic: Dr. George
Rev. R. Boog Watson.—Note
in Allied Species: E. Daydon

ses of Mixed Liquids: F. T.
—On the Action of Alkyl-
Ammonia: J. B. Jopp and
Acid on Naphthaquinone: F.
ged Formation of Nitrous Acid
ntaneously in the Absorption of
in the Blue Test of the Ammo-
nical Principle of Indian Ally-
mmic.
H. Stephens.
of Vapour, with Experiments

H 18.
Lessons: Prof. Flower.
Dr. W. H. Stone.

RCH 19.
ogue: Rev. G. R. Hawes.

SUBSCRIPTIONS TO "NATURE."

	£	s.	d.
Yearly	28	0	
Half-yearly	14	6	
Quarterly	7	6	

To the Colonies, United States, the Continent, and all places within the Postal Union :—

	£	s.	d.
Yearly	30	6	
Half-yearly	15	6	
Quarterly	8	0	

OFFICE: 29, BEDFORD STREET, STRAND, W.C.

NOTICE OF REMOVAL.

JAMES HOW & CO.,

SCIENTIFIC INSTRUMENT MAKERS,

73, FARRINGDON ST., LONDON

(LATE OF 3, ST. BRIDE ST., AND 8, FOSTER LANE)

HOW'S STUDENT'S MICROSCOPE. HOW'S MICROSCOPE LAMP

Rock Sections and other Objects for the Microscope.

SECOND EDITION,

GRIFFIN'S CHEMICAL HANDICRAFT.

PRICE 4s. 3d. POST FREE.

A CATALOGUE OF CHEMICAL APPARATUS:

ILLUSTRATED, CLASSIFIED, DESCRIPTIVE.

Demy 8vo, 480 pp., Illustrated with 1,600 Woodcuts.

Most Complete and Cheapest List of Apparatus.

JOHN J. GRIFFIN AND SONS, 22, GARRICK STREET, LONDON, W.C.

LIGHTNING CONDUCTORS.

Experience, accumulated since the time of Benjamin Franklin, proves conclusively that a Conductor made of Copper of adequate size is the best of all appliances for the protection of every description of building from the destructive effects of lightning.

NEWALL & CO.'S

PATENT COPPER LIGHTNING CONDUCTOR,

As applied to all kinds of Buildings and Shipping in all parts of the world with unvarying success; is the most Trustworthy, most Effective, and also the Cheapest Conductor ever offered to the public.

It is simple in its application, no insulators being required, and it costs only one shilling per foot for the standard size, which ensures safety in any storm.

R. S. NEWALL & CO., 339, STRAND, W.C.
15, WATERLOO ROAD, LIVERPOOL.
15, ANDERSTON QUAY, GLASGOW.

MANUFACTORY—GATESHEAD-ON-TYNE.

J. ORME & CO.,

(Late M. JACKSON & CO.)

MANUFACTURERS AND IMPORTERS OF

SCIENTIFIC APPARATUS AND CHEMICALS.

SOLE AGENTS FOR HICKLEY'S PATENT TELEPHONES,

Price 50s. per Pair, Cash with Order,

Price Lists sent on receipt of Three Stamps for Postage.

For Trade Terms inclose Business Card.

65, BARBICAN, LONDON, E.C.

ARATUS AND SCIENTIFIC INSTRUMENTS.

PURE CHEMICALS, &c.

TERS AND MANUFACTURERS.

AUG. BEL & CO.,

N LANE, COVENT GARDEN, LONDON, W.C.

s as required by the Universities, Colleges, and Schools always ready and kept in stock. Professor Foster's
mended by Dr. Voelcker. Description on Application. A Liberal Discount allowed to the Trade.

W. LADD & CO.,
SCIENTIFIC INSTRUMENT MANUFACTURE
(By Appointment to the Royal Institution of Great Britain),
11 AND 12, BEAK STREET, REGENT STREET, W.
IMPROVED HOLTZ ELECTRICAL MACHINES. GRAMME'S MAGNETO-ELECTRIC MACHI
PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3*s.* p
Physical Apparatus of every Description.
ILLUSTRATED CATALOGUE, SIXPENCE.

PATERSON'S NEW CATALOGUE OF PHYSICAL A
LANTERN SLIDES for SCIENTIFIC LECTURES. Season 1880-1. Post free 6 Stamps.
Complete Sets of Physical Apparatus for Science Primers and all the Physical Text-books in use in Schools and
Siemens and Gramme Dynamo Machines and Lamps for hire.
Schools supplied with Apparatus as per Science and Art Departments' Requirements in the Sections of Light, H
Electric Signals for Houses, Hotels, &c., Colliery Signals, Lightning Conductors. The Gower-Bell Loud-speak
EDWARD PATERSON, Electrical Engineer.
SHOW ROOMS AND STEAM WORKS:—56, LITTLE BRITAIN, E.C. (late 3, Bedford Cou
MOLISON'S HARMONOGRAPH; executes the Harmonic Curves in the most perfect manner.
Illustrated Catalogue of Electrical Apparatus, Part 1, *post free*, 6 *Stamps. Ditto, Electric S*

Liberal Terms to Science Teachers and the Trade.
THOMAS CRAMPTON (formerly of 4, Little Britain, London, E.C.), ELECTRICIANS, OPTICIANS, and PHILOSOPHICAL INSTRUMENT MAKERS. Electric Bells, New Metallic Base Pattern, Constant Batteries, Indicators, Thief and Fire Alarms, and Automatic Switches, Induction and Medical Coils, or Specialities. Insulated Wires of every description. Microscopic and Optical Materials. Telescopes, Opera Glasses, Microscopes, Aneroid Barometers, and Lime-light Apparatus. Illustrated Catalogue Three Stamps.
THOMAS CRAMPTON & CO., 351, HIGH HOLBORN, LONDON, W.C.
For Trade Terms send Card.

ELECTRICAL AND SCIENTIFIC APPARATUS.
Wholesale Manufacturer of Metallic Base Electric Bells, Electric Reversing Indicators, and Constant Manganese Batteries, Telephone Switches and Transmitters. Induction Coils and Vacuum Tubes, Terminals. Carbons, Wire and all Materials. Instruments made, repaired, or altered on the premises. Illustrated Bell List free. Complete Catalogue Two Stamps. Special Quotations to the Trade.
HENRY J. DALE, MANUFACTURING ELECTRICIAN and OPTICIAN, 4, Little Britain, London, E.C.

R. W. NEEVES,
PHILOSOPHICAL INSTRUMENT
AND
INTENSITY COIL MAKER.
PRICE LIST, FOUR STAMPS.
55, SIDMOUTH STREET, LONDON, W.C.

EAGLE INSURANCE COMPANY,
79, PALL MALL.
FOR LIVES ONLY. ESTABLISHED 1807.
Accumulated Funds £3,043,542
Also a Subscribed Capital of more than £1,500,000
Reports, Prospectuses, and Forms may be had at the Office, or from any of the Company's Agents, post free.
GEORGE HUMPHREYS, Actuary and Secretary.

S. C. TISLEY & Co.,
OPTICIANS,
172, BROMPTON ROAD, S.W.
(Close to South Kensington Museum.)
THE PHONEIDOSCOPE
An Instrument for Observing the Colour-Figures of Liquid Films under the action of Sonorous Vibrations.
Being a visible demonstration of the Vibratory and Molecular Motion of a Telephone Plate.
The PHONEIDOSCOPE, with 3 Discs, Bottle of Solution, Descriptive Pamphlet, &c., in Cardboard Box, 10*s.* 6*d.*
MANUFACTURED AND SOLD WHOLESALE AND RETAIL BY
S. C. TISLEY & CO., 172, BROMPTON ROAD, LONDON, S.W.
TELEPHONIC ELECTRICITY. All Materials supplied for Experimental Purposes.
Price Lists of Electrical and Acoustic Apparatus, with Drawings and Description of the Harmonograph. Post Free, 2d.

NATURE

THE SPECTROSCO
PLICATIONS. By J. N. LOCK
Second Edition. Crown 8vo. 3*s.*

THE ORIGIN AND
OF INSECTS. By Sir JOHN
Illustrations. Crown 8vo. 3*s.* 6*d.*

THE TRANSIT OF
FORBES, B.A., Professor of Na
University, Glasgow. With nu
3*s.* 6*d.*

THE COMMON FR
MIVART, F.R.S. Illustrated.

POLARISATION OF
SPOTTISWOODE, LL.D., Pres
traced. Second Edition. Crown 8

ON BRITISH WILL
SIDERED IN RELATION TO
BOCK, M.P., F.R.S. Illustrat
4*s.* 6*d.*

THE SCIENCE OF
MEASURING. By H. W. CHI
Illustrated. Crown 8vo. 4*s.* 6*d.*

HOW TO DRAW A
A Lecture on Linkages. By A. B.
8vo. 1*s.* 6*d.*

LIGHT: A Series of
and Useful Experiments in the
Students of every Age. By ALF
BARNARD. With Illustrations.

SOUND: A Series of
and Inexpensive Experiments in th
of Students of every Age. By
in the Stevens Institute of Techn
tions. Crown 8vo. 3*s.* 6*d.*

SEEING AND THIN
K. CLIFFORD, F.R.S. With I

DEGENERATION:
WINISM. By Prof. E. RAY
Crown 8vo. 2*s.* 6*d.*

(Others
MACMILLAN &

HOLLOWAYS OIN
For BAD BREASTS, OLD
effectually rubbed on the Ne
THROATS, BRONCHITIS, CO
GOUT, RHEUMATISM, and all

T. COOKE & SONS,

OPTICIANS

TO

H.R.H. the late Prince Consort, the Royal Family, Her Majesty's Home, Indian, and Colonial Governments, and most of the Foreign Governments.



Messrs. T. COOKE & SONS are now in a position to construct with punctuality and on the most reasonable terms every size and form of Equatorial Telescope; also Observatories, Transit Instruments, Spectroscopes, Chronographs, Theodolites, Levels, Astronomical Turret Clocks, &c.

Catalogues of Scientific Instruments on Application; also Catalogues of Amateurs' Lathes and Lathe Apparatus.

15-INCH EQUATORIAL MOUNTING, CONSTRUCTED FOR THE ROYAL OBSERVATORY, BRUSSELS, 1880.

T. COOKE AND SONS, Buckingham Works, York.

Messrs. MACMILLAN & CO.'S PUBLICATIONS.

BLACKS, BOERS, and BRITISH: a Three-Corner PROBLEM. By F. R. STATHAM. Crown 8vo. [Immediately

ANTHROPOLOGY: an Introduction to the Study MAN AND CIVILISATION. By E. B. TYLOR, D.C.L., F.R.S. With numerous Illustr Crown 8vo. 7s. 6d.

GRAPHICAL DETERMINATION OF FORCES IN ENGINEERI STRUCTURES. By J. B. CHALMERS, C.E. With Illustrations. 8vo. 24s.

MANUAL OF ANCIENT GEOGRAPHY. From the German of Dr KIEPERT. Crown 8vo. 5s.

THE COLLECTED WORKS OF FRANCIS SIBSON, M.D. LOND. F.R.S., &c. Edited by WILLIAM ORD, M.D. With Illustrations. 4 vols., 8vo. £3 3s.

THROUGH THE RANKS TO A COMMISSION. Crown 8vo. 6s.

This volume records the experiences of an aspirant to a military career, who, being too old to obtain a commission by the road of Examination, made up his mind to win it by working his way up through the ranks. He succeeded in the unprecedented short period of fifteen months. No one has hitherto had such an opportunity of describing the daily life of our soldiers from inside. As it bears no author's name, the Publishers feel bound to state that they have seen documents and letters from various persons which leave no doubt in their minds as to the authenticity of the narrative.

"This very interesting and indeed instructive narrative . . . is exceptionally interesting."—*Army and Navy Gazette.*

FO'C'S'LE YARNS. Including "Betsy Lee" and other Poems. Crown 8 7s. 6d.

"MACMILLAN'S BIOGRAPHICAL SERIES." NEW VOLUME.

CATHERINE AND CRAUFURD TAIT, WIFE AND SON OF ARCH BALD CAMPBELL, ARCHBISHOP OF CANTERBURY: a Memoir. Edited, at the request of the Archbishop, by Rev. W. BENHAM, B.D., Vicar of Marden, and one of the Six Preachers of Canterbury Cathedral. With Two Portraits engraved by JEENS. New and Cheaper Edition. Crown 8vo. 6s.

GUIDE TO THE UNPROTECTED. In Every-day Matters relating to Property and Income. By a BANKER'S DAUGHTER. Fifth Edition revised. Extra fcp. 8vo. 3s. 6d.

ENGLISH MEN OF LETTERS. Edited by JOHN MORLEY. New Volumes Crown 8vo. 2s. 6d.

DRYDEN. By GEORGE SAINTSBURY.

NEW NOVEL BY HENRY JAMES, Jun.

WASHINGTON SQUARE: THE PENSION BEAUREPAS: A BUNDLE OF LETTERS. 2 vols. Crown 8vo. 21s.

"To me it is unquestionably Mr. James's best book. . . . It is brimful of wit and sparkle, of tact and cleverness and humour of fun, and knowledge of life and of the world, of tact, measure, and resource."—*Truth.*

NEW NOVEL, A STORY OF THE GREEK WAR.

LOUKIS LARAS; or, the Reminiscences of a Chiote Merchant during the Great War of Independence. From the Greek of D. BIKÉLAS. Translated, with Introduction on the Rise and Development of Modern Greek Literature, by J. GENNADIUS, late Chargé-d'Affaires at the Greek Legation in London. Crown 8vo.

"Mr. Bikélas is a kind of Greek Erckmann-Chatrian, he paints the manners of country people. . . . The description of the in Chios, of the approach of the Turkish Fleet, of the flight to the old defenceless tower, are most vivid and full of simple force. *Pall Mall Gazette.*

THE AMERICAN JOURNAL OF PHILOLOGY. Edited by BASIL L. GILDERSLEEVE. Vol. I., No. IV. 8vo. 4s. 6d.

MACMILLAN'S ELEMENTARY CLASSICS.—NEW VOLUME.

HORACE.—ODES. Book II. Edited, with Notes, &c., by T. E. PAGE, M. Assistant Master at the Charterhouse. 18mo. 1s. 6d.

MACMILLAN AND CO., LONDON, W.C.

Printed by R. CLAY, SONS, AND TAYLOR, at 7 and 8, Bread Street Hill, Queen Victoria Street, in the City of London, and published by MACMILLAN AND CO., at the Office, 29 and 30, Bedford Street, Covent Garden.—THURSDAY, March 17, 1881.

NATURE

A WEEKLY ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
Of Nature trusts the mind which builds for aye."—WORDSWORTH

NO. 595, VOL. 23] THURSDAY, MARCH 24, 1881 [PRICE SIXPENCE

Registered as a Newspaper at the General Post Office.]

[All Rights are Reserved.

SOLAR PHYSICS.

The following COURSE of LECTURES will be given by Members of the Committee on SOLAR PHYSICS, appointed by the Lords of the Committee of Council on Education:—

An Introductory Lecture. By Prof. STOKES, Sec.R.S. 6th April, 1881.

A Lecture on the Practical Importance of Studying the Influence of the Sun on Terrestrial Phenomena. By Lieut.-General STRACHEY, R.E., C.S.I., F.R.S. 8th April.

Two Lectures on the Connection between Solar and Terrestrial Phenomena. By Prof. BALFOUR STEWART, F.R.S. 27th and 29th April.

Six Lectures on Spectroscopy in Relation to Solar Chemistry. By Mr. J. NORMAN LOCKYER, F.R.S. 4th, 6th, 11th, 13th, 18th, and 20th May.

Three Lectures on the Photography of the Infra-red of the Spectrum in its Application to Solar Physics. By Capt. ABNEY, R.E., F.R.S. 25th and 27th May, and 1st June.

The LECTURES will be delivered in the Lecture Theatre of the South Kensington Museum at 4 p.m. on the days stated above.

Admission will be by Tickets, which may be obtained, as far as there is room, on application by Letter to the SECRETARY, Science and Art Department, South Kensington, S.W.

SOCIETY FOR THE ADVANCEMENT OF CHEMICAL INDUSTRY.

A Meeting for the purpose of forming a Society for the Advancement of Chemical Industry will be held on MONDAY, April 4th, 1881, in the rooms of the Chemical Society, Burlington House, Piccadilly, London, W., at 4 p.m.

Prof. ROSCOE, F.R.S., President of the Chemical Society, will occupy the chair.

All persons interested in the Chemical Industries are hereby invited to attend.

GEORGE E. DAVIS, Hon. Sec. *pro tem.*

THE ENDOWMENT OF RESEARCH.

The ASTRONOMER-ROYAL, in a Letter of much import addressed by him to Captain W. NOBLE on the 10th inst., wrote as follows:—

"The very utmost, in my opinion, to which the State should be expected to contribute is exhibited in the large Grants entrusted to the Royal Society. The world, I think, is not unanimous in believing that THEY have been useful."

"THE PROCEEDINGS" and "THE PHILOSOPHICAL TRANSACTIONS OF THE ROYAL SOCIETY" contain many elaborate Papers with details of painful Experiments upon Animals for Scientific Purposes. These practices extend over a long series of years down to the present generation. They are as much wanting in real Humanity and true Wisdom as, perhaps, they ever were. Which is asserting much, for two great Surgeons of distinguished ability and learning have said of the ROYAL SOCIETY:—"Their old and favourite experiment, so often repeated by Hooke, Croone, and others, before our ROYAL SOCIETY, viz., of blowing up the lungs of a Dog, and then compressing them, is good for nothing."

"Hujusmodi doctrinas bene adumbravit fabula
de Ixione; qui cum Junonis, potentiæ deæ,
concubitum animo sibi designaret, cum
evanida nube rem habuit; ex qua Centauros
et Chimæras progenuit."

FRANCISCI BARONIS DE VERULAMIO.

SOCIETY for the TOTAL ABOLITION and UTTER SUPPRESSION of VIVISECTION.

Honorary Secretary and Treasurer,
GEORGE R. JESSE, Esq.,
Henbury, near Macclesfield, Cheshire.

February, 1881.

SILVERED GLASS SPECULA.

JOHN BROWNING begs respectfully to inform the scientific public that he can supply Specula from 3½ in. to 18 in. diameter, of Mr. With's parabolising. The stock is composed of the choicest reserves of the last ten years of Mr. With's productions, and Mr. With's Specula are generally admitted to be the finest ever made.

Each Mirror bears Mr. With's signature.

A reduced Price List of Specula, Mounted or Unmounted, will be forwarded post free.

JOHN BROWNING,

Optical and Physical Instrument Maker to H.M. Government, the Royal Society, the Royal Observatories of Greenwich and Edinburgh, and the Observatories of Kew, Cambridge, Durham, Utrecht, Melbourne, &c., &c.

63, STRAND, LONDON, W.C.

FACTORY—SOUTHAMPTON STREET, LONDON, W.C.

TRAVELLERS' SCIENTIFIC REQUISITES.



ANEROID BAROMETER with ALTITUDE SCALE, THERMOMETER and COMPASS in Flat Pocket Case, various Forms,

£7 7s. and £8 8s.

Price Lists of Instruments free by post.

NEGRETTI & ZAMBRA,

Opticians and Scientific Instrument Makers

To HER MAJESTY THE QUEEN,

HOLBORN VIADUCT,

45, CORNHILL, & 122 REGENT STREET, LONDON.

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 48N, Tollington Road, Holloway, London, N.

LONDON UNIVERSITY, ARMY, CIVIL SERVICE.

Dr. R. H. JUDE, D.Sc. (Lond.), M.A. (Cantab.), High Wrangler, First Class Natural Science Tripos, late Scholar of Christ's and sometime Demonstrator of Chemistry at Caius College, Cambridge, with qualified Assistants, prepares Gentlemen in all the subjects for the above Exams.

Natural Science treated both experimentally and theoretically.

Highest Testimonials and References to present and former Pupils. A few Pupils taught by Correspondence. Special Classes now forming for Matriculation, B.A., B.Sc., and Prel. Sci.

119, Cambridge Gardens, Notting Hill, W.

SKELETON LEAVES WANTED.—State

Kind, Quantity, and Price.—Letters only to A. M. S., 71, Bessboro' Street, London, S.W.

ROYAL POLYTECHNIC.—CLASSES for

the Preparation of Students for University Examinations, under the direction of EDWARD B. AVELING, D.Sc., F.L.S. London University Matriculation, 1st and 2nd B.Sc., Preliminary Scientific M.B., Botany, Physiology, Chemistry. All the work practical.

INSTRUCTION IN MATHEMATICS.—

Youths or Adults attended at their Residence, on Reasonable Terms, by a M.A. of Cambridge. Unquestionable references if required.—Address, by letter, O. P., Post Office. Turnham Green.

"NATURE," Nov. 14, 1878, No. 472.—One

Shilling each will be paid for Copies of this number.—Address Publishers of NATURE, 29, Bedford Street, Strand W.C.

MINERALOGY AND GEOLOGY.

MAGNIFICENT DERBYSHIRE FLUOR SPAR VASE. Height, with Pedestal, 2ft. 8in.; Diameter 13½in. This is, with one exception, the finest vase of the kind known, the vein having been worked out some forty years ago.

FINE PINK APOPHYLITE, EISENROSE, CONNELLITE, CALC SPAR, BARYTA, FAHLERZ, LIBETHENITES.

COLLECTIONS FOR STUDENTS, from £2 2s. COLLECTIONS FOR BEGINNERS, from 4s. BLOWPIPE CASES AND APPARATUS.

PRIVATE LESSONS AND EVENING CLASSES.

Catalogues free.

SAMUEL HENSON,

277 (*Late* 113*a*), STRAND, LONDON, W.C.

GEOLOGY AND MINERALOGY.

Special Collections for Teachers and Students, used with success by all Lecturers and Teachers of Geology in Great Britain. Obtained Gold and Bronze Medals at Sydney Exhibition, 1879, also in London, 1862, and Paris, 1867.

200 Specimens in Cabinet	...	...	...	...	£2	2	0
100 ditto	ditto	...	...	...	1	1	0
50 ditto	ditto	...	...	...	0	10	6

New Lists of Collections, Apparatus, &c., now ready, and free on application to

JAMES R. GREGORY'S

Geological Museum and Repository,

88, CHARLOTTE STREET, FITZROY SQUARE.

EVERY BOY A GEOLOGIST.

Now ready, and highly recommended, complete, price 7s. 6d.

This admirable little Work and most extraordinary Cabinet of wonderfully well-selected Natural Specimens, together with other Geological Preparations, and a powerful Lens, are calculated to start a boy thinking till he has mastered for himself no ordinary knowledge of the formation of the Earth's Crust.—THOMAS J. DOWNING, GEOLOGIST, &c., 38, Whiskin Street, London, E.C.—Catalogues free.

DIAMONDS IN MATRIX.

R. C. NOCKOLD, Diamond and Oriental Stone Cutter and Dealer, has for sale Specimens of the above; also Cut Precious Stones in all Colours.

Precious Stones valued and bought.

12, FRITH STREET, SOHO, W.

THE "HANSA"

Published since 1864 in Hamburg, is the only independent professional paper in Germany, dedicated exclusively to Maritime Objects. Essays, Critiques, Reviews, Reports, Advertisements. Strict eye kept upon the development of Maritime Affairs in every respect. Every second Sunday one Number in 4to at least; frequent supplements and drawings. Subscription at any time; preceding numbers of the year furnished subsequently. Price 12s. for twelve months. Advertisements 4d. a line, widely spread by this paper; considerable abatement for 3, 6, 12 months' insertion. Business Office: Aug. Meyer and Dieckmann, Hamburg, Alterwall, 28. Edited by W. v. FREEDEN, M.R., Hamburg, Alexander Street, 8.

LIVING SPECIMENS FOR THE MICROSCO

THOMAS BOLTON, NATURALISTS' and MICROSCOPIST

STUDIO, 57, NEWHALL STREET, BIRMINGHAM.

T. B. has last week sent to his subscribers Young Salmon, Sam... in the "Alevin" Stage. He has also sent out the Marine Polyzoa *... bankia imbricata*, and *Alcyonidium polyoum* and the Hydrozoa, *Syn... exuvia*, and Sertularia, Periwinkle Spawn, &c., as well as many Fres... Organisms. He has also a few Specimens of the Dutch Frogs, *Ran... lenta*, One Shilling each.

Weekly announcements will be made in this place of organisms ... is supplying.

Specimen Tube, One Shilling, post-free.

Twenty-six Tubes in course of Six Months for Subscription ...

Price List of Specimens on application, with stamped addressed en...

Portfolio of Drawings, No. 4, One Shilling.

In unserem Verlage erscheint:

DER NATURFORSCHER

Wochenblatt zur Verbreitung der Fortschritte in den Naturwissenschaften.

Herausgegeben von Dr. WILHELM SKLAREK.

Wochentlich 1—1½ Bgn. in 4°.

Preis vierteljährlich 4 Mk.

Die nunmehr ihren XIV. Jahrgang beginnende Zeitschrift hat ... welche sich mit Naturwissenschaften beschäftigen, grossen Beifall ... Probenummern sind durch jede Buchhandlung zu erhalten ... Berlin, S.-W., 77, Charlottenstr.

FERD. DÜMMLER'S VERLAGSBUCHHANDL...

(Harrwitz & Gossmann.)

On the 1st of every Month, price Sixpence.

THE ENTOMOLOGIST:

AN ILLUSTRATED JOURNAL OF BRITISH ENTOMO...

Edited by JOHN T. CARRINGTON,

With the Assistance of

FREDERICK BOND, F.Z.S. | JOHN A. POWER, M.D.
EDWARD A. FITCH, F.L.S. | J. JENNER WEIR, F.L.S.
F. BUCHANAN WHITE, M.D.

Contains Articles by well-known Entomologists on all branches ... Science; on Insects injurious or beneficial to Farm or Garden, ... Habits, Life-Histories; occurrence of Rarities, &c.; there are ... of Duplicates and Desiderata.

Numerous WOODCUT ILLUSTRATIONS, to the printing of which ... attention is given, and occasional LITHOGRAPHED and CHROMO-... GRAPHED PLATES.

SIMPKIN, MARSHALL, & CO., Stationers' Hall Court.

THE ENTOMOLOGIST'S MONTHL... MAGAZINE.

Price Sixpence, Monthly, 24 pages 8vo, with occasional Illustrations. Conducted by C. G. BARRETT, J. W. DOUGLAS, R. MCLACHLAN, F... E. C. RYE, F.Z.S., E. SAUNDERS, F.L.S., and H. T. STAINTON, F...

This Magazine, commenced in 1864, contains standard articles and ... on all subjects connected with Entomology, and especially on the ... the British Isles.

Subscription—Six Shillings per Volume, post free. The volumes ... mence with the June number in each year.

Vols. I. to VI. (strongly bound in cloth) may be obtained by purchas... the entire set to date, at the increased price of 10s. each; the ... vols. may be had separately or together, at 7s. each.

London: JOHN VAN VOORST, 1, Paternoster Row.

N.B.—Communications, &c., should be sent to the Editors at the address.



Chaque Samedi 16 pages grand in-8°, 2 colon...

REVUE HEBDOMADAIRE

Scientifique, illustrée, spéciale, seul journal tenant les lecteurs au courant de tous les détails de l'Exposition universelle d'Hiver... organe indépendant des exposants

RÉDACTEUR EN CHEF : W. de PONVIELLE

E. de CLISSON : DIRECTEUR

Un numéro, 40 *centimes.* — *L'année*, 18 *francs*. *Union postale* 20 *francs.*

PARIS, 16, rue du Croissant, PA...

Envoi de numéros spécimens gratis sur demande.

NORTH BRITISH AGRICULTURIST

is the only Agricultural Journal in Scotland, and circulates extensively amongst Landed Proprietors, Factors, Farmers, Farm-bailiffs, and others interested in the management of landed property throughout Scotland and the Northern Counties of England.

The AGRICULTURIST has also a very considerable circulation on the Continent of Europe, America, Australia, and the Colonies.

The AGRICULTURIST is published every Wednesday afternoon in time for the evening mails, and contains Reports of all the principal British and Irish Markets of the week, besides Telegraphic Reports of those held on the day of publication.

The Veterinary Department is edited by one of the leading Veterinarians in the country, and is invaluable to the breeder and feeder as a guide to the rearing of animals, and their treatment when labouring under disease.

Full Reports are given of the Meetings of the Royal Agricultural Society of England, the Royal Agricultural Society of Ireland, the Highland and Agricultural Society of Scotland, the Scottish Chamber of Agriculture, and all the principal Agricultural Associations throughout Great Britain and Ireland.

For Advertisers addressing themselves to Farmers a better medium does not exist

Price 3*d*. By post 3½*d*. Annual Subscription, payable in advance, 14*s*.

Office—377, High Street, Edinburgh.

Post-Office Orders payable to Charles Anderson, Jun., Edinburgh.

ESTABLISHED 1843.

LA SEMAINE FRANÇAISE: a Weekly

Newspaper and Review in the French Language. Politics, Literature, Science, Art, Varieties, Notes. Price 3*d*., through booksellers, and at the railway bookstalls. Office, 37, Southampton Street, Strand, W.C.

LA SEMAINE FRANÇAISE: Journal Français pour l'Angleterre: Politique, Littérature, Sciences, Arts, Variétés, Nouvelles, et Notes. Un exemplaire par la poste, 3½*d*., en timbres poste. Abonnement franco par la poste—un an, 15*s*. 2*d*.; six mois, 7*s*. 7*d*. Prix 3*d*., chez tous les libraires et aux gares des chemins de fer. On s'abonne aux bureaux, 37, Southampton Street, Strand, Londres, W.C.

LA SEMAINE FRANÇAISE.—"'La Semaine Française' has been brought out in London for the benefit of those English readers who may wish to study contemporary French from all points of view, instead of confining their reading to one particular Gallic print. It certainly merits success."—*Graphic*.

LA SEMAINE FRANÇAISE.—"The numbers before us are full of good things. . . . . It will be far better for most than any one of the best papers published in Paris itself. We are much pleased with the character of it, and believe it will be highly valued in all those many households where French is cultivated. The printing is very well done."—*Queen*.

TERMS OF SUBSCRIPTION:—

	s.	*d.*
Three months	3	10
Six "	7	7
Twelve "	15	2

P.O.O. payable to T. SPANSWICK, at King Street, Covent Garden, W.C.

Publishing Office, 37, Southampton Street, Strand, W.C.

THE ZOOLOGIST:

A MONTHLY MAGAZINE OF NATURAL HISTORY.

Third Series. Edited by J. E. HARTING, F.L.S., F.Z.S., Member of the British Ornithologists' Union; contains—

Original articles by well-known naturalists in every branch of zoology: habits of animals; arrival and departure of migratory birds; occurrence of rare birds; distribution and migration of British fresh-water fish; new or rare marine fish; local aquaria; British reptiles; British land and fresh-water mollusca, with remarks on the haunts and habits of the species; and other matters of general interest to those who delight in natural history. Reports of the Linnean, Zoological, and Entomological Societies. Reviews of natural history books. Occasional translations from foreign zoological journals of important and interesting articles in various branches of zoology. There are occasional woodcuts.

JOHN VAN VOORST, 1, Paternoster Row

THE BREWERS' GUARDIAN:

A Fortnightly Paper devoted to the Protection of Brewers' Interests, Licensing, Legal, and Parliamentary Matters.

REVIEW OF THE MALT AND HOP TRADES; AND WINE AND SPIRIT TRADE RECORD.

The Organ of the Country Brewers.

"The Brewers' Guardian" is published on the evenings of every alternate Tuesday, and is the only journal officially connected with brewing interests. Subscription, 16*s*. 6*d*. per annum, post free, dating from any quarter-day. Single Copies 1*s*. each. Registered for transmission abroad.

Offices—5, Bond Court, Walbrook, London, E.C.

"The leading Farmers' paper."—CLARE SEWELL READ, ESQ., M.P.

THE CHAMBER OF AGRICULTURE JOURNAL AND FARMERS' CHRONICLE

(PRICE 3*d*. WEEKLY).

The representative organ of the Central and Provincial Chambers of Agriculture; *gives fuller reports of the discussions and proceedings* of this extensive organisation than any other agricultural paper. It devotes *special attention to the treatment of Agricultural Questions by Parliament*, besides containing ample Reports of the LATEST LONDON and COUNTRY CORN, CATTLE, HOP, PROVISION, and other Markets, with Original Articles on Practical Farming, the Dairy, Herd and Flock News, Horticulture, &c., &c. It is despatched every Monday evening in time for the country post.

Terms of Subscription, payable in advance, post free:—3 months, 3*s*. 9½*d*.; 6 months, 7*s*. 7*d*.; 12 months, 15*s*. 2*d*.

Published by W. PICKERING, 21, Arundel Street, Strand, London, W.

THE CHEMICAL NEWS AND JOURNAL OF PHYSICAL SCIENCE.

EDITED BY W. CROOKES, F.R.S., &c.

Published every Friday. Price 4*d*.

No. 1113 (March 25, 1881) contains—On the Calorific Power of Fuel, and Thompson's Calorimeter, by J. W. Thomas, F.C.S., &c.—Determination of Ammonia in Water-Analysis, by W. H. Watson, F.C.S.—Analysis of Bisulphide of Carbon, by H. Macagno.—The Alkaloid from Piturie, by Prof. Liversidge.—Proceedings of Societies.—Reviews.—Correspondence.—Chemical Notices from Foreign Sources.—Notes and Queries, &c., &c.

London: Boy Court, Ludgate Hill, E.C.

On the 1st of every Month.

TRIMEN'S JOURNAL OF BOTANY,

BRITISH AND FOREIGN.

New Series. Edited by JAMES BRITTEN, F.L.S., British Museum.

CONTENTS.—Original Articles by leading Botanists.—Extracts, and Notices of Books and Memoirs.—Articles in Journals.—Botanical News.—Proceedings of Societies.

Price 1*s*. 3*d*. Subscription for One Year, payable in advance, 12*s*.

London: WEST, NEWMAN, & CO., 54, Hatton Garden, E.C.

In fcap. 8vo, price 3*s*. 6*d*.

SOUND: ELEMENTARY LESSONS ON.

By Dr. W. H. STONE, Lecturer on Physics at St. Thomas's Hospital. With numerous Illustrations.

"This is an excellent little text-book, well adapted for students of the Science and Art Classes, but also of considerable value to those who desire to do something more than cram. The student of acoustics will find it a very acceptable help, and a stepping-stone to the more elaborate works on the subject, while the musician will find in its pages information which may be of great assistance to him in the acquisition of his art."—*English Mechanic*.

MACMILLAN & CO., LONDON.

NATURE SERIES.

THE SPECTROSCOPE AND ITS APPLICATIONS. By J. N. LOCKYER, F.R.S. With Illustrations. Second Edition. Crown 8vo. 3*s*. 6*d*.

THE ORIGIN AND METAMORPHOSES OF INSECTS. By Sir JOHN LUBBOCK, M.P., F.R.S. With Illustrations. Crown 8vo. 3*s*. 6*d*. Second Edition.

THE TRANSIT OF VENUS. By G. FORBES, B.A., Professor of Natural Philosophy in the Andersonian University, Glasgow. With numerous Illustrations. Crown 8vo. 3*s*. 6*d*.

THE COMMON FROG. By St. George MIVART, F.R.S. Illustrated. Crown 8vo. 3*s*. 6*d*.

POLARISATION OF LIGHT. By W. SPOTTISWOODE, LL.D., President of the Royal Society. Illustrated. Second Edition. Crown 8vo. 3*s*. 6*d*.

ON BRITISH WILD FLOWERS CONSIDERED IN RELATION TO INSECTS. By Sir JOHN LUBBOCK, M.P., F.R.S. Illustrated Second Edition. Crown 8vo. 4*s*. 6*d*.

THE SCIENCE OF WEIGHING AND MEASURING. By H. W. CHISHOLM, Warden of the Standards. Illustrated. Crown 8vo. 4*s*. 6*d*.

HOW TO DRAW A STRAIGHT LINE; A Lecture on Linkages. By A. B. KEMPE, B.A. Illustrated. Crown 8vo. 1*s*. 6*d*.

LIGHT: A Series of Simple, Entertaining, and Useful Experiments in the Phenomena of Light for the Use of Students of every Age. By ALFRED M. MAYER and CHARLES BARNARD. With Illustrations. Crown 8vo. 2*s*. 6*d*.

SOUND: A Series of Simple, Entertaining, and Inexpensive Experiments in the Phenomena of Sound, for the Use of Students of every Age. By A. M. MAYER, Professor of Physics in the Stevens Institute of Technology, &c. With numerous Illustrations. Crown 8vo. 3*s*. 6*d*.

SEEING AND THINKING. By Prof. W. K. CLIFFORD, F.R.S. With Diagrams. Crown 8vo. 3*s*. 6*d*.

DEGENERATION: A Chapter in DARWINISM. By Prof. E. RAY LANKESTER, F.R.S. Illustrated. Crown 8vo. 2*s*. 6*d*.

(Others to follow.)

MACMILLAN & CO., LONDON.

Just ready,

VOLUME XII. (HIR—IND) of the

ENCYCLOPÆDIA BRITANNICA.

EDITED BY

PROF. THOS. SPENCER BAYNES, LL.D.

4to, Cloth, 30s.; Half Russia, 36s.

PRINCIPAL CONTENTS.

HISSAR. C. E. D. BLACK.
HISTOLOGY. Profs E. A. SCHÄFER and W. R. M'NAB.
HISTORY. J. C. MORISON.
HITTITES. Rev. T. K. CHEYNE.
HOBBES. Prof. G. CROOM ROBERTSON.
HODOGRAPH. Prof. JAMES BLYTH.
HOGARTH. AUSTIN DOBSON.
HOLBEIN. J. A. CROWE.
HOLBERG. E. W. GOSSE.
HOLLAND—
GEOGRAPHY. Prof. C. M. KAN.
HISTORY. Rev G. W. KITCHIN.
LANGUAGE. J. B. VINCKERS and Dr. J. H. GALLÉE.
LITERATURE. E. W. GOSSE.
HOMER. D. B. MONRO.
HOMESTEAD. E. P. HANNA.
HOMŒOPATHY. Dr. J. G. GLOVER.
HONDURAS. E. G. SQUIER.
HONEY. F. H. BUTLER.
HONG-KONG. A. MACDONALD.
HOOD, THOMAS. LORD HOUGHTON.
HOOKER, RICHARD. T. F. HENDERSON.
HOP. E. M. HOLMES.
HORACE. Prof. W. Y. SELLAR.
HORNBILL. Prof. ALFRED NEWTON.
HORSE—
ANATOMY. Prof. W. H. FLOWER.
HISTORY, MANAGEMENT, &c. E. D. BRICKWOOD.
RACING. E. D. BRICKWOOD, Major J. R. HUBBARD, and W. T. CHESTER.
HORTICULTURE. Dr. M. T. MASTERS and T. MOORE.
HOSEA. Prof. W. ROBERTSON SMITH.
HOSIERY. JAMES PATON.
HOSPITALS. Prof F. DE CHAUMONT.
HOTTENTOTS. JOHN NOBLE.
HOUND. E. D. BRICKWOOD.
HUGUENOTS. Rev. G. W. KITCHIN.
HUMBOLDT, A. VON. Miss A. M. CLERKE.
HUMBOLDT, W VON. Prof. A. H. SAYCE.
HUME, DAVID. Prof. R. ADAMSON.
HUMMING-BIRD. Prof. NEWTON.
HUNGARY. E. D. BUTLER.
HUNT, LEIGH. RICHARD GARNETT.
HUNTER, JOHN AND WILLIAM. F. H. BUTLER.
HUNTING. E. D. BRICKWOOD.
HUSBAND AND WIFE. Prof. EDMUND ROBERTSON.
HUSS. Rev. J. SUTHERLAND BLACK.
HUTCHESON. Prof. T. FOWLER.
HUTTON, JAMES. Prof. A. GEIKIE.
HWEN T'SANG. Col. H. YULE.
HYÆNA. JOHN GIBSON.
HYBRIDISM. G. J. ROMANES.
HYDROCEPHALUS. Dr. J. O. AFFLECK.
HYDROGEN. Prof. H. E. ARMSTRONG.
HYDROMECHANICS. Profs. A. G. GREENHILL and W. C. UNWIN.
HYDROMETER. W. GARNETT.
HYDROPATHY. Dr. W. B. HUNTER.
HYDROPHOBIA. Dr. AFFLECK.
HYDROZOA. Prof. E. RAY LANKESTER.
HYGIENE. Prof. F. DE CHAUMONT.
HYGROMETRY. ALEX. BUCHAN.
HYMENOPTERA. P. CAMERON.
HYMNS. LORD SELBORNE.
HYSTERIA. Dr. J. BATTY TUKE.
IAMBLICHUS. W. R. SORLEY.
IBN BATUTA. Col. YULE.
ICE. CARGILL G. KNOTT, D.Sc.
ICELAND. J. A. HJALTALIN and F. Y. POWELL.
ICHTHYOLOGY. Dr. A. GÜNTHER.
IDAHO. HENRY GANNETT.
ILLINOIS. J. W. SHEAHAN and J. MEDILL.
ILLUMINATION. H. B. WILSON.
ILLYRIA. W. M. RAMSAY.
IMAGE WORSHIP. Rev. J. S. BLACK.
INCENSE. Dr. GEORGE BIRDWOOD.
INDEPENDENTS. Principal A. M. FAIRBAIRN, D.D.
INDEX. H. B. WHEATLEY.
INDIA. W. W. HUNTER, LL.D.
INDIANA. A. C. HARRIS.
INDIAN ARCHIPELAGO. H. A. WEBSTER.
INDIAN OCEAN. Dr. W. B. CARPENTER, C.B.
INDIANS, AMERICAN. A. H. KEANE and H. GANNETT.
INDIAN TERRITORY. H. GANNETT.
INDIA-RUBBER. E. M. HOLMES and T. BOLAS.
INDIGO. JAMES PATON.

Edinburgh: ADAM & CHARLES BLACK.

NEW WORK BY LIONEL S. BEALE.

Now ready, pp. 230, demy 8vo, 5s.

SLIGHT AILMENTS:

THEIR NATURE AND TREATMENT.

By LIONEL S. BEALE, M.B., F.R.S., F.R.C.P.

Professor of the Principles and Practice of Medicine in King's College, London.

J. & A. CHURCHILL, New Burlington Street.

New Edition, very much enlarged, 21s.

HOW TO WORK WITH THE MICROSCOPE.

By LIONEL S. BEALE, F.R.S.,

President of the Royal Microscopical Society.

THE FIFTH EDITION,

Strongly bound and enlarged to 530 Pages, with 100 Plates, some of which are Coloured, is now ready.

HARRISON & SONS, Pall Mall.

Price £1 1s.

PHILOSOPHICAL TRANSACTIONS.

The FELLOWS of the ROYAL SOCIETY are hereby informed that the Third Part of the PHILOSOPHICAL TRANSACTIONS, Vol. for the year 1880, is now published, and ready for delivery on application at the Office of the Society in Burlington House, daily, between the hours and 4.

Burlington House. WALTER WHITE, Assistant Secretary. R.S.

Just Published, price 2s. 6d.

An ELEMENTARY COURSE of PRACTICAL PHYSICS. By A. M. WORTHINGTON, M.A., F.R.A.S. Assistant Master at Clifton College.

RIVINGTONS, Waterloo Place, Pall Mall, London.

CHEMISTRY: a TREATISE ON. By Prof. ROSCOE, F.R.S., and Prof. SCHORLEMMER, F.R.S., of Victoria University, Owens College, Manchester. With Illustrations, &c. Vols. I. and II. Inorganic Chemistry.

Vol. I. The NON-METALLIC ELEMENTS. 18s.
Vol. II. Part 1.—METALS. 18s.
Vol. II. Part 2.—METALS. 18s.
Vol. III. ORGANIC CHEMISTRY. [*In the press.*

"It would be difficult to praise this most valuable Manual too highly. . . . . The arrangement is clear and scientific; the facts gained by modern research are fairly represented and judiciously selected, and the style throughout is singularly lucid."—*Lancet.*

"A most valuable contribution to the literature of chemistry . . . . . The work when finished will afford the most complete systematic exposition of the existing state of chemical science that has yet appeared in the English language."—*Nature.*

By Prof. ROSCOE, F.R.S.

LESSONS IN ELEMENTARY CHEMISTRY; Inorganic and Organic. With numerous Illustrations. New Edition. Fcap. 8vo. 4s. 6d.

PRIMER OF CHEMISTRY. With Illustrations. 18mo. 1s.

By Prof. SCHORLEMMER, F.R.S.

THE CHEMISTRY OF THE CARBON COMPOUNDS; or, Organic Chemistry. With Illustrations. 8vo. 14s.

"Must prove eminently useful to the chemical student."—*Athenæum.*

MACMILLAN AND CO., London.

GEOLOGY AND MINERALOGY.

IN the Preface to the "Student's Elements of Geology" by Lyell he says, "As it is impossible to enable the reader to recognise rocks and minerals at sight by aid of verbal descriptions or figures, he will do well to obtain a well-arranged collection of specimens." These can be had from BRYCE WRIGHT, MINERALOGIST, 90, Great Russell Street, W.C.

50 Specimens in Cabinet	...	...	£1 0 0
100 ,, ,,	...	...	3 0 0
200 ,, ,,	...	...	5 0 0

&c., &c.

More extensive Collections from 50 to 2000 Guineas.

THURSDAY, MARCH 24, 1881

MACQUORN RANKINE'S SCIENTIFIC PAPERS

Miscellaneous Scientific Papers by W. J. Macquorn Rankine, C.E., LL.D., F.R.S., late Regius Professor of Civil Engineering and Mechanics in the University of Glasgow. From the Transactions and Proceedings of the Royal and other Scientific and Philosophical Societies and the Scientific Journals. With a Memoir of the Author by P. G. Tait, M.A., Professor of Natural Philosophy in the University of Edinburgh. Edited by W. J. Millar, C.E., Secretary to the Institute of Shipbuilders in Scotland. With Portrait, Plates, and Diagrams. (London : Charles Griffin and Co., 1881.)

THE volume before us contains thirty-seven papers of rare scientific interest written by the late Prof. Rankine, who died now eight years ago. As to the cause of this long interval the Editor gives us no hint, nor is there anything in the volume to explain it. All the papers are reprints, without note or comment, except such as is contained in the concise but extremely graceful Memoir. These papers are not by any means all Rankine's original works. They are principally those relating to Thermodynamics and Hydrodynamics. There are however two important papers on the latter subject which are not contained in the volume ("On Stream Lines," *Philosophical Magazine*, 1865; "On the Mathecal Theory of Stream Lines," *Phil. Trans.* Royal Society, 1871). These can hardly have been omitted by design, as in the very last paper contained in the volume the author resumes the subject, directing attention to his paper of 1865, while the paper of 1871 is the most general and important paper Rankine wrote on this subject, besides being his last work.

The first twenty-seven papers contain the development by Rankine of that most modern of mathematical sciences, Thermodynamics, from its foundation-stone to the complete edifice as it exists at the present day. This by no means constitutes Rankine's entire work, nor do we think it his most useful work. But it is the largest gem in the casket, and should he be forgotten in all the rest this alone will secure for him a foremost place amongst those who have left their mark on philosophy.

The rapidity of the development of this branch of science is unrivalled. As profound as anything ever brought to light by the power of reason, it only occupied Rankine four years from the publication of his first paper until the theory was completed and applied to all cases. That the burning of coal was necessary to the production of steam, which was necessary for the working of an engine, and that the proportion of coal burnt bore some relation to the work done, were facts which for 200 years had been forcing themselves into notice, and gradually there had come to be an idea that in some way heat was the same thing as other forms of mechanical energy. But this was all, till, in 1843, Dr. Joule published his first experimental determination of the mechanical equivalent of heat. Published in an obscure way, it was some years before this novel but definite relation between heat and energy excited notice. The first published notice is by Thomson in 1849, although that Rankine had known it for some time previously is shown by the first of these papers, published in July of that year. In December of the same year Rankine sent in the Papers III. and XIV.,[1] containing the elements and some applications of his theory, and in 1854 he had published the complete theory and its applications to various engines, making instant use of the splendid experimental results just then obtained by Regnault. From this time it has been as possible definitely to forecast the result to be expected from any kind of engine as from 1690 to predict the behaviour of the moon.

From a philosophical point of view, there was a keen race in discovery between Thomson, Rankine, and Clausius, a race in which Thomson had the start, but which was neck and neck between Rankine and Clausius. But from the practical point of view Rankine was alone. And in this respect these papers, as indeed all his others, have a value both intrinsic and as examples of method which even transcends their philosophical value.

It was Rankine's practical knowledge which gave him his great advantage, but he had in some respects an advantage in having based his theory by means of an hypothesis on the fundamental laws of motion. Rankine worked from an hypothesis of his own creation as to the molecular constitution of matter, which was perfectly definite and capable of including all the phenomena which he had to consider. The definiteness of his hypotheses gave that definite form to his formula which suggested many points otherwise overlooked.

But as often happens, the definiteness of his hypotheses was also his source of weakness ; he assumed the atoms of matter to be masses of fluid subject to eddies and vibrations, but otherwise at rest. This suited the conditions of his problem, but it was only an hypothesis, and as it was definite, so any phenomenon with which it was incompatible sufficed to disprove the hypothesis and bring down the edifice raised upon it. And such phenomena, those of diffusion, existed ; although they did not come within the range of his work.

Rankine was himself fully alive to his position, and having once obtained his ideas and framed his formulæ, took and acknowledged a hint from his contemporaries, Thomson and Clausius ; and having shown that Carnot's theorem, which they had modified and made the basis of their reasoning, was a consequence of his molecular vortices, he adopted a general law as the base of his reasoning, and cut himself off from his hypotheses. This was easy for him to do, for, as may be seen in § 15*a* of Paper III., he had with no small care framed his hypotheses so as to fit the same law, though expressed in other words. This article is also interesting as showing the unlimited faith he must have reposed in the design and care of Providence. Not only does he conceive each atom of matter to possess a fluid atmosphere, in which exist a number of similar cyclones or eddies, symmetrically placed all over the atom, but he required that wherever two atoms touched there two eddies should face, and so exactly as to be coaxial. Many complicated properties were attributed by Newton and others to the corpuscles of light, but such a demand as is here implied on the attention of Providence has probably never been equalled

[1] Why this paper is placed so far out of its chronological order does not appear.

—a whole crew of Maxwell's demons on each atom would be required to warp and moor for every movement that might occur. But so true was Rankine's knowledge of mechanics that all this elaborate refinement did not prevent his hypothesis leading him to correct results.

This refined organisation, however, which renders his hypothesis in the highest degree improbable, suggests a most important consideration. For the almost infinite complexity of his particular arrangement indicates almost to the extent of a proof that the results he obtained must depend upon circumstances so general as to be independent of any particular hypothesis, so long as it is in conformity with the laws of motion, and hence the trail of these general circumstances is crossed.

In Rankine's hypothesis the temperature comes out as a direct measure in any particular substance of the kinetic or actual energy of the molecular motion. This conclusion, to which he adhered in the final foundation of his theory, is general, but it does not appear to be the most general conclusion of which our present experiments admit. It led Rankine to give a definite form as well as name to his thermodynamic function, which forms the fundamental equation of all the mathematical work. But it was subsequently shown that the differential equation to the same lines could be obtained without the assumption with regard to temperature, and then it did not appear that there was sufficient experimental data for the complete determination of the constants which enter into the integral. This is owing to the hitherto impossibility of determining the exact form of the adiabatic curve for solids and liquids. With gases it is different, and with these Rankine's law is found to fit, but so might a law framed on the supposition that in other cases the kinetic energy was some other function of the temperature. What is proved therefore is not that the temperature is a direct measure of the kinetic energy, but that this is some function of the temperature. This is apparently all that has yet been accomplished, so that Rankine's definite conclusion must be looked upon as suggested rather than proved by experiment. There can be no doubt however that this definiteness led to a vast development of the subject, and hence it was no mere fancy or partiality for his own view which led him to adhere to that form of second law which included his earlier view. Nor will the study of Rankine's earlier papers be time wasted on the part of those who seek to understand this extremely difficult subject. They will there find a model of the machinery by which the general result might be obtained, and if, as is the case with most new inventions, the machinery is unnecessarily complex, it is still the only machine which has accomplished the results.

They will also find, what must for ever add an interest to these papers, the first use of the terms thermodynamic function, adiabatic curve, potential energy, and others now in general use; for Rankine's nomenclature, to a great extent his notation, and entirely his graphic method, have been universally adopted.

Rankine's methods have been called "uncouth," "diffuse and obscure," and without doubt they must seem all this to those who come to the subject with all the latest inventions in the form of mathematical machine tools in perfect working order,—just as the axe or adze must seem barbarous when there is a planing machine at hand to do the work, and the material has been prepare for it. But let the shape required be of a novel kind, let the material be in the rough, and then how does fare with the planing machine?

Like that of Green, the whole career of Rankine is a rebuke to those who would exhaust the finest material this earth—the best brain of our youth—converting into elaborate mechanism only adapted to reduce, however elegant a manner, already prepared billets elegant and improved copies of masterpieces which having once been shaped, although roughly with prim tools, can never have to be shaped again. The mate at last existed for a great mathematical edifice, of wh the want had long been felt, and our great mathema workshop was crowded with the most refined mecha rusting for want of material to work upon. Bu material was in the rough, and while waiting for so one to strip off the bark the chance was lost, fo obscure, self-taught mechanic who set to work wit and adze did not stop at the bark, but with rapid and w directed strokes brought out the form divine. How uncouth Rankine's methods may be, they have the g merit that they require nothing but a bold fron result being obtained without adventitious aid. T are inscrutable to those who, having learnt the rela between quantities as expressed by symbols, have gotten if they ever knew the purpose of their for But to the reader who thinks Rankine's methods a statement of his thoughts, and though often a ha task, any one who succeeds in understanding Ran finds to his satisfaction that he has done more than that he understands what Rankine understood.

Nor is this true only of his great work. What see to us his most useful work is that of showing h the elementary mathematical methods were sufficie adaptable to be applied to almost all cases of practi mechanics. The results are only approximate; but when neither the data nor the desired result can be exa measured, this is all that could be obtained, were methods never so exact. One might as well set bra by Sir Joseph Whitworth's millionth-of-an-inch machi as use the exact equation of thermodynamics to det mine the probable work to be obtained from a steam engine.

The graphic method was Rankine's great weapo This, which is probably as old as any mathemati method, had been long neglected, except that it w sometimes used for engineering purposes. Rankine ear perceived its applicability to the subjects he had to teach and in his treatises on Applied Mechanics, Shipbuildin and the Steam-Engine there are many instances of novel and useful application which have been copied in and wide, while his graphic treatment of the subject thermodynamics has been universally adopted. But the height of his achievement in the application and develop ment of the graphic method is only reached in his papers on the motion of fluids.

These papers, with the omission already noticed, are collected at the end of the volume, and they constitute by no means its least valuable part. They are *comparatively* his later work. The first, "On the Exact Form of Waves at the Surface of Deep Water," was published in 186 after his thermodynamical work was essentially complete

Both the method and matter of this paper are unique. e results are obtained by a simple geometrical study rolling circles. And there for the first time definite soning is adapted to the actual proportions of deep- waves, all previous work on the subject having been sed on the assumption that the height of the wave is all compared with its length.

It is however in the next paper that he first shows what ıy be done by Maxwell's method of the graphic use of nilies of surfaces or curves. Here we have what is visible in the fluid itself and had only been expressed complex algebraical formulæ—the internal motion of e fluid—shown in such a way that not only the direction ıt the magnitude of the motion at every point may be ken in at a glance as well as definitely measured, and l deduced by simple but rigorous geometrical methods. he credit of this, which is certainly one of the highest hievements in the art of expression, must be divided. was Faraday who first conceived the force of a magnet pressed by a family of lines; and it was Maxwell who iscovered the rigorous method of drawing Faraday's nes; while Rankine realised in this the means of apply- ıg and expressing the principles of the steady flow of ıids propounded by Stokes now forty years ago.

In these papers on Hydrodynamics, as in all his other ork, Rankine had a practical purpose in view. In this ıse it was the skin resistance and wave resistance of ıips. And if, owing to the neglect of friction in the ındamental equations of motion, some of the results are ill doubtful, yet in this respect the work is on a par ith all the rest that has been done on this subject. And ıese papers, owing to the clear conception they convey f the internal motions of fluid and the direct purpose of ıe means adopted to elucidate these, afford by far the est chance for any one wishing to pursue the subject up) the highest position it has at present attained.

That Rankine himself owed much to having early irected his thoughts to fluid motion appears in all his work, s well as being shown by his theory of molecular vortices —a strictly hydrodynamical conception—amongst the in- ricacies of which nothing but his exact knowledge of the ubject could have kept him straight.

It must be remembered however by those who would nake a like use of such knowledge that Rankine did not egin his career by the study of mathematics; but that ıs an engineer from his birth, as we are told in the Memoir, he first became aware of the circumstances and problems of mechanics, and only evolved or acquired his mathematics as he found them necessary to his work. In this way his knowledge of mathematics must have included the knowledge of the necessity for each step. It was necessity first, and then method or invention; and not, as is too often the case with those who begin to learn mathematics before they are aware of what it is they are to do, all means and no ends.

In Rankine's text-books, as in his original papers, the ends are always kept in view. It is often impossible for others to follow him unless they begin by actually mastering the circumstances of the problem and trying to solve it for themselves, then if they honestly fail they will find that Rankine will help them; while if they succeed they will find that Rankine was before them. These books, both as regards originality of matter and the attention paid to the circumstances of each problem, have more the character of original papers than orthodox text-books. From this as well as his other writings it is clear that he acquired his knowledge of mathematics from the original works of the master, and not from text-books.

His example should therefore be the best recommendation for all those who would really understand mechanics to read the works direct from the hand of this master—a task which, with the aid of this volume, they may now accomplish without that trouble of search which, small as it is, leaves many a masterpiece on the shelf in some dark corner, while a mutilated and garbled extract disgusts the reader and discredits the thinker.

OSBORNE REYNOLDS

THE FERNS OF NORTH AMERICA

The Ferns of North America; Coloured Figures and Descriptions, with Synonymy and Geographical Distribution, of the Ferns of the United States of North America and British North American Possessions. By D. C. Eaton, Professor of Botany in Yale College. The Drawings by J. H. Emerton and C. E. Faxon. 2 Vols. quarto, pp. 352 and 285; 81 Plates. (Boston: S. E. Cassino, 1880.)

THIS handsome work, which has been brought out in parts, issued about one every two months, beginning with 1878, is now completed. Although ferns have long been popular in the United States, both with collectors and cultivators, this is the first large illustrated monograph of the indigenous species which has been attempted. For our own country we have several, of which the best known are Hooker's "British Ferns," with coloured figures, in large octavo; Lindley and Moore's "Nature Printed Ferns," in more than one edition; and Newman's "British Ferns," in which the plates are uncoloured woodcuts; but of the American ferns there are but few figures, and those widely scattered in general works, and even leaving figures out of the question there has been no descriptive handbook specially devoted to them, so that those who wanted to work at the subject have been placed at a great disadvantage. Prof. Eaton, who is the grandson of a well-known botanical author, has been universally recognised for the last twenty years as the leading authority on the subject. He has a large library and general collection of his own, has visited Europe and studied the American ferns in the public herbaria of the Old World, has proved himself in other departments of botany to be a careful and judicious systematist, and he is a teacher of botany of many years' experience, and has been looked up to for a long time by all the collectors of ferns throughout the Union as their referee in cases of doubt and difficulty; so that he has had every advantage for dealing with his subject in a thorough and exhaustive manner, and as he has been ably seconded by his two artists, the result is a monograph which is thoroughly satisfactory in every way, and which will be universally accepted both at home and in Europe as a standard work.

The geographical area which it covers is the whole of the American continent, from the Pole to the southern boundary of the United States. The true ferns only are included, not the Lycopodiaceæ, Equisetaceæ, and Rhizocarps, which are monographed along with the ferns by

Hooker, Milde, and in the earlier editions of Newman. In North America the order is represented by 139 species and 31 genera. The number of species is quite double what we have in the whole of Europe. The northern area outside the United States produces very few species that have not been found within the bounds of the Union. As in Europe there are no Cyatheaceæ, Marattiaceæ, nor Gleicheniaceæ. Of the other sub-orders the Schizœaceæ, which we do not possess, are represented in the United States by three genera and four species. Ceratopteris, of which Prof. Eaton makes a special sub-order, is also American, but not European. The other four sub-orders—Polypodiaceæ, Hymenophyllaceæ, Osmundaceæ, and Ophioglossaceæ—are represented, both in America and Europe. One peculiarity of ferns is that the genera show exceedingly little tendency to geographical localisation. The nearest approach to this that we have in North America is the predominance of Pellæa, Cheilanthes, and Nothochlæna, which are allied dwarf types with a greater power of resisting drought than any other set of ferns, and which are represented in this area by a large proportionate number of endemic species. These three genera take up thirty-nine species in North America against four for Europe. Out of the 139 species about forty are endemic, and about forty are European, the latter including several of our high mountain types, such as *Cystopteris montana*, *Aspidium Lonchitis*, *Polypodium alpestre*, *Woodsia ilvensis*, *glabella*, and *hyperborea*. The southern boundary of the States corresponds broadly with the limit in a northern direction of the great tropical flora of Equatorial America, the richest tropical flora in the world. But out of the 139 ferns at least twenty are characteristically widely-spread tropical species which do not extend beyond Florida, which have several of them only been discovered there within the last few years. Such are *Ophioglossum palmatum*, *Acrostichum aureum*, *Polypodium aureum*, *P. Phyllitidis*, *P. Plumula*, and *P. pectinatum*, *Vittaria lineata*, and *Nephrolepis exaltata*. Amongst the remaining species there are some curious cases of a *rôle* of distribution it is difficult to explain or understand. *Adiantum pedatum* and *Osmunda cinnamomea* are examples in ferns of a considerable group of American plants which reach Asia by way of Japan and run down through China to the Eastern and Central Himalayas; *Pteris serrulata*, found lately in America in Alabama, and South Carolina, reappears only in China; *Pellæa andromedæfolia*, which from California passes down the Andes to Chili, reappears in Cape Colony. *Nothochlæna tenera* is supposed to be divided between Southern Utah and the Andes of Bolivia and Chili, but here I think that the States plant will most likely have to rank as a distinct species. *Aspidium mohrioides*, long supposed to be endemic in extra-tropical South America, has been discovered lately by Mr. Moseley in Marion Island, and by Mr. Lemmon in one place at an elevation of 8000 feet above sea-level amongst the mountains of California.

As regards the limitation of genera and species Prof. Eaton differs but little from Sir William Hooker, as the English author's views are expounded in his great monograph of the ferns of the whole world, his "Species Filicum." Prof. Eaton treats Hymenophyllaceæ and Ceratopteridæ as distinct sub-orders; the former at any rate a decided improvement upon Sir W. Hooker's cla... sification, and he maintains Ophioglossaceæ as a distin... order. In genera the principal deviations are that ... keeps up Phegopteris as distinct from Polypodium, ... merges Nephrodium in Aspidium.

A very curious North American fern is *Asplen... ebenoides* of Scott. It is very rare, and always grow... company with the walking leaf (*Camptosorus rhi... phyllus*) and *Asplenium ebeneum*, two common Ameri... species. These are very dissimilar plants, but ... *ebenoides* is quite intermediate between them. Pr... Eaton seems not disinclined to the idea that it may ... produced by natural hybridisation, as was suggested ... the Rev. M. J. Berkeley in the *Journal* of the Roy... Horticultural Society for 1866, p. 87.

An observation of Prof. Eaton's under *Nothochl... Fenaleri* is interesting as bearing upon Milde's cla... fication of ferns into a catadromous and anadrom... series, according as to whether their lowest second... branches originate on the posterior or anterior si... the pinnæ. Prof. Eaton notes that in this species ... is always a decided inequality in their origin; but ... it is sometimes on the anadromous, and at others on ... catadromous plan.

J. G. Baker

KÖLLIKER ON ANIMAL DEVELOPMENT

Grundriss der Entwickelungsgeschichte des Menschen ... der höheren Thiere. Von Albert Kölliker, Professor ... Anatomie an der Universität Würzburg. (Leipzig: ... Engelmann, 1880.)

THIS book is essentially a reproduction of ... Kölliker's large treatise on Embryology, with a ... part of the detail and controversial matter omitted, ... intended for the use of medical students. The ... work has more the character of a monograph on ... development of birds and mammals than of a text-... and as such, though of very great value to those engag... in teaching and research, is necessarily too bulky ... use of ordinary students. We think, therefore, that ... Kölliker has done very wisely in publishing the ... before us; and we need hardly say that, his larger ... having been already universally recognised as one of ... most important contributions to embryology during ... years, the present work may safely be regarded as ... accurate statement of the facts of avian and mammal... embryology. We may add that no trouble has ... spared in the illustrations, which fully come up to ... high standard characteristic of German works of ... class.

While, however, we can say this much in praise ... Prof. Kölliker's treatise, we cannot help recognising ... it has some rather serious defects. Prof. Kölliker is ... extremely objective writer. He describes with great ... clearness the objects as they present themselves to ... observer, but he scarcely ever attempts to connect ... together or to point out the general principles which ... underlie the mass of detail with which he has to deal. ... In his larger work this peculiarity is of comparatively ... small importance, in that those who are likely to use ... are able to supply the general principles for themselves, ... and the work has already become a great mine of fact ... to which every anatomist who is engaged in studying the ... morphology of vertebrates will necessarily turn.

In a book however intended for medical students, it is, in our opinion at least, of the utmost importance that the facts of embryology should not merely be stated in succession, but that their significance should be pointed out. Embryology is of but little practical value to a medical student, and the small amount he must necessarily know could be given in a very few pages, and is, we believe, usually to be found in works on human anatomy. Considered however as an educational instrument, embryology is of the utmost value. It gives to the student an insight into the meaning of the structures which he meets with in his dissections, and by so doing often renders details of anatomical structure comparatively easy and pleasant of acquisition, which would otherwise be a great and almost repulsive strain on the memory.

Embryology should be taught to the medical student as a comparative science; with the facts duly marshalled, their significance pointed out, and general principles deduced from them. In such a form it ought to constitute an important part of medical training, which every medical school of any pretence to excellence should impart to its students.

We would venture to call attention to the following instances as illustrative of what we consider the unsatisfactory treatment of certain parts of the subject to be found in Prof. Kölliker's work. In dealing with the phenomena of segmentation Prof. Kölliker makes no effort to point out that the differences in the early development of the mammal and bird are in the main the result of the presence of food yolk in the one case and its absence in the other. After reading his very careful and elaborate treatment of the primitive streak, the student would, we think, be left in complete ignorance of the real significance of this interesting structure.

Again, in his account of the placenta, which he describes in man and the rabbit, he has so little to say as to any comparison between the two that we are at a complete loss to understand why he should have made any mention of the former.

In his account of the development of the vascular and excretory systems we are struck with the almost entire lack of any attempt to put the facts which have been so admirably described to their legitimate use, viz. to the explanation of the arrangement of these and other structures in the human body, and of the presence of rudimentary organs.

In making these strictures on Prof. Kölliker's work we should be sorry to convey the impression that we underestimate the value of this in most respects admirable treatise. It has already become justly popular in Germany, and we trust that it will also become widely known in this country.

OUR BOOK SHELF

Bulletin of the United States Geological and Geographical Survey of the Territories, 1879-80. Vol. v. (Washington, 1880.)

THE publications issued by the American Government under the above title are so appreciated in this country that it seems unnecessary to compliment Dr. Hayden and his coadjutors on the appearance of another of their useful volumes. During the last few years, however, there have been brought out by the U.S. Department of the [illegible] some works by Dr. Elliot Coues, which for patient industry must compare with any that have ever been compiled in scientific literature. The title of the volume now before us reads as follows:—Art. 26. Third Instalment of American Ornithological Bibliography, by Dr. Elliot Coues, U.S.A., and consists of 545 octavo pages of small print. How many titles of papers and books are quoted in this laborious treatise we should be sorry to have to count. The labour must have been enormous, and it is only those who have to follow the intricate windings of synonymic literature who can appreciate the work here performed by Dr. Coues. We learn that we may expect at some future time a similar conspectus of titles relating to the ornithology of the Old World, but although the present volume professedly deals with American Birds only, many standard works of general interest are passed in review by the author, who exhibits great judgment as a critic. Taking Gray's "Hand-List of Birds" as a basis of classification to follow, Dr. Coues treats of each family separately, and then in chronological order he records every work, every paper, and every note which directly or indirectly affects the American species, and as regards each year the publications are separately entered under the authors' names in alphabetical order. We must however again warn ornithologists that so many collateral references are given to Old World papers where the families are at all cosmopolitan, that therefore no one writing on any group of birds can afford to neglect this book. As for Dr. Coues himself, we can only imagine the sigh of relief with which he must have corrected the last proof of such a toilsome undertaking, although he must have been assured beforehand of the heartfelt gratitude of every ornithological *confrère* throughout the globe. R. B. S.

(i.) *Exposition Géométrique des Propriétes générales des Courbes.* Par Charles Ruchonnet (de Lausanne). Quatrième édition augmentée. (Paris, 1880.)

(ii.) *Éléments de Calcul approximatif.* Par C. Ruchonnet (de Lausanne). Troisième édition revue. (Paris, 1880.)

HAVING noticed both these works on the appearance of the last previous editions in 1874, we need say little here. The reasoning in i., we may remark, is always upon the curve itself, and is not derived by taking the limiting form of the inscribed polygon; and similarly in the case of surfaces. The work has grown from 160 pp. to 174 pp., and there is one more plate of figures.

The pamphlet ii. is, what it is stated to be, a revised form of the last edition. It consists of 64 pp. in place of 65 pp.

Geschichte der geographischen Entdeckungsreisen im Alterthum und Mittelalter. Von J. Löwenberg. (Leipzig und Berlin: Otto Spamer, 1881.)

THIS is a volume in the publisher's Illustrated Library of Geography and Ethnology. It is, as its title indicates, a History of Geographical Discovery in Antiquity and during the Middle Ages. The story is brought down to the time of Magellan and Martin Behaim. The first book, under the heading of Night and Morning, treats of the earliest dawn of geographical knowledge with the Hebrews, Egyptians, Babylonians, Phœnicians, Greeks, and Romans; the second book embraces the period from Herodotus to Ptolemy; the third, the Middle Ages; and the fourth the Century of Discovery, in which Spain and Portugal did such splendid work. Herr Löwenberg has evidently taken great pains to master his subject, and has been quite successful. He treats it in considerable detail, both in its historical and scientific aspects; the arrangement is excellent, and while popular and attractive in style, the work seems to us to be accurate and altogether trustworthy. There are numerous illustrations, some of them rather fanciful, but most of them useful and appropriate—portraits, ships of various periods, maps, some of them reproductions of very early ones, and

places and monuments illustrative of various countries. Altogether the work is a really good specimen of its kind. Another volume will bring the story down to the present time.

LETTERS TO THE EDITOR

[*The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts. No notice is taken of anonymous communications.*

The Editor urgently requests correspondents to keep their letters as short as possible. The pressure on his space is so great that it is impossible otherwise to ensure the appearance even of communications containing interesting and novel facts.]

The Tide Predicter

I SEE in your last number (p. 467), among the editorial notes, the following:—"Mr. Roberts of the *Nautical Almanac* office is authorised, by resolution of Council of the Secretary of State for India, dated August 7, 1880, to make it generally known that his Tide Predicter may be employed for the preparation of Tide Tables for any port for which the requisite data are forthcoming."

I think it right to call your attention to the fact that the Tide Predicter is in no sense of Mr. Roberts's invention or design. He was employed in 1873 by me, as chairman of the British Association Tidal Committee, to calculate the number of teeth in the wheels of the first Tide Predicter (now the property of the British Association, permanently deposited in South Kensington Museum), and to superintend its construction in London by Messrs. A. Légé and Co. The second Tide Predicter was made for the India Office, according to my advice, by Messrs. A. Légé and Co. of London, under the superintendence of Mr. Roberts. In respect to the plan of the wheelwork, which is wholly due to Messrs. Légé, it is a copy of the first instrument. It is an improvement on the first instrument in having twenty tidal components instead of ten, and in having the well-known rigorous method of the slide (Thomson and Tait's "Natural Philosophy," § 55, or "Elements of Natural Philosophy," § 72) for producing simple harmonic motion in a straight line from circular motion, instead of the approximate method of pulleys centred on crank-pins, which for simplicity and economy I used in the first instrument.

WILLIAM THOMSON

The University, Glasgow, March 19

The Magnetic Storm of 1880, August

THE Astronomer-Royal has handed to me a copy of the photographic record of the variations of magnetic horizontal force as registered at Toronto during the disturbed period of August 11 to 14 last. The records of declination and vertical force were imperfect and have not been received.

The comparison of the Greenwich and Zi-ka-wei (China) curves for the same period (NATURE, vol. xxiii. p. 33) indicated that the commencement and end of disturbance (especially the commencement) occurred nearly simultaneously at both places, and this circumstance is now further corroborated by the Toronto horizontal force curve.

In what follows, the reference throughout is to Greenwich time.

The disturbance at Toronto commenced on August 11 at 10.20 a.m. At Greenwich (NATURE, vol. xxiii. p. 33) it commenced also at 10.20 a.m., and at Zi-ka-wei at 10.16 a.m.; at Melbourne (NATURE, vol. xxii. p. 558) it commenced at 10.33 a.m.

Disturbance ceases at Toronto at about midnight of August 11, and at Greenwich and Zi-ka-wei also at about or near midnight, but it dies out more or less gradually, not allowing the limit of disturbance to be always very precisely fixed.

Sudden motion is again shown (after some hours of quiet) at Toronto on August 12 at 11.40 a.m.; also at Greenwich at 11.40 a.m.; some minutes sooner at Zi-ka-wei; and at Melbourne at about 11.38 a.m.

Disturbance again dies out more or less gradually at Toronto on August 14 about 7 a.m.; at Greenwich and Zi-ka-wei at about 6 a.m.; and at Melbourne at about 7 a.m.

The commencement of disturbance in the above instances is definite, and the agreement in time, considering the widely-separated geographical position of the four places concerned, is noteworthy. The cessation of disturbance is less definite, as i been already remarked, but even here the discordance in time not very wide.

WILLIAM ELLIS

Royal Observatory, Greenwich, March 12

Prehistoric Europe

I MUST adhere to my decision not to play the part of Secu any further to a glacial Retiarius in the arena of NATURE. If net be strong enough to carry the Upper Pleiocene and the Plei cene mammalia of Europe, as well as Palæolithic man and Neolithic skull of Olmo, I wish him joy of them. If, fortu he will kindly give me the proof that the mammalia of Anver considered Upper Pleiocene by Falconer, Gaudry, Gervais, other leading palæontologists, are, as he terms them, "i up," they shall be properly served and *iced*, if necessary, in second edition.

I feel however that it is only right for me to notice the gladiator who springs to the aid of his friend. The antiquity man in the Victoria Cave is solely due, as it appears to me the *perfervidum ingenium* (I speak in all respect) of Tiddeman. It was first based on a fragment of fibula wh ultimately turned out to belong to a bear. Then it was shown the cuts on two small bones, which were exhibited and discu at the British Association, at the Anthropological Institute a at the Geological Society of London. The bones are rec and belong to sheep or goat, two domestic animals introduc into Britain in the Neolithic age. The cuts have been pro made by a metallic edge. Numerous bones of the same ani in the same condition and hacked in the same way, occurred in Romano-British refuse-heap on the top of the clay, and quently slipped down over the working face to the bottom the cutting before I resigned the charge of the explorati Mr. Tiddeman after nearly four years' work. There were frequ slips afterwards. Under these circumstances the reader decide whether it is more probable that the mutton-bone question did slip down from a higher level to be picked up the bottom, or that there is evidence of "interglacial Geikie) or "preglacial" (Tiddeman) man possessed of domes animals and probably using edged tools of metal. The mu bones seem to me to prove so much on the latter hypothes that they may be thrown aside without further thought.

The reindeer (bones of feet) was found in 1872 along with rhinoceros, elephant, hyæna, and bison in the cave at the ol horizon, which afterwards was proved to contain the hippop mus. It was omitted in Mr. Tiddeman's lists up to 1876, wh I called his attention to the fact. Then he wrote that the that it was so found was "noteworthy," and that "these remai [his generalisations] were made solely on the evidence wh passed through your present reporter's hands since he under to conduct the exploration of the cavern" (Brit. Ass. Rep., 18 p. 118). Surely it is too late, in his letter to NATURE (March 1881), to recall this on the grounds that these remains discovered in a shaft, that my exploration was not carried so accurately as his own, and further, that because he did find the reindeer in the lower strata that I did not. It is not me to compare my own experience in cave-hunting with h to point out the value of negative evidence. The explorat while under my charge was *not* carried on by shafts only. W the hyæna-layer was reached it was followed in the deep cut visited by the British Association in 1873. The presence reindeer in the hyæna-layer renders Mr. Tiddeman's views tenable which are based on its assumed absence. Most of the points have been so fully argued out before the above-mentio societies, that I am sorry to be obliged to repeat them in letter.

W. BOYD DAWKINS

Owens College, March 11

Oceanic Phenomenon

H.M.'s surveying ship *Alert* was recently engaged in search for a "shoal" which was reported as existing some 200 miles the southward of Tongatabu, in the South Pacific. In the cour of the survey—which I may add tended to disprove the existe of any such shoal—it was observed that for several days the s surface exhibited large discoloured patches, due to the presen of a fluffy substance of a colour, and resembling consistency the vegetable only seen on the stagnan wat[illegible] the surface in irregul [illegible] and al[illegible] particles impregnat

ıe sea-water to a depth of several feet. Samples for examina-on were obtained by "dipping" with a bucket, as well as by ıe tow-net. It seemed to be a Confervoid Alga.

On slightly agitating the water in a glass jar, the fluffy masses roke up into minute particles, which, under a magnifying power f sixty diameters, were found to be composed of spindle-shaped undles of filaments. Under a power of 500 diameters these laments were seen to be straight or slightly-curved rods, articu-ated but not branching, and divided by transverse septa into ylindrical cells, which contained irregularly-shaped masses of ranular matter. These rods, which seemed to represent the ıdult plant, measured $\frac{1}{1000}$ inch in width. On carefully examin-ng many samples, some filaments were detected, portions of which seemed to have undergone a sort of varicose enlargement, eing more than twice as wide as the normal filaments. These propagating filaments (if I am right in so calling them) were nvested by a delicate tubular membrane, and contained some ranular semi-transparent matter, in which was imbedded a row of liscoid bodies; the latter appearing as if about to be discharged from the ruptured extremity of the tube. These bodies measured $\frac{1}{1000}$th of an inch in diameter: when seen edgewise presented a



lozenge-shaped appearance, and were devoid of cilia or striæ. Conjugation was not observed.

On allowing a jarful of the sea-water to stand by for twenty-four hours it was found that the confervoid matter had all risen to the surface, forming a thick scum of a dull green colour, while the water had assumed a pale purple colour, resembling the tint exhibited in a weak solution of permanganate of potash.

From November 24 to 29, during which time the ship traversed slowly a distance of 330 miles, the sea contained these organisms. For the first three days the large patches were frequently in sight, and during the rest of the time the surrounding water presented a dusty appearance from the presence of the tiny spindle-shaped bundles. On the evening of the 26th an unusually dense patch was sighted and mistaken for a reef, being reported as such by the look-out-man aloft.

Sydney, January 24 R. W. COPPINGER

Feeding a Gull with Corn

IN Prof. Semper's recently-published work on the "Conditions of Existence as they Affect Animal Life," a review of which from the pen of Prof. Lankester appeared in your columns a fortnight ago (vol. xxiii. p. 405), allusion is made on pp. 67, 68, and elsewhere to John Hunter's celebrated experiment of feeding a gull with corn. Prof. Semper, however, seems not to have been aware of the precise nature of the result of Hunter's experiment. He says: "The English anatomist Hunter purposely fed a sea-gull for a whole year on grain, and he thus succeeded in so completely hardening the inner coat of the bird's stomach, which is naturally soft and adapted to a fish diet, that in appearance and structure it precisely resembled the hard, horny skin of the gizzard of a pigeon."

The original account, I believe, of Hunter's experiment, was published in Sir Everard Home's "Lectures on Comparative Anatomy" (vol. i. p. 271, 1814), and an extract from that work is appended to the description of Hunter's original preparation, still preserved in the College of Surgeons, in the descriptive catalogue of that collection (vol. v., 1833, pp. 149-50, Prep. 523). What Hunter succeeded in effecting was to very much increase the thickness of the *muscular* walls of the gizzard, which, as may be seen by comparing his specimen (No. 523) with that of the stomach of another gull close by, have become developed to an extent about double their usual size. There is no manifest increase in the thickness of the "inner"—or so-called "epithelial"—coat of the stomach visible in the preparation, nor do Home or Owen allude to any such feature in their descriptions. Hunter's experiment, therefore, simply comes under the numerous well-ascertained instances of the increased development, consequent on increased use, of muscle, and has no real connection with the "modifying effects of food," such as that produced in canaries by feeding them on cayenne pepper, and others cited by Semper. W. A. FORBES

Zoological Society's Gardens, N.W., March 18

Dynamics of "Radiant Matter"

As the chief object of Mr. Preston's paper under the above title in NATURE, vol. xxiii. p. 461, seems to be to support Le Sage's "shelter theory" for gravity, you will perhaps let me point out one objection to that theory in any form which has hitherto been deemed conclusive, and with which Mr. Preston does not deal. It is that under it gravity would not vary, as it is known to do, equally with mass, but would vary *not* equally.

The theory applies perhaps so long as you consider only the case of isolated atoms, but it fails entirely when applied to clusters of atoms.

Observation shows that gravity varies only with distance and with mass; but if it were caused by any form of shelter hitherto imagined, it would vary also with density and with bulk in such a way that a pound of, say water, would weigh more than a pound if raised into steam, because its atoms, in loose order as steam, would give each other less shelter from the action of the kinetic æther than when in close order as water, and in such a way also that two spheres of, say iron, each weighing one pound, would weigh less than two pounds if welded into one sphere, because some atoms in the one sphere would be better sheltered than any atoms in the two spheres. WM. MUIR

March 21

The Oldest Fossil Insects

MR. S. H. SCUDDER has published (Anniversary *Memoirs* of the Boston Society of Natural History, 1880, pp. 41, plate 1) a memoir on the Devonian Insects of New Brunswick. The fragments of the six described species were discovered by the late Prof. C. F. Hartt in 1862, and have been since 1865 described in several papers by the same author. The new paper is a very detailed and elaborate one, with entirely new and improved figures, and is followed by a number of conclusions, as the final result of his work (Report, *Amer. Journ. of Sci.*, Feb. 1881). The conclusions would be of prominent importance for the history of the evolution of insects, if they could be accepted without reserve. Of course facts and conclusions should be able to stand the most severe test; and that is not the case with this publication. "As the simpler Devonian insects have certain special relations," he says, "with the Ephemeridæ, their description is preceded by an account of the wing-structure of the modern Mayflies as a basis of comparison" (p. 4).

The simple fact that not one of the described species has any relationship to the Ephemeridæ is sufficient to cause us to object to his descriptions and conclusions related to this family. This statement is not based upon a difference of opinion, but simply on the evidence of facts which cannot be denied by any one conversant with the families Ephemeridæ and Odonata.

Platephemera antiqua is a part of the apical half of the wing, without the tip, of a gigantic dragonfly. The suddenly narrowed second cubital space is to be found in Isophlebia of the Solenhofen slate. The imperfectness of the fragment allows no further conclusions.

Gerephemera simplex is a diagonal fragment of the middle of

a wing of a gigantic dragonfly. The reverse has a small part of the base, not to be seen in the obverse, with a straight sector crossing the horizontal ones. The same arrangement is to be seen in Isophlebia. Every other character important for nearer determination is wanting in the fragment.

Lithentomum Hartii.—The fragment is very insufficient, and recalls the venation of the Sialids, and among them those of the Chauliodes type.

Homothetus fossilis.—This is a Sialid of the Corydalis type, with a small number of transversals. The basal vein, spoken of as homologous with the arculus of the Odonata, and as proving a synthetic type, is the part in which the wing breaks off easily in actually living species. I have not seen the type.

Xenoneura antiquorum.—Some details given for this species are not exact. It has not been observed that parts of one wing cover the other; I can only say that the wing belongs to the Neuroptera, and that the venation is nearer to the Chauliodes type than to any other. The famous "stridulation" apparatus at the base is justly retracted by the author.

Four new families are proposed for these insects by the author. One of them, the Atoxina, is now out of the question, as Gerephemera belongs to the Odonata. The three others are only indicated by extremely vague characters, in fact by no characters at all. Can science accept such families? I believe not.

I omit *Dyscritus vetustus* because this fragment is undeterminable.

My conclusions are, that two of the insects belong to the Odonata, three to the Sialids. There is no Ephemerid among them, nor any synthetic species. The proofs for my statements will be given in a detailed paper. H. A. HAGEN

Cambridge, Mass.

Ice-Casts of Tracks

As I was riding along the highway late this afternoon, my attention was attracted to a phenomenon no less curious than beautiful. A couple of days ago there was a fall of a few inches of very damp snow, after which the temperature fell rapidly, and this morning everything was frozen hard. A large dog had trotted along in the snow while it was yet damp, and where it lay upon the old drifts by the road-side. To-day the sun has been shining very warm, cutting away all the new snow and leaving the tracks of the dog in exquisitely perfect ice-casts, thin as writing-paper, and standing on the most delicate thread-like columns, about an inch above the surface of the old snow.

Lyons, N.Y., March 7 J. T. BROWNELL

Migration of Birds

THE following extracts from a work entitled "Bible Customs in Bible Lands," by Henry J. Van Lennep, D.D. (1873), may prove interesting to some of your readers, as containing important and reliable evidence with regard to the migration of birds, which has formed the subject of two recent letters in NATURE.

Speaking of the great numbers of small birds which inhabit Western Asia, as compared with Europe and North America, Dr. Van Lennep explains the circumstance by the fact that "even those of feeblest wing have an easy road from Palestine, Syria, and Mesopotamia, by the Isthmus of Suez, and over the narrow Red Sea, to their winter quarters in tropical Africa, while nature has provided them with *extraordinary means* of conveyance from Asia Minor southward across the Mediterranean . . . The swallow, and many other birds of similar powers of flight, are able to cross over the entire breadth of the Mediterranean, especially by taking advantage of a favourable wind. But many birds are quite incapable of flying over a surface of 350 miles from headland to headland across the Mediterranean without alighting, and would require many days, and even weeks, to perform the trip through Syria and Palestine. Such are the ortolans, darnagas, bec-figs, wren, titmouse, smaller thrushes and finches, with a hundred other diminutive specimens of the feathered tribes . . . and as the severity of the winter would be fatal to them, not only in Asia Minor but even in Syria and Palestine, He who is ever mindful of the smallest of His creatures has provided them with means of transportation to a more genial clime. Many of them, indeed, find their way downward from Palestine into Arabia and Egypt, but this would be difficult, if not impossible where lofty mountains and broad seas intervene, and to meet such cases *the crane has been provided*. . . . Most of these birds are migratory. In the autumn numerous flocks may be seen coming from the north with the first cold blasts from that quarter, flying low, and uttering a peculiar cry as if of alarm, as they circle over the cultivated plains. Little birds of every species may then be seen flying to them, while the twittering songs of those already confined settled upon their backs may be distinctly heard. On their return in the spring they fly high, apparently considering their little passengers can easily find their way down to the earth. As Dr. Van Lennep has "spent almost a lifetime in the East," I conclude he has been an eye-witness of the above facts and therefore his testimony is conclusive. G. A.

Bath, March 16

Sound of the Aurora

WITH reference to the question mooted in last week's NATURE (p. 459) by M. L., Rouse as to the sounds emitted by aurora, perhaps the accompanying extracts may be of interest.

Brighton, March 20 EDWD. ALLOWAY PAKENHAM

"*Record of a Girlhood*," *F. A. Kemble. Vol. I.*

"Standing on that balcony [at Edinburgh] late one cold night, I saw for the first time the sky illuminated with the aurora borealis. It was a magnificent display of the phenomenon, and I feel certain that my attention was first attracted to it by the crackling sound which appeared to accompany the motion of the pale flames as they streamed across the sky. . . . indeed *crackling* is not the word that properly describes the sound I heard, which was precisely that made by the flickering of blazing fire; and as I have often since read and heard discussions upon the question whether the motion of the aurora is or is not accompanied by an audible sound, I can only say that on this occasion it was the sound that first induced me to observe the sheets of white light that were leaping up the sky. At this time I knew nothing of such phenomena or the doubts among scientific men to which they had given rise, and can therefore trust the impression made on my senses."

I BEG to assure Mr. Rouse that about fifteen years ago, as in the evening, in this very quiet locality, I listened, along with my father, to the sound of an aurora, pulsing above us, and the zenith, and appearing nearer to us, or lower, than the auroras I had seen. The sound was somewhat like the rustling or switching of silk, and we listened to it for some time with great curiosity. The aurora was not coloured, as more intense ones have sometimes appeared, but white. It recalled to me the lines of Burns in a fragment entitled "A Vision."

"The cauld blue north was streaming forth
Her lights, wi' hissing eerie din;
Athort the lift they start and shift,
Like fortune's favours tint as won."

Dumfriesshire, March 20 J. SHAW

Tacitus on the Aurora

WITH reference to the passage of Tacitus, "Germ." 45, quoted in NATURE, vol. xxiii. p. 459, I would suggest that the word *equorum*, proposed by some commentators, is far happier than *deorum*. "It is believed that a sound is heard, that the forms of the horses and rays from a head are seen." R. O. S.

Heidelberg, Germany

Aberration of Instinct

As an instance of "Aberration of Instinct," or I should rather say of *instinct at fault*, may be mentioned the following:—It is well known, I believe, that rooks in attacking young mangold wurtzel pick out the plants to obtain the wireworm at their roots. It happens that plants most infested with these insects are most flagged in the leaf. Now a neighbour whose sowing has been a partial failure transplanted some young wurtzels into the vacant places. These of course for a few days presented a flagged appearance, and were all seized on by the rooks to the exclusion of the rest. Poor disappointed creatures, what must have been their chagrin at finding no wireworm as they evidently expected!

Waldringfield Rectory, Woodbridge, March 16 T. H. WALLER

Squirrels Crossing Water

A CORRESPONDENT in NATURE (vol. xxiii. p. 340) is surprised to learn of the squirrel taking to the water. It is not an

amon thing for them to do so here, and they are frequently wned in making attempts beyond their strength.

Some years ago I was rowing on Lake George in this State, en I observed one of these little animals in an open place, ere from the course he was pursuing he must have swum urly half a mile. He seemed almost exhausted, and when I id my oar towards him he readily accepted the invitation to me on board, ran up the oar, and then to my surprise ran up r arm and ascended to my shoulder! I do not know whether simply followed his climbing instincts, or whether he sought elevated point to get an observation. However this may have en, after a short pause he descended and took his station in e bow of the boat, from which in a few minutes he plunged to the lake and struck out for land. He evidently miscalculated s remaining powers, for he was unequal to the effort, and soon adly availed himself of a second opportunity of gaining a place refuge. He now sat quietly while I rowed him towards the nd, evidently satisfied that he was in friendly hands, and that is wisest plan was to remain as a passenger. When close to ie shore he made a flying-leap and scampered for the trees, oubtless grateful in his little heart for the kindness that had elped him over the critical part of his voyage.

This was near the narrows of the lake, where it is about one ile in width, with groups of islands which shorten the traverses o less than a quarter of a mile. My little friend however had ot availed himself of the easier and more circuitous route, but ad boldly undertaken a directer course and a longer swim, which, ut for the timely rescue, would very likely have been his last quatic attempt. FREDERICK HUBBARD

New York, March 10

IN connection with a recent letter in NATURE on the squirrel aking to water, the following facts may be of interest:—While amping for two summers recently in the wilderness of northern New York, I was much surprised at frequently seeing squirrels rossing the ponds and lakes of the region. We would sometimes find several of these strange navigators in the course of an afternoon's row. They were seen most abundantly during the early part of July; indeed, later in the season, they were but rarely found. During many summers of camping elsewhere I have never seen them take to the water. It has occurred to me that the explanation of this peculiarity (if it be such) of the squirrels of this locality may be found in the nature of the region visited; for we find there a most intricate water-system, the whole region being dotted with ponds and lakes connected by small streams. The necessity of taking to the water at times has perhaps enabled the squirrels to overcome their aversion to this element, and they have thus become semi-aquatic in their habits. The squirrel to which reference is made is the common "red squirrel," *Sciurus Hendsonius*. C.

Worcester, Mass., March 8

IN the autumn of 1878 I was salmon fishing in the River Spey, a few miles from its mouth, where the stream was broad, strong, and deep—when just beyond the end of my line I perceived a squirrel being carried down, but swimming higher out of the water than is usual with most animals. Its death by drowning seemed inevitable, as the opposite bank was a high, perpendicular cliff of Old Red Sandstone, where even a squirrel could hardly land. However it swam gallantly on, heading straight across the stream, and finally, after being swept down a long distance, emerged on the other side, where a burn intersected the rock, and fir-trees grew down to the water's edge. The left bank, where the squirrel must have entered the river, was low and shelving, and it selected a spot, accidentally or otherwise, whence the current carried it opposite to an easy landing-place on the right bank. CECIL DUNCOMBE

March 18

THE LATE MR. E. R. ALSTON

THE death of Edward Richard Alston, which took place at his rooms in Maddox Street on the 7th inst., leaves a vacancy in the thin ranks of the working naturalists of this country that will not be easily filled up. At the time of his death Mr. Alston was secretary to the Linnean Society, a member of the Council of the Zoological Society, and treasurer to the Zoological Club, and up to within a few days of his decease was engaged in active zoological work. Mr. Alston, who died of phthisis at the early age of thirty-five, although somewhat retiring in disposition, was of a particularly kind and amiable nature, always most friendly with those with whom he was brought into contact, and ready to help them by advice or assistance. Mr. Alston was of Scotch parentage, and a native of Ayrshire. Being from infancy of delicate constitution he was educated chiefly under private tuition, and did not go to school or college. Notwithstanding these disadvantages he was a good scholar and a neat and concise writer, and had an excellent acquaintance with comparative anatomy. Taking early to the pursuit of natural history he became a contributor to the *Zoologist* and other popular journals, principally upon mammals and birds. Mr. Alston's first important paper was an account (published in the *Ibis*) of his journey to Archangel, made in 1872, in company with his friend Mr. J. Harvie Brown, in which excellent observations are given on the summer migrants and other feathered inhabitants of that previously little explored district. Shortly afterwards Mr. Alston moved his head-quarters to London during the first part of the year, and undertook the compilation of the portion of the *Zoological Record* relating to mammals, which he carried on in a very painstaking and methodical way for six years (1873-78). A new edition of Bell's British Mammals, which had long been called for, appeared in 1874. Mr. Alston, although he is only credited with having "assisted" in this work, was, we believe, its virtual compiler. From that date also he became a frequent reader of papers at the meetings of the Zoological Society and author of several excellent memoirs in the *Proceedings*. Amongst these we may call special attention to his revision of the genera of Rodentia, published in 1876, as a most successful exposition of the many difficult points connected with the arrangement of this group of mammals, and to his memoirs on the Mammals of Asia Minor, collected by Mr. C. G. Danford (1877 and 1880). Mr. Alston's last and most important work, which he had fortunately just brought to an end before his untimely death, was the "Mammals" of Salvin and Godman's "Biologia Centrali-Americana"—a great work on the fauna and flora of Mexico and Central America. The first part of this was published in 1879, the eighth number containing the completion of the Mammals in December last. The death of this promising naturalist, when in the full tide of work, must be a subject of universal regret among all lovers of science.

RECENT MATHEMATICO-LOGICAL MEMOIRS

THE Boolian reform of logical science is at last beginning to manifest itself and to bear the first-fruits of controversy. Thirty years ago Boole's remarkable memoirs were treated as striking but almost incomprehensible enigmas. Even De Morgan did not know exactly how to regard them, and in his "Syllabus of a Proposed System of Logic" (p. 72) thus allows their mysterious truth:—"In these works the author has made it manifest that the symbolic language of algebra, framed wholly on notions of number and quantity, is adequate, by what is certainly not an accident, to the representation of all the laws of thought." But time and the efforts of several investigators have cleared up much of the mystery in which Boole wrapped his logical discoveries. The controversies now going on touch rather the precise form to be given to the calculus of logic, than the former question of the new logic against the old orthodox Aristotelian doctrine.

The most elaborate recent contributions to mathematico-logical science, at least in the English language, are the memoirs of Prof. C. S. Peirce, the distinguished mathematician, now of the Johns Hopkins University, Baltimore. Not to speak of his discussions of logical ques-

tions in the *Proceedings* of the American Academy of Arts and Sciences (vol. vii. pp. 250-298, 402-412, 416-432), we have from him the wonderful investigation contained in his "Description of a Notation for the Logic of Relatives, resulting from an Amplification of the Conceptions of Boole's Calculus of Logic" (*Memoirs* of the American Academy, vol. ix. Cambridge, U.S., 1870, 4to). The contents of this remarkable treatise, which fills sixty-two quarto pages, demand the most careful study, but it would be quite impossible in this article to enter upon such study. Prof. Peirce has however quite recently interpreted his own views in a new memoir "On the Algebra of Logic," of which the first part, completed by the author in April last, was printed in the *American Journal of Mathematics*, vol. iii., and issued in September (4to, 57 pp.). After noticing the beautiful typography in which the *American Journal* rejoices, we find in this memoir a very careful inquiry as to what is really the form and nature of logical inference.

Prof. Peirce treats in succession of the Derivation of Logic, of Syllogism and Dialogism (a new name for a form of argument), of Forms of Propositions, the Algebra of the Copula, the Internal Multiplication and the Addition of Logic, the Resolution of Problems in Non-relative Logic, with a further chapter on the Logic of Relatives. The fundamental point, however, which is under discussion in the first two chapters touches the nature of the copula. There is abundance of evidence to show that given a few elementary forms, it is possible to spin out logical or mathematical formulæ simply without limit. But the superstructure rests entirely upon the basis of elementary truth contained in the first axioms. In logical science it is emphatically true that "C'est le premier pas qui coûte." There is a momentous choice to be made at the outset, and if we then take a wrong view of the nature of the logical copula, we can never come right again by any amount of development or formulisation.

Prof. Peirce after mentioning that four different algebraic methods of solving problems in the logic of non-relative terms have been proposed by recent English and German logicians, adopts a fifth, which he thinks is perhaps simpler and certainly more natural than any of the others. Peirce commences by expressing all the premises by means of the copulas $-<$ and $\overline{-<}$, "remembering that $A = B$ is the same as $A -< B$ and $B -< A$" (p. 37). These new symbols are to be interpreted so that $A -< B$ means (A implies B), in the way that water implies liquidity, or all water is liquid. The symbol $\overline{-<}$ is the negative of the above, so that $C \overline{-<} D$ means that C does not imply D. He then lays down five other processes which give the elementary theorems of the calculus, showing how to develop, simplify, transpose, and infer equivalency by these symbols. As however these processes occupy two quarto pages in their first statement, it is evident that they cannot be reproduced here. The question which really emerges is not as to the power and originality shown by Prof. Peirce, about which no reader of his memoirs can entertain the slightest doubt, but as to the wisdom of the first step, the selection of the relation expressed by the symbol $-<$ instead of that expressed by the familiar sign of equality $=$. Prof. Peirce begins by remarking that $A = B$ is the same as $A -< B$ with $B -< A$. For instance, all equilateral triangles are equiangular, and all equiangular triangles are equilateral. But though these two assertions are equivalent to "equilateral triangle = equiangular triangle," Prof. Peirce elects to treat the two parts of the apparently compound proposition separately, his reasons being given partially on p. 21. This is not the first time that the same choice has been made; for, not to speak of Aristotle and the Aristotelians generally, De Morgan elected to base his systems of logic upon inclusion and exclusion, instead of upon equality. In his symbols $X \parallel Y$ is compounded of $X)) Y$ and $X ((Y$ (Syllabus, p. 24). [illegible] to say all Xs are all Ys is made of all Xs are Ys a[nd] Ys are Xs. Now without going far afield, I believ[e] a sufficient reason may be given for holding that bo[th] Morgan and Peirce have chosen wrongly. A cl[ass] made up of individuals, and the very conception of a [class] thus implies the relation of identity expressed in A[ll] If I say the colour of glacier ice is identical wi[th] colour of pure rain water, it is impossible to bre[ak] assertion up into "The colours of glacier ice are [the] those of pure rain water," and "The colours of pure water are, &c." The colour is one indivisible and ide[al] Now if there is at the basis of all reasoning an elemen[tary] assertion of the form $A = B$, which is incapable of [reso]lution into anything simpler, this sufficiently proves Peirce's $A -< B$, or De Morgan's $A)) B$ cannot be original elementary form of assertion. Moreover, we say that all equiangular triangles = all equ[ilateral] triangles, the real basis of assertion is that each pos[sible] equiangular triangle is identical with one possible [equi]lateral triangle. The plural is made up of the singular, the singular is incapable of logical decomposition. may decompose $A = B$ into As are Bs, and Bs are but ultimate decomposition gives us $A' = B', A'' = A''' = B'''$, A', A'', &c., being individuals.

It is highly curious, however, that this very ques[tion] arises again with reference to the so-called Calcu[lus] Equivalent Statements recently published by Mr. [Hugh] MacColl, B.A., in the *Proceedings* of the London Ma[the]matical Society (First paper, November 1877, vol. [viii.] 9-20; Second paper, June 13, 1878, vol. ix. pp. 17[7]. Third paper, vol. x. pp. 16-28; Fourth paper, vol. [xi.] see also *Mind*, January 1880, pp. 45-60, and the *Philo[s]sophical Magazine* for September 1880).

There can be no doubt that Mr. MacColl has sho[wn] much skill in devising neat symbolic forms, and m[uch] power in using them. Comparing his processes w[ith] those of De Morgan, for instance, it is impossible [not] admire their symmetry and lucidity. But when we [go] the real point, the nature of assertion and inference, [we] obliged to hold that Mr. MacColl has, like De Morg[an] and Peirce, elected wrongly. What De Morgan expresse[d] by $X)) Y$, and Peirce by $X -< Y$, MacColl puts in [the] form $x : y$, calling the assertion an *implication*. Curiou[sly] enough, he professes never to treat of things, but only assertions, so that with him $x : y$ means that the asser[tion] x implies the assertion y, or whenever x is true, y is [true]. Having carefully considered Mr. MacColl's proposals, [I] felt obliged to write of them in a recent publication [as] follows:—"It is difficult to believe that there is [any] advantage in these innovations; certainly, in preferr[ing] implications to equations, Mr. MacColl ignores the neces[s]ity of the equation for the application of the Principle [of] Substitution. His proposals seem to me to tend towar[ds] throwing Formal Logic back into its Ante-Boolian con[fu]sion."

In a paper printed in the *Philosophical Magazine* [for] January 1881, Mr. MacColl takes me to task and invites me to make good the charge about Ante-Boolian con[fu]sion, by entering into a friendly contest in the problem columns of the *Educational Times*. Having just recently spent the better part of fifteen months in solving other people's problems, and in inventing some two or three hundred new ones, published in "Studies in Deductive Logic," I certainly [illegible] bound to sacrifice my peace of mind for [illegible] ears by engaging to solve any problem [illegible] Mr. MacColl or h[is] I therefore declin[e] easily explain w[hy] comes to much t[he] The great reform [illegible] tion the [illegible] mat[h]

ld true and simple results within the sphere of logic, t it disclosed wonderful analogy between logical and athematical forms, to which De Morgan adverts in the ssage quoted above. All true progress in the philoophy of those fundamental sciences depends upon ever eeping in view the fundamental identity of the reasoning ocesses, as depending on the process of substitution, actised explicitly by algebraists for some two or three nturies past, and implied in the geometrical reasoning Euclid.

But Mr. MacColl takes a backward step; he says he an make a simpler notation by taking $\alpha : \beta$ instead of y $\alpha = \alpha\beta$. In regard to form there is absolutely no ovelty in the implication, for it is simply De Morgan's)) Y, or the ancient Aristotelian proposition A is B. t is true that Mr. MacColl makes his terms consist of ssertions, so that all his assertions would appear to be ssertions about assertions—a needless complexity, landing s in the absurdity that a calculus of equivalent statements as no means of exhibiting the statements themselves. Mr. MacColl claims indeed considerable advantage for is notation on the ground that in the syllogism $(\alpha : \beta)$ $\beta : \gamma) : (\alpha : \gamma)$, the very same relation which connects α with β, and β with γ, connects also the combined premises $\alpha : \beta)$ $(\beta : \gamma)$ with the conclusion $\alpha : \gamma$. He thinks that ny notation is very clumsy and roundabout, because, as ny propositions treat of things or qualities, I should have o use words to express the inference of one proposition rom others. In that case Mr. MacColl must bring the ike charge of clumsiness against the whole body of mathematicians, because their equations are between hings or their magnitudes, and they still use language "hence," "therefore," &c., to express the fact that certain equations lead to other equations. If there is any mathematical sign to denote inference, it is rarely used, unless it be the familiar '.' and '∴', which are merely shorthand signs.

Mr. MacColl however, while pointing out the excellence of his implications, objects to my statement that he rejects equations in favour of implications on the ground that his method admits of both forms: "As a matter of fact," he says, "I employ both, sometimes even in the same problem. In my first paper . . . I adopt the equational form throughout; in my second and third papers, which relate entirely to questions of pure logic, I generally adopt the implicational form, as the simplest and most effective; while in my fourth paper, which treats of probability, I mainly adopt the equational form." There is nothing which I can see in this to contradict my objection that Mr. MacColl rejects equations *in favour of* implications. Mr. MacColl uses implications as "the simplest and most effective," but he adopts the equational form, I suppose, when he finds it indispensable; if not, why does he not hold to his simple and effective implication? If he finds one form best in logic and the other in mathematics, then he is ante-Boolian, because it was the whole point of Boole's labours to establish identity of method in logic and mathematics. I have really no wish to condemn Mr. MacColl's calculus or to enter into controversy with him, but in the interests of truth and sound science I must assert my belief that his implication $\alpha : \beta$ is at the best but a shorthand rendering of $\alpha = \alpha\beta$, which is Boole's form adopted by me. I have not said, and do not undertake to say, that Mr. MacColl's formulæ are not concise and neat. But a shorthand notation is bad if it obscures the real nature of the reasoning operation, and the fact that Mr. MacColl always keeps the equation in the background as a reserve method to call into operation when needed, shows to my mind that his methods are m n in a philosophical point of view. The very m method is "The Calculus of Equivalent and the word equivalent sufficiently implies n is at the bottom of the matter. The is that $\alpha : \beta$ has one letter less in it than $\alpha = \alpha\beta$, and to save the trouble of writing this one little letter Mr. MacColl would have us obscure all the grand and fertile analogies which Boole disclosed to the astonishment of mathematicians in 1847 and 1854. Mr. MacColl says: "The question whether the implication $\alpha : \beta$ or its equivalent the equation $\alpha = \alpha\beta$ should be preferred in a symbolical system of logic, must be decided on the broad grounds of practical convenience." It is not however a question of practical convenience, but of philosophical truth which is at issue, and in thus playing fast and loose with the equation, Mr. MacColl shows his entire want of comprehension of what is involved in the Boolian reform of logic. It may be added that were Mr. MacColl to discard implications and use only the equations which he admits are equivalent to them, there would be no formal difference between his calculus and that modified form of Boole's calculus which I proposed in 1864, and have been ever since engaged in developing, excepting indeed Mr. MacColl's unaccountable adoption of assertions as terms.

Perhaps it ought to be added that Boole, both in his "Mathematical Analysis of Logic," and in his great "Laws of Thought," introduces chapters on what he calls "Secondary Propositions" or Hypotheticals, which deal, like Mr. MacColl's assertions, with the truth of other assertions; but nothing emerges from Boole's discussion of secondary propositions except that they obey exactly the same formal laws as primary propositions, and are of course expressed equationally.

W. STANLEY JEVONS

ILLUSTRATIONS OF NEW OR RARE ANIMALS IN THE ZOOLOGICAL SOCIETY'S LIVING COLLECTION[1]

III.

THE animals we now speak of are again inhabitants of North-Eastern Asia—a country which, as before remarked, has of late years produced a considerable number of accessions to the list of Mammals. Both of them also belong to the great group of Ruminants—which is of special interest, as embracing all the animals upon the flesh of which civilised man principally subsists.

6. The Japanese Goat-Antelope (*Capricornis crispa*). For many years Siebold's "Fauna Japonica" was almost our only authority on Japanese zoology. The Dutch, having long had a monopoly of Japan, were enabled to stock their great National Museum at Leyden with a host of objects unknown to the other cabinets of Europe, but of which their travellers and residents managed to obtain specimens from various parts of the land where they only were permitted to penetrate. The "Fauna Japonica," although Japan is now open to all the world, still remains the best work of reference on the mammals of Japan. In it will be found the first description of the singular goat-like antelope of which the Zoological Society have recently obtained their first living example, drawn up by the celebrated naturalist Temminck, formerly director of the Leyden Museum. Temminck named the animal *Antelope crispa*, from the rough coat of hair which covers it, and tells us that it inhabits the higher alps of the Japanese Islands Nippon and Sikok, and is known to the Japanese as the "Nik." But a more complete account of its habits has lately been published by Capt. H. C. St. John in his recently-issued "Notes and Sketches from the Wild Coasts of Nipon." Capt. St. John tell us that the Japanese chamois, as he calls it, "is a very difficult animal to find, and to bag when found; they keep to the highest mountains, and to the highest and must rugged peaks of these ranges. I have hunted them with the natives, and with their dogs, and this often; and yet only once, although often close to the creatures, have I had a

[1] Continued from p. 417.

glimpse of one, much less a shot. On one occasion I was lucky enough to see one, and this was by mere accident, and when not in search of game. I have often been told fabulous stories about the Nigou, the native name for this wary animal. They were supposed to have one horn, and to use this single frontal ornament as a means of hanging on to trees as well as in self-defence. After some years of anticipation and endeavour to get even a dead specimen, I got a couple, and then, strange to say, several others were brought to me. A young male, alive, was caught, after its mother was shot. Only one specimen of all that were brought to me by the native hunters had both their horns intact—always one, and often both, being more or less broken. In hunting them with dogs, it soon became evident why this was so generally the case. The Japanese, who knew the animal's habits intimately, invariably placed me near some huge bare slab of rock, on which the Nigou, when pressed

FIG. 6.—The Japanese Goat-Antelope.

by the dogs, was expected to appear, and on looking at these slippery sloping platforms, I tried to conjecture—when waiting for the animal to appear—where, if I knocked one over, it would tumble, and what shape or form it would be in by the time it stopped. I could then easily understand why the horns were usually so damaged.

"I have no doubt also they are often caught in the bushes or trees by the slightly turned-back horns, on their falling and reaching the foot of these rocks; hence the origin of the story of their holding on to the trees.

"The young one which was brought to me alive was the most fierce little thing I ever saw. Any dog, large or small, that approached its cage, down went its head, and with a quick sudden spring the creature invariably came bang up against the wooden bars. Its horns were about two inches long, as sharp as needles, and quite capable of inflicting a very nasty wound.

"The colour of the 'Nigou' is a brownish slate; the older they get the lighter-coloured they beco
actually had one in my hands, I was unab
whether they had a beard or not, and was p
they do not possess this ornament—there
true antelopes, and not goats."

For their unique specimens of this scarc
Zoological Society are greatly indebted to th
operation of one of their Corresponding Mem
Fryer of Yokohama, Japan, by whom it wa
as a present to the Collection in April, 1879.
was then quite young, but has now attained
and presents a very singular and characteristi
—quite different from that of either goats o
which is well shown in Mr. Smidt's drawing

The goat-like or mountain antelopes,
presents animal belongs, constitute a small
family Bovidæ, which is distributed over
chains of Eastern Asia and its islands.
geographical neig
Japanese animal
cornuis Swinhoii
and *C. caudata*
the Himalayas
represented by
the Thaar or Tah
sportsmen, and i
ranges of Sumatra
trensis. In the R
tains of North Am
a far-separated m
same group, whi
as the "Mountain
the American hu
locapra American
ropean Chamois
tragus) is not ve
related to these an

7. Lühdorf's D
Luehdorfi).—The
North-Eastern As
deer of the same
North American "
long been known,
animal has never
clearly identified.
authors it seems t
referred to the Re
vus elephas), by o
Persian Deer (*C. M*
the horns upon
name *Cervus custo*
founded by Blanfo
Zoological Society
ings for 1875) appea
to the same spec
only quite recently however that examples
animal have reached Europe alive, and its
characters have become better known. In t
of 1876 two pairs of this deer were sent
Lühdorf, the German Consul at Nicolajefs
Pacific coast of Siberia, as a present to the
Garden of Hamburg. They had been brought
river Amoor from the far interior, having been
from some Nomads in the Bureati Steppe of
Martschuria. The strangers throve well in
quarters at Hamburg under the care of Direc
and propagated their species. Several ma
having been produced, one of them was pa
in exchange to our Zoological Society in Lon
received in the Regent's Park in May last.
specimen thus obtained, which is at present
this country, the accompanying illustration
prepared.

It will be at once evident to those who are ac

is of true deer, that the new stag exceedingly like the Wapiti. The f the two animals is so close that acter of the horns it would be o distinguish them. But so far from an examination of the present ow believed to be nearly four years iculars given of other horns by Dr. n of the present animal,[1] Luhdorf's aracter of its antlers, more nearly than its American ally.

deer so closely allied to the Wapiti a fact of special interest in geo-

Taken in connection with other hich have lately come to light, it evidently that es its many Isarctic fauna, nd connection North America, posed by the us "Atlantis," nsion of land and Western such passage ubt that the iti, the Ameri- ain Goat, and Sheep found ew World, to of which they nship.

FIG. 3.—The Luhdorf's Deer.

N MEXICO

position of high plateau s and two vast vestigation of larly interest- han four years s begun to be ittle ability by ologists, and, he country affo- ly a spirit and d every conve- se will not ag- n we say that s for the city r of the pres- nditys, clouds, velocity of the miscellaneous hour of the he day, from

October 16, 1880 ; and on the same he above, a daily statement of the elements for some thirty stations orts of Mexico and at heights 80 feet above the sea. Annual re as, that for 1879 having been ce- an atmospheric pressure at Vera- the sea and only 11 feet above it, ng to the maximum, 30·075 inches to the minimum 29·851 inches in l distribution of the pressure holds evated stations are reached, when pressure remains pretty constant during the year. This peculiarity becomes strongly marked at Zacatecas, the highest station, 8189 feet above the sea, where the January and July pressures are the same, and the lowest mean, that of March and August, falls only 0·016 inch below the annual mean, and the highest, that of November, rises only 0·024 inch above it. At all the stations the singular protrusion of a high pressure into the Atlantic and adjoining regions in the height of summer is represented in the means.

Of the greatest possible interest are the curves of the diurnal oscillations of the barometer, deduced from the hourly observations at the central station at Mexico, these curves being quite distinct, so far as we are aware, from the curves of any other intertropical place for which observations exist. The peculiarity lies in this, that while the morning maximum and the afternoon minimum remain large at all seasons, the morning minimum diminishes in amount as the summer advances; and during the strictly summer months it does not even fall so low as the daily mean. Now this is an outstanding peculiarity of the curves of diurnal pressure in the extra-tropical inland region of the great European-Asiatic continent, and it becomes the more pronounced the more we advance into the interior of that continent. This result, viewed in connection with the other diurnal curves, forms a very valuable contribution to this difficult branch of the science.

The mean temperature for 1879 at Mexico, 7434 feet high, was 59°·5, May being the warmest month, 64° 6, and December and January the coldest, 55°·4; and these were generally the months of extreme temperature over the

[1] Hamburg, 1880, p. 32.
Resumen de las Observaciones practicadas en ... durante el Año de 1879." (Proceedings of the Institute)
Boletin del Ministerio de Fomento de ... ii. 21, 79, &c.

different districts of Mexico. The period of the year when temperature is highest is also the period when the air is driest, the mean relative humidity of Mexico for April and May for 1878 and 1879 being only 42. The mean temperature of Tlacotalpam, the lowest station, was 77°·5, and of Zacatecas, the highest from which mean temperatures are published, 61°·7. The difference of the two is thus 15°·8, and as the difference of height is 8178 feet, the fall of temperature with the height is comparatively slow, being only one degree for each 518 feet.

At Mexico during 1879, out of the 8760 observations made of the wind, 4156 cases were reported as calm, being nearly a half of the whole of the observations. By far the most frequent wind is the north-west, which was observed 1299 times; next follow the north-east, 789 times, and north 636 times; and the least frequent, south, 174 times, and south-west 278 times. As regards direction, the prevailing winds at Mexico were a point to the north of east in February and March, from which they gradually worked round to north-east in the beginning of May, north in July, north-west in September, thence again to north in the end of November, and back to east in February. On these changes of the wind, considered with reference to the Gulf of Mexico and the Pacific, largely depends the rainfall. The rainy season extends from about the middle of May to the end of October; but at eastern stations showers are of not infrequent occurrence from November to April, when prevailing winds are northerly and easterly. The largest annual rainfall was 89·16 inches at Tlacotalpam, and the least 15·66 inches at San Luis Potosí. Thunder and lightning are of common occurrence during the summer months, these phenomena occurring on 66 per cent. of the days during June, July, and August. During the five months from December to April thunderstorms occur only on 7 per cent. of the days. The position of Mexico, as already stated, marks it out as a region peculiarly suited for the investigation of some of the more interesting meteorological problems, particularly those which concern the vertical distribution of the phenomena, in connection with which an increase to the number of low-level stations on the Gulf of Mexico and the Pacific sea-boards is very desirable.

ON THE IDENTITY OF SOME ANCIENT DIAMOND MINES IN INDIA, ESPECIALLY THOSE MENTIONED BY TAVERNIER

HAVING recently endeavoured to correlate the diamond deposits of India, I have been surprised to find what a mass of contradiction exists in both Indian and English literature as to the identity of some of the most famous mines which were worked little more than 200 years ago.

In this brief account I propose to give results, not the steps which have led me to them. Tavernier about the middle of the seventeenth century visited and described three diamond-mines, which were named respectively Raolconda in the Carnatic, Gani, called Coulour by the Persians, and Soumelpour on the Gonel River.

Raolconda, Tavernier says, was five days distant from Golconda and eight or nine from Bijapur, and most writers with signal unsuccess have tried to fix it accordingly. But elsewhere Tavernier gives nine stages, aggregating probably 189 miles, on the road from Golconda to Raolconda, so that in the first statement the distances were probably transposed. With these new indications we are led to an old town called Rawdukonda, lat. 15° 41′, long. 76° 50′. I have not yet succeeded in obtaining any independent testimony of the existence of diamond-mines at this locality, but hope to be able to hear more about it ere long.

Gani, or Coulour, where Tavernier says the Great Mogul diamond was found in the sixteenth century, has been variously located by authors, being supposed by many to be identical with Gani Purtial, on the K… River; but I am satisfied from the evidence afforde… old maps that it is to be identified with Kollur, lat. 1… 30″, long. 80° 5′, which is also on the Kistna, about twe… six miles further to the west. Now as to this word G… which has been treated of as a proper name, its re… rence in connection with two different localities sugge… that it means mine. In fact since G and K are … changeable letters in some Indian languages we sho… probably read for Gani *Kan-i*, or the mine of Purti… of Kollur.

If, as seems most probable, the Koh-i-nur is ide… with the Great Mogul diamond described by Taver… and that the great age claimed for it by the Hindus … be regarded as mythical, then in fact for the first … the identity of the source from whence this fa… diamond was obtained may be regarded as settled. … of the eighteenth century indicate diamond mines at … (*i.e.* Kan-i) Kollur, though local memory of their … existence appears to have died out.

Soumelpour, on the Gonel River of Tavernier, … generally by recent authors been identified with Sa… pur, on the Mahanadi, in the Central Provinces. … Tavernier's somewhat precise indication of its positio… led me to the conclusion that it was situated much f… to the north, namely, in the valley of the Koel Rive… tributary of the Sone. At about the distance stat… Tavernier (which I calculate to be the equivale… eighty miles), to the south of the well-known fortre… Rhotas, there are near the banks of the Koel Rive… Tavernier's Gonel) the remains of an ancient town … Semah, which word is identical with *Semul* (the … name of a species of cotton-tree, *Bombax Malabaric… Semulpour, or the town of the *Semul*, is therefor… seems probable, Tavernier's Soumelpour. The posi… of Semah is lat. 23° 45′, long. 84° 21′; it is inclu… the sub-division of Palamow, in the Chutia Na… Province. There is independent evidence of impo… diamond mines having existed in a neighbouring pa… Chutia Nagpur in the sixteenth century, but there … been none in operation there for many years.

The last locality is Beeragurh, which is mentione… the *Ain-i-Akbari*, and also in several other … writings. This is unquestionably identical wi… modern Wairagarh in the Chanda district of … Central Provinces, where excavations locally know… have been diamond mines are still to be seen. Waira… is in lat. 20° 26′, long. 80° 10′. Many allusions wh… believe to refer to this locality might be quoted. Co… the fifteenth century by Nicolo Conti is of espe… interest. He says that at Albenigaras, fifteen … journey north of Bijapur (Bijengalia), there is a mou… which produces diamonds. The method of obtai… them, which he describes on hearsay, is similar to tha… the celebrated Arabic myth which the travels of Sinde… the sailor and of Marco Polo have made familiar … every one.

The idea of the diamonds being collected by throwi… pieces of meat freshly cut from a slaughtered cow … buffalo into a valley inhabited by venomous serpent… which pieces, with diamonds sticking to them, were picke… up by birds of prey and recovered from them by th… diamond-seekers, probably took its rise from some sac… ficial custom in connection with the worship of the … sanguinary goddess of riches, wh… (Thom… p. 95) allud… nder the name … wars, as the… partners … The piece… from th… victim w… hrown abou… were nat… p and carr… This I be… een the fou… the fabulo… was erecte… Beeragur… is, as th… 324 miles f… thwards, … might therefo… mplish…

as there is sufficient resemblance with the Arabic prefix *Al* to make re identical. V. BALL

NOTES

ress is being made with the reprint of d's scientific papers, the publication early in the summer. It will form a vo pages, illustrated by more than woodcuts. Mr. Hubert Herkomer, rtist, has most kindly undertaken to ate professor, as a frontispiece to the be limited to a very small number of are already subscribed for. Those nes to the list of subscribers before d to communicate at once with the lemorial Fund, 11, Hanover Square, ad to receive subscriptions already crossed "London and County Bank,

y on Friday last, Mr. Sclater calls e collection of birds of the late John id been offered to the Trustees of the and expressed a hope that there will : of the Treasury in sanctioning the in is stated to embrace about 1500 inted specimens of humming-birds, s the descriptions and figures in the the Trochilidæ" were taken. There s of various groups, amongst which milies of Toucans, Trogons, Birds of

lectures will be given by Members of ysics appointed by the Lords of the ducation:—An Introductory Lecture, S., April 6. A Lecture on the tudying the Influence of the Sun on y Lieut.-General Strachey, R.E., Two lectures on the Connection rial Phenomena, by Prof. Balfour and 29. Six lectures on Spectro- r Chemistry, by Mr. J. Norman , 6, 11, 13, 18, and 20. Three of the Infra-red of the Spectrum in sies, by Capt. Abney, R.E., F.R.S.

The lectures will be delivered in South Kensington Museum at 4 p.m. Admission will be by tickets, which here is room, on application by letter ind Art Department, South Ken-

aders that the French Association April at Algiers, beginning on the en enrolled members will have the railway travelling, and of a special s to Algiers. This ship will leave ling at Port Vendres on the 12th. ime ago, but by addressing, without neral Secretary of the Association, rticulars relating to the excursions, nd attractive, some of them includ- ahara, will be given. An industrial ed in Algiers, with races, *fêtes*, and n Institute, which is directed by M. Faswell-Lyte, Hon. Foreign Secre- tary of the Association, Science Club, Savile Row, will be happy to afford further information to intending English visitors.

THE arrangements for the International Medical and Sanitary Exhibition are progressing so satisfactorily that it promises to be the most important Sanitary Exhibition hitherto organised in this country. Applications for space are now being rapidly sent in, as the 31st inst. is the last day fixed by the Committee for receiving them. Up to March 15 applications for 984 feet had been received by the Committee. The Certificates of Merit which are to be given will be valuable awards to the public and to the successful exhibitors on account of the high character of the list of jurors, which already includes among many other the following:—Medical Section: Christopher Heath, F.R.C.S., Wm. S. Playfair, M.D., Charles Higgins, F.R.C.S., Chas. S. Tomes, F.R.S., Prof. John Marshall, F.R.S., Dr. Robert Farquharson, M.P., the president of the Pharmaceutical Society, C. H. Golding-Bird, F.R.C.S., Lionel Beale, F.R.S., W. B. Carpenter, C.B., F.R.S., J. S. Bristowe, M.D., Major Duncan, R.A., Surgeon-General Longmore, C.B., E. H. Sieveking, M.D., &c., &c.; Sanitary Section: Sir Joseph Fayrer, K.C.S.I., M.D., F.R.S., Geo. Aitchison, F.R.I.B.A., Edwd. C. Robins, F.S.A., T. Roger Smith, F.R.I.B.A., F. J. Monat, M.D., Alfred Waterhouse, A.R.A., Capt. Douglas Galton, C.B., F.R.S., Ernest Hart, M.R.C.S., Prof. Corfield, Wm. Eassie, C.E., Roger Field, M. Inst. C.E., R. Thorne Thorne M.B., Prof. Pretwich, F.R.S., &c., &c. In addition to the interest taken in the Exhibition by medical men, architects, and manufacturers, the general public have recognised the importance of the work thus initiated by the Executive Committee of the Parkes Museum of Hygiene by subscribing to the Guarantee Fund, which at the meeting of the Committee last Tuesday was reported to amount to 1026*l.* 7*s.* At this meeting the Secretary read a letter from Mr. MacCormac, the Hon. Sec. General of the International Medical Congress, forwarding the following resolution which had been unanimously passed by the Executive Council of the International Medical Congress at their last meeting:—"That the sum of fifty pounds be guaranteed to the Committee of the International, Medical, and Sanitary Exhibition, to be held at South Kensington in connection with the Parkes Museum of Hygiene, on the occasion of the International Medical Congress."

THE programme for the annual meeting of the Iron and Steel Institute on the 4th, 5th, and 6th of May has just been issued. The first item on the programme is the presidential address of Mr. Josiah T. Smith, the president-elect, whose experience as one of the earliest and for many years one of the largest steel manufacturers in this country, and as the head of the most extensive works of their kind in the world, will give his address an exceptional interest. The papers to be read cover pretty fairly the whole field of the manufacture and application of steel for shipbuilding purposes. A paper will be read by Mr. Alexander Wilson of Sheffield on the manufacture of armour plates. The subject of the manufacture of steel and steel plates will be dealt with by Mr. Sergius Kern of Russia, who will describe improvements recently practised in Russia; while the experience lately gained in the practical use of steel for shipbuilding purposes will be dealt with in a paper by Mr. Denny of Dumbarton, at whose works on the Clyde a considerable amount of steel shipbuilding has been turned out during the last two years. The important question of the relative corrosion of iron and steel will be discussed by Mr. William Parker of Lloyd's. Another paper is promised by Capt. Jones, manager of the Thomson Steel Works, Pittsburg, on the manufacture of Bessemer steel and steel rails in America.

SCIENTIFIC honours are being paid to John Duncan, the weaver botanist. Recently the Inverness Scientific Society and

Field Club elected him an honorary member with a gift of 5*l.*, and the Banff Field Club gave 1*l.* 1*s.* When his story was first told by Mr. Jolly in *Good Words* in 1878, the Largo Naturalists' Society, one of the most active in the country, elected him an hon. member. The Edinburgh Field Naturalists' Club have lately issued a special circular and appeal on his behalf. Last week he was elected an hon. member by the Aberdeen Natural History Society, when a sketch of his life was given by Mr. Taylor, one of his pupils. Miss E. Brown has sent us 1*l.* for the John Duncan Fund.

WE see from a long article on the subject in the New York *Nation*, that the "Reports on the Total Solar Eclipses of July 29, 1878, and January 11, 1880, issued by the U.S. Naval Observatory," have appeared. We have not received a copy of the work yet, but from the article in the *Nation* it is evidently a valuable contribution to some of the questions suggested by solar eclipses.

THE Commission Supérieure of the Paris Electrical Exhibition has already deliberated on all the demands sent by French electricians. The utmost liberality has prevailed, and only a few technical questions have been reserved for more mature deliberation. But the authorisations will not be made definitive until after April 1, when the list of would-be exhibitors will be closed. The resolution of the Society of Telegraph Engineers and Electricians to organise the English section has been received with great satisfaction.

WE take the following from the *Gardener's Chronicle*:—Dr. Aitchison, Surgeon-Major in the Punjaub army, whose collections in the Kurrum Valley we alluded to on a former occasion, has returned from Afghanistan with another extensive collection of dried plants, and is now at Kew engaged in working them up. Amongst other interesting museum objects Dr. Aitchison has brought home specimens of *Chamærops Ritchieana*, a palm that covers miles of the alluvial plains with a dense bushy thicket. Frequently too it occurs as a branching tree fifteen to twenty-five feet high, but then usually in the vicinity of other trees or buildings. Dr. Aitchison's specimens illustrate this peculiarity exhibited by comparatively few other palms.

WE are glad to learn that the museum building begun some time ago under the auspices of the Perthshire Society of Natural Science is approaching completion. To equip and endow the museum a bazaar will be held in Perth towards the end of the year.

THE translation of Nägeli and Schwendener's treatise on the Microscope is approaching completion. Messrs. W. Swan Sonnenschein and Allen now announce its speedy issue to the public, which they trust will be effected during the present spring. The English editors, whose names will appear on the title-page, are Mr. F. Crisp (Secretary of the Royal Microscopical Society) and Mr. J. Mayall, jun., F.R.M.S., though several others have collaborated in the work. Messrs. Sonnenschin and Allen also announce for immediate issue an illustrated "Manual of Insects Injurious to Agriculture," by E. A. Ormerod, whose "Report of Injurious Insects for 1880" we reviewed in a recent number; and a second edition of "Prantl's Text-Book of Botany," by Vines, greatly revised, the first edition of which appeared last year.

WHERE is Mackay? "Here," we fancy a score of our readers will reply; but none of them would be "the real Mackay," as they say in the North, at least not the Mackay whose local habitation we inquire after. Happily we can answer our own question from the Christmas number of the *Mackay Standard*, a fact that shows that our Mackay must be considerably to the fore somewhere. "Mackay, according to the single archive at present extant to which we have been able to attain access, was first discovered by a gentleman of the name of M Scotchman as his name would denote. That this is more than probable, but it does not appear that, beyo his name to the place, he ever did anything to rende famous. It may accordingly be accepted as a fact tha covered the existence of the Pioneer River on which th situated, and the date of this discovery is placed at 186 within a few days Mackay is twenty years of age. Th District is in latitude 21° 10′, and is situated at a distan miles to the north-west of Brisbane, on the Pioneer Ri then Mackay is nobody at all, but a flourishing new would be a "city" in the States) in Queensland, with and wharves and warehouses, and prosperous sugar- "Clifton-on-the-Sea," a fashionable summer resor Mackayites, twelve miles off. The municipality (345 said to have fifty miles of streets under its control nothing said about houses, so most of them may not the quarry or the brick-kiln yet. The population of is given as 7500.

ON Friday will take place at Père Lachaise the in of the monument erected by public subscription Spinelli and Sivel, the two victims of the tragic *Zen* Speeches will be delivered by M. Paul Bert, Pr Physiology to the Sorbonne, who organised the su Hervé Mangon, director of the Arts-et-Métiers, wh president of the Société de Navigation Aérienne, then and M. Gaston Tissandier, who was a party in the a escaped by a marvellous concurrence of circumstances.

ON Wednesday last week at 12.10 a.m. another shoc quake was felt at Casamicciola and Lacco Ameno people fled to the open country; much consternation the people fear other shocks. Little damage was do few injured walls and a tile factory have fallen. Ves

A RATHER severe shock of earthquake was felt at March 17 at 3h. p.m., duration two seconds. It w panied by wave-like motions of the ground.

IT is announced that the entire length of the St Railway between Airolo and the Lago Maggiore will by the end of June; but the great tunnel, owing to about the vaulting, cannot be completed before Novem

THE Conseil d'Hygiène of Paris has just issued a volume of 700 pages recounting all the precautions tak several so-called "Industries Insalubres" practised in P work of the Conseil d'Hygiène extends over a peri years, from 1872 to 1877, and relates to more than 200 in some of their essential details. Amongst the recomm made are a refrigerating machine for dead-houses and establishment for cleansing contaminated objects w heated vapours. Amongst the curious observation analysis of a parasitic vegetation developing on brea military. It appears the original sporulæ were bro Germany by soldiers taken prisoners in the Franco-Ger returning home.

AS the preparation of dynamite has acquired great im M. Gobi shows (*Memoirs* of the St. Petersburg Soc. of formerly the best dynamite was made with the "Kiesel Hanover, which can absorb as much as 75 per cent. glycerine, but is now made with the diatomaceous depo Randanne, in the department of Puy-de-Dôme, w absorb from 73 to 78 per cent. of nitroglycerine. It i of notice that both these formations have been dest Ehrenberg. It is obvious that the good quality of prepared from these two deposits depends upon the pr the small *débris* of the frustules of the microscopical and that, when determining the qualities of a distu

account not only its purity, but also
it contains; thus, M. Gobi recom-
osits which contain mostly frustules
ia, *Navicula*, *Synedra*, and *Meloëra*,
greater size and more porous than
Terpomeli, *Nitzschia*, &c. As to the
es, and of sand, it ought to be quite

of the Davenport (U.S.) Academy of
y satisfactory report was given of the
l of the good work it is doing. The
in which he sketched the progress
knowledge of the Mound Builders,
the Mississippi Valley, to whose
ll along devoted special attention.

memoriam volume on the late Prof.
ssued at Cambridge, Mass. It com-
poems, addresses, &c., that appeared
, including three funeral sermons.

rt of the Dulwich College Science
its condition. The Society has been
s already collected a museum "which
older society." The *Report* contains
apers and lectures given during the

Report (the forty-seventh) has been
ool Natural History Society; all its
en doing well. In connection with
hat, under the title of the *Natural
Reporter*, the journal conducted by
hools has assumed a new and more
time that its programme has been
two numbers for February and March
ginal papers.

r. W. C. Wyckoff's "Silk Goods of
n published; the first edition was
. p. 574.

ological Society's Gardens during the
2-fronted Capuchin (*Cebus albifrons*)
ented by Mr. C. Drake Sewell; a
nsfa) from South America, presented
1 Badger (*Meles taxus*), British, pre-
Black-winged Peafowl (*Pavo nigri-*
x, presented by Mr. J. Marshall; a
gator sclerops) from South America,
C. Punseby; a Horrid Rattlesnake
azil, presented by Mr. C. A. Craven;
a atrox) from Brazil, presented by
S.; a Macaque Monkey (*Macacus*
eposited; a Goral Antelope (*Nemo-
died Geese (Anser indicus*) from India,
dain (Tragulus javanicus) from Java,
uralline variegatus), a Twelve-wired
ise alba), a Marmoset (*Mystax oedi-*

NOMICAL COLUMN

—In a communication to the Academy
e 7th inst., M. Puiseux has discussed
al contacts during the last transit of
at stations occupied by the French
de observations of second and third
d, Nagasaki, Saigon, and Kobé, and
nnea. Seventeen equations are fur-
3 various combinations are made by
the method of Delisle. The former method supplies twelve separate results, the concluded parallaxes varying from 8″·78 to 9″·17, which are arranged according to the amount of the parallax factor: the simple arithmetical mean is 8″·98. On Delisle's method the combinations for second contact give fourteen values between 8″·86 and 9″·20, of which the mean is 9″·01, and those for third contact furnish ten values between 8″·63 and 8″·90—the mean being 8″·92. These figures considered with respect to others which have been obtained from observations of the same transit and on other methods, cannot be said to enlighten us materially as to the true amount of the sun's mean parallax. M. Puiseux thinks the observations of contact in 1874 have not given results so accordant as astronomers had looked for, but he nevertheless is far from discouraging efforts to secure observations of contacts in 1882; the phenomena in 1874 did not present that geometrical simplicity which had been formerly expected, but presented a succession of phases which were the more difficult to identify in the records of the observers according as the telescopes employed were more dissimilar; and he urges (1) that the different stations should be provided with telescopes of large aperture, to be employed under as identical circumstances as practicable, and (2) that the observers should be exercised "à l'aide d'appareils convenables," to appreciate in the same manner the appearances which the contacts may offer. The former consideration at least is too well understood as of paramount importance to be likely to be overlooked by any of the national committees now engaged in arranging for the most efficient observation of the transit in 1882.

VARIABLE STARS.—Minima of Algol occur by Schönfeld's formula on April 3 at 10h. 51m. G.M.T., and April 6 at 7h. 40m., and the next series observable in this country commences on May 13 at 14h. 17m.

In the uncertainty that exists with respect to the period of Ceraski's circumpolar variable, the following calculated times of minima are only to be regarded as rough indications:—

	h. m.		h. m.
April 3 ...	12 56 G.M.T.	April 18 ...	11 58 G.M.T.
8 ...	12 37	23 ...	11 38
13 ...	12 17	28 ...	11 19

A constant period of 2·49326 days is here assumed. Prof. C. H. Peters publishes details of his observations of a number of new variable stars (*Astron. Nach.*, No. 2360), and Dr. Pümer notifies the variability of the red star Schj. 57 *a*, which stands thus in the *Durchmusterung*:—

	h. m. s.		
9·4m. ...	R.A. 5 17 32·7 ...	Decl. + 34 2′1

This star was invisible in the Lund refractor on January 29, but was well seen on February 23; in September and October, 1878, he had confirmed its fiery-red colour, and found the spectrum of the Class III. δ. V Hercules varies from 8m. to 12m., and the period seems to be about 290 days; the next maximum may be expected in October of the present year.

ANCIENT ASTRONOMY.—In No. 2 of the new periodical, *Uranía*, is an elaborate paper by Prof. Schjellerup of Copenhagen, "Sur le Chronometre Céleste d'Hipparque," in which he discusses the question "Comment les anciens astronomes ont-ils déterminé l'heure de la nuit, et à quelle exactitude ont-ils pu parvenir?" In this paper he has calculated by the strict trigonometrical formulæ (an investigation of which is prefixed) the positions of the forty-four stars mentioned in the third book of the only work of Hipparchus which has descended to us. His "Three Books of Commentaries on the phenomena of Aratus and Eudoxus," printed for the first time in 1567 (Lalande, "Bibliographie," p. 91) from two manuscripts of the Bibliothèque Medicea and the Library of the Vatican. Petau brought out a new edition, to which he availed himself of an ancient well-written manuscript preserved in the Bibliothèque Royale, and which forms part of the third volume of his "Uranologion." Prof. Schjellerup gives the Greek text essentially after the edition of Petau, with as nearly as possible a literal translation. He concludes his paper with the remark, "Dans l'état actuel on peut prouver que les Astronomes d'Alexandrie ont pu déterminer le temps sidéral presqu'à une minute près." It contains the right ascensions and declinations of the stars in question for every hundredth year, from − 300 to + 100, with the amount of proper motion to the respective epochs, and is a production which merits the attention of those who are interested in the Astronomy of the Ancients.

THE ACADEMY OF SCIENCES, PARIS.—At the annual public sitting of the Paris Academy on the 14th inst. the Lalande Prize

was awarded to Mr. E. J. Stone, director of the Radcliffe Observatory, Oxford, for his great catalogue of southern stars, involving newly-determined places of all the stars observed by the French astronomer Lacaille during his memorable visit to the Cape of Good Hope, in the years 1751 and 1752; the observations for the catalogue having been made while Mr. Stone occupied the position of Her Majesty's Astronomer at the Cape. The commission to whom the consideration of the award was referred consisted of MM. Faye, Mouchez, Lœwy, Janssen, and Tisserand, who have called attention in their Report to the "fundamental importance" of the Catalogue, in view of the study of the proper motions, &c., of the stars in the southern heavens.

At the same sitting the Valz Prize was adjudged to M. Tempel of Florence for his numerous cometary discoveries.

The Damoiseau Prize (10,000 francs) has been again proposed for 1882. It had been offered without response in 1869, 1872, 1876, 1877, and 1879; the subject on all occasions being the same and a very important one in the actual state of astronomy, viz., "To review the theory of the satellites of Jupiter, to discuss the observations and to deduce the constants which it contains, and particularly that which furnishes a direct determination of the velocity of light; and lastly, to construct special tables for each satellite."

BIOLOGICAL NOTES

Algæ of the Gulf of Finland.—M. Chr. Gobi made an excursion along the borders of the Gulf of Finland in the summer of 1879 with the object of investigating the algæ of this district. In spite of the weather being of the most unfavourable character he was enabled to work out the whole south-west coast of this district, from St. Petersburg to the comparatively open sea at Hapsal. Along the southern coast of the Island of Kotlin, on which Cronstadt is built, and also along the opposite coast shore at Oranienbaum, chlorophyllaceous algæ were almost exclusively met with, and these belonging to species to be also met with in the fresh waters of the adjoining lands, for example, three distinct species of Cladophora (among these *C. glomerata*), several forms of the genera Oedogonium, Spirogyra, Zygnema, and other filamentous Mesocarpeæ; various Desmidiaceæ (Cosmarium, Closterium, Scenedesmus), a much-branched, very fine, almost hair-like Enteromorpha (apparently *E. salina*), also various oscillatoriaceous forms and diatoms. Besides at Cronstadt an Ulothrix, more commonly in the early summer months, and a Merismopœdia (probably *M. Kützingii*) at Oranienbaum, the pretty *Spirulina Jenneri*, amidst various Oscillatoria, was met with, also Vaucheria, and in larger quantities *Hydrodictyon utriculatum*, in the various stages of development (middle of August). About seven versts west of Oranienbaum Tolypothrix was met with in some quantity, forming floating ball-shaped masses. By the end of July some excursions to the environs of Hapsal led to the discovery of the interesting Phœospore, which up to this had only once been found by Pringsheim at Heligoland, and called by him Strebloncma; in Hapsal Bay it lived on Ruppia, several Charas, and in company on these with *Ulothrix confervicola*, which latter grew in great abundance on these plants and on Ceramia and other red algæ. It is interesting to note that along with marine forms there grew some of the fresh-water filamentous algæ, such as Spirogyra, Zygnema, and in large quantities that half fresh-water species *Monostroma Balticum*. Out in the bay towards the open sea the red algæ increased in number, but the merging of the fresh-water forms into those of a truly marine type could be well studied in the Bay of Hapsal. (*Botanische Zeitung*, February 20.)

The "Blake" Cruise.—Numbers 1 and 2 of volume 8 of the *Bulletin* of the Museum of Comparative Zoology at Harvard College contain preliminary reports on the Echini collected during the cruises of the *Blake*, by Alex. Agassiz, and on the Crustacea by Alphonse Milne-Edwards, have just reached us. The report on the Echini contains descriptions of thirteen new species belonging to such genera as Dorocidaris, Cœlopleurus, Asthenosoma, Phormosoma, Palæotropus, and Schizaster. Perhaps no group of animals has received such marked additions to its ranks through the deep-sea dredging expeditions. There was a time, and that not long ago, when we remember that the prevalent idea was that in this class new species were scarcely to be expected to turn up. Alphonse Milne-Edwards' report, of which the first part only is published, treats of the Brachyurous Decapods and of a portion of the Macrura. Many new genera and species are described, and several are figured. One very remarkable new genus, Coryeodus, is formed to receive a what mutilated example, which however exhibits different from any known Crustacea, belonging apparently the family Dorripedæ. Its carapace is globular, and connected to (coudée) the sternal plastron and between insertion of the articulations of the first and those of the pair of feet there is to be found a considerable space. very interesting new genera belonging to the Paguridæ scribed. Among the new species of the Galatheidæ no less than eleven belonging to the genus Munida; and genus allied to Munida, Galathodes is described with species. It is evident that the number of species belonging the Crustacea have been very largely increased by the sea exploration carried on by the United States Coast steamer *Blake*.

Food of Birds, Fishes, and Beetles.—The State Legislature of Illinois authorised at its last session an investigation the food of the birds of the State, with especial reference agriculture and horticulture, and a similar investigation of food of the fishes, with especial reference to fish-culture. result several Bulletins have been issued from the State Laboratory of Natural History, of which the last just received contains a report on the food of fishes by S. A. Forbes, director of the Laboratory, the class especially reported on the Acanthopteri, and another on the food of birds by the same. A very interesting series of notes on the food of predaceous beetles, by F. M. Webster, is added. Many species are found to be vegetarians, sometimes doing the growing crops a great deal of mischief.

Physiological Significance of Transpiration in Plants.—Prof. Weiss concludes from experiments (Vienna Acad. *Anz.*) that transpiration is only prejudicial to the functions of plants, excepting the process of lignification of cell-walls, which it favours; hence it is to be regarded as a necessary evil for plants. Prof. Weiss also obtains striking evidence in favour of Wiesner's theory of heliotropism; and he considers prove that through transpiration certain inorganic constituents the ground are carried to plants in excess, and are got rid on the fall of leaves in autumn, and consequently that transpiration is also the cause of the influence exercised by the nature the ground on the quantitative composition of the ashes plants. The view that the stronger growth of non-transpiring plants is due to mere expansion of cells without simultaneous over-production of organic substances, is controverted.

Signs of Death.—Observations with regard to the manifestations of life in animals variously killed have lately made by Drs. Verga and Biffi (*Real. Ist. Lomb. Rend.*). The following conclusions are arrived at:—1. In the higher animals, when sensibility, circulation, and respiration have ceased, the life of histological elements of the nervous centres especially of the ganglionic system and the spinal cord, remains for a short time. 2. Contraction of the pupil and of the eyelids are effects of this reduced latent life, and more remarkable effects, in guinea-pigs, rabbits, and cats, are the constant and uniform movements of inward curvature, which have the significance of respiratory efforts, presented under like conditions in the dog and the ass. 3. These movements appear in the same whether drowned in water, or hung, or bled to death. 4. To indicate the point beyond which the organism loses the power of recovery.

Classification of Statures.—In view of the increasing need of exactness in anthropological descriptions, Prof. Bertillon has lately proposed in the Lombard Institute a system of classification of human statures. He first constitutes three divisions, denoting by the terms *mesosoma*, *megasoma*, and *microsoma* medium, high, and low stature respectively. At the ends of each series are added divisions for gigantic and dwarfish stature, *gigantosoma* and *nanosoma*. Each of these five classes is divided into three parts, on this plan: *medium mesosoma*, *hypermesosoma*, and *hypomesosoma*. To attach numerical values to all these fifteen divisions is more difficult. The author makes 2·00 metres the division between very high and gigantic stature, and gigantosoma ranges from that point up to 2·51 m. or more (hypergigantosoma). On the other hand 1·25 m. is made the limit between very low and exceptionally low stature; and nanosoma ranges from this to 0·74 or less (hyponanosoma). Medium stature (mesosoma) ranges from 1·60 m. to 1·70 m.

Equus Prjevalski.—The St. Petersburg Geographical Society has just published a pamphlet, by M. Poliakoff, on the

species of wild horse discovered in
1 by hunters who were sent from the
full and skin were sent to the St.
cimens. M. Poliakoff discusses at
new species of horse to our domestic
ensor with drawings of the new horse
es.

REMOVE.—Many of our readers will
health and wonderful activity of this
from the annual address of the presi-
ty of Edinburgh, as published in the
Society's *Transactions*, we learn that
n was the faithful custodian of that
, which, among naturalists, has long
pellation of "Granny," and which,
her fifty-second if not her fifty-ninth
et ceased to people the waters with
th day of March, 1879, to the 4th day
r, on which occasion the last official
ie has given origin to twenty-seven
ng to her prolific powers in 1857, for
rear she gave birth to no less than 240
have put Priam himself to shame,
and taxed all the energy of all the
nd its surrounding districts. She was
North Berwick by Sir John Dalzell,
ded over to the care of Prof. John
s M'Bain; he on the prospect of his
to find a proper guardian for such a
he spoke declined to undertake so
t last Mr. Sadler, the curator of the
at Edinburgh, cordially responded to
heard of the old lady was doing well.

PHICAL NOTES

eographical Society on March 14 Mr.
Livingstonia, read a paper on Lake
te to the Lake-region of Africa. In
ns he remarked upon the fact that,
miles in length, no fewer than seven
ken on one side only, all belonging to
ud that natives from the south end
t the north end. He dwelt upon the
a missionaries enjoyed for performing
exceedingly small cost, though their
n from doing very much. Mr. Stewart
t of his journey up the western side of
lake and thence to Tanganyika and
ed one stream, the Mera, which he
one of the most remote of the sources
art concluded by stating that he was
Lake Nyassa, where he hoped to have
his geographical work in opening a
ake Tanganyika.

bers of several geographical journals
number of *Petermann's Mittheilungen*
scribes his journey, in considerable
n 1878. To accompany a map of the
Herr H. Wichmann summarises the
ave on that region. M. Sibiriakoff
he *Oscar Dickson* to the mouth of the
number contains the geographical
r, besides the usual monthly summary.
he Berlin Geographical Society Herr
aper gives some valuable directions for
up of languages. Herr K. Himly has
the forms of Turkish, Mongolian, and
n books of geography. Herr Gustav
long paper some of the scientific results
ition to the Rio Negro in Patagonia,
tion on a large scale of Dr. Kiepert's
ries in the Balkan Peninsula.—In the
same Society is a paper by Herr K.
s and their exploration, and some
thickness of the ice formed each year
ad its connection with Arctic tempera-
of vol. iv. of the *Deutsche geographische*
s a long paper by Dr. Lindemann on
the woods of the Bavarian Spessart, and by the same author a summary of recent Arctic work.—To the December number of the *Bulletin* of the French Geographical Society M. De Castries contributes a paper on the region of the Wed Draâ; M. Ch. Velain, geological notes on Upper French Guiana; and M. H. Duveyrier, on the question of the sources of the Niger.

DR. RAE sends us the following extract from a letter to him by Capt. Howgate, dated Washington, March 4, 1881:—"I write . . . to tell you that Congress has given the appropriation asked for the continuance of our work and Lady Franklin Bay, and also for an expedition *via* Behring Strait—ostensibly to look after the *Jeannette*, but also to prosecute the work of discovery in that direction. In addition to this it is proposed that the Signal Service will this year establish the Point Barrow station, making a noble programme of Arctic work for the United States, and one in which I take just pride, for it is the direct result of my persistent work, since 1877, in raising public interest in the cause."

THE preparations for the commencement of the survey of Eastern Palestine are now complete. The War Office have granted to the Committee of the Palestine Exploration Fund the services of Lieut. Conder, who executed most of the survey of Western Palestine, and Lieut. Mantell, both of the Royal Engineers. The party will include the two non-commissioned officers (now both pensioners) Black and Armstrong, who first went out in the year 1871. Lieutenants Conder and Mantell started for Beyrout on Tuesday evening, March 15, and the men will follow with the instruments. The work will be commenced in the north—the land of Bashan.

FROM a Buenos Ayres paper we learn that the long-promised exploring expedition to Neuquen, the most fertile spot perhaps in all South America, and part of the territory secured by General Roca's memorable expedition, has at last started, and important results are expected from it. This territory lies along the foot of the Andes, is watered by innumerable streams flowing from the great range into the Rio Neuquen, one of the two rivers which form the Rio Negro, and presents facilities for agriculture unknown in any other part of the Republic.

THE current number of *Les Missions Catholiques* contains a long letter from Père Schmitt, written from Mboma on the Lower Congo, in which he describes a journey lately made to the foot of the Yellala Falls. He paid a visit to the station of the Livingstone (Congo) Inland Mission at Matadi or Matavi, which is situated on the left bank of the Congo, opposite Mr. Stanley's settlement at Vivi. Owing to the whirlpools in the river, landing at Matadi was accomplished with great difficulty. From Père Schmitt's account, the spot hardly appears to have been well chosen, being a melancholy sort of place, covered with rocks, as its name imports. The mission establishment consists of five or six tents, the interior of which reminded the visitor of a bazaar. On the return journey Père Schmitt spent a few days at Noki, where he had an opportunity of collecting information respecting the Congo region from the son of the king, who had been educated at St. Paul de Loanda.

ACCORDING to the *London and China Express*, the sole obstacle to the contemplated maritime surveying operations in China and Japan, under the direction of the United States Hydrographic Office, has been removed by the consent of the Russian Government to the occupation of an astronomical station at Vladivostock by United States naval officers. They are to proceed there at once, and by telegraphic exchange of time signals, working from Vladivostock through Japan and China to Madras, will determine with great exactness the longitudes of Yokohama, Nagasaki, Shanghai, Amoy, Hong-kong, Manila, Saigon, and Singapore.

THE Wellington correspondent of the *Colonies and India* states that the New Zealand Government have just succeeded in acquiring a large tract of land at Rotorua, in the famous Hot Lake district, every acre of which the Maoris have hitherto jealously preserved. Even now tourists from all parts of the world visit this wonderful and beautiful district, but, when it is made more accessible, it is thought that Rotorua will become a great sanatorium for India and the colonies.

KING OSCAR of Sweden has just conferred decorations on Prof. Virchow, Dr. Nachtigal, and Herr William Schoulank, in recognition of their services in the cause of geographical discovery and commerce.

DR. HAYOT has been deputed by the French Minister of Marine to explore the upper part of the Niger.

ON THE CONVERSION OF RADIANT ENERGY INTO SONOROUS VIBRATIONS[1]

MESSRS. GRAHAM BELL and Sumner Tainter (American Association for the Advancement of Science, Boston, August 27, 1880) have shown that under certain conditions intense rays of light, if allowed to fall with periodic intermittence upon thin disks of almost every hard substance, will set up disturbances in those disks corresponding to this periodicity which result in sonorous vibrations. Mr. Bell (*Journal* of the Society of Telegraph Engineers, December 8, 1880) has subsequently shown that such effects are not confined to hard substances, but that they can be produced by matter in a liquid or gaseous form.

These discoveries have elicited a considerable amount of interest, and have led to the inquiry whether the sonorous effects are due, as the discoverers themselves surmised, to *light*, or as the president of the Royal Society, Prof. Tyndall, and others have suggested, to radiant *heat*.

Messrs. Bell and Tainter have partially answered this question by showing that the disturbances are not necessarily due to light, for they found that sheets of hard rubber or *ebonite*—a substance opaque to light—do not entirely cut off the sounds, but allow certain rays to pass through, which continue the effect. M. Mercadier, who has studied the subject with great care (*Comptes rendus*, December 6, 1880), has shown that the effects are confined to the red and ultra-red rays. Moreover Mr. Bell has shown that gases, such as sulphuric ether, which Prof. Tyndall has proved to be highly absorbent of heat rays, while they are transparent to light rays, are remarkably sensitive to this intermittent action. Dr. Tyndall has more recently read a paper before the Society (*Proc.* Roy. Soc., January 3, 1881) proving that these sonorous effects are a function of all gases and vapours absorbing radiant heat, and that the intensity of the sounds produced is a measure of this absorption.

The negative proof of Messrs. Bell and Tainter can be rendered positive if it can be shown that ebonite is *diathermanous*.

By very careful experiments made upon the diathermancy of different materials, ebonite proved to be as diathermanous as rock-salt.

It is therefore clear that the sonorous vibrations of Bell and Tainter are the result of disturbances produced by some thermic action rather than by any luminous effect.

Now the questions arise, Is this thermic action expansion and contraction of the mass due to its absorption of heat? Or is it a disturbance due to molecular pressure similar to that which produces the rotation of the radiometer? Or is it due to some other cause?

The argument against the first assumption when applied to hard disks is that *time* is a material element in such actions, and that the rate of cooling of warmed diaphragms is too slow to admit of such effects. Lord Rayleigh (NATURE, January 20, 1881) has questioned the validity of this argument, and has shown that if the radiating power of the body experimented on were sufficiently high a slow rate of cooling would be favourable to rapid fluctuations of temperature. It became desirable to test this point experimentally. Very delicate apparatus was constructed for the purpose.

Heat from various sources and at various distances, from bright lime-light to dull heat from hot metallic surfaces, was allowed to fall through rotating vanes intermittently on different bodies; but notwithstanding every precaution, and the many materials used, not more than six interruptions per second could be produced, although the system was beautifully sensitive to the smallest changes of temperature.

It was evident from these experiments that the sonorous effects of hard disks could not be explained by the change of volume due to the impact of heat rays and their absorption by the mass of the disk.

Is the action then due to molecular pressure similar to that which produces the rotation of the radiometer?

It is quite true that the radiometer effect is one visible only in very high exhaustions, but Mr. Crookes (*Phil. T* Part i., § 220) detected "the existence of mole when radiation falls on a black surface in density."

Whenever radiant energy falls on an absorbent such as a disk of blackened wood, its wave-leng

[1] Abstract of a paper by Mr. William Henry Preece, re Society, March 10.

or lowered, and it is converted in thermometric hea molecules of air striking this warmed surface acquire hea move away from it with increased velocity, and as actio reaction are always alike in moving away, they give the "kick." Since there is no such action on the other side disk, there is a difference of pressure between the tw which gives it a tendency to move away from the sou energy. The effect is very much smaller in air at ve pressures than in air at a very low vacuum, becaus former case the mean free path of the molecules is very and the rebounding molecules help to keep back the slowly approaching molecules. Nevertheless, molecular is experienced, and if of sufficient magnitude and mas ought to produce sonorous vibrations. It seemed probab the element of time does not enter here so prominen the previous case, for the radiometer effect is a mere action of the disk, and not one affecting its mass. It was hoped that the retarding effects would be eliminate the sonorous action, therefore, be due to a radiometer act difference of effect would be observed if the side of *exposed* to the source of energy be either blackened by black or camphor carbon, or if it be polished or whitene

An apparatus was constructed similar in principle described by Messrs. Bell and Tainter.

An ebonite disk well blackened on one side when expo the intermittent rays was found to produce sounds, w similar ebonite disk equally well-whitened, gave slig intense sounds. A zinc disk blackened gave weak sounds a similar disk polished gave sounds much weaker. A mic blackened gave scarcely any sounds at all, while a clean disk gave slightly better sounds.

These effects were produced many times and on occasions, and they were so unsatisfactory as to throw the accuracy of the radiometer explanation. They were decided as theory led one to anticipate. The effects by the zinc disk, though very weak, favoured the theory given by the mica disk completely refuted it; while those by the ebonite disks were almost of a neutral character.

The question occurred whether in Bell and Tainter's ments *the disks vibrated at all*.

A delicate microphone was fixed in various ways on or holding the disks. Although the sounds emitted in the tube were quite loud, scarcely any perceptible effect was on the microphone. Had the disk sensibly vibrated, tions must have been taken up by the case. A mic never fails to take up and magnify the minutest mec disturbances.

It was thus evident that the disk did not play a prime this phenomenon, but that the result might be due wh expansion and contraction of the air contained in the behind the disk.

With a new clean case and an ebonite disk the sonorous were feeble, but if a lens were placed close in fron ebonite disk, so as to make a second air space in fron disk, the sonorous effects were magnified considerably.

The ebonite disk was fitted with an extremely delicate phone, which in this case gave good indications upon phone, but whether the vibrations were the result vibrations of the disk itself, or of the air in which the mic was placed, was doubtful.

If the lens were removed and the disk left supported any air cavity, either behind or in front of it, *no perceptible could be obtained*, proving that the effects were really due vibrations of the confined air, and *not to those of the d* was therefore determined to dispense with the disk alto The disk was therefore removed, the lens remaining sonorous effects were *nil*.

Another case was tak out the disk, but the ef results which had ye between the one case blacked in the interio Hence the former c h when clean it g phor smoke, it g ceed. It was t assisted by coat absorbent su phor. It this pheno

ed from the front of the case, and it
glass plate (1·5 millims. thick); the
they gradually ceased on gradually
g of the case, so as to give the air

ced by a heavy rigid plate of rock-salt
ounds were equally loud. The plate
paper. The sounds were very faint,
eplaced by thin cardboard, and the

ident that these sonorous vibrations
he contained air, and not to those of
tally improved by the removal of the
s is materially assisted by lining the
pace with an absorbent substance;
the heat rays that pass through; and
e rays are cut off from the air cavity
gm.
vn in the paper already referred to,
ded actively to these intermittent
e-ounce glass flask was taken and
beams. No sound was produced.
water-vapour by pouring a small
d warming it in a flame; fair sounds

th the dense smoke from burning
ere intensified considerably.
glass flask was taken. When clear
hen filled with tobacco-smoke fair
h heavy camphor smoke very loud
side of the flask was blackened on the
aining clear. On exposing the clear
s were obtained, but on exposing the
were produced. The flask was
one side only. When the blackened
sounds, and when it was away from
were heard. When the flask was
ared. A thin glass plate was now
placed in front of the case. When
de *no sounds were obtained*. When
side good sounds were the result.
the sounds became still better. An
eated. When the blackened surface
re obtained. When the blackened
sounds were the result.
result, several experiments were now
r of opaque and transparent bodies,
ule in the previous experiments the
blackened surface faced the interior,
result produced, *viz.*, the greatest
the blackened surface was on the

s then made, from which it appeared
have in an opposite way to opaque
n be rendered athermanous and silent
ait sufficiently thick. Zinc, copper,
norous effects by a proper disposition
ese latter cases may be due either to
to a radiometer effect, though very
ay be the result of conduction through
, that is, radiant heat is reduced to
rption by the carbon deposit on the
s heat is transmitted through the disk
nt gases in the interior.
e made whilst fully establish the in-
e of conduction, and that the black-
e body like zinc acts as though the
ferred to the outside surface of the

and dimensions were now tried to
Tainter's observations on tubes. They
clory sounds when the intermittent
e interior of the tubes, which were
fied by blackening their interiors and
a glass plate.
is a time element, and that the loud-
pends upon the rapidity with which
absorbs the degraded energy, but upon
gives up its heat to the sides of the
. Though the pitch of the maxi-

mum note varied with the cavity and the amount of radiant heat transmitted, its quality never varied, notwithstanding the great diversity of materials used as diaphragms.

Since these sonorous effects are due to the expansions of absorbent gases under the influence of heat, and since wires are heated by the transference of electric currents through them, it seemed possible that if we inclosed a spiral of fine platinum wire in a dark cavity, well blacked on the inside, and sent through it by means of the wheel-break, rapid intermittent currents of electricity from a battery, heat would be radiated, the air would expand, and sounds would result. This was done, and the sounds produced were excellent. In fact, with four bichromate cells sounds more intense than any previously observed were obtained.

Furthermore it was evident that if the wheel-break were replaced by a good microphone transmitter, articulate speech should be heard. This was done, and an excellent telephone receiver was the consequence, by means of which speech was perfectly reproduced.

The explanation of these remarkable phenomena is now abundantly clear.

It is purely an effect of radiant heat, and it is essentially one due to the changes of volume in vapours and gases produced by the degradation and absorption of this heat in a confined space. The disks in Bell and Tainter's experiments must be diathermanous, and the better their character in this respect the greater the effect; remove them, and the effect is greater still. Messrs. Bell and Tainter (*Journal* of Society of Telegraph Engineers, December 8, 1880) showed that the sounds maintained their *timbre* and pitch notwithstanding variation in the substance of the disk, and M. Mercadier found that a split or cracked plate acted as well as when it was whole. These facts are consistent with the expansion of the contained air, but not with any mechanical disturbance of the disks. Moreover M. Mercadier showed that the effect was improved by lampblack, but he applied it in the wrong place.

The disks may, and perhaps do, under certain conditions, vibrate, but this vibration is feeble and quite a secondary action. The sides of the containing vessel must possess the power to reduce the incident rays to thermometric heat, and impart it to the vapour they confine, and the more their power in this respect, as when blackened by carbon, the greater the effect. The back of the disk may alone act in this respect. Cigars, chips of wood, smoke, or any absorbent surfaces placed inside a closed transparent vessel will, by first absorbing and then radiating heat rays to the confined gas, produce sonorous vibrations.

The heat is dissipated in the energy of sonorous vibrations. In all cases, time enters as an element, and the maximum effect depends on the diathermancy of the exposed side of the cavity, on its dimensions and surfaces, and on the absorbent character of the contained gas.

THE EARTHQUAKE IN ISCHIA

THE Island of Ischia, the Pithecusa of the ancients, is some twenty miles in circumference, and appears to be the continuation of the north-western boundary of the Gulf of Naples. It consists of an old volcanic mountain sloping down on all side to the sea. The southern rim of the old crater has been remove by denudation, leaving the northern as a curved serrated ridge, forming the peak of Monte Epomeo.

Situated on the southern slopes of the island are only a few and unimportant villages.

Going from east to west along the northern slope we have first the capital Ischia, then we encounter the great trachytic lava stream which issues laterally from the slope of Epomeo, and after a course of two miles entered the sea, forming a promontory. This is the so-called lava Del' Arso, of A.D. 1302. Next are encountered two very fresh-looking craters, from which lava streams have flowed. Then we come to Casamicciola, a small town of about 4000 inhabitants, to the north-west of which is the village of Lacco Ameno. At the eastern end of the island is the town of Forio.

The district in which are situated Casamicciola and Lacco is thus bounded on the north by the sea, on the south by the ridge of Monte Epomeo, on the west by a spur stretching from the latter into the sea, forming the Punta Cortiacchio, and on the east are the two hills called Monte Rotaro and Montagnone, the new-looking craters already spoken of.

It is worth observing that from this side of the island the four or five historic eruptions have occurred, and all the principal thermo-mineral springs are confined mostly to this district.

It is at this very spot that the late earthquake has taken place, resulting in the total destruction of Casamicciola, with the exception of the hotels, baths, and a few well-constructed private houses. A hundred and twenty bodies have been excavated, and they are not all, besides 160 seriously wounded. At the village of Lacco thirteen houses have fallen, and five deaths are reported.

On March 4, at five and a half minutes past one p.m., a terrific shock shook the whole island, but its maximum intensity was at this point leaving Ischia and Forio almost uninjured, together with the villages on the opposite side of the mountain.

There was but a moment of premonitory trembling, when the terrific blow shook the houses about the ears of their inhabitants. The corpse of the shoemaker was found in his usual position, with the last between his knees, and we saw the corpse of a woman with the half-finished stocking in her hand and the needle in its sheath. The two cases show the suddenness of the catastrophe.

The first shock was described as a sudden blow beneath the feet, followed by a series of undulations, which appear from accounts to have radiated from a point which I shall immediately describe. This was followed shortly by faint vibrations, accompanied by loud subterranean thunder, such as was heard in the slight earthquake of last July.

On visiting the island a few hours after we were struck by the severity of the shock and by its extremely limited area. Following the methods adopted by our eminent countryman Mr. Mallet, F.R.S., in his investigations of the great Neapolitan earthquake of 1857, we have come to the conclusion that the undulations occurred in a series of closed curves radiating from a point which must have been situated about a quarter of a kilometre to the south-west of the upper town, that is in the direction of Lacco.

It is interesting to note that the seismographs at Naples and Vesuvius were not at all affected by the earthquake. This led Prof. Palmieri to conclude from the extremely local effects produced that the phenomenon was due to the excavation and removal of matter by the mineral springs and the collapse and falling in of the superincumbent ground. It seems difficult to satisfy oneself with the theory of my respected teacher and friend Prof. Palmieri for the following reasons :—

1. The collapse of earth in Cheshire in no way produces effects at all similar or equivalent to those under consideration, and yet the amount of salt in solution removed is equal to much more solid matter than is removed by the dilute mineral waters of Ischia which are also small in quantity. Landslips like that of Lyme Regis are quite incomparable in effects to the present case.

2. The waters that issued immediately after the disaster were as usual clear, and flowed at the same rate. If this explanation was tenable, then the collapse of the earth should have forced out a large body of water and vapour and have rendered the former turbid and muddy. Such however was not the case.

3. The disturbance in Ischia was coincident with the seismic movements that were felt in various parts of Europe from the 2nd to the 5th of March, and which was severe throughout Northern Italy.

We know from the following facts that Ischia cannot be reckoned amongst extinct volcanoes. The great number of fumaroles and thermo-springs that exist on its surface ; the sand on the sea-shore in some parts is so hot a few inches from the surface that the hand cannot be borne in it ; the continual seismic disturbances to which it was and is subject—all point to the conclusion that there still exists igneous matter not far from the surface.

The seismic waves of the beginning of March causing increased tension in the igneous matter through which they travelled would tend to rupture the superficial crust at its weakest point ; the Island of Ischia presents to us such suitable conditions, and the volcanic matter, vapour, or lava may by those means have endeavoured to force its way towards the surface.

The formation of a fissure, together with the blow that would be produced by the immediate falling of such, would explain the phenomena. Much the same results occur from the formation of a dyke in an active volcanic mountain ; in fact the conditions may be looked upon as analogous.

Although lava has failed to reach the surface on the present occasion, a repetition may be sufficient to produce an eruption such as has often occurred at this spot. We may look for homologues of the present earthquake in that of A.D. 63, preceding the outburst of Vesuvius in 79, or those that destroyed Pozzuoli and its neighbourhood immediately before the formation of Monte Nuovo, but which were not felt at Naples.

The fact that the undulations produced little effect on the southern side of the island shows the extreme thinness of the earth-crust at this spot ; the weight and bulk of the mountain configuration acting as deterrent agents to the propagation of the seismic undulations to any great distance. The earthquakes in Ischia have at times been very disastrous, compelling even Greek colonies to forsake the island. There is generally a slight shock about once a year, nearly always accompanied by subterranean thunder. These have sometimes caused ruin, as on February 2, 1828, when three or four houses fell and some thirty people were killed. The details of the observations being made will be published as soon as they are formulated.

It is an interesting fact that since writing the above, on comparing notes with Signor P. Franco, my colleague, who our observations were quite independent and unknown to other, yet we have arrived at exactly the same conclusions almost every detail.

H. J. Johnston-Lavis

UNIVERSITY AND EDUCATIONAL INTELLIGENCE

Oxford.—The following notice respecting scholarships Natural Science has been published by Merton College :—

There will be an election in June next to one (or two) Physical Science Postmastерships.

The examination will begin on Tuesday, June 28 ; it will be held in common with Magdalen College, and at the same time and place. Candidates may give in their names at either College, but all will be regarded as standing at both, unless special notice is given to the contrary. In the event of election a candidate will be requested to state which College he would prefer. The Postmasterships are of the annual value of 80*l*., and are tenable for five years from election, provided that the holder does not accept or retain any appointment incompatible with the pursuance of the full course of University studies. After two years' residence the College may raise, by a sum not exceeding 50*l*. per annum, the Postmastership of such Postmasters as shall be recommended by the Tutors for their character, industry, and ability. Candidates for the Postmasterships, if members of the University, must not have exceeded six terms of University standing, but there is no limit of age. The subjects of examination will be Chemistry and Physics. There will be a practical examination in Chemistry. Candidates will have an opportunity of giving evidence of a knowledge of Biology ; but it must be borne in mind that in such cases the examiners will look for evidence of an acquaintance with the principles of Chemistry and Physics at least equal in extent to that which is required in the Preliminary Honour Examination in the Physical Science School. A paper will be set in Algebra and Elementary Geometry (Books I.-VI.), and a Classical paper of the standard required by the University for Responsions.

Magdalen College has published the following notice respecting Natural Science Scholarships (Demyships) :—There will be an election at this College in June next to not less than three Demy-ships, of which one at least will be Mathematical, one at least in Natural Science, and the rest Classical. No person will be eligible for the Demyships who will have attained the age of twenty years on October 10 next. The stipend of the Demyships is 95*l*. per annum, inclusive of all allowances : and the are tenable for five years, provided that the holder does not accept or retain any appointment which in the judgment of the electors will interfere with the completion of his University studies.

The Oldham Lyceum and Science and Art Schools, opened by Lord Derby last Thursday, seems to be a handsome and useful building, and under Mr. Phythian's superintendence we have no doubt much good work will be done in the future as in the past. Chemical and physical laboratories and other arrangements for scientific work have been provided for.

'FIC SERIALS

4, March, 1881.—D. S. Jordan and
ns on the salmon of the Pacific.—J.
y and development of Agalma, part
tion of agriculture to science.—Wm.
ena in the Yellowstone Park.—E.
e's notes on the breeding of some

di Scienze e Lettere. Rendiconti,
of observations on the amplitude of
gnetic needle, made in 1880, at the
lian, by S. Schiaparelli.—On Prof.
Mathematics, by the same.—Some
its theory, by Prof. Serpieri.—On
the southern Alps, by Prof. Tara-
of true death, by Doctors Verga and
ion in the bottom of the eye and in
through death by hanging, by Prof.

ungen der naturf. Gesells. zu Freiburg
80.—On the optical structure of ice,
haviour of crystals in solution that
ation, by the same.—On torsion, by
f vibration of plucked and rubbed
—Contribution to a knowledge of

AND ACADEMIES

LONDON

.—A paper by C. Greville Williams,
xction of Sodium upon Chinoline."
historical sketch of what he had
ject, calls attention to the fact that
line to give a red crystalline hydro-
reaction. He also states further on
chlorate is so brilliant that the finest
comparison. His most successful
n chinoline purified by conversion
. The base so prepared is almost
ow with extreme slowness as com-
ned without that precaution. On
m, converting the resulting purplish
rating the scarlet crystals by filtra-
pitating with platinic chloride, the
most conspicuous being a salt of
1, $PtCl^4$. Sodium amalgam reacts
this appears to be the best way of
lorate of dichinoline in its greatest

line reacted on from the mother
ng-point as before the treatment with
recovered base again with sodium
ellow resinous base, instead of the
L. The author studies all the basic
hydrochlorates, and fractionally pre-
ide, and points out the remarkable
s of platinum obtained from the
hydrochlorate of dichinoline, from
om the hydrochlorate of the yellow

March 15.—Prof. W. H. Flower,
n the chair.—The Secretary read a
t had been made to the Society's
th of February, and called special
trian Camel (*Camelus Bactrianus*),
b Khan, which Col. O. H. St. John,
a its captors at Candahar and pre-
a male Wild Sheep (*Ovis cycloceros*),
, and presented to the Society by
Mr. A. G. More exhibited some eggs
se, believed to have been taken in
Tree-Pipit, taken near Dublin, this
d only doubtfully Irish. Mr. More
f the Red-crested Pochard, obtained
t record of the occurrence of this
Bowdler Sharpe exhibited a speci-
's Snipe (*Gallinago Saboini*). This
bird had been shot in July last by the Hon. W. W. Palmer at Woolmer Pond, near Selborne, Hants.—Prof. F. Jeffrey Bell, F.Z.S., read the fourth of his series of observations on the characters of the Echinoidea. The present paper dealt with most of the genera of the Echinometidæ; their systematic affinities were discussed and their relations to the Echinidæ shown to be so intimate as not to justify their separation into two distinct families.—A second paper by Prof. Bell gave the description of a new species of the genus *Mesoplita*, obtained at Samoa by the Rev. S. J. Whitmee, which the author proposed to name after its discoverer, *M. Whitmei*.—Mr. W. A. Forbes read the fourth of his series of papers on the anatomy of Passerine birds. The present communication was devoted to the consideration of some points in the anatomy of the genus *Conopophaga* and of its systematic position.—A communication was read from Prof. Newton, F.R.S., in which he proposed to substitute the name *Hypositta* for *Hyphorhyx*, which he had formerly proposed for a genus of Passerine birds found in Madagascar.—A communication was read from Mr. M. Jacoby containing descriptions of new genera and species of phytophagous coleoptera.

Physical Society, March 12.—Sir W. Thomson in the chair.—New Members: Mr. Colville Brown, Dr. J. P. Joule.—Col. Festin read a paper by Capt. Abney and himself, on the absorption spectra of organic bodies. The method of photographing the infra-red region of the spectrum gave better results for absorption than thermopile. Organic compounds were chosen as giving the larger molecules. The apparatus employed consisted of a small Gramme machine driven by a Brotherhood engine, and an electric lamp with a plexlex for shifting the negative pole so as to get the crater on one side of the other carbon point. The image of the positive pole was allowed to fall on the slit of the spectroscope; the light of the arc not being used. Three prisms were used, and a camera with a back-swing to it so as to get a considerable length of spectrum in focus. Maps of the various spectra were made with six inches of the substance examined inclosed in a glass tube. Alcohols, acids, oils, and water were examined, and gave spectra of bands and lines. When hydrogen was absent in the compound there were no lines, and the authors conclude the lines to be due to hydrogen. Oxygen appeared to obliterate the space between the lines and make it a band. The authors hope by this method to detect the radicles present in a substance. They found correspondences between some lines and lines in the solar map. Dr. Coffin said that two kinds of chloroform, apparently the same, produced different physiological results: the method might distinguish between these. Sir William Thomson thought it might throw light on the ultimate constitution of matter.—Mr. Brown read a paper on the definition of work in text-books, and gave reasons for preferring that in Rankine's books.

Anthropological Institute, March 8.—F. W. Rudler, F.G.S., vice-president, in the chair.—The election of Dr. G. D. Thane was announced.—A collection of rubbings taken from door-posts and window-frames in New Zealand was exhibited. They were chiefly interesting from the proof which they afforded of the clear influence of matted and woven materials on the ornamentation of stone architecture, a parallel to the influence of wood architecture on stone architecture pointed out by Fellows in Lycia and by Lepsius in Egypt; also from the remarkable coincidence between some of these ornamentations and the outlines on the tombstones of Mykenæ, a near approach to the triglyph in New Zealand.—A short note by Mr. S. E. Peal, on Assam pile-dwellings, was read, and was illustrated by a series of sketches by the author.—Lieut.-Col. R. G. Woodthorpe, R.E., read a paper on the wild tribes inhabiting the so-called Naga Hills on our North-Eastern frontier of India. The paper dealt only with the Angami Nagas, who, it was stated, differ from all the other hill tribes of Assam in many important particulars, such as appearance, architecture, mode of cultivation, language, and dress. In appearance they are a finer, cleaner, and better-looking race than their neighbours; they build their houses resting on the ground, and not raised on piles as all the other hill tribes of Assam (except the Khasias) do, and after a pattern not seen elsewhere. Differences in physical or topographical conditions do not account for this difference in the style of architecture, as the Angami villages are found on the same ridges as, and often not a mile from, villages constructed on the other principle. In dress the Angami differs most strikingly from all the other tribes in the kilt or short petticoat of dark cloth ornamented with rows of white cowrie

shells, the waistcloth of all other Nagas consisting only of a flap of cloth in front and behind, and often only in front. The Angamis erect tall monoliths in commemoration of the dead or of some social event. These monoliths, often of great size, are dragged up hill on sledges running on rollers. The paper was illustrated by a large collection of specimens and drawings, and also by some fine diagrams, in the preparation of which the author had been much assisted by Mr. C. Holroyd.

Royal Microscopical Society, March 9.—The president, Prof. P. Martin Duncan, F.R.S., in the chair.—Swift and Sons' new "working" microscope and fine adjustment and the "Griffith Club Portable Microscope" were exhibited.—Mr. Powell showed *Amphipleura pellucida* with the vertical illuminator, and Mr. Stephenson pointed out that the illumination was not "opaque," as supposed, but that the diatom was illuminated by transmitted light reflected back by its own under-surface.—Mr. Crisp exhibited Prof. Abbes' radiation apparatus for showing the increased amount of light emitted by a radiant in glass or balsam compared to one in air.—Mr. A. D. Michael read a paper on a supposed new species of Acarus, *Dermaleichus heteropus*, and Dr. E. Cutter's paper on a supposed Infusorian in the nasal passage in cases of catarrh was explained by Mr. Stewart and commented on by the president.—Discussions also took place on carbolic acid for mounting, and on the "Society" standard screw.

Meteorological Society, March 16.—Mr. G. J. Symons, F.R.S., president, in the chair.—Rev. A. J. C. Allen, E. Chapman, Rev. E. W. Ford, G. T. Gwilliam, H. B. Jupp, A. Ramsay, and J. Stokes were elected Fellows.—The President gave a historical sketch of various classes of hygrometers, and described about 120 different patterns; after which an exhibition of instruments was held, showing various kinds of hygrometers, and also some new instruments which have been brought out since January 1, 1880.

Victoria (Philosophical) Institute, March 21.—Mr. J. F. Bateman, F.R.S., read a paper on meteorology, in which he analysed the causes of a variation of rainfall in the United Kingdom. In the discussion special remarks were made as to the causes and effects of the almost tropical rainfall that once obtained in these islands; after which a paper on Indian rain-seedings it was announced that Prof. Balfour, F.R.S., would read a paper on the visible universe at the next meeting.

EDINBURGH

Royal Society, March 7.—Lord Moncrieff, president, in the chair.—The President read the second part of his paper on the rise of the constitutional idea. In the half-century that elapsed after the publication of Buchanan's "De Jure Regni apud Scotos," important political changes were taking place and were shaping themselves, under the skilful hand of James VI. of Scotland, especially after his accession to the English throne, towards a despotism that would place the king alongside the arbitrary monarchs of the Continent. Charles I. however lacked the kingcraft to carry on successfully this policy of diminishing the power of the Parliament; and in 1644, in the heat of the contest between King and Commons, Samuel Rutherford published his "Lex Rex," which contains the first enunciation in the English language of the true *rationale* of the British Constitution. Passing on to the time of the Commonwealth, his lordship touched on the famous controversy on the divine right of kingship between Salmasius and Milton, a controversy which was continued by Hobbes and Harrington. Lastly, the paper discussed Algernon Sidney's work on Government, which was characterised as out of sight the best and ablest of the list.—Dr. D. J. Cunningham, in a paper on the intrinsic muscles of the mammalian foot, gave an interesting account of several of the most striking modifications that occur in the arrangement of these muscles in different animals. The typical arrangement of three layers of four muscles each was found in certain marsupials, and the deviations from this typical arrangement could be grouped in two classes—those that resulted from division, and those that resulted from fusion. The peculiar modifications in the ox, horse, ape, baboon, gorilla, and man were specially referred to, many of these deviations being of the nature of degeneration or retrograde development.—Mr. A. H. Anglin communicated a paper on the expansion of rational fractions.—Dr. A. Macfarlane, in his third paper on the algebra of relationship, showed the nature of the problems that came under the scope of his symbolic method.—Prof. Tait communic
on a problem in kinetics of peculiar difficulty. C
equal masses, originally balanced on an Atwood's
set oscillating through a small arc. What is the
motion? The equations of motion are peculiarly
but may by suitable transformation be thrown into
which may be derived by simple inspection the po
that the oscillating mass moves under the action of
acceleration, so that the mixed potential and kin
tend to become altogether kinetic. When both m
oscillating, a further complication is of course intr
it is found that the mass that is oscillating through
angle is subject to a downward acceleration.

VIENNA

Imperial Academy of Sciences, March 1
in the chair.—C. Ludwig, studies made at the
Institute at Leipsic during the time of 1879-80.—
mann, enunciation of formulæ useful for determinin
of diamagnetism.—Dr. Synas Klemencic, relating
mination of the proportion of the magnetical to
unit of the intensity of circuit.—Dr. F. Streintz,
tion of water on platinum-electrodes caused by the
Leyden-jars.—E. Ratkay, on *Exoascus Wiener*
Edm. Reitlinger and Dr. F. Woechter, on the "dis
electrodes by positive electricity and explanation
of Lichtenberg.—Dr. P. Weselsky and R. Benedi
packet containing the description of some new dye
—Josef Wentze, on the flora of the Tertiary distr
Sulloditz (Bohemia), central chain of mountains.—F
on the oxidation of Borneolacetate.—E. Stefan,
brium of a solid elastic body at a different or var
ature.—Dr. Ernst. v. Fleischl, physiologico-optic
Puluj, on radiant electrode-matter (third paper).

CONTENTS

MACQUORN RANKINE'S SCIENTIFIC PAPERS. By Prof.
REYNOLDS, F.R.S.
THE FERNS OF NORTH AMERICA. By J. G. BAKER
KÖLLIKER ON ANIMAL DEVELOPMENT
OUR BOOK SHELF:—
Bulletin of the United States Geological and Geograph
of the Territories, 1879-80
Ruchonnet's "Exposition Géométrique des Propriété
des Courbes". "Éléments de Calcul approximatif"
Löwenberg's "Geschichte der geographischen Entdeck
in Alterthum und Mittelalter"
LETTERS TO THE EDITOR:—
The Tide Predicter.—Sir WILLIAM THOMSON, F.R.S.
The Magnetic Storm of 1880, August.—WILLIAM ELLIS
Oceanic Phenomenon.—Dr. R. W. COPPINGER (With I
Feeding a Gull with Corn.—W. A. FORBES
Dynamics of "Radiant Matter."—WM. MUIR
The Oldest Fossil Insects.—Dr. H. A. HAGEN
Ice-Casts of Tracks.—J. T. BROWNELL
Migration of Birds.—G. A.
Sound of the Aurora.—EDWD. ALLOWAY PAUKHURST
Tacitus on the Aurora.—R. O. S.
Aberration of Instinct.—Rev. T. H. WALLER
Squirrels Crossing Water.—FREDERICK HUBBARD; C
DUNCOMBE
THE LATE MR. E. R. ALSTON
RECENT MATHEMATICO-LOGICAL MEMOIRS. By Prof. W.
JEVONS, F.R.S.
ILLUSTRATIONS OF NEW OR RARE ANIMALS IN THE Z
SOCIETY'S LIVING COLLECTION, III. (With Illustration
METEOROLOGY IN MEXICO
ON THE IDENTITY OF SOME ANCIENT DIAMOND MINES
ESPECIALLY THOSE MENTIONED BY TAVERNIER. By V.
NOTES
OUR ASTRONOMICAL COLUMN:—
The Solar Parallax
Variable Stars
Ancient Astronomy
The Academy of Sciences, Paris
BIOLOGICAL NOTES:—
Algæ of the Gulf of Finland
The *Ilirbe* Cruise
Food of Birds, Fishes, and Beetles
Physiological Significance of Transpiration of Plants
Signs of Death
Classification of Statures
Equus Prjevalski
Sir John Dalrell's Anemone
GEOGRAPHICAL NOTES
ON THE CONVERSION OF RADIANT ENERGY INTO SONOR
TONS. By WILLIAM HENRY PERKIN
THE EARTHQUAKE IN ISCHIA. By H. J. JOHNSTON-LAVIS
UNIVERSITY AND EDUCATIONAL INTELLIGENCE
SCIENTIFIC SERIALS
SOCIETIES AND ACADEMIES

S TO "NATURE."

	£	d.
. . . . .	28	0
. . . . .	14	6
. . . . .	7	6

ed States, the Continent, and
al Union :—

	£	d.
. . . . .	30	0
. . . . .	15	6
. . . . .	8	0

DVERTISEMENTS.

12s. 6d. 0d. per Line after.

	£	s.	d.
ter Column	0	18	0
olumn	1	15	0
. . . . .	3	5	0
. . . . .	6	6	0

le to MACMILLAN & CO.
ND STREET, STRAND, W.C.

F SOCIETIES.

ONDON

DAY, MARCH 24.
resident on the Locomotor System of
s, F.R.S., and Dr. J. G. Eccles.—The
ster Museum of the Brachial and Lumbo-
C.S., and Dr. G. F. Yeo.—On the Hin-
Evening Calendar: J. N. Langley.
es, at 8.—Telegraphoscope Japan: J. Morris.
sent: H. H. Statham.
ory of the "Stone" Fossil Plant.
Development of Electrical Appliances?

F, MARCH 25.
ather and Health of London: Alex.

AY.—*On Cocoa-nuts*.—Heat the Sponge
.
and Cultivation of Land in India: Sir

DAY, MARCH 26.
ious Humorists: Rev. H. R. Haweis.
Field Club, at 7.—Hemicranion and its
A. Walker, F.L.S.—On Bockwaster
G.S.—The Development Characters of
determining the Affinities of that Group
ration and its Neighbourhood, as Visited

AY, MARCH 27.
—Chemically: Dr. Zerffi.

AY, MARCH 28.
at 8.15.—Eastern Wood and the Great

Principles involved in Electric Lighting:
On the Position of the Insurance Pres-
ers and Insurance Interests: Lambert.
Kent: S. Oliver.
AY, MARCH 29.
Blood: Prof. Schäfer.
DAY, MARCH 30.
Lighting: W. H. Preece.
DAY, MARCH 31.
sent: H. H. Statham.
AY, APRIL 1.
ning on its relation to early Civilization

DAY, APRIL 2.
ious Humorists: Rev. H. R. Haweis.

LIGHTNING CONDUCTORS.

Experience, accumulated since the time of Benjamin Franklin, proves conclusively that a Conductor made of Copper of adequate size is the best of all appliances for the protection of every description of building from the destructive effects of lightning.

NEWALL & CO.'S
PATENT COPPER LIGHTNING CONDUCTOR,

As applied to all kinds of Buildings and Shipping in all parts of the world with unvarying success; is the most Trustworthy, most Effective, and also the Cheapest Conductor ever offered to the public.

It is simple in its application, no insulators being required, and it costs only one shilling per foot for the standard size, which ensures safety in any storm.

R. S. NEWALL & CO., 155, STRAND, W.C.
35, WATERLOO ROAD, LIVERPOOL.
68, ANDERSTON QUAY, GLASGOW.
MANUFACTORY—GATESHEAD-ON-TYNE.

R. W. NEEVES,
PHILOSOPHICAL INSTRUMENT
AND
INTENSITY COIL MAKER.
PRICE LIST, FOUR STAMPS.

55, SIDMOUTH STREET, LONDON, W.C.

Liberal Terms to Science Teachers and the Trade.

THOMAS CRAMPTON (formerly of 4, Little Britain, London, E.C.), ELECTRICIANS, OPTICIANS, and PHILOSOPHICAL INSTRUMENT MAKERS. Electric Bells, New Metallic Base Pattern, Constant Batteries, Indicators, Thief and Fire Alarms, and Automatic Switches, Induction and Medical Coils, &c. Specialties. Insulated Wires of every description. Microscopic and Optical Materials. Telescopes, Opera Glasses, Microscopes, Aneroid Barometers, and Lime-light Apparatus. Illustrated Catalogue Three Stamps.
THOMAS CRAMPTON & CO., 357, HIGH HOLBORN, LONDON, W.C.
For Trade Terms send Card.

J. ORME & CO.,
(Late M. JACKSON & CO.)
MANUFACTURERS AND IMPORTERS OF
SCIENTIFIC APPARATUS
AND
CHEMICALS,
SOLE AGENTS FOR HICKLEY'S PATENT TELEPHONES,
Price 50*s.* per Pair, Cash with Order.
Price Lists sent on receipt of Three Stamps for Postage.
For Trade Terms inclose Business Card.

65, BARBICAN, LONDON, E.C.

ELECTRICAL AND SCIENTIFIC
APPARATUS.

Wholesale Manufacturer of Metallic Base Electric Bells, Electric Reversing Indicators, and Constant Manganese Batteries, Telephone Switches and Transmitters, Induction Coils and Vacuum Tubes, Terminals, Carbons, Wire and all Materials. Instruments made, repaired, or altered on the premises. Illustrated Bell List free. Complete Catalogue Two Stamps. Special Quotations to the Trade.
HENRY J. DALE, Manufacturing ELECTRICIAN and OPTICIAN,
4, Little Britain, London, E.C.

EAGLE INSURANCE COMPANY,
79, PALL MALL.
FIRE LIFE ONLY. ESTABLISHED 1807.
Accumulated Funds £1,043,527
Annual Subscribed Capital of more than £1,600,000
Report, Prospectus, and Forms may be had at the Office, or from any of the Company's Agents, post free.
GEORGE HUMPHREYS, Actuary and Secretary.

APPARATUS AND SCIENTIFIC INSTRUMENTS.
PURE CHEMICALS, &c.
PORTERS AND MANUFACTURERS.
AUG. BEL & CO.,
MAIDEN LANE, COVENT GARDEN, LONDON, W.C.
Apparatus as required by the Universities, Colleges, and Schools, always fully on hand in stock. Professor Tyrer's as recommended by Dr. Frankland. Descriptions on Application. A Liberal Discount allowed to the Trade.

W. LADD & CO.,

SCIENTIFIC INSTRUMENT MANUFACTURERS,

(By Appointment to the Royal Institution of Great Britain),

11 AND 12, BEAK STREET, REGENT STREET, W.

IMPROVED HOLTZ ELECTRICAL MACHINES. GRAMME'S MAGNETO-ELECTRIC MACHINE for Laboratory use.

PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3*s.* per oz.

Physical Apparatus of every Description.

ILLUSTRATED CATALOGUE, SIXPENCE.

PATERSON'S NEW CATALOGUE OF PHYSICAL APPARATUS.

LANTERN SLIDES for SCIENTIFIC LECTURES. Season 1880-1. Post free 6 Stamps.

Complete Sets of Physical Apparatus for Science Primers and all the Physical Text-books in use in Schools and Colleges.

Siemens and Gramme Dynamo Machines and Lamps for hire.

Schools supplied with Apparatus as per Science and Art Departments' Requirements in the Sections of Light, Heat, Sound, and Electricity.

Electric Signals for Houses, Hotels, &c., Colliery Signals, Lightning Conductors. The Gower-Bell Loud-speaking Telephone.

EDWARD PATERSON, Electrical Engineer.

SHOW ROOMS AND STEAM WORKS:—76, LITTLE BRITAIN, E.C. (late 3, Bedford Court, W.C.).

MOLISON'S HARMONOGRAPH; executes the Harmonic Curves in the most perfect manner. 15*s.* and 20*s.*

Illustrated Catalogue of Electrical Apparatus, Part 1, *post free,* 6 *Stamps. Ditto, Electric Signals, Part* 2, 6 *Stamps.*

With Illustrations and Maps, medium 8vo, 18*s.*

ISLAND LIFE:

OR, THE PHENOMENA AND CAUSES OF INSULAR FAUNAS AND FLORAS, INCLUDING A REVIEW AND ATTEMPTED SOLUTION OF THE PROBLEM OF GEOLOGICAL CLIMATES. By ALFRED R. WALLACE, Author of "The Malay Archipelago," "The Geographical Distribution of Animals," &c.

"Mr. Wallace discusses in an admirably clear and able manner the questions of geological climate and time . . . only a few of the great problems discussed in this most instructive volume—a volume that ought to interest every thoughtful While its theories are likely to meet with keen criticism from Mr. Wallace's fellow-scientists, his volume ought more than we know of to spread among the intelligent reading public a knowledge of and interest in some of the most momentous problems of our time."—*Times.*

"His wonderful grasp of detail, depth of insight, and breadth of view remind one at every turn of Darwin, with shares the honours of discovery in the theory of natural selection; but beyond this he has a lightness of touch, a beauty and an ingenuity in unravelling intricate difficulties which are all his own. . . . 'Island Life' is a work to be accepted without reservation from beginning to end. . . . Whoever reads his book must be charmed with it."—*St. James's Gazette.*

"The work throughout abounds with interest. . . . It may be read with equal pleasure by those who are already acquainted with the general principles of distribution and by those who wish for the first time to learn something about modern geography."—*Athenæum.*

"We have said enough to show that Mr. Wallace is led to discuss subjects of great interest to speculative minds. The numerous special maps 'Island Life' ought to prove as interesting as it is instructive."—*Pall Mall Gazette.*

MACMILLAN AND CO., LONDON.

SECOND EDITION,

GRIFFIN'S

CHEMICAL HANDICRAFT.

PRICE 4*s.* 7*d.* POST FREE.

A CATALOGUE OF CHEMICAL APPARATUS:

ILLUSTRATED, CLASSIFIED, DESCRIPTIVE.

Demy 8vo, 480 pp., Illustrated with 1,600 Woodcuts.

Most Complete and Cheapest List of Apparatus.

JOHN J. GRIFFIN AND SONS, 22, GARRICK STREET, LONDON, W.C.

NOTICE OF REMOVAL.

JAMES HOW & CO.,

SCIENTIFIC INSTRUMENT MAKERS,

73, FARRINGDON ST., LONDON

(LATE OF 5, ST. BRIDE ST., AND 2, FOSTER LANE).

HOW'S STUDENT'S MICROSCOPE. HOW'S MICROSCOPE LAMP.

Rock Sections and other Objects for the Microscope.

HOLLOWAY'S PILLS

THIS MEDICINE

Is a Certain Cure for all Disorders of the LIVER, STOMACH AND BOWELS. A Great PURIFIER of the BLOOD; a Powerful Invigorator of the System, in cases of WEAKNESS AND DEBILITY, and is unequalled in Female Complaints.

S. C. TISLEY & Co.

OPTICIANS,

172, BROMPTON ROAD, S

(Close to South Kensington Museum.)

THE PHONEIDOSCOPE

An Instrument for Observing the Colour-Figures of Liquid Films under action of Sonorous Vibrations,

Being a visible demonstration of the Vibratory and Molecular Motion Telephone Plate.

The PHONEIDOSCOPE, with 3 Discs, Bottle of Solution, Pamphlet, &c., in Cardboard Box, 10*s.* 6*d.*

MANUFACTURED AND SOLD WHOLESALE AND RETAIL BY

S. C. TISLEY & CO., 172, BROMPTON ROAD, LONDON.

TELEPHONIC ELECTRICITY. All Materials supplied for Experimental Purposes.

Price Lists of Electrical and Acoustic Apparatus, with Description of the Harmonograph. Post Free, 2d.

DRAPER'S INK (DICHROIC)

THE NEW BLACK INK

DIFFERING FROM ANYTHING ELSE EVER PRODUCED

Writing becomes a pleasure when this Ink is used. It has been adopted by the principal Banks, Public Offices, and Railway Companies throughout Ireland.

It writes almost instantly Full Black. | Flows easily from the Pen.
Does not corrode Steel Pens. | Blotting-paper may be applied the moment of writing.
Is cleanly to use, and not liable to Blot.

Can be obtained in London, through Messrs. BARCLAY & SONS, London Street; W. EDWARDS, Old Change; F. NEWBERY & SONS, Street; WM. MATHER, London and Manchester; J. AUSTIN & CO. Street, Liverpool; and STACY & COOK, Paternoster Row; and to all Stationers.

BEWLEY & DRAPER (Limited), Dublin.

Messrs. MACMILLAN & CO.'S PUBLICATIONS.

LACKS, BOERS, and BRITISH: a Three-Cornered PROBLEM. By F. R. STATHAM. Crown 8vo. [*Next week.*

NTHROPOLOGY: an Introduction to the Study of MAN AND CIVILISATION. By E. B. TYLOR, D.C.L., F.R.S. With numerous Illustrations. Crown 8vo. 7*s.* 6*d.*

RAPHICAL DETERMINATION OF FORCES IN ENGINEERING STRUCTURES. By J. B. CHALMERS, C.E. With Illustrations. 8vo. 24*s.*

NUAL OF ANCIENT GEOGRAPHY. From the German of Dr. H. KIEPERT. Crown 8vo. 5*s.*

HE COLLECTED WORKS OF FRANCIS SIBSON, M.D. LONDON, F.R.S., &c. Edited by WILLIAM ORD, M.D. With Illustrations. 4 vols., 8vo. £3 3*s.*

HROUGH THE RANKS TO A COMMISSION. Crown 8vo. 6*s.*

"This very interesting and indeed instructive narrative."—*Army and Navy Gazette.*

"The account of the daily routine and duties in camp are plainly written. . . . He has no stirring tales to tell; no great entures to enlarge upon; no battles to fight again; no slain to slay; but his book seems to deserve attention . . . it is a and clear account of a career not common in England."—*St. James's Gazette.*

D'C'S'LE YARNS. Including "Betsy Lee" and other Poems. Crown 8vo. 7*s.* 6*d.*

NEW AND REVISED EDITION. VOL. I. OF

HE LIFE OF JOHN MILTON. Narrated in connection with the Political, Ecclesiastical, and Literary History of his Time. By DAVID MASSON, M.A., LL.D., Professor of Rhetoric and English Literature in the University of Edinburgh. Vol. I. New and Revised Edition. 8vo. 21*s.*

ol. II. 8vo. 16*s.* Vol. III., 8vo. 18*s.* Vols. IV. and V., 8vo. 32*s.* Vol. VI., with Portrait, 8vo. 21*s.*

HE METAPHYSICS OF THE SCHOOL. By THOMAS HARPER (S.J.). In Five Volumes. Vol. II., 8vo. 18*s.* [*Immediately.*

ol. I., 8vo. 18*s.*

"We can only recommend professors, students, and cultured readers of all sorts to study it and to try to master it."—*lin Review.*

"MACMILLAN'S BIOGRAPHICAL SERIES." NEW VOLUME.

ATHERINE AND CRAUFURD TAIT, WIFE AND SON OF ARCHIBALD CAMPBELL, ARCHBISHOP OF CANTERBURY: a Memoir. Edited, at the request of the Archbishop, by the Rev. W. BENHAM, B.D., Vicar of Marden, and one of the Six Preachers of Canterbury Cathedral. With Two Portraits engraved by JEENS. New and Cheaper Edition. Crown 8vo. 6*s.*

UIDE TO THE UNPROTECTED. In Every-day Matters relating to Property and Income. By a BANKER'S DAUGHTER. Fifth Edition revised. Extra fcp. 8vo. 3*s.* 6*d.*

NGLISH MEN OF LETTERS. Edited by JOHN MORLEY. New Volume. Crown 8vo. 2*s.* 6*d.*

DRYDEN. By GEORGE SAINTSBURY.

NEW NOVEL BY HENRY JAMES, Jun.

ASHINGTON SQUARE: THE PENSION BEAUREPAS: A BUNDLE OF LETTERS. 2 vols. Crown 8vo. 21*s.*

"To me it is unquestionably Mr. James's best book. . . . It is brimful of wit and sparkle, of tact and cleverness and humour, fun, and knowledge of life and of the world, of tact, measure, and resource."—*Truth.*

NEW NOVEL, A STORY OF THE GREEK WAR.

OUKIS LARAS; or, the Reminiscences of a Chiote Merchant during the Greek War of Independence. From the Greek of D. BIKÉLAS. Translated, with Introduction on the Rise and Development of Modern Greek Literature, by J. GENNADIUS, late Chargé-d'Affaires at the Greek Legation in London. Crown 8vo. 7*s.* 6*d.*

"Mr. Bikélas is a kind of Greek Erckmann-Chatrian, he paints the manners of country people. . . . The description of the life Chios, of the approach of the Turkish Fleet, of the flight to the old defenceless tower, are most vivid and full of simple force."—*ll Mall Gazette.*

MACMILLAN AND CO., LONDON, W.C.

Every Saturday. Price 6d.

LAND

A JOURNAL FOR ALL INTERESTED IN LANDED AND HOUSE PROPERTY.

WITH

INDEX TO THE ESTATE EXCHANGE REGISTERS.

TERMS OF SUBSCRIPTION:—**One Year, 26s.** (*or by post,* **28s.**); **Half-year, 13s.** (*or by post,* **14s.**); **Quarter, 6s. 6d.** (*or by post,* **7s.**).

Printed and Published for the Proprietors by

Cassell, Petter, Galpin & Co., La Belle Sauvage Yard, Ludgate Hill, E.C.

*** *All Communications respecting Advertisements in* LAND *should be addressed to the Manager, Advertisement Department, La Belle Sauvage Yard.*

The Live Stock Jour

AND FANCIER'S GAZETTE

A Chronicle for Country Gentlemen, Breed Exhibitors.

Every FRIDAY. Price 4d.

The Journal, which is the official organ ROYAL AGRICULTURAL, SHORTHORN, SMI CLUB, BRITISH DAIRY FARMERS', ENGLISH HORSE, CLYDESDALE, and other ASSOCIATIONS stands without a rival as a Chronicle for C Gentlemen, Breeders, and Exhibitors.

Publishing and Advertisement Office:

LA BELLE SAUVAGE YARD, LUDGATE HI

Now ready, Part I. Price 2s. 6d.

(To be Completed in 48 Parts.)

Picturesque Americ

UNIFORM WITH "PICTURESQUE EUROPE."

WITH 48 EXQUISITELY ENGRAVED STEEL PLATES,

And Several Hundred Engravings on Wood,

From ORIGINAL DRAWINGS specially made for the **Work.**

CASSELL, PETTER, GALPIN & CO., Ludgate Hill, London; and all Booksellers.

Popular Issue of **The Doré Milton.**

Messrs. CASSELL, PETTER, GALPIN & Co. have arranged to publish

in Sevenpenny Monthly Parts,

MILTON'S PARADISE LOST,

With 50 Superb Full-page Illustrations

By GUSTAVE DORÉ.

To be Completed in 25 Monthly Parts at *7d.* Part I. ready APRIL 25.

*** *Prospectuses at all Booksellers', or post free from CASSELL, PETTER, GALPIN & CO., Ludgate Hill, Lon*

Price 12s. 6d.

FAMILIAR GARDEN FLOWERS. FIRST SERIES. Complete in One Volume. By SHIRLEY HIBBERD, with forty full-page Coloured Plates from original paintings by F. E. HULME, F.L.S., F.S.A.

"Refined in colouring and admirably true to Nature are Mr. Hulme's drawings. . . Mr. Hibberd tells just what is needful respecting the history and culture of each plant, and amateur gardeners will be delighted with the volume."—*Graphic.*

Cassell, Petter, Galpin & Co., Ludgate Hill, London.

A CHARMING AND USEFUL GIFT BOOK.

Now ready. Price 12s. 6d. each.

FAMILIAR WILD FLOWERS. FIRST SECOND SERIES. By F. E. HULME, F.L.S., F.S.A. series is complete in one volume, and contains forty COLOURED PLATES, with descriptive text.

"An exquisite volume. . . It is illustrated with forty plates among the most beautiful illustrations of plants which have appe popular work; and there are elegant woodcuts forming bo pieces."—*Westminster Review.*

"The coloured figures are exquisitely beautiful."—*Gardener*

Cassell, Petter, Galpin & Co., Ludgate Hill, London

Just ready, complete in Five Handsome Quarto Volumes.

Prof. Morley's LIBRARY of ENGLISH LITERATUR

Selected, Edited, and Arranged by HENRY MORLEY, Professor of English Literature at University College, London. With Illustra Original MSS. and other authentic sources, consisting of Copies of trustworthy Portraits, Sketches of Places, Contemporary Illus Manners and Customs, &c. &c.

VOL. I.—SHORTER ENGLISH POEMS. **12s. 6d.**
VOL. II.—ILLUSTRATIONS OF ENGLISH RELIGION. **11s. 6d.**
VOL. III.—ENGLISH PLAYS. **11s. 6d.**
VOL. IV.—SHORTER WORKS IN ENGLISH PROSE. **11s. 6d.**
VOL. V.—LONGER WORKS IN ENGLISH PROSE. **11s. 6d.**

"The plan of this valuable publication differs considerably from that of previous works of its class, and its survey of the field of English L is certainly *far more searching and extensive than anything to be met with elsewhere.* Among the most striking features of the contr handsome volumes are the freshness of matter selected and the intrinsic interest of the woodcuts, which are all of them authentic."—*Daily Ne*

CASSELL, PETTER, GALPIN & CO. *London.*

Printed by R. CLAY, SONS, AND TAYLOR, at 7 and 8, Bread Street Hill, Queen MACMILLAN AND CO., at the Office, 29 and 30, Bedford Street, C

City of London, and publ MAY, March 24, 188

NATURE

A WEEKLY ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
Of Nature trusts the mind which builds for aye."—WORDSWORTH

NO. 596, VOL. 23] THURSDAY, MARCH 31, 1881 [PRICE SIXPENCE

Registered as a Newspaper at the General Post Office.]

[All Rights are Reserved.

OCIETY FOR THE ADVANCEMENT OF CHEMICAL INDUSTRY.

A Meeting for the purpose of forming a Society for the Advancement of emical Industry will be held on MONDAY, April 4th, 1881, in the rooms the Chemical Society, Burlington House, Piccadilly, London, W., at 4 1.

Prof. ROSCOE, F.R.S., President of the Chemical Society, will occupy chair.

All persons interested in the Chemical Industries are hereby invited to end.

GEORGE E. DAVIS, Hon. Sec. *pro tem.*

UNIVERSITY COLLEGE, NOTTINGHAM.

The Town Council of Nottingham have resolved to APPOINT FOUR ROFESSORS as follows:—

ONE PROFESSOR who shall undertake one or more of the following bjects:—Classics, Literature, History, Political Philosophy, Moral Science; d

THREE PROFESSORS who shall each undertake one or more of the llowing Subjects:—Mathematics (including Theoretical and Applied echanics), Physics, Chemistry, Physiology, Biology, Geology.

The work of the College will be divided into FOUR DEPARTMENTS, whose rangement will depend to some extent on the subjects undertaken by the rofessors elected, but it is intended that the three Scientific Departments all severally comprehend—

1. Mathematics and Mechanics,
2. Chemistry,
3. Natural Science,

nd that the subject of Physics shall be placed as a subject of principal mportance in one or other of those Departments.

Applicants are invited to specify the subjects which they would be pre- ared to undertake. Applications for the above Appointments to be ad- ressed to the Town Clerk, Municipal Offices, Nottingham, endorsed "University College," on or before the 7th day of May next. Particulars f Salaries, Duties, and Conditions will be sent upon application to the own Clerk.

Candidates are especially requested to abstain from canvassing.

SAM. GEO. JOHNSON, Town Clerk.

Municipal Offices, Nottingham, 22nd March, 1881.

THE COUNCIL OF FIRTH COLLEGE,

SHEFFIELD, intend to APPOINT a PRINCIPAL, who shall also be Professor either in the Literary or in the Mechanical Department of the College.

These Departments will comprehend respectively the following Subjects:—

1. Classes, History, Literature, Political Economy, Moral Science.
2. Mathematics, Mechanics, Engineering, Geology, Physics.

Applicants are requested to state in which of these Departments they would be prepared to act as Professor, and which of the Subjects in that Department they would be prepared to undertake.

The Salary of the said Principal will be £500 per annum, with Half the Fees of his own Classes.

The Council will only make the Appointment in event of suitable Candidates presenting themselves.

Candidates are requested to give full particulars concerning Age, Experience, and any Academical Distinctions they may have gained, together with any other information likely to affect the decision of the Council. The names of three gentlemen to whom references may be made should be given, but no testimonials need be sent unless they are asked for.

Applications to be sent on or before the 25th day of April next, to

ENSOR DRURY, Registrar.

Firth College, Sheffield, March 24, 1881.

BROWNING'S BINOCULARS.

The "Panergetic" Opera, Field, and Race Glass,

For general use, brilliant light, extensive field of view, and sharp definition.

"Brings out figures with marvellous distinctness, and has a very large field of view, and so many advantages over the other Binoculars that we have seen, that we confidently award very high praise indeed."
Popular Science Review.

PRICE £4 10s., £5 10s., and £6 10s.

ILLUSTRATED LIST FREE BY POST.

JOHN BROWNING,

Optical and Physical Instrument Maker to H.M. Government,

63, STRAND, LONDON, W.C.

TRAVELLERS' SCIENTIFIC REQUISITES.



ANEROID BAROMETER with ALTITUDE SCALE, THERMOMETER and COMPASS in Flat Pocket Case, various Forms,

£7 7s. and £8 8s.

Price Lists of Instruments free by post.

NEGRETTI & ZAMBRA,

Opticians and Scientific Instrument Makers

To HER MAJESTY THE QUEEN,

HOLBORN VIADUCT,

45, CORNHILL, & 122 REGENT STREET, LONDON.

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 48N, Tollington Road, Holloway, London, N.

ST. THOMAS'S HOSPITAL MEDICAL SCHOOL,

ALBERT EMBANKMENT, S.E.

The SUMMER SESSION will commence on May 2nd. Students entering in summer are eligible to compete for the Natural Science Scholarships of £100 and £60 awarded in the following October.

Special Classes are held for the Matriculation, Preliminary Scientific, and 1st M.B. of the University of London.

There are numerous Prizes and Scholarships, and all Appointments are open to Students without extra payment.

Several Medical Practitioners and Private Families in the neighbourhood receive Students for residence and supervision, and a register of inspected lodgings is kept in the Secretary's office.

Prospectuses and all particulars may be obtained from the Secretary, Dr. Gillespie.

W. M. ORD, M.D., Dean.

SOLAR PHYSICS.

The following COURSE of LECTURES will be given by Members of the Committee on SOLAR PHYSICS, appointed by the Lords of the Committee of Council on Education:—

An Introductory Lecture. By Prof. STOKES, Sec.R.S. 6th April, 1881.

A Lecture on the Practical Importance of Studying the Influence of the Sun on Terrestrial Phenomena. By Lieut.-General STRACHEY, R.E., C.S.I., F.R.S. 8th April.

Two Lectures on the Connection between Solar and Terrestrial Phenomena By Prof. BALFOUR STEWART, F.R.S. 27th and 29th April.

Six Lectures on Spectroscopy in Relation to Solar Chemistry. By Mr. J. NORMAN LOCKYER, F.R.S. 4th, 6th, 11th, 13th, 18th, and 20th May.

Three Lectures on the Photography of the Infra-red of the Spectrum in its Application to Solar Physics. By Capt. ABNEY, R.E., F.R.S. 25th and 27th May, and 1st June.

The LECTURES will be delivered in the Lecture Theatre of the South Kensington Museum at 4 p.m. on the days stated above.

Admission will be by Tickets, which may be obtained, as far as there is room, on application by Letter to the SECRETARY, Science and Art Department, South Kensington, S.W.

LONDON UNIVERSITY, ARMY, CIVIL SERVICE.

Dr. R. H. JUDD, D.Sc. (Lond.), M.A. (Cantab.), High Wrangler, First Class Natural Science Tripos, late Scholar of Christ's and sometime Demonstrator of Chemistry at Caius College, Cambridge, with qualified Assistants, prepares Gentlemen in all the subjects for the above Exams.

Natural Science treated both experimentally and theoretically.

Highest Testimonials and References to present and former Pupils. A few Pupils taught by Correspondence. Special Classes now forming for Matriculation, B.A., B.Sc., and Prel. Sci.

119, Cambridge Gardens, Notting Hill, W.

ROYAL POLYTECHNIC.—CLASSES for

the Preparation of Students for University Examinations, under the direction of EDWARD B. AVELING, D.Sc., F.L.S. London University Matriculation, 1st and 2nd B.Sc., Preliminary Scientific M.B., Botany, Physiology, Chemistry. All the work practical.

B.A. (High Honours), F.L.S., requires a

SCIENTIFIC POST. Exceptional References.—Address B.A., NATURE OFFICE.

INSTRUCTION IN MATHEMATICS.—

Youths or Adults attended at their Residence, on Reasonable Terms, by a M.A. of Cambridge. Unquestionable references if required.—Address, by letter, O. P., Post Office, Turnham Green.

WANTED.—NATURE at HALF PRICE,

three or four days after publication. A Permanency probable.—Address P. E., care of Messrs. Dawson and Sons, 121, Cannon Street, London, E.C.

EVERY BOY A GEOLOGIST.

Now ready, and highly recommended, complete, price 7s. 6d.

This admirable little Work and most extraordinary Cabinet of wonderfully well-selected Natural Specimens, together with other Geological Preparations, and a powerful LENS, are calculated to start a boy thinking till he has mastered for himself no ordinary knowledge of the formation of the Earth's Crust.—THOMAS J. DOWNING, GEOLOGIST, &c., 38, Whiskin Street, London, E.C.—Catalogues free.

DIAMONDS IN MATRIX.

R. C. NOCKOLD, Diamond and Oriental Stone Cutter and Dealer, has for sale Specimens of the above; also Cut Precious Stones in all Colours.

Precious Stones valued and bought.

18, FRITH STREET, SOHO, W.

LIVING SPECIMENS FOR THE MICROSC

THOMAS BOLTON, NATURALISTS' and MICROSCOPI

STUDIO, 57, NEWHALL STREET, BIRMINGHAM

T. B. has last week sent to his subscribers the Marine Polyzo *bankia imbricata*, with drawing and description. He has also *Alcyonidium polyoum*, *Triticella pedicellata*, *Pedicellina cernua*, *eximia*, Zoëa Stage of *Carcinus mœnas*; also a very rich Colleen swimming Fresh-water Rotifers, with *Pandorina morum* and Dwarf Dutch Frogs, *Rana esculenta*, One Shilling each.

Weekly announcements will be made in this place of orders is supplying.

Specimen Tube, One Shilling, post-free.

Twenty-six Tubes in course of Six Months for Subscription

Price List of Specimens on application, with stamped addressed

Portfolio of Drawings, No. 4, One Shilling.

GEOLOGY AND MINERALOGY

Special Collections for Teachers and Students, used with great Lecturers and Teachers of Geology in Great Britain. Obtained Bronze Medals at Sydney Exhibition, 1879, also in London, 1871 and 1867.

200 Specimens in Cabinet	...	...	...	£1 1
100 ditto	ditto	...	...	1 1
50 ditto	ditto	...	...	0 10

New Lists of Collections, Apparatus, &c., now ready, and free on application to

JAMES R. GREGORY'S

Geological Museum and Repository.

88, CHARLOTTE STREET, FITZROY SQUARE

MINERALOGY AND GEOLOGY

MAGNIFICENT DERBYSHIRE FLUOR SPAR VASE, Blue Pedestal, 2ft. 8in.; Diameter 13½in. This is, with one exception, the vase of the kind known, the vein having been worked out 20 years ago.

FINE PINK APOPHYLITE, EISENROSE, CONNELLITE, SPAR, BARYTA, FAHLERZ, LIBETHENITES.

COLLECTIONS FOR STUDENTS, from £2 2s. COLLECTIONS for BEGINNERS, from 4s. BLOWPIPE CASES AND APPARATUS.

PRIVATE LESSONS AND EVENING CLASSES.

Catalogues free.

SAMUEL HENSON,

277 (*Late* 113*a*), STRAND, LONDON.

THE ZOOLOGIST:

A MONTHLY MAGAZINE OF NATURAL HISTORY.

Third Series. Edited by J. E. HARTING, F.L.S., Member of British Ornithologists' Union; contains—

Original articles by well-known naturalists in every branch of the habits of animals; arrival and departure of migratory birds; occurrence of rare birds; distribution and migration of British fresh-water fish or rare marine fish; local aquaria; British reptiles; British land- and water mollusca, with remarks on the haunts and habits of the species; other matters of general interest to those who delight in nature. Reports of the Linnean, Zoological, and Entomological Societies. Reviews of natural history books. Occasional translations from foreign works and journals of important and interesting articles in various branches of zoology. There are occasional woodcuts.

JOHN VAN VOORST, 1, Paternoster Row.

"The leading Farmers' paper."—CLARE SEWELL READ, Esq., M.P.

THE CHAMBER OF AGRICULTURE JOURNAL AND FARMERS' CHRONICLE

(PRICE 3*d.* WEEKLY).

The representative organ of the Central and Provincial Chambers of Agriculture; *gives fuller reports of the discussions and proceedings* at this extensive organisation than any other agricultural paper; pays *special attention to the treatment of Agricultural Questions by Parliament*, besides containing ample Reports of the LATEST LONDON COUNTRY CORN, CATTLE, HOP, PROVISION, and other Markets, with Original Articles on Practical Farming, the Dairy, Herd and Flock, News, Horticulture, &c., &c. It is despatched every Monday evening in time for the country post.

Terms of Subscription, payable in advance, post free:—3 months, 3s. 3d.; 6 months, 7s. 7d.; 12 months, 15s. 2d.

Published by W. PICKERING, 21, Arundel Street, Strand, London.

On the 1st of every Month, price Sixpence.

THE ENTOMOLOGIST:

AN ILLUSTRATED JOURNAL OF BRITISH ENTOMOLOGY.

Edited by JOHN T. CARRINGTON,

With the Assistance of

FREDERICK BOND, F.Z.S. | JOHN A. POWER, M.D.

EDWARD A. FITCH, F.L.S. | J. JENNER WEIR, F.L.S.

F. BUCH[illegible]

Contains Articles by well-k[illegible] all branches of Science; on Insects injurious [illegible] Habits, Life-Histories; occu[illegible] of Duplicates and Desiderata [illegible] Numerous WOODCUT ILLU[illegible] attention is given, and occ[illegible] GRAPHED PLATES.

SIMPKIN MARSH[illegible]

E INSTITUTE OF CHEMISTRY OF GREAT BRITAIN AND IRELAND.

Incorporated under the 30th and 31st Victoria, Chap. 131, Sec. 23, on October 2, 1877.

LIST OF OFFICERS AND COUNCIL.

President—F. A. ABEL, C.B., F.R.S., &c.

Vice-Presidents.

s Bell, F.C.S.
Mills, D.Sc., F.R.S.
T. Redwood, Ph.D., F.C.S.
H. E. Roscoe, Ph.D., F.R.S.
E. Frankland, Ph.D., D.C.L., F.R.S., &c.
W. N. Hartley, F.R.S.E., F.C.S.

Treasurer—C. R. Alder Wright, D.Sc., F.C.S.

Ordinary Members of Council.

Attfield, Ph.D., F.R.S., &c.
ald Campbell, F.C.S.
Dupré, Ph.D., F.R.S., &c.
. Friswell, F.C.S.
riess, Ph.D., F.R.S., &c.
V. Heaton, F.C.S.
glas Herman, F.C.S.
. Hodges, M.D., F.C.S.
id Howard, F.C.S.
E. W. T. Jones, F.C.S.
T. W. Keates.
C. T. Kingzett, F.C.S.
J. W. Kynaston, F.C.S.
F. A. Manning, F.C.S.
W. Odling, M.A., M.B., F.R.S., &c.
F. J. M. Page, F.C.S.
John Pattinson, F.C.S.
B. H. Paul, Ph.D., F.C.S.
J. Spiller, F.C.S.
T. Stevenson, M.D., F.C.S.
A. Norman Tate.
C. Meymott Tidy, M.B., F.C.S.
W. A. Tilden, D.Sc., F.R.S., &c.
R. V. Tuson, F.C.S.
A. Voelcker, Ph.D., F.R.S., &c.
W. Wallace, Ph.D., F.R.S.E.
T. Way, F.C.S.

Secretary—C. E. Groves, F.C.S. Offices—Somerset-house-terrace, W.C.

The Institute has been established to ensure that consulting and analytical chemists are duly qualified for the proper discharge of the duties they ertake by a thorough study of chemistry and allied branches of science, in their application to the arts, public health, agriculture, and technical industry. The Members of the Institute are divided into two grades, having the distinguishing ranks or degrees of Fellow and Associate respectively. In the case of a Fellow, the Council requires that the Candidate should have been admitted to the Institute as an Associate, and that since his admission for a period of three years therefrom he should have been continuously engaged in the study and practical work of Applied Chemistry in a manner ifactory to the Council.

In the case of Associates the present regulations require every applicant for admission to this grade to submit to a stringent examination in practical nistry, and to show to the satisfaction of the Council that he has passed through a course of three years' study of theoretical and analytical chemistry, sics, and elementary mathematics. An Associate must be at least 21 years of age before admission, and is not eligible for the higher rank of Fellow until nas been continuously engaged for three years in the study and practical work of Applied Chemistry, in a manner that shall be considered satisfactory by Council.

NAMES OF FELLOWS.

el, F. A., C.B., F.R.S., F.C.S., Royal Arsenal, Woolwich, S.E.
ney, Capt. W. W., F.R.S., F.C.S., 3, St. Alban's-road, Kensington, W.
croyd, William, M.Ph.S., Wharf-street, Sowerby-bridge, Yorks.
worth, Joseph J., F.C.S., Vitriol Works, near Abbey Mills, Stratford, E.
air, Alfred, 2, Route du Landi, St. Denis, Paris.
ken, A. P., D.Sc., F.R.S.E., Royal Veterinary College, Edinburgh.
en, Alfred H., F.C.S., 2, Collegiate-crescent, Sheffield.
son, R. E., 37, Lamb's Conduit-street, W.C.
ison, Henry T., Thornaby Iron Works, Stockton-on-Tees.
gell, Arthur, Ph.D., 4, Portland-terrace, Southampton.
gell, John, F.C.S., Grammar School, Manchester.
pleyard, G. C. W., 2, Gardeners' Buildings, North-road, Clayton, Manchester.
mstrong, H. E., Ph.D., F.R.S., F.C.S., London Institution, E.C.
hwell, J. R., New Basford, Nottingham.
kinson, Edmund, Ph.D., F.C.S., Portesbury-hill, Camberley.
kinson, Robert William, B.Sc., F.C.S., University of Tokiô, Japan.
tfield, J., Ph.D., F.R.S., F.C.S., 17, Bloomsbury-square, W.C.

mber, H. K., 5, Westminster-chambers, Victoria-street, S.W.
nnister, Richard, F.C.S., Laboratory, Somerset House, W.C.
rff, Frederick S., F.C.S., 100, Abbey-road, Kilburn, N.W.
rret, Edward Louis, B.Sc., F.C.S., 53, Springfield-road, N.W.
sett, Henry, F.C.S., 26, Belitha-villas, Barnsbury, N.
ynes, James, jun., F.C.S., Kingston-upon-Hull.
an, C. E., F.C.S., Brooklyn-house, Shepherd's-bush, W.
ilby, George, Midcalder, Scotland.
ll, J. Carter, F.C.S., Assoc. R.S.M., Kersal Clough, Higher Broughton, Manchester.
ell, James, F.C.S., Laboratory, Somerset-house, W.C.
ell, W. Gomm, Assoc. R.S.M., 52, Duchess-road, Birmingham.
ernays, A. J., Ph.D., F.C.S., St. Thomas's Hospital, S.E.
est, T. F., 66, Aldersgate-street, E.C.
ickerdike, William Edward, F.C.S., Surbiton-place, Blackburn.
lickerton, A. W., Christchurch, New Zealand.
ischof, Gustav, F.C.S., 4, Hart-street, Bloomsbury, W.C.
lourchier, C. E., Messrs. Birdley and Co., The Brewery, Burton-on-Trent.
lowdler, Arthur Clegg, 20, Wellington-street, Blackburn.
lowrey, James John, F.C.S., Kingston, Jamaica.
Brady, H. B., F.R.S., Hillfield, Gateshead.
Brazier, James Smith, F.C.S., University, Aberdeen.
Brock, John, British Alkali Works, Widnes, Lancashire.
Brown, A. Crum, M.D., D.Sc., F.C.S., 8, Belgrave-crescent, Edinburgh.
Brown, Adrian John, F.C.S., Burton-on-Trent.
Brown, E. Ormond, F.C.S., Royal Arsenal, Woolwich, S.E.
Brown, James Campbell, D.Sc., F.C.S., Liverpool.
Brown, Horace T., F.C.S., Burton-on-Trent.
Buch, Carl von, B.A., Laboratory, Christchurch, Oxford.
Buchanan, J. Young, F.R.S.E., 10, Moray-place, Edinburgh.
Bullock, J. Lloyd, F.C.S., 3, Hanover-street, W.
Burge, Charles H., Laboratory, Somerset House, W.C.
Burghardt, C. A., Ph.D., Owens' College, Manchester.
Butterfield, John Copa, F.C.S., 106, Queen Victoria-street, E.C.

Calderwood, John, Addiewell, West Calder, Scotland.
Cameron, Charles A., M.D., F.R.S.C.I., 15, Pembroke-road, Dublin.
Cameron, James, Laboratory, Somerset House, W.C.
Cameron, J. M., F.C.S., Glenthorne-road, Hammersmith.
Cammack, John, Shaw-street, St. Helen's.
Campbell, Gerald, F.C.S., 7, Quality-court, Chancery-lane, E.C.
Carey, [illegible] Widnes, Lancashire.
Carpenter, R. F., 56, Regent's Park-road, N.W.
Carteighe, Michael, F.C.S., 180, New Bond-street, W.
Caswell, C. B., F.C.S., 13, George-road, Birmingham.
Church, Arthur Herbert, F.C.S., Royston-house, Kew.
Clark, John, Ph.D., F.C.S., 138, Bath-street, Glasgow.
Claudet, F., F.C.S., 6 and 7, Coleman-street, E.C.
Cleaver, Edward Lawrence, F.C.S., 389A, King's-road, S.W.
Cleminshaw, Edward, F.C.S., Greenhill, Sherborne.
Cloud, T. C., F.C.S., Assoc. R.S.M., Wallaroo, South Australia.
Clowes, Frank, D.Sc., F.C.S., Newcastle-under-Lyme.
Coleman, J. J., F.C.S., 45, West Nile-street, Glasgow.
Collinge, T. A., 1, Milton-street, Rochdale.
Cooke, Samuel, M.A., College of Science, Poona, India.
Coomber, Thomas, F.C.S., 80, Kingsdown-parade, Bristol.
Corfield, W. H., M.A., M.D., F.C.S., 10, Bolton-row, Mayfair, W.
Cownley, Alfred John, F.C.S., 13, Fenchurch-avenue, E.C.
Cranston, G., Messrs. Storer and Sons, Sydney-street, Glasgow.
Criper, W. R., Assoc.R.S.M., Carew and Co., Rosa, N.W.S. India.
Crookes, William, F.R.S., F.C.S., 7, Kensington Park-gardens, W.
Crowder, W., 2A, Evering-villa, Evering-road, Upper Clapton, E.
Dalziel, J. Graham, F.R.S.E., United College, St. Andrews, N.B.
Darby, Stephen, F.C.S., 140, Leadenhall-street, E.C.
Darling, W. Howarth, F.C.S., 126, Oxford-street, Manchester.
Davies, Edward, F.C.S., Royal Institution, Liverpool.
Davies, R. Higgins, F.C.S., Rutland-road, Hammersmith, W.
Davis, G. E., F.C.S., Dagmar-villa, Heaton Chapel, near Stockport.
Davis, Henry Wilson, Laboratory, Somerset-house, W.C.
Day, James John, 18, London-street, Derby.
Deacon, Henry Wade, Appleton-house, Widnes.
De Chaumont, Francis, S.B.F., M.D., Army Medical School, Netley.
Deering, W. H., F.C.S., Chemical Department, Royal Arsenal, Woolwich, S.E.
De la Rue, Warren, D.C.L., F.R.S., F.C.S., 73, Portland-place, W.
Dent, William V., F.C.S., Royal Arsenal, Woolwich, S.E.
Dewar, James, F.R.S., Cambridge.
Dibdin, W. J., 37, St. Stephen's-avenue, Shepherd's-bush, W.
Dickinson, A. J., Neptune Tar Works, Trundley-lane, Deptford, S.E.
Dittmar, W., Anderson's College, Glasgow.
Divers, E., M.D., F.C.S., Tokiô, Japan.
Dixon, W. A., F.C.S., Chemical Laboratory, School of Arts, Sydney.
Dodd, T. H., F.C.S., Las Minas de Rio Tinto, Rio Tinto, Huelva, Spain.
Donkin, W. F., M.A., F.C.S., St. George's Hospital, S.W.
Dougall, Samuel S., Glenpark-villa, Busby, near Glasgow.
Downar, George Frederick, 1, Chapel-road, Bexley Heath, Kent.
Dreyfus, C., Clayton Aniline Co., Clayton, near Manchester.
Duncan, James, F.C.S., 71, Cromwell-road, S.W.
Dupré, Auguste, Ph.D., F.R.S., Westminster Hospital, S.W.
Dyer, Bernard, F.C.S., 17, Great Tower-street, E.C.

Early, William, Trinity College, Dublin.
Estcourt, Charles, F.C.S., St. James's-square, Manchester.
Evershed, Frank, 138, Glenarm-road, Clapton, E.

Fairley, Thomas, F.R.S.E., F.C.S., 26, East-parade, Leeds.
Farries, Thomas, F.C.S., 16, Coleman-street, E.C.
Fenton, Henry J. H., Christ's College, Cambridge.
Ferguson, John, M.A., F.C.S., University, Glasgow.
Ferguson, W. B., M.A., 2, Pensarn-terrace, Moss-lane east, Manchester.
Field, Frederick, F.R.S., F.C.S., Upper Marsh, Lambeth, S.E.
Foord, George, F.C.S., Royal Mint, Melbourne.
Foster, William, B.A., F.C.S., Middlesex Hospital, W.
Francis, Ernest E. H., F.C.S., George Town, Demerara.
Frankland, E., D.C.L., F.R.S., F.C.S., Royal College of Chemistry, South Kensington Museum, S.W.

OVER.

The Institute of Chemistry of Great Britain and Ireland (*continued*).

Friswell, R. J., F.C.S., 10, Clapton-square, E.
Fuller, William James, F.C.S., The Retreat, Sutton, Surrey.

Gale, Samuel, F.C.S., 338, Oxford-street, W.
Galloway, Robert, F.C.S., M.R.I.A., 47, Leeson-park, Dublin.
Gardner, J., F.C.S., 11, St. Paul's-Crescent, Camden-square, N.W.
Garrick, A. R., Ph.D., St. Helen's, Lancashire.
Gatehouse, James Wright, 36, Broad-street, Bath.
Gilbert, J. H., Ph.D., F.R.S., F.C.S., Harpenden, St. Albans.
Gilchrist, P. C., F.C.S., Assoc. R.S.M., 12, Well-road, Hampstead, N.W.
Gladstone, J. H., Ph.D., F.R.S., F.C.S., 17, Pembridge-square, Hyde-Park, W.
Glover, G. T., F.C.S., 30, Donegall-place, Belfast.
Gordon, Joseph Gordon, F.C.S., 20, King-street, S.W.
Graham, A. McDonald, F.C.S., 38, Albany-street, North Leith, Edinburgh.
Graham, Charles, D.Sc., F.C.S., University College, W.
Greenaway, A. J., F.C.S., 11, Pemberton-gardens, Upper Holloway, N.
Greenway, Thomas, The Sheffield Smelting Company, Sheffield.
Gregory, Henry Richard, 7, Quality-court, Chancery-lane, E.C.
Greville, H. Leicester, F.C.S., 4, Moreland-villas, Lambton-road, Hornsey-rise.
Griess, Peter, Ph.D., F.R.S., F.C.S., Burton-on-Trent.
Grimwood, R., Laboratory, Court House, Marylebone.
Grosjean, B. J., F.C.S., J. B. Lawes's Chemical Works, Millwall, E.
Groves, Charles Edward, F.C.S., Somerset-house-terrace, W.C.
Gurney, H. S. Lewis, Wilderspool, Warrington.

Hake, C. N., Albyn House, Parson's-green, Fulham, S.W.
Hake, Henry Wilson, Ph.D., F.C.S., Queenwood College, near Stockbridge, Hants.
Halse, William Edward, F.C.S., 21, Mincing-lane, E.C.
Hanbury, Cornelius, F.C.S., Plough-court, E.C.
Hannay, J. B., F.C.S., Sword-street, Glasgow.
Harcourt, Vernon A., M.A., F.R.S., Cowley Grange, Oxford.
Harland, R. H., 79, Great Tower-street, E.C.
Harkness, William, F.C.S., Laboratory, Somerset House, W.C.
Harris, F. W., L.N.W. Railway, Crewe.
Hartley, W. Noel, F.R.S.E., F.C.S., Royal College of Science, Stephen's-green, Dublin.
Hastings, Henry Mitchell, F.C.S., 54, Edith-road, The Cedars, West Kensington, W.
Heaton, C. W., F.C.S., Charing-cross Hospital, W.C.
Heddle, M. Forster, M.D., F.R.S.E., St. Andrews, Scotland.
Hehner, Otto, F.C.S., 54, Holborn Viaduct, E.C.
Heisch, Charles, City Gas Examiner's Office, 79, Mark-lane, E.C.
Helm, Henry James, F.C.S., Laboratory, Somerset House, W.C.
Henry, W. C., M.D., F.R.S., F.C.S., Hatfield, near Ledbury.
Herman, Douglas, F.C.S., Cropper's-hill, St. Helen's, Lancashire.
Heron, Francis, Laboratory, Royal College of Surgeons, Dublin.
Hewitt, D. B., Beech-house, Prestwich, Radcliffe, near Manchester.
Hibbert, Walter, F.C.S., 22, Chapel-street, Edgware-road, W.
Higgin, James, F.C.S., Woodhey, Kersall, Manchester.
Hill, Alfred, M.D., F.C.S., Birmingham.
Hill, A. Bostock, M.D., Unity-buildings, Temple-street, Birmingham.
Hills, Thomas Hyde, F.C.S., 338, Oxford-street, W.
Hodges, Frederick, Queen's College, Belfast.
Hodges, John Frederick, M.D., F.C.S., Queen's College, Belfast.
Hodgkinson, W. R., Ph.D., Newark-house, Warbeck-road, Shepherd's-bush, W.
Hoffman, G. C., 76, St. Gabriel-street, Montreal, Canada.
Holmes, John, Laboratory, Somerset-house, W.C.
Hopwood, G. Manley, F.C.S., Department of Agriculture, Melbourne.
Howard, David, F.C.S., Rectory-manor, Walthamstow, E.
Howard, T., F.C.S., 52, Swinton-street, Gray's-inn-road, W.C.
Howard, William Dillworth, Stratford, E.
Hughes, John, F.C.S., 79, Mark-lane, E.C.
Humpidge, T. S., Ph.D., B.Sc., University College, Aberystwyth.
Huntington, A. K., Assoc. R.S.M., King's College, W.C.
Hurter, Ferdinand, Ph.D., Widnes.
Huskisson, Henry Owen, F.C.S., 42, Highbury-park, N.
Huson, C. W., B.Sc., 5, York-buildings, Dale-street, Liverpool.
Hutchings, W. Maynard, Swansea Zinc Ore Co., Swansea.
Huxley, J. H., Assoc. R.S.M., Crescent-road, Sharrow, Sheffield.

Ivey, W. E., Canterbury College, Christchurch, New Zealand.

Jackson, Edgar, Assoc. R.S.M., 106, Queen Victoria-street, E.C.
Jameson, Thomas, 235, Union-street, Aberdeen.
Japp, Francis Robert, M.A., Ph.D., F.C.S., 27, Woodstock-road, Bedford-park, Turnham-green.
Jarmain, George, F.C.S., 84, Northgate, Huddersfield.
Johnson, George Stillingfleet, F.C.S., 11, Savile-row, W.
Johnson, Thomas H., F.C.S., 96, Duke-street, Liverpool.
Johnstone, W., Athenæum-chambers, King's Lynn.
Jones, E. W. T., F.C.S., Wolverhampton.
Jones, Francis, F.R.S.E., F.C.S., Grammar School, Manchester.
Jones, H. Chapman, F.C.S., 166, Blackstock-road, Highbury, N.
Jutsum, Sydney C., 14, Tredegar-street, Bow, E.

Keates, Thomas William, 10, Spring-gardens, W.
Keene, J. Boddely, 38, Hartham-road, Camden-road, N.
Kellner, William, Ph.D., F.C.S., Royal Arsenal, Woolwich, S.E.
Kendall, James Alfred, F.C.S., Silvertown, E.
Kinch, Edward, F.C.S., Tokiô, Japan.
King, John Falconer, F.C.S., Edinburgh.
Kingzett, C. T., F.C.S., 12, Auriol-road, West Kensington, W.
Kitchin, Archibald, F.C.S., 27, King-street, Whitehaven.
Knights, J. West, County and Borough Analyst, Cambridge.
Kynaston, Josiah W., F.C.S., St. Helen's, Lancashire.

Lawes, John Bennet, F.R.S., F.C.S., Rothamstead, St. Albans.
Lawson, G., LL.D., Dalhousie College, Halifax, Nova Scotia, Canada.
Leebody, J. Robinson, M.A., Magee College, Londonderry.
Legg, J. E., Grammar School, Berkhampstead.
Leibius, A., Ph.D., F.C.S., Royal Mint, Sydney.
Letts, Edmund Albert, Queen's College, Belfast.
Lewin, George, Laboratory, Somerset House, W.C.
Liveing, George Downing, M.A., F.C.S., Cambridge.
Liversedge, A., Assoc. R.S.M., University, Sydney.
Lloyd, F. J., F.C.S., 16, Barbara-terrace, Barnsbury, N.
Lott, F. E., Assoc. R.S.M., Stapenhill, Burton-on-Trent.
Loram, H. Y., F.C.S., 1, Mackintosh-lane, Homerton, E.
Louis, Henry, Assoc. R.S.M., London-road Iron Foundry, Leeds.
Edinburgh.
Lovett, William Jesse, 96, Lionel-street, Birmingham.
Lowe, Alfred John George, 167, Fenchurch-street, E.C.
Lowe, W. Foulkes, F.C.S., Assoc. R.S.M., Cambrian View, Chester.
Lucas, R., 5, Sydney-terrace, Kilburn, N.W.
Luff, A. S., 13, Lisson-street, Marylebone-road, N.W.
Lupton, Sidney, F.C.S., The Harehills, Leeds.
Lyon, Isidore Bernadotte, Grant Medical College, Bombay.
Lyon, John George, Pontefract.
Lyte, F. Maxwell, F.C.S., Cotford, Oakhill-road, Putney, S.W.

Macadam, Stevenson, Ph.D., F.R.S.E., F.C.S., Edinburgh.
Macadam, W. Ivison, F.C.S., Surgeon's Hall, Edinburgh.
Macallan, J., Laboratory, Royal College of Surgeons, Dublin.
McAlley, K., Chemical Laboratory, Falkirk, Scotland.
MacCarthy, John, Port of Spain, Trinidad.
Macdougald, G. D., 41, Reform-street, Dundee.
Mackenzie, G. S., Ph.D., 23, Deangate, Dundee.
MacNamara, J. Moore, 46, Great College-street, Brighton.
Mactear, James, F.C.S., St. Rollox, Glasgow.
Makins, George Hogarth, F.C.S., Walton-on-Thames.
Manning, F. A., F.C.S., 18, Billiter-street, E.C.
Marcet, William, M.D., F.R.S., F.C.S., Athenæum Club, Pall-mall.
Marreco, A. F., F.C.S., College of Physical Science, Newcastle-on-
Marsden, R. Sydney, D.Sc., F.R.S.E., F.C.S., Tapton Grove, Sh
Maskelyne, Nevil Story, F.R.S., F.C.S., 112, Gloucester-terrace, H
Mathew, W. E., Langer House, Felixstowe, Ipswich.
Matthey, George, F.C.S., 73, Hatton-garden, E.C.
McLeod, Herbert, F.C.S., Cooper's hill, Staines.
Meldola, Raphael, F.C.S., 21, St. John-street, Bedford-row, W.C.
Midwinter, E. J. H., Woodlands, Gloucester-road, New Barnet.
Miller, F. Bowyer, F.C.S., Royal Mint, Melbourne.
Miller, J., 381, Dobbies' Loan, Glasgow.
Mills, E. J., D.Sc., F.R.S., F.C.S., Anderson's College, Glasgow.
Mond, Ludwig, F.C.S., Winnington-hall, Northwich.
Morfit, Campbell, Ph.D., F.C.S., Melford House, Grove-end-road.
Morgan, Thomas M., Victoria College, Jersey.
Moss, John, F.C.S., Hirdir-lodge, Salisbury-park, Wrexham.
Moss, R. J., Laboratory, Royal Dublin Society, Dublin.
Morrison, R. Milner, D.Sc., 13, Douglas-crescent, Edinburgh.
Mucklow, John Davies, F.C.S., 34, Penn-road, N.
Müller, Hugo, Ph.D., F.R.S., F.C.S., 110, Bunhill-row, E.C.
Muspratt, Edmund K., F.C.S., Seaforth-hall, near Liverpool.
Muter, J., Ph.D., F.C.S., Winchester House, Kennington-road, S.

Napier, James, F.C.S., Gipping-cottage, Bramford, near Ipswich.
Neison, Edmund, F.C.S., Scientific Club, Savile-row, W.
Newlands, J. A. R., F.C.S., 18, Josephine-avenue, Brixton-rise, S.
Newlands, Benjamin E. R., F.C.S., Clyde-wharf, Victoria-dock, E.
Newth, G. S., New College, Hampstead.
Nicholson, E. Chambers, F.C.S., Carlton-house, Herne-hill.
Nicholson, Edward, M.D., F.C.S., St. Thomas Mount, Madras.
Nickels, Benjamin, F.C.S., Sudbury, Harrow.
Nimmo, James, 17, Great Tower-street, E.C.

Odling, W., M.B., F.R.S., F.C.S., 15, Norham-gardens, Oxford.
Odling, Walter, F.C.S., Burton-on-Trent.
Ogilvie, T. Robertson, F.C.S., 13, Forsyth-street, Greenock.
Ogston, George Henry, F.C.S., 3, St. James-street, S.W.
O'Keefe, C., Laboratory, Queen's College, Cork.
Ollerenshaw, Samuel, Sutton Alkali Works, St. Helen's.
O'Neill, Charles, F.C.S., 72, Denmark-road, Manchester.
O'Sullivan, Cornelius, F.C.S., 140, High-street, Burton-on-Trent.

Packer, George Smithers, F.C.S., Cambuslang, by Glasgow.
Page, David, M.D., F.C.S., Netherfield, Kendal, Westmoreland.
Page, F. J. M., B.Sc., F.C.S., Assoc. R.S.M., University College, W.
Parker, John Spear, 297, Western-road, Sheffield.
Parkinson, Robert, Ph.D., Bradford.
Patterson, T. Law, F.C.S., Belmont, Margaret-street, Greenock.
Pattinson, John, F.C.S., 75, The Side, Newcastle-on-Tyne.
Paul, B. H., Ph.D., F.C.S., 1, Victoria-street, Westminster, S.W.
Pearce, G. A., B.A., M.B., F.C.S., &c., Northumberland House, Blackheath road, Lee, S.E.
Pearce, Walter, B.Sc., F.C.S., Assoc. R.S.M., Maidenhead.
Pedler, Alexander, F.C.S., Presidency College, Calcutta.
Perkin, W. H., F.R.S., F.C.S., The Chestnuts, Sudbury.
Phillips, A. G., 20, Canning-street, Liverpool.
Phillips, J. A., C.E., F.C.S., 18, Fopstone-road, Kensington, W.
Piesse, C. H., 7, Moore-Park-Villa, Fulham-road, S.W.
Plowman, Sydney, Residences, St. Thomas's Hospital, S.E.
Pochin, Henry Davis, F.C.S., Barn Elms, Barnes, S.W.
Prévost, E., Ph.D., F.C.S., Royal Agricultural College, Cirencester.
Price, Astley P., Ph.D., F.C.S., 47, Lincoln's-inn-fields, W.C.
Price, David S., Ph.D., F.C.S., 26, Great George-street, W.
Proctor, William Wilson, 33 and 35, Side, Newcastle-on-Tyne.
Purdie, T., jun., B.Sc., F.C.S., Assoc. R.S.M., Ardenlee, Lanark.

Ramsey, William, Ph.D., F.C.S., University College, Bristol.
Reddrop, Joseph, F.C.S., London and North-Western Railway, Crewe.
Redwood, T., Ph.D., F.C.S., 17, Bloomsbury-square, W.C.
Redwood, T. Bo[illegible] S., Fairlawn, North Finchley, Middlesex.
Rennie, E. H., [illegible]-lodge, 38, Maida-vale, W.
Reynolds, J. Em[illegible] F.C.S., Trinity College, Dublin.
Reynolds, W. J., [illegible] Royal Military Asylum, Chelsea, S.W.
[illegible] road, Croydon.
[illegible]-on-Tyne.
[illegible], E.C.
[illegible]ford.

e Institute of Chemistry of Great Britain and Ireland (*continued*).

rts, T. Vaughan, 14, Alfred-road, Handsworth, near Birmingham.
rts, W. C., F.R.S., Royal Mint, Tower-hill, E.C.
nson, John, F.C.S., 13, Devon-square, Newton Abbot.
nson, George Carr, F.R.S.E., Chemical Laboratory, Royal Institution, all.
son, Thomas S. 57, Side, Newcastle-on-Tyne.
oll, Heinrich, Middlesboro'-on-Tees.
well, George Farrer, F.C.S., Marlborough College.
ald, E., Ph.D., F.R.S.E., Bonnington-house, Edinburgh.
oe, H. E., Ph.D., F.R.S., F.C.S., Owens College, Manchester.
enthal, G., Ph.D., Wandsworth-bridge-wharf, Fulham, S.W.
, Taraprosanna, Chemical Examiner, Medical College, Calcutta.
sell, W. J., Ph.D., F.R.S., F.C.S., St. Bartholomew's Hospital, E.C.
n, Dennis, The School of Medicine, Liverpool.

er, Mortyn John, F.C.S., 112, Forest-road, Dalston, E.
ery, T. J., 11, Salisbury-square, E.C.
unck, E., Ph.D., F.R.S., F.C.S., Kersall, near Manchester.
. William James, B.A., 1, Benet-place, Cambridge.
ier, Alfred, M.D., F.C.S., 17, Bloomsbury-square, W.C.
dwell, J. E. S., Meadow Bank, Melksham, Wilts.
nstone, W. A., F.C.S., Clifton College, Bristol.
pherd, H. H. B., F.C.S., Charnock-road, Clapton, E.
ppard, Thomas Williams, M.D., Patna, Bengal.
ber, C. H., 64, Corporation-street, Manchester.
bold, Louis, F.C.S., Oxford-street, Manchester.
mens, C. W., D.C.L., F.R.S., F.C.S., 12, Queen Anne's-gate, S.W.
tter, G. W., Saltaire, near Bradford, Yorkshire.
ee, A. H., F.C.S., The Grange, Wallington, Carshalton, Surrey.
ith, Arthur Percy, F.C.S., Temple Observatory, Rugby.
ith, R. Angus, Ph.D., F.R.S., F.C.S., 22, Devonshire-street, Manchester.
ith, Watson, F.C.S., Owens College, Manchester.
elus, George James, F.C.S., Assoc. R.S.M., Workington.
nstadt, Edward, F.C.S., 4, Hartham-road, Camden-road, N.
iller, John, F.C.S., 2, St. Mary's-road, Canonbury, N.
iller, William, F.C.S., Atlas Works, Hackney Wick, N.E.
ead, John Edward, Middlesborough.
euart, Daniel Rankin, Broxburn, Scotland.
evenson, J. Cochran, M.P., F.C.S., Westoe, South Shields.
evenson, T., M.D., F.C.S., Laboratory, Guy's Hospital, S.E.
ewart, A. Young, F.C.S., 212, Camden-road, N.W.
ock, W. Frederick Keating, F.C.S., Darlington.
oker, G. Naylor, Laboratory, Somerset-house, W.C.
utton, Francis, F.C.S., Norwich.
wan, J. Wilson, F.C.S., Mosley-street, Newcastle-on-Tyne.
szczepanowski, Stanislas A. Prus, F.C.S., 6, Stafford-place, Buckingham-gate, S.W.

ate, Alexander Norman, 7, 9, and 11, Hackins Hey, Liverpool.
ate, Walter, Norwood-grove, Liverpool.
atlock, J., 138, Bath-street, Glasgow.
atlock, Robert R., F.C.S., 138, Bath-street, Glasgow.
aylor, J., F.C.S., Farmers' Club, Inns of Court Hotel, Holborn, E.C.
aylor, Robert L., F.C.S., 52, Great Cheetham-street, Broughton, Manchester.
homas, Joseph William, F.C.S., Pen-y-lan, Cardiff.
homson, John Millar, F.C.S., King's College, W.C.
homson, William, F.C.S., Royal Institution, Manchester.
horp, W., B.Sc., F.C.S., 39, Sandringham-road, West Hackney, N.E.
ichborne, Charles R. C., M.R.I.A., F.C.S., 40, Mary-street, Dublin.
idy, C. M., M.B., F.C.S., 3, Mandeville-place, Manchester-square, W.
ilden, W. A., D.Sc., F.C.S., Mason's Science College, Birmingham.
omlinson, Charles, F.R.S., F.C.S., 3, Ridgmount-terrace, Highgate.
ookey, Charles, F.C.S., The Museum, Jermyn-street, W.
ribe, Alfred, F.C.S., Dulwich College.
ucker, A. E., The Rhymney Iron Works, Rhymney, South Wales.
uson, R. V., F.C.S., Royal Veterinary College, N.
yrer, Thomas, F.C.S., Garden Wharf, Battersea, S.W.

Umney, Charles, F.C.S., 50, Southwark-street, S.E.

Vacher, Arthur, F.C.S., 12, Fitzroy-street, W.
Versmann, F., Ph.D., 15, Trinity-square, Great Tower-street, E.C.
Viccajee, K. R., 10, Churney-road, Bombay.
Vincent, C. W., F.R.S.E., F.C.S., Royal Institution, Albemarle-street, W.
Vinson, W. E., Gloucester Gas Light Company, Gloucester.
Voelcker, A., Ph.D., F.R.S., 39, Argyle-road, Kensington, W.
Voelcker, E. W., Analytical Laboratory, 11, Salisbury-square, E.C.

Walenn, W. H., F.C.S., Delmar Villa, 520, Caledonian-road, N.
Walker, J. F., M.A., F.C.S., Sidney Sussex College, Cambridge.
Wallace, William, Ph.D., F.R.S.E., 138, Bath-street, Glasgow.
Walton, T. U., 63, Newton-street, Greenock.
Ward, G., F.C.S., Buckingham-terrace, Headingly, Leeds.
Warington, Robert, F.C.S., Harpenden, Herts.
Watt, Alexander, F.C.S., 24, Thackery-street, Liverpool.
Watson, David, D.Sc., F.C.S., Assoc. R.S.M., Broughton Copper Works, Manchester.
Watts, John, D.Sc., F.C.S., University Laboratory, Oxford.
Way, John Thomas, F.C.S., 9, Russell-road, Kensington, W.
Weldon, Walter, F.C.S., Rede-hall, Burstow, Surrey.
Wells, G. I. J., Lugsdale Chemical Works, Widnes.
Westmoreland, W. J., Bowling Iron Works, Bradford, Yorkshire.
Whewell, George, F.C.S., Exchange-chambers, Blackburn.
Whiffen, William George, Lombard-road, Battersea.
Wigner, G. W., 79, Great Tower-street, E.C.
Williams, John, F.C.S., 16, Cross-street, Hatton-garden, E.C.
Williams, M. W., F.C.S., 18, Kempsford-gardens, Brompton, S.W.
Williams, William John, F.C.S., 20, Chichester-street, Chester.
Williamson, Robert, F.C.S., Messrs. Burt, Bolton, and Heywood, Silvertown, E.
Wilson, G. Ferguson, F.R.S., F.C.S., Heather Bank, Weybridge.
Wilson, James Henry, Oak Hall, East Ham, Essex.
Wilson, William V., F.C.S., Jubilee-street, Mile-end, E.
Winser, Percy James, F.C.S., Marsden-street, Manchester.
Witton, J. C., B.A., B.Sc., Grammar School, Andover, Hampshire.
Wood, Charles Henry, F.C.S., 46, Lorraine-road, Holloway, N.
Wood, G. W., A.K.C., F.C.S., 12, Hope-park, Bromley, Kent.
Wood, W. H., Northgate Chambers, Halifax.
Woodcock, R. C., F.C.S., 23, Abingdon-street, Westminster, S.W.
Wright, C. R. Alder, D.Sc., F.C.S., St. Mary's Hospital, W.

Young, James, F.R.S., F.C.S., Kelly, near Greenock.
Young, William Charles, F.C.S., 1, Lee-terrace, Plaistow, Essex.

NAMES OF ASSOCIATES

Arnold, A. E., 7, Jeffreys-square, E.C.

Bascombe, Frederick, 180, New Bond-street, W.
Bayne, James, F.C.S., Royal Veterinary College, N.
Beckett, George Henry, F.C.S., 277, Edgware-road, W.
Bendix David, F.C.S., Prince Regent's-wharf, Victoria Docks, E.
Billing, Henry Samuel, Messrs. Burnard, Lack, and Alger, Plymouth Chemical Works, Plymouth.
Carpenter, H. S., F.C.S., Beckington-house, Weighton-road, Anerley, S.E.
Copley, James, Gregory-street, Nottingham.
Cowper, Richard, F.C.S., Assoc. R.S.M., 3, The Residences, South Kensington Museum, W.

Davey, G. W., 8, Hawthorne-terrace, Barking, Essex.
Davidson, James, jun., Summerville, near Dumfries.
Dobbin, Leonard, Chemical Laboratory, University, Edinburgh.

Firby, Alfred, 2, Fallowfield-terrace, Leeds.

Gahan, William Patrick, Bishop's Stortford, Herts.
Gaskell, Francis, Newnham-lodge, Spring-grove, Isleworth.
Gill, Edward J. G., 59, King Henry's-road, N.W.
Gibson, J., Ph.D., F.R.S.E., 29, Greenhill-gardens, Edinburgh.
Graham, Christopher C., Silwood, Tulse Hill, S.W.
Greenish, H. G., 20, New-street, Dorset-square, N.W.

Haddock, A., Runcorn Soap and Alkali Company, Weston, near Runcorn
Hellon, R., Assoc. R.S.M., 2, Route du Landi, St. Denis, Paris.
Hollis, Percy Best, Borax and Alkali Works, Widnes.
Holmes, Frederick George, 46, Hill-street, Peckham, S.E.
Hooker, Ayerst Henham, Court-lodge, Lessness-heath, S.E.
Hughes, Hugh, 81, Troughton-street, Edgehill, Liverpool.
Hutchinson, T. J., Lower Croft Bleach and Dye Works, Elton, near Bury.

Jago, William, F.C.S., School of Science and Art, Brighton.
Jobson, Thomas, jun., Stocksbridge Works, near Sheffield.
Jude, K. H., D.Sc., 37, Kempsford-gardens, South Kensington.

Lapraik, W., F.C.S., Chemical Laboratory, St. Bartholomew's Hospital.

MacIvor, R. W. Emerson, 29, Queen-street, Melbourne.
McGowan, George A., 22, East Claremont-street, Edinburgh.
Matthews, C. G., F.C.S., St. John's-lodge, Beckenham.

Naegamvala, K. D., 35, Malabar Hill, Bombay.
Neison, Cuthbert Gordon, Royal Veterinary College, N.

Paterson, George, 93, Canning-street, Liverpool.
Paterson, W. G. Spence, 24, Pitt-street, Edinburgh.
Patterson, George, 73, Nicholson-street, Greenock.
Pearson, Alfred Naylor, Victoria and Albert Museum, Bombay.
Powell, L. S., F.C.S., 56, St. James's-square, Notting Hill, W.

Sear, Frederick, 17, Rodney-street, Pentonville, N.
Senier, H., F.C.S., 5, Romola-terrace, Norwood-lane, Tulse Hill, S.E.
Smetham, Alfred, F.C.S., 18, Brunswick-street, Liverpool.
Smith, Henry Russell, 1, Aubert-park, Highbury-park, N.
Starling, John H., F.C.S., The Avenue, Erith.

Thorne, L. Temple, 52, Fortess-road, Kentish Town, N.W.
Toms, F. Woodland, F.C.S., 7, Busby-place, Camden-road, N.W.

Walker, Henry Herbert, 344, Glossop-road, Sheffield.
Williams, P. Caradoc, 6, Parliament-place, Liverpool.

Members are requested to send notice of change of address, &c., without delay, to the Secretary, Mr. Charles E. Groves, Somerset-house-terrace, W.C.

LA SEMAINE FRANÇAISE: a Weekly Newspaper and Review in the French Language. Politics, Literature, Science, Art, Varieties, Notes. Price 3*d.*, through booksellers, and at the railway bookstalls. Office, 37, Southampton Street, Strand, W.C.

LA SEMAINE FRANÇAISE: Journal Français pour l'Angleterre: Politique, Littérature, Sciences, Arts, Variétés, Nouvelles, et Notes. Un exemplaire par la poste, 3½*d.*, en timbres poste Abonnement franco par la poste—un an, 15*s.* 2*d.*; six mois, 7*s.* 7*d.* Prix 3*d.*, chez tous les libraires et aux gares des chemins de fer. On s'abonne aux bureaux, 37, Southampton Street, Strand, Londres, W.C.

LA SEMAINE FRANÇAISE.—"'La Semaine Française' has been brought out in London for the benefit of those English readers who may wish to study contemporary French from all points of view, instead of confining their reading to one particular Gallic print. It certainly merits success."—*Graphic.*

LA SEMAINE FRANÇAISE.—"The numbers before us are full of good things. . . . . It will be far better for most that any one of the best papers published in Paris itself. We are much pleased with the character of it, and believe it will be highly valued in all those many households where French is cultivated. The printing is very well done."—*Queen.*

Terms of Subscription:—							s.	d.
Three months	...	...	...	...	...	...	3	10
Six "	...	...	...	...	...	...	7	7
Twelve "	...	...	...	...	...	...	15	2

P.O.O. payable to T. Spanswick, at King Street, Covent Garden, W.C

Publishing Office, 37, Southampton Street, Strand, W.C.

Just ready,

VOLUME XII. (HIR—IND) of the

ENCYCLOPÆDIA BRITANNICA.

EDITED BY

PROF. THOS. SPENCER BAYNES, LL.D.

4to, Cloth, 30s.; Half Russia, 36s.

PRINCIPAL CONTENTS.

HISSAR. C. E. D. BLACK.
HISTOLOGY. Profs E. A. SCHÄFER and W. R. M'NAB.
HISTORY. J. C. MORISON.
HITTITES. Rev. T. K. CHEYNE.
HOBBES. Prof. G. CROOM ROBERTSON.
HODOGRAPH. Prof. JAMES BLYTH.
HOGARTH. AUSTIN DOBSON.
HOLBEIN. J. A. CROWE.
HOLBERG. E. W. GOSSE.
HOLLAND—
GEOGRAPHY. Prof. C. M. KAN.
HISTORY. Rev. G. W. KITCHIN.
LANGUAGE. J. B. VINCKERS and Dr. J. H. GALLÉE.
LITERATURE. E. W. GOSSE.
HOMER. D. B. MONRO.
HOMESTEAD. E. P. HANNA.
HOMŒOPATHY. Dr. J. G. GLOVER.
HONDURAS. E. G. SQUIER.
HONEY. F. H. BUTLER.
HONG-KONG. A. MACDONALD.
HOOD, THOMAS. LORD HOUGHTON.
HOOKER, RICHARD. T. F. HENDERSON.
HOP. E. M. HOLMES.
HORACE. Prof. W. Y. SELLAR.
HORNBILL. Prof. ALFRED NEWTON.
HORSE—
ANATOMY. Prof. W. H. FLOWER.
HISTORY, MANAGEMENT, &c. E. D. BRICKWOOD.
RACING. E. D. BRICKWOOD, Major J. R. HUBBARD, and W. T. CHESTER.
HORTICULTURE. Dr. M. T. MASTERS and T. MOORE.
HOSEA. Prof. W. ROBERTSON SMITH.
HOSIERY. JAMES PATON.
HOSPITALS. Prof F. DE CHAUMONT.
HOTTENTOTS. JOHN NOBLE.
HOUND. E. D. BRICKWOOD.
HUGUENOTS. Rev. G. W. KITCHIN.
HUMBOLDT, A. VON. Miss A. M. CLERKE.
HUMBOLDT, W VON. Prof. A. H. SAYCE.
HUME, DAVID. Prof. R. ADAMSON.
HUMMING-BIRD. Prof. NEWTON.
HUNGARY. E. D. BUTLER.
HUNT, LEIGH. RICHARD GARNETT.
HUNTER, JOHN AND WILLIAM. F. H. BUTLER.
HUNTING. E. D. BRICKWOOD.
HUSBAND AND WIFE. Prof. EDMUND ROBERTSON.
HUSS. Rev. J. SUTHERLAND BLACK.
HUTCHESON. Prof. T. FOWLER.
HUTTON, JAMES. Prof. A. GEIKIE.
HWEN T'SANG. Col. H. YULE.
HYÆNA. JOHN GIBSON.
HYBRIDISM. G. J. ROMANES.
HYDROCEPHALUS. Dr. J. O. AFFLECK.
HYDROGEN. Prof. H. E. ARMSTRONG.
HYDROMECHANICS. Profs. A. G. GREENHILL and W. C. UNWIN.
HYDROMETER. W. GARNETT.
HYDROPATHY. Dr. W. B. HUNTER.
HYDROPHOBIA. Dr. AFFLECK.
HYDROZOA. Prof. E. RAY LANKESTER.
HYGIENE. Prof. F. DE CHAUMONT.
HYGROMETRY. ALEX. BUCHAN.
HYMENOPTERA. P. CAMERON.
HYMNS. LORD SELBORNE.
HYSTERIA. Dr. J. BATTY TUKE.
IAMBLICHUS. W. R. SORLEY.
IBN BATUTA. Col. YULE.
ICE. CARGILL G. KNOTT, D.Sc.
ICELAND. J. A. HJALTALIN and F. Y. POWELL.
ICHTHYOLOGY. Dr. A. GÜNTHER.
IDAHO. HENRY GANNETT.
ILLINOIS. J. W. SHEAHAN and J. MEDILL.
ILLUMINATION. H. B. WILSON.
ILLYRIA. W. M. RAMSAY.
IMAGE WORSHIP. Rev. J. S. BLACK.
INCENSE. Dr. GEORGE BIRDWOOD.
INDEPENDENTS. Principal A. M. FAIRBAIRN, D.D.
INDEX. H. B. WHEATLEY.
INDIA. W. W. HUNTER, LL.D.
INDIANA. A. C. HARRIS.
INDIAN ARCHIPELAGO. H. A. WEBSTER.
INDIAN OCEAN. Dr. W. B. CARPENTER, C.B.
INDIANS, AMERICAN. A. H. KEANE and H. GANNETT.
INDIAN TERRITORY. H. GANNETT.
INDIA-RUBBER. E. M. HOLMES and T. BOLAS.
INDIGO. JAMES PATON.

Edinburgh: ADAM & CHARLES BLACK.

New Edition, very much enlarged, 512

HOW TO WORK WITH THE MICROSCOPE.

By LIONEL S. BEALE, F.R.S.,
President of the Royal Microscopical Society.

THE FIFTH EDITION,
Strongly bound and enlarged to 530 Pages, with 100 Plates, some are Coloured, is now ready.
HARRISON & SONS, Pall Mall.

NEW WORK BY LIONEL S. BEALE.
Now ready, pp. 230, demy 8vo, 5s.

SLIGHT AILMENTS:

THEIR NATURE AND TREATMENT.
By LIONEL S. BEALE, M.B., F.R.S., F.R.
Professor of the Principles and Practice of Medicine in King's London.
J. & A. CHURCHILL, New Burlington Street.

London, 15 Piccadilly, Mar

Nearly ready.

CATALOGUE of BIRDS in the BRITISH MUSEUM.

Vol. V., describing the Families of THRUSHES and WARBLERS
Edited by Mr. HENRY SEEBOHM and Dr. G. BATHER.
The previous Volumes can still be supplied.
Vol. I., containing the *Accipitres*, with 14 Coloured Plates, 2
„ II., „ *Striges*, „ „
„ III., „ *Passeriformes* „ „
„ IV., „ „ (Part II.) „ „
All the British Museum Publications are supplied by
BERNARD QUARITCH.

Now Ready, with 200 Illustrations, medium 8vo, 3s.

The CAT. An Introduction to the Study of Back-boned Animals, especially Mammals. By ST. MIVART, F.R.S., Author of "Lessons from Nature," &c. President of the Linnean Society and of the Zoological Society.
JOHN MURRAY, Albemarle Street.

THE CHEMICAL NEWS AND JOURNAL OF PHYSICAL SCIENCE.

EDITED BY W. CROOKES, F.R.S., &c.
Published every Friday. Price 4d.

No. 1114 (April 1st, 1881) contains—Action of Sodium upon Oxygen. Greville Williams, F.R.S.—Bases produced by the Distillation with Potash, by Greville Williams, F.R.S.—Estimation of Phosphorus in Steel, by J. Oliver Arnold, F.C.S.—Elimination of Carbon Disulphide from Commercial Benzol, by Benjamin Nickels.—Atmospheric Oxidation of Phosphorus, and Reactions of Ozone and Hydric Peroxide. By Dr. Schöne.—Phenol or Carbolic Acid: Qualitative and Quantitative Tests. E. Waller, Ph.D.—Proceedings of Societies.—Notices of Books.—Correspondence.—Chemical Notices from Foreign Sources.—Notes and Queries, &c., &c.

London: Boy Court, Ludgate Hill, E.C.

Now ready, price 3s. Quarterly; Yearly, 12s., post free.

MIND: No. XXII.

I. Monism. E. Gurney.
II. Renouvier's Psychology. S. H. Hodgson.
III. Dictionary-defining. Rev. W. L. Davidson.
IV. Buckle and the Economics of Knowledge. A. W. Bennett.
Notes, Critical Notices, &c., by A. J. Balfour, Prof. Croom Robertson, Sully, G. Allen, F. Pollock, A. Seth.
WILLIAMS & NORGATE, London and Edinburgh.

GEOLOGY AND MINERALOGY.

IN the Preface to the "Student's Elements of Geology" Lyell he says, "As it is impossible to enable the reader to recognise rocks and minerals at sight by aid of verbal descriptions or figures, he will do well to obtain a well-arranged collection of specimens." These can be had from BRY. WRIGHT, MINERALOGIST, 90, Great Russell Street, W.C.

50 Specimens in Cabinet	...	...	...	...	£1 0 0
100 „ „	...	...	...	...	2 0 0
200 „ „	...	...	...	...	5 0 0

&c., &c.

More ex[illegible]tions from 50 to 2000 Guineas

Y, MARCH 31, 1881

IN ANIMALS

Prof. Ludwig Büchner, author of
&c. Translated, by the author's
German of the Third Revised
esant. (London: Free-thought
1880.)

) English of Büchner's work on
" (which was originally published
welcome to persons of all shades
itly opinions may differ as to the
any which has undertaken and
n. The Company, among other
ranslation of works from foreign
of a series entitled "The Inter-
ence and Free-thought," and of
ork on "Mind in Animals" con-
r. It is to be hoped that the
Company in this direction will
neficial as the one we are about
islation has here, on the whole,
h occasionally we meet with an
action which a little more care
ces might easily have obviated.
ious question a highly valuable
ring to Comparative Psychology,
slation into English supplies a
ndeavouring to recommend it to
aders.

called "Mind in Animals," and
ur hundred closely-printed pages,
sychology of articulata, and even
nited group it treats only of four
era, *Orthoptera*, *Arachnida*, and
owever, can read the work and
if its subject-matter is a defect, al-
e title might perhaps have been
to "Mind in Insects." As he
author has not thought it neces-
le of his observations over the
ely narrow and yet infinitely wide
ligent insect life; he considers it
gle species thoroughly, rather than
nd superficially," &c. Such being
ppears to have read most of the
the subject that is worth reading,
tion tolerably well sifted, of all the
These he has presented in a form
ing to a general reader of the
most useful alike to the working
inary psychologist. The labour
s is very considerable, and Büch-
and praise, both from the scientific
ic, for the patient industry with
the bee that he is so fond of up-
e has collected and arranged his

his of the book is devoted to ants
ion constitutes a compendium of
hology of these interesting animals
y Büchner inserts in accordance with popular

which we do not hesitate to regard as the most instructive that has hitherto been made. There are however no original observations in the book—or rather no original observations recorded as made by Büchner himself, for there are several highly interesting observations recorded as made by friends and correspondents. Some of the more important of these we may here present.

Herr Lehr, a "bee-keeping friend of the author," noticed that when his bees were attacked by dysentery, and "no longer able to retain their excrements, one hive suffered less than the others." Investigation showed that the bees of this hive had made a drain from the upper part of the hive, "where they were accustomed to sit together during the winter," to the exterior.

The same (?) friend observed that when the wind blew down one of his hives and he replaced it, a few days later "the bees had left their old home in the lurch, and tried to enter other hives, clearly because they could no longer trust the weather, and feared that the terrible accident might again befall them."

Another friend, Herr Schlüter, saw a hornet catch a cicada, sting it, and try to fly off with the bulky prey. The hornet's strength not being sufficient to enable it to fly with the cicada from the ground, it dragged its burden up the stump of a mulberry-tree that stood close by. Arrived at the top of the stump—twelve feet from the ground—"it rested for a moment, grasped its victim firmly, and flew off with it to the prairies. That which it was unable to raise off the ground it could now carry easily once high in the air."

Again, Herr Merkel communicates the following. He saw a little grey wasp dragging a long caterpillar to its hole. Arrived there, it put one end of the caterpillar over the hole, "and went to the other end and lifted it up so high that the caterpillar fell in. But a piece of it stuck out"; so the wasp pulled it out, and, laying it down near the hole, "went in again and brought out several little stones of the size of small peas. It then again let the caterpillar fall into the hole in the way described." This time it was quite absorbed by the hole, and was buried by the wasp.

More interesting is an observation due to Herr Nottebohm, Inspector of Buildings at Karlsruhe, who carefully syringed off all the aphides from a weeping-ash in March, to the great benefit of the tree. But in June he was astonished to see multitudes of ants running up and down the trunk of the tree, busied in carrying up aphides all over the tree in order to re-stock it, and "after some weeks the evil was as great as ever."

Again Herr Theuerkauf showed Büchner a maple tree, round which he had "smeared about a foot width of the ground with tar," in order to check the mischief caused by ants cultivating aphides. But the ants on the tree turned back on finding the tar, and "carried down aphides, which they stuck down on the tar one after another, until they had made a bridge over which they could cross the tar-ring without danger."

Highly interesting also is an observation communicated to the author by Herr Krepin concerning the Ecitons crossing streams, which is even more wonderful than anything that has been related of these wonderful insects by Bates or Belt. "If no natural bridge is available for the passage, they travel along the bank of the river until they arrive at a flat sandy shore. Each ant now seizes a bit of

dry wood, pulls it into the water, and mounts thereon. The hinder rows push the front ones even further out, holding on to the wood with their feet and to their comrades with their jaws. In a short time the water is covered with ants, and when the raft has grown too large to be held together by the small creatures' strength, a part breaks off and begins its journey across, while the ants left on the bank busily pull their bits of wood into the water and work at enlarging the ferry-boat until it again breaks. This is repeated as long as an ant remains on the shore."

Similarly, Dr. Ellendorf informs the author that he has witnessed ants using a straw for a bridge across a saucer of water which he had placed as a barrier between the ants and his provisions. He then pushed the straw about an inch from one of its two landing-places. After much confusion and crossing of atennæ, the ants "soon found out where the fault lay, and with united forces they quickly pulled and pushed the straw until it again came into contact with the wood, when the communication was again restored."

The same observer communicates another very interesting observation on the leaf-cutting ants. He interrupted a marching column by placing a withered branch across their road. The loads were laid aside by more than a foot's length of the column, and the ants began on both sides of the branch to tunnel beneath it, and when the tunnel was completed "each ant took up its burden again, and the march was resumed in the most perfect order."

These being the most important additions which Prof. Büchner's work has made to our previous knowledge of insect psychology, we shall now proceed to make a few criticisms upon the work as a whole. In the first place, the author is not quite free from the failing common to less critical writers on animal intelligence, of admitting dubious cases without sufficient reserve. Thus, for instance, on no better authority than Plutarch, he gives (p. 57) a case "related by a certain Cleanthes," of ants going from one ant-heap to the entrance of another, carrying a dead ant. Other ants came out of the visited heap, consulted with the bearers of the body, went back again and brought a worm "out of the depths of the nest, which was evidently intended to serve as a ransom for the dead body. Then the ants which had brought the corpse left it lying there, and carried away the worm instead." He then adds, "However incredible this may sound, it is beyond doubt that ants and bees have been seen carrying away and even burying their dead, and of this further details will be given later." As the fact of "burying" is highly dubious, we looked forward from this statement to afterwards meeting with some new evidence upon the subject; but in the case of ants only found the unsupported assertion of Dupont, followed by a confusion of the well-ascertained fact that ants carry their dead away from their nests, with the inference that they bury them (p. 167), while in the case of bees we only met with (p. 249) a very flimsy anecdote, which we had previously read in Watson's "Reasoning Powers of Animals," quoted from the *Glasgow Herald* on the authority of an anonymous correspondent; it presents a pathetic account of two bees flying out of a hive "carrying between them the corpse of a dead comrade," till, after searching for a suitable hole, they "carefully pushed in the dead body, head foremost, and finally placed above it two small stones. They then watched for about a minute before they flew away, doubt, of course, performing some appropriate service. And this is the evidence on which the statement rests, "*it is beyond doubt* that ants have been seen . . . burying their dead"! Such of careless judgment, however, in admitting alleged on wholly inadequate evidence, are fortunately work exceptional.

Another point on which criticism has to be the frequent failure of references. Important constantly stated without any information being as to the authority on which the statements rest even when the authority is stated, after the first quoting the reference is always to *loc. cit.*, so the name of the work is carried in the reader's he has to hunt back through an indefinite pages of letterpress till he finds it.

Another feature of the work which must be a blemish upon it as a work of science, is a breaking out of allusions to matters religious and The strong bias which the author displays in the sions, apart from being singularly out of place in which aims at scientific method, constantly into obvious fallacies. For instance, when speaking ants, he asks, "Why should we take it for granted a perfectly free community men would only work pelled, when these animals give proof that such commonwealth is very possible, and is compatible the voluntary work of all?" Certainly any one disposed to take such a supposition for granted scarcely be convinced by such a false analogy between an ant and a man; and he might well show up the nonsense by replying, "Why should it for granted that men in a perfectly free *would* work without compulsion, when the ants give proof that such a free commonwealth is very and is compatible with no work at all?" So logic of many of these passages, and we do that in others of the same kind the sentiments more fortunate. It is, for instance, to be doubted the following picture of "the widest Socialism munism" as revealed in bees, and held out as for humanity to imitate, will prove as attractive eyes of all his readers as it evidently appears to of the writer. "They have no private property family, no private dwelling, but hang in thick within the common-room in the narrow space the combs, taking turns for brief nightly repose On all such matters opinions may legitimately allusions to them are, as we have said, out of treatise on Comparative Psychology.

Coming next to criticisms of a more purely character, we have first to notice a meagre which the whole subject of instinct is treated anxiety to combat the supernaturalists, Büchner the side of too closely assimilating the psychic faculties of insects with those of men. That is endeavours to explain most, if not all, instinctive as being one with "reason" and "reflection." an enormous and damaging mistake in the evolution to disparage the distinction which unably exists between mind in animals and mind The function of an historical psychologist is to

nd the development of rational
two together as presenting but
xplained. Yet in two chapters
have in this treatise scarcely a
probable mode of origin, and
y may be supposed to have deve-
s "inverted anthropomorphism"
thor into statements which are
s, for instance, when speaking of
es he observes that their leaving
ie air "seems as though a feeling
queen from performing this act
owd."

w places where he does touch
cts, his treatment of the subject
Taking, for example, his remarks
ed by the case of neuter insects
its which display totally different
geny, he adopts the view that
nally workers, lost their working
t now leave them as perpetual
offspring. Now, although this
a mitigation of the difficulty, it
en as a full "answer" to its
ses round a mountain of trouble
opinion, if correct, would also
insects, and especially to ants,
l argument." This is a most
t way of eluding what Darwin
ficulty" which is presented by
having instincts differing, not
arents, but from one another.
heory advanced by Büchner is
to meet the facts; and he does
read, or else to have entirely
ndensed and candid reasoning
the beautiful theory concerning
igin of Species."

atters of fact there are some
serious sin of omission is to be
ription of the habits of the leaf-
llusion is made to the theory of
n since supported both by Belt
regarded as highly probable, if
—concerning the object with
nd garnered, namely, to grow
aling with the so-called agricul-
think, somewhat too definite in
e insects planting seed. So far
is head rests on the unsupported
(not Linecum, as repeatedly mis-
may prove true, ought not, until
thus unreservedly accepted.

same kind might be passed, and
would have been well to have
o the translation bringing the
to date, and likewise an index;
to signify our general estimate
rs of fact it is, as a rule, most
ive. In its philosophy it is not
is a decidedly valuable addition
rative Psychology.

GEORGE J. ROMANES

AMERICAN INDIAN LANGUAGES

Introduction to the Study of Indian Languages. By J. W. Powell. Second Edition. (Washington: Government Printing Office, 1880.)

THIS is one of the most useful of the many useful works issued under Mr. Powell's able management by the ethnological bureau of the Smithsonian Institution. It was originally published in 1877, and it is satisfactory to find that another edition has so soon been called for. At the same time one cannot but regret that this opportunity was not taken to somewhat modify the title, which, as it stands, is apt to deceive the unwary. The book is in no sense an abstract treatise on the nature, structure, or classification of the American languages, either regarded independently or in relation to other forms of speech. It has nothing to do with the philosophy, or even with the grammar of these idioms taken collectively or individually. Its object, if less ambitious, is perhaps far more useful in the present state of these studies. American philologists have confessedly shown a disposition to dogmatise on the morphology of the native idioms, and have indulged in some very wild speculation on utterly insufficient data regarding their origin, development, and affinities. The old school of etymologists, who held that Eliot's Massachusetts Bible was merely a thinly disguised form of Welsh, that Delaware and Lapp were first cousins, and that Basque sailors stranded on the Brazilian seaboard could hold converse with the Tupinambas and other Guarani peoples of that region, has had its day. But it has been succeeded by another, which, if slightly more cautious, is scarcely less extravagant, and which, notwithstanding the warning voice of science, still flourishes in both hemispheres. It will suffice here to refer to the astonishing theories seriously advocated by the late Abbé Brasseur de Bourbourg on the relations of the Maya-Quiché and Aryan families, by the Abbé Petitot on the Athabascan and Chinese, and quite recently by Mr. John Campbell of Montreal on "The Hittites in America." "The Aleutians and Barabra," writes the last-mentioned authority, "agree in being worshippers of the sun like other Hittites, in the manufacture of red waterproof leather, and in their manner of adorning the head. . . . Physical ethnology would never have dreamt of uniting white Basques and Circassians, black Nubians, yellow Japanese, and red American Indians; but philology, which knows no colour but that of words and constructions, makes them one. It may be that in the Barabra we shall yet find the purest surviving form of the ancient Hittite language. Some of its numerals help to connect those of the Peruvian dialects with other Hittite forms." One thing more surprising perhaps than such insanities is their appearance in the pages of a professedly scientific journal (*The Canadian Naturalist and Quarterly Journal of Science* for August, 1880, p. 359).

A wholesome check to writers inclined to indulge in tendencies of this sort is afforded by the modest and unpretending character of the work under consideration. It is put forward simply as a guide and aid to students in the collection of linguistic materials in a very wide field, where the labourers are still too few for the urgent and extensive character of the work to be performed. It thus brings us back to the domain of hard facts, wisely

reserving all speculation for a time when these facts will have been accumulated in sufficient number to afford a sound basis for more general inductions. "The book is a body of directions for collectors" (Preface vi.). It is divided into three chapters, one "On the Alphabet," another containing "Hints and Explanations," and a third supplying a large number of forms or "Schedules" to be filled up by the collector. The chapter on the Alphabet aims at establishing some uniform system of spelling for all the native tongues, and puts forth a comprehensive scheme embodying many useful suggestions well deserving the attention of our "spelling reformers." These are summed up in a few fundamental rules, the chief of which are the exclusion of all characters and diacritical marks except those found in ordinary English printing offices, and the restriction of each sign to a single sound. The difficulty of adapting the Roman system to the Indian tongues will be understood when it is stated that "there are probably sounds in each which do not appear in the English or any other civilised tongue; and perhaps sounds in each which do not appear in any of the others, and further, that there are perhaps sounds in each of such a character, or made with so much uncertainty, that the ear is unable to clearly determine what these sounds are, even after many years of effort" (p. 2). Nevertheless the difficulty is manfully faced and largely overcome by the scheme here adopted, which is founded on one originally proposed by Prof. J. D. Whitney, and which is consequently at once scholarly, simple, and comprehensive. A few improvements might here and there be suggested, but on the whole there is little to complain of, except perhaps the use of the circumflex (^), to mark both a long *a* sound, as in *all*, and a short *u* sound as in *but*. Some confusion is caused by an awkward misprint at p. 5, where this û appears instead of the German *ü*. It might also perhaps be better to indicate excessive vowel length by doubling the vowel as in Dutch, than by the clumsy addition of the sign +. Thus *maan* rather than *ma* + *n*.

Chapter II. contains a number of well-digested and tersely-expressed remarks on dress, ornaments, dwellings, implements, food, colours, plants, animals, medicine, social organisation, kinship, government, and many other topics, which at first sight seem to have little connection with the subject of American philology. But the author has wisely endeavoured thus "to connect the study of language with the study of other branches of anthropology; for a language is best understood when the habits, customs, institutions, philosophy—the subject-matter of thought embodied in a language are best known. The student of language should be a student of the people who speak the language; and to this end the book has been prepared, with many hints and suggestions relating to other branches of anthropology" (Preface vi.). But besides these matters the chapter contains what will be welcomed as a boon by all linguists, a reprint of J. H. Trumbull's masterly paper "On the Best Method of Studying the North American Languages," originally published in the *Transactions* of the American Philological Association, 1869-70, but strangely neglected by many subsequent writers on the subject. No other treatise perhaps of equal length contains so clear and philosophic an account of the peculiar genius and morphology of these polysynthetic tongues. A great deal devoted to the question of kinship, the true ba tribal society, and this intricate subject is full by a series of four "kinship charts" or diagrams, which the original investigator will greatest service in collecting and arranging h The general student will also find them extr in comparing the American systems of family with those prevalent especially amongst th of the Deccan and the Australian aborigines importance has perhaps been attached to res this sort in tracing racial affinities; but thei in the history of the evolution of huma undeniable. Connubial society develops society, or the clan, in which all the membe relations, whence the tribe and nation. It i that the connubial, or lowest form, still so many parts of the eastern hemisphere, se long disappeared, at least from the northern New World, although some of its custom those associated with kinship, still survive advanced tribal state. This explains the ba of family nomenclature with which the Indi are still encumbered. In the printed forms, of which Chapter III. exclusively consists, relationship occupy about forty pages, hundreds of complicate affinities such as, elder brother's daughter's daughter's daughte "my father's mother's brother's son's son" "my mother's father's brother's son's daught daughter," "my mother's mother's sister son's daughter's daughter," "my mother's daughter's daughter's daughter's husband," and even more intricate degrees of parentag tongues supply equivalents, which the accordingly required to discover and insert columns prepared for the purpose in the sch arrangement of the other matter contai schedules seems to be somewhat needlessly least the advantages are scarcely so obvious venience of breaking up the strictly lexi upwards of twenty sub-headings, instead of whole in one general vocabulary arranged a Experience has abundantly shown how t the use of such minutely-classified lists of w the compiler. This remark does not of co the lists of sentences (Schedules 26-9), whi have been carefully prepared, and are w to bring out the structure and varied gramm of the Indian languages.

A.

LETTERS TO THE EDITO

[The Editor does not hold himself responsible for op by his correspondents. Neither can he underta to correspond with the writers of, rejected ma notice is taken of anonymous communications. The Editor urgently requests correspondents to kee short as possible. The pressure on his space is is impossible otherwise to ensure the appearanc munications containing interesting and novel f

Hot Ice

THE letter of Mr. Perry (NATURE, vol. xxi answer to mine on the subject of Dr. Carnelley (p. 264) has remained a long time unanswered, pa

pose that Prof. Ayrton himself might ay regarding his views as soon as he mainly because I did not see any point immediate reply. I find however that cautious scepticism and suspense of the subject—a scepticism which Prof. ter of a month ago (p. 383) has not e, though there can be no doubt of his hat ice in a hot vacuum is *infinitely* re is nothing in his letter confirming *hot*, which is the only point under

fully and unreservedly accept this as unt of Dr. Carnelley's experimental I imagine myself to perceive exactly that it might conceivably have been fureland.

ion therefore is merely to remove as of mystification which Prof. Perry's produce, and to indicate the ground of

Perry, with their stiff paper models, , on the assumption that the ordinary e two laws of thermodynamics will s is exactly how I started myself. I ssary to investigate the behaviour of ties were defined, not by two inde- usual, but by three; the pressure, erature, being all three arbitrary and in the Carnelley experiment; and I l equations to suit this case. But it they did not apply at all, and for this w is only true for processes that are tion of hot ice is essentially an *irrever-* d the whole gist of the matter, and it is e ice gets hot. Ordinary evaporation g-point against a pressure less than irreversible process, and accordingly y indefinite, and depends on the rate the rate of evaporation. So also with at, that is, ice subliming under a less n tension; its temperature depends ly of heat and on the rate of evapo- g is perfectly simple and absolutely

on that can arise is whether internal will not set in and prevent its rising whether in fact a solid cannot boil as a reasons for believing that in a solid out air bubbles, and constantly rising not occur; and I deny that under these rticularly unstable condition analogous water on the point of "boiling by

mit is a point distinctly open to dis- at without an experiment one could not . But personally I feel that the evi- by Dr. Carnelley, together with the icated in my former letter (p. 264), is

hat staggering to learn (NATURE, vol. McLeod, with his well-known experi- hitherto failed to repeat the experiment, above zero;[1] but I take this as an ose rare cases where refined experi- tructions rather than aids, for I believe due to the fact that Prof. McLeod's ret, and the evaporation therefore so ot have a fair chance of showing its erature; it could not in fact get even if Prof. McLeod will discreetly spoil ssure is only just below the vapour- the temperature shown by his thermo- ; that he will see the ice rise to any

[1] I am received, by the kindness of M. Boutlerow, bef re the St. Petersburg Academy of Sciences, ers which have appeared on the subject, relative eriment, and confesses himself a sceptic. It M. Boutlerow's carefully-wrought memoir to is my impression that his failure is due to the ve ventured to suggest above as accounting for ct apparatus and too great experimental skill.

temperature he likes, and he will find that when it is crossing zero it will be utterly regardless of the fact.

The same kind of statement applies to solid carbonic acid, on which I have made a few experiments with a view to raising its temperature. I squeezed it into the ice form in a hydraulic press (to diminish the evaporating surface), put a thermometer in it, and held it over a fire. The evaporation is so excessively rapid, however, that it remains apparently just as cold as before.

I have not time to follow it up just now, but the obvious thing is to put it under pressure, so as to diminish the rate of evaporation, and then heat it. Prof. McLeod informs me that the boiling-point of CO_2 continues below its melting-point (which is given by Frankland as $-57°$ C.), until the pressure is four atmospheres; so that anything just under four atmospheres may be applied to this substance with impunity, and it will then be exactly in the most favourable condition for the Carnelley experiment; and I have not the slightest doubt that it can then be warmed, and if at the same time the pressure be judiciously and gradually increased, that it can be made as warm as one pleases until it has all disappeared.

Experiment with substances other than water however are likely to be more difficult, simply because few substances have such a large latent heat both in the liquid and gaseous condition, and therefore few substances will be anything like so permanent and outlive the evaporation so long. OLIVER J. LODGE

17, Parkhurst Road, N.

THE announcement made some time since by Dr. Carnelley that ice *in vacuo* could be raised to a temperature far above its ordinary melting-point, seemed so thoroughly in opposition to the experience derived from the great work of Regnault on the tensions of vapours; and as it called for a complete change of ideas in a field in which I am much interested, and as Dr. Carnelley asked others to repeat his experiments, I was induced to examine for myself the experiments on which so curious a statement was founded.

I used two different methods: the Torricellian vacuum and the Sprengel vacuum. As the experiment, as conducted by the Torricellian method, can easily be repeated by any one, and is much simpler in form than Dr. Carnelley's, I shall detail it. In the first place I wished to obtain a clear continuous piece of ice round the thermometer, as Dr. Carnelley's method gave flaky ice, which I found might lead to errors, owing to its discontinuity leaving the thermometer bare in parts. To obtain clear ice the following method was used:—Some distilled water was boiled in a test-tube A fitted with a two-holed stopper, with a thermometer through one hole dipping into the water; when all the air was expelled, a glass plug was pressed into the other hole against the boiling steam, and the whole allowed to cool, and then frozen in a freezing-mixture. A long-necked "German Florence flask" was then rinsed with distilled water and filled with mercury, and also placed in a freezing-mixture. The tube A was then gently warmed with the hand, and the plug of ice adhering to the thermometer withdrawn. The glass plug in the second hole in the stopper was then replaced by a marine barometer-tube of about forty inches in length, having been drawn out about four inches from the top to facilitate sealing. The plug of ice round the thermometer was then inserted into the neck of the flask full of mercury, and the stopper pressed home. This caused the mercury to rise in the barometer-tube, and the whole was then inverted as at B; and when the mercury had all run out, the fall tube was melted through at the constriction B, leaving a Torricellian vacuum above. The flask was now laid on its side in a freezing mixture and well covered over with ice and salt as at C. After a few minutes, to allow the receiver to cool, heat was applied to the neck of the flask with a Bunsen lamp, and even with a blowpipe, till the glass softened, but the temperature of the thermometer did not rise until some part of it became denuded of ice, or until air had been admitted. The experiment was repeated again and again, but in no case while the vacuum was intact could the temperature of the ice be raised materially above that of the receiver. If the temperature of the receiver was $-12°$, then the ice was a little over $-12°$, say about $-11°$, but never more than two degrees above the receiver, although the glass almost in contact with the ice was at its softening point. This is exactly what we would expect from Regnault's experiments; the temperature of the receiver determines the vapour-tension, and therefore the "boiling point" of the ice. The ice was certainly never hot, and was not even

infusible, because when pressed against the hot glass it at once splashed out, freezing again in long thin flakes when it obtained free space for evaporation. All the heat passing to the ice is used up in volatilising it, and increase of the source of heat merely increases the rate of evaporation, as in the case of water boiling under atmospheric or other constant pressure; provided the condenser be efficient. These experiments were repeated with different thermometers and thicknesses of ice, varying from ½ inch to the thinnest film, $\frac{1}{10}$ inch, or thereby, and the temperature of the ice was always dependent upon the temperature of the receiver (when vacuous) and quite independent of the temperature surrounding it; the latter merely determining the rate of evaporation. Whenever a hole appeared in the ice covering the thermometer the latter rose, and if close to the bu rapidly. When the ice wore away, as shown at D, t ature registered by the thermometer could be made con under zero. If the source of heat was made to play of the tube, then the temperature would read over zero if made to play on the bottom it would read − 8°, the rea − 12°. When however the ice was made to lie on the of the thermometer by turning the latter round, the te could not be raised over zero, and sometimes not These experiments were repeated by exhausting with a pump, and it was invariably found that the pressure or vapour in the receiver determined the temperatu tilisation of the ice, and when the "vacuum" cou



water vapour the temperatures of the receiver and of the ice round the thermometer (however far apart they were placed) were practically the same. For instance, let the receiver be − 5°, then the thermometer in the ice is also − 5° or − 4°; now let the receiver be suddenly cooled to − 14° while the flame round the ice is urged to a higher temperature; the ice will nevertheless fall to − 13° or thereby; in short, the *temperature* of the "boiling" ice is determined by that of the receiver, while the *rate* of its "boiling" is determined by the temperature of the tube surrounding it. The ice remains perfectly dry, but if air be admitted or the receiver be raised above 0°, melting takes place.

As it has been objected that the thermometer might yield anomalous readings under such conditions (though why I cannot see), another method was tried, as shown at E. A small bulb blown on the end of a tube open at the other end, a little water, had ice frozen round it, as in the case mometer, and was then placed in the flask as bef there was a piece of ice under ordinary atmospheric co closed in the ice *in vacuo*. The tube round the outer raised to the softening point, but the ice in the bulb d and continued solid till the bulb was denuded of extern evaporation, showing that the ice *in vacuo* was never It appears then that ice cannot be raised above 0° circumstances, and that the pressure determines the or "boiling" points of both solids and liquids, as ha work would lead us to suppose.

J. B. Hay

Private Laboratory, Sword Street, Glasgow

BEING a reader of NATURE, I have become quite interested in Mr. Thos. Carnelley's experiments with hot ice. Although Mr. Carnelley's experiments would seem to be sufficiently accurate to prove that the ice was in a heated condition, I would still like to offer an additional method to heat the ice, and also a method to test for heat in the ice. To heat the ice I would suggest a small coil of fine platinum wire placed in position in the tube where the water is to be frozen, and the two ends of the coil passed through the sides of the tube and hermetically sealed.

If now the water be frozen around the coil, and a current of electricity passed through the wire of sufficient amount to heat the wire as much as might be determined upon, and the ice yet remain frozen, there would seem to be no doubt the ice having become heated by contact with the hot pl wire.

The method I would suggest to test for heat in the ice be to take a couple of pieces of heavy platinum wire and through the sides of the tube and hermetically sealed as except to have a small space between the two ends of the on the inside of the tube, of one-eighth or one-quarter inch as much space as might be thought best.

If now the water be frozen between the ends or all round ends of the wire, and a small battery and galvanometer in circuit with the terminals of the platinum wire, and a jet be applied to heat the ice, if the ice becomes heated

meter should show a stronger current of electricity pass-
the principle that most, if not all, non-metallic sub-
that are conductors of electricity become better conduc-
the application of heat. I judge that the galvanometer
uld be a very perfect one. GEORGE B. RICHMOND
ing, Michigan, U.S.A., March 5

The Oldest Fossil Insects

ALL be glad if you will afford me an opportunity of
ing one or two personal matters referred to in p. 11 of
udder's memoir on the Devonian Insects of New Bruns-
which was mentioned in your last number (pp. 483, 4).
ry justly takes exception to some bibliographical and
raphical errors committed by me in *Trans.* Entom. Soc.
1871, pp. 38-40, in a notice of fossil insects named and
ed by him, and naturally regards them as evidence of
ient study of the literature relating to them. It is difficult
precisely what happened upwards of ten years ago, but I
isfied that the mistakes must have arisen in one or the
of these two ways. Either I attributed the authorship of
mes to the person who first published figures of the fossils,
ground that names bestowed upon insect-fossils by the
ation of descriptions, without accompanying figures, rank
re "Catalogue" or MS. names devoid of priority; or else
re due to circumstances under which the citations were
ed. Closely pressed for time, and without much experience
art of citation, it is as likely as not that, after forming an
n upon the plates and consulting the letterpress to see what
thor had to say about them, I referred from force of habit
title-page of the volume for the date of publication and
thor's name, instead of turning to the heading of the article
is last.

the same page of his memoir Mr. Scudder alludes to the
wing passages in p. 39 of my work, over which we had
fun when he was last in England, though the strictures
not aimed at him more than at the others. "Palæon-
ists have adopted a ridiculous course with regard to some
t fossils. Whenever an obscure fragment of a well-reticu-
insect's wing is found in a rock, a genus is straightway set
nd the fossil named as a new *species*. The species is then
red to the *Ephemeridæ*, and is immediately pronounced to
synthetic type of insects at present distantly related to one
her in organisation. This enunciation of synthetic types is
nothing less than a resort to random conjecture respecting
ffinities of animals which the writer is at a loss to classify.
nsect allied to the *Ephemeridæ* which chirped like a locust
as *Xenoneura* is imagined to have been), is a tolerable
ple of these synthetic types. When a fossil comprises only
gment, or even a complete wing of an Ephemerid, it is
lly possible to determine the *genus*, and impossible to assert
species. The utmost that can be learned from such a speci-
is the approximate relations of the insect. Neuration by
f is not sufficient to define the species or even the genera of
nt *Ephemeridæ*." What I meant to be deduced from this
that, where in the nature of things actual precision is un-
inable, palæontologists should be content to learn and state
"approximate relations" of fossil insects, and not presume
n the ignorance of scientific men in the matter of *genera* and
ies. And I further thought that the *Ephemeridæ* had served
te long enough as an asylum for fossil cripples; I wished to
imate gently that refuse of other groups of insects should
henceforth "shot" elsewhere.

Mr. Scudder does not know by whom the Devonian insects
ave all been regarded as allies of the Ephemeridæ." My
thority for stating such to have been the case is Sir John Lub-
ck's Presidential Address in *Trans.* Ent. Soc. London, v.;
oc. cxxviii. (1868), where "*Haplophlebium Barnesii* . . . is
erred to the Ephemerina," and likewise "*Platephemera*
tiqua, *Homothetus fossilis*, *Lithentomon Hartii*, and *Xenoneura*
tiquorum" are said to be "all Neuropterous and allied to the
hemeridæ." As members of this family they are quoted by
arschall. *Dyscritus vetustus* was not cited by Sir John; but
ice Mr. Scudder now states it (p. 22) to be "most closely
lied" to Homothetus, there was no harm done in classing it
th the rest.

The reason why I thought, prior to the publication of Dr.
agen's letter in NATURE, that Platephemera might have been
Ephemeron, was that in some respects Mr. Scudder's figure
esents an appreciable likeness to the neuration of the fore-wing
in species of Palingenia, of which I possess unpublished drawings; but these certainly are not quite so odonatous in detail as Platephemera. Without inspecting actual specimens, it is hazardous to pronounce an opinion about fossils.

A. E. EATON

Chepstow Road, Croydon, S.W., March 28

Oceanic Phenomenon

FROM the description given by Dr. Coppinger of the "confervoid alga" observed on board H.M.S *Alert* some 200 miles to the southward of Tongatabu (NATURE, vol. xxiii. p. 482), the conferva in question would appear to be of a species similar to that from which the Red Sea is said to obtain its name. Whilst proceeding up the Red Sea in H.M.S. *Hornet* during the month of June of last year, I had many opportunities of observing the dirty-reddish scum on its surface—a phenomenon which must be familiar to all navigators of this sea. Each of the little bundles composing it measured about $\frac{1}{16}$th of an inch in length and $\frac{1}{100}$th in breadth, and contained from twenty to fifty filaments, each filament being composed of a linear series of short cells, and measuring $\frac{1}{3000}$th of an inch in breadth. I did not observe the discoid bodies referred to by Dr. Coppinger, but their absence may be explained by assigning to this conferva a particular season for the production of these bodies. Scattered among the bundles were tiny spherical bodies possessing a bristly appearance, which proved to be formed of a confused network of the filaments that composed the bundles.

This conferva would appear to have a very wide distribution. It was observed by Mr. Darwin near the Abrothos Islets which lie off the east coast of South America; and it is with regard to this phenomenon that the author of the "Journal of the *Beagle*" thus writes:—"Mr. Berkeley informs me that they are the same species (*Trichodesmium erythræum*) with that found over large spaces in the Red Sea, and whence its name of Red Sea is derived. In almost every long voyage some account is given of these confervæ. They appear especially common in the sea near Australia; and off Cape Leeuwin I found an allied but smaller and apparently different species. Capt. Cook in his third voyage remarks that the sailors gave to this appearance the name of sea sawdust."

H. B. GUPPY

17, Woodlane, Falmouth, March 28

The Banks of the Yang-tse at Hankow

AT the end of January, 1878, when the waters of the Yang-tse occupied their lowest level, I had the opportunity of examining the left bank of the river immediately below the foreign settlement. The bank, which varied from thirty to thirty-five feet in height, did not present a single perpendicular face, but was cut up into two or more terraces formed by the lingering of the waters at those levels for some extent of time. A calcareous loam, homogeneous in appearance and dark in colour, composed the entire bank with the exception of the upper portion, where a layer of sand a few inches in thickness separated two layers of laminated loam, each of them of similar thickness. After a little trouble I was enabled to observe that the apparently homogeneous loam was made up of fine horizontal layers varying from one-thirtieth to one-tenth of an inch in thickness; but the lamination was often concealed; and it was only where the loam had been freshly broken away that the layers were sufficiently distinct to be counted. Shells were embedded in the loam, but mostly in the lower half of the bank; those of the genus "Paludina" were the most abundant, whilst bivalves of the genus "Corbicula" occurred, but not in any numbers. The upper three feet of the river-bank were riddled with the burrows of annelids, and these burrows were often filled with little rounded masses of loam, evidently the excrementitious droppings of the worms.

If, as in the case of the alluvial valley of the Nile, it be considered that each of the fine layers which compose the bank of the Yang-tse was deposited during the periodic annual inundation of the river, then every layer will represent a year's deposit; and taking the average thickness of each layer to be one-twentieth of an inch, it would require twenty years to form an inch and a century to form five inches; whilst the whole thickness as exposed in the river-bank would require for its formation a period of between 7000 and 8000 years.[1]

[1] The borings and excavations round the pedestal of the statue of Rameses at Memphis enabled Mr. Horner to estimate the rate of deposition of the alluvium of the Nile at 3½ inches in a century. (*Vide* Lyell's "Principles of Geology.")

It may be pertinent to the subject of this paper to remark on the general appearance of the region around Hankow. A vast alluvial plain extends to the horizon in all directions; whilst dotted over its surface are several shallow lakes, which are lost in the general flood of waters when the Yang-tse overflows its banks in the summer months. Rising abruptly out of this alluvial formation are a few isolated groups of low hills, which in the time of flood stand out like islands from the surrounding waste of waters.

It would be interesting to asertain whether the banks of the Yang-tse possess this lamination whenever the river winds its way through an alluvial plain. I noticed the same appearance in the low banks of the estuary near the village of Wusung; the horizontal layers varying in this instance from one-tenth to one-fourteenth of an inch in thickness. Shells of both fresh-water and salt-water genera—"Paludina" and "Mactra"—were embedded in the bank.

H. B. GUPPY

An Experiment on Inherited Memory

WHEN I was a boy I had an electrical machine and Leyden jar; there was also a dog in the family. As a matter of course I "electrified" the dog, and ever afterwards during the remainder of his natural life he ran away in extreme terror when a bottle was presented to him.

The recollection of this has recently suggested an experiment that may be made by some of the readers of NATURE. By means of a small Leyden jar moderately charged startle *both the father and the mother* of an intended forthcoming generation of puppies. When these are full grown and away from their parents observe whether they are at all disturbed by the sight of a bottle or a Leyden jar, care being taken that the bottle is never shown to the parents in the presence of the offspring.

A single experiment will not be sufficient. It should be tried by several; for which reason I suggest it here. There is no more cruelty involved than in an ordinary practical joke. It is not the pain of the shock, but its startling mystery that frightens the animal, especially if the shock is given by placing the jar on a piece of tinfoil or sheet metal, and allowing the dog spontaneously to investigate by smelling the knob of the jar while his fore-feet are in communication with the outer coating. Under ordinary circumstances the dog obtains through his nose much information concerning the properties of things before he actually touches them, but in this case his whole life experience is contradicted by the mysterious, inodorous, diabolical vitality of the vitreous fiend. A bottle thenceforth makes upon the intellect of the dog a similar impression to that which a sheeted broomstick in a churchyard makes upon the similar intellect of a superstitious rustic.

W. MATTIEU WILLIAMS

Stonebridge Park, Willesden

Meteors

THREE very bright meteors were observed here during the month of December, 1880, and are, I think, worthy of record.

1. December 2, 1h. 14m. 50s. a.m. A meteor brighter than Jupiter descended towards the west point of the horizon, passing about 1° N. of Saturn, and somewhat farther from Jupiter, and in a line therefore nearly parallel to that joining those two planets. The train was visible about three seconds.

2. December 8, 10h. 55m. 30s. p.m. A meteor as bright as Jupiter descended towards the north point of the horizon, about 1° below η Ursæ Majoris, its path being inclined at an angle of about 35° to the horizon. The train was brilliant, but vanished speedily.

3. December 24, 10h. 4m. p.m. A very bright meteor, seen through (or below) the clouds in the south-south-east, shot down towards the south-south-west point of the horizon, at an angle of about 30°. No stars were visible in that part of the heavens at the time.

J. PARNELL

Upper Clapton, March 17

Classification of the Indo-Chinese and Oceanic Races

IN your issue of December 20 (p. 199), just to hand (February 12), I notice a contribution by Mr. A. H. Keane on the classification of the Indo-Chinese and Oceanic races.

As the *Orang Semang* of the Malay Peninsula is only just referred to, I conclude that the author has not seen Maclay's papers on the wild tribes of the Malayan Penin
second number of the *Journal* of the Straits Branch
Asiatic Society and a memoir by the same writer in
of Eastern Asia, of which unfortunately only
appeared. On the Jakuns, Maclay, who has probab
of their inner life and habits than any other ethnol
as follows of the *Semang* and *Lakai* tribes:—"Logan
of the Indian Archipelago, vol. vii. p. 31, 32), "tho
from some others, says that the *Orang Semang*
Negritos, but he calls them a mixed race. Accor
experience I must declare this also to be incorrect.

"From my own experience and observations I have
conclusion that the *Orang Lakai* and the *Orang*
tribes of the same stock, that further, in their phy
and in respect of language they are closely connecte
other, and represent a pure unmixed branch of the
race; anthropologically therefore they absolutely dif
Malays. The Melanesian tribes of the Malay Penin
because of the form of their skull, which has a ten
brachycephalic, approach the *Negritos* of the Philip
like the latter, they do not differ very widely from
tribes of New Guinea."

In the fifth number of the *Journal* of the Straits
the R.A.S., Mr. Swettenham, the Assistant Colonial
for the Native States S.S., thus describes the
Ijoh:—

"These people are short in stature, dark in colour,
hair is close and woolly like that of negroes, with
ence, that all the men wear four or five short tufts or c
of hair growing on the back of their heads, called

During my botanical excursion through Perak
had two *Semangs* as guides, answering to Mr. Swe
description.

The Straits Branch of the R.A.S. is as yet in
having been established only in 1877, and its Journa
bably not yet secured a very wide circulation, although
numbers that have been published contain practi
authentic information about the Malayan Peninsula
found elsewhere.

The characters Mr. Keane has employed to indicate
"papûwah" are certainly not Malayan; at any rate
a matter of impossibility to secure the services of a
Singapore who would be capable of deciphering the
word, which is a corruption of the Malayan or Javan

tive *puwah-puwah*, is usually spelt thus— 

Writing about New Guinea, Crawfurd ("A Descrip
tionary of the Indian Islands," p. 300) thus expres
about the word Papua:—"Some recent geograph
thought proper to give the great island the name of Pa
an innovation which is correct neither in sound, sense
graphy seems to possess no advantage over one whi
borne now for nearly three centuries and a half."

It may not be out of place here to remark that
Trübner and Co. are the London agents of the Straits
Singapore S.S., February 12

H. J. M

Fascination

IN the interior of the province Valdivia, South Chili
of wood-snipe (*Paipayen inc.*) is often caught by the
the following manner:—When the bird flies into one of
bushes, which in spots of about three to six metres diame
found frequently in the wood-meadows there, two men on
back go round it in the same direction, swinging their
the bush. After ten or more rounds one man slips down
his horse, whilst the other continues, leading his compa
horse behind. Carefully then the first man creeps on to the
where the paipayen is sitting nearly motionless or stupefied
the rider's circular movements, and kills it by a quick blow
stick.

When I first was told so I would not believe it; but in
or 1854 I took part myself in this kind of capture in the
San Juan, in Valdivia, belonging to my chief, Dr. Ph
now professor in the University and director of the
Santiago. I had left the house without gun, accompanied
native servant, when, in a part of the wood called
observed a paipayen falling into a dense but low bush

-mentioned kind. Desiring to obtain a good specimen of ot very common bird for our collection, I expressed my at not having the gun, but the servant replied: "Never if you wish, we will get the bird." And he caught it ny assistance in the above way without injuring it.
rburg, March 16 CARL OCHSENIUS

Flying-Fish

NE 11, 1873, at sea 300 miles south of Panama, I saw a of-war hawk and a school of bonitos in pursuit of a school ing-fish. As one of the latter came out of the water, y pursued by his enemy, the hawk swooped down, not fifty from the ship, but missed his prey, the fish *apparently* ag from its course to avoid him. A second attempt was successful, and the hawk flew off with the flying-fish in his s. The whole affair was plainly seen, as also was the nued chase of the flying-fish by the bonitos.

ALLAN D. BROUN,
Commander U.S. Navy
S. Torpedo Station, Newport, R.I., U.S.A., March 10

THE OXFORD COMMISSIONERS ON PROFESSORS

E are not disposed to agree with the outcry which has been raised in some quarters in reference he proposition of the Oxford University Commis-ers to enact certain regulations with the view of pelling Oxford Professors to reside in the University to give lectures.

me of the Commissioners' regulations relating to subject appear to many to be ill-advised, but they e been improved by the recent modifications, and the eral intention seems not only a right one, but also which must be carried out whenever public opinion ought to bear on the matter.

very simple view of the matter may be suggested. The essors in the English Universities might be put on same footing as are the professors in German Uni-ities. In those Universities the professors carry on adant research; they also give very numerous lec-s, usually what may be called "representative ses," that is, courses in which an attempt is made resent to the student the main outlines and much he detail of the subject professed. Even in the ège de France at Paris, which is *not* (strictly speaking) educational institution, each professor is required to an annual course of lectures (to the number of forty, believe).

esearch and the advancement of learning are, we do for a moment doubt, the highest, and therefore in a ain sense the first business of University professors. s perhaps because this is so generally admitted that Commissioners did not at first insist upon it. But it is rder that he may teach—not huge popular audiences cram-classes, but devoted thoroughgoing students— the professor creates new knowledge. His best ult is not new knowledge itself, but new youthful inves-tors ready and able to carry on the researches which as commenced, and through which they have learnt hod and gained enthusiasm. There is no stimulus to earch so healthy and so sure as that afforded by the ortunity of converting a class of generous-minded ng men into ardent disciples and loving fellow-workers. lence, it may be maintained, there is no neces-y antagonism between *true professorial teaching* (*i.e.* nite courses of lectures) and the profoundest study research.

hat the Commissioners have introduced no binding ulations with the object of forcing a professor to carry research, is, we believe, a proof of wisdom and a tribute to the dignity of such work. No regulations make an investigator: the question as to whether a n professorship will be used for the advancement of science and learning is decided before any regulations can have effect, viz., when the choice of a person to fill the post is made. If he is a "searcher" already, he will remain so; if he is not, a bad choice will have been made, and no regulations as to research can ever amend it. It is, however, well that the Commissioners have seen fit to improve their first set of regulations in so far as to state that an Oxford professor is *expected* to advance the study of the subject to which his chair is assigned.

The measures which the Commissioners propose for insuring the delivery of lectures by Oxford professors are objectionable on the ground that they are purely penal. They should be persuasive. The German professor is only too glad to give a thorough and attractive course of lectures if he has it in him to do so, because he thereby doubles or trebles the income which he derives from endowment. The Oxford Commissioners have made a great mistake in prohibiting the professors from charging fees for the compulsory course of two or three lectures a week. All students, whether belonging to the professor's own college or not, should be liable to pay fees to the professors for attendance on their courses of instruction, whether lectures or laboratorial. It is only by so arranging the position and endowment of a professor that he is both able and willing to increase his income by the fees paid by his class, that a really firm and satisfactory basis for the regulation of a professor's duties can be obtained.

It has been maintained that where an income derived from an endowment of 600*l.* can be increased to 1000*l.* a year by the receipts from lecture-fees, the professor will be anxious to give such lectures as will attract students—and in spite of objections ready to hand, it is held that those are the lectures which should be given. It is not true that a professor so circumstanced will necessarily degenerate into a mere examination coach. If he should be tempted to do so the fault lies with the examination. The professor should himself have a voice in the arrangement of the examination, and care should be taken by the University that it is so organised and defined in all its parts that students who have carefully followed a high class of professorial teaching, such as would be offered by a Huxley, a Ludwig, a Bunsen, or a Fischer, should come to the front in it rather than those who have crammed with some newly-fledged classman, or with an experienced "coach" versed in all the artifices of sham knowledge.

It appears to be an excellent and necessary provision to which it is to be hoped that the Commissioners will adhere in spite of all opposition, that the professors in each faculty should with other University teachers in the same faculty constitute a council having the power of controlling to some extent the lectures of each individual professor. There is no degradation in this; it is the almost universal custom in existing Universities. The faculty has to provide for the teaching of its proper studies, and naturally must exercise a friendly control over the extent and scope of the courses of instruction offered by its members.

It is owing to the absence of any such control at the present moment that even by those Oxford professors who do lecture, no representative course on *any subject* is ever given. A student in Oxford cannot by any possibility attend a thorough *course* of lectures or laboratory instruction in physiology, nor in zoology, nor in botany, nor in physics, nor in chemistry. And yet in the smallest as well as the largest of the often despised "medical schools" of London, a student has provided for him courses of from thirty to a hundred lectures every year in all these subjects, as well as in others, to be attended, of course, in successive sessions. The same absence of complete or representative courses of instruction is to be noted at Oxford in other departments, such as philology, archæology, various departments of history, &c.

The sole cause of the existence of such complete courses in other institutions than Oxford—over and above the primary one connected with the income from fees—is that the professor has to submit his scheme of lectures for the ensuing session or year in a general way to his colleagues, who would suggest to him a more complete or more representative program, were his proposals considered insufficient, and might take steps to supplement his teaching by the appointment of a supplementary professor (thus diminishing the original professor's income from fees), were he to prove intractable.

The keystone of the professorial system, on which all such control and persuasion, co-operation and reciprocal criticism, must rest, is the income from class-fees. In having not only not insisted upon this, but in having actually prohibited the free levying of fees, the Oxford Commissioners have made their scheme for professors absolutely unworkable. They have simply played into the hands of those who have at present a most injurious monopoly of the fees paid by students, and who give in return as little and as inadequate teaching as they please, namely, the confederacy of boarding-house keepers known as "college tutors and lecturers."

The proposal that professors should examine their classes and report to the Heads of Colleges as to the performance of each student was characterised by a spirit of petty interference quite unworthy of the large objects placed before the Commissioners, and has very properly been withdrawn. Such details, together with some other points, might well have been left by the Commissioners to the Councils of Faculties, which they so wisely intend to bring into existence.

It may be urged that if the Commissioners were to confine themselves in these and similar matters to creating the organisation which is terribly needed at Oxford, and of which these Councils of Faculties promise to be the most powerful and important part, they might with very great advantage leave the question of terminal examinations, and the scale of fees to be charged for lectures, &c., to be worked out by the reorganised University itself. But instead of prohibiting class-fees they should have strengthened the hands of the professoriate in the competition with the powerful band who are interested in maintaining the disastrous and absurd system of college tuition and tuition-fees. So long as the undergraduate is forced to pay to college tutors a lump sum of 25*l.* a year, he will seek his instruction (whether he finds it or not) from those whom he has been compelled to pay, and not from the professors whom he is not allowed to pay.

It is clear that with the present body of free-holders it was necessary for the Commissioners to insist on the new principle that a professor is not to be free from responsibility (*Lehrfreiheit*, we may observe, does *not* mean "freedom *from* teaching," as some writers who in the daily papers have recently appealed to German precedents almost seem to fancy), but is, on the contrary, to be charged with certain duties and to be responsible in a measure to his brother professors for performing those duties in a satisfactory manner.

ACADEMICUS

THE INTERNATIONAL GEOLOGICAL CONGRESS

THIS Congress is to hold its second session at Bologna, commencing on September 29, 1881, under the presidency of Signor Q. Sella, president of the Accademia dei Lincei of Rome, and under the patronage of His Majesty the King of Italy, who has liberally placed the necessary funds at the disposal of the Italian Committee of Organisation, of which Prof. J. Capellini of the Bologna Museum is the president, and General Trannelli of the University of Pavia the secretary.

The movement sprang out of a suggestion made at a meeting of the American Association of Scien Buffalo, New York, August 25, 1876, that a tional Geological Congress was advisable, uniformity of methods of representing geolog mena, and the value of terms. Towards this mittee of organisation was formed, of wh James Hall was president and Dr. Sterry H tary, in which England was represented by Pr and Sweden by Dr. Otto Torell. The res deliberations was the first session of the Co at Paris, in the Palace of the Trocadéro, unde dency of Prof. Hébert and the patronage of t of Public Instruction. At the Congress, whic days, two International Commissions were ap one to consider geological cartography, with adopting a common system of signs and c other to investigate the possibility of effecting cation of geological nomenclature and to c matters relating to stratigraphical classifi nomenclature, to a certain extent involving into the value and significance of petro palæontological characters. A third Commissi French, was also appointed to report on Bolo rules to be followed in establishing the nome species in mineralogy and palæontology.

M. Renevier, general secretary of the first C has just published his second report of pr states that advantage was taken of the presenc members of the Commission during the fi versary meeting of the Geological Society of April 2, 1880, to hold a meeting of the Com which five European countries were represe the presidency of M. Daubrée; since then, m detailed reports from nearly all the committee ing different countries have been received, e Canada, presided over by Mr. Selwyn, and G by Prof. Ramsay. In some of these schemes considerable amount of agreement. Quaterna being represented by a pale green, Plioce yellow, Miocene dark yellow or orange, Eocen Cretaceous by green, Jurassic by blue, Lias Trias by burnt sienna, Permian and Carbo dark grey, Devonian by brown, or brown stripe Crystalline schists by rose carmine, Granit carmine, divisions in the various rocks being by tints of the same colour, or by shading or d

The General Secretary of the Commission f fication of Nomenclature is M. Devalque, w that this Commission also met at the Paris Society's anniversary, France being represen Hébert, Switzerland by Prof. A. Favre, and Ge by Prof. Hughes. The latter Commissioner Prof. Prestwich, has now succeeded in or British sub-Commission, who have appointed mittees to inquire into groups of formations, draw up a list of the names now in use; (2) t the true significance of such names or terms, gi ence to the authors by whom they were used i instance, or subsequently with a modified mea to investigate into the synonomy of such names in the first place as regards the British Isles, wards to inquire into their correlation with them other areas; and (4) to offer suggestions for th tion of the nomenclature. As the committees c sit, as their members are scattered, they h modelled on the principle of the Inquiry Com the British Association, and have attached to or two "reporters," charged with assimilating and facts collected by the Committee. The rep the British Isles, are for Recent and Tertiary rock Starkie Gardner and H. B. Woodward; for C rocks Messrs. Topley and Jukes-Browne; for rocks Messrs. Huddlestone and Blake; for T Permian, Mr. De Rance and the Rev. A. Ir

an, and Old Red, Messrs. Morton
ian, Cambrian, and Pre-Cambrian,
l Marc. For chemical, dynamical
mineral veins Messrs. Bauerman

committee is specially to consider
ature under the following general
nded on physical characters; (2)
mposition; (3) founded on names
on local peculiarities and common
theories of origin and other hypo-
; (7) suggestions for systematising
omenclature.

a or General Committee has Prof.
an, and Mr. E. B. Tawney for its
to receive the reports of the Com-
er the value of terms. The list of
ub-Commission includes those of
Professors Bonney, Boyd Dawkins,
Lebour, Morris, Prestwich, Rupert
octors Clement Le Neve Foster,
ie, Hicks, Nicholson, and Sorby,
y mentioned, of members acting
, and the Chairman. The Sub-
iat the word *system* should be used
the largest sub-division, applied to
by itself, easily and clearly distin-
ocks above and the rocks below,
elow by triads in stratigraphical
rised by special forms of life.
smaller group, with some litho-
gical characters in common, but
tinuous sequence with the rocks
eposit implies similarity of litho-
ers, *lamina*, *bed*, *group*, *series*, and
scussion. *Zone* and *horizon* were
data were left open questions.

ity of His Majesty the King of
of organisation are able to offer
for the best suggestion for an
colours and conventional signs
to geological maps and sections,
all scale. The index of colours
companied by maps representing
ical structure, and by an explana-
ench language. The documents
a motto, which should be placed
elope containing the name of the
e opened until the Congress, when
ful competitor will be made known.
nying papers should be sent in to
tor of the Museum at Bologna, by
award will be made by a jury of
presidents of sub-commissions.
ought worthy of the grand prize,
gold medal of the value of 1000
vo next will be given medals of
ilar shape. C. E. DE RANCE

NIAGARA IN WINTER

last February it fell to my lot to
y the transcontinental journey of
Francisco to New York. Before
the one stoppage which I could
ould be made at Niagara. I had
early summer of 1879, and was so
y them that I could not resist the
them again under their wintry
nfirmed in my resolve by seeing
merican papers to the effect that,
nued and exceptionally severe cold
ie Ice-mountains at the Falls were
higher than had ever been previously known. These statements were confirmed to me on the spot by several persons long resident in the village.

Two or three preliminary notes on the journey across the Rocky Mountains in midwinter may not be without interest for the readers of NATURE. I left San Francisco on February 2nd in the midst of most serious floods, and on that particular day they attained their maximum, which was one inch higher than any previously recorded. It was estimated that 3500 square miles of the most fertile land of California was under water, and in many parts steamboats of light draught were plying over the country. Any assessment of damage would have to be made by millions of dollars. I heard many and grievous complaints of the damage done to the agricultural interests of the country by the "hydraulic mining," which washed the hillsides down into the river beds, filling them up, and thus prevented much flood-water from being carried off. In some places the railroad track had been apparently washed away, for it could not be found, and from this cause our journey to Sacramento was lengthened about fifty miles, as the gigantic ferry-boat *Solano* could not be used for the short route. This boat has four tracks upon it, and will carry twenty-four cars. As each car seats fifty people, this is equal to carrying a train that will accommodate 1200 people. It has four side-wheels, each with its engine and set of boilers. In crossing the Sierras we encountered little snow, but a great deal of rain. The greatest amount of snow on the journey was in the upper part of the Weber Cañon, 100 miles east of Ogden and Salt Lake. Here there had been considerable difficulty in keeping the line open during January, but the train-service had not been interrupted for a single day, although the snow-sheds and snow-ploughs were constantly required. That the weather had been unusually severe was shown by the very large number of dead cattle along the line, from Ogden across the Laramie plains, and also, I was informed, in Colorado. In the four days between San Francisco and Omaha (where we arrived punctually), the terminus of the Pacific Railroad, the temperature was never below 26° F., and the air so still that I frequently saw smoke rings from the locomotive funnel expand to 6 or even 8 feet diameter, rising perhaps 30 or 40 feet in doing so. All the cars were warmed, usually to too great an extent, from 70° to 75° F., being the normal temperature for the interior of railway cars, hotels, private houses, and schools, as far as my experience went.

East of the Missouri (which, like all the rivers I crossed, was frozen over) trains were everywhere very much delayed, owing to snowstorms, or to the slippery state of the rails, which were coated with ice. The utmost caution was used by those in charge of trains, and a strong impression was left on my mind that safety, and not speed or punctuality, was the primary consideration in such American railway management as I came across.

On leaving Chicago a phenomenon presented itself which is common enough in America, though but rarely seen in this country, and never on so gigantic a scale. For several days the temperature had been very low, and every object was exceedingly cold. On the night of February 6th, the air-temperature rose to 33° F., and fine rain fell. This froze upon everything and encased it with transparent ice, from which in many instances delicate icicles depended. Sad havoc was played with the overhead telegraph wires in Chicago itself (which were broken by the weight); but on leaving the city in the early morning the exceeding beauty of the whole country, usually so uninteresting from its flatness, became apparent. A light coating of snow lay on the ground, but everything, every twig, every dead leaf, every blade of grass, had its own transparent covering, which in the occasional gleams of the sun shone with the most gorgeous colours.

Gigantic icicle under Table Rock, photographed in January, 1893. The upper right-hand corner is rock, and a portion of the Canadian (or Horse-Sh is seen on the left. The whole of the apparent ground is a mass of frozen spray which has accumulated many feet in thickness on the slough a the foot of the rock.

Probably the most wonderful exhibition ever seen, of, not frozen rain, but frozen spray, was to be found at the Falls of Niagara. A large number of readers of NATU have visited them, and possibly all are sufficiently fam

through the medium of books and
r any general description unneces-
onfine myself to the special features
er's cold.
lay under a thin coating of snow,
e in good condition for sleighing.
falls were so completely ice-covered
to render no other mode of loco-
ose who have seen both places have
as I was, with the strong resem-
rge of the Niagara river below the
f the Avon at Clifton, Bristol. The
he two, being narrower, and having
are limestone gorges, and similar
e Niagara gorge numerous springs
into the chasm at various points in
sides, and at these points numerous
and massive icicles appeared as
e rock, measuring perhaps seventy
th, and eight to ten feet in irre-
he exquisite purity of their colour
nce, they reminded me strongly
in the upper part of the Rhone

ver itself was not a little lessened,
ve and the comparatively still water
e ice at the banks, and it was a
otice how much ice accumulated at
was running very rapidly. At the
all itself there were so many accu-
e Fall was actually divided into five
Falls, in the same way as, even in
of the Fall which is in front of the
is cut off by rocks on the upper
ody of the Fall.
"Cave of the Winds" recalls also
"Rock of Ages," in front of this
That however is only one of many
American Fall, and these boulders
ntic nuclei, round which the frozen
nd produces the Ice-mountain of
ich, and the remains of which are
be seen even by summer visitors.
f this is about half the total height
inter it has attained to the unpre-
within twenty feet of the top of the
point is at about one-third of the
all, measuring from Goat Island,
he incline from Prospect Park and
s another very high mass. The ice
e to the front of the Fall, and the
h the water descends is thus closely
lly covered, with an enormous and
e semi-transparent ice, of (on the
ost beautiful emerald green hue.
id the good fortune to fall in with
rist who is so well known for his
scenery, and in discussing the ice
erfalls, he mentioned that, having
Yo Semité valley in California, he
close to one of the celebrated Falls
ast 600 feet in height.
w years a considerable portion of
llen away. In its present condition
ut one foot in thickness falls over it
g to the amount of its overhanging,
en this Fall and the rock, and thus to
At the time of my visit (February
le of this portion of the Fall was *com-*
Enormous icicles, of the most sur-
ided from the rock above, while at
of the frozen spray from the Horse-
e emerald green of the water of that
nd between these magnificent ice-

pendants, could be reproduced by no artist, but will never be effaced from my memory. The accompanying woodcut, photographed on to the wood block from a photographic picture taken a few days prior to my visit, will, to those who know the place, give some faint idea of the beauty of the scene, and of the gigantic scale of the icicles. It is scarcely necessary to say, perhaps, that the circular wooden staircase by which the descent under Table Rock is effected, was covered with many feet thickness of ice on the side next the Fall. As the air-temperature was slightly above 32° F. and the icicles were occasionally falling around us, my guide was unwilling that I should remain long, or make any attempt to measure any of the ice-masses.

The fourth, and to the casual visitor perhaps the most remarkable effect of the cold in the immediate neighbourhood of the Falls, is the manner in which every surrounding object is coated with an immense thickness of frozen spray. The trees on Goat Island and in Prospect Park are thus covered to a slight extent, and present a very beautiful appearance. The strangest examples, however, occur on the Canadian side, close to the Horseshoe Fall, where huge irregularly-shaped masses of ice are seen, some of which resemble, in general form, merely a colossal bunch of grapes standing erect on its stalk. A little investigation shows that these are trees, staggering under the weight of tons of ice. Not unnaturally they have many broken branches, and have almost invariably lost their tips. In one instance which I saw, and of which I obtained a photograph, the spray had so accumulated in front of the trunk of a tree about nine inches in diameter, that it had formed a wall of ice *five feet* in width, and of the same thickness as the diameter of the tree-trunk. A flagstaff planted on Table Rock had four or five projections from its top, varying from three to five feet long, and looking like "frozen streamers," or as though watery flags had been flying, and had suddenly been frozen. These were so inaccessible and so dangerous to the passer-by, that they were daily shot down with rifle-bullets! The museum with its pagoda and the adjoining houses close to the Horseshoe Fall were cased with sheet-ice and pendant icicles to such an extent that much of the frozen spray had to be removed daily with an axe.

I mounted to the pagoda (well remembered, I have no doubt, by summer tourists) and there I listened to the "Music of Niagara," of which Mr. Eugene Schuyler has given in the February number of *Scribner's Magazine* an account so interesting, that I venture to conclude this article with a short abstract of it.

Mr. Schuyler starts with the statement that "the tone of Niagara was like that of the full tone of a great organ. So literally is this true that I cannot make my meanings clear without a brief outline of the construction of that great instrument." He then explains the mutual relation of the various pipes, the "ground-tone, over-tones or harmonics, and under-tones or sub-harmonics," and relates his experiences in the Cave of the Winds, on Luna Island above the Central Fall, at the Horseshoe Fall among the rapids, and at the Three Sister Islands. "In fact, wherever I was, I *could not* hear anything else! There was no *roar* at all, but the same great diapason—the noblest and completest one on earth!" Further details of visits to various points are given, and it is interesting to notice that although previously unacquainted with the difference in height of the two Falls, Mr. Schuyler unhesitatingly pronounced the Horseshoe Fall to be several feet lower than the other, guided solely by his musical ear. He then proceeds thus:—

"Now, what is this wonderful tone of Niagara? or rather, what are all these complex tones which make up the music of Niagara? With more or less variation of pitch at various points (to be accounted for), here are the notes which I heard everywhere:—



Just these tones, but *four octaves lower!*

"At once it will be incredulously replied, 'No human ear ever has heard, or ever can hear, tones at such a depth.' I arrived at my conclusions both theoretically and practically, and the two results coincided exactly." For the explanation of this, those interested will do well to consult the article itself. It may be noted here, however, that notes 3 and 4 were heard *everywhere;* that the 5th and 6th were perfectly distinct, but of far less power; that the 7th (the interval of the tenth) was of a power and clearness entirely out of proportion to the harmonics as usually heard in the organ, &c.; and that the 8th, 9th, and 10th notes were only heard occasionally and with a transient impression. Mr. Schuyler then points out that, allowing for the fact that the diameter of Niagara is the *greatest* possible compared with its height, the length of an organ-pipe necessary to give the key-note of Niagara (four octaves below note 1 in the diagram) would be just the average height of the Falls! The figures given are 170·66 feet – 10·24 feet = 160·42 feet, where the 10·24 feet is the allowance for the extra diameter of Niagara treated as an organ-pipe.

It appears, then, that the tone of Niagara is, *note for note*, the dominant chord of our natural scale in music. Its rhythm is one note per second, with three notes in each measure, the first note being the accented one, and the single beats are represented by groups of three semi-quavers, where M.M. 60 = ♩ or three times three, three times repeated.

Mr. Schuyler thus concludes in words with which I heartily sympathise. "I have spoken only of the pitch and rhythm of Niagara. What is the *quality* of its tone? Divine! There is no other word for a tone made and fashioned by the Infinite God. I repeat, there is no *roar* at all—it is the sublimest music on earth!"

WILLIAM LANT CARPENTER

ZOOLOGICAL RESULTS OF THE VISIT OF PROF. K. MOEBIUS TO MAURITIUS[1]

THIS work, which is illustrated by a map and twenty-two plates, contains the results of the investigations of Prof. Möbius on the marine fauna of Mauritius and the Seychelle Islands, embodying the account of observations made by him on the spot, and of work done on the collections which he brought home with him on his return from his visit to the islands. It commences with an account of the journey to Mauritius in 1874-75; an account of the Suez Canal is given, and of the voyage through the Red Sea, where Trichodesinium, the yellowish-red floating algæ supposed by some to have given the name to the sea, was met with in abundance. After the well-known tanks of Aden and the Somali divers who surround every ship that comes into the port have been described, Réunion is touched at, and at last Mauritius.

A concise account is given of the geographical, geological, and climatic peculiarities of this island, which is about one-third the size of Holstein. The centre of the island is occupied by a plateau elevated over 1700 feet above sea-level, the highest point being 2711 feet in height. The plateau is surrounded on nearly all sides by mountains, and from these on all sides but the northern, where there is a gradual inclination, rivers and streams fall down very steep slopes with frequent waterfalls into the sea. Rains are very heavy, and the mountain torrents swell with remarkable rapidity. The geological structure of the island is entirely volcanic, with the exception of beds of coral rock. The mean temperature of the year is about 25°85 C. Rain is most abundant from December to May. The prevailing wind is the south-east trade. Cyclones are sometimes experienced in the period, December to April, but do not occur every year.

Mauritius had originally no mammalian inhabitants excepting bats. The great fruit-bat (*Pteropus vulgaris*) is abundant in the woods. These fruit-bats are easily tamed. One of them was a great pet of Mr. G. Clark, now dead, who was the author of "A Brief Notice of the Fauna of the Mauritius," published in the *Mauritius Almanac* for 1859, and containing some very good observations. This tame bat was taken when young from its mother's breast and brought up by hand. It could not fly, because its wing membranes had been cut through to prevent its doing so. It usually passed its time hanging on to the back of a chair. Directly Mr. Clark came into the room it cried out loudly to be nursed. If it were not taken up at once it climbed up to him, rubbed its head against him, and licked his hands. If Mr. Clark sat down the bat hung on at once to the back of the chair, and followed all the movements of its master with its bright eyes. If its master caught hold of a fruit it climbed forth with down his arm to his hand to get its share, and it always got two teaspoonsful out of every cup of tea or coffee. If Mr. Clark took any kind of object in his hand the bat climbed to it, examined it with its eyes and nose, and only returned to its chair-back after completely satisfying its curiosity. It followed its master even into the open air if the door was not shut to prevent its getting out.

A good many mammals have been introduced into the island, and are now abundant. A monkey from the East Indies (*Macacus cynomolgus*) inhabits the woods, and makes excursions from thence to plunder the sugar-cane fields. One of the species of the curious hedgehog-like insectivora of Madagascar (*Centetes ecaudatus*) was introduced in the island at the end of the last century. The animals live in damp places and lie in a state of sleep (= hybernation) in the dry season, sleeping therein so soundly that they do not awake even when dug up. As soon as the rainy season begins in November they wake up and breed, producing three litters of fifteen or sixteen young every year. The young follow the mother, who calls them with a grunting noise, in a row behind, and protects them when molested with her teeth and spines. A full-grown male weighs as much as four pounds. The animals are so abundant that on a moonlight night with trained dogs twenty or thirty may be caught by one hunter. They are eaten by the working classes.

Besides these there is a shrew mouse, also introduced from the East Indies, a small hare, and the ubiquitous common rat, both of which latter gnaw and destroy the sugar-cane. A stag (*Cervus hippelaphas*) introduced by the Portuguese inhabits the woods. It breeds in July and August, and casts its horns in December or January.

We cannot follow the author in his short reference to the birds and account of the fish. The coral-reefs of the island appear to abound with animal life of all kinds. Several of the corals composing them are laid dry constantly at low tide, and remain exposed to the air without injury. *Goniastræa retiformis* and *Leptoria gracilis* are cited as examples of such. Whilst these corals are in this condition, the polyps remain entirely withdrawn, and the whole surface of the coral laid bare is covered with slime, which prevents its drying up.

In the Seychelles, of which a short account is given, the giant turtle (*Chelone virgata*) is kept in ponds as at Ascension, and is caught with a rope round the flipper and dragged out to be slaughtered when convenient. The

[1] Beiträge zur Meeresfauna der Insel Mauritius und der Seychellen, bearbeitet von K. Möbius, F. Richter und E. von Martens, u.s.w. (Berlin: Otto Enslin. 1880.)

or here dug up a Cæcilian (*Cæcilia virgata*), and ied himself with the curious leaf insect (*Phyllium folium*).

ıe Introduction to the book is followed by a long r by Prof. Möbius on the Foraminifera of the ritius, illustrated by many finely-executed plates. ıngst other Rhizopods a Haliphysema occurs, the ıal which, by a most extraordinary blunder, was made by Häckel to have a multicellular structure, and ıosed to represent a Gastræa of modern times. Prof. ıius confirms the observations of Carter, Savile Kent, Ray Lankester, to the effect that the animal is in ty simply a Rhizopod. He has examined the struc- of the Foraminiferous shells which he describes, very fully by means of sections. He does not, however, anything of importance to our knowledge of the cture of the soft tissues of the group.

n account of the Decapod Crustacea by Dr. F. ıter follows that of the Foraminifera. Two crabs of t extraordinary habits are described in this portion he work. Both belong to the family Polydectinæ. : crabs of this family have their front claws armed ı large teeth. Latreille, who first named the crab *ydectes cupulifer*, remarked that a gummy substance always to be found at the ends of the claws of this cies, and Dana described the animal as having always ıething spongy in its hands. Dr. Möbius has discovered remarkable fact that these things held in the two ws of the crab are in reality living sea-anemonies. ese sea-anemonies are attached to the immovable joint each claw, whilst the teeth of the movable joint of claw are kept buried deep into the flesh of the sea- monies, and thus hold them fast, although each mony can easily be pulled away from its position with forceps in specimens preserved in spirits. The mouth he sea-anemony is always turned away from the crab. e same curious combination exists in the case of ther species of the same family but of a different ius, *Melia tessellata*, which also inhabits Mauritius. igure is given of this crab with its pair of Actinias, ned by Möbius *A. prehensa*, with fully expanded tacles, held out one in each hand. Möbius gives the lowing account of the matter. "I collected about fifty le and female specimens of *Melia tessellata;* all of se held in each claw an *Actinia prehensa*. The re- ved hooks of the inner margins of the claw joints of crab are particularly well adapted to hold the Actinias t. I never succeeded in dragging the living Actinias t without injuring them. If I left the fragments of em when pulled out lying in the vessel in which the *elia* was, the crab collected them again into its clutch a short time. If I cut the Actinias in pieces with the ssors, I found them all again in the claws of the crab er a few hours. It is very probable that the Actinias l the crab in catching its prey by means of their thread- lls, and that the Actinias, on the other hand, gain by ing carried from place to place by the crab, and thus ought into contact with more animals which can serve food to them, than they would if stationary. This is very interesting case of commensalism."

The work closes with a long account of the Mollusca Mauritius and the Seychelles by Prof. E. von Martens.

H. N. MOSELEY

NOTES

THE centenary of the birth of George Stephenson is not to be lowed to pass by in a fruitless way in Newcastle-upon-Tyne. inners, speeches, trade-processions, enthusiasm and bunting—l this was to be expected in a place so intimately connected th the birth of railways. But more than this will probably be ne, and we are glad to hear that a scheme is on foot for com- emorating the 9th of June in a more useful and more lasting nner, viz. by providing a "Stephenson College" for the use of the houseless but hard-working College of Physical Science of the University of Durham in Newcastle.

THE French Association for the Advancement of Science has been in existence only ten years, but in that short time it has met with astonishing success, and has done some excellent work. To the fifteen sections already existing it proposes to add a sixteenth, under the name of the Section of Pedagogy, and a committee of members will discuss its formation at the forthcoming meeting at Algiers. The subjects of which the Association takes cognisance are divided into four groups, viz., Mathematical Sciences, Physical and Chemical Sciences, Natural Sciences, and Economic Sciences. A goodly list of papers has been already announced, among the authors of which we notice some of the most prominent *savans* in France. We trust, however, that the Association will not degenerate into a great excursion organisation, as to some extent it appears to have done this year. Thus the meeting lasts for six days, while the return tickets, issued in connection with the Association under very liberal terms, are good for six weeks, and no less than fifteen excursions in the neighbourhood of Algiers have been arranged. Five of these each occupy a week, and one of them a fortnight. The great number of applications for tickets both from France and Spain compel us to imagine that in many cases the membership of the Society has been sought this year rather for the sake of the tempting excursions than for the love of science. April is one of the most lovely months in the year at Algiers: the mean temperature is 16·5° C., with a possible minimum of 8°, and a possible maximum of 30°. In May the mean temperature is 19·5° C., and there may be eight days of rain; while at Biskra the maximum may be as high as 40° C. (104° F.), and not more than one day of rain may be expected in May. A proclamation has been issued by the local committee asking the inhabitants to place rooms at the disposal of the visitors. Among those who will cross the Mediterranean will be Admiral Mouchez, MM. Quatrefages, Wurtz, Saporta, the naturalist, M. Cartaillac, the geologist, and many others, who will give interesting papers on a variety of subjects.

MR. ASHTON DILKE tried in vain on Tuesday to get the House of Commons seriously to consider the advisability of adopting the decimal system of coinage in this country. It is hopeless in the present state of public affairs to induce Parliament to attend to a matter of this kind. On the widely beneficial results of the adoption of the metric system in whole or in part we have often insisted. That there would be some inconvenience in making the transition, of course every one will admit; but as compared to the ultimate benefits from the adoption of the metric system, they are not worthy of consideration. Mr. Dilke does well not to let the matter drop out entirely of public notice.

THE Thore prize of the Académie des Sciences of Paris has been awarded to M. A. Vayssière, préparateur des cours de Zoologie à la Faculté des Sciences de Marseille, for an anatomical memoir of *Prosopistoma punctifrons*, Lat. Some of our readers interested in comparative anatomy may remember having seen the original drawings in London last summer, and will be glad to know that it will soon be forthcoming. M. Vayssière is a careful expert.

THE French Minister of Public Instruction intends to do a great service to science by publishing monthly a *résumé* of the scientific work being done over France, under the title of *Revue des Sciences*. The review will be under the direction of the venerable M. H. Milne-Edwards, and will consist exclusively of analyses and summaries, but of sufficient detail to give a fair idea of the nature of the work being done. It will embrace the work of individuals and of societies all over the country, and each number will contain about 100 pages.

M. Delesse, a member of the Institute, vice-president of the Geographical Society of Paris, and author of a number of works and papers on geology, died in Paris at the age of sixty-three years.

The death is announced on the 25th inst. of Sir Charles Reed, M.P., the much-respected chairman of the London School Board.

A meteorological observatory has been erected at Port-au-Prince, Haiti, under the care of the Rev. Father Wiek, on ground granted by the State. It is an octagon of two stories and a platform. Besides the indispensable instruments it has electric clocks (for communicating the time to clocks outside), telephones, microphones, phonographs, radiometers, &c.

The inaugural meeting of a Society of Chemical Industry will be held in the rooms of the Chemical Society, Burlington House, Piccadilly, on April 4, at 4 p.m. This Society is not intended to represent any one particular branch of chemical industry. It is hoped that it will be representative of many manufactures—alkali-making, manure-making, the textile colour industries, the glass and pottery manufactures, tar distilling, soap-making, sugar-making, brewing, metallurgy, the manufacture of fine chemicals, and all other industries which show any connection with chemical science.

The newly-issued part of the *Medical Reports* which are from time to time issued by order of the Inspector-General of Chinese Maritime Customs, contains an elaborate monograph by Dr. Duane B. Simmons on the subject of Beriberi, or the Kakké of Japan, which includes some interesting notes on the history and geographical distribution of the disease, and is illustrated by a sketch-map.

Mr. Bowdler Sharpe, F.L.S., delivered on Thursday last the concluding lecture of a series on the "Birds of the World," which he has been giving at Tonbridge School. Throughout the winter lectures have been given on various literary and scientific subjects by Prof. Henry Morley, Rev. A. Lucas, and others, and large and attentive audiences have shown great interest in all the series. The school already possesses a small museum, which is increasing under the auspices of the present head-master, the Rev. T. B. Rowe, who is evidently doing his best to encourage a taste for science and literature in the institution under his charge.

Every ornithologist should read a little pamphlet recently sent to us by the Dundee Naturalists' Society, entitled "The Grallatores and Natatores of the Estuary of the Tay; the great decrease in their numbers of late years; the causes; with suggestions for its mitigation. A paper read by Col. Drummond Hay." The author, whose long residence in the district alluded to renders his experiences doubly interesting, makes out a good case for his friends the birds in regard to their alleged destruction of fish and spawn, and no doubt some notice will be taken of his statements at the approaching Fisheries' Exhibition at Norwich. The principal cause in the decrease of the birds on the Tay he attributes chiefly to the increased number of gunners on the river, who disregard the close-season, while the wilful destruction of the sea-birds' eggs also plays sad havoc amongst their numbers. Drainage and cultivation of the land has also altered the conditions under which certain species nested, and has driven them further afield.

A Conference on the reform of the Educational Code is to meet in London in the third week in April, and to sit for two days, for the purpose of drawing up a series of recommendations, to be submitted in the form of a memorial to the Vice-President of the Committee of Council. The gentlemen invited to attend are persons conversant with the practical working of the public elementary school system, head-masters of secondary schools, persons experienced in education, and others interested. Invitations have been accepted by the chairmen of the Education and School Management Committees of the School Boards for London, Liverpool, Birmingham, Leeds, Sheffield, Bristol, Bradford, Leicester, and Nottingham; also by Dr. Abbott, Dr. Caldicott, Mr. Eve, Professors Max Müller, Carey Foster, Heurici, Gladstone, and Mekliejohn; Sir J. Kay-Shuttleworth, Sir. John Lubbock, the Rev. Mark Pattison, and numerous others.

Mr. Stephen Bretton, F.M.S., writes from Eastbourne to the *Times*, under date March 28, that he saw a meteor of great splendour that morning (1.15 a.m. Greenwich mean time), the finest he ever observed. Its size was apparently rather greater than Venus at her brightest, and for two or three seconds illuminated the heavens very brilliantly. Its colour was of an intense purple white, and moved somewhat slowly. He first noticed it a little south of Regulus, and going in direction of Castor. It immediately below Præsepe it burst into about five or six fragments, each about the size of a star of the third or fourth magnitude, these assuming a deep fiery red. It then immediately disappeared. The night was especially clear; temperature of air about 30°; barometer about 29·850.

The Committee of the "Frank Buckland Memorial Fund" have decided that the memorial shall take the form of a bust to be placed in the Fish Museum at South Kensington; the proceeds of an annuity to be presented to Mrs. Buckland; and, if there be any surplus, it will be applied in some way to promote the welfare of the fishermen of this country. The honorary secretaries are Col. Bridges and Mr. T. Douglas Murray, to whom subscriptions may be sent at 34, Portland Place.

Smart shocks of earthquake occurred at Agram on March 24 at 3h. 40m. a.m., duration three seconds, and on March 25 at 6h. 45m. a.m., both accompanied by loud subterranean noise.

There was another earthquake shock at Casamicciola on Sunday morning at 6.45.

M. van Malderen, who was the electrical engineer of the Alliance, and constructed the so long unrivalled magneto-electric machine belonging to this Company, died at Brussels at the age of seventy a few days ago.

All the obstacles which have prevented the reconstruction of the Sorbonne being accomplished, have been removed by M. Jules Ferry, and the work will begin immediately. The same may be said of the isolation of the Public Library of Paris, the required expropriations having been decreed.

The date for admission of exhibits to the International Exhibition of Electricity at Paris has been prolonged to April 15.

The Geologists' Association Easter Excursion will, as on Monday and Tuesday, April 18 and 19, to Salisbury, Stonehenge, and Vale of Wardour.

Colonel Paris, the head of the Paris fire brigade, has concluded his report on the destruction of the Printemps Establishment by proposing that large warehouses be compelled to light by electricity. The burning of the Nice Theatre, which was occasioned by a gas explosion, has given a new importance to that movement.

M. de Meritens has completed the construction of one of his magneto-electric engines intended for lighthouse illumination. An experimental trial took place on March 25 before MM. Becquerel, Cornu, Mascart, and other members of the Technical Commission of the International Exhibition. It was proved that with fifteen horse-power his machine illuminates at one more than thirty Jablochkoff lights, and that it could, at a moment's notice, be used in a regulator for marine purposes.

D, the Banff naturalist, has reprinted in ful and interesting papers on the Pro- The pamphlet is to be had at the e.

Zoological Society's Gardens during the gyptian Gazelle (*Gazella dorcas*) from Earl of March, F.Z.S.; a Common South European, presented by the Rev. oad (*Bufo agua*) from Brazil, presented k; a Long-snouted Snake (*Passerita* presented by Mr. H. H. Black; an *Varanus amboinensis*) from Szechuen, *Cygnus atratus*) from Australia, pur- *Hegri*), a Bactrian Camel (*Camelus* Deer (*Cervus aristotelis*), born in the

ONOMICAL COLUMN

TAR.—On July 26, 27, and 29, 1783, which he twice estimated 6m., and on is No. 5057-9 in Gould's reduced cata- ree observations giving for 1800, R.A. Decl. + 17° 19′ 42″·8. The only sub- have yet found of this star is in the it is rated as low as 9·4m.; there is obability that it will prove to be a ne position brought up to the beginning 9h. 27m. 22ˢ·1s., Decl. + 17° 29′ 28″; rvations will be found at pp. 542, 544. *Histoire* of Lalande.

ETC., IN 1880.—Prof. Julius Schmidt ations, or rather the results of his obser- er variable stars, made at Athens during paring his epochs of minima with the ld's last catalogue, it will be found that mpletely determined minima the calcu- rly half an hour. But the differences observation are very irregular, so that whole, the true minimum would appear computed by only nineteen minutes, ugust 28 and December 21 are here

ervations of the same indefatigable as at a maximum between July 20 and tained about 4·2 m. A maximum of it November 9; the determination is e intervals between maximum and d of a Hercalis were as irregular as

N JUPITER'S DISK.—Dr. Jedrzejewicz nces from observations for ascertaining e eastern extremity of the large red spot , made at his private observatory at of 1880-81. The instrument employed apertura, with powers 225 to 300. In he length of the spot 9″·8, and considers compared with those of Prof. Schmidt the length of the spot remained un- r. On this assumption he finds for the m. 34′·414s. ± 0′·13s. by 174 rotations 1880, and February 5, 1881. Prof. ions between July 23, 1879, and Sep- d the value 9h. 55m. 34·422s. ± 0·05s. pot. In 1862, by observations upon a much darker and a more favourable than the spots observed by Airy and which was not much larger than the ite he had found for the time of rotation g with the previously-determined values. bservations of the red spot is 9s. greater, at it agrees very nearly with that already

.—It appears that the object detected v Observatory of Vienna on the 23rd of last month, and which was announced as No. 220 of the small-planet group, may prove to be No. 139 *Juewa*, which had not been observed since 1874. It was discovered by the late Prof. Watson at Pekin on October 10 in that year, while he was engaged upon one of the United States expeditions for the observation of the transit of Venus, and as was reported at the time, without the aid of a chart of telescopic stars, but from his memory of their configuration about the particular spot occupied by the planet. It was observed on November 8 by Rumker at Hamburg, but the length of observation was not sufficient to determine the mean motion with any degree of accuracy; hence although the elements had been several times brought up to more recent dates by Watson, the planet had not been recovered up to last month.

By the last Berlin circular it would seem that *Irmene* will fall little short of *Hilda* in the length of its revolution, and these two minors will thus stand out as exceptional members of the group. By the latest elements the period of *Hilda* is 2860 days or 7·832 years, and that of *Irmene* 2854 days or 7·814 years.

Calculation has assigned the shortest period to No. 149 *Medusa*, but this awaits confirmation, perhaps in the next summer, when the planet should again come into opposition according to the imperfect elements at present available.

PHYSICAL NOTES

M. PLANTAMOUR continues to study with his sensitive levels the phenomena of periodic rise and fall of the ground which he has observed in Switzerland. He believes he has established a connection between these periods and those of the changes of temperature of the earth's surface, there being an annual change of level in an east-west direction corresponding with the mean temperatures of the surface during the year.

M. ROSENSTIEHL concludes from his researches on the sensations of colour recently noticed that the three fundamental colour sensations of the Young-Helmholtz-Maxwell theory correspond to the following tints of the pure spectrum. *Orange-red*, three-fourths of the distance from C to D amongst the Fraunhofer lines, a *yellow-green* three-quarters of the distance from D to E, and a *blue* situated at one-third from F towards G. The principle upon which this selection is made is that the selected tint fulfils the following conditions: (*a*) it is equidistant between two tints which are complementary to one another; (*b*) it produces with either of the other selected tints another colour having a minimum of white admixed with it. Thus the yellow-green chosen is midway between that yellow and that blue which produce the best white with one another, and it gives with the selected orange-red a yellow more intense than any known yellow pigment under equal illumination, and with the selected blue gives a green more intense than the richest green pigment.

M. HENRI BECQUEREL observes that the specific magnetism of ozone exceeds that of oxygen, and is much greater than could be accounted for by the difference in density of these two allotropic forms of the gas.

IN view of recent terrible colliery explosions in Belgium, M. Cornet has called attention (in the Belgian Academy) to a possible interference of winds, blowing in an inclined direction, with the proper ventilation of mines. Most of the "fiery" Belgian mines have two shafts, one for raising the coal and for descent of air, which, passing along the galleries, is drawn up the other shaft by a ventilating engine. The orifice of the latter shaft is generally (unlike that of the other) unsheltered by buildings; it debouches directly in the air a little above the ground. Obviously, then, a strong wind, blowing with downward inclination towards this orifice, might seriously affect the ventilating action. It is noted that one explosion in Hainaut on November 19, 1880, followed a night of very high wind, which M. Cornet shows to have been capable of depressing ventilation considerably. Mines with large sections are more dangerous than others to atmospheric perturbations. The true remedy, however (in the author's opinion), is not increasing the resistance to the air-currents, but sheltering the orifices of the ventilating shaft against descending winds.

IN a recent paper on the optical structure of ice (to the Freiburg Society of Naturalists) Prof. Klocke finds that while in the ice individuals the plane of the secondary axes is fixed by the position of the principal axis, they are subject to no law as to direction in that plane.

THE phenomenon of *vergiss* occurred at Urbino in Italy twice in January; and from his observations of it Prof. Serpieri con-

cludes (*Real. Ist. Lomb. Rend.*) that surfusion of the rain-drops is not indispensable to its production. Surfusion indeed accelerates it, as do also violence of wind and intense cold; but a rain with temperature not so low as zero falling into an air-current in rapid motion and below zero gives the phenomenon. It is pointed out, however, that the mist which usually accompanies verglas being driven against objects by the wind, and its particles being in a state of surfusion (the temperature being below zero), probably contributes to the general result, helping to make the ice-layer regular and uniform. If the verglas be such that the drop freezes wholly at once, the latter has probably contained many small crystals of ice.

M. MERCADIER sums up his researches on Radiophony by saying that he believes that the phenomena are due to a vibratory movement set up by the alternate heating and cooling, due to the intermittent beams of heat-rays, of the gaseous layer adjacent to the solid surface at which the radiations are absorbed; being an anterior layer in the case of solid bodies, a posterior layer in the case of transparent bodies.

M. JANSSEN has succeeded in photographing the *lumière cendrée*, or "earth-shine" on the moon when three days old: in the photograph the "continents" were to be distinguished clearly from the "seas." This disposes of the view sometimes advanced, and held, we believe, by some most eminent astronomers, that the "new moon in the arms of the old" was an optical illusion.

PROF. D. W. BEETZ, of the Technical High School of Munich, wishes us to say that in the note (vol. xxiii. p. 442) on the modulus of elasticity of rods of carbon, he, and not Herr Holtz, should have been mentioned as the author of the paper on the subject in *Wied. Ann.*

GEOGRAPHICAL NOTES

AT the meeting of the Geographical Society on Monday Mr. J. B. Minchin, who has spent some seven years in the country, read an excellent paper on Eastern Bolivia, which also included some observations on the Gran Chaco. After some preliminary remarks Mr. Minchin dwelt at length on the water-system of the country, and, speaking first of the lakes, he mentioned that between the Rivers Pilcomayo and Paraguay, in the unexplored Chaco, the Indians report the existence of a lake which no white man has ever yet seen, but which is perhaps near 22° S. lat. The rivers belong to Amazon and Plate systems, and with the exception of the Paraguay and the Itenez, they mostly have their sources among the highest summits of the Andes. The Parapite, Mr. Minchin added, is the most southerly affluent of the Amazons, which in some maps has been made to flow across the Chaco into the Paraguay. The Pilcomayo also does not, as has been thought, receive any tributaries on its course through the Chaco, so far as can be learned from the Indians. Mr. Minchin afterwards alluded to his expedition over the Matto Grossi Mountains, which he succeeded in crossing for the first time. The latter part of the paper was largely devoted to the animal and vegetable productions of Eastern Bolivia and to the commercial condition of the country. The discussion which followed turned chiefly on the route of the future into Bolivia, whether it would be most advantageous to follow the Paraguay route or develop a new one by the Madera.

MR. E. G. RAVENSTEIN has nearly completed for the Council of the Geographical Society the large map of Eastern Equatorial Africa, on which he has been engaged for nearly three years under the direction of their Scientific Purposes Committee. The original drawings will be reduced before they are engraved, and the map when published will be in twenty-four sheets, and on a scale of 1 : 1,000,000. It will take in the lake region, the Upper Congo, and the Upper Nile, and on the east coast will extend from Somali Land to a little south of the Zambesi, the precise limits of the map being from 10° N. to 20° S. lat., and from 25° to 52° E. long. A very complete bibliography of authorities, compiled *pari passu* with the map, will be published afterwards.

MR. BROUMTON, an agent of the China Inland Mission at Kweiyang-fu, in the province of Kweichow, has lately sent home an account of a visit which he had paid by invitation to the Miao-tsze tribes a short distance off. He had been told by one of them, from whom he had been learning something of the language, that in the third moon of the year his people had large gatherings in the hills, and was asked to be present at these festivities. He accordingly went and had an excellent opportunity for observing the manners and customs of this [illegible] this comparatively unknown people. He describes the character of the festivities witnessed, the singular instruments used, &c. The particular tribes visited by Broumton are known as the Black (from the colour of clothes) and the Ka-teo tribes, and live near Hwanging-[illegible]

MR. CARL BOCK is leaving for Siam next week, where he intends to make an excursion into the interior. His book "The Headhunters of Borneo," will be published shortly by Messrs. Sampson Low and Co.

WE hear that Mr. Edward Whymper, who has already given an account of some phases of his South American journey to the Alpine Club and the Society of Arts, will read a paper on the Andes of Ecuador before the Geographical Society on May 9.

PRIZES OF THE PARIS ACADEMY OF SCIENCES

AT the public *séance* of the Academy on March [illegible] annual distribution of prizes took place. While some of these prizes are offered for particular subjects, others are devoted to rewarding the most important advances made during the year in special departments of science.

The Grand Prize of the Mathematical Sciences was awarded to M. Halphen for work on the theory of linear differential equations.

In astronomy Mr. Stone receives the Lalande prize for his stellar researches, following those of Abbé de Lacaille at the Cape of Good Hope; and the Valz prize goes to M. [illegible] for his observations on comets. M. Vinot's labours in [illegible] and editing *Le Ciel* are recognised by the award of the Tremont prize.

The Montyon prize of the mechanical arts is given to M. Cornut for his study of the faults of iron plates; the Plumey prize to M. Leauté for various works; while a recompense of 1500 francs on the Bordin foundation is given to M. Le[illegible] improved modes of combustion, diminishing the trouble and harm from smoke, &c. (in steel heating). The economy prize of 6000 francs (for improving the efficacy of naval [illegible] and the Plumey prize, are not awarded.

In physics we find a recompense of 3000 francs given to M. Ader, on the Vaillant foundation, for improvements in [illegible] telegraphy. The grand prize for researches on elasticity of crystalline bodies is not awarded.

The Jecker prize goes to M. Demarçay for important work in organic chemistry; the Gegner prize to M. Jacquemin for skill in preparing a large number of substances in a pure state, &c.

Two prizes on the Bordin foundation are awarded in geology, one to M. Gosselet for a geological sketch of the North of France, the other to MM. Falsan and Chantre for their geological monography of ancient glaciers and erratic deposits in the middle of the Rhone Valley. Recompenses on the Gay foundation are awarded to MM. Delage and Chevremont for observations on movements of the coast-line in France.

In medicine and surgery three Montyon prizes are awarded, one to Dr. Charcot for his work on localisation of disorders in the brain; another to Dr. Sappery for researches on the [illegible] atic apparatus of fishes; the third to Dr. Jullien for important medical researches. On the Bréant foundation M. Colin receives 5000 francs for physiological researches. Dr. Segond receives the Godard prize for an important work in surgery; [illegible] Quinand the Barbier prize for researches on the quantity of oxygen in human blood in health and in disease. The Desportes prize (having regard to prevention of premature burial) is not given, but MM. Onimus, Peyrand, and Le Bon are recompensed for their researches. The Boudet prize is awarded to Dr. Lister.

In experimental physiology the Montyon prize is given to M. Bonnier for researches on the nectaries and colours of flowers.

The Fons-Melicocq prize for botanical research in the north of France is gained by M. de Vicq; and M. de la Chapelle receives 1000 francs on the Desmazières foundation for studies on [illegible] cryptogams.

In anatomy and zo[illegible] Prize with reference to distribution of marine [illegible] ach coast is withheld

e Savigny prize for researches on the Madagascar; while the Thorel prize is ss-ares and M. July, for observations otand in streams to be the larva of an phemeram.

r statistics goes to Dr. Rieoux for his f Algeria.

M. Birckel receives 1500 francs on the an improvement in the Davy lamp, gives the Delaland-Guerineau prize for in.

ubjects for prize competition in 1881, mprises the following subjects (briefly Motor for tramways; physiology of of environment on plant-organs; struc- ork; internal organisation of European ans; cure of Asiatic cholera; genito- of the theory of Jupiter's satellites; udies; origin of atmospheric electricity, nomena in thunderstorms; inoculation mestic animals; coloured parts of the animals, and fecundating matter of , lacustrine, and terrestrial deposits on e Roman epoch; botany of the North ns of death and prevention of premature

ON INDEX OF REFRACTION OF EBONITE[1]

at when an intermittent beam of light lenium cell the sound produced in a battery was attached to the selenium) d by interposing a thin sheet of ebonite ttent rays of light, or, in other words, y transparent for invisible rays that curred to us some months ago that if all of the nature of light, they probably assing through the ebonite, or that e if the sheet of ebonite were replaced ns, a result we have been able experi- at the same time to measure the index

ntrating a parallel beam coming from le it in a rapidly revolving brass disk constructed many times as thick as the



d, and have thus succeeded in eliminat- d by the syren action of the disk, so periments. c d is a stationary zinc maller than the holes in the rotating

as these intermittent rays on a selenium *ite* lens, and so determine the focal our lens was then not mounted on an e moved parallel to it-elf, or rotated d as the rays were invisible, so that our uide us as to the proper position in failed to succeed in this very delicate r our subsequent experiments, now to t ultimately succeed with the lens

the intermittent light which passed rotatory disk was allowed to fall on assing through a slit in a zinc screen e Royal Society by Professors Ayrton and o f, the slit being arranged parallel to the edge of the ebonite prism. The prism employed had an angle of 27°5. M N is another zinc screen with a slit in it also parallel to the edge of the prism, and placed in front of a sensitive selenium cell s (the cell described by us in the account of our experiments on "Seeing by Electricity"). This screen M N was moved parallel to itself, while an experimenter listened with a telephone to each ear, and who was placed in another room, so as not to be influenced by seeing what changes were being made in the position of the screen or in the position of the ebonite prism. The telephones had each a resistance of 74 ohms, and the battery an electromotive force of about 40 volts. No direct light falling on the selenium, the listener at the telephones heard nothing for the majority of positions of the screen M N, but in one position represented in the figure a faint distant sound was distinctly heard, which was entirely cut off by interposing the hand in front of the selenium, or by moving away the prism.

The invisible rays that affect selenium after passing through ebonite are consequently refracted, and some preliminary experiments, when the ebonite prism was arranged for minimum deviation, gave 1'7 as a first rough approximation for the index of refraction of these rays by ebonite. It is interesting to notice that the square, 2'89, of this index of refraction is between the highest and lowest limits obtained by different experimenters for the specific inductive capacity of ebonite, so far agreeing with Maxwell's electromagnetic theory of light.

We are now having prisms of ebonite and of other opaque substances of different angles mounted on a goniometer stand, to enable us to measure the indices of refraction accurately.

MOLECULAR ELECTROMAGNETIC INDUCTION[1]

THE induction currents balance which I had the honour of bringing before the notice of the Royal Society (*Proc. Roy. Soc.* vol. xxix. p. 56) showed how extremely sensitive it was to the slightest molecular change in the composition of any metal or alloy, and it gave strong evidence of a peculiarity in iron and steel which its magnetic properties alone failed to account for. We could with all non-magnetic metals easily obtain a perfect balance of force by an equivalent piece of the same metal, but in the case of iron, steel, and nickel it was with extreme difficulty that I could obtain a near approach to a perfect zero. Two pieces of iron cut off the same bar or wire, possessing the same magnetic moment, never gave identical results; the difficulty consisted, that notwithstanding each bar or wire could be easily made to produce the same inductive reaction, the time during which this reaction took place varied in each bar; and although I could easily change its balancing power as regards inductive force by a change in the mass of the metal, by heat or magnetism, the zero obtained was never equal to that obtained from copper or silver.

This led me to suppose the existence of a peculiarity in magnetic metals which could not be accounted for except upon the hypothesis that there was a cause, then unknown, to produce the invariable effect.

Finding that it would be impossible to arrive at the true cause without some new method of investigation, which should allow me to observe the effects from an electrical circuit, whose active portion should be the iron wire itself, I constructed an apparatus or electro-magnetic inducti n balance, consisting of a single coil reacting upon an iron wire in its axis, and perpendicular to the coil itself; by this means the iron or other wire itself became a primary or secondary, according as the current passed through the coil or wire. Now with this apparatus we could induce secondary currents upon the wire or coil, if the coil was at any angle, except when the wire was absolutely perpendicular; in this state we could only obtain a current from some disturbing cause, and the current so obtained was no longer secondary but tertiary.

The whole apparatus however is more complicated than the general idea given above, as it was requisite not only to produce effects, but to be able to appreciate the direction of the electrical current obtained, and have comparative measures of their value. In order to fully understand the mode of experiments, as well as the results obtained, I will first describe the apparatus employed.

The electro-magnetic induction balance consists—(1) of an

[1] Paper read at the Royal Society, March 17, by Prof. D. E. Hughes, F.R.S.

520 NATURE [March 31, 1

instrument for producing the new induction-current; (2) sonometer or balancing coils; (3) rheotome and battery; (4) telephone.

The essential portion of this new balance is that wherein a coil is so arranged that a wire of iron or copper can pass freely through and forming its axis, the iron or copper wire rests upon two supports 20 centims. apart; at one of these the wire is firmly clamped by two binding screws; the opposite end of the wire turns freely on its support, the wire being 22 centims. long, having 2 centims. projection beyond its support, in order to fasten upon it a key or arm which shall serve as a pointer upon a circle giving the degrees of torsion which the wire receives from turning this pointer. A binding screw allows us to fasten the pointer at any degree, and thus preserve the required stress the time required.

The exterior diameter of the coil is 5½ centims., having an interior vacant circular space of 3½ centims., its width is 2 centims.; upon this is wound 200 metres of No. 32 silk-covered copper wire. This coil is fastened to a small board so arranged that it can be turned through any desired angle in relation to the iron wire which passes through its centre, and it can also be moved to any portion of the 20 centims. of wire, in order that different portions of the same wire may be tested for a similar stress.

The whole of this instrument, as far as possible, should be constructed of wood, in order to avoid all disturbing inductive influences of the coil.

The iron wire at its fixed end is joined or makes contact with a copper wire, which returns to the front part of the dial under its board and parallel to its coil, thus forming a loop, the free end of the iron wire is joined to one pole of the battery, the copper wire under the board is joined to the rheotome and thence to the battery.

The coil is joined to the telephone; but, as in every instance we can either pass the battery through the wire, listening to its inductive effects upon the wire, or the reverse of this, I prefer, generally, in order to have no voltaic current passing through the wire, to join the iron wire and its loop direct to the telephone, passing the voltaic current through the coil.

In order to balance, measure, and know the direction of the new induction currents by means of a switching key, the sonometer (*Proc.* Roy. Soc., vol. xxix. p. 65) I described to the Royal Society is brought into the circuit. The two exterior coils of the sonometer are then in the circuit of the battery, and of the coil upon the board containing the iron wire or stress bridge. The interior or movable coil of the sonometer is then in the circuit of the iron wire and telephone. Instead of the sonometer constructed as described in my paper to the Royal Society, I prefer to use one formed upon a principle I described in *Comptes rendus*, December 30, 1878. This consists of two coils only, one of which is smaller and turns freely in the centre of the outside coil. The exterior coil being stationary, the centre coil turns upon an axle by means of a long (20 centims.) arm or pointer, the point of which moves over a graduated arc or circle. Whenever the axis of the interior coil is perpendicular to the exterior coil no induction takes place, and we have a perfect zero; by turning the interior coil through any degree we have a current proportional to this angle, and in the direction in which it is turned. As this instrument obeys all the well-known laws for galvanometers, the readings and evaluations are easy and rapid.

If the coil upon the stress bridge is perpendicular to the iron wire, and if the sonometer coil is at zero, no currents or sounds in the telephone will be perceived, but the slightest current in the iron wire produced by torsion will at once be heard; and by moving the sonometer coil in a direction corresponding to the current, a new zero will be obtained, which will not only balance the force of the new current, but indicate its value. A perfect zero however will not be obtained with the powerful currents obtained by the torsion of 2 millims. diameter iron wire; we then require special arrangements of the sonometer, which are too complicated to describe here.

The rheotome is a clockwork having a rapid revolving wheel which gives interruptions of currents in fixed cadences in order to have equal intervals of sound and silence. I employ four bichromate cells or eight Daniell's elements, and they are joined through this rheotome to the coil on the stress bridge, as I have already described.

The magnetic properties of iron, steel, nickel, and cobalt have been so searchingly investigated by ancient as well as by modern scientific authors, that there seems little left to be as regards its molar magnetism. I use the word molar simply to distinguish or separate the idea of a magnetic iron or steel magnetised longitudinally or transversely by polarised molecules which are supposed to produce its magnetic effects.

Molar magnetism, whilst having the power of inducing electric current in an adjacent wire, provided that there motion or a change in its magnetic force, as shown by Fa in 1832, has no power of inducing an electric current itself or its own molar constituent, either by motion or of its magnetic moment. Molecular magnetism (the new which I believe I have been the first to obtain) has no, or feeble, power of inducing either magnetism or an electric in an adjacent wire, but it possesses the remarkable pow strongly reacting upon its own molar wire, inducing (rel tively with its length) powerful electric currents, in a circ which this forms a part.

We may have also both cases existing in the same wire occurs when the wire is under the influence of stress, external or internal; it would have been most difficult to se these two, as it was in my experiments with the inductive b without the aid of my new method.

Ampère's theory supposes a molecular magnetism or pol and that molar magnetism would be produced when the mo lar magnetism became symmetrical; and his theory I believ fully capable of explaining the effects I have obtained. admit that we can rotate the paths of the polarised molecu an elastic torsion.

Matteucci made use of an inducing and secondary coil year 1847 (*Compt. rend.* t. xxiv. p. 301, 1847), by mean which he observed that mechanical strains increased or dimi the magnetism of a bar inside this coil.

Wertheim published in the *Comptes rendus*, 1852 (*Comptes* t. xxv. p. 702, 1852), some results similar to Matteucci in the *Annales de Chimie et de Physique*, 1857 (*Ann. de Chim. et Phys.* (3) t. l. p. 385, 3857), he published a long series of remarkable experiments, in which he clearly proves the exi ence of torsion upon the increment or decrement of a magne wire.

Vilari showed (*Poggendorff's Annalen*, 1868) increase diminution of magnetism by longitudinal pull according the magnetising force is less or greater than a certain cri value.

Wiedermann (Wiedermann's "Galvanismus," p. 447; remarkable work, "Galvanismus," says that an iron through which an electric current is flowing becomes magnet by twisting the wire. This I have repeated, but found the re very weak, no doubt due to the weak battery I use, viz quart bichromate cells.

Sir W. Thomson shows clearly in his remarkable contri to the *Phil. Trans.* Roy. Soc., entitled "Effects of Str the Magnetisation of Iron, Nickel, and Cobalt" (*Phil. Tr* May 6, 1878), the critical value of the magnetisation of metals under varying stress, and also explains the longitu magnetism produced by Wiedermann as due to the combin twist of the wire, making the current pass as in a spiral fixed centre. Sir William Thomson also shows clearly the e of longitudinal as well as transversal strains, both as regar molar magnetism and its electric conductivity.

My own researches convince me that we have in mag magnetism a distinct and separate form of magnetism from when we develop, or render evident, longitudinal or tra magnetism, which I have before defined as molar.

Molecular magnetism is developed by any slight strain other than longitudinal, and it is only developed by an twist; for however much we may twist a wire, provided fibres are not separated, we shall only have the result of reaction of its remaining elasticity.

If we place an iron wire, say 20 centims. long, 1 millim meter, in the axis of the coil of the electro-magnetic s and if this wire is joined, as described, to the telephone, that on passing an electric current through the inducing current is perceptible upon the iron wire; but if we give slight twist to this wire at its free end—one-eighteenth of a or 20°—we at once hear, clear and comparatively loud, rents passing the coil; and although we only gave a slight twist of 20° of a whole turn, and this spread over 20 centi length, making an extremely slight molar spiral; yet the are more powerful than if, using a wire free from

ed the whole coil 40°. The current obtained when we turn coil, as just mentioned, is secondary, and with the coil at angle any current produced by its action, either on a copper, r, iron, or steel wire; in fact it is simply Faraday's discovery, the current from an elastic twist is no longer secondary under same conditions, but tertiary, as I shall demonstrate later on. current passing through the coil cannot induce a current n a wire perpendicular to itself, but the molecules of the ide of the wire, being under a greater elastic stress than the itself, they are no longer perpendicular to the centre of the , and consequently they react upon this wire as separate nets would upon an adjacent wire. It might here be readily posed that a wire having several twists, so a fixed molar twist i given amount would produce similar effects. It however s not, for in most cases the current obtained from the molar its are in a contrary direction to that of the elastic torsion. is, if I place an iron wire under a right-handed elastic twist 20° I find a positive current of 50° sonometer; but if I tinue this twist so that the index makes one or several entire olutions, thus giving a permanent molar twist of several is, I find upon leaving the index free from any elastic ion, that I have a permanent current of 10°, but it is no ger positive but negative, requiring that we should give an tic torsion in the previous direction, in order to produce a itive current. Here a permanent elastic torsion of the mole- s is set up in the contrary direction to its molar twist, and we e a negative current, overpowering any positive current which uld have been due to the twisted wire.

The following table shows the influence of a permanent twist, l that the current obtained when the wire was freed from its stic torsion was in opposition to that which should have been duced by the permanent twist. Thus a well-softened iron e 1 millim. in diameter, giving 60° positive current for a ıt-handed elastic torsion of 20°, gave after 1°·80 permanent sion a negative current of 10°.

complete permanent torsion (right-handed) negative	...		10
,,	,,	,,	... 15
,,	,,	,,	... 15
,,	,,	,,	... 16
,,	,,	,,	... 12
,,	,,	,,	... 10
,,	,,	,,	... 5
,,	,,	,,	... 4
,,	,,	,,	... 3
,,	,,	,,	... 3

At this point the fibres of a soft wire commence to separate, l we have no longer a complete single wire, but a helix of arate wires upon a central structure.

If now, instead of passing the current through the coil, I pass through the wire, and place the telephone upon the coil cuit, I find that I obtain equally as strong tertiary currents on the coil as in the previous case, although in the first case ere was produced longitudinal electro-magnetism in the per- ndicular wire by the action of the coil, but in the latter case ne or the most feeble electro-magnetism was produced, yet in ese two distinct cases we have a powerful current produced t only upon its own wire, but upon the coil, thus proving that e effects are equally produced both on the wire and coil.

If we desire, however, in these reversible effects to produce in th cases the same electromotive force, we must remember that e tertiary current when reacting upon its own short wire oduces a current of great quantity, the coil one of comparative gher intensity. We can, however, easily convert the great antity of the wire into one of higher tension by passing it rough the primary of a small induction coil whose resistance not greater than one ohm. We can join our telephone, nich may be then one of a high resistance, to the secondary of is induction coil, and by this means, and without changing the sistance of the telephone, receive the same amount of force, ther from the iron wire or the coil.

Finding that iron, steel, and all magnetic metals produce a rrent by a slight twist, if now we replace this wire by one of pper or non-magnetic metals we have no current whatever by elastic twist, and no effects, except when the wire itself is isted spirally in helix; and whatever current we may obtain om copper, &c., no matter if from its being in spiral or from t being perpendicular to the axis of the coils, the currents tained will be invariably secondary and not tertiary. If we place the copper by an iron wire, and give it a certain fixed rsion, not passing its limit of elasticity, we find that no in- crease or decrease takes place by long action or time of being under strain. Thus a wire which gave a sonometric force of 50° at the first observation remained perfectly constant for several days until it was again brought to zero by taking off the strain it had received. Thus we may consider that as long as the wire preserves its elasticity, exactly in the same ratio will it preserve the molecular character of its magnetism.

It is not necessary to use a wire to produce these effects; still more powerful currents are generated in bars, ribbons, or sheets of iron; thus no matter what external form it may possess, it still produces all the effects I have described.

It requires a great many permanent twists in a wire to be able to see any effect from these twists, but if we give to a wire, 1 millim. diameter, forty whole turns (or until its fibres become separated) we find some new effects; we find a small current of 10° in the same direction as its molar twist, and on giving a slight twist (20°) the sonometric value of the sound obtained is 80° instead of 50°, the real value of a similar untwisted wire; but its explanation will be found by twisting the wire in a contrary direction to its molar twist. We can now approach the zero but never produce a current in the contrary direction, owing to the fact that by the spiral direction, due to the fibrous molar turns, the neutral position of its molecule is no longer parallel with its wire, but parallel with its molar twist, consequently an elastic strain in the latter case can only bring the molecules parallel with its wire, producing no current, and in the first case the angle at which the reaction takes place is greater than before, consequently the increased value of its current.

The measurements of electric force mentioned in this paper are all sonometric on an arbitrary scale. Their absolute value has not yet been obtained, as we do not, at our present stage, require any except comparative measures.[1] Thus, if each wire is of 1 millim. diameter and 20 centims. long, all render the same stress in the axis of its coil. I find that the following are the sonometric degrees of value:—

	°	
Soft iron	60	Tertiary current.
Hard drawn iron...	50	,, ,,
Soft steel	45	,, ,,
Hard tempered steel	10	,, ,,
Copper, silver, &c.	−0	,, ,,
Copper helix, 1 centim. diameter, 20 turns in 20 centims.	45	Secondary currents.
Iron, spiral, ditto	45	,, ,,
Steel	45	,, ,,

The tertiary current increases with the diameter of the wire, the ratio of which has not yet been determined; thus an ordinary hard iron wire of 1 millim. diameter giving 50°, one of 2 millims. diameter gave 100°; and the maximum of force obtained by any degree of torsion is at or near its limit of elasticity, as if in the same time we also pass this point, producing a permanent twist, the current decreases, as I have already shown in the case of a permanent twist. Thus, the critical point of 1 millim. hard iron wire was 20° of torsion, but in hard steel it was 45°.

Longitudinal strains do not produce any current whatever, but a very slight twist to a wire, under a longitudinal strain, produces its maximum effects: thus, 20° of torsion being the critical point of iron wire, the same wire, under longitudinal strain, required but from 10° to 15°. It is very difficult however to produce a perfect longitudinal strain alone. I have therefore only been able to try the effect of longitudinal strain on fine wires, not larger than 1 millim in diameter, but as in all cases no effect whatever was produced by longitudinal strain alone, I believe none will be found if absolutely free from torsion. The molecules in a longitudinal strain are equally under an elastic strain as in torsion, but the path of their motion is now parallel with its wire, or the zero of electric inductive effect, but the compound strain composed of longitudinal and transverse, react upon each other, producing the increased effect due to the compound strain.

The sonometer is not only useful for showing the direction of the current and measuring it by the zero method, but it also shows at once if the current measured is secondary or tertiary. If the current is secondary its period of action coincides with that of the sonometer, and a perfect balance, or zero of sound, is at once obtained, and its value in sonometric degrees given, but if the current is tertiary, no zero is possible, and if the value of the tertiary is 60°, we find 60° the nearest approach to zero

[1] 50° sonometer has the same electromotive force as 0°·10 of a Daniell battery.

possible. But by the aid of separate induction coils to convert the secondary into a tertiary, a perfect zero can be obtained if the time of action and its force correspond to that which we wish to measure.

If I place a copper wire in the balance and turn the coils at an angle of 45°, I obtain a current which can be perfectly balanced by the sonometer at 50°, proving, as already said, that it is secondary. If I now replace the copper by an iron wire, the coil remaining at 45°, I have again exactly the same value for the iron as copper, viz., 50°, and in both cases secondary. Now, it is evident that in the case of the iron wire there was produced at each passage of the current a strong electro-magnet, but this longitudinal magnetism did not either change the character of the current or its value in force.

A most beautiful demonstration of the fact that longitudinal magnetism produces no current, but that molecular magnetism can act equally as well, no matter the direction of the longitudinal magnetism, consists in forming an iron wire in a loop, or taking two parallel but separate wires, joined electrically at their fixed ends, the free ends being each connected with the circuit, so that the current generated must pass up one wire and down the adjacent one. On testing this loop, and if there are no internal strains, complete silence or absence of current will be found. Now, giving a slight torsion to one of these wires in a given direction, we find, say 50° positive; twisting the parallel wire in a similar direction produces a perfect zero, thus, the current of the second must have balanced the positive of the first. If, instead of twisting it in similar directions, we twist it in the contrary direction, the sounds are increased in value from 50° positive to 100° positive, showing, in this latter case, not only a twofold increase of force, but that the currents in the iron wires travelled up one wire and down the other, notwithstanding that both were strongly magnetic by the influence of the coil in one direction, and this experiment also proves that its molar magnetism had no effect, as the currents are equally strong in both directions, and both wires can double or efface the currents produced in each. If instead of two wires we take four, we can produce a zero, or a current of 200°, and with twenty wires we have a force of 1000°, or an electromotive force of two volts. We have here a means of multiplying the effects by giving an elastic torsion to each separate wire, and joining them electrically in tension. If loops are formed of one iron and one copper wire, we can obtain both currents from the iron wire, positive and negative, but none from the copper, its *rôle* is simply that of a conductor upon which torsion has no effect.

I have already mentioned that internal strains will give out tertiary currents without any external elastic strain being put on. In the case of iron wire these disappear by a few twists in both directions, but in flat bars or forged iron they are more permanent; evidently portions of these bars have an elastic strain, whilst other portions are free, for I find a difference at every inch tested: the instrument however is so admirably sensitive and able to point out not only the strain but its direction, that I have no doubt its application to large forged pieces, such as shafts or cannon, would bring out most interesting results, besides its practical utility; great care is therefore necessary in these experiments that we have a wire free from internal strains, or that we know their value.

Magnetising the iron wire by a large steel permanent magnet has no effect whatever. A hard steel wire thus placed becomes strongly magnetic, but no current is generated, nor has it any influence upon the results obtained from molecular movement, as in elastic torsion. A flat wide iron or steel bar shows this better than iron wire, as we can here produce transversal instead of longitudinal, but neither shows any trace of the currents produced by molecular magnetism. I have made many experiments with wires and bars thus magnetised, but as the effect in every case was negative when freed from experimental errors, I will not mention them; but there is one very interesting proof which the instrument gives, that longitudinal magnetism first passes through its molecular condition before and during the discharge or recomposition of its magnetism. For this purpose, using no battery, I join the rheotome and telephone to the coil, the wire having no exterior circuit. If I strongly magnetise the two ends of the wire, I find by rapidly moving the coil that there is a Faradaic induction of 50° at both poles, but very little or none at the centre of the wire; now fixing the coil at the central or neutral point of the wire and listening intently, no sounds are heard, but the instant I give a slight elastic torsion to the free pole, a rush of electric tertiary induction is heard, whose value is 40°. Again, testing this wire by [illegible] coil, I find only a remaining magnetism of 10, and [illegible] ing the experiment of elastic torsion I find a tertiary [illegible] we can go on gradually discharging the wire, but in [illegible] will be found to be a recomposition, and that it has [illegible] through the stage I have mentioned.

Heat has a very great effect upon molecular magnets [illegible] On iron it increases the current, but in steel the current is [illegible] ished. For experimenting on iron wire, which gives a [illegible] rent of 50° positive (with a torsion of 20°), upon the [illegible] the flame of a spirit-lamp the force rapidly increases [illegible] taken not to approach red-heat) until the force is [illegible] 100 positive. The same effects were obtained in steel [illegible] tion, and were not due to a molar twist or thermo-[illegible] care had been taken to put on not more than 10° of [illegible] wire came back to zero at once on removal of the [illegible] tempered steel, whose value was 10° whilst cold, with [illegible] of 45°, become only 1° when heated, but returned [illegible] much heated) to 8° when cold. I very much doubled [illegible] periment at first, but on repeating the experiment [illegible] several times I found that on heating it I had softened [illegible] treme hard (yellow) temper to that of the well-known [illegible] temper. Now at blue temper, hot, the value of steel [illegible] to 2°, whilst soft iron of a similar size gave 50° of [illegible] and 100° at red heat. Now as I have already shown [illegible] effects I have described depend on molecular elasticity, [illegible] tively perfect elastic body, such as tempered steel, has [illegible] molecular elasticity, and that heat reduces it, but that [illegible] having but little molar elasticity, has a molecular elasticity [illegible] very high degree, which is increased by heat.

The objects of the present paper being to bring the [illegible] mental facts before the notice of the Royal Society, and [illegible] give a theoretical solution of the phenomena, I will [illegible] that if we assume with Poisson that the paths of the [illegible] of iron are circles, and that they become ellipses by [illegible] or strain, and also that they are capable of being [illegible] would sufficiently explain the new effects.

Joule has shown that an iron bar is longer and narrower [illegible] magnetisation than before, and in the case of the [illegible] strain the exterior portions of the wire are under a [illegible] strain than those near the centre, and as the polarised [illegible] at an angle with the molecules of the central portions [illegible] wire, its polarisation reacts upon them, producing the [illegible] tively strong electric currents I have described.

SCIENTIFIC SERIALS

Transactions and Proceedings of the Botanical Society of [illegible] *burgh*, vol. xiv., part 1, 1881, contains—Address by the [illegible] dent, Dr. T. A. G. Balfour (this address gave brief [illegible] of J. M'Nab, Sir W. C. Trevelyan, Dr. M. Bain, Fred. [illegible] bach, A. Forbes, A. J. Adie, Dr. J. Cumming, Karl Kuch [illegible] J. Murchison, Dr. D. Moore, P. S. Robertson, Wm. [illegible] Dr. J. F. Th. Inmisch, S. Hay, Dr. M. A. E. Wilkinson, [illegible] W. B. Cunningham, E. V. Sandilands, and A. Graham)—[illegible] W. Traill, on the growth of *Phormium tenax* in the Or[illegible] Islands.—Wm. Gorrie, on the hardiness of New Zealand [illegible] (1878-79).—Prof. G. Lawson, on British-American species [illegible] Viola.—S. Grieve, flora of Colonsay and Oransay.—Jas. Mac[illegible] botanical tour in Engadine.—Sir R. Christison, on the [illegible] ment of trees.—Prof. J. H. Balfour, on *Rheum nobile*.—T. [illegible] Thomson, the flowering plants of New Zealand, and their [illegible] tion to the insect fauna.—J. Sadler, on the flowering of [illegible] *gloriosa*.—Prof. Dickson, on the septa across the [illegible] *Bougainvillea glabra* and *Testudinaria elephantipes*.

Proceedings of the Linnean Society of New South Wales, [illegible] v., parts 1 and 2 (1880).—F. M. Bailey, medicinal plants [illegible] Queensland; on Queensland ferns, with descriptions of two [illegible] species; on a new species of Nepenthes.—M. A. Hasvell, [illegible] some Queensland Polyzoa, plates 1 to 3; on some new Am[illegible] pods, plates 5 to 7.—Wm. Macleay, on a new species [illegible] Galaxias, with remarks on the distribution of the species; [illegible] new species of Otolithus and of Synaptura.—Rev. E. T. Wo[illegible] and F. M. Bailey, on the fungi of New South Wales [illegible] Queensland.—Rev. E. T. Woods, on the littoral marine fau[illegible] of North-East Australia; on a fossiliferous bed at the mouth [illegible] the Endeavour River; on the habits of some Australian Echi[illegible] —E. P. Ramsay, on a new species of Oligorus; note on Gal[illegible]

alph Tate, rectification of the nomen-
ata, Angas.—E. Meyrick, descriptions
doptera: parts 3 and 4, Tineina.—J.
of *Bulimus Caledonicus*.

S AND ACADEMIES

LONDON

March 17.—Prof. Roscoe, president, in
ig papers were read:—On the volume
. Brown. The author has determined
alteration in volume which takes place
mixed. The liquids experimented with
ul benzene, carbon disulphide and car-
tetrachloride and benzene, dichlorethane
ane and benzene, and carbon tetra-
The experiments were made at 20° C.
t these changes of volume are depen-
aracter of the molecules, and not on
as vapour tension, molecular volume,
alcohol on mercuric nitrate, by R.
is dissolved in twelve times its weight
lution allowed to stand until all nitrous
twelve parts by weight of pure alcohol
pitate is formed, with or without heat-
investigated; it has the constitution
has also prepared the hydrate and
al ($C_2H_5Hg_2O_3$).—On boron hydride,
aylor. Magnesium boride is first pre-
ce of recently-ignited boric anhydride,
nagnesium dust, in a covered crucible.
n boride with hydrochloric acid, boron
ys however mixed with a large excess
olition is probably BH_3; it resembles
arsine (AsH_3) and silane (SiH_4).—
es on phenanthraquinone in presence
ep and E. Wilcock.—On the action of
quinone, by F. R. Japp and N. H. J.
pearance of nitrous acid during the
R. Warington. The author proves
ways derived from the atmosphere or
duction from the source of heat used
gave some account of the marvellously
Griess for nitrous acid. The solution
phanilic acid with some hydrochlorate
if nitrous acid be present, equal to one
millions of water; a rose-red tint is
t principle of *Smilax sysophylla*, by
nnie.—Note on uric acid and some
ition, by the late J. Stenhouse and C.
orption of solar rays by atmospheric
tint of the atmosphere, by W. N.
cludes that the higher regions of the
more ozone than the layers near the
the blue tint of the atmosphere is
the nature of certain volatile products
ar benzenes, by Watson Smith.—On
e, by E. H. Rennie. On distillation
boiling at 157°-158°.

March 9.—Robert Etheridge, F.R.S.,
Robert Thompson Burnett, William
James Fox, and the Rev. T. Granger
s of the Society.—The following com-
Description of parts of the skeleton
le (*Platypodosaurus robustus*, Ow.);
Prof. Owen, C.B., F.R.S. In this
l the remains of the pelvis of *Platypo-*
ve now been relieved from the matrix,
right "os innominatum," and a great
There are five sacral vertebræ, which
the total number in *Platypodosaurus*.
last lumbar vertebra is 8 lines in
sacral 9 lines, diminishing to 6 lines
an expansion of the neural in the
ccordance with the great development
acral vertebræ increase in width to the
widest centrum. This coalescence of
onsideration of the mass, as in Mam-
sacrum," which may be regarded as
at of the Megatherioid mammals,
although including fewer vertebræ. Its length is 7½ inches; its greatest breadth at the third vertebra, 5½ inches. The ilium forms the anterior and dorsal walls of the acetabulum, the posterior and postero-ventral walls of which are formed by the ischium and pubis. The diameter of its outlet is 3 inches, the depth of the cavity 1½ inch; at its bottom is a fossa 1¼ inch broad. The foramen is subcircular, 1 inch in diameter. The ventral wall of the pelvic outlet is chiefly formed by the pubis; it is a plate of bone 6 inches broad, concave externally, convex towards the pelvic cavity. The subacetabular border is 7-8 lines thick; it shows no indication of a pectineal process, or of a prominence for the support of a marsupial bone. The author remarks that of all examples of pelvic structure in extinct Reptilia this departs furthest from any modification known in existing types, and makes the nearest approach to the Mammalian pelvis. This is shown especially by the number of sacral vertebræ and their breadth, by the breadth of the iliac bones, and by the extent of confluence of the expanded ischia and pubes.—On the order Theriodontia, with a description of a new genus and species (*Elurosaurus felinus*, Ow.), by Prof. Owen, C.B., F.R.S. The new form of Theriodont reptile described by the author in this paper under the name of *Elurosaurus felinus* is represented by a skull with the lower jaw, obtained by Mr. Thomas Bain from the Trias of Gough, in the Karoo district of South Africa. The post-orbital part is broken away. The animal is monotrial; the alveolar border of the upper jaw is slightly sinuous, concave above the incisors, convex above the canines and molars, and then straight to beneath the orbits. The alveolar border of the mandible is concealed by the overlapping teeth of the upper jaw; its symphysis is deep, slanting backward, and destitute of any trace of suture; the length of the mandible is 3¼ inches, which was probably the length of the skull. The incisors are $\frac{5-5}{5-5}$, and the molars probably $\frac{5-5}{5-5}$ or $\frac{6-6}{6-6}$, all more or less laniariform. The length of the exserted crown of the upper canine is 12 millims.; the root of the left upper canine was found to be twice this length, extending upwards and backwards, slightly expanded, and then a little narrowed to the open end of the pulp-cavity. There is no trace of a successional canine; but the mandibular of the pulp-cavity and petrified pulp would seem to indicate renewal of the working part of the canine by continuous growth. The author infers that the animal was monophyodont. *Elurosaurus* was said to be most nearly allied to *Lycosaurus*, but its incisor formula is Dasyurine. With regard to the characters of the Theriodontia the author remarked that we may now add to those given in his "Catalogue of South African Fossil Reptiles" that the humerus is perforated by an entepicondylar foramen and the dentition monophyodont.—Additional observations on the superficial geology of British Columbia and its adjacent regions, by G. M. Dawson, D.Sc. This paper is in continuation of two already published in the Society's *Journal* (vol. xxxi. p. 603, and vol. xxxv. p. 89). In subsequent examinations of the southern part of the interior of British Columbia the author has been able to find traces of glaciation in a north to south direction as far as or even beyond the 49th parallel. Iron Mountain, for instance, 3500 feet above the neighbouring valleys, 5280 feet above the sea, has its summit strongly ice-worn in direction N. 29° W. to S. 29° E. Other remarkable instances are given which can hardly be explained by local glaciers; boulder-clay is spread over the entire district; terraces are cut in the rearranged material of this, bordering the river-valleys, and at greater elevations expanding over the higher parts of the plateau and mountains. At Mount Ita-cha-chay they are 5270 feet above the sea. The author considers that the higher terraces can only be explained by a general flooding of the district. Some of the wide trough-like valleys of the plateau contain a silty material which the author regards as a glacial mud. North of the 54th parallel and west of the Rocky Mountains similar evidence of glaciation is obtained; erratics are found in the Peace and Athabasca basins. The fiords of British Columbia are extremely glaciated, the marls being generally in conformity with the local features; terraces are scarce and at low levels. The Strait of Georgia was filled by a glacier which overrode the south-east part of Vancouver's Island; evidence is given to show that this ice came from the neighbouring mountainous country. Queen Charlotte's Island shows evidence of local glaciation. Boulder-clays and stratified drifts are found, with occasional Arctic shells. The author considers that the most

probable explanation of the phenomena of the whole region is to suppose the former existence of a great glacier mass resembling the inland ice of Greenland, and that the Glacial period was closed by a general submergence, during which the drifts were deposited and, at its close, the terraces cut.

Photographic Society, March 8.—J. Glaisher, F.R.S., president, in the chair.—Papers were read by Mr. Payne Jennings on art photography. It was asserted that unfavourable criticisms, both from artists and the press, had been the result from the exhibition of works which deserved such severity, and that to raise the status of art in photography more attention must be given to art-rules.—Also by Mr. Edwin Cocking, on notes on photography and art. An incisive comparison was drawn between the art of the painter and that of the photographer, showing the essential difference between the two in the production of a pictorial work, both in the *modus operandi* of production and the individuality capable of being infused into each result. Also that art in photography required a totally different training to that necessary for the painter, and that the time had arrived when special instruction by a thoroughly organised school for art photography had become absolutely necessary.

Institution of Civil Engineers, March 22.—Mr. Abernethy, F.R.S.E., president, in the chair.—The paper read was on the comparative endurance of iron and mild steel when exposed to corrosive influences, by Mr. D. Phillips, M. Inst. C.E.

PARIS

Academy of Sciences, March 21.—M. Wurtz in the chair.—The following papers were read:—On determination of the masses of mercury, Venus, the Earth, and of solar parallax, by M. Tisserand.—Observations of Faye's comet, at Paris Observatory, by MM. Tisserand and Bigourdan.—On the possibility of making sheep refractory to anthrax through preventive inoculations, by M. Pasteur, with MM. Chamberland and Roux. M. Pasteur controverts M. Toussaint's views on the subject, and says his method is very uncertain.—The vaccine matter of anthrax, by the same. A wholly harmless bacterium can be got from the most virulent by cultivation in animals different from those apt to take the disease. There are as many distinct germs as there are different kinds of virulence.—Researches on formic ethers, by MM. Berthelot and Ogier. They are formed with absorption of heat.—New navigation-maps, giving both the direction and force of the wind in the Indian Ocean, by M. Brault. Meteorologically the parts of that ocean above and below the equator are distinct (and the author indicates how).—On the operations of the Syndical Association of the Beziers Arrondissement to oppose phylloxera, by M. Jansan.—Report on the work of the Council of Public Hygiène and Salubrity, by M. Brezançon.—On the surface with sixteen singular points and Θ functions with two variables, by M. Darboux.—On the funcional determinant of any number of binary forms, by M. Le Paige.—On the decomposition into primary factors of uniform functions having a line of essential singular points, by M. Picard.—On certain simultaneous linear differential equations with partial derivatives, by MM. Picard and Appell.—On generator polygons of a relation between several imaginary variables, by M. Lecornu.—Solution of a general problem on series, by M. Andre.—On linear differential equations with algebraic integrals, by M. Poincare.—On the distribution of energy in the normal solar spectrum, by Prof. Langley. The total heat coming from the sun to the earth is much greater than has been believed (even in estimates accused of exaggeration). If the totality of the solar radiations reached us we should have a sensation of blue rather than white. (The author studied the absorption for each ray).—On a synthetic apparatus reproducing the phenomenon of circular double refraction, by M. Gouy. This consists of a number of thin and narrow rectangular lamelle of crystal placed side by side like floor-boards, and cemented between two glass plates. In a given direction the optic axis of each band forms a constant angle with the preceding one. A half-wave plate is placed above.—On radiophony with selenium, by M. Mercadier. The sounds here result chiefly from the luminous rays from the limit of blue to extreme red, and even a little in infra-red, the maximum being in the yellow.—Experiments at the Crenson works in optical measurement of high temperatures, by M. Crova. The spectropyrometer is proved practically useful.—On the electromotive force of the voltaic are, by M. Le Roux. With a galvanometer of great resistance and a single contact operated with the hand, one may prove the difference of potential of the carbons even $\frac{1}{75}$ of a second after cessation of the current. The phenomenon is probably thermo-elec... The hissing of the voltaic are, by M. Mandet. The ... of potential between the carbons is very great when the ... silent, very small when it hisses.—On magic mirrors of ... glass, by M. Laurent. The magic effect can be had through ... mode of mounting of the mirror.—On the flow of gases, ... Neyreneuf. The laws of this may be verified by a method ... that for determining electric resistances.—On new ... of hydrobromic and hydriodic acid with ammonia, by M. ... —Action of hydrochloric acid on chloride of lead, by M. ... —Action of sulphuric acid newly heated to 320°, and ... M. Maumené.—On a new means of analysis of oils, ... same. This consists in treating a measured quantity of ... one of a titrated aqueous solution of caustic alkali.—Separ... of oxide of nickel and oxide of cobalt, by M. Delvaux.—... process of industrial manufacture of carbonate of potash, ... M. Engel.—On some complex compounds of sulphur and ... gen, by M. Demarçay.—On tar from cork, by M. Bouis. ... contains more hydrocarbons than tar from coal, and less ... genated substances than tar from hard woods.—On the ... ation of urea, by M. Richet. The stomachal mucus of ... in general causes ammoniacal fermentation of pure ... Physiological and therapeutical properties of codeine and ... vine, by MM. Dujardin-Beaumetz and Restrepo.—Physio... action of *Erythrina corallodendron*, by MM. Bochefontaine ... Rey.—On lesions of the bones in locomotor ataxy, by ... Blanchard.—On the presence of trichina in adipose ... M. Chatin.—On the virulent state of the foetus in sheep that ... symptomatic anthrax, by MM. A. Arloing, Cornevin, and ... —Illusion relative to the size and distance of objects from ... one withdraws, by M. Charpentier. The objects seem to ... on approach.—On the organs of taste of osseous fishes, ... Jourdan.—Toxical power of pancreatic microzymas in ... venous injections, by MM. Béchamp and Balten.—Human ... found in the diluvium of Nice—the geological question, ... Desor. The deposit (at Carnbacel) belongs to the ... strata contemporary with the erosion of tertiary plateaux. ... scription of the bones, by M. Niepce.—Determination of the ... by M. de Quatrefages. It seem to be the same as that ... men of Cro-Magnon.—On a new genus of primary fish, ... Gaudry. MM. Riche found it in the Permian of Igornay. ... remarkable for the great size of its ribs, and is called *Megal... Rochei*. It had lozenge scales.—On the existence and ... of the Cambrian formation in the Puy-de-Dôme and Al... M. Jullien.—General law of formation of mineral ... application to Greoux (Basses-Alpes), by M. Héraud. ... the discovery at Noir-Montiers (Vendée) of the Eocene fos... *Sabalites Andegavensis*, Sch., by M. Crié.—Observations ... variations of temperature of the human body during ... by M. Villari. The results agree with M. Bonnal's.

CONTENTS

MIND IN ANIMALS. By GEORGE J. ROMANES, F.R.S. . . . .
AMERICAN INDIAN LANGUAGES. By A. H. KEANE . . . .
LETTERS TO THE EDITOR:—
Hot Ice.—Dr. OLIVER J. LODGE; J. B. HANNAY; Colonel ... RICHMOND (*With Diagrams*) . . . .
The Oldest Fossil Insects.—Rev. A. E. EATON . . . .
Oceanic Phenomenon.—Surgeon H. B. GUPPY . . . .
The Banks of the Yang-tse at Hankow.—Surgeon H. B. Guppy . . . .
An Experiment on Inherited Memory.—W. MATTIEU WILLIAMS . . . .
Meteors.—J. PARNELL . . . .
Classification of the Indo-Chinese and Oceanic Races.—R. MORTON . . . .
Fascination.—CARL OCHSENIUS . . . .
Flying-Fish.—Commander ALLAN D. BROWN . . . .
THE OXFORD COMMISSIONERS ON PROFESSORS . . . .
THE INTERNATIONAL GEOLOGICAL CONGRESS. By C. E. DE RANCE . . . .
THE FALLS OF NIAGARA IN WINTER. By WILLIAM LANT CARPENTER (*With Illustration*) . . . .
ZOOLOGICAL RESULTS OF THE VISIT OF PROF. K. MOEBIUS TO MAURITIUS. By H. N. MOSELEY, F.R.S. . . . .
NOTES . . . .
OUR ASTRONOMICAL COLUMN:—
A New Variable Star . . . .
Minima of Algol, &c., in 1880 . . . .
The Red Spot upon Jupiter's Disk . . . .
The Minor Planets . . . .
PHYSICAL NOTES . . . .
GEOGRAPHICAL NOTES . . . .
PRIZES OF THE PARIS ACADEMY OF SCIENCES . . . .
MEASURING THE INDEX OF REFRACTION OF EBONITE. By Professor AYRTON and PERRY (*With Diagram*) . . . .
MOLECULAR ELECTROMAGNETIC INDUCTION. By Prof. D. E. HUGHES, F.R.S. . . . .
SCIENTIFIC SERIALS . . . .
SOCIETIES AND ACADEMIES . . . .

ONS TO "NATURE."

	£	d.
. . . . .	28	0
. . . . .	14	6
. . . . .	7	6

nited States, the Continent, and Postal Union :—

	£	d.
. . . . .	30	6
. . . . .	15	6
. . . . .	8	0

ADVERTISEMENTS.

nin 2s. 6d. *or*, per Line after.

	£	s.	d.
quarter Column	0	18	6
Column	1	15	0
n	3	5	0
. . . . .	6	6	0

ayable to MACMILLAN & CO.

FORD STREET, STRAND, W.C.

OF SOCIETIES.

LONDON

STAY, March 31.

ne Co-efficients of Expansion of the Dioxide (Y) of Iodide of Lead with Inside of Silver Permanent Molecular Torsion of Conical Gauge (Carl Electric Current): Prof. Higgins. ntersection of the Digastric): G. E. Dobson, ons, F.R.S.

ssistant: H. H. Statham.

DAY, April 1.

e King in his relation to early Civil Institu

S.—Note on a Mandible of an *Indrodon* Dorchester, in the Portland Museum): J. J. logy of Colorado): S. R. Pattison, F.G.S.

RDAY, April 2.

ecision Humorists: Rev. H. R. Haweis.

DAY, April 3.

4.—Diseases: Edward Cheshl

DAY, April 4.

ne Visible Universe): Prof. Balfour Stewart. Lace-making: Allan S. Cole.

DAY, April 5.

—Note on the Habits of the Monster): Prof. ipture of the Amphisbænians and Ophidians on the Island of Socotra): W. A. Forbes). H. Gatty). Ancient and Modern Methods of the Coloration of Animals): A. Forbes, F.R.S.

e Blood): Prof. Schafer.

Jas. E. Hoppe Hall.

ESDAY, April 6.

ns in the Microscope, Structure of Decorated ownlow): Frank Bailey.—On Measuring ks of Shadow, F.R.S.—Frank Bailey.—The of to Lanchester, T. Mellard Reade, C.E.

ne Stones): Prof. A. H. Church.

RDAY, April 7.

ndensers of Electricity): Prof. T. E. Gilliard. ocarbs for Motors): on the Open Colouring ... Individual Variations in the ... W. A. Herdman.

ssion): H. H. Statham.

DAY, April 8.

xpansion of Iodizing Matter into Silver)

RDAY, April 9.

on Thermal Electrolysis): By J. H. Gladstone, F.R.S.

ecision Humorists: Rev. H. R. Haweis.

ion.—Visit to British Museum.

RONOMERS.

copes should send for "Hints on Silvered by G. SALVER (maker of the 37-inch scope)," containing important Testimonials. post free. Nine Stamps.

F.R.A.S.,
HILL HOUSE,
WILFORD,
HELMSFORD.

and Refractors frequently for Sale.

LIGHTNING CONDUCTORS.

Experience, accumulated since the time of Benjamin Franklin, proves conclusively that a Conductor made of Copper of adequate size is the best of all appliances for the protection of every description of building from the destructive effects of lightning.

NEWALL & CO.'S
PATENT COPPER LIGHTNING CONDUCTOR,

As applied to all kinds of Buildings and Shipping in all parts of the world with unvarying success; is the most Trustworthy, most Effective, and also the Cheapest Conductor ever offered to the public.

It is simple in its application, no insulators being required, and it costs only one shilling per foot for the standard size, which ensures safety in any form.

R. S. NEWALL & CO., 130, STRAND, W.C.
26, WATERLOO ROAD, LIVERPOOL.
65, ANDERSTON QUAY, GLASGOW.
MANUFACTORY—GATESHEAD-ON-TYNE.

SECOND EDITION,
GRIFFIN'S
CHEMICAL HANDICRAFT.

PRICE 4*s.* 7*d.* POST FREE.

A CATALOGUE OF CHEMICAL APPARATUS:

ILLUSTRATED, CLASSIFIED, DESCRIPTIVE.

Demy 8vo, 480 pp., Illustrated with 1,600 Woodcuts.

Most Complete and Cheapest List of Apparatus.

JOHN J. GRIFFIN AND SONS, 22, GARRICK STREET, LONDON, W.C.

ELECTRICAL AND SCIENTIFIC APPARATUS.

Wholesale Manufacturer of Metallic Base Electric Bell, Electric Reversing Indicators, and Constant Manganese Batteries, Telephone Switches and Transmitters, Induction Coils and Vacuum Tubes, Terrestrial Carbon Wire and all Materials. Instruments made, repaired, or altered on the premises.

Illustrated Bell List free. Complete Catalogue Two Stamps. Special Quotations to the Trade.

HENRY J. DALE, MANUFACTURING ELECTRICIAN AND OPTICIAN, 4, Little Britain, London, E.C.

Liberal Terms to Science Teachers and the Trade.

THOMAS CRAMPTON (formerly of 4,

Little Britain, London, E.C.), ELECTRICIANS, OPTICIANS, and PHILOSOPHICAL INSTRUMENT MAKERS. Electric Bells, New Metallic Base Pattern, Constant Batteries, Indicators, Dial and Fire Alarms, and Automatic Switches, Induction and Medical Coils, or Specialities. Insulated Wires of every description. Microscopic and Optical Materials. Telescopes, Opera Glasses, Microscopes, Aneroid Barometers, and Lime-light Apparatus. Illustrated Catalogue Three Stamps.

THOMAS CRAMPTON & CO., 231, HIGH HOLBORN, LONDON, W.C.
For Trade Terms send Card.

R. W. NEEVES,
PHILOSOPHICAL INSTRUMENT
AND
INTENSITY COIL MAKER.

PRICE LIST, FOUR STAMPS.

53, SIDMOUTH STREET, LONDON, W.C.

NOTICE OF REMOVAL.

JAMES HOW & CO.,
SCIENTIFIC INSTRUMENT MAKERS,
73, FARRINGDON ST., LONDON
(LATE OF 5, ST. BRIDE ST., AND 2, FOSTER LANE).

HOW'S STUDENT'S MICROSCOPE. HOW'S MICROSCOPE LAMP.

Rock Sections and other Objects for the Microscope.

EAGLE INSURANCE COMPANY.

79, PALL MALL.

FOR LIVES ONLY. ESTABLISHED 1807.

Accumulated Funds £3,043,540
Also a Subscribed Capital of more than £1,500,000

Reports, Prospectuses, and Forms may be had at the office, or from any of the Company's Agents, post free.

GEORGE HUMPHREYS, Actuary and Secretary.

W. LADD & CO.,

SCIENTIFIC INSTRUMENT MANUFACTURERS,

(By Appointment to the Royal Institution of Great Britain),

11 AND 12, BEAK STREET, REGENT STREET, W.

BIDWELL'S SELENIUM RHEOSTAT. AND OTHER APPARATUS FOR BELL'S PHOTOPHONE

PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3s. per oz.

Physical Apparatus of every Description.

ILLUSTRATED CATALOGUE, SIXPENCE.

PATERSON'S NEW CATALOGUE OF PHYSICAL APPARATUS

LANTERN SLIDES for SCIENTIFIC LECTURES. Season 1880-1. Post free 6 Stamps.
Complete Sets of Physical Apparatus for Science Primers and all the Physical Text-books in use in Schools and Colleges.
Siemens and Gramme Dynamo Machines and Lamps for hire.
Schools supplied with Apparatus as per Science and Art Departments' Requirements in the Sections of Light, Heat, Sound, and Electricity.
Electric Signals for Houses, Hotels, &c., Colliery Signals, Lightning Conductors. The Gower-Bell Loud-speaking Telephone.

EDWARD PATERSON, Electrical Engineer.

SHOW ROOMS AND STEAM WORKS:—76, LITTLE BRITAIN, E.C. (late 3, Bedford Court, W.C.)

MOLISON'S HARMONOGRAPH: executes the Harmonic Curves in the most perfect manner. 15s. and 20s.

Illustrated Catalogue of Electrical Apparatus, Part 1, post free, 6 Stamps. Ditto, Electric Signals, Part 2, 6

FLETCHER'S

PATENT VENTILATED

HOT-AIR OVEN.

At a cost of less than one halfpenny per hour for gas this oven will grill, roast, toast, bake, warm dishes and plates; and with the assistance of Fletcher's Patent Solid Flame Boiling Burners will do everything possible with a first-rate open fire (except drying clothes on washing days).

It is unapproached by any oven for pastry, and is fully hot in one minute after the gas is lighted.

Fish, joint, and pastry can be cooked all at once, in the most perfect manner, without the slightest taint from one to the other. The cooking is always good and always alike.

It will roast joint and fowls both at once, at least as well as an open fire.

Complete illustrated list of gas cooking and labour-saving appliances free by post. List of Gas and Petroleum Laboratory Furnaces and Apparatus, price 2d.

THOS. FLETCHER,

4 & 6, *MUSEUM STREET, WARRINGTON.*

HOLLOWAY'S PILLS

THIS MEDICINE

Is a Certain Cure for all Disorders of the LIVER, STOMACH AND BOWELS. A Great PURIFIER of the BLOOD; a Powerful Invigorator of the System, in cases of WEAKNESS AND DEBILITY, and is unequalled in Female Complaints.

"NATURE," Nov. 7, 1878.—One Shilling each will be paid for Copies of this number.—Address Publishers of NATURE, 29, Bedford Street, Strand, W.C.

S. C. TISLEY & (

OPTICIANS,

172, BROMPTON ROAD

(Close to South Kensington Museum.)

THE PHONEIDOSCOPE

An Instrument for Observing the Colour-Figures of Lycopodium, &c., by action of Sonorous Vibrations.

Being a visible demonstration of the Vibratory and Molecular Telephone Plate.

The PHONEIDOSCOPE, with 3 Discs, Bottle of Spores, Pamphlet, &c., in Cardboard Box, 10s. 6d.

MANUFACTURED AND SOLD WHOLESALE AND RETAIL BY

S. C. TISLEY & CO., 172, BROMPTON ROAD, LONDON.

TELEPHONIC ELECTRICITY. All Materials for Experimental Purposes.

Price Lists of Electrical and Acoustic Apparatus, post free. Description of the Harmonograph. Post Free.

BROKEN!!

DAVY'S DIAMOND CE

SECURELY AND NEATLY

CHINA, GL

CABINET WOR

AND

FANCY ARTIC

Of all Chemists in the Kingdom.

See the name "E. DAVY" on the Inventor, is on the Label.

BARCLAY & SONS, 95, Farringdon Street.

FRY'S COCOA

GOLD MEDAL, PARIS EXHIBITION

In Packets only.

"If properly prepared, there is no nicer or more wholesome preparation of cocoa."—*Food, Water, and Air, edited by Dr. Hassall.*

EXTRA

J. S. FRY & SONS, Bristol and London.

In unserem Verlage erscheint:

DER NATURFORSCHER

Wochenblatt zur Verbreitung der Fortschritte auf dem Gebiete der Naturwissenschaften.

Herausgegeben von Dr. WILHELM SKLLER.

Wochentlich 1—1½ Bgn. in 4°.

Preis vierteljährlich 4 Mk.

Die nunmehr ihren XIV. Jahrgang beginnende Zeitschrift, welche sich mit Naturwissenschaften beschäftigen, grosse Verbreitung. Probenummern sind durch jede Buchhandlung zu erhalten.

Berlin, S.-W., 77, Charlottenstr.

FERD. DÜMMLER'S VERLAGSBUCHHANDLUNG

(Harrwitz & Gossmann.)

In medium 8vo, price 18s., Vol. I.

A TEXT-BOOK OF THE

SIOLOGICAL CHEMISTRY OF THE ANIMAL BODY,

INCLUDING

N ACCOUNT OF THE CHEMICAL CHANGES OCCURRING IN DISEASE.

By ARTHUR GAMGEE, M.D., F.R.S.,

Professor of Physiology in the Victoria University, the Owens College, Manchester.

LONDON: MACMILLAN AND CO.

s work, of which the first volume is now published, and of which the second and concluding volume will be published in ns at giving a more complete account of the present state of physiological and pathological chemistry than is to be found f the existing text-books. The special features of the work are the following:—

st.—Physiological Chemistry is treated of from the points of view of the physiologist and physician rather than from that of : chemist, although no chemical fact and even no chemical speculation is omitted which appears to throw any light upon a al question. The classification adopted is, however, based upon physiological and pathological rather than chemical ations.

ondly.—It has been sought to combine a thoroughly systematic treatment of each subject with a full description of those methods rch which have in the past proved of the greatest value to the investigator. In the pursuit of this aim, detailed accounts are f methods which have, in many cases, hitherto been only incidentally referred to by the systematic writer. It seemed the portant to do this in a work intended for the scientific worker, anxious not merely to learn what had been already acquired ce, but wishful himself to extend her boundaries. Methods of analysis are described with great care, so as to render the work rorthy laboratory guide for the student of physiological chemistry and the practical physician.

irdly.—The history of each subject treated of is dwelt upon with great thoroughness, a detailed account of all epoch-making es being given, and the full titles of nearly all papers quoted being given.

urthly.—The work is copiously illustrated, the illustrations being in many cases original.

fthly.—Whereas in the first volume the chemical composition of and the chemical processes connected with the elementary of the organism are mainly dwelt upon, the second volume will deal with the chemical history of the complex animal es.

THE BREWERS' GUARDIAN:

tnightly Paper devoted to the Protection of Brewers' Interests, Licensing, Legal, and Parliamentary Matters.

OF THE MALT AND HOP TRADES; AND WINE AND SPIRIT TRADE RECORD.

The Organ of the Country Brewers.

Brewers' Guardian" is published on the evenings of every alternate , and is the only journal officially connected with brewing interests, ription, 16s. 6d. per annum, post free, dating from any quarter-day. opies 1s. each. Registered for transmission abroad.

Offices—5, Bond Court, Walbrook, London, E.C.

On the 1st of every Month.

MEN'S JOURNAL OF BOTANY,

BRITISH AND FOREIGN.

Series. Edited by JAMES BRITTEN, F.L.S., British Museum.

INTS.—Original Articles by leading Botanists.—Extracts, and of Books and Memoirs.—Articles in Journals.—Botanical News.— ngs of Societies.

:e 1s. 3d. Subscription for One Year, payable in advance, 12s.

don: WEST, NEWMAN, & CO., 54, Hatton Garden, E.C.

THE "HANSA"

ed since 1864 in Hamburg, is the only independent professional Germany, dedicated exclusively to Maritime Objects. Essays, s, Reviews, Reports, Advertisements. Strict eye kept upon the deve- of Maritime Affairs in every resp ct. Every second Sunday one in 4to at least; frequent supplements and drawings. Subscription ime; preceding numbers of the year furnished subsequently. Price twelve months. A vertisements 4d. a line, widely spread by this considerable abatement for 3, 6, 12 months' insertion. Business Aug. Meyer and Dieckmann, Hamburg, Alterwall. 28. Edited by REEDEN. M.R., Hamburg, Alexander Street, 8.

E ENTOMOLOGIST'S MONTHLY MAGAZINE.

e Sixpence, Monthly, 24 pages 8vo, with occasional Illustrations.

ted by C. G. BARRETT, J. W. DOUGLAS, R. MCLACHLAN, F.R.S., RYE, F.Z.S., E. SAUNDERS, F.L.S., and H. T. STAINTON, F.R.S.

Magazine, commenced in 1864, contains standard articles and notes bjects connected with Entomology, and especially on the Insects of ish Isles.

ription—Six Shillings per Volume, post free. The volumes com- with the June number in each year.

I. to VI. (strongly bound in cloth) may be obtained by purchasers of re set to date, at the increased price of 10s. each; the succeeding ay be had separately or together, at 7s. each.

London: JOHN VAN VOORST, 1, Paternoster Row.

—Communications, &c., should be sent to the Editors at the above

Chaque Samedi 16 pages grand in-8°, 2 colonnes

REVUE HEBDOMADAIRE

Scientifique, illustrée, spéciale, seul journal tenant les lecteurs au courant de tous les détails de l'Exposition universelle d'électricité, organe indépendant des exposants

RÉDACTEUR EN CHEF: **W. de FONVIELLE**

E. de CLISSON: DIRECTEUR

Un numéro, **40** *centimes.* — *L'année*, **48** *francs.*
Union postale **20** *francs.*

PARIS, 16, rue du Croissant, PARIS

Envoi de numéros spécimens gratis sur demande.

NORTH BRITISH AGRICULTURIST

is the only Agricultural Journal in Scotland, and circulates extensively amongst Landed Proprietors, Factors, Farmers, Farm-bailiffs, and others interested in the management of landed property throughout Scotland and the Northern Counties of England.

The AGRICULTURIST has also a very considerable circulation on the Continent of Europe, America, Australia, and the Colonies.

The AGRICULTURIST is published every Wednesday afternoon in time for the evening mails, and contains Reports of all the principal British and Irish Markets of the week, besides Telegraphic Reports of those held on the day of publication.

The Veterinary Department is edited by one of the leading Veterinarians in the country, and is invaluable to the breeder and feeder as a guide to the rearing of animals, and their treatment when labouring under disease.

Full Reports are given of the Meetings of the Royal Agricultural Society of England, the Royal Agricultural Society of Ireland, the Highland and Agricultural Society of Scotland, the Scottish Chamber of Agriculture, and all the principal Agricultural Associations throughout Great Britain and Ireland.

For Advertisers addressing themselves to Farmers a better medium does not exist

Price 3d. By post 3½d. Annual Subscription, payable in advance, 14s.

Office—377, High Street, Edinburgh.

Post-Office Orders payable to Charles Anderson, Jun., Edinburgh.

ESTABLISHED 1843.

Now publishing in Crown 8vo, price 2s. 6d. each.

ENGLISH MEN OF LETT

EDITED BY JOHN MORLEY.

JOHNSON. By Leslie Stephen.

"The new series opens well with Mr. Leslie Stephen's sketch of Dr. Johnson. It could hardly have been done better, and it will convey to the readers for whom it is intended a juster estimate of Johnson than either of the two essays of Lord Macaulay."—*Pall Mall Gazette.*

SCOTT. By R. H. Hutton.

"We could not wish for a more suggestive introduction to Scott and his poems and novels."—*Examiner.*

GIBBON. By J. C. Morison.

"As a clear, thoughtful, and attractive record of the life and works of the greatest among the world's historians, it deserves the highest praise."—*Examiner.*

SHELLEY. By J. A. Symonds.

"The lovers of this great poet are to be congratulated at having at their command so fresh, clear, and intelligent a presentment of the subject, written by a man of adequate and wide culture."—*Athenæum.*

HUME. By Prof. Huxley, F.R.S.

"It may fairly be said that no one now living could have expounded Hume with more sympathy or with equal perspicuity."—*Athenæum.*

GOLDSMITH. By William Black.

"Mr. Black brings a fine sympathy and taste to bear in his criticism of Goldsmith's writings, as well as his sketch of the incidents of his life."—*Athenæum.*

DEFOE. By W. Minto.

"Mr. Minto's book is careful and accurate in all that is stated, and faithful in all that it suggests. It will repay reading more than once."—*Athenæum.*

BURNS. By Principal Shairp.

"None of the series has given a truer estimate either of character or of genius than this volume."—*Spectator.*

SPENSER. By the Very Rev. the Dean of St. Paul's.

"Dr. Church is master of his subject, and writes always with good taste."—*Academy.*

THACKERAY. By Anthony Trollope.

"Mr. Trollope's sketch is excellently adapted to fulfil the purpose of the series in which it appears."—*Athenæum.*

BURKE. By John Morley.

"Perhaps the best criticism yet published on the life and character of Burke is contained in Mr. Morley's compendious biography. His style is vigorous and polished, and both his political and personal judgment, and his literary criticisms, are just, generous, subtle, and in a high degree interesting."—*Saturday Review.*

MILTON. By Mark Pattison

"Every page gives us something new to old put in such a way as to be almost equiv is new."—*Academy.*

HAWTHORNE. By Henry

"Probably no one living could have done Hawthorne as Mr. James has done."—*Satu*

SOUTHEY. By Prof. Dowd

"A truly scholarly and delightful ma writer, who has been of late years undeser *Examiner.*

CHAUCER. By A. W. War

"An enjoyable and excellent little bo Ward's. Far away the best connected acco his work to be found in English."—*Academ*

COWPER. By Goldwin Smi

"Mr. Goldwin Smith has sketched, touches, the genius of the poet and weak *Daily News.*

BUNYAN. By J. A. Froude.

"The life and character of Bunyan stand and for the first time the author of the 'P portrayed as he really existed."—*Westminst*

BYRON. By John Nichol.

"Decidedly one of the most careful whole series. When a book is so good as is little to be said about it, except to recom may be."—*Athenæum.*

LOCKE. By T. Fowler.

"In the case of Locke's biographer we Mr. Morley has been exceptionally fortu competent than Prof. Fowler's for this pa have been sought, and sought in vain."—*E*

POPE. By Leslie Stephen.

"The sketch of Pope's life which Mr. written is interesting throughout. . . . A only lay down with the wish to have a goo same subject by the same hand."—*Academy.*

WORDSWORTH. By F. W

"Mr. Myers gives us a picture of the m of his work which is certainly not inferior has preceded it. . . . Possibly the best cha every chapter of which is excellent—is that o —*Academy.*

DRYDEN. By George Saints

*** **Other Volumes to follow.**

MACMILLAN AND CO., BEDFORD STREET, COVENT GARDEN, W

With Illustrations and Maps, medium 8vo, 18*s*.

ISLAND LIFE:

THE PHENOMENA AND CAUSES OF INSULAR FAUNAS AND FLORAS, INCLUDING A REVISION ATTEMPTED SOLUTION OF THE PROBLEM OF GEOLOGICAL CLIMATES. By ALFRED RUSSEL WALLACE, Author of "The Malay Archipelago," "The Geographical Distribution of Animals," &c.

Mr. Wallace discusses in an admirably clear and able manner the questions of geological climate and time . . . such are few of the great problems discussed in this most instructive volume—a volume that ought to interest every thoughtful reader. its theories are likely to meet with keen criticism from Mr. Wallace's fellow-scientists, his volume ought more than any other ow of to spread among the intelligent reading public a knowledge of and interest in some of the most momentous scientific ms of our time."—*Times*.

His wonderful grasp of detail, depth of insight, and breadth of view remind one at every turn of Darwin, with whom he the honours of discovery in the theory of natural selection; but beyond this he has a lightness of touch, a beauty of style, ingenuity in unravelling intricate difficulties which are all his own. . . . 'Island Life' is a work to be accepted almost it reservation from beginning to end. . . . Whoever reads his book must be charmed with it."—*St. James's Gazette*.

The work throughout abounds with interest. . . . It may be read with equal pleasure by those who are already acquainted he general principles of distribution and by those who wish for the first time to learn something about modern biological phy."—*Athenæum*.

We have said enough to show that Mr. Wallace is led to discuss subjects of great interest to speculative minds. With its ous special maps 'Island Life' ought to prove as interesting as it is instructive."—*Pall Mall Gazette*.

MACMILLAN AND CO., LONDON.

A HANDBOOK OF DOUBLE STARS.

a Catalogue of Twelve Hundred Double Stars, and extensive Lists of Measures. With additional Notes bringing the ires up to 1879. For the use of Amateurs. By EDWARD CROSSLEY, F.R.A.S., JOSEPH GLEDHILL, F.R.A.S., AMES M. WILSON, M.A., F.R.A.S. With Illustrations. 8vo. 21*s*.

Just ready. 44 pages 8vo. 1*s*.

RRECTIONS, TOGETHER WITH NOTES, CRITICISMS, RECENT MEASURES AND DISCOVERIES, &c., &c., TO THE HANDBOOK OF DOUBLE STARS.

THE BIBLIOGRAPHY HAS ALSO BEEN BROUGHT UP TO DATE.

he volume is one which may be expected to find its way to the shelves of most amateurs and students of astronomy."—*Nature*.
his is a truly delightful work, and one which will admirably supply a want. Into the hands of abler, more impartial and aking observers and compilers than the authors' its preparation could not have fallen."—*The Astronomical Register*.
/ill be welcomed by all who take an interest in the subject of double stars."—*Acaaemy*.
he names of the authors, noted authorities on the subject treated of, will lead the reader to open this volume with the feeling i it he has a treasure of lore on the knowledge brought to light in the last hundred years respecting the relative motions of ally connected stars, nor will he be disappointed."—*Athenæum*.
ne of the most valuable additions to the library of the amateur astronomer that has been made for many years. It is full of iation of perennial interest to the student and the practical observer, and assuredly ought to be upon the table of every single atory in the United Kingdom, and of all those in other parts of the world where the language in which it is written is ible."—*The English Mechanic*.
he book is well and clearly printed, and we heartily recommend it to our readers as a most valuable contribution to the ire of double-star astronomy."—*The Observatory*.

MACMILLAN AND CO., LONDON.

SCIENTIFIC WORTHIES.

ENGRAVED BY THE LATE C. H. JEENS.

The following is a list of the Portraits that have appeared in the above Series.

MICHAEL FARADAY.
THOMAS HENRY HUXLEY.
CHARLES DARWIN.
JOHN TYNDALL.
GEORGE GABRIEL STOKES.
SIR CHARLES LYELL.
SIR CHARLES WHEATSTONE.
JEAN BAPTISTE ANDRÉ DUMAS.
SIR WYVILLE THOMSON.
SIR WILLIAM THOMSON.
HERMANN L. F. HELMHOLTZ.
SIR JOSEPH DALTON HOOKER.
WILLIAM HARVEY.
SIR GEORGE B. AIRY.
J. LOUIS R. AGASSIZ.
RICHARD OWEN.

f impressions of these, printed on India paper, may be had from the Publishers, price 5s. each, or the Set of 16 Portraits in a Handsome portfolio for £4 5s. carriage paid.

THE PORTFOLIO MAY BE HAD SEPARATELY, PRICE 6*s*.

NOTE.—ONLY A VERY FEW COMPLETE SETS CAN BE MADE UP.

Cheques and P.O.O.s payable to MACMILLAN & CO.,

ICE OF "NATURE," 29, BEDFORD STREET, STRAND.

Messrs. MACMILLAN & CO.'S PUBLICATIONS

BLACKS, BOERS, and BRITISH: a Three-Corne
PROBLEM. By F. R. STATHAM. Crown 8vo. 6s.

ANTHROPOLOGY: an Introduction to the Study
MAN AND CIVILISATION. By E. B. TYLOR, D.C.L., F.R.S. With numerous Illustra
Crown 8vo. 7s. 6d.

GRAPHICAL DETERMINATION OF FORCES IN ENGINEERI
STRUCTURES. By J. B. CHALMERS, C.E. With Illustrations. 8vo. 24s.

MANUAL OF ANCIENT GEOGRAPHY. From the German of Dr.
KIEPERT. Crown 8vo. 5s.

THE COLLECTED WORKS OF FRANCIS SIBSON, M.D. LOND
F.R.S., &c. Edited by WILLIAM ORD, M.D. With Illustrations. 4 vols., 8vo. £3 3s.

THROUGH THE RANKS TO A COMMISSION. Crown 8vo. 6s.
"This very interesting and indeed instructive narrative."—*Army and Navy Gazette.*
"The account of the daily routine and duties in camp are plainly written. . . . He has no stirring tales to tell; n
adventures to enlarge upon; no battles to fight again; no slain to slay; but his book seems to deserve attention . . .
fair and clear account of a career not common in England."—*St. James's Gazette.*

FO'C'S'LE YARNS. Including "Betsy Lee" and other Poems. Crown
7s. 6d.

NEW AND REVISED EDITION. VOL. I. OF
THE LIFE OF JOHN MILTON. Narrated in connection with the Po
Ecclesiastical, and Literary History of his Time. By DAVID MASSON, M.A., LL.D., Professor of Rhetoric and
Literature in the University of Edinburgh. Vol. I. New and Revised Edition. 8vo. 21s.
Vol. II. 8vo. 16s. Vol. III., 8vo. 18s. Vols. IV. and V., 8vo. 32s. Vol. VI., with Portrait, 8vo. 21s.

NOW READY, VOL II.
THE METAPHYSICS OF THE SCHOOL. By THOMAS HARPER
In Five Volumes. Vol. II., 8vo. 18s. (Vol. I., 8vo. 1
"We can only recommend professors, students, and cultured readers of all sorts to study it and to try to ma
Dublin Review.

"MACMILLAN'S BIOGRAPHICAL SERIES." NEW VOLUME.
CATHERINE AND CRAUFURD TAIT, WIFE AND SON OF AR
BALD CAMPBELL, ARCHBISHOP OF CANTERBURY: a Memoir. Edited, at the request of the Archbish
Rev. W. BENHAM, B.D., Vicar of Marden, and one of the Six Preachers of Canterbury Cathedral. With Two
engraved by JENS. New and Cheaper Edition. Crown 8vo. 6s.

GUIDE TO THE UNPROTECTED. In Every-day Matters relating to Pr
and Income. By a BANKER'S DAUGHTER. Fifth Edition revised. Extra fcp. 8vo. 3s. 6d.

ENGLISH MEN OF LETTERS. Edited by JOHN MORLEY. New V
Crown 8vo. 2s. 6d.
DRYDEN. By GEORGE SAINTSBURY.

NEW NOVEL BY HENRY JAMES, Jun.
WASHINGTON SQUARE: THE PENSION BEAUREPAS: A BU
OF LETTERS. 2 vols. Crown 8vo. 21s.
"In 'Washington Square' Mr. James has struck a new chord and achieved a new success . . . contriving to the v
keep us in suspense as to the result . . . make up some of the most amusing pages Mr. James has ever written."—*Athen*

NEW NOVEL, A STORY OF THE GREEK WAR.
LOUKIS LARAS; or, the Reminiscences of a Chiote Merchant during the
War of Independence. From the Greek of D. BIKÉLAS. Translated, with Introduction on the Rise and Deve
Modern Greek Literature, by J. GENNADIUS, late Chargé d'Affaires at the Greek Legation in London. Crown 8
"We have here an unmistakably genuine cast of the original, not a smug and inaccurate copy, in which the author is
translator. . . . The work also has the advantage of being very excellently printed, the glories of Elzevir type and p
been revived in Mr. Bikélas's favour."—*Observer.*

MACMILLAN AND CO., LONDON, W.C.

Printed by R. CLAY, SONS, AND TAYLOR, at 7 and 8, Bread Street Hill, Queen Victoria Street, in the City of London, and publish
MACMILLAN AND CO., at the Office, 29 and 30, Bedford Street, Covent Garden.—THURSDAY, March 31, 1881.

NATURE

WEEKLY ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
Of Nature trusts the mind which builds for aye."—WORDSWORTH

23] THURSDAY, APRIL 7, 1881 [PRICE SIXPENCE

[All Rights are Reserved.

ry at the General Post Office.)

OTICE.

TURE"

APRIL 28, 1881.

AIT, Engraved on Steel by the late H. JEENS,

OF

ILHELM BUNSEN.

s for this number should be sent to the

FORD STREET, STRAND.

I ASSOCIATION FOR THE ENT OF SCIENCE,

LE STREET, LONDON, W.

GENERAL MEETING will be held at ng on WEDNESDAY, August 31, ensington Place.

M.P., D.C.L., LL.D., F.R.S., F.L.S., F.G.S.

EPORTS OF MEMOIRS.—Authors are re- greement during from 1881, the acceptance of which they are to be read (or, more as far as ir arising Committees of the several Sections eeting. It has therefore become necessary, in the Committee of any Section to the several uthors should prepare beforehand an Abstract uitable for insertion in the published Transac- e Council request that he will send it, together Book-post, on or before August 1, addressed Bristol Association, 22, Albemarle Street.

Authors who comply with are accepted, will be forwarded before the their Reports or Abstracts. If it should be ast Paper should be read on any particular nformation thereof to the SECRETARIES in a

e Science, and of Researches instituted to must be forwarded to the GENERAL SECRE- e Organising Committees, accompanied by a will be present at the Annual Meeting. exact can be inserted in the Report of the before the conclusion of the Meeting.

G. GRIFFITH, Acting Secretary.

ROYAL INFIRMARY OF MEDICINE.

HIPS of £40, for two years, will be ch applicants as have taken the highest posi- either of the Matriculation Examinations of

Apply, etc., Abercrombie Square, Liverpool.

BROWNING'S BINOCULARS.

THE NEW THREE-POWER GLASS.
VERY POWERFUL.

By turning a stud, the eye-pieces are made changeable at pleasure, so that the object becomes instantly for either Marine, Field, or theatre purposes. The arrangement is so strong and simple that it cannot get out of order, nor can the eye-pieces be lost.

PRICE FROM £4 4s.

COMPLETE ILLUSTRATED LIST OF PRICES FREE.

JOHN BROWNING,

Optical and Physical Instrument Maker to H.M. Government,

63, STRAND, LONDON, W.C.

TRAVELLERS' SCIENTIFIC REQUISITES.

ANEROID BAROMETER with ALTITUDE SCALE, THERMOMETER and COMPASS in Flat Pocket Case, various Forms,

£7 7s. and £8 8s.

Price Lists of Instruments free by post.

NEGRETTI & ZAMBRA,

Opticians and Scientific Instrument Makers

TO HER MAJESTY THE QUEEN,

HOLBORN VIADUCT,

45, CORNHILL, & 122 REGENT STREET, LONDON.

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 48a, Tollington Road, Holloway, London, N.

ST. THOMAS'S HOSPITAL MEDICAL SCHOOL,

ALBERT EMBANKMENT, S.E.

The SUMMER SESSION will commence on May 2nd. Students entering in summer are eligible to compete for the Natural Science Scholarships of £100 and £60 awarded in the following October.

Special Classes are held for the Matriculation, Preliminary Scientific, and 1st M.B. of the University of London.

There are numerous Prizes and Scholarships, and all Appointments are open to Students without extra payment.

Several Medical Practitioners and Private Families in the neighbourhood receive Students for residence and supervision, and a register of inspected lodgings is kept in the Secretary's office.

Prospectuses and all particulars may be obtained from the Secretary, Dr. Gillespie.

W. M. ORD, M.D., Dean.

THE MIDDLESEX HOSPITAL MEDICAL SCHOOL.

SUMMER SESSION, 1881.

Lectures and Clinical Instruction in the Wards will commence on May 2nd. Gentlemen can enter to any one Course or to Hospital Practice only.

TWO ENTRANCE SCHOLARSHIPS, of the annual value of £35 and £20 respectively, tenable for two years, and a SCIENCE SCHOLARSHIP value £50, will be offered for competition at the beginning of the Winter Session.

For Prospectus, containing particulars as to other Scholarships, Resident Appointments, Fees, &c., apply to the Dean or the Resident Medical Officer, at the Hospital.

ANDREW CLARK, Dean.

UNIVERSITY COLLEGE, NOTTINGHAM.

The Town Council of Nottingham have resolved to APPOINT FOUR PROFESSORS as follows:—

ONE PROFESSOR who shall undertake one or more of the following Subjects:—Classics, Literature, History, Political Philosophy, Moral Science; and

THREE PROFESSORS who shall each undertake one or more of the following Subjects:—Mathematics (including Theoretical and Applied Mechanics), Physics, Chemistry, Physiology, Biology, Geology.

The work of the College will be divided into FOUR DEPARTMENTS, whose arrangement will depend to some extent on the subjects undertaken by the Professors elected, but it is intended that the three Scientific Departments shall severally comprehend—

1. Mathematics and Mechanics,
2. Chemistry,
3. Natural Science,

and that the subject of Physics shall be placed as a subject of principal importance in one or other of those Departments.

Applicants are invited to specify the Subjects which they would be prepared to undertake. Applications for the above Appointments to be addressed to the Town Clerk, Municipal Offices, Nottingham, endorsed "University College," on or before the 7th day of May next. Particulars of Salaries, Duties, and Conditions will be sent upon application to the Town Clerk.

Candidates are especially requested to abstain from canvassing.

SAM. GEO. JOHNSON, Town Clerk.

Municipal Offices, Nottingham, 22nd March, 1881.

THE COUNCIL OF FIRTH COLLEGE, SHEFFIELD,

intend to APPOINT a PRINCIPAL, who shall also be Professor either in the Literary or in the Mechanical Department of the College.

These Departments will comprehend respectively the following Subjects:—

1. Classes, History, Literature, Political Economy, Moral Science.
2. Mathematics, Mechanics, Engineering, Geology, Physics.

Applicants are requested to state in which of these Departments they would be prepared to act as Professor, and which of the Subjects in that Department they would be prepared to undertake.

The Salary of the said Principal will be £500 per annum, with Half the Fees of his own Classes.

The Council will only make the Appointment in event of suitable Candidates presenting themselves.

Candidates are requested to give full particulars concerning Age, Experience, and any Academical Distinctions they may have gained, together with any other information likely to affect the decision of the Council. The names of three gentlemen to whom references may be made should be given, but no testimonials need be sent unless they are asked for.

Applications to be sent on or before the 25th day of April next, to

ENSOR DRURY, Registrar.

Firth College, Sheffield, March 24, 1881.

INSTRUCTION IN MATHEMATICS.—

Youths or Adults attended at their Residence, on Reasonable Terms, by a M.A. of Cambridge. Unquestionable references if required.—Address, by letter, O. P., Post Office, Turnham Green.

LIVING SPECIMENS FOR THE MICROSCOPE

THOMAS BOLTON, NATURALISTS' and MICROSCOPICAL STUDIO, 57, NEWHALL STREET, BIRMINGHAM.

T. B. has last week sent to his subscribers a Collection of Freshwater Rotifers, including *Amœrura acuminata*, *Brachionus urceolaris*, and many others, with *Panderina morum* and Diatoms. He has also sent out *Floscularia charis* thickly encrusted with tube-dwelling Rotifers, including *Melicerta ringens*, *Limnias ceratophylli*, *Floscularia cornuta*, and *Cothurnia*, also commensal upon them.

Weekly announcements will be made in this place of organisms he is supplying.

Specimen Tube, One Shilling, post-free.

Twenty-six Tubes in course of Six Months for Subscription of £1.

Price List of Specimens on application, with stamped addressed envelope.

Portfolio of Drawings, No. 4, One Shilling.

"THE ENDOWMENT OF RESEARCH."

See Front Page of NATURE of March 24.

Letter from the Rev. THOMAS P. KIRKMAN, M.A., F.R.S.

"Croft, near Warrington, March 26, 1881.

"MY DEAR SIR,—Many thanks for your Fifth Report. I have read the inclosed papers with great pleasure.

"I wish you could get some Medical Man to look through the papers of the Vivisectors, and bring out the evidence that shows that they have *no clear question proposed* for solution. They are not for answers to scientific questions, but for hints how to frame questions. What a horrible thing it is that after three thousand years of as they dared), they have really nothing to show for a result, saving carving living men and animals (they Vivisected slaves innocently as B. has always found it easy and glorious to prove that Dr. A. was a blunderer; while neither B. nor A. ever yet had a sensible question of him which he could show likely to be solved by Vivisection. The Vivisectors have Benevolent and Scientific Aims. I don't believe it for all the as their Fathers ever were, under the false impression that these and Greek compounds. They carve away in the vain hope that the new will turn up for them to shine about, while hitherto they have done nothing which they could not find or infer from anatomy and physiology of health and disease. Any scientific thinker can satisfy himself of the of my remarks by a logical examination of their papers.

"Sincerely yours,

"THO. P. KIRKMAN.

"P.S.—You have given a capital account of all your antagonists.

"G. R. JESSE, Esq.,

"Henbury, near Macclesfield."

SOCIETY for the TOTAL ABOLITION and UTTER SUPPRESSION of VIVISECTION.

Honorary Secretary and Treasurer,

GEORGE R. JESSE, Esq.,

Henbury, near Macclesfield, Cheshire.

Bankers—Messrs. HERRIES, FARQUHAR, AND CO., 16, St. James's Square, London, S.W.

LONDON UNIVERSITY, ARMY, CIVIL SERVICE.

Dr. R. H. JUDE, D.Sc. (Lond.), M.A. (Cantab.), High Wrangler, 1st Class Natural Science Tripos, late Scholar of Christ's and assistant-demonstrator of Chemistry at Caius College, Cambridge, with qualified assistants, prepares Gentlemen in all the subjects for the above Exams.

Natural Science treated both experimentally and theoretically.

Highest Testimonials and References to present and former Pupils.

A few Pupils taught by Correspondence.

179, Cambridge Gardens, Notting Hill, W.

ROYAL POLYTECHNIC.—CLASSES

the Preparation of Students for University Examinations, under the direction of EDWARD B. AVELING, D.Sc., F.L.S. London University Matriculation, 1st and 2nd B.Sc., Preliminary Scientific, Botany, Physiology, Chemistry. All the work practical.

MINERALOGY AND GEOLOGY

VERY FINE SPECIMENS of CRYSTALS of BLACK TOURMALINE in ROCK CRYSTAL—MADAGASCAR.

SOME FINE EXAMPLES OF ITACOLUMITE OR FLEXIBLE SANDSTONE—INDIA—IN SLABS 1 FOOT TO 7 FEET 6 INCHES.

BLOWPIPE CASES AND APPARATUS.

COLLECTIONS FOR STUDENTS, from £2 2s. COLLECTIONS FOR BEGINNERS, from 42.

PRIVATE LESSONS AND EVENING CLASSES.

Catalogues free.

SAMUEL HENSON,

277 (*Late* 113*a*), STRAND, LONDON, W.C.

MUSEUMS AND COLLECTORS.

MR. DAMON, of WEYMOUTH, will forward his Abridged Catalogue of his Collections in Natural History Objects, including RECENT SHELLS (Foreign and British), FOSSIL REMAINS, MINERALS, ROCKS, MARINE ZOOLOGY, &c., &c., &c.

: COLLECTION OF ALS FOR SALE.

... now for Sale a very fine Old Collection, ... one of the best in Cornwall. The Collection ... y years ago, and contains most of the old ... of which now not to be found for many years; ... one, including a large number of Foreign Specimens, ... Cabinets of rosewood Mahogany Cabinets, ... two tiers of twenty-four Drawers each, with ... Keys, and to inspect the same, apply to—

SS A. GREGORY,
STREET, FITZROY SQUARE.

OY A GEOLOGIST.

... recommended, complete, price *31. 6d.*
... and most extraordinary Cabinet of wonderfully ... ens, together with other Geological Preparations ... the cabinet to start a boy thinking till he ... ordinary knowledge of the Formation of the ... THOWNING, GEOLOGIST, &c., 38, Whitcomb ... ches free.

IDS IN MATRIX.

... nd and Oriental Stone Cutter and Dealer, has ... ve; also Cut Precious Stones in all Colours. ... stones valued and bought.
... STREET, SOHO, W.

FRANÇAISE : a Weekly

... the French Language, Politics, Literature, ... ntes. Price 3*d.*, through booksellers, and at ... offices, 17, Southampton Street, Strand, W.C.

NÇAISE: Journal Français pour

... literature, Sciences, Arts, Variétés, Nouvelles, ... pour la poche, 32*d.*, en timbres poste. Abonne- ... an, 16*s.* 6*d.*; six mois, 7*s.* 7*d.* Prix 30*c.*, chez ... parek des chemins de fer. On s'abonne aux ... Street, Strand, Londres, W.C.

NÇAISE.—"La Semaine Fran-

... at in London for the benefit of those English ... study contemporary French from all points of ... their reading to one particular Gallic print. ... —*Graphic.*

NÇAISE.—"The numbers before

... It will be far better for most than any ... lished in Paris itself. We are much pleased ... nd believe it will be highly valued in all those ... French is cultivated." The printing is very well

... OF SUBSCRIPTION:—

				s.	*d.*
—	—	...	...	3	10
—	—	...	...	7	7
—	—	...	...	15	0

... ster, at King Street, Covent Garden, W.C.
... Southampton Street, Strand, W.C.

... ber.—CHARLES SEWELL READ, Esq., M.P.

CHAMBER OF TURE JOURNAL

MERS' CHRONICLE

... RICK nd WEEKLY).

... of the Central and Provincial Chambers of ... ety of the discussions and proceedings of ... on any other agricultural paper. It devotes ... *Journal of Agricultural Questions by Particu-* ... he Reports of the LATEST LONDON and ... E, HAY, PROVISION, and other Markets. ... ctical Farming, the Dairy, Herd and Flock. ... It is despatched every Monday evening in ...

... ble in advance, post free:—3 months, 3*s.* 3½*d.*; ... 13*s.* 7*d.*
... NG ST., Arundel Street, Strand, London, W.

OLOGIST'S MONTHLY AGAZINE.

... 24 pages 8vo, with occasional Illustrations.
... J. W. DOUGLAS, R. MCLACHLAN, F.R.S., ... CHER, F.L.S., and H. T. STAINTON, F.R.S.
... in 1864, contains standard articles and notes ... Entomology, and especially on the Insects of ...

... per Volume, post free. The volumes com- ... in each year.
... and in cloth may be obtained by purchasers of ... increased price of 10*s.* each; the succeeding ... together, at 7*s.* each.
... AN VOORST, 1, Paternoster Row.
... should be sent to the Editors at the above

Chaque Samedi 16 pages grand in-8°. 2 colonnes

REVUE HEBDOMADAIRE

Scientifique, illustrée, spéciale, seul journal tenant les lecteurs au courant de tous les détails de l'Exposition universelle d'Électricité organe indépendant des exposants

RÉDACTEUR EN CHEF : W. de FONVIELLE
E. de CLISSON ; DIRECTEUR

Un numéro, 40 *centimes*. — *L'année*, 18 *francs*. *Union postale* 20 *francs*.

PARIS, 16, rue du Croissant, PARIS

Envoi de nombreux spécimens gratis sur demande.

On the 1st of every Month, price Sixpence.

THE ENTOMOLOGIST:

AN ILLUSTRATED JOURNAL OF BRITISH ENTOMOLOGY,
Edited by JOHN T. CARRINGTON,
With the Assistance of
FREDERICK BOND, F.Z.S. | JOHN A. POWER, M.D.
EDWARD A. FITCH, F.L.S. | J. JENNER WEIR, F.L.S.
F. BUCHANAN WHITE, M.D.

Contains Articles by well-known Entomologists on all branches of the Science; on Insects injurious or beneficial to Farm or Garden; Notes on Habits, Life-Histories, occurrence of Varieties, &c.; there are monthly Lists of Duplicates and Desiderata.

Numerous WOODCUT ILLUSTRATIONS to the printing of which especial attention is given, and occasional LITHOGRAPHIC and CHROMO-LITHOGRAPHIC PLATES.

SIMPKIN, MARSHALL, & CO., Stationers' Hall Court.

THE ZOOLOGIST:

A MONTHLY MAGAZINE OF NATURAL HISTORY.
Third Series. Edited by J. E. HARTING, F.L.S., F.Z.S., Member of the British Ornithologists' Union; contains—

Original articles by well-known naturalists in every branch of zoology; habits of animals; arrival and departure of migratory birds; occurrence of rare birds; distribution and migration of British fresh-water fish; new or rare marine fish; local seasons; British reptiles; British land and fresh-water mollusca, with remarks on the haunts and habits of the species; and other matters of general interest to those who delight in natural history. Reports of the Linnean, Zoological, and Entomological Societies. Reviews of natural history books. Occasional translations from foreign zoological journals of important and interesting articles in various branches of zoology. There are occasional woodcuts.

JOHN VAN VOORST, 1, Paternoster Row.

In unserem Verlage erschien:

DER NATURFORSCHER.

Wochenblatt zur Verbreitung der Fortschritte in der Naturwissenschaften.
Herausgegeben von Dr. WILHELM SCHARFF.
Wöchentlich 1—1½ Bgn. in 4.
Preis vierteljährlich 4 Mk.

Die vorstehende ihres XIV. Jahrgang beginnende Zeitschrift hat bei Allen, welche sich mit Naturwissenschaften beschäftigen, grossen Beifall gefunden. Probenummern sind durch jede Buchhandlung zu erhalten.

Berlin, S.-W., 29, Charlottenstr.

FERD. DÜMMLER'S VERLAGSBUCHHANDLUNG.
(Harrwitz & Gossmann.)

NORTH BRITISH AGRICULTURIST

is the only Agricultural Journal in Scotland, and circulates extensively amongst Landed Proprietors, Factors, Farmers, Farm-bailiffs, and others interested in the management of landed property throughout Scotland and the Northern Counties of England.

The AGRICULTURIST has also a very considerable circulation on the Continents of Europe, America, Australia, and the Colonies.

The AGRICULTURIST is published every Wednesday afternoon in time for the evening mails, and contains Reports of all the principal British and Irish Markets of the week, besides Telegraphic Reports of those held on the day of publication.

The Veterinary Department is edited by one of the leading Veterinarians in the country, and is invaluable to the breeder and feeder as a guide to the rearing of animals, and their treatment when labouring under disease.

Full Reports are given of the Meetings of the Royal Agricultural Society of England, the Royal Agricultural Society of Ireland, the Highland and Agricultural Society of Scotland, the Scottish Chamber of Agriculture, and all the principal Agricultural Associations throughout Great Britain and Ireland.

For Advertisers addressing themselves to Farmers a better medium does not exist.

Price 3*d.* By post 3½*d.* Annual Subscription, payable in advance, 14*s.*

Office—377, High Street, Edinburgh.
Post-Office Orders payable to Charles Anderson, Jun., Edinburgh.
ESTABLISHED 1843.

Now publishing, in Crown 8vo. Price 2s. 6d. each,

ENGLISH MEN OF LETTERS.

Edited by JOHN MORLEY.

*** Upwards of 150,000 Vols. of this series have been sold.

WORDSWORTH. By F. W. H. MYERS.

"Mr. Myers gives us a picture of the man and an estimate of his work which is certainly not inferior to anything that has preceded it."—*Academy.*

LOCKE. By Prof. FOWLER.

"In the case of Locke's biographer we venture to say that Mr. Morley has been exceptionally fortunate. A pen more competent than Prof. Fowler's for this particular work might have been sought, and sought in vain."—*Examiner.*

BYRON. By Prof NICHOL.

"Decidedly one of the most careful and valuable of the whole series."—*Athenæum.*

POPE. By LESLIE STEPHEN.

"The writer's eminent qualities as a critic, his judgment, his wit, his abundant knowledge of eighteenth-century literature, and his keen enjoyment of literary form, have equipped him handsomely for the task he has undertaken."—*St. James's Gazette.*

COWPER. By GOLDWIN SMITH.

"Mr. Goldwin Smith has sketched, in a few decisive touches, the genius of the poet and weakness of the man."—*Daily News.*

CHAUCER. By Prof. A. W. WARD.

"Far away the best connected account of Chaucer and his works to be found in English."—*Academy.*

BUNYAN. By J. A. FROUDE.

"He has given us a real study of Bunyan's life and character, and at the same time a real study of his books."—*Athenæum.*

SOUTHEY. By Prof. DOWDEN.

"A truly scholarly and delightful monograph."—*Examiner.*

HAWTHORNE. By HENRY JAMES, JUN.

"He has made a careful, conscientious, and even vivid literary portrait, such as few of our own writers could have made."—*New York Nation.*

MILTON. By MARK PATTISON.

"Mr. Pattison's achievement is deserving of high praise. He has put life into old facts, he has taken an impartial estimate of a great man whose name is too often used for purposes of poetry."—*Spectator.*

JOHNSON. By LESLIE STEPHEN.

"The new series opens well with Mr. Leslie Stephen's sketch of Dr. Johnson. It could hardly have been done better, and it will convey to the readers for whom it is intended a juster estimate of Johnson than either of the two essays of Lord Macaulay."—*Pall Mall Gazette.*

SCOTT. By R. H. HUTTON.

"We could not wish for a more suggestive introduction to Scott and his poems and novels."—*Examiner.*

GIBBON. By J. C. MORISON.

"As a clear, thoughtful, and attractive record of the life and works of the greatest among the world's historians, it deserves the highest praise."—*Examiner.*

SHELLEY. By J. A. SYMONDS.

"The lovers of this great poet are to be congratulated at having at their command so fresh, clear, and intelligent a presentment of the subject, written by a man of adequate and wide culture."—*Athenæum.*

HUME. By Prof. HUXLEY, F.R.S.

"It may fairly be said that no one now living could have expounded Hume with more sympathy or with equal perspicuity."—*Athenæum.*

GOLDSMITH. By WILLIAM BLACK.

"Mr. Black brings a fine sympathy and taste to bear in his criticism of Goldsmith's writings."—*Athenæum.*

DEFOE. By W. MINTO.

"Mr. Minto's book is careful and accurate in all that is stated, and faithful in all that it suggests."—*Athenæum.*

BURNS. By Principal SHAIRP.

"... None of the series has given a truer estimate either of character or of genius than this volume."—*Spectator.*

SPENSER. By the Very Rev. the DEAN OF ST. PAUL'S.

"Dr. Church is master of his subject, and writes always with good taste."—*Academy.*

THACKERAY. By ANTHONY TROLLOPE.

"Mr. Trollope's sketch is excellently adapted to fulfil the purpose of the series in which it appears."—*Athenæum.*

BURKE. By JOHN MORLEY.

"It is no disparagement to the literary studies already published in this admirable series to say that none of them have surpassed, while few have equalled, this volume on Burke."—*British Quarterly Review.*

*** *Others in Preparation.*

MACMILLAN AND CO., LONDON.

Now Ready.

ZOOLOGICAL SOC PUBLICATIONS

PROCEEDINGS of the SCIENTIFIC MEETIN for 1880. Part IV., concluding the Volume, contain the Scientific Meetings in November and December, mostly coloured, 12s. ; with Plates uncoloured, 3s.

TRANSACTIONS OF THE SOC

Vol. XI., Part 3, price 10s., containing—

Mr. F. Moore. On the Genera and Species of th Family Orthoderinæ Inhabiting the Indian Region. W

Mr. W. K. Parker, F.R.S., On the Structure of th leons. With 5 Plates.

Vol. XI., Part 4, price 12s., containing—

Mr. W. A. Forbes. On the Male Generative O Rhinoceros (*Ceratorhinus sumatrensis*). With 1 Pl

Dr. M Watson. On the Anatomy of the Female cidea. With 2 Plates.

These Publications may be obtained at the Socie Square, W.): at Messrs. LONGMANS', the Society's Row, E.C.); or through any Bookseller.

New Edition, very much enlarged,

HOW TO WORK WI MICROSCOPE.

By LIONEL S. BEALE, F.R President of the Royal Microscopical

THE FIFTH EDITION,

Strongly bound and enlarged to 330 Pages, with so are Coloured, is now ready.

HARRISON & SONS, Pall M

NEW WORK BY LIONEL S. B

Now ready, pp. 230, demy 8vo

SLIGHT AILME

THEIR NATURE AND TREAT

By LIONEL S. BEALE, M.B., F. Professor of the Principles and Practice of Medic London.

J. & A. CHURCHILL, New Burling

THE CHEMICAL NEW JOURNAL OF PHYSICAL

EDITED BY W. CROOKES, F.R

Published every Friday. Price

No. 1175 (April 8th, 1881) contains—Estimation of Hamlet, F.C.S.—Estimation of Peroxide of Hydro F.C.S., &c.—Detection of Aniline Colours in Red Microspectroscope, by H. Macagno.—Chemistry of Bevan and C. F. Cross.—New Alkalimetric Indicato —Report on London Water Supply.—Proceedings o Books—Correspondence.—Chemical Notices from F and Queries, &c., &c.

London: Boy Court, Ludgate Hill,

THE "HANSA"

Published since 1864 in Hamburg, is the only in paper in Germany, dedicated exclusively to Mari Critiques, Reviews, Reports, Advertisements. Strict lopment of Maritime Affairs in every respect. Eve Number in 4to at least; frequent supplements and d at any time; preceding numbers of the year furnishe 12s. for twelve months. Advertisements 4d. a line, paper; considerable abatement for 3, 6, 12 month Office: Aug. Meyer and Dieckmann, Hamburg, Al W. C. FREDERK, M.M., Hamburg, Alexander Street,

THE BREWERS' GUA

A Fortnightly Paper devoted to the Protection o Licensing, Legal, and Parliamentary REVIEW OF THE MALT AND HOP TRADES; AND W RECORD.

The Organ of the Country Brewe "The Brewers' Guardian" is published on the eve Tuesday, and is the only Journal officially connected Subscription, 12s. 6d. per annum, post free, dating Single Copies 1d. each. Registered for transmission a Offices—5, Bond Court, Walbrook, Lon

GEOLOGY AND MINER

In the Preface to the "Student's Element Lyell he says, "As it is impossible to en recognise rocks and minerals at sight by aid tions or figures, he will do well to obtain a lection of specimens." These can be ha WRIGHT, MINERALOGIST, 90, Great Russe

50 Specimens in Cabinet ... ... 100 " " ... ... 200 " " ... ... &c., &c.

More extensive Collections from 50 to 200

Y, APRIL 7, 1881

'YAN VILLAGE

India and Ceylon. By Sir John Macmillan and Co., 1880.)

since a remarkable page in Sir ancient Law" drew attention to f the village-community, a system modern English mind. Before special students had little idea munism, under which the Aryan of Asia and Europe, was still to elic of ancient society, but as the ndern life among Hindus and portance of this early institution and our archæologists are alive village-communities in England. in the public commons, but here fields where, after harvest, the right of turning their cattle in le even a few of the great old once each family had its free to be discerned by the baulks ur hem into the three long strips, swise into the family lots. Thus argument on the development of the communism of ancient times.

The present volume is such a al ways new and important. Sir describes and carefully describes Ceylon, and one of his points is n of the agricultural village, as it two widely-separated districts. the development of the village. ywhere on much the same lines, ce. It springs naturally out of which, living together on its in common, and subsisting on a few generations a family- now to be seen in and about o 400 (including servants) living 100 is a usual number. The the *father*, who as usually the s, and what the members want ouside the common board and ave in small sums out of the l; then there is a great quarrel, ke up and the land is divided easily seen how such a joint- lies settling together in waste parcel into a village-community, hen crowded out of the family ared by, but all would work and still dwell under one roof. In of village settlement, according ng on at this day in Ceylon. In ent Europe, patches of forest are give a couple of years' crop of wlands rice-cultivation requires ul the whole settlement at work dly socialistic way. The some-

what different communistic system prevails more in India, where the land is still the common property of the village, and the cultivated plots are apportioned out from time to time among the families, but these families labour by and for themselves, pay the rent or tax, and live each on the crop of their own raising. In Bengal a step toward our notion of proprietorship is made, where custom more and more confirms each family in permanent ownership of the fields which their fathers have long tilled undisturbed. Tenant-right, so pertinaciously remembered by the Irish peasant, is older in history than the private ownership of land. Next, in the Hindu village as it now exists, a further stage of social growth appears. Families carrying on certain necessary professions have been set apart, or have settled in the village. The hereditary carpenters and blacksmiths and potters follow their trades, the hereditary washerman washes for his fellow-villagers, and the hereditary barber shaves them, paid partly for their services at fixed customary rates, and partly by having their plots of village-land rent free, or nearly so. All this is intelligible and practical enough, and indeed strongly reminds those of us who got our early politics out of "Evenings at Home," of the boy colonists providing for their future wants under the direction of discreet Mr. Barlow, by taking with them the carpenter and the blacksmith and the rest of the useful members of society. But the village-community as it actually exists in India, or Servia, or anywhere else, only forms the substratum of society, on the top of which appear other social elements whose development it is not so easy to trace with certainty. The "gentleman," with his claims to live in a better house than the others whose business is to drudge for him, seemed absurd to Dr. Aikin's political economy, yet he makes his appearance in the Hindu village-community as elsewhere. Sir John Phear seems disposed partly to account for what may be called the landholding class, as well as the endowed priesthood, as having held a privileged position from the first settlement of the villages, and it is in favour of this view that in such settlements the founder's kin naturally have superior rights over the land to new-comers. But he does not the less insist on another and yet stronger social process which has tended to give to individuals a landlord-right over fields they do not till. When quarrels between two villages end in actual war, the conquering warriors (whose claims however seem to be here somewhat confused with the rights of the chief's family) would be rewarded for their prowess by grants of land carved out of the common lands of the conquered village, and the new lords being absentees would naturally put in tenants who would pay in return a share of the crops. Such metayage, or farming "on shares," is as common in India as in the south of Europe, and is evidently the stage out of which arose our rent-system of landlord and tenant.

One great value of books like the present is in showing the analogies and differences of social institutions which have much of their history in common with our own, but have developed under other conditions. Feudal lordship and feudal sovereignty have in the East overridden the old village-system in ways curiously like those of the West. Thus, as Sir John Phear says, the English manor was the feudal form of the Oriental village; the Bengal

zamindar collects rents from his ryots and pays to the superior holder, or the Crown, living on the difference. Singhalese villagers may do suit and service either to a feudal chieftain or a Buddhist monastery, much as in England the fief might have been held either by a fighting baron or a praying abbot. It is interesting to find in Ceylon the notion that the existing tenure of land comes from the king having granted it subject to service, whereas its real history seems just the opposite, that the village-community came first, which the sovereign made himself paramount over and levied land-tax from. This reminds us of the theory of English law, that a cottager pastures his donkey on the common by sufferance of the lord of the manor, whose waste it is; the fact being that the peasant is exercising a relic of his old village-rights which has escaped the usurpation of the feudal system, and outlived it.

Though the village-community is much broken down in the districts so well described by Sir John Phear, it still shows the old framework in the division of the tilled land in allotments to each ryot, and the equitable settlement of rights and duties by the *mandal* or headman and his *panchayat* or village-council, which is one of the most admirable features of the ancient patriarchal system. But on the whole the village commune here shows practical results by no means admirable, and the husbandman's life on the roadless mud-flats of Bengal, minutely drawn by the author in all its details of dreary poverty and ignorance and hatred of improvement, is about as depressing a social picture as can be met with.

EDWARD B. TYLOR

NILE GLEANINGS

Nile Gleanings. By Villiers Stuart of Dromana, M.P. (London: John Murray, 1879.)

THE land of Egypt has of late caused the issue of a multitude of books, and that in consequence of the increased knowledge which half a century of Egyptian research has produced. Classical authorities no longer avail the traveller; he requires translations from the original hieroglyphic inscriptions, an insight into the discovery of a new world of antiquity and an acquaintance with the recent excavations which have revealed to the eye of the traveller an unveiled city of the dead. Scriptural texts alone garnished the older voyages. Above all the accomplished traveller should be acquainted with the various sciences which enable him to detect what is new or salient in the country that he visits, and its development, political institutions, progress, or decay should be seen at a glance even if it demands pages to describe them. The grand Egyptian tour is however a promenade of the land of monuments. Mr. Villiers Stuart's "Nile Gleanings" follow the usual track, and offer to the archæologist, besides the usual discussions on art, hieroglyphs, and language, and an occasional notice on the fauna and flora of Egypt, several new facts of archæological interest. At the description of Meidoum, the period of which is now known to be that of Senofrou, the tomb of Nofre Maat, with its strange figures inlaid with incrustations of red ochre, is new and interesting for its peculiar art and its remote age of the third dynasty; nor less important is the discovery of the flint flakes, the *débris* of the old chisels which sculptured it. Other tombs at the spo remarkable for their gigantic masonry. These r indeed to the more recent discoveries, but the a paid his respects to the dog mummy pits at Beb sites of Minieh and Dayr-el-Nakel. Considerable attaches to the heretical worshippers of the su who flourished about the close of the eighteenth dy and who endeavoured to remove the capital of Egy Thebes with "its hundred gates," to Tel-el-Am Psinaula. The idea fashionable amongst Egyp has been that Amenophis III. of that line, the b of whose statues is the celebrated vocal Mem menced an attempted religious reform and inst stitute the worship of the sun's disk or orb, the Ate is called, for that of the god Amen-Ra, or the hi To this it is supposed that he was invited by the influence of his wife, Tai or Taiti. After his dea conjectured that he was succeeded by his brother ophis IV., and that this Amenophis IV. was a co the most pronounced zeal for the worship of the s or pure Sabæanism. For this purpose, from the hept, or the Peaceful Amen, he changed his na Khuenaten, the Light or Spirit of the Sun. The de for this arrangement of the monarchs of the pen eighteenth dynasty were the stones used for the co tion of the Pylon or gateway of Haremheb a of the same dynasty, which were found to ha taken from an edifice of the so-called disk wor Thebes, and built with their faces inside the wall ing the erasure of the name of Amenophis IV substitution of Khuenaten in the cartouches for phis. Some objections indeed might have be from the fact that the features of Amenophis and aten were different, it being of course facile to new faith, impossible to secure fresh features, even enviable ones as those of Khuenaten. Mr. Villiers discovered a new tomb at Thebes, with Amenoph his queen on one side of the door and Khuenaten queen on the other, both dissimilar in features ment, and condition—one perfect, the other As both sovereigns could hardly have occupied the sepulchre, evidently one of the two appropriated by struction of his predecessor. The theory of Mr Stuart is that Khuenaten was a foreigner, which always asserted, although it is more difficult to de which of the races of mankind he belonged; the however some reasons to believe that after all h come from Nubia or the South. The discover tomb is in fact the principal new point of the work the one new and important contribution to the history of the heretical division which took place the thirteenth century B.C.

The various sites of Esneh, Dendera, Assouan and the Nubian temples are well known, but are des in a light and graceful way, and much old materia duced in a polished and not pedantic form. Necess a great deal is already well known to the student, a inconsiderable portion to the general public. A chronology the numerous systems and theories have been started, amounting in all to above one any choice which suits best the proclivities of the re The present work has a new date for Rameses I throws his reign back to B.C. 1567, but it is difficult

ble to reconcile a period so exalted with the ceiling
o-called Memnonium and the date of the heliacal
of the dog-star on the calendar of Thothmes III.
hantine. Every fact connected with the Exodus is
ct of continual dispute, dates, line of march, names
Pharaohs, place of the House of Bondage whence
ws swarmed out. The only safe view to take is
he problem is insoluble, and that its resolution
be tied up with the sheaf of paradoxes collected
Morgan. Mr. Villiers Stuart found the cultivation
ar prosperous, by means, though, of that apology for
y "forced labour," and he is indignant at the
ngs of the unhappy fellaheen, as also at the urgent
e of taxation and the system of baksheesh and
l bribery which pervades the modern as extensively
did the ancient land of bondage; but *corvées*, it
rs, are necessary for the payment of Daira bonds,
the drachm," as in the Roman times, must be wrung
the hard hands of peasants. While however glancing
modern state of Egypt the interest of the writer is
ntrated on the Egypt of the past, Pharaohs, their
s and their princesses, and a fair popular account is
of Thebes. His weakness is a love of dabbling in
ology, and venturing out of his depth on general ques-
of comparative philology. Although, for example, an
ional word may resemble its Greek or Latin equiva-
the construction of the hieroglyphic or old Egyptian
the Coptic is totally different from those two classical
ues, the Egyptian having a closer resemblance to the
itic than the Aryan or Indo-Germanic languages.
o the Etruscan, the few known facts about its con-
ction point to the Turanian or Tartaric family rather
the Egyptian. The origin of the Egyptians is still
lved in obscurity, and belongs to the province of
ectural ethnology. More Caucasian in the north
at the earliest period, more Nigritic on the south and
later epoch, the Egyptians seem historically a mixed
, a fusion of conterminous races of Northern Africa,
Eastern foreigners, and Nigritic blood. The oldest
bitants still remain a mystery. One theory is that the
ptian was the primitive man of a vast continent, the
representative being the aboriginal Australian.
ongst other interesting points are visits to the Der-
es, especially the fortune-tellers, and a description of
ride of the Sheikh of the Saidieh over the bodies of
ng men, who must have suggested to the apostle, had
seen him, the subject of Death on the Pale Horse.
e the car of Juggernaut, the Sheikh of the Saidieh is
d to have been abolished. The ceremony might have
n the relic of an old Egyptian one, and Pharaoh riding
r his prostrate enemies may have anticipated the
ik of the Saidieh. Altogether the work is entertaining
d amusing; it is not so dry as a guide or handbook,
r so learned as an Egyptological history such as that of
rugsch-Bey, nor so elaborate as Wilkinson's Manners
d Customs, and Topography, or other travels by pro-
ssed Egyptologists; but its style is light and sparkling,
d the principal details of history, mythology, and archæo-
gy have been fairly mastered. In the minute details of
ilology it is weak, but they do not affect the general
ader, and are easily set right *en passant* by the expert.
hey will do no harm to scientific research, and they will
ause and to some extent instruct the public. The plates
are also fairly done, and their colouring renders them more
than usually attractive. It is decidedly agreeable to while
away the monotony of a voyage down the river of the
desert, as the Nile may be justly styled, and to those
whose only travels are round their room, it will convey
some pleasing impressions of what a visit to Egypt might
show them.

LETTERS TO THE EDITOR

[*The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts. No notice is taken of anonymous communications.*

[*The Editor urgently requests correspondents to keep their letters as short as possible. The pressure on his space is so great that it is impossible otherwise to ensure the appearance even of communications containing interesting and novel facts.*]

Improved Arrangement of Scale for Reflecting Instruments

THE inconvenience resulting from the position of the scale in the ordinary well-known form of Thomson's reflecting galvanometer must have been experienced by all who have had occasion to use it much, and especially by myoptic individuals. This I have been able to eliminate very easily, as hereafter described, so that there is no further craning over to see "the spot," or getting in one's "light" in so doing.

The scale is mounted as shown in the sketch, which gives a front view of one end of the scale and a cross-section of the same.

B is a wooden scale-board with longitudinal slot, as shown at C; P is the paper scale, cut so that all the division lines reach the inferior edge; A is a slip of plane glass, finely ground as to its lower half on the side towards C, from one end of the slip to the other; the scale is so placed that the lower end of the division lines just touches the ground part of the glass slip. The image of the slit with a fine wire stretched across it is focussed in the ordinary manner on the ground part of the glass, and will of course be clearly seen by the observer on the opposite side of the scale; as the line and printed divisions are in the same plane, there is no parallax; and a great increase in accuracy of



reading the position of the hair line is obtained, owing to the greater ease of observing that two lines coincide when end on to one another than when superimposed; and further, from the circumstance that the room need not be darkened.

This arrangement has been introduced at the beginning of this year by me in the testing-room of Messrs. Siemens Brothers and Co. at Woolwich, and has been most readily accepted by all my assistants, and I venture to say that any who adopt this arrangement will never return to the previous form.

I may state that I place the lamp and its slit on one side and reflect the beam of light on to the galvanometer by a mirror or total reflection prism, and further by means of two long plane mirrors reduce the actual distance between the galvanometer and scale, so as to have everything close to the observer's hand. The scale I have adopted is divided into half millimetres, and it is perfectly easy to read to a quarter of a division, and with a hand magnifying-glass still further.

This method is of course applicable to any physical instruments which are read by a reflected spot, and as there are no "patent rights" it is placed at the disposal of all.

Charlton F. JACOB

A Note on Flame-Length

THREE years ago, whilst endeavouring to make use of flame-length as a means of testing the economic values of different qualities of coal-gas by the determination of their specific flame-

lengths, I was led to the discovery of some simple relations, the further study of which will perhaps one day help to simplify the theory of flames. By specific flame-length I mean the length of flame of a combustible gas burning in a normal atmosphere at a standard rate through a simple circular orifice under such conditions as to produce a symmetrical, vertical, steady flame capable of being measured. These conditions are not difficult to obtain in the case of coal gas. In fact for a very long time a flame-length test has been in use amongst gas-makers, but as the comparison has not always been made on the basis of volume the results have not always been satisfactory. The system I advocated was that of stating the flame-length for some standard rate. It occurred to me at that time that the flame-length should be proportional to the consumption or rate of issue of the gas. On submitting this theory to experiment I obtained satisfactory evidence that such was the case, as the following table taken at chance from a series of experiments will show:—

Flame-length. Inches.	Rate of consumption per hour. Cubic feet.	Calculated rate for 10″ flame. Cubic feet.
2	·75	3·75
3	1·13	3·77
4	1·5	3·75
5	1·85	3·70
6	2·25	3·75
7	2·6	3·71
8	2·98	3·72

I have therefore formulated the following laws:—

1. That the flame-length of a combustible gas is proportional to the consumption.

2. That the flame-length is the distance travelled by a gas in obtaining oxygen for its consumption.

3. That the flame-lengths of different gases are proportional to the relative amounts of oxygen required for their combustion.

The last remains to be proved, and I have been led to experiment upon simple gases such as hydrogen, carbonic oxide, and sulphuretted hydrogen, with the object of determining their specific flame-lengths; but these gases give flames offering great difficulties in measurement. The flames given by coal-gas under suitable and easily-obtained conditions offer no difficulty, but I have not been able at present (owing to the difficulty mentioned above) to obtain very satisfactory results with the above-mentioned three simple gases. Other simple gases have suggested themselves, but the cost of preparing them in a state of purity in sufficient quantity has at present prevented their use. However, with regard to sulphuretted hydrogen and carbonic oxide, I have found their flame-lengths stand in the relation of 3·2 to 1.

In view of the difficulty of measuring the flames of these simple gases I am about to effect the determination by indirect means. By preparing mixtures of known composition that will give easily-measurable flames, I hope to be able to throw some light upon this subject of flame-lengths.

March 22 LEWIS T. WRIGHT

Future Development of Electrical Appliances

As many of your readers have doubtless read Prof. Perry's interesting paper on the future development of electrical appliances, a remark on one or two points might not be out of place. In speaking of the application of electricity to railway travelling, Prof. Perry says that the weight of the train would be much reduced under the proposed conditions, and rail friction would be minimised. It strikes us that to have light trains would not be altogether an advantage, for several reasons. The lighter the train the less profitable would be the *vis viva* against a strong wind (and the latter is an important element in railway locomotion). Again, the stability of a heavy carriage is much greater than that of a light one, and a heavy engine in front of the train must steady the whole system. It would be interesting to ascertain from a practical engineer whether a train of six coaches with self-propelling powers could safely run at a speed of fifty-eight miles an hour. GEORGE RAYLEIGH VICARS

Woodville House, Rugby

Prehistoric Europe

I AM sorry to have to ask you again to allow me to correct some statements made by Prof. Dawkins in the matter of the Victoria Cave explorations (NATURE, vol. xxiii. p. 482).

1. He says that "the antiquity of man in the Vict... solely due to the *perfervidum ingenium* of Mr. Tiddi... was first based on a fragment of fibula which ultimat... out to belong to a bear. Then it was shifted to the ... small bones." It is not, I believe, usual in the ... over your own broken disabled weapon to your ... defend himself with when you take a new one. ... appears to be one of Prof. Dawkins's tactics. Wh... the above remark, would believe that Prof. Dawkins ... the following opinion? "Although the fragment [of ... is very small, its comparison with the abnormal ... Prof. Busk's possession removes all doubt from my ... its having belonged to a man who was contemporary ... cave-hyena and the other Pleistocene animals found in ... ("Cave-Hunting," p. 120.)

So far from the evidence having been "shifted" ... small bones, on the breaking down of the fibula ... latter event happened in 1878, whereas attention was ... the former in the Reports for 1875-6, the respective ... their discovery.

2. "The bones are recent," says Prof. Dawkins. ... evidently a very old bone," said Prof. Busk, after inspe... experimenting on one of them submitted to him; and ... of the circumstances of its discovery confirm that opinion.

3. "The cuts have been probably made by a me... That is a mere opinion, and to show what it is ... remark that at the discussion at the Anthropological In... 1877, when Prof. Dawkins stated that the marks ... they had been made with a Sheffield whittle, another ... at least equally distinguished, and apparently equall... to oppose the evidence, said that the marks seemed to ... made by a rock slipping across the bones.

4. Prof. Dawkins states that there were frequent ... materials after I took charge of the work. He has ... misinformed, for his own visits to the Cave during ... were not sufficiently frequent to warrant any such ... and our endeavour was to work the Cave in such a ... would entirely prevent the possibility of such accident ... mixture of the remains.

5. Prof. Dawkins goes on to show:—(1) Either ... Geikie and I believe that "there is evidence of inter... pre-glacial man, possessed of domestic animals, and ... using edged tools of metals" (which we certainly d... that (2) in his opinion goat has never existed anywhere ... a domesticated animal, for his remarks proceed upon ... other of these two assumptions.

6. Bones of goat were far from uncommon in the ... of the Cave, and found under such circumstances as ... render their slipping down from higher beds out ... possible. The same is the experience of that distin... explorer, M. E. Dupont, Director of the Geological Sur... Belgium, in the caves of that country:—"J'en maintiens ... ment la co-existence avec ces espèces perdues" (*Journ. Anth. Inst.*, vol. vii. No. 2, p. 168). Unfortunately the ... of goats in Pleistocene deposits in Great Britain has ... elevated to a dogma, and when the animals are found ... association it is immediately assumed that they have ... from above—a confession to a very slipshod method of ... —or, that the beds have previously been disturbed. All ... cases should be most carefully inquired into and observed ... time without prejudice.

7. Again, Prof. Dawkins says that I wrote that the fact ... finding of reindeer with the earlier Pleistocene animals ... "noteworthy," and that it is now too late to recall it. I ... recall my statement, but I should like it quoted ... "Your reporter had an impression that the reindeer ... occurred at some height above the hyena-bed.[1] Be ... may, Prof. Dawkins's opinion[2] is entitled to great weight ... is indeed the view generally held. At the same time, ... ing that hyena and reindeer are not uncommonly found ... in caves, when, as in this case, we see them mixed ... one or both ends of a section, but separated through ... of seventy feet in length by a thickness of deposits ... regard the fact as at least an interesting one, and, when ... noteworthy" (Brit. Assoc. Reports, 1876, p. 118). ... Dawkins shall have the whole of that. I will not ... the middle sentence. R. H. Tiddeman

Hastings, March 26

[1] This was also the opinion ... our palæontologist ... dept, who was daily at the ...

[2] ... of the co-existence ...

Induction Current from Leyden-jar Discharge

WAS led to try the following simple experiments with the ent induced from Leyden jar discharge, from the knowledge hat is the case in the Ruhmkorf's coil induced currents.

have since found the experiments have often been tried re; but all may not be aware how simply and easily the lts are shown.

fter trying flat coils I found it more convenient to coil stout lated wire round glass tubes. A few yards of stout wire id a tube A one foot long and 1¼ inches diameter gave me primary coil; a similar tube B of less diameter to put de A formed my secondary; and a third coil C enabled me to mine the current induced in B, with respect to its magnetising ver, at a distance, away from the influence of the primary A.

electrical machine, a Leyden jar or two, a number of un-gnetised knitting-needles marked with paper at one end, and ompass-needle to test polarity, are also required.

The experiments are as follows :—

(1) With coil A alone show that a needle is magnetised accord- to Ampère's law; if we regard the direction of current to from the + coat of the jar to the − coat.



(2) Now arrange the coils as shown, A as primary, B as condary, C in the circuit of B, and a needle in C. Let there be break in the circuit of B and C.

Then the magnetism induced in knitting-needle shows by (1) an tion as of a current *inverse* to that in A.

(3) Now interpose a break in circuit of B and C, so that induced rrent gives a spark. We now get the needle oppositely mag-etised, showing a direct induced current; and the magnetisation *far stronger* than in (2).

This points to the two opposite induced currents both passing hen there is no air-break; and the inverse having the strongest agnetising action; but the result weak. An air-break stops ie inverse current, and the far greater effect of the direct rrent un-neutralised by the inverse is very marked; it can asily be shown to a class, for example.

I may add that I have been unable to try what results one ets with galvanometers from lack of instruments.

Cheltenham W. LARDEN

Classification of the Indo-Chinese and Oceanic Races

IT is surprising that Mr. Murton should have had any difficulty bout the characters used by me to indicate the word *Paptwah*. he form in question is identical with his own, the apparent ifference being due to the two different characters respectively mployed by us to express the labial *p*. In the Arabic alphabet here is no sign for this letter, because the sound does not occur n the Arabic phonetic system. Hence other Muhammadan nations using the Arabic alphabet supply the missing letter in various ways, the Persians, Afghans, and Indians by the form ب, the Malays usually by ڤ. Hence the two apparently different but really identical forms پتوه and فتوه which have puzzled Mr. Murton and his Malays of Singapore.

A. H. KEANE.

Crabs and Actinia

THE account of the actinia on the claws of a crab in your last number (p. 515) is of interest as raising the point as to what benefit the crab derives from its friends. In the *Annals of Natural History*, many years ago, I wrote that, having for a long period kept *Adamsia palliata* with *P. Prideauxii* in confinement, I had no doubt but that the white tentacles of the anemone were a bait which attracted various small animals within reach of the crab's claws, though it did not, as Möbius seems to think, in any way aid the crab in capturing its prey.

In the South Sea Islands I saw a splendid specimen of a crab carrying a large actinia. The habit of the crab was to conceal itself entirely in the sand, leaving the actinia waving its tentacles on the surface. No sooner however did a small crab, annelid, or other creature come within reach than the crab, shooting its claw out of its concealment in the sand, struck out, and in most cases captured it. Here there was no doubt of the use of the actinia as a decoy.

H. STUART WORTLEY

Patent Office Museum, South Kensington, W, April 4

Migration of the Wagtail

WITH reference to the statement of Herr Adolf Ebeling (*apud* the correspondence from the New York *Evening Post*, quoted in your issue of February 24, vol. xxiii. p. 387), that the fact that wagtails in their wintering "came to Africa, and especially to Nubia and Abysssinia, was then unknown to us," permit the remark that as "*then*" must refer to a date not earlier than 1850 (when Heuglin went to Egypt), the appearance of wagtails on the west coast of Africa, as far south as Cape Verd, had been observed more than half a century before.

In the *Annales de Chimie* for July, 1793, M. Prélong, one of the lieutenants of Stanislas, Chevalier de Boufflers, and director of the hospital at Gorée, records the arrival on September 14, 1788, of a flight of *bergeronnettes* from the north. In connection with this M. Prélong remembered that Adanson had seen swallows at Senegal October 9, 1750 (?), while he himself could testify to their leaving his native *pays* (the Hantes-Alpes) towards the end of September. Prélong took ship for home in the middle of May, 1789, and was accompanied by his feathered friends the wagtails.

N. J.

New York, March 15

Sound of the Aurora

UPON this subject it may not be out of place to recall the fact that the passage of large meteors is not uncommonly described as accompanied by a hissing sound. I have met with statements of this kind in the case of meteors which were proved to have been twenty, thirty, or forty miles distant from the observer, and the sound of which, therefore, if it had reached him at all, must have reached him after such an interval of time that he would have been very unlikely to connect the two phenomena. Moreover the sound described in these cases is of a totally different character from the true sound of meteors, which is spoken of by those who have heard it as a heavy roaring or rumbling sound.

The explanation of the alleged "hissing" is not difficult when we remember that the untrained observer of a bright meteor (although it may be distant fifty or a hundred miles from him) invariably regards it as a near object, falling, it may be, into the next field, or behind a neighbouring hill. Regarding it in this light, he attributes to it, by a well-known mental process, a sound such as a firework at the same distance might be expected to produce.

May not the "rustling" of the aurora be equally a subjective phenomenon?

GEORGE F. BURDER

Earthquake Warnings

IN *Comptes rendus*, lxxxi. October, 1875, I find it stated, on the authority of M. Rivet, Telegraph Superintendent at Fort de France, Martinique, that when that island was visited by repeated earthquake shocks in September, 1875, each shock was preceded by a very marked disturbance of the electric telegraph needles. M. Rivet suggested that in this way warnings otherwise unattainable of impending shocks might be obtained.

It would be interesting to learn whether this observation has been confirmed by recent experience on the Continent.

Such warnings might often be the means of averting loss of life and property, and in cases like that at Ischia would, by their occurrence or non-occurrence, afford some additional clue to the real nature of the forces at work.

H. M. C.

Charlton, March 31

ON THE EARTHQUAKES AT AGRAM IN 1880-81

[At our request Prof. Szabo, Professor of Geology and Mineralogy in the University of Budapest, has prepared for the pages of NATURE the following account of the recent earthquakes at Agram. This account is a thoroughly reliable one, as it is drawn up from information obtained from Dr. von Hantken, the Director of the Hungarian Geological Survey, and Mr. Schafarrik (Prof. Szabo's assistant), both of whom were officially deputed to visit the district and inquire into the whole of the facts.]

On November 9, 1880, at 7h. 33m. 53s., a very violent earthquake passed over the south-western quarter of Hungary and also Bosnia and Herzegovina. The limits of this large territory are approximately as follows:—West, the peninsula of Istria and the town of Trieste; north, Vienna and Gödöllö (north-east from Budapest); east, the flat lands between the Danube and the Theiss; and south it reached far beyond Serajewo, because the earthquake was felt in this town also very strongly. It is said by some that the earthquake was even observed in Budweis (in Bohemia) and in Debreczen (east-north-east from Budapest). This territory is approximately equal to a circle, the radius of which is forty geographical miles long, and therefore its area is nearly 5000 square miles. From all information received up to the present time it may be asserted that the earthquake was not equally felt over the whole territory, but mostly in the centre of the circle—in the environs of Agram, where the damage occasioned was considerable.

According to the testimony of trusty witnesses the earthquake began on the day mentioned above with a strong shock in an upward direction, which was accompanied simultaneously with a perceptible and loud subterranean noise; this was followed by a subsidence; then came a perpendicular shock from below; and lastly came an oscillatory movement of the earth in an east-south-east to west-north-west-direction. This movement, which lasted nearly ten seconds, was so intense that in the town of Agram not only all the larger public buildings, but with few exceptions every dwelling-house, was damaged more or less.

One peculiarity of this first shock is that not only were objects of small weight removed out of their original positions, and this was especially the case with objects standing on a flat surface, but it also produced a certain rotatory motion upon them (contrary to the hand of a watch); even some trustworthy witnesses affirm that the first shock had a rotatory effect on them.

Chimneys are the objects which are the most easily damaged by earthquakes, and so in Agram there was scarcely a chimney to be seen after the earthquake which had not been either cracked or entirely ruined. The number of fallen chimneys amounts to nearly a thousand. An enormous amount of damage was also done to the roofs of houses; one could see from the roof-tiles placed on laths that they had been shaken by the oscillation, and were partially broken and fallen down, especially those which were situated towards the east or west. All this happened in the morning when the streets were mostly crowded with people, and one must be astonished indeed that the great quantity of falling masonry, parts of walls, stone cornices, huge beams of wood, and pieces of broken glasses, &c., did not hurt more people; altogether only twelve were severely wounded (broken arms, hands, feet, head wounds, &c.), but only in two cases did the injuries prove fatal; about twenty suffered slight contusions. In the surrounding country three men died, and some suffered from various injuries.

Among the public buildings and the larger dwelling-houses in Agram not one has actually fallen to ruin, but the number of those houses, whose outward walls were obliged to be supported by long beams on every side, is considerable; much more terrible, however, is the [illegible] of destruction inside the buildings; the mortar from the walls of the rooms is for the greatest part fallen down, and the thinner walls have been shaken so much that some of them are totally fallen to ruin. Almost [illegible] buildings were so ruined by the earthquake that it is necessary to forbid their reconstruction, and the Senate of the town found itself compelled to order their demolition. Here is the corner house belonging to [illegible] Priester, with two storeys facing the Marie-Valerie Street and Jellacsics Square, whose western frontal wall separated itself from the other parts of the house, and entirely bent towards the Marie-Valerie Street; the house of Mrs. Zorgách in the Petrijani Street is ruined, must be demolished; the building of the Military Academy in Ujlak has been a real and sad ruin. In the upper part of the town the following edifices are designated to be demolished:—Br. Orsegovich's house, Mednyanszka Barracks, a certain part of the military "General-Commando" building, &c. The majority of those buildings which have been rendered uninhabitable by the earthquake is great, but with great difficulty using iron braces—they can be renewed. To these buildings belong the cathedral, which is erected in the [illegible] square courtyard of the archbishop's palace. In the cathedral the vault of the sanctuary has fallen in and covered the high altar and the space before it with [illegible] ments of wall and rubbish; further, a part of the just before the organ and a little to the right of the entrance has fallen down in the centre nave; in the nave a very heavy horizontally-placed buttress fell down, and broke through the tombs where a coffin of a canon was; besides these more damages the main wall was split in several parts. The archbishop's palace itself has been damaged to such extent that the archbishop and the canons were obliged to leave their apartments for a long time. In the manner the Franciscan and St. Mark's Churches are also damaged. One can also add among the others St. Catharine's Church, which has been sadly damaged, also the edifices of the University and of the "Reischule," and many other private houses. The chimneys of the gas-factory and of Grator's brick-yard were only partially damaged at the upper part.

After these come those houses which, though they very greatly damaged, yet the people were not obliged to quit them; and lastly follows the great number of buildings which sustained only smaller damages. For instance, little rifts near the windows or along the corners of the walls, through mortar, &c., falling down). The proportion between the number of the edifices which became uninhabitable and had to be demolished, in comparison with those which were slightly damaged, in a [illegible] degree and those which were damaged in a greater degree and those which were damaged in a greater degree, is 1 : 1 : 4. This arithmetical proportion nevertheless does not at all express the damage that happened, because among the two first categories are the most valuable buildings, viz. the churches, barracks, the largest and newest houses, while the mass of the third category consists of small low buildings; one must attend to the above descriptions because it is impossible to set exact bounds between the single categories, for there are many houses whose ground-floors were totally [illegible] chinks, the first- and second-floors already showed [illegible] ally more chinks in the walls, while the third-floor presented a terrible picture of destruction. The damage edifices caused by earthquakes depends on their situation, on their height, and on their solidity, they found that the weaker the walls were, where iron braces were not applied, the more were buildings damaged; as regards the height, on the occasion of this earthquake it was observed that the second floor was more damaged than the first, and the third more than the second; and finally as to the situa

are some remarkable examples, houses forming east and north-west corners were exceedingly ed, viz. south-east was the direction where the ock came from.

he environs of Agram the earthquake appeared with strength than in the town itself, but the damage surrounding country is not so general, because here peasants' cottages all built of wood. Here therefore e churches, the parsons' houses, schools, castles, ntlemen's private houses were the objects on which thquake left visible marks.

he buildings of any strength in the villages which ated at the south-east slope of the mountain called north from Agram, were damaged in a more or in legree; there is for instance the well-known place grimages, Remete (5 km. north of Agram), where lls of the church, which is ornamented inwardly ry beautiful frescoes, and of the steeple are strongly in all directions, while the vaulted roof of the nave lly fallen down; so is also the residence of the ; the damage caused in these two edifices amounts, ing to an official valuation, to 38,000 florins. In ina (7 km. north-east from Agram) the steeple, down in an easterly direction, broke through the d the vault of the church, so that now one can see e four very ruptured walls. On the other side of untain Sleme, in a certain part of Croatia named a, many castles were ruined.

circle, where the earthquake caused the heaviest has approximately the following bounds:—South-Karlstadt; west, Landstrass, Gurkfeld; north-north Rohitsch; north, Warasdin, Csáktornya; north-aproncza (Kopreinitz); east, Belovár; south-east, which corresponds to a territory of about 120 square the centre of this circle was the place where the first manated from. The data kept in the surrounding lative to the direction and the greatest intensity hock indicate the territory which lies to south-east gram, and forms the alluvium of the River Save starting-point of the whole phenomenon. Here vice in the earth appeared also, caused by the -oscillated motion. A little to the east from the of Resnik (east-south-east from Agram) was the cre- the alluvium of the Save. It was 5 kilometres long, l several interruptions, and extended in a south- ection, from which here and there some smaller radiated. This chief crevice, which continued the Save as far as the village of Scitarjevo, showed places a few days after the earthquake openings wo feet broad, but for the most part the crevice d with bluish alluvial sand, which was forced out, vith water by the opening and closing of the being formed by the oscillation of the soil, the rcing its way through this dense pulp, produced upheaval those small flat craters which many re inclined to declare volcanoes of mud. The n of these small craters is very variable; their rs differ between 2 and 75 c.m., their height 1 to and, calculating from these numbers the cubic s of the largest flat cone, we receive nearly 0·5 netres; this little quantity of the out-pressed l is enough to exclude the hypothesis that these ere the result "of a slow action for some hours." o-sulphuric gas was present during this pheno- as some believe, it is not known, because we want and trusty evidence on this point. Moreover it npossible that there should be an appearance of uantities of hydrosulphuric gas dissolved in the an alluvial slimy soil, because such water gener- tains decaying substances and finely-dispersed s, but one can in no case suppose that a great f hydrosulphuric gas would have produced the d ejected the sand mixed with water.

[redacted] ritory of 120 square miles the earthquake was felt with a gradually diminishing strength, and in many places the motion was so weak that a great many of the inhabitants did not remark it. Among these can be mentioned Fiume, where they felt only a very slight shock; then Budapest and Vienna, where only one or two became attentive to this phenomenon.

Beyond the territory of 120 square miles, where they suffered the strongest shocks, there are yet some environs, though far enough from the centre, where destruction also happened, for instance in Styria, and in Hungary, in the neighbourhood of Pécs (Fünfkirchen). To explain the connection of these cases with the entire phenomenon deeper researches must be made.

It remains to communicate shortly the statics of the earthquake.

1. November 9, at 7h. 33m. 53s. in the morning, the first shock enduring 10 seconds with a subterranean noise. This one has caused all the damage.

2. November 9, at 7h. 37m. in the morning: an oscillatory motion without a noise.

3. November 9, at 8h. 27m. 55s. in the morning: slight motion.

4. November 9, at 10h. 50m. in the evening: very slight motion.

5. November 10, at 6h. in the morning: very slight motion.

6. November 11, at 11h. 26m. in the forenoon: a strong oscillation, which effected some damage.

7. November 16, at 12h. 4m. in the morning: a sufficiently strong shock accompanied with a dull noise.

8. November 16, at 12h. 44m.
9. " " 12h. 49m.
10. " " 1h. 9m.
11. " " 4h. 24m.

} in the morning:

weak oscillations, of which only the last had a little more strength than the others.

So it lasted continually during December. Even in this year (1881) in January and February feeble shocks recurred after longer interruptions; the last shock was recorded in the newspapers from March 4

Budapest, March 18

THE ST. PETERSBURG DYNAMITE MINE

THE following account of the mine recently discovered in St. Petersburg, extracted from Russian sources, gives a remarkable picture of the state of society in the empire, where able chemists and expert miners can be found to engage in such desperate undertakings.

It appears from a sketch-plan which accompanied the translation put into our hands, that the mine extended from one side of Malaya Sadobaya Street to the centre of the roadway; the total length of the mine gallery being fifteen paces, the street must be thirty paces, say seventy-five feet wide.

The gallery terminated in a chamber about double its diameter, and in this was found the charge contained in a case twenty-two inches long and eight inches diameter, weighing sixty-five pounds, and beside this a glass jar contained about thirty pounds more of the explosive substance, apparently an excess quantity over that required for the actual explosion. The explosive consisted of a species of dynamite made by mixing nitro-glycerine with powdered charcoal. This is more powerful in its effects than the ordinary substance, in which an inert body, generally a soft infusorial earth, takes the place of the charcoal. The description of the fuse, as contained in the Russian account, is very obscure, but so far as can be made out it would appear to have consisted of a wide heavy glass tube containing an explosive, described some time back in NATURE, and prepared by mixing nitro-glycerine with about 10 per cent. of gun-cotton, the result being a very explosive substance of a partially gelatinous character. In the midst of this, and

surrounded by a mixture of potassic chlorate and antimonious sulphide, was a sealed glass tube containing concentrated sulphuric acid and a leaden weight. The whole was then apparently connected with the dynamite in the case by means of an india-rubber tube also containing explosives. If this was the actual construction the *modus operandi* of the conspirators was very simple, for the heavy glass tube had only to be allowed to fall, when the lead would have broken the sulphuric acid tube, and the chlorate mixture would have at once inflamed, and the explosion of the jelly would have communicated by means of the rubber tube with the torpedo. At the same time it is very difficult to imagine the reasons which could have induced the conspirators to adopt so crude a method when, as it appears from the account, they had at their disposal in the room adjoining that from which the mine was driven no less than four galvanic batteries, with which the explosion could have easily been instantaneously effected by those on the watch for the passage of the intended victims, a method of operation much more consonant with the skilled character of the other parts of the work. It is however very difficult to understand a description such as this when derived from a non-scientific source, as may be imagined when one of our daily contemporaries stated that the fuse contained "*bartholley salts*," and another "chlorate of potash and *sulphide of ammonium*."

Whatever may have been the real mode intended to have been used by the conspirators, the results would have been sufficiently frightful, as it is probable that the charge found would have made a "crater" of about fifty feet in diameter.

The jelly contained in the glass tube was, when analysed, found to contain about 4 per cent. of camphor. This was added to render the mass less sensitive to any accidental shock which it might incur, and is an ingenious application of principles laid down by Abel (*Proc.* Roy. Soc. xxii. p. 163) in his well-known paper on "The History of Explosive Compounds," in which, though not actually mentioning the dilution of a liquid or semi-liquid explosive by the solution in it of another body, he clearly indicates the probable effects of such a treatment. That men of education and ability should so apply their undoubted powers must be a matter of regret to every student of science.

FISH-CULTURE IN THE UNITED STATES

IT is a common saying that everything in America is on a larger scale than in this country. The longest rivers, the largest lakes, the highest mountains, the broadest plains, the most stupendous waterfalls, and the biggest hotels, are all to be found in the New World. Fortunes are made with a rapidity which is unparalleled in Europe; and men who only lately were penniless adventurers are losing or winning millions in New York. The latest example of the scale on which everything in America is conducted may be found in a volume of more than 1000 pages, printed in the Government printing-office, bound in the Government "bindery" of the United States, and containing the Annual Report of the United States Commission on Fish and Fisheries. The volume, it may be added, has been preceded by five others of almost equal length; and gives a remarkable idea of the importance which the Americans attach to fish-culture.

It would obviously be impossible to attempt, within the compass of a newspaper article, any adequate review of a work of this character. But we may perhaps indicate its nature by rapidly describing its contents. The volume, then, is roughly divisible into two parts. The first 64 pages contain the Report of the Commission; the last 988 pages are occupied with appendices and an index. Forty-four appendices of unequal importance are thus published. The greater portion of them consists of translations or reproductions of papers published in other countries and having more or less reference to the work of the Commission. For instance, there is a report by Herr Wallem (the well-known Norwegian Inspector of Fisheries) on the American Fisheries; by Prof. G. O. Sars on the Norwegian Deep-sea Expedition of 1878; by Dr. Stirling of Edinburgh on the Recent Outbreak of Salmon Disease; and by other authorities on various subjects. In addition the appendices contain [illegible] papers by Messrs. Livingston Stone, C. G. Atkins, and other American fish-culturists on matters more or less connected with fish-culture in the United States. The volume undoubtedly contains a vast mass of information. Much of it indeed is written in a style which in this country would be considered more suitable to a private view than to an official report. But the American point of view of government is so different from our own that the Englishman cannot easily form an impartial opinion on this point.

Herr Wallem estimates the yearly profit, by which I think he means the gross yield, of the fisheries of the United States at 27,300,000 dollars. In this are "naturally not included what foreign nations capture on the banks of America, nor what the fisheries of Canada yield. If one should take both these factors into calculation the amount mentioned may perhaps be increased by one half, because the French fisheries on the Newfoundland Islands have a yearly produce of \$1,365,000 to \$1,638,000, and the Canadian fisheries yield \$10,920,000 to \$12,285,000 yearly." Herr Wallem adds in a note that "for comparison it may perhaps be instructive to state that the Norwegian Marine Fisheries may be estimated at \$12,285,000 to \$13,650,000 yearly, and the French at \$15,015,000 to \$16,380,000." If these figures may be accepted as correct on the high authority of Herr Wallem, the American fisheries must be worth about 5,500,000*l.* a year; the French fisheries 3,000,000*l.*; the Norwegian fisheries 2,600,000*l.*; and the Canadian fisheries 2,250,000*l.* We have unfortunately no statistics at our command which would enable us to compare these values with the produce of our own fisheries, but we do not believe that any competent authority would place their value at less than 6,300,000*l.* We believe that most persons would be disposed to name a higher sum. Englishmen, therefore, may feel the satisfaction of reflecting that the fisheries of the British Islands are still the most important in the world, though the fishermen of the United States are fast overtaking British fishermen.

Those persons who are most familiar with the British fisheries are aware that for years past complaints have been made of the injury done both to fish and fishing by the operations of trawling. It is very singular that trawling is also objected to in the United States. The Commissioners print in their appendices a paper from the fishermen of Block Island on the subject. From the similarity between the complaints disappointed examination. A trawl in England is a large net, attached to a heavy beam raised upon trawl or irons at either end, and dragged along the bottom of the sea. A trawl in Scotland is simply a draft net; a trawl in America is a long line baited with and left on the bottom of the sea. It is very odd these three distinct modes of fishing are all objected in the different countries in which they are employed. In Scotland the drift-net fishermen object to the trawl seine-nets; in England the drift-net fishermen object to the line fishermen object to the beam trawls. In America the hand-line fishermen object to the set-line fishermen whom they call trawlers. Among the fishermen of three countries there is a cry against trawling, and fishermen of the three countries are all alluding to distinct modes of fishing. These complaints may, of

, puzzle some antiquarians, who may naturally ıe that these races, speaking the same language, the same thing by the same word. They all are ɔ the jealousy usually felt by the introduction of new inery in any industry. The set-line fishermen, who lain of the beam trawls in this country, form the ɔlass which the hand-line fishermen complain of in ica under the name of trawlers; and the Govern- ; of both countries may safely disregard both laints, since one of them is the most effective answer · other.

· have reserved for the close of this article all refer- ːo what the Commissioners would consider the most ·tant portion of their Report. The Americans are the ɔst fish-breeders in the world, and fish-breeding is ıcted in the United States at a cost and to an extent ich in this country we can have little idea. According ː Report, the Commissioners distributed in 1878 no less 15,700,000 shad and 4,460,000 Californian salmon, es other fish. Such prodigious efforts will excite ise among persons who are acquainted with the diffi- s of obtaining even a few thousand ripe salmon eggs, ve naturally turn for information as to the results ı have ensued from such unprecedented efforts. Here ver we find, as it seems to us, the least satisfactory ɔn of the Report. The Commissioners claim indeed ıo less than 500 salmon were taken in the mouth of the ecticut River in 1878, a river which they imply had ew or no salmon in it for many years. It is possible fore that the Commissioners' efforts may have been .ssful in restocking that river with salmon; though we ːhat we should feel more certain of this if the fish ɔeen taken in the river itself, and not in the mouth But when they go on to infer that they may increase ·ield of shad, and even of herring and of cod, we with admiration of their energy, but without being ːnced by their reasoning. In this country, at any the best observers are satisfied that cod, herring, and · fish are annually bred in numbers compared with ˈı the fifteen millions of fry of the United States ːmission would represent an insignificant fraction, hat the destruction which is going on among them ıtural causes is so vast that even the capture of white by the ton-load makes no appreciable addition to it. arguments which Malthus, at the commencement of ·entury, used to illustrate the principles of population hought in this country to be strictly applicable to fish. fish, like all other animals, are undoubtedly increasing ·eater proportion than their food; and it is obvious efore that unless man can increase their food it is lost labour to increase their number.

ˈe have thus reviewed, at some length, a few of the ing facts in this long and interesting Report. With y of the conclusions in it we are unable to agree; but ːannot part from it without expressing a feeling of ɔst envy at the elaborate pains which the Government he United States is taking to understand the best hods of developing the great industries of their seas. his country we do not even take steps to obtain the statistical information on the subject. Might we in such a matter with advantage follow the example ·ur Transatlantic kinsmen?

THE PARIS OBSERVATORY[1]

BOUT two years ago Rear-Admiral Mouchez, director · of the Paris Observatory, resolved to bring together exhibition the instruments scattered in various parts, by joining to that collection the portraits of great onomers and methodically grouping all the documents ting ɔ the history of astronomy which could be pro- ·quest or otherwise, to lay the basis of a special museum of very great interest. This proposal, having received the approval of the Minister of Public Instruction, is now being realised. One of the large rooms on the first floor of the Observatory has already been fitted up and occupied, and through the kindness of Admiral Mouchez, who himself did us the honour of giving full details of his new collection, we are able to publish the description.

The first hall of the Astronomical Museum is very artistically decorated. It is circular in form, and well lighted by several windows. The ceiling will probably be adorned by a painting representing the transit of Venus over the Sun. There are nine paintings in the room, representing Louis XIV., founder of the Observatory, and directors and eminent astronomers who have



FIG. 1.—Plan of the Observatory, with the proposed extension on the south side to the Boulevard Arago. Present state: A, the Observatory; B, the "sidérostat," C, the meridian circle; D, the great telescope; E, equatorials; M, ditch to be filled up; L L, ditches. Ground to be annexed; F, the Bischoffsheim equatorial; G, the great refractor of 0·74m. aperture; H, Fortin's circle; K, the astronomers' dwelling-house.

succeeded each other to the present day: Cassini, Lalande, Delambre, Laplace, Bouvard, Arago, Delaunay, and Leverrier; the latter painted after death by Giacomotti, is the gift of M. Bischoffsheim. In the embrasures of the windows are displayed astronomical paintings representing groups of nebulæ, Saturn's rings, lunar volcanoes, clusters of stars, the remarkable drawings of Jupiter and Mars executed by MM. Henry, &c.

On the oak mantelpiece stands a magnificent Louis-Quatorze clock made by Coypel and recently restored by M. Passerat, a specimen of art so unique that virtuosos would certainly attach a great value to it. Round the room are observed several globes mounted on marble and oak pillars, two being especially worthy of attention: the celestial sphere of Gerard Mercator (1551), and the terrestrial sphere of the same geographer (1541). On the latter globe may be seen figured a certain number of the great lakes of Central Africa already known and their

[1] ɛ by M. Gaston Tissandier in *La Nature*, and M. ·rt of 1880.

positions well indicated in the middle of the sixteenth century. These spheres, which constitute documents of great importance historically, were recently discovered at the Brussels library through a folio pamphlet bought in 1868, and have been reproduced with great accuracy, by M. Malou.

The objects exhibited are carefully classified in glass cases, so that they can be examined by the visitor without being touched. In the first case, which is set apart for optical instruments, is observed Fresnel's great lens; also some of the object-glasses made use of by Cassini, and other valuable objects presented to the Observatory by Mme. Laugier, such as the optical apparatus made use of by Arago; the photometer, prismatic mirrors, and the polarimeter, by means of which the great astron... enriched science with so many beautiful discoveries.

The second case contains objects relating to the ... of the "metric system," comprising a standard ... several curious specimens of foreign measures. ... other glass cases, arranged in a circle round the ... contain various astronomical instruments, among ... we may mention the apparatus made use of by M. ... to measure the velocity of rays of light, a large ... of Rigaud, another of Bruner, one of the first ... ever constructed; also several instruments of ... modern date, the first portable meridian circle ... Mouchez, Gambey's theodolite, &c.

The case in the centre of the room is ...



FIG. 2.—Aërial telescope of the seventeenth century, after Hevelius, from an engraving in the new Astronomical Museum of the Observatory ...

noticeable: it contains a curious collection of German instruments of the sixteenth century, in perfect preservation. The attention is at once attracted by several instruments of gilt brass, most artistically carved, which were made at Nüremberg in the sixteenth century. Amongst them we observed a curious mechanical arrangement for casting dice, which was probably used for some demonstration of the doctrine of probability and chances; a valuable sun-dial of carved brass, dated 1578, full of groups of allegorical personages; a species of altazimuth; a handsome repeating-circle, highly ornamented, and bearing the two-headed eagle of Germany; some astrolabes, quadrants, mariner's-compasses, a small ivory sun-dial of the sixteenth century, presented by M. Eichens. The history of all ... instruments except the last is unknown; but it ... posed that they were either presented to Louis ... are what is left from the spoil of the First ... having escaped the notice of the Allies in 1815.

On the lower part of this case are shown photo... of old engravings representing the astronomical ... ments of former ages. One of those curious pic... reproduced above (Fig. 2), showing the astron... telescope with a simple object-glass of long focus ... was constructed in the seventeenth century, and of ... an engraving was published by Hevelius. It may ... to convey an idea of the singular and gigantic instru... which astronomers of bygone times made use of.

floor above there is a special exhibi-
mber of photographs, which is being
d by new additions. They consist
all the ancient instruments copied
the period; and all the foreign instru-
e, taken from nature. There are also
ng the principal observatories in the

ıencement of the astronomical museum
ratory. It will be completed by organ-
cular room resembling that which we
passed under review. This new room
ith portraits of the most illustrious of
ers :—Newton, Galileo, Tycho-Brahe,
ıs, Herschel, Bradley, and others. It
special exhibition of large astronomical
ably a quadrant of Lalande's, a sextant
uadrant of Langlois' which was used by
Committee, and a meridian telescope of

eful to bring together in the Paris Ob-
ıstruments which are scattered here and
other national institutions, so as to com-
already so rich in valuable objects. The
so gratefully accept of any bequests that
ed to them from private individuals, as
ne. Laugier with reference to the instru-
o and Delambre which she had in her

vey of the new Astronomical Museum, it
say a few words regarding the extension
ory, which is about to be made by annexing
the Boulevard Arago (Fig. 1). This waste
a superficies of at least 9000 metres, and
a which at present divides it from the Ob-
en is filled up, it will be united to the rest
tion without any separation. On these
be erected the great 75 m. telescope, the
for which are already well advanced; also
presented by M. Bischoffsheim, the circle
ich long rendered excellent service, and was
in 1862 to make room for the the great
le, and several instruments for the special
pols.
which we give above (Fig. 1) from official
shows what the Paris Observatory will be as
n the projected improvements are completed.
t that the works are being so slowly carried
standing the praiseworthy energy evinced by
s of the Observatory. A ditch to be filled in,
be laid out, a few buildings to be erected, all
but very little. But before the masons cut a
*garden*ers trace an alley there is a path to be
ich is not exactly the shortest or quickest,
limini strative and official routine.

ACHILLE DELESSE

to h ve to record the death of this eminent
st, w hich took place, after a long illness, on
eles e was born at Metz, and was educated
n of that town, afterwards proceeding, at
enty, to the École Polytechnique at Paris.
ligen and successful student, and in 1839
ee as a mining engineer. He then travelled
me th rough his own country, in Germany,
l the British Islands, and in 1845 was ap-
fessor of Geology and Mineralogy at Besan-
he also practised as a mining engineer. It
his res idence here that he wrote his "Notice
aractères de l'Arkose dans les Vosges," and
oire sur la Constitution minéralogique et chi-
Roches de Vosges," both of which works
n 1847. After a stay of five years at Besançon

Delesse returned to Paris, where he was employed as a mining engineer, and was especially engaged in superintending the quarrying operations about the city for nearly eighteen years. In 1855 he prepared the report on building materials in connection with the Exposition Universelle of that year in Paris. In 1864 he was nominated Professor of Agriculture, Drainage, and Irrigation in the École des Mines. Delesse's earliest researches were directed to pure mineralogy, and he paid great attention to the subjects of pseudomorphs and the association of minerals, and this led him to study the question of the metamorphism of rocks. The outcome of this period of study was his well-known work, "Recherches sur l'Origine des Roches," published in 1865, in which he argued ably and forcibly in favour of the view that crystalline rocks owe many of their characters to the action of superheated water, and are not produced by simple dry fusion. This important work of Delesse has exercised a marked and very beneficial influence on the progress of petrographical science, and its originality and value were at once recognised by the most advanced thinkers of the time. Already in 1858 Delesse had published two of his valuable maps, namely, the "Carte géologique souterraine de la Ville de Paris" and the "Carte hydrologique de la Ville de Paris," and his subsequent studies came to be especially directed into the channels of inquiry which were associated with the professorship that he had created and so ably filled. In 1868 appeared his work on the Rainfall of France, and other memoirs treating of the agricultural bearings of geology were produced about the same period.

The war of 1870 caused an interruption in the scientific labours of Delesse, and we find him at this period superintending the construction of cartridges in the departments. But in 1878 he was appointed an Inspector-General of Mines, and the south-east of France was assigned to him as his district. During the last twenty years Delesse has issued, in conjunction with MM. Langel and de Lapparent, a series of annual volumes entitled "Revue de Géologie," a work of such value that we regret to hear that it is to be discontinued in the future. Delesse received many honours in recognition of his valuable labours. He was an officer of the Legion of Honour, and filled the post of President of the Geological Society of France. As long ago as 1859 he was elected a Foreign Member of our own Geological Society. He was also for two years President of the French Geological Society, and he occupied the chair during the International Congress of that Society in 1875. In 1879 Delesse was elected a Member of the Academy of Sciences. In Delesse France has lost one of her most distinguished and widely-known scientific men.

PROFESSOR HELMHOLTZ'S FARADAY LECTURE

ON Tuesday evening Prof. Helmholtz gave the Faraday Lecture of the Chemical Society at the Royal Institution. We have so recently (NATURE, vol. xv. p. 389) given a full account of the life and work of the eminent German worker in various departments of science, that it is unnecessary to go over the ground again. A very fair estimate of his position was given in a leading article in the *Times* of Saturday last; and we are glad to notice that the leading journal now is glad to draw attention to men of science whose work is deserving of public notice. The University of Cambridge did itself the honour of conferring upon Prof. Helmholtz the degree of LL.D. on Thursday last, on which occasion the public orator, Mr. Sandys, made the following elegant and appropriate speech :—

"Dignissime domine, domine Procancellarie, et tota Academia :

"Singularum quidem scientiarum terminos protulisse,

plurimis concessum est; uni vero plurimarum fines extendisse raro contigit. Atqui hodie virum salutamus, qui rerum naturae regionem plusquam unam feliciter occupavit, qui primum physiologiae penetralia perscrutatus, deinde physicorum studiorum campo amplissimo potitus, ipsam denique mathematicorum arcem fortiter expugnavit, ex alia deinceps in aliam provinciam progressus, velut militum Romanorum ille maximus, 'victrices aquilas alium laturus in orbem.'

"Militarium medicorum ordini adhuc adscriptus, argumentum magnum intra unius libelli fines artiores complexus, ostendit vim illam, quae nonnunquam viva vocatur, in universa rerum natura esse conservatam, partes eius aliam ex alia posse generari, summam esse immutabilem. Quid huius ingenio excogitatas commemorem quaestiones illas hydrodynamicas, quid vortices illos qui scientiae mathematicae ad interiora pertinent? Illa vero magna opera, quorum in uno sensus audiendi clarissime explicatur, in altero videndi sensus pulcherrime illustratur, omnes, nisi fallor, aut vidistis ipsi, aut fama certe audivistis. Pulcbrum est (uti hunc ipsum confitentem legimus), pulchrum profecto est, e scopulo quodam excelso late tumultuantem oceanum prospicere, fluctusque procul albescentes, modo breviores, modo longiores, oculis discernere: pulchrius autem in physiologiae templo intimo versatum, oculorum ipsorum structuram exquisitam introspicere, et, lucis legibus obscuris ordine lucido evolutis, fluctuantes luminis motus metiri variamque colorum venustatem explicare: omnium fortasse pulcherrimum, in iisdem arcanis morantem, undas illas aeris quas nulla nisi mentis acie contemplari possumus, inter sese audiendo distinguere; sonitus cuiusque, dum tremit vibratque, intervalla numerare; universam denique musices theoriam et mathematicis et physicis et physiologicis probavisse argumentis.

"Ille igitur qui tot provinciarum confinia lustravit, tot scientiarum fines propagavit, a nostra praesertim Academia, cuius alumni totiens ex eodem studiorum campo laureas reportarunt, ea qua par est reverentia hodie excipitur. Qui Academiae nostrae nemora, et iuventutis Academicae ludos et certamina iampridem admiratus est, idem fortasse severiora nostra studia quo melius noverit, eo benignius indies aestimabit. Vos certe, qui, talium virorum exemplar procul venerati, etiam nostras inter silvas verum quaeritis, quanquam hodie nemora illa nostra gravis umbra contristat, tamen inter ipsas lacrimas non sine gaudio virum magnum vidistis, quaque soletis benevolentia laudatum audivistis.

"Vobis igitur praesento Academiae Berolinensis Professorem illustrem, HERMANNUM LUDOVICUM FERDINANDUM HELMHOLTZ."

The Society of Telegraph Engineers are to give a *conversazione* in honour of the distinguished electrician at University College, Gower Street, on the evening of the 11th inst. The large library and entrance hall will be lit up by electric light, and it is hoped there will be a full display of all the recent novelties in electrical science.

As might have been expected, there was a distinguished audience on Tuesday evening to listen to Prof. Helmholtz at the Royal Institution. Prof. Roscoe, the President of the Chemical Society, in introducing the lecturer, made the following remarks:—

"Ladies and Gentlemen, Fellows of the Chemical Society—The cordial welcome which you have just given to Prof. Helmholtz shows me that he needs no formal introduction at my hands. His name is honoured wherever science is valued, and both his face and his voice are well remembered in this room. It may therefore suffice if I say that eminent as an anatomist, as a physiologist, as a physicist, and as a mathematician, we chemists are now about to claim him also as our own.

"Prof. Helmholtz, in the name of the Chemical Society, and on behalf of its Fellows here assembled, I beg to welcome you amongst us; I have the honour to you with the Faraday Medal of the Society request that you will favour us with your le which we shall all listen with pleasure and profit"

The Faraday Lecture[1]

THE majority of Faraday's own researches w nected, directly or indirectly, with questions r the nature of electricity, and his most import most renowned discoveries lay in this field. Th which he has found are universally known. I theless, the fundamental conceptions by which h has been led to these much-admired discoveries h been received with much consideration. His g aim was to express in his new conceptions as with the least possible use of hypothetical subst forces. This was really a progress in general m method, destined to purify science from the last re of metaphysics. Now that the mathematica tation of Faraday's conceptions regarding the na electric and magnetic force has been given Maxwell, we see how great a degree of exactne precision was really hidden behind his words w his contemporaries appeared so vague or obscure is astonishing in the highest degree to see what number of general theories, the methodical deci which requires the highest powers of mathematica he has found by a kind of intuition, with the c of instinct, without the help of a single mathem formula.

The electrical researches of Faraday, altho bracing a great number of apparently minute an nected questions, all of which he has treated w same careful attention and conscientiousness always aiming at two fundamental problems of philosophy, the one more regarding the nature forces, or of forces working at a distance; the the same way, regarding chemical forces, or those act from molecule to molecule, and the relation these and the first.

The great fundamental problem which Fara up anew for discussion was the existence of forc ing directly at a distance without any intervening m During the last and the beginning of the present the model after the likeness of which nearly all theories had been formed was the force of gr acting between the sun, the planets, and their sa It is known how, with much caution and even re Sir Isaac Newton himself proposed his grand hyp which was destined to become the first great posing example, illustrating the power of true method.

But then came Oerstedt's discovery of the ac magnets under the influence of electric currents force acting in these phenomena had a new a singular character. It seemed as if it would single isolated pole of a magnet in a circle arou wire conducting the current, on and on without end coming to rest. Faraday saw that a motion of th could not be produced by any force of attract repulsion, working from point to point. If the is able to increase the velocity of the magnet, the m must react on the current. So he made the experi and discovered induced currents; he traced the through all the various conditions under which ought to appear. He concluded that somewhere in of the space traversed by magnetic force there e peculiar state of tension, and that every change tension produces el rce. This ul hypothetical state h nally the elec nic state, and he s ns and po

[1] Ab

ing out what was this electrotonic state. He dis-ered at first, in 1838, the dielectric polarisation of tric insulators, subject to electric forces. Such bodies w, under the influence of electric forces, phenomena fectly analogous to those exhibited by soft iron under influence of the magnetic force. Eleven years later, 849, he was able to demonstrate that all ponderable ter is magnetised under the influence of sufficiently nse magnetic force, and at the same time he disco-ed the phenomena of diamagnetism, which indicated t even space, devoid of all ponderable matter, is gnetisable; and now with quite a wonderful sagacity l intellectual precision Faraday performed in his brain work of a great mathematician without using a single thematical formula. He saw with his mind's eye that these systems of tensions and pressures produced by dielectric and magnetic polarisation of space which rounds electrified bodies, magnets or wires conducting ctric currents, all the phenomena of electro-static, gnetic, electro-magnetic attraction, repulsion, and luction could be explained, without recurring at all to ces acting directly at a distance. This was the part his path where so few could follow him; perhaps a erk Maxwell, a second man of the same power and lependence of intellect, was necessary to reconstruct the normal methods of science the great building, the an of which Faraday had conceived in his mind and tempted to make visible to his contemporaries.

Nevertheless the adherents of direct action at a distance ave not yet ceased to search for solutions of the electro-agnetic problem. The present development of science, owever, shows, as I think, a state of things very favour-ble to the hope that Faraday's fundamental conceptions ay in the immediate future receive general assent. His eory, indeed, is the only existing one which is at the me time in perfect harmony with the facts observed, nd which at least does not lead into any contradiction gainst the general axioms of dynamics.

It is not at all necessary to accept any definite opinion bout the ultimate nature of the agent which we call lectricity.

Faraday himself avoided as much as he could giving ny affirmative assertion regarding this problem, although e did not conceal his disinclination to believe in the xistence of two opposite electric fluids.

For our own discussion of the electro-chemical pheno-nena, to which we shall turn now, I beg permission to se the language of the old dualistic theory, because e shall have to speak principally on relations of quantity.

I now turn to the second fundamental problem aimed at by Faraday, the connection between electric and chemical force. Already, before Faraday went to work, an elaborate electro-chemical theory had been established by the re-nowned Swedish chemist Berzelius, which formed the connecting-link of the great work of his life, the systema-tisation of the chemical knowledge of his time. His starting point was the series into which Volta had arranged the metals according to the electric tension which they exhibit after contact with each other. A fundamental point which Faraday's experiment contra-dicted was the supposition that the quantity of electricity collected in each atom was dependent on their mutual electro-chemical differences, which he considered as the cause of their apparently greater chemical affinity. But although the fundamental conceptions of Berzelius' theory have been forsaken, chemists have not ceased to speak of positive and negative constituents of a compound body. Nobody can overlook that such a contrast of qualities, as was expressed in Berzelius' theory, really exists, well-developed at the extremities, less evident in the middle terms of the series, playing an important part in all chemical actions, although often subordinated to other influences.

When Faraday began to study the phenomena of de-composition by the galvanic current, which of course were considered by Berzelius as one of the firmest sup-ports of his theory, he put a very simple question, the first question indeed which every chemist speculating about electrolysis ought to have answered. He asked, What is the quantity of electrolytic decomposition if the same quantity of electricity is sent through several elec-trolytic cells? By this investigation he discovered that most important law, generally known under his name, but called by him the law of definite electrolytic action.

Faraday concluded from his experiments that a definite quantity of electricity cannot pass a voltametric cell containing acidulated water between electrodes of plati-num without setting free at the negative electrode a corresponding definite amount of hydrogen, and at the positive electrode the equivalent quantity of oxygen, one atom of oxygen for every pair of atoms of hydrogen. If instead of hydrogen any other element capable of substi-tuting hydrogen is separated from the electrolyte, this is done also in a quantity exactly equivalent to the quantity of hydrogen which would have been evolved by the same electric current.

Since that time our experimental methods and our knowledge of the laws of electrical phenomena have made enormous progress, and a great many obstacles have now been removed which entangled every one of Faraday's steps and obliged him to fight with the con-fused ideas and ill-applied theoretical conceptions of some of his contemporaries. We need not hesitate to say that the more experimental methods were refined, the more the exactness and generality of Faraday's law was confirmed.

In the beginning Berzelius and the adherents of Volta's original theory of galvanism, based on the effects of metallic contact, raised many objections against Faraday's law. By the combination of Nobili's astatic pairs of magnetic needles with Schweigger's multiplicator, a coil of copper wire with numerous circumvolutions, galvano-meters became so delicate that the electro-chemical equivalent of the smaller currents they indicated was imperceptible for all chemical methods. With the newest galvanometers you can very well observe currents which would want to last a century before decomposing one milligram of water, the smallest quantity which is usually weighed on chemical balances. You see that if such a current lasts only some seconds or some minutes, there is not the slightest hope to discover its products of decomposition by chemical analysis. And even if it should last a long time the feeble quantities of hydrogen collected at the negative electrode can vanish, because they combine with the traces of atmospheric oxygen absorbed by the liquid. Under such conditions a feeble current may continue as long as you like without pro-ducing any visible trace of electrolysis, even not of galvanic polarisation, the appearance of which can be used as an indication of previous electrolysis. Galvanic polarisation, as you know, is an altered state of the metallic plates which have been used as electrodes during the decomposition of an electrolyte. Polarised electrodes, when connected by a galvanometer, give a current which they did not give before being polarised. By this current the plates are discharged again and returned to their original state of equality.

This depolarising current is indeed a most delicate means of discovering previous decomposition. I have really ascertained that under favourable conditions one can observe the polarisation produced during some seconds by a current which decomposes one milligram of water in a century.

Products of decomposition cannot appear at the elec-trodes without motions of the constituent molecules of the electrolyte throughout the whole length of the liquid. This subject has been studied very carefully and for a

great number of liquids, by Prof. Hittorff, of Münster, and Prof. G. Wiedemann, of Leipsic.

Prof. F. Kohlrausch, of Würzburg, has brought to light the very important fact that in diluted solutions of salts, including hydrates of acids and hydrates of caustic alkalis, every atom under the influence of currents of the same density moves on with its own peculiar velocity, independently of other atoms moving at the same time in the same or in opposite directions. The total amount of chemical motion in every section of the fluid is represented by the sum of the equivalents of the cation gone forwards and of the anion gone backwards, in the same way as in the dualistic theory of electricity, and the total amount of electricity flowing through a section of the conductor corresponds to the sum of positive electricity going forwards and negative electricity going backwards.

This established, Faraday's law tells us that through each section of an electrolytic conductor we have always equivalent electrical and chemical motion. The same definite quantity of either positive or negative electricity moves always with each univalent ion, or with every unit of affinity of a multivalent ion, and accompanies it during all its motions through the interior of the electrolytic fluid. This we may call the electric charge of the atom.

Now the most startling result, perhaps, of Faraday's law is this: If we accept the hypothesis that the elementary substances are composed of atoms we cannot avoid concluding that electricity also, positive as well as negative, is divided into definite elementary portions, which behave like atoms of electricity. As long as it moves about on the electrolytic liquid each atom remains united with its electric equivalent or equivalents. At the surface of the electrodes decomposition can take place if there is sufficient electromotive power, and then the atoms give off their electric charges and become electrically neutral.

Now arises the question, Are all these relations between electricity and chemical combination limited to that class of bodies which we know as electrolytes? In order to produce a current of sufficient strength to collect enough of the products of decomposition without producing too much heat in the electrolyte, the substance which we try to decompose ought not to have too much resistance against the current. But this resistance may be very great, and the motion of the ions may be very slow, so slow indeed that we should need to allow it to go on for hundreds of years before we should be able to collect even traces of the products of decomposition; nevertheless all the essential attributes of the process of electrolysis could subsist. If you connect an electrified conductor with one of the electrodes of a cell filled with oil of turpentine, the other with the earth, you will find that the electricity of the conductor is discharged unmistakably more rapidly through the oil of turpentine than if you take it away and fill the cell only with air.

Also in this case we may observe polarisation of the electrodes as a symptom of previous electrolysis. Another sign of electrolytic conduction is that liquids brought between two different metals produce an electromotive force. This is never done by metals of equal temperature, or other conductors which, like metals, let electricity pass without being decomposed.

The same effect is also observed even with a great many rigid bodies, although we have very few solid bodies which allow us to observe this electrolytic conduction with the galvanometer, and even these only at temperatures near to their melting-point. It is nearly impossible to shelter the quadrants of a delicate electrometer against being charged by the insulating bodies by which they are supported.

In all the cases which I have quoted one might suspect that traces of humidity absorbed by the substance or adhering to their surface were the electrolytes. I show you therefore this little Daniell's cell, in which the porous septum has been substituted by a thin stratum of [illegible]. Externally all is symmetrical at both poles; there is nothing in contact with the air but a closed surface of glass, through which two wires of platinum penetrate. The whole charges the electrometer exactly like Daniell's cell of very great resistance, and this it would not do if the septum of glass did not behave like the electrolyte. All these facts show that electrolytic conduction is not at all limited to solutions of acids or salts.

Hitherto we have studied the motions of positive matter as well as of electricity, going on in an electrolyte. Let us study now the forces which are able to produce these motions. It has always appeared somewhat startling to everybody who knows the mighty power of chemical forces, the enormous quantity of heat and mechanical work which they are able to produce, who compares with it the exceedingly small electric attraction which the poles of a battery of two Daniells show. Nevertheless this little apparatus is able to decompose water.

The quantity of electricity which can be conveyed by very small quantity of hydrogen, when measured by electrostatic forces, is exceedingly great. Faraday this, and has endeavoured in various ways to give least an approximate determination. The most powerful batteries of Leyden jars, discharged through a voltameter give scarcely any visible traces of gases. At present can give definite numbers. The result is that the electricity of 1 mgrm. of water, separated and communicated two balls, 1 kilometre distant, would produce an attraction between them, equal to the weight of 25,000 kilos.

The total force exerted by the attraction of an electric body upon another charged with opposite electricity always proportional to the quantity of electricity contained in the attracting as on the attracted body, therefore even the feeble electric tension of two Daniells elements acting through an electrolytic cell upon enormous quantities of electricity with which the constituent ions of water are charged, is mighty enough separate these elements and to keep them separated.

We now turn to investigate what motions of the positable molecules require the action of these forces. Let begin with the case where the conducting liquid is rounded everywhere by insulating bodies. Then electricity can enter, none can go out through its surface but positive electricity can be driven to one side, negative to the other, by the attracting and repelling forces external electrified bodies. This process going on well in every metallic conductor is called "electric induction." Liquid conductors behave quite like metals under these conditions. Prof. Wüllner has proved that our best insulators, exposed to electric forces for a time, are charged at last quite in the same way as would be charged in an instant. There can be no doubt that even electromotive forces going down to less than $\frac{1}{100}$ Daniell produce perfect electrical equilibrium in the interior of an electrolytic liquid.

Another somewhat modified instance of the effects is afforded by a voltametric cell containing electrodes of platinum, which are connected with Daniell's cell, the electromotive force of which is sufficient to decompose the electrolyte. Under this condition the ions carried to the electrodes cannot give their electric charges. The whole apparatus behaves was first accentuated by Sir W. Thomson, like a denser of enormous capacity.

Observing the polarising and depolarising current a cell containing two electrodes of platinum, hermetically sealed and freed of all air, we can observe these phenomena with the most feeble electromotive forces of Daniell, and I found that down to this limit the capacity of the platinum surfaces proved to be constant. By taking greater surfaces of platinum I suppose it will be possible to reach a limit much lower than that. If

nical force existed besides that of the electrical charges ch could bind all the pairs of opposite ions together, required any amount of work to be vanquished, an rior limit to the electromotive forces ought to exist, ch forces are able to attract the atoms to the elec- les and to charge these as condensers. No pheno- non indicating such a limit has as yet been discovered, l we must conclude therefore that no other force resists motions of the ions through the interior of the liquid n the mutual attractions of their electric charges.

On the contrary, as soon as an ion is to be separated m its electrical charge we find that the electrical forces the battery meet with a powerful resistance, the over- wering of which requires a good deal of work to be ne. Usually the ions, losing their electric charges, e separated at the same time from the liquid; some of em are evolved as gases, others are deposited as id strata on the surface of the electrodes, like gal- noplastic copper. But the union of two constituents ving powerful affinity to form a chemical compound, as u know very well, produces always a great amount of at, and heat is equivalent to work. On the contrary, decomposition of the compound substances requires work, because it restores the energy of the chemical forces, hich has been spent by the act of combination.

Metals uniting with oxygen or halogens produce heat the same way, some of them, like potassium, sodium, nc, even more heat than an equivalent quantity of ydrogen; less oxidisable metals, like copper, silver, latinum, less. We find therefore that heat is generated hen zinc drives copper out of its combination with the ompound halogen of sulphuric acid, as is the case in a Daniell's cell.

If a galvanic current passes through any conductor, a metallic wire, or an electrolytic fluid, it evolves heat. Mr. Prescott Joule was the first who proved experimentally hat if no other work is done by the current the total mount of heat evolved in a galvanic circuit during a ertain time is exactly equal to that which ought to have een generated by the chemical actions which have been erformed during that time. But this heat is not evolved t the surface of the electrodes, where these chemical ctions take place, but is evolved in all the parts of the ircuit, proportionally to the galvanic resistance of every art. From this it is evident that the heat evolved is an mmediate effect, not of the chemical action, but of the galvanic current, and that the chemical work of the battery has been spent in producing only the electric action.

If we apply Faraday's law, a definite amount of elec- tricity passing through the circuit corresponds to a definite amount of chemical decomposition going on in every electrolytic cell of the same circuit. According to the theory of electricity the work done by such a definite quantity of electricity which passes, producing a current, is proportionate to the electromotive force acting between both ends of the conductor. You see therefore that the electromotive force of a galvanic circuit must be, and is indeed, proportional to the heat generated by the sum of all the chemical actions going on in all the electrolytic cells during the passage of the same quantitity of electricity. In cells of the galvanic battery chemical forces are brought into action able to produce work; in cells in which decomposition is occurring work must be done against opposing chemical forces; the rest of the work done appears as heat evolved by the current, as far as it is not used up to produce motions of magnets or other equivalents of work.

Hitherto we have supposed that the ion with its electric charge is separated from the fluid. But the ponderable atoms can give off their electricity to the electrode, and remain in the liquid, being now electrically neutral. This makes almost no difference in the value of the electro- motive force. For instance, if chlorine is separated at the anode, it will remain at first absorbed by the liquid; if the solution becomes saturated, or if we make a vacuum over the liquid, the gas will rise in bubbles. The electro- motive force remains unaltered. The same may be observed with all the other gases. You see in this case that the change of electrically negative chlorine into neutral chlorine is the process which requires so great an amount of work, even if the ponderable matter of the atoms remains where it was.

The more the surface of the positive electrode is covered with negative atoms of the anion, and the negative with the positive ones of the cation, the more the attracting force of the electrodes exerted upon the ions of the liquid is diminished by this second stratum of opposite electricity covering them. On the contrary, the force with which the positive electricity of an atom of hydrogen is attracted towards the negatively charged metal increases in proportion as more negative electricity collects before it on the metal, and the more negative electricity collects behind it in the fluid.

Such is the mechanism by which electric force is con- centrated and increased in its intensity to such a degree that it becomes able to overpower the mightiest chemical affinities we know of. If this can be done by a polarised surface, acting like a condenser, charged by a very mode- rate electromotive force, can the attractions between the enormous electric charges of anions and cations play an unimportant and indifferent part in chemical affinity?

You see, therefore, if we use the language of the dualistic theory and treat positive and negative electrici- ties as two substances, the phenomena are the same as if equivalents of positive and negative electricity were attracted by different atoms, and perhaps also by the different values of affinity belonging to the same atom with different force. Potassium, sodium, zinc, must have strong attraction to a positive charge; oxygen, chlorine, bromine to a negative charge.

Faraday very often recurs to this to express his convic- tion that the forces termed chemical affinity and electri- city are one and the same. I have endeavoured to give you a survey of the facts in their mutual connection, avoiding, as far as possible, introducing other hypotheses, except the atomic theory of modern chemistry. I think the facts leave no doubt that the very mightiest among the chemical forces are of electric origin. The atoms cling to their electric charges and the opposite electric charges cling to the atoms. But I don't suppose that other molecular forces are excluded, working directly from atom to atom. Several of our leading chemists have begun lately to distinguish two classes of com- pounds, molecular aggregates and typical compounds. The latter are united by atomic affinities, the former not. Electrolytes belong to the latter class.

If we conclude from the facts that every unit of affinity of every atom is charged always with one equivalent either of positive or of negative electricity, they can form com- pounds, being electrically neutral, only if every unit charged positively unites under the influence of a mighty electric attraction with another unit charged negatively. You see that this ought to produce compounds in which every unit of affinity of every atom is connected with one and only with one other unit of another atom. This is, as you will see immediately, indeed, the modern chemical theory of quantivalence, comprising all the saturated compounds. The fact that even elementary substances, with few exceptions, have molecules composed of two atoms, makes it probable that even in these cases electric neutralisation is produced by the combination of two atoms, each charged with its electric equivalent, not by neutralisation of every single unit of affinity.

But I abstain from entering into mere specialities, as, for instance, the question of unsaturated compounds; perhaps I have gone already too far. I would not have dared to do it if I did not feel myself sheltered by the

authority of that great man who was guided by a never-erring instinct of truth. I thought that the best I could do for his memory was to recall to the minds of the men, by the energy and intelligence of whom chemistry has undergone its modern astonishing development, what important treasures of knowledge lie still hidden in the works of that wonderful genius. I am not sufficiently acquainted with chemistry to be confident that I have given the right interpretation, that interpretation which Faraday himself would have given perhaps, if he had known the law of chemical quantivalence, if he had had the experimental means of ascertaining how large the extent, how unexceptional the accuracy of his law really is; and if he had known the precise formulation of the law of energy applied to chemical work, and of the laws which determine the distribution of electric forces in space as well as in ponderable bodies transmitting electric current or forming condensers. I shall consider my work of to-day well rewarded if I have succeeded in kindling anew the interest of chemists for the electro-chemical part of their science.

At the conclusion of the lecture Prof. Roscoe made the following remarks :—

"The pleasing duty now devolves upon me of proposing a vote of thanks to our distinguished friend for his interesting, suggestive, and most appropriate address.

"Prof. Helmholtz has shown us that Faraday's conception of electricity is in exact accordance with the most modern developments of this science. He has told us that although Faraday was unacquainted with the technical details of mathematics, all his conclusions are capable of the most exact mathematical expression, and that our great experimentalist possessed the spirit and thoughts characteristic of a truly mathematical mind. But our lecturer has gone further, for upon Faraday's well-known law of electrolysis he has founded a new electro-chemical theory, which reveals to us chemists, conclusions of the utmost importance. He tells us as the results of the application of the modern theory of electricity to Faraday's great experimental law, that the atom of every chemical element is always united with a definite unvarying quantity of electricity. Moreover—and this is most important—that this definite amount of electricity attached to each atom stands in close connection with the combining power of the atom which modern chemistry terms quantivalence. For if the amount of electricity belonging to the monad atom be taken as the unit, then that of the dyad atom is two, of the triad atom three, and so on.

"Hence then, thanks first to Faraday and now to Helmholtz, chemists have now a new and unlooked-for confirmation of one of their most important doctrines from the science of electricity.

"These, Ladies and Gentlemen, are indeed sufficient grounds for our claiming Prof. Helmholtz as a chemist, and justify me in requesting that he will allow his name to be placed on the list of Honorary Fellows of the Chemical Society.

"I have much pleasure in proposing a hearty vote of thanks to the Faraday Lecturer for the year."

This proposal was seconded by Prof. Tyndall.

NOTES

MR. CLARENCE KING has resigned his position as Director of the Geological Survey of the United States. It has long been no secret that he wished to retire from an appointment which confined him chiefly to executive functions, left him with practically no time for independent scientific work, and hampered him in those mining and other financial operations in which he is understood to have large investments. In a letter [illegible] ult., addressed to the President of the United [illegible] that he believes he "can render more important service to science as an investigator than as the head of an executive bureau." All well-wishers to the cause of geology must hope that this belief will be fully justified; that the relief he will obtain from official trammels will enable him once more to devote to geological research the energy and experience which have already borne such good fruit. His tenure of office in the Geological Survey has hardly been long enough to enable him fully to develop the plans he had sketched out for the vigorous prosecution of the Survey as a truly national undertaking, alike creditable to the scientific spirit of the Republic and important to the development of its industrial resources. But he will be held in honourable remembrance as the first head of the National Survey, and as having taken a leading share in its initial organisation. It is reported that Mr. J. W. Powell, so long and well known by his work in the Rio Colorado basin, is to be the new director.

A WISH having been expressed by certain members of the Torquay Natural History Society to have a portrait of Mr. William Pengelly, F.R.S., &c., and he having kindly consented to sit for the same, a committee has been formed for carrying the suggestion into effect. The portrait will, at Mr. Pengelly's request, be placed in the museum of the Society, Torquay. It was at first proposed to limit the list of subscribers to members of the Torquay Natural History Society, but as many members of the Devonshire Association, and other friends having expressed a wish to join in the work, it has been decided to make the contribution general. Subscriptions will be received by the hon. treasurer, Mr. Robert Kitson, Torquay Bank.

THE Royal Academy of Sciences of Turin gives notice that from January 1, 1879, the new term for competition for the Bressa Prize has begun, to which, according to the testator, scientific men and inventors of all nations will be admitted. The prize will therefore be given to the scientific author or inventor, whatever be his nationality, who during the years 1877-78, "according to the judgment of the Royal Academy of Sciences of Turin, shall have made the most important and useful discovery, or published the most valuable work on physics, experimental science, natural history, mathematics, chemistry, physiology and pathology, as well as geology, history, geography and statistics." The term will be closed at the end of December 1882. The value of the prize amounts to 12,000 lire. The prize will in no case be given to any of the national members of the Academy of Turin, resident or non-resident.

THE Literary and Philosophical Society of Manchester recently completed the first century of its existence. Dr. Angus Smith is writing a history of the Society since its foundation, which will be read at an early meeting, and no doubt published in its *Proceedings*.

WE are glad to learn that the appeal on behalf of Mr. Smerdon, who has done such good work as foreman of the Kent's Cavern explorations, has resulted in a sum sufficient to procure him an annuity of 10*l*.

THE results of appointing a totally inexperienced and untrained man to the head of the Registrar-General's department, before the taking of the census, are already beginning to be felt. Complaints of mismanagement are rife—whole streets in London not served with the census-papers, and in many cases papers which were delivered have not yet been collected, and run the risk of being utilised for fire-lighting purposes. Certainly the interests of the country would have been best served by appointing Dr. Farr to the post of Registrar-General until after the census work had been completed. Dr. Farr's long experience would have been of great service, and these useful errors would have been [illegible] ing like scientific matters.

THERE was [illegible] subject of Technical Education [illegible] ation in the [illegible] ther night, on the

Anderson to appoint a roving Commission to inspect the al schools of the Continent. The fact is, as Mr. Mundella l out, we know quite well what is wanted here, and if the uilds would only spend the amount of money they ought here need be no want of technical instruction for all who pared to take advantage of it. As it is, such institutions us College, the Mason College, and others are putting a e scientific technical education within the reach of all and what is really wanted is the teaching of elementary in all our primary schools. The House was counted out motion.

EETING for the purpose of forming a society for the ment of chemical industry was held on Monday after- the rooms of the Chemical Society, Burlington House, ly, Prof. Roscoe presiding. The chairman explained some time the want of a Society had been felt, the which was the advancement of chemical industry in the Kingdom. Its main purpose would be to bring together intervals all those who possessed chemical, physical, neering knowledge, and who used this knowledge in ation of chemical action on a manufacturing scale, and the charge of or an interest in chemical industries. It erwards prove desirable to found a distinct branch of eering profession, who might be designated as chemical . He drew attention to the advantages which would accrue to the various branches of chemical industry by lishment of such an organisation. Briefly stated, its ould be to enable persons interested in chemical in- o meet, to correspond, and to interchange ideas improvements in the various processes, to publish n relating thereto by means of a journal or otherwise, and dispose of property for such purposes, and to do hings incidental or conducive to the objects aimed at. oe concluded by moving that it was desirable to form ciety as that suggested. This was seconded by Mr. l carried. Formal resolutions were then passed with f carrying out the object thus agreed upon.

e the following significant passage from a paper read orge Campbell, K.C.S.I., M.P., late Lieutenant- f Bengal, to the Society of Arts on March 25 last:— us who go to India know very little about agriculture l; and of agriculture under the conditions of Indian mate we know nothing whatever. The consequence at when we have attempted to show the natives how their agriculture we have generally egregiously failed, a native expression, our faces have been blackened. ect I am afraid we are not improving. The old- ivil servant, if not so literary as the new class, and much more agricultural, settled down more in the learned more of native agricultural habits and ways. inistrators, I am afraid, know very little of any kind re, and it is much the same with the native public merly they knew nothing of English literature, but great deal of the country; now they are very highly it do not know much more of agriculture than their periors."

of Curator of the Herbarium of the Royal Botanic lcutta, has been filled up by the India Office by the , on the nomination of the Director of the Royal w, of Mr. L. J. K. Brace, of New Providence, Mr. Brace was educated at Christ's Hospital, and linate post in the colony. Having turned his atten- r, he was employed by the late Governor, Mr. W. make a collection for Kew of the indigenous

rs the cultivation of Liberian coffee (*Coffea Liberica*) getically pushed in English coffee-growing colonies and possessions. This has been due to two causes:—First, the cultivation of Arabian coffee (*Coffea Arabica*) has been severely crippled in the New World by the "white fly" (*Cemiostoma caffeellum*), and in the Old by the "leaf disease" (*Hemileia vastatrix*); secondly, Liberian coffee being a more tropical plant, grows well at a zone of altitude below that which Arabian coffee requires. The produce of the plantations of the new species is now coming into commerce. At present it does not find much favour apparently in England, but in America it is better appreciated. Recent sales at New York of Ceylon-grown Liberian coffee have realised 93*s.* per cwt., or 12*s.* above the current quotation for middling plantation coffee (Arabian) in the London market. This is a result of great importance for the West Indian Islands. Liberian coffee has been found in Dominica to possess a comparative immunity from the attacks of the white fly, the ravages of which had all but completely extinguished the coffee-cultivation of the island. Not merely therefore can West Indian coffee cultivation be revived with reasonable prospect of success, but there is the additional encouragement of a ready market easy of access in the United States.

THE death is announced, at the age of seventy-five, of Sir Philip de Malpas Grey Egerton. Sir Philip was an occasional contributor to our pages.

A STRONG shock of earthquake occurred on Sunday afternoon at Chio, which has caused terrible destruction. Many houses in the principal town and thirty villages in the island are said to have been destroyed, and 4000 persons killed. Fresh shocks of earthquake occurred on Monday, and the inhabitants were taking refuge on board the steamers in the harbour. The country around and the town Tsesme, on the mainland, suffered considerably, and shocks were also felt on Monday at Zante, Syra, Smyrna, Carosto, Eubœa, and Tinos. The island of Chio, Scio, or Skio, for the name is thus variously spelt, is situated in the Ægean Sea, separated from the coast of Anatolia by a channel not more than seven miles wide where narrowest, and about fifty-three miles west of Smyrna.

SOME of our readers may be glad to learn that the French Association has resolved to curtail the number of scientific meetings in order to extend the time left for excursions and festivals. The programme includes two receptions by the Mayor of Algiers, one by the Governor-General, and a large Arabian *fête* called *Bita*, dancing and singing by native women, &c. Possibly the reported massacre of the Flatters Expedition may put a stop to these ultra-scientific festivities.

WE notice that the names of Drs. Gladstone and Tribe are down for a paper in the Physical and Chemical Section of the meeting of the French Association at Algiers, as also that of Mr. Rodwell.

AT the ordinary meeting of the Sanitary Insttiute, to be held at 9, Conduit Street, on Wednesday, April 13, at 8 p.m., the Chairman of Council, Dr. Richardson, F.R.S., will give a short address entitled, "Some Brief Suggestions on the Best Mode of dealing with Small Pox and other Infectious Diseases in the Metropolis and other large Towns," to be followed by a discussion.

MR. R. J. FRISWELL writes:—As the following novel "facts" have their origin in *Truth* there can, I presume, be no gainsaying of them. As they are entirely new and are published in a journal not so well known as a scientific paper as it ought to be, will you be good enough to give them a wider currency for the information of chemists. Their value needs no comment:—"The bomb with which the Emperor was killed appears to have been filled with nitro-glycerine, and it is unfortunate that this compound, like gun-cotton, is so easy to make. A certain amount of glycerine is taken, and to this

sulphuric and nitric acid are added. Glycerine has an affinity for water. A molecule of water is abstracted, and a molecule of nitrous acid takes its place. Nitro-glycerine may be put into the fire or it may be struck without any dangerous consequence. If however it be set on fire by a fulminant, there is an explosion. If, as stated, the Russian bombs were made of glass, there must have been small projections made in the glass shell when manufactured, filled with fulminating powder. The explosive character arises from this: Nitrogen is composed of molecules in pairs of atoms. Nitric acid contains only one atom in its molecules. Upon this atom being set free from its unstable combination in the glycerine, the two atoms of nitrogen rush together, producing a vast amount of energy of combination in the shape of heat. The gaseous products are thus heated, and an explosion takes place immediately."

A SCHOOL of Gardening and Practical Floriculture has been established at the Crystal Palace, under the superintendence of Mr. Edward Milner.

M. DAUDIGNY, electrical engineer in Paris, has sent to the Municipal Council a petition asking for authority to establish on the top of the Colonne de Juillet a large electric lamp fed by a magneto-electric machine of fifty horse-power. This enormous light is to be diffused by a large reflector of special construction.

A MOST successful experiment in theatre illumination was tried on March 30 and 31, at the Athenæum of the rue des Martyrs, Paris, with the Werdermann incandescent light. The peculiarity of it is that it can be graduated at will for scenic effects, either by introducing resistance coils or varying the velocity of the Gramme machine. These experiments were witnessed by several influential members of the Municipal Council, who on the following morning proposed an inquiry into the propriety of obliging all the theatrical managers to light their halls with electricity.

MR. F. W. PUTNAM sends us a paper on Pueblo Pottery, which he contributed to the February number of the *American Art Review*. There are some well-executed coloured illustrations of specimens of the pottery which show some little taste in colour and ornamentation.

WE have had several replies to our inquiry concerning the late Dr. Thomas Dick's astronomical instruments. They seem to have been disposed of after his death, and only one small instrument can be definitely traced. None of the instruments seem to have been of much scientific value.

MR. JOHNSTON-LAVIS writes, under date March 29:—"Vesuvius is to-night again active, lava running down the north-western slope of the cone. Only the reflection is visible from Naples. On Sunday morning a slight shock, or more correctly subterranean thunder, was felt at Casamicciola, although those in the ruins at the moment only became aware of it by the palor of others present, whose whole attention is arrested by the faintest move or noise."

A SCIENCE Students' Association has been formed in Liverpool, which includes all departments of science in its programme; the president is Mr. A. Norman Tate.

THE system of compressed-air clocks, of the use and construction of which in Paris we gave an account some time ago, is likely to have a trial in London. A Bill has been introduced into Parliament for this purpose. The number of stations proposed for the metropolis is ten.

IN the notice of the meeting of the Mathematical Society in NATURE, vol. xxiii. p. 379, Mr. Wooster Woodruff Beman's name was misspelt Benson.

LIEUT.-COL. H. COLLETT, of Meean Meer, North-West Punjab, has sent us a money-order for 3*l*. towards the John Duncan Fund. We also acknowledge receipt of 1*l*. from M. G. S.

THE additions to the Zoological Society's Gardens [illegible] past week include a Two-Spotted Paradoxure (*Nandinia* [illegible] from West Africa, presented by Mr. A. Wentworth [illegible] Golden Sparrow (*Auripasser euchlorus*) from Abyssinia, [illegible] by Mr. J. Abrahams; a Chukar Partridge (*Caccabis* [illegible] Grey Francolin (*Francolinus ponticerianus*) from India, [illegible] by M. J. M. Cornely, C.M.Z.S.; two Indian Antelopes (*Antilope cervicapra* ♂ ♂) from India, deposited; two Æthiopian Hogs (*Phacochærus æthiopicus* ♂ ♀) from South-East [illegible] Dusky Parrot (*Pionus violaceus*) from Guiana, three [illegible] Hanging Parrakeets (*Loriculus asiaticus* ♂ ♂ ♀) from [illegible] a Yellow Troupial (*Xanthosoma flavus*) from Buenos [illegible] purchased; a Fork-tailed Jungle Fowl (*Gallus furcatus*) [illegible] Java, on approval; two Four-horned Antelopes (*Tetracerus quadricornis* ♂ ♀), a Burrhel Wild Sheep (*Ovis burrhel*) [illegible] India, a Javan Adjutant (*Leptoptilus javanicus*) from [illegible] Rock-hopper Penguin (*Eudyptes chrysocome*) from the [illegible] Islands, received in exchange.

OUR ASTRONOMICAL COLUMN

THE VARIABLE STARS U CEPHEI AND U GEMINORUM.—We learn from Mr. Knott that Ceraski's short-period [illegible] in Cepheus was at a minimum on March 29 at about [illegible] G.M.T.; clouds prevented observations till 11h. 3[illegible] it had barely fallen to minimum; for two hours, [illegible] —13h. 45m., the star's light was sensibly constant—abo[illegible] On April 3 Mr. Knott again obtained a pretty com[illegible] vation; the time of minimum, taking the middle of [illegible] was 12h. 24m. G.M.T.; for nearly 2h. 30m., or from [illegible] to 13h. 36m., the star remained about 9·4m. Guide [illegible] and previous observations the following approximate [illegible] minima are inferred, and it is to be hoped that the [illegible] be well observed:—

	h. m.		h. m.		
April 8 ...	12 4	April 23 ...	11 2	May 8	
13 ...	11 43	28 ...	10 41	13	
18 ...	11 22	May 3 ...	10 20	18	

This variable has been hitherto called T Cephei in the [illegible] but Mr. Knott draws attention to the circumstance that [illegible] (*Astron. Nach.*, No. 2343) applied that designation [illegible] to another variable discovered by him, the position of [illegible] meridian observations at Moscow was found to be [illegible] 21h. 7m. 57·05s., Decl. + 68° 0′ 8″·4 for 1880·0, [illegible] accordingly follow his suggestion that the short-period [illegible] will be more properly termed U Cephei.

U Geminorum was observed by Mr. Knott at [illegible] maximum, or about 9·3 m., on April 2 and 3. Maxim[illegible] very irregular variable star are by no means easy to [illegible] precedes the principal component of Σ 1158 by 1m. Σ [illegible] is north of it 7′ 31″. Prof. Winnecke gave a series [illegible] parison stars in *Astron. Nach.*, No. 1120. Argelander's [illegible] for 1855 is R.A. 7h. 46m. 29·88s.; Decl. + 22° 22′ 41″.

While writing upon variable stars we may mention [illegible] B.A.C. 4767 is probably to be included among [illegible] was estimated 4m. by D'Agelet on May 15, 1783; it [illegible] 6m. by Lacaille, Lalande, and Piazzi, and was so [illegible] Argelander's Zone, No. 301; but although rated 5[illegible] *Uranometria Argentina* it is not found in Heis's Atlas [illegible] Uranometria of Argelander. Its place for the present [illegible] R.A. 14h. 18m. 1s., with south declination, 24° 15′·6.

THE COMET OF 1812.—Several years since, Mr. [illegible] Plummer of the University Observatory, Oxford, after [illegible] reduction of the observations made at Paris and Vivers, [illegible] we possess in their original form, found the period of [illegible] about 1½ years less than that given by Encke, so that [illegible] possible that the comet may arrive again at perihelion [illegible] present year. We have already mentioned that M. Schulhof, [illegible] Paris is engaged upon a strict investigation of the elements [illegible] this comet, and has the intention of preparing extended [illegible] rides, in the same manner that he has done for several [illegible] minor planets which had not been observed at several [illegible] tions, but the sweeping lines for every fourth day throughout [illegible] the year are given in Herr Mahn's ephemeris computed [illegible] suggestion of Prof. Winnecke, which will be found [illegible] *Vierteljahrsschrift* [illegible] *tischen Gesellschaft*, 12 Jahrg.

BIOLOGICAL NOTES

SLAVE-MAKER (POLYERGUS LUCIDUS).—The ant is as fortunate as he is energetic in his studies ants. At the December 1880, meeting of the ural Sciences of Philadelphia he read a paper at the foot of the Allegheny Mountains, near st of *Polyergus lucidus*, the American represen- egionary Ant of Hubee (*P. rufescens*), an ant that author's discovery of ant-nests, in which e associated with them, in a sort of slavery, ants ies. The nest had four gates separated a few h other; the chambers were placed one above l by tubular galleries. In an inner ovoid chamber ants, male and female, appeared; mingled with numbers were workers in three forms—major, art of *Formica Schaufussi*. A portion of the was broken into, and on the next day but one lone of the shining ants were at work, but the very busy cleaning out the galleries; a portion of engaged in an extensive migration; a few were ellows, but for the most part the deportation was males and female of the shining ants. It was re the large virgin-queens carried up the perpen- the cutting for eighteen or twenty inches, and then e of six feet over the ground and through the grass, ew seconds over a minute. The shining ants are nt of wonderful grip. One of them had fallen dea ure of another, who held her firmly grasped e thorax. Anxious to preserve the colony from s, Mr. McCook lifted the two out on the point of ife, laid them on his hand, and thrust the fine pull between the jaws of the agressor, and so teased released her fellow. The rescued ant instantly alm of his hand, threw her abdomen under her, h back curved like that of an angry cat, sawed and at the skin until an abrasion was made. The other ; fast by her mandibles only to the toothpick's point, tched out into space, her limbs stretched outwards, ind leg, which was a little bent upward, and thus perceptible support except that which her jaws gave e *quill point*, she hung outstretched for several *sant* a month after its discovery the nest was again as abundantly peopled; the winged forms of the ve however gone. Having succeeded in colonising M'Cook was able to confirm in many particulars of Huber, Forel, and others, but he never has e slave- feeding their masters. He noticed that like to move towards both warmth and light, but m to have settled the question whether they would rarial h without the light. They would appear to r ways and persons. Various experiments dish U he fact that these slave-makers always keep at une e for any attack.

ON COLOUR OF SALT COD.—During the hot and of summer in the United States the dried codfish ibit a peculiar redness of colour. These red fish, wn, patrefy comparatively quickly, and this fact, ction with the disagreeable, and in such fish unusual, s them unfit for market, so that in seasons when evails dealers in codfish suffer often very con- es. Prof. Farlow, M.D., was requested by the Fish Commission to investigate this subject, and ears in the Fish Report for 1880. In September, nt to Gloucester to examine the fish stores. The at that time hot and damp, and the codfish then ed for the market were largely affected by the red- redness disappears until the return of cool weather. s it does not appear until the fish have been landed sels, though in a few cases the colour has appeared k while still on board. A microscopical examina- that the redness was owing to a very minute plant, *rosa-persicina*, a species known to be closely related *incus*, so common in fresh-water ponds, and which ome into public notice in the States in consequence of ad *pig iron* colour which it exhales when decaying. pecies is known both in America and Europe, and has recently investigated by Cohn and others. It may some- found tinging the surface of damp ground with a nge, and the anatomist is not unfamiliar with it as growing in his macerating tubs. It would appear not to flourish or increase very rapidly at a temperature below 65° Fahr. How it got to attack the dried fish was the next question. It was found that the plants could come from many sources, for it was found present in quantities in the wood-work of the wharves and packing-stores, but above all Prof. Farlow detected it in the salt with which the fish were cured. The salt from Cadiz had even a slight rose tinge. It will be a matter of interest, which perhaps some of our readers may help to solve, as to whether this plant is known in European fish-stations. In the great Norwegian cod-fisheries the temperature may not be high enough to favour its growth. As remedies Prof. Farlow suggests care in the selection of salt, and the constant cleaning of all wood-work or vessels that may come in contact with the fish. In addition to the red alga small quantities of cells destitute of colouring-matter and arranged in fours were not unfrequently found in the infected cod-fish. These suggested the genus Sarcina, but were not *S. ventriculi*. They rather, except in the absence of colouring-matter, resembled *Gleiocapsa crepidinum*, Thuret, which species is common enough on the wood-work of the Gloucester wharves. While there is this resemblance Prof. Farlow prefers for the moment, and pending further investigation, to call it a Sarcina, and to describe it as a new species (*S. ? morrhuæ*).

MARINE ISOPODS OF NEW ENGLAND.—One of the most remarkable papers forming the extensive series of appendices to the Report of the United States Commissioners of Fish and Fisheries for 1878 is perhaps that by Oscar Harger on the marine Isopods of New England and adjacent waters. The limits chosen commence at Nova Scotia to the north and extend southwards to New Jersey. Forty-six species are recorded, and figures of these with the requisite details of anatomy are given on thirteen plates; several new species and one new genus (Syscenus) are described. It will be noted that the number of species is very considerably less than that known to frequent the British coasts, and of the former only eight are identical with British forms. This difference is very marked in the genus Sphæroma, of which genus there is but one species native to New England, while Bate and Westwood describe a dozen species belonging to this family as natives of Britain. *Limnoria lignorum*, one of the most destructive of the group, is apparently as common on the American coasts as on our own shores. It does not usually occur much below high-water mark, though Prof. Verrill has found it at a depth of ten fathoms in Casco Bay, and it was dredged by the U.S. Fish Commission at a depth of 75 fathoms in Cape Cod Bay, Massachusetts. Of the family of the Cymothoidæ, of which we believe as yet no species has been found around the British Islands, three species belonging to three different genera are in Mr. Harger's list.—To this memoir there is appended a very complete list of authorities and an alphabetical index.

STATISTICS OF DISEASE IN ITALY.—In a recent paper to the Lombard Institute, Prof. Sangalli gives statistics of the diseases which terminated fatally in the Civic Hospital of Pavia during the period 1855 to 1881. The material was 6644 bodies which came up for autopsy, and the causes of death were, in decreasing order, genuine inflammation, 4504 deaths; tuberculosis, 808; pyæmia, 337; cancer, 306; hepatic cirrhosis, 252; extravasation of blood in the brain, 254; chronic ulcer (gastric and duodenal), 72, &c. (there being 2140 deaths apart from those by true inflammation). The 4504 deaths from inflammation presented 7962 separate inflammations. The deaths from tuberculosis are seen to be about 12 per cent. The ages most exposed to that disease lie between 20 and 30; next come those between 10 and 20, and between 30 and 40, about equal. There were twelve cases between 70 and 80, and one in an old man of 84. It does not appear that one sex suffers more than the other. Cancer occurs most between 50 and 60, and most largely in liver, lymphatic glands, and stomach. The patients were largely of the peasant class, and the author cannot support Niemeyer's view, that people living in marshy districts, liable to malaria, have a certain immunity from tuberculosis. Nor do the figures confirm the asserted tendency of ulcer in the stomach to favour the development of tuberculosis. Pyæmia appeared mostly in the lungs (149 cases out of 470), pleura, 99; liver, 73, &c. In some years there was a remarkable diminution of this disorder.

THE EYE AND INTENSITY OF COLOUR.—With an apparatus consisting of two Nicols with a gypsum plate between, and a spectroscope with a third Nicol attached to the eye-piece, Herr Dobrowolsky has examined the sensibility of the eye to spectral

colours with different intensities of light (Pflüger's *Archiv*, v. 24, p. 189). From a large number of measurements it was found that, on an average, the red-colour sensation first occurred with a light-quantity equal to $\frac{1}{3283}$, while for blue the lowest amount of light was $\frac{1}{51111}$. Thus blue gives a sensation with an amount of light sixteen times less than that required for red. With rise in the degree of brightness, the increase of sensibility to red proceeds pretty regularly; but for blue the increase becomes gradually greater (with the weakest degrees of brightness this increase was = 0·22, with the strongest 0·82, with the mean 0·36). Comparing the two sensibilities together, from the maximum of light strength to the minimum, the sensibility to blue is always found to exceed that to red (maximum thirteen and a half times, minimum sixteen times, mean four times).

ISOETES LACUSTRIS.—In an interesting paper read before the Academy of Sciences of Paris (January 10, 1881), M. E. Mer calls attention to the peculiar conditions under which different forms of this fresh-water plant seem to originate in the Lake of Longemer. The basin of this lake was once occupied by a glacier, and now presents several different sorts of bottom. The soil to a depth of two to three metres is composed in part of a gravel formed of rock *débris* united by an iron cement, in part of ancient moraines, or where near the surface these will be mixed with the remains of plants and form a pretty tenacious mud. In all these situations Isoetes is to be found, but the plants differ most remarkably both as to their form, their structure, and their mode of reproduction as they are found in the different habitats. Taking the leaf-development as a guide, four varieties are easily discerned:—(1) *humilis*, growing sparsely in the gravel and sterile shallows, the leaves are not only few in number, but always of diminutive dimensions; sporange generally wanting or represented by a small cellular mass which rarely ever forms a propagule, and then these with puny leaves; (2) *stricta*, found on the borders of the lake or in the old alluvial, therefore in less sterile quarters than the preceding; leaves more numerous, stout, but still of small size; (3) *intermedia*, growing on ground formed of a mixture of mud and clay, either on the borders of the lake or at a depth of from one to two metres, leaves quite intermediate in character between the previous variety and the next; (4) *elatior*, growing on the clayey depths, with long leaves. The first form is always found isolated, and as to its asexual reproduction there is nothing more to be said; but the other three, according as they are subject to more or less heat, present each three varieties characterised by the mode of reproduction. 1. *Sporifera*, isolated individuals, mostly furnished with well-developed sporangia, stem large, roots numerous, leaves large. 2. *Gemmifera*, few fertile sporangia, but most of the leaves are furnished with propagula, and these well furnished with leaves, generally dextral, stem fairly developed. 3. *Sterilis*, individuals growing in compact masses, stems and roots slender, leaves not numerous, long and narrow, fertile sporangia very rare, and more often undeveloped masses of cells or abortive propagula. It would seem as if these facts had a practical interest to the collector, who may find in them a guide as to where to look for fertile specimens.

GEOGRAPHICAL NOTES

ON Friday, April 1, the French Geographical Society held a meeting in the large hall of the Sorbonne for the reception of Dr. Lenz on his return from Timbuctoo. M. Milne-Edwards was in the chair. Dr. Lenz, as our readers know, has been very successful, although his conclusions are adverse to the construction of a railway from the Niger to Algeria throughout the Sahara. On the following morning the Society received a telegram stating that Col. Flatters had been murdered by Touaregs at some distance from the Lebhkha Amagdor. In the evening the sad news was confirmed by an official message, stating that four starving Arabs from the mission had arrived at Ouargla, and that the Khobfa had left with four hundred mehari and camel horsemen to rescue the survivors, who were besieged south of Messaguer in the Touat region proper. Happily the news of the disaster to Col. Flatters' expedition has not yet been further confirmed, and authorities in Paris are inclined to believe that it has been much exaggerated, and that the story of the four natives has many elements of suspicion about it.

DR. LENZ, in his lecture at Paris, gave some interesting details on the present condition of Timbuctoo. Its houses a[re] brick, and the population is now only 20,000. It [is] decayed, and the inhabited part of the town is sur[rounded] great spaces covered with ruins. There are numerous and rich libraries. Dr. Lenz had a cordial reception, a night during his twenty days' stay he was present at conferences which the learned men of the city held [with] interpreter; the commentaries on the Koran formed a subject of conversation. Timbuctoo is united with the six miles off, by a series of lakes, formerly canals. [He] has also made some interesting observations on the [Niger] tending to confirm the conclusions of Rholfs and other scientific travellers as to the variety which is to be met [with] the great desert. It is really a plateau about 300 metres [in] tude, no part of it being below the level of the sea, [with] hills, sandy plains, shallow lakes, fertile oases, sterile nearly the whole surface, while beasts of prey are [rarely] met with. Dr. Lenz will contribute a full account of his to the Berlin Africa Society, in whose journal many [of] have already appeared.

IT is with sincere regret that we record the death of Karl Weyprecht, at the age of forty-three, on March consumption. Lieut. Weyprecht will be known to [fame] as the discoverer, with Lieut. Payr of Franz-Josef Land, Austro-Hungarian Expedition of 1872-4. His observations the aurora borealis were of especial value, and he has several papers on the subject. He was also the originator the scheme for establishing a series of international stations around the Pole, which is likely to be realised next year.

THE Rev. G. Brown, the well-known representative of church militant in the South Pacific, contributes to the number of the Geographical Society's *Proceedings* a [de]scriptive of a recent journey which he has made along the of New Ireland and the adjacent islands, the latter [being] Sandwich Island, Portland Islands, and New Hanover. Benjamin Bradshaw, who has spent some years in collecting natural history specimens in the Upper Zambesi region, contributes a brief paper on the Chobe River, together with sketch-map of a portion of its course, adding materially knowledge of the geography of this region. Mr. [Hale's] paper on Saráwak and Northern Borneo, lately read before Society, is also given, and is illustrated with a good map. geographical notes are full of interesting matter, one [being] account, by Mr. Sibiriakoff himself, of the voyage of the *Dickson* to the Yenisei Gulf in 1880. Another feature is clusive proof of the usefulness of the course of scientific provided by the Council for intending travellers in countries. From the last note we learn that Mr. C. [R.] ham, the indefatigable secretary, is preparing for the [press] volume of the *Journal* a sketch of the Society's work past fifty years.

IN the current number of *Les Missions Catholiques* Richard, a missionary in Algeria, commences an account journey, in company with Père Kermabon, among the Azguer tribes of the Sahara. The object of their [visit] to study this almost unknown region, and to cultivate relations with the chiefs and people generally with a formation of a missionary station. The more interesting to Père Richard's narrative, as it deals with the [region] which Col. Flatters has been now exploring with the settling the best practicable route for the projected [Trans-Saharan] railway. An entirely new map of this part of Africa, Père Richard's notes, accompanies the number.

A LATELY-ISSUED batch of *Reports* from H.M. [Consuls] vi. of last year) contains useful geographical information ing portions of South America, that relating to Chili being specially interesting at the present moment.

UNIVERSITY AND EDUCATIONAL INTELLIGENCE

CAMBRIDGE.—On the 31st inst. the honorary degree was conferred on Prof. Helmholtz of Berlin at a special gation.

Prof. Humphrey [will] M.B. and Natura[l] strator will give d[emon]- Prof. Babington [will] beginning A[pril]

iatic botany, with practical work in the

of Comparative Anatomy will take an uction in the mammalia during the Easter

n opens his new workshops and drawing n-truction will be given in mechanical designing, and also in graphical statics ie theory of structures.
mmence an elementary course of lectures etism on May 2 in the chemical laboratory

ved of Lord Rayleigh's appointment of s of physics instead of me, and of the £100 to each.
ures on the embryology of aves and mam- ve a practical class in that subject.

ants of the Haberdashers' Company have the schools under their management a rchased from the executors of the late hood of the Company are at Monmouth, d Hoxton.

NTIFIC SERIALS

and Chemie, No. 3.—Constants of elasti- L. Kleng.—On the source of beats and intervals, by R. Koenig.—Description of for lecture experiments, by the same.— heory of resonance, by F. Kolacek.— e law of dispersion in transparent, semi- media, by F. Kettler.—Researches on bustion, by F. Tiipich.—On the electro- combinations formed of zinc, sulphuric copper, silver, gold, or carbon, by C. ction of the Toepler mercury pump, and e with it, by E. Dessel-Hagen.—Ex- of the atmosphere and the constitution of (continued), by A. Ritter.—On absorp- by the sulphuric acid of our atmosphere, Arden of galvanic polarisation, by W. ly-formed body which takes polar direc- ttractions, by W. Hallo.

aturhistorische Zeitschrift, vol. xxxv part 2, J. Adler, on the alternation of generations pp. 150-246, a very exhaustive treatise, loured plates of the galls and one of the gall insects.—Hans Virchow, on the e appendages of the eyes in frogs, with haikoff, researches on the Orthonectidæ Cattle, contribution to a knowledge of e of the Isopleuræ and of the central, eric nervous system in caterpillars, with a on the pairing and propagation of a lium.—N. Klemenberg, on the origin of with a woodcut).

S AND ACADEMIES

LONDON

ch 24.—"Observations on the Loomma- ermata." (The Croonian Lecture.) By F.R.S., and Prof. J. C. Ewart, M.D. had reference to the tube-systems and thrombidæ. It was shown by injection m and the so-called blood-vascular sys- ons, save at their common origin in the sys- tems communicate through this plate ; but the one much more freely than system being the least patent, so that of two feet is maintained for a number fluid slowly permeates the stone-canal, ugh the madreporic plate. Regarding us to and in Echinus that lateral branches ial trunks to escape with the pedicels the pore plates. Each of these branches edicel, with which it escapes in the ter- ese lateral branches there also arises an hich covers the whole external surface of the shell, lying almost immediately beneath the surface epithelium, and extending from the shell to all the spines and pedicellariæ. In stained specimens the nerve-fibres and cells were traced to the capsular muscles at the bases of the spines, and delicate fibres were detected running up the spines and pedicellariæ, immediately below their epithelium. In the case of the policellariæ it appeared from several preparations that delicate fibres extended as far as the sensitive epithelial pad situated on the inner surface of each trident mandible, a short distance from the apex.

Such being the principal morphological results, the paper went on to detail a number of physiological experiments. First it was pointed out that the natural movements of echinodermata exhibit a high degree of co-ordination. Thus, for instance, all the echinoderms are able when inverted on a flat floor to right themselves. The common starfish does this by twisting the ends of two or more of its rays round, so as to bring the terminal suckers into action upon the floor of the tank, and then by a successive and similar action of the suckers further back in the series the whole ray is progressively twisted round, so that its ambulacral surface is applied flat against the floor. The rays which perform this action twist their spirals in the same direction, and by this concerted action drag the disk and the remaining rays over themselves as a fulcrum. Other species of starfish which have not their ambulacral suckers sufficiently developed to act in this way execute their righting movements by doubling under two or three of their adjacent rays, and turning a somersault over them, as in the previous case. Echinus rights itself when placed on its aboral pole, by the successive action of two or three adjacent rows of suckers—so gradually rising from aboral pole to equator, and then as gradually falling from equator to oral pole. Spatangus executes a similar manœuvre entirely by the successive pushing and propping action of its longer spines.

Experiments in stimulation showed that all the echinoderms observed sought to escape from injury in a direct line from the source of irritation. If two points of the surface are stimulated the direction of escape is the diagonal between them. When several points all round the animal are simultaneously stimulated the direction of advance becomes uncertain, with a marked tendency to rotation upon the vertical axis. If a short interval of time be allowed to elapse between the application of two successive stimuli the direction of advance will be in a straight line from the stimulus applied latest. If a circular band of injury be quickly made all the way round the equator of echinus, the animal crawls away from the broadest part of the band, *i.e.* from the *greatest amount* of injury.

The external nerve plexus supplies innervation to three sets of organs—the pedicels, the spines, and the pedicellariæ ; for when any part of the external surface of echinus is touched, all the pedicels, spines, and pedicellariæ within reach of the point that is touched immediately approximate and close in upon the point, so holding fast to whatever body may be used as the instrument of stimulation. In executing this combined movement the pedicellariæ are the most active, the spines somewhat slower, and the pedicels very much slower. If the shape of the stimulating body admits of it, the forceps of the pedicellariæ seize the body and hold it till the spines and pedicels come up to assist.

And here we have proof of the function of the pedicellariæ. In climbing perpendicular or inclined surfaces of rock covered with waving seaweeds it must be no small advantage to an echinus to be provided on all sides with a multitude of forceps adapted, as described, to the instantaneous grasping and arresting of a passing frond ; for in this way not only is an immediate hold obtained, but a moving piece of seaweed is held steady till the pedicels have time to establish a further and more permanent hold upon it with their sucking disks. That this is the chief function of the pedicellariæ is indicated by the facts that (1) if a piece of seaweed is drawn over the surface of an echinus this wonderfully tenacious grasp of the forceps is timed as to its duration with an apparent reference to the requirements of the pedicels, for after lasting about two minutes (which is about the time required for the suckers to bend over and fix themselves to the object held by the pedicellariæ, if such should be a suitable one) this wonderfully tenacious grasp is spontaneously released ; and (3) that the most excitable part of the trident pedicellariæ is the inner surface of the mandibles, about a third of the way down their serrated edges, *i.e.* the part which a moving body cannot touch without being well within the grasp of the forceps.

When the forceps are closed they may generally be made immediately to expand by gently stroking the external surface of their bases.

With regard to stimulation of the spines, if severe irritation be applied to any part of the external or internal surface of an echinus, the spines all over the animal take on an active bristling movement. The tubercles at the bases of the spines are the most irritable points on the external surface.

With regard to stimulation of the pedicels, if an irritant be applied to any part of a row, all the pedicels in that row retract in succession from the seat of stimulation, but the influence does not extend to other rows. A contrary effect is produced by applying an irritant to any part of the external nerve-plexus, all the pedicels being then stimulated into increased activity. Of these antagonistic influences, the former, or inhibitory one, is the stronger, for if they are both in operation at the same time the pedicels are retracted.

Starfish (with the exception of brittle-stars) and echini crawl towards, and remain in, the light; but when their eye-spots are removed they no longer do so. When their eye-spots are left intact they can distinguish light of very feeble intensity.

Experiments in section showed that single rays detached from the organism crawl as fast and in as determinate a direction as do entire animals. They also crawl towards light, away from injuries, up perpendicular surfaces, and when inverted, right themselves. Dividing the ray-nerve in any part of its length has the effect of destroying all physiological continuity between the pedicels on either side of the division. Severing the nerve at the origin of each ray, or severing the nerve-ring between each ray, has the effect of totally destroying all co-ordination among the rays; therefore the animal can no longer crawl away from injuries, and when inverted it forms no definite plan for righting itself. Each ray acting for itself, without reference to the others, there is as a result a promiscuous distribution of spirals and doublings, which as often as not are acting in antagonism to one another. This division of the nerve usually induces, for some time after the operation, more or less tetanic-like rigidity of the rays. This operation however, although so completely destroying physiological continuity in the rows of pedicels and muscular system of the rays, does not destroy or perceptibly impair physiological continuity in the external nerve-plexus; for however much the nerve-ring and nerve-trunks may be injured, stimulation on the dorsal surface of the animals throws all the pedicels and muscular system of the rays into active movement. This fact proves that the pedicels and the muscles are all held in nervous connection with one another by the external plexus, without reference to the integrity of the main trunks.

If a cork-borer be rotated against the external surface of an echinus till the calcareous substance of the shell is reached, and therefore a continuous circular section of the overlying tissues effected, the spines and pedicellariæ within the circular area are physiologically separated from those without it, as regards their local reflex irritability. That is to say, if any part of this circular area is stimulated, all the spines and pedicellariæ within that area immediately respond to the stimulation in the ordinary way, while none of the spines or pedicellariæ surrounding the area are affected, and conversely. Therefore it is concluded that the function of the spines and pedicellariæ of localising and gathering round a seat of stimulation is exclusively dependent upon the external nervous plexus. If the line of injury is not a closed curve, so as not to produce a physiological island, the stimulating influence will radiate in straight lines from its source, but will not irradiate round the ends of the curve or line of injury.

Although the nervous connections on which the spines and pedicellariæ depend for their function of localising and closing round a seat of stimulation are thus shown to be completely destroyed by injury of the external plexus, other nervous connections, upon which another function of the spines depends, are not in the smallest degree impaired by such injury. This other function is that which brings about the general co-ordinated action of all the spines for the purposes of locomotion. That this function is not impaired by injury of the external plexus is proved by severely stimulating an area within a closed line of injury on the surface of the shell; all the spines over the whole surface of the animal then manifest their bristling movements, and by their co-ordinated action move the animal in a straight line of escape from the source of irritation.

We have, therefore, to distinguish between what may be called the local reflex function of the spines, which they show in common with the pedicellariæ, and which is exclusively dependent upon the external plexus, and what we may call the universal reflex function of the spines, which consists in general co-ordinated action for the purposes of locomotion, which is wholly independent of the external plexus. For therefore, this more universal function must depend upon some other set of nervous connections (which, however, the author were not able to detect histologically), and experiment proves that these, if present, are distributed over all the internal surface of the shell. For if the internal surface be painted with acid or scoured out with emery paper and brick-dust, the spines and pedicellariæ, after a short period of increased activity at first, become perfectly quiescent, lie flat, and lose both their tetaneity and irritability. After a few hours, however, the tetaneity and irritability of the spines return, though in a less degree, and also those of the pedicellariæ in a more marked degree. These effects take place over the whole external surface of the shell, if the whole of the internal surface be painted with acid or scoured with brick-dust; but if any part of the internal surface be left unpainted or unscoured, the corresponding part of the external surface remains uninjured. From these experiments it is concluded:—(1) that the general co-ordination of the spines is wholly dependent on the integrity of the hyponeural or internal plexus; (2) that the hypothetical internal plexus is everywhere in intimate connection with the external plexus through the calcareous substance of the shell; and (3) that complete destruction of the former, while profoundly modifying through shock the functions of the latter, nevertheless does not wholly destroy them.

Echini may be divided into pieces, and the pedicels and pedicellariæ upon these pieces will continue to exercise functions of local reflex irritability, however small the pieces may be. If an entire double row of pedicels be divided with a segment and then placed upon its aboral end, it may be seen to right up on its oral end by the successive action of its pedicels, and then proceed to crawl about the floor of the tank. We have therefore to meet the question: Is the action of the ambulacral feet in executing these righting movements of a merely reflex kind, *a*, *b*, and *c* first securing their hold on the tank floor in response to the stimulus supplied by contact, and then by their combined tilting over the globe, till *d*, *e*, and *f* are able to take hold, and so on; *or* does the righting action depend upon nervous co-ordination? Experiments showed that both principles are combined, the action of the pedicels being serial, but also co-ordinated by nervous co-ordination. This conclusion is sustained by the experiment of shaving off the spines and pedicels over the whole of one hemisphere, *i.e.* the half from the equator to the oral pole. When then inverted and forced to use their ambulacral pedicel-rows, the echini reared themselves upon their oral pole, and then, having no more pedicels wherewith to continue the manœuvre, came to rest. This rest was permanent, the aboral pole remaining, if accidents were excluded, upon its equator when it died. The question then here seems to resolve itself into this: Is the mechanism of the pedicels so constructed as to ensure that their serial action shall always take place in the same direction? For if it can be shown that their serial action may take place indifferently in either direction it would follow that the persistent position which the partly shaved echini continue reared upon their oral pole is the expression of some stimulus (such as a sense of gravity) continuously acting upon some central apparatus, and impelling the latter to a continuous, though fruitless, endeavour to co-ordinate the absent pedicels. If the pedicels are able to act serially in either direction, there is no more reason why a partly-shaved echinus should remain permanently reared upon its oral pole than that it should remain permanently inverted upon its aboral pole; and therefore the fact that in the latter position the pedicels bring about an immediate rotation of the animal, while in the former and quite as unnatural position, they hold the animal in persistent stasis—this fact tends to show that the righting movements of the pedicels are something more than serial. Thus the whole question as between the two hypotheses comes to this: to whether the pedicels are able to act serially from the oral to the aboral pole. Observation showed that they are so, for echini spontaneously rear themselves from their normal position at the oral pole, to the position of resting upon their equators. For as additional evidence that the righting movements are also assisted by some centralising influence, is the fact that when the evolution is nearly completed by the pedicel-rows engaged in executing it, the lower pedicels in the other rows are seen strongly protruded and curved downwards, in anticipation of shortly coming into contact with the floor of the tank.

mal nerve-ring has no effect at all upon
e local reflex action of the spines; both
lose round an instrument of stimulation.
ation of the spines is totally and perma-
anisling movements no longer serving to
a source of irritation, but only causing
yrate. This shows that the pentagonal
nsure the function of a nerve-centre.
by the effect of its removal upon the
hese are gravely impaired, though not
n twelve specimens so mutilated con-
selves. These facts, together with the
of echinoderms behaving in all respects
that the nervous system is in function,
both central and peripheral; although
ted on the co-ordination both of the
n oval of the pentagonal ring, proves
naralising function than any other part

rch 30.—Anniversary Meeting.—The
gave his annual address. He con-
ts flourishing condition. At no period
ber of Fellows been so large, while
during the past twelve months had
ural in importance. The research fund
had done much for the progress of
nuclied upon the more important dis-
supposed decomposition of chlorine
ner has been found to be capable of
e solar and stellar evidence of the
accumulated by Mr. Lockyer has not
ance by chemists. Capt. Abney and
red that the organic radicals methyl,
tatic absorption spectra in the infra-red
ayer has succeeded in preparing indigo
ture on the commercial scale is rapidly
y has lost by death ten Fellows, includ-
Stenhouse, Prof. W. H. Miller, and
gstaff medal was presented to Prof.
e College, Leeds, as the Fellow who
mote chemical science by research.—
ent and Treasurer were received and
and Council elected for the ensuing
ensure. Vice-Presidents: F. A. Abel,
Frankland, J. H. Gladstone, A. W.
yon Playfair, A. W. Williamson, A.
J. H. Gilbert, A. V. Harcourt, J. E.
cretaries: W. H. Perkin, H. E. Armstrong, Hugo Müller. Treasurer, W. J.
. Brown. M. Carteighe, H. McLeod,
ds, W. C. Roberts, C. Schorlemmer,
Tidy, W. Thorp, T. E. Thorpe, R.

rch 26.—Prof. Fuller in the chair.—
Wright, author and editor.—On
r on electrostatic induction, especially
of the reduction in the differential
electrophorus. The author's experi-
the-is of induction as enunciated by
suggested the importance of adding
ates of the five-plate inductometer in
e mathematical calculations could not
ld the experimental determination of
y would be doubtful. Dr. Moser
the theory was not absolutely correct
er to get results very approximately
he of the secretaries of the Society,
and Prof. Buckert on the electrical
with a revision of Newton's scale of
s were in continuation of those pub-
877. Their object was to determine
under the action of gravity gave any
s specific resistance, of an approach to
e the radius of molecular attraction,
hod of finding the amount of water
y or evaporated from it. The thick-
mined from their colour by means of
different mirrors on them.—Newton's
1 by observations on Newton's rings,
1000 observations on the rings them-
selves. The thicknesses determined by direct observations on Newton's rings and those in the corrected table rarely differ by 1 per cent., while Newton's scale in parts differs from both by as much as 10 per cent. of the thickness. The films were formed from a solution of oleate of soda in glycerine, with a little nitrate of potash added to increase their electric conductivity. They were blown in a glass case from which the outer air could be excluded. Precautions were taken to keep the air in contact with the films inside the case at a proper humidity. These consisted in placing disks containing the solution at the bottom of the case and suspending within it sheets of blotting-paper, the lower edges of which dipped into the liquid. A hair hygrometer indicated changes in the humidity of the interior. The resistance of the films was measured by piercing them with gold wires, which were connected with the electrodes of a quadrant electrometer. The resistance of the film between the needle was calculated by comparing the deflection caused by the difference of potential of the two wires when a current was passing through the film with that produced by the difference of potential above and below a known resistance placed in the same circuit. The specific resistance of the liquid from which the films were formed was measured by a method identical in principle with the above. The liquid was contained in a glass tube with turned-up ends. Platinum wires were cemented into small holes drilled in the straight part of the tube, and their difference of potential compared with that of two points in the same circuit separated by a known resistance. This method has the great advantage of getting rid of any difficulties connected with polarisation. Test experiments on sulphuric acid proved the method to give results agreeing with those of Kohlrausch, who employed alternating currents and Wheatstone's bridge. The results of the experiments may be summed up as follows:—It is difficult to form a soap film under conditions precluding a slight evaporation or absorption of water, but the more nearly these conditions are attained the more closely does the specific resistance of the film agree with that of the liquid in mass. The films observed under the most favourable conditions obeyed Ohm's law with great accuracy, and much better than the others. The films indicate no approach to a thickness equal to the diameter of molecular attraction. A soap-film may even in an inclosed space readily lose 23 out of 57·7 volumes of water contained in every 100 volumes of the solution, when special precautions are not taken to maintain the surrounding space in a constant hygrometric condition. Prof. Ayrton suggested that in measuring the liquid and film the distance between the electrodes should be varied. Prof. Guthrie pointed out that the results of Prof. Reinold and Kohlrausch agreed with his own in showing that the conductivity of liquids obeyed Ohm's law.

Geological Society, March 23.—Robert Etheridge, F.R.S., president, in the chair.—Rev. Daniel Dutton and Capt. George Ernest A. Ross were elected Fellows of the Society.—The following communications were read:—The Upper Greensands and chloritic marl of the Isle of Wight, by C. Parkinson, F.G.S. In this paper the author described the Upper Greensand as exposed at St. Lawrence and along the Undercliff. At the base of the St. Lawrence Cliff there are hard bands of blue chert from which astaciform Crustacea have been obtained; and quite recently, in a large boulder of the same material lying on the beach, there were found the remains of a Chelonian, referred by Prof. Owen to the family Paludinidæ, and named by him *Trachyaspis hilli*. The presence of these fresh-water organisms was thought to imply a connection with the Wealden continent. The chert-bed, 2 feet thick, was regarded by the author as marking the boundary between the Gault and the Greensand. Above it the author described 56 feet of compact red and yellow sands, of which the first 20 feet are unfossiliferous, the upper 32 feet show traces of organic remains; between them there is a fossiliferous zone 4 feet in thickness, containing *Ammonites inflatus*, *A. auritus*, and species of *Pinna*, *Cucullæa*, *Arca*, and *Trigonia*, and immediately below this a separate band containing an undetermined species of Ammonite. These sands are followed by 38 feet of alternate beds of hard chert and coarse greensand, having at the bottom 6 feet of inferior building-stone surmounted by 5 feet of freestone. The latter contains *Ammonites rostratus*, and the cherts various fossils, chiefly bivalves. *Clathraria Lyelli* also occurs at this level. Above the greensands come 6 feet of chloritic marl: the upper 3½ feet fossiliferous, with a base of hard phosphatic nodules containing crushed specimens of *Pecten asper*; the lower 2½ feet compact, with darker grains and few fossils. The author compared the sections of

this series given by Capt. Ibbetson and Dr. Barrois; his own views closely correspond with those of the latter writer.—On the flow of an ice-sheet, and its connection with glacial phenomena, by Clement Reid, F.G.S. The author considers that the boulder-clays have been formed beneath an ice-sheet, and consequently there must have been formerly a huge mass of ice, which would have to flow 500 miles on a nearly level surface, and then to ascend a gentle slope for nearly another 100 miles. He does not think a great piling up of the ice at the North Pole can be assumed to account for this motion. This he explains by the gradual passage of the earth's heat through the mass of ice, raising the temperature of the whole instead of liquefying the surface-layer. As the heat passes upwards it raises the temperature of a particular layer, causes it to expand, and so to put a strain upon the layer above, and then to rupture it. The broken part spreads out, reunites by regelation, and then, receiving the heat from the layer below, again expands and ruptures the layer next above. Thus the movement is from the base upwards rather than from the surface downwards. The author estimates that the ice-sheet in Norfolk was only about 400 feet thick, because boulder-clay does not appear above that level, but only coarse boulder-gravel; in North Yorkshire it extends up to about 900 feet. The author considers that the shell-bed of Moel Tryfaen were not deposited under water, but thrust up-hill by this advancing ice-sheet.—Soil-cap motion, by R. W. Coppinger, communicated by the the president. The author described numerous cases in Patagonia where the stumps, &c., of trees are to be seen in the marginal waters of the sea and of lakes. These, together with stones and rocks, sometimes simulating perched blocks, he considers to have been brought down by the motion of the soil-cap—a thick spongy mass resting upon rock often worn smooth by the action of ice, and so sliding down the more easily under the influence of vegetation. The appearances are not unlike those due to subsidence; but he point out that all the evidence is in favour of recent upheaval, instead of subsidence.

Victoria (Philosophical) Institute, April 4.—Prof. Balfour Stewart, F.R.S., read a paper on the visible universe, which he described in general terms, and then sought to trace its history back, giving a passing sketch of the views of the theologian on the one hand and the materialist on the other, through its many forms to its first logical origin. A discussion ensued, which was taken part in by several who had been specially invited, the question being treated from the scientific and the metaphysical point of view.

Paris

Academy of Sciences, March 28.—M. Wurtz in the chair.—On account of the death of M. Delesse, the Academy went early into Secret Committee.—The following papers were communicated:—On the heats of formation of diallyl, chloro-compounds, and i aldehyde, by MM. Berthelot and Ogier.—Remarkable case of globular lightning: diffuse flashes near the surface of the ground, by M. Trécul. On August 25, 1880, during a thunderstorm, and in full daylight, he saw a very brilliant body, slightly elongated (say 38 to 40 ctm. long by 25 ctm. broad), and with conical ends, pass from one part of a dark cloud to another; and before disappearing, a small part of its substance fell, *as if having weight*, and gave a luminous vertical track with reddish globules at the sides. It divided in falling, and disappeared a little above the houses. The other phenomenon M. Trécul has often noticed in thunderstorms, viz, a band of feeble light, momentarily illuminating a street and reaching right across it, or only part of the width. The author adds some reflections on the phenomena he described on August 23, 1880.—On the representation of numbers by forms, by M. Poincaré.—On a class of linear differential equations, by M. Halphen.—On the reduction of positive quaternary quadratic forms, by M. Charve.—New researches on the winter egg of phylloxera; its discovery at Montpellier, by M. Mayet. To find the winter egg in Languedoc, he recommends searching on young American vines of the species *Riparia*, and only where galls are observed on the leaves; further, only raising the bark of two or three years (preferably the former).—Attempted application of the principle of Carnot to electro-chemical actions, by M. Chaperon.—On the construction of photophonic selenium receivers, by M. Mercadier. These consist of two strips of brass (1 to 4 or 5m. long) separated by two strips of parchment paper, the whole wound in a close spiral, and held in position by two wooden pieces with screws. The arrangement is heated to the melting-point of selenium and a pencil of selenium passed over the surface. These receivers are continuous, are easily made and repaired, have the same properties as the discontinuous ones, &c. It is possible to give them a very variable resistance, from 8000 to 20000 ohms., without their ceasing to act well. A large number arranged in series or in surface may be placed in the same circuit, and many persons enabled to hear photophonic effects at once. In one of M. Mercadier's arrangements the sounds were heard at 2 or 3 m. distance.—On the causes of distinctness in telephonic transmission, by M. Gaiffe. He notices the disturbing effects of friction of wires with each other, and of vibrations caused by wind or otherwise.—On the preparation and the properties of protochloride of chromium, and of sulphate of protoxide of chromium, by M. Moissan.—On phosphoplatinic combustion, by M. Pomey.—Products of action of hydrochlorate of ammonia on glycerine, by M. Etard.—Irian grafts; pathogeny of cysts and epithelial tumours of the iris, by M. Masse. He has found (with rabbits) that small pieces of the conjunctiva or of skin introduced into the anterior chamber of the eye, through an incision made in the cornea, are pretty easily grafted on the iris. After some time the graft takes the form of a fine small cyst very like the cysts or epithelial tumours which sometimes occur on the human iris after wounds of the cornea. The grafts of skin consist of a thick layer of pavement epithelium, with connective tissue beneath united to that of the iris. In the case of the grafts of conjunctiva a true cystic cavity is developed. Hairs with their follicles may also be grafted on the iris. Rothmund's theory of the cause of cysts and tumours of the eye (pieces of skin, &c., carried through a wound) is supported and verified by these researches.—On the nature and origin of the appearance of old eruptive rocks observed in the region of volcanoes with craters of Puy-de-Dôme, by M. Julien.

Vienna

Imperial Academy of Sciences, March 31.—V. in the chair.—The following papers were read:—H. Wild, the temperatures of the Russian Empire.—Dr. H. Goldschmidt, on the action of molecular silver on carbon chlorides.—Dr. Hocevar, on some experiments made with a Holtz's machine.—R. Andrasch, synthesis of methylated parabanic acid, of methylthioparabanic acid, and of thiocholestrophane.—Dr. Emil Holub and A. v. Pezeln, ornithological results of Holub's voyage in South Africa.—Kachler and Spitzer, on Borneol- and camphocarbonic acid.—Max Groger, on sulphochromates.—Alb. Ott, contribution to the dissociation of tungsten from antimony, silver and iron, with an analysis of a so-called pseudo-meteor.

CONTENTS

The Aryan Village. By Edward B. Tylor, F.R.S. . . .
Nile Gleanings . . . .
Letters to the Editor:—
Improved Arrangement of Scale for Reflecting Instruments.—A Note on Flame-Length.—Lewis T. Wright . . . .
Future Development of Electrical Appliances.—George Ravlei
Prehistoric Europe.—R. H. Tiddeman . . . .
Induction Current from Leyden-jar Discharge.—W. Lan
(*With Diagram*) . . . .
Classification of the Indo-Chinese and Oceanic Races.—A. Keane . . . .
Crabs and Actinia.—Col. H. Stuart Wortley . . . .
Migration of the Wagtail.—N. J. . . . .
Sound of the Aurora.—George F. Bueder . . . .
Earthquake Warnings.—H. M. C. . . . .
On the Earthquakes at Agram in 1880-81. By Prof. Szabo . . . .
The St. Petersburg Dynamite Mine . . . .
Fish-Culture in the United States . . . .
The Paris Observatory (*With Illustrations*) . . . .
Achille Delesse . . . .
Professor Helmholtz's Faraday Lecture . . . .
Notes . . . .
Our Astronomical Column:—
The Variable Stars U Cephei and U Geminorum . . . .
The Comet of 1812 . . . .
Biological Notes:—
The Shining Slave-Maker (*Polyergus lucidus*) . . . .
On the Red Colour of Salt Cod . . . .
Marine Isopods of New England . . . .
Statistics of Disease in Italy . . . .
The Eye and Intensity of Colour . . . .
Insecta Inconspicua . . . .
Geographical Notes . . . .
University and Educational Intelligence . . . .
Scientific Serials . . . .
Societies and Academies . . . .

...IS TO "NATURE."

	£	s.
. . . . .	28	0
. . . . .	14	6
. . . . .	7	6

...ed States, the Continent, and ...tal Union :—

	£	s.
. . . . .	30	6
. . . . .	15	6
. . . . .	8	0

...DVERTISEMENTS.

...2s. 6d. 0s. per Line after.

	£	s.	d.
...er Column	0	18	6
...umn	1	15	0
. . . . .	3	5	0
. . . . .	6	6	0

...s to MACMILLAN & CO.
...ld STREET, STRAND, W.C.

... SOCIETIES.

...NDON
...AY, April 7.
...inute Structure of the Lung of the Newt ...vere Apparatus: Prof. W. Stirling ...ories of Elephants: Prof. T. S. Cobbold, ...ar: Dr. Watt, on "In the Green Calculating ...ophy," 4 to Dollfond Varnishes, by the ...W. A. Herdman ...ervations of Hydra. Parasite by means ...Asexual Agency.—On the Action of Compounds ...Muscles. ...ay.—H. H. Statham ...Y, April 8 ...ression of Radiant Matter into Steam ...

...8 ...AY, April 9. ...Thermal Electrolysis; Dr. J. H. Glad- ...on Hammatite; Rev. H. B. Hawkes ...—Visit to British Museum. ...Y, April 10 ...—Physical Education: H. Ashton ...

...Y, April 11. ...B ...—Kaffirdom and the Irish Pitch ...H. C. Lipper. ...ution, A. J. Wallis ...on Palæolithic Tools of the Valley of ...

...moking: Alfon S. Cile ...Y, April 12. ...—The Ethnological Relations of the ...published Remains in Kaffraria, &c. ...

...—Scientific Committee. ...AY, April 13. ...—On the Distance of the Earth ...ion ...Y, April 14. ...—On the Application of Fluctuating ...ents and other purposes—On Voltage ...Alternators for Strong Currents—On ...Transformation Dynamometer—Indicators ...

...er by Prof. Carey Foster, F.R.S.

...NCE COMPANY.

...1, MALL. ...ESTABLISHED 1807. ...

...may be had at the office, or from any ...

...IPHREYS, Actuary and Secretary

LIGHTNING CONDUCTORS.

Experience, accumulated since the time of Benjamin Franklin, proves conclusively that a Conductor made of Copper of adequate size is the best of all appliances for the protection of every description of building from the destructive effects of lightning.

NEWALL & CO.'S
PATENT COPPER LIGHTNING CONDUCTOR,

As applied in all kinds of Buildings and Shipping in all parts of the world with unvarying success; is the most Trustworthy, most Effective, and also the Cheapest Conductor ever offered to the public.

It is simple in its application, no insulation being required, and it costs only one shilling per foot for the standard size, which ensures safety in any ...stance.

R. S. NEWALL & CO., 109, STRAND, W.C.
26, WATERLOO ROAD, LIVERPOOL.
66, ANDERSTON QUAY, GLASGOW.
MANUFACTORY—GATESHEAD-ON-TYNE.

MICROSCOPIC SPECIALITIES

SECTION LAVA SURFACE FLOW, MOUNT VESUVIUS POLAR. 1s. 6d. post free.
SECTION PALATE of the EAGLE RAY, Opaque and Transparent. 2s. 6d. post free.
Catalogue of 25 Pages free on application to
JOHN T. NORMAN,
195, CITY ROAD, E.C.

SECOND EDITION,
GRIFFIN'S
CHEMICAL HANDICRAFT.
PRICE 4s. 6d. POST FREE.
A CATALOGUE OF CHEMICAL APPARATUS:
ILLUSTRATED, CLASSIFIED, DESCRIPTIVE.
Demy 8vo, 480 pp., illustrated with 1600 Woodcuts.
Most Complete and Cheapest List of Apparatus.
JOHN J. GRIFFIN AND SONS, 22, GARRICK STREET, LONDON, W.C.

NOTICE OF REMOVAL.
JAMES HOW & CO.,
SCIENTIFIC INSTRUMENT MAKERS,
73, FARRINGDON ST., LONDON
(LATE OF 5, NEW BRIDGE ST., AND 2, FOUNTAIN COURT)
HOW'S STUDENT'S MICROSCOPE. HOW'S MICROSCOPE LAMP.
Stock Sections and other Objects for the Microscope.

Liberal Terms to Science Teachers and the Trade.
THOMAS CRAMPTON (formerly of 4, Little Britain, London, E.C.), ELECTRICIAN, OPTICIAN, and PHILOSOPHICAL INSTRUMENT MAKER, Advises, Sells, Sets Metallic Base Patents, Constant Batteries, Indicators, Dial and Fire Alarms, and Automatic Switches, Induction and Medical Coils, a Specialities. Insulated Wires of every description. Microscopic and Optical Materials. Telescopes, Opera Glasses, Microscopes, Aneroid Barometers, and Lime-light Apparatus. Illustrated Catalogue Three Stamps.
THOMAS CRAMPTON & CO., 307, HIGH HOLBORN, LONDON, W.C.
Trade Terms and Card.

R. W. NEEVES,
PHILOSOPHICAL INSTRUMENT
AND
INTENSITY COIL MAKER.
PRICE LIST, FOUR STAMPS.
55, SIDMOUTH STREET, LONDON, W.C.

...PPARATUS AND SCIENTIFIC INSTRUMENTS.
PURE CHEMICALS, &c.
...ORTERS AND MANUFACTURERS.
AUG. BEL & CO.,
...IDEN LANE, COVENT GARDEN, LONDON, W.C.
...paratus as required by the Universities, Colleges, and Schools always ready and kept in stock. Professor Foster's ...recommended by Dr. Voelcker. Description on Application. A Liberal Discount allowed to the Trade.

WESLEY COLLEGE, SHEFFIELD

(*Affiliated to the London University*, 1844.)

Governor and Chaplain, Rev. W. H. DALLINGER, F.R.S. Head Master, H. M. SHERA, Esq., M.A., LL.
Second Master, R. SHINDLER, Esq., M.A. (Lond.).
And Eighteen Assistant Masters and Professors.

The object aimed at in this Institution is a sound and comprehensive mental training. The course of study is fully a... the requirements of the present time and to the prospective wants of the pupils, who, whether in preparation for the U... training for scientific pursuits, or for professional or commercial life, are provided with the most efficient aids.

... BIOLOGY, PHYSICS, and CHEMISTRY, the Modern Languages of Europe, Hebrew and Syriac, Vocal and In... Music, and Drawing, are taught by accomplished Professors.

The Rev. W. H. DALLINGER, F.R.S., has undertaken the Professorship of NATURAL SCIENCE, and gives Lectures and Class Instruction in Practical Zoology, Botany, &c.

Physics and Chemistry are taught by A. H. ALLEN, Esq., F.C.S.

Scholarships are awarded, worth in the aggregate 300*l.* a year.

Prospectuses may be had by application to the GOVERNOR or HEAD MASTER.

W. LADD & CO.,

SCIENTIFIC INSTRUMENT MANUFACTURERS,

(*By Appointment to the Royal Institution of Great Britain*),

11 AND 12, BEAK STREET, REGENT STREET, W.

BIDWELL'S SELENIUM RHEOSTAT. AND OTHER APPARATUS FOR BELL'S PHOTOPHONE

PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3*s.* per oz.

Physical Apparatus of every Description.

ILLUSTRATED CATALOGUE, SIXPENCE.

PATERSON'S NEW CATALOGUE OF PHYSICAL APPARATUS

LANTERN SLIDES for SCIENTIFIC LECTURES. Season 1880–1. Post free 6 Stamps.
Complete Sets of Physical Apparatus for Science Primers and all the Physical Text-books in use in Schools and Colleges.
Siemens and Gramme Dynamo Machines and Lamps for hire.
Schools supplied with Apparatus as per Science and Art Departments' Requirements in the Sections of Light, Heat, Sound, and Electr...
Electric Signals for Houses, Hotels, &c., Colliery Signals, Lightning Conductors. The Gower-Bell Loud-speaking Telephone.

EDWARD PATERSON, Electrical Engineer.

SHOW ROOMS AND STEAM WORKS:—76, LITTLE BRITAIN, E.C. (late 3, Bedford Court, W.C.).

MOLISON'S HARMONOGRAPH; executes the Harmonic Curves in the most perfect manner. 15*s.* and 30*s.*

Illustrated Catalogue of Electrical Apparatus, Part 1, *post free*, 6 *Stamps. Ditto, Electric Signals, Part* 2, 6 ...

In Medium 8vo, price 18*s.* Vol. I.

A TREATISE ON

COMPARATIVE EMBRYOLOGY

By F. M. BALFOUR, M.A., F.R.S., Fellow and Lecturer of Trinity College, Cambridge. In Two Vols. ...

"It is scarcely possible to exaggerate the expressions of gratitude which are due from zoologists to Mr. Balfour for the ... tion of the great task which some three or four years ago he set himself. . . . Zoologists have to be thankful to him for the ... style in which he has carried out his work."—*Nature*.

MACMILLAN AND CO., LONDON.

The MORPHOLOGY of the SKULL. By

W. K. PARKER, F.R.S., Hunterian Professor, Royal College of Surgeons, and G. T. BETTANY, B.Sc., Lecturer on Botany in Guy's Hospital Medical School. Illustrated. Crown 8vo. 10*s.* 6*d.*

MACMILLAN & CO., London.

DRAPER'S INK (DICHROIC).

THE NEW BLACK INK

DIFFERING FROM ANYTHING ELSE EVER PRODUCED.

Writing becomes a pleasure when this Ink is used. It has been adopted by the principal Banks, Public Offices, and Railway Companies throughout Ireland.

It writes almost instantly Full Black. | Flows easily from the Pen.
Does not corrode Steel Pens. | Blotting-paper may be applied at the moment of writing.
Is cleanly to use, and not liable to Blot.

Can be obtained in London, through Messrs. BARCLAY & SONS, Farringdon Street; W. EDWARDS, Old Change; F. NEWBERY & SONS, Newgate Street; WM. MATHER, London and Manchester; J. AUSTIN & Co., Duke Street, Liverpool; and STACY & COOK, Paternoster Row; and to be had of all Stationers.

BEWLEY & DRAPER (Limited), Dublin.

HOLLOWAY'S PILLS

THIS MEDICINE

Is a Certain Cure for all Disorders of the LIVER, STOMACH AND BOWELS. A Great PURIFIER of the BLOOD; a Powerful Invigorator of the System, in cases of WEAKNESS AND DEBILITY, and is unequalled in Female Complaints.

ELECTRICAL AND SCIENTIFIC APPARATUS.

Wholesale Manufacturer of Metallic Base Electric Bells, Electric ... Indicators, and Constant Manganese Batteries, Telephone ... Transmitters, Induction Coils and Vacuum Tubes, Terminals ... and all Materials. Instruments made, repaired, or altered on the ... Illustrated Bell List free. Complete Catalogue Two Stamps. Quotations to the Trade.

HENRY J. DALE, MANUFACTURING ELECTRICIAN and ... 4, Little Britain, London, E.C.

S. C. TISLEY & Co.,

OPTICIANS,

172, BROMPTON ROAD, S...

(Close to South Kensington Museum.)

THE PHONEIDOSCOPE

An Instrument for Observing the Colour-Figures of Liquid Films ... action of Sonorous Vibrations.

Being a visible demonstration of the Vibratory and Molecular M... Telephone Plate.

The PHONEIDOSCOPE, with 3 Discs, Bottle of Solution, ... Pamphlet, &c., in Cardboard Box, 10*s.* 6*d.*

MANUFACTURED AND SOLD WHOLESALE AND RETAIL BY
S. C. TISLEY & CO., 172, BROMPTON ROAD, LONDON.

TELEPHONIC ELECTRICITY. All Materials supplied ... Experimental Purposes.

Price Lists of Electrical and Acoustic Apparatus, with Drawings ... Description of the Harmonograph. Post Free.

With Illustrations and Maps, medium 8vo, 18s.

ISLAND LIFE:

THE PHENOMENA AND CAUSES OF INSULAR FAUNAS AND FLORAS, INCLUDING A REVISION ATTEMPTED SOLUTION OF THE PROBLEM OF GEOLOGICAL CLIMATES. By ALFRED RUSSEL WALLACE, Author of "The Malay Archipelago," "The Geographical Distribution of Animals," &c.

Mr. Wallace discusses in an admirably clear and able manner the questions of geological climate and time . . . such are few of the great problems discussed in this most instructive volume—a volume that ought to interest every thoughtful reader. : its theories are likely to meet with keen criticism from Mr. Wallace's fellow-scientists, his volume ought more than any other ow of to spread among the intelligent reading public a knowledge of and interest in some of the most momentous scientific ems of our time."—*Times.*

'His wonderful grasp of detail, depth of insight, and breadth of view remind one at every turn of Darwin, with whom he the honours of discovery in the theory of natural selection; but beyond this he has a lightness of touch, a beauty of style, a ingenuity in unravelling intricate difficulties which are all his own. . . . 'Island Life' is a work to be accepted almost ut reservation from beginning to end. . . . Whoever reads his book must be charmed with it."—*St. James's Gazette.*

'The work throughout abounds with interest. . . . It may be read with equal pleasure by those who are already acquainted the general principles of distribution and by those who wish for the first time to learn something about modern biological aphy."—*Athenæum.*

'We have said enough to show that Mr. Wallace is led to discuss subjects of great interest to speculative minds. With its rous special maps 'Island Life' ought to prove as interesting as it is instructive."—*Pall Mall Gazette.*

MACMILLAN AND CO., LONDON.

A HANDBOOK OF DOUBLE STARS.

a Catalogue of Twelve Hundred Double Stars, and extensive Lists of Measures. With additional Notes bringing the ures up to 1879. For the use of Amateurs. By EDWARD CROSSLEY, F.R.A.S., JOSEPH GLEDHILL, F.R.A.S., JAMES M. WILSON, M.A., F.R.A.S. With Illustrations. 8vo. 21s.

44 pages 8vo. 1s.

RRECTIONS, TOGETHER WITH NOTES, CRITICISMS, RECENT MEASURES AND DISCOVERIES, &c., &c., TO THE HANDBOOK OF DOUBLE STARS.

THE BIBLIOGRAPHY HAS ALSO BEEN BROUGHT UP TO DATE.

The volume is one which may be expected to find its way to the shelves of most amateurs and students of astronomy."—*Nature.*

This is a truly delightful work, and one which will admirably supply a want. Into the hands of abler, more impartial and taking observers and compilers than the authors' its preparation could not have fallen."—*The Astronomical Register.*

Will be welcomed by all who take an interest in the subject of double stars."—*Acaaemy.*

The names of the authors, noted authorities on the subject treated of, will lead the reader to open this volume with the feeling in it he has a treasure of lore on the knowledge brought to light in the last hundred years respecting the relative motions of cally connected stars, nor will he be disappointed."—*Athenæum.*

One of the most valuable additions to the library of the amateur astronomer that has been made for many years. It is full of mation of perennial interest to the student and the practical observer, and assuredly ought to be upon the table of every single vatory in the United Kingdom, and of all those in other parts of the world where the language in which it is written is igible."—*The English Mechanic.*

The book is well and clearly printed, and we heartily recommend it to our readers as a most valuable contribution to the ture of double-star astronomy."—*The Observatory.*

MACMILLAN AND CO., LONDON.

SCIENTIFIC WORTHIES.

ENGRAVED BY THE LATE C. H. JEENS.

The following is a list of the Portraits that have appeared in the above Series.

MICHAEL FARADAY.
THOMAS HENRY HUXLEY.
CHARLES DARWIN.
JOHN TYNDALL.
GEORGE GABRIEL STOKES.
SIR CHARLES LYELL.
SIR CHARLES WHEATSTONE.
JEAN BAPTISTE ANDRÉ DUMAS.
SIR WYVILLE THOMSON.
SIR WILLIAM THOMSON.
HERMANN L. F. HELMHOLTZ.
SIR JOSEPH DALTON HOOKER.
WILLIAM HARVEY.
SIR GEORGE B. AIRY.
J. LOUIS R. AGASSIZ.
RICHARD OWEN.

of impressions of these, printed on India paper, may be had from the Publishers, price 5s. each, or the Set of 16 Portraits in a Handsome portfolio for £4 5s. carriage paid.

THE PORTFOLIO MAY BE HAD SEPARATELY, PRICE 6s.

NOTE.—ONLY A VERY FEW COMPLETE SETS CAN BE MADE UP.

Cheques and P.O.O.s payable to MACMILLAN & CO.,

FICE OF "NATURE," 29, BEDFORD STREET, STRAND.

Messrs. MACMILLAN & CO.'S PUBLICATIONS

BLACKS, BOERS, and BRITISH: a Three-Corner
PROBLEM. By F. R. STATHAM. Crown 8vo. 6s.

ANTHROPOLOGY: an Introduction to the Study
MAN AND CIVILISATION. By E. B. TYLOR, D.C.L., F.R.S. With numerous Illustra
Crown 8vo. 7s. 6d.

"It is a most attractive and entertaining introduction to the science of anthropology. . . . His writing is clear and
and his arrangement masterly."—*Saturday Review.*

GRAPHICAL DETERMINATION OF FORCES IN ENGINEERI
STRUCTURES. By J. B. CHALMERS, C.E. With Illustrations. 8vo. 24s.

MANUAL OF ANCIENT GEOGRAPHY. From the German of Dr
KIEPERT. Crown 8vo. 5s.

QUESTIONS ON BALFOUR STEWART'S ELEMENTARY LESS
IN PHYSICS. By Prof. THOMAS H. CORE, Owens College, Manchester. 18mo. 2s.

THE COLLECTED WORKS OF FRANCIS SIBSON, M.D. LON
F.R.S., &c. Edited by WILLIAM ORD, M.D. With Illustrations. 4 vols., 8vo. £3 3s.

THROUGH THE RANKS TO A COMMISSION. Crown 8vo. 6s.

"This very interesting and indeed instructive narrative."—*Army and Navy Gazette.*

"The account of the daily routine and duties in camp are plainly written. . . . He has no stirring tales to tell
adventures to enlarge upon; no battles to fight again; no slain to slay; but his book seems to deserve attention
fair and clear account of a career not common in England."—*St. James's Gazette.*

NEW AND REVISED EDITION. VOL. I. OF
THE LIFE OF JOHN MILTON. Narrated in connection with the P
Ecclesiastical, and Literary History of his Time. By DAVID MASSON, M.A., LL.D., Professor of Rhetoric a
Literature in the University of Edinburgh. Vol. I. New and Revised Edition. 8vo. 21s.
Vol. II. 8vo. 16s. Vol. III., 8vo. 18s. Vols. IV. and V., 8vo. 32s. Vol. VI., with Portrait, 8vo. 21s.

NOW READY, VOL. II.
THE METAPHYSICS OF THE SCHOOL. By THOMAS HARPER
In Five Volumes. Vol. II., 8vo. 18s. (Vol. I., 8vo.
"We can only recommend professors, students, and cultured readers of all sorts to study it and to try to
Dublin Review.

MATERIALISM, ANCIENT AND MODERN. By a Late Fellow of
College, Cambridge. Crown 8vo. 2s.

"MACMILLAN'S BIOGRAPHICAL SERIES." NEW VOLUME.
CATHERINE AND CRAUFURD TAIT, WIFE AND SON OF A
BALD CAMPBELL, ARCHBISHOP OF CANTERBURY: a Memoir. Edited, at the request of the Archbi
Rev. W. BENHAM, B.D., Vicar of Marden, and one of the Six Preachers of Canterbury Cathedral. With T
engraved by JEENS. New and Cheaper Edition. Crown 8vo. 6s.

GUIDE TO THE UNPROTECTED. In Every-day Matters relating to I
and Income. By a BANKER'S DAUGHTER. Fifth Edition revised. Extra fcp. 8vo. 3s. 6d.

ENGLISH MEN OF LETTERS. Edited by JOHN MORLEY. New
Crown 8vo. 2s. 6d.
DRYDEN. By GEORGE SAINTSBURY.

NEW NOVEL BY HENRY JAMES, Jun.
WASHINGTON SQUARE: THE PENSION BEAUREPAS: A BI
OF LETTERS. 2 vols. Crown 8vo. 21s.

"In 'Washington Square' Mr. James has struck a new chord and achieved a new success . . . contriving to th
keep us in suspense as to the result . . . make up some of the most amusing pages Mr. James has ever written."—*Ac*

EXERCISES IN ANALYTICAL GEOMETRY. Compiled and arra
J. M. DYER, M.A., Senior Mathematical Master in the Classical Department of Cheltenham College. Crown 8

MACMILLAN AND CO., LONDON, W.C.

Printed by R. CLAY, SONS, AND TAYLOR, at 7 and 8, Bread Street Hill, Queen Victoria Street, in the City of London, and pu
MACMILLAN AND CO., at the Office, 29 and 30 Bedford Street, Covent Garden.—THURSDAY, April 7, 1881.

NATURE

EEKLY ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
Of Nature trusts the mind which builds for aye."—WORDSWORTH

THURSDAY, APRIL 14, 1881 [PRICE SIXPENCE

(the General Post Office.)

(All Rights are Reserved.

TICE.

'URE"

RIL 28, 1881.

. Engraved on Steel by the late

JEENS.

OF

HELM BUNSEN.

this number should be sent to the

D STREET, STRAND.

OSPITAL MEDICAL
HOOL.

BANKMENT, S.E.
ommence on May 3rd. Students enter-
e for the Natural Science Scholarships
owing October.
triculation, Preliminary Scientific, and
al
Scholarships, and all Appointments are
ient.
Private Families in the neighbourhood
upervision, and a Register of Inspected
ses.
y be obtained from the Secretary, Dr.

W. M. ORD, M.D., Dean.

FIRTH COLLEGE,
INT & PRINCIPAL, who shall also
ge in the Mechanical Department of

l respectively the Following Subjects:—
, Political Economy, Moral Science,
ngineering, Geology, Physics,
in which of these Departments they
e, and which of the Subjects in that
e undertake.
ll be £200 per annum with Half the

ointment in event of suitable Candi-

ll particulars concerning Age, Exper-
ons they may have gained together
ffect the decision of the Council. The
erences may be made should be given.
they are asked for,
the 25th day of April next, to

ENSOR DRURY, Registrar.

1881.

uction given in Ana-
Microscopy. Apply to the PRINCIPAL,
Holborn Viaduct, E.C.

BROWNING'S
SELF-LUMINOUS POCKET COMPASSES.

These Compasses are prepared under special arrangement with the Patentees of the Self-Luminous Paint. The dials can be distinctly seen without a light in absolute darkness.

Price, in Gold, with Patent Stop ... ... 55s.
,, in Silver ... ... 28s. 6d.
,, Large Size, Bronzed ... ... 28s. 6d.

TO BE HAD ONLY OF

JOHN BROWNING,
Optical and Physical Instrument Maker to H.M. Government,
&c., &c.,
63, STRAND, LONDON, W.C.

TRAVELLERS' SCIENTIFIC REQUISITES.

ANEROID BAROMETER with ALTITUDE SCALE, THERMOMETER and COMPASS in Flat Pocket Case, various Forms,
£7 7s. and £8 8s.

Price Lists of Instruments free by post.

NEGRETTI & ZAMBRA,
Opticians and Scientific Instrument Makers
TO HER MAJESTY THE QUEEN,
HOLBORN VIADUCT,
45, CORNHILL, & 122 REGENT STREET, LONDON.

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 418, Tollington Road, Holloway, London, N.

BRITISH ASSOCIATION FOR THE ADVANCEMENT OF SCIENCE,

22, ALBEMARLE STREET, LONDON, W.

The NEXT ANNUAL GENERAL MEETING will be held at YORK, commencing on WEDNESDAY, August 31.

PRESIDENT-ELECT.

SIR JOHN LUBBOCK, Bart., M.P., D.C.L., LL.D., F.R.S., F.L.S., F.G.S.

NOTICE TO CONTRIBUTORS OF MEMOIRS.—Authors are reminded that, under an arrangement dating from 1871, the acceptance of Memoirs, and the days on which they are to be read, are now, as far as possible, determined by Organising Committees for the several Sections *before the beginning of the Meeting*. It has therefore become necessary, in order to give an opportunity to the Committees of doing justice to the several Communications, that each Author should prepare beforehand an Abstract of his Memoir, of a length suitable for insertion in the published Transactions of the Association, and the Council request that he will send it, together with the original Memoir, by book-post, on or before August 1, addressed thus:—"General Secretaries, British Association, 22, Albemarle Street, London, W. For Section....." Authors who comply with this request, and whose Papers are accepted, will be furnished *before* the Meeting with printed copies of their Reports or Abstracts. If it should be inconvenient to the Author that his Paper should be read on any particular days, he is requested to send information thereof to the SECRETARIES in a separate note.

Reports on the Progress of Science, and of Researches instructed to individuals or Committees, must be forwarded to the GENERAL SECRETARIES, for presentation to the Organising Committees, accompanied by a statement whether the Author will be present at the Annual Meeting.

No Report, Paper, or Abstract can be inserted in the Reports of the Association unless it is given in before the conclusion of the Meeting.

G. GRIFFITH, Acting Secretary.

ROYAL INSTITUTION OF GREAT BRITAIN,

ALBEMARLE STREET, PICCADILLY, W.

LECTURE ARRANGEMENTS AFTER EASTER, 1881.

Lecture-Hour, 3 o'Clock p.m.

Prof. DEWAR, M.A., F.R.S.—Six Lectures on "The Non-Metallic Elements"; on Tuesdays, April 26 to May 31. One Guinea the Course.

Prof. TYNDALL, D.C.L., F.R.S.—Six Lectures on "Paramagnetism and Diamagnetism;" on Thursdays, April 28 to June 2. One Guinea.

Prof. H. MORLEY.—Three Lectures on "Scotland's Part in English Literature;" on Saturdays, April 30, May 7, 14. One Lecture on "THOMAS CARLYLE;" on Tuesday, June 7. Half-a-Guinea.

E. C. TURNER, Esq., Lector at the University of St. Petersburg.—Five Lectures on "The Great Modern Writers of Russia;" on Saturdays, May 21, 28, June 4. Thursday, June 9, and Saturday, June 11. Half-a-Guinea.

Subscription (to Non-Members) to all the Courses during the Season, Two Guineas.

ELLEN WATSON MEMORIAL FUND.

It has been decided to found a Prize or Scholarship in Mathematics at University College, London, open equally to Men and Women, as a Memorial of the mathematical genius of the late MISS ELLEN WATSON. More than £200 has been already subscribed in sums varying from £1 to £40. Further Subscriptions will be gladly received, and may be paid to the Hon. Secs. of the Fund—Mrs. W. K. Clifford, 26, Colville Road, Bayswater; or Miss A. M. Palmer, 68, Grosvenor Street, London, W.; or to the account of the Ellen Watson Fund, Messrs. Dimsdale & Co., Bankers, Cornhill, London.

THE MASON SCIENCE COLLEGE, BIRMINGHAM.

APPOINTMENT OF ADDITIONAL PROFESSORS.

Applications for the additional Chairs of Physiology—Geology and Mineralogy, Civil and Mechanical Engineering, Latin and Greek, English Language and Literature, and Lectureships in the French and German Languages (see former Advertisements), must be sent in by the 30th instant, addressed to Mr. G. H. MORLEY, Secretary, The Mason Science College, Birmingham.

LIVERPOOL ROYAL INFIRMARY SCHOOL OF MEDICINE.

TWO ENTRANCE SCHOLARSHIPS of £21, for two years, will be awarded in October next to such applicants as have taken the highest position in the Honours Division at either of the Matriculation Examinations of London University of the year.

Apply to the Registrar, Dr. CATON, 18A, Abercromby Square, Liverpool.

ROYAL POLYTECHNIC.—CLASSES for

the Preparation of Students for University Examinations, under the direction of EDWARD B. AVELING, D.Sc., F.L.S. London University Matriculation, 1st and 2nd B.Sc., Preliminary Scientific M.B., Botany, Physiology, Chemistry. All the work practical.

LIVING SPECIMENS FOR THE MICRO

THOMAS BOLTON, NATURALISTS' and MICRO

STUDIO, 57, NEWHALL STREET, BIRMING

T. B. has last week sent to his subscribers a Collection of Fr Rotifers, including *Anuræa aculeata*, *Brachionus* others, with *Pandorina morum* and Diatoms. He has the charis thickly encrusted with tube-dwelling Rotifers, *ringens*, *Limnias ceratophylli*, *Floscularia cornuta*, and Stentors and Hydra, with the curious Vorticellids *Trich* commensal upon them.

Weekly announcements will be made in this place of wh is supplying.

Specimen Tube, One Shilling, post-fr

Twenty-six Tubes in course of Six Months for Subscrip

Price List of Specimens on application, with stamped addres

Portfolio of Drawings, No. 4, One Shilling

LONDON UNIVERSITY, ARMY, SERVICE.

Dr. R. H. JUDE, D.Sc. (Lond.), M.A. (Cantab.), High W Class Natural Science Tripos, late Scholar of Christ's and monstrator of Chemistry at Caius College, Cambridge, with g antes, prepares Gentlemen in all the subjects for the above Ex Natural Science treated both experimentally and theoretic Highest Testimonials and References to present and form few Pupils taught by Correspondence.

119, Cambridge Gardens, Notting Hill, W.

BRITISH MUSEUM.—The Br

MUSEUM (NATURAL HISTORY), Cromwell Road, South will be OPEN to the Public, FREE, on EASTER M 18th of April, and Daily from that date. Hours of Admi British Museum.—EDW. A. BOND, Principal Librarian.

INSTRUCTION IN MATHEMA

Youths or Adults attended at their Residence, on Reas by a M.A. of Cambridge. Unquestionable references Address, by letter, O. P., Post Office, Turnham Green.

SCIENCE CLUB,

This Club is now open for the use of Members. Annual Town Members, £4 4s.; Country Members, £3 3s. A limited number of Members will be admitted without Entr For further information apply to the Honorary Secretary House.

MINERALOGY AND GEOL

VERY FINE SPECIMENS of CRYSTALS of BLACK LINE in ROCK CRYSTAL—MADAGASCAR.

SOME FINE EXAMPLES OF ITACOLUMITE OR FLEXIB STONE—INDIA—IN SLABS 1 FOOT TO 7 FEET 6 INCHES.

BLOWPIPE CASES AND APPARATUS.

COLLECTIONS FOR STUDENTS, from £222. COLLECT BEGINNERS, from 42.

PRIVATE LESSONS AND EVENING CLA

Catalogues free.

SAMUEL HENSO

277 (*Late* 113a), STRAND, LONDON

VALUABLE COLLECTION MINERALS FOR SALE.

JAMES R. GREGORY has now for Sale a very fine Co chiefly of Cornish Minerals, one of the best in Cornwall. Th was commenced forming sixty years ago, and contains mos Minerals of the County, many of which have not been found for It consists of over 4000 Specimens, including a large number of F ments, and is contained in four large well-made Spanish Mahogan two of thirty drawers each, and two of twenty-four Drawers Bookshelves over. For Price, &c., and to inspect the same, app

JAMES R. GREGORY,

88, CHARLOTTE STREET, FITZROY SQUARE

DIAMONDS IN MATRIX.

R. C. NOCKOLD, Diamond and Oriental Stone Cutter and for sale Specimens of the above; also Cut Precious Stones in all Precious Stones valued and bought.

19, FRITH STREET, SOHO, W.

EVERY BOY A GEOLOGIST

Now ready, and highly recommended, complete, price 5s. This admirable little Work and most extraordinary Cabinet of well-selected Natural Specimens, together with other Geologica lessons, and a powerful Lens, are calculated to start a boy think has mastered for himself no ordinary knowledge of the forma Earth's Crust.—THOMAS J. DOWNING, GEOLOGIST, &c., Street, London, E.C.—Catalogues free.

SELENIUM FROM £10 per Kilo

THORITE from £20 per kilogram, is to be had of Dr. S. R. L Stockholm.

DOWMENT OF EARCH."

7th inst. and March 24.

:S of the ROYAL SOCIETY for 9, is a Paper "On the Nature and e Cerastes Poison as Compared with nd other Indian Venomous Snakes; e Nature of the Influence of Naja illary and Amœboid Action, and on ience of In-spiration of Pure Oxygen T. LAUDER BRUNTON, M.D., ER, C.S.I., M.D., &c.

in the title for solution by the : as the phrase: "the Nature and Poison" and "the Nature of the hey are evidently framed not so iety at what the investigator was admit of any amount of definition ight thing upon them. The results st two pages. "We have already s] "our belief that death is caused Hydrophis poison—1st, through its d nerve centres, especially on the of respiration; or, 2nd, in some eally in systole, of cardiac action, ion on the cardiac ganglia; 3rd, by previous causes; 4th, by a septic ature, and which [*sic*] being more its bearings, the details were not cussion here." Observe that Society the Greek and Latin are of sums up the thanatological results cruelty in previous experiments. o the belief that death is caused— indicating stoppage of breath; 2nd, f action, probably owing to some n of the two; 4th, by a septic conssion here. The words ending in great scientific weight. Next come s detailed in 17 pages. "There is is caused in the same way by the it though the actual cause of death course the reader grants that this entleman], "the phenomena which for in some degree." Here is the phenomena and results; for in a Society they are sure to be indi- e "some degree" of difference? information to be added to that nts recently performed in Calcutta rs of the committee appointed by can find, except that vague thing, But we observe (and in this our with those of Weir Mitchell) that both local and general hæmorrhage d of the colouring matter of the g by either cobra or viper." . . "this blood of the dead animal"— d itself we have observed that it eath, generally, if not invariably, as papers] "to be the case" . . . ntributed to the *Daboia*-virus." To : "In Dr. Fayrer's Indian experi- dead from *Daboia*-poison nearly leath." Then follows an account ta committee about fluidity and introduction here finishes, and the

continued.]

TOTAL ABOLITION AND ION OF VIVISECTION.

tary and Treasurer,
GEORGE K. JESSE, Esq.,
ry, near Macclesfield, Cheshire.

THE CHEMICAL NEWS AND JOURNAL OF PHYSICAL SCIENCE.

EDITED BY W. CROOKES, F.R.S., &c.

Published every Friday. Price 4*d*.

No. 1116 (April 14th, 1882) contains—Coefficients of Expansion of the Dioxide of Lead, and of an Alloy of Iodide of Lead with Iodide of Silver, by G. F. Rodwell, F.R.A.S., F.C.S.—Detection of Aniline Colours in Red Wines by Browning's Micro-spectroscope, by H. Mungeer.—Examination of Fat in Milk, by W. M. Hamlet, F.C.S.—Methods for Judging of the Wholesomeness of Drinking Water, by Reuben Haines.—Report on the London Water Supply.—Proceedings of Societies.—Notices of Books.—Correspondence.—Chemical Notices from Foreign Sources.—Notes and Queries, &c., &c.

London: Bury Court, Leadenhall Street, E.C.

THE QUARTERLY REVIEW, No. 302,

Will be PUBLISHED on TUESDAY, APRIL 25.

Contents.

I. THE REVOLUTIONARY PARTY.
II. LITERARY LIFE OF LORD BOLINGBROKE.
III. THE SPEAKER'S COMMENTARY ON THE NEW TESTAMENT.
IV. THOMAS CARLYLE AND HIS REMINISCENCES.
V. RUSSIAN LANDLAWS AND PEASANT PROPRIETORS.
VI. SIR ANTHONY PANIZZI.
VII. ENDOWMENTS OF THE CHURCH IN 1832 AND 1882.
VIII. MINISTERIAL EMBARRASSMENTS.

JOHN MURRAY, Albemarle Street.

THE EDINBURGH REVIEW, No. 314,

IS JUST PUBLISHED.

Contents.

I. THE OXFORD MOVEMENT.
II. EGYPT BOUND AND UNBOUND.
III. THE SONG OF ROLAND.
IV. THE PUBLIC LIFE OF MR. HERRIES.
V. RIVER FLOODS.
VI. THE PELLAGRA IN ITALY.
VII. REMINISCENCES OF THOMAS CARLYLE.
VIII. DARWIN ON THE MOVEMENTS OF PLANTS.
IX. SCHLIEMANN'S TROJA.
X. LOCAL DEBTS AND GOVERNMENT LOANS.

London: LONGMANS & CO.; Edinburgh: A. & C. BLACK.

Now ready, Price 6*s*., Vol. XV., Part III., April, 1882.

THE JOURNAL OF ANATOMY AND PHYSIOLOGY, NORMAL AND PATHOLOGICAL,

CONDUCTED BY

Profs. HUMPHRY, TURNER, M'KENDRICK, & Dr. CREIGHTON.

Contents.

1. Bones, Articulations, and Muscles of Rudimentary Hind-Limb of Greenland Right Whale. By J. Struthers, M.D.
2. Specializing Apparatus of Cuttlefish's Gigma. By A. C. Haddon, B.A. (Plate XX.)
3. Stereum as Index of Sex and Age. By T. Dwight, M.D.
4. Mechanism of Costal Respiration. By J. M. Hobson, M.D. (With Figures.)
5. Membrana Tympani of Mammary Gland. By C. W. M. Moullin, M.D. (With Figures.)
6. Epidermal Tactile Sensory Organs of Mammalia. By W. Stirling, M.D.
7. Comparative Anatomy of Integument of the Mammalian Urinary Bladder. By G. Hoggan, M.D., and F. E. Hoggan, M.D. (Plate XXI.)
8. Notes on Dissection of Case of Epispadias. By R. J. Anderson, M.D.
9. Morphology of Muscles of Tongue and Pharynx. By R. J. Anderson, M.D.
10. The so-called Myxœdematoid Processing and Separation in Hind-Limb of certain Mammals. By A. B. Young, M.B.
11. Contribution to Pathological Anatomy of Pneumatic Dentine (*Chalicosis pulmonum*). By L. Harris. (Plate XXII.)
12. Histology of some Rarer Forms of Malignant Bone Tumours. By R. Maguire.
13. Morbid Histology of Liver in Acute Yellow Atrophy. By Prof. J. Dewsbury.
14. Relationship between Muscle and its Contraction. By J. T. Cash, M.D. (With Figures.)
15. Anatomical Notices.

MACMILLAN & CO., London and Cambridge.

In unserem Verlage erscheint:

DER NATURFORSCHER.

Wochenblatt zur Verbreitung der Fortschritte in den Naturwissenschaften.

Herausgegeben von Dr. WILHELM SKLLERS.

Wochentlich 1—1½ Bgn. in 4°.

Preis vierteljährlich 4 Mk.

Die rasonable ihren XIV. Jahrgang beginnende Zeitschrift hat bei Allen, welche sich mit Naturwissenschaften beschäftigen, grossen Beifall gefunden. Probenummern sind durch jede Buchhandlung zu erhalten.

Berlin, S.W., 77, Charlottenstr.

FERD. DÜMMLER'S VERLAGSBUCHHANDLUNG.
(Harrwitz & Gossmann.)

NEW WORK ON GARDENING.

Next Week will be published, in crown 8vo, cloth, price 6s. 6d.

EPITOME OF GARDENIN

By THOMAS MOORE, F.L.S., F.R.H.S.,

Curator of the Botanic Garden, Chelsea.

With an Introductory Chapter on the Principles of Horticulture by MAXWELL T. MASTERS, M.D.,

Illustrated with upwards of Two Hundred Wood Engravings.

Edinburgh: ADAM & CHARLES BLACK.

WESLEY COLLEGE, SHEFFIE

(*Affiliated to the London University*, 1844.)

Governor and Chaplain, Rev. W. H. DALLINGER, F.R.S. Head Master, H. M. SHERA, Esq., M.A

Second Master, R. SHINDLER, Esq., M.A. (Lond.).

And Eighteen Assistant Masters and Professors.

The object aimed at in this Institution is a sound and comprehensive mental training. The course of study is the requirements of the present time and to the prospective wants of the pupils, who, whether in preparation for training for scientific pursuits, or for professional or commercial life, are provided with the most efficient aids.

BIOLOGY, PHYSICS, and CHEMISTRY, the Modern Languages of Europe, Hebrew and Syriac, Vocal Music, and Drawing, are taught by accomplished Professors.

The Rev. W. H. DALLINGER, F.R.S., has undertaken the Professorship of NATURAL SCIENCE, an Lectures and Class Instruction in Practical Zoology, Botany, &c.

Physics and Chemistry are taught by A. H. ALLEN, Esq., F.C.S.

Scholarships are awarded, worth in the aggregate 300*l.* a year.

Prospectuses may be had by application to the GOVERNOR or HEAD MASTER.

With 119 Engravings and 5 Maps of the Stars.

POPULAR ASTRONOMY.

BY

PROFESSOR S. NEWCOMB, LL.D.

8vo, cloth, price 18*s.*

"As affording a thoroughly reliable foundation for more advanced reading, Prof Newcomb's 'Popular Astronomy' is deserving of strong recommendation."—*Nature.*

"When we take up a book written by one of the foremost astronomers, mathematically and practically, of the day, we need not fear that, however popular, it will be inexact in its language or evasive in its descriptions. Nor are we disappointed in the book before us. Throughout the whole of it we are struck by the total absence of the defects so common in popular writings. . . . It is unlike anything else of its kind, and will be of more use in circulating a knowledge of astronomy than nine-tenths of the books which have appeared on this subject of late years."—*Saturday Review.*

MACMILLAN & CO., LONDON.

This Day is Published.

ON THE STRUCTURE AND AFFINITIES OF

THE GENUS MONTICULIPORA

AND ITS SUB-GENERA.

WITH CRITICAL DESCRIPTIONS OF ILLUSTRATIVE SPECIES.

By H. ALLEYNE NICHOLSON,

M.D., D.Sc., F.R.S.E., F.L.S., Professor of Natural History in the University of St. Andrews.

Author of "A Manual of Palæontology," &c., &c.

Illustrated with numerous Engravings on Wood and Lithographed Plates.

In One Volume, large 8vo, price 18*s.*

WILLIAM BLACKWOOD & SONS, Edinburgh and London.

Just issued, price 5*s.*, handsomely bound in cloth, with Portrait of Author,

MIND IN ANIMALS. By Prof. Ludwig BÜCHNER. Translated by ANNIE BESANT.

"It is a decidedly valuable addition to the literature of Comparative Psychology."—*Nature.*

London: FREETHOUGHT PUBLISHING COMPANY, 28, Stonecutter Street, E.C.

Just Published, crown 8vo, 5*s.*

ACCENTED FOUR-FIGURE LOGARITHMS and other TABLES, for Purposes both of Ordinary and of Trigonometrical Calculations, and for the Correction of Altitudes and Lunar Distances. Arranged and Accented by LOWIS D'A. JACKSON, Author of "Canal and Culvert Tables," "Hydraulic Manual," &c.

London: WM. H. ALLEN & CO., 13, Waterloo Place.

TEXT-BOOKS OF SCIENCE.

In small 8vo, with 372 Figures on Wood, price

SYSTEMATIC MINERALO

HILARY BAUERMAN, F.G.S., Associate of th

Mines. (Forming one of Messrs. LONGMANS & Co

Books of Science, Mechanical and Physical, Edited

FIELD, F.R.S.)

London: LONGMANS & CO.

THE BRONZE AGE OF GREAT BRIT

New ready, in 8vo, with 540 Illustrations engraved on

cloth,

The BRONZE IMPLEMENT

and ORNAMENTS of GREAT BRITAIN and

JOHN EVANS, D.C.L., L.L.D., F.R.S., &c., Auth

Stone Implements, Weapons, and Ornaments of Grea

London: LONGMANS & CO.

NEW WORK BY LIONEL S. BEAL

Now ready, pp. 230, *demy* 8vo, 5

SLIGHT AILMEN

THEIR NATURE AND TREATMEN

By LIONEL S. BEALE, M.B., F.R.S

Professor of the Principles and Practice of Medicine in

London.

J. & A. CHURCHILL, New Burlington S

New Edition, very much enlarged, 212

HOW TO WORK WIT

MICROSCOPE.

By LIONEL S. BEALE, F.R.S.,

President of the Royal Microscopical Soci

THE FIFTH EDITION,

Strongly bound and enlarged to 530 Pages, with 100 Plat

are Coloured, is now ready.

HARRISON & SONS, Pall Mall.

GEOLOGY AND MINERAL

In the Preface to the "Student's Elements of

Lyell he says, "As it is impossible to enable

recognise rocks and minerals at sight by aid of

tions or figures, he will do well to obtain a well

lection of specimens." These can be had fr

WRIGHT, MINERALOGIST, 90, Great Russell S

50 Specimens in Cabinet ... ...

100 " " ... ...

200 " " ... ...

&c., &c. ... ...

More extensive Collections from 50 to 2000 Ge

THURSDAY, APRIL 14, 1881

THE NEW MUSEUM OF NATURAL HISTORY

THE great terra-cotta building facing Cromwell Road, South Kensington, and occupying the site of the old 1862 Exhibition, about which for the past twelve months public curiosity has been raised, is about to draw up its blinds, and to offer a part of its extensive galleries for inspection on Easter Monday.

It is no secret that for thirty years past the accommodation in the British Museum, Great Russell Street, Bloomsbury, "both for man and beast," had become too restricted, and the necessity for a larger building was keenly felt. As usually happens in such cases, the most adventurous and energetic officer was the first to obtain for his department what he required, namely, *more room*.

Sir A. Panizzi (then Keeper of Printed Books) projected, shortly after the 1851 Exhibition, his scheme for a great central Reading-room and Library, and some five years after witnessed its completion. Some years later on, the Department of Antiquities, represented by Mr. C. T. Newton, C.B., also obtained an addition to its galleries on the western side, and still more recently on the southern side, next the great Entrance Hall.

Great praise is due to Mr. Bond, the present Principal Librarian, for putting an end to the use made of the fine colonnade in front of the British Museum, which for twenty-five years was blocked by antiquities covered in with a row of extremely unsightly and incongruous wood and glass sheds. These are now happily removed. The Department of Prints and Drawings lacking a gallery, obtained possession of the "King's Library" floor on the east side for an exhibition space; and even the conservative Coin Department likewise laid out for the public a few show-cases here of coins and medals.

But, like the clothes of the rising son, in the old caricature, the collections everywhere had outgrown their receptacle, and none more so than the departments of Natural History. Scientific men were however not unanimous, and a fierce controversy was carried on in 1858-59 as to the relative merits of enlargement on the old site, or dismemberment. Finally, after a Committee of the House of Commons had taken evidence upon the subject, the removal of the Natural History Collections was decided upon by Government.

But the death of the Prince Consort, the delay of the House of Commons to vote the necessary funds, the retirement of Sir A. Panizzi from the post of Principal Librarian, the discussion of rival plans, the inevitable delays about the completion of any Government building, caused twenty years to pass before the plans of the chosen architect, Mr. Alfred Waterhouse, were realised in a solid and material form.

Midsummer, 1880, barely sufficed to enable the Office of Works to certify to the fulfilment of the Contractor's work and to hand over the building to the Trustees ere collections began to be moved in.

Nine months only have elapsed, and already three Departments, viz. Botany, Mineralogy, and Geology, have transferred their entire collections from the old to the new building. But less than half the cases for the entire building have yet been supplied, and everywhere the labour of completing the structure as well as fixing cases and fittings is being busily carried on. Under these circumstances it seems not improbable that two years may elapse before the Zoological Collections will be removed and housed in their new quarters.

Let us now take a glance at what Mr. Sala styles "this Temple of Nature." The architectural character of the new building may be termed "Decorated Norman," but it is in many respects unique, especially as regards the treatment of its details. The first, or "ground-floor," is above the road, and the entrance is approached by a broad flight of steps and by a sloping carriage-drive. The entire structure is of brick cased with terra cotta, the doorways and the windows being ornamented with columns designed from natural history objects, chiefly from plants. Reproductions of various animals are also introduced. The main part of the building has a tower at each end, and there are also two central towers rising on either side of the entrance. The south front of the building is about 650 feet in length, running due east and west, and is three storeys high, in addition to the basement, which is above the level of the garden in which the building stands.

The Central Hall or "Index Museum" runs from south to north; it is 150 feet long, 97 feet wide, and about 60 feet high; along its two sides are twelve arched recesses. At the north end is a wide and handsome staircase which branches off right and left to the open corridors or side aisles on either hand upon the first floor. This Central Hall is more richly decorated than any part of the building. The floor of mosaic work, where Italian marble is employed, has been skilfully laid by Italian workmen. The side aisles or corridors look out into the Central Hall by an open balustrade surmounted by large arches, each containing three smaller ones, the centre one being much higher than the others. The pillars supporting these are ornamented with a nearly natural treatment of *Lepidodendron*; in some few cases animals, monkeys, birds, &c., are introduced. The decoration of the ceiling is very effective. A double row of panels runs along the central line, and on either side of this, between the iron girders and following the curve of the roof, are panels in groups of six; these are ornamented with representations of different species of trees, shrubs, and flowering-plants treated somewhat conventionally. That portion of the ceiling over the main body of the hall is decorated with trees, each of which occupies six panels, as they can be most easily seen from the floor and need bold treatment. At the south end, where the ceiling is over a staircase and landing leading from the first to the second floor, each panel contains but one species: the eye being nearer to the ceiling greater detail has been introduced. The effect of the whole is very fine, and as the hall is at present without any cases or specimens, it has the general appearance of a cathedral. This idea is further heightened by the introduction of a triforium, though this has been added merely for effect, the passages being interrupted.

Beyond the Index Museum is a smaller and less lofty hall quite divided from it, save by two arched entrances, 97 feet by 70 feet, intended to hold the British Zoological Collection. It is surrounded by arched recesses similar to those in the Index Museum. In this hall the decora-

tion of the ceiling is also botanical, but all the species selected are of British plants. Underneath the staircases and in the recesses a plain light colour is introduced, relieved with gilding. The decorations of the saloons or galleries are much simpler. The columns throughout are of terra cotta, ornamented with natural history objects.

The other parts of the building consist of series of galleries running north from the front or main building, but only one storey above the basement. The rooms on each floor, at the end of the long front galleries and under the two end towers, are called pavilions. The main or front galleries facing Cromwell Road are lighted by windows north and south. The Central Hall or Index Museum, the Hall for British Zoology, and all the other galleries of one storey high running north, are lighted by skylights. The Index Museum has however, in addition to its roof-lights, windows in the corridors on either side.

The distribution of the space available is as follows:—The long galleries to east of the entrance on the ground-floor, and all the galleries from it, running north, are devoted to Geology and Palæontology. The first floor above the Geological Gallery is devoted to Mineralogy, and the floor above this to Botany. The whole of the galleries on the west side of the building are given to Zoology. The Index Museum, according to Prof. Owen, is designed to present to the public, in a series of twelve recesses, typical examples of all the collections—in fact, an epitome of the whole animal, vegetable, and mineral kingdoms. Prof. Owen further desires to show the marvels of nature and objects of special interest, as exemplifying size, &c., such as whales, basking sharks, &c. These are to occupy the centre of this great hall. Passing to the right from the Index Museum (on the ground floor) we enter the South-East Gallery of the Geological Department (233 feet in length by 50 feet in width, and lighted by windows on either side), at the east end of which is the Pavilion, a room 60 feet by 40 feet. These two galleries are entirely devoted to the exhibition of the fossil Mammalia and Birds, and are provided with pier-cases and table-cases. The larger objects are arranged down the centre of the floor.

The cases on the left hand are nearly all occupied with the remains of *Proboscidea*. Commencing with the *Deinotherium* from Epplesheim, with its tusk-like incisors in the lower jaw, we pass to the *Mastodons*, in which, as a rule, the tusks are developed in the upper jaw and not in the lower. But to this there are exceptions; one American Mastodon having immature tusks in the lower jaw, and the *Mastodon augustidens*, from Sansau in France, having tusks in both the upper and the lower jaw.

Nearest the entrance door, in the centre of the gallery, is placed the entire skeleton of the great American mastodon from Ohio, which must have been considerably larger in bulk than that of any existing elephant; on the same stand is placed the head of a young Mastodon from New Jersey, and in front of it the skull and lower jaw of the South American Mastodon from Chili. It is interesting to notice that both the mastodon and elephant had overspread the North and South American continents in Tertiary times, and they were equally widely distributed over the European and Asiatic continents; their modern representatives however are confined, the one to the continent of Africa, the other to India, Ceylon, &c. The tusks of some of the old fossil elephants were of enorm proportions: witness the head of *Elephas ganesa* from Siwalik Hills, India, and that of the mammoth (*Elep primigenius*) from the valley of the Thames, near Lon Large numbers of elephant remains have been dredg up year by year for the past sixty years off the Dogg Bank and the Norfolk coast, affording good eviden that in comparatively modern times the North Se was a great valley watered by the Rhine, Moselle & giving pasturage to vast herds of deer, bison, oxen, a elephants; where also the rhinoceros and the hip potamus found a pleasant home. A goodly series of remains of these animals from British and Continen localities may be seen in this gallery, and also abundan evidence of the old Siberian mammoth and rhinocer both of which have been met with "in the flesh," frozen solid in mud and ice. Here are also exhibited an in teresting series of the "pigmy elephant" from Ma brought home by Admiral Spratt, R.N., and Prof. Le Adams. By far the larger collection of elephant rema are those from the Siwalik Hills, India, obtained by C Sir Proby T. Cautley and described by Dr. Hugh Falcon F.R.S. The "gigantic Irish deer" (*Megaceros Hiberni* forms a prominent and striking object in the centre of the gallery, with its branching antlers 10 feet across, a ready prey for its contemporary, the "sabre-toothed tiger (*Machairodus latidens*), remains of both animals have been found together in Kent's Cavern, Torquay.

Passing by the cases of carnivora, of thick-skinned animals, and of ruminants, our attention is next arrested by the great bandless armadillo from South Americ (*Glyptodon*), whose carapace is bigger than a hogshe and which measured nearly 12 feet from its head to the tip of its armour-plated tail.

Another of these extinct Edentates from the La Plat the *Megatherium Americanum*, stands in the centre of the floor of the Pavilion. This colossal "ground-sloth measured 18 feet in length, its bones being more massive than those of an elephant. It displays in every part of its framework enormous strength and weight combined sufficient to break down or uproot the trees, upon the leaves and succulent branches of which it fed, like its pigmy modern congener *Bradypus tridactylus*, which leads an arboreal existence, climbing from bough to bough in the Brazilian forests.

The extinct Marsupial fauna of the great island conti nent of Australia is here well represented by the hu *Diprotodon*, the *Nototherium*, and the anomalous *Thy coleo*. Of the Wombat family only a small living repre sentative is known, of burrowing habits, found in Tas mania; formerly they were abundant on the contine of Australia, varying in size from a marmot to that of tapir. The largest of these are called *Phascolo magnus* and *P. gigas*.

The collection of remains of the great extinct wingless birds of New Zealand forms a very interesting feature this gallery. The tallest skeleton measures 12 feet in height, and the smallest not more than 3 feet.

Madagascar had also its extinct wingless birds, simi to those of New Zealand. Eggs of both the *Dinor* and the *Æpyornis* may here be seen, one of the latter having a capacity of two gallons.

The rarest of all avian fossils is still the *Archæop*

ic stone quarries of Solen-
ncredulous a second speci-
ned, and is preserved in the
ian affinities are well shown
of twenty vertebræ and its
fore-limb (or wing?). The
is too obscure to give evi-
d jaws are clearly seen in
nal specimen described by

south-east gallery is the
length and 21 feet wide,
entirely occupied with the
Ichthyosauria and *Plesio-*
the old Liassic seas of
s of which have even been
ic regions and from New
long-necked Plesiosaurs
14 feet across its extended
osaur was probably even
rth side are displayed the
rds, *Dinosauria*, of which
most familiar example. A
f the *Omosaurus* from the
Wilts, the femur of which
and the humerus nearly
road; they were probably
n their habits, but their
ssion on the land.

iurian remains are to be
lo not know the teeth of
we are unable to speak
ut it is certain that from
ups have existed side by
dentition and the other
osaurus of the Trias of
and *Cyndracon* from the
he Stonesfield Slate and
whilst the *Iguanodon*,
and the South African
urus were all vegetable-
Omosaurus), *Hylæosaurus*,
ect dental evidence. No
at the present day, the
and the minority were

ted the flying lizards of
hich have been found in
hofen and a few in our
k, and Greensand.
be trusted, some of the
Kent give evidence of a
xpanse of wings of from

eat horned lizard (*Megal-*
length, with nine horn-
l an armour-plated tail

h Africa form a singular
ent life forms long since
l in Prof. Owen's groups
.
have representatives of

both the marine turtles, the fresh-water *Trionyx* and *Emys*, and the gigantic and lesser land-tortoises. Of the first of these are the remains of the great *Chelone Hoffmanni* from Maestricht, and the *Chelone gigas* from the London Clay of Sheppey, larger by far than the "logger-head" turtle of the present day. Of the last (land-tortoises) may be mentioned the *Colossochelys atlas* from the Siwalik Hills, which out-rivals the *Glyptodon* in bulk.

Three wide and four narrow galleries built at right angles to the Reptile Gallery, each 137 feet in length, the former being 40 feet and the latter 20 feet in width, are placed alternately, running due north and south, and lighted from above. These fine rooms afford ample accommodation for the fossil fishes, all the classes of the Invertebrata (mollusca, brachiopoda, bryozoa, insecta, myriopoda, arachnida, crustacea, annelida, echinoder-mata, corals, foraminifera, sponges, and plants). These long galleries, or annexes, and the ones corresponding with them on the western side, are built upon the plan recommended by the Royal Commission of 1874. But the wall-cases are all constructed to open in front, *not at the back* of the case, as suggested. They are however the best-lighted galleries in the whole building, and best suited for museum purposes. Two of these large gal-leries are not yet ready for occupation, and the third is under arrangement; the narrow galleries give space for a library, special reference collections, a stratigraphical series, and working-rooms for students.

In the basement are twelve workshops, studies, and store-rooms devoted to Geology, ten studies, work-rooms, and laboratories to Mineralogy, and three to Botany.

The Mineralogical Gallery, on the first floor, which corresponds with the South-East Gallery and Pavilion in extent, is also lighted by windows on either hand; it has seven wall-cases, two at each end of the long gallery and three in the Pavilion, the collection being mainly contained in forty-eight large table-cases.

These table-cases form a long row on either hand, com-mencing at the entrance of the gallery, the odd numbers being on the left hand and the even on the right. Each of the first forty cases nearly equals in capacity two of the cases in the old mineral gallery; we have therefore a much more magnificent display than could have been attempted formerly, when the minerals and fossils were all crowded together in the same gallery.

The collections of naturally and artificially-prepared crystals occupy two large cases in the Pavilion, whilst two of similar construction are filled with meteorites. The great Cranbourne Meteorite and that from Mexico occupy special cases on the east side. In the wall-cases are arranged the extensive collection of rocks, two cases being devoted to polished marbles.

The general plan pursued in the arrangement remains the same as in the old Museum gallery, so that by using boxes corresponding to one quarter of a table-case, the minerals were transported from the old to the new build-ing and re-arranged in an incredibly short space of time, and with the exception of the Pavilion and the wall-cases have long been ready for exhibition.

In the Botanical Gallery the glazed cases for the exhi-bition of specimens project from the wall into the room like square shop-fronts, having three plate-glass sides. The whole of the glass is permanently fixed, except one

division forming the door. A "cell" inside, inclosed by curtains, gives access to the specimens; by this contrivance it is hoped that the dust will be excluded to a great extent.

Accommodation for large specimens, as, for example, portions of stems and sections of various kinds of wood, such as oak, walnut, pine, cedar, and other dicotyledons, and trunks of palms, cycads, tree-ferns, bamboos, and other striking examples of the vegetable kingdom, is provided for by three tall metal and glass cases 14 feet high, occupying the floor-space in the centre of the gallery.

One-half of the main gallery is partitioned off from the public room, and fitted up with cabinets for the reception of the *Herbarium*, the nucleus of which was obtained by Sir Joseph Banks and Solander in their voyage round the world with Captain Cook. This first series of cabinets is entirely occupied with the flowering plants, which are all fastened on single sheets of paper. The Pavilion contains similar cabinets for the reception of the British plants and Filicinæ, whilst the room above in the tower is intended for the Cryptogamia. Down the centre of the large room are cabinets fitted to receive the great collection of fruits and seeds, each being placed near its appropriate family in the Herbarium on either side. These inner rooms, with the valuable library attached to them, are of course only available for purposes of study, but are always accessible to the botanical student and worker.

On the south-west side of the Index Museum, the gallery on the second floor which corresponds with that appropriated to Botany is designed to contain the great collection of Recent Osteology; that on the first floor is to be devoted to stuffed animals, and the front ground-floor gallery to birds. The eight galleries in rear of the main building on the west side will be appropriated to the Reptilia, Fishes, and Invertebrata. The collections preserved in spirits are to be placed in a special building at the north end of these galleries. The basement on the west side contains sixteen studies and work-rooms and a large open space well fitted for workshops and stores.

The Assistant-Secretary (Mr. J. T. Taylor) is provided with offices adjoining the Board Room on the first floor above the British Zoological Hall. The Superintendent, Prof. Owen, C.B., and the Keepers of Geology (Dr. H. Woodward, F.R.S.), of Mineralogy (Mr. L. Fletcher, M.A., F.G.S.), and of Botany (Mr. W. Carruthers, F.R.S.), have each a study in the central towers on either side the entrance.

There are a few scientific men who still strongly protest against the removal of the Natural History Collections from the old to the new building, on the ground that the locality is inconveniently far west, and that they are thereby precluded from using the Collections so freely as heretofore. One of the strong grounds for protesting against the removal has been the serious inconvenience arising from the separation of the collections from the great National Library. This injury will however be gradually removed by the formation of a new Natural History Library in the present building, a vote for which has been already taken.

The comparatively small band of scientific men who use the Natural History Museum for purposes of special work and study, would always do so wherever the collections happened to be located.

So too the holiday-makers, who come to the Mus merely to be amused, will as willingly travel to S Kensington as to the Regent's Park Zoological Gard or to the Crystal Palace.

Undoubtedly the highest aim and use of our n National Natural Historical Collections should b impart instruction to the young and rising genera and afford every facility for the advancement of scientific students, and the question whether they are conveniently placed is mainly for them to answer. the future South Kensington is to become a great ce of scientific instruction, then, and not otherwise. Natural History Collections have been placed in th most suitable position.

We cannot conclude this hasty notice without say that the old restrictions as to days of admission hav been swept away, and the collections will from and a the 18th be open daily to the public, save on Sun Christmas Day, and Good Friday, and other public days, &c.; good and cheap guide-books are also t ready for the 18th.

For this and other concessions the public are m indebted to the untiring energy and determination of present principal Librarian, Mr. Edward A. Bond, C who has also been the means of introducing many nec sary and useful reforms into the old building; not the le being the electric light, which it may be hoped will ex cast its beams over the collections in the Natural His Museum, Cromwell Road, South Kensington.

TEXT-BOOK OF MECHANICS

A Text-Book of Elementary Mechanics, for the Colleges and Schools. By Edward S. Dana, Assis Professor of Natural Philosophy in Yale College. (N York: John Wiley and Sons, 1881.)

THIS is a small-sized book of 290 pages printed fairly clear type, and bound in an unpleas looking cover, and we learn from the preface that has been prepared to meet the special wants of Yale College instruction. An endeavour has been mad dwell more fully than usual on the principles of the s ject, at the same time illustrating these principles in practical bearings by descriptions of various machi and appliances, while no mathematical knowledge beyo the rudiments of algebra and trigonometry is requi From this it may be presumed that the book is intend for a very elementary class of students, at a lower st if possible, than "Poll" men at Cambridge, or else it aims at assisting self-education by supplying the pl of a tutor. An undoubtedly good feature in the boo the collection of examples, some of which are interspers in the text, and others collected in a body at the e where the answers are given. The metrical and order units are both employed. These examples are perha the only part of the book which would be of any value teachers in this country. With regard to the su subject-matter of the book, Dynamics is placed first, a Statics follows, with a chapter on the Pendulum at t end. The definitions and the explanation of the pr ciples of the subj[illegible] aiming at fulness and cle ness, are not alw[illegible]ory as might be wish A tendency to lo[illegible]on sometimes caus

balances the value of the fuller explanation. To explain *solidity* we are told that "A solid is characterised by a greater or less degree of rigidity," which in the absence of a separate definition of rigidity leaves us much where we were before. Again, the definition of a *liquid* is this, "A liquid is characterised by its mobility; the molecules are free to move about each other, and the liquid takes the shape of any containing vessel," which is equally true of a *gas*. The proof of the formula $S = \frac{1}{2}ft^2$ is clenched by the proposition that "when two sets of variable quantities, which are always equal, simultaneously approach their limits, these limits are equal," which is suddenly introduced without any explanation of its meaning. This, in a book intended for beginners unacquainted with the idea of a "limit," would be likely to cause some bewilderment. There is a chapter devoted to Work and Energy, as should be the case with all text-books of mechanics nowadays.

In the dynamical section there is an entire omission of "Sliding in Chords of a Vertical Circle" and the pretty problems connected with it. In the statics there is no mention of the stability or instability of equilibrium of one curved surface rolling on another. The micrometer screw surprises us by appearing with the mechanical powers alongside of the wheel and axle and differential screw.

As the compiler has not acknowledged his indebtedness to other works, it is difficult to say how much of this book is original. But we seem to catch echoes of Ganot's "Physics" and of Goodeve's two text-books on Mechanics and Mechanism here and there. For instance, Articles 7, 8, 107, 111 remind one of Ganot, Articles 197, 207, 209, 239 of Goodeve. The woodcuts, some of which are good, and others (*e.g.* those in the chapter on Centre of Gravity) very indifferent, are 190 in number. Some of them are apparently reproductions of woodcuts in English books. We instance Figs. 44 and 175, which are strikingly like Figs. 365 [Joule's apparatus] and 19 [block and tackle] in the eighth edition of Ganot's Physics, translated by Atkinson, and Figs. 142*a*, 150, 152, 155 (in Dana), which bear a very close resemblance to Figs. 49, 58, 110, 113 respectively in Goodeve's "Principles of Mechanics," second edition, Fig. 117 in the latter having apparently supplied Dana's three figures, 162, 163, 164 [on Pulleys]. Fig. 145 in Goodeve's "Elements of Mechanism," fifth edition, may well have been the original of Dana's Fig. 156.

It would have been graceful in the compiler of this work to have expressed his acknowledgments to the two excellent little text-books of Goodeve. On the whole, with the reserve above made in favour of the "examples," we think that neither English teachers nor English students will be the losers if they continue to use already existing English text-books of Mechanics, and leave this American competitor to find an audience on the other side of the water.

CONSCIOUS MATTER

Conscious Matter; or, The Physical and the Psychical Universally in Causal Connection. By Stewart Duncan. (London: David Bogue, 1881.)

AS the title of this little work sufficiently indicates, the aim of its writer is to furnish a scientific basis for the theory of materialism in the region of mind. It is doubtful whether at this time of day anything very original can be said upon this topic, but Mr. Duncan has succeeded in placing some of the facts in a stronger light than previous writers. The facts to which we allude are those which he calls the "analogies" between forces and feelings. Up to a certain point it is by every one recognised that there is some quantitative relation between neurosis and psychosis; mental processes are universally known to entail wear and tear of cerebral substance. Mr. Stewart Duncan traces this quantitative relation as much into detail as he can, by setting forth in a series of twelve "analogies" the resemblances between forces and feelings. These "analogies" are far from being unopen to criticism severally; but here we shall merely mention what they are, as there is more important criticism to apply to them collectively. The analogies are that feeling and force are each without extension, both related to matter, have "plurality predicable of them as respects their locality," are diverse, have time-extension or duration, also the quality of degree and capability of being compounded or combined, are respectively transmutable *inter se*, &c. Doubtless, as Mr. Duncan observes, such analogies, or, as we should prefer to call them, parallelisms, might be largely multiplied; but what would any number of such parallelisms prove? Not, surely, what Mr. Duncan desires them to prove, viz. that forces stand to feelings in the relation of causes to effects. So far as the tracing of such mere parallelisms is concerned, we might almost as reasonably conclude the recent earthquake at Chio to have been the cause of this review, in that they each possess extension, have diverse parts, and so on. In order to establish a relation of causality we should require to show that the observed parallelism is due to that relation; we cannot argue from the observed parallelism as itself sufficient proof of such relation. Were this not so, there would be no need for Mr. Duncan or any one else to write a book on "The Physical and Psychical Universally in Causal Connection"; for as the fact of a constant parallelism between neural processes and mental processes is now no longer an open question, were mere parallelism sufficient to establish proof of causality, materialism would now be a demonstrated theory.

It is needless here to go into the whole question as to the relation of body and mind, or to point out all the shortcomings of materialism as a philosophical theory. But it is a defect in Mr. Duncan's work that he does not attempt to meet some of the most formidable of the difficulties with which this theory is beset. Thus he does not consider the fact that what we know as matter and force we know only as affections of mind, and therefore that in all speculations upon the nature and potentialities of the former, we already by implication have necessarily assumed priority of the latter. Nor does he seek to explain the apparent want of equivalency between supposed physical antecedents and supposed mental consequents—why it is that the brain of a Newton required less nourishment than that of an elephant. Lastly, the greatest of all the difficulties is not adequately treated—that, namely, which is connected with the doctrine of the conservation of energy. Are we or are we not to suppose that thought has a mechanical equivalent? If materialists say that we are, then thought itself becomes a mode of

energy, or rather energy by becoming thought ceases to be energy—is destroyed as energy; and so this answer would militate against the doctrine in question. If, on the other hand, it is said that thought has no mechanical equivalent, and yet that energy causes thought, the statement is still in conflict with the doctrine of conservation, because it supposes that energy in the brain differs from energy everywhere else in producing more than its equivalent measure of result. How then under any view are we to conceive of thought as an *effect* of energy? By no stretch of imagination can we attain to the idea of a motor becoming a motive; and if we could attain to such an idea, it would seem to be at the cost of upsetting the most fundamental doctrine of modern physics. And let it be observed in this connection that Mr. Duncan is not very accurate in the statement of his first "analogy," where he says that "Feeling and Force are alike in being both destitute of space-extension." Force in activity is only known as motion in space, while Feeling in activity cannot be conceived as here or there; the conception of Force without any actual or potential relation to space is as impossible as the conception of Feeling in such a relation.

Mr. Duncan's book, however, is worthy of the attention of psychologists, because although we think his attempt to prove a causal relation between physics and psychics a necessary failure, his work is interesting and suggestive if viewed from the standpoint of Clifford's doctrine of "Mind-stuff." If we suppose that Force and Feeling are everywhere one, and so that "all the universe is made up of Mind-stuff," we have a logically possible theory which does not labour under any of the logical disadvantages attending the theory of causality proceeding from matter in motion to mind, or *vice versâ*. Some passages in Mr. Duncan's work seem to show that he has very nearly entered this conception himself; and we therefore feel that he would have written a more valuable treatise if, going a little further, he had discarded the obsolete attempt to explain parallelisms by an impossible theory of *causality*, and undertaken to argue that these parallelisms are really due to a fundamental *identity*, which, as Lewes puts it, is phenomenally diverse only in relation to our modes of apprehension.

GEORGE J. ROMANES

LETTERS TO THE EDITOR

[*The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts. No notice is taken of anonymous communications.*

[*The Editor urgently requests correspondents to keep their letters as short as possible. The pressure on his space is so great that it is impossible otherwise to ensure the appearance even of communications containing interesting and novel facts.*]

Study of the Physical Nature of the Sun

HAVING been engaged for some time past in discussing with that able scientist, the Spanish Astronomer-Royal, Signor Antonio Aguilar, Director-General of both the Astronomical and Meteorological Observatories of Madrid, the best method of realising for the requirements of modern science the peculiar advantages presented by the Peak of Teneriffe for studying and eliminating the interfering effects of the earth's atmosphere on many classes of astronomical, meteorological, and physical observations—it has just resulted, not exactly in the general facilitation which I had hoped for towards the attai nations—but in a particular letter to myself of gracio mendation by Spanish royal authority to the Captain-Ge the Canarian Archipelago.

As however I am totally unable, for reasons well kno own Government both now and for many years past, to a any such research, however useful or pressing—it m service to the cause, and to other workers who are mo ably situated financially, to make known how Sp Spanish Government is inclined at the present momen any genuine efforts, even of individuals, to improve ledge of the great central luminary by making experi tions with improved instruments at some considerable the ordinary clouds and winds of the summer season superiority of site can only be well obtained on this world by means of that grand Mountain-island which ruled so long and so well,—viz. the Island of Teneriff therefore now the pleasure of appending a close tra the official letter, or rather Royal Order, from Madri of which Don Antonio Aguilar kindly informs me been communicated by the Spanish Government to Governor of the Canarian Islands.

"*From the Ministry 'de Fomento,' Madrid, to the General of Public Instruction.*

"ILLUSTRIOUS SIR,—In consequence of the Re Director-General of the Astronomical and Meteorolo vatories of this capital, the King has deigned to or Governor of the Province of the Canaries, and al dependent upon him, should give special attentio whatever assistance he may require to Mr. Piazzi Sm of the Observatory, Edinburgh, in the expedition w posed to the Island of Teneriffe, with the object of t height of the Peak of Teyde, the instruments desi proved by him for the study of the physical consti Sun.

"By Royal Order I transmit this to you for your and may God preserve you many years.

"(Signed) — —

"On the 22nd Ma

A friend well acquainted with both England and me that we have not in this country any exact an Ministry "de Fomento." The literary or theoretic the word is "supporting, encouraging, cherishing practical result in this case has been, that a poor in unrecommended by the Government, or the gr Societies, or Universities of his own land, but havi natural object to labour at, has received this ver testimony and encouraging recommendation. Al to the Government of Spain therefor; and may last with a more worthy subject for their gracious than

Edinburgh, April 9 Your obedient se

PLA

Winter Gnats (Trichocera)

THE winter gnat (*Trichocera hiemalis*, D. G.) subjects of phenological observations undertaken l rological Society. Its appearance directly after l frost, often whilst the thaw is in progress, has entomologists to inquire whether the insects then s hybernating during the cold weather, or have n from the pupa. No evidence has been adduced either alternative. Some facts concerning the ha noted as opportunity occurred during the last two upon the matter in question, and may therefore be both the above classes of your readers. The na *hiemalis* is used here in its meteorological sens would pretend to distinguish this abundant species from the common *T. rufescens*.

With a view to learning what becomes of the winter gnats ring inclement weather I frequently jotted down, when the es were upon the wing, the temperature of the air in the places their resort, the time of the day, and any peculiarity notice-le in the flight of the insects. Upon other occasions, at cor-sponding periods of the day, when the weather was colder and gnats could be seen anywhere, I made similar entries of the mperature prevailing in their usual playgrounds. The instru-ent employed was a Casella's pocket-thermometer mounted in bonite, graduated upon the stem at intervals of every two egrees, and duly compared with a standard.

From the notes thus obtained, which need not be quoted in etail, it appears that the flight of *Trichocera* varies in style ith the temperature, and, as a general rule, is altogether dis-ontinued when the cold exceeds 36° F. Once indeed I saw a nat flying when the thermometer stood at 34°·5 F., but there as reason for suspecting that it had just been startled out of the edge by a passing carriage. When such low readings as these re obtained the insects do not congregate, but fly singly with a eavy drowsy flight, as though impelled by business rather than leasure; and very few venture to show themselves upon the ing at all. At temperatures of 38° to 42° F. they may be seen ccasionally flying steadily in places sheltered from wind; and when a warmth of 45° F., or more, is attained, they throng together and dance for joy. These particulars, by the way, need not prompt meteorologists to do something with their phenolo-gical tables by entering in them "*Trichocera* flying" every calm winter's afternoon if the temperature exceeds 40° F., with-out troubling themselves to go out of doors and look after the gnats.

It was some time before I succeeded in tracing *Trichocera* to the places where it seeks repose after its gambols and whiles away periods of weather too cold or boisterous for excursions abroad. The flies may be seen sometimes at rest upon fences, with their legs stretched out flat, and it appeared probable that they took refuge in the hedges somewhere. A very favourite harbourage of theirs however seems to be the under side of boards and stones frequented by woodlice and earthworms They stand back downwards on the wood or stone, not upon the earth below; and although the specimens found in such situations are mostly females who have gone there to lay eggs, I have once or twice noticed males taking shelter in similar places. Beneath a single flower-pot saucer standing upon damp earth, and eight inches across the bottom, I have counted as many as ten females at once; an individual gnat dislodged crept back underneath it again; but the site became dry, and they forsook it. The wonder was how they managed to enter so shallow a crevice in the first instance. The haunts of the isopod, *Trichoniscus pusillus*, are not too damp for them; but in frosty weather they are apt to take shelter under any dry pieces of wood lying loosely upon the ground. It is obvious that flies with such habits as these cannot fail to be snowed up in great numbers at the first fall; and when the frost is over, having been securely protected from extreme cold, they are ready to take wing again as soon as the snow has melted sufficiently to admit of their creeping forth. Hence, though the temperature may be relatively mild directly after a snowstorm, no gnats are likely to be seen flying until the snow has largely disappeared, when *Trichocera* will become common. Similarly after frost without snow, when the thaw sets in the flies will probably not issue from their retirement immediately, but will rest quietly until the change of temperature has had time to reach them in their lurking-places, whatever may be the warmth of the outer air meanwhile. Perhaps this is the cause of so few winter gnats being seen in the mornings early in the year; but whether it be r not, the other foregoing surmises harmonise well with my vations.

imum of cold to which winter gnats can be exposed consequences has not yet been ascertained.

oad, Croydon, April A. E. EATON

ustralian Plants in India

xiii. p. 370, some remarks are made (with llace's observations in "Island Life") nability of Australian plants to become rn hemisphere. It may therefore be r. Wallace to learn of some striking case of Australian plants which Nilgiri plateau in Southern India, at elevations ranging from about 5500 to nearly 8000 feet above sea-level. Acacias and Eucalypti in particular have found a congenial home in this region, and visitors from Australia who have seen them say that they appear even more vigorous than in their native soil. Hundreds of acres of *Eucalyptus Globulus* and of *Acacia melanoxylon* and *A. dealbata* have been planted by Government as firewood reserves, and the trees have grown up splendidly. The only drawback to the success of the experiment has been that the *Acacia melanoxylon* has been greatly injured by Loranthaceous parasites. In fact this species will apparently in course of time be exterminated by these indigenous pests. Besides *Eucalyptus Globulus* the following species of the genus have also been introduced, and thrive well:—*E. sideroxylon*, *E. obliqua*, *E. fissilis*, *E. rostrata*, *E. viminalis*, *E. amygdalina*, and *E. perfoliata*. In addition to the two species of *Acacia* already mentioned, the following have also been added to the list of healthy growing exotics on the Nilgiris, viz. *A. pycnantha*, *A. salicina*, *A. longifolia*, *A. decurrens*, *A. cultriformis*, *A. elata*, and others, might also be enumerated. As regards other Australian plants on these hills we have *Hakea*, *Banksia*, *Myoporum*, *Kunzea*, *Tristania*, *Pittosporum*, *Beaufortia*, &c. In short there is a very considerable Australian flora flourishing on the "Blue Mountains" of Madras, and so extensively have the trees been planted out about the principal stations that they have given quite a new character to the scenery. Some of the acacias have a considerable resemblance in shape and colour to the Scotch fir, and this likeness has, to some visitors, added a fresh charm to the beauties of the scenery. G. BIDIE

Madras, March 15

The Tide Predicter

WITH regard to the letter of Sir William Thomson in NATURE, vol. xxiii. p. 482, respecting the above instrument, I may say that the Tide Predicter which I have planned and designed for the prediction of Indian tides owes its development, not to the British Association Tide Predicter, but to a complete two-component working model made by me in the spring of 1873. This model was made before the British Association instrument was designed.

It was on the express recommendation of the Surveyor-General and Superintendent of the Great Trigonometrical Survey of India that I was invited to plan and undertake the construction of the instrument, and I was left absolutely unfettered in my choice of mechanicians to carry out the work. My connection with the instrument is clearly explained in the official prefaces to the Tide Tables for Indian Ports, 1881, published by authority of the Secretary of State for India in Council. I may point out that my paper upon this instrument (*Proceedings* Roy. Soc., No. 197, 1879) was written at the desire of Sir William Thomson, to whom it was first submitted, and by whom it was entirely approved and originally communicated. He was also present at the meeting of the Royal Society when the paper was read, and never expressed the least objection to any of its contents. In that paper credit is given to him for the improved slide, which he, with Prof. James Thomson's assistance, had devised for an harmonic analyser, and also to Mr. A. Légé for the admirable plan of the wheel-gearing. EDWARD ROBERTS

3, Verulam Buildings, Gray's Inn, W.C., March 26

"The Oldest Picture in the World"

IN Mr. Loftie's "Ride in Egypt" is a woodcut (p. 209) of what is called "the oldest picture in the world," a fresco from a tomb at Maydoom, now in the museum at Boolak, wherein are represented six "pasturing geese." Two of these are undoubtedly *Anser albifrons*, two, probably *A. ferus* or *A. segetum*, and the other two seem to be the rare *A. ruficollis*, from Northern Asia. I should be greatly obliged to any one who would let me see a *coloured* copy of this picture, that I might be assured as to my determination of the figures. Mr. Dresser, in his excellent "Birds of Europe," mentions his having received a specimen of *A. ruficollis* sent him from Alexandria by the late Mr. Stafford Allen. Otherwise its appearance in Egypt seems to have been hitherto unrecorded. ALFRED NEWTON

Magdalene College, Cambridge, April 10

Probably New Variable Star

ON January 22, 1879, I observed near O^2 Canis, a very remarkable double star, with one component a fiery red 8·5

magnitude, and the other a blue 9. The contrast of colours was very striking, but there was little difference in size. In a letter recently received from the Rev. Mr. Webb, I find that it was previously observed by him, and it appears as one of his own discoveries in the second edition of "Celestial Objects," published in 1868. The red star is there classed as 6·5 mag., and the blue as 8. The two stars, therefore, appeared to differ very considerably in magnitude when seen by Mr. Webb, while to me, eleven years subsequently, they seemed quite nearly equal. Hence I conclude that the red is a variable, and I wish to call the attention of observers to it while it still remains in view. By a rough measurement I make out its position for 1881 = α 7h. 10m. 44s., and δ − 23° 6′·6. JOHN BIRMINGHAM.

Millbrook, Tuam, April 9

Concealed Bridging Convolutions in a Human Brain

IN his work on the "Convolutions of the Human Brain" Ecker denies explicitly that the first and second external bridging convolutions of Gratiolet, as seen in Cercopithecus, Inuus, &c., are ever concealed, either in the higher apes or in fœtal or adult man. I have however in my possession an adult human brain in which *a* convolution nearly corresponding in position to the external bridging one of Gratiolet is concealed, while another slightly external to it is nearly so. The brain was hardened in nitric acid with the membranes on (a much preferable method, by the by, to that of first removing the membranes; as these, by absorbing the acid and swelling, serve, like so many wedges, to keep the convolutions apart, and prevent the shrinkage that otherwise takes place). There was no indication of any concealed convolution until the membranes, just moistened for the purpose with water, were being removed. Then, owing to the opening out of the sulcus occipitalis transversus of Ecker, the tip of one became visible, and this tip, even now that the edges of the sulcus are widely separated, is from one-eighth to one-sixth of an inch beneath the general surface.

Its position relative to the great longitudinal fissure and to the posterior border of the gyrus supramarginalis seems to me pretty accurately to correspond to that of the external bridging convolution to those parts in the brain of an Indian pig-tailed baboon of undetermined species with which I have compared it; but in the latter the sulcus occipitalis transversus does not exist, while in this human brain, as is very common, the lateral or horizontal portion of the fissura parieto occipitalis, beneath the bevelled edge of which in the baboon the convolution lies concealed, has a very short course indeed.

The only difference then is that in the one specimen (the human) the concealed convolution lies in the transverse occipital fissure, there being no lateral extension of the parieto-occipital fissure, while in the other it lies in the parieto-occipital fissure, the transverse fissure not existing WILLIAM CARTER

Liverpool, March 26

Sound of the Aurora

IF I had consulted Franklin's account of his Polar researches before I sent you my extract from Tacitus, I should not have revived the question of sounds being heard with the aurora borealis. Franklin and his companions watched the aurora 343 times in two successive winter seasons; and never once, he says, did they observe a sound. Were, then, the experiences quoted by your other correspondent and myself mere illusions? Perhaps not. Franklin made his observations at and about the southern shore of Bear Lake, in latitudes varying from 67° to 69° north; might not the greater volume of air through which the phenomenon had to pass in reaching our island have caused the electric fluid to work up a sound? Surely that is possible. The attractive force of the aurora is—we learn from Franklin himself—increased within a certain limit as its rays proceed southwards; for whereas Parry and his party at Port Bowen in latitude 73° 15′ noticed no deflection of the compass-needle under the influence of coruscations, Franklin and his party on the shores of the Bear Lake, six degrees further south, constantly observed this effect. And the attractive force is strongly felt here—hindering telegraphic communication at all events. Might not the vibratory force not sensible at within so short a distance from its origin as the attraction be increased within a greater limit? M. L. ROUSE

Sunnymead, Chislehurst Common

PERIODIC OSCILLATIONS OF BAROMET PRESSURE

THE MSS. of the accompanying article, which left unfinished by the late Mr. John Allan B F.R.S., were handed over to me some time ago by Balfour Stewart, with a request that I would put into shape for publication.

I have not found it necessary to make many alter in, or additions to the original, and where made the mostly indicated in initialed foot-notes.

E. DOUGLAS ARCHIBA

In an article which appeared in NATURE (vol. xx a remarkable relation was shown to exist betwee annual ranges of the atmospheric pressure and t temperature of the air, as derived from the mon means obtained from several years' observations o barometer and thermometer at certain stations n The results and the conclusions from them do not ap to have been always understood, and as they bea some of the most interesting questions on meteor I shall now examine them anew with the aid of ot vations at some other stations, under different conditions.

For this end it is desirable to employ some elemen considerations. Let us, first of all, consider the e of varying temperature on a vertical column of the atmosphere. Let us consider a column of air reaching from the soil at B to the upper limit of the atmosphere at A; and suppose that the pressure shown by a barometer at B is 30 inches, while at a higher station, C, it is only 20 inches. If, now, the column of air is heated so that the temperature of the part B C is increased by 10° F. we know from laboratory experiments that the air will expand, so that a part of that which was below C will be pushed above it, and while the barometer at B will continue to show 30 inches, that at C will show 20·2 inches, the mercury at C will have risen two-tenths of an inch.

If, now, we suppose that the mass of air remains constant throughout the year, there will be an annual variation of the barometer at C, where its height will be greatest in the warmest month and lowest in the coldest month. For the same reason the difference of the barometric heights at B and C will be least in the warmest mo and greatest in the coldest.

It has been supposed that the mass of the atmosp remains constant throughout the year; if this is not case the variations of pressure at C will not depend temperature alone, but also on the other causes wh produce variations at B.

In NATURE, vol. xx. p. 55, Mr. Douglas Archibald h given a series of differences of barometric heights at hig and low stations in India for the months from October April. The month of lowest mean temperature, January shows always, as in the case just supposed, the greate difference of pressures. As the high and low station never in the same vertical, the one being sometimes fi miles horizontally distant from the other, it is difficult eliminate the part of the variation due to temperature the higher station, but if we take as an approximation however rude, the mean of the temperatures at the s stations as that of the vertical column, we can see that considerable part of the variation at the upper stati may be due to the expansion of the column with t perature.

Thus for Leh and Lahore the mean temperatures a difference of barometric heights are[1]:—

[1] The numbers are taken from the work cited by Mr. Archibald Indian Meteorologist's *Vade Mecum*," by Mr. H. F. Blanford, F.R.S. 176, 178.

	Mean temp.	Diff. of Pressures.
	°	in.
January	35·0 Fahr.	... 9·690
July	74·1 ,,	... 9·105

Now as the difference of the mean temperature of these two months is nearly 40°, according to what has been said before, the expansion of the air from January to July should have increased the pressure at the upper station by about 0·8 inch (eight-tenths of an inch of mercury) and have diminished the difference of pressures by that amount. The observed diminution is, however, less than 0·6 inch, a deficiency of two-tenths, which has to be accounted for in some other way.

In the case of the annual variation of atmospheric pressure near the sea-level, we have to consider only the atmosphere above the station; but in that for a high station we have a much more complicated problem in which the atmosphere below the station plays an important part, a part also which may vary greatly, according as the upper station is on a mountain top, on a gradually ascending height, or on high table land.

It was for these reasons that in the article (NATURE, vol. xix. p. 6) under consideration, nothing was said of the annual variation on mountains or at great heights; the results were obtained from observations at stations little above the sea level, and from them it appeared that for every degree Fahrenheit on the range of monthly mean temperature, there was a variation of from ·021 inch at Singapore, to ·025 inch at Bombay and Madras, in the range of the monthly mean barometric height; while at Pekin the amount was diminished to ·015 inch. The conclusion that this ratio was nearly constant in India referred necessarily to stations under similar conditions. Mr. Archibald's letter has brought to notice a series of Indian observations made at stations farther from the sea and in North India, which are given in an interesting and useful work by Mr. H. F. Blanford, Meteorological Reporter to the Government of India, and which merit consideration. The means employed by me previously were derived from observations at standard observatories during five to twenty-six years; and it was mentioned that, as single years gave somewhat variable results, the monthly means from several years' observations were necessary for accurate values. In the cases to be found in Mr. Blanford's work, several are of observations during only two years (or even less), and we have no exact idea of the weight which in any case can be accorded to the observations at the stations. As, however, the results for different stations in general confirm each other (the exceptional cases will be noticed apart), I shall here form a series of groups of stations, each group under nearly the same local conditions as regards latitude, height above, and distance from, the sea. The value of k, the variation in thousandths of an inch, of pressure-range for 1° F. of the temperature-range, is the same for all stations in each group, with the exceptions referred to below.

Thus the most northerly group near latitude 30° N. and 600 miles from the sea, viz., Lahore, Delhi, Dera Ismail Khan, Mooltan, and Roorkee, gives the following result :—

Mean latitude of group (λ).	Mean height above the sea (h).	Mean annual temperature (t).	Mean ranges of temperature and pressure		Mean barometric oscillation for 1° Fahr. $\left(k=\frac{\Delta\phi}{\Delta t}\right)$.
			Δt.	$\Delta\phi$	
°	feet.	°	°	inch.	
30½	660	75·2	39·0	0·620	0·016

This group extends about 450 miles from Delhi to Dera Ismail Khan, and the heights vary from 440 to 890 feet. The value of k is the some for each station.

The next group comprises Bareilly, Lucknow, Jhansi, and Benares, for which the following are the values of the different elements :—

λ	h	t	Δt	$\Delta\phi$	k
	feet.			in.	
26	520	77·7	32·4	0·554	0·017

The distance of the extreme stations is not 300 miles; the heights vary from 270 feet at Benares to 860 feet at Jhansi. For each station k = 0·017.[1]

The third group includes Patua and Gya, and the values are—

λ	h	t	Δt	$\Delta\phi$	k
	feet.			in.	
25½	260	78·5	28·0	0·537	0·019

The distance between the two stations is about 70 miles; the heights are 179 and 347 feet respectively, and the values of k are within half a thousandth of each other.

The fourth group includes Berhampore, Burdwan, Dacca, Goalpara, Chittagong, Calcutta, and Saugor Island, for which the values are—

λ	h	t	Δt	$\Delta\phi$	k
	feet.			in.	
23½	100	78·0	18·7	0·471	0·025

With the exception of Goalpara and Chittagong, these stations all lie in the Gangetic delta, at nearly the same elevation, and with an extreme variation in the value of k amounting to 0·004 inch.[2]

The fifth group includes Bombay alone, the values for which are—

λ	h	t	Δt	$\Delta\phi$	k
	feet.			in.	
18½	37	78·8	11·6	0·287	0·024

The sixth, Madras, Negapatam, Trichinopoly, and Madura, with the values—

λ	h	t	Δt	$\Delta\phi$	k
	feet.			in.	
11½	190	81·7	11·1	0·243	0·021

The seventh, Colombo, with the values—

λ	h	t	Δt	$\Delta\phi$	k
	feet.			in.	
6½	42	81·3	3·6	0·069	0·019

It will be seen from this table that the value of k is a maximum (= 0·025) nearly under the tropic of Cancer, that it diminishes thence both north and south. This diminution cannot, however, be attributed altogether at least to the latitude, since the value is nearly the same at Pekin and at Delhi.

The variation of the value in Northern India from the maximum near Calcutta has an apparent relation to the height above the sea and the distance from it,[3] as well as to the amount of the temperature oscillation; the value of k diminishing as the others increase. We cannot, however, relate the value to any one of the other variables. No doubt height above the sea may have some influence, as has already been shown, but here mountain stations have been avoided; and while in the Lahore group the heights vary from 420 feet (Mooltan) to 890 feet (Roorkee), the value of k remains constant.

It should be observed that the temperature ranges are those of the stratum of air a few feet above the soil, while the ranges of pressure include the whole atmosphere above each station. We see that the value of k dimi-

[1] There appears to be some difference in the values of $\Delta\phi$ as got by Mr. Broun and those derived from my edition of the "Vade Mecum" for these two groups. Thus from my edition (1877), the value of $\Delta\phi$ for Group I. is 0·614, and therefore k = 0·015; there are also slight differences in the value of k at each station. In Group II. k is 0·017 only for Bareilly and Lucknow, the value for Jhansi and Benares being 0·016.—R. D. A.

[2] The figures for the fourth group have been supplied, and the fifth, sixth, and seventh groups have been added as the text seemed to imply their intended formation by the author.—E. D. A.

[3] Mr. Archibald has considered height not to be an element, and he cites in evidence Lucknow and Sibsagar, very nearly at the same height; the former having k = 0·017 and the latter k = 0·028 (NATURE, vol. xx., footnote p. 54). The latter value, however, is a mistake, for at Sibsagar k = 0·018, very nearly as at Lucknow. Mr. Archibald's conclusion is that it is not height, but distance from the sea, as the stations are at widely different distances from the sea. We should, owing to this error, be obliged to reverse the conclusion, and say it is not distance from the sea, but height, that is in question; but, in reality, Sibsagar though not so far from the sea, is still as far as Patua or Gya, with nearly the same value of k.

[See my note on this point, NATURE, vol. xxi. p. 131.—E. D. A.]

nishes as the range of the surface-temperature increases, and it is certain that the ranges of the temperature at all the stations as we ascend above *the soil*, will approach always nearer to each other the higher we go; so that if we knew in what way the relation between the oscillations is produced, and thence, in all probability, the part of the atmosphere which is chiefly in question, we might find a more constant relation between Δt and Δp at all the stations.

I will now proceed to make some remarks which may aid in the study of these questions. I would first observe with relation to the stations in the preceding table that the value of k is only 0·024 at Chittagong, while it is nearly 0·029 at Saugor Island. I have no doubt, however, that this difference is due to some local or instrumental cause.

In the first article I have, as already stated, used only observations made in first-class observatories. Every one acquainted with the difficulties of obtaining good observations in India, especially at out-stations, will understand that the mere printing of their results cannot give them any certain weight. Thus from the tables of means given in Mr. Blanford's work, it appears that the value of k at Vizagapatam is 0·032, while at Cuttack less than 3° to the north, it is 0·025. This great difference would lead to the conclusion that there must be some remarkable local cause, or that there is some error in the observations; if the former, then farther research as to this cause would be of the highest importance; the latter seems to me the most probable explanation. The following example, that of a station so well known as Madras, will show some reason for this belief. The results for Madras, given in the table, are those employed in the first article, and deduced from observations made in the Magnetic and Meteorological Observatory from 1841 till 1855. In Mr. Blanford's tables, however, means are given from observations for nine years. These means give results markedly different from the others. The following summary for the months of December, January, and June, will prove this:—

Group of Years.	Height of Barometer. December.	January.	June.
1841–45	29·954	29·998	29·691
1846–50	·957	·986	·693
1851–55	·992	·998	·702
Means	·967	·994	·695
1868–71	·978	·967	·671
1872–76	·955	·926	·802
Mr. Blanford's means for nine years	·965	·944	·744

Now the three means for January, each deduced from five years' observations, do not deviate from the mean of the whole more than ·008 inch, while the corresponding extreme deviation for June is ·0 7 inch. Whereas the means from nine years, according to Mr. Blanford's tables, differ by 0·050 inch from the means of fifteen years, and the annual range, which is 0·299 by the fifteen years' observations, becomes only 0·200 by the last series. Judging from the means for four years—given by Mr. Blanford in his valuable memoir in the *Phil. Trans.* on the winds of North India—which I believe to be part of the nine years, the means for five years, 1872–76, give a range of only 0·124 inch from January to June; but even the mean pressure for the place and the annual law of variation is altered by the nine-year series, the maximum pressure occurring in December instead of January. It is essential in such investigations that some confidence can be placed in the observations, and if this can be done anywhere it is certainly in observations made at such a station as Madras. I have employed previously means deduced from fifteen years' observations in the Magnetic and Meteorological Observatory; but these means differ in a manner so extraordinary (for a South Indian station) from the means given by Mr. Blanford from nine ye observations, that this demands attention and explan tion.[1]

We see that the annual oscillation of pressure increa with that of temperature, and as shown in the ar already cited, that this relation holds for two places opposite sides of the Ghâts, nearly at the same lat within sixty miles of each other, for which the ann oscillations at one are twice those for the other.

Let us now see what our knowledge from laborat experiments of the laws of expansion and equilibrium gases would induce us to conclude with reference to stations in question.

In the first place, let us remember that the yearly m temperature at Pallamcottah is about 7° Fahr. grea than at Trevandrum, while the yearly mean pressu the same. We conclude at once from this result that mean pressure does not depend on the mean temperatu

I stated that the mean temperature in January at lamcottah, on the east side of the Ghâts, was 4° F greater than at Trevandrum, sixty miles distant on west side of the mountains, and that the mean pressu was 0·065 greater at the former than at the latter. John Herschel has shown that according to our kn ledge of the expansion of gases, there should be a s diurnal atmospheric tide due to one side of the w being warmer than the other, and this due to the ex sion of the gases in the warmer half causing the cen gravity of the air to be higher than in the other, an produce a sliding motion of the warmer air towards colder in twelve hours.

If such a result is what may be supposed to occ the period of a day, there cannot be the smallest d that if a mass of the atmosphere has a lower pressure a lower temperature than another mass at a short dist the former should flow towards the latter, and pr equilibrium within twenty-four hours. Here, how we find that there is a difference of pressure of 0·06 which remains during a whole month at a distan sixty miles, and this continued difference of pressu not to be explained by any known property of gases

We see, indeed, the remarkable fact that the osci of the monthly mean pressure at one station pro quite independently of that at the other, and both constant ratio with the variation of the temperature atmosphere in the lowest stratum.[2] All this is i cable by any heating action alone.

I have omitted all notice of the aqueous vapour atmosphere. It is obvious, however, that this explain the annual oscillation of pressure, since it when the tension of vapour is greatest, that the metric height is least. The introduction of more into the atmosphere does not make the whole light heavier; and when we adopt the arithmetical op of Dove and subduct the vapour pressure from th metric height, we find the oscillation to be great less, than before.

It is not easy to determine the variation of pressure from the indications of the dry- and w thermometers, and the exact result of the total above the barometer cannot as yet be determined, amount will not explain the annual law, nor will it the independent oscillations in question. I hav ever, long ago suggested that the humidity of the humidity of the lower mass are probably related temperature, the oscillations of pressure may related to them.

Sedgwick has said, in his inaugural discourse

[1] Mr. Broun asked me if I knew what years made up the nin know of no one except Mr. Blanford himself who can give a sa answer to this question, and he is in India. The "Vade Mecum official work, ought certainly to be trustworthy.—E. D. A.

[2] And probably of the mean temperature of a layer of some co height.

udies of his University: "To explain difficulties in ıese questions, the atmospheric strata have been shuffled ı accordance with laboratory experiments." Thus, for ĸample, the mean pressure of the atmosphere remains, n the average of the whole year, 0·038 inch lower for very 100 miles we proceed north in this country, a differnce which is called a *gradient*, as if it were a fall on a ailway line, though it is really the position of equilibrium ke that of the watery ocean, which has also a gradient f nearly thirty miles from the equator to the poles.

I have previously remarked that at Bombay the maximum pressure precedes nearly by a month the minimum emperature, while the minimum pressure is a month ater than the maximum temperature. This is also true or all the stations in North India. At Madras, however, ınd Trevandrum, January becomes the month of maximum pressure. I do not, therefore, place much weight ɔn this fact as showing that the two oscillations are not ɔause and effect. The month of maximum pressure at Pekin agrees most nearly with that of minimum temperature.

I have stated in the first article on this subject that I did not admit that the oscillation of pressure was due to that of temperature, and therefore could not allow that a higher annual mean temperature [would in any case cause a lower annual mean pressure] From the fact that the annual variation of pressure and temperature in Central Asia is greater than in any other portion of the globe, the greatest pressure coinciding nearly with the lowest temperature, and the least pressure with the highest temperature, it was concluded by Mr. Chambers that years of greatest mean pressure should also be years of least mean temperature. Now if we assume that the pressure depends only on the mass of the air and watery vapour in it, as the former is constant, and the latter, the only variable part, is greatest when the temperature is highest, it would follow that years of greatest heat should be years of greatest pressure, which is just the reverse of the conclusion deduced by the analogy from the annual variations.

Indeed, it is one of the great difficulties in the hypotheses which have been proposed, to explain the annual variation of pressure of the mixed atmosphere, that when we subduct the vapour pressure, as far as our means of calculating this exist, we have a much larger dry air oscillation than before.

I gave, however, different reasons for concluding that the range of temperature was not itself the cause of the diminished pressure, although the two go nearly together. One was that the observations of Bombay showed the greatest pressure to precede the lowest temperature by a month, and this is true for all the stations in the groups of North India already given. I also pointed out that were the two directly related, the mean pressure at Trevandrum should be greater than at Pallamcottah by nearly one-tenth of an inch, which is not the case, the isobars and isotherms having no relation to each other.

If we suppose that we have the same atmosphere over each station as over the whole earth, there is no possibility of explaining the variation of pressure by that of temperature. The only known property of heat which affects the mass has no doubt been employed to cause the hotter air to flow away somewhere, and surely in that case it should flow to the nearest colder station, where the pressure is less; but we have seen that this is not so in the case of Trevandrum and Pallamcottah, nor is it so in the valleys of the Ganges and Indus, where the oscillation increases as we ascend from the sea. These oscillations proceed with the greatest regularity, approximately in proportion to the temperature variation from month to month, and without the slightest regard to the hypothesis which should cause equilibrium in twenty-four hours, by the sliding of the most expanded masses over those least so. In what way, then, can we associate the two oscillations if one is not the cause of the other? I have long ago suggested that the varying humidity of the air may be in question; this is only a suggestion. I do not mean the mere tension of vapour—as already stated when we try to get rid of that from the total atmospheric pressure, the subject becomes more difficult, the dry air oscillation being greater not less than that of the whole—but if we suppose that the attraction of gravity is not the only attraction which affects the pressure of the atmosphere, but that this pressure varies through some other attracting force such as an electric attraction of the sun depending upon the varying humidity of the air, and this again depending on its temperature; we should find a method of relating the two variations which does not exist if gravitation alone is employed.

It is quite certain that many physicists will not admit the idea of an electric attraction on our atmosphere in the present state of our knowledge, hence the efforts to make expansion, and a shuffling of the atmospheric strata suffice. We must not, however, in our ignorance, attempt to force conclusions in opposition to facts, and if these can be satisfied more easily and with greater probabilities in its favour by the aid of the hypothesis of an electric attraction of the sun, that hypothesis will have a better claim to acceptation than the other.

I shall here note a few facts which cannot be explained by thermic actions.

1. I have shown that on the average of many years' observation in our latitudes the mean pressure diminishes at the rate of 0·038 inch of mercury for every one hundred geographical miles we proceed towards the north. This has been called a gradient from the similar term used in railway slopes; but it is no slope, it is a level of a surface of equilibrium like that of the sea. It is the mean heights of the barometer at the sea-level which indicate the form, if we may say so, of the equilibrating atmosphere.

2. In India we have seen that the atmospheric pressure oscillates at each station even when these are quite near to each other, independently of the known laws of equilibrium of pressure of gases.

When we turn to the semi-diurnal oscillation of the barometer we are only amused at the attempts made to explain it by shuffling the atmospheric strata. Nothing can be more certain than that the theories of expansion, or resistance to expansion and overflow, are the vain efforts to make the laws of nature agree with a theory. Over the great ocean within the tropics, where the diurnal variations of temperature are small and the air is absolutely without perceptible currents for days together, the barometer rises and falls a tenth of an inch twice in twenty-four hours with the regularity of the solar clock. The action of the sun on the whole atmosphere which produces this movement varies chiefly during the day hours at inland stations with the temperature oscillation, so that, as in the case of the annual variation, the fall of the barometer at 4 P.M. is greater in the same latitude as the temperature is higher. This variation occurs during the most complete calms; the smoke rises vertically from the plains of Tinnevelly; no current is visible in the motion of the clouds; yet the barometer falls at four in the afternoon as it did at four in the morning, only it falls farther.

THE ETNA OBSERVATORY

THE accompanying illustration of the Observatory on Mount Etna is reproduced from the *Memoirs* of the Italian Spectroscopic Society. It shows that the building is so far complete, and surmounted by its revolving dome for the protection of the large Merz equatorial of thirty-five centimetres aperture. In the engraving the volcanic cone appears much nearer the Observatory than it really is. The work of building was suspended during the stormy weather of 1879, but was completed in the summer of last year. But it cannot be said that the

building is yet quite finished and ready for occupation; a good deal of work has yet to be done to the internal walls, the doors and windows, flooring, &c., besides the scientific equipment of the building. Therefore the announcement by the Alpine Club of Catania that the building would be ready for inauguration at t of the Alpine Congress in Catania nex was premature. The Observatory will not re to be opened till 1882. The difficulties that be contended with can only be comprehen

who have visited the place; all the materials have to be conveyed 3000 metres above the level of the sea, and that during only three months in the year. So that even if not ready till 1882, the work may be said to have been rapidly accomplished. The mounting of the equatorial is finished and the construction of the apparatus is being proceeded with. Th Agriculture and Public Instruction are do provide the Observatory, by 1882, with a staff both of astronomers and meteorolo

---

MODE OF MASKING OR CUTTING OFF SHARPLY THE LIGHT FROM REVOLVING APPARATUS ON ANY DESIRED COMPASS-BEARING BY MEANS OF A RECIPROCATING SCREEN

OWING to the optical properties of the lens employed in revolving lights, a formidable element of difficulty comes in the way of effecting a sharp cut-off on a particular bearing; for the direction of the axis of the beam of light which is projected by the lens is being continually changed in the horizontal plane by the revolution of the frame on which it is fixed. So long as the axis of this beam of rays points outside of the line of obscuration the light will not of course encroach on the danger arc, unless to a small extent, when the axis is nearly on the line of cut-off due to the ex-focal rays proceeding from the outer edges of the flame. The light however will begin to be diminished in power from a bearing varying from 12° to 21° outside of the line of cut-off dependent on the size of the lens, the light on the line of cut-off being diminished to the power of one- the axis crosses that line, then as the r from that part of the apparatus which i the darkened panes of the lantern is not them, the light will begin to be seen wi danger, and as the apparatus goes on revol at last point from about 12° to 21° within according to the breadth of the lens whi Owing to this peculiarity of a revolving li of confining the flashes within any requ horizon by means of *fixed* screens is in mountable one.

The mode which I have to suggest is front of the revolving apparatus and on of the danger arc, let a light canvas or be constructed for running on rollers on a rail or circular path close to the apparatus projecting rod or snug be fixed to the si it will in revolving be brought against screen, and will gradually press the scre the inclined plane at the same rate of mo

that of the lens forwards. By the time the lens reaches the edge of the danger-arc the screen will have been pushed to the top of the inclined plane, and the full beam of light coming from the now entirely uncovered lens will be pointing in the required line of cut-off which is the border of the danger-arc. But whenever the further revolution of the apparatus causes the snug to pass clear of the edge of the screen so as to free it from pressure, it will immediately run back again to its original position in front of the lens, so as to prevent any light being now sent forwards. If that light were not at once intercepted part of it would, by the movement of the flame, begin to pass across the line of cut-off, so as to be seen within the danger-arc. By this continued reciprocative movement of the screen as lens after lens comes round, the same effect will be successively produced, and the light will always be cut off in the line of obscuration as sharply as in the case of a fixed light, so that the flashes will never be seen within the danger-arc.

In cases where the light has to be cut off on both sides of a danger-arc a similar reciprocating screen is as applicable to the lenses when passing out as when passing into the danger-arc. But in this case the lens, on leaving the danger-arc, will take the screen round with it up an inclined plane until the axis of the lens is parallel to the line of cut-off, when the screen will recoil and the light become visible with full power in the line of cut-off.

A small spherical mask placed inside of the apparatus may be made to produce the same effect by reciprocating between the lenses and the flame. When the danger-arc is of small amplitude the screens, which must always be as broad as the lens, might come in the way of the light passing over the safety-arcs. To obviate this, cloth curtains might be made to wind up on vertical rollers similar in construction to those used for ordinary house-blinds.

THOMAS STEVENSON

CHLOROPHYLL[1]

AN account was given in NATURE, vol. xxi., p. 85, of Prof. Pringsheim's first publication on this subject. He had then found that exposure to intense light for a few minutes causes the chlorophyll-corpuscles contained in the cells of plants to lose their green colour; he also pointed out that this effect is produced not by heat but by light, and only in the presence of oxygen, and further, that the highly refrangible rays of the spectrum are those which are principally concerned in it. He also announced the discovery in the chlorophyll-corpuscles of a substance termed Hypochlorin.

The paper now under consideration gives a full account of all the observations and experiments which he has made up to the present time, and he considers that they tend to confirm the conclusions at which he had previously arrived. It will be well, before entering upon a discussion of the very difficult questions which are raised, briefly to enumerate the principal new facts which he now brings forward.

In the first place, he is able to throw some light upon the intimate structure of chlorophyll-corpuscles by means of a new method for investigating them. This method consists in treating them with a dilute acid (*e.g.* 1 vol. of glacial acetic acid to 2 of water, or 1 vol. of picric acid to 3-6 of water, or 1 vol. of sulphuric acid to 20-40 of water, or 1 vol. of strong hydrochloric acid to 4 of water), or warming them in water, or exposing them to the action of steam. The effect of this treatment is to cause the escape of the chlorophyll from the corpuscle, together with certain fluid or semi-fluid substances which accompany it, in the form of viscid drops, leaving the ground-substance of the corpuscle as a colourless, apparently protoplasmic, hollow sphere, with a much perforated wall.

[1] "Untersuchungen über Lichtwirkung und Chlorophyllfunction in der Pflanse," by Prof. N. Pringsheim (*Jahrbücher für Wiss. Bot.*, Bd. XII., Heft 3: Leipsig, 1881).

These viscid green drops, when produced by the action of warm water or of steam, appear to consist of an oil which holds the chlorophyll and other substances in solution. When they are produced by means of a dilute acid, they appear to contain a substance which is not present when they are extracted by warm water or by steam. Certain dark brown masses make their appearance which are of a tolerably firm consistence and of varying form. These gradually become harder, and assume a crystalloidal appearance, probably, as Prof. Pringsheim suggests, in consequence of a conversion into resin of the oily matter which is present; but it is by no means the whole of the substance which thus solidifies, but only a certain constituent of it. The colour of the mass is doubtless due to the presence of altered chlorophyll, and this may affect even the crystalloids, but they may be obtained colourless. It is to the substance which assumes the crystalloidal form, or rather to some substance pre-existent in the chlorophyll-corpuscle from which these crystalloids are derived by the action of the acid, that Prof. Pringsheim gives the name of Hypochlorin.

He meets the doubts that may arise as to the chemical individuality of this substance, as also the suggestion that it may be a product of the alteration of the chlorophyll, by pointing out that it cannot usually be obtained at any one time from all the corpuscles of a given cell. It is therefore a substance which, as it is present in some and not in others, cannot be derived from chlorophyll which is present in them all, and which probably bears some definite relation to the metabolic processes going on in the corpuscles.

Since no hypochlorin can be obtained from cells which have been warmed in water or acted upon by steam, it appears that this substance is decomposed by heat.

After giving a detailed description of the arrangement of the apparatus used in his observations, Prof. Pringsheim goes on to give an account of the effects produced by exposure to intense light in the different parts of which the cell consists. He again insists that none of the following phenomena can be the results of excessive heating of the object, for he found that cells not containing chlorophyll (*e.g.* colourless zoospores) could bear the exposure for half-an-hour without injury, and further, that the phenomena were produced more readily by blue or green light than by red light which has a much greater heating effect. The principal phenomena observed are as follows:—

1. The colouring-matter.

The chlorophyll-corpuscles lose their colour in a few minutes, but this does not take place when oxygen is not present, nor in red light. There is no trace of chlorophyll left in the corpuscles. Prof. Pringsheim is therefore of opinion that its decolorisation is a phenomenon of oxidation, and that the products are gases. Further, this disappearance of the chlorophyll is not prevented by the absence of carbonic acid gas. The corpuscles which have lost their green colour do not regain it, although the cell in which they are contained, still continues to live; on this account Prof. Pringsheim regards the decomposition of chlorophyll as a pathological and not as a normal process.

Colouring matters, other than chlorophyll, which occur in the cells of plants, are likewise decomposed, but not all of them. Thus, the blue pigment of the Phycochromaceæ, the brown of Fucus, the red of the Florideæ, the orange of the corolla of Calendula, the blue in the cells of the staminal hairs of *Tradescantia virginica*, disappear, but the blue pigment in various flowers is not decomposed by exposure to intense light.

2. The ground-substance of the chlorophyll-corpuscles and their contents.

If a cell of Nitella or of Spirogyra be killed by the action of heat, for instance, the chlorophyll-corpuscles of the one and the spiral band of the other will absorb water

and swell up. If the cell has been killed by prolonged exposure to light, no such absorption of water will take place.

Prof. Pringsheim mentions starch, oil, and tannin as commonly occurring in the chlorophyll-corpuscles[1]; these substances, which contain a considerable proportion of oxygen in their molecule, are not affected by the action of light.

3. Hypochlorin.

No trace of this substance can be detected in cells which have been exposed.

4. The protoplasm of the cell.

The turgidity of exposed cells is lost; the protoplasm readily allows colouring matters to pass through it, and treatment with plasmolytic reagents produces no contraction. In a long cell, part of which has been exposed to the action of light, it is only the portion of the protoplasm which has been exposed that exhibits these alterations in its properties. Moreover, these changes are apparently accompanied by a perceptible loss of substance.

A brief exposure causes an arrest of the rotatory movements of the protoplasm in cells which exhibit it. If the exposure has not been prolonged, these movements will recommence after a time. If a portion only of such a cell be exposed for not too long a time, the movements will be arrested in the exposed portion, whereas it continues in the rest of the cell.

5. The cell-wall.

The only effect which the exposure produced on cell-walls appears to have been that the cells of the more delicate filaments of species of Spirogyra and Mesocarpus become isolated.

The following are the general conclusions which Prof. Pringsheim draws from the facts which have been stated above. He concludes that the injurious effects produced by the exposure of a cell to intense light in an atmosphere containing oxygen, are due to an increased oxidation of certain substances which are essential to its life. The rays which are active in this process are not those which reach the interior of the cell after having passed through the chlorophyll-corpuscles, but those which reach it directly. He finds, it is true, the cells which do not contain chlorophyll are, on the whole, less sensitive to the action of light than those which do contain it, but there are no grounds for believing that this greater sensitiveness is due to the absorption of any light-rays by the chlorophyll. On the contrary, the presence of chlorophyll in a cell seems rather to diminish than to increase the oxidising action of light. Facts are adduced to show that chlorophyll exercises a protective influence in this respect, and it is further pointed out that the death of the cell, when exposed to intense light, takes place *before* the complete decolorisation of the chlorophyll-corpuscles has been effected. The greater sensitiveness to the action of light of a cell containing chlorophyll is ascribed to the presence in it of the readily-oxidisable products of its assimilatory activity, and of these hypochlorin is the most important.

Prof. Pringsheim's theory of the function of chlorophyll is, then, (1) that the respiration of a cell is increased by exposure to light; (2) that, in consequence of the absorption which takes place when light passes through chlorophyll, the presence of chlorophyll in a cell tends to counteract the influence of light, so that, when the light is not intense, the respiration of the cell is so far diminished that processes of reduction can take place within it, but when the light is very intense the chlorophyll itself undergoes decomposition, and the death of the cell is brought about by the excessive oxidation of certain of its essential constituents.

[1] He quotes the observations of Briosi to prove that oil, and not starch, is the substance which is formed in the chlorophyll-corpuscles of the Musaceæ, without being aware, apparently, that Briosi's results have been shown to be incorrect by Holle and Godlewski ("Flora," 1877).

After having stated his own views, Prof. Pra proceeds to criticise the current hypotheses co the function of chlorophyll. The first of these is according to which chlorophyll is itself conver carbohydrate in the assimilatory process. It is to understand, from a chemical point of view, ho conversion can be effected in the plant, and it quite impossible when it is shown, as Prof. Pri has done, that chlorophyll does not undergo ceptible change when it is exposed to light in sphere containing carbonic acid but no oxygen. The relates to the absorption-spectrum of chlorophy question naturally arises as to whether or not which chlorophyll absorbs are those which e reduction of carbonic acid and water in the chlo corpuscle. That it must be answered in the aff clear when it is borne in mind that the maximum decomposition of carbonic acid does not coincid the maximum of absorption in the chlorophyll-spe From what source, then, is the energy derived w necessary for this reduction? It is derived, accord Prof. Pringsheim, from light-rays absorbed, not chlorophyll, but by the other cell-contents. He opinion that the chlorophyll takes no direct part process.

The next question which is dealt with is the e of an optimum intensity of light for the decompos carbonic acid. Prof. Pringsheim does not consid this is the intensity which effects the greatest evol oxygen, for, from his point of view, the amount of given off at any time is the resultant of the action distinct processes, respiration and assimilation, bo which are affected by the intensity of the ligh concludes that, so far as an actual gain of car concerned, there is no general optimum intensity applies this mode of reasoning also to the question relative activity of the different rays of the spectrum the process of assimilation. The green and yellow have been found to be more active than the blue, be as he points out, they are not absorbed to the extent by the chlorophyll, and not because the endowed with any special reducing power. Fin proceeds to the discussion of the fact that the vo of an atmosphere in which green plants are expos light remains constant. This fact has led to the sion that, since the volume of carbonic acid decom and of oxygen exhaled is the same, the substance fo in the process is a carbohydrate. Prof. Pringsh inference from this fact is very different. He argues since oxidation and reduction are going on simultaneo the substance formed contains a smaller quantity oxygen than a carbohydrate,—in fact a quantity is smaller by just that amount of oxygen which has used up in respiration.

Stated in the briefest possible manner, Prof. Pringsh principal results are as follows:—

1. That the presence of chlorophyll favours the ass latory activity of the chlorophyll-corpuscle in consequ of the absorption, by the chlorophyll, of light, w would promote the respiratory activity.

2. That hypochlorin is the substance which is the visible product of this assimilatory activity, and the other substances (starch, glucose, oil, tannin), w are found in chlorophyll-corpuscles are derived hypochlorin by oxidation. This conclusion is based the general occurrence of hypochlorin in chloro corpuscles, upon the fact that the amount of hypoc in a corpuscle varies inversely as the quantity of which is present, and upon the observation that hy chlorin cannot be detected in seedlings until they been exposed to light of such an intensity as to ca them to assimilate.

It is of interest to note that hypochlorin make appearance at the later stages of germination in

of Pinus which have grown in the
has long been known that these
darkness.
e regarded as other than a most
to our knowledge of the physio-
ill be readily admitted that Prof.
f the function of chlorophyll is at
any which are now current. But
of facts upon which the theory is
vidence in favour of it can hardly
complete at present; there are
equire further elucidation. For
eim regards the chlorophyll of a
no change under ordinary circum-
ult to reconcile this view with the
solution of chlorophyll loses its
circumstances. Then again, as
educing energy in the process of
s absorbed by the chlorophyll are
n it, it is most desirable that more
obtained as to the nature of the
nd as to the particular cell-contents.
Further, the correctness of the
ase in the intensity of light to
produces an increase of its respi-
re direct and general experimental
en here. In his views as to the
appears to insist too strongly that
les are to be regarded not only as
ts respiratory organs. It is not
the observations which he gives
uggest such a view; on the con-
to show that exposure to intense
n in the *whole* of the protoplasmic
ngsheim evidently desires to bring
s *the* substance which undergoes
id since it is present exclusively
n the chlorophyll-corpuscles, he
dies are the especial seats of the
His observations, however, do not
n; what they prove is that the
ophyll-corpuscles is oxidised when
nse light in an atmosphere con-
t certain changes (including a loss
c in the rest of the protoplasm, in
of the excessive oxidation of some
es which it contains. His view
the *à priori* objection that it is
the same organ should be the seat
nctions as respiration and assimi-
ological significance of the chloro-
es apparent when it is borne in
loes not take place in cells which
reas respiration proceeds actively,
n such cells.
pochlorin, it is to be hoped that a
for the extraction of this substance
allow its properties to be studied
osition to be ascertained. The
lorin cannot be detected in plants
y green (Diatomaceæ, Fucaceæ,
r investigation.
perhaps be supplied in the future
subject which Prof. Pringsheim

SYDNEY H. VINES

NOTES

from the *Times*.—At their meeting
Council of the Royal Society selected,
fifty-two candidates for the fellowship,
ecommended to the Society for election
June 2 next:—W. E. Ayrton, H. W.
H. M. Christie, G. Dickie, A. B.
Kempe, A. Macalister, H. McLeod, J. A. Phillips, W. H. Preece, R. Samuelson, M.P., B. B. Stoney, R. H. Traquair, Rev. H. W. Watson, C. R. A. Wright.

A *conversazione* of the Society of Telegraph Engineers was held in honour of Prof. Helmholtz in the rooms of University College on Monday night. Among those who were present to meet the guest of the evening were many eminent English men of science. Many of the members of the Society and other had lent instruments and apparatus showing some of the purposes to which electricity has recently been applied, and also the means by which electrical research is still being carried on. On entering the College grounds the visitors saw a very pretty effect caused by one of Mr. Crompton's electric lights, which had been placed on the top of the portico. The reception-room itself was lit up with little incandescent electric lamps on Mr. Swan's principle. They were arranged in bunches of three or four in ground glass globes suspended from the ceiling, and in fact at first sight they looked like very brilliant gas-burners, no wires being visible. On each side and down the centre of the room were placed tables on which were arrayed all the newest inventions in electrical science. On one it was demonstrated how perfectly easy it was to manage Mr. Swan's lamps; taking one lamp out of the stand and putting in a new one occupying only a few seconds, there being no binding-screws or switches to attend to. Perhaps the most interesting experiment of the evening was the transmission of pictures of natural objects by telegraph, the picture of a butterfly being most beautifully transmitted by means of a selenium plate. This was shown by Mr. Shelford Bidwell's telephotographic machine. Mr. Latimer Clark exhibited some rare books on electricity and magnetism, autographs and portraits of eminent electricians; also a portion of the original telegraph line which was laid by the late Sir Francis Ronalds in 1816, with the original model of Ronalds' telegraph, the original type cast for the Morse telegraph, with autograph of Prof. Morse, and a portion of line laid by W. F. Cooke in 1837. Mr. Cotterell of the Royal Institution exhibited a very delicate mercury electrometer on Lippman's principle, belonging to Prof. Dewar; and Mr. Robert Sabine performed some pretty experiments illustrating the cause of the motion of the mercury. Mr. Stroh showed the beautiful apparatus made by him to illustrate Prof. Helmholtz's vowel theory, and Mr. Preece performed several experiments in explanation of the remarkable sounds produced by intermittent light on solid, liquid, and gaseous matter. Mr. George Lund, of the firm of Messrs. Lund and Blockley, exhibited some synchronous clocks for the London, Chatham, and Dover Railway Company for coupling up two ordinary telegraph lines at 10 a.m., in order to send the time current. They also applied to the clock a novel automatic arrangement of their own invention, by which, at two minutes to 10 a.m. daily, the current will ring a warning bell, couple up and block against false currents two ordinary telegraph wires, then at 10 a.m. the clock sends the time-current of two seconds' duration, giving time to the clocks in circuit. Immediately upon the termination of the two seconds' current the lines will be automatically re-established as distinct lines for their ordinary telegraph purposes. All present were pleased to have the opportunity of inspecting Prof. Kennedy's engineering laboratory, where the machine for testing the strength of materials up to fifty tons was seen in operation, and various pieces of brass and copper were tested. The machine-tools were in operation, and a steam-engine of peculiar construction driving them. We look forward with interest to the scientific results we may expect to be brought to light with the testing-machine. The President (Prof. Carey Foster) showed some interesting electrical instruments; Mr. Richard Anderson a portable galvanometer for testing lightning-conductors; Profes-

sors Ayrton and Perry a variety of apparatus, as also Siemens Brothers, Newall and Co., and others. Prof. Helmholtz ended on Tuesday his visit to London, and went with Mr. Spottiswoode, president of the Royal Society, to his country house at Coombe Bank, Sevenoaks. From thence he proceeds to Dublin to receive an honorary doctor's degree from the University of that city.

THE National Fisheries Exhibition will be opened at Norwich by the Prince of Wales on the 18th inst. The delay in opening it has been caused by the necessity for enlarging the space to admit of satisfying the numerous applications that have poured in. Every point connected with the growth and nurture of fish, the modes of capturing them, the condition of the fishermen will be illustrated. The aquatic fauna of Norfolk and Suffolk will be a special feature, as also fish-eating birds. The Earl of Ducie, Viscount Powerscourt, Lord Lovat, Mr. Spencer Walpole, and Prof. Huxley, H.M. Inspectors of Fisheries; and Mr. Calcraft, Permanent Secretary to the Board of Trade, have been appointed by the Home Secretary to act as Her Majesty's Commissioners. In addition to a large number of special money prizes, Government gold, silver, and bronze medals, diplomas of honour, will be awarded by the jurors. Prof. Huxley will give an address on the occasion.

MUSEUM No. 1 in the Royal Gardens, Kew, will be reopened to the public on Easter Monday, after being closed during the winter. It has been enlarged by the addition of a new wing, terminating in a wide staircase with ascending and descending flights. The expense has been borne by the India Office in consideration of the maintenance at Kew of the botanico-economical collections recently forming part of the India Museum. The whole collections have been entirely re-arranged by the curator, Mr. John Jackson, A.L.S. On the staircase has been placed a large painted window, presented to the museum by Alderman W. J. R. Cotton, M.P. This window represents the successive stages of cotton cultivation and manufacture. Amongst other recent additions to the museum may be mentioned a series of models of farm and garden vegetables prepared and presented by Messrs. Sutton of Reading; a collection formed by Col. Pearson, who has charge of the Indian forest-students at Nancy, of the various objects manufactured in France from native-grown woods; a further series of vegetable products and manufactured articles, collected in Afghanistan by Surgeon-Major Aitchison. The collection of portraits of botanists has also been much enlarged and re-arranged. An oil portrait of Thomas Andrew Knight, F.R.S., well known for his classical researches in vegetable physiology, has been presented on behalf of the family by Sir Charles Rouse Boughton, Bart.

THE President of the United States of America has notified to the French Government his intention of appointing a special commission to preside over the arrangement of the American Section at the Electrical Exhibition. A number of commissioners have been already selected for the purpose. M. Philippart has written to M. Berger, placing at his disposal a sum of 4000*l.* for the best system presented of transporting electric force at a distance.

ON Sunday week a deputation composed of eminent representatives of French science waited upon the venerable M. Milne-Edwards to present him with a medal in commemoration of the completion of the great naturalist's work on Comparative Physiology and Anatomy. Warm congratulatory addresses were made by MM. Quatrefages, Blanchard, and Dumas, the last speaking of himself as the oldest of M. Milne-Edward's friends. In thanking the deputation the recipient of this well-earned honour was naturally much moved.

ON March 26, in presence of the Minister of the Interior, the Commission of the Observatory, several State functionaries and men of science, there were repeated at the Brussels Observatory experiments with Van Rysselberghes' telemeteorograph to prove that the registration of the meteorological elements by this instrument may be made automatically at very great distances (several hundred kilometres). The author explained to the Minister a plan of International Telemeteorography, the realisation of which would be of the greatest interest to the scientific study of the atmosphere, and which would render possible the prevision of the weather.

THE destruction caused by the Chios earthquake is even greater than we stated last week. The Constantinople Correspondent of the *Daily News* sends some interesting particulars: The temperature on the 3rd was heavy and oppressive, and the horizon was broken by broad flashes of light like sheet lightning to denote a coming storm. In all this atmospheric disturbance however the inhabitants saw nothing extraordinary, and were far from being alarmed by what they fancied would be another thunderstorm. At ten minutes to two in the afternoon a terrific shock was felt, bringing three-fourths of the houses in Chios to the ground like so many packs of cards, and burying thousand persons under the falling ruins. Then commenced a fearful scene of horror. The ground rocked and heaved, kneading the ruin already formed into an unrecognisable mass of stone. The survivors ran hither and thither, not knowing where to flee to escape the horrible fate that menaced them. They were tossed and flung about by the heaving earth, like straws in a breeze. Even those who gained the open country were by no means safe. The earthquake attacked not only the towns and villages, but worked its ravages in the hills and mountains of the island. Enormous masses of rock and earth came thundering down the hill-sides, carrying all before them, bounding across the plains, and tearing roads in the solid rocks of the mountains such as might have been formed by a torrent a thousand years old. The town presented a pitiable spectacle. Great fissures and crevices yawned in the streets, walls were falling with a crashing report, and entire buildings crumbled in fragments to the ground. In many places whole streets had disappeared, and it was hard to say where the different well-known buildings had been. The ground still heaved and tossed, bringing fresh victims to the ground at every moment, and hurrying innumerable others to destruction. It is impossible to say what the number of victims would have been if a second shock had not thrown down the ruins formed by the first and thus permitted thousands of sufferers to escape or to be rescued by others from the horrible imprisonment to which they had been condemned. The great fissures and crevices run from east to west. In the country the effects of the horrible upheaval have been even more terrible than in the town. The shocks are now, April 8, diminishing, but all there were counted 250 since the first three awful shocks which destroyed the greater part of the island. A telegram of the 12th states that earthquake shocks of considerable violence have recommenced in Chios, and it is estimated that only twenty houses now remain habitable in the whole island. Four or five villages have been totally destroyed, and in many cases the population has absolutely disappeared.

SOME slight shocks of earthquake were felt on the morning of the 5th inst. at San Cristobal, Cuba. A violent shock was felt at two o'clock on Sunday morning throughout the coast of California. Earthquakes were reported from South Hungary Wednesday last week.

THE *Daily News* Naples correspondent, telegraphing on the 6th, states that Mount Vesuvius was displaying greater activity. Abundant streams of lava were descending northwards. Two great numbers of smoke fissures had opened round the crater, some at 100 metres distance from the centre of eruption.

F. C. V. RILEY has just published, in the Second Report : United States Entomological Commission, "Further about the Natural Enemies of Locusts," meaning, of , by the latter term, the Rocky Mountain pest in particular. bservations entirely concern insect parasites. The most sting are on the habits of two species of *Diptera*, allied to *ylius*, the larvæ of which feed on the eggs of "locusts." plate (xvi.) illustrating the subject is above praise, not only count of the scientific accuracy shown in the drawings h are by the author), but also as regards the reproduction em by the "lithocaustic" process adopted by a Baltimore We have seen other plates of entomological subjects ating from the same firm, and the impression formed on our is that no other process is equally adapted for the purpose. cannot some of our own enterprising "lithographers" uce the same result?

HE following are the lecture arrangements after Easter, at Royal Institution :—Prof. Dewar, M.A., F.R.S., six lectures ne Non-Metallic Elements, on Tuesdays, April 26 to May Prof. Tyndall, D.C.L., F.R.S., six lectures on Paramag- m and Diamagnetism, on Thursdays, April 28 to June 2; . H. Morley, three lectures on Scotland's Part in English rature, on Saturdays, April 30, May 7, 14; one lecture on mas Carlyle, on Tuesday, June 7; Mr. E. C. Turner, or at the University of St. Petersburg, five lectures on the at Modern Writers of Russia, on Saturdays, May 21, 28, 4, Thursday, June 9, and Saturday, June 11. The Friday ing meetings will be resumed on April 29, at 8 p.m. Prof. . Blackie, F.R.S.E., will give a discourse on "The Lan- ge and Literature of the Scottish Highlands," at 9 p.m. ceeding discourses will probably be given by the Hon. G. Brodrick, Mr. Francis Galton, Mr. W. H. Pollock, Prof. E. Roscoe, Prof. W. G. Adams, and Prof. Dewar.

THE usual course of Mayfair Lectures will commence, under auspices of the National Health Society, on Friday, April 22, 13, Hertford Street, Mayfair. The list of lecturers will this r include the names of Dr. Siemens, F.R.S., Dr. Robert rquharson, M.P., and Prof. Fleeming Jenkin.

WE are glad to find from an announcement in the current mber of the *Quarterly Journal of Microscopical Science* that . C. T. Hudson, of Manilla Hall, Bristol, is preparing a lume for the Ray Society on the "British Rotifers." Dr. dson is known not only for his numerous contributions to our owledge of this group, but especially for his discovery and cellent illustrations of one of the most important members of e group (Pedalion). Dr. Hudson will have the advantage of e use of Mr. P. H. Gorse's beautiful drawings of Rotifers, hich that observer has placed at his disposal.

A LARGE party of the Members of the Geologists' Association ere on Saturday last conducted through the Geological Depart- ent of the British Museum (Natural History), South Ken- ngton, by Dr. Henry Woodward, F.R.S., &c., the Keeper of at Department.

Apropos of the meeting of the French Association at Algiers e *Revue Scientifique* for April 9 devotes most of its space to a ries of articles on Algeria, its colonisation, statistics, botany, nthropology, hygiene, and zoology.

THE additions to the Zoological Society's Gardens during the ast week include a Macaque Monkey (*Macacus cynomolgus*) rom India, presented by Mr. R. J. Short; a Common Para- loxure (*Paradoxurus typus*), from India, presented by Mr. C. W. . Fletcher; a Viverrine Cat (*Felis viverrina*) from India, pre- ented by Major C. R. Oxley; two Squirrel-like Phalangers *Belideus sciureus*) from Australia, presented by Mr. D. W. Barker; three Paradise Whydah Birds (*Vidua paradisea*), a Pin- tailed Whydah Bird (*Vidua principalis*), a Red-shouldered Weaver Bird (*Urobrachya axillaris*), a Red-beaked Weaver Bird (*Quelea sanguinirostris*), a Wiener's Finch (*Pytelia wieneri*), two Yellow-rumped Seed-Eaters (*Crithagra chrysopyga*) from Mozam- bique, presented by Mr. Maurice C. Angel, F.Z.S.; two Laughing Kingfishers (*Dacelo gigantea*) from Australia, presented by Mr. Edward Trelawny; an Alexandrine Parrakeet (*Palæornis alex- andri*) from India, presented by Mr. Henry Day; a Common Gannet (*Sula bassana*), British, presented by Mr. G. Randall; a Common Marmoset (*Hapale jacchus*) from South America, deposited; an Indian Chevrotain (*Tragulus meminna*) from India, six Weeper Capuchins (*Cebus capucinus*) from Brazil, four Chestnut-eared Finches (*Amadina castanotis*) from Australia, three Common Crowned Pigeons (*Goura coronata*) from New Guinea, an American Tantalus (*Tantalus loculator*) from South America, purchased; two Sclater's Curassows (*Crax sclateri* ♂ ♀) from South America, on approval; an Indian Darter (*Plotus melanogaster*) from India, received in exchange.

GEOGRAPHICAL NOTES

THE Royal Medals of the Geographical Society have this week been awarded as follows :—The Founder's Medal to Major Serpa Pinto, "for his remarkable journey across Africa, from Benguela to Natal, during which he explored nearly 500 miles of new country, defined the fluvial systems of the southern slopes of the Benguelan Highlands, and fixed the position of numerous places by a series of astronomical observations; also for the admirable account of his journey, now in course of publication in London, containing numerous original maps, tables of observations, and a large amount of valuable and exact informa- tion regarding the African interior;" and the Patron's Medal to Mr. Benjamin Leigh Smith, for his discoveries on the south coast of Franz-Josef Land during last summer, as well as for his previous expeditions along the north-east land of Spitzbergen.

AT the meeting of the Geographical Society on Monday last Mr. R. N. Cust read a paper by Col. Tanner on Kafiristan and the Siah-posh Kafirs of the Hindu Kush. The paper, which was hardly a geographical one in any sense, dealt chiefly with the inhabitants of the Valley of Dara Nur and the Chugan tribe, and to a less extent with the Kafirs, who are called "Siah- posh" from their wearing black clothes, and furnished some very interesting information regarding their manners and customs. Some philological notes had also been sent by Col. Tanner, but these will be communicated to the Asiatic Society. Some of the more striking passages in Col. Tanner's notes, if we re- member rightly, were read at the Swansea meeting of the British Association. As much interest attaches to Kafiristan and the Kafirs, and the results expected from Col. Tanner's expedi- tion were so eagerly looked forward to, it was rather disap- pointing to be told by Col. Yule that we have even now learned no more than was buried in the record of a Jesuit Missionary's travels some 200 years ago. No doubt had his health not failed at the critical moment, and compelled him to return to India, Col. Tanner would have succeeded in penetrating into Kafiristan itself, and collected valuable geographical infor- mation.

THE Society formed at Milan for commercial exploration in Africa is showing increased activity, and has despatched another expedition to Tripoli, under the command of Capt. Camperio, who is accompanied by Signor Cingia, an ex-cavalry officer. The principal objects of this expedition are the explora- tion of the Gulf of Bomba, and it will particularly examine the ports of Tobruek and Derna, not far from the Egyptian frontier. Capt. Camperio will afterwards make an attempt to penetrate into the interior of the oasis of Jazabud, in order to open com- mercial relations with its inhabitants.

WE are glad to learn that there is good hope that Col. Flatters and many of his followers, who were reported to have been massacred by the Touaregs, are still alive, though probably retained as prisoners.

DOCTORS SCHWEINFURTH AND RIEBECK, who have been travelling in Egypt, left Cairo last month to explore the island of Socotra. They do not seem to be aware that quite recently

Prof. I. B. Balfour visited the island on behalf of our Zoological Society.

THE April number of *Petermann's Mittheilungen* has a long article, with map, on Mr. A. Forrest's expedition through North-West Australia in 1879; Herr Clemens Denhardt continues his paper on Researches in Equatorial East Africa; Herr F. v. Stein gives details on the new French land fortifications, with map, and there are several interesting letters from Dr. Junker, on his experiences in the Niam-Niam country.

NO. 2, for 1880, of the *Bulletin* of the American Geographical Society contains an unusually interesting paper by Prof. J. B. M'Master, of Princeton College, on the Bad Lands of Wyoming, in which he endeavours to trace out their geological history; Mr. B. R. Curtis describes his journey round the world; and there is a historical article on Arctic Exploration by the Rev. B. F. De Costa.

THE *Bulletin* of the Antwerp Geographical Society (tome v. fasc. 6) contains a paper of considerable value by the Abbé van den Gheyn, on the present state of research with regard to the primitive cradle of the Aryan race. M. A. Baquet contributes a paper on the fauna and the chace in the countries of South America watered by the Paraguay and the Parana.

CHEMICAL NOTES

B. HEINDL has recently made investigations into the compounds of calcium chloride with ethyl alcohol, isobutyl alcohol, and amyl alcohol, and has obtained the following formulæ:—

$CaCl_2 . 3(C_2H_6O)$; $CaCl_2 . 3(C_4H_{10}O)$; and $CaCl_2 . 3(C_5H_{12}O)$.

IN continuation of his investigation of the action of hydrochloric acid on metallic chlorides, already referred to in these notes, M. Ditté describes several new compounds of this acid with mercuric chloride, viz.,

$2HgCl_2 . 4HCl . 7H_2O : 3HgCl_2 . 4HCl . 7H_2O$:
$2HgCl_2 . HCl . 6H_2O : 4HgCl_2 . 2HCl . 9H_2O$: and
$3HgCl . HCl . 5H_2O$.

MM. FOUQUÉ AND LÉVY describe (in *Compt. rend.*) the artificial preparation of the basaltic minerals peridote and labradorite, by prolonged heating of a homogeneous mixture of the constituents of a basalt rich in olivine.

DR. A. R. LEEDS has recently examined the action of nitrogen tetroxide—N_2O_4—on various hydrocarbons (*Journ.* of American Chem. Soc.). The results are interesting, and promise to be even more so. Benzene, when acted on by N_2O_4 yields mononitro-benzene, picric acid and oxalic acid; two other compounds were also obtained, but under conditions which have not been successfully realised a second time. One of these the author calls monoxy-benzene—C_6H_4O—an isomer or metamer of quinone; the other has not been purified. Naphthalene yields mononitronaphthalene, α and β dinitro-naphthalene, and two compounds which, so far as they have been examined, appear to be napthodiquinone, $C_{10}H_4O_4$, and tetroxy-naphthalene, $C_{10}H_8O_4$. The products of the action of nitrogen tetroxide on cymene are chiefly α nitrocymene (probably also a dinitro derivative) and paratoluic acid.

THE American Chem. Soc. *Journal* (vol. i. Nos. 11 and 12) contains an interesting historical sketch of the lines of discovery of ozone, and of peroxide of hydrogen, by Dr. A. R. Leeds; to these papers is added a full list of references to all publications on ozone and hydrogen peroxide; the ozone references occupy thirty-two pages, and the hydrogen peroxide, ten pages.

AN important paper by M. Étard—important both by reason of the results obtained and because of the nature of the problem attacked—on the oxidising action of chromyl dichloride, appears in *Annales Chim. et Phys.* for February. M. Étard has studied the mechanism, so to speak, of the chemical changes which occur when chromyl dichloride acts as an oxidiser; he finds that in the case of the hydrocarbons containing methyl groups attached to an "aromatic" nucleus the methyl groups are transformed into the aldehydic group (COH), and that when the aromatic nuclei are themselves attacked, quinones are produced. The chromyl dichloride forms compounds with the aromatic hydrocarbons, which may be formulated as $X . 2CrO_2Cl_2$ (where X = hydrocarbon): these compounds are then decomposed by water, and yield the products already mentioned.

IN the same journal there is a lengthy and interes... by M. W. Spring on the effects of great pressure ... bodies. It is shown in this paper—which is chiefly pr... that the particles of crystalline bodies tend to solder the... closely together at high pressures, the effect of press... analogous to that of fusion; and that amorphous bodies ... divided into two classes, viz. those which behave like ... crystalline bodies, and those which are not thus affected ... pressures.

THE influence of pressure on chemical changes is ... sidered, and it is shown that as a general rule a chemical ... which results in the production of a system the volume of ... less than the volume of the initial system, may be brought ... by subjecting the initial system to great pressure, but ... change involves an increase of volume, pressure alone ... cause the change to proceed.

M. BRAME describes (in *Compt. rend.*) experiments ... with pure hydrocyanic acid, the results of which seem ... that the bodies of animals killed by this acid (pure ... undergo decomposition even when kept for a month. ... acid remains during that time in the animal tissues, ... in the stomach, and that the acid is readily obtained ... tion from the tissues of a herbivorous, but much less ... those of a carnivorous animal.

IN continuing his researches on chemical affinity Herr ... (*Journ. für pract. Chem.*) has made the remarkable ... that while the solvent action of polybasic acids ... diminished by the presence of the normal salts of ... employed, the solvent action of monobasic acids is ... increased by the presence of the normal salts of these ... his third paper Herr Ostwald gives a large series of ... ments which show that the solvent action of free nitric ... chloric acid on calcium or zinc oxalate is increased by ... potassium, sodium, ammonium, or magnesium nitrate ... The solvent action increases proportionally to the increase ... quantity of normal salt added. Ostwald confesses that ... as yet give no thoroughly satisfactory explanation of ... menon; the explanation which appears at present most ... involves the assumption that there is a slight chemical ... between the normal salt (potassium nitrate, &c.) and ... which is being dissolved by the acid (calcium or zinc ... this small chemical change alters the "stability" of the ... system, and so increases the amount of the primary change ... solution of calcium oxalate, &c., in a given time.

FROM thermochemical data J. Thomsen regards the ... accepted formula for benzene as incorrect. The number ... by him for the heat of combustion of benzene (805,300 ... units) agrees fairly well with that calculated (800,400 ... assumption that all the carbon atoms in benzene are ... linked." The heat of combustion of the metamer of ... viz. dipropargyl, is, according to Berthelot, 853,600 ... Thomsen's caculations, assuming the formula

$$HC{\equiv}C{-}CH_2{-}CH_2{-}C{\equiv}CH$$

to be correct, give the number 888,400. The formula given for dipropargyl is therefore probably correct.

IN the last number of the German Chemical Society ... are published some recent observations on dipropargyl by ... the discoverer of this curious compound. He describes ... yet in any detail, a solid polymer produced by the action ... on dipropargyl. He also describes the tetriodide $C_6H_4I_4$, ... the octobromide $C_6H_6Br_8$.

THE arguments in favour of the number 240 being ... the atomic weight of uranium have been strengthened ... preparation by C. Zimmermann (*Berliner Berichte*) of the ... uranate of lithium, Li_2UO_4, analogous with the normal ... mates, tungstates, and molybdates.

IN the *Chem. Soc. Journ.* for March Dr. Ramsay ... his investigations on atomic and molecular volumes; he ... evidence in support of the number 7 as representing ... atomic volume of nitrogen; the generally-accepted number ... 2·3. He also shows that the molecular volumes of ... of the benzene, naphthalene, and anthracene series are ... than those calculated from the best established atomic ... of the constituent elements, and his numbers suggest that ... condensation in these compounds may very probably be ... tional to the number of carbon atoms in each molecule, ... to the manner of "linking" of these atoms.

N A METHOD OF MEASURING CONTACT ELECTRICITY[1]

r my reprint of papers on electrostatics and magnetism (§ 400, of date January, 1862) I described briefly this hod, in connection with a new physical principle, for exhibit- contact electricity by means of copper and zinc quadrants stituted for the uniform brass quadrants of my quadrant trometer. I had used the same method, but with movable cs for the contact electricity, after the method of Volta, and own quadrant electrometer substituted for the gold-leaf troscope by which Volta himself obtained his electric indi- ons, in an extensive series of experiments which I made in years 1859–61.

was on the point of transmitting to the Royal Society a paper ich I had written describing these experiments, and which I still e in manuscript, when I found a paper by Hankel in Pog- dorff's *Annalen* for January, 1862, in which results altogether ccordance with my own were given, and I withheld my paper I might be able not merely to describe a new method, but if sible add something to the valuable information regarding perties of matter to be found in Hankel's paper. I have de many experiments from time to time since 1861 by the same method; but have obtained results merely confirmatory of what had been published by Pfaff in 1820 or 1821, showing the phenomena of contact electricity to be independent of the surrounding gas, and agreeing in the main with the numerical values of the contact differences of different metals which Hankel had published; and I have therefore hitherto published nothing except the slight statements regarding contact electricity which appear in my "Electrostatics and Magnetism." As interest has been recently revived in the subject of contact electricity, the following description of my method may possibly prove useful to experimenters. The same method has been used to very good effect, but with a Bohnenberger electroscope instead of my quadrant electrometer, in researches on contact electricity by Mr. H. Pellat, described in the *Journal de Physique* for May 1880.

The apparatus used in these experiments was designed to secure the following conditions:—To support two circular disks of metal about four inches in diameter in such a way that the opposing surfaces should be exactly parallel to each other and approximately horizontal, and that the distance between them might be varied at pleasure from a shortest distance of about one-fiftieth of an inch to about a quarter or half an inch. This part of the apparatus I have called a "Volta-condenser." The lower plate, which was the insulated one, was fixed on a glass



em rising from the centre of a cast-iron sole plate. The upper late was suspended by a chain to the lower end of a brass rod liding through a steadying socket in the upper part of the case. stout brass flange fixed to the lower end of this rod bears hree screws, one of which, S, is shown in the drawing, by which he upper plate can be adjusted to parallelism to the lower plate. The other apparatus used consisted of a quadrant electrometer, nd in my original experiments an ordinary Daniell's cell, in my ater ones a gravity Daniell's cell of the form which I described n *Proc.* R.S. 1871 (pp. 253–259) with a divider by which any ntegral number of per cents. from 0 to 100 of the electromotive orce of the cell could be established between any two mutually nsulated homogeneous metals in the apparatus.

Connections.—The insulated plate was connected by a brass vire passing through the case of the Volta-condenser to the lectrode of the insulated pair of quadrants. The upper plate vas connected to the metal case of the Volta-condenser and to he metal case of the electrometer, one pair of quadrants of vhich were also connected to the case. One of the terminals of he divider, which connected the poles of the cell, was connected to the case of the electrometer, and to the other terminal was attached one of the contact wires, which was a length of insulated copper wire having soldered to its outer end a short piece of platinum. The other contact surface was a similar short piece of platinum fixed to the insulated electrode of the electrometer. Hence it will be seen that metallic connection between the two plates was effected by putting the divider at zero and bringing into contact the two pieces of platinum wire.

Order of Experiment.—The sliding piece of the divider was put to zero, and contact made and broken and the upper plate raised: then the deflection of the spot of light was observed. These operations were repeated with the sliding piece at different numbers on the divider scale until one was found at which the make-break and separation caused no perceptible deflection. The number thus found on the divider scale was the number of per cents. which was equal to the contact electric difference of the plates in the Volta-condenser.

[*Addendum*, November 23, 1880.—Since the communicatio of this paper to the British Association, I have found that a dry platinum disk, kept for some time in dry hydrogen gas, and then put into its position in dry atmospheric air in the Volta-condenser, becomes positive to another platinum disk

[1] By Prof. Sir William Thomson, M.A., F.R.S.; being a paper read before Section A of the British Association at Swansea, 1880, with additions.

which had not been so treated, but had simply been left undisturbed in the apparatus. The positive quality thus produced by the hydrogen diminishes gradually, and becomes insensible after two or three days.]

P.S.—On December 24, 1880, one of two platinum plates in the Volta-condenser was taken out; placed in dried oxygen gas for forty-five minutes; taken out, carried by hand, and replaced in the Volta-condenser at 12.30 on that day. It was then found to be negative to the platinum plate, which had been left undisturbed. The amount of the difference was about ·33 of a volt. The plates were left undisturbed for seventeen minutes in the condenser; and were then tested again, and the difference was found to have fallen to ·29 of a volt. At noon on the 25th they were again tested, and the difference found to be ·18. The differences had been tested from time to time since that day, the plates having been left in the condenser undisturbed in the intervals. The following Table shows the whole series of these results:—

Time.	Electric difference between surfaces of a platinum plate in natural condition, and a platinum plate after 45 minutes' exposure to dry oxygen gas.
Dec. 24, 12.30 p.m.	·33 of a volt.
24, 12.47 p.m.	·29 ,,
25, noon	·18 ,,
27, noon	·116 ,,
28, 11.20 a.m.	·097 ,,
31, noon	·047 ,,
Jan. 4, 11.0 a.m.	·042 ,,
11, 11.40 a.m.	·020 ,,

Mr. Rennie, by whom these experiments were made during the recent Christmas holidays, had previously experimented on a platinum plate which had been made the positive pole in an electrolytic cell with an electromotive force of one volt, tending to decompose water acidulated with sulphuric acid; the other pole being a piece of platinum wire. After the plate had been one hour under this influence in the electrolytic cell he removed it, and dried it by lightly rubbing it with a piece of linen cloth. He then placed it in the Volta-condenser, and found it to be negative to a platinum plate in ordinary condition; the difference observed was ·27 of a volt. This experiment was made on October 21; and on November 8 it was found that the difference had fallen from ·27 to ·07. Mr. Rennie also made similar experiments with the platinum disk made the negative pole in an electrolytic cell, and found that this rendered the platinum positive to undisturbed platinum to a degree equal to about ·04 of a volt. The effect of soaking the platinum plate in dry hydrogen gas, alluded to in my first postscript, which also was observed by Mr. Rennie, was found to be about ·11 of a volt. Thus in the case of polarisation by hydrogen, as well as in the case of polarisation by oxygen, the effect of exposure to the dry gas was considerably greater than the effect of electro-plating the platinum with the gas by the electromotive force of one volt.

THE NAVAL ARCHITECTS

THE session of the Institution of Naval Architects just concluded was remarkable for the number of papers on the use of steel both for shipbuilding and marine engineering. This was perhaps to be expected in consequence of the commotion among steel-users caused by the total failure of the steel plates supplied for the boilers of the Russian yacht *Livadia*. Accordingly we find four papers on this subject. The first, by Mr. Samuda, deals with the effect which the introduction of steel hulls and steel-faced armour has had upon the design of ships of war. This paper is based upon the results attained by the author with a steel corvette which he has recently constructed for the Argentine Government. The dimensions of this vessel as actually constructed, and the corresponding dimensions which must of necessity have been adopted, had the material of construction been iron instead of steel, should be carefully noted in order to appreciate the true benefits to be derived from the use of the latter material.

The vessel as actually constructed is 240 feet long by 50 feet wide; the displacement is 4200 tons, the power 4500 horses, and the coal-supply 650 tons, which is sufficient to allow her to steam 6000 miles at a speed of 8 knots, or 4300 miles at a speed of 10 knots. The speed which it is expected will be attained on the measured mile is 13½ knots. If the vessel had been built of iron and cased with iron armour, the speed and shot-resisting power remaining the same, the dimensions would have been as follows:—Length, 260 feet; breadth, 55 feet; [illegible] 5200 tons; power, 5000 horses; and coal-supply, [illegible] This example is a very good illustration of the great [illegible] which naval architects will derive from the use of steel. It should be remarked, which comes most opportunely to [illegible] powerful ordnance; for not only has the steel-[illegible] about 25 per cent. more resisting power than an equal [illegible] of iron, but also the weight saved in the hull and [illegible] the use of steel enables a greater quantity of [illegible] carried.

The second paper on steel was by Mr. W. Pole, [illegible] Engineer Surveyor to Lloyd's Registry, "On the Cause [illegible] Failure of the Steel Plates supplied for the Boilers of the [illegible] Steel, as is well known, had formerly a bad repu[illegible] treachery and uncertainty of behaviour. Lately [illegible] more intimate knowledge of the methods of manufac[illegible] better acquaintance with the processes of working [illegible] quite removed this impediment to its general introduc[illegible] failure therefore above referred to came as a surprise [illegible] builders, and the circumstances demanded and receive[illegible] searching inquiry at the hands of the engineer officers [illegible] It was found that samples cut from the broken plat[illegible] every test demanded by Lloyd's, the Admiralty, and [illegible] of Trade. The tensile strength proved to vary betwee[illegible] narrow limits of 26·1 and 28·3 tons per square [illegible] elongation after fracture of samples 8 inches in leng[illegible] from 27·3 to 34·3 per cent. Nevertheless in spite of [illegible] rently excellent quality of the plates, it was found that [illegible] had been punched and worked into place they had [illegible] brittle as to be unable to stand the hydraulic proof [illegible] is usual to subject boilers, and in some instances even [illegible] cracked before the hydraulic test was applied. T[illegible] investigations of Mr. Parker proved that wherever [illegible] the plates were punched, the material became so [illegible] break into pieces under the blow of an ordinary sledg[illegible] the tensile strength dropped to 18·4 tons per square [illegible] the extensibility disappeared altogether.

Specimens were next subjected to chemical analysis [illegible] result of proving that, the material was from the che[illegible] of view far from homogeneous. A portion of the pl[illegible] 8 inches long by 4 inches wide, was carefully freed f[illegible] grinding, and successive layers were planed off from [illegible] the other. Each layer was one-sixteenth of an inch [illegible] and they were numbered in succession as they were [illegible] The result of analysis showed that the quantities [illegible] manganese, sulphur, and phosphorus varied in an [illegible] degree. These differences in the chemical compos[illegible] ever, did not satisfactorily account for the behaviour [illegible] It was not till the appearance of the fractures exp[illegible] the material had not been properly worked under [illegible] and rolls, that a really satisfactory solution of the [illegible] arrived at. "A piece cut from the fractured plate was [illegible] red heat and rolled to half its original thickness. [illegible] then cut from this ½ inch plate, and punched with [illegible] diameter, being one half the size of those in the [illegible] This extra work on the material seemed to raise [illegible] appreciably, the strips being found to bend well after [illegible] several of them bending to right angles, and only [illegible] breaking short off, while none of them showed such [illegible] nary signs of brittleness as were observable in the mat[illegible] of the original thickness. Three pieces tested for ten[illegible] after rolling broke under a stress of 33 tons, 34·7[illegible] 32·3 tons per square inch respectively, with an el[illegible] 8 inches of 12 per cent., 11·25 per cent., and 17·5[illegible] respectively, the last-mentioned specimen being annea[illegible]

Mr. Parker concludes his paper by expressing the [illegible] the facts which he was able to lay before the meeting [illegible] to allay alarm and to strengthen confidence in the [illegible] steel for constructive purposes. When it is considered [illegible] enormous quantity of this material is now being used [illegible] struction of marine boilers, as well as for the hull [illegible] this wish will be heartily re-echoed. In the spring [illegible] there were only two marine boilers of the modern Ad[illegible] mild steel in existence. Within twelve months [illegible] that date 120 steamers had been fitted with boiler[illegible] material, and during the same period in the following [illegible] vessels more. At the present moment there are [illegible] 1100 steel boilers in use in steamships, weighing [illegible] 17,000 tons.

eel was by Mr. J. R. Ravenhill, and improvements which have recently been gs. Many portions of machinery and quite recently were invariably made of rmed of cast steel, with the attendant ngth and saving in weight.

resting paper of the four was that by e eminent French naval architect, "On for the Construction of the Hulls of avy." The French were undoubtedly this material into the national navy; ence of it is longer than our own, acquired the same confidence in its use country. For instance, we are in the e entire hulls of ships, including the steel; the French, on the other hand, ll work which has to be exposed to the e reason advanced is that they find that salt water corrodes with far greater Berrier Fontaine quotes as examples nd the *Tromblon*, the hulls of which, have both given proof of rapid and *Tromblon* was launched at Toulon on emained afloat till October 27 of the period of nine months it was found ree times, that it is to say, about every e hull, the plates being rapidly and ly in the neighbourhood of the water- is corrosion went on with such unusual ase came to pass the *Tromblon* into the essary to haul her on to a ship instead The whole subject of the corrosion of involved in great mystery, and no two gree about the cause. In the English believed that it is due to the presence es of portions of black oxide, which o many active galvanic couples, which te corrosion, and hence great care is traces of this oxide before the plates ay be the cause, it is perfectly certain English builders does not tally with ature in this particular. Certain cases ubt occurred in this country, and the ample in point; but as far as present es are the exception instead of the rule. ves an interesting account of the trials e French dockyards for the working of the early difficulties which the work- hich have been successfully overcome. of manufacture adopted in France, it results are obtained from the Bessemer s, so much so that when contracts are fied that the material is to be prepared ocesses. In some works the Siemens the superior sorts of steel, and the l for inferior descriptions, such as rails, tly the opposite takes place. In this , it is almost universally the rule to ces for the production of mild steel al for boiler purposes.

ND MOVING SANDS

ade to the Russian Society of Natu- has given a description of the dunes is-touryetsk, at the eastern end of the hole of the isthmus between the Gulf etsk is covered with dunes which have which are close by the sea-shore are overed with vegetation, parallel to one the form of a straight line, while those east are true dunes, built up of sand y have the direction north and south, of a hundred feet. Several of them e-forests and with moss, while others The latter are constantly brought into and south of the Sestra River a high e houses of the working men of the r. This dune, about 700 feet broad, al houses, and it is always advancing further, forming smaller parallel dunes fifteen feet high; its western side is covered with numerous excavations, from which the wind has taken the sand to move it further east. M. Sokoloff, while agreeing with the well-known classification of dunes established by the explorer of Sahara, M. Vatonne, thinks that the dunes of the deserts, which owe their origin to the action of wind, might be very easily distinguished from the mostly lower ridges which appear on the sea-shores under the influence of waves, these last usually having the form of straight lines, whilst the true dunes always have a semicircular form. M. Severtzoff observed after this communication that in the steppe of Kyzyl-koum, true dunes often have the same form of parallel, quite straight ridges. However, having at their origin a circular form which is so characteristic of the *barkhani* of the steppe, they lose by and by this form, and several smaller dunes, uniting together at their ends, take the form of a long straight ridge perpendicular to the prevailing direction of wind. M. Moushketoff, who has made a close acquaintance with the sands of Central Asia, observed that these sands, which are all sporadic, being spread among older formations, are very different as to their extent, their stratigraphical and petrographical characters, and their origin. They might be subdivided into three different classes:—1. Those which have a marine origin and which might be observed on the south-eastern shores of Lake Aral, and especially in the Kara-koum steppe. They are about 250 yards and 70 feet high, and mostly parallel to the shore. They are typical marine dunes, but their extension closely depends upon the extension of the Aralo-Caspian formation, the fossils of which are always found broken in these sands. 2. The fluvial dunes, which are very common in the valleys of the Amou, Syr, Sourkhan, and others; their height rarely exceeds 10 to fifteen feet, and their length is from 100 to 150 feet; their sand is steel-gray, and contains gypsum and clay. 3. The *barkhani* are subaerial formations; they prevail in the central part of the steppe Kyzyl-koum, but are rather rare in the Kara-koum steppe. They have the form of a sickle, and are somewhat conical, their maximum height being as much as 20 to 30 feet; their slopes are very different, that which is under the influence of the wind having an inclination from 5 to 13 degrees, whilst the other slope is short and steep, the inclination reaching sometimes as much as 45 degrees; they consist of a dirty-yellow or red sand, owing to their origin in the Tertiary sandstone, or sometimes in other harder rocks, as for instance, in the valley of the Ili River. Sometimes typical *barkhani* are met with among dunes, being a secondary formation arising out of the marine dunes. As to the plantations of trees on dunes, M. Moushketoff thinks that it would be far more rational first to determine whence the sand is brought by the wind, and to make the plantations of trees or bushes, according to the chemical character of the sand on this place, instead of making them on the dunes themselves.

UNIVERSITY AND EDUCATIONAL INTELLIGENCE

MANCHESTER.—We learn that the Council of the Owens College proposes shortly to establish an independent Chair of Applied Mathematics.

EDINBURGH.—The tercentenary of the University of Edinburgh will be celebrated in 1883. The senatus are to invite representatives from other universities to be present; they also propose to bring out a history of the University during the first 300 years.

THE winter session of the College of Agriculture, Downton, Salisbury, was brought to a close on Wednesday, when the prizes were presented by Earl Nelson, who dwelt at considerable length on the present state and future prospects of British agriculture, taking a very hopeful view of the latter. The High Sheriff of Wilts warmly advocated such a combination of science with practice as was in vogue at the College. The Scholarship offered for competition amongst students who have completed their first year at the College was awarded to Mr. Louis Johnstone, son of Sir Harcourt Johnstone, Bart., Hockanss Hall, Scarborough, the Hon. Victor A. N. Hood *proxime accessit*.

SOCIETIES AND ACADEMIES

LONDON

Royal Society, March 31.—"Permanent Molecular Torsion of Conducting Wires produced by the Passage of an Electric Current," by Prof. D. E. Hughes, F.R.S.

In a paper on "Molecular Electro-Magnetic Induction," presented to the Royal Society (March 7, 1881, I gave a description of the induction currents produced by the torsion of an iron wire, and the method by which they are rendered evident. The electro-magnetic induction-balance there described is so remarkably sensitive to the slightest internal strain in anywise submitted to it, that I at once perceived that the instrument could not only determine any mechanical strain such as torsion or longitudinal stress, but that it might indicate the nature and cause of internal strains. Upon putting the question to it, Does the passage of electricity through a wire produce a change in its structure? the answer came, It does, and that to a very considerable extent; for an iron wire adjusted to perfect zero, and which would remain free from any strain for days, becomes instantaneously changed by the first passage of a current from a single cell of a Daniell's battery; the wire has now a permanent twist in a direction coinciding with that of the current, which can be brought again to zero by mechanically untwisting the wire, or undoing that which the passage of electricity has caused. Before describing the new phenomenon, I will state that the only modification required in the apparatus is a switch or key by means of which the telephone upon the wire circuit is thrown out of this circuit, and the current from a separate battery of two bichromate cells passed through the wire alone, at the same time, care being taken that no current passes through the coil, but that its circuit should remain open during the passage of the electric current through the wire under observation; an extra switch on this circuit provides for this. The reason for not allowing two currents to react upon each other, is to avoid errors of observation which may be due to this cause alone. When, however, we take an observation, the battery is upon the coil and the telephone upon the wire alone. An experiment thus consists of two operations. First all external communications interrupted, and an electric current passed through the wire; and, second, the electric currrent taken off the wire, and all ordinary communications restored. As this is done rapidly by means of the switches, very quick observations can be made, or if desired the effects of both currents can be observed at the same instant.

Now if I place upon the stress bridge a soft-iron wire ⅛ millim. diameter, 25 centims. long, I find, if no previous strain existed in the wire, a perfect zero, and I can make it so either by turning it slightly backwards or forwards, or by heating the wire to a red heat. If I now give a torsion of this wire, I find that its maximum value is with 40° torsion, and that this torsion represents or produces electric currents whose value in sonometric degrees is 50; each degree of torsion up to 40 produces a regular increase, so that once knowing the value of any wire, we can predict from any sonometric readings the value in torsion, or the amount of torsion in the opposite direction it would require to produce a perfect zero.

If now I place this wire at zero, and thus knowing that it is entirely free from strain I pass an electric current through it, I find that this wire is no longer free from strain, that it now gives out induction currents of the value of 40, and although there is no longer any battery current passing through this wire that the strain is permanent, the outside coil neither increasing nor diminishing the internal strain it has received by the passage of an electric current through the wire; upon giving a torsion to the wire in one direction, I find the inductive force increase from 40 to 90, but in the other direction it is brought to zero, and the amount of torsion, some 35°, required to bring the wire again to zero represents exactly the twist or strain that had been produced instantaneously by the passage of an electric current. If I repeat the experiment, but reverse the battery current sent through the wire, I find an opposite twist of exactly the same value as previously, and that it now requires an opposite torsion to again bring the wire to zero. It is not necessary however to put on an equal opposite torsion on wire to bring the currents to zero, for as I have shown in my late paper, the sonometer not only allows us to measure the force and indicate its direction, but allows us to oppose an equal electric current of opposite name, thus producing an electrical zero in place of the mechanical one produced by torsion.

Evidently here there has been a sudden change in the structure of the wire, and it is a twist which we can both measure and reproduce. The question at once becomes, Has a molar twist been given to the wire such as would be detected by the arm or free end of the wire, or a molecular change leaving no trace upon its external form of what has passed?

It will be found that, notwithstanding that it requires some 40° of torsion to annul the effects of a passage of an electric [illegible] no visible movement nor any tendency of the free end [illegible] in the direction of the twist it has received can be observed believe however to have noticed a slight tremor or movement half a degree, but as I could not always reproduce it, and [illegible] so slight compared with the 40° of internal twist, I [illegible] taken it into account, for if the wire is firmly fastened [illegible] ends no molar torsion being possible, except an elastic [illegible] which would instantly spring back to zero, the current once [illegible] produces its full effects of twist and it is permanent. The molecules have in some extraordinary way rearranged themselves into a permanent twist, without the slightest external evidence of so great a change having taken place. An equally remarkable change takes place in aid of, or against (according to direction of current) an elastic permanent strain. Thus, if I first put the wire under 40° right-handed permanent torsion, I find its value is 50. Now, passing the positive of battery through its fixed and negative to fixed end, the induction currents rise at once to value to 90; if, now, the negative is momentarily passed to the free end and positive to fixed end the induced currents at once fall to 10, and these effects remain, for on taking off the elastic torsion the wire no longer comes to zero, but has a twist value produced by the current.

Tempered steel gave only one or two degrees against the soft iron, but supposing this might be due to its greater rigidity, I carefully brought the wire to zero, and then with the first contact only. I found then that the first contact gave a value of 40, but the second and following only one or two. On bringing the wire back to zero by a momentary touch of the magnet a continued force of 40, or if constant reversals were used instead of a simple contact, there was constant production of similar great molecular change by the passage of a current in steel as well as iron.

I can find no trace of the reaction of the wire upon the magnetism of the earth, as in all positions the same degree of zero was obtained, if great care is taken that the wire is absolutely free from longitudinal magnetism; there is however a slight reaction upon its own return wire if brought within a certain distance of the wire, and this reduces the twist some 10°. The maximum effects are obtained when the return wire is at more than 25 centims.; thus the action is not one produced by reaction, but by direct action upon its internal structure.

Copper and silver wires so far show no trace of the action. I believe, however, that a similar strain takes place in all cases, and I have obtained indirectly indications of this fact; I hope however, to verify this, would require a different mode of observation from the one I have described, and I have not yet perfected the apparatus required.

It seemed probable that if I approached a strong permanent magnet to the wire, I should perceive a twist similar to that produced by the passage of a current; but no such effect can be observed. But it has a most remarkable effect of the kind in bringing to zero a strain produced by the current, and to a wire which pole, the effect was the same. Thus, a strain of 40° which remains a constant, instantly disappears upon the presentation of longitudinal magnetism, and I have found this method of reducing an iron wire to zero of strain far more effective than any other method yet tried, such as vibrations, heat, [illegible]

It will be seen from this that the molecular arrangement up by magnetism is very different from that produced by the passage of an electric current. It evidently has a strength its own, else it would not have instantly destroyed the strain left by the passage of electricity if it had not taken new form, as rendered evident in the longitudinal magnetism which we could at once perceive on the wire. This point, however, belongs to a separate investigation, and I hope apparatus will aid me later in throwing some new light this subject.

Another method of reducing the wire to zero, after the passage of a current, is to keep the wire in a constant state of vibration. It requires in time about one minute to bring it to zero, but on the contrary, I set the wire vibrating during the passage the current, the permanent twist becomes greater and more difficult to reduce to zero.

If a wire which has internal strains is heated to redness the strains almost entirely disappear, and I can thus reduce by heat a strain which a current had produced, but heat, whilst allowing greater freedom and motion of its molecules, does not produce an internal strain being set up, for whilst heat can reduce the wire to zero, after the passage of the current, the effect is increased. If, during the time that the wire is at a red heat

t is passed in the same time, and at the same instant we ff the current and the external heat, the wire when cold : found to have a higher degree of strain than previously le with the wire when cold.

have seen that both mechanical vibrations and heat can : the wire to a zero, but its action is very slow, several es being required; but the action of electricity in producing manent twist is exceedingly quick. I have found that a contact, whose duration was not more than 0·01 of a l, was equal to that of a prolonged contact of several es, and magnetism was equally as quick in reducing this to zero. And it is the more remarkable when we con the very great mechanical force required by torsion of the to untwist the strain produced in an instant of time by icity.

e results I have given are those obtained upon soft iron of ½ millim., but I have experimented with different sizes 3 millims. diameter. The results with 1 millim. diameter quite as evident as the ½ millim., but on the 3 millim. wire rain was reduced to 25° instead of 50°, owing to the extreme ity and low electrical resistance compared with my small ry wires. On a telegraph line, the wire of which is almost ely of iron, there must be a very great strain set up, which ver would remain a constant, except where reversed currents sed, and in this case a constant movement of the molecules e wire must be the result.

believe it to be most important that we should determine, as s we can by experimental research, the nature of all mole- changes produced by electricity and magnetism, and in this f I am happy in being able to bring this paper before the al Society.

hemical Society, April 7.—Dr. Russell in the chair.—The wing papers were read:—On the organic matter in sea- r, by W. Jago. The author concludes that the organic ter of sea-water is much more capable of resisting oxidising ts than that present in ordinary fresh water, and that it is bably organised and alive.—On the action of compounds ical to bacterial life, by W. M. Hamlet. The cultivating ls used comprised Pasteur's fluid, beef tea, hay infusion, e, brewer's wort, and extract of meat; these were sterilised oiling for ten minutes in Pasteur's flask, cooled with suitable autions, and then seeded with hay solution, and the sub- ce under examination added. Many gases, &c., were tried. orine and hydric peroxide were fatal to bacteria, while chloro- n, creosote, carbolic acid, salicylic acid, &c., hindered their elopment, but did not destroy them.

nthropological Institute, March 22.—F. W. Rudler, .S., vice-president, in the chair.—The election of George Waterhouse was announced.—Mr. R. W. Felkin exhibited a es of photographs of scenes and natives of Central Africa, en by Herr Buchta.—Prof. Flower, F.R.S., exhibited a col- ion of crania from the Island of Mallicollo in the New brides, which had been lately presented to the Museum of Royal College of Surgeons by Mr. Luther Holden. The uliar conformation of the heads of the people of this island racted the attention of Capt. Cook and the naturalist Forster, o accompanied the great navigator on his second voyage, and o writes that "the depressed and backward inclining forehead ises an appearance in the looks and countenances of the tives similar to those of monkeys." Yet Cook bears testi- ny to the activity, intelligence, and honesty of this "ape-like ion," as he calls them. A few years ago Mr. Busk described ne skulls collected in the island by the late Commodore odenough, and found that they all showed signs of having dergone alterations in form from pressure applied in infancy. e present collection corroborates Mr. Busk's views; some of skulls being deformed to a remarkable degree, and closely embling the well-known Peruvian crania from the neighbour- od of Lake Titicaca. This is the more remarkable, as on no other the numerous islands of the neighbouring ocean is the prac- e known to exist. Besides the deformed crania the collection ntained several monumental heads, said to be those of chiefs. these the features are modelled in clay upon the skull, appa- ntly with the intention of preserving a likeness of the dead rson; the face is painted over with red ochre, artificial eyes troduced, and the hair elaborately dressed and ornamented ith feathers. In one case the hair had been entirely removed, d a very neatly-made wig substituted. The head thus pre- ared is stuck upon a rudely-made figure of split bamboo and ay, and set up in the village temple, with the weapons and small personal effects of the deceased. This is a custom not hitherto known to exist among the Mallicollese, and its motive is not completely understood, but it is obviously analogous to many others which have prevailed throughout all historical times and in many nations, manifesting itself, among other forms, in the mummified bodies of the Ancient Egyptians and the marble busts over the mouldering bones in Westminster Abbey.—Mr. Joseph Lucas read a paper on the ethnological bearings of the terms Gipsy, Zingaro, Rom, &c.

Zoological Society, April 5.—Prof. W. H. Flower, LL.D., F.R.S., president, in the chair.—Mr. Sclater exhibited five bird's skins obtained by the Rev. G. Brown, C.M.Z.S., on the Island of Rotumeh, and presented by him to the *Challenger* Expedition. Mr. Sclater also exhibited specimens of two new species of birds from New Britain, belonging to the Museum Godeffroi, which he proposed to call *Trichoglossus rufigularis* and *Ortygocichla rubiginosa*.—Mr. H. E. Dresser exhibited and made remarks on a specimen of *Saxicola deserti* killed in Scotland, and a specimen of *Picus pubescens* believed to have been killed in Normandy.—Mr. W. A. Forbes, F.Z.S., read some notes on the external characters and anatomy of the Californian Sea Lion (*Otaria gillespii*), and exhibited some coloured drawings of this animal.—Prof. Flower, F.R.S., read a note upon the habits of the Manatee, chiefly in reference to the question as to whether this animal had the power of voluntarily leaving the water for the purpose of feeding on the herbage of the banks, as stated by many authors, and as supported by a communication from the late Mr. R. B. Dobree, notwithstanding which Prof. Flower considered the evidence upon which the statement was based to be very unsatisfactory.—A paper was read upon the same animal by Miss Agnes Crane, consisting of observations upon the Manatees lately living in the Brighton Aquarium.—Dr. A. Günther, F.R.S., read an account of the Amphisbænians and Ophidians collected by Prof. Bayley Balfour in the Island of Socotra. A new form of snakes allied to *Tachymenis* was named *Dityophis vivax*, a new species of *Zamenis* was named *Z. Socotræ*, and a new form of Amphisbænian *Pachycalamus brevis*.—Mr. W. T. Blanford, F.R.S., gave an account of six species of lizards which had been collected by Prof. Bayley Balfour in Socotra; of these the three following appeared to be undescribed:—*Hemidactylus homœolepis*, *Pristurus insignis*, and *Eremias Balfouri*.—Mr. Charles O. Waterhouse read a paper on the coleopterous insects which had been collected by Prof. Bayley Balfour in Socotra. The number of species of which examples were collected was twenty-four, and showed that the fauna of Socotra, judging from this collection, was distinctly African. Twelve of the species appeared to be new.—A communication was read from Prof. J. O. Westwood containing observations on two species of Indian butterflies, *Papilio castor* and *P. pollux*.—A communication was read from Mr. Edgar A. Smith, containing some observations on the shells belonging to the genus *Gouldia* of C. B. Adams.—Mr. Sclater read the fifth of his series of notes on the birds of the vicinity of Lima, Peru, with remarks on their habits by Prof. Nation, C.M.Z.S. A new species of *Buarremon*, of which an example was in the collection, was proposed to be dedicated to its discoverer as *B. Nationi*.—Mr. G. E. Dobson read some notes on certain points in the muscular anatomy of the Green Monkey, *Cercopithecus callithrix*.

EDINBURGH

Royal Society, March 21.—Sir Wyville Thomson, vice-president, in the chair.—Prof. Geikie communicated a paper by Mr. C. A. Stevenson, B.Sc., on the earthquake of November 28, 1880, in Scotland and Ireland. The main conclusions at which the author arrived were the following:—The centre of the disturbance was at a point some thirteen miles south-west of Fladda, in the continuation of the line of the fault that lies along the great glen which stretches in a south-westerly direction from Inverness. The disturbance was felt over an area of 19,000 square miles, extending as far east as Blair Athole, as far north as the Butt of Lewis, and as far south as Armagh in Ireland. The undulation was everywhere of an up-and-down character; its breadth was estimated at 1100 feet, and its velocity seemed to vary from 3·75 to 7·75 miles per minute, having a mean value of 6·75 over the sea and 4·68 over the land. The accompanying rumbling was not heard at all the stations, and appeared to have been best heard where but little soil covered the hard dense substratum of rock. The disturbance was felt better over the older rocks. Noises were not heard outside a radius of 38 miles from the centre, except in the north of Ireland, where however it was

suggested that the noise was due to the indirect action of the earthquake in causing a secondary local disturbance.—Mr. P. Geddes read his first communication on the classification of statistics. After pointing out the utter confusion that exists in many of the national classifications of the present time, the author criticised the arrangements suggested by Deloche and Mouat, which were equally unsatisfactory, because of their unscientific and artificial methods. Any classification, to be natural, must be based upon some broad principle common to all kinds of communities or societies. A fundamental meaning must therefore be attached to the word society—a definition given to it that will include societies of all kinds of organisms. Such a definition must obviously take account of the vital functions of organisms in relation to the matter and energy of the universe. We have thus matter and energy on the one hand, organisms on the other. Mr. Geddes, confining himself meanwhile to the first of these two great divisions, proceeded to classify the sources of energy, adopting the classification given by Prof. Tait in his Thermodynamics, and showing how naturally such things as food, fuel, machines, &c., fell into their places in such an arrangement. He then considered the classification of sources of matter used for other than energy-properties, taking for this purpose the well-known three-fold division into minerals, vegetables, and animals. The development of ultimate products through their successive phases of raw material, manufacture, exportation, trade, &c., and the classification of all products under the three chief headings of potential, mediate, and ultimate, completed the one aspect of the statistical method in so far as it related to the matter and energy of the universe. It still remained however to take account of the loss, or more properly the degradation or dissipation, suffered. The classification must indicate not only the kind of loss, *e.g.* whether in raw material, in manufacture, in trade, in ultimate product, or in remedial effort, but also the agency that was the direct cause of the loss, whether physical, as earthquake, flood, storm, &c.; or biological, as insects, fungi, &c.; or social, as crime, war, or folly.—Mr. T. Muir communicated three mathematical notes: on Prof. Cayley's theorem regarding a bordered skew determinant; on the law of extensible minors in determinants; and on a problem of arrangement.—Mr. J. Y. Buchanan read a short paper on the oxidation of ferrous salts.—Prof. Tait made a brief communication on some space loci.

PARIS

Academy of Sciences, April 4.—M. Wurtz in the chair.—M. de Quatrefages presented an example of the Edwards Medal.—The following papers were read:—On micrometric measurements during the transit of Venus of 8 December, 1874, by M. Puiseux. These measurements (393 in number and in five categories) at St. Paul and Pekin fairly agree, though the conditions were unfavourable, and give for the parallax 9″·05.—On the same subject, by M. Mouchez. He considers the method is to be strongly recommended for 1882.—Note on the methods of Wronski, by M. Villarceau.—On photographic photometry and its application to study of the comparative radiating powers of the sun and of stars, by M. Janssen. A shutter with triangular aperture is made to pass with uniform motion of known rate before a sensitised plate; this gives (with light) a series of shades on the plate, decreasing from the base side to the apex side. To compare the sensibility of two plates, differently prepared, or the photogenic intensity of two sources (using two like plates) the points of equal shade on the plates are noted. (The photographic intensity does not increase as rapidly as the luminous intensity.) For the sun he finds the time of action (with gelatine bromide of silver plates) must be reduced to $\frac{1}{1000}$ sec. to give the most rapid variation in the opacity. The sides of the slit are curved (for a special reason). A series of circular images of stars are obtained by putting the plate a little out of focus.—On alcoholate of chloral, by M. Berthelot.—On lightning flashes without thunder, by M. d'Abbadie. He observed such quite near, in a fog, when in Ethiopia.—On the combinations of phtalic anhydride with hydrocarbons of the benzene series, by MM. Friedel and Crafts.—Note on chalcomenite, a new mineral species (selenite of copper), by MM. des Cloizeaux and Damour. This is from near Mendoza in the Argentine Republic.—Researches on changes of state near the critical point of temperature, by MM. Cailletet and Hautefeuille. By colouring carbonic acid the liquid is rendered always visible. It is found that Andrews's undulatory striæ dissolve blue oil of galbanum, so that they are produced by streaks of liquefied carbonic acid. Neither in disappearance of a meniscus through compression, nor in change of state at the critical temperature does matter pass by imp[erceptible] the liquid to the gaseous state.—Magnetic [pro]iron of Santa Catharina, by Prof. Lawr[ence] fragments are very feebly affected by a m[agnet] been flattened on a steel surface with a stro[ng] red hot.—Attenuation of effects of virulen[ce] of small quantities of virus, by M. Chauv[eau] elected Member in Geometry in room of th[e] On the winter egg of phylloxera, by M searches on the causes which enable the vin[e] in sandy soils, by M. Saint-André. Weak a soil seems to be the direct or indirect cau[se] vines.—On the bismuthine produced by c[ar] M. Mayençon.—On functions proceeding f[rom] by M. Halphen.—On a new application properties of Fuchsian functions, by M. Fo[ur] tions between solar spots and magnetic va[r] Tables for 1880 are given. The solar curv[e] quickly rising again; a maximum may be ex[pe] The increase of magnetic declination for formula, 0°·99 by observation.—On the Mr. Crookes.—Luminous intensity of incandescent platinum, by M. Violle. ranging from 775° to 1775° he constructs change of volume accompanying the galva by M. Bouty. It is always possible in el salt to diminish the intensity of current be[yond] that the compression produced by the de into attraction (the metal dilating inst[ead] solidifying).—On the voltaic conductivit[y] M. Blondlot. He describes an experim[ent] putting the conductivity of gases beyond parts of the apparatus are constantly op[erated] the internal discharges of electric conde[nser] The laws of the phenomenon are enu[nciated] mirrors, by M. Laurent. A common thickness may be rendered magical by applying the end of a heated brass tube the tube is imaged.—On hydrosulphite of berger.—On some new processes of dess[ilvering] solutions, by M. Scheurer-Kestner.—On tals of lead chambers, by M. Sulliot. Fo[rmation] he places in them porous vessels contai[ning] acid, and to attenuate the irritating acti[on] vessel is placed in another containing eth[er] ease odorous gases are drawn through a [tube] ened with nitrous sulphuric acid.—On amylamines from the active amylic alcoh[ol] Mr. Plimpton.—Action of perchloride o[f] tylic aldehyde, by M. Œconomides.—P[repa]acetal, by the same.—On the products phony, by M. Renard.—Artificial repr[oduction] dolerites, and meteorites of ophitic stru[cture] and Levy.—On the Devonian formation Gilly (Saône-et-Loire), by M. Jullien.

CONTENTS

THE NEW MUSEUM OF NATURAL HISTORY . . .
TEXT-BOOK OF MECHANICS . . .
CONSCIOUS MATTER. By GEORGE J. ROMANES . . .
LETTERS TO THE EDITOR:—
Study of the Physical Nature of the Sun.—[illegible]
Winter Gnats (Trichocera).—Rev. A. E. Ea[ton]
Australian Plants in India.—Dr. G. Bidie .
The Tide Predicter.—EDWARD ROBERTS .
"The Oldest Picture in the World."—Pr[of.]
F.R.S. . . . .
Probably New Variable Star.—JOHN BIRM[INGHAM]
Concealed Bridging Convolutions in a Hu[man]
CARTER . . . . .
Sound of the Aurora.—M. L. ROUSE . . .
PERIODIC OSCILLATIONS OF BAROMETRIC PRES[SURE].
J. ALLAN BROUN, F.R.S. . . . .
THE ETNA OBSERVATORY (*With Illustration*) .
MODE OF MASKING OR CUTTING OFF SHADE[S].
REVOLVING APPARATUS ON ANY DESIRED
MEANS OF A RECIPROCATING SCREEN. By T[HOMAS]
CHLOROPHYLL. By SYDNEY H. VINES. .
NOTES . . . . .
GEOGRAPHICAL NOTES . . . . .
CHEMICAL NOTES . . . . .
ON A METHOD OF MEASURING CONTACT ELEC[TRICITY].
WILLIAM THOMSON, M.A., F.R.S. (*With Illu[stration]*)
THE NAVAL ARCHITECTS . . . . .
DUNES AND MOVING SANDS . . . . .
UNIVERSITY AND EDUCATIONAL INTELLIGENCE
SOCIETIES AND ACADEMIES . . . . .

NS TO "NATURE."

	£	s.	d.
	1	8	0
	0	14	6
	0	7	6

ited States, the Continent, and stal Union :—

	£	s.	d.
	1	10	6
	0	15	6
	0	8	0

DVERTISEMENTS.

1 2s. 6d., 9d. per Line after.

	£	s.	d.
rter Column	0	18	0
Column	1	15	0
	3	5	0
	6	6	0

ble to MACMILLAN & CO.

ARD STREET, STRAND, W.C.

F SOCIETIES.

LONDON

DAY, APRIL 14.

ns, at 8.—On the Application of Electricity Semiotic and other purposes: Sir George e Galvanometer for Strong Currents; Pro- on Transmission Dynamometer; Professor

On the Geometric Curvature of a Curve, as —On Operative Symbols in the Differential

SDAY, APRIL 20.

—On the Frequency and Duration of Rain: s of Experiments made at the Kew Observ- 's Barometers: G. M. Whipple, F.R.A.S. ton's Table of the Barometric Height at ity: G. M. Whipple, F.R.A.S.

DAY, APRIL 21.

e Genera of Plants from Socotra: Prof. water Shells of Australia: Edgar A. Smith: Lister, and certain Allied Species. II. d Variation in the Branchial Sac of Simple

Fractional Distillation, Part II.: F. D. lydes. Peroxide by means of Potassic Per- ne Oxidation of Sulphurous Acid: H. B.

—On the History of Theatres in London, s to their Closing in 1642: Frederick G. ationes Jewish and Christian Baptisms in ces.

DAY, APRIL 22.

4.8.—On the Histology of the Ossifactory I. Charters White, M.R.C.S.

AN COINS. Catalogue

GEORGE SIM, F.S.A. Scot., Edinburgh.

& CO., LONDON.

LIGHTNING CONDUCTORS.

Experience, accumulated since the time of Benjamin Franklin, proves conclusively that a Conductor made of Copper of adequate size is the best of all appliances for the protection of every description of building from the destructive effects of lightning.

NEWALL & CO.'S

PATENT COPPER LIGHTNING CONDUCTOR,

As applied to all kinds of Buildings and Shipping in all parts of the world with unvarying success; is the most Trustworthy, most Effective, and also the Cheapest Conductor ever offered to the public.

It is simple in its application, no insulators being required, and it costs only one shilling per foot for the standard size, which ensures safety in any form.

R. S. NEWALL & CO., 130, STRAND, W.C.
96, WATERLOO ROAD, LIVERPOOL.
62, ANDERSTON QUAY, GLASGOW.

MANUFACTORY—GATESHEAD-ON-TYNE.

NOTICE OF REMOVAL.

JAMES HOW & CO.,

SCIENTIFIC INSTRUMENT MAKERS,

73, FARRINGDON ST., LONDON

(LATE OF 5, ST. BRIDE ST., AND 9, FOSTER LANE).

HOW'S STUDENT'S MICROSCOPE. HOW'S MICROSCOPE LAMP.

Rock Sections and other Objects for the Microscope.

TO ASTRONOMERS.

Intending Purchasers of Telescopes should send for "Hints on Silvered Glass Reflecting Telescopes," by G. CALVER (maker of the 37-inch Ealing Reflector, &c.), and "Appendix," containing important Testimonials as to their efficiency, &c., &c. Post free Nine Stamps.

G. CALVER, F.R.A.S.,
HILL HOUSE,
WIDFORD,
CHELMSFORD.

N.B.—Second hand Reflectors and Refractors frequently for Sale.

Liberal Terms to Science Teachers and the Trade.

THOMAS CRAMPTON (formerly of 4,

Little Britain, London, E.C.), ELECTRICIANS, OPTICIANS, and PHILOSOPHICAL INSTRUMENT MAKERS. Electric Bells, New Metallic Base Pattern, Constant Batteries, Indicators, Thief and Fire Alarms, and Annunciators, Switches, Induction and Medical Coils, or Specialties. Insulated Wires of every description. Microscopes and Optical Materials, Telescopes, Opera Glasses, Microscopes, Aneroid Barometers, and Lime-light Apparatus. Illustrated Catalogue Three Stamps.

THOMAS CRAMPTON & CO., 281, HIGH HOLBORN, LONDON, W.C.

For Trade Terms send Card.

R. W. NEEVES,

PHILOSOPHICAL INSTRUMENT

AND

INTENSITY COIL MAKER.

PRICE LIST, FOUR STAMPS.

55, SIDMOUTH STREET, LONDON, W.C.

W. LADD & CO.,

SCIENTIFIC INSTRUMENT MANUFACTURERS,

(By Appointment to the Royal Institution of Great Britain),

11 AND 12, BEAK STREET, REGENT STREET, W.

SELENIUM RHEOSTAT AND OTHER APPARATUS FOR BELL'S PHOTOPHONE

PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3s. per oz.

Physical Apparatus of every Description.

ILLUSTRATED CATALOGUE SIXPENCE.

'S NEW CATALOGUE OF PHYSICAL APPARATUS.

SCIENTIFIC LECTURES. Season 1880-1. Post free 6 Stamps.

Apparatus for Science Primers and all the Physical Text-books in use in Schools and Colleges.

amo Machines and Lamps for hire.

ratus as per Science and Art Departments' Requirements in the Sections of Light, Heat, Sound, and Electricity.

, Hotels, &c., Colliery Signals, Lightning Conductors. The Gower-Bell Loud-speaking Telephone.

EDWARD PATERSON, Electrical Engineer,

OMS AND STEAM WORKS:—76, LITTLE BRITAIN, E.C. (late 3, Bedford Court, W.C.).

HARMONOGRAPH, executes the Harmonic Curves in the most perfect manner. 15s. and 20s.

Electrical Apparatus, Part 1, post free, 6 Stamps. Ditto, Electric Signals, Part 2, 6 Stamps.

FLETCHER'S
PATENT VENTILATED
HOT-AIR OVEN.

At a cost of less than one halfpenny per hour for gas this oven will grill, roast, toast, bake, warm dishes and plates; and with the assistance of Fletcher's Patent Solid Flame Boiling Burners will do everything possible with a first-rate open fire (except drying clothes on washing days).

It is unapproached by any oven for pastry, and is fully hot in one minute after the gas is lighted.

Fish, joint, and pastry can be cooked all at once, in the most perfect manner, without the slightest taint from one to the other. The cooking is always good and always alike.

It will roast joint and fowls both at once, at least as well as an open fire.

Complete illustrated list of gas cooking and labour-saving appliances free by post. List of Gas and Petroleum Laboratory Furnaces and Apparatus, price 2d.

THOS. FLETCHER,
4 & 6, *MUSEUM STREET, WARRINGTON.*

EAGLE INSURANCE COMPANY,
79, PALL MALL.
FOR LIVES ONLY. ESTABLISHED 1807.
Accumulated Funds £3,043,542
Also a Subscribed Capital of more than £1,500,000
Reports, Prospectuses, and Forms may be had at the Office, or from any of the Company's Agents, post free.
GEORGE HUMPHREYS, Actuary and Secretary.

FRY'S COCOA
GOLD MEDAL, PARIS EXHIBITION.
In Packets and Tins. Pure Cocoa only, with the superfluous oil extracted.
"If properly prepared, there is no nicer or more wholesome preparation of cocoa."—*Food, Water, and Air, edited by Dr. Hassall.*
FRY'S EXTRACT
J. S. FRY & SONS, Bristol and London.

THE "HANSA"
Published since 1864 in Hamburg, is the only independent professional paper in Germany, dedicated exclusively to Maritime Objects. Essays, Critiques, Reviews, Reports, Advertisements. Strict eye kept upon the development of Maritime Affairs in every respect. Every second Sunday one Number in 4to at least; Frequent supplements and drawings. Subscription at any time; preceding numbers of the year furnished subsequently. Price 12m. for twelve months. Advertisements 40f. a line, widely spread by this paper; considerable abatement for 3, 6, 12 months' insertion. Business Office: Aug. Meyer and Dieckmann, Hamburg, Alterwall 28. Edited by W. v. Freeden, M.R., Hamburg, Alexander Street, 3.

HOLLOWAYS OINTMENT
A CERTAIN REMEDY
For BAD BREASTS, OLD WOUNDS, and SORES. If effectually rubbed on the Neck and Chest, it cures SORE THROATS, BRONCHITIS, COUGHS and COLDS; and for GOUT, RHEUMATISM, and all Skin Diseases it is unequalled.

S. C. TISLEY & Co.,
OPTICIANS,
172, BROMPTON ROAD,
(Close to South Kensington Museum.)
THE PHONEIDOSCOPE
An Instrument for Observing the Colour-Figures of Liquid
action of Sonorous Vibrations.
Being a visible demonstration of the Vibratory and Molecular
Telephone Plate.
The PHONEIDOSCOPE, with 3 Dises, Bottle of Solution,
Pamphlet, &c., in Cardboard Box, 10s. 6d.
MANUFACTURED AND SOLD WHOLESALE AND
S. C. TISLEY & CO., 172, BROMPTON ROAD.
TELEPHONIC ELECTRICITY. All Materials
Experimental Purposes.
Price Lists of Electrical and Acoustic Apparatus, with
Description of the Harmonograph. Post Free.

BROKEN!!
DAVY'S DIAMOND CE
SECURELY AND NEATL
CHINA, G
CABINET WO
AND
FANCY ART
Of all Chemists in
See the name "E. DAVY"
ventor, is on the Label,
BARCLAY & SONS, 95, Farringdon Stre

SECOND EDITIO
GRIFFIN'S
CHEMICAL HANDIC
PRICE 42. 7d. POST FREE.
A CATALOGUE OF CHEMICAL AP
ILLUSTRATED, CLASSIFIED, DES
Demy 8vo, 480 pp., Illustrated with 1,600 Wo
Most Complete and Cheapest List of Ap
JOHN J. GRIFFIN AND SONS, 22, GARRI
LONDON, W.C.

THE ENTOMOLOGIST'S MO
MAGAZINE.
Price Sixpence, Monthly, 24 pages 8vo, with occasio
Conducted by C. G. Barrett, J. W. Douglas, R. M
E. C. Rye, F.Z.S., E. Saunders, F.L.S., and H. T.
This Magazine, commenced in 1864, contains standard
on all subjects connected with Entomology, and especial
the British Isles.
Subscription—Six Shillings per Volume, post free.
Vols. I. to VI. (strongly bound in cloth) may be obtain
the entire set to date, at the increased price of 10s. ea
vols. may be had separately or together, at 7s. each.
London: JOHN VAN VOORST, 1, Paterno
N.B.—Communications, &c., should be sent to the
address.

"The leading Farmers' paper."—Clare Sewell Re
THE CHAMBER OF
AGRICULTURE JOU
AND FARMERS' CHRONIC
(PRICE 3d. WEEKLY).
The representative organ of the Central and Provi
Agriculture; *gives fuller reports of the discussions a*
this extensive organisation than any other agricultural
special attention to the treatment of Agricultural Q
ment, besides containing ample Reports of the LATE
COUNTRY CORN, CATTLE, HOP, PROVISION,
with Original Articles on Practical Farming, the Dair
News, Horticulture, &c., &c. It is despatched every
time for the country post.
Terms of Subscription, payable in advance, post free:
6 months, 7s. 7d.; 12 months, 15s. 2d.
Published by W. PICKERING, 21, Arundel Street, S

OOKE & SONS,

OPTICIANS

TO

the late Prince Con-
e Royal Family,
'ajesty's Home,
and Colonial
ernments,
ıost of the
reign
ıments.

KE & SONS
ion to con-
ality and on
able terms
n of Equa-
also Obser-
nstruments,
ronographs,
els, Astro-
locks, &c.

tific Instru-
dition : also
eurs' Lathes
paratus.

15 INCH EQUATORIAL MOUNTING, CONSTRUCTED FOR THE ROYAL OBSERVATORY, BRUSSELS, 1880.

. COOKE AND SONS, Buckingham Works, York.

Now ready, Ninth Edition, Revised and Enlarged, with 3 Steel Plates and 377
8vo. £1 11s. 6d.

CARPENTER'S HUMAN PHYSIOL

By HENRY POWER, M.B. Lond., F.R.C.S.,

Examiner in Anatomy and Physiology in the Royal College of Surgeons; Senior Ophthalmic Surgeon to St. B

London: J. & A. CHURCHILL.

Now ready, 70 Coloured Plates, imperial 8vo. £5 5s.

ATLAS OF PATHOLOGICAL ANA

By DR. LANCEREAUX.

Translated by W. S. GREENFIELD, M.D.,

Lecturer on Pathological Anatomy at St. Thomas's Hospital, Professor-Superintendent of the Brown

*** This English Edition contains all the plates of the original work, with ten added

London: J. & A. CHURCHILL.

Now ready, Tenth Edition, with 450 Engravings (including 26 Coloured Plates), crow

WILSON'S ANATOMIST'S VADE-M

Edited by GEORGE BUCHANAN,

Professor of Clinical Surgery in the University of Glasgow; and

HENRY E. CLARK,

Lecturer on Anatomy at the Royal Infirmary School of Medicine, Glasgow.

London: J. & A. CHURCHILL.

New Series, No. LXXXII., April, 1881, Price 7s. 6d.

THE QUARTERLY JOURNAL OF MICROSCOPICAL SCIENCE.

Edited by
E. RAY LANKESTER, M.A., F.R.S., F.L.S.,
Fellow of Exeter College, Oxford, and Professor of Zoology and Comparative Anatomy in University College, London;
With the co-operation of
F. M. BALFOUR, M.A., F.R.S., F.L.S.,
Fellow and Lecturer of Trinity College, Cambridge;
W. T. THISELTON DYER, M.A., F.R.S., F.L.S.,
Assistant Director of the Royal Gardens, Kew; and
E. KLEIN, M.D., F.R.S.,
Lecturer on Histology in St. Bartholomew's Hospital Medical School, London.

MEMOIRS.

The Minute Anatomy of the Branchiate Echinoderms. By P. HERBERT CARPENTER, M.A., Assistant-Master at Eton College. With two Plates.
On Young Stages of Limnocodium and Geryonia. By E. RAY LANKESTER, M.A., F.R.S., Jodrell Professor of Zoology in University College, London. With Plate.
The Origin and Significance of the Metamorphosis of Actinotrocha. By EDMUND B. WILSON, Fellow in Biology, Johns Hopkins University. With two Plates.
A Further Contribution to the Minute Anatomy of the Organ of Jacobson in the Guinea-Pig. By E. KLEIN, M.D., F.R.S., Lecturer on Histology and Embryology in the Medical School of St. Bartholomew's Hospital. With two Plates.
Histological Notes. By E. KLEIN, M.D., F.R.S.
On the Development of Certain Microscopic Organisms occurring in the Intestinal Canal. By D. D. CUNNINGHAM, M.B., Surgeon-Major, Indian Medical Service; Fellow of the Calcutta University. With Plate.
Researches upon the Development of Starch-Grains. By A. F. W. SCHIMPER. With Plate.
On the Cause of the Striation of Voluntary Muscular Tissue. By JOHN BERRY HAYCRAFT, M.B., B.Sc., F.R.S.E., Senior Physiological Demonstrator in the University of Edinburgh.
On the Relation of Micro-Organisms to Disease. By JOSEPH LISTER, F.R.S., Professor of Clinical Surgery in King's College, London.
Observations and Reflections on the Appendages and on the Nervous System of *Apus cancriformis*. By E. RAY LANKESTER, M.A., F.R.S., Jodrell Professor of Zoology in University College, London. With Plate.

NOTES AND MEMORANDA.

Claus on Intracellular Digestion in Hydrozoa.
Kent's Manual of the Infusoria.

London: J. & A. CHURCHILL.

Printed by R. CLAY, SONS, AND TAYLOR, at 7 and 8, Bread Street Hill, Queen Victoria Street, in the City of Londo
MACMILLAN AND CO., at the Office, 29 and 30, Bedford Street, Covent Garden.—THURSDAY, April 14

Sixth Edition, in Two vols., 8

COOLEY'S CYCLO

PRACTICAL RECEIPTS and Collateral
Manufactures, Professions, and Trades, incl
Hygiene, and Domestic Economy; designe
plement to the Pharmacopœia and General
Manufacturer, Tradesman, Amateur, and
This Edition exceeds the last by some 600 pa
increased number of receipts culled from the
foreign journals; numerous articles on Appli
Hygiene, Human and Veterinary Medicine, &c
of the old articles are extended: and, where de
by woodcuts.
"We cannot spare space to enumerate all the
have the old edition of this work will do well t
successor; those who have no copy of it will do
this edition."—*Chemist and Druggist.*
"It is a storehouse of scientific knowledge, an
every house."—*Lancet.*
*** *This Work can also be had in 16 Pa*

London: J. & A. CHURC

Third Edition, Revised and Enlarged, with
Post 8vo. 7s. 6d.

PRACTICAL AND AN

CHEMISTRY, Specially adapted for Sch
Beginners. By FRANK CLOWES, D.Sc
at the High School, Newcastle-under-Lyme.

London: J. & A. CHURC

Fourth Edition, with nearly Three Hundred

CHEMISTRY, INORG

ORGANIC. WITH EXPERIMENTS. By C
Professor of Chemistry in King's College, L
By the SAME AUTHOR. Fourth Edition, with
2s. 6d.

LABORATORY TEACHIN

Exercises in Practical Chemistry.

London: J. & A. CHURC

Fifth Edition, 8vo. with Engravi

VALENTIN'S QUALITA

CAL ANALYSIS. Revised and Corrected b
Ph.D., Demonstrator of Practical Chemistr
South Kensington.

London: J. & A. CHURC

NATURE

A WEEKLY ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
Of Nature trusts the mind which builds for aye"—WORDSWORTH

23] THURSDAY, APRIL 21, 1881 [PRICE SIXPENCE

...ster at the General Post Office.

[All Rights are Reserved.

...OTICE.

...TURE"

...APRIL 28, 1881,

...RAIT, Engraved on Steel by the late ... C. H. JEENS,

...OF

...VILHELM BUNSEN.

...ns for this number should be sent to the ...le.

...OFORD STREET, STRAND.

CHEMICAL INDUSTRY.

...In accordance with a resolution unanimously ... on April 4th that all persons interested ... for the space of Six Months, between Members signing the necessary Forms, which may be ... requisites provided such applicants be considered ... that they pay a Subscription of One Guinea for ... they shall continue to the bye-laws of the Society. ... the first Six Months are exempted from the ...

... outside all who are engaged in any Chemical ... where Chemistry plays a part and the Secretary ... information on the subject.

... may be made to any of the Secretaries [illegible] ... Covent Garden Wharf, Battersea, London ...

... General Meeting is constituted as follows:—

... F.R.S.

... Esq., F.R.S., Latham Hill, Esq., F.R.S., ... Capt. Abney, M.E., F.R.S., Macpherr, Esq., ... H. Perkin, Esq., F.R.S., Dr. C. W. Siemens, ... W. Weldon, Esq., F.R.S.E., Dr. A. W. ... Esq., F.R.S.

... ney, Esq., M.E., F.R.S., Alexander Chaney, ... F.R.S., Dr. Chas. Graham, Peter Jeffrey, Esq., ... M.P., David Howard, Esq., James Macfie, ... H. Spengel, F.R.S., H. Tate, jun., Esq.,

... Esq., East London Soap Works, Bow, E. ... Steel, George E. Davis, Heaton Chapel, Stockport, Thomas Tyrer, Garden Wharf, Battersea, ... Sec., Eustace Carey, Widnes, Hon. Foreign ... Eaton Hall, Northwich.

... will be held in London in June next, and due ... be given. At this meeting Papers will be read ... Industry discussed.

... that all those gentlemen present at the Inaugural ... and there address to the roll, and who desire to ... communicate with the Hon. Metropolitan ...

... H. E. ROSCOE, President.

THE HOUSTON BOTANICAL MICROSCOPE.

This ingenious and efficient little instrument provides botanical students with a dissecting microscope at a very low price.

It consists of a lens contrived so that it will form a dissecting stage; a duplex lens giving 3 powers, 4, 6, and 12 diameters, which can be removed and carried in the pocket, and a brass focussing tube on pillar; a cork slide, a hollowed glass for holding liquids, and a pair of forceps.

PRICE COMPLETE, 6s. 6d.

JOHN BROWNING,

Optical and Physical Instrument Maker to H.M. Government &c., &c.,

63, STRAND, LONDON, W.C.

TRAVELLERS' SCIENTIFIC REQUISITES.

ASTEROID BAROMETER with ALTITUDE SCALE, THERMOMETER and COMPASS in Flat Pocket Case, various Forms.

£7 7s. and £8 8s.

Price Lists of Instruments free by post.

NEGRETTI & ZAMBRA,

Opticians and Scientific Instrument Makers

TO HER MAJESTY THE QUEEN,

HOLBORN VIADUCT,

45, CORNHILL, & 122 REGENT STREET, LONDON.

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 48a, Tollington Road, Holloway, London, N.

ST. THOMAS'S HOSPITAL MEDICAL SCHOOL,

ALBERT EMBANKMENT, S.E.

The SUMMER SESSION will commence on May 2nd. Students entering in summer are eligible to compete for the Natural Science Scholarships of £100 and £60 awarded in the following October.

Special Classes are held for the Matriculation, Preliminary Scientific, and 1st M.B. of the University of London.

There are numerous Prizes and Scholarships, and all Appointments are open to Students without extra payment.

Several Medical Practitioners and Private Families in the neighbourhood receive Students for residence and supervision, and a register of inspected lodgings is kept in the Secretary's office.

Prospectuses and all particulars may be obtained from the Secretary, Dr. Gillespie.

W. M. ORD, M.D., Dean.

THE MIDDLESEX HOSPITAL MEDICAL SCHOOL.

SUMMER SESSION, 1881.

Lectures and Clinical Instruction in the Wards will commence on May 2nd. Gentlemen can enter to any one Course or to Hospital Practice only.

TWO ENTRANCE SCHOLARSHIPS, of the annual value of £75 and £20 respectively, tenable for two years, and a SCIENCE SCHOLARSHIP value £50, will be offered for competition at the beginning of the Winter Session.

For Prospectus, containing particulars as to other Scholarships, Resident Appointments, Fees, &c., apply to the Dean or the Resident Medical Officer, at the Hospital.

ANDREW CLARK, Dean.

CITY AND GUILDS OF LONDON INSTITUTE for THE ADVANCEMENT OF TECHNICAL EDUCATION.

VICE-PRESIDENTS.

The Right Hon. Lord SELBORNE, Lord Chancellor, Chairman of Council
F. J. BRAMWELL, Esq., F.R.S., Chairman of Executive Committee.
Sir S. H. WATERLOW, Bart., Ald., M.P., Treasurer.

The Executive Committee are prepared to grant a limited number of

FREE ADMISSIONS

to the Classes in CHEMICAL TECHNOLOGY (Bread-making, Brewing Alkali Trade, Soap, Glass, &c.) in MECHANICAL TECHNOLOGY (Iron and Steel Manufacture, Strength of Materials), under Professors GRAHAM and KENNEDY, at University College; and also to the Classes in METALLURGY (Assaying, Quantitative Blowpipe Analysis, Metals and their Alloys), and in PRACTICAL FINE ART, under Professors HUNTINGTON and DELAMOTTE, at King's College.

In the selection of Candidates preference will be given to Foremen in Chemical Works, Artisans, Apprentices, Designers, and Artistic Tradesmen.

Applications for admission to be sent in the first instance to the Director and Secretary of the City and Guilds of London Institute, from whom, as well as from the Professors at University College and King's College, further particulars can be obtained.

PHILIP MAGNUS, Director and Secretary.

Gresham College, E.C.

THE COUNCIL OF FIRTH COLLEGE,

SHEFFIELD, intend to APPOINT a PRINCIPAL, who shall also be Professor either in the Literary or in the Mechanical Department of the College.

These Departments will comprehend respectively the following Subjects:—

1. Classics, History, Literature, Political Economy, Moral Science.
2. Mathematics, Mechanics, Engineering, Geology, Physics.

Applicants are requested to state in which of these Departments they would be prepared to act as Professor, and which of the Subjects in that Department they would be prepared to undertake.

The Salary of the said Principal will be £500 per annum, with Half the Fees of his own Classes.

The Council will only make the Appointment in event of suitable Candidates presenting themselves.

Candidates are requested to give full particulars concerning Age, Experience, and any Academical Distinctions they may have gained, together with any other information likely to affect the decision of the Council. The names of three gentlemen to whom references may be made should be given, but no testimonials need be sent unless they are asked for.

Applications to be sent on or before the 25th day of April next, to

ENSOR DRURY, Registrar.

Firth College, Sheffield, March 24, 1881.

CHEMISTRY.—Instruction given in Analytical and General Chemistry and Microscopy. Apply to the PRINCIPAL, The Metropolitan Laboratory, 32, Holborn Viaduct, E.C.

SELENIUM FROM £10 per Kilogram, THORITE from £20 per kilogram, is to be had of Dr. S. R. PALKULL, Stockholm.

LIVING SPECIMENS FOR THE

THOMAS BOLTON, NATURALISTS' and

STUDIO, 57, NEWHALL STREET, BI

T. B. has last week sent to his subscribers *Trichodi* Infusorian found parasitic, or rather commensal, up He has also sent out the Green Trumpet Animalcule also *Ophrydium longifex*, Volvox, Euglena, Na Desmids and Diatoms, *Zoea* Crabs, and some Polyzoa.

Weekly announcements will be made in this pla is supplying.

Specimen Tube, One Shilling,

Twenty-six Tubes in course of Six Months for

Price List of Specimens on application, with stamp

Portfolio of Drawings, No. 4. One Sh

LONDON UNIVERSITY, A SERVICE.

Dr. R. H. JUDE, D.Sc. (Lond.), M.A. (Cantab.), Class Natural Science Tripos, late Scholar of Chr monstrator of Chemistry at Caius College, Cambrid ants, prepares Gentlemen in all the subjects for the Natural Science treated both experimentally and Highest Testimonials and References to present few Pupils taught by Correspondence.

119, Cambridge Gardens, Notting Hill, W.

EXETER SCH

Chairman of Governors—The LORD BISHO Head-Master—The Rev. EDWARD HARRIS, M.A., Master at Clifton College.

The New School, with Chemical Laboratory, bu Mr. W. Butterfield, is now in use.

Tuition Fee, £15 to £21, according Boarding Fee, £50 to £60, "

There are valuable Scholarships tenable at the Sch Also Exhibitions to the Universities and other pla of the aggregate value of £500 per annum.

Apply to the CLERKS, Messrs. DAW & SON, 13, B or to the HEAD-MASTER, at the School.

NOTICE.—LIVERP

MR. A. NORMAN TATE, in reply to several in others, and to avoid further misconception arising fr surname and that of one of the principals of another in this city whose announcements of commencement appeared, desires to say that his only Office an Hackins Hey.

The publishers of one magazine, evidently misled name, having mentioned him (as "Mr. Norman Tat cipals of the Liverpool College of Chemistry, he des no way connected with that establishment, and he has Analytical Laboratory and School of Technical Ch 7, 8, 9, and 11, Hackins Hey.

ROYAL POLYTECHNIC.—C

the Preparation of Students for University Ex direction of EDWARD B. AVELING, D.Sc., versity Matriculation, 1st and 2nd B.Sc., Prelim Botany, Physiology, Chemistry. All the work pra

INSTRUCTION IN MATHE

Youths or Adults attended at their Residence, by a M.A. of Cambridge. Unquestionable re Address, by letter, O. P., Post Office, Turnham G

THREE LARGE MUSEU

Cases for Sale, Second-hand, Cheap, Best Glass, Perfect Fittings.—JOHN METCALFE, Richmond,

MINERALOGY AND G

VERY FINE SPECIMENS of CRYSTALS of LINE in ROCK CRYSTAL—MADAGASCAR.

SOME FINE EXAMPLES OF ITACOLUMITE OR F STONE—INDIA—IN SLABS 1 FOOT TO 7 FEET 6 IN

BLOWPIPE CASES AND APPARA

COLLECTIONS FOR STUDENTS, from £2 2s. C BEGINNERS, from 4s.

PRIVATE LESSONS AND EVENING Catalogues free.

SAMUEL HE

277 (*Late* 113*a*), STRAND, LO

EVERY BOY A GEOLO

Now ready, and highly recommended, complete This admirable little Work and most extraordinary Ca well-selected Natural Specimens, together with other tions, and a powerful Lens, are calculated to start a has mastered for himself no ordinary knowledge of Earth's Crust.—THOMAS J. DOWNING, Geologi Street, London, E.C.—Catalogues free.

VALUABLE COLLECTION OF MINERALS FOR SALE.

JAMES R. GREGORY has now for Sale a very fine Old Collection, chiefly of Cornish Minerals, one of the best in Cornwall. The Collection was commenced forming sixty years ago, and contains most of the old Minerals of the County, many of which have not been found for many years. It consists of over 4000 Specimens, including a large number of Foreign Specimens, and is contained in four large well-made Spanish Mahogany Cabinets, two of thirty drawers each, and two of twenty-four Drawers each, with Bookshelves over. For Price, &c., and to inspect the same, apply to—

JAMES R. GREGORY,
88, CHARLOTTE STREET, FITZROY SQUARE.

DIAMONDS IN MATRIX.

R. C. NOCKOLD, Diamond and Oriental Stone Cutter and Dealer, has for sale Specimens of the above; also Cut Precious Stones in all Colours.
Precious Stones valued and bought.
18, FRITH STREET, SOHO, W.

THE QUARTERLY REVIEW, No. 302,

Will be PUBLISHED on TUESDAY, APRIL 26.

Contents.

I. THE REVOLUTIONARY PARTY.
II. LITERARY LIFE OF LORD BOLINGBROKE.
III. THE SPEAKER'S COMMENTARY ON THE NEW TESTAMENT.
IV. THOMAS CARLYLE AND HIS REMINISCENCES.
V. RUSSIAN LANDLAWS AND PEASANT PROPRIETORS.
VI. SIR ANTHONY PANIZZI.
VII. ENDOWMENTS OF THE CHURCH IN 1830 AND 1880.
VIII. MINISTERIAL EMBARRASSMENTS.

JOHN MURRAY, Albemarle Street.

LA SEMAINE FRANÇAISE: a Weekly Newspaper and Review in the French Language. Politics, Literature, Science, Art, Varieties, Notes. Price 3*d.*, through booksellers, and at the railway bookstalls. Office, 37, Southampton Street, Strand, W.C.

LA SEMAINE FRANÇAISE: Journal Français pour l'Angleterre: Politique, Littérature, Sciences, Arts, Variétés, Nouvelles, et Notes. Un exemplaire par la poste, 3½*d.*, en timbres poste Abonnement franco par la poste—un an, 15*s.* 2*d.*; six mois, 7*s.* 7*d.* Prix 3*d.*, chez tous les libraires et aux gares des chemins de fer. On s'abonne aux bureaux, 37, Southampton Street, Strand, Londres, W.C.

LA SEMAINE FRANÇAISE.—"'La Semaine Française' has been brought out in London for the benefit of those English readers who may wish to study contemporary French from all points of view, instead of confining their reading to one particular Gallic print. It certainly merits success."—*Graphic.*

LA SEMAINE FRANÇAISE.—"The numbers before us are full of good things. . . . It will be far better for most than any one of the best papers published in Paris itself. We are much pleased with the character of it, and believe it will be highly valued in all those many households where French is cultivated. The printing is very well done."—*Queen.*

TERMS OF SUBSCRIPTION:—

	s.	*d.*
Three months	3	10
Six ,,	7	7
Twelve ,,	15	2

P.O.O. payable to T. SPANSWICK, at King Street, Covent Garden, W.C
Publishing Office, 37, Southampton Street, Strand, W.C.

In unserem Verlage erscheint:

DER NATURFORSCHER.

Wochenblatt zur Verbreitung der Fortschritte in den Naturwissenschaften.
Herausgegeben von Dr. WILHELM SKLAREK.
Wochentlich 1—1½ Bgn. in 4°.
Preis vierteljährlich 4 Mk.

Die nunmehr ihren XIV. Jahrgang beginnende Zeitschrift hat bei Allen, welche sich mit Naturwissenschaften beschäftigen, grossen Beifall gefunden. Probenummern sind durch jede Buchhandlung zu erhalten.
Berlin, S.-W., 77, Charlottenstr.

FERD. DÜMMLER'S VERLAGSBUCHHANDLUNG.
(Harrwitz & Gossmann.)

"The leading Farmers' paper."—CLARE SEWELL READ, ESQ., M.P.

THE CHAMBER OF AGRICULTURE JOURNAL AND FARMERS' CHRONICLE

(PRICE 3*d.* WEEKLY).

The representative organ of the Central and Provincial Chambers of Agriculture; *gives fuller reports of the discussions and proceedings* of this extensive organisation than any other agricultural paper. It devotes *special attention to the treatment of Agricultural Questions by Parliament*, besides containing ample Reports of the LATEST LONDON and COUNTRY CORN, CATTLE, HOP, PROVISION, and other Markets, with Original Articles on Practical Farming, the Dairy, Herd and Flock News, Horticulture, &c., &c. It is despatched every Monday evening in time for the country post.

Terms of Subscription, payable in advance, post free:—3 months, 3*s.* 9½*d.*; 6 months, 7*s.* 7*d.*; 12 months, 15*s.* 2*d.*
Published by W. PICKERING, 21, Arundel Street, Strand, London, W.

"THE ENDOWMENT OF RESEARCH."

See NATURE *of April* 14, 7, *and March* 24.

There may be something profound, of which Dr. Brunton has entirely concealed all conception from the Royal Society, in the fact that the same poisoned blood, after death by torture, remains fluid at Calcutta and coagulates in England. We are informed that the *Crotalus*-poison came from Philadelphia, looking like fragments of dried gum-arabic.

In Experiments III. and IV. two full-grown guinea-pigs, of equal weight, were selected, and into their peritoneal cavities, at 1.52 and at 1.56 p.m., were injected *Crotalus* and *Cobra*-poison, one poison for each. Two pages of notes follow, such as those on the former:—"At 2.42. Sluggish; drags the hind-legs. At 2.58. Weaker; rolls partially over on one side, but can run when roused. At 3.7. Can still be roused; abdomen distended and painful; cries out when it is touched, as though peritonitis were setting in. 3.12. Can be roused with difficulty" . . . "can still stagger a few paces, but co-ordination of muscular power much diminished. 3.30. In violent convulsions. 3.38. Convulsions continue." Then death at 3.55, and electrodes and *post-mortem* carving. The other guinea-pig was lucky enough to die in 21 minutes. The null summary compares the effects of the two poisons:—"There were no very marked differences in the action of the poison in these two cases, except in the energy with which the *Cobra* exceeded the *Crotalus*:—*Crotalus*: twitchings; restless; squeaks; sluggish; ataxy; paralysis; hurried respiration; peritonitis; convulsions. Death in 2h. 3m. Coagulated blood; ecchymosis and extravasation of serous effusion well marked; cord paralysed; muscles retain irritability. *Cobra*: Twitchings; excitement; squeaks; sluggish; ataxy; weakness; paralysis; convulsions. Death in 21 minutes. Spinal cord and nerves paralysed; muscles irritable; heart distended; blood congested; ecchymosis; congestion less than in *Crotalus*." I wonder what definite question is freshly answered or elucidated in all this. It is not pointed out that anything is new, nor that anything is of either theoretical or practical value, in these cruel demonstrations. Five such experiments on guinea-pigs are detailed, all with similar vague results. Then three on rabbits. Then, up to XXVIII., experiments on cats and frogs, comprising vivisections. "Experiment XXVIII. To test the effects of *Cobra*-poison, when swallowed, on the frog. [Can any man assign the exact matter tested?] June 24, 1874. At 2.25 p.m. About one-eighth of a grain of dried *Cobra*-poison was passed down a frog's throat. 2.30. Frog makes violent efforts to vomit; gaping; head thrown back tetanically. 2.34. Bloody mucus vomited with violent efforts"—on which hangs the foot-note:—"This experiment is *especially interesting*, as showing that frogs do occasionally vomit, a fact which has been denied by some physiologists." This, at least, is something new, though not exactly the matter tested. The doctor cleverly places his deadly obstruction on the rails of frog life, and waits behind his tree for the coming smash. Calmly, in that tornado of wreck and agony, he says, "Now for Science!" and picks out his chance discovery. I wonder whether the doctrine that frogs do not vomit cost as much cruelty as this triumphant refutation. "2.50. Moves with difficulty; is becoming paralysed; efforts to vomit continue. 3.0. Much the same. 3.5. Very weak; still tries to vomit. 3.10. Reflex action still well marked." How much torment does that mean? "3 15. Motor nerves apparently quite paralysed. 3.20. Apparent death." Whether it died or no, it did vomit. That immortalises Dr. Brunton. If it does not quite follow that all "frogs do occasionally vomit," this one poisoned and tortured frog did. This page of the *Proceedings* of the Royal Society will never be forgotten. This pet experiment so "*especially interesting*" is talked of already. Was the poison given to the serpent to deaden the pain of its victims, or to enable biologists to inflict random and lingering torture, in order that they may talk Science, which, summed up, amounts to so little, and points the way to less?

[*To be continued.*]

SOCIETY FOR THE TOTAL ABOLITION AND UTTER SUPPRESSION OF VIVISECTION.

Honorary Secretary and Treasurer,
GEORGE R. JESSE, Esq.,
April, 1881. Henbury, near Macclesfield, Cheshire.

Now publishing, in Crown 8vo. Price 2s. 6d. each.

ENGLISH MEN OF LETTERS.

Edited by JOHN MORLEY.

*** Upwards of 150,000 Vols. of this series have been sold.

WORDSWORTH. By F. W. H. MYERS.
"Mr. Myers gives us a picture of the man and an estimate of his work which is certainly not inferior to anything that has preceded it."—*Academy.*

LOCKE. By Prof. FOWLER.
"In the case of Locke's biographer we venture to say that Mr. Morley has been exceptionally fortunate. A pen more competent than Prof. Fowler's for this particular work might have been sought, and sought in vain."—*Examiner.*

BYRON. By Prof. NICHOL.
"Decidedly one of the most careful and valuable of the whole series."—*Athenæum.*

POPE. By LESLIE STEPHEN.
"The writer's eminent qualities as a critic, his judgment, his wit, his abundant knowledge of eighteenth-century literature, and his keen enjoyment of literary form, have equipped him handsomely for the task he has undertaken."—*St. James's Gazette.*

COWPER. By GOLDWIN SMITH.
"Mr. Goldwin Smith has sketched, in a few decisive touches, the genius of the poet and weakness of the man."—*Daily News.*

CHAUCER. By Prof. A. W. WARD.
"Far away the best connected account of Chaucer and his works to be found in English."—*Academy.*

BUNYAN. By J. A. FROUDE.
"He has given us a real study of Bunyan's life and character, and at the same time a real study of his books."—*Athenæum.*

SOUTHEY. By Prof. DOWDEN.
"A truly scholarly and delightful monograph."—*Examiner.*

HAWTHORNE. By HENRY JAMES, JUN.
"He has made a careful, conscientious, and even vivid literary portrait, such as few of our own writers could have made."—*New York Nation.*

MILTON. By MARK PATTISON.
"Mr. Pattison's achievement is deserving of high praise. He has put life into old facts, he has taken an impartial estimate of a great man whose name is too often used for purposes of poetry."—*Spectator.*

JOHNSON. By LESLIE STEPHEN.
"The new series opens well with Mr. Leslie Stephen's sketch of Dr. Johnson. It could hardly have been done better, and it will convey to the readers for whom it is intended a juster estimate of Johnson than either of the two essays of Lord Macaulay."—*Pall Mall Gazette.*

SCOTT. By R. H. HUTTON.
"We could not wish for a more suggestive introduction to Scott and his poems and novels."—*Examiner.*

GIBBON. By J. C. MORISON.
"As a clear, thoughtful, and attractive record of the life and works of the greatest among the world's historians, it deserves the highest praise."—*Examiner.*

SHELLEY. By J. A. SYMONDS.
"The lovers of this great poet are to be congratulated at having at their command so fresh, clear, and intelligent a presentment of the subject, written by a man of adequate and wide culture."—*Athenæum.*

HUME. By Prof. HUXLEY, F.R.S.
"It may fairly be said that no one now living could have expounded Hume with more sympathy or with equal perspicuity."—*Athenæum.*

GOLDSMITH. By WILLIAM BLACK.
"Mr. Black brings a fine sympathy and taste to bear in his criticism of Goldsmith's writings"—*Athenæum.*

DEFOE. By W. MINTO.
"Mr. Minto's book is careful and accurate in all that is stated, and faithful in all that it suggests."—*Athenæum.*

BURNS. By Principal SHAIRP.
". . . None of the series has given a truer estimate either of character or of genius than this volume."—*Spectator.*

SPENSER. By the Very Rev. the DEAN OF ST. PAUL'S.
"Dr. Church is master of his subject, and writes always with good taste."—*Academy.*

THACKERAY. By ANTHONY TROLLOPE.
"Mr. Trollope's sketch is excellently adapted to fulfil the purpose of the series in which it appears."—*Athenæum.*

BURKE. By JOHN MORLEY.
"It is no disparagement to the literary studies already published in this admirable series to say that none of them have surpassed, while few have equalled, this volume on Burke."—*British Quarterly Review.*

*** *Others in Preparation.*

MACMILLAN AND CO., LONDON.

Small 8vo. 12s.

ZOOLOGICAL CLASSIFICATI
Handy-Book of Reference, &c. By FRANCIS P
Second Edition, with Additions and a Glossary.
JOHN VAN VOORST, 1, Paternoster Row.
"We know of no volume which, in the space, contains
information."—*Nature* (1st Ed.).
"It is rare for any one to go through so much thought
involved in a classification of the genera of the animal
for this to be accomplished by a naturalist whose judgment
by thraldom to theories."—*Westminster Review* (1st Ed.).
"An extremely valuable compendium of zoology."—
Review.
"Notwithstanding the extreme conciseness with which
is treated, the author generally indicates not only the
ing points in the structure, habits, or development of the
which the different groups are to be distinguished, but also
them, and, not content with merely mentioning the
he adopts, usually, in cases of doubt, or where different
discusses briefly the opinions he has not followed."—*Annals*
of Natural History.
"We cordially recommend the work as likely to
service as 'a handy-book of reference.'"—*Edinburgh*
Magazine.

New Edition, very much enlarged, 12s.
HOW TO WORK WITH THE MICROSCOPE.
By LIONEL S. BEALE, F.R.S.,
President of the Royal Microscopical Society.
THE FIFTH EDITION,
Strongly bound and enlarged to 530 Pages, with 190 Plates, are Coloured, is now ready.
HARRISON & SONS, Pall Mall.

NEW WORK BY LIONEL S. BEALE.
Now ready, pp. 230, *demy* 8vo, 5s.
SLIGHT AILMENTS:
THEIR NATURE AND TREATMENT.
By LIONEL S. BEALE, M.B., F.R.S.,
Professor of the Principles and Practice of Medicine in the
J. & A. CHURCHILL, New Burlington Street, London.

This Day is published, super royal 4to, with Six Plates,
A MEMOIR of the ECHINODERMATA of the ARCTIC SEA to the WEST of GREENLAND.
TIN DUNCAN, M.B. (Lond.), F.R.S., F.G.S.,
PERCY SLADEN, F.G.S., F.L.S., &c.
JOHN VAN VOORST, 1, Paternoster Row.

TEXT-BOOKS OF SCIENCE.
In small 8vo, with 372 Figures on Wood, prices 6s.
SYSTEMATIC MINERALOGY.
HILARY BAUERMAN, F.G.S., Associate of the Royal School of
Mines. (Forming one of Messrs. LONGMANS & Co.'s Series of
Books for Science, Mechanical and Physical, Edited by
FIELD, F.R.S.)
London: LONGMANS & CO.

GREEK and ROMAN COINS.
of the Collection formed by GEORGE SIM, F.S.A.
4to, price 21s.
MACMILLAN & CO., LONDON.

Just issued, price 5s., handsomely bound in cloth, with Portrait,
MIND IN ANIMALS. By Prof.
BÜCHNER. Translated by ANNIE BESANT.
"It is a decidedly valuable addition to the literature of
Psychology."—*Nature.*
London: FREETHOUGHT PUBLISHING COMPANY,
Street, E.C.

GEOLOGY AND MINERALOGY.
IN the Preface to the "Student's Elements of Geology" Sir
Lyell he says, "As it is impossible to enable the student to
recognise rocks and minerals at sight by aid of written descriptions or figures, he will do well to obtain a well-selected collection of specimens." These can be had from
WRIGHT, MINERALOGIST, 90, Great Russell Street.
50 Specimens in Cabinet ... ...
100 " ... ...
200 " ... ...
&c., &c. ... ...
More extensive Collections from 50 to 1000 Guin

APRIL 21, 1881

AM HERSCHEL.[1]

III.

ter of his Memoir Prof. Holden the scientific labours of William ible the general reader to follow d discoveries, astronomical and *d'Analyse de la Vie et des Travaux* published by Arago in 1842 for ise account suited to the pro- lso to "A Subject-Index and ntific Writings of Sir William himself and Dr. Hastings, and blications of the Smithsonian

commences his review with ical instruments and apparatus to his time the principal and Newtonian telescopes of Short of Dollond, the six-foot New- er, aperture 9¼ inches, and the of Dollond, aperture 36 inches, one of each class was in use at Greenwich, in 1765. Herschel he progress of his manufacture ption of the forty-feet reflector iety in 1795. When he resided I long been acquainted with the hanics, and wanted only that the practice of these sciences. d by way of amusement in his n that he was closely occupied er of music), and thus he made ot, seven-foot, ten-foot, and escopes, besides others, of the elve, and eighteen inches, and feet focal length," in all, as less than 200 seven-feet, 100 ty-feet mirrors, in addition to

The number of stands he nts he states it would not be g further, as early as 1781 he ced the construction of what reflector," and invented and cast the mirror, "which was at 36 inches in diameter," but tal being a little too brittle, it was cast a second time, but nd the metal ran into the fire. discovery of Uranus, which patronage of the King, put a truction of a great telescope. y good twenty-feet reflector after two years observation d of the advantages of such to his previous intention of r. Soon afterwards, by the ph Banks, president of the his sister relates, obtained

from p. 455

"the promise that 2000*l.* would be granted for enabling him to make himself an instrument."

The forty-feet reflector, the *chef d'œuvre* of Herschel's optical and mechanical efforts, was commenced about the latter end of 1785, and, as Prof. Holden remarks, the history of the instrument extends from this date until the year 1811. The work was carried on assiduously with no further interruption than was occasioned by the removal from Clay Hall to Slough, where, soon after arrival, Herschel began to lay the foundation of the whole structure, and the highly-polished speculum was put into the tube, and the first view through it was obtained on February 19, 1787. But he dates the completion of the instrument from a much later period, for the first speculum came out thinner than was intended, and from its weakness did not permit of a good figure being given to it; a second mirror, cast in January, 1788, cracked in cooling; but in the next month it was recast and proved of the proper degree of strength. In October following a pretty good figure and polish had been assured, and Herschel says he observed the planet Saturn with it; he continued to work upon it till August 27, 1789, when upon trial on the fixed stars it gave a pretty sharp image, and on the following night he records,[2] "Having brought the telescope to the parallel of Saturn, I discovered a *sixth* satellite of that planet, and also saw the spots upon Saturn, better than I had ever seen them before, so that I may date the finishing of the forty-feet telescope from that time." The diameter of the polished surface of the great mirror was 48 inches. In proof of the efficiency of the mechanism for giving horizontal and vertical motions to so large an instrument he mentions that in the year 1789 he had many times taken up Saturn two or three hours before meridian passage and kept the planet in view with the greatest facility till two or three hours after the passage. On the 17th of September a *seventh* satellite of Saturn, the minute object now called *Mimas*, was discovered with the forty-feet telescope, and though the instrument was used for various purposes till 1811, these discoveries of satellites constitute its most prominent additions to our knowledge. Sir John Herschel has stated that the entire cost of construction, including the apparatus for casting, grinding, and figuring the mirrors, of which two were constructed, amounted to 4000*l.*, which sum was provided by King George III. His father observed the great nebula of Orion with the forty-feet telescope on January 19, 1811, and this was one of his latest observations. In 1839 the wood-work had so far decayed as to be dangerous, and Sir John Herschel pulled it down, but piers were erected upon which the tube was placed. Writing in March, 1847, he remarks that it was so well preserved that "although not more than one-twentieth of an inch thick, when in the horizontal position it sustained within it all my family, and continues to sustain inclosed within it to this day, not only the heavier of the two reflectors, but also all the more important portions of the machinery."

As Prof. Holden remarks, and a similar opinion has been expressed previously, it is probable that the general public expected more from the forty-feet telescope than it actually performed; but Herschel gave valid reasons why he did not make more extended use of the instrument: the time required to get it into proper working order and

the number of assistants necessary were impediments in the way of its being utilised for regular observation, and he assures us he "made it a rule never to employ a larger telescope when a smaller will answer the purpose." It is certain that the mirror which was in the tube in October, 1789, the month following that in which Herschel dates the completion of the telescope, was of excellent definition. On the 16th of that month he followed the sixth and seventh satellites (*Enceladus* and *Mimas*) up to the limb of the planet, and witnessed their occultation. Holden writes: "I have never seen so good definition, telescopic and atmospheric, as he must have had on these occasions."

Between the years 1796 and 1799 Herschel made an elaborate classification of stars visible to the naked eye according to their comparative brightness, which he communicated to the Royal Society in four papers published in the *Phil. Trans.* It formed the first general catalogue of the kind, exhibiting the exact state of the sky in his time. A reduction of Herschel's observations was undertaken by Mr. C. S. Peirce, and the results appear in vol. ix. of the *Annals* of the Observatory of Harvard College. So far as we know, their reduction had not been previously attempted. Instances of variability in the light of naked-eye stars were detected during the progress of the classification, the most notable discovery in this direction being perhaps that of the periodical fluctuations of α Herculis, in about sixty days. Another star in the same constellation he considered had totally disappeared in 1791, though he had seen it distinctly in 1781 and 1782.

Herschel was led to his numerous discoveries of double stars by his expectation of being able to determine the parallaxes of stars from measures made at opposite seasons of the year of the distances of pairs which appeared near together, and in the search for such pairs, his first catalogue of upwards of 200 double stars was formed and presented to the Royal Society in 1782. Long had previously measured stars upon a similar plan without success, but Herschel pointed out that his stars were not well chosen.

For the successful application of the method it is necessary that one of the pair of stars should really be situated at a much greater distance from us than the other, and as the most reasonable test of distance, Herschel assumed their difference of brightness, so that he sought for pairs where the components differed widely in this respect. The view therefore which he adopted at this time with respect to two stars seen in close proximity to each other was that one was in nearly the same line of sight as the other, but might be far more distant, thus constituting together what we now term an *optical* double star. From this beginning he was led to the discovery of revolving double stars, stars changing their relative position from year to year; and in 1803 he communicated to the Royal Society his memorable paper: "An account of the changes which have happened during the last twenty-five years in the relative situation of double stars, with an investigation of the cause to which they are owing." He was then satisfied that there were in the heavens pairs of stars which were physically connected with each other. The research for stellar parallax was not successful, but in place of it he discovered the existence of binary systems. He could not in his day decide whether the motions of suns round suns was obedient to the laws of gravitation, but five years after his death the French astronomer Savary proved that one of the revolving double stars, discovered by Herschel, Ursa Major, really was subservient to that law, and every student of astronomy will be aware, the number of physically connected systems where the elements of orbits have been determined, is now a large one, and gradually increasing.

Following at present the order in which Prof. Holden refers to the scientific labours of Herschel, we now look at his researches on planets and satellites, respecting which the improvements he made in the construction of telescopes enabled him to advance knowledge so greatly. He was not particularly occupied with the inferior planets, but he determined the time of axial rotation of Mars with greater precision than before, and also the position of its axis. The times of the rotation of the satellites of Jupiter were found from observations on their changes of brightness, and Herschel also remarked the apparently perfectly explained phenomena attending the transits of the satellites across the disk of the planet. Saturn, Prof. Holden remarks, was the object of his constant attention, and in addition to the discovery of the interior satellites, *Enceladus* and *Mimas*, he left upon record an extensive series of observations of the seven attendants of Saturn at that time known, and determined the time of rotation of the outer satellite *Japetus* upon its axis by similar observations to those made upon the satellites of Jupiter. He ascertained the time of axial rotation of Saturn, and was the first who had succeeded in effecting this in a reliable manner. He also remarked the so-called square-shouldered appearance which the globe of the planet has been suspected to present, and of which we still occasionally hear, though it was long ago proved by Bessel to be an illusion. It is remarkable that notwithstanding Herschel's frequent scrutiny of the planet with all his experience of observation and the advantage of optical means surpassing by far those of his contemporaries, he does not appear to have at any time suspected the existence of the interior obscure ring. He proved beyond doubt that *Uranus* was attended by two satellites, and believed he had observed four others, and for a time on his authority the planet was credited with six attendants.

In 1795 Herschel communicated to the Royal Society a memoir upon the nature and construction of the sun and fixed stars. As to the former he adopted a modified view of the theory which had been advanced by his colleague Wilson of Glasgow; he regarded the sun as consisting of three essentially different parts: a solid and non-luminous nucleus, cool and perhaps capable of habitation, surrounded the atmosphere proper, and still higher the luminous bodies which cause the sun's intense brilliancy. In this paper occurs a remark which, as Prof. Holden observes, has often been brought to bear, in considerations of the causes which maintain the solar light and heat. "Perhaps," he says, "the many telescopic comets may restore to the sun what is lost by the emission of light." We know that however credible in his day points of this theory have given way under our greatly advanced knowledge.

One of the discoveries, or perhaps we should rather

especially mark his powers of
as that of the motion of the sun
ace and the direction of this
idered generally, has received
ecent and refined investigation.
d the proper motions of a limited
tars, and Lambert, Mayer, and
leas upon the subject, and, fol-
is, he showed that the sun was
s a point in the constellation
the apex of solar motion" with
astonishing degree of accuracy
s subject (1805) his biographer
le that can possibly be given of
hing the heart of a matter, and
hich his philosophical powers
rcise."

of the "Construction of the
med it, of the laws of distribu-
, the star-clusters and nebulæ
main object of his astronomi-
irs bearing upon this subject
riod of his scientific career.
ed a system of *star-gauging*,
in pointing his 20-feet reflec-
of the sky and counting the
of view 15′ in diameter. In
servation, the great differences
ertain portions of the sky over
were reliably defined, and in
ce was very marked, as in one
re in R.A. 19h. 41m., N.P.D.
Sagitta, the number of stars
;88, while in R.A. 16h. 10m.,
was only 1·1—"*ein Loch in*
f his review the author briefly
rtained by Herschel at various
1817: he considers that while
researches the whole subject
hey progressed data for the
ost important questions were
of Herschel's whole labours
which future investigators
founder of a new branch of

ale of celestial measures, on
dimensions of the stars, on
t and heat from the sun, are
s observations on the spectra
we believe, very much over-
e *Philosophical Transactions*
1798 he made some experi-
f the stars of the first magni-
to the eye-glasses of his
ngle and direction, with the
t of *Sirius* consists of red,
urple, and violet; *a Orionis*
ut the red is more intense
less copious in proportion
yon contains all the colours,
e and purple than *Sirius*.
nd orange, and less yellow
Aldebaran contains much
orange and very little yellow. *a Lyræ* contains much yellow, green, blue, and purple." Holden suggests that if we were to attempt to classify these stars by Herschel's observations alone we should put *Sirius* and *Procyon* into one type of stars, which have all the colours in their spectra; *Arcturus* and *Aldebaran* would represent another group, with a deficiency of yellow and an excess of orange and red in the spectrum; *a Orionis* would form a type of those stars, with an excess of red and a deficiency of orange; and *a Lyræ* would represent a sub-group of the first class. The correspondence with Secchi's types and representatives is almost complete.

There remains one other great section of Herschel's researches and discoveries, that relating to the nebulæ and clusters of stars. When he commenced his observations in 1774 very few of these objects were known. Meissier's catalogue of sixty-eight such objects did not appear till 1784, and they were chiefly objects found in his long-continued search for comets. Lacaille contributed twenty-eight from his observations at the Cape of Good Hope. Herschel discovered more than 2500, which he distributed in classes as follows:—Class I. "Bright nebulæ" (1188 in all); II. "Faint nebulæ" (909); III. "Very faint nebulæ" (984); IV. "Planetary nebulæ" (79); V. "Very large nebulæ" (52); VI. "Very compressed and rich clusters of stars" (42); VII. "Pretty much compressed clusters" (67); VIII. "Coarsely scattered clusters" (88). In addition he pointed out large spaces of the sky covered with very diffused and faint nebulosity, which do not appear to have been re-observed. Holden advises that they should be sought for with a powerful refractor, which would be less open to illusions than Herschel's reflectors, and that the instrument should be used in the way he adopted—in sweeping.

Throughout Prof. Holden's interesting memoir there is evinced the same enthusiastic admiration of Herschel and his scientific labours, and he concludes in the same strain: "He was born with the faculties which fitted him for the gigantic labours which he undertook, and he had the firm basis of energy and principle which kept him steadily to his work. As a practical astronomer he remains without an equal. In profound philosophy he has few superiors."

Lists of Herschel's scientific memoirs and of works bearing upon them, are appended to the volume which has formed the subject of our notice, and which, if it has a fault, is of only too limited extent to do full justice to a long life of discovery and research. We will reiterate the hope expressed by Prof. Holden in his preface, as we understand it, that some member of Sir William Herschel's family may at no distant period "let the world know more of the greatest of practical astronomers" . . . "of a great and ardent mind whose achievements are and will remain the glory of England;" and in this connection, that whatever may be found amongst his manuscripts (and as regards the drawings of the nebulæ, no less an authority than the late Prof. D'Arrest has expressed a strong hope of further publication) may at the same time be given to the astronomical public.

J. R. HIND

[1] Prof. Holden's work is published in London by Messrs. W. H. Allen and Co.

BRITISH FISHES

Natural History of British Fishes: their Structure, Economic Uses, and Capture by Net and Rod. Cultivation of Fish Ponds, Fish suited for Acclimatisation, Artificial Breeding of Salmon. By Frank Buckland, Inspector of Fisheries. (London: Society for Promoting Christian Knowledge.)

IT would have been difficult for Mr. Buckland to produce a dull book on any question connected with the economy of our fisheries; his merit in this respect has tended, however, to lead him too much in an opposite direction. It is painful, now that we are deprived of the living presence of the genial naturalist and industrious fishery inspector, to write an unkind word regarding any branch of his life's work; but of this book we are compelled to say that we would have appreciated it better had it been less "familiar" and more scientific. That it should be full of interesting information about fishery matters was quite to be expected from the richness of the stores which its author always had at his command, and if Mr. Buckland had taken pains to digest the *matter* so lavishly extracted from *Land and Water*, and had likewise collated the miscellaneous information contained in the volume with care, he might then have enjoyed the satisfaction of presenting to the public a natural history of British fishes which probably would have compared satisfactorily with other good books of the kind. It is not too much to affirm that a carefully edited selection from the numerous essays contributed to the various blue-books to which the deceased gentleman was so voluminous a contributor, would have made a more interesting volume than the present work. The fact is, Mr. Buckland was nothing if he was not sketchy and rapid; he would not be tied down to severe statements, but preferred to give an off-hand opinion in a dashing way, no matter that he might find out within the year that what he had advanced was very far wrong. In the present volume, as a glance at the plethoric title-page will show, Mr. Buckland attempted too much, with the result that portions of the information conveyed are scrappy, while some of it is probably slightly imaginative: books and articles written in railway trains often enough provide hard work for the reader. In a preface to his work Mr. Buckland takes pains to point out how greatly we are deficient in *exact* knowledge of the habits of our sea-fish, of the times and places of their spawning, of the food they eat, and of the period at which they are able to repeat the story of their birth. Some of the many questions which are asked by Mr. Buckland we are under the impression he should himself have been well able to answer. Whether cods' eggs "sink or swim" has been often discussed, and the author ought to have been able to tell us the truth in that matter; but, on turning to the account given of the cod-fish in the present book (p. 50), it seems to be singularly deficient in its details of the natural history of that animal. So far as we can observe, no reference whatever is made to the theory of Sars with reference to the floating of the eggs, but a few pages relative to the personal adventures of the author are not wanting, whilst the old story of "the Logan fish-pond" is re-told with great circumstantiality. Twenty-five pages of the work are devoted to the salmon (*Salmo salar*), and the essay, confused as it perusal, although it contains, a the book, a good deal about Mr. tulates, as usual from *Land and* some of the big fish in "my mus tedious process to anatomise the co History of British Fishes"; taking its true value, we set down the v collection of miscellanea. The Loch Leven trout (*Salmo Leve* meagre, as is likewise the de other fresh-water fishes, notably Maben. The most suggestive par is that which is devoted to "P to 375). Under the title of "Th Ponds," much interesting matter is of information that must be new to forth. But notwithstanding the m ture which have at various times questionable if the cultivation of than the salmon would *pay* as a foo supply of trout would no doubt be w because the trout is *the* fish of the moreover in many places angling ha and lairds in Scotland who let their always lease them to greater adva well stocked.

OUR BOOK SHE

Proceedings of the Aberdeenshire A tion. (Fourth Annual Repo

WE have here an account of the experiments carried out by Mr. Jam deenshire Association during the ye experimented on were turnips and the principal object in view was to parative manuring value of vari different states of aggregation. only a few points in the results. Mr. Jamieson claims to have s powdered mineral phosphate, as, for coprolite, is nearly equal as a manur same amount of phosphate applied in superphosphate, while the simply p is of course much cheaper than the ma There is probably no doubt that on powdered mineral phosphate is suf produce a considerable effect on th phosphate is applied in sufficient c present a considerable surface for a Jamieson belongs the credit of giving fact, though it was by no means u experiments. There is however no re that dissolved and undissolved phosph manurial value. When large doses the manures may appear of equal v the undissolved phosphate is sufficie the crop, the dissolved phosphate requirements, and is therefore wastefu Jamieson applies 100 lbs.[1] of phosph both as dissolved and undissolved ph say, about 3 cwts. of bone ash and superphosphate. Such a comparison unfair to the soluble phosphate. crops obtained in Mr. Jamieson's expe

[1] On page 15 of the appendix the amount of ph acre is stated to be 100 lbs., but on page 16 the quan

d with the seed would be found
obably fully equal in effect to twice
phoric acid applied as powdered

applied alone was found to have
the turnip crop, and the effect of
m was but little; this is pretty
spect. There is apparently some
ed analysis of the phosphate of
is made to contain 38·28 per cent.
·6 per cent. of ferric oxide and

of the turnip soils cannot pass
reporter is surely unaware of the
analyses present. The soil of
the five experimental fields was
again in 1870, after three turnip

The analyses show that on an
cent. of the nitrogen, and about
sphoric acid in the soil had been
three years, and yet the total
in crops grown on the five fields
aged but 16 tons per acre! The
e reporter on these figures is that
ecome reduced in nitrogen, and
tates; the fact that either the soil
s must be utterly wrong seems to
his attention.

oats do not call for any special
he patience which shelled 136,000
r to determine the proportion of
duce of the various plots.

in a report of field experiments
d of harvest should always be
ription of the character of the
owing period. Without such
possible to interpret the results

ion Mathematical Society. Vol.
879, to November, 1880).

e than usual, there being fewer
m of a great length. The pure
ewhat more than a mile over the

es articles "On the Binomial
risection and Quadrisection," a
gonometry, on a formula of el-
Cockle writes "On a Binomial
nts of its Complete Solution."
n a Method of obtaining the
plitude in Elliptic Functions";
; "Notes on a General Method
ential Equations of the First
dent Variables," and a proliminon of Pfaff's Theorem; Mr J. J.
e Calculus of Operations"; and
a a Class of Dionne Integrals."
nature are—Mr. J. Griffiths, on
nden's theorem with regard to
a class of closed curves whose
perty as two Faganian arcs of
the focal conics of a bicircular
, on the equation of two places
ch two given points to touch a
olme, a form of the equation
directions of a conic whose
dinates is given. Dr Klein of
the transformation of ellip-
dll applies elliptic co-ordinates
of motion to Euler's problem
nd Mr Routh writes on funcs functions. Lord Rayleigh's
vibrations at the confines of

two media between which the transition is gradual, and on the stability or instability of certain fluid motions. Mr. Samuel Roberts has two notes: one on a problem of Fibonacci's, and the other on the integral solution of $x^2 - xy^2 = -z^2$ or $\pm 2z^6$ in certain cases; Mr. R. F. Scott writes on cubic determinants and other determinants of higher class, and on determinants of alternate numbers (a treatment which he has adopted in his work on "Determinants"). Mr. Hugh McColl contributes a fourth paper on the calculus of equivalent statements (cf. Prof. Jevons's remarks, NATURE, vol. xxiii. p. 485). Other minor articles conclude the volume.

LETTERS TO THE EDITOR

[The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts. No notice is taken of anonymous communications.

[The Editor urgently requests correspondents to keep their letters as short as possible. The pressure on his space is so great that it is impossible otherwise to ensure the appearance even of communications containing interesting and novel facts.]

The New Museum of Natural History

THE new Natural History Museum, opened on Easter Monday, was visited by some 16,000 people of a most orderly and respectable class. Owing to the great exertions of Dr. Woodward, whose zeal is beyond praise, the main gallery, the Pavilion, and the Gallery of Reptiles were shown in a practically completed state. The Mineral Gallery has long been ready, but the arrangement of the botanical section is still incomplete, and it was entirely closed. Some little trouble was caused with the umbrellas, and it might be worth a hint to consider whether a cloak portal is not wanted, the umbrella need be taken away. The idea that people poke with sticks at objects in museums has been long exploded, and no inconvenience is felt at the Kensington Museum, the Louvre, and nearly all foreign galleries and exhibitions, where umbrellas are admitted.

The architecture in the Mammalia Gallery is very effective, and its over-massive character and the variety of tone of the terra-cotta, and the similarity of this material to the shells and skeletons of the fossil mammalia, are most felicitous.

It seems a pity that some style with more repose than "Venetian Renaissance" was not selected. Although very beautiful as a building, and with many features deserving high praise from an architectural point of view, it is evidently not the style most adapted to show off natural history specimens. The polished tiles, Indian Museum, with its rather stark side-chapels, and the Museum of British Zoology are of proportions that will render it difficult to make an effective display in them.

I hope that it is not finally decided to place the recent mammalia on the first floor and the fossils on the ground floor, because the architect's string course would be interfered with otherwise by the cases. The living and extinct mammalia should face each other, and the birds go aloft. Convenience has already been too much sacrificed to architecture. Every time the first floor is visited the length of the Index Museum, 150 feet, must be traversed to reach the stairs, and the same distance must be run by the custodian to reach the door of the Mineral Gallery. That means an immense waste of time. I also notice that the crane is close to the main entrance, and that there are no power lifts.

If it was ever easy to fashion all the ornaments from natural-history objects, it is a pity that the restorations were not accurately made. The oft-repeated figure of a Dipterus wallowing a fish almost its own size, and of spiral shells large to accommodate them to the moulding of an arch, is not instructive. The humour of ornamenting the arch leading into the pavilion with a hideously represented Archæopteryx in high relief, repeated a dozen times, is not obvious, but some joke must doubtless be intended.

The rest of the small bronze and glass conservatories in the botanical department is out of all proportion to the objects they are to contain. Dried stems of tree-ferns and palms, though very interesting in their way, do very well in other museums without glass cases, and can be replenished for next to nothing.

F. G. S.

The Tide-Predicter

MR. EDWARD ROBERTS' letter in NATURE for April 14 contains statements giving an erroneous view of the origin of the tide-predicter. Any one who feels sufficient interest in the subject to derive full information will find it in my paper on "The Tide-Gauge, Tidal Harmonic Analyser, and Tide-Predicter," read before the Institution of Civil Engineers on March 1 and in the abstract of the discussion which followed it, to be published in the *Minutes of the Proceedings* of the Institution (vol. lxv. sess. 1880-81, part iii.), and he will see that my letter in NATURE of March 31 is correct.

WILLIAM THOMSON

The University, Glasgow, April 16

Geological Relations of Gold in Nova Scotia

IN the notice of the report of Mr. Murray on the gold of Newfoundland (NATURE, vol. xxiii. p. 472) I observe a reference to my own opinion of the age of the gold of Nova Scotia which needs some correction. In the second edition of "Acadian Geology" (1868) the gold-bearing series is included in the Lower Silurian, but this referred to the larger sense of that term in which it was used to include the Cambrian as well. In the third edition (1878, Supplement, pp. 81, 85, 92) I have referred this formation, on the evidence of fossils and stratigraphical position, to the age of the Lower Cambrian or Longmynd series, thus placing it on a lower horizon than the fossiliferous Primordial of Eastern Newfoundland, which I suppose to be of the age of the Acadian or Menevian group. There is therefore little difference between Mr. Murray's estimate of the age of the gold-bearing rocks of Newfoundland and my own of that of the similar rocks in Nova Scotia, except that I presume he would classify the Newfoundland series as Upper Huronian rather than Lower Cambrian. With reference to this I have been disposed to regard Mr. Murray's *Aspidella* slates and the associated rocks as equivalents of the Kewenian or "Upper copper-bearing group" of the West, and probably Upper Huronian, in which case they might be a little below my Nova Scotia Lower Cambrian; but the precise age of both series is determined merely by the fact that they appear to belong to the period between the Huronian proper, or Lower Huronian, and the Acadian group, or Menevian (Etage C. of Barrande).

It is proper to add that in the third edition of "Acadian Geology" I have shown that the filling of the Nova Scotia gold veins is much more recent than the containing rocks, and belongs to the time intervening between the Upper Silurian and the Lower Carboniferous, the richer deposits also appearing to be related to the occurrence of intrusive granites of Devonian age. There is no reason, therefore, other than the mineral character of the containing beds, why such veins might not occur in any rocks older than the Devonian, and gold discoveries have been reported in localities where the rocks are supposed to be Huronian and Silurian; but I have had no opportunity of personally verifying these statements. Thus far the important gold veins are known only in that great series of slates and quartzites of the Atlantic coast which I have referred to the Lower Cambrian.

J. W. DAWSON

McGill College, Montreal, April 4

Symbolical Logic

PROF. JEVONS, in his criticism of my method in NATURE, vol. xxiii. p. 485, has stated the main points at issue between us so fully and clearly, and on the whole so fairly, that I need only say a very few words in reply.

As to the charge that my method is ante-Boolian or anti-Boolian, I do not seek to repel it; on the contrary, I maintain that my method is different from Boole's in principle, and very different indeed in its practical working. The really important questions to be settled are these:

1. Are the definitions which I give of my symbols clear and unambiguous?

2. Are the rules and formulæ which I derive from these definitions correct?

3. Are the innovations which I propose of any practical utility?

Now, I do not think that any one who has read my papers in the *Proceedings* of the London Mathematical Society and my articles in *Mind* and in the *Philosophical Magazine* will refuse to answer *Yes* to questions 1 and 2; and with regard to question 3 I can only say that any one who answers *No* is bou... ness to prove the inutility of my innovations by solving ... two of my hardest problems without their aid, and in a ... clear and concise manner. My proposal of an amend... in the *Educational Times* meant nothing more serious ...

Some of my critics (not including Prof. Jevons however ... anxious to magnify the points of resemblance betw... method and its predecessors, especially Boole's, and to ... the points of difference. It may be as well therefore ... briefly what characteristics distinguish my method, ... know, from all the methods which have preceded it, ... advantages, in my opinion, accompany these characteris...

In the first place, then, every single letter in my nota... well as every combination of letters, denotes a *statem...* this simble device I gain the important advantages of ... of expression and uniformity of interpretation and treatm... enables me to express many important logical laws a ... and symmetrical formulæ, as, for instance,

$$(A : a)\,(B : b)\,(C : c) : (A + B + C : a + b + c),$$

which otherwise could not be so expressed. To secure ... advantages I sacrifice absolutely nothing. The rela... classes, including the ordinary syllogisms, I express by ... throughout of *one individual*, just as mathematicians ex... properties of curves, surfaces, and volumes, by speaking ... out of the varying distances *of one representative point*.

My claim to priority on this head has been called in ... on the ground that Boole too, in his equations about "... propositions," denotes statements by single letters. The ... truth however is that Boole takes some pains to prev... readers from imagining that he does anything of the ... says distinctly, and in perfect consistency with the whole ... of his book, in which he describes his algebra of logic ... offshoot and part of the ordinary algebra of quantity, the ... equations any single letter, such as x, denotes the *portion* during which some proposition x is true, the whole time to which the discourse refers being the unit (see "Laws of Thought," from p. 164 to p. 170). Neither will one ... where in Boole's work the idea (suggested to me by ... geometry) of investigating the relations of different classes ... speaking only of *one individual*, and thus dispensing ... with the quantitative words *all*, *some*, and *none*, which ... characteristic of the old logic.

Another peculiarity of my method is that my symbol of ... (an accent) is made repeatedly to apply to expressions of ... complexity, as, for instance, $(x\,y)'$, $(x + y\,z)'$, $(x : y')'$, ... rules and formulæ of operations, to which I find no ... any prior symbolic system with which I am acquainted.

Boole uses $\bar{x}$ as an abbreviation for $1 - x$. Let those ... insist that Boole's horizontal stroke is exactly equivalent ... accent express in his notation the complex equation

$$(x = y)' = (x : y)' + (y : x)',$$

and explain its meaning clearly *without departing from ... quantitative interpretation of his symbols*.

Lastly, my symbol : expresses *implication* or *inference*, ... not, therefore, exactly coincide in meaning with Prof. ... symbol of inclusion —<, as defined by him in his "Logic ... Relatives," published in 1870. This symbol of inclusion ... understand Prof. Peirce's definition of it, is simply equiva... the words "is not greater than," and is therefore restric... number and quantity. It is true that Prof. Peirce in his ... memoir on the "Algebra of Logic" extends the meaning ... this symbol of inclusion, so as to make it also convey the ... meaning as my symbol of implication; but as this meaning ... published subsequently to my second and third papers in ... *Proceedings* of the Mathematical Society, to which Prof. Pe... explicitly refers in his memoir and accompanying circular, ... this later definition does not bear upon the point in discus...

Prof. Jevons objects to my $\alpha : \beta$ as an abbreviation ... $\alpha = \alpha\beta$, because he thinks it obscures the real nature ... reasoning operation. But one might with equal justice ... on the same grounds to α^3 as an abbreviation for $\alpha\alpha\alpha$, or ... left side of the equation in the binomial theorem as an ab... viation for the right side. The symbol $\alpha : \beta$ is the exact ... lent of $\alpha = \alpha\beta$, just as $\alpha = \beta$ is the exact equivalent of ... $(\beta : \alpha)$, and I do not see that I create any obscurity by ... in any investigation, and at any stage of the investigation, ... ever form seems most suitable for the immediate purpose ... view. But whether I am right or wrong in this opinion ...

mination of my published papers on
Prof. Jevons has very kindly given
plete list. HUGH MACCOLL
gne-sur Mer, April 7

Communism in Greece

, vol. xxii. p. 525, on Aryan villages
lties reminds me of what I saw in
journey through Greece. On St.
val with the Greek peasants, when
ount Cithæron between Thebes and
n, who was about half a mile ahead,
men, and then pulled from his horse.
interpreter, guide, and protector, the
matter of course, thinking we had
ls; but when I reached the scene of
d that the yelling and uproar heard
murderous nor at all malignant, but
agged from my horse also, and sur-
ung fellows with shaven heads and
ed, half drunk, and very dirty, but

o join in a wild dance, a survival of
ty, which we improved very success-
. Clayton, from Delaware, doing a
sailor's hornpipe.
ur dragoman we learned that the
others, and that the old man with
vely looking on and playing a sort
was their father. On our expressing
sons being so nearly of the same age
not always signify a blood relation,
agricultural brethren. They were
ers (I do not remember which) of
the surrounding land, which they
n of the old man whom they had
was entrusted with the custody and
profits, who arbitrated in cases of
beyed in most things.
ism of communism that we after-
instances, but in this and the other
unmarried men. There were no
visible on this farm, which was
arest village, Platæa.
brigands, were united in similar
ured all communication with the

ir dance and paid for sufficient
circle we found that before going
rs or give mortal and dangerous
man, with the inventive faculty of
this by solemnly stating that in
ed custom to show respect for a
er only, and bowing separately to

urther particulars concerning the
communities, cannot say whether
e Greeks or the Albanians (the
on of the agricultural population of
when the brothers become married
it with no account of them in the
not at all surprised at this, seeing
norance of everything pertaining
is most glaringly displayed by
ho speak of Athens as though it
proceedings as though they were

rather startling festive encounter
ticular holiday, we might have
eeting any visible indications of
have passed the brothers if they
the patriarch had he been sitting
thout special notice. It was only
cited that we discovered other
by special inquiry where their

E there may be some who have
Greek people, outside of Athens,
g particulars concerning these
curious communities. They may be survivals of our ancient communism, or a modern device for mutual protection forced upon the rural population by the absence of any enforcement of law and social order by those who consume the taxes in Athens.
W. MATTIEU WILLIAMS

Heat of Stellar Masses

I SEND you a working hypothesis which I think will well pay for its place in the world. It is as to the heat of large stellar masses; that the imperfect conduction of the kinetic force producing gravitation through large stellar masses causes heat in them.
The quantity of heat stored up may depend partly on the proportion of mass to radiating power, and partly, perhaps, on the condition of the mass for such conduction.
Washington, D. C., March 25 SAML. J. WALLACE

Shadows Cast by Venus

ON March 21 last, about 8 p.m., I was walking among some trees by a river's bank. The ground was covered with recently-fallen snow, and the shadows of the trees were unmistakably, though faintly, traceable on the white surface. The night was dark and the shadows were thrown by Venus, which was shining with unusual brilliancy. I believe this obvious form of the phenomenon is not a common one in our latitude.
CHAS. T. WHITMELL
31, Havelock Street, Sheffield, April 18

The Sparrow and Division of Labour

THE following curious fact may possibly interest your ornithological readers:—Last year and the year previous two pairs of swallows made their nests and successfully reared their broods under the eaves of my house. Within the past fortnight a brace of astute London sparrows have apparently recognised the principle of division of labour as applicable to their requirements in the art of nest-building. They have selected the largest and most substantial of the swallows' nests referred to; and, after devoting a day or two, on starting on their enterprise, to the enlargement of the entrance hole, which was probably too narrow for them, have constructed their bed within of bits of grass and feathers in the usual fashion. They are now enjoying their honeymoon in their new quarters. G. C. WALLICH
3, Christchurch Road, Roupell Park, April 11

SIR PHILIP DE MALPAS GREY EGERTON, M.P., F.R.S.

IN Sir Philip Egerton geologists have lost one of that band of workers who placed their science upon the footing which it now occupies in this country. Unfortunately that band has been of late years greatly diminished by death. Born in 1807, Sir Philip Egerton with his old friend and fellow-worker, Lord Cole (now the Earl of Enniskillen), while still at Oxford commenced the collection of fossils, and very soon their attention was especially directed to fossil fish, of which but very little was at that time known. As specimens of this group of organisms often occur in duplicate, the individuals breaking across so that two opposite slabs each contain one-half, the two friends agreed to share their spoils, and thus both collections were enriched. When in 1840 Agassiz visited this country, intent upon his great ichthyological memoirs, he found in the museums of Sir Philip Egerton and Lord Cole an abundance of materials ready to his hand. The specimens were carefully figured, and descriptions of them included in the several great works which Agassiz successively issued. The original drawings by Dinkel are now among the archives of the Geological Society. But Sir Philip Egerton was by no means merely a collector of fossils, he was a very diligent and successful student of ichthyology. Many valuable papers on fossil fishes were written by him at different times, and a series

of papers published in the decades of the Geological Survey of the United Kingdom are among the most valuable of the works issued by that body. An excellent man of business, Sir Philip took an active part in the administration of the British Museum, the London University, the Geological Society, and other institutions for the promotion of science. All who knew him will miss the kindly face and cheerful manners which distinguished him. Only two days before his death he was in his place in Parliament, but a chill caught during the lately prevalent east winds proved rapidly fatal. At the last meeting of the Geological Society the vice-president, Mr. J. Whitaker Hulke, F.R.S., made announcement of his death, and the sudden and unexpected tidings concerning one who was so widely known and so universally respected cast a sad gloom over the proceedings of the evening.

A correspondent sends us the following additional note on the late Sir Philip Egerton:—

The knowledge of the extinct species of fishes is one of the latest additions to palæontology, and the creator of this department of the science, Louis Agassiz, found the richest materials for his great work in the British Isles. In their acquisition he was greatly aided by Lord Cole, now Earl of Enniskillen, and by Sir Philip de Malpas Grey Egerton, Bart., M.P. Their gatherings resulted in most complete collections of fossil fishes, and science is much indebted to the catalogues drawn up and published by Sir P. Egerton of that preserved at Oulton Park. Besides the species named by Agassiz this collection includes many which have been subsequently determined and described by Sir P. Egerton, whose name will be ever associated with that of Agassiz in palichthyology. In his public career Sir Philip Egerton has been distinguished by his unremitting attention to his parliamentary duties in the long period since his election in 1830. The British Museum sustains a severe loss in a Trustee, elected in 1851, whose scientific knowledge, sound judgment, and administrative ability were of the greatest value, especially to the Natural History Departments. Sir Philip's last attendance at the Board was but a few days—apparently in his usual good health—before his lamented death.

THE SCIENTIFIC PRINCIPLES INVOLVED IN ELECTRIC LIGHTING

FOUR Cantor Lectures on this interesting subject have just been delivered at the Society of Arts by Prof. W. Grylls Adams, F.R.S.; the lectures will be published in full in the *Journal* of the Society of Arts, but we are able to give an abstract of them by Prof. Adams. In the first lecture, the discoveries of Œrsted, Ampère, Arago, and the early discoveries of Faraday on magnetic and current induction were considered in their relation to the principles of conservation and transformation of energy.

Lecture I.—Prof. Adams began by stating and illustrating the fact that important discoveries, after they are made, often pass through a stage of neglect or a stage of quiet development, then enter on the practical stage, when new facts and new inventions follow with great rapidity. The potential energy of the discoverer is transformed into energy of action in many directions with more or less efficiency, according to the retarding state of the medium through which that action takes place.

Electrical science has passed through these stages, whether we regard telegraphy from the work of Sir Francis Ronalds in 1816, who said, "Let us have electrical *conversazione* offices communicating with each other all over the kingdom," down to the establishment of telephonic exchanges, or whether we consider electric lighting from the grand experiment of Sir Humphry Davy in 1813 with a battery of 2000 cells, down to the latest results obtained by means of the most [illegible] magneto- or dynamo-electric machines.

In the year 1819 Œrsted observed the action [illegible] current of electricity on a suspended magnetic [illegible] and in the year 1820 Ampère studied the laws of [illegible] mutual actions, and propounded his celebrated theory [illegible] magnets and of terrestrial magnetism, making magnetism [illegible] the resultant action of electric currents. In the same year Arago discovered the magnetisation produced [illegible] electric currents, laying the foundation of the science [illegible] electro-magnetism.

The discoveries of Œrsted, Ampère, and Arago were [illegible] fully illustrated by experiments, and their connection [illegible] with one another explained. In the same year [illegible] Schweigger invented the galvanometer, and in 1827 [illegible] deduced his simple theory of the action of batteries [illegible] the principle of Volta.

The relation of the experiments of Œrsted, Ampère, [illegible] and Arago to the principle of conservation of energy [illegible] then fully considered. Considering Ampère's experiment of the motion of wires towards one another [illegible] when like parallel currents are flowing in them, it [illegible] shown that the currents must be diminished while they [illegible] are actually approaching, and increased whilst they are [illegible] separating, and so by supposing one of the original currents very small, the relation between Ampère's theory [illegible] and the induction of a current by moving a wire in the neighbourhood of another current was deduced.

The laws of induced currents were then explained and illustrated by some of the early experiments of Faraday, who discovered the induction of electric currents by magnets in 1831.

"In his first series of papers to the Royal Society, entitled—(1) On the Induction of Electric Currents, (2) On the Evolution of Electricity from Magnetism, (3) On a New Electrical Condition of Matter, (4) On Atomic Magnetic Phenomena, Faraday unfolds step by step the laws of the induced current in a helix of wire B placed near to another helix A, carrying a voltaic current.

"That as long as a steady current was maintained in A there was no current induced in B; that on making contact in A or on approaching the wires there was a momentary inverse current in B, and on breaking contact in A or on separating the wires, there was a momentary induced current in B. That as this current was of the nature of an electric wave like the shock of a Leyden jar it might magnetise a steel needle, although it produced a slight effect on a galvanometer, and how this experiment was confirmed, and that the needle was magnetised in opposite ways on making and on breaking contact. Then in his evolution of electricity from magnetism he gives an account of the greatly increased effects on introducing soft iron cores into his helices of wire, and shows that similar effects are obtained by using stationary magnets in place of a helix carrying a battery current round an iron core, *i.e.*, in place of an electro-magnet. He then describes the experiment of introducing a magnet into a coil of wire, and shows that the same current is obtained whether the marked end of the magnet be introduced at one end of the coil or the unmarked end introduced at the other, and that a current is produced in the opposite direction to the former on withdrawing the magnet from either end. Then after describing the method of producing his induction spark and the muscular contractions of a frog by means of a battery and coil, and remarking that the intensity of the spark produced depends upon the rate of separation of the wire from the poles of the loadstone, he concludes thus: An agent which is conducted along metallic wires in the manner described; which, whilst so passing possesses the peculiar magnetic action and force of a current of electricity; which can agitate and convulse the limbs of a frog, and which finally can produce a spark, can only be electricity.

d the difference of time between
urrent in a coil, which is instan-
by a magnet, which requires an
p to its full value ; and accounted
pposing that there is a redistri-
currents in the iron itself, so that
e to rise to its full power.
am of the rapid development and
uch were to flow from his experi-
ago, he established the laws of
duction, being stimulated (as he
erimentally the inductive effects
the view of elucidating Ampère's
letism, and in the hope of obtain-
ary magnetism.
wn in the last lecture that a circu-
a coil of wire acted as a magnet,
ich, as we look at it, the current
o the hands of a watch, corre-
l pole or the pole of a magnet
h, and the opposite face of the
hat pole of the magnet which
Each of the Amperian circular
olecules of a magnet is equiva-
th poles of the same magnetic
nd occupying the same position,
mperian currents will have the
the bundle of small magnets,
direction of the magnetic force
urate fine magnets may be re-
s of force, and the number of
netic pole will be a measure of
net. The magnetic field of the
space to which the influence of
e current which will be produced
cting wire in the magnetic field
e strength of the magnetic field,
number of lines of force cut by
e current produced in each half
olving on an axis is proportional
force cut by the coil during its
current from the coil will be
ber of lines of force multiplied
the wire is repeated in the coil.
wire rotating in the field of a
ation is parallel to the lines of
ed, but as the axis of rotation
e nearly at right angles to the
in the coil is increased. Taking
, when the axis of rotation is
s of force and still in the mag-
it in that half of the coil which
ist will be from north to south,
other half of the coil which is
will be from south to north, so
ger during every half turn an
irection in the coil. The direc-
coil, as we look at it from the
direction of rotation of the coil
north. The direction of the
ately in opposite directions for
inuous current may be obtained
nnections with the ends of the
e same instant as the currents

es of all magneto-electric ma-
of lines of force in the magnetic
nagnets is well shown by pro-
P. Thompson's transparencies,
effects resulting from the mutual
nets on one another.
araday, in 1831, of the method
of electricity by the sudden
rom the pole of a magnet, the
laws of these currents were being developed, but for twenty years no attempt was made to apply them for the purposes of electric lighting. Voltaic batteries were being improved, and the more constant batteries of Daniell, of Grove, and of Bunsen were discovered, and these were the sources of electricity employed to produce the more powerful currents of electricity. In this country forty or fifty cells of Grove have given us the electric light for optical experiments in our laboratories, and the light was kept steadily in the same position by the elaborate arrangements of wheel-work and electromagnets devised by Staite in 1847 and by Foucault, which have reached very great perfection in the hands of Duboscq. In the Duboscq lamp the current passes always in the same direction, and the positive carbon becomes hollowed out, and burns away about twice as fast as the negative carbon, which becomes pointed. The carbons are moved towards one another by means of a drum carrying two wheels, whose diameters are as 2 to 1, which move two racks which bring the carbons together. This lamp is especially adapted for projection on a screen, and we may study the forms of the carbons by projecting them, and also study the kind of light given out by the vapours of metals burning in the arc ; if we burn silver in the arc we shall see that it is rich in the violet or chemical rays, which points to the reason why the salts of silver are so much used in photography.

Even with constant batteries there is great variation in the steadiness of the electric light, but much more is this the case when the current of electricity is obtained by the motion of a coil of wire in a magnetic field, for every alteration in the resistance in the circuit reacts on the machine producing the current so as to increase the disturbance. Hence regulators are necessary in order to control the current, so as to keep the light constant. In electric lighting regulators may act on the electric lamps themselves so as to give a steady current between the carbons by keeping them the same distance apart, or regulators may be used in another part of the circuit to control the current automatically by causing it to introduce extra resistance when the current increases, and to diminish the resistance when the current diminishes.

Various methods of regulating the current, including those employed by Siemens, Lane Fox, and Edison, were then described. In order to find the yield or effective work of batteries or magneto-electric machines and their efficiency, measurements of the current and of the work done by the current must be made.

There are four principal methods of measuring electric currents :—

1. The galvanometer method, by which with a galvanometer of small resistance a very small fraction of the current is measured, and any error of observation is multiplied in estimating the total current flowing.

2. The heat method, in which the current is measured by the heat developed by the current in a given resistance in the circuit according to Joule's law, that the heat is proportional to the square of the strength of current.

3. The electrometer or potentiometer method, in which the difference of potential between two points in the circuit with a given resistance between them is directly measured and the current deduced from Ohm's law.

In using Thomson's quadrant electrometer for strong currents, the needle and one pair of quadrants should be connected together, so that the deviation is then proportional to the square of the difference of potential, and this method is applicable for continuous currents and also for alternate currents. By means of two electrometers in different parts of the circuit the current and also the work done by it may be at once measured. If, for instance, one of the electrometers be connected with the two carbons, the difference of potential and work done between the carbons may be determined. By such measurements it has been found that there is an electro-

motive force of 30 or even 40 volts between the carbons in the electric arc, but that the actual resistance of the arc is small.

4. The electro-dynamometer method, the best method fitted for ready measurement, in which the current in one coil is attracted by the same current flowing in another coil, and the attraction is balanced by a spring as in Siemens's electro-dynamometer, or by weights as in Trowbridge's electro-dynamometer. A beautifully-made instrument by Elliott and Co. was exhibited, in which the coils are thick copper bands, fixed coils being placed on each side like the coils of a tangent galvanometer, the suspended coil being placed between them in place of the magnet of the galvanometer. This instrument is especially useful for the measurement of very large currents in absolute measure.

The remainder of the second lecture was devoted to the consideration of the efficiency of batteries or of magneto-electric machines when employed as motors to do work by means of electricity, and it was shown that the greatest amount of effective work is produced when one-half the energy of the battery or current-generating machine is converted into useful work in the electric circuit. Numerous experiments were made with Clarke's and other magneto-electric machines to show that by the same machine work may be produced by sending a battery current through it, causing motion of the armature carrying the current in accordance with Ampère's laws, or a current of electricity may be generated by turning the armature, *i.e.* by doing work upon the machine, so that a magneto-machine is a reversible engine. A small magneto-machine with a Siemens armature was made to work a pump, or when turned by hand produced a current of electricity. Also a battery current in a Gramme ring in front of the poles of a Jamin magnet caused rotation of the ring and turned the heavy driving-wheel of the machine, and on removing the battery and turning the driving-wheel by hand, a current of electricity was produced which caused a piece of platinum wire to glow. Also a Tisley's hand dynamo-machine was employed either to heat a long piece of platinum wire or to drive another magneto-electric machine, so producing a secondary current capable of heating a considerable length of platinum wire.

(*To be continued.*)

THE FRENCH ASSOCIATION FOR THE ADVANCEMENT OF SCIENCE AT ALGIERS

Algiers, April 14

THE number of members enrolled for the present Congress is much larger than might have been expected when we consider the length of the journey. To a Parisian member this is such as would be experienced by a Londoner if our British Association met in Gibraltar. Yet more than 1500 names are on the list. Few of these are familiar to us. There appear to be an unusual number of doctors and professors of anatomy and physiology, and of civil engineers. We fear we must also confess that a great many people possessing little or no interest in science, who will not be present at a single sectional meeting, have joined the Association for the sake of seeing Algiers. The general character of the meeting appears to be that of a great excursion. There are only five days partially devoted to work; while the banquets, balls, fêtes, courses, and "fantasias" are rapidly multiplying.

On arriving in Paris we were told that the steamer which was to have conveyed us to Algiers had been requisitioned by the Government for the transport of troops to Tunis; but the Company determined at last to take both soldiers and *savants*, and the result was of course an overcrowded boat and excessive discomfort. With accommodation for fifty first-class passengers no less than one hundred and twenty-nine were crowded in the vessel, and had the voyage been anything but the smoothest, it would have been most wretched. As it was bad enough; the food was insufficient in quantity and detestable in quality, and passengers were glad to find six feet of floor to sleep upon. In Algiers itself hotels are quite full, and the salons will be used as dormitories.

The Congress will be opened to-day by the inaugural address of M. Chauveau, which is to be given in the theatre at three o'clock, after which the members will remain and resolve themselves into a general committee to discuss the creation of a sixteenth section relating to pedagogy; afterwards the secretaries of sections will meet to arrange their proceedings, and at 9 p.m. the members will be received by the Municipality at the Hôtel de Ville. The general programme for the rest of the week is as follows:—

Friday, April 15.—Sectional meetings in the forenoon, general meeting at 2 p.m.; conference at half-past 3.

Saturday.—Sectional meetings in the morning, excursion to the Algerian Exhibition in the afternoon; Arab fête and a *soirée* given by the Municipality.

Sunday.—"Courses et fantasia."

Monday.—Sectional meetings in the morning; grand procession through the town in the afternoon, and a ball or *fête* in the evening.

Tuesday.—Sectional meetings; general concluding meeting; in the evening a ball given by the Governor.

On *Wednesday* the excursions commence; there are both general and sectional, and the longest lasts a fortnight.

A complete list of the papers to be read has not yet appeared, but in the list already published we do not notice anything of special interest.

English science is represented by Dr. G. H. Glaisher and Mr. Siemens, who will both read papers.

The Association has presented to each member a work in two volumes entitled "Notices scientifiques, historiques, et economiques sur l'Alger et Algérie."

April 16.

The theatre was well filled yesterday afternoon to hear the address of the president, M. Chauveau, who is Professor of Physiology in the Lyons Veterinary College. His discourse was of a far too technical character to be of interest to the majority of his audience, and dealt principally with the germ theory and Pasteur's theory of fermentation. It was read throughout without the slightest attempt at oratory, and it contained various political allusions which were much applauded. In the evening the members were entertained by the Municipality, and the town was illuminated. The real work of the Association commenced this morning, when the sections met at hours varying from eight to ten o'clock. We fear that the number of papers is small, and that the Association does not represent French science at all completely. In the Physical Section, for example, the names of only two authors of papers appear to-day—MM. Brillouin and Crova. At 9 a.m., when the section was announced to meet, no one was present. Shortly afterwards the secretary arrived, but an hour later the section had not met. The average number of the audience at the sections which had already met did not at this time exceed ten.

Among the more interesting papers announced for to-day are the following:—M. Marcheray, on Telephonic Communication in large towns; M. Tacchini, on the Observatories of Etna and of Chimona; M. Thoulet, on the Employment of the Microscope in Chemical and Physical Researches connected with Mineralogy; M. Prungrueber, on 300 Anthropological Observations on the Kabyles of the Djurdjura Mountains.

The Medical and Agronomical Sections have also communications. The new section of Pedagogy has been established under the honorary presidency of

odard, Director of the École Monge in Paris, who has ought twenty of the pupils with him. M. Fau, ttorney-General of Algiers, is the President, and two ıpers are announced for to-day:—One by M. Robert, ı the Humanitarian and Pedagogic Ideas of Jean omimiac (1572-1670); the other by M. Berdellé, on the mployment of Colours as a Means of Retaining in the ind certain given Numbers.

An excellent geological map of Algiers to the scale of in 800,000 has recently been completed, and the forma- on of it has led to the simultaneous observation of ırious facts connected with the physical geography of ıe Central Sahara. A map of the proposed interior sea of ıe Sahara has also been prepared, and the Trans-Sahara ailway is spoken of as more than a probability. But e very much doubt if this can ever be a success. If it onnected flourishing towns or portions of territory in hich great cities are ever likely to be established, as in ıe case of the new American railways, there would be ome hope for it. As it is, however over-populated the orld may become, there is no likelihood of the forma- on of settlements in the heart of an unhealthy tropical egion.

G. F. RODWELL

MR. DARWIN ON VIVISECTION

FROM the *Times* we reproduce the following letter addressed by Mr. Darwin to Prof. Holmgren of Upsala, in answer to a request for an expression of his opinion on the question of the right to make experiments on living animals for scientific purposes—a question which is now being much discussed in Sweden:—

"Down, Beckenham, April 14, 1881

"Dear Sir,—In answer to your courteous letter of April 7 I have no objection to express my opinion with respect to the right of experimenting on living animals. I use this latter expression as more correct and comprehensive than that of vivisection. You are at liberty to make any use of this letter which you may think fit, but if published I should wish the whole to appear. I have all my life been a strong advocate for humanity to animals, and have done what I could in my writings to enforce this duty. Several years ago, when the agitation against physiologists commenced in England, it was asserted that inhumanity was here practised and useless suffering caused to animals; and I was led to think that it might be advisable to have an Act of Parliament on the subject. I then took an active part in trying to get a Bill passed, such as would have removed all just cause of complaint, and at the same time have left physiologists free to pursue their researches—a Bill very different from the Act which has since been passed. It is right to add that the investigation of the matter by a Royal Commission proved that the accusations made against our English physiologists were false. From all that I have heard however I fear that in some parts of Europe little regard is paid to the sufferings of animals, and if this be the case I should be glad to hear of legislation against inhumanity in any such country. On the other hand I know that physiology cannot possibly progress except by means of experiments on living animals, and I feel the deepest conviction that he who retards the progress of physiology commits a crime against mankind. Any one who remembers, as I can, the state of this science half a century ago must admit that it has made immense progress, and it is now progressing at an ever-increasing rate.

"What improvements in medical practice may be directly attributed to physiological research is a question which can be properly discussed only by those physiologists and medical practitioners who have studied the history of their subjects; but, as far as I can learn, the benefits are already great. However this may be, no one, unless he is grossly ignorant of what science has done for mankind, can entertain any doubt of the incalculable benefits which will hereafter be derived from physiology, not only by man, but by the lower animals. Look, for instance, at Pasteur's results in modifying the germs of the most malignant diseases, from which, as it so happens, animals will in the first place receive more relief than man. Let it be remembered how many lives and what a fearful amount of suffering have been saved by the knowledge gained of parasitic worms through the experiments of Virchow and others on living animals. In the future every one will be astonished at the ingratitude shown, at least in England, to these benefactors of mankind. As for myself, permit me to assure you that I honour, and shall always honour, every one who advances the noble science of physiology.

"Dear sir, yours faithfully,

"CHARLES DARWIN

"To Prof. Holmgren"

THE MAGNETIC SURVEY OF MISSOURI

IN the summer of 1878 the writer began a magnetic survey of the State of Missouri. The work of the first summer was confined to the north-east part of the State, and no points of interest were brought out. During the summer of 1879 the work was extended over the western half of the State, and it was made apparent that diversity of surface exerted a much more important influence than had been suspected. The lines of equal declination were found to bend very sharply upon entering the large valleys, and the needle showed a *tendency* to set at right angles to the valleys. This tendency seemed to be greatest when the general direction of the valley made an angle of 45° with the *normal* position of the needle, or roughly, when the valley runs north-east and south-west, or north-west and south-east. This tendency seems to be inappreciable when the valleys run north and south, or east and west.

In the report of 1878 (*Trans.* St. Louis Acad. of Sc., vol. iv. No. 1, p. 143) it was suggested that this might result from the bending of the stream-lines of the earth-current sheet, due to the greater conducting power of the moist valleys. In order to settle this point, further examination is necessary, and it is proposed to determine the earth-currents at a number of properly selected stations.

During the summer of 1880 the work extended over the south-eastern part of the State, where still more important flexures of the isogonic lines were discovered. Here, however, the position of the needle is probably affected by the iron deposits, and the effect of contour is studied to less advantage. At the close of 1880 observations had been made at forty-five stations. In order to bring out the effect of contour, a relief map of the State was constructed in wax, and was finally reproduced in plaster. In this work use was made of the profiles of all the railroads in the State, together with a list of over 300 elevations in the State, collected by Gannett. The isogonic lines, which were first drawn upon an ordinary map, in the usual manner, to represent the observations thus far made, were then copied upon the relief map. In doing this it became apparent at once that the forty-five stations were wholly inadequate, and that the isogonic lines thus drawn are probably deserving of about the same weight that a topographical map would deserve if constructed from elevations at these stations.

The Chart is made after an artotype, which will accompany the third annual report in No. 2, vol. iv. *Trans.* St. Louis Academy of Science. In the original map the horizontal scale is twenty miles to the inch, the elevations being exaggerated 200 times. This exaggeration was necessary in order to bring out the form in the photograph, since on a relief map, 150 feet square, the

greatest difference in elevation in the State would be represented by a vertical height of one inch. The horizontal scale of the cut is sixty-two miles to the inch.

The map represents only the grand outlines of surface as obtained from railroad profiles, and barometrical measurements. The dotted lines on the map are lines of equal variation of the magnetic needle: thus, on every part of the line marked 8°, the needle points 8° east of north, &c. These lines are drawn to represent the observations already made, and show in a general way the variation of the needle in the State. The map also shows that there is a marked relation between the direction of these lines and the contour of the surface. It cannot be said that it shows what this relation is, but it is probably due largely to the deflection of the stream lines of the earth current sheet, caused by unequal conducting power. This explanation necessitates the existence of

looped areas in certain regions in the St
of which is already indicated by the det
loop in the 7° 30′ line, with its incle
probably complicated with the iron depo
of the State.

Three stations in the Missouri valle
vertently omitted in the cut. One of
lies on the 8° 30′ line, a few miles n
Another (Glasgow) lies on the river a l
from Corrollton. The third (Columbi
the 8° line, and about south-east fr
fourth station omitted, is nearly due e
terminus of the 8° line, and just outsi
The other stations, represented by the
shown on the cut, and an inspection of
the weight to be given to different pa
At stations situated at points of abru



lines, the observations have been repeated at various localities in the region, until it was clear that no minute local effects existed.

The value in the Iron Mountain region is the mean of many hundreds of determinations made with a solar compass by Pumpelly and Moore in 1872. This region is in the east part of the 7° 30′ loop. In the western iron-field, which is nearly coincident with the 7° oval, our observations were repeated at various points (the aim being to *avoid* iron deposits) without finding any local action.

In conducting the survey, a magnetometer belonging to Washington University was used, but the dip circle and declinometer were kindly furnished by Prof. J. E. Hilgard of the U.S. Coast and Geodetic Survey. Thus far the survey has been conducted wholly on private means, in which we have been aided by the railroad companies, and by citizens of St. Louis for the completion of the survey is now lature of the State.

FRA

PRIMITIVE MARRIAGE. C

THE chief object of Mr. Fison's memoir on Kamilaroi marriage, de ship, is "to trace the formation of the marrying divisions which have been fou savage and barbaric tribes of the pr show that what Mr. Morgan calls the pu the "Turanian" system of kinship, lo

"Kamilaroi and Kurnai: Group Marriage, Marriage by Elopement; also the Kurnai Tribe, th War." By Lorimer Fison, M.A., and A. W. H Introduction by Lewis H. Morgan, LL.D. (George 1880.)

em. His coadjutor, Mr. Howitt, though he has had me interesting information to give about the Kurnai ibes of Gippsland, has had the same chief object; so at the work the two have produced is much more a olemic on behalf of Mr. Morgan than a record of new ustralian facts. We must begin, then, by stating what Ir. Morgan's theories are (so far as the work before us concerned with them), and indicating, and estimating ie value of, the evidence on which they rest.

Mr. Morgan, having collected a great mass of facts oncerning the terms in use between relations and connections throughout the world, and having found that ose terms were, broadly speaking, divided into three rders, proceeded to spell out of the two earlier orders he third consists of the modern terms of consanguinity nd affinity) the whole of the early history of marriage nd of the family. In what he has called the Malayan ystem of relationships, parent and child, grand-parent nd grandchild, and brother and sister (or rather elder rother, younger brother, elder sister, younger sister, for here are no words for brother and sister) are the only erms in use; and one or other of these terms is used in ddressing a person, according as the person addressed s of the speaker's generation or of the generation above, r of that below it. They are the terms always used hen persons address one another, there being among hose who use the system an invincible objection to the nention of their personal names. Mr. Morgan assumed hat those terms were expressive of consanguinity and ffinity; and conjectured that when first used they accuately described the relationships at the time existing, as near as the parentage of children could be known." And it appeared to him that if there were a body of men nd a body of women in the same tribe who all regarded ach other as brothers and sisters, and all the men narried all the women in a group, there would exist a narriage and family system which would explain the Malayan terms—the relationships arising out of which, o far as they were ascertainable, "as near as the arentage of children could be known," those terms would accurately express.

Accordingly, he framed the hypothesis that the first tage of marriage was the marriage in a group of men nd women of the same blood calling themselves brothers and sisters. The family founded upon this kind of marriage he has named the consanguine family, and he regards it as the earliest form of the family. He does not say that such a system of marriage, or such a family system as he has supposed, has been found at any time anywhere; what he says is that this supposition of his explains the origin of the Malayan terms, and that nothing else can explain them. But does it explain them? It is at once obvious that there is one term, and that the most important of all, the use of which Mr. Morgan's hypothesis does not account for. Paternity may be doubtful—and if it were thought of at all in a group such as Mr. Morgan has conceived of, any man of the group might have as good a right as any other to be called father of any child born within it. But there can be no doubt about a man's relationship to his mother. In the case of mother and child the parentage is known with certainty, and therefore, on Mr. Morgan's hypothesis, a man should in the Malayan system have had only one mother. Now that system applies the term for mother to many women besides the actual mother—mother's sisters, father's sisters, uncle's wives, and so on, if not indeed to all women of the mother's generation. Here then the hypothesis breaks down; and the point at which we find it breaking down is really the only point at which it can be tested. The relationship between mother and child, too, which is confused or ignored in the Malayan system, is the one relationship of which it can be said with confidence that no system really founded on relationship could fail to recognise it. The explanation Mr. Morgan offers is that in the Malayan system the relationship of stepmother "is not discriminated," and there being no name for stepmother, stepmothers had to be called mothers, because "otherwise they would fall without the system." And he has what may be called a subsidiary hypothesis to account for there having been no discrimination between stepmother and mother. It is that the affiliation of children to the groups of men and of women to which they belonged would be so strong "that the distinction between relationships by blood and by affinity would not be recognised in every case." The fact of motherhood would be made little of, that is —there would be no discrimination between stepmother and mother—because the whole group would be, by a child, regarded as its mother. But this is equivalent to saying that, from the nature of the case, it was not to be expected that note should be taken of the relationships that could be known; and that is to abandon the hypothesis—as well as to deny us all chance of judging whether it is a good or a bad one. Possibly explanations of the failure of his hypothesis, such as Mr. Morgan suggests, might have some weight were he accounting for the Malayan terms as terms of address; but he takes them to denote actual relationships "as near as the parentage of children could be known." And no explanations can get over the fact that the Malayan terms are equally extensive in their application where, in the consanguine family, parentage would be known with certainty, and where it would not be known at all. The consanguine family is clearly a bad hypothesis. It might be thought it would hardly seem to anybody a plausible one; but Mr. Morgan always speaks of it as if it were among the best vouched of historical facts; and we are bound to say that Mr. Howitt believes in it as implicitly as Mr. Morgan.

To show the hypothesis of the consanguine family to be unstateable is to undermine Mr. Morgan's whole history of marriage and of the family. But Mr. Morgan has propounded a hypothesis as to the second form of marriage and the second form of the family, and as it is at this point that Mr. Fison (who does not quite believe in the consanguine family) lends him his advocacy, it is indispensable that we should give some account of it. Punaluan marriage, upon which was founded the punaluan family, was introduced by some reformatory movement, according to Mr. Morgan, to put a stop to the evils attendant upon brother and sister marriages. It existed in two forms. In one form of it a group of men, brothers or reputed brothers, had in common their wives who were not their sisters and not the sisters of each other; in the other form, a group of women, sisters or reputed sisters, lived in common with husbands who were not their brothers and not the brothers of each other. Punaluan marriage has not been observed at any time anywhere any more than the consanguine family; but Mr. Morgan believes that, in both its forms, it has existed everywhere, and probably during many ages. A correspondent wrote to Mr. Morgan stating that in the Sandwich Islands men whose wives were sisters and women whose husbands were brothers called each other punalua, which meant dear friend or intimate companion. And possibly drawing his bow at a venture, "the relationship," he said, "is rather amphibious. It arose from the fact that two or more brothers with their wives, or two or more sisters with their husbands, were inclined to possess each other in common." Whether conjecture or fact, this amounts to very little; but it was this which gave Mr. Morgan the suggestion of punaluan marriage. For proof of his hypothesis he again relied upon the terms he had collected—and at first upon its fitness to explain those same Malayan terms which, as we have seen, have more than enough to do to bear the weight of the consanguine family. In his latest work ("Ancient Society") he holds it to be proved by a nomenclature considerably

different from the Malayan—his second order of terms which he has named the Turanian system of relationships. He regards the terms in this system also as accurately describing, "as near as the parentage of children could be known," the relationships existing at the time when they came into use. It differs from the Malayan in including words for cousin, uncle and aunt, and nephew and niece—or words which Mr. Morgan has so translated. It will be found, however, that Mr. Morgan does not use the punaluan family in accounting for any one of the Turanian terms. Those of them which coincide, or partly coincide, with the Malayan terms he had already accounted for by the hypothesis of the consanguine family, and he does this over again; the others he accounts for, or tries to account for ("Ancient Society," pp. 442–445), by means of exogamy alone. His reasoning is exactly what it would have been had the punaluan family never occurred to him. Indeed it has been an embarrassment to him; he has had to keep it out of his reasonings. For the punaluan family is, *ex hypothesi*, in two forms, and neither form could, "as near as the parentage of children could be known," yield both the Turanian sense of father and the Turanian sense of mother. Where the husbands were punalua, Mr. Morgan's reasoning would make them all, though not brothers, fathers of children born within the group, and it would exclude their brothers from being considered fathers. But, in the Turanian system, a father's brothers are called fathers. Similarly where the wives were punalua, Mr. Morgan's reasoning would make them, though not sisters, all mothers of the children of each of them, and would exclude their sisters from being considered as mothers. But, in the Turanian system, a mother's sisters are called mothers. Mr. Morgan has not failed to see this, and he has actually again framed a subsidiary hypothesis to give his hypothesis of the punaluan family a chance of living. This is (see "Ancient Society," p. 445) that where a group of sisters married men who were not brothers, they also became the wives of all the brothers "own and collateral"—that is, all the brothers and one-half of the cousins, however far removed—of each of their husbands; and, similarly, that when a group of brothers married women who were not their sisters, they also became the husbands of all the sisters and one-half of the cousins of each of their wives. All that need be said of this subsidiary hypothesis is that it gives quite a new look to the punaluan family—and that the effect of it, like that of the secondary hypothesis formerly noticed, is to deny us all chance of judging whether the principal hypothesis is a good or a bad one. The justification offered for it is that "the system (the Turanian) treats all brothers as the husbands of each other's wives, and all sisters as the wives of each other's husbands, and as intermarried in a group"—but that is equivalent to saying that the system has taken no impression of the punaluan family, and gives no countenance to Mr. Morgan's hypothesis. As, apart from "the system," he finds nothing to say for it, it is difficult to see how any one can resist the conclusion that that hypothesis must be dismissed, and that it must be ranked among the wildest chimeras that have ever possessed the brain of a man of science.

Now, do Mr. Fison and Mr. Howitt give in any degree to Mr. Morgan's hypotheses the support of which they are in need? The answer must be no—and must be no even if we receive as facts the assumptions as to fact from which they set out. Mr. Howitt accepts both the consanguine family and the punaluan family, while Mr. Fison offers himself as the advocate of the latter only. But Mr. Howitt has nothing new to say for the consanguine family; he believes in it, and argues from it as if it were known historical fact—that is all; and so of it no more need be said. What then do his colleague and he find to say for the punaluan family? Literally, not a word. Mr. Howitt simply takes it for granted as he does the consanguine family. Mr. Fison, in beginning, takes to show that it results logically fro a his type —for it is no more than that—of "exogamous marrying divisions," but he does not attempt to And, in fact, his "intermarrying divisions" are different from the punaluan family, and leave no it, and no room for it; that is, his hypothesis is from and exclusive of Mr. Morgan's. In Mr. hypothesis, a group of men who are considered and a group of women who are considered sisters the men and women of the same generation divisions which intermarry with each other, with each other—are by birth husbands and each other; whereas, in the punaluan family, husbands are brothers the wives are not sisters punalua; and when the wives are sisters the are not brothers—they are punalua. Men brothers are restricted to women who are each sisters, on Mr. Fison's hypothesis; but, on Mr. men who are brothers marry women who, as not each other's sisters. The marriage law Mr. Fison's hypothesis would have to be given the punaluan family could have a chance of justly observes, his intermarrying divisions "wo precisely the reformatory effect" which Mr. attributes to the punaluan family—so that, divisions, the punaluan family would not be reformatory purposes; and as Mr. Fison's vie the totem clan grew up within his divisions, marriage law still subsisted, the punaluan fam not be needed to give birth to the clan (which M says it has done). And, clearly, there would b room than need for it. It thus appears that, supporting the hypothesis of the punaluan fa Fison has put it aside, and offers an improved (suggested, no doubt, by Mr. Morgan's) in p We have seen that he does not accept the o family either. He does not, indeed, repudiat to connect it with his intermarrying division him so difficult that he thinks the one could changed into the other only through the inte "a higher power." He is not afraid of the which he might be exposed were he to acco first formation of the divisions by such a hypo he thinks it unnecessary to go behind them. now shown in what manner Mr. Fison su Morgan—and we have shown that Mr. Morga position to give any support or countenance t

To show that the Turanian terms would res from his own hypothesis is what Mr. Fison ha There are in a tribe two divisions which do marriage within the division, and are restrict marrying with one another. All the men in are the husbands of all the women of the sam in the other; the wife does not come into th division; and descent is reckoned through The group of men marries the group of wome the group that is husband, the group that group that is father, mother, son, or nep person in it taking, however, all the relati arise to it. Such is the hypothesis. See relationships are called group relationships, thought that Mr. Fison considered the Tu to have been, in the first instance, something terms of blood-relationship, say terms of add denies that they are terms of address, and r as having been real relationships from the fi natural sense of relationship, however, a g women in it other than the actual mother—ca of a child he does not tell us; and till he ca plain, his theory must be held to be as unte hypothesis of the consanguine family. As fo strations (Q.E.D. at the end of each) of th

ely pretend to follow them. The
ally Turanian are laid down by him
hese definitions are used in the
at, so far as these terms are con-
assume what he is going to prove.
ie proves that certain groups are
atement of three definitions. What
mmediately after, he proves, by a
, that the same groups are not
and sisters-in-law. Similarly, he
p is another group's nephew, and
-law. This brings us to say that
Morgan has translated uncle, aunt,
sin, and which he regards as de-
cording to Mr. Fison really mean
aw, and brother and sister-in-law
ng except that a person is called
er or sister, as the case may be, by
one is free to marry. How these
arriage, be more than terms of
to see. What it is necessary to
ustrations, however—and nothing
ry—is that while by hypothesis
hrough the mother—which must
ad to some extent been the sub-
so far as descent is concerned, the
ity," they all proceed on the view
the hypothesis would be in each
n, is as much a relative as the
his, no more need be said of Mr.

It should be added, however,
ong relatives in Australia are, so
rn, in the main Malayan—and he
ot for the Malayan terms. He
of the terms in use among the
imself found the native terms
g." Several terms may be used
ne relationship, and, as he says,
tionship appear to be taken into
of initiation, for example, affects
n will designate another, though,
oes not touch their relationship."
itself, an essential part of it (and
ypotheses too) is that, as regards
exes, there should have been no
hat only men and women of the
have been husbands and wives.
om particular families, can be
it for Mr. Fison's purposes it
some precision. At any rate,
he elderly men should have been
ung women, and the young men
it what an assumption this is—
arily of Australian natives, of
nown than that the elderly men
and especially the young ones,
ough much license is allowed)
nless it be an old one, except
r. This assumption, experience
f itself enough to put out of the
hich it forms a part. The idea
s with groups of husbands all
ives all sisters, no doubt sprang
Mr. Morgan, but apart from Mr.
which must be told. Briefly, it
ler's mistake.

illiam Ridley, a Presbyterian
blished a statement as to the
nilaroi, which statement is now
own authority, to have been
r. Fison still treats it as entirely
id more correct information as
rder. Mr. Ridley said that the
into four castes of men and
four of women, and that (with one exception) the men of a caste could marry only women of one other caste. Murri, feminine mata; kubbi, feminine kubbitha; kumbo, feminine butha; and ipai, feminine ipata, were the castes; and he said that a murri could marry a butha and no other woman, and that his children were not murri and butha, but ipai and ipata; and that, similarly, a kubbi could marry only an ipata, his children being kumbo and butha; and a kumbo only a mata, his children being kubbi and kubbitha; while an ipai, besides being free to marry any kubbitha, could marry any ipata not of his own family—his children, when he married a kubbitha, being murri and mata, and when he married an ipata, kumbo and butha. Mr. Ridley repeated this statement without change in 1855, and he told it in 1871 to Mr. Fison with this amount of change, that instead of castes he now spoke of classes (in unhappy imitation of Mr. Morgan), and of four classes, with men and women in each, instead of four classes of men and four of women; and that he described the marriage of ipai with ipata (that is with a woman of his own class) as an infringement of rule—changes that may fairly be ascribed to the initiative of Mr. Fison. Mr. Fison, putting aside the marriage of ipai with a woman of his own class as an irregularity, and idealising Mr. Ridley's statement, at once formed the hypothesis that all the men of one class originally were by birth the husbands of all the women of the same generation in the class with which they might intermarry. This, although he knew from Mr. Ridley that polygamy was largely practised among the Kamilaroi. Much licence was allowed; and the only word for spouse signified a person whom one is free to marry; and these two facts seemed to him to override Kamilaroi practice, and to prove that marriage had been communal, to begin. In the same year (1871), however, Mr. Ridley was again among the Kamilaroi, and sent to Mr. Fison a statement which should have shaken his faith in his hypothesis—both because of the new matter it contained, and because there were in it what he himself perceived to be errors of observation. Mr. Ridley has published several statements since, all containing obvious errors of observation or slips of memory, and it is impossible to receive even his latest statement as final. But observe what his latest statement is, and compare it with Mr. Fison's hypothesis. It is that the Kamilaroi are divided into totem clans (iguanas, paddy-melons, opossums, emus, blacksnakes, bandicoots); that every native has three names—a personal name (carefully concealed), a "class" name, and a totem name; that children take both the class name and the totem name through the mother; that the men and women of every class are free to marry one another, provided they are not of the same totem—and that, besides, murri may marry any butha, kubbi any ipata, kumbo any mata, and ipai any kubbitha. If his statements can be trusted, murri and butha, kubbi and ipata, kumbo and mata, and ipai and kubbitha, who are free to marry one another, are never of the same totem—so that all the marriages which certainly are permitted are marriages between persons of different totems. Mr. Ridley still leaves each class restricted from intermarrying with two others. So much of his original statement he has not yet found to be wrong. But the class name does not prevent marriage within the class. The notion that the Kamilaroi were in intermarrying or husband and wife "castes" was certainly erroneous. Is it likely then that the class-name is any bar to marriage outside the class? Is it not far more likely that there is still something for Mr. Ridley or some other inquirer to find out, and that, in the main, identity of totem is the only bar to marriage? We say in the main, because it is very likely that there are also regulations to prevent marriage between persons near in blood who are of different totems. Mr. Lance, who is a great authority with Mr. Fison, and who was Mr. Ridley's first informant, had got into his

head that the Kamilaroi were divided by their names into castes with the marriage law which Mr. Ridley first described, and, meeting with an ipai whose wife was an ipata, he regarded him as a daring transgressor of the customary rule. The man told him that he and his wife were free to marry because they were not of the same mudji (totem); and, thereupon, Mr. Lance (who evidently had never before heard of totems) told Mr. Ridley that the ipai were privileged above their neighbours in being free to marry women of their own class who were not of the same family with them; and Mr. Ridley told the world that they were the aristocratic caste among the Kamilaroi. (He has since stated that the murri are the aristocratic class.) This is the sort of observation we are questioning. Had Mr. Lance seen in operation a rule intended to prevent, say a man from marrying his own daughter, he might easily have magnified it into a rule prohibiting two whole "castes" from marrying. And in all probability it was something like this he did. It is the ludicrously wrong impression he had before he met the ipai aforesaid that Mr. Fison has taken for the basis of his hypothesis—but from even that to the hypothesis is a tremendous jump. And, after all, even if we overlook the inadmissible assumption which forms an essential part of the hypothesis, it appears not to be good for anything.

What have been called caste or class names appear, so far as the evidence goes at present, to be names merely, and to have no effect on the right of intermarriage. The system of naming is certainly very peculiar. The names alternate in successive generations. That is not in itself peculiar; but the same name is taken by all the sons, the same name by all the daughters. Thus ipata's children are the sons all kumbo, and the daughters all butha; and, again, butha's children are ipai and ipata. It is a pretty widely spread system. Mr. Howitt says that, as far as he knows, it prevails among all Australian tribes; but this is going a vast deal too far; and is calculated to undermine faith in Mr. Howitt's judgment, for it plainly does not prevail among the Kurnai whom he himself has described. His report shows nothing like castes or classes among them; the men, he says, are all called yeerung (emu-wren) by the women, and the women all djeetgun (superb-warbler) by the men; but this (whatever it may mean, and it may mean very little) does not divide the Kurnai into anything other than men and women. Mr. Fison has had from a number of correspondents statements which he takes to mean that among tribes other than the Kamilaroi which have this system of naming, there is no marriage between persons of the same name; but his correspondents are neither, as regards opportunity or observing power, above Mr. Lance; and Mr. Ridley's study of the Kamilaroi, imperfect as it has been, gives the only evidence that can be regarded as trustworthy. Mr. Fison has amended the list of marriages allowed among the Kamilaroi, given by Mr. Ridley, as he says, on later information; but anonymous information cannot be thought of much value on this matter as against the authority of Mr. Ridley. Mr. Fison is too easily satisfied with anything that seems to make for his view to be indly trusted in such a matter. We find him inferring from there being no marriage between blood-relations—which may mean totem clans—among people who have the class names that there is no marriage within the class. We find totem clans, too, reported to him as classes and ranked by him as classes; and "divisions," which probably mean totem clans, are also ranked by him as classes. On the other hand he candidly gives at least one case in which the class-names are said not to restrict marriage. He gives at the very beginning of his book a native legend of brothers and sisters having married at the first—a legend which both Mr. Morgan and he make much of. We are surprised, however, at his missing the true point of it. What it exhibits is not a movement to "intermarrying divisions" or classes, but to the establishment of totem [illegible] *These* are all the natives seem to have thought [illegible] explanation.

We should have been glad to notice Mr. H[illegible] account of the Kurnai at some length, but we [illegible] brief. The Kurnai have kinship through males [illegible] gamy—that is, prohibition of marriage within the [illegible] and as was to be expected in such a case, the [illegible] form local tribes. He does not expressly tell us [illegible] or not these clans or local tribes are distinguish[illegible] totems (which shows that he meant to be careful, [illegible] his information was very far from being comple[illegible] incidentally he lets out that they are. When a [illegible] young woman meets a young fellow who, being a [illegible] looks as if he might make a husband for her, [illegible] eat kangaroo, opossum, blacksnake? is her first [illegible] after saluting him. Presumably the animal she [illegible] her own totem. If the stranger may eat it he [illegible] her. As for his discovery of marriage by elopem[illegible] have no doubt that it is (as a missionary friend of [illegible] Bulmer, hinted to him it must be) a mere proc[illegible] misconception. Young men among the Kurnai, [illegible] could get wives only by eloping with them on the [illegible] of the women. This may be; an Australian you[illegible] could scarcely ever get a wife except by running [illegible] with her. But how did the elderly men get their [illegible] He appears never to have asked that. But he is [illegible] that there was a system of exchanges. The Kurn[illegible] polygamous, and no doubt among them, as amo[illegible] Australians, the elderly men had, by means of ex[illegible] nearly all the young women for wives. Mr. H[illegible] writes so candidly, and his account of the Kurn[illegible] many respects so interesting, that we should glad[illegible] brought ourselves to think better of this discovery [illegible] But after reading Mr. Fison's most amazing accoun[illegible] origin of marriage by elopement, we find ourselves [illegible] to holding that it is simply a big blunder. Noth[illegible] could have elicited so preposterous an explanation. [illegible] such words as preposterous fall harshly on the ea[illegible] we would part from our authors without unk[illegible] Their exertions to advance a growing science are [illegible] commendable. If the result has been rather to [illegible] than to elucidate, there is but one more illustration [illegible] way in which good intentions, industry, and [illegible] are wasted when men have started in the wrong [illegible]

D. MACLEOD

NOTES

THE evening discourses at the meeting of the British Asso[illegible]tion at York will be delivered by Prof. Huxley and Mr. [illegible]woode. Mr. Huxley will speak of the "Rise and Pro[illegible] Palæontology" on Friday, September 2, and Mr. Spot[illegible] "On the Electric Discharge, its Forms and its Functi[illegible] Monday, September 5.

THE Honorary Fellowship of the Royal College of Sur[illegible] in Ireland was on Wednesday last week conferred on Helmholtz, and the Honorary Degree of LL.D. by the Uni[illegible] of Dublin. On Monday night, at an ordinary meeting [illegible] Royal Society of Edinburgh, Sir William Thomson in the [illegible] Prof. Helmholtz read a paper on "Electrolytic Conduc[illegible] There was a crowded attendance, and Prof. Helmholt[illegible] warmly received.

ON Monday the National Fisheries Exhibition, which [illegible] been organised at Norwich under the care of numerous [illegible] bodies, from the Board of Trade downwards, was opened [illegible] Prince and Princess of Wales. The exhibition is divided [illegible] six classes, as follows:—1. Pisciculture and shell-fish cul[illegible] 2. Models, trawling gear, drifting gear, canvas and rope [illegible] inland fishing tackle; 3. Life-saving apparatus, lamps, fog [illegible] signalling, &c., architectural plans for fish markets, &c.[illegible]

and fishermen's clothing; 4. Pictures, fish and fish refuse as a manure, and polluted streams: 5. Dried, salted, shell fish, fish oils, manure, and disinfected fauna, and birds which prey upon it. In the last class a fine collection late Frank Buckland, which has been of South Kensington Museum. The classes of aquatic, or rather fish eating, eresting and instructive. In the class fish there are a large number of tanks, appliances for hatching the ova of fish, , &c. There are also shown live fish in gal which are specimens of nearly every indigenous to this country, the local nydete. Next week we hope to give the ley, who is now one of the Inspectors of nnection with the Exhibition.

ning Herald we are glad to learn that a it to be established at Watson's Bay, Baron N. de Miklouho-Maclay, on a ined from the Government. After a clane-an Islands and in Queensland he ention of remaining in Sydney until he began in 1878, and see the zoological . The land granted by the Government ed near Camp Cove, and is about half on this a cottage of five work rooms building will be for the use of naturalists Wales for the purpo e of studying the tralia. The Government, understand- ve given what assistance they can, and 2, to be collected by private subscription ributed towards the expense of erecting dic revenue. The subscriptions up to out 200*l.*, and it is hoped there will be e the balance which will be necessary al station on the small scale contem- This station will be the first of the sphere, and will supply a serious

d, at the end of February last, of Mr. alian naturalist. Mr. Krefft was born in 1830, and early conceived a taste for pending some time in the United States in November, 1852. Mr. Krefft was e collecting expedition fitted out by the 855. Having succeeded the keeper in e returned to Melbourne with a large and a well-filled portfolio, and was assistant in the Museum. He gave animals obtained and an account of the he aboriginals, illustrated by numerous and his position and returned to Ger- n left home for foreign lands, having ing from Messrs. Godeffroy and Son, th round the world, and after a two- th Africa he took up his quarters in l secretary in the Australian Museum r. Ulard, its curator. On the latter's ent succeeded to the vacant curatorship r years of his appointment he had a with the trustees of the Museum, which his institution, September, 1874. Mr. first man who thoroughly studied the . Krefft was a F.L.S., C.M.Z.S., and learned societies.

AMONG Mr. Murray's forthcoming works are the following:—"The Formation of Vegetable Mould through the Action of Worms, with Observations on their Habits," by Charles Darwin, F.R.S.; "The Life and Letters of the late Sir Charles Lyell, Bart.," edited by his sister-in-law, Mrs. Lyell; "The Land of the Midnight Sun," being a narrative of summer and winter journeys through Sweden, Norway, Lapland, and Northern Finland, by Paul B. du Chaillu, of gorilla fame; also a second and revised edition of Mr. W. H. White's "Manual of Naval Architecture."

AT the meeting of the Sanitary Institute of Great Britain on April 13, Dr. Richardson read a paper of suggestions for the management of cases of small-pox and of other infectious diseases in the metropolis and large towns. Dr. Richardson maintains the thesis that there should be no aggregation of infectious cases in large central institutions, and describes the objections to such aggregation. He suggests further that the sanitary committee or authority in every parish should have all the special centres of infection in each of its districts thoroughly mapped out, and that it should know, on a calculation of cases occurring in quinquennial periods, what is the permanent accommodation required for its infectious sick. He urges that the required accommodation being known, the local authorities should keep ready at all times within the parish such necessary accommodation in small hospitals situated in different parts of the parish or locality. Dr. Richardson described what he thought should be the size, mode of construction, and position of such hospitals:—(*a*) That each hospital should not be larger than is sufficient to receive twenty-four persons at one time. (*b*) That each should be constructed on the separate system for the patients. (*c*) That each should be constructed of iron, so that it may at any time be absolutely purified by fire throughout all its structure. (*d*) That each should be placed on the upper storey of a building, forming in fact the top storey of one or more houses, so that it may be lighted and ventilated directly from its roof. (*e*) That all the air that passes out of the hospital when it is occupied by infectious persons should pass through fire. (*f*) That each patient should be carried into the hospital by a valved lift, which lift should pass through a shaft, so as to draw up air during its ascent, and which should, when required, be effective for flushing the hospital with air. Dr. Richardson entered into the subject of the organisation of these hospitals in respect to general supervision and nursing. Under this head he recommended—(*a*) That the general supervision should be in the hands of the Medical Officer of Health. (*b*) That the nursing, also under the supervision of the Medical Officer of Health, should be carried out by trained nurses, who might be educated to their work in the Union infirmaries. Lastly he suggested that the medical attendance should be conducted by a special staff of duly qualified medical men acting under the Medical Officer of Health and responsible to the local authority, by whom they should be appointed and remunerated. An interesting discussion followed, which was adjourned to the 27th inst.

UNDER the auspices of the National Health Society the following Drawing-Room Lectures will be delivered at 23, Hertford Street, Mayfair (by kind permission of Mr. Charles Matthews), to commence at 4 o'clock p.m.:—Friday, April 22: Prof. Fleeming Jenkin, F.R.S., "Sanitary House Inspection"; Friday, April 29: Dr. Robert Farquharson, M.P. (formerly Medical Officer of Rugby School), "Health in Public Schools"; Friday, May 6: Mr. C. N. Cresswell, "Sanitary Relations of Local Self-Government"; Friday, May 13: Mr. Henry Power, M.B., F.R.C.S., "Care and Education of the Eye"; Friday, May 20: Dr. Siemens, F.R.S., LL.D., "Stoves and Grates"; Friday, May 27: Mr. Ernest Hart, M.R.C.S., "Recent Progress in Health Knowledge." Tickets may be obtained from the

secretary at the offices of the Society, 44, Berners Street, on Mondays and Fridays from 2 to 5, or will be forwarded by post on application. Patronesses: H.R.H. Princess Christian; H.R.H. Princess Louise, Marchioness of Lorne; H.R.H. Princess Mary Adelaide, Duchess of Teck. The president of the Society is His Grace the Duke of Westminster, and the Chairman of Council, Mr. Ernest Hart, M.R.C.S. The objects of the Society are to diffuse sanitary knowledge in every possible way, by the delivery of simple practical lectures on air, ventilation, food, and cookery, the prevention of the spread of infectious disease, and kindred subjects, at working men's clubs, mothers' meetings, and elsewhere, in all parts of London and the suburbs; by the circulation of sanitary tracts and papers; by encouraging the teaching of the laws of health in high schools and Board schools, by offering prizes, &c., to both teachers and pupils; and to secure open spaces for the healthy recreation of the people. Membership is constituted by the payment of 1*l.* 1*s.* annually; life membership by the single payment of 10*l.* 10*s.* Communications to be addressed to Miss Lankester, the Secretary, at the offices of the Society, 44, Berners Street, Oxford Street. It is evident that this Society has adopted effectual means to do a good and highly necessary work; it deserves the heartiest support from all who can in any way lend a helping hand.

Two Art Exhibitions were opened under the auspices of the Sunday Society on Easter Sunday, one at Whitechapel, the other in New Bond Street. That at the East-end consisted of a Loan Collection of Paintings, &c., organised by the Rev. S. A. Barnett, to which the Council on Education contributed largely from the National Collection at South Kensington. More than 2500 persons visited the Exhibition during the day, it being open from 2 till 9 p.m. The West-end Exhibition was the first Exhibition of the new Society of Painter-Etchers at the Hanover Gallery, and this was visited by about 578 members of the Sunday Society between the hours of 4 and 6.30 p.m. On Sunday, April 24, this Exhibition will be open to ticket-holders. Free tickets may be had by all who make a written application, inclosing a stamped and *addressed* envelope to Mr. Mark H. Judge, Hon. Sec. of the Sunday Society, 8, Park Place Villas, W.

THE second series of meetings organised by the Sunday Evening Association at the Neumeyer Hall was brought to a successful close on Easter Sunday by a lecture on "Lessing," by Mr. Moncure D. Conway. The hall was crowded, and at the close it was announced that the first annual meeting of the Association would be held in May, and that in the autumn the Committee intended to organise a series of meetings in the different Metropolitan suburbs, in order if possible to start local branches. The object of the Sunday Evening Association is to bring together all persons who, estimating highly the elevating influence of music and the sister arts, literature and science, desire by means of meetings on Sunday evenings to see them more fully identified with the religious life of the people. The subscription is 2*s.* 6*d.* per annum, which may be paid to the treasurer, Mr. Godfrey Shaen, 15, Upper Phillimore Gardens, W.

WE take the following from the *Electrician*:—The following correspondence over the telephone wires yesterday, says the Kansas City *Times*, is a further proof of the fact that no one but a bald-headed man could do without one:—"Hello, central!" "Hello!" "Connect me with the signal bureau." "All right—go ahead." "Hello, signal!" "Hello!" "Is it going to thaw to-day?" "Yes, there are indications." "How's the wind?" "Getting round to the south." "Do you think I can safely have my hair cut?" "Wait a minute until I consult the barometer, thermometer, and wind gauge." (Silence for half a minute.) "Hello!" "Hello!" "Yes, you can go ahead. There won't be any change to speak of for the next twelve hours. There is a cold wave moving a Ohio River, and a snow-storm is reported at Cheyenne. were you I'd take my chances on the hair-cutting." "—much obliged." "Good bye."

MR. PFOUNDES has reprinted, in a separate form, but interesting paper at the Anthropological Institute "Japanese People: their Origin and the Race s exists."

THE usual meeting of delegates of the Sociétés Savan place this week at the Sorbonne on a somewhat enlarg It is the first time that members of Parisian societies w in combination with their provincial brethren.

A NEW fortnightly journal, *L'Electricien*, has appe Paris.

THE *Times'* Swiss correspondent states that the accl of the ibex in Switzerland would appear to be so far a The herd which was turned out some time ago in the G reported to have got through the winter without damage being at present in an excellent state of health.

A CORRESPONDENT of the *Daily News* points out the exact time of the great Chios earthquake on the 3rd ins 1.50 p.m.

NO. 2 of vol. iii. of the *American Antiquarian and Journal* (Chicago, Jameson and Morse) contains several butions relating to American archæology, especially mound-builders. The editor, the Rev. S. D. Peet, has on the military architecture of the emblematic mound- and there are various other contributions from various the States bearing on the life and works of the peoples of America. In the Oriental department resting points connected with Eastern antiquities are

PROF. CORNELIUS DOELTER of Grätz has safely from his journey to West Africa. He has brought mineralogical and ethnographical collections.

THE Report of the West Kent Natural History speaks of its continued prosperity. It contains an address by the President, in which he points out portant bearings of recent researches on light. Speaking Blackheath holes, the President is inclined to think over the sites of pockets or pipes in the chalk, the cause of the subsidence is the drawing away subsoil by the action of water, the subterranean drainage duced by the pumping up of the water by the Kent Wate at Deptford, drawing away sand and chalk in mechan suspension.

THE following are among the papers in the *Transa* of the Cumberland Association, part v.:—"Distribution Boulders in West Cumberland," by J. D. Kendall, F.G. "Soul-Cells and Cell-Souls," from the German of Haeck the Rev. C. H. Parez; "The Influence of Geological on Scenery," by Mr. Kendall; "The *Local Museum* Relation to the Natural History of the District," by Mr. Arlosh; "The Moths of the District," by Mr. George Dix "The Character and Distribution of the Diatomaceæ," by B. Taylor; "Notes on Inglewood Forest," by Mr. Jackson.

AN Electric Rail down in the ground Crystal Palace.

THE Academy Philadelphia are Spring courses of the Paleontology Mineralogy.

Zoological Society's Gardens during the
mon Rhea (*Rhea americana*) from South
Mr. A. D. M. Stewart; a Mountain
from New Zealand, presented by Dr.
S.; an Undulated Grass Parrakeet
from Australia, two Californian Quails
rom California, two Common Quails
Greenfinch (*Ligurinus chloris*), a Gold-
two Chaffinches (*Fringilla cœlebs*), two
via curvirostra), a Common Lapwing
ah, a Barred Dove (*Geopelia striata*), a
dulata) from India, two Rufous-necked
tenuis texana) from West Africa, two
ornata, var.), from Tunis, presented by
a Green Turtle (*Chelone viridis*) from
by Mr. J. C. Robinson, R.M.S. *Dun-*
n Viper (*Vipera berus*), two Common
ters), British, presented by Mr. J. Foyer
si (*Brachyurus rubicundus*), a Horrid
rubra) from South America, a Brown
Spain, a Great Kangaroo (*Macropus*
Dasyures (*Dasyurus ursinus*), three
llangida vulpina) from Australia, de-
se (*Oryx beisa*), a Bandel Ichneumon
Squirrel-like Phalanger (*Phalangista*
rdens.

ONOMICAL COLUMN

e.—M. Puiseux, in a communication to
ces of Paris, discusses the numerous
made during the last transit of Venus
roject at St. Paul's, and MM. Fleuriais
If these observations had possessed a
he considers that they would have fur-
of the solar parallax, but unfortunately,
the measures at St. Paul's Island, the
unfavourable; indeed in a note which
munication Admiral Mouchez remarks
vided for that station had no special
of observation, and were still, "les
s exactement au moment du passage du
lone, pendant la courte éclaircie qui
le dépression barométrique." The in-
doore particularly adapted to proposed
and were very weakly mounted; easily
by the violent wind, so that the prac-
nfidence in their results. Notwithstand
M. Puiseux has discussed the measures,
which he regards as the most favour-
on that appear affected with considera-
saving 312 measures for calculation, he
solar parallax 9".05; the mean value of
ls is 0".78, and the extreme residuals
nsidering that under such disadvanta-
ervations accord passably, M. Puiseux
de grounds to expect that with firmly-
ometrical measures may be obtained at
in 1882, which will furnish a pretty
arallax.

HERSCHEL 3945.—The double-star to
rew attention in NATURE last week on
lists of the components and variability
a longer history than is noted in his
ngle star of sixth magnitude in Bode's
observation, and is Canis Majoris 164.
components on March 2, 1796, magni-
uary 23, 1835, Sir John Herschel,
lls them 7 and 8, "large star orange:
on January 31, 1837, he estimated the
"large star, very high yellow; small,
observations occur in Sweeps 532 and
metrical measures we find for the epoch
nd 7, and for 1837·301 magnitudes 6½
and 8, with the note "Orange and green, fine contrast of
colours." Next we have three meridian observations of the
principal star by Argelander in vol. vi. of the "Bonn Observa-
tions," on January 26 and March 13 and 14, 1854, magnitudes
noted, 5·5, 4·5, and 5·0, and one observation of the companion
on March 23 in the preceding year, when it was estimated 7·5.
In Heis and Argelander the naked-eye estimate is 5 m. The
components are separately noted in Gould's *Uranometria
Argentina* A. 53 red, B. 7. The star does not occur in D'Agelet,
Taylor, or in Argelander's Southern Zones. The mean place
for the beginning of the present year is in R.A. 7h. 11m. 31·80s.,
N.P.D. 113° 6′ 19″·4.

THE TOTAL SOLAR ECLIPSE OF 1878.—In one of the hand-
somely executed volumes which issue from the Government
Printing Office at Washington, the U.S. Naval Observatory has
published the detailed reports of the various expeditions organised
for the observation of the total eclipse of the sun on July 29,
1878, which possess a high degree of interest. A large number
of wood-engravings and lithographic plates accompany the
reports. There is also appended a brief account of the observa-
tions made in California during the total solar eclipse of January
11, 1880.

THE EARTHQUAKE OF NOVEMBER 28, 1880, IN SCOTLAND AND IRELAND[1]

THE data on which the paper has been founded have been collected from upwards of fifty stations, and special reliance may be placed on the results, as a large proportion of these stations were lighthouses, in each of which at the time of the occurrence there was a keeper *on watch*, the earthquake having occurred after sunset at a time when the lamps were lighted.

The paper at the outset gave the effects and nature of the shock experienced by various observers at those lighthouse stations where the disturbance was felt.

The data acquired were then discussed, and the following are the general conclusions arrived at:—

1. That the earthquake occurred in November, a month in which many of the British earthquakes are recorded as having happened.

2. That it occurred after a wet and stormy period, which had been preceded by an unusually dry summer and spring; that there was a widespread thunderstorm at the time, and that the barometer was rising slowly over the greater part of the west of Scotland; the average height of the barometer at the lighthouse stations at which the earthquake was felt being at 9 a.m. 29·4 inches, and at 9 p.m. 29·5 inches. The thermometer at 9 a.m. averaged 50° F., and at 9 p.m. 48° F.

3. That the seismal area was about 19,000 square geographical miles, the shock having been felt as far north as the Butt of Lewis, as far south as Armagh in Ireland, as far east as Blair Athole, and as far west as Barra Head Lighthouse, though how much farther it was propagated into the Atlantic it is impossible to say.

4. That the range of the earthquake or distance to which the wave was propagated was greater over the sea than over the land.

5. That the earthquake was not a simultaneous shake over the disturbed area, but was produced by a wave propagated from a centre.

6. That the undulation seems to have been chiefly of an "up and down" character like a wave of the sea, and that calculating the "breadth" from the mean velocity of transit and the minimum duration of the shock, the wave appears to have been fully 1100 feet "broad."

7. That the observations warrant the assumption that a spot near Philadda Lighthouse (north-east of Colonsay) was the source, and calculating the velocities of transit with a point 13 miles south-south-west of Philadda Lighthouse as a centre, it appears that the wave travelled with a greater velocity over the sea-basin than over the land, probably due to the fact that over the sea there was a thinner and lighter crust to throw into vibration; the average velocity on sea journeys being 6·74 geographical miles per minute, and the average velocity on land journeys 4·65 miles per minute, the mean of the whole being about 5¾ miles per minute.

8. That the source of the earthquake lay at or near the great

[1] By Charles Alex. Stevenson, B.Sc., Edinburgh, communicated to the Royal Society of Edinburgh by Prof. Geikie, F.R.S., March 21, 1881.

fracture of the earth's crust which runs in a south-westerly direction from Inverness.

9. That all the observers who heard the noise agree in stating that it was a "rumbling" sound.

10. That of the fourteen observers within 38 miles of the source who felt the shock, thirteen of them mention having heard the rumbling noise, and none of the other observers in Scotland mention noise as an accompaniment of the earthquake, and hence that the noise was confined chiefly, if not entirely, to places situated near the source.

11. That the stations where the noise was heard were for the most part situated on hard dense rocks, with little or no soil near them.

12. That the average duration of the disturbance was 4·4 seconds for observers situated within the sound area.

13. That of twenty-two lighthouse observers between Cape Wrath and the Mull of Galloway who were situated on the older formations (Laurentian, Cambrian, and metamorphosed Lower Silurian) eleven felt the shock, whilst of thirteen observers situated on newer rocks it made itself known only to two of them, and that the earthquake was therefore more generally felt on the older rocks of Scotland.

14. That stations situated near one another and on the same formation did not necessarily both receive the shock, and that faults and trap dykes did not seem to affect the passage or intensity of the wave in any way.

15. That the observations of time at Armagh, Belfast, and Omagh show that the shocks at these places were most probably propagated direct from Phladda in Scotland, and that the severity of the shock and the "rumbling" noises heard in and around Leterkenny were probably due to a s source of disturbance generated by the arrival Phladda.

MAGNETIC DECLINATI

1. IT is well known that Prof. Rudolph Wo to render observations of sun-spots made and by different observers, comparable with e thus formed a list exhibiting approximately th activity for each year. This list extends ba teeth century, and is unquestionably of much less it must be borne in mind that we possess sufficiently accurate for a discussion in a co questions relating to solar periodicity befo Schwabe had finally matured his system of which was not until the year 1832.

We have however a much longer series of of magnetic declination. Now these are alre follow very closely all the variations of sun-spo greatest when there are most, and least when spots; and it may even be imagined that such better estimate of true solar activity than derived from the direct measurement of spotte

The long-period inequalities of the diurnal declination are thus, we may imagine, precis activity, so that to analyse the former is prob analysing the latter.

2. Our method of analysis is not new. T by us is in fact that which has been pursued



probably other astronomers, with observations of variable stars, and it has already been applied by one of us in a preliminary manner to magnetic declination ranges (*Proc.* Lit. and Phil. Society, Manchester, February 24, 1880).

3. The observations at our disposal are those which have been used by Prof. Elias Loomis in his comparison of the mean daily range of the magnetic declination with the extent of the black spots on the surface of the sun (*American Journal of Science and Arts*, vol. i., No. cxlix.). These observations are recorded as monthly means of diurnal declination range, and we found it necessary to multiply each by a certain factor, firstly, on account of the well-known annual inequality of declination range, and secondly, to bring them all to the standard of the Prague observations. We have applied for this latter purpose precisely the same corrections as those made by Prof. Loomis.

4. The result of an analysis of these observations has been to indicate the existence of three inequalities: two dominant ones with periods of about 10½ and 12 years, and a subsidiary one with a period of about 16½ years. By these means we have been enabled to reproduce the observed annual values of declination range with an average difference of 39". The amount of agreement between the observed and calculated values will be seen from a diagram which accompanies this note. We are however of opinion that the series of observed values at present obtainable is too short to render this analysis a very accurate one. It will certainly not bear carrying back forty or fifty years beyond its starting-point, which was in 1784, and it would be very hazardous to carry it forward any considerable length into the future. We may however mention that our calculations indicate a maximum of declination range about pronounced a maximum as that of 1871.

5. During our analysis an observation was m we think worthy of record.

It is a well-known fact that the so-called e lations of declination renge are at certain ti other times small. Thus, for instance, they ha the last forty years, but they were small about the present century. It is clear to us from an observations that a series of large oscillations with an exaltation of the base line, or line efficiency, while a series of small oscillations with a depression of the same. The result is a of the base line, the beat period, so to speak yearly inequality.

Now a phenomenon precisely similar occur with shorter periods. If we take inequalities of three or four months we find that such are developed or of large range, and badly develop range; and that a large range of such is accom exaltation of the base line or line of average e small range is accompanied with a depression of result is a curve of the base line, of which the p speaking, eleven years. May we not therefore so-called eleven-yearly period, or, to speak mo

1 "Note on an Attempt to Analyse the Recorded M Magnetic Declination." By Balfour Stewart, M.A., LL Professor of Natural Philosophy at the Owens College, and Read at the Manchester Literary and Philosophical Socie

d a half and twelve-yearly periods into which the eleven- period may perhaps be analysed, may be in reality beat ls for shorter disturbances? Is it not therefore possible study of these shorter periods may give us information ling the nature of the eleven-yearly period, whether for pots or declination ranges, which the small series of actual vations is incompetent to afford?

: beg to take this opportunity of thanking Mr. William d for the help he has given us in this investigation.

UNIVERSITY AND EDUCATIONAL INTELLIGENCE

MBR IDGE.—At Trinity College the following distinguished iates of the College have been elected Honorary Fellows:—Rayleigh, M.A., F.R.S., Professor of Experimental ics; Mr. Henry Sidgwick, M.A., Prælector in Moral and ical Philosophy, the author of "The Method of Ethics"; Edward Herbert Bunbury, M.A., author of "A History of ent Geography," &c.; and Mr. William Henry Waddington, ., Member of the French Institute, late President of the ncil, and Minister of Foreign Affairs in France.

he Adams Prize is to be given in 1883 for a general investi- on of the action upon each other of two closed vortices in a ect incompressible fluid. In particular it is suggested that case of two linked vortices should be fully discussed, with view of determining (1) whether any steady motion is sible, and (2) whether any motion can occur in which there periodical changes in the forms and dimensions of the ices. Each essay should be accompanied by a full and ful abstract pointing out the parts which the author con- rs to be new, and indicating the parts which are to be arded as of more importance than the rest. The competition pen to all graduates of Cambridge; essays must be sent in or before December 16, 1882. Essays must not be written the candidate's own hand. The successful candidate will eive about 170*l*. He must print the essay at his own expense. e examiners are the Vice-Chancellor, and Messrs. A. Free- n, W. H. Besant, and E. J. Routh.

VICTORIA UNIVERSITY.—The following summary of draft gulations on degrees, examinations, and courses of study has en issued:—1. These regulations are, with the exception of tain general proposals with reference to University Matricu- ion, confined to the subjects of Degrees, Examinations, and urses of Study in the Faculties of Arts and Science. 2. cording to the proposals in the Report any certified student a College incorporated in the University may matriculate at tain times in the year, the definition of College studentship ng left to the College or Colleges, subject in each case to the proval of the University. No University examinations leading a degree will be open to any persons who are not matriculated dents. 3. According to the proposals in the Report there e to be two distinct Faculties of Arts and of Science. The grees in these faculties are to be those of B.A. and M.A., Sc. and M.Sc., and a Doctorate common to the two Faculties d varying as a Doctorate of Literature, of Philosophy, and of cience. 4. In consonance with a main principle of the Univer- ty Charter, the degrees of B.A. or of B.Sc. are to be conferred pon students who have passed certain prescribed University xaminations, and who have attended certain prescribed Univer- ty courses of study in a College of the University. 5. In the xaminations for the degrees of B.A. and B.Sc., and in the rivileges conferred by these degrees, a distinction is to be rawn between the Ordinary B.A. or B.Sc. degree, and the .A. or B.Sc. degree with Honours. 6. The regular period of tudy required of candidates for the degrees of B.A. and B.Sc. s to be three years, of which two shall be after the date of their assing the Preliminary Examination (see § 7 of this summary); ut students who have passed the Preliminary Examination (see 7 of this summary) next in date after their matriculation, and ave been placed in the first division of the list of successful andidates, shall be allowed to proceed to their degree in two ears. 7. All candidates for the degrees of B.A. or B.Sc. are equired to pass a general examination called the Preliminary Examination, and to present themselves for this examination not ater than two years from the date of their matriculation. ular st year courses of study are arranged as preparatory is mination, to be taken by all students except those mmediately after matriculation (see § 6 above), or the first year's course of one of the Honours Schools approved by the University. 8. The subjects of the Preliminary Examination are arranged in two groups (A and B), in one of which every candidate must pass. The essential difference between the two groups is that in A, Latin and Greek are compulsory, but that a choice is given between four subjects, including two modern languages and two elementary sciences; while in B a choice is given between the alternatives of two languages (ancient or modern) and one elementary science, or two sciences and one language (ancient or modern). In B the requirements in modern languages and mathematics are rather greater than in A. 9. The other examinations for the degrees of B.A. and B.Sc. will be open to such students only as have passed the Preliminary Examination, and as have attended the prescribed University courses of study in a College of the University. These further examinations will differ for students intending to present themselves for an Ordinary B.A. degree and for those desirous of a B.A. degree with Honours. 10. The degree of B.A. with Honours is to imply that a student has attended, during three years, prescribed courses of study (approved by the University) in a distinct branch of learning or science forming the subject of one of the Honours Schools of the Faculties of Arts and Science, and that he has passed a prescribed examination in such Honours School after attending its third year's course. The Honours Schools recommended in the Report for immediate establishment in the University are those of (1) Classics, (2) English, (3) History, (4) Philosophy, (5) Mathematics, (6) Engineering, (7) Chemistry, (8) Zoology, (9) Physiology, and (10) Geology, Mineralogy, and Palæontology. For all of these Honours Schools the Owens College is prepared to supply classes meeting the proposed requirements of the several Schools. 11. The Ordinary degree of B.A. or B.Sc. is to imply that a student has attended, during at least two years, prescribed courses of study (approved of by the University) forming a connected whole, and that he has passed an examination corresponding to the earlier year's course, to be called the Intermediate Examination, and an examination corresponding to the later year's course, to be called the Final Examination. 12. The courses of study, and the corresponding examinations, prescribed for the Ordinary degrees of B.A. and B.Sc., and open to the choice of candidates who have passed either group of the Preliminary Examination, vary according to the predominance in each course (with its examinations) of one branch of learning or science. This predominance is not however such as to warrant the maintenance of the designations given (for convenience' sake) in the Draft Regulations of "mainly Classical, Historical, English, Philosophical, Mathematical, Engineering, Experimental Science, and Biological." Candidates for an Ordinary B.A. or B.Sc. degree may choose any of these groups, but must go through the whole two years' course, and pass both the examinations of the group chosen. The examinations and classes however largely coincide in particular portions of the several groups. 13. With a view to encourage more advanced study in special branches of learning or science in students whose bent has been determined, or whose capabilities have been developed, at a later stage of their University career, students who have passed the Final Examination for an Ordinary B.A. or B.Sc. degree, are to be allowed to present themselves for examination for a B.A. or B.Sc. degree with Honours, after attending the third, or second and third, year's Honours Course, only in one of the Honours Schools. 14. The degree of Master of Arts or of Science is to be conferred upon Bachelors of Arts of three years' standing, after not less than six years from the date of their matriculation. B.A.s who have graduated with Honours are not to be required to pass any further examination for the M.A. degree; those who have taken the Ordinary B.A. or B.Sc. degree are to be required to pass an examination in some portion of one of the Honours Schools Examinations. 15. The Doctor's degree in the Faculties of Arts or Science is to be conferred upon M.A.s or M.Sc.s who have furnished evidence of special research or learning, to be supplemented when desirable by an examination test.

SCIENTIFIC SERIALS

Bulletin de l'Académie Impériale des Sciences de St. Petersbourg, t. xxvii., No. 1, February, 1881.—On the results of experiments on the resistance of the air and their application to the solution of problems of firing, by M. Mayevski.—On variations of the fur and on the geographical distribution of the sea-otter (*Enhydris marina*), by M. Brandt.—On the integration of partial equations of the first order with several variables whose co-efficients are constant,

by M. Alexéeff.—On the rotation of Jupiter, by M. Kortazzi.—Crystals of beryl from a part of the Southern Oural, by M. Kokscharow.—On the formation of some nitrated derivatives of some hydrocarbons of the fatty series by direct action of nitric acid, by M. Konowalof.—On the variability of forms of *Lubomirskia Baïcalensis*, and on the distribution of sponges of Lake Baikal, by M. Dybowski.—On universal time, and on the choice for this purpose of a prime meridian, by M. Struve.—Anatomy of the lactiferous glands during the period of lactation, by M. Saefftigen.—On the spectroscopy of hydrogen, by M. Hasselberg.

Reale Istituto Lombardo di Scienze e Lettere. Rendiconti, vol. xiv. fasc. 4 (February 24).—On a method of finding with the microscope the adulterations of the more common varieties of farina, by Dr. Cattared.—Experimental researches with the Crookes' apparatus, by Prof. Ferrini.—On a quadratic Cremonian correspondence between the elements of two fundamental forms of the fourth species, or ruled spaces, by S. Aschieri.—Considerations on new species of partial blindness in Arachnida, by Prof. Pavesi.

Fasc. 5.—Materials to serve for the study of *Peronospora viticola*, by Count Trevisan.—On primary and secondary psoïtis, by Prof. Sangalli.—The sanitary administration in Spain, by Dr. Quechi.—Determination of the maximum moments due to weights linked on a supported beam, by Prof. Clericetti.—On an abnormal case of fructification in Florideæ, by S. Ardissone.

Revue Internationale des Sciences, February, 1881.—Prof. Vulpian, physiological study of poisons, vii. Curare (end).—Prof. R. Lankester, embryology and classification of animals.—Fernand Lataste, a few more words on the fecundation of the urodele batrachians.—Notices of learned societies.—Belgian Academy (abstract of Van Bambeke's paper on the formation of the embryonic lamellæ and the notochord in the urodela).—Paris Academy: on the appointment of M. Bouley to the Chair of Comparative Pathology at the Natural History Museum, Paris.

Journal de Physique, March.—On the division of instantaneous currents (continued), by M. Brillouin.—On the psychrometer, by M. Angot.—New tourmaline pincer, by M. Bertin.—Constitution of the flame of the Bunsen lamp, and some modifications in the construction of this lamp, by M. Terquem.—On some experiments in acoustics, by M. Neyreneuf.

Atti della R. Accademia dei Lincei, vol. v. fasc. 7 (March 6).—On solar observations at the Royal Observatory of the Roman College in 1880, by P. Tacchini.—Observations of comets and planets at the same college with the Merz equatorial, during 1880, by the same.—M. Janssen's solar photographs taken at Meudon Observatory, by the same.—Thermal laws of the exciting spark of condensers, by E. Villari.—On sodio-ammoniacal trimolybdate, by F. Mauro.—Studies on rotatory power, by R. Inasinio.—On some compounds of the pyrolic series, by L. G. Ciamician.—On the electrophorus, by G. Govi.—On pathological bases, by F. Selmi.—On the causes of distinctness in solar photographs, by S. Respighi.—On experiments made at the Observatory of Campidoglio for determination of gravity, by the same.

Sitzungsberichte der naturwissenschaftlichen Gesellschaft Isis in Dresden (1880).—A modern investigation of the flora of Saxony, by Prof. Drude.—On the Pycnodontidæ, especially the genus Gyrodus, by Prof. Vetter.—The Nudibranchia of the sea, by Herr Blaschka.—On the determination of fixed points of normal mercury thermometers and the measurement of temperatures, by Prof. Neubert.—On various finds in the neighbourhood of Dresden, by Dr. Caro.—Hydroid medusæ or Craspedotes, by Herr Blaschka.—Progress of geological researches in North America, by Dr. Geinitz.—On plant-remains from the Tertiary formations of Liebolitz and Putschein, by Herr Engelhardt.—Observations on the growth of the leaf of *Victoria regia*, Lindl., in the Dresden Botanical Gardens in 1880, by Prof. Drude.—The Slav and German immigration into Saxony, by Prof. Meitzen.—The urn-field of Persia, by Herr Wiechel.

Archives des Sciences Physiques et Naturelles, No. 3, March 15. Swiss geological review for 1880 (continued) by M. Favre.—Considerations on the study of phyllotaxy, by M. de Candolle.—Notice of researches by Drs. Tenchini and Staurenghi, on the anatomy of the human cerebellum.

Rivista Scientifico-Industriale, No. 5, March 15.—On Reese's fusing disk, by Prof. Bombicci.—Volta's pile rendered constant and depolarised, by Count Mocenigo.

SOCIETIES AND ACADEMIES

LONDON

Royal Society, March 31.—On the coefficients of ex[pansion] of the iodide of lead, and of an alloy of iodide of le[ad] iodide of silver, by G. F. Rodwell, Science Maste[r] borough College.

The iodide of lead was examined by the speci[al] described by the author in former communications [to] Society, and was found to possess three coefficients of expa[nsion] Between 0° and 205° C. the coefficient of cubical expa[nsion] 1° C. is ·00007614, increasing to ·00008307 between 2[05°] 253° C.

Between 253° and 265° C. the mass expanded very [much] with a coefficient nearly eight times greater than the pre[ceding] viz. ·0006378. After the subsidence of this rapid expa[nsion] coefficient became ·000180. The volumes of the iodide [at] 0° and the fusing point (383° C.) are given, and are [the] curve-table.

Iodide of lead was fused with iodide of silver [in] proportions as to form an alloy containing one [molecule] of each constituent, viz. PbI_2, AgI. This contains [66·2] per cent. of iodide of lead, and 33·80 per cent. of [iodide] of silver. The melting-point of the alloy was found to [be] C., the specific gravity 5·912. On heating it was [found] expand under a very low coefficient between 0° and 11[0°] then it neither expanded nor contracted while heated [to 124°] C.; at 124° C. it commenced to contract, and [continued] between 124° and 139° C. as much contraction as iodide [of lead] itself; again it was stationary for 5° C., and at 144° C. [began] to expand again, with a much higher coefficient than it [possessed] between 0° and 118° C.

The following are some noticeable points about the [alloy]:

1. It possesses similar densities at three different temperatures.

2. Although it contains only 33·8 per cent. of iodide of [silver] it contracts as much during heating as the iodide of silver [alone].

3. While the iodide of silver commences to contract at [145°] C., and terminates at 145°·5 C., the alloy commences to contract 18° C. lower, and terminates its contraction 6°·5 C. lower.

4. The harsh sounds emitted during the cooling of the [alloy] and the tremors simultaneously propagated through its [mass] prove that violent molecular agitation is taking place while [the] iodide of silver is passing from the amorphous plastic condition into the brittle crystalline condition within the mass surrounded by the molecules of the iodide of lead.

5. The fusing-point of the alloy is 33° lower than that of iodide of lead, which constitutes *two-thirds of its weight*; [and] 177° lower than that of the iodide of silver, which constitutes one-third of its weight.

6. And if this is due to the fact that *similar* particles of matter attract each other more powerfully than dissimilar; hence that when the particles of two bodies are mutually [attracted] the attraction becomes less than that of the molecules of [each] one of them singly, and the molecular motion is hence [more] easily assimilated, the same cause may explain the contrast[ed] ment of the phase of contraction on heating the alloy to [a] perature 18° C. lower than that of the iodide of silver [to] it owes this property.

7. If we compare one of the chlorobromiodides of [silver] before described by the author (*Proc.* Roy. Soc., [vol.] p. 295) with the lead-silver iodide alloy, some curious [analogies] present themselves. The alloy, AgI, AgBr, AgCl ([the] discovered as a mineral), contains 41·484 per cent. of [the] silver, and 58·516 per cent. of the chloride and [bromide] silver (which from an expansion point of view may be [regarded] as the same substance, because their co-efficients are [practically] the same). But although the mean coefficients of [expansion] the chloride and bromide scarcely exceed those of the [iodide] lead, and although the chlorobromiodide contains 8 per cent. [more] iodide of silver than the lead-silver iodide alloy, the [amount] *contraction* by heat of the latter is more than twenty times [greater] than that of the former, although we must believe this [effect] be solely due in each case to the presence of the iodide of [silver].

Mathematical Society, April 14.—S. Roberts, [F.R.S.] president, in the chair.—The chairman briefly, but [feelingly] alluded to the loss the Society had sustained by the [recent] of Mr. T. Cotterill, M.A., formerly Fellow of St. [John's] lege, Cambridge, who was for many years a member [of the] Council, and had always taken a warm interest in the [Society].

following communications were made :—On the geodesic ıre of a curve on a surface, Prof. Cayley, F.R.S.—On ive symbols in the differential calculus, Prof. Crofton, .—Note on the resolution in factors of numbers differing ghtly from π, Mr. J. W. L. Glaisher, F.R.S.—On the of the quadric represented by the general equation of the l degree in tetrahedral co-ordinates, and on the five focal ics of a cyclide, Mr. H. Hart, M.A.—The discrimination maximum or minimum path of a ray of light reflected at n curve, Mr. H. M. Taylor, M.A.—On certain tetrahedra lly related to four spheres meeting in a point, and his- l note on Dr. Graves's theorem on confocal conics, the lent.

ysical Society, April 9.—Prof. W. G. Adams in the —Prof. Helmholtz was elected an honorary member of the ty, and Dr. James Moser an ordinary member.—Dr. Gladstone read a note on thermal electrolysis, by himself Mr. Alfred Tribe. The authors found that when sheet- was plunged into fused silver chloride or iodide of silver ıls of silver formed on the sheet. When copper was im- ed in fused cuprous chloride copper crystals deposited on it, hen zinc was placed in melted zinc chloride or iron in melted ıs chloride, these two metals crystallised on the plates. They l this to be due not to a difference in the physical condition of olled metals, but to the unequal heating of the different parts ıe immersed metals. By the contact theory of voltaism will be a difference of potential between the metal and the l chloride in contact with it, and this difference of potential vary with temperature. Since all parts of the immersed l cannot be supposed at the same temperature always, there is ossibility of a current being set up and consequent electrolysis e salt. This view was corroborated by heating the metal un- lly, when a crop of crystals appeared in the cooler part of iquid. Again, two silver rods connected together were ged, the one in a hotter, the other in a cooler part of fused chloride, and at the end of fifteen minutes the latter was Led with crystals of silver, whilst the former was clean. A nometer showed a stronger current between the rods, the er the difference of temperature between the parts of the in which they were placed, and transposing the rods reversed current. These experiments bear on the nature of voltaic n, and form a lecture-illustration of the conversion of heat electricity and chemical force. Mr. W. H. Walenn stated that d found when zinc is immersed in an electro-brassing solution, als of brass (*i.e.*, zinc and copper) were deposited on it.— Abney exhibited a number of photographic negatives n by himself and Col. Festing, by radiation through thin ts of ebonite. The light from the positive pole of an electric was sent through a thin sheet of ebonite $\frac{1}{64}$ inch thick, photographs taken showed the radiation to have a low wave- th, from 8000 to 14,000. The carbon points of the lamp ld be photographed through the sheet, and Col. Festing erved the sun's disk through it. The ebonite showed a grained cture, and different samples of ebonite gave different results, all gave some result in course of time at least; old ebonite, that used in some of Mr. Preece's experiments, scattering the it more than new ebonite.—Dr. Moser exhibited the passage the rays through the ebonite to the audience by means of a vanometer. Prof. Guthrie observed that Capt. Abney had ved that light as well as heat traversed the ebonite, and Coffin stated that the composition of ebonite apparently the ıe might vary considerably, and hence its radiant transparency ght vary too.—Prof. Helmholtz addressed the meeting on localisation of objects by the eyes. We estimate distance h one eye by the outlines of the more distant objects being ered by the nearer ones where they meet, and by the shadows own by the anterior objects. These conditions are very rarely rpowered by others, as, for instance, binocular vision. This shown by Dove's pseudoscope and the fact that closing or ading one eye makes little difference to the power of judging tance, especially when not very close to the eye. The relative fting of objects, as the eye is moved from side to side, or to l fro, or up and down, which may be called the parallax of tion of the head, is also a strong factor in estimating distance. e author had concluded from a study of the stereoscope that the ception of the absolute convergence of our eyes is very indistinct, l that only differences of convergence related to apparently ır or distant objects produce the stereoscopic effect. Recent servations of his show that the incongruity between the degree convergence and the parallax of motion is perceived with great accuracy. Dr. Stone remarked that a person suddenly blinded in one eye acquires a new judgment of distance by moving the head (a habit seen in nocturnal birds), and in taking certain French stereoscopic pictures the camera is shifted to another point, so that the combined images produce an impression of smallness in the object. These facts corroborated Prof. Helmholtz's view; and Mr. Lewis Wright pointed out that santonin, which changes the sense of colour, also appears to change the sense of distance, perhaps by relaxing the muscular sense.

Geological Society, April 6.—J. W. Hulke, F.R.S., vice-president, in the chair.—Edward F. Boyd, Lieut. Herbert de Haga Haig, R.E.; J. C. Margetson, Edward David Price, and James Tonge were elected Fellows of the Society.—The following communications were read :—The microscopic characters of the vitreous rocks of Montana, U.S., by F. Rutley, F.G.S., with an appendix by James Eccles, F.G.S.—On the microscopic structure of devitrified rocks from Beddgelert, Snowdon, and Skomer Island, by F. Rutley, F.G.S.—The date of the last change of level in Lancashire, by T. Mellard Reade, C.E., F.G.S. The author described some observations made by him at Blundellsands, on the coast of Lancashire, near Liverpool, according to which, judging from the position of high-water mark, the land had gained considerably upon the sea between 1866 and 1874. The author adduced evidence in support of his view, and concluded that if the last change of level in South-West Lancashire was a downward one it could not have taken place within 2500 years.

Institution of Civil Engineers, April 5.—Mr. Brunlees, F.R.S.E., vice-president, in the chair.—The paper read was on the actual lateral pressure of earthwork, by Mr. B. Baker, M. Inst. C.E.

EDINBURGH

Royal Society, April 4.—Prof. Balfour in the chair.—Prof. Tait communicated the results of his experiments on the pressure errors of the *Challenger* thermometers, the correction for which, as originally furnished to the expedition, was 0°·5 F. per mile of depth. The mode of experimenting was to subject the thermometers to considerable pressure in a hydraulic press, which was essentially a strong steel cylinder that was warranted to stand a pressure of 25 tons weight on the square inch. It was supported in an upright position upon a strong tripod stand. Water was filled in from above; and into the upper end of the cylinder there was lowered a tight-fitting plug which was fixed in position by a transverse steel bolt. The lower end of the cylinder was connected through a narrow copper tube to a hydraulic pump, which, by pumping in water to the cylinder, raised the pressure to the required amount. At three tons pressure an average effect of 1°·5 F. was produced upon the inclosed thermometers. Before drawing any conclusions as to the correction to be applied in deep-sea sounding, it was necessary to consider how far this effect could be explained as resulting from the peculiar conditions under which the experiments were made. From the known compressibility of glass it was calculated that the volume of the bore of a thermometer tube, closed at both ends, would be diminished by only one-thousandth part for an increase of pressure of one ton weight on the square inch; and from a direct experiment made with a metre-long tube this was proved to represent very approximately the real effect. Hence it was quite out of the question that this could have any appreciable effect on such comparatively short thermometers as those of the *Challenger*, which were besides subject to much graver errors, such as those arising from the shifting of the indices during the ascent from the depths, or even from the effect of parallax when taking the reading. The direct action of pressure may then be disregarded, and the effect produced upon the thermometers in the compression apparatus must be due to secondary effects of pressure, such as evolution of heat. The various sources of heat were four: 1. Heating of the water by compression. This depends greatly on the original temperature of the water, being *nil* at the point of maximum density (40° F.), and larger for higher temperatures. One-fourth of the total effect is due to this. 2. Heating of the water due to pumping in through the narrow tube. This accounts for three-twentieths of the effect. 3. Heating of the vulcanite frame by compression. This explains another fifth. 4. Heating due to the effect upon the protecting bulb. This probably explains the remaining two-fifths of the effect. In this last case however there is not only compression, but distortion; and of the thermal effects of such a strain no one yet knows anything. These four sources of error

cannot be supposed to exist under the conditions in which deep-sea temperatures are taken; and the only other possible source, that namely due to the direct effect of pressure, gives rise to an error which requires a correction of only 0°·04 F. per mile of depth. In the course of the description of experiments Prof. Tait had occasion to describe the various kinds of pressure-gauges which he had found it necessary to devise, the ordinary forms of gauge being altogether useless for scientific work.—Mr. W. W. J. Nicol read a paper on the action of heat on thioformanilide, being an account of experiments he had made in Prof. Hoffman's laboratory at Berlin during the preceding winter.—Mr. Patrick Geddes read the second instalment of his scheme for the classification of statistics. In it he discussed the arrangement of statistics relating directly to the organisms of the society. Three great parallel classes, A, B, C, were formed: A being concerned with the *source* of the organisms forming a community as arising from survival, immigration, and birth; C with the *loss*, from emigration and death; while B contained the biological and social characteristics of the individuals forming a community at any given instant of time. Classes A and B formed the one side and C the other side of the social balance sheet. In treating of occupations the same three classes appeared again: A dealing with operations on matter and energy, B with services rendered to society (including education, government, &c.), and C forming the class of the essentially unproductive, *e.g.* the unemployed, the disabled, the destructive, &c. The question of partition, both mediate and ultimate, amongst the organisms of matter and energy fell next for discussion; and this led on to the final classification of uses made after partition, in all of which it was shown that the classification fitted naturally into the three original classes, A, B, and C, indicated above. In a future paper Mr. Geddes hoped to demonstrate the *practical* value of his system.

VIENNA

Imperial Academy of Sciences, April 7.—L. Fitzinger in the chair.—The following papers were read:—Dr. G. Becka, on the orbit of the "Ino" planet (No. 173).—Dr. E. Ludwig, on a new method for the quantitative determination of uric acid.—Dr. D. Dublier, on the influence of continual use of carbonate of soda on the composition of the blood.—Dr. James Moser, electrostatic investigations especially into the ramification of induction on the differential inductometer and electrophorus.—Dr. Moritz Holl, on the blood-vessels of the placenta of man.—L. Haitinger, on nitro-olefines.

Imperial Institute of Geology, March 15.—E. Kittl, on a recent find of Listriodon (found at Nussdorf, near Vienna, in 1879).—Dr. E. Mojsisowics, on the cephalopod-fauna of the Triassic formations at Mora d'Ebro, in Spain.—K. M. Paul, on the occurrence of ozokerite and petroleum at Boryslaw (Gallicia).

April 5.—E. Kittl, on Bohemian spas.—Baron H. Fullon, observations on crystallisation.—Dr. V. Hilber, on the terminal stratifications of gypsum in Eastern Gallicia.

PARIS

Academy of Sciences, April 11.—M. Wurtz in the chair.—The following papers were read:—On peroxide of ethyl, by M. Berthelot. This may be prepared by sending through anhydrous ether, for several hours, a slow current of quite dry and strongly ozonised oxygen. The formation of oxygenated water by action of ozone on ether is not immediate, but by destruction of a first compound, viz. peroxide of ethyl. This substance is a sesqui-oxide $C_{16}H_{20}O_6$.—On the Eulerian integral of the second species, by M. Gyldén.—Researches on the liquefaction of gaseous mixtures, by MM. Cailletet and Hautefeuille. Operating with a gas easily liquefiable and a so-called permanent gas, in capillary tubes, total liquefaction (yielding a homogeneous liquid) is obtained by first compressing the mixture at a temperature so high that the strongest pressures prove powerless to abolish the gaseous state, then lowering the temperature regularly, so that all points of the tube pass at the same time through the temperature at which is produced a change of state. The authors thus obtained condensed carbonic acid, holding a large proportion of oxygen, hydrogen, or nitrogen, these latter substances concurring to form the liquid, though the temperature was too high for them to exist separately in that state. The results of experiment with cyanogen and carbonic acid are analysed. The assimilation (generally very imperfect) of solution of a gas to its liquefaction probably here applies. The mixture retains its characters at temperatures considerably above that corresponding to the point of its less easily liquefied element.—On the [illegible] the sun, by Mr. N. Lockyer. He shows reason for [illegible] iron does not exist in the heart of the sun, but only [illegible] tuents, and these exist at different levels in the sun's [illegible] and produce more complex forms by condensation.—On [illegible] attacked by a champignon, by MM. Cornu and [illegible] The insect belongs to the cycle of development of [illegible] *rubra*, which produces the red galls of elm. The [illegible] *Pleospora*; it attacks the dead puceron. It is probable [illegible] of affecting much the multiplication of phylloxera.—[illegible] integration of linear equations by means of Abelian [illegible] by M. Poincaré.—On formulæ of representation of [illegible] by M. du Bois-Reymond.—Study of the vapour [illegible] drate of ammonia, by M. Isambert. The substance [illegible] volatile in presence of its elements than *in vacuo*, [illegible] gas such as hydrogen.—On chlorides, bromides, and [illegible] sulphur, by M. Ogier. A thermo-chemical study [illegible] development of *Tricuspidaria nodulosa* or *Trichocephalus* of Rudolph, and on its cysticercus, by M. Mégnin. [illegible] perches of the Seine are greatly affected by the [illegible] present.—Studies on some points of the anatomy of [illegible] *scutata*, by M. Rietsch.—On the different species [illegible] whose remains are buried in the cavern of Lherm (Ariège), by M. Filhol. Remains of an enormous *Ursus* [illegible] rently) have been found among about 100 bones [illegible] *spelæus*. M. Filhol doubts the descent of the former from the latter. He supposes that *Ursus arctos*, [illegible] distant regions (perhaps North America), gradually [illegible] was substituted in our countries for *Ursus spelæus*. [illegible] ments of a new type of bear have been found in this cave; author names it *Ursus Gaudryi*. The fossil femur of a [illegible] mous lion has also been found.—Production of [illegible] silicate of baryta in crystals, by M. Le Chatelier. The [illegible] on the inner surface of vessels of baryta water [illegible] uncleaned a long time.—On the production of a [illegible] phosphide of iron and of anorthite felspar in the [illegible] Commentry coal-pits, by M. Mallard.—On the [illegible] Seine during the winter of 1881, by M. Lemoine. [illegible] at Paris has been pretty high from the middle of January [illegible] middle of March. Usually (as M. Belgrand has [illegible] maximum of flood at Paris is due to the waters of [illegible] rivers mostly in the upper part of the valley and [illegible] impermeable strata. But last winter, it is chiefly [illegible] nearest Paris, those of Brie, that, by their quite unusual [illegible] have brought on the maximum (which has therefore [illegible] great rapidity). The subsoil of La Brie is like a [illegible] when it is gorged with water the least rain causes [illegible] floods.

CONTENTS

Sir William Herschel, III. By J. R. Hind, F.R.S. . .
British Fishes . . . . . .
Our Book Shelf:—
"Proceedings of the Aberdeenshire Agricultural Association"
"Proceedings of the London Mathematical Society" . .
Letters to the Editor:—
The New Museum of Natural History.—F. G. S. . .
The Tide Predicter.—Sir William Thomson, F.R.S.
Geological Relations of Gold in Nova Scotia.—Principal Dawson, F.R.S . . . . . .
Symbolical Logic.—Hugh McColl . . . . . .
Agricultural Communism in Greece.—W. Matthieu Williams
Heat of Stellar Masses.—Saml. J. Wallace . . . .
Shadows Cast by Venus.—Chas. T. Whitmell . . . .
The Sparrow and Division of Labour.—G. C. Wallich .
Sir Philip de Malpas Grey Egerton, M.P., F.R.S. . .
The Scientific Principles Involved in Electric Lighting. Prof. W. Grylls Adams, F.R.S. . . . . .
The French Association for the Advancement of Science. Algiers. By G. F. Rodwell . . . . . .
Mr. Darwin on Vivisection . . . . . .
The Magnetic Survey of Missouri. By Prof. Francis E. [illegible] (*With Chart*) . . . . . .
Primitive Marriage Customs. By D. MacLennan .
Notes . . . . . .
Our Astronomical Column:—
The Solar Parallax . . . . . .
The Double-Star Herschel 3945 . . . . . .
The Total Solar Eclipse of 1878 . . . . . .
The Earthquake of November 28, 1880, in Scotland and Ireland. By Charles Alex. Stevenson, B.Sc. . .
Magnetic Declination. By Prof. Balfour Stewart, M.A., F.R.S. (*With Diagram*) . . . . . .
University and Educational Intelligence . . .
Scientific Serials . . . . . .
Societies and Academies . . . . . .

ONS TO "NATURE."

	£	s.	d.
	28	0	
	14	6	
	7	6	

nited States, the Continent, and Postal Union :—

	£	s.	d.
	30	6	
	15	6	
	8	0	

ADVERTISEMENTS.

mm 2s. 6d. *od.* per Line after.

	£	s.	d.
arter Column	0	18	6
Column	1	15	0
n	3	5	0
	6	6	0

ıable to MACMILLAN & CO.
FORD STREET, STRAND, W.C.

OF SOCIETIES.

LONDON

SDAY, April 21.
New Genera of Plants from Sokotra: Prof. Isocrater Shells (Australia): Edgar A. Smith. ıs, Linn., and certain Allied Species: R. ual Variation in the Branchial Sac of Simple ate.
n Frictional Installation, Part III.: E. O. Hydric Permeable by steam.—I. Periodic Per- The Oxidation of Sulphurous Acid: H. E.

y.—On the Histology of Thymus in Lacer- ages to their Classification: Frederick G. y between Jewish and Christian Baptism in Jacobs.
DAY, April 28.
s, at 8.—On the Histology of the Gustatory w. J. Charles Wroe, M.R.C.S.
SDAY, April 29.
at 4.—George Combe and his Work: Dr.

SDAY, April 25.
—Schelling and Hegel: Prof. W. T. Harris

y.—Notes on the Mortality of the Danish Harald Westergaard.
SDAY, April 26.
ng 8.—Isotropic Organisms: Archaic Structures ers: A. T. Lewis.—On a New Instrument ght: G. M. Atkinson.—Thomas Aquinas on S. Gaspe, B.A.
IV., at 1.—Scientific Committee
n-Metallic Elements: Prof. Dewar.
ESDAY, April 27.
n the Present Mode of Accumulation and ion Shelley Dupuis on the Enjoyment of on the Ancient Shores of the Welsh Major Prof. Evans showing probable Variations in Man's Jaunch.—Notes on a Mammalian Jaw mage, Dorset: R. Willett.—Communicated ern Limits of the Upper Jurassic Rocks of Lincoln: Rev. T. T. Wood: Rev. J. J. Blake, M.A.—On Fossil n the Yarra-Yarra, Victoria, Australia: A.

Marine Evaporation: Edmund Johnson.
AY, April 28.
influence of Snow and Strain on the Action ion.—The Meteorological Conditions of London: a Brooke.
ance, at 8.
ipation: Prof. Tyndall.
ges in Water: Dr. S. Schwendeler.
SDAY, April 29.
ıguage and Literature of the Scottish High-

ilding Arts of India: General Maclagan.
DAY, April 30.
eland's Part in English Literature: Prof.

LIGHTNING CONDUCTORS.

Experience, accumulated since the time of Benjamin Franklin, proves conclusively that a Conductor made of Copper of adequate size is the best of all appliances for the protection of every description of building from the destructive effects of lightning.

NEWALL & CO.'S
PATENT COPPER LIGHTNING CONDUCTOR,

As applied to all kinds of Buildings and Shipping in all parts of the world with unvarying success: is the most Trustworthy, most Effective, and also the Cheapest Conductor ever offered to the public.

It is simple in its application, no insulators being required, and it costs only one shilling per foot for the standard size, which ensures safety in any event.

R. S. NEWALL & CO., 130, STRAND, W.C.
16, WATERLOO ROAD, LIVERPOOL.
66, ANDERSTON QUAY, GLASGOW.
MANUFACTORY—GATESHEAD-ON-TYNE.

Liberal Terms to Science Teachers and the Trade.

THOMAS CRAMPTON (formerly of 4,

Little Britain, London, E.C.), ELECTRICIAN, OPTICIAN, and PHILOSOPHICAL INSTRUMENT MAKER. Electric Bells, New Metallic Base Pattern. Constant Batteries. Indicators. Thief and Fire Alarms, and Automatic Switches. Induction and Medical Coils, on Specialities. Insulated Wires of every description. Microscopic and Optical Materials. Telescopes, Opera Glasses, Microscopes, Aneroid Barometers, and Lime-light Apparatus. Illustrated Catalogue Three Stamps.

THOMAS CRAMPTON & CO., 351, HIGH HOLBORN, LONDON, W.C.
For Trade Terms send Card.

DRAPER'S INK (DICHROIC).
THE NEW BLACK INK

DIFFERING FROM ANYTHING ELSE EVER PRODUCED.

Writing becomes a pleasure when this Ink is used. It has been adopted by the principal Banks, Public offices, and Railway Companies throughout Ireland.

It writes almost instantly Full Black. | Flows easily from the Pen.
Does not corrode Steel Pens. | Blotting-paper may be applied at the moment of writing.
Is cleanly to use, and not liable to fillet. |

Can be obtained in London, through Messrs. BARCLAY & SONS, Farringdon Street; W. EDWARDS, Old Change; F. NEWBERY & SONS, Newgate Street; WM. MATHER, London and Manchester; J. AUSTIN & CO., Duke Street, Liverpool; and STACY & COOK, Paternoster Row; and to be had of all Stationers.

DEWLEY & DRAPER (Limited), Dublin.

R. W. NEEVES,
PHILOSOPHICAL INSTRUMENT
AND
INTENSITY COIL MAKER.

PRICE LIST, FOUR STAMPS.

55, SIDMOUTH STREET, LONDON, W.C.

NOTICE OF REMOVAL.
JAMES HOW & CO.,

SCIENTIFIC INSTRUMENT MAKERS,

73, FARRINGDON ST., LONDON

(LATE OF 5, ST. BRIDE ST., AND 3, FOSTER LANE).

HOW'S STUDENT'S MICROSCOPE. HOW'S MICROSCOPE LAMP.
Rock Sections and other Objects for the Microscope.

ELECTRICAL AND SCIENTIFIC APPARATUS.

Wholesale Manufacture of Metallic Base Electric Bells, Electric Reversing Indicators, and Constant Manganese Batteries, Telephone Switches and Transmitters, Induction Coils and Vacuum Tubes, Terminals, Cabinets, Wires and all Materials. Instruments made, repaired, or altered to order promptly. Illustrated Bell List free. Complete Catalogue, two Stamps. Special Quotations to the Trade.

HENRY J. DALE, MANUFACTURING ELECTRICIAN and OPTICIAN,
4, Little Britain, London, E.C.

APPARATUS AND SCIENTIFIC INSTRUMENTS.
PURE CHEMICALS, &c.
PORTERS AND MANUFACTURERS.
AUG. BEL & CO.,
MAIDEN LANE, COVENT GARDEN, LONDON, W.C.

of Apparatus as required by the Universities, Colleges, and Schools always ready and kept in stock. Professor Ferry's ık, as recommended by Dr. Voelcker. Description on Application. A Liberal Discount allowed to the Trade.

W. LADD & CO.,

SCIENTIFIC INSTRUMENT MANUFACTURERS,

(By Appointment to the Royal Institution of Great Britain),

11 AND 12, BEAK STREET, REGENT STREET, W.

BIDWELL'S SELENIUM RHEOSTAT. AND OTHER APPARATUS FOR BELL'S PHOTOPHONE.

PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3s. per oz.

Physical Apparatus of every Description.

ILLUSTRATED CATALOGUE, SIXPENCE.

PATERSON'S NEW CATALOGUE OF PHYSICAL APPARATUS

LANTERN SLIDES for SCIENTIFIC LECTURES. Season 1880-1. Post free 6 Stamps.

Complete Sets of Physical Apparatus for Science Primers and all the Physical Text-books in use in Schools and Colleges.

Siemens and Gramme Dynamo Machines and Lamps for hire.

Schools supplied with Apparatus as per Science and Art Departments' Requirements in the Sections of Light, Heat, Sound, and Electricity.

Electric Signals for Houses, Hotels, &c., Colliery Signals, Lightning Conductors. The Gower-Bell Loud-speaking Telephone.

EDWARD PATERSON, Electrical Engineer.

SHOW ROOMS AND STEAM WORKS:—76, LITTLE BRITAIN, E.C. (late 3, Bedford Court, W.C.).

MOLISON'S HARMONOGRAPH; executes the Harmonic Curves in the most perfect manner. 15s. and 20s.

Illustrated Catalogue of Electrical Apparatus, Part 1, *post free, 6 Stamps. Ditto, Electric Signals. Part* 2, 6 [illegible]

S. C. TISLEY & Co.,

OPTICIANS,

172, BROMPTON ROAD, S.W.

(Close to South Kensington Museum.)

THE PHONEIDOSCOPE

An Instrument for Observing the Colour-Figures of Liquid Films under the action of Sonorous Vibrations,

Being a visible demonstration of the Vibratory and Molecular Motion of a Telephone Plate.

The PHONEIDOSCOPE, with 3 Discs, Bottle of Solution, Descriptive Pamphlet, &c., in Cardboard Box, 10s. 6d.

MANUFACTURED AND SOLD WHOLESALE AND RETAIL BY

S. C. TISLEY & CO., 172, BROMPTON ROAD, LONDON, S.W.

TELEPHONIC ELECTRICITY. All Materials supplied for Experimental Purposes.

Price Lists of Electrical and Acoustic Apparatus, with Drawings and Description of the Harmonograph. Post Free, 2d.

NORTH BRITISH AGRICULTURIST

is the only Agricultural Journal in Scotland, and circulates extensively amongst Landed Proprietors, Factors, Farmers, Farm-bailiffs, and others interested in the management of landed property throughout Scotland and the Northern Counties of England.

The AGRICULTURIST has also a very considerable circulation on the Continent of Europe, America, Australia, and the Colonies.

The AGRICULTURIST is published every Wednesday afternoon in time for the evening mails, and contains Reports of all the principal British and Irish Markets of the week, besides Telegraphic Reports of those held on the day of publication.

The Veterinary Department is edited by one of the leading Veterinarians in the country, and is invaluable to the breeder and feeder as a guide to the rearing of animals, and their treatment when labouring under disease.

Full Reports are given of the Meetings of the Royal Agricultural Society of England, the Royal Agricultural Society of Ireland, the Highland and Agricultural Society of Scotland, the Scottish Chamber of Agriculture, and all the principal Agricultural Associations throughout Great Britain and Ireland.

For Advertisers addressing themselves to Farmers a better medium does not exist

Price 3*d*. By post 3½*d*. Annual Subscription, payable in advance, 14*s*.

Office—377, High Street, Edinburgh.

Post-Office Orders payable to Charles Anderson, Jun., Edinburgh.

ESTABLISHED 1843.

THE "HANSA"

Published since 1864 in Hamburg, is the only independent professional paper in Germany, dedicated exclusively to Maritime Objects. Essays, Critiques, Reviews, Reports, Advertisements. Strict eye kept upon the development of Maritime Affairs in every respect. Every second Sunday one Number in 4to at least; frequent supplements and drawings. Subscription at any time; preceding numbers of the year furnished subsequently. Price 12*s*. for twelve months. Advertisements 4*d*. a line, widely spread by this paper; considerable abatement for 3, 6, 12 months' insertion. Business Office: Aug. Meyer and Dieckmann, Hamburg, Alterwall. 28. Edited by W. v. FREEDEN, M.R., Hamburg, Alexander Street, 8.

HOLLOWAY'S PILLS

THIS MEDICINE

Is a Certain Cure for all Disorders of the LIVER, STOMACH AND BOWELS. A Great PURIFIER of the BLOOD; a Powerful Invigorator of the System, in cases of WEAKNESS AND DEBILITY, and is unequalled in Female Complaints.

EAGLE INSURANCE COMPANY

79, PALL MALL.

FOR LIVES ONLY. ESTABLISHED 1807.

Accumulated Funds ... ...

Also a Subscribed Capital of more than ... ...

Reports, Prospectuses, and Forms may be had at the Office of the Company's Agents, post free.

GEORGE HUMPHREYS, Actuary.

SECOND EDITION

GRIFFIN'S CHEMICAL HANDICRAFTS

PRICE 4*s*. 7*d*. POST FREE.

A CATALOGUE OF CHEMICAL APPARATUS

ILLUSTRATED, CLASSIFIED, DESCRIPTIVE.

Demy 8vo, 480 pp., Illustrated with 1,600 Woodcuts.

Most Complete and Cheapest List of Apparatus

JOHN J. GRIFFIN AND SONS, 22, GARRICK STREET, LONDON, W.C.

THE ZOOLOGIST:

A MONTHLY MAGAZINE OF NATURAL HISTORY.

Third Series. Edited by J. E. HARTING, F.L.S., F.Z.S., &c. British Ornithologists' Union: contains—

Original articles by well-known naturalists in every branch; habits of animals; arrival and departure of migratory birds; occurrence of rare birds; distribution and migration of British freshwater or rare marine fish; local aquaria; British reptiles; British land and water mollusca, with remarks on the haunts and habits of the species; other matters of general interest to those who delight in natural history. Reports of the Linnean, Zoological, and Entomological Societies. Reviews of natural history books. Occasional translations from foreign journals of important and interesting articles in various branches. There are occasional woodcuts.

JOHN VAN VOORST, 1, Paternoster Row.

THE ENTOMOLOGIST'S MONTHLY MAGAZINE.

Price Sixpence, Monthly, 24 pages 8vo, with occasional Plates.

Conducted by C. G. BARRETT, J. W. DOUGLAS, R. MCLACHLAN, E. C. RYE, F.Z.S., E. SAUNDERS, F.L.S., and H. T. STAINTON.

This Magazine, commenced in 1864, contains standard articles on all subjects connected with Entomology, and especially as to the British Isles.

Subscription—Six Shillings per Volume, post free. The volumes commence with the June number in each year.

Vols. I. to VI. (strongly bound in cloth) may be obtained by subscribers the entire set to date, at the increased price of 10*s*. each; the first two vols. may be had separately or together, at 7*s*. 6*d*. each.

London: JOHN VAN VOORST, 1, Paternoster Row.

N.B.—Communications, &c., should be sent to the Editor's address.

On the 1st of every Month.

TRIMEN'S JOURNAL OF BOTANY

BRITISH AND FOREIGN.

New Series. Edited by JAMES BRITTEN, F.L.S., British Museum.

CONTENTS.—Original Articles by leading Botanists.—Short Notices of Books and Memoirs.—Articles in Journals.—Botanical Proceedings of Societies.

Price 1*s*. 3*d*. Subscription for One Year, payable in advance.

London: WEST, NEWMAN, & CO., 54, Hatton Garden.

MACMILLAN & CO.'S PUBLICATIONS.

BOERS, and BRITISH: a Three-Cornered
F. R. STATHAM. Crown 8vo. 6s.
mint yet given to the English public of South African politics, but it is that and very much more. It
in itself. . . . His book shows a complete grasp of the subject and great power of presentation and

POLOGY: an Introduction to the Study of
ILISATION. By E. B. TYLOR, D.C.L., F.R.S. With numerous Illustrations.
6d.
it before the lay readers in a clear, condensed, and interesting form the main settled results of modern
ge of man. . . . Mr. Tylor's admirable little book certainly deserves the success with which it will
l Gazette.
and entertaining introduction to the science of anthropology. . . . His writing is clear and luminous,
y."—*Saturday Review.*

ANCIENT GEOGRAPHY. From the German of Dr. H.
vo. 5s.
ceeds in making ancient geography interesting, connecting it as he is able to do from his extensive and
e natural features of the various countries, the movements of various races, and modern conditions.
ical and the treatment clear and well defined, the connection between the Old World and the New
. . . Altogether the English edition of the Manual will form an indispensable companion to Kiepert's
four leading schools."—*The Times.*

DETERMINATION OF FORCES IN ENGINEERING
J. B. CHALMERS, C.E. With Illustrations. 8vo. 24s.

ENGINE AND ITS INVENTORS: a Historical Sketch.
LOWAY, Mining Engineer. With numerous Illustrations. Crown 8vo. 10s. 6d.
little book."—*English Mechanic.*
and general interest."—*Newcastle Weekly Chronicle.*
ble addition to engineering literature."—*Colliery Guardian.*

)N BALFOUR STEWART'S ELEMENTARY LESSONS
of. THOMAS H. CORE, Owens College, Manchester. 18mo. 2s.

TED WORKS OF FRANCIS SIBSON, M.D. LONDON,
WILLIAM ORD, M.D. With Illustrations. 4 vols., 8vo. £3 3s.

IE RANKS TO A COMMISSION. Crown 8vo. 6s.
l indeed instructive narrative."—*Army and Navy Gazette.*
. . . such a peep behind the curtain has seldom been offered to the public. . . . We have already said
the book, and we hope to induce the public to read it."—*Athenæum.*

NEW AND REVISED EDITION. VOL. I. OF
JOHN MILTON. Narrated in connection with the Political,
ary History of his Time. By DAVID MASSON, M.A., LL.D., Professor of Rhetoric and English
sity of Edinburgh. Vol. I. New and Revised Edition. 8vo. 21s.
. III., 8vo. 18s. Vols. IV. and V., 8vo. 32s. Vol. VI., with Portrait, 8vo. 21s.

NOW READY, VOL. II.
PHYSICS OF THE SCHOOL. By THOMAS HARPER (S.J.).
II., 8vo. 18s. (Vol. I., 8vo. 18s.)
ed professors, students, and cultured readers of all sorts to study it and to try to master it."—

, ANCIENT AND MODERN. By a Late Fellow of Trinity
Crown 8vo. 2s.

NEW PART—XIII. (PLANCHÉ to RICHTER).
Y OF MUSIC AND MUSICIANS, A.D. 1450-1881. By
h and Foreign. With Engravings and Woodcuts. Edited by GEORGE GROVE, D.C.L. In Three
II. 21s. each; Parts I. to XIII. 3s. 6d. each.

OUS CHRISTIANITY AND OTHER SERMONS, preached
ity College. By GEORGE SALMON, D.D., Chancellor of St. Patrick's Cathedral, and Regius
the University of Dublin. Crown 8vo. 6s.

ANALYTICAL GEOMETRY. Compiled and arranged by
ior Mathematical Master in the Classical Department of Cheltenham College. Crown 8vo. 4s. 6d.

MACMILLAN AND CO., LONDON, W.C.

Mr. HUBERT HERKOMER, A.R.A., has executed a large Design PICTORIAL ADVERTISEMENT (size, 11 ft. 6 in. by 9 ft.), in reference to Article will appear in the MAGAZINE of ART for MAY, under the Title STREETS as ART-GALLERIES."

The STREETS as ART-GALLERIES.—Mr. HUBERT HERKOMER large Design for a Pictorial Advertisement has been reproduced on a small scale the pages of the MAGAZINE of ART, and will appear in this Magazine for M the Article above referred to.

THE MAGAZINE OF ART, FOR MAY.

Ready APRIL 25th, price 1s., will contain—

"The SYMBOL." From the Painting by FRANK DICKSEE, A.R.A. Frontispiece.
TREASURE HOUSES of ART: the COLLECTION of Mr. C. P. MATTHEWS. By ARTHUR GRIFFITHS. With 5 Engravings.
ENGLISH BIRDS and their HAUNTS. By GRANT ALLEN. With 5 Illustrations.
OUR LIVING ARTISTS: WILLIAM QUILLER ORCHARDSON, R.A. By ALICE MEYNELL. With Portrait and 2 Engravings.
"APPLE BLOSSOM." From the Painting by M. BEYLE.
CHILDREN in PAINTING and SCULPTURE. By J. H. P. With 4 Engravings.
The HOMES of our ARTISTS: Mr. MILLAIS' HOUSE GATE. By JOHN OLDCASTLE. With 5 Illustrations.
The FUTURE of SCULPTURE in LONDON. By [illegible]
DECORATIVE IRON-WORK. With 6 Illustrations.
The STREETS as ART-GALLERIES. With 2 Engravings.
PICTURES of the YEAR. With 4 Illustrations.
"SHEPHERDS DISCOVERING the HEAD of ORPH[illegible] the Bas-Relief by M. CONDONNIER.
ART NOTES.

"*The* Magazine of Art *contains a very storehouse of art.*"—Times.
CASSELL, PETTER, GALPIN & CO., Ludgate-hill, London.

BOOKS ON THE LAND QUESTION.

SECOND EDITION.—Now ready, price 6s.; post free, 6s. 4d.

ENGLISH AND IRISH LAND QUESTIONS. Collected Essays, by the Right Hon. G. SHAW-LEFEVRE, M.P., First Commissioner of Her Majesty's Works and Public Buildings.

NEW EDITION, REVISED AND ENLARGED.—Price 3s. 6d.; post free, 4s.

LAND TENURE IN VARIOUS COUNTRIES, SYSTEMS OF. A Series of Essays, published under the sanction of the Cobden Club. Edited by J. W. PROBYN.

*** This New Edition is published at the special request of the Right Hon. W. E. GLADSTONE.

Just published, price 12s. 6d.

ENGLISH LAND AND ENGLISH LANDLORDS. By the Hon. GEORGE C. BRODRICK. An Inquiry into the Origin and Character of the English Land System, with Proposals for its Reform. Published for the Cobden Club.

CASSELL, PETTER, GALPIN & CO., Ludgate-hill, London.

WORKS FOR THE SPRING-T[illegible]

FAMILIAR GARDEN FLOWERS. By SHIRLEY HIBBERD, F.R.H.S. With Plates from Original Paintings by F. E. HULME, F.L.S., &c. The MAY Part, price 9d., contains Two Plates—Scarlet Geranium and Cuphea.

*** *The First Series is published complete in containing 40 Coloured Plates, price 12s.*

"Refined in colouring and admirably true to Hulme's drawings. . . . Mr. Hibberd tells just respecting the history and culture of each plant gardeners will be delighted with the volume."—G.

FAMILIAR WILD FLOWERS. By F. E. HULME, F.L.S., F.S.A. With Coloured Plates. The MAY Part, price 7d. Two Coloured Plates—Tansy and Hedge Stachys.

*** *The First and Second Series are published in One Volume, containing 40 Plates, price 12s.*

"The coloured figures are exquisitely [illegible] more like finished paintings than prints, and the work is elegant throughout."—Gardeners' Chronicle.

Cassell, Petter, Galpin & Co., Ludgate Hill.

On APRIL 25th will be published, PART 1, price 7d. (to be Completed in 25 Parts), of

MILTON'S PARADISE LOST,

ILLUSTRATED BY GUSTAVE DORÉ.

Prospectuses at all Booksellers, or post free from CASSELL, PETTER, GALPIN & CO., Ludgate-hill.

Every FRIDAY, price 4d.

THE LIVE STOCK JOURNAL

AND FANCIER'S GAZETTE

A Chronicle for Country Gentlemen, Breeders, and Exhibitors.

THE LIVE STOCK JOURNAL AND FANCIER'S GAZETTE, which is the official organ of the ROYAL AGRICULTURAL, SHORTHORN, SMITHFIELD CLUB, BRITISH DAIRY FARMERS', ENGLISH CART HORSE, CLYDESDALE, and other ASSOCIATIONS, now stands without a rival as a Chronicle for Country Gentlemen, Breeders, and Exhibitors.

Publishing Office and Office for Advertisements:
LA BELLE SAUVAGE YARD, Ludgate-hill, E.C.

Every Saturday

LAND

WITH WHICH IS INCORPORATED "LAND[illegible] THE ESTATE EXCHANGE REGISTER.

A Journal for all Interested in Land[illegible] House Property.

Printed and Published for the Proprietors by
Cassell, Petter, Galpin & Co., Ludgate-hill, [illegible]

*** *All Communications respecting Advertisements addressed to the Manager, Advertisement Department, Sawage Yard, Ludgate-hill, London, E.*

Printed by R. CLAY, SONS, AND TAYLOR, at 7 and 8, Bread Street Hill, Queen Victoria Street, in the City of London, and published by MACMILLAN AND CO., at the Office, 29 and 30, Bedford Street, Co[illegible] THURSDAY, April 21, 1881.

NATURE

A WEEKLY ILLUSTRATED JOURNAL OF SCIENCE

"To the solid ground
Of Nature trusts the mind which builds for aye."—WORDSWORTH

600, VOL. 23] THURSDAY, APRIL 28, 1881 [PRICE SIXPENCE

tered as a Newspaper at the General Post Office.]

[All Rights are Reserved.

TY AND GUILDS OF LONDON 'ITUTE for THE ADVANCEMENT)F TECHNICAL EDUCATION.

IER COURSES of LECTURES and LABORATORY IN- 'ION at the temporary Class Rooms of the Institute, COWPER ', FINSBURY, commencing May 2nd, 1881.

Chemical Technology—Prof. ARMSTRONG, Ph.D., F.R.S.

COURSES:—
BREWING, SPIRIT DISTILLING, &c.—Mondays.
PHOTOGRAPHY—Wednesdays.

URSES (Preliminary):—
LECTURES—Wednesdays and Fridays.
LABORATORY—Tuesdays and Fridays.

Physical Technology—Prof. AYRTON, A.M., Inst. C.E.

COURSES:—
ELECTRICAL INSTRUMENT MAKING—Tuesdays.
ELECTRIC LIGHTING—Fridays.

URSES (Preliminary):—
:CTRICITY and MAGNETISM—Mondays and Wednesdays.
3ORATORY PRACTICE—Mondays and Thursdays.

ng Class for Practice in Mathematical Calculations *free* to all s attending any of the above Courses, Thursdays, 7.30 to 9.30.
for Lectures and Laboratory Course together, 5s. and 7s. 6d.
led Prospectus on application to the Professors at Cowper Street , or to Gresham College, E.C.

PHILIP MAGNUS, Director and Secretary.

THOMAS'S HOSPITAL MEDICAL SCHOOL,

ALBERT EMBANKMENT, S.E.

SUMMER SESSION will commence on May 2nd. Students enter- ummer are eligible to compete for the Natural Science Scholarships o and £60 awarded in the following October.
ial Classes are held for the Matriculation, Preliminary Scientific, and B. of the University of London.
re are numerous Prizes and Scholarships, and all Appointments are o Students without extra payment.
ral Medical Practitioners and Private Families in the neighbourhood : Students for residence and supervision, and a register of inspected gs is kept in the Secretary's office.
ipectuses and all particulars may be obtained from the Secretary, Dr. ie.

W. M. ORD, M.D., Dean.

THE MIDDLESEX HOSPITAL MEDICAL SCHOOL.

SUMMER SESSION, 1881.

tures and Clinical Instruction in the Wards will commence on May 2nd: itlemen can enter to any one Course or to Hospital Practice only.
ENTRANCE SCHOLARSHIPS, of the annual value of £25 and espectively, tenable for two years, and a SCIENCE SCHOLARSHIP £50, will be offered for competition at the beginning of the Winter n.
Prospectus, containing particulars as to other Scholarships, Resident intments, Fees, &c., apply to the Dean or the Resident Medical r, at the Hospital.

ANDREW CLARK, Dean.

INT PAUL'S SCHOOLS.—About Eight

SCHOLARSHIPS will be AWARDED Next Term.—For informa- ion address CLERK to GOVERNORS, Mercers' Hall, E.C.

BROWNING'S BINOCULARS.

THE "ECONOMICAL" FIELD GLASS.

This Binocular has achromatic object-glasses 1½ inch in diameter, and sliding shades to shelter the object-glasses from sun or rain, and is fitted in a solid leather sling case, price £1 5s.; sent free for £1 6s. 6d.

Illustrated Catalogue of Binoculars post free.

JOHN BROWNING, 63, Strand, London, W.C.

TRAVELLERS' SCIENTIFIC REQUISITES.



ANEROID BAROMETER with ALTITUDE SCALE, THERMOMETER and COMPASS in Flat Pocket Case, various Forms,

£7 7s. and £8 8s.

Price Lists of Instruments free by post.

NEGRETTI & ZAMBRA,

Opticians and Scientific Instrument Makers

TO HER MAJESTY THE QUEEN,

HOLBORN VIADUCT,

45, CORNHILL, & 122 REGENT STREET, LONDON.

MICROSCOPIC OBJECTS

Of superlative perfection, illustrating Histology and every branch of Microscopy.

Catalogues post free and gratis on application.

NEW EDITION, 1880, NOW READY.

EDMUND WHEELER, 48B, Tollington Road, Holloway, London, N.

EXETER SCHOOL.

Chairman of Governors—The LORD BISHOP OF EXETER.

Head-Master—The Rev. EDWARD HARRIS, M.A., late Classical Assistant-Master at Clifton College.

The New School, with Chemical Laboratory, built from the designs of Mr. W. Butterfield, is now in use.

Tuition Fee, £15 to £21, according to age.
Boarding Fee, £50 to £63, ,, ,,

There are valuable Scholarships tenable at the School.

Also Exhibitions to the Universities and other places of higher education of the aggregate value of £500 per annum.

Apply to the CLERKS, Messrs. DAW & SON, 13, Bedford Circus, Exeter; or to the HEAD-MASTER, at the School.

OWENS COLLEGE, MANCHESTER.

The Council having decided to found a new Professorship of Applied Mathematics, invite applications from gentlemen desirous of becoming Candidates. The fixed stipend is £350 per annum, in addition to two-thirds of the fees paid by students. The appointment will date from the 29th September next. Further information respecting the duties of the Professor may be obtained from the Principal of the College.

Applications and testimonials addressed to the Council will be received up to the 28th May

J. HOLME NICHOLSON, Registrar.

ROYAL POLYTECHNIC.—CLASSES for

the Preparation of Students for University Examinations, under the direction of EDWARD B. AVELING, D.Sc., F.L.S. London University Matriculation, 1st and 2nd B.Sc., Preliminary Scientific M.B., Botany, Physiology, Chemistry. All the work practical.

CHARLES DARWIN, LL.D., F.R.S., and

the SOCIETY ABOLITION of VIVISECTION.—The Correspondence concerning the Letter to Prof. Holmgren of Upsala can be obtained gratis on sending a Stamped Directed Wrapper to the Honorary Secretary, GEORGE R. JASSE, Henbury, near Macclesfield, Cheshire.

INSTRUCTION IN MATHEMATICS.—

Youths or Adults attended at their Residence, on Reasonable Terms, by a M.A. of Cambridge. Unquestionable references if required.—Address, by letter, U. P., Post Office, Turnham Green.

CHEMISTRY.—Instruction given in Ana-

lytical and General Chemistry and Microscopy. Apply to the PRINCIPAL, The Metropolitan Laboratory, 32, Holborn Viaduct, E.C.

EVERY BOY A GEOLOGIST.

Now ready, and highly recommended, complete, price 7*s.* 6*d.*

This admirable little Work and most extraordinary Cabinet of wonderfully well-selected Natural Specimens, together with other Geological Preparations, and a powerful Lens, are calculated to start a boy thinking till he has mastered for himself no ordinary knowledge of the formation of the Earth's Crust.—THOMAS J. DOWNING, GEOLOGIST, &c., 38, Whiskin Street, London, E.C.—Catalogues free.

MINERALOGY AND GEOLOGY.

VERY FINE SPECIMENS of CRYSTALS of BLACK TOURMALINE in ROCK CRYSTAL—MADAGASCAR.

SOME FINE EXAMPLES OF ITACOLUMITE OR FLEXIBLE SANDSTONE—INDIA—IN SLABS 1 FOOT TO 7 FEET 6 INCHES.

BLOWPIPE CASES AND APPARATUS.

COLLECTIONS FOR STUDENTS, from £2 2*s.* COLLECTIONS FOR BEGINNERS, from 4*s.*

PRIVATE LESSONS AND EVENING CLASSES.

Catalogues free.

SAMUEL HENSON,

277 (*Late* 113*a*), STRAND, LONDON, W.C.

VALUABLE COLLECTION OF MINERALS FOR SALE.

JAMES R. GREGORY has now for Sale a very fine Old Collection, chiefly of Cornish Minerals, one of the best in Cornwall. The Collection was commenced forming sixty years ago, and contains most of the old Minerals of the County, many of which have not been found for many years. It consists of over 4000 Specimens, including a large number of Foreign Specimens, and is contained in four large well-made Spanish Mahogany Cabinets, two of thirty drawers each, and two of twenty-four Drawers each, with Bookshelves over. For Price, &c., and to inspect the same, apply to—

JAMES R. GREGORY,

88, CHARLOTTE STREET, FITZROY SQUARE.

LIVING SPECIMENS FOR THE MICROS

THOMAS BOLTON, NATURALISTS' and MICROS

STUDIO, 57, NEWHALL STREET, BIRMINGHAM

T. B. has last week sent to his subscribers the Fresh-water ... *marus pulex*, with drawing and description. He has also ... *dium longipes*, *Carchesium polypenum* and *spectabile*, Stent... and *Müller*, *Volvox globator*, Crayfish, Swan-Mussel, and ... He hopes to send out this week Elvers (Young Eels).

Weekly announcements will be made in this place of ... is supplying.

Specimen Tube, One Shilling, post-fr...

Twenty-six Tubes in course of Six Months for Subscription

Price List of Specimens on application, with stamped address...

Portfolio of Drawings, No. 4, One Shilling

DIAMONDS IN MATRIX

R. C. NOCKOLD, Diamond and Oriental Stone Cutter ... for sale Specimens of the above; also Cut Precious Stones ...

Precious Stones valued and bought.

12, FRITH STREET, SOHO, W.

GEOLOGY AND MINERALOG

IN the Preface to the "Student's Elements of ... Lyell he says, "As it is impossible to enable ... recognise rocks and minerals at sight by aid of ... tions or figures, he will do well to obtain a well-... lection of specimens." These can be had fr... WRIGHT, MINERALOGIST, 90, Great Russell Street.

50 Specimens in Cabinet	...	...	...	...	...	...
100 ,, ,,	...	...	...	...	...	...
200 ,, ,,	...	...	...	...	...	...

&c., &c.

More extensive Collections from 50 to 1000 Guine...

SELENIUM FROM £10 per Kilo...

THORITE from £30 per kilogram, is to be had of Dr. ... Stockholm.

THE QUARTERLY REVIEW, No...

IS PUBLISHED THIS DAY.

Contents.

I. THE REVOLUTIONARY PARTY.
II. LITERARY LIFE OF LORD BOLINGBROKE.
III. THE SPEAKER'S COMMENTARY ON THE ... TAMENT.
IV. THOMAS CARLYLE AND HIS REMINISCEN...
V. RUSSIAN LANDLAWS AND PEASANT PROP...
VI. SIR ANTHONY PANIZZI.
VII. ENDOWMENTS OF THE CHURCH IN ...
VIII. MINISTERIAL EMBARRASSMENTS.

JOHN MURRAY, Albemarle Street.

LA SEMAINE FRANÇAISE: A ...

Newspaper and Review in the French Language. ... Science, Art, Varieties, Notes. Price 3*d.*, through ... the railway bookstalls. Office, 37, Southampton Street, Str...

LA SEMAINE FRANÇAISE: Journal Fra...

l'Angleterre: Politique, Littérature, Sciences, Arts, Variétés ... et Notes. Un exemplaire par la poste, 3½*d.*, en timbres-poste ... ment franco par la poste—un an, 15*s.* 4*d.*; six mois, 7*s.* 8*d.* ... tous les libraires et aux gares des chemins de fer. On ... bureaux, 37, Southampton Street, Strand, Londres, W.C.

LA SEMAINE FRANÇAISE.—"'La Semaine ...

çaise' has been brought out in London for the benefit of ... readers who may wish to study contemporary French from ... view, instead of confining their reading to one particular ... It certainly merits success."—*Graphic.*

LA SEMAINE FRANÇAISE.—"The number ...

us are full of good things. . . . . It will be far better ... one of the best papers published in Paris itself. We are ... with the character of it, and believe it will be highly valued ... many households where French is cultivated. The printing ... done."—*Queen.*

TERMS OF SUBSCRIPTION:—

Three months	—	—	—	—	—	—	...
Six ,,	—	—	—	—	—	—	...
Twelve ,,	—	—	—	—	—	—	...

P.O.O. payable to T. SPANSWICK, at King Street, Covent Garden.

Publishing Office, 37, Southampton Street, Strand.

THE "HANSA"

Published since 1864 in Hamburg, is the only independent ... paper in Germany, dedicated exclusively to Maritime Affairs. ... Critiques, Reviews, Reports, Advertisements. Strict eye kept upon ... lopment of Maritime Affairs in every respect. Every second ... Number in 4to at least; frequent supplements and drawings ... at any time; preceding numbers of the year furnished subsequently ... 12*s.* for twelve months. Advertisements 4*d.* a line, widely spread ... paper; considerable abatement for 3, 6, 12 months' insertion. ... Office: Aug. Meyer and Dieckmann, Hamburg, Alsterufer 2. ... W. v. FREEDEN, M... Alexander Street, ...

WESLEY COLLEGE, SHEFFIELD.

THE SUMMER TERM COMMENCES ON TUESDAY, MAY 3RD.

Governor and Chaplain ... ... Rev. W. H. DALLINGER, F.R.S.
Head Master ... ... H. M. SHERA, Esq., LL.D.,
With Nineteen Assistant Masters and Professors.

In addition to Classics and English with Continental Languages, Modern Culture and Science are specialised.

THE

NITHOLOGICAL LIBRARY

OF THE LATE

SIR WILLIAM JARDINE,

NET OF JARDINE HALL, LOCKERBEE, N.B.,

just come into my possession. It includes the following Valuable Books:—

D'S Birds of EUROPE, 5 vols.
D'S Birds of AUSTRALIA, 7 vols. and Supplement.
D'S Birds of ASIA, *as far as out.*
D'S Birds of GREAT BRITAIN, 25 parts.
D'S Partridges of AMERICA, 3 parts.
BON'S Birds of North America, 4 vols. elephant folio; and 5 vols. of text.
and MITCHELL'S Genera of Birds, 3 vols. folio.
IS, a COMPLETE SET *from the commencement.*
SACTIONS of the ZOOLOGICAL SOCIETY, 10 vols. 4to. *A plete set.*
EEDINGS of the ZOOLOGICAL SOCIETY, 33 vols. 8vo. *A plete set.*
ON, Planches Enluminées, 5 vols. folio of 1008 *Coloured Plates of rds.*
MINCK ET LANGIER, Planches Coloriées, 5 vols impl. 4to. *coloured plates of Birds.*
MARS, Iconographie Ornithologique, 1 vol. impl. 4to.
TER and SALVIN'S Exotic Ornithology, 1 vol.
ER'S Birds of New Zealand, 4to.
HERBE, Histoire nat. des Piscidés, 4 vols., large folio.
OLD'S Birds of Japan, folio. *An early coloured copy.*
EVILLE, Revue de Zoologie. 31 vols. 8vo. from the commencement.
E EDINGS of the PHILADELPHIA ACADEMY of NATURAL ISTORY, 16 vols. *from the commencement.*
ON and BONAPARTE'S Birds of North America. 13 vols. folio. *e original Philadephia edition.*
CK'S British Birds and Quadrupeds, 3 vols. 8vo.
ER'S British Birds, 4 vols. folio.
S Birds of Brazil, 2 vols. folio.
Y'S British Ornithology, 2 vols. atlas folio.

☞ ALL CHOICE COPIES, WITH UNCUT EDGES.

ther, the ORNITHOLOGICAL WORKS of Azara, Bird, Baldamas, tein, Belanger, Blyth, Bonaparte, Cabanis, Cassin, Decken, Eyton, , Hartlaub, Heuglin, Hume, Jerdon, Lesson, Marshall, Pallas, Rüppell, , Sharpe, Schlegel, Sclater, Swainson, Temminck, Vieillot, Yarrell, n; the Ornithological portions of the great Scientific Voyages and ditions; Ornithological Journals, &c., &c.
pecial CATALOGUE of Sir WILLIAM JARDINE'S LIBRARY is in *prepara-* and will be forwarded *gratis* on application.
ady now are the following CATALOGUES of my extensive stock of s on NATURAL HISTORY:—

I. General Works, Collections, Scientific Voyages, the Palæarctic Region, Europe. Price *2d.*
II. The Palæarctic Region: the British Isles. Price *4d.*
III. " " North and West Asia, China, Japan, North Africa, Egypt, and North-East Africa, and Natural History Works, arranged in CLASSES. Price *1s.*
IV. The Ethiopic Region, the Oriental Region, the Australian Region, the Nearctic Region (North America), the Neotropical Region (South America). *6d.*

BERNARD QUARITCH, Bookseller, 15 Piccadilly, London.

The leading Farmers' paper."—CLARE SEWELL READ, ESQ., M.P.

THE CHAMBER OF GRICULTURE JOURNAL

AND FARMERS' CHRONICLE

(PRICE *3d.* WEEKLY).

he representative organ of the Central and Provincial Chambers of iculture; *gives fuller reports of the discussions and proceedings* of extensive organisation than any other agricultural paper. It devotes *ial attention to the treatment of Agricultural Questions by Parlia-t*, besides containing ample Reports of the LATEST LONDON and UNTRY CORN, CATTLE, HOP, PROVISION, and other Markets, Original Articles on Practical Farming, the Dairy, Herd and Flock ws, Horticulture, &c., &c. It is despatched every Monday evening in for the country post.
'erms of Subscription, payable in advance, post free:—3 months, *3s. 9½d.*; months, *7s. 7d.*; 12 months, *15s. 2d.*
ublished by W. PICKERING, 21, Arundel Street, Strand, London, W

THE SCIENTIFIC RESULTS OF THE VOYAGE OF H.M.S. "CHALLENGER."

Now ready, ZOOLOGY, Vol. II., Copiously Illustrated, in royal 4to, price *50s.*

REPORT on the SCIENTIFIC RESULTS

of the VOYAGE of H.M.S. "CHALLENGER" during the YEARS 1873-6, under the Command of Capt. G. S. NARES, R.N., F.R.S., and Capt. F. T. THOMSON, R.N. Prepared under the Superintendence of Sir C. WYVILLE THOMSON, Knt., F.R.S., &c. Provisional Title. ZOOLOGY, Vol. II.

*** This Volume may be had also in Two Separate PARTS, being Parts VII. and VIII. of the entire work as follows:—

PART VII. *Report on the Corals*, by H. N. MOSELEY, M.A., F.R.S., &c. Price *15s.*

PART VIII. *Report on the Birds*, by Dr. P. L. SCLATER, F.R.S., with the assistance of the late Marquis of Tweeddale, F.R.S., Dr. O. Finsch, C.M.Z.S., Prof. Salvadori, C.M Z.S., W. A. Forbes, F.Z.S., O. Salvin, F.R.S., H. Saunders, F.R.S., and the late Prof. Garrod, F.R.S. Price *35s.*

*** Published by Order of H.M. Government, and Printed for H.M. Stationery Office.

ZOOLOGY—Vol. III., containing Memoirs on the *Echinoida*, by Prof. AGASSIZ; and on the *Pycnogonida*, by Dr. HOEK, is nearly ready.

London: LONGMANS & CO, JOHN MURRAY, MACMILLAN & CO., SIMPKIN, MARSHALL, & CO., TRÜBNER & CO., E. STANFORD, J. D. POTTER, and C. KEGAN PAUL & CO. Edinburgh: A. & C. BLACK and DOUGLAS & FOULIS. Dublin: A. THOM & CO., and HODGES, FIGGIS & CO.

TEXT-BOOKS OF SCIENCE.

In small 8vo, with 372 Figures on Wood, price *6s.* cloth.

SYSTEMATIC MINERALOGY. By

HILARY BAUERMAN, F.G.S., Associate of the Royal School of Mines. (Forming one of Messrs. LONGMANS & Co.'s Series of Text-Books of Science, Mechanical and Physical, Edited by C. W. MERRIFIELD, F.R.S.)

London: LONGMANS & CO.

NEW WORK BY LIONEL S. BEALE.

Now ready, pp. 230, *demy* 8*vo*, *5s.*

SLIGHT AILMENTS:

THEIR NATURE AND TREATMENT.

By LIONEL S. BEALE, M.B., F.R.S., F.R.C.P.,

Professor of the Principles and Practice of Medicine in King's College, London.

J. & A. CHURCHILL, New Burlington Street.

New Edition, very much enlarged, *21s.*

HOW TO WORK WITH THE MICROSCOPE.

By LIONEL S. BEALE, F.R.S.,

President of the Royal Microscopical Society.

THE FIFTH EDITION,

Strongly bound and enlarged to 530 Pages, with 100 Plates, some of which are Coloured, is now ready.

HARRISON & SONS, Pall Mall.

Just issued, price *5s.*, handsomely bound in cloth, with Portrait of Author.

MIND IN ANIMALS. By Prof. Ludwig

BÜCHNER. Translated by ANNIE BESANT.

"It is a decidedly valuable addition to the literature of Comparative Psychology."—*Nature.*

London: FREETHOUGHT PUBLISHING COMPANY, 28, Stonecutter Street, E.C.

In unserem Verlage erscheint:

DER NATURFORSCHER.

Wochenblatt zur Verbreitung der Fortschritte in den Naturwissenschaften.

Herausgegeben von Dr. WILHELM SKLAREK.

Wochentlich 1—1½ Bgn. in 4°.

Preis vierteljährlich 4 Mk.

Die nunmehr ihren XIV. Jahrgang beginnende Zeitschrift hat bei Allen, welche sich mit Naturwissenschaften beschäftigen, grossen Beifall gefunden. Probenummern sind durch jede Buchhandlung zu erhalten.

Berlin, S.-W., 77, Charlottenstr.

FERD. DÜMMLER'S VERLAGSBUCHHANDLUNG.
(Harrwitz & Gossmann.)

SOCIETY FOR PROMOTING CHRISTIAN KNOWLEDGE.

NATURAL HISTORY OF BRITISH FISHES: their Structure, Economic Uses, and Capture by Net and Rod. Cultivation of Fish-ponds. Fish suited for Acclimatisation. Artificial Breeding of Salmon. By the late FRANK BUCKLAND, H.M. Inspector of Fisheries. With numerous Woodcuts. Crown 8vo, cloth boards, 5s.

MANUALS OF ELEMENTARY SCIENCE.

Fcap. 8vo, limp cloth, 1s. each.

Just Published.

ELECTRICITY. By Prof. FLEEMING JENKIN, F.R.S. With numerous Illustrations.

Already Issued.

ASTRONOMY. By W. H. M. CHRISTIE, M.A., F.R.A.S., Chief Assistant of the Royal Observatory, Greenwich.

BOTANY. By Prof. BENTLEY, of King's College, London.

CHEMISTRY. By ALBERT J. BERNAYS, Ph.D., F.C.S., Professor of Chemistry at St. Thomas's Hospital.

CRYSTALLOGRAPHY. By HENRY PALIN GURNEY, M.A., Fellow of Clare College, Cambridge. With numerous Illustrations.

GEOLOGY. By T. G. BONNEY, M.A., F.G.S., St. John's College, Cambridge.

MATTER AND MOTION. By J. CLERK MAXWELL, M.A., &c.

PHYSIOLOGY. By F. LE GROS CLARK, F.R.S., Surgeon of St. Thomas's Hospital.

THE SPECTROSCOPE AND ITS WORK. By R. A. PROCTOR, Esq. With Coloured Diagram of the Spectra and many Illustrations.

ZOOLOGY. By ALFRED NEWTON, M.A., F.R.S.

NATURAL HISTORY R

In Search of Minerals. By D. T. ANSTED, M.A., F Fellow of Jesus College, Cam With numerous Woodcuts. Fca boards, 2s. 6d.

"It is probable that his interesting induce many to go in search of mine selves."—*Athenæum*

Ponds and Ditches. By M. C M.A., LL.D., Author of "Th With numerous Woodcuts. Fca boards, 2s. 6d.

Lane and Field. By the Re WOOD, M.A., Author of "H Hands," &c. With numer Fcap. 8vo, cloth boards, 2s. 6d

The Woodlands. By M. C M.A., LL.D. With numer Fcap. 8vo, cloth boards, 2s. 6d

Lakes and Rivers. By C. NAPIER, F.G.S., Author of and Beauty of British Birds," & rous Woodcuts. Fcap. 8vo, cloth b

Mountain and Moor. By TAYLOR, Esq., F.L.S., F "Science Gossip." With numer Fcap. 8vo, cloth boards, 2s. 6d

Underground. By J. E Esq., F.L.S., F.G.S., Editor Gossip." With numerous W 8vo, cloth boards, 2s. 6d.

The Sea-shore. By Prof. P. DUNCAN, M.B. (Lond.), F.R.S rous Woodcuts. Fcap 8vo, cloth

"These handy little volumes together, and seem to us decided works of a similar kind with which familiar in our youth."—*Nature*

At the Depôts in London and Brighton a discount of 2d. in the shilling is allowed to Non-Members off all the miscellaneous publications of

LONDON: NORTHUMBERLAND AVENUE, CHARING CROSS, W.C.; 43, QUEEN VICTORIA STREET; 48, PICCADILLY, W.; and 135, NORTH STREET, BRIGHTON.

With 200 Illustrations, Medium 8vo, 30s.

THE CAT.

AN INTRODUCTION TO THE STUDY OF BACK-BONED ANIMALS, ESPECIALLY MAMMALS.

By ST. GEORGE MIVART, F.R.S.,

Author of "Lessons from Nature," &c., &c.

The principal feature of this work is that while giving a detailed account of one animal, it serves to explain the principal facts of all the different sciences with which the Student of Natural History has to deal.

JOHN MURRAY, ALBEMARLE STREET.

JUST PUBLISHED, crown 8vo, cloth, 5s.

CONSCIOUS MATTER;

OR, THE PHYSICAL AND THE PSYCHICAL UNIVERSALLY IN CAUSAL CONNECTION.

By W. STEWART DUNCAN.

"The writer is evidently a vigorous thinker. There is more gain to philosophy in a bit of independent thinking like this . . . than in a load of orthodox doctrine, where learned industry passes for original criticism."—*Westminster Review.*

London: DAVID BOGUE, 3, St. Martin's Place, W.C.

Ready this day, Demy 4to, Price 14s.

With 30 Outline Plates, 1 Coloured Plate, and 27 Wood Engravings.

A TEXT-BOOK OF PRACTICAL HISTOLOGY.

By WILLIAM STIRLING, M.D., Sc.D., F.R.S.E.,

Regius Professor of the Institutes of Medicine in the University of Aberdeen.

LONDON: SMITH, ELDER AND CO., 15, WATERLOO PLACE.

DAY, APRIL 28, 1881

TIFIC WORTHIES

ERG WILHELM BUNSEN

fe devoted to original scientific work
y the new paths and new fields
ns out. In this respect the labours
Bunsen stand second to those of no

Outwardly the existence of such a
nsen has been from the first, exclu-
, seems to glide silently on without
ıt or stirring incident. His inward
e contrary full of interests and of
riking and exciting kind. The dis-
n overthrows or remodels our ideas
science; the experimental proof of
unrecognised; the employment of
bination of known facts to effect an
applicability and utility: these are
of the man of science which may
tweigh the high-sounding achieve-
ble professions.

inently a soldier of science, his
as been unwavering and life-long,
e has been a noble struggle for the
secrets. Born on March 31, 1811, at
father was Professor of Theology,
that ancient University before he
is teens, and published an inaugural
ratio ac descriptio hygrometrorum."
he age of twenty-two, he became a
university of his native town thus
a teacher, which he has consistently
ainous success for close on half a
Bunsen became Professor of Che-
chnic School in Cassel; in 1838
o the Chair of Chemistry in the
g, where he remained for thirteen
e was for a short time at Breslau,
to Heidelberg, of which renowned
on one of the chief ornaments and
thirty years.

ntific investigation was one which
ention, and the results of which are
ance. In conjunction with Berthold,
ogen, he showed that moist freshly
droxide acts as a certain antidote in
arsenic, provided that it is exhibited
and early enough in the history of
lonation of this action is the for-
uble ferrous arsenite: 100 parts of
carry down from five to six parts
known and valued is this anti-
or it is kept by apothecaries ready

scribed some singular compounds
yanides form with ammonia. He
neral statement (that ammonium
ed by boiling prussian blue with
ed that it is formed by digesting
lead ferrocyanide with ammonium carbonate. He also measured the angles of crystals of many of the double cyanides.

In 1837 he struck the first note of one of his most important and fruitful investigations in a memoir on the existence of arsenic as a constituent of organic bodies. In the year 1760 the French chemist Cadet had observed that a mixture of acetate of potash and white arsenic yields, when heated, a heavy brownish-red liquid, which has a frightful smell and fumes strongly in the air, and this liquid was termed Cadet's fuming arsenical liquid. Little more than the fact of its existence was ascertained concerning this body until Bunsen undertook its examination, and in a series of memoirs which have now become classical, and which extended over many years, placed its composition in a true light, thus giving to the world the first member of the now well-known family of the organo-metallic bodies.

Bunsen showed that Cadet's liquid, as well as its numerous derivatives, contains a radical having the formula C_2H_6As, and that this substance in its chemical relations exhibited striking analogies with a metal, being indeed, as he terms it, "a true organic metal." He succeeded in isolating this body, and this discovery formed not only the starting-point for the preparation of hundreds of other similar bodies, but also contributed largely to the development of one of the most important of our chemical theories, that of compound radicals. This body, like most of its compounds, possesses a most offensive odour, so much so that the air of a room containing a trace of the vapour is rendered absolutely unbearable. Hence to this substance Bunsen gave the name of Cacodyl (κακόδης, a bad smell). Not only however are these compounds unpleasant, but they are highly poisonous, very volatile, dangerously explosive, and spontaneously inflammable. It is difficult enough nowadays for a chemist to work with such substances armed as he is with a knowledge of the danger which he has to encounter, as also with improved appliances of every kind to assist him in overcoming his difficulties. But Bunsen forty years ago was a traveller in an unknown and treacherous land, without sign-posts to guide him, or more assistance on his journey than was furnished by his own scientific acumen and his unfaltering determination. Nor did he escape scot-free from such a labour, for in analysing the cyanide of cacodyl the combustion tube exploded, Bunsen lost the sight of an eye, and for weeks lay between life and death owing to the combined effects of the explosion and the poisonous nature of the vapour. "This substance," he writes, "is extraordinarily poisonous, and for this reason its preparation and purification can only be carried on in the open air; indeed, under these circumstances it is necessary for the operator to breathe through a long open tube so as to ensure the inspiration of air free from impregnation with any trace of the vapour of this very volatile compound. If only a few grains of this substance be allowed to evaporate in a room at the ordinary temperature, the effect upon any one inspiring the air is that of sudden giddiness and insensibility, amounting to complete unconsciousness."

Taking a totally different direction, Bunsen's next important investigations were concerned with the examination of the chemical changes which occur in the blast-

furnace. In 1838 he proved, by accurate analyses of the gases escaping, "that at least 42 per cent. of the heat evolved from the fuel employed is lost, and that in view of the ease with which such combustible gases can be collected and led off to a distance for subsequent use, a new and important source of economy in the iron manufacture is rendered possible." This research is however not only noteworthy as pointing the way to a method of economical working without which probably but few iron-masters at the present day could exist, but also as being the first experiment in which an accurate method of gas-analysis was employed. This important branch of analytical chemistry has been created and brought to its present wonderful degree of precision solely by the head and hands of the Heidelberg experimental philosopher. Simplicity and accuracy constitute the rare merits of Bunsen's system of gaseous analysis. To have gone completely through his course of gas analytical manipulations from the sealing-in of the platinum wires in the eudiometer to the absorption- and explosion-analyses of the Heidelberg coal-gas, under the eye and with the guilding help of the hand of the master, is in itself an experimental education of no mean order. But it is only on reference to his "Gasometric Methods" that we learn the general adaptability of this marvellously accurate system to all those numerous problems in which the analysis of a mixture of gases is required.

Next in order (1841) comes the invention of the Bunsen battery, an invention which has proved of the greatest practical value to mankind, inasmuch as this form of battery is now very largely used all over the world, not only as a scientific instrument, but also for ordinary telegraphic purposes. The chief point in this invention consists in the employment of carbon as the negative pole in place of copper or platinum. In his first communication on this subject, Bunsen accurately measures the absolute intensity of the current from his zinc-carbon battery, and compares it with that of a Grove (zinc-platinum) battery, invented a short time before by Sir William Grove.

Bunsen's next great achievement consists in the investigation from both the chemical and the physical point of view of the volcanic phenomena of Iceland. The several memoirs on this subject are the result of a visit to Iceland in 1847. They consist, in the first place, of a careful and extended series of analyses giving the average composition of the volcanic rocks of different ages occurring in the island, upon which he founded a most important and very general theory of volcanic action, a theory which he has since proved is applicable to the formation of other volcanic rocks of widely different origin, both as regards time and locality. This theory consists, to begin with, in a proof that all the Islandic rocks, of whatever age, may be considered as mixtures in varying proportions of two normal silicates, the trachytic and pyroxenic. In the first of these (an acid silicate) the relation of the oxygen of the acid to that of the bases is as 3 : 0·596, whilst in the latter (a basic silicate) the relation is as 3 : 1·998. This result, accompanied by an experimental proof that the melting-point of different bodies is differently raised under increase of pressure, led Bunsen to assume that a crystallisation of these two normal silicates occurs in the earth's interior, and that all the eruptive rocks which reach the surface consist either [illegible] other of these or of mixtures of the same. In [illegible] place they contain a full and successful research [illegible] so-called pseudo-volcanic phenomena of Iceland; he investigates the formation of zeolites and other [illegible] line minerals by the joint action of heat, acid [illegible] moisture on the volcanic rocks. He also examines [illegible] composition of the fumerolle gases as well [illegible] issuing from the crater of Hecla, and explains [illegible] of the changes effected by these gases on the [illegible] ing rocks. Lastly, he investigates the far-famed Geyser, and places the cause of the periodic [illegible] boiling water on its true physical basis. His [illegible] observations on the spot, first as to the [illegible] the geyser-tube, then as to its mode of formation; finally, his thermometric measurements of the temperature of the water-column taken a few moments the eruption and at different depths, disposed [illegible] of what may be called the old tea-kettle theory showed indisputably that in no part of the tube water reach the temperature of ebullition under [illegible] sure of the superincumbent column, whilst the [illegible] quiescent, but that when the geyser column is [illegible] the rush of steam from the volcanic vents at the [illegible] the boiling-point of the water at each point of the [illegible] thus raised is reached, and "the whole mass [illegible] middle downward suddenly bursts into ebullition; water above mixed with steam-clouds is projected into atmosphere, and we have the Geyser eruption in [illegible] grandeur. By its contact with the air the [illegible] cooled, falls back into the basin, partially refills the [illegible] in which it gradually rises, and finally fills the tube before. Detonations are heard at intervals, and [illegible] of the water in the basin. These are so many attempts at an eruption, for not until the water in the tube comes sufficiently near its boiling-point to allow lifting of the column effective can we have an eruption" (Tyndall).

To do justice to all the contributions with which [illegible] has enriched our science would fill several numbers of NATURE, and to many of them the writer must [illegible] himself with a mere cursory reference. One of his favourite and fruitful themes was the preparation by electrolysis of the rarer or more difficultly [illegible] metals. This is one of the purposes for which he employed his battery. Metallic magnesium was [illegible] the first of his preparations of this kind, and in the description of this preparation his fertility of resource is clearly seen. Metallic magnesium in the molten state is specifically lighter than the fused *mixture of salts* from which it is obtained. Hence as soon as a globule of the metal is formed, it rises to the surface, and there takes fire and burns. To obviate this difficulty the carbon vessel in which the metal was formed was serrated, and the globule on rising was caught, below the surface of the fused salts, in one of a series of small pockets, and thus prevented from burning.

Then followed the reduction of chromium, aluminium, and, in conjunction with the late Dr. Matthiessen, of the alkaline-earth metals, and more recently by Hillebrand and Norton, of the metals of the [illegible] group. These electrolytic researches are marked by the thoroughness and completeness which is characteristic

nsen's work. He seeks for the explanation of that hitherto the reduction of these metals electric current had proved a failure, and he in what he terms the density of the current, electromotive force divided by the area of the power of the current to overcome chemical ncreasing with its density. Thus if a constant ɔe led through an aqueous solution of chromic , the result as to whether hydrogen is evolved, and chromium, or whether metallic chromium is d, depends upon the area of the pole through ıe current passes into the liquid.

were these experiments made merely for the of preparing the metals in question. Thus the magnesium was pressed into wire and used in the series of photo-chemical researches, to which :e will hereafter be made, for the purpose of g an interesting conclusion respecting its light-power on combustion, and comparing this with ıal and chemical brightness of the sun, a compari- ıich led to the commercial manufacture of this by the Magnesium Metal Company, and to the listribution and general use of this metal as an ıating agent of great brilliancy. Thus again the lytic preparation in the Heidelberg laboratory of ınt masses of cerium, lanthanum, and didymium, e further object of the determination of the specific ɔf these metals by help of the now well-known d with Bunsen's ice-calorimeter, by means of which nination the true atomic weights of these metals ıe proper formulæ of their oxides and compounds been definitely ascertained.

e Bunsen battery has however not only been of :e in inorganic chemistry, but has thrown clear upon the constitution of organic bodies. The clas- researches of Kolbe on the electrolysis of acetic and the other fatty acids were carried out in the ɔurg laboratory, and owe their inspiration to Bunsen. subsequent equally important labours of Kolbe Frankland, and those of the latter chemist alone, he isolation of the organic radicals, have a like n.

mongst the numerous physico-chemical investigations :h Bunsen has carried out, none perhaps show more rly the fertility of his experimental ability than the in which he describes the ice calorimeter, and another ɔted to an explanation of a new method of determining ɔur densities. Translations of these memoirs are ıd in the *Philosophical Magazine* for 1867 and 1871, may be taken as typical of his calorimetric re- rches.

ınother group of researches is formed by those which closely related to his gasometric methods. One of the st interesting and important of these refers to the law absorption of gases in water. This subject was first ımined by Dalton and Henry at the beginning of the ıtury, and the well-known law which gases follow in sorption is known by the names of these two Manchester ilosophers. But although generally admitted, its limits error had not been ascertained, and the crude experi- ental methods of the year 1803 required to be replaced y the refined ones of the latter half of the century. 'hese researches, carried on by Bunsen and by several of his pupils, proved that Henry's law of direct—as well as that of Dalton of partial—pressures is exactly true within certain limits; but ceases to be so beyond a given increase of pressure, whilst some gases which obey the law at one temperature do not do so at others, and some again whilst obeying it in the pure state, do not do so when mixed with other gases.

The mere mention of his other researches in the wide field of gaseous chemistry is sufficient to indicate his devotion to this branch of experimental inquiry. We find experiments on laws of gaseous diffusion, on applications of gaseous diffusion in gasometric analysis, on the phenomena of the combustion of gases, on the temperature of ignition of gases, and all these, be it remembered, involving exact measurement, and in many cases elaborate calculations.

Brief reference must next be made to a series of investigations in a totally different direction, viz. on the measurement of the chemical action of light, with the carrying out of which the writer of this article had the great good fortune and pleasure to be connected, and in which he had full opportunity of admiring Bunsen's untiring energy and wonderful manipulative power. In all the difficulties and perplexities by which the experimental investigation of such a subject is beset, the writer never knew Bunsen discouraged or at a loss for an expedient by which an obstacle could be overcome. Cheerful and self-reliant under the most depressing circumstances, he never gave up hope, and thus it was that these somewhat intricate and difficult investigations were brought to a successful close.

Again, in the department of Analytical Chemistry how numerous and valuable have been his contributions! There is scarcely one important problem in this subject which has not benefited from his extensive experience and keen insight. Bunsen's methods of silicate analysis, of mineral water analysis, and a dozen of other complicated laboratory processes, are simply perfect. Then his original method for the estimation of nitrogen in organic bodies will always be remembered as one of the most accurate of its kind when employed by an experimentalist as expert as Bunsen himself, but as most difficult and even dangerous in less able hands. Again, all chemists use and appreciate the much simpler methods for the estimation of nitrogen and sulphur admirably worked out by his pupils—Maxwell Simpson and Russell.

We all employ his beautiful general method of volumetric analysis, but chemists do not always remember that in this research Bunsen first determined the exact percentage composition of the higher oxide of cerium, a determination of the greatest scientific importance as regards the chemistry of the metals of the rare earths. Moreover they may be apt to forget that Bunsen was the first to introduce a general method of the separation of these rare earths, by which he for the first time prepared pure yttria and erbia, and by which subsequently, in the hands of other chemists, many new metals have been discovered. His well-known method of flame-reactions is a standard example worked out by every student. Again, modern chemists can now scarcely carry on the simplest experiment without using the "Bunsen gas-lamp," a burner which is also now employed in every household, and in many manufactories,

and has become so necessary that it is difficult to conceive how we worked before its invention. To him we are also indebted for the apparatus for accelerating filtration, the "Bunsen-pump," together with all its appliances, now employed in every laboratory.

Of all the contributions to the advancement of our science, that by which the name of Bunsen has, however, become best known, and by virtue of which future generations will place him on the highest pinnacle of experimental fame, is the foundation, with his no less celebrated colleague Kirchhoff, of the science of Spectrum Analysis, and the discovery by its means of the two new alkali metals, cæsium and rubidium. It is true, of course, that many facts were ascertained and many observations made relating to the power possessed by matter in the state of incandescent gas emitting rays of a peculiar and characteristic kind. Few great discoveries are made at one step. But the glory of having established a new branch of science, of having placed "Analysis by Spectrum Observations" on a sound and firm experimental basis, belongs to the Heidelberg philosophers, and to them alone.

The history of the establishment of spectrum analysis, as that of its enormous recent developments, is too well known to the readers of NATURE to require repetition. All that is necessary here is to recall the masterly way in which Bunsen worked out the properties and showed the relationships of the new metals and their compounds. He first saw the cæsium lines in a few milligrams of the alkaline residue obtained in an analysis of the Dürkheim mineral waters, and the discovery of a second new metal (rubidium) soon followed that of the first. So certain was he of the truth of his spectroscopic test that he at once set to work to evaporate forty tons (44,000 kilos) of the water, and with 16·5 grammes of the mixed chlorides of the two new metals which he thus obtained, he separated the one metal from the other (no easy task) and worked out completely their chemical relationship and analogies, so much so that the labours of subsequent experimenters have done little more than confirm and extend his observations; such a result is truly a marvel of manipulative skill!

Another less widely known, but no less interesting and important research, is that on the spark-spectra of the metals contained in cerite and other rare minerals. In this he shows his power both as physicist and chemist. He first describes a new chromic-acid battery suited to the performance of the special experiments which he afterwards details. He determines with great care all the physical constants of this battery, and then proceeds to investigate the spectra of the earths which give no colour to the non-luminous flame. The spark-spectra of these earths he carefully maps, so completely, indeed, that the separation and identification of these metals now for the first time became possible.

The many hundreds of pupils who during the last half-century have been benefited by personal contact with Bunsen will all agree that as a teacher he is without an equal. Those who enjoy his private friendship regard him with still warmer feelings of affectionate reverence. All feel that to have known Bunsen is to have known one of the truest and noblest-hearted of men.

H. E. ROSCOE

JAPAN

Japan, nach Reisen und Studien im Auf... Preuss. Regierung dargestellt. Von J. ... fessor der Geographie in Marburg. Erst... Natur und Volk des Mikadoreiches. (Leip... mann, 1881.)

Notes and Sketches from the Wild Coasts of N... Capt. H. C. St. John, R.N. (Edinburgh ... 1880.)

THE present year has already brought tw... tributions to the rapidly increasing stock o... literature in "Japan, nach Reisen und Studien... Rein of Marburg, and "The Wild Coasts of N... Capt. St. John. The two works thus thrown to... tion by subject and time of publication have ... nothing else in common.

Had Capt. St. John's book been written a fe... rations ago, or had it related to a country ... unexplored, it would have possessed a great ... upon popular interest; but Japan has in late ye... so far the object of careful study by residents ... descriptions by tourists, that the *raison d'être* ... Wild Coasts of Nipon" is not easy to perceive.

In the preface the reader is assured that ev... stated in the text, with a few exceptions, ... under the observation of the author, and ... doubt that he has scrupulously confined himself ... own personal experience, without seeking to ... augment it by reference to other sources. The ... of such a limitation of matter must however ... altogether upon the extent of the experience ... special qualifications of the observer, and ... opinion that had the author taken the trouble to ... what his predecessors have already made kn... would have largely altered his notes.

The author as a sportsman and naturalist dis... self in a more favourable light than as a ke... observer. His sporting memoranda are am... give a character to the volume, while as a ... naturalist he shows more than average knowl... contributes some interesting facts on the subje... animal kingdom. In the flora he is on less secure ... and on one occasion, at page 137, confuses ... least, two such well known trees as the Hinok... *spora obtusa*) and the *Cryptomeria Japonica*.

In his remarks upon the people he bears test... to the simplicity and kindness of the peasantry, ... must have seen a good deal. Unfortunately, for ... unlearned in the language, and chiefly dependent ... entertainment upon ordinary tea-houses, he ha... rashly ventured into generalisations requiring ... that very few foreigners possess. At page ... Japanese men, as a race, are said to be "... muscular, active, and strong, and averaging ... feet five inches[1] in height," a description ... fairly well to the northern fishermen, but cert... tering to the nation in general. Again, in several ... the author follows a common fashion in deplori... evils brought upon the people by European "civili... but makes no allusion to the greater evils ...

[1] Dr. Rein's estimate of the average height of the male ... This is nearly as much below the mark as Capt. St. John's ... above it.

ling, and ignores the fact that any deterioration
n has followed the recent change of circumstances
t the work of "civilisation," but of the vile or foolish
)-followers that may cling to the skirts of even the
est army.

pon the religion of the country he says little more
is to be found in a footnote at page 127; but students
be interested to learn from this that "Shinto is never
esented by any figure, but worshipped as the Unseen
it which pervades everything. Buddha, as is well
vn, is always represented by a male figure; Shinto,
unrepresented, is supposed to be a female."

riticism of the volume is to some extent disarmed by
modesty of its preface, and it no doubt contains much
will amuse the general reader.

n Dr. Rein's "Japan" we have the work not only of a
ent thoroughly versed in his subject, but of a practised
ary architect. The present volume deals with the
graphical conformation, climate, flora, and fauna of
Japanese group, and the history, ethnography, and re-
on of the people, concluding with a useful chapter on
ography. A future volume is to comprise an account
he industries and commerce, and will be welcomed by
who read the part now before us.

The geographical summary is far more complete and ac-
ate than any to which the public has yet had access, and
very page shows the hand of an expert who has brought
ginal knowledge and personal observation to bear upon
task. The climatic peculiarities are for the first time
ve by the author himself in 1876) systematically de-
ibed, and all the more important meteorological details
umulated in the past eighteen years in different parts
the country are reproduced in tabular form.

In the study of the flora and fauna the accumulation of
ts is already too large to allow the author to go far
yond the limits of enumeration. Since Dr. Rein's ac-
unt has been written a new addition has been made to
e fauna in a catalogue of the birds of Japan by Capt.
akiston and Mr. Pryer, and the number of known
ecies raised from about 250 to 325, of which about 180
cur also in China, and about 100 are represented in
reat Britain.

It is to be regretted that space could not have been
pared for a little supplementary information upon some
f those members of the animal kingdom which possess
more popular interest. For example, a few details
especting the dangerous and unpleasantly common
Mamushi (*Trigonocephalus Blomhoffii*) and the wrongly
naligned little *Hibakari* (*Tropidonotus Martensii*) would
ave been useful. The poisonous properties of certain
species of the *Fugu* or genus *Tetrodon* are pointed out,
and the symptoms produced by their use as food described;
but in the reference to the "*hungerige, blutgierige Mos-
quitos*," though feeling tribute is paid to the vexatious side
of their character, the grave charges to which they are
open are omitted, their probable agency, long recognised
by native physicians, in the conveyance of malignant pus-
tule, and the suspicion raised by Dr. Patrick Manson's
investigations in Amoy, that the spread of Elephantiasis
Arabum in the south of Japan is due to the same pest.

The second and less technical part of the book em-
braces subjects upon which the author is less able to speak *in verbâ magistri* than on geographical science. The section, "Das Japanische Volk," opens with an historical abstract of about 200 pages, compiled from Klaproth, Kæmpfer, Siebold, Satow, Aston, and other authorities. The purely mythical stories of the age of the gods are passed over rapidly, and the commencement of the history of the country is fixed at the reign of Jimmu Tenno (660 to 585 B.C.). Dr. Rein is generous enough to acknowledge without question the reputed founder of the imperial lore, of whose existence there is little more proof than of that of the *Uwabami* and *Kamaitachi*, which the Professor does not consider entitled to a place in the fauna. As is mentioned in a footnote, the earliest written records extant originated in the first part of the eighth century of our era, and admitting the possibility that these were compiled from lost manuscripts of older date, they still offer satisfactory internal evidence that the historical being of Japan is at least a thousand years younger than is indicated by the list of the ancient emperors from whom the reigning Mikado traces his descent. The fact will perhaps be sufficiently demonstrated by a citation of the ages attributed to certain of the primitive rulers. The inaugurative myth, Jimmu Tenno, is said to have lived 127 years; Koan, the sixth Mikado, 137 years; Nintoku, the seventeenth Mikado (D. 399 A.D.), 122 years; and it is not until the fifth century A.D. that the viability of the rulers appears to have become permanently limited to a reasonable degree. It is true that the birth and death of Jimmu are solemnised as national festivals, and that writers on such sober topics as the industrial arts do not hesitate to refer for their landmarks to periods long antedating the true historical period; but all allowance must be made for inherited credulity in ancient traditions, which here form part of a state religion and establish the very sanctity of the throne.

We are glad to see that Dr. Rein does not altogether reject the romantic episodes of Japanese history. Awaiting the advent of a native Walpole to bruise the simple faith of his countrymen with historic doubts, it is a grateful relief to the tedium of the long series of wars and court intrigues that form the burden of the rather monotonous recitative of the Oriental Clio, to dwell for a moment on such stories as those of the gentle wife of Yamato Dake, who cast herself into the sea to propitiate the angry gods that threatened the safety of her husband's ship; of Kesa, who sacrificed her life to preserve her wifely fidelity; and many others of the number that have lent inspiration to the pencils of Hokusai, Yosai, and a hundred lesser artists. They are probably no more apocryphal than many of the wearisome details through which the student of history must plod.

The title "Geschichte des Japanischen Volkes" adopted by the author is somewhat misplaced. The history is not that of the people but of their rulers, and it would have been well had the author given the section a better claim to the heading by interspersing the story of battle and murder by some account of the development of laws, literature, painting, the various industrial arts, and such important social ceremonies as those of the *Cha-no-yu*, which lose much of their significance when divorced from the general history of the empire.

The most valuable portion of the sketch to the foreign world is that relating to the pregnant events of the last

twenty years. In the narration of occurrences which have compelled the foreign powers, and especially Great Britain, to join issue with the Japanese Government Dr. Rein displays an absence of partisanship quite novel to those experienced in the discussion of Anglo-Japanese politics. His review of the present position and future prospects of the nation is thoughtfully cautious, and while drawing attention to the recent educational studies and the many wise acts of the present Government, shows a dark reverse to the picture in the financial difficulties now threatening serious obstruction to the path of improvement. The question of the opening of new ports or of the entire country to foreign enterprise and capital is also considered, and the writer points out the deadlock created on the one side by the great disadvantages which the Japanese foresee in admitting to competition an infinitely stronger commercial race, over whose actions they can have no judicial control, and on the other by the inexpediency, from the foreigners' point of view, of a surrender of the treaty rights while the laws and means of administration in Japan are in so unsatisfactory a condition as at the present time.

In an interesting chapter upon the Ethnography of the Japanese the author takes up the vexed problem of the origin of the now dominant race, who displaced the aboriginal Ainos. He believes, from considerations of speech, physiognomy, and traditions that they are a branch of the old Altaic family, which spread from its birthplace in all directions over the continent of Asia, some reaching Japan *vid* Tsushima, Iki, and Oki, others settling at various parts of the mainland to form the Korean, Mandschurian, and other kindred people. In this view he is supported to some extent by the physiognomical identity with the Japanese of the yet pure descendants of the Korean potters brought over as trophies of Taiko's victorious arms at the end of the sixteenth century, and established in the province of Satsuma. Mr. Aston's researches into the comparative philology of the Japanese and Korean languages (*Trans.* Royal Asiatic Society, 1879) tend to a similar conclusion, but leave the question still open.

The analyses of literature, language, and religion are necessarily incomplete, but awaiting the further progress of the labours of the scholars now engaged in the study of these special branches, Dr. Rein's summary of the present knowledge will be of great service.

The author's views as to the character of the Japanese as a race are neither romantically favourable, like those of the great majority of travellers, nor unjustly contemptuous, like the convictions cherished by nearly all settlers. The national defects Dr. Rein considers to be a greed for novelty and a lack of stability and perseverance; but although this verdict would appear to be sanctioned by recent experience, the history of the country really points to nothing less than instability. A blind admiration for antiquity and a persevering if not energetic industry has characterised nearly the whole of their older manufactures and artistic productions, and the many centuries of persistence in the path opened by their forefathers were terminated only by a sudden change of circumstances, and an entirely forced and unsought relationship with the outer world. They are now learning an entirely new exercise of their powers, and some clumsiness at the outset is inevitable, while the very impetuous progression necessarily brings their faults within the scope of a passing glance. They bought experience, and until the world sees can utilise their expensive purchase any premature. They have indeed two serious poverty of material resources, and a writ that isolates them from the European world, serious limitations upon the interchange of order of ideas amongst themselves; but generation can scarcely be blamed for ei there be a charge in the past and present are fairly open it is defect of invention, for knowledge is taken from Europe, so in former they indebted to the Asiatic continent for lite religion, and laws, as well as for a thous traits of civilisation, some of which they ha longer or better than their teachers.

Whatever dispraise is laid upon the peop writers agree to credit them with remarkable Miss Bird, however, who has studied Jap new aspect, gives a different testimony interior, and the few travellers who ha glimpse of the unbeaten tracks of the great co make strange revelations. As the better cla generally knows little or nothing of the secrets metropolitan slums, it is conceivable that living in Tokio may not be aware that *it* contai habitations than those he passes in the publ fares; but were curiosity or chance to lead him some of the little, hardly noticeable, inlets whi there break the line of the street dwellings he startled by the new world revealed to him—on hundreds of thousands of poor of the gre densely packed in filth and disease, *in* dilapid with crumbling walls and roofs that would rende the spell of Asmodeus to the Don Cleofas wh peer at the miseries only half concealed by the of sheds, moated with foul stagnant drains, reeking accumulations of sewage and garbage, from ventilating breezes by the dwellings of fortunate but less numerous citizens. *Had* he extended his pilgrimage to the *Uradana* he w written a new and curious chapter.

As regards bathing, it is certainly a common but with the poorer classes it is far less freque travellers would lead us to believe. It is more so much dictated by any unconquerable intolera dirt as by the combined attractions of warm wat neighbourly gossip. Whatever purification may rived from the common use of a limited *quantity* by several dozens of people, it is doubtful whe may not take as a set-off the odoriferous condition unwashed winter garments which often do unre duty day and night for the whole season, and the scant attention that the native feels impelled to upon his hands and face in the intervals of his the bathing-house. These remarks *however* do not that the working orders in Japan compare unfav in respect to physical purity with their European bre

The maps and illustrations are excellent in their execution. One error must however be indicated woodcut described as a "*Riu-kiu-Insulaner*," wh

.n accurate portrait of the Korean envoy who Japan in 1877.

impossible to do justice to Dr. Rein's important the space at our command. Its construction is tly scientific, and its thoroughness will excite the tion of all who know the difficulty of obtaining, ɔecially of selecting, information upon many of the s so exhaustively treated. The errors are few and ı important, and will probably disappear in the next .. One powerful recommendation is the absence of › from its pages; the author everywhere studiously his own individuality concealed, and in the dis- n of most points he is nearly always contented with ı statement and grouping of the principal facts as ave the inference well within the grasp of the reader's

In conclusion, it is the best of the many publi- ıs upon the subject of Japan that have appeared in ıst ten years, and, unlike most of the number, sup- a real want, and will be received gratefully by all seek for solid, trustworthy information. We trust he completion of the work will soon be issued.

OUR BOOK SHELF

les géométriques et cinématiques. Note sur quelques uestions de Géométrie et de Cinématique, et Réponse x Réclamations de M. l'Abbé Aoust. Par E. J. Habich. pp. (Lima, 1880.)

L'ABBÉ AOUST, author of the "Analyse infinitésimale Courbes planes," and our author put forward con- ng claims as to priority of discovery.

he polemics have fired off their powder in *Les Mondes* ıe iv., 1880, Aoust: tome l., 1879, Habich; see also *Comptes rendus*, lxxxv., 1877, and lxxxix., 1879), and object of the present pamphlet is "de réduire à leur e valeur les assertions" of the Abbé. The matters in ɔute can be inferred from the three divisions of the ɜent work:—

1. Développoïdes—considérations historiques, étude enveloppes des droites par la considération du centre :antané de rotation, développoïdes des divers ordres levellopoïdes inverses.

'2. Coordonnées tangentielles-polaires.

'3. Mouvement géométrique d'une figure plane dans ı plan—considérations générales, mouvement géo- :trique déterminé par deux systèmes d'enveloppées et :nveloppes, mouvement d'une droit sur un plan."

We have, of course, but one side of the quarrel pre- nted to us, but leaving polemics on one side there is a eat deal of interesting matter put before us. Time will, ı doubt, settle the question of priority.

Synopsis of Elementary Results in Pure and Applied Mathematics. By G. S. Carr, B.A. Vol. i. part viii. (C. F. Hodgson and Son, 1880.)

VE recently noticed with approval the volume con- ıining the first seven parts. This eighth part carries on ıe articles from 1400 to 1868, and is concerned with the ifferential calculus. It contains an abstract of the usual rocesses, and besides gives a succinct account of the heory of operations, and an analysis of matters which .re treated of in the higher algebra, as Jacobians and ıuantics, and closes with maxima and minima, the ɜeometrical applications being reserved for the parts on Co-ordinate Geometry.

These fifty-six pages are very correctly printed, at least we have not detected more than three or four trivial typographical errors.

This part maintains the handy character for reference of its forerunners.

The Practical Fisherman. By T. H. Keene. (London: *The Bazaar* Office.)

THIS book deals with the natural history, the legendary lore, and the capture of British freshwater fish, together with the art of tackle-making. The author has bestowed great care on his work, and seems to have studied every book written or published on the charming subject from Oppian to the present time. Mr. Keene is besides an enthusiastic fisherman, and has thus produced a treatise of great interest to the practical angler. We may add that this work is almost the only one on angling which treats of the natural as well as the traditional history of fishes.

LETTERS TO THE EDITOR

[*The Editor does not hold himself responsible for opinions expressed by his correspondents. Neither can he undertake to return, or to correspond with the writers of, rejected manuscripts. No notice is taken of anonymous communications.*

[*The Editor urgently requests correspondents to keep their letters as short as possible. The pressure on his space is so great that it is impossible otherwise to ensure the appearance even of communications containing interesting and novel facts.*]

The Movements of Leaves

FRITZ MUELLER has sent me some additional observations on the movements of leaves, when exposed to a bright light. Such movements seem to be as well developed and as diversified under the bright sun of Brazil, as are the well-known sleep or nyctitropic movements of plants in all parts of the world. This result has interested me much, as I long doubted whether paraheliotropic movements were common enough to deserve to be separately designated. It is a remarkable fact that in certain species these movements closely resemble the sleep movements of allied forms. Thus the leaflets of one of the Brazilian Cassiæ assume when exposed to sunshine nearly the same position as those of the not distantly allied Hæmatoxylon when asleep, as shown in Fig. 153 of "The Movements of Plants." Whereas the leaflets of this Cassia sleep by moving down and rotating on their axes, in the same peculiar manner as in so many other species of the genus. Again, with an unnamed species of Phyllanthus, the leaves move forwards at night, so that their midribs then stand nearly parallel to the horizontal branches from which they spring; but when they are exposed to bright sunshine they rise up vertically, and their upper surfaces come into contact, as they are opposite. Now this is the position which the leaves of another species, namely *Phyllanthus compressus*, assume when they go to sleep at night. Fritz Müller states that the paraheliotropic movements of the leaves of a Mucuna, a large twining Papilionaceous plant, are strange and inexplicable; the leaflets sleep by hanging vertically down, but under bright sunshine the petiole rises vertically up, and the terminal leaflet rotates by means of its pulvinus through an angle of 180°, and thus its upper surface comes to stand on the same side with the lower surfaces of the lateral leaflets. Fritz Müller adds, "I do not understand the meaning of this rotation of the terminal leaflet, as even without such a movement it would be apparently equally well protected against the rays of the sun. The leaflets, also, on many of the leaves on the same plant assume various other strange positions." With one species of Desmodium, presently to be mentioned as sleeping in a remarkable manner, the leaflets rise up vertically when exposed to bright sunshine, and the upper surfaces of the lateral leaflets are thus brought into contact. The leaves of *Bauhinia grandiflora* go to sleep at an unusually early hour in the evening, and in the manner described at p. 373 of "The Movements of Plants," namely, by the two halves of the same leaf rising up and coming into close contact: now the leaves of *Bauhinia Brasiliensis* do not sleep, as far as Fritz Müller has seen, but they are very sensitive to a bright light, and when thus exposed the two halves rise up and stand at 45° or upwards above the horizon.

Fritz Müller has sent me some cases, in addition to those given in my former letter of March 3, of the leaves of closely-allied plants which assume a vertical position at night by widely different movements; and these cases are of interest as indicating that sleep-movements have been acquired for a special purpose. We have just seen that of two species of Bauhinia the leaves of one sleep conspicuously, while those of a second species appa-

rently do not sleep at all. The leaves of *Euphorbia jacquiniæflora* depend vertically at night, whereas those of a dwarfish Brazilian species rise vertically up at night. The leaves of this Euphorbia stand opposite one another—a position which is rather rare in the genus; and the rising movement may be of service to the plant, as the upper surfaces of the opposite leaves mutually protect one another by coming into contact. In the genus Sida the leaves of two species rise, while those of a third Brazilian species sink vertically down at night. Two species of Desmodium are common plants near Fritz Muller's house: in one the leaflets move simply downwards at night; but in the other not only do the three leaflets move vertically down, while the main petiole rises vertically up, as is likewise the case with *D. gyrans*, but in addition the lateral leaflets rotate so as to stand parallel with the terminal leaflet, behind which they are more or less completely hidden. This, as far as I have seen, is a new kind of nyctitropic movement; but it leads to a result common to several species, namely, that of packing the three leaflets closely together and placing them in a vertical position.

Down, Beckenham, Kent, April 14 CHARLES DARWIN

Spectrum of the Star Ll. 13412

THE spectrum of the star Ll. 13412 appears to be in some respects unique. It consists mainly of three bright lines having wave-lengths of 545, 486, and 466 millionths of a millimetre. Four other stars have hitherto been found whose spectra are of this character. Three of them are in Cygnus, and have lines whose wave-lengths are 580, 568, 536, and 467. The fourth star, Oeltzen 17681, has lines at about 582 and 470 (NATURE, vol. xxii. p. 483). The line or band at 467 appears to be common to all, and that at 580 to the last four. The line at 486 in Ll. 13412 coincides with the F line of hydrogen, but is not visible in the other stars. The line at 545 is also absent in them. This star therefore appears to resemble the others in kind, but not in the material of which it is composed. It is also much brighter than the others, so that it is not a difficult object with a small telescope. Its position for 1880 is in R.A. 6h. 49·3m. and Dec. −23° 47′. It is easily found as a seventh magnitude star about 15′ north of *o Canis Majoris*.

Cambridge, U.S., April 14 EDWARD C. PICKERING

The Indian Winter Rains

IN NATURE, vol. xxiii. p. 400, Mr. F. Chambers very properly points out that the winter rains of Northern India, though usually heaviest in years when the *mean* pressure is above the average, are yet coincident with short periods of low rather than of high pressure. The way in which Mr. Chambers accounts for the low pressure seems, however, rather far-fetched. It is true that on one or two of the American weather charts storm tracks are shown extending from the Mediterranean to Northern India or the Bay of Bengal, but these paths are drawn with dotted lines indicating that they are doubtful, and, considering the absence of meteorological stations in the greater part of the area between the Mediterranean and India, and the nature of the intervening country—especially Afghanistan with its high mountains—I should say the evidence up in the strength of which the American chartographer laid down these storm tracks, was of the slightest possible description. The winter rains are however accompanied by a cyclonic movement of the air over Northern India, and I wish to point out that, whether the cyclonic disturbance be a European or Trans-atlantic visitor, as Mr. Chambers supposes, or a native of the Indian region, generated by the rainfall, as Mr. Eliot has taught in his report for 1877, the "old notion" of the connection of the rains with the upper anti-monsoon current is by no means exploded. The progress of the disturbance and of the rainfall is usually from north-west to south-east, and the rainfall is heaviest, as a rule, on the eastern side of the disturbance. The winds which bring the rainfall therefore come from some southerly quarter, and as northerly winds generally continue blowing in the extreme south of India at the time when these disturbances occur in the north, the southerly rainy winds must be derived from an upper current which descends in the anti-cyclone or region of high pressure in the centre and south of India, or in the zone between the south of India and the equator. Mr. Blanford's modification of his former views regarding the origin of these rains appears from his remarks and the accompanying charts in the Meteorological Report for 1878 to be merely that the indraught towards the region of precipitation is not confined to N occasionally, though rarely, felt as far sou

In a letter of mine that appeared in NA week (p. 409), there was a mistaken inf ford's investigation regarding the "Barome India and West Siberia that I beg your The mean pressure at sea-level in the Ind Siberian regions appears from Mr. Bucha the same both on the average of the year a Also no wind blows directly from the one re cannot therefore infer anything regarding th from Mr. Blanford's results, but we may The proper inferences of this kind from the r Blanford and Mr. Archibald appear to be of temperature in the 11-year period is grea surrounding countries; (2) Siberia is col neighbouring countries, at times of maxima relation is most marked in winter; and (the Pacific (Nertchinsk, Pekin, Zi-ka-wei), Indo-Malayan stations, especially those nea Atlantic (London) oceans, where presumab perature is less than in the heart of the co of the barometer in the 11-year period is opp in Siberia.

Allahabad, March 29

Palæolithic Man

IT is desirable that further search should ments made by man in the deposits of this be older than the well-known and accepte river-gravels.

In the gravels belonging to the Thames, i palæolithic implements are of not infreque my own collection I have more than 120 e exceptions found by myself—and I know hundred specimens found chiefly by Londo availed themselves of hints given by me.

My object now is to direct attention to the ments are not only found in and near Londo middle terraces of gravel some 25 to 70 feet a datum, but at far greater heights. Some of London may, and others no doubt do, belong to tributaries, but they all (in different degrees) more remote time than the period when the lo Thames and its tributaries were formed. So ments now found in the lower gravels are from more ancient deposits. For instance, I white in colour and highly porcellaneous;—the been brought about by the decomposition of ancient loam or clay, and not from the gravel plement was found; this is proved by seve highly-polished accidental fractures at the ed colour from the general white surface: these e are more recent than the white facets, and da deposition of the implement in the lower te abraded flakings belong to a highly remote time records the finding of an implement in the T Highbury, at 102 feet, whilst I have found Highbury), at an elevation of 144 feet. Last an implement on the eminence at the north of, Ealing Dean, at a height of 164 feet. This is than the implementiferous beds of Ealing Dea General Pitt Rivers, and between 80 and 100 fee instance 104 feet higher) than the implement-be Acton described by the same gentleman. The gr feet elevation forms an isolated patch on the ex hill. I watched the excavations here (which we road-making, with great care, and with the imp several flakes. These heights agree well with the of the implementiferous gravels found capping t South of England, also with the Erith position a land Heath, where Mr. F. C. J. Spurrell found a an elevation of 175 feet.

Most geologists know the high gravels overlook Ware, and Amwell; their altitude is from 130 to above the ordnance datum. Gravel from the two places is brought to London for ballast in thous A year or two ago great quantities of gravel f were brought to Finsbury Park by the Great N way, and in the gravel thrown down near Finsb

up a good sub-triangular wedge-shaped implement. search produced a second implement, a good trimmed nd a few simple flakes. The worked flints in the Hert- avel are however so rare that the search for them is the opeless task conceivable. There is not more than one 500 tons, not one implement in 5000 tons of gravel. avel from Ware is also brought to the east of London for and I happened last year to mention the fact of my dis- s to Mr. J. E. Greenhill, the Principal of a school near ey Downs. Mr. Greenhill at once not only searched him- it set his pupils to look over the Ware gravel, then laid in large quantities near Clapton, with the result that a roken ovate implement was found and several flakes. I also a large and heavy "slice" flake with numerous facets on its l side in the same gravel. Mr. Greenhill's success caused me carefully over a similar lot of gravel from Ware, laid down ictoria Park. In this I found a sub-triangular implement iree flakes. I have also found a large greatly abraded n the Amwell gravel at Amwell. Elsewhere in east and east London I have looked over thousands of tons of Hert- nd Ware gravel without decisive result. A week or two owever, as my younger son was returning home through ury Park, he picked up a good scraper-like implement in the (presumably from Hertford), just thrown on to the road the park. On hearing of the discovery I at once went to ury Park and looked carefully over all the recently thrown material, but with no further result. I have visited the nt pits at Hertford, Ware, and Amwell several times, but is never enough gravel exposed (considering the extreme arative rarity of the implements and flakes) to give one a e of finding an implement. I have found in the pits l simple flakes, with the cone of percussion, and that is At what depth the implements occur in the gravel I do not , but that implements really do come out of the high ls overlooking Hertford and Ware I think there can o doubt. Reference was made by me to these imple- s at the Anthropological Institute three years ago, when r three specimens were exhibited by me.

WORTHINGTON G. SMITH

5, Grosvenor Road, Highbury, N.

Sound of the Aurora

ITH every respect for the ability and acuteness of the late ohn Franklin and his companions, I do not think it con- ve, as Mr. Rouse seems to do, that because they heard no ds "with the aurora borealis" (NATURE, vol. xxiii. p. 556), ounds are produced by it.

ll Indians, both on the shores of Hudson's Bay and near Lake, and the Eskimos on many parts of the coast, assert tively that the bright, varying, flickering,[1] and rapidly- ing auroræ do produce sound. The senses of hearing and lling in the Indian and Eskimo are far more acute than in civilised man; and both sounds and smells which to the er are not perceptible are perfectly so to the more sensitive itory and olfactory organs of the savage.

he theory that "the attractive force of the aurora is increased ain a certain limit as its rays proceed southward" is scarcely ne out by my experience.

When wintering at Fort Hope, Repulse Bay, in 1846-47 and 3-54, lat. 66° 32′ N., the result of my observations was, as as I can discover, exactly similar to that of Parry in 1824-25 Port Bowen in lat. 73° 15′ N., 400 miles further north and fifty es west of Fort Hope: at both no effect was produced on the gnetic needle.

At Repulse Bay, and it may have been the same at Port wen, the character of the aurora was perfectly different from t generally seen at Great Bear Lake, which acted so power- ly on the needle, the former being almost always of a uniform le yellow or straw colour, with little rapid motion, whereas the ter was generally flashing, flickering, rapidly moving, and of rerse hues.

One peculiarity of the auroræ observed at Repulse Bay may worthy of notice: they were chiefly seen to the magnetic uth—that is south 62° east true—usually in the form of an arch ther low down—and I may add that in that direction at a stance of thirty or forty miles from our head-quarters a large tent of sea is kept open all winter by strong currents. The Eskimos of Repulse Bay do not say much about the aurora beyond expressing a belief that it is the spirits of their dead visiting each other in the heavens.

It is probably a matter of little or no importance in a question of this kind, but Mr. Rouse has given the latitudes of the southern shores of Great Bear Lake from 90 to 200 miles too far north.

Fort Franklin, where Franklin made his chief observations, is situated in latitude 65° 12′ N. at the extreme south-west of Great Bear Lake, whereas Fort Confidence, where Sir J. Richardson and I made ours with like results, is at the extreme north-east of the lake in lat. 66° 54′ N., the stations being 150 miles distant from each other.

It is perhaps not being too sanguine to hope that in this period of marvellous discoveries, some instrument may be—if not already—invented, with the aid of which one may be able to decide the question satisfactorily as to whether the aurora in any form does or does not produce sound.

JOHN RAE

4, Addison Gardens, April 16

[1] I borrow this most appropriate term from Prof. Stokes, F.R.S., &c., of Cambridge.

THE SCIENTIFIC PRINCIPLES INVOLVED IN ELECTRIC LIGHTING[1]

II.

Lectures III. and IV.

ALL machines for the conversion of mechanical work into electricity are founded on Faraday's great discovery of the induced current derived from the relative motion of a magnet and a coil of wire. They are either continuous-current or alternate-current machines. From the continuous-current machines of Pixii in 1832 and Saxton and Clarke in 1835 and 1836, we pass to Wheatstone's introduction in 1845 of electromagnets in place of permanent magnets to produce the magnetic field. In 1854 Werner Siemens and Halske introduced the Siemens armature, in which the coil is wound longitudinally in a groove. In 1854 Hjorth patented an improved magneto-electric battery, in which the currents induced in the revolving armature pass round the electromagnets and produce the magnetic field. This is the principle of the dynamo-electric machine, which was afterwards rediscovered by Siemens and by Wheatstone simultaneously in 1867, when on the same evening their two papers were presented to the Royal Society.

Then followed the Gramme armature, in which coils of wire are wound in sections all in the same direction round a ring; each section, when a current is flowing through it, may be regarded as an electro-magnet, and its principle of action is clear at once from the principles of Arago and from Lenz's laws for induced currents.

In dynamo-electric machines the external work in the electric arc is proportional to the square of the current, and is also proportional to the number of turns of the armature per minute.

Any disturbance in the resistance of the arc reacts on the electro-magnet, altering the strength of the magnetic field, thereby increasing the disturbance; this is the great disadvantage of dynamo-electric machines as compared with magneto-electric machines, where the magnet is either a permanent magnet or is excited by means of a separate current. Wilde, in 1863, employed a separate continuous current machine to give a permanent magnetic field, and made the armature of the second machine to revolve in this magnetic field. In alternate-current machines there is no commutator for making the current continuous, but the currents from the coil are collected and sent through the external resistance in opposite directions for every half-turn of the armature. The Alliance magneto-electric machine was the first of these, which was converted by Holmes into a continuous-current machine, and was by him first used in 1858 to produce the electric light for lighthouse illumination. He afterwards again converted his machine into an alternate-

[1] By Prof. W. Grylls Adams, F.R.S. Continued from p. 582.

current machine by removing the commutator, thereby producing a very effective machine.

All theoretical determinations of the efficiency of machines are complicated by the retardation of magnetisation of the magnets, which necessitates a change of position of the commutator or brushes in the direction of the rotation of the armature. The practical determinations of efficiency which have been made show that from 86 to 88 per cent. of the energy communicated to a dynamo-machine is converted into electrical energy, and that from 44 to about 50 per cent. of the total work may be converted into useful work in the external circuit. Among the more recent continuous current machines are the Brush and the Bürgin machines, which promise to give good results.

At intervals during the lecture the room was lighted by various electric lamps, the peculiarities of each of which were explained. The Brockie lamp, lent by the British Electric Light Company, and served by one of their Gramme machines; the Siemens pendulum-lamp lent by Dr. Siemens, and the Crompton lamp lent by Mr. Crompton, were each tried in turn, and attention was drawn to the Siemens' differential lamp, the Brush lamp, and other lamps and electric candles which were also exhibited.

The subject of the fourth Cantor lecture was the subdivision of the electric current and lighting by incandescence. Prof. Adams showed that objections raised to the electric light were similar to those which had been urged with regard to gas when it was first introduced. He then compared the energy of Grove's cells with the energy derived from a small Gramme machine, and showed how impracticable it was to attempt to do by means of batteries the work which can be done by such machines. He then explained how the same amount of energy might be spent in two classes of machines, those of low internal resistance and low electromotive force which send a strong current through small external resistance, or tension-machines. quantity machines, and those of high internal resistance and high electromotive force sending a smaller current through large external resistance, or tension-machines. For very high resistances the discharge of an induction-coil is taken, the action of which was compared to the action of the hydraulic ram. Prof. Adams proceeded to describe the Werdermann and the Joel lamps, and explained the kind of machine specially suited for such lamps, and regretted that it would not be possible to show them to the best advantage, or to give them a fair trial, because the machine actually in use at the speed at which it was running was not adapted for them. An electromotive force of 130 volts will send 50 webers through 10 lamps in series, and give an illumination of 320 candles in each lamp for an expenditure about 10 h.p. Taking Mr. A. Siemens' facts as to the cost, it appears that the electric light from the Joel lamp would be as cheap as gas at the rate of 2s. per 1000 cubic feet. The laws of the subdivision of the electric current were discussed, and their application to the system of incandescent lighting adopted by Swan, and by Lane-Fox and Edison was clearly shown. With the Bürgin machine, then in use, giving at 1620 revolutions a minute an electromotive force of 160 volts, and a current of 24 webers through an external resistance of about 7 ohms, it was shown that 24 rows of two Swan lamps in series or 48 lamps could be lit up: each lamp being of 80 ohms resistance, and giving a 48 candle-power light. If the resistance of each lamp be 40 instead of 80 ohms, then double the number of lamps might be taken in series, giving about 100 lamps from the machine.

With the Brush machine at least 140 lamps might be lit up in 10 parallel rows of 14 lamps in series. The early attempts of King, and Staite, and Konn to light by incandescence were then explained, and experiments made to illustrate the phenomena seen in high vacua, such as are necessary to enable Mr. Fox to preserve their carbons from dered incandescent by means of the

The room was well lighted by lamps, each giving a pleasant and s 40 or 50 candle-power, the lamps be rows of two in series. Two table-la the lecture-table, which could be pu made to glow at pleasure, and the lifted off their stands and others put i out disturbing other lights which wer tiple arc and worked from the same dy

THE FRENCH ASSOCIATIO ADVANCEMENT OF SCIENCE

II.

ON Friday afternoon various papers were read to a general audienc the theatre. They related to the geolo demography of Algeria, but the most was by our Consul-General, Col. Play the country of the Kroumirs—interes cause the aggressions of this tribe have complications in Tunis, which will pro but also because Col. Playfair and Lord only Europeans who have visited the inhabit the district near Le Calle, th northern portion of the boundary bet Tunis, and they only nominally acknowle of the Bey of Tunis.

On Friday evening a discourse was theatre "On Paludisme from a Surgical It was of such a very technical char members of the Association did not att Congress is to a great extent medical. W and Botanical Sections are positively want of papers, and will probably come ending on Monday, the papers waiting t the Medical Section fill two pages of gramme.

More activity was manifested in the s the second day of the Congress; the pape sections were more numerous and the a The physical section is the most neglecte after the proper time of commencement th not made his appearance, and at length the only honorary vice-president, was re the chair. Of the four papers read Englishmen, and on the first day of mee alone was read by a Dutchman. Pure ph is unfortunately quite unrepresented at In the Chemical Section M. Baunhauer "On the Crystallisation of the Diamon Foreland "On a New Apparatus for There were several good papers on mete jects. Only three papers were read in t Section, the most important of these by "On the Unification of Geological Nomen Anthropological Section was well attende of considerable local interest were read. of Geography and Political Economy mainly Sahara—on the one hand its physical geogr the other its colonisation.

In the Agricultural Exhibition one of teresting machines is the solar engine, t which is placed in the axis of a mirror 14 feet and formed of three portions of hollow trun so as to get a close approximation to the paral the sun shines a pressure of from three to spheres is produced in the boiler, and a fo horse power is produced through the interve

Continued from p. 583.

ine. The mirror is of silvered copper; ened and is surrounded by a glass ourse permits the passage of the sun's obstructs its escape after absorption. osts 4000 francs, and it could be used or at least 200 days in the year.

G. F. RODWELL

THE HERRING[1]

en years since my attention was first ted to the natural history of the her- nany important economical and legal ed with the herring fisheries. As a cessive Royal Commissions, it fell to in inquiries held at every important he United Kingdom between the years l to hear all that practical fishermen e matter; while I had free access to of the Fishery Boards. Nor did I neg- ties as presented themselves of study- and of determining the scientific value ch, in the language of fishermen, the of the herring are distinguished.

of the body of evidence thus collected eview, led to the satisfactory clearing nd of some of the obscurities which, at ed the natural history of the fish. But nained, the solution of which was not stigations which, after all, were only ourse of a large inquiry, embracing a topics beside herrings and herring only within the last few years that the man West Baltic Fishery Commission large additions to the state of our s, that the history of the herring is asurable distance of completeness. vast importance of the herring fisheries unties, it occurred to me when the ational Fishery Exhibition did me the to address you, that nothing could be erest my audience than a summary is now really known about a fish herman's point of view, is probably

I may lay myself open to the applica- about carrying coals to Newcastle, observations with a description of the tinctive characters of a fish which is majority of my hearers. And perhaps should at once express my belief that is little likely to mistake a herring for I am. Nay, I will go further. I have that any herring-merchant, in a large who may be here, knows these fish so I do, that he is able to discriminate a from a Scotch herring and both from ; a feat which I could not undertake to n it is possible that I may know some s not. He is very unlike other fishermen s with whom I have met, if he has any otions of the way of life of the fish; or nything about those singularities of its h perples biologists; or if he can say ex- y he knows that a herring is not a sprat, ard. And all kinds of real knowledge he facts of nature do so bear upon one out in strange ways practically helpful, pour out my scientific budget, in the ing more may come of it than the grati- gent curiosity.

its to exemplify the meaning of the word

[1] By Prof. Huxley at the National Fishery Exhibition.

"fish" he cannot choose a better animal than a herring. The body, tapering to each end, is covered with thin, flexible scales, which are very easily rubbed off. The taper head, with its underhung jaw, is smooth and scaleless on the top; the large eye is partly covered by two folds of transparent skin, like eyelids—only immovable and with the slit between them vertical instead of horizontal; the cleft behind the gill cover is very wide, and, when the cover is raised, the large red gills which lie beneath it are freely exposed. The rounded back bears the single moderately long dorsal fin about its middle. The tail fin is deeply cleft, and on careful inspection small scales are seen to be continued from the body, on to both its upper and its lower lobes, but there is no longitudinal scaly fold on either of these. The belly comes to an edge, covered by a series of sharply-keeled bony shields between the throat and the vent; and behind the last is the anal fin, which is of the same length as the dorsal fin. There is a pair of fore-limbs, or pectoral fins, just behind the head; and a pair of hind-limbs, or ventral fins, are situated beneath the dorsal fin, a little behind a vertical line drawn from its front edge, and a long way in front of the vent. These fins have bony supports or rays, all of which are soft and jointed.

Like most fishes, the herring is propelled chiefly by the sculling action of the tail-fin, the rest serving chiefly to preserve the balance of the body, and to keep it from turning over, as it would do if left to itself, the back being the heaviest part of the fish.

The mouth of the herring is not very large, the gape extending back only to beneath the middle of the eye, and the teeth on the upper and lower jaws are so small as to be hardly visible. Moreover, when a live herring opens its mouth, or when the lower jaw of a dead herring is depressed artificially, the upper jaw, instead of remaining fixed and stationary, travels downwards and forwards in such a manner as to guard the sides of the gape. This movement is the result of a curious mechanical arrangement by which the lower jaw pulls upon the upper, and I suspect that it is useful in guarding the sides of the gape when the fish gulps the small living prey upon which it feeds.

The only conspicuous teeth, and they are very small, are disposed in an elongated patch upon the tongue, and in another such patch, opposite to these, on the fore part of the roof of the mouth. The latter are attached to a bone called the vomer, and are hence termed vomerine teeth. But, if the mouth of a herring is opened widely, there will be seen, on each side, a great number of fine, long, bristle-like processes, the pointed ends of which project forwards. These are what are termed the gill rakers, inasmuch as they are fixed, like the teeth of a rake, to the inner sides of those arches of bone on the outer sides of which the gills are fixed. The sides of the throat of a herring, in fact, are as it were cut by four deep and wide clefts which are separated by these gill arches, and the water which the fish constantly gulps in by the mouth flows through these clefts, over the gills and out beneath the gill covers, aerating the blood, and thus effecting respiration, as it goes. But since it would be highly inconvenient, and indeed injurious, were the food to slip out in the same way, these gill rakers play the part of a fine sieve, which lets the water strain off, while it keeps the food in. The gill rakers of the front arches are much longer than those of the hinder arches, and as each is stiffened by a thread of bone developed in its interior, while, at the same time, its sides are beset with fine sharp teeth, like thorns on a brier, I suspect that they play some part in crushing the life out of the small animals on which the herrings prey.

Between these arches there is, in the middle line, an opening which leads into the gullet. This passes back into a curious conical sac which is commonly termed the stomach, but which has more the character of a crop.

Coming off from the under side of the sac and communicating with it by a narrow opening, there is an elongated tubular organ, the walls of which are so thick and muscular that it might almost be compared to a gizzard. It is directed forwards, and opens by a narrow prominent aperture into the intestine, which runs straight back to the vent. Attached to the commencement of the intestine, there is a score or more of larger and shorter tubular organs which are called the pyloric cæca. These open into the intestine, and their apertures may be seen on one side of it, occupying an oval space, in the middle of which they are arranged three in a row.

The chief food of the herring consists of minute Crustacea, some of them allied to the shrimps and prawns, but the majority belonging to the same division as the common *Cyclops* of our fresh waters. These tenant many parts of the ocean in such prodigious masses that the water is discoloured by them for miles together, and every sweep of a fine net brings up its tens of thousands.

Everybody must have noticed the silvery air-bladder of the herring, which lies immediately under the backbone, and stretches from close to the head to very near the vent, being wide in the middle and tapering off to each end. In its natural state, it is distended with air; and, if it is pricked, the elastic wall shrinks and drives the air out, as if it were an indiarubber ball. When the connexions of this air-bladder are fully explored it turns out to be one of the most curious parts of the organisation of the whole animal.

In the first place, the pointed end of the sac or crop into which the gullet is continued runs back into a very slender duct which turns upwards and eventually opens into the middle of the air-bladder. The canal of this duct is so very small and irregularly twisted, that, even if the air-bladder is squeezed, the air does not escape into the sac. But, if air is forced into the sac by means of a blowpipe, the air passes without much difficulty the other way, and the air-bladder becomes fully distended. When the pressure is removed, however, the air-bladder diminishes in size to a certain extent, showing that the air escapes somewhere. And if the blowing up of the air-bladder is performed while the fish is under water, a fine stream of air-bubbles may be seen to escape close to the vent. Careful anatomical investigation, in fact, shows that the air-bladder does not really end at the point where its silvery coat finishes, but that a delicate tube is continued thence to the left side of the vent, and there ends by an opening of its own.

Now the air-bladder of all fishes is, to begin with, an outgrowth from the front part of the alimentary canal, and there are a great many fishes in which, as in the herring, it remains throughout life in permanent communication with the gullet. But it is rare to find the duct so far back as in the herring; and, at present, I am not aware that the air-bladder opens externally in any fishes except the herring and a few of its allies.

There is a general agreement among fishermen that herrings sometimes make a squeaking noise when they are freshly taken out of the water. I have never heard this sound myself, but there is so much concurrent testimony to the fact that I do not doubt it; and it occurs to me that it may be produced when the herrings are quickly brought up from some depth by means of this arrangement. For under these circumstances the air, which the air-bladder contains, expands to such a degree, on being relieved from the pressure of the water, that deep-sea fishes with a closed air-bladder which are brought to the surface rapidly are sometimes fairly turned inside out by the immense distension, or even bursting, of the air-bladder. If the same thing should happen to the herring the like misfortune would not befall it, for the air would be forced out of the opening in question, and might readily enough produce the squeak which is reported. The common Loach[1] is said to produce a pip air which this fish takes into it purposes.

At the opposite end of the ai more curious arrangement. T bladder ends in front just behin bladder itself does not termin canals, each of which is not m of an inch in diameter, thoug relatively thick wall of cartilage, side, from the air-bladder to the canals enter the walls of the sk into two branches. Finally, each a bag which lies in a spheroidal c size and form; and, in consequen contain, these bags may be seen through the side walls of the sku a peculiar structure where it these two bags, which constitute air-bladder on each side, are in organ of hearing. Indeed, a pro jects into the front chamber on ea by only a very delicate partition f the air-bladder. Any vibrations or any change in the pressure of thus tell upon the hearing apparat

There is no doubt about the ex tures which, together with the poste bladder, were most accurately des years ago, by the eminent anato afraid we are not much wiser re than we were when they were first in general, there can be little doub the air-bladder is to diminish the fish and, by rendering its body of as so much water, to render the easier. In those fishes in which the cation between the air-bladder and closed, the air is no doubt secreted by its vessels, which are often ver herring, the vessels of the air-bladde it seems probable that the air is s into the air-bladder just as the loa drives it into its intestine. And, suggested, it may be that the nar which leads from the air-bladder to of safety-valve allowing the air to es rapidly ascending or descending, a the water upon the contained air.

This hypothesis may be put forwar probability, but I really find it diffic thing with respect to the physiologi connection between the air-bladder a theless such an elaborate apparatus physiological importance; and, this co ened by the well-known fact that there fishes in which the air-bladder and th nected in one way or another. In example, the front end of the air-bladde series of little bones with the organ of as it were, prolonged backwards to me the hinder end of the skull. But her which is very large, may act as a re the herring, the extreme narrowness of t connect the air-bladder with the ear re suppose that the organ can have any su

In addition to the singular connectio the exterior by the roundabout way o there are membranous spaces in the w by which vibrations can more directly re ear. And there is no doubt that the fish

[1] See Müller, "Ueber Fische welche Töne von sic *Physiologie*, 1837, p. 267. The herring is not mentio vocal fishes.

a vibrations. In a dark night, when the water is horescent or, as the fishermen say, there is plenty erefire," it is a curious spectacle to watch the effect irply tapping the side of the boat as it passes over il. The herrings scatter in all directions, leaving s of light behind them, like shooting stars.

herring, like other fishes, breathes by means of the the essential part of which consists of the delicate, vascular filaments, which are set in a double row outer faces of each of the gill arches. The venous which returns from all parts of the body to be ted in the heart, is pumped thence into the gills, there exchanges its excess of carbonic acid gas e gaseous oxygen which is dissolved in sea-water. freedom of passage of the water, and the great size lelicacy of the gills, facilitate respiration when the s in its native element; but the same peculiarities itting of the rapid drying and coherence of the gills, hus bringing on speedy suffocation, render its tenure e, after removal from the water, as short as that of any

It may be observed, in passing, that the wide clefts id the gill-covers of the herring have some practical rtance, as the fish, thrusting its head through the ies of the drift-net, is caught behind them and cannot cate itself. In the herring, the upper end of the last left is not developed into a sac or pouch, such as we find in some of its near neighbours.

ne only other organs of the herring, which need be tioned at present, are the milt and roe, found in the and female herring respectively.

hese are elongated organs attached beneath the air- der, which lie, one on each side of the abdominal ty, and open behind the vent by an aperture common ne two. The spermatic fluid of the male is developed ie milt and the eggs of the female in the roe. These s, when fully formed, measure from one-sixteenth to twenty-fifth of an inch in diameter; and, as, in the female, the two roes or ovaries stretch from one end he abdominal cavity to the other, occupying all the ce left by the other organs, and distending the cavity, number of eggs which they contain must be very st. Probably 10,000 is an under-estimate of the nber of ripe eggs shed in spawning by a moderate-sized ale herring. But I think it is safer than the 30,000 of ie estimates, which appear to me to be made in forget- iess of the very simple anatomical considerations that roe consists of an extensive vascular framework as l as of eggs; and, moreover, that a vast number of eggs which it contains remain immature, and are not d at the time of spawning.

In this brief account of the structure of the herring I ve touched only on those points which are peculiarly eresting, or which bear upon what I shall have to say and by. An exhaustive study of the fish from this int of view alone would require a whole course of tures to itself.

The herring is a member of a very large group of fishes read over all parts of the world, and termed that of the *upeida*, after *Clupea*, the generic name of the herring elf. Our herring, the *Clupea harengus*, inhabits the White a and perhaps some parts of the Arctic Ocean, the tem- rate and colder parts of the Atlantic, the North Sea, d the Baltic, and there is a very similar, if not identi- l, species in the North Pacific. But it is not known to cur in the seas of southern Europe, nor in any part of e intertropical ocean, nor in the southern hemisphere.

There are four British fishes which so closely resemble errings, externally and internally, that, though prac- cal men may not be in any danger of confounding iem, scientific zoologists have not always succeeded in efining their differences. These are the Sprat, the Allice nd Twaite Shads, and the Pilchard.

The sprat comes nearest; indeed young herrings and prats have often been confounded together, and doubts have been thrown on the specific distinctness of the two. Yet if a sprat and a young herring of the same size are placed side by side, even their external differences leave no doubt of their distinctness. The sprat's lower jaw is shorter; the shields in the middle of the belly have a sharper keel, whence the ventral edge is more like a saw; and the ventral fin lies vertically under the front edge of the dorsal fin, or even in front of it; while in the herring, though the position of the ventral fin varies a little, it lies more or less behind the front margin of the dorsal fin. The anal fin is of the same length as the dorsal, in the herring, longer than the dorsal in the sprat. But the best marks of distinction are the absence of vomerine teeth in the sprat, and the smaller number of pyloric cæca, which do not exceed nine, their openings being disposed in a single longitudinal series.

Shads and pilchards have a common character by which they are very easily distinguished from both sprat and herring. There is a horizontal fold of scaly skin on each side of the tail above and below the middle line. Moreover they have no teeth in the inside of the mouth, and their pyloric cæca are very numerous—a hundred or more—their openings being disposed five or six in a row.

The shads have a deep narrow notch in the middle line of the upper jaw, which is absent in the pilchard. The intestine of the shad is short and straight, like that of the herring; while that of the pilchard is long and folded several times upon itself.

Both of these fishes, again, possess a very curious structure, termed an accessory branchial organ, which is found more highly developed in other fishes of the herring family, and attains its greatest development in a fresh-water fish, the *Heterotis*, which inhabits the Nile. This organ is very rudimentary in the shad (in which it was discovered by Gegenbaur [1]), but it is much larger in the pilchard, in which, so far as I know, it has not heretofore been noticed. In *Chanos* and several other Clupeoid fishes it becomes coiled upon itself, and in *Heterotis* the coiled organ makes many turns. The organ is commonly supposed to be respiratory in function; but this is very doubtful.

Herrings which have attained maturity and are distended by the greatly enlarged milt or roe are ready to shed the contents of these organs or, as it is said to spawn. In 1862, we found a great diversity of opinion prevailed as to the time at which this operation takes place, and we took a great deal of trouble to settle the question, with the result which is thus stated in our Report:—

"We have obtained a very large body of valuable evidence on this subject, derived partly from the examination of fishermen and of others conversant with the herring fishery; partly from the inspection of the accurate records kept by the fishery officers at different stations, and partly from other sources; and our clear conclusion from all this evidence is, that the herring spawns at two seasons of the year, in the spring and in the autumn. We have hitherto met with no case of full or spawning herrings being found, in any locality, during what may be termed the solstitial months, namely June and December; and it would appear that such herrings are never (or very rarely) taken in May or the early part of July, in the latter part of November, or the early part of January. But a spring spawning certainly occurs in the latter part of January, in February, in March, and in April; and an autumn spawning in the latter part of July, in August, September, October, and even as late as November. Taking all parts of the British coast together, February and March are the great months for the spring spawning, and August and September for the autumn spawning. It is not at all likely that the same fish spawn twice in the year; on the contrary, the spring and the autumn shoals are probably perfectly distinct; and if the herring, according to the hypothesis advanced above, come to maturity

[1] "Ueber das Kopfskelet von *Alepocephalus rostratus*," *Morphologisches Jahrbuch*, Bd. iv., Suppl. 1878.

in a year, the shoals of each spawning season would be the fry of the twelvemonth before. However, no direct evidence can be adduced in favour of this supposition, and it would be extremely difficult to obtain such evidence."[1]

I believe that these conclusions, confirmatory of those of previous careful observers[2] are fully supported by all the evidence which has been collected, and the fact that this species of fish has two spawning seasons, one in the hottest and one in the coldest months of the year, is very curious.

Another singular circumstance connected with the spawning of the herring is the great variety of the conditions, apart from temperature, to which the fish adapts itself in performing this function. On our own coasts, herrings spawn in water of from ten to twenty fathoms, and even at greater depths, and in a sea of full oceanic saltness. Nevertheless herrings spawn just as freely, not only in the narrows of the Baltic, such as the Great Belt, in which the water is not half as salt as it is in the North Sea and in the Atlantic, but even in such long inlets as the Schlei in Schleswig, the water of which is quite drinkable and is inhabited by freshwater fish. Here the herrings deposit their eggs in two or three feet of water; and they are found, along with the eggs of freshwater fish, sticking in abundance to such freshwater plants as *Potamogeton*.

Nature seems thus to offer us a hint as to the way in which a fish like the shad, which is so closely allied to the herring, has acquired the habit of ascending rivers to deposit its eggs in purely fresh water.

If a full female herring is gently squeezed over a vessel of sea-water, the eggs will rapidly pour out and sink to the bottom, to which they immediately adhere with so much tenacity that, in half an hour, the vessel may be inverted without their dropping out. When spawning takes places naturally the eggs fall to the bottom and attach themselves in a similar fashion. But, at this time, the assembled fish dart wildly about, and the water becomes cloudy with the shed fluid of the milt. The eggs thus become fecundated as they fall, and the development of the young within the ova sticking to the bottom commences at once.

The first definite and conclusive evidence as to the manner in which herring spawn is attached and becomes developed that I know of, was obtained by Prof. Allman and Dr. MacBain in 1862,[3] in the Firth of Forth. By dredging in localities in which spent herring were observed on the 1st of March, Professor Allman brought up spawn in abundance at a depth of fourteen to twenty-one fathoms. It was deposited on the surface of the stones, shingle, and gravel, and on old shells and coarse shell-sand, and even on the shells of small living crabs and other crustacea, adhering tenaciously to whatever it had fallen on. No spawn was found in any other part of the Forth; but it continued to be abundant on both the east and the west sides of the Isle of May up to the 13th of March, at which time the incubation of the ovum was found to be completed in a great portion of the spawn, and the embryos had become free. On the 25th scarcely a trace of spawn could be detected, and nearly the whole of the adult fish had left the Forth.

Prof. Allman draws attention to the fact "that the deposit of spawn, as evidenced by the appearance of spent herrings, did not take place till about sixty-five days after the appearance of the herring in the Firth," and arrives at the conclusion that "the incubation probably continues during a period of between twenty-five to thirty days," adding however that present be regarded as only this and other evidence that w the eggs of the herring "are h to three weeks after deposition

Within the last few years a upon this question by the la Fishery Commission, to which casion to refer.[4] It has been dation is easily practised, and be kept in aquaria for as long great body of accurate inform unexpected character, has bee development of the eggs, and young herring.

It turns out that, as is the ca period of incubation is closely When the water has a temperat eggs of the herring hatch in fr age being seven days. And thi when we bear in mind the cor quiries of the Dutch meteorolo those of the Scottish Meteorolo tend, namely, that the shoals pr At 50° Fahrenheit, the period ened to eleven days; at 46° to fi lasts forty days. As the Forth i in the month of March, it is prob estimate comes very near the t case which he investigated.

The young, when they emerge one-fifth to one-third of an inch tremely unlike the adult herring tha termed larvæ. They have enormo ingly slender body, with a yelk b forepart. The skeleton is in a ve tion; there are no ventral fins; an dorsal, caudal, and anal fins, there extending from the head along th and then forwards to the yelk bag simple tube, ciliated internally; th and no branchiæ are yet developed. contractile vessel, and the blood is corpuscles. At first the larvæ do not at the expense of the yelk, which gr

Within three or four days after has increased by about half the orig yelk has disappeared, the cartilagino and the heart becomes divided int the young fish attains nearly dou before blood corpuscles are visible.

By the time the larva is two-thirds length which it attains one month primitive median fin is separated and anal divisions, but the ventral peared. About this period the youn feed on small crustacea; and it grow two months, it is 1¼ inch long, and, at attained a length of about two inches.

Nearly up to this stage the elongate retains its larval proportions; but, in t third month, the body rapidly deepens to appear, and the larva passes into t —that is, assumes the form and propo though it is not more than two inches l goes on growing at the same rate (11 mi half an inch) per month, so that, at six as large as a moderate-sized sprat.

The well-known "whitebait" of the

[1] "Report of the Royal Commission on the operation of the Acts relating to Trawling for Herrings on the Coast of Scotland (1863)," P. 28.
[2] Brandt and Ratzeburg, for example, in 1833 strongly asserted that the herring has two spawning seasons.
[3] "Report of the Royal Commission on the Operation of the Acts relating to Trawling for Herring on the Coast of Scotland, 1863."
[4] See the four valuable memoirs, Kupffer, "Ueber ebung des Herings in der westlichen Ostsee," *Jahr* des Herings im Ei"; Meyer, "Beobachtungen in des Herings"; Heincke, "Die Varietäten des Hering in the *Jahresbericht der Commission zu Kiel* Widegren's essay "On the Herring," 1871, translat U.S. Commission Reports, 1873–75, also contains im

s I have seen, almost exclusively of herrings, under
ıths old, and as the average size of whitebait
:s, from March and April onwards, until they be-
ıspiciously like sprats in the late summer, it may
cluded that they are the progeny of herrings
spawned, early in the year, in the neighbourhood
estuary of the Thames, up which these dainty
h have wandered. Whether it is the general habit
ıg herring, even of those which are spawned in
ater, to migrate into the shallow parts of the sea,
ı into completely fresh waters, when such are
ɔle, is unknown.

e Report on Trawling (1863) we observe :—

is extremely difficult to obtain any satisfactory
:e as to the length of time which the herring re-
to pass from the embryonic to the adult or *full*
on. Of the fishermen who gave any opinion on
bject, some considered that a herring takes three,
ıers that it requires seven, years to attain the full
vning condition; others frankly admitted that they
ıothing about the matter; and it was not difficult,
ittle cross-examination, to satisfy ourselves that
vere all really in this condition, however strongly
ıight hold by their triennial or septennial theories.
arrell and Mr. Mitchell suppose with more reason
erring attain to full size and maturity in about
en months.

does not appear, however, that there is any good
ıce against the supposition that the herring reaches
ıwning condition in one year. There is much rea-
believe that the eggs are hatched in, at most, from
ɔ three weeks after deposition, and that in six to
weeks more (that is at most ten weeks from the
of laying the eggs) the young have attained three
s in length. Now it has been ascertained that a
g smolt may leave a river and return to it again in a
e of months increased in bulk eight or tenfold, and
ıerring lives on very much the same food as a smolt,
ıears possible that it should increase in the same
ratio. Under these circumstances nine months
l be ample time for it to enlarge from three to ten or
n inches in length. It may be fairly argued, how-
that it is not very safe to reason analogically from
ate of growth of one species of fish to that of
ıer; and it may be well to leave the question
ıer the herring attains its maturity in twelve, fifteen,
xteen months open, in the tolerably firm assurance
he period last named is the maximum."

ı comparing these conclusions with the results of the
ul observations of the Baltic Commissioners, it
ars that we somewhat over-estimated the rate of
th of the young herring, and that the view taken
Farrell and Mitchell is more nearly correct. For
ıosing that the rate of growth after six months
inues the same as before, a herring twelve months
will be nearly six inches long, and at eighteen
ths eight or nine inches. But full herrings may be
with little more than seven inches long, and they
very commonly found not more than nine inches in
th.[1]

ishermen distinguish four states of the herring. Fry
ile, when not larger than sprats; maties, when larger
ı this, with undeveloped roe or milt; full fish, with
ely developed roe or milt; and spent or shotten
, which have recently spawned.

ıerring fry of the size of sprats are distinguished from
fish not merely by their size, but in addition, by the
y slight development of the milt or roe, and by
accumulation of fat in the abdominal cavity. Bands
fat are found in the mesentery alongside the intestine,
l filling up the interspaces between the pyloric cæca.

Ljungman ("Preliminary Report on Herrings and Herring Fisheries on West Coast of Sweden," translated in U.S. Commision Report, 1873-5) aks of full herrings ready to spawn only 100-110 mm. (4 to 4½ in.) long, as erved by himself.

Maties (the name[1] of which is a corruption of the Dutch word for a maiden) resemble the fry in these particulars; but, if they are well fed, the deposit of fatty and other nutritive matter takes place, not only about the abdominal viscera, but also beneath the skin and in the interstices of the flesh. Indeed, when nourishment is abundant, this infiltration of the flesh with fat may go so far that the fish cannot readily be preserved and must be eaten fresh. The singularly delicate Loch Fyne herrings are in this condition early in the season. When the small crustaceans, on which the maties chiefly feed, are extremely abundant the fish gorge themselves with them to such an extent that the conical crop becomes completely distended, and the Scotch fishermen give them the name of "gut-pock herrings," as much as to say pouch-gutted fish, and an absurd notion is current that these herrings are diseased. However, the "gut-pock" herrings differ from the rest only in having their pouch full instead of empty, as it commonly is.

As the fish passes from the matie to the full condition, the milt and roe begin to grow at the expense of the nutriment thus stored up; and, as these organs become larger and occupy more and more space in the abdominal cavity, the excess of nutritious substance is transferred to them. The fatty deposit about the intestine and pyloric cæca gradually disappears and the flesh becomes poorer. It would appear that by degrees the fish cease to feed at all. At any rate, there is usually no food in the stomach of a herring which approaches maturity. In all these respects there is the closest resemblance between the history of the herring and that of other fishes such as the salmon—the parr correspnding to the herring fry or sile, the grilse and the "clean fish" of larger size to the maties.

At length spawning takes place, the accumulated nutrition, transformed into eggs or spermatic fluid, is expelled, and the fish is left in that lean and depauperated state which makes a "shotten herring" proverbial. In this condition it answers to the salmon "kelt," and the milt or roe are now shrunk and flaccid and can be blown up with air like empty bags. If the spent fish escapes its myriad enemies, it doubtless begins to feed again and once more passes into the matie state in preparation for the next breeding season. But the nature of this process of recuperation has yet to be investigated.

When they have reached the matie stage, the herrings, which are at all times gregarious, associate together in conspicuous assemblages, which are called shoals. These are sometimes of prodigious extent—indeed eight or nine miles in length, two or three in breadth, with an unknown depth, are dimensions which are credibly asserted to be sometimes attained. In these shoals the fish are closely packed, like a flock of sheep straying slowly along a pasture, and it is probably quite safe to assume that there is at least one fish for every cubic foot of water occupied by the shoal. If this be so, every square mile of such a shoal, supposing it to be three fathoms deep, must contain more than 500,000,000 herrings. And when it is considered that many shoals approach the coasts, not only of our own islands, but of Scandinavia and the Baltic, and of Eastern North America, every spring and autumn, the sum total of the herrings which people our seas surpasses imagination.

If you read any old and some new books on the natural history of the herring, you will find a wonderful story about the movements of these shoals. How they start from their home in the Polar Seas, and march south as a great armada which splits into minor divisions—one destined to spawn on the Scandi-

[1] "Halecum intestina, non modo multa gaudere obesitate, sed et totum corpus eo adeo esse impletum ut aliquando, cum discinditur, pinguedo ex cultro defluat, et præsertim eo quidem tempore ubi halecum lactes aut ova crescere primum incipiunt, unde nostrates eos *Maatgens-Haringen* dicere solent."—A. v. Leeuwenhoek, "Arcana Naturæ," Ep. xcvii. (1696).

Leeuwenhoek also mentions having heard of "gut pock" herrings from Scotch fishermen.

navian, and one on our own shores; and how, having achieved this spawning raid, the spent fish make their way as fast as they can back to their Arctic refuge, there to repair their exhausted frames in domestic security. This story was started in the last century, and was unfortunately adopted and disseminated by our country-man Pennant. But there is not the least proof that anything of the kind takes place, and the probabilities are wholly against it. It is, for example, quite irreconcilable with the fact that herring are found in cods' stomachs all the year round. And the circumstance to which I have already adverted, that practised eyes distinguish local breeds of herrings, though it does not actually negative the migration hypothesis, is very much against it. The supposition that the herring spawn in the north in the early spring, and in the south in the autumn, fitted very well into the notion that the vanguard of the migrating body of herrings occupied the first spawning ground it reached, and obliged the rest of the horde to pass on. But, as a matter of fact, the northern herrings, like the southern, have two spawning times; or perhaps it would be more correct to say that the spawning time extends from autumn to spring, and has two maxima—one in August-September, and one in February-March.

Finally, there is no evidence that herrings are to be met with in the extreme north of their range, at other times, or in greater abundance, than they are to be found elsewhere.

In the matter of its migration, as in other respects, the herring compares best with the salmon. The ordinary habitation of both fishes is no doubt the moderately deep portion of the sea. It is only as the breeding time draws near that the herrings (not yet advanced beyond the matie state) gather together towards the surface and approach the land in great shoals for the purpose of spawning in relatively or absolutely shallow water. In the case of the herring of the Schlei we have almost the connecting link between the exclusively marine ordinary herring and the river ascending salmon.

The records of the herring fisheries are, for the most part, neither very ancient nor (with the exception of those of the Scotch Fishery Board) very accurately kept; and, from the nature of the case, they can only tell us whether the fish in any given year were readily taken or not, and that may have very little to do with the actual strength of the shoals.

However, there is historical evidence that, long before the time of Henry the First, Yarmouth was frequented by herring fishers. This means that, for eight centuries, herrings have been fished on the English coast, and I cannot make out, taking one year with another, in recent times, that there has been any serious fluctuation in their numbers. The number captured must have enormously increased in the last two centuries, and yet there is no sign of diminution of the shoals.

In 1864, we had to listen to dolorous prophecies of the coming exhaustion of the Scotch herring fisheries. The fact that the returns showed no falling off was ascribed to the improvement of the gear and methods of fishing, and to the much greater distances to which the fishermen extend their operations. Yet what has really happened? The returns of subsequent years prove, not only that the average cure of the decade 1869-78 was considerably greater than that of the previous decade, but that the years 1874 and 1880 are absolutely without parallel in the annals of the Scotch herring fishery, a million barrels having been cured in the first of these years, and a million and a half in 1880. In the decade 1859-68, the average was 670,000 barrels, and the highest 830,000.

In dealing with questions of biology, *à priori* reasoning is somewhat risky, and if any one tells me "it stands to reason" that such and such things must happen, I generally find reason to doubt the safety of his standing.

It is said that "it stands to reason" that destruction on such a prodigious scale as that effected by her must tell on the supply. But again let us look It is said that 2,500,000,000, or thereabouts, are every year taken out of the North Sea a lantic. Suppose we assume the number to be so as to be quite safe. It is a large number but what does it come to? Not more than herrings which may be contained in one shoal half a dozen square miles—and shoals of size are on record. It is safe to say that through the North Sea and the Atlantic, at same time, there must be scores of shoals which would go a long way towards supplying of man's consumption of herrings. I do that all the herring fleets taken together do cent. of the total number of herrings in the year, and I see no reason to swerve from the my colleagues and I expressed in our Report destructive operations are totally insignificant pared with those which, as a simple calculu must regularly and normally go on.

Suppose that every mature female herring eggs, that the fish are not interfered with b that their numbers remain approximately year after year, it follows that 998 of th of every female must be destroyed before maturity. For if more than two out of the n destruction, the number of herrings will be ately increased. Or in other words, if the avera of the shoals which visit a given locality i the same year by year, many thousand times contained in those shoals must be annually And how this enormous amount of destruction will be obvious to any one who considers the of the fin-whales, the porpoises, the gannets, the codfish, and the dogfish, which accom shoals and perennially feast upon them; to s of the flat-fish, which prey upon the newly-deposi or of the mackerel, and the innumerable small which devour the fry in all stages of their de It is no uncommon thing to find five or six— ten or twelve—herrings in the stomach of a cod in 1863, we calculated that the whole take of Scotch herring fisheries is less than the number which would in all probability have been con the codfish captured in the same waters if they left in the sea.[1]

Man, in fact, is but one of a vast co-operative herring-catchers, and the larger the share he take there is for the rest of the company. If man t the other shareholders would have a larger divi would thrive and multiply in proportion, but come to pretty much the same thing to the her

As long as the records of history give us inf herrings appear to have abounded on the east co British Islands, and there is nothing to show, so am aware, that, taking an average of years, t ever either more or less numerous than they are at But in remarkable contrast with this constancy, th of herrings have elsewhere exhibited a chang ciousness—visiting a given locality for many great numbers, and then suddenly disappearing. well-marked examples of this fickleness are reco the west coast of Scotland; but the most remarkab furnished by the fisheries of Bohúslan, a provinc lies on the south-western shore of the Scand peninsula. Here a variety known as the "

[1] In his valuable Report on the Salt Water Fisheries of Norw Prof. Sars expresses the belief that full-grown codfishes feed exclusively on herrings.

[2] In 1877 rather more than 5,000,000 cod, ling, and hake, were the Scottish fishermen. Allowing each only two herrings a day, th would have consumed more than three thousand five hundred millio rings in a year. As to the Norwegian fisheries, 20,000,000 cod said to be taken annually by the Lofoden fishermen alone.

herring, after being so extremely abundant, for xty years, as to give rise to a great industry, disd in the year 1808, as suddenly as they made their nce, and have not since been seen in any number. lesertion of their ordinary grounds by the herring n attributed to all imaginable causes, from fishing unday to the offence caused to the fish by the osing carcases of their brethren, dropped upon om out of the nets. The truth is that absolutely is known on the subject; and that little is likely nown, until careful and long-continued meteoroand zoological observations have furnished definite tion respecting the changes which take place in perature of the sea, and the distribution of the crustacea which constitute the chief food of the shoals. The institution of systematic observations kind is an object of international importance, s the attainment of which the British, Scandinavian, and French Governments might wisely make a ied effort.

eat fuss has been made about trawlers working over wning grounds of the herring. "It stands to reason," re told, that they must destroy an immense quanthe spawn. Indeed this looked so reasonable, ve inquired very particularly into a case of the l malpractice which was complained of on the ast of Scotland, near Pittenweem. Off this place, is a famous spawning ground known as the Traith and we were told that the trawlers worked vigorover the spot immediately after the herring had ited their spawn. Of course our first proceeding was the trawlers why they took the trouble of doing looked like wanton mischief. And their answer easonable enough. It was to catch the prodigious lance of flat-fish which were to be found on the a at that time. Well, then, why did the flat-fish conte there? Simply to feed on herring eggs, which to be a sort of flat-fishes' caviare. The stomachs flat-fish brought up by the trawl were, in fact, med with masses of herring eggs.

us every flat-fish caught by the trawl was an enerdestroyer of herring arrested in his career. And the ng, instead of injuring the herring, captured and ed hosts of their worst enemies. That is how ood to reason" when one got to the bottom of the r.

not think that any one who looks carefully into the ct will arrive at any other conclusion than that ied by my colleagues and myself: namely, that the thing for Governments to do in relation to the ng fisheries, is to let them alone, except in so far as olice of the sea is concerned. With this proviso, let le fish how they like, as they like, and when they

At present, I must repeat the conviction we essed so many years ago, that there is not a icle of evidence that anything man does has an reciable influence on the stock of herrings. It will ime to meddle, when any satisfactory evidence that chief is being done is produced

NOTES

THE fifty-first Annual Meeting of the British Association for Advancement of Science will commence at York on Wednes., August 31, 1881. The President-Elect is Sir John Lubbock, t, M.P., F.R.S. Vice-Presidents Elect: His Grace the Archop of York, D.D., F.R.S.; the Right Hon. the Lord Mayor York; the Right Hon. Lord Houghton, F.R.S.; the Ven. hdeacon Creyke, M.A.; the Hon. Sir W. R. Grove, F.R.S.; f. G. G. Stokes, Sec. R.S.; Sir John Hawkshaw, C.E., .S.; Allen Thomson, M.D., F.R.S. L. and E.; Prof. Allen, M.D., F.R.S. L. and E. General Secretaries: Capt. uglas Galton, C.B., D.C.L., F.R.S.; Philip Lutley Sclater, Ph.D., F.R.S. Acting Secretary: George Griffith, M.A., F.C.S., Harrow; General Treasurer: Prof. A. W. Williamson, F.R.S., University College, London, W.C. Local Secretaries: Rev. Thomas Adams, M.A.; Tempest Anderson, M.D., B.Sc., York. Local Treasurer: W. W. Wilberforce, York. The Sections are the following:—A.—Mathematical and Physical Science.—President: Prof. Sir William Thomson, F.R.S. L. and E. Vice-Presidents.—Prof. J. C. Adams, F.R.S.; T. Archer Hirst, Ph.D., V.P.R.S. Secretaries: Prof. W. E. Ayrton; Oliver J. Lodge, D.Sc.; Donald McAlister, B.A., B.Sc. (Recorder). B.—Chemical Science.—President: Prof. A. W. Williamson, For. Sec. R.S., V.P.C.S. Vice-Presidents: F. A. Abel, C.B., F.R.S.; Prof. Odling, F.R.S. Secretaries: Harold B. Dixon, M.A.; P. Phillips-Bedson, D.Sc. (Recorder). C.—Geology.—President: Andrew Crombie Ramsay, LL.D., F.R.S., Director-General of the Geological Survey of the United Kingdom and of the Museum of Practical Geology. Vice-Presidents: Prof. Prestwich, F.R.S.; Prof. W. C. Williamson, F.R.S.; Secretaries: W. Topley, F.G.S. (Recorder); W. Whitaker, F.G.S. D.—Biology.—President: Richard Owen, C.B., F.R.S. Vice-Presidents: Prof. W. H. Flower, F.R.S.; Prof. J. S. Burdon Sanderson, F.R.S. Secretaries: G. W. Bloxam, M.A., F.L.S.; W. L. Distant; W. A. Forbes, F.Z.S.; Prof. M'Nab, M.D.; John Priestley; Howard Saunders, F.L.S., F.Z.S. Department of Zoology and Botany.—Richard Owen, C.B., F.R.S. (President), will preside. Secretaries: Prof. M'Nab, M.D. (Recorder); Howard Saunders, F.L.S., F.Z.S. Department of Anthropology.—Prof. W. H. Flower, F.R.S. (Vice-President), will preside. Secretaries: G. W. Bloxam, M.A., F.L.S. (Recorder); W. L. Distant. Department of Anatomy and Physiology.—Prof. J. S. Burdon Sanderson, F.R.S. (Vice-President), will preside. Secretaries: John Priestley (Recorder); W. A. Forbes, F.Z.S. E.—Geography.—President: Sir J. D. Hooker, K.C.S.I., C.B., F.R.S. Vice-Presidents: Francis Galton, F.R.S.; Prof. Sir C. Wyville Thomson, F.R.S. L. & E. Secretaries: H. W. Bates, Assist.-Sec.R.G.S., F.L.S.; E. C. Rye, Librarian R.G.S., F.Z.S. (Recorder). F.—Economic Science and Statistics.—President: The Right Hon. M. E. Grant Duff, M.P., F.R.S. Vice-Presidents: Sir George Campbell, K.C.S.I., M.P.; James Heywood, F.R.S. Secretaries: Constantine Molloy (Recorder); J. F. Moss. G.—Mechanical Science.—President: Sir W. G. Armstrong, C.B., F.R.S. Vice Presidents: W. H. Barlow, F.R.S., Pres.Inst.C.E.; C. W. Siemens, D.C.L., F.R.S. Secretaries: A. T. Atchison, M.A. (Recorder); H. Trueman Wood, B.A. Tickets for the meeting may be obtained of the Local Secretaries at York, and at the Office of the Association, 22, Albemarle Street, London, W.; or on application by letter, from August 17 to August 24, to the General Treasurer, Prof. A. W. Williamson, British Association, University College, London, W.C. The First General Meeting will be held on Wednesday, August 31, at 8 p.m. precisely, when A. C. Ramsay, F.R.S., V.P.G.S., Director-General of the Geological Survey of the United Kingdom, and of the Museum of Practical Geology, will resign the chair, and Sir John Lubbock, Bart., M.P., F.R.S., President-Elect, will assume the presidency, and deliver an address. On Thursday evening, September 1, at 8 p.m., a *soirée;* on Friday evening, September 2, at 8.30 p.m., a discourse by T. H. Huxley, LL.D., Sec.R.S., Professor of Natural History in the Royal School of Mines; on Monday evening, September 5, at 8.30 p.m., a discourse by W. Spottiswoode, D.C.L., LL.D., President of the Royal Society; on Tuesday evening, September 6, at 8 p.m., a *soirée;* on Wednesday, September 7, the concluding general meeting will be held at 2.30 p.m. No report, paper, or abstract, can be inserted in the Report of the Association unless it is given in before the conclusion of the meeting. Excursions to places of interest in the neighbourhood of York

will be made on the afternoon of Saturday, September 3, and on Thursday, September 8.

THE honorary degree of LL.D. has been conferred on the following gentlemen by the University of Glasgow:—F. M. Balfour, M.A., Fellow of Trinity College, Cambridge; Dr. Angus Smith, F.R.S., Government Inspector of Alkali Works; Prof. Richard Owen, C.B., F.R.S., Superintendent of Natural History Collections of the British Museum; Andrew Buchanan, M.D., Emeritus Professor of Physiology in the University of Glasgow.

THE honorary degree of LL.D. has been conferred by the University of Edinburgh on Prof. A. W. Williamson, of University College, London.

IT is intended to celebrate in Edinburgh the centenary of the birthday of Sir David Brewster, on December 9, by a public dinner.

THE annual meeting of the Iron and Steel Institute will be held in London on May 4, 5, and 6. On May 4 the Bessemer Medal for 1881 will be presented to Mr. William Menelaus, and the president-elect (Mr. Josiah T. Smith) will deliver his inaugural address. The following is the list of papers to be read:—On the Results of Experiments relative to Corrosion in Iron and Steel, by Mr. William Parker of Lloyd's Registry, London; On the Manufacture of Armour Plates, by Mr. Alexander Wilson, Sheffield; On the Manufacture of Steel and Steel Plates in Russia, by Mr. Sergius Kern, St. Petersburg; On the Use of Steel for Shipbuilding, by Mr. William Denny, Dumbarton; On some Physical Properties of Cast Iron, by Mr. Charles Markham, Staveley; On the Desulphurisation of Iron, by M. Rollet, St. Chamond, France; On Iron and Steel Permanent Way, by Mr. R. Price Williams, London; On Hydraulic Appliances for the Bessemer Process, by Mr. Michael Scott, London; On the Manufacture of Bessemer Steel and Steel Rails in America, by Capt. Jones, Edgar Thomson Steel Works, Pittsburg, U.S.A.; On Hydrogen and Carbonic Oxide in Iron and Steel, by Mr. John Parry, Ebbw Vale; On the Preservation of Iron and Steel Surfaces, by Mr. George Bower, St. Neots; On a new method for the determination of Oxygen in Iron and Steel, by Mr. Alex. E. Tucker, Rhymney.

DURING the Summer Term of the City and Guilds of London Institute, commencing May 2, 1881, Prof. Armstrong, Ph.D., F.R.S., and Prof. Ayrton, A.M., Inst.C.E., will continue their tutorial and laboratory courses of instruction in chemistry and physics as applied to the arts and manufactures, at the Cowper Street Schools, pending the present erection of the City and Guilds of London Technical College, Finsbury, the foundation stone of which will be laid by Prince Leopold on May 10. There are both day and evening classes at the institute, with means for ample laboratory practice, at fees which place the education within reach of all classes. We would specially draw attention to the fact that these classes and the laboratory practice are open, at an almost nominal fee, to female as well as to male students. For every hour of lecture there are two hours laboratory work included in this nominal fee. The day classes would be of service to girls who have not the means to obtain a Girton or a Newnham education, while the evening classes will be of great use to those women who take more than a mechanical interest in their daily work; for from the course of instruction and their own work in the laboratory they will gain such a thorough knowledge of principles as should distinguish a skilled workwoman from a mere machine.

THE Annual Report for the past year of the Jamaica Public Gardens, by Mr. D. Morris, the new director, is one of great interest. As the year has been the first under the new organisation, the chief work has naturally been of a departmental character, but from the details given, it is evident that important [illegible] been made in developing several industries which [illegible] important influence for good on the future of the [illegible] the variation in altitude of the different [illegible] Morris's charge excellent opportunities are [illegible] menting on various kinds of cultivation, and those [illegible] prepared to take full advantage of. Among the [illegible] concerning which interesting information is [illegible] Report, are Cinchona, Liberian Coffee, Sugar Cane, [illegible] Mahogany, Pine-Apples, Jalap, Cacao, Tobacco, [illegible] various spices, Oranges, Bananas Fibre, &c. The [illegible] may be looked for from Mr. Morris's vigorous and [illegible] directorship.

WE have also a very satisfactory Report of work [illegible] ending March 31, 1880, from Mr. Duthie, superintendent [illegible] Government Botanical Gardens at Saharanpur and [illegible] As in Jamaica, experiments, some of them very [illegible] been carried on in the rearing of various useful plants, [illegible] vegetable and medicinal plants. Much difficulty [illegible] experienced by Mr. Duthie in training *Malkie* for [illegible] gardens, and he has some trials before him ere he [illegible] turn out a staff of properly-trained natives.

MR. M. G. MULHALL sends us the following [illegible] which we give without comment:—"Although Shakespeare [illegible] supposed to have taken the idea of Hamlet from the [illegible] historian Saxo-Grammaticus, there are such points of resemblance [illegible] with the Arabic chronicle of Nigiaristan, respecting Mohammed [illegible] tenth Caliph of Bagdad, that I venture to call your attention [illegible] the same. The points of analogy are as follows: [illegible] Montasser is murdered by putting poison in his ear. 2. The [illegible] ghost scene, in which his father appears to him. 3. The [illegible] playing of tapestry before the Caliph and his court, in which [illegible] the tapestry represents a tragedy identical with the late [illegible] murder."

THE *Daily News* New York correspondent telegraphs that [illegible] aldermen have passed, over the mayor's veto, the ordinance [illegible] giving the Edison Electric Lighting Company permission [illegible] tubes in the streets. "The company will proceed [illegible] to introduce its new electric lamps in the offices in the [illegible] portion of the city around Wall Street. The construction [illegible] the lamp is simple. It consists of a small bulbous glass [illegible] four inches long, an inch and a half in diameter, with a [illegible] loop which becomes incandescent when the electric [illegible] passes through. Each lamp is of sixteen candle-power, with [illegible] perceptible variation in intensity. The light is turned on [illegible] with a thumbscrew. Wires have already been put into [illegible] buildings. The company will compete with the gas companies [illegible] by charging the same rates. If the latter reduce, the [illegible] Company will also reduce, and are prepared to go lower than [illegible] gas companies can."

AT five o'clock on Saturday morning a strong shock of [illegible] quake was felt at Paola in the province of Calabria. On the [illegible] night of April 19 there was another severe shock of earthquake [illegible] at Chios.

A NEW illustrated work on the Butterflies of Europe [illegible] we understand, in active preparation by Dr. Lang, F.L.S. [illegible] publication, in monthly parts, will be commenced very [illegible] by Messrs. Lovell, Reeve, and Co.

MRS. BURTON, the wife of the well-known Capt. R. [illegible] our Consul at Trieste, is evidently doing a good work in that [illegible] in teaching the people kindness to animals. The [illegible] evidently much needed, and judging from Mrs. Burton's [illegible] at her last fête and distribution of prizes, her efforts are meeting [illegible] with decided success. Of course all this costs money; [illegible] some of our readers may be inclined to help by sending a [illegible]

d Burton, British Consulate, Trieste,

used by the sale to a private person of
the Blue Mountains, the New South
ding to the *Colonies and India*, has set
tracts of land round Dangar's Falls,
t Falls in the same district, and Moona
itation of the reserves or national parks
America.

is said to have occurred in Guatemala
reat damage to the tropical vegetation.

s. Fison and Howitt's "Kamilaroi and
last week, we should have mentioned
ed in England by Messrs. Macmillan

ve received two satisfactory Reports—
Museum, presided over by Mr. James
Mitchell Library, under Mr. F. T.

EN school teachers nominated on purpose
ers of elementary schools in France, and
of the Government, were summoned to
e Pedagogic Congress, which came to a
he same time the Ligue de l'Enseigne-
an Macé, held a series of meetings at
ncluding sitting, which took place last
by all the school teachers and an im-
eal leaders. M. Gambetta delivered a
stages of education, commending school
dvocating the importance of interesting
sion of knowledge.

APP, AND CO., have published a useful
ollook of Geological Rambles around
and to add much interest to a Saturday
ountry.

VAN RAAY writes to us from Batavia,
meration of the different geographical
NATURE, vol. xxiii. p. 299, the Geo-
marang (Java), founded in 1879, was

HN of Augsburg has issued a priced
ive library of the late Prof. W. P.

he *Proceedings* of the Bristol Natural
some good papers:—Some Optical
Thompson; Underground Tempera-
A; The Structure and Life-History of
Sollas; On some Cases of Prolification
by Mr. A. Leipner; The Ethnology of
J. Beddoe, F.R.S.; Catalogue of the
District, by Mr. A. E. Hudd, and of
Bucknall; The Pomerine Skua, by M.

ological Society's Gardens during the
Short-tailed Wallabys (*Halmaturus*
Australis, presented by Sir Harry St.
F.Z.S.; three Green Lizards (*Lacerta*
ented by Mrs. E. H. Bland; a Rufous
minus rufescens) from Australia, pre-
ratt; a Lion (*Felis leo* ♀) from Africa,
lus Monkeys (*Semnopithecus entellus*
based; a Lion (*Felis leo* ♀) from Africa,
vulgaris ♀), British, received in ex-
Bat (*Cynonycteris collaris*), a Vulpine
alpina), born in the Gardens.

CHEMICAL NOTES

IN *Journal pract. Chemie*, Herr Ceeh, in the course of a paper on the decompositions which occur during the rotting of eggs, describes experiments which he thinks establish the possibility of obtaining a good soap free from smell, by saponifying with soda the residue obtained by evaporating to dryness rotten eggs, freed from their shells. Such a dried residue yields about 10·5 per cent. of oil, fresh eggs giving about 11 per cent.

THE changes undergone by grain when stored in underground magazines have been recently studied by M. Müntz (*Compt. rend.*). The magazines of the Paris Omnibus Company are partly underground; the grain in the upper parts is, however, exposed to the influence of atmospheric changes; it is found to contain much more moisture and to be at a higher temperature than that in the lower parts. The relative amounts of deterioration in grains may be measured by the quantities of carbonic anhydride exhaled. When grain is freely exposed to air about ten times as much carbonic anhydride is given off as when the grain is kept in closed receptacles; less oxygen is absorbed than corresponds with this evolution of carbon dioxide. Normal grain contains from 11 to 19 per cent. of moisture: the greater the moisture the greater the exhalation of carbon dioxide. The amount of the gas evolved also increases with increase of temperature until a point is reached at which true chemical combustion of the carbon begins, as distinguished from the physiological combustion which has preceded it. Grain which is to be kept for any time ought to be very dry, the receptacle containing it ought to be completely closed, and all parts of this receptacle ought to be at approximately the same temperature.

MR. V. LEWES, in the same journal, describes barium pentathionate, $BaS_5O_6 . 3H_2O$, and several potassium pentathionates, prepared by slow evaporation in a vacuum of "Wackenroder's solution." These experiments appear to establish beyond doubt the existence of pentathionic acid.

DRS. DUPRÉ AND HAKE have applied their method for the estimation of carbon (*Chem. Soc. Journ.*)—viz. burning in oxygen, absorbing carbonic anhydride in baryta water, converting the barium carbonate into sulphate, and weighing as such—to the estimation of carbon in air; their experiments apparently demonstrate the presence in London air of carbon in forms other than carbonic anhydride, and probably in the form of some volatile organic compounds, not as suspended matter. Drs. Dupre and Hake claim that their method of analysis enables them to estimate carbonic anhydride, carbon in the peculiar forms already noticed, and suspended carbonaceous matter in air.

IN the same journal there is a contribution to the history of ozone by Prof. Hartley of Dublin. The main conclusions drawn from experimental data are these: Ozone is a normal constituent of the higher atmosphere, and is present therein in larger proportion than near the surface of the earth. The limitation of the solar spectrum in the ultra-violet is readily accounted for by the absorptive action of atmospheric ozone, without taking into account the possible absorptive power of nitrogen and oxygen. The blue tint of the atmosphere is probably due to ozone. It is shown in the paper that the wave-length of the extreme ray capable of absorption by considerable quantities of ozone is about 316. A quantity of 2·5 mgm. of ozone in each square centimetre of sectional area of a column of air produces, it is said, a full sky-blue tint. Incidentally experiments are described in which one volume of ozone was distinctly detected by the sense of smell in 2,500,000 volumes of air.

MR. G. S. JOHNSON has obtained ammonia (*Chem. Soc. Journal*) by passing hydrogen and (presumably) pure nitrogen over cold or moderately heated spongy platinum: when however the mixed gases were passed over hot asbestos before traversing the spongy platinum, *no* ammonia was formed. Mr. Johnson thinks that nitrogen probably exists in two forms, an active and an inactive form, the latter being produced by the action of heat on the former.

DR. DUPRÉ has introduced (*Analyst*) a slight modification into the ordinary method for observing a colour change in titrating with standard solutions, which is said to render the perception of the change very sharp and accurate. He views the liquid to be titrated through a glass cell containing a solution of the same colour as, and about equal in intensity to, the liquid itself.

M. LONGUININE has recently determined (in *Compt. rend.*) the heats of combustion of various alcohols of the allyl series, and compared the numbers with those expressing the heats of combustion of metameric aldehydes. He finds very marked differences between the two series of numbers, showing once more a distinct connection between the energy lost by a carbon compound in passing from one state to another standard state, and the structure of the molecule of that compound.

M. BERTHELOT, in continuation of his researches on compounds of metallic halogen salts with haloid acids, describes in *Compt. rend.* the action of gaseous hydrochloric and hydrobromic acids on alkali chlorides and bromides; he shows that the gaseous acids are absorbed by the dry salts with disengagement of heat, and that the products of the actions are possessed of properties which distinguish them from mere mixtures.

M. BERTHELOT also considers the reciprocal actions between alkali haloid salts and haloid acids; he shows that as a rule alkali chlorides are decomposed by hydrobromic acid, but that in some cases and under special conditions of temperature, bromides are decomposed by hydrochloric acid. The general results are shown to be in keeping with the laws of thermochemistry. That action in which most heat is evolved occurs, but the products of the action may be unstable under experimental conditions, and hence the primary change may be modified, or even reversed.

M. MÜNTZ states that his investigations have shown that traces of alcohol exist in all natural waters, whether rain, river, sea, or snow water. He describes his method of applying the iodoform test for alcohol, whereby one part can be detected in 1,000,000 parts of water.

PHYSICAL NOTES

M. LAURENT of Paris has constructed "magic mirrors" giving similar effects to those brought from Japan, but of glass silvered at the back instead of metal. By engraving patterns at the back and silvering the front surface, the mirror has a perfectly plane surface only when the air-pressures at the front and back are equal. If the air behind be compressed or rarefied the thinner parts will have relatively a greater convexity or concavity than the rest, and in the disk of light which the mirror reflects on to a wall from a luminous point the pattern engraved on the back will accordingly appear dark or light.

FROM experiments on the radiation and conduction of heat in rarefied gases (*Wied. Ann.*, No. 13) Herr Graetz finds the results in much better agreement with Stefan's law of radiation than with that of Dulong and Petit, and "it may be affirmed that in the temperature-interval from 0° to 250° C. the radiation is very nearly proportional to the fourth power of the temperature." The factor of proportionality σ (in Stefan's formula $Q = \sigma T^4$) is then that amount of heat which is radiated from one square centimetre of a substance of $-272°$ C. in a second towards a space of the absolute temperature 0° ($-273°$). By the method of least squares Herr Graetz finds

$$\sigma \text{ for glass} = 1{\cdot}0846 - 12 \frac{\text{gramme centigrade}}{\text{centim. seconds}}.$$

Certain divergences at low temperatures suggest that while the intensity of radiation grows with rising temperature, it perhaps grows differently for different heat colours.

IN a recent communication to the Munich Academy, Herren Nies and Winkelmann describe an inquiry into the volume-changes of various metals in solidifying. Of eight metals examined, six (viz. tin, zinc, bismuth, antimony, iron, and copper) were proved to undergo expansion in passing from the liquid to the solid state. For three of the metals approximate values for the amount of this expansion were obtained (tin showed an expansion of 0·7 per cent., zinc 0·2, and bismuth 3). Two metals (lead and cadmium) gave doubtful results; but the authors find some reason to believe that they also expand in solidifying. So far then the rule would appear to be general for metals.

M. TRÈVE describes in the *Comptes rendus* some curious observations from which it would appear that when light is admitted from a natural or artificial source through a slit, more light passes if the slit be horizontal than if it be vertical. M. Trève has produced photographs taken behind slits in various positions to prove that the effect is not an illusion of the eye. The phenomenon appears to us inexplicable, [illegible] requires further proof to substantiate its reality.

M. MERCADIER still continues to study radiophonic phenomena. He finds it possible to increase the effects [illegible] one tube the vibrations of several receiving disks. He finds it possible to construct tubes whose length corresponds wave-length of the vibrations radiophonically excited, and respond to the note emitted. M. Mercadier hopes by means to re-determine with increased accuracy the velocity sound in air and other gases.

WITH regard to the beats and beat-tones of harmonic [illegible] Dr. Koenig argues (*Wied. Ann.* No. 3) against Prof. [illegible] view, that these are due to harmonic tones of the lower sounding with the higher (Dr Koenig, in his former [illegible] having used strongly-excited tuning-forks). He shows phenomena may be studied with the aid of a "[illegible]" which a blast of air is sent through a slit against the border of a rotating disk, or of a ring-section of a [illegible] He has the border of the disk cut to represent some curve produced by combination of the curves of two [illegible] giving an air motion, when blown against, quite like two tones sounded together. The beats and beat-tone heard. With a mere wavy outline for the border at right angles one hears a quite simple tone, which [illegible] once changed to a "clang" with strong overtones, [illegible] is slanted a little. Now, with two simple tones [illegible] beat-tone heard when the slits are at right angles shows holtz's supposition) be less distinct than when, the [illegible] slanted, the overtones are brought out; whereas the [illegible] the case.

DR. KOENIG, in the same number, describes a simple apparatus for producing beat-tones. It consists of two [illegible] of different length, clamped in vertical position by the [illegible] a jointed frame, which, through an elastic connection their lower ends pressed against the cloth-covered [illegible] wheel which dips in water in a trough. The friction [illegible] the longitudinal tones and the beat-tone.

AN improved form of the Töpler air-pump has been [illegible] by Herr Bessel-Hagen (*Wied. Ann.* No. 3), with which considerably higher vacua can be reached than those which obtains with the more complicated and fragile Sprengel-Ham apparatus. The average limit of rarefaction with [illegible] be $\frac{1}{25}$ millionths of an atmosphere ($\frac{1}{25}$ in one case [illegible] other pump only gives $\frac{1}{17}$ millionth. (It is noted that Ogden Rood has obtained $\frac{1}{54}$, and in one case even [illegible] modified Sprengel.) With his highest vacua the [illegible] electricity to pass (using plate-electrodes and a [illegible] machine, with Leyden jars). He considers mercury [illegible] insulator for electricity; but shows that radiometric [illegible] depend greatly on its pressure *in vacuo*. No [illegible] hydrogen through the glass could be detected.

AN artificially-formed body showing polar effects [illegible] of attraction and direction is produced by Herr Hess (*Wied. Ann.*, No. 3) thus: To one end of a short glass rod [illegible] a plane piece of glass, and to this a short narrow glass [illegible] a line with the rod). In the tube is placed a screw, [illegible] longer than it, and carrying at its head a *thin* paper [illegible] (22 mm. across), which has attached on one half of [illegible] phery, reaching over both above and below, a pasteboard [illegible] (10 mm. broad); opposite this, on one of the surfaces, [illegible] a small projecting point of tin-foil. Brought between [illegible] disks fixed to the rods of a Holtz machine, the tin-foil always turned to the positive pole. Next, the glass rod [illegible] disk was attached to the end of a light horizontal [illegible] hung bifilarly, and so brought between the hollow disks, disk first turned into position, and was then attracted to the negative pole. The phenomena are thought to [illegible] unipolar conductivity.

THE simple tourmaline-pincette, by reason of its [illegible] can be used with only a small number of crystals. To the field M. Bertin has applied to it a part of the [illegible] polarising microscope. This, it is known, consists [illegible] polariser and focus; second, of a microscope and [illegible] polariser and analyser, at the extremities, are pretty [illegible] and if replaced by two tourmalines placed between the [illegible] the microscope (of simplified form) the apparatus [illegible] much smaller and handier [illegible] principle of the [illegible] new tourmaline-pincette [illegible] will be found [illegible]

or March). It showed very well the fringes 3 in diameter and ¼ mm. in thickness, and ive fringes in it. With the old pinnette ds can be observed (nitre and lead crystal), ur angle of the axis being about 17°; but nt, a small calamine plate, with axes 78° fringes well.

August (*Jour. de Phys.*, March) the psyer form, may give pretty good indications observers, in these regions (France), so long re-sure is not far from 760 mm., the wet above 12° or 2°, and the difference of the ains below 12°; but otherwise the ordinary ory.

mospheric electricity on the vegetation of ified near Palermo by M. Macagno (*Jour.* Sixteen stocks were rendered more subject electric tension by means of a copper wire h platinum point in the upper end of the mother wire connected the bottom of the und. This continued from April to Sepion of vegetation was proved by the wood ining less mineral matters and potash than ocks, while the contrary occurred in the e potash was mostly in the bitartrate formantity of must was got from the grapes of d considerably more glucose and less acid.

ts of the electric phenomena which occur s and gases has been attempted by Herr lin (*Wied. Ann.*, No. 2). He worked with two circular plates of a given metal, the nected with an electrometer and submitted ss gases or to vacuum; the lower connected y of electricity from a known source requirted to the upper plate to make its potential as measured. *Inter alia*, ozone was found nan, and brass negative to a plate of the Hydrogen always made platinum strongly luence on gold was hardly perceptible, and g various. Chlorine made platinum negative (from aqueous solution) made brass positive, nce of potential with as similar treatment en pair of plates was very different in the of a series. Nor could a certain relation en it and the time of action of the gas. It wo platinum plates, one in hydrogen (viz. ally decreased to a point generally somewhat eginning. As to the cause of this decrease, probable that a gradual neutralisation of the es takes place.

VELOPMENT OF HUMAN INTELLIGENCE

ent of Education of the American Social sociation has issued the following Cir, which we commend to the notice of e of whom may be able to give Mrs. the questions given below:—

ible familiar with the habits of plants and eful investigations which have from time to d—the intelligence of animals, even, coming attention. One author alone contributes a d pages upon "Mind in the Lower Animals." tors in this country have been chiefly thinke natural development of a single child is Noah's ark full of animals. Little has been t least little has been recorded. It is certain others might contribute observations of their development that might be at some future ic psychologist. To this belief the Education American Social Science Association has ying Register, and asks the parents of very terest themselves in the subject—

; the importance of the study of the youngest

the simplest manifestations of their life and

3. By answering fully and carefully the questions asked in the Register.

4. By a careful record of the signs of development during the coming year, each observation to be verified, if possible, by other members of the family.

5. By interesting their friends in the subject and forwarding the results to the secretary.

6. Above all, by *perseverance* and exactness in recording these observations.

From the records of many thousand observers in the next few years it is believed that important facts will be gathered of great value to the educator and to the psychologist.

First Series—REGISTER OF PHYSICAL AND MENTAL

Development of (Girl or Boy?) (Give name.)
Name and occupation of the father?.....
Place and time of father's birth?.....
" " mother's " ?.....
" " baby's " ?.....
Baby's weight at birth?..... at 3 months?.....
" " 6 months?..... at 1 year?.....
Is baby strong and healthy, or otherwise?.....
At what age did the baby exhibit consciousness, and in what manner?.....

AT WHAT AGE DID THE BABY

smile?.....
recognise its mother?.....
notice its hand?.....
follow a light with its eyes?.....
hold up its head?.....
sit alone on the floor?.....
creep?.....
stand by a chair?.....
stand alone?.....
walk alone?.....
hold a plaything when put in its hand?.....
reach out and take a plaything?.....
appear to be right or left handed?.....
notice pain, as the prick of a pin?.....
show a like or dislike in taste?.....
appear sensible to sound?.....
notice the light of a window or turn towards it?.....
feel the heat from stove or grate?.....
speak, and what did it say?.....

HOW MANY WORDS COULD IT SAY

at 1 year?....., at 18 months?....., at 2 years?.....

Will the mother have the kindness to carefully answer as many as possible of these questions and return this circular, before July 15, 1881, to Mrs. Emily Talbot, Secretary of the Education Department of the American Social Science Association, 66, Marlborough Street, Boston, Mass.

Boston, March 1, 1881

In connection with the inquiry indicated above, the following letter from Dr. Preyer of Prussia, addressed to Mrs. Talbot, will be found of interest:—

Jena, November 22, 1880.

DEAR MADAM,—It has given me much pleasure to read your letter and the extract of a paper of mine on "psychogenesis," or "the growth of volition, intellect, &c., in infants," and I readily comply with your wish to have this paper sent off without delay. You will find it reprinted in the book accompanying this letter, p. 199–237. I am about to publish an extensive work on the same subject, which is to contain all my observations and a careful analysis of the phenomena which the development of the faculty of speech presents. This book is to be printed next year. I am sorry to say that a reliable investigator of the whole subject is not known to me. Your newspaper seems to be right in calling the field "as yet almost unbroken." Prof. Kussmaul's "Seelenleben des neugeborenen Menschen" (Leipzig and Heidleberg, 1859), and Mr. C. Darwin's biographical sketch of an infant, contain some good observations, but both are very short. Many excellent remarks on infants and very young children I find in Mr. C. Darwin's book, "On the Expression of the Emotions." The German books on the subject, although numerous, are nearly worthless; many are sentimental, giving no facts, or, what is worse, false statements. B. Sigismund's "Kind und Welt" (1851) is an exception.

The case you mention of a child of eleven months expressing

its wishes and inducing the nurse to comply with them cannot be definitely looked at as a case of self-consciousness, but only of consciousness. This is one of the most intricate questions to decide—*when* the child distinguishes its own body, head, hands, &c., from other objects, as belonging to himself. The first time a child says "I" and "me," in the correct sense, it may be considered to have passed the limit. The formation of ideas by associating impressions, as well as the formation of general ideas (*Begriffe*) by uniting similar qualities of different objects, is intellectual work done by the child long before it knows anything of its own individuality. It seems to me that self-consciousness does not arise suddenly, but by degrees, after many experiments have shown the difference between touching his own body and external objects with his little hand.

I have been occupied with psychogenetical problems since nearly four years, continually collecting facts. Should you be able to awaken some interest for these most important investigations (I mean the physiology and psychology of infants), I think the trouble taken would soon be repaid by the results.

I am, sincerely,

DR. WM. PREYER, Professor

P.S.—Perhaps the observations and experiments on the senses (sight, hearing, smell, taste) of new-born animals and infants which I published in *Kosmos* (Zeitschrift herausgegeben von E. Krause), vol. iii. pp. 22–37, 128–132 (1878, Leipzig), may have some little interest. In England Romanes has written very able papers on the development of instinct and intelligence. His address is 18, Cornwall Terrace, Regent's Park, London.

Yours, &c., W. P.

ABNORMAL BAROMETRIC GRADIENT BETWEEN LONDON AND ST. PETERSBURG IN THE SUN-SPOT CYCLE

BEFORE alluding to the subject which forms the heading of the present communication, I must apologise for having allowed some rather serious errors to creep into the figures given for the barometric abnormals of London in my letter to NATURE, vol. xxiii. p. 243. The errors were caused by a friendly computer taking the differences from the mean for each year incorrectly in one or two cases.

I am glad to say however with respect to the relation between the barometric abnormals as there given and the sun-spot numbers, that far from its being vitiated by the corrections which have now been made, they on the contrary considerably strengthen it, as is evident when the following corrected values for the mean cycles are compared with those given in my former letter:—

LONDON

Annual Barometric Abnormals, Mean Cycles

	Maximum years in fifth line. Pressure (1811–77)	Sun-spots (1811–77).	Minimum years in seventh line Pressure (1816–79).	Sun-spots (1816–79).
1.	+0·011	−33·9	−0·006	+23·3
2.	+0·024	−23·4	−0·003	+14·5
3.	+0·017	0·0	−0·002	+ 4·8
4.	−0·003	+28·2	−0·004	− 5·6
5.	−0·011	+43·1	−0·006	−19·0
6.	−0·012	+34·2	−0·002	−32·5
7.	−0·008	+16·8	+0·003	−37·1
8.	±0·000	+ 0·2	+0·020	−25·4
9.	+0·002	−14·2	+0·025	+ 1·8
10.	+0·010	−24·2	+0·010	+30·9
11.	+0·008	−26·3	−0·009	+44·8

If now we take these corrected figures, and subtract from them those given in NATURE, vol. xx. p. 28, for St. Petersburg (reduced to inches), which comprise very nearly the same period, we get for the abnormal annual baric gradient from London to St. Petersburg in each year of the mean cycle, the following figures:—

Abnormal Annual Barometric Gradient between London and Petersburg

	(B) Maximum years in fifth line. Pressure. London–St. Petersburg (1811–77). (1822–71).	Sun-spots (1811–77).	(A) Minimum years in seventh line. Pressure. London–St. Petersburg (1816–79). (1822–71).
	inches.		inches.
1.	+0·032	−33·9	−0·012
2.	+ ·038	−23·4	− ·027
3.	+ ·036	0·0	− ·033
4.	+ ·007	+28·2	− ·029
5.	− ·029	+43·1	− ·018
6.	− ·040	+34·2	+ ·010
7.	− ·040	+16·8	+ ·036
8.	− ·025	+ 0·2	+ ·048
9.	− ·012	−14·2	+ ·041
10.	+ ·013	−24·2	+ ·016
11.	+ ·043	−26·3	− ·018

An inspection of these figures at once reveals the exist-



baric gradient oscillation of single period, closely following inverse sun-spot oscillation.

e constancy of the lag in the occurrence
s behind those of the sun spots, as well
arity in form of the two oscillations, I
have figures graphically in the accom-
which the barometric gradient abnormals are
ously with the *inverted* sun-spot ab-

at there is an almost uniform lag in the
hind the inverted sun-spot curve of a
while a variation of ·01 inches on the
onds very nearly throughout (allowance
to 10 on the sun-spot scale.
e prevailing west and south-west winds
ecessarily depend on the amount of the
places on the edge of the European
and those inland, and to the north as St.
r ground for concluding that the west
ast on the whole be stronger in years of
in those of maximum sun-spot.
e in favour of this notion has already
NATURE by Mr. S. A. Hill and Mr.
Observatory.
of variation in the strength of the wind
. Petersburg, following upon the change
nt between the two during the cycle,
se a *sensible* variation in the character of
ding to Mr. Blanford the mean baro-
e Bay of Bengal during the south-west
inches in 100 miles.
from London to St. Petersburg is about
maintain a current of air between them
al to that of the summer monsoon in the
uld have to be a total annual barometric
s. As the range of the abnormal gradient
ounts to 0·08 inches it should cause a
ual to one-fourth that of the monsoon.
t the normal mean annual gradient from
ng is 0·098 inches. The variation of
e nearly equal to the normal gradient.
t obtained with the e given by Mr. H.
cle in NATURE, vol. xxi. p. 477, it may
e is a barometric "see-saw" between
ria and the Atlantic coasts of Europe,
the former districts and Indo-Malaysia.
e the relation will probably be found to
winter months, and may also be found to
erous facts already ascertained regarding
ll, cloud, and temperature of Western
chs of the sun-spot cycle.

E. DOUGLAS ARCHIBALD

THE FRENCH LEARNED SOCIETIES

ongress of the French Learned Societies
ree days, but has exhibited an unusual
lany papers were read in the section of
M. Milne-Edwards, the veteran member

ed the results of rotation of the wind as
ters at an altitude where it is not to be
tion should interfere. The number of
to south was 113. Of these 83 were
, or by east, and only 30 by west; 49 of
ntinued to the west, and 34 stopped at
consequently when a wind has come from
he greater probability is that it will con-
e. When it has rotated to the west the
ter that it will continue to the north.
ree quarter rotations observed not less
l, and only 17 stopped at the west and
ng cannot be said of the negative rota-
a north to east, and of these only 6 were
west. These results are a confirmation
law.
e director of the Pic du Midi Observa-
e new buildings on the top of the moun-
and that next winter he will use them
is curious that the fact winter has been
s in this exalted altitude.

M. Hébert read a long paper on the formation of cyclones, which he explains by the influence of mountain ranges on the great atmospheric currents loaded with humidity.

M. Vidal presented a photometer based on the action of light on a selenium element of the ordinary construction. M. Vinot, editor of *Le Ciel*, presented a refractor mounted equatorially, of which the price is less than 10*l*., with a magnifying power of 150. M. Joubert gave details on the working of the Trocadéro Popular Observatory, which is now in constant operation, and where lectures on astronomical subjects are delivered regularly.

M. Guillemare read a paper on the use of soleine for lighting purposes. This product has been obtained by the distillation of a number of resinous matters, which have a point of ebullition from 150 to 160 Centigrade and a mean density of 0·860. When they have been freed from every other matter they can be used in a specially-prepared burner. This soleine can be prepared in immense quantities in all countries where pines are abundant.

A number of interesting communications were made on palæontology and zoology, generally advocating Darwinian views.

The final sitting was presided over, as usual, by the Minister of Public Instruction, and took place in the large hall of the Sorbonne. A number of crosses of honour and medals were distributed.

UNIVERSITY AND EDUCATIONAL INTELLIGENCE

OXFORD.—The lectures of the summer term commence this week. At the University Museum Prof. Clifton will conduct a class in practical physics and will lecture informally on the use of optical instruments. Mr. Stocker will give an experimental lecture in mechanics, and Mr. V. Jones will lecture on mechanical problems, in continuation of their courses last term. Prof. Odling will continue his course of lectures on organic chemistry, and Mr. Fisher will finish his inorganic course.

At Christ Church Mr. Harcourt lectures on the metals, and Mr. Baynes on the theory of gases. At Balliol Mr. Dixon gives an experimental lecture in elementary physics.

In a Congregation holden on Tuesday, April 27, it was resolved that candidates, not being members of the University, may present themselves at any of the ordinary examinations for Responsions. Last term a statute was passed instituting an examination to take place in the Long Vacation. This examination, which can be passed by candidates before matriculation into the University, is to be passed in lieu of Responsions. The effect of the statute will be that all young men may pass Responsions before they matriculate, and less of their University time will be consumed in getting up school work.

The proposal to designate the unattached students as students of the University Hall was lost by a large majority, 99 voting against the proposal and only 9 for it.

SOCIETIES AND ACADEMIES

LONDON

Chemical Society, April 21.—Dr. Debus in the chair.—It was announced that a ballot for the election of Fellows would take place at the next meeting, May 5.—The following papers were read:—On the distillation of mixtures of carbon disulphide and carbon tetrachloride, by F. T. Brown. The objects of the research were to find the boiling-point of every possible mixture of the two liquids, and the composition of the vapour evolved by any mixture when boiling. Tables and curves giving these results accompany the paper. The author also finds that the composition of the vapour evolved is independent of the pressure under which ebullition takes place.—On the estimation of hydric peroxide by means of potassic permanganate, by W. E. Adeney.—On the oxidation of sulphurous acid, by H. E. Dixon. The author finds that when sulphur dioxide, steam, and oxygen are exposed to a temperature of 100° C. no diminution of volume takes place, and therefore no sulphuric acid is formed. If the temperature be allowed to fall so that water condenses, a slight contraction in volume is observed.—On the reduction of cinnamic alcohol, by F. Hatton and W. R. Hodgkinson. When this substance is heated to 100° C. for three or four days

with sodium amalgam (containing 15 per cent. sodium), and a small quantity of water cinnamene and methylic alcohol are produced.

Entomological Society, April 6.—W. L. Distant, vice-president, in the chair.—One Ordinary and one Honorary Member were elected.—Mr. J. Jenner Weir exhibited an undetermined *Noctua*, apparently allied to the genera *Dicycla*, or *Gortyna*, which was found in a nursery garden at Blackheath in August last.—Mr. R. McLachlan exhibited three rare species of the Neuropterous genus *Dilar*, Rambl.—Rev. A. E. Eaton exhibited a specimen of *Haplophthalmus elegans*, Schöbl., a woodlouse new to the British fauna.—Miss E. A. Ormerod exhibited two termites' nests from British Guiana.—Mr. T. R. Billups exhibited specimens of two rare British insects—*Ichneumon erythrinus*, Gr., and *Lasiosomus enervis*, Herr. Schäff.—The Secretary announced the death of Herr J. H. C. Kawall, a well-known entomologist of Courland, at the age of eighty-two.—Mr. R. McLachlan read a description of a new species of *Cordulina* (*Gomphomacromia fallax*) from Ecuador.—Mr. J. B. Bridgman communicated a paper entitled "Some Additions to Mr. Marshall's Catalogue of British *Ichneumonidæ*." Upwards of sixty species (most of which were exhibited to the meeting) were noticed as new to the British fauna, including thirteen new to science.

Meteorological Society, April 20.—Mr. C. Greaves, F.G.S., vice-president, in the chair.—W. H. Goss, F.G.S., and Admiral J. L. Massie were elected Fellows of this Society.—The following papers were read:—On the frequency and duration of rain, by Dr. Wladimir Köppen of Hamburg.—Results of experiments made at the Kew Observatory with Rogen's and George's barometers, by G. M. Whipple, B.Sc., F.R.A.S.—On a discussion of Mr. Eaton's table of the barometric height at London with regard to periodicity, by G. M. Whipple, B.Sc., F.R.A.S.

Anthropological Institute, April 12.—F. W. Rudler, F.G.S., vice-president, in the chair.—The election of Lieut.-Col. R. G. Woodthorpe, R.E., and of Thomas Vincent Holmes, F.G.S., was announced.—Mr. Joseph Lucas read a paper on the ethnological relations of the Gypsies. In tracing back the past history of the races described under the common name of Gypsies we pass through two periods—the first *historical*, dating from A.D. 1414; the second partly historical, partly inferential. This older section formed the subject of Mr. Lucas's paper. The author premised that linguistic evidence shows that the various tribe of Gypsies now scattered over Europe can be referred to several Eastern tribes from India to Persia. The investigation dates back to archæological times, especially in relation to the working of metals and the presence of a large number of pure Sanscrit words in the language of European Gypsies, many of which do not occur in Hindustani. The "archæological" section embraces all that was not included under the several sections—"The Gypsies in Egypt," "Gypsies among the Romans," or "The Dark Ages"; but a good deal of the evidence upon which the archæological conclusions rest runs through those several sections, as well as through sections specially devoted to the names *Zingáro* and *Rom*. It will thus appear that the term "Gypsy" is used by the author in the widest sense as meaning "an Asiatic tribe which has wandered into Europe," though strictly it should mean only those who came by way of Egypt.

PARIS

Academy of Sciences, April 18.—M. Wurtz in the chair.—The following papers were read:—Microscopic inscription of movements observed in physiology, by M. Marey. The accuracy of the curves from M. Marey's instruments has been doubted, on the ground that vibrations proper to the light lever may be added to the physiological movement. He now removes this objection by greatly diminishing the range and velocity of the lever so as to give microscopic curves on smoked glass (which is also moved more slowly). The inertia of the lever becomes negligible. The curves, when examined in the microscope or by projection, are found identical with the others. The method greatly extends the field of phenomena that may be registered, *e.g.* the vibrations of blood in the vessels, which give a sound, produce a distinct microscopic trace. The portable character of the apparatus is an advantage.—On the Eulerian integral of the second species, by M. Gyldén.—On the surface of Kummer with sixteen singular points, by M. Brioschi.—On the action of beat on ammoniated bases, by M. Hofmann.—Report on a memoir of M. Perisé, entitled "Causes which tend to warp the Girders of Iron Bridges, and Means of [illegible] these Girders for Resistance of Warping Force," [illegible] secondary battery of M. Faure, by M. Keyser.—Improvement on M. Planté's, M. Faure quickly [illegible] power of almost unlimited accumulation by [illegible] two sheets of lead are each covered with minium [illegible] oxide of lead, then with a felt envelope held [illegible] They are then placed near each other (in [illegible] acidulated water. The electric current changes [illegible] peroxide on the positive electrode, and to [illegible] negative. On discharging, the reduced lead is [illegible] peroxidised lead reduced. A quantity of [illegible] giving 1-horse power for one hour may be [illegible] battery of 75 kg. The battery, under certain [illegible] 80 per cent. of the work expended in charging [illegible] Ampère to Lacroix was read. It was written [illegible] fessor in the Lyceum of Lyons, and expresses [illegible] mathematical studies.—On the earthquake of [illegible] Pelissier, Consul-General at Smyrna. The [illegible] first oscillation, on the afternoon of April 3, was [illegible] between 0·15 m. and 0·20 m. From then till the [illegible] were felt, thirty or forty of which were capable [illegible] down a solid wall. All the oscillations were [illegible] east to west. The Governor's palace, of very light [illegible] but chained throughout at the level of each storey, [illegible] the shocks, while the wall inclosing the ground, [illegible] was everywhere thrown down. Smyrna has been [illegible] for the wounded.—On Fuchsian functions, by M. Poincaré.—On Abelian functions, by the same.—On a class of [illegible] logarithms of which are sums of Abelian integrals of the first and third species, by M. Appell.—On the representation of functions (continued), by M. Reymond.—On stellar photography, by Prof. H. Draper. By exposing 140 minutes in the telescope, he has succeeded in photographing stars of magnitude 14·1, 14·2, and 14·3 (Pickering's scale). The weakest is of the magnitude on Herschel's scale. The minimum of visibility of the 9-inch telescope used has been thus nearly reached. Mr. Draper hopes soon to be able to go still further.—Action of light extends over a surface about 15′ in diameter.—Action of light on toluene, by M. Renard.—Structure and [illegible] texture of the ink-bag in cephalopoda of the French coast (continued), by M. Girod. The species observed were *Sepia officinalis*, *Loligo vulgaris*, *Sepiola Rondeletii*, and *Octopus vulgaris*.—The large dunes of sand of the Sahara, by M. Rolland. These move toward the south-east, and the sum of sand is almost insensible in a generation.

CONTENTS

SCIENTIFIC WORTHIES. XVII.—ROBERT WILHELM BUNSEN. By Prof. H. E. ROSCOE, F.R.S. (*With Steel Plate Engraving*) . . . .
JAPAN . . . .
OUR BOOK SHELF:—
Habich's "Études géométriques et cinématiques" . . . .
Carr's "Synopsis of Elementary Results in Pure and Applied Mathematics" . . . .
Keene's "Practical Fisherman" . . . .
LETTERS TO THE EDITOR:—
The Movements of Leaves.—CHARLES DARWIN, F.R.S. . . . .
Spectrum of the Star Ll. 13412.—Prof. EDWARD C. PICKERING . . . .
The Indian Winter Rains.—S. A. HILL . . . .
Palæolithic Man.—WORTHINGTON G. SMITH . . . .
Sound of the Auroræ.—Dr. JOHN RAE, F.R.S. . . . .
THE SCIENTIFIC PRINCIPLES INVOLVED IN ELECTRIC LIGHTING. By Prof. W. GRYLLS ADAMS, F.R.S. . . . .
THE FRENCH ASSOCIATION FOR THE ADVANCEMENT OF SCIENCE. At Algiers, II. By G. F. RODWELL . . . .
THE HERRING. By Prof. HUXLEY, F.R.S. . . . .
NOTES . . . .
CHEMICAL NOTES . . . .
PHYSICAL NOTES . . . .
THE DEVELOPMENT OF HUMAN INTELLIGENCE . . . .
ABNORMAL BAROMETRIC GRADIENT BETWEEN LONDON AND PETERSBURG IN THE SUNSPOT CYCLE. By E. DOUGLAS ARCHIBALD (*With Chart*) . . . .
CONGRESS OF THE FRENCH LEARNED SOCIETIES . . . .
UNIVERSITY AND EDUCATIONAL INTELLIGENCE . . . .
SOCIETIES AND ACADEMIES . . . .

ONS TO "NATURE."

	£	s.	d.
	1	8	0
	1	14	6
		7	6

United States, the Continent, and Postal Union :—

	£	s.	d.
	1	10	6
		15	6
		8	0

EDFORD STREET, STRAND, W.C.

OF SOCIETIES.

LONDON

THURSDAY, APRIL 28.

The Influence of Stress and Strain on the Atomic Structure of ...—The Metamorphosis of Lucifer; a ... Brooks.

...—Discussion on Mr. St. George ... Application of Electricity to Lighting and Heating purposes.

...Magnetism: Prof. Tyndall.

Inequalities in Water: O. S. Johnson.

FRIDAY, APRIL 29.

...Language and Literature of the Scottish Highlands.

The Problem Arts of India: General Maclagan.

SATURDAY, APRIL 30.

...—Scotland's Part in English Literature? Prof. ...

...ATION, Evening Class, at 7.—Exhibition and Distribution of Prizes. Address by Prof. Huxley, F.R.S. ... Lecture to Ladies: James Ingham.

MONDAY, MAY 2.

...Luncheon: Alan S. Cole.

8.—The Philosophy of Mr. Herbert Spencer: ...

...7.30.—Hegel (continued): Prof. W. T. Harris.

...—Annual Meeting.

TUESDAY, MAY 3.

...—On some Points in the Anatomy of the Mammalian Skull: W. N. Parker.—Contributions to the Theory of Natural Selection. Part I. On the Species of the Malayan Region: Alfred Russel Wallace, F.Z.S.—Additional Observations on Fossil Hyænas: Dr. M. Watson, F.Z.S.—On the Fossil Mammals of Madeira: Clifford Browne, F.Z.S.

...—Scientific Education: Prof. Dewar.

WEDNESDAY, MAY 4.

...—Buying and Selling: Prof. Bonamy Price.

...

THURSDAY, MAY 5.

...—On the Dragon's Blood Trees and the Products of New Species of *Calamus* from the Challenger Expedition.—New Genera of Plants from Madagascar: ...

...On the Action of Nitrous Acid on Atmospheric Air. On the Active and Inactive Modifications of Oxygen. On the Action of Alkalies on Ethyl, Methyl, and Allyl Chloride. On the Action of Sodium Alcoholates on Ethyl, ...

...—Magnetism: Prof. Tyndall.

FRIDAY, MAY 6.

...—The Land Systems of England and Ireland: ...

...

SATURDAY, MAY 7.

...—Scotland's Part in English History: Prof. H. ...

TISH MUSEUM.

...EUM will be closed on MONDAY, the 2nd, and ... the 9th of May.

...LOW A. BOND, Principal Librarian.

...ND EDITION,

RIFFIN'S

AL HANDICRAFT.

...ICK 4s. 5d. POST FREE.

... OF CHEMICAL APPARATUS: ...

... CLASSIFIED, DESCRIPTIVE, ...

...pp., Illustrated with 1,600 Woodcuts.

...t and Cheapest List of Apparatus.

...S AND SONS, 22, GARRICK STREET, LONDON, W.C.

C. KEGAN PAUL & CO.'S LIST.

Crown 8vo, cloth, 5s.

SIGHT: An Exposition of the Principles of Monocular and Binocular Vision. By JOSEPH LE CONTE, LL.D., Professor of Geology and Natural History in the University of California. With 132 Illustrations.

"Vol. XXXIII. of "The International Scientific Series."

Second Edition.

GENERAL PHYSIOLOGY of MUSCLES and NERVES. By Prof. J. ROSENTHAL. Crown 8vo, with Illustrations, cloth, 5s.

"Vol. XXXII. of "The International Scientific Series."

"A well-written and careful summary of existing knowledge by a patriotic compatriot authority, set forth in as simple language as is consistent with the very abstruse nature of the problems discussed."—*St. James's Gazette.*

Second Edition.

The NATURAL CONDITIONS of EXISTENCE as they AFFECT ANIMAL LIFE. By KARL SEMPER. With 106 Illustrations, crown 8vo, cloth, 5s.

"Vol. XXXI. of "The International Scientific Series."

"Unquestionably one of the most interesting contributions to zoological literature that has appeared for years. . . . The book is very freely illustrated with well-executed woodcuts."—*Popular Science Review.*

Second Edition.

THE ATOMIC THEORY. By Prof. WURTZ. Translated by E. CLEMINSHAW, F.C.S. Crown 8vo, cloth, 5s.

"At once a scientific treatise and an artistic work. The translator has very fairly maintained the clearness and crispness of the French style, whereby the book is marked with a distinct individuality and self-completeness."—*Nature.*

Demy 8vo, cloth, price 7s. 6d.

MATHEMATICAL PSYCHICS: An Essay on the Application of Mathematics to the Moral Sciences. By F. Y. EDGEWORTH, M.A.

2 vols., large post 8vo, cloth, 32s.

The EVOLUTION of MAN: A Popular Exposition of the Principal Points of Human Ontogeny and Phylogeny. By Prof. ERNST HAECKEL. With Coloured Plates and numerous Engravings on Wood.

"Prof. Haeckel's work is written in an admirably clear style, and the statements of scientific details, illustrated by excellent engravings and diagrams, is such that any attentive reader, however little conversant with such things, can have no difficulty in understanding it."—*Academy.*

2 vols., large post 8vo, cloth, 32s.

The HISTORY of CREATION. By Prof. ERNST HAECKEL. Translation revised by E. RAY LANKESTER, M.A. With Coloured Plates and Genealogical Trees of the various Groups of both Plants and Animals.

"The author has undergone a most difficult task with conscientious skill and marvellous ability."—*Nature.*

Crown 8vo, cloth, 5s.

FREEDOM in SCIENCE and TEACHING. From the German of Prof. ERNST HAECKEL. With a Prefatory Note by T. H. HUXLEY, F.R.S.

Crown 8vo, cloth, 4s. 6d.

CLAIRAUT'S ELEMENTS of GEOMETRY. Translated by Dr. KAINES. With 145 figures.

Crown 8vo, cloth, price 5s.

A CLASS-BOOK of CHEMISTRY, on the Basis of the New System. By EDWARD L. YOUMANS. With 200 Illustrations.

"He has furnished a series of questions which will be found not the least extremely useful by the young student."—*Popular Science Review.*

"We have the greatest possible pleasure in recommending his excellent book, which is certain in its present form to obtain a most honourable position."—*Glasgow News.*

New and Cheaper Edition.

FIRST BOOK of BOTANY. Designed to Cultivate the Observing Powers of Children. By ELIZA A. YOUMANS. With 200 Engravings, crown 8vo, cloth, price 2s. 6d.

"It is not rarely that a school-book appears which is at once so well planned, so well executed in every sense, and so sound in the general views on which it proceeds, as the present volume. . . . It has been everywhere welcomed as a timely and invaluable contribution to the improvement of primary education."—*Pall Mall Gazette.*

New and Cheaper Edition.

FIRST BOOK of ZOOLOGY. With numerous Illustrations. By EDWARD S. MORSE, Ph.D. Crown 8vo, cloth, price 2s. 6d.

"A comprehensive and useful little treatise for pupils who desire to obtain a general knowledge of the structure, habits, modes of growth, and other leading features of the various forms of animal life."—*Standard.*

London: 1, PATERNOSTER SQUARE.

W. LADD & CO.,
SCIENTIFIC INSTRUMENT MANUFACTURERS,
(By Appointment to the Royal Institution of Great Britain),
11 AND 12, BEAK STREET, REGENT STREET, W.
BIDWELL'S SELENIUM RHEOSTAT. AND OTHER APPARATUS FOR BELL'S PHOTOPHONE.
PHOSPHORESCENT POWDER—very brilliant—for Paint and other purposes, 3*s.* per oz.
Physical Apparatus of every Description.
ILLUSTRATED CATALOGUE, SIXPENCE.

PATERSON'S NEW CATALOGUE OF PHYSICAL APPARATUS.
LANTERN SLIDES for SCIENTIFIC LECTURES. Season 1880–1. Post free 6 Stamps.
Complete Sets of Physical Apparatus for Science Primers and all the Physical Text-books in use in Schools and Colleges.
Siemens and Gramme Dynamo Machines and Lamps for hire.
Schools supplied with Apparatus as per Science and Art Departments' Requirements in the Sections of Light, Heat, Sound, and Electr
Electric Signals for Houses, Hotels, &c., Colliery Signals, Lightning Conductors. The Gower-Bell Loud-speaking Telephone.
EDWARD PATERSON, Electrical Engineer,
SHOW ROOMS AND STEAM WORKS:—76, LITTLE BRITAIN, E.C. (late 3, Bedford Court, W.C.).
MOLISON'S HARMONOGRAPH; executes the Harmonic Curves in the most perfect manner. 15*s.* and 20*s.*
Illustrated Catalogue of Electrical Apparatus, Part 1, *post free*, 6 *Stamps. Ditto, Electric Signals, Part* 2, 6 St

Liberal Terms to Science Teachers and the Trade.
THOMAS CRAMPTON (formerly of 4, Little Britain, London, E.C.), ELECTRICIANS, OPTICIANS, and PHILOSOPHICAL INSTRUMENT MAKERS. Electric Bells, New Metallic Base Pattern, Constant Batteries, Indicators, Thief and Fire Alarms, and Automatic Switches, Induction and Medical Coils, or Specialities. Insulated Wires of every description. Microscopic and Optical Materials. Telescopes, Opera Glasses, Microscopes, Aneroid Barometers, and Lime-light Apparatus. Illustrated Catalogue Three Stamps.
THOMAS CRAMPTON & CO., 251, HIGH HOLBORN, LONDON, W.C.
For Trade Terms send Card.

TO ASTRONOMERS.
Intending Purchasers of Telescopes should send for "Hints on Silvered Glass Reflecting Telescopes," by G. CALVER (maker of the 37-inch Ealing Reflector), &c.; and "Appendix," containing important Testimonials as to their efficiency, &c.; &c. Post free Nine Stamps.
G. CALVER, F.R.A.S.,
HILL HOUSE,
WIDFORD,
CHELMSFORD.
N.B.—Second-hand Reflectors and Refractors frequently for Sale.

NOTICE OF REMOVAL.
JAMES HOW & CO.,
SCIENTIFIC INSTRUMENT MAKERS,
73, FARRINGDON ST., LONDON
(LATE OF 5, ST. BRIDE ST., AND 9, FOSTER LANE)
HOW'S STUDENT'S MICROSCOPE. HOW'S MICROSCOPE LAMP.
Rock Sections and other Objects for the Microscope.

S. C. TISLEY & Co.,
OPTICIANS,
172, BROMPTON ROAD, S.W.
(Close to South Kensington Museum.)
THE PHONEIDOSCOPE
An Instrument for Observing the Colour-Figures of Liquid Films under the action of Sonorous Vibrations.
Being a visible demonstration of the Vibratory and Molecular Motion of a Telephone Plate.
The PHONEIDOSCOPE, with 3 Discs, Bottle of Solution, Descriptive Pamphlet, &c., in Cardboard Box, 10*s.* 6*d.*
MANUFACTURED AND SOLD WHOLESALE AND RETAIL BY
S. C. TISLEY & Co., 172, BROMPTON ROAD, LONDON, S.W.
TELEPHONIC ELECTRICITY. All Materials supplied for Experimental Purposes.
Price Lists of Electrical and Acoustic Apparatus, with Drawings and Description of the Harmonograph. Post Free, 2d.

HOLLOWAY'S OINTMENT A CERTAIN REMEDY
For BAD BREASTS, OLD WOUNDS, and SORES. If effectually rubbed on the Neck and Chest, it cures SORE THROATS, BRONCHITIS, COUGHS and COLDS; and for GOUT, RHEUMATISM, and all Skin Diseases it is unequalled.

R. W. NEEVES,
PHILOSOPHICAL INSTRUM
INTENSITY AND COIL MAK
PRICE LIST, FOUR STAMPS.
55, SIDMOUTH STREET, LONDON,

BROKEN!!
DAVY'S DIAMOND CEM
SECURELY AND NEATLY
CHINA, GL
CABINET WORK
AND
FANCY ARTICL
Of all Chemists in the Kingdom
See the name "E. DAVY." the O
ventor, is on the Label, and als
BARCLAY & SONS, 95, Farringdon Street,

EAGLE INSURANCE COMPA
For Lives only. Established 1807.
Accumulated Funds ... 79, PALL MALL.
Also a Subscribed Capital of ... more than ...
Reports, Prospectuses, and Forms may be had at the Office, of the Company's Agents, post free.
GEORGE HUMPHREYS, Actuary and Se

LIGHTNING CONDUCTOR
Experience, accumulated since the time of Benjamin Franklin conclusively that a Conductor made of Copper of adequate size of all appliances for the protection of every description of buildi destructive effects of lightning.

NEWALL & CO.'S
PATENT COPPER LIGHTNING CONDUC
As applied to all kinds of Buildings and Shipping in all parts of with unvarying success; is the most Trustworthy, most Effective, the Cheapest Conductor ever offered to the public.
It is simple in its application, no insulators being required, and only one shilling per foot for the standard size, which ensures safe storm
R. S. NEWALL & CO., 130, STRAND, W.C.
MANUFACTORY—GATESHEAD-ON-TYNE.

FRY'S COCOA EXTRAC
GOLD MEDAL, PARIS EXHIBITION, 1878.
"If properly prepared, there is no nicer or more wholesome preparation of cocoa."—*Reeds, Waiter, and Air.*
In Packets and Tins
Cocoa only, with the
edited by Dr. Hassall, and Air.
J. S. FRY & SONS, Bristol and London.

Now publishing in Crown 8vo, price 2s. 6d. each.

.ISH MEN OF LETTERS.

EDITED BY JOHN MORLEY.

r Leslie Stephen.

is well with Mr. Leslie Stephen's sketch uld hardly have been done better, and it der- for whom it is intended a juster an either of the two essays of Lord *Gazette*.

H. Hutton.

for a more suggestive introduction to novels."—*Examiner*.

J. C. Morison.

'ul, and attractive record of the life and mong the world's historians, it de-erves *xaminer*.

r J. A. Symonds.

great poet are to be congratulated at d so fresh, clear, and intelligent a pre- written by a man of adequate and wide

ofessor Huxley, F.R.S.

id that no one now living could have more sympathy or with equal per-

By William Black.

fine sympathy and taste to bear in his writings, as well as his sketch of the *Athenæum*.

V. Minto.

is careful and accurate in all that it l that it suggests. It will repay reading *neum*.

rincipal Shairp.

has given a truer estimate either of an this volume."—*Spectator*.

the Very Rev. the Dean of

ster of his subject, and writes always *emy*.

By Anthony Trollope.

ch is excellently adapted to fulfil the which it appears."—*Athenæum*.

ohn Morley.

criticism yet published on the life and contained in Mr. Morley's compendious is vigorous and polished, and both his dgment, and his literary criticisms, are and in a high degree interesting."—

MILTON. By Mark Pattison.

"Every page gives us something new to learn, or something old put in such a way as to be almost equivalent to that which is new."—*Academy*.

HAWTHORNE. By Henry James, Jun.

"Probably no one living could have done so good a book on Hawthorne as Mr. James has done."—*Saturday Review*.

SOUTHEY. By Prof. Dowden.

"A truly scholarly and delightful monograph of a great writer, who has been of late years undeservedly neglected."—*Examiner*.

CHAUCER. By A. W. Ward.

"An enjoyable and excellent little book is this of Professor Ward's. Far away the best connected account of Chaucer and his work to be found in English."—*Academy*.

COWPER. By Goldwin Smith.

"Mr. Goldwin Smith has sketched, in a few decisive touches, the genius of the poet and weakness of the man."—*Daily News*.

BUNYAN. By J. A. Froude.

"The life and character of Bunyan stands out in bold relief, and for the first time the author of the 'Pilgrim's Progress' is portrayed as he really existed."—*Westminster Review*.

BYRON. By Professor Nichol.

"Decidedly one of the most careful and valuable of the whole series. When a book is so good as Prof. Nichol's, there is little to be said about it, except to recommend it as widely as may be."—*Athenæum*.

LOCKE. By Professor Fowler.

"In the case of Locke's biographer we venture to say that Mr. Morley has been exceptionally fortunate. A pen more competent than Professor Fowler's for this particular work might have been sought, and sought in vain."—*Examiner*.

POPE. By Leslie Stephen.

"The sketch of Pope's life which Mr. Leslie Stephen has written is interesting throughout. . . . A work which one can only lay down with the wish to have a good deal more on the same subject by the same hand."—*Academy*.

WORDSWORTH. By F. W. H. Myers.

"Mr. Myers gives us a picture of the man and an estimate of his work which is certainly not inferior to anything that has preceded it. . . . Possibly the best chapter in the book . . . every chapter of which is excellent—is that on Natural Religion."—*Academy*.

DRYDEN. By George Saintsbury.

"Mr. Saintsbury's very careful, fine, and interesting volume . . . seems to us to hold a place of its own amongst the series."—*Daily News*.

***** Other Volumes to follow.**

MILLAN AND CO., BEDFORD STREET, COVENT GARDEN, W.C.

Messrs. MACMILLAN & CO.'S PUBLICATIONS

Eversley Edition.

CHARLES KINGSLEY'S NOVELS

MESSRS. MACMILLAN & CO. have the pleasure to announce a **NEW EDITION** of the **NOVELS** of **CHARLES KINGSLEY**, which they will publish immediately under the above title.

This Edition has been planned to meet the wish expressed by many admirers of Mr. KINGSLEY for a beautiful Edition of his Novels. **THE EVERSLEY EDITION** will therefore be printed from new type by Messrs. R. & R. CLARK, on a paper specially manufactured for this work by Messrs. JOHN DICKINSON & Co. The binding will be done by Messrs. JAMES BURN & Co., and the Publishers hope that the mechanical productions will be found in every respect worthy of the books themselves.

THE EVERSLEY EDITION will be comprised in Eleven volumes, Globe 8vo, and will be published at the uniform price of **FIVE SHILLINGS** per volume.

A Portrait by Mr. LOWES DICKINSON of **CHARLES KINGSLEY** in his Study at **Eversley**, newly engraved, will appear as a Frontispiece in the First Volume.

The Books will be published in the following order:—

WESTWARD HO!	**2 vols. 10s.**	*May.*
TWO YEARS AGO	**2 vols. 10s.**	*June.*
HYPATIA	**2 vols. 10s.**	*July.*
YEAST	**1 vol. 5s.**	*August.*
ALTON LOCKE	**2 vols. 10s.**	*September.*
HEREWARD THE WAKE	**2 vols. 10s.**	*October.*

*** *Subscribers' Names will be received by all Booksellers.*

ANTHROPOLOGY: an Introduction to the Study of MAN AND CIVILISATION. By E. B. TYLOR, D.C.L., F.R.S. With numerous Illustrations. Crown 8vo. 7*s.* 6*d.*

"It is an endeavour to put before the lay readers in a clear, condensed, and interesting form the main settled results of investigations into the science of man. . . . Mr. Tylor's admirable little book certainly deserves the success with which it doubtless meet."—*Pall Mall Gazette.*

"It is a most attractive and entertaining introduction to the science of anthropology. . . . His writing is clear and terse and his arrangement masterly."—*Saturday Review.*

MANUAL OF ANCIENT GEOGRAPHY. From the German of Dr. KIEPERT. Crown 8vo. 5*s.*

"Dr. Kiepert actually succeeds in making ancient geography interesting, connecting it as he is able to do from his extensive scholarly knowledge with the natural features of the various countries, the movements of various races, and modern travel. The arrangement is methodical and the treatment clear and well defined, the connection between the Old World and the New being always kept in sight. . . . Altogether the English edition of the Manual will form an indispensable companion to the 'Atlas,' now used in many of our leading schools."—*The Times.*

GRAPHICAL DETERMINATION OF FORCES IN ENGINEERING STRUCTURES. By J. B. CHALMERS, C.E. With Illustrations. 8vo. 24*s.*

THE STEAM ENGINE AND ITS INVENTORS: a Historical Sketch. By ROBERT L. GALLOWAY, Mining Engineer. With numerous Illustrations. Crown 8vo. 10*s.* 6*d.*

"Mr. Galloway's capital little book."—*English Mechanic.*

"A book of singular local and general interest."—*Newcastle Weekly Chronicle.*

"We regard it as a valuable addition to engineering literature."—*Colliery Guardian.*

QUESTIONS ON BALFOUR STEWART'S ELEMENTARY LESSONS IN PHYSICS. By Prof. THOMAS H. CORE, Owens College, Manchester. 18mo. 2*s.*

EXERCISES IN ANALYTICAL GEOMETRY. Compiled and arranged by J. M. DYER, M.A., Senior Mathematical Master in the Classical Department of Cheltenham College. Crown 8vo.

MACMILLAN'S POPULAR 6*s.* NOVELS.—NEW VOLUME.

WHITE WINGS: a Yachting Romance. By WILLIAM BLACK, Author of "Strange Adventures of a Phæton," "A Princess of Thule," "Madcap Violet," &c. Crown 8vo. 6*s.*

FIRST LESSONS IN PRACTICAL BOTANY. By G. T. BETTANY, M.A., F.L.S., Lecturer in Botany at Guy's Hospital. 18mo. 1*s.*

[Immediately.

MACMILLAN AND CO., LONDON, W.C.

Printed by R. CLAY, SONS, AND TAYLOR, at 7 and 8, Bread Street Hill, Queen Victoria Street, in the City of London, and published by MACMILLAN AND CO., at the Office, 29 and 30, Bedford Street, Covent Garden.—THURSDAY, April 28, 1881.

USE IN THE LIBRARY
DO NOT REMOVE
FROM LIBRARY

Stanford University Libraries
3 6105 007 821 734

v.25 Nov 1880-Apr 1881

DATE
NAME

FOR LIBRARY USE ONLY